


**FIVE-YEAR REVIEW REPORT FOR
HATHEWAY & PATTERSON SUPERFUND SITE
BRISTOL COUNTY, MASSACHUSETTS**



Prepared by

**U.S. Environmental Protection Agency
Region 1, New England
Boston, Massachusetts**


James T. Owens, III, Division Director
Office of Site Remediation and Restoration
U.S. EPA, New England



Date

TABLE OF CONTENTS

EXECUTIVE SUMMARY	ES-1
SECTION 1.0 INTRODUCTION.....	1-1
SECTION 2.0 SITE CHRONOLOGY.....	2-1
SECTION 3.0 BACKGROUND	3-1
3.1 PHYSICAL CHARACTERISTICS AND LAND AND RESOURCE USE.....	3-1
3.2 HISTORY OF CONTAMINATION.....	3-2
3.3 INITIAL RESPONSE	3-2
3.4 BASIS FOR TAKING ACTION.....	3-3
SECTION 4.0 REMEDIAL ACTIONS	4-1
4.1 REMEDY SELECTION.....	4-1
4.2 REMEDY IMPLEMENTATION.....	4-2
4.3 OPERATION AND MAINTENANCE	4-3
SECTION 5.0 PROGRESS SINCE THE LAST FIVE YEAR REVIEW	5-1
SECTION 6.0 FIVE-YEAR REVIEW PROCESS	6-1
6.1 COMMUNITY NOTIFICATION AND INVOLVEMENT	6-1
6.2 DOCUMENT REVIEW.....	6-1
6.3 DATA REVIEW	6-1
6.3.1 Hydrogeology	6-1
6.3.2 Groundwater Monitoring Results	6-3
6.3.3 Sediment Monitoring Results	6-4
6.3.4 Fish Survey.....	6-4
6.4 SITE INSPECTIONS	6-4
6.5 INTERVIEWS.....	6-5
SECTION 7.0 TECHNICAL ASSESSMENT	7-1
7.1 Question A: Is the remedy functioning as intended by the decision documents?.....	7-1
7.2 Question B: Are the exposure assumptions, toxicity data, cleanup levels, and remedial action objectives (RAOs) used at the time of remedy selection still valid?.....	7-1
7.2.1 Review of Human Health Risk Assessment.....	7-1
7.2.2 Review of Ecological Risk Assessment	7-6
7.2.3 ARARs Review	7-8
7.3 Question C: Has any other information come to light that could call into question the protectiveness of the remedy?.....	7-9
SECTION 8.0 ISSUES.....	8-1
SECTION 9.0 RECOMMENDATIONS AND FOLLOW-UP ACTIONS.....	9-1
SECTION 10.0 PROTECTIVENESS STATEMENTS	10-2
SECTION 11.0 NEXT FIVE-YEAR REVIEW	11-1

TABLES

Table 1: Chronology of Site Events

Table 2: Comparison of 2005 and 2014 Oral Reference Doses and Oral Cancer Slope Factors for Compounds of Potential Concern

Table 3: Soil Cleanup Levels (Commercial/Open Space)

Table 4: Issues

Table 5: Recommendations and Follow-Up Actions

APPENDICES

APPENDIX A: Figures

APPENDIX B: List of Documents Reviewed and References

APPENDIX C: Analytical Data

APPENDIX D: MSR Technical Memorandum

APPENDIX E: Interview Record Forms

APPENDIX F: Risk Calculations

APPENDIX G: ARARs Review Tables

LIST OF ACRONYMS AND ABBREVIATIONS

ACRONYM	DEFINITION
AAL	Allowable Ambient Air Limits
ACGIH	American Conference of Governmental Industrial Hygienists
ARAR	Applicable or Relevant and Appropriate Requirement
AST	Above Ground Storage Tank
AUL	Activity and Use Limitation
AWQC	Ambient Water Quality Criteria
BERA	Baseline Ecological Risk Assessment
BLM	Biotic Ligand Model
BOH	Board of Health
CCA	Chromated copper arsenate
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act, 42 USC § 9601 et seq.
CFR	Code of Federal Regulations
CIC	Community Involvement Coordinator
COC	Contaminant of Concern
COPC	Contaminant of Potential Concern
CWA	Clean Water Act
DA	Domestic Auxiliary
DEQE	Massachusetts Department of Environmental Quality Engineering
EPA	Environmental Protection Agency (U.S. EPA - Region 1)
EPC	Exposure Point Concentration
ESD	Explanation of Significant Differences
FCAP	Fluoro-chrome-arsenate-phenol
FIFRA	Federal Insecticide, Fungicide, and Rodenticide Act of 1947
FS	Feasibility Study
GERE	Grant of Environmental Restrictions and Easements
HHRA	Human Health Risk Assessment
HI	Hazard Index
HQ	Hazard Quotient
ICs	Institutional Controls
ICA	Industrial/Commercial Auxiliary
IRIS	Integrated Risk Information System
LEL	Lowest Effect Level
LI	Limited Industrial
LNAPL	Light Non-Aqueous Phase Liquid
M&E	Metcalf & Eddy
MADEQE	Massachusetts Department of Environmental Quality Engineering
MassDEP	Massachusetts Department of Environmental Protection
MCLs	Maximum Contaminant Levels
MSR	Management System Review
NAWQC	National Ambient Water Quality Criteria
NCP	National Contingency Plan, 40 CFR Part 300
NE	Northeast
NESHAPS	National Emission Standards for Hazardous Air Pollutants

ACRONYM	DEFINITION
NPL	National Priority List
NW	Northwest
O&M	Operation and Maintenance
OMEE	Ontario Ministry of Environment and Energy
PAHs	Polycyclic Aromatic Hydrocarbons
PA/SI	Preliminary Assessment/Site Investigation
PCP	Pentachlorophenol
PRP	potentially responsible party
RA	Remedial Action
RAC	Response Action Contract
RAFU	Reasonable Anticipated Future Land Use
RAO	Remedial Action Objective
RCRA	Resource Conservation and Recovery Act, 42 U.S.C. ' ' 6901 <i>et seq.</i>
RD	Remedial Design
RME	Reasonable Maximum Exposure
RfD	Reference Dose
RI	Remedial Investigation
ROD	Record of Decision
SDWA	Safe Drinking Water Act
SE	Southeast
SEL	Severe Effect Level
SF	Slope Factor
SVOCs	Semivolatile Organic Compounds
SW	Southwest
TBC	To Be Considered
TEL	Threshold Exposure Limit
TEQ	Toxicity Equivalent
TLV	Threshold Limit Value
TRV	Toxicity Reference Value
UCL	Upper Confidence Limit
USACE	United States Army Corps of Engineers
UST	Underground Storage Tank
VOCs	Volatile Organic Compounds

EXECUTIVE SUMMARY

This is the first five-year review for the Hatheway & Patterson Superfund Site (the site). This review is required by statute because the selected remedy will, upon completion, leave hazardous substances, pollutants, or contaminants on site above levels that allow for unlimited use and unrestricted exposure. The trigger date for this statutory five-year review is the initiation of the remedial actions at the site on September 2, 2009.

The site is a former wood treatment facility located at 35 County Street in Mansfield, Massachusetts. Approximately 36 acres of the 38.17-acre site are located in the Town of Mansfield. The remaining 1.77 acres are located in the Town of Foxborough, also referred to as the Foxborough parcel (see Figure 1.2 in Appendix A). The Mansfield portion of the site is divided into four quadrants by the Rumford River, which runs north to south, and by a railroad right-of-way, which runs east to west. The northeast and northwest quadrants are referred to as the "Process Area", the southeast and southwest quadrants ("SE/SW quadrants") cover the area south of the Rumford River, and the "County Street area" lies north of the site fence in the northeast and northwest quadrants (see Figure 1.2 in Appendix A).

The selected remedy identified in the 2005 Record of Decision (ROD) included demolition of buildings in and near Hatheway & Patterson's former manufacturing area; excavation of soils with contaminants exceeding cleanup levels; testing of soils containing pentachlorophenol (PCP), semi-volatile organic compounds (SVOCs), and arsenic for leachability, stabilization/solidification of the soils, if necessary, and consolidation of stabilized/solidified soils under a low-permeability cover; off-site disposal of soils containing dioxin and oily material (LNAPL) at a licensed facility; institutional controls to prohibit the use of site groundwater and restrict land uses in a manner that ensures the protectiveness of the remedy; and long-term monitoring of groundwater, surface water, fish tissue, and sediment.

The remedy was modified via an Explanation of Significant Differences (ESD) in 2011. Based on a zoning change for the Foxborough parcel from residential use to "Limited Industrial" use, and intended reuse of the parcel as a parking lot, EPA and MassDEP determined that the Foxborough parcel should be remediated to a Reasonably Anticipated Future Use of commercial/open space and changed the cleanup level accordingly. It was determined that a consolidation area for soils in Foxborough contaminated with arsenic could be built on the Foxborough parcel and designed with an asphalt cover in order to facilitate use as a parking lot. The 2011 ESD also modified the remedy for the management of PCP and arsenic-contaminated soils from consolidation on the lots in the Mansfield portion of the Site to disposal at an off-site facility. In addition, the EPA clarified the extent of institutional controls to be placed on the site properties as called for in the ROD.

Protectiveness Statement

The remedy at the Hatheway & Patterson Superfund Site currently protects human health and the environment because remediation of the soil (soil removal and on-site consolidation) has been completed to cleanup levels that are considered protective for the anticipated future use of the property, and there is no current use of on-site groundwater which is classified as non-potable. However, in order for the remedy to be protective in the long-term, institutional controls need to be created and recorded to restrict inappropriate land uses (including use of groundwater) and protect the consolidation area cover. Operation and maintenance activities have been initiated and will ensure that the consolidation area and associated components of the remedy (e.g., groundwater monitoring wells) remain in good condition. In addition, monitoring of groundwater will continue to assess the protectiveness of the remedy.

Five-Year Review Summary Form

SITE IDENTIFICATION

Site Name: Hatheway & Patterson Superfund Site

EPA ID: MAD001060805

Region: 1

State: MA

City/County: Bristol

SITE STATUS

NPL Status: Final

Multiple OUs?

No

Has the site achieved construction completion?

Yes

REVIEW STATUS

Lead agency: EPA

If "Other Federal Agency" was selected above, enter Agency name: [Click here to enter text.](#)

Author name (Federal or State Project Manager): Kimberly White

Author affiliation: U.S. EPA, Region 1 – New England

Review period: February 2014 to August 2014

Date of site inspection: June 3, 2014

Type of review: Statutory

Review number: 1

Triggering action date: September 2, 2009

Due date (five years after triggering action date): September 2, 2014

Five-Year Review Summary Form (continued)

Issues/Recommendations

Issues and Recommendations Identified in the Five-Year Review:

OU(s):	Issue Category: Institutional Controls			
	Issue: Institutional controls restricting land uses that may impact the protectiveness of the remedy (including preventing the use of groundwater, protecting the consolidation area cover and other components of the remedy) need to be established. Also, an updated risk evaluation shows that the railroad right-of-way will also require institutional controls to protect workers who may contact soil in that area.			
	Recommendation: EPA, MassDEP, and the property owners should begin discussions as soon as possible and establish institutional controls by the next five-year review.			
Affect Current Protectiveness	Affect Future Protectiveness	Implementing Party	Oversight Party	Milestone Date
No	Yes	State	EPA	Aug 2019

OU(s):	Issue Category: Monitoring			
	Issue: The 2012 sediment sampling event included locations which did not correspond with the historic sampling locations and the results showed lower contaminant concentrations than seen previously. As a result, it is uncertain whether the higher concentrations historically seen remain at the Site. If the historic concentrations are still present, recent changes to toxicity values and exposure parameters included in risk evaluation for sediment may result in a future change to the protectiveness determination with respect to sediment exposure.			
	Recommendation: If accessible, collect sediment samples from locations which correspond to historical sampling locations and assess the new data.			
Affect Current Protectiveness	Affect Future Protectiveness	Implementing Party	Oversight Party	Milestone Date
No	Yes	State	EPA	Dec 2018

OU(s):	Issue Category: Monitoring			
	Issue: The fish tissue collection required by the ROD was not performed due to a lack of fish in the Rumford River. Also, surface water sampling required by the ROD was not performed due to EPA and MassDEP's agreement to continue discussions about the future operation and maintenance plan for the site.			
	Recommendation: Review current site information, determine the need for and, if necessary, collect any additional data. Update/ document changes in the monitoring requirements accordingly.			
Affect Current Protectiveness	Affect Future Protectiveness	Implementing Party	Oversight Party	Milestone Date
No	Yes	EPA/State	EPA	Dec 2018

OU(s):	Issue Category: Monitoring			
	Issue: Determine whether a PCP detection above its MCL in a non-potable private groundwater supply well is site-related.			
	Recommendation: Perform evaluation which potentially includes the following: determine if detection is real (potential resampling); review well construction and any potential hydrogeologic connection to the site; and review nearby potential sources.			
Affect Current Protectiveness	Affect Future Protectiveness	Implementing Party	Oversight Party	Milestone Date
No	Yes	EPA	EPA	Dec 2016

OU(s):	Issue Category: Monitoring			
	Issue: Active irrigation wells have been identified approximately 300 feet beyond the compliance boundary. Irrigation wells are not expected to create enough drawdown to induce groundwater to flow to them from the compliance boundary. An on-site monitoring well just east (upgradient) of the compliance boundary does indicate the presence of contamination at concentrations above performance standards.			
	Recommendation: Additional investigations should be conducted to confirm whether groundwater flow directions have been impacted by the irrigation wells.			
Affect Current Protectiveness	Affect Future Protectiveness	Implementing Party	Oversight Party	Milestone Date
No	Yes	EPA/State	EPA	Dec 2015

Protectiveness Statement(s)

Sitewide Protectiveness Statement (if applicable)

Protectiveness Determination:
Short-term Protective

Addendum Due Date (if applicable):
[Click here to enter date.](#)

Protectiveness Statement:

The remedy at the Hatheway & Patterson Superfund Site currently protects human health and the environment because remediation of the soil (soil removal and on-site consolidation) has been completed to cleanup levels that are considered protective for the anticipated future use of the property, and there is no current use of on-site groundwater which is classified as non-potable. However, in order for the remedy to be protective in the long-term, institutional controls need to be created and recorded to restrict inappropriate land uses (including use of groundwater) and protect the consolidation area cover. Operation and maintenance activities have been initiated and will ensure that the consolidation area and associated components of the remedy (e.g., groundwater monitoring wells) remain in good condition. In addition, monitoring of groundwater will continue to assess the protectiveness of the remedy.

SECTION 1.0 INTRODUCTION

The purpose of this five-year review is to determine whether the remedy for the Hatheway & Patterson Superfund Site continues to be protective of human health and the environment. The methods, findings, and conclusions of this review are documented in this five-year review report. In addition, five-year review reports identify issues found during the review, if any, and present recommendations to address them.

EPA Region I has conducted this five-year review pursuant to the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) and the National Contingency Plan (NCP). Section 121(c) of CERCLA 42 USC § 9621(c) states:

If the President selects a remedial action that results in any hazardous substances, pollutants, or contaminants remaining at the site, the President shall review such remedial action no less often than each five years after the initiation of such remedial action to assure that human health and the environment are being protected by the remedial action being implemented. In addition, if upon such review it is the judgment of the President that action is appropriate at such site in accordance with section [104] or [106], the President shall take or require such action. The President shall report to the Congress a list of facilities for which such review is required, the results of all such reviews, and any actions taken as a result of such reviews.

The Agency interpreted this requirement further in the NCP; 40 CFR §300.430(f)(4)(ii) states:

If a remedial action is selected that results in hazardous substances, pollutants, or contaminants remaining at the site above levels that allow for unlimited use and unrestricted exposure, the lead agency shall review such action no less often than every five years after the initiation of the selected remedial action.

This is the first five-year review for the Hatheway & Patterson Site. This review was performed by EPA Region I - New England and is required by statute because the selected remedy will, upon completion, leave hazardous substances, pollutants, or contaminants on site above levels that allow for unlimited use and unrestricted exposure. The trigger date for this initial five-year review is the initiation of the remedial actions at the site in September 2009.

SECTION 2.0 SITE CHRONOLOGY

The chronology of the site, including all significant events and dates is provided below in Table 1.

Table 1: Chronology of Site Events	
Event	Date
Discovery of a tar seep on the banks of the Rumford River by representatives of the Town of Mansfield and Massachusetts Department of Environmental Quality Engineering (MADEQE) and subsequent request that Hatheway & Patterson contain the “oily seepage”.	1972
Hatheway & Patterson took steps to control the “oily seepage” including booms and sorbents, a collection pit and trench, and other measures including recovery of 2,500 gallons of oil through groundwater pumping operations.	1973 – 1982
Additional report of “oily seepage” in the Rumford River and soil and groundwater sampling by a prospective property buyer.	1981
MADEQE issued a Notice of Noncompliance letter to Hatheway & Patterson requiring a Phase I Initial Site Investigation.	May 1987
Phase I site investigations conducted.	1987-1988
MADEQE issued a Notice of Responsibility letter to Hatheway & Patterson requiring a Phase II Site Investigation, Risk Assessment, and an alternative evaluation.	August 1988
Phase II site investigations conducted.	late 1988 – early 1989
The Massachusetts Department of Environmental Protection (MassDEP), formerly MADEQE, issued a Request for Short Term Measure letter to Hatheway & Patterson to address the imminent hazard to the Rumford River area based on an additional report of “oil seepage”.	June 1990
Short-term measure investigation conducted and included “sampling of the worst-case visibly stained soil along the river bank.”	Fall 1990
Hatheway & Patterson constructed a collection trench along the eastern bank of the Rumford River to intercept groundwater and oils migrating to the river from oil-contaminated river bank.	September 1991
The collection trench was modified to include groundwater treatment with activated carbon prior to discharge to the Rumford River.	February 1992
Two RCRA inspections found that drip pads were not in compliance with RCRA regulations.	March 1992

Table 1: Chronology of Site Events	
Event	Date
MassDEP inspection and report of petroleum product flowing from the river bed into the Rumford River, a release of oil into nearby wetlands, and free-product in the wetlands. MassDEP requested that Hatheway & Patterson conduct additional assessment and plans for corrective action.	January 1993
Hatheway & Patterson filed for bankruptcy protection and closed the manufacturing facility, leaving wood-treatment chemicals and sludge in ASTs, UST sumps and drums at the abandoned property.	February – May 1993
EPA and MassDEP initiated a Preliminary Assessment/Site Investigation (PA/SI).	June 1993
EPA initiated a Removal Action to address the presence of ASTs and USTs containing hazardous wastes located inside and outside the buildings. 100,000 gallons of liquid and solid wastes were removed and disposed off-site. Subsequently, a comprehensive surface soil investigation was conducted and several areas of the property received temporary geotextile/gravel and/or asphalt cover. Also, perimeter fencing was repaired and installed, and locks to manways of tanks and on-site buildings were installed.	December 1993 – September 1995
Additional on-site reconnaissance and environmental investigation and sample collection is conducted by MassDEP and EPA.	1998
Town of Mansfield conducted environmental investigation under an EPA Brownfields Pilot Program grant.	2000
EPA contractors conducted additional groundwater, surface water, and sediment sampling.	Fall 2001
The site was added to the EPA National Priorities List.	September 5, 2002
Surface soil samples were analyzed from outside of the perimeter fence on both sides of County Street.	April 2003
EPA initiated a Removal Action to address the arsenic-contaminated soil located outside the perimeter fence. 376 tons of contaminated soils were excavated from both sides of county road and disposed of off-site.	August 2003
Completion of Remedial Investigation/Feasibility Study (RI/FS).	June 2005
EPA issued the Record of Decision.	September 30, 2005
Process buildings are demolished and disposed of off-site.	Spring 2006
Remedial Design is (RD) completed.	September 2008
Start of on-site construction.	September 2009

Table 1: Chronology of Site Events	
Event	Date
EPA issued an Explanation of Significant Differences to document changes made to the remedy on the Foxborough, Massachusetts parcel, including changes to the anticipated future land use, design of the consolidation area, and the tax foreclosure and rezoning of the property by the Town; to document the shipment of certain pentachlorophenol and arsenic contaminated soils to an off-site facility, rather than the on-site consolidation specified in the Record of Decision (ROD); and to clarify the extent of institutional controls to be placed on portions of the site.	August 29, 2011
Final Remedial Action Completion Report completed by Severson Environmental Services, Inc. for the U.S. Army Corps of Engineers.	September 2011

SECTION 3.0 BACKGROUND

3.1 PHYSICAL CHARACTERISTICS AND LAND AND RESOURCE USE

The Hatheway & Patterson Superfund Site is located at 35 County Street in Mansfield, Massachusetts (see Figure 1.1 in Appendix A). Approximately 36 acres of the 38.17-acre site are located in the Town of Mansfield. The remaining 1.77 acres are located in the Town of Foxborough, also referred to as the Foxborough parcel (see Figure 1.2 in Appendix A). The Mansfield portion of the site is divided into four quadrants by the Rumford River, which runs north to south, and by a railroad right-of-way, which runs east to west. The northeast (NE) and northwest (NW) quadrants are referred to as the "Process Area" and are located north of the active railroad tracks operated by CSX. The southeast (SE) and southwest (SW) quadrants cover the area south of the railroad tracks. The "County Street area" lies north of the site fence in the northeast and northwest quadrants (see Figures 1.2 and B-1 in Appendix A).

The site lies within the Taunton River Basin which drains approximately 528 square miles and empties into the Narragansett Bay at Fall River, Massachusetts. The Rumford River flows north to south and is primarily fed by the Glue Factory Pond, which is located approximately 1 mile north of the site. The area to the north of the site is developed with residences and light industry.

Much of the southwestern portion of the site is covered by wetlands, and several potential vernal pool-like habitats exist in this area. The southerly section of the site is bounded by the Rumford River backwash channel. Portions of the site are located within areas of the 100-year flood zone (Zone A3) and between limits of the 100-year flood and 500-year flood zone (Zone B) for the Rumford River. The Rumford River is a Class B surface water. Class B waters are designated as habitat for fish, other aquatic life and wildlife, and for primary and secondary contact recreation. They are also designated as suitable for irrigation and other agricultural uses and for compatible industrial cooling and process uses. The Rumford River backwash channel (the southern boundary of the site) was the former course of the main channel of the river until it was redirected further to the south during the 1960's (see Figure 2.1 in Appendix A). The channel presently runs in a southeasterly direction for about 450 meters until it joins with the Rumford River.

The majority of the historical operational areas and buildings were located on the northern portion of the property, north of the railroad tracks, and contained process buildings, drip pads, support buildings, an office, and a laboratory. With the exception of the office building, which was outside the remediation area, these structures have been demolished or removed (Sevenson, 2011).

The remedy selected in the ROD for the 1.77-acre Foxborough portion of the site was based on a residential future use scenario because of the residential zoning in place at the time of the 2005 ROD signature. At the time of the ROD, the parcel was unused. During Hatheway & Patterson operations, it may have been used for wood storage. Subsequent to the 2005 ROD, the Town of Foxborough foreclosed on the approximately 1.7 acres of the site located within the Town, with the intent of redeveloping the parcel as a parking lot to service the nearby MBTA commuter rail station. The Town subsequently changed the zoning of the lot from R-40 Residential and Agricultural District to Limited Industrial (LI) district. Modifications were made to the remedy based on this new information as documented in an Explanation of Significant Differences (ESD; USEPA, 2011a).

The 36-acre Mansfield portion of the site is zoned as I-3, which is a flexible mixed-use industrial zone that allows an array of uses from heavy manufacturing to multi-family dwellings to day care. The Town of Mansfield utilizes a portion of the site north of the railroad tracks for storage of emergency vehicles and uses the one remaining building for office space. The site has been used for commercial/industrial purposes intermittently since 1927. The area of the site south of the railroad tracks has historically been used for storage, but has not been developed. During ROD development, the Town of Mansfield notified EPA that the reasonable anticipated future land use (RAFU) of the Mansfield portion of the site will be commercial use for the front parcel located on County Street (north of the railroad tracks) and Open Space or Commercial, for the back parcel (south of the railroad tracks) (USEPA, 2005).

The site and surrounding area are served by municipal drinking water. Groundwater underlying the site is designated as Class III (non-potable) by the Commonwealth of Massachusetts. The remedy outlined in the ROD was based on an assumption that groundwater at the site is not available for drinking water by future users of the site (USEPA, 2005).

3.2 HISTORY OF CONTAMINATION

Initially, the Hatheway & Patterson property consisted only of the land between County Street and the railroad tracks, and the land from the present eastern property boundary to approximately the Rumford River. Hatheway & Patterson reportedly began operations at the site in 1927, but did not begin wood treating until 1953. It is unknown what operations might have been conducted at the site between 1927 and 1953 (USEPA, 2005).

The land west of the Rumford River was owned by the Penn Central Railroad, who used it for bulk chemical transfer and storage of electric/utility poles and railroad ties, until the land was purchased by Hatheway & Patterson in 1978. The land south of the railroad tracks was purchased by Hatheway & Patterson in 1981 and was apparently not used between 1955 and 1971, but was reportedly used for coal storage prior to 1955 (USEPA, 2005).

Wood treatment was accomplished by a variety of methods that changed over time. From 1953 through 1958, a solution of pentachlorophenol (PCP) in fuel oil, or creosote, was used for dipping lumber. After dipping, excess chemicals were allowed to drip off of the treated wood onto the ground surface. From 1958 through 1974, solutions of PCP in fuel oil and fluoro-chrome-arsenate-phenol (FCAP) salts in water were used in a pressure treatment process. From 1960 through 1984, PCP in mineral spirits was also used to pressure-treat lumber. From 1974 to 1984, operations incorporated PCP in fuel oil and chromated copper-arsenate (CCA) salts in water. From 1984 until operations ceased in 1993, solutions of CCA salts in water and PCP in water were utilized at the property. Wood was also infused with fire retardants, including Dricon™ (boric acid and anhydrous sodium tetraborate). The various wood-treating chemicals were stored in aboveground storage tanks (ASTs), underground storage tanks (USTs), and sumps located inside and outside of the former process buildings (USEPA, 2005).

Contamination was initially discovered in 1972, when a tar seep (approximately 62 feet long and 6 inches thick) was discovered on the banks of the Rumford River on the southern portion of the property by representatives of the Town of Mansfield and the MADEQE. Additionally, "oily water and dead fowl were reported in Fulton Pond, downstream of the property" (USEPA, 2005).

3.3 INITIAL RESPONSE

Following the initial discovery of contamination in 1972, Hatheway & Patterson took steps to control the "oily seepage" including booms and sorbents, a collection pit and trench, and other measures including groundwater pumping operations between approximately 1973 and 1982. Under MADEQE requests, Hatheway & Patterson conducted Phase I and Phase II site investigations between 1987 and early 1989. In June 1990, MassDEP (formerly MADEQE) issued a Request for Short Term Measure letter to Hatheway & Patterson to address the imminent hazard to the Rumford River area based on an additional report of "oil seepage" and in response, soil investigation was conducted along river bank. In September 1991, Hatheway & Patterson constructed a collection trench along the eastern bank of the Rumford River to intercept groundwater and oils migrating to the river from oil-contaminated river bank. In February 1992, the collection trench was modified to include groundwater treatment with activated carbon prior to discharge to the Rumford River.

In 1993, Hatheway & Patterson declared bankruptcy, ceased operations, and left the site. In 1993, EPA conducted a PA/SI at the site and, based on the results, a Removal Action was conducted between December 1993 and September 1995. The Removal Action addressed the presence of ASTs and USTs containing hazardous wastes located inside and outside the buildings. Liquid and solid wastes were

removed and disposed off-site. Subsequently, a comprehensive surface soil investigation was conducted and several areas of the property received temporary geotextile/gravel and/or asphalt cover. Also, perimeter fencing was repaired and installed, and locks to manways of tanks and on-site buildings were installed. Following the Removal Action, MassDEP assumed oversight of the property. EPA conducted another Removal Action in 2003 to excavate and dispose off-site the arsenic-contaminated surface soil located outside the perimeter fence. Additional environmental investigations were conducted by MassDEP, EPA, and the Town of Mansfield between 1998 and 2005, when the ROD was completed.

3.4 BASIS FOR TAKING ACTION

Based on the Remedial Investigation (TRC, 2005), the following summarizes the affected media and contaminants:

Surface and Subsurface Soil. In general, surface and subsurface soils contaminated with the highest concentrations of PCP, arsenic, dioxin, and polycyclic aromatic hydrocarbons (PAHs) were located north of the railroad tracks in the Process Area (NE and NW quadrants).

Groundwater. Groundwater at the Site is impacted primarily by arsenic and PCP. Groundwater plumes in both overburden and bedrock flow southwesterly from the Process Area and the light non-aqueous phase liquid (LNAPL) hot spot toward the Rumford River and the Rumford River backwash channel to the south. It was concluded that the extent of contamination in overburden and bedrock groundwater appeared to be confined to the site and bounded by the Rumford River and the backwash channel.

LNAPL. A sizable LNAPL hot spot area was located just south of the railroad tracks in the SE/SW quadrants, near the Process Area. Isolated pockets of free product and LNAPL-saturated subsurface soils were detected throughout the site.

Surface Water. PCP and two PAHs (benzo(a)anthracene and benzo(a)pyrene) were detected above surface water screening criteria in on-site Rumford River surface water samples. The highest concentration of PCP in surface water was detected in an on-site vernal pool sample.

Sediment. Several PAHs were detected in upstream and on-site sediment samples at concentrations exceeding sediment screening criteria. Other semivolatile organic compounds (SVOCs) (2-methylphenol, dibenzofuran, diethyl phthalate, and PCP) and dioxin also exceeded sediment screening levels.

Fish. Fish tissue collected from the Rumford River contained concentrations of PCP and dioxin that were higher in on-site samples than upstream samples.

The baseline human health risk assessment concluded that exposure to surface and subsurface soil in the Process Area (NE and NW quadrants) containing arsenic, dioxin, and pentachlorophenol was associated with an unacceptable human health risk outside EPA's acceptable risk range under current and future exposure scenarios. On-site overburden and bedrock groundwater was also associated with an unacceptable human health risk based on a conservative assumption that the contaminant plume of PCP, arsenic, and chromium will migrate to a location outside the current site boundary and will be used by off-site residents via existing wells on their properties which are currently designated as non-potable.

The baseline ecological risk assessment concluded that benthic invertebrates, water column invertebrates, fish, piscivorous birds and mammals feeding along the Rumford River are unlikely to be at a substantial risk from exposure to site-related contaminants.

SECTION 4.0 REMEDIAL ACTIONS

4.1 REMEDY SELECTION

The EPA ROD for the site was signed on September 30, 2005. Remedial Action Objectives (RAOs) were developed for various media at the site based on the results of the RI and risk assessments. The RAOs were developed to aid in the development and screening of remedial alternatives.

The RAOs for the selected remedy for the site are:

- Surface Soil (Process Area) – Prevent current and future trespassers and future on-site residents (Foxborough parcel), commercial workers, town workers, and utility workers from ingestion of or dermal contact with Contaminants of Potential Concern (COPCs) (including arsenic, dioxin, and PCP) which would result in a cumulative excess cancer risk greater than 10^{-4} to 10^{-6} or $HI=1$;
- Subsurface Soil (Process Area) – Prevent future commercial workers and future on-site residents (Foxborough parcel) from ingestion of or dermal contact with COPCs (including arsenic, dioxin, and PCP) which would result in a cumulative risk greater than 10^{-4} to 10^{-6} or $HI=1$;
- Groundwater – Prevent discharge of pentachlorophenol and other COPCs from soil to groundwater and from groundwater to surface water at concentrations that would result in an in stream exceedence of the Ambient Water Quality Criteria (AWQCs) through source control. Prevent exposure to groundwater by future residents, recreational users, or commercial workers by monitoring extent of plume (to ensure it is remaining on-site) and implementing institutional controls to restrict groundwater use within the site boundary;
- Inter-Media Transfer – Eliminate or reduce potential for leaching through source control and inter-media transfer of COPCs from soil to groundwater and surface water;
- LNAPL – Minimize further contaminant transfer from LNAPL source material to groundwater by reducing LNAPL source material in soil excavation/treatment areas. Minimize further migration of LNAPL free product to groundwater and surface water by removing free product “hotspots” to the extent feasible.

The selected remedy for the site consisted of the following components:

- Excavation of approximately 31,000 cubic yards of soil exceeding cleanup levels.
- Demolition of the buildings in and near Hatheway & Patterson’s former manufacturing area to allow excavation of underlying contaminated soils and replacement of the excavated soil with clean backfill.
- Excavation of soils containing PCP, SVOCs, and arsenic, and testing of soils for leachability and, if they fail, utilization of a stabilization/solidification agent(s). Consolidation of the stabilized/solidified soils on-site under a low-permeability cover.
- Off-site disposal of soils containing dioxin and oily material (LNAPL) at a licensed facility.
- Institutional controls to prohibit the use of site groundwater and restrict land uses in a manner that ensures the protectiveness of the remedy as described in this ROD, and ensures the integrity of the on-site low-permeability cover and other remedial components. Evaluation of risks from soil exposures within the area of the existing railroad right of way during design and implementation of appropriate action such as deed restrictions or other legal and administrative measures if necessary.

- Long term monitoring of groundwater, surface water, fish tissue and sediment.
- Five-year reviews, and operation and maintenance of remedial components, including the low permeability cover

An ESD (USEPA, 2011a) was issued in August 2011 in order to document certain changes and clarifications to the remedy that was set forth in the ROD. The ESD had three main purposes as summarized below.

The remedy outlined in the ROD for the Foxborough parcel was based on future residential use of the parcel, as the property was zoned for residential use in 2005. After the ROD was issued, the Town of Foxborough took ownership of the parcel through tax foreclosure with the intent of redeveloping the parcel as a parking lot. In connection with this plan, the town voted at the May 2008 Town Meeting to adopt a change in zoning of the lot from R-40 Residential and Agricultural District to "Limited Industrial." The Town notified EPA of its intention to use the parcel as a parking facility for the nearby MBTA commuter rail station. Based on the change in zoning and intended reuse of the parcel, EPA and MassDEP determined that the Foxborough parcel should be remediated to a Reasonably Anticipated Future Use (RAFU) of commercial/open space and changed the cleanup level accordingly from 9.1 ppm to 16 ppm for arsenic and to 90 ppm for PCP (note that there was no Residential Cleanup Level for PCP in the ROD). EPA also determined that a consolidation area for soils in Foxborough contaminated with arsenic could be built on the Foxborough parcel and designed with an asphalt cover in order to facilitate reuse as a parking facility.

Second, EPA reevaluated the remedy for PCP and arsenic-contaminated soils excavated from the lots in the Mansfield portion of the site. The remedy chosen in the ROD called for on-site consolidation of these soils, rather than disposal at an off-site facility. Subsequent to the signing of the ROD, the relative costs of off-site disposal decreased significantly. EPA reevaluated both options using criteria required under CERCLA to compare different remedial options. The criteria included overall protection, long-term effectiveness and permanence, community support, and cost. The remedy was changed since the costs were similar, but the off-site disposal option offered the greatest overall protection, long-term protectiveness, and permanence.

Lastly, EPA clarified the extent of institutional controls to be placed on the site properties as called for in the ROD. Specifically, restrictions on future soil excavation, in the form of institutional controls, will be needed in the northeast quadrant of the site: 1) below the depth of the vertical extent of excavation reached during the remedial action (RA); and 2) at depths of two feet and below in a strip of land bordering the northeast quadrant and County Street to a distance about 5 feet laterally with the fence line. Institutional controls will also be necessary to protect the cover placed over the consolidated soils in the Foxborough parcel.

Risks from soil exposures within the area of the existing railroad right of way were evaluated during design and remedial action as specified by the ROD and institutional controls or other legal and administrative measures were deemed not to be necessary. The ESD stated that risk from the railroad right of way would be reevaluated as part of the five-year review process for the site. In addition, institutional controls to eliminate on-site exposures to groundwater and to prevent residential use will be necessary on all four quadrants of the site property.

4.2 REMEDY IMPLEMENTATION

Through an Interagency Agreement with EPA Region I, the U.S. Army Corps of Engineers New England District (USACE) contracted with Severson Environmental Services (Severson) to perform the remedial construction in accordance with Construction Specifications developed by Metcalf & Eddy and TRC Corporation (TRC, 2008). USACE provided construction management technical oversight.

Remedial construction activities commenced in September 2009 and were substantially completed in September 2010. The work conducted included the following:

- mobilization;
- geotechnical investigation;
- preparation of all required infrastructure including the construction of two small bridges;
- demolition and off-site disposal of one on-site building, including asbestos abatement;
- removal and disposal of six underground storage tanks;
- removal and disposal of all surficial and subsurface concrete and asphalt within the northeast and northwest quadrants of the site;
- installation of groundwater monitoring wells and groundwater sampling;
- pre-excavation soil investigation for waste characterization and to refine excavation limits;
- excavation of contaminated soils in the northeast, northwest, and southeast quadrants;
- consolidation of arsenic contaminated soils from the Foxborough parcels and installation of an asphalt cover over the consolidation area; and
- site restoration and demobilization.

A total of 34,000 tons of soil was removed from the NE and NW quadrants and 9,500 tons of soil was removed from the SE quadrant for off-site disposal as non-hazardous waste.

Buffer zone planting was initially completed in the fall of 2010 and then monitored for the first year after planting. Replanting of some trees was determined to be needed and was conducted in September 2011. Final inspection of the remedy construction occurred in September 2011.

Operation and maintenance of the remedy is currently being performed as described below. Institutional controls, as required by the ROD and ESD, are being prepared, but have not yet been implemented.

4.3 OPERATION AND MAINTENANCE

Operation and maintenance (O&M) of the remedy for the Hatheway & Patterson Site is being performed in accordance with the ROD and the O&M Manual (USEPA, 2011b). MassDEP is the lead agency performing O&M of the site.

The ROD required long-term monitoring of groundwater, surface water, fish tissue and sediment and operation and maintenance of the low-permeability cover. The monitoring frequencies and timing were described in the ROD as follows: 1) annual monitoring of sediment and surface water until completion of the first five-year review; 2) one round of fish tissue sampling in conjunction with the five-year review; and 3) sampling of on-site and off-site groundwater twice a year, every other year, until the first five-year review and continued monitoring after the five-year review in accordance with the O&M Manual to ensure that contaminated water is not impacting off-site receptors and to ensure protectiveness of the remedy. In addition to the monitoring schedule described in the ROD, the O&M Manual specifies annual monitoring of groundwater following the first five-year review and sampling of sediment, surface water, and fish tissue once every five years following the first five-year review. Maintenance activities required by the O&M Manual include inspections and maintenance of the asphalt cover, storm filter, catch basins and monitoring wells. Surface water sampling required by the ROD was not performed and frequency of sediment sampling was reduced due to EPA and MassDEP's agreement to continue discussions about the future operation and maintenance plan requirements for the site, as a result of changes to the remedy, which were documented in the ESD.

Inspections of the asphalt cover, storm filter, monitoring wells, and site security measures (fence, gates, locks, and signage) were conducted in May 2012, October 2012, April 2013, and November 2013 in conjunction with the groundwater monitoring events. No significant issues were noted.

To date, five rounds of groundwater monitoring were conducted since remedy construction: May 2011, May 2012, and October 2012, April 2013, and October/November 2013. Sediment monitoring was performed in May 2012 and a fish survey was conducted in June 2013. Monitoring activities were performed by subcontractors to MassDEP. A discussion of the monitoring results is provided in Section 6.3.

In addition to the sampling activities, a hydrogeological conditions report was prepared in 2013 (AECOM, 2013) which summarized the groundwater flow and groundwater quality data collected during the RI/FS, RD, and the RA. The report also presented recommendations for additional investigations and potential locations for new monitoring wells that may be needed to confirm that contaminated groundwater is not migrating beyond the site compliance boundary. A summary of the evaluation and resulting recommendations is provided in Section 6.3.1.

4.4 Institutional Controls

In order for the remedy at the Hatheway & Patterson Site to be protective in the long-term, institutional controls need to be created and recorded to restrict inappropriate land uses (including use of groundwater) and protect the consolidation area cover. The remedy is protective in the short-term, as there is no current use of on-site groundwater, and operation and maintenance activities ensure that the consolidation area and associated components of the remedy (e.g., groundwater monitoring wells) remain in good condition.

Implementation of institutional controls (ICs) in Massachusetts, namely the recording of Grants of Environmental Restrictions and Easements (GEREs), has been a continued challenge for EPA. The need to complete ICs has often been identified as an issue potentially impacting future protectiveness as part of five-year reviews at this and other Massachusetts sites. In an effort to address this issue and improve the process of completing ICs at Massachusetts NPL sites, EPA worked with the MassDEP to develop a new approach using Notices of Activity and Use Limitations (AUL Notices). This process involved first working with MassDEP to update and amend their regulations governing AULs (both Notices and GEREs) embodied in the Massachusetts Contingency Plan (310 CMR 40.0000). The MCP amendments published in May 2014 included new requirements allowing for use of AUL Notices at NPL sites. EPA and MassDEP are currently working on model documents and forms that will be used to implement AUL Notices. Once fully implemented, the overall process for IC implementation will be streamlined as AUL Notices do not require the signature of the MassDEP Commissioner nor do they require Subordination Agreements from those holding prior encumbrances on properties. Both of these requirements served to slow the GERE implementation process at many sites. EPA and MassDEP will work together to determine whether specific circumstances at sites still require GEREs or whether the new AUL Notices can be used instead. This new approach to ICs in Massachusetts should allow EPA to complete these activities more quickly and efficiently and implement ICs at the site within a reasonable timeframe. Implementation of the necessary Hatheway & Patterson ICs will follow the above approach.

SECTION 5.0
PROGRESS SINCE THE LAST FIVE YEAR REVIEW

This is the first five-year review for the Hatheway & Patterson Site.

SECTION 6.0 FIVE-YEAR REVIEW PROCESS

This section describes the activities performed during the five-year review process and provides a summary of findings. The Hatheway & Patterson Superfund Site Five-Year Review was led by Kimberly White of the U.S. EPA, Remedial Project Manager for the Site, and Emily Zimmerman, the Community Involvement Coordinator (CIC). Gary Waldeck, of the MassDEP, assisted in the review as the representative for the support agency.

The review, which began in February 2014, consisted of the following components:

- Community Involvement;
- Document Review;
- Data Review;
- Site Inspection; and Five-Year Review Report Development and Review.

6.1 COMMUNITY NOTIFICATION AND INVOLVEMENT

On February 13, 2014, EPA issued a press release announcing that EPA was beginning five-year reviews of 27 Superfund sites across New England, including the Hatheway & Patterson site. A similar press release will be issued by EPA once the five-year reviews are complete.

6.2 DOCUMENT REVIEW

This five-year review included a review of relevant documents for the site including the ROD, the 2011 ESD, the Remedial Action Completion Report, and site groundwater and sediment monitoring data as presented in various reports prepared by MassDEP's contractors. See Appendix B for a list of documents that were reviewed and other references.

6.3 DATA REVIEW

As noted in Section 4.2.3, there have been a number of field monitoring efforts since the remedial action was completed. These results are summarized in this section. A summary of the site hydrogeology, the results of three rounds of groundwater monitoring, one round of sediment monitoring, and a fish survey performed by subcontractors for MassDEP are also provided in this section. Surface water sampling was not conducted during the five year review period due to EPA's and MassDEP's agreement to continue discussions about the future operation and maintenance plan requirements for the site following completion of the ESD in 2011.

In addition to monitoring required in the ROD and O&M Plan, several off-site private wells were sampled. These wells were identified during a review of information from the Mansfield Board of Health during preparation of a hydrogeologic conditions report in 2013 (discussed below), and were determined to be used either for irrigation or for industrial purposes.

6.3.1 Hydrogeology

A hydrogeological conditions report was prepared in 2013 (AECOM, 2013) which summarized the groundwater flow and groundwater quality data collected during the RI/FS, the RD, and the RA. The report also presented recommendations for additional investigations and potential locations for new monitoring wells that may be needed to confirm that contaminated groundwater is not migrating beyond the site compliance boundary. For reference, the compliance boundary defined in the 2005 ROD is the property boundary on the south side of the site, the Rumford River backwash channel on the west side of the site, and the Rumford River on the north side of the site. Figure A-1 in Appendix A presents

monitoring locations discussed in this section.

Groundwater generally flows to the west-southwest, toward the backwash channel (see Figures 2 and 3 in Appendix A, originally from the RI report). The piezometric surface map indicates that if site contaminants were going to migrate beyond the compliance boundary, they would most likely do so along the backwash channel on the west side of the site. Although migration of contaminated groundwater beyond the compliance boundaries on the north and south sides of the site is less likely, those possibilities are also discussed below.

Flow to the North. The compliance boundary to the north of the site is the Rumford River. Groundwater flow to the north is not indicated by the available piezometric surface data. Furthermore, the Rumford River is a major discharge feature, and it is reasonable to anticipate that groundwater would not flow beneath it to the north or northwest unless there were a pumped well or other groundwater “sink” in that direction. No such “sinks” are known to exist in that direction. Furthermore, the absence of contamination in MW-107 and MW-107R, which are west of the site but north of the Rumford River, suggests that plumes are not migrating past the compliance boundary on the north side of the site.

Flow to the West/Southwest. The compliance boundary to the west of the site is the backwash channel. This stream and wetland area appears to be a groundwater discharge zone, and it is reasonable to anticipate that groundwater would not flow beneath it and continue flowing to the west or southwest unless a pumped well or other groundwater “sink” existed in that direction.

The available information suggests that groundwater flow beyond the backwash channel is unlikely under natural conditions. However, a review of a list of private wells from the Mansfield Board of Health (BOH) indicated that three of the parcels on Highland Avenue have permits for “domestic auxiliary” (DA) water wells (see Figure 5 in Appendix A). The existence of two of these wells was confirmed during the site inspection. The well at 136 Highland Avenue is a driven point and is 12 feet deep, according to the owner. Although the well at 132 Highland Avenue is completely below ground and therefore not visible, it is suspected to be of similar construction. Shallow driven well points are probably less likely than bedrock wells to pull contaminated groundwater beneath the backwash channel since, unlike overburden wells, bedrock wells could be connected to the groundwater beneath the backwash channel by discrete fractures that could act as preferential pathways. Nonetheless, with heavy prolonged use during the dry season, the possibility cannot be discounted that the shallow well points could create gradients that would cause groundwater to cross beneath the compliance boundary.

The existence of the third possible well on Highland Avenue could not be confirmed. Figure 5 in Appendix A also shows four DA wells farther to the west, beyond the wells on Highland Avenue. Three of these wells have been confirmed not to exist, and the owner of the fourth property with a possible well did not respond to EPA’s inquiries. In June 2014, EPA collected groundwater samples from the two wells on Highland Avenue. The results are discussed in Section 6.3.2.

While movement of groundwater beyond the backwash channel/compliance boundary in response to groundwater withdrawals from the wells on Highland Avenue is possible, the absence of contamination in MW-109R suggests that a plume is not migrating past the backwash channel to the north of those wells. If additional wells are to be installed to investigate possible migration beyond the compliance boundary, the wells should be located opposite the MW-111 and MW-113 well clusters (see Figure A-1 in Appendix A), where moderate to high concentrations of PCP have been recently detected and where there are currently no monitoring wells west of the compliance boundary.

Flow to the South. Prior to the early to mid-1950’s, the backwash channel was the course of the Rumford River as it flowed south and crossed what is now Howe Street, Chauncy Street (Rt. 106), and the main railroad tracks south of the site. Sometime between 1951 and 1956, at approximately the same time that wood treatment operations began at the site, the Rumford River was diverted west into a new channel, and the backwash channel became a backwater and wetland. It is assumed that the former riverbed between the site and the railroad tracks south of Rt. 106 was filled with soil, and that no underdrains were placed in the filled channel. As a result, water levels would have risen in the filled area

between Howe Street and Rt. 106, and the backwash channel would have been forced to drain to the north into the new Rumford River channel. An aerial photograph of this area from 1977, which shows ponding of water at the southern end of the backwash channel, supports this conclusion, as does the observation of northwestward flow in the backwash channel during a site visit in 2010 and during the recent site inspection. Higher groundwater levels to the south would have prevented movement of plumes in that direction, so it is unlikely that contaminated groundwater would have flowed south from the site.

The review of the list of private well records from the Mansfield BOH indicated the possible presence of non-drinking water industrial/commercial auxiliary (ICA) and domestic auxiliary (DA) supply wells to the south of the site (see Figure 5 in Appendix A). The four wells that are closest to the site are listed as follows: 18 Thomas Street, ICA well for a laundry facility; 46 Chauncy Street, DA well for a car wash; 325 N. Main Street, DA well for irrigation; and 17 Pratt Street, no permit and use unknown. During the recent site inspection, the existence of three of these wells was confirmed. The well at 18 Thomas Street is reportedly a gravel-packed overburden well about 35 feet deep (used for laundry business); the well at 46 Chauncy Street is reportedly a bedrock well about 800 feet deep (used for car wash, “fracked” to increase yield); and the well at 325 North Main Street is a driven point (used for lawn irrigation). In addition, it was learned that permanent dewatering systems exist at the two railroad underpasses at Route 106 and North Main Street. While the three confirmed wells and the Route 106 underpass are about 1,000 feet from the site and do not appear to be downgradient, samples were collected by EPA in June 2014 to confirm that site contaminants are not following an unlikely pathway to the south in response to the combined pumping. The underpass at North Main Street is also not believed to be downgradient of the site; furthermore, the water from the dewatering system is discharged to the backwash channel wetland, which would tend to limit the effect of the dewatering at the site. Sampling results are discussed in Section 6.3.2.

6.3.2 Groundwater Monitoring Results

Groundwater monitoring for remedy compliance has been performed multiple times since completion of remedy construction: May 2011, May 2012, October 2012, April 2013, and October/November 2013. Locations both inside and outside the compliance boundary have been selected for this long-term compliance monitoring. Figure A-1 in Appendix A presents the locations sampled during the events. It should be noted that an apparent field error resulted in a sample being incorrectly collected from an interior well (RCA-8) rather than the planned perimeter well (RCA-9) in the two 2012 monitoring rounds.

Analyses included the three analytes which have performance standards established in the ROD: PCP, arsenic, and chromium. Maximum Contaminant Levels (MCLs) were identified in the ROD as groundwater performance standards at the site compliance boundary. As dioxins are a known site contaminant, dioxin congeners (forms of dioxin differing only in the number and location of chlorine atoms) were also analyzed and compared to the dioxin MCL (following conversion to a dioxin toxicity equivalency [TEQ]). Appendix C presents results from each monitoring round, as well as a summary table (Table C-1) compiling the monitoring rounds along with historical results for comparison purposes. As shown in this table, there have been no exceedances of compliance boundary performance standards in the wells located beyond the compliance boundary. However, detection limits for PCP in the 2012 monitoring events exceeded the performance standard. Other monitoring rounds did not show detections of PCP in these wells with lower detection limits. There were detections of the four analytes in interior wells, but no exceedances of on-site performance standards established for protection of surface water.

As described in the previous section, non-potable DA/private wells were sampled for metals, PCP and dioxins in June 2014. Figure 6 in Appendix A shows the location of the wells sampled. The monitoring event summary memorandum and analytical data are presented in Appendix C. The results showed no exceedances of MCLs for metals or dioxin. There was only one PCP detection (2.7 µg/L), but this detection was also above the MCL (1 µg/L). Based on a brief review of this non-potable well (shallow) and its location relative to the site, the detection is not likely site-related. In addition, there were no detections above MCLs in the other wells in the same area. However, further investigation/evaluation will be performed to confirm this.

6.3.3 Sediment Monitoring Results

The 2005 ROD included annual sediment monitoring prior to the first five-year review as part of the long-term monitoring to document conditions at and near the site. Monitoring was performed in May 2012 at four locations in the Rumford River (see Figure 1 included in Appendix C). These four sampling locations were different from the sampling locations used prior to the remedial action. Some or all of the previous locations were inaccessible during the May 2012 sampling event due to modifications of the riverbank made during the remedial action. Similar to the groundwater monitoring, samples were analyzed for dioxins, PCP, arsenic, and chromium. Appendix C presents results from the monitoring event, as well as a summary table (Table C-3). As there were no sediment performance standards in the ROD or ESD, the table presents historical statistical data (e.g., maximum detections) from the 2004/2005 risk assessments for comparison purposes. All detections in the 2012 monitoring event were below the historical maximum detections, except for one dioxin congener (1,2,3,7,8,9-HxCDF). Further discussion of these results as they relate to the risk assessments can be found in Section 7.2. Only one round of sediment sampling was conducted before this five year review due to MassDEP's interpretation of the monitoring requirements described in the Operations and Maintenance Plan. MassDEP and EPA will determine the locations and frequency of any additional sediment samples to be obtained before the next five year review.

6.3.4 Fish Survey

The 2005 ROD recommended a round of fish tissue sampling to be performed in conjunction with the five-year review. A fish survey was conducted during June 2013 at three locations along the Rumford River. The sampling procedures and results are summarized in a report prepared by Environmental Strategies and Management, Inc., dated October 1, 2013 (ESM, 2013). The report documents that no fish were collected in Area 1, which was a reference area located upstream of the site. In both Area 1 (reference) and Area 2 (on site between County Street and the railroad tracks), only crayfish were collected, and no fish were observed. In the downstream area of the river (Area 3, located approximately 400 feet downgradient of the site, immediately upstream of where Henkes Brook flows into the Rumford River), a few crayfish and fish were observed as part of the survey. Fish samples were not collected at that time; however, EPA and MassDEP will determine what, if any, samples can be collected before the next five year review.

6.3.5 Surface Water Monitoring

Surface water sampling has not yet been implemented at the Site. However, on-site groundwater performance standards established to protect surface water have been monitored and have not been exceeded. Surface water monitoring is required under the 2005 ROD, and the O&M Manual was based on the remedy selected in the ROD; however, due to changes in the remedy outlined in the ESD (no on-site consolidation of PCP and arsenic contaminated soils in the Mansfield portion of the Site), MassDEP and EPA determined that the requirement to sample surface water would be further discussed. EPA and MassDEP will evaluate whether surface water sampling is necessary or whether monitoring of the groundwater performance standards is sufficient to determine impacts to surface water.

6.4 SITE INSPECTION

A site inspection was performed by the EPA Project Manager and AECOM on June 3, 2014. The MassDEP Project Manager was also present for part of the inspection. The inspection included cursory examinations of the site fences and gates; the asphalt cover on the Foxborough portion of the site that is used as a commuter parking lot; a subset of the site monitoring wells; and the Rumford River and its confluence with the backwash channel. The site inspection checklist and photographs from the site inspection are included in the Management System Review (MSR) Technical Memorandum in Appendix D.

The site was observed to be secure, and no evidence of trespassing or vandalism was noted. The NW Quadrant of the site is mostly covered with crushed rock except for a vegetated buffer along the Rumford River and a commuter parking lot for the Town of Foxborough in the extreme northwest corner. As described in the site inspection checklist, the parking lot is well maintained, and the fencing and gates that surround the entire NW and NE Quadrants of the site are in good condition (except for very minor damage to the stockade fence on the northwest side of the commuter lot).

The monitoring wells that were observed were locked and appeared to be in good condition. The compliance boundary on the southwest side of the site is the backwash channel, which is a vegetated marshy area and is difficult to traverse. Where observed near its confluence with the Rumford River, the amount of water in the backwash channel was miniscule, and no flow was observable. However, at the actual confluence, it was confirmed that the trickle of flow in the channel was moving northwest and discharging to the river. The wells along the compliance boundary had been sampled several weeks before the site inspection and were found to be in good condition, and therefore were not inspected.

6.5 INTERVIEWS

Representatives of the Town of Mansfield DPW and the Town of Foxborough, and the MassDEP Project Manager each responded to a request for an interview by providing written responses to a series of interview questions. Appendix E includes a detailed summary of the interviews. In general, representatives from both towns were very pleased with the work conducted at the site. The town representatives stated that they have been well informed throughout the process and that they have no concerns. The representative from the Town of Mansfield would like to see the institutional controls implemented so that the town can move forward with potential reuse of the property. Town of Mansfield personnel periodically inspect the site. It was noted by the representative from Mansfield that, although vandalism has generally not been an issue at the site, a few fence cuts in the deep woods have been found. EPA has followed up with the town and is waiting for an update on the status of the repairs. The Project Manager for the MassDEP also stated that the project was a success, that he was well informed, and that he has no concerns.

SECTION 7.0 TECHNICAL ASSESSMENT

This section discusses the technical assessment of the remedy for the site and provides answers to the three questions posed in the EPA guidance for five-year reviews (USEPA, 2001).

7.1 Question A: Is the remedy functioning as intended by the decision documents?

Yes. The remedy resulted in the removal of soil to the ROD cleanup levels and/or on-site consolidation under a protective cover. Site related groundwater contaminants have not been detected beyond the compliance boundary at concentrations exceeding performance standards, nor on-site at concentrations exceeding performance standards established to protect surface water. However, institutional controls, as required under the ROD and ESD, have not been established yet.

The groundwater monitoring program may be modified via recommendations presented in the recent hydrogeological evaluation report (AECOM, 2013; see Section 6.3.1).

7.2 Question B: Are the exposure assumptions, toxicity data, cleanup levels, and remedial action objectives (RAOs) used at the time of remedy selection still valid?

No. EPA's dioxin reassessment has been developed and undergone review for many years, with the participation of scientific experts in EPA and other federal agencies, as well as scientific experts in the private sector and academia. The Agency followed current guidelines and incorporated the latest data and physiological/biochemical research into the reassessment. On February 17, 2012, EPA released the final human health non-cancer dioxin reassessment, publishing an oral non-cancer toxicity value, or reference dose (RfD), of 7×10^{-10} mg/kg-day for 2,3,7,8-tetrachlorodibenzo-p-dioxin (TCDD) in EPA's Integrated Risk Information System (IRIS). The dioxin cancer reassessment will follow thereafter. The dioxin RfD was approved for immediate use at Superfund sites to ensure protection of human health.

These changes do not affect the current protectiveness of the remedy. However, institutional controls will now also be required along the railroad right-of-way due to changes in toxicity values (see below).

7.2.1 Review of Human Health Risk Assessment

The baseline human health risk assessment performed in 2005 (M&E, 2005) concluded that there would be significant risk to human health if groundwater from the site containing VOCs, SVOCs, dioxins, and metals was used as a potable water supply in the future. The risk assessment further determined that the following exposures to site soil exceeded EPA risk management guidelines:

- Adolescent trespasser, due primarily to arsenic in surface and subsurface soil;
- Town worker, due primarily to arsenic in surface soil;
- Commercial worker, due primarily to dioxin and arsenic in surface soil, and pentachlorophenol and arsenic in subsurface soil;
- Utility worker, due primarily to arsenic in surface soil; and
- On-site resident (Foxborough only), due primarily to dioxin, arsenic, and chromium in surface soil, and pentachlorophenol and arsenic in subsurface soil.

While there were no exceedances of EPA's risk management guidelines due to exposures of site surface water and sediment, it was noted in the 2005 ROD that, for the surface water and groundwater dermal contact pathways, risk associated with dermal absorption could not be quantified for all contaminants (due to lack of chemical-specific dermal absorption factors). This uncertainty was noted as something that needed to be periodically reviewed as changes in dermal exposure assessment occurred.

MCLs were selected as compliance boundary groundwater performance standards for pentachlorophenol, arsenic, and chromium. Additional onsite groundwater performance standards for the

protection of surface water were developed based on Massachusetts ambient water quality criteria and dilution associated with groundwater and river discharge. Risk-based soil cleanup levels were developed based on site-specific exposure assumptions used in the human health risk assessment.

The 2005 ROD also noted that soil exposures within the area of the existing railroad right of way would be evaluated during design, with appropriate action being implemented as necessary. This evaluation was performed by EPA initially in 2007, using existing site data, and then updated in 2011 using data collected in 2010 during the remedial action (Sevenson, 2011). The results indicated that risks were within the acceptable risk range in the railroad right of way and that, therefore, deed restrictions were not required. The 2011 ESD recommended a review of this risk evaluation during the five-year review. EPA completed this review in June 2014 utilizing updated toxicity information, and determined that the potential estimated exposure exceeds the acceptable level of 1 for hazard index, but that the exposure scenario is unlikely to occur at the railroad right-of-way. Details of the review are provided in the June 2014 memo in Appendix F. The implementation of institutional controls regulating land use in the railroad right-of-way is necessary to assure that construction and utility worker exposures do not occur in the future.

The 2011 ESD included a change in the anticipated future land use on the Foxborough parcel, from “residential” to “limited industrial” zoning, with the property being used as a parking facility. This change resulted in a reevaluation of the arsenic cleanup level designated in the 2005 ROD. It was concluded that the cleanup level being used for the rest of the site (for commercial/open space areas) was also protective for the Foxborough parcel.

In this five-year review report, the toxicity values that served as the basis for the soil cleanup levels, as contained in the 2005 ROD, have been re-evaluated to determine whether any changes in toxicity impact the protectiveness of the remedy. Changes in toxicity values since the 2005 risk evaluation are also discussed to determine whether reuse decisions remain valid. Any changes in current or potential future exposure pathways or exposure assumptions that may impact remedy protectiveness are also noted. In addition, environmental data, available since the 2005 ROD and implementation of the remedy, have been qualitatively evaluated to determine whether exposure levels existing at the site present a risk to current human receptors.

Changes in Toxicity

Table 2 presents a summary of the changes in toxicity values (oral reference doses and oral cancer slope factors) for compounds selected as COPCs as identified in the 2005 risk assessment. Updated toxicity information was obtained from the Integrated Risk Information System (USEPA, 2014a) and other current EPA sources (e.g., the Superfund Health Risk Technical Support Center). Note that an increase in an oral reference dose will decrease the resulting hazard quotient, while an increase in an oral slope factor will increase the resulting cancer risk.

For most contaminants, any changes to toxicity information have been minimal and most would not have any impact on selected site Contaminants of Concern (COCs) or remedy protectiveness. It should be noted that not all site COCs (i.e., analytes which exceeded EPA's risk criteria) were utilized when developing performance standards to protect receptors outside of the groundwater compliance boundary. Therefore, although 1,1'-biphenyl would have been selected as a COC based solely on changes in toxicity values, it would likely not have been used to set a performance standard. Furthermore, groundwater performance standards were developed based either on water quality standards or federal MCLs, so changes to toxicity values would not impact the performance standards.

With respect to soil, if chromium at the site is evaluated as hexavalent chromium (typical unless speciation or other justification is available), it would also have been selected as a COC based on the changes in toxicity values. It was likely co-located with the other soil COCs which were remediated (either excavated or covered), which would therefore not impact remedy protectiveness.

A noteworthy change between 2005 and 2014 toxicity values is for dioxin. EPA's dioxin reassessment has been developed and undergone review for many years, with the participation of scientific experts in EPA and other federal agencies, as well as experts in the private sector and academia. The Agency followed current guidelines and incorporated the latest data and physiological/biochemical research into the reassessment. On February 17, 2012, EPA released the final human health non-cancer dioxin reassessment, publishing an oral non-cancer toxicity value, or RfD, of 7×10^{-10} mg/kg-day for TCDD in EPA's IRIS database. The dioxin cancer reassessment is ongoing. The dioxin RfD was approved for immediate use at Superfund sites to ensure protection of human health. While dioxin was already a COC in groundwater and soil (based on cancer risk), the new oral reference dose would have also resulted in a hazard quotient above 1 for a nearby resident wading in the Rumford River, based on sediment exposure. The sediment exposure point concentration (EPC) used for dioxin TEQ (toxicity equivalency) in 2005 was 1,641 ng/kg. The maximum dioxin TEQ resulting from sediment detections in 2012 was 173 ng/kg (see Appendix C), which results in a hazard quotient equal to 1 when applying the site-specific parameters utilized in the 2005 Human Health Risk Assessment (HHRA). Therefore, the remedy is still considered protective.

In addition, based on a compilation and review of data on relative bioavailability of arsenic in soil (USEPA, 2012), arsenic was found to be less bioavailable via soil ingestion relative to other analytes. A default value of relative bioavailability (RBA) of 60% is now applied during soil/sediment ingestion calculations of risk/cleanup levels. This default RBA value reduces arsenic contribution to risk and/or increases arsenic cleanup levels. The remedy remains protective with respect to arsenic exposures.

Table 2: Comparison of 2005 and 2014 Oral Reference Doses and Oral Cancer Slope Factors for Compounds of Potential Concern

Contaminant of Potential Concern	Oral Reference Dose (RfD) (mg/kg-day)		Oral Slope Factor (SF) (mg/kg-day) ⁻¹	
	2005	2014	2005	2014
1,1,2-Trichloroethane	0.004	0.004	0.057	0.057
1,2-Dichloroethane	0.02	0.006	0.091	0.091
Trichloroethene	0.0003	0.0005	0.4	0.046
Vinyl chloride (a)	0.003	0.003	0.75	0.72
Xylenes (total)	0.2	0.2	N/A	N/A
1,1'-Biphenyl	0.05	0.5	N/A	0.008
2,3,5,6-Tetrachlorophenol	0.03	0.03	N/A	N/A
2,4,6-Trichlorophenol	0.0001	0.001	0.011	0.011
2,4-Dinitrophenol	0.002	0.002	N/A	N/A
2,6-Dinitrotoluene	0.001	0.0003	0.68	1.5
2-Methylnaphthalene	0.004	0.004	N/A	N/A
4,6-Dinitro-2-methylphenol	0.0001	0.00008	N/A	N/A
Acenaphthene	0.06	0.06	N/A	N/A
Acenaphthylene (c)	0.02	0.06	N/A	N/A
Acetophenone	0.1	0.1	N/A	N/A
Atrazine	0.035	0.035	0.22	0.23
Benzo(a)anthracene	N/A	N/A	0.73	0.73
Benzo(a)pyrene	N/A	N/A	7.3	7.3
Benzo(b)fluoranthene	N/A	N/A	0.73	0.73
Benzo(k)fluoranthene	N/A	N/A	0.073	0.073
Bis(2-ethylhexyl)phthalate	0.02	0.02	0.014	0.014
Chrysene	N/A	N/A	0.0073	0.0073

Contaminant of Potential Concern	Oral Reference Dose (RfD) (mg/kg-day)		Oral Slope Factor (SF) (mg/kg-day) ⁻¹	
	2005	2014	2005	2014
Dibenz(a,h)anthracene	N/A	N/A	7.3	7.3
Dibenzofuran	0.002	0.001	N/A	N/A
Fluorene	0.04	0.04	N/A	N/A
Indeno(1,2,3-cd)pyrene	N/A	N/A	0.73	0.73
Naphthalene	0.02	0.02	N/A	N/A
Pentachlorophenol	0.03	0.005	0.12	0.4
Phenanthrene (c)	0.02	0.03	N/A	N/A
2,3,7,8-TCDD (Dioxin TEQ)	N/A	7E-10	1.5E+05	1.56E+05
Antimony	0.0004	0.0004	N/A	N/A
Arsenic	0.0003	0.0003	1.5	1.5
Barium	0.07	0.2	N/A	N/A
Cadmium (food)	0.001	0.001	N/A	N/A
Cadmium (water)	N/A	0.0005	N/A	N/A
Chromium	0.003	0.003	N/A	0.5
Lead (b)	N/A	N/A	N/A	N/A
Manganese (drinking water)	0.024	0.024	N/A	N/A
Manganese (diet)	0.07	0.14	N/A	N/A
Mercury	0.0001	0.0001	N/A	N/A
Thallium	0.00008	0.00001	N/A	N/A
Vanadium	0.001	0.005	N/A	N/A
Zinc	0.3	0.3	N/A	N/A

N/A = Not Applicable or Not Available

a. Vinyl chloride has toxicity values for both adult and child to account for mutagenic mode of action (see discussion below).

Toxicity values presented in table are for adult receptors.

b. Lead is currently evaluated through the use of exposure modeling for adults and children.

c. Naphthalene was used as a surrogate in the 2005 HHRA. Based on toxicity changes since that time, it would be considered more appropriate to use acenaphthene as a surrogate for acenaphthylene and pyrene as a surrogate for phenanthrene due to structural similarities.

Changes in Exposure Pathways/Assumptions

Since the 2005 HHRA, the Foxborough parcel was rezoned such that residential use is no longer applicable (it is now a parking facility). The 2011 ESD changed the cleanup levels for this parcel to be similar to the rest of the site (commercial/open space). No other changes in land use have occurred on or near the site since the 2005 HHRA. Therefore, the land use assumptions used in the risk assessments continue to be valid for the site. However, the implementation of institutional controls regulating land use is necessary to assure that land use changes resulting in more intense human exposures than under current conditions do not occur in the future.

The consolidation area cover on the Foxborough parcel remains intact, based on recent inspections. Because contamination is present beneath the cover, prevention of a complete exposure pathway between human receptors (e.g., commuters) and subsurface contamination is necessary. Continued maintenance of the cover is required to assure that human exposure to the covered material does not occur.

Changes in Risk Assessment Methodology/New Guidance

A new method to evaluate compounds with mutagenic modes of action such as the carcinogenic PAHs and vinyl chloride, which was not in use in 2005, is now recommended by EPA. The current methodology calls for the use of age-specific adjustment factors to account for an increased sensitivity during early life. Vinyl chloride also has a unique set of exposure equations to account for early-life exposures with a separate set of toxicity values for adult and child. The early-life calculation does not affect the conclusions of the 2005 evaluation for the commercial scenario (the land use which was utilized to define cleanup levels), because workers are assumed to be greater than 16 years of age for which the early-life component is not applicable. The 2005 evaluation showed that the cancer risk for the adolescent trespasser scenario was less than that for the commercial worker scenario. However, as noted above, the supplemental early-life calculation for child trespassers was not included as part of the 2005 evaluation. A supplemental calculation that included the early-life component for carcinogens with mutagenic modes of action, performed as part of this five-year review, confirmed the conclusion that adolescent trespasser cancer risk is less than the commercial worker risk. Therefore, the conclusions of the 2005 supplemental risk evaluation continue to be valid. Institutional controls, as required by the ROD and ESD, should be implemented to assure that future use of the site is consistent with the commercial land use assumptions used in the 2005 risk evaluation, and that adolescent exposures of greater frequency and intensity than assumed for trespassing (78 days per year for 10 years) do not occur. The implementation of comprehensive institutional controls, as required by the ROD and ESD, is on-going, and when complete, will provide long-term protectiveness for soil and groundwater remedies.

A recent EPA directive (USEPA, 2014b) was published which provides revised default exposure parameter assumptions for various exposure scenarios. Many of these parameters differ from those utilized in the 2005 site-specific HHRA. Most are related to residential exposures, which would not impact the protectiveness of the remedy. There are, however, changes to the worker soil adherence factor (reduction from 0.2 to 0.12 mg/cm-day), the worker skin surface area (increase from 3,300 cm² to 3,470 cm²), and the worker body weight (increase from 70 to 80 kg). These changes result in an increase in the cleanup levels which would provide the same level of Reasonable Maximum Exposure (RME) risk as defined in the ROD. However, when the new toxicity values (see above) are also incorporated, the cleanup levels for dioxin (due to non-cancer hazards) and pentachlorophenol would actually be reduced. The following table shows the residual risk associated with the ROD cleanup levels (which were used during the remedial action) using the current toxicity values, recommended arsenic RBA of 60%, and updated exposure parameters:

Table 3. Soil Cleanup Levels (Commercial/Open Space)

Compound	ROD Cleanup Level (ppm)	Risk-Level (established in the ROD)	Risk-Level (using current toxicity values and exposure parameters)	Hazard Quotient (using current toxicity values and exposure parameters)
Benzo(a)pyrene	2.1	1×10^{-5}	7×10^{-6}	N/A
Dioxin TEQ	0.001	6×10^{-5}	5×10^{-5}	1*
Arsenic	16	1×10^{-6}	5×10^{-6}	0.03
Pentachlorophenol	90	1×10^{-5}	2×10^{-5}	0.03
Residual Risk		9×10^{-5}	8×10^{-5}	

* The HQ value of 1 is rounded down from HQ of 1.4. In addition, after remediation a 6" soil cover was placed across the site in areas not excavated.

The residual risk remains within EPA's target risk range.

No other changes to dermal exposure assessment have occurred which would change the protectiveness of the remedy.

Evaluation of Railroad Right-Of-Way

A review of the railroad right-of-way evaluations performed by EPA in 2007 and 2011 (Sevenson, 2011) was performed as part of this five-year review, incorporating the toxicity value and exposure parameter changes listed above. Using the 2010 soil data collected in the railroad right-of-way (see Figure 4.1 in Appendix F), EPCs were established and used in risk calculations for a utility worker, using the current toxicity values, arsenic RBA of 60%, and updated exposure parameters described above (see Appendix F). The utility worker scenario was deemed the most appropriate for the active railroad right-of-way given the fact that any intrusive work in the area is limited and carefully controlled by the railroad company. The calculations resulted in a cancer risk of $1E-5$, which is within EPA's target risk range. There is currently no utility work being conducted in the railroad right-of-way so the remedy remains protective in the short term. However, the non-cancer hazard index of 5 for utility worker (due primarily to applying the new dioxin RfD) exceeds EPA's target hazard index of 1. The utility worker results show that institutional controls, as required by the ROD and ESD, should also be applied to this area to protect future utility workers.

Evaluation of Recent Sampling Data

As noted in Section 6.3.2, there have been no exceedances of groundwater performance standards for site related contaminants beyond the compliance boundary in site monitoring wells. There is no evidence at this time showing that the groundwater remedy is not protective. However, as discussed in Section 6.3.1, improvements to the groundwater monitoring network have been recommended. While there was one private well detection of PCP above its MCL, based on a brief review of this well (shallow) and its location relative to the site, the detection is not likely site-related. However, further investigation/evaluation may be necessary to confirm this.

As discussed in Section 6.3.3, 2012 sediment detections were all below the maximum historical detections of the same analytes, except for one dioxin congener (1,2,3,7,8,9-HxCDF) (see Table C-3 in Appendix C). While there were two detections of arsenic above the 95% Upper Confidence Limit (UCL) from the HHRA, which was used as the RME scenario EPC, these concentrations would not have changed the HHRA conclusions regarding sediment risk. However, as the locations sampled in 2012 may not correspond with the historical locations which provided the maximum concentrations used in the HHRA, it may be appropriate to include additional monitoring locations in future sampling efforts to determine if those higher concentrations remain in the river.

While surface water monitoring data was not collected during the five years since remedy construction, on-site groundwater concentrations have not been detected at levels above performance standards developed to be protective of surface water.

7.2.2 Review of Ecological Risk Assessment

The baseline ecological risk assessment (BERA) (Lockheed Martin, 2004) performed for the site was based on data collected during the remedial investigations (RI). The media of concern were surface water, sediments, and aquatic biota in the Rumford River. Due to the lack of habitat in contaminated soil areas, soils were not evaluated in the BERA for risk to terrestrial receptors due to a lack of a complete exposure pathway. The conclusion of the BERA was that benthic invertebrates, water column invertebrates, fish, piscivorous birds and mammals feeding along the Rumford River are unlikely to be at a substantial risk from exposure to site-related contaminants. Based on the results of the risk assessment, the remedy did not include clean-up in the Rumford River, but recommended long-term monitoring of groundwater, surface water, sediment, and fish tissue in order to confirm that groundwater is not migrating off-site or adversely impacting the Rumford River above acceptable levels. Monitoring of sediment and surface water was to be continued annually to ensure that contaminated groundwater is not impacting off-site receptors and to ensure the protectiveness of the remedy.

The BERA was conducted using methodology which would generally comply with current EPA risk assessment guidance. The minor discrepancies between current guidance and previous guidance exist in the areas of benchmarks and toxicity values utilized. For most contaminants, changes to toxicity information have been minimal. There have been minor changes in National Ambient Water Quality Criteria (NAWQC) since 2005. The NAWQCs were used as screening values (mainly metals and pentachlorophenol) to select COCs in the BERA for surface water in the Rumford River. The NAWQCs for metals used in the BERA were not adjusted for hardness in the river and the analytical data for inorganics represented unfiltered metals which were not corrected to represent the dissolved fraction. However, the selection of COCs would not have been different in the BERA if these adjustments had been made, since all of the hardness-dependent inorganics that were likely to be site-related were selected as COCs during the screening process, with the exception of copper.

The only change in NAWQCs relevant to the site was the change in the basis of the copper standard in 2007 with the adoption of the Biotic Ligand Model (BLM)-based criterion. The BLM is a metal bioavailability model that uses receiving water body characteristics to develop site-specific freshwater aquatic life criteria (USEPA, 2007). The BLM requires ten input factors, and these data were not all collected in the surface water of Rumford River, so the site-specific value could not be calculated from the data provided in the BERA. However, the selection of copper as a COC in surface water would not have changed the conclusions of the BERA, or the protectiveness of the remedy. Additional measurement endpoints, including toxicity testing, were utilized to evaluate surface water toxicity, and were the primary basis for determination in the BERA that there were not significant risks to aquatic receptors in the river.

The selection of COCs in sediment was based on screening that is generally consistent with methodology and benchmarks currently used in ecological risk assessments and consistent with guidance.

Dioxins and furans were major COCs of concern evaluated in the BERA. All of the methods used in the BERA were generally consistent with current guidance (USEPA, 2008). In the BERA, the concentrations of individual dioxin and furan congeners in surface water, sediments and aquatic biota were measured and multiplied by published toxic equivalence factors (TEFs) for fish, birds and mammals. The TEFs were summed to calculate receptor-specific toxic equivalent (TEQ) values for use in the exposure calculations. The BERA used toxicity reference values (TRVs) and critical body residues that were conservative. More recent data, particularly for mink (piscivorous mammal), have indicated that the TEQ method and TRVs used in the BERA are likely to over-estimate reproductive effects (Moore et al., 2012; Blankenship et al., 2008). Exceedance of the TRVs used in the mink food-chain models would not necessarily be expected to lead to adverse effects. The BERA concluded that there was no significant risk to piscivorous mammals (mink) expected based on the conservative analysis and TRVs utilized; consequently, the remedy is considered protective.

The ROD recommended monitoring of sediment and surface water be continued annually until completion of the first five-year review after construction of the remedy is completed in order to document conditions at and near the site. A round of fish tissue sampling was to be performed in conjunction with the five-year review as well. Although a fish survey was performed prior to this five-year review, no additional fish tissue data were collected, thus it could not be confirmed whether or not the concentrations of contaminants in fish continue to indicate negligible risk to fish populations.

Sediment monitoring was performed in May 2012 at four locations in the Rumford River. As discussed in Section 6.3.3, 2012 sediment detections were all below the maximum historical detections of the same analytes, except for one dioxin congener (1,2,3,7,8,9-HxCDF) (see Table C-3 in Appendix C).

In conclusion, since the BERA was prepared in 2005, there are no newly promulgated standards, relevant to the site, which bear on the protectiveness of the remedy. The reference values and exposure assumptions in the BERA were conservative and therefore protective. There are no major changes in site conditions or exposure assumptions upon which the risk assessment was based that would result in increased exposure or risk. Recent sediment sampling data from the Rumford River indicate that sediment COC concentrations detected in 2012, with the exception of one dioxin congener (1,2,3,7,8,9-HxCDF). Were below measurements evaluated for exposures in the BERA.

7.2.3 ARARs Review

A review of Applicable or Relevant and Appropriate Requirements (ARARs) was performed to check the impact on the remedy due to any changes in standards that were identified as ARARs in the ROD, newly promulgated standards for chemicals of potential concern, and TBCs (to be considered) that may affect the protectiveness of the remedy. Tables documenting the review of each ARAR, using the regulations and requirement synopses listed in the ROD as a basis, are presented in Appendix G. The evaluation included a determination of whether the regulation is currently ARAR or TBC and whether the requirements have been met. A discussion of the review is summarized below.

The 2005 ROD set forth the following ARARs for the selected remedy:

Location-Specific:

- Executive Order 11990 (Protection of Wetlands)
- Executive Order 11988 (Floodplain Management)
- Fish and Wildlife Coordination Act
- Resource Conservation and Recovery Act (RCRA)
- Endangered Species Act
- 310 CMR 10.00 - Massachusetts Wetlands Protection Regulations
- 321 CMR 10.00 - Massachusetts Endangered Species Act Regulations

Action-Specific:

- Clean Water Act (CWA)
- Rivers and Harbors Act of 1899
- Safe Drinking Water Act (SDWA)
- Resource Conservation and Recovery Act (RCRA)
- National Emission Standards for Hazardous Air Pollutants (NESHAPs)
- 314 CMR 4.00 - Massachusetts Surface Water Quality Standards
- 314 CMR 9.00 - Massachusetts Certification for Dredging, Dredged Material Disposal, and Filling in Waters
- 314 CMR 3.00 – Massachusetts Surface Water Discharge Permit Program
- 314 CMR 6.00 - Massachusetts Groundwater Quality Standards
- 310 CMR 22.00 - Massachusetts Drinking Water Regulations
- 310 CMR 6.00 - Massachusetts Ambient Air Quality Standards
- 310 CMR 7.00 - Massachusetts Air Pollution Control Regulations
- 310 CMR 30.00 - Massachusetts Hazardous Waste Management Regulations

Additional policies, criteria, and guidance were identified in the ROD as TBC, including:

- American Conference of Governmental Industrial Hygienists (ACGIH) Threshold Limit Values (TLVs)
- EPA Risk RfDs, Carcinogen Assessment Group Potency Factors, and Carcinogenicity Slope Factors
- EPA Draft Guidance for Evaluating the Vapor Intrusion to Indoor Air Pathway from Groundwater and Soils
- EPA Guidance: Approach for Addressing Dioxin in Soil at CERCLA and RCRA Sites
- Ontario Ministry of Environment and Energy Lowest and Severe Effect Levels (LELs and SELs) for Freshwater Sediments
- EPA Policy on Floodplains and Wetland Assessments for CERCLA Actions
- Massachusetts Threshold Effects Exposure Levels (TELs) and Allowable Ambient Air Limits - Annual (AALs)
- EPA Revised Alternative Cap Design Guidance Proposed for Unlined, Hazardous Waste Landfills in the EPA Region I
- EPA Technical Guidance Document: Final Covers on Hazardous Waste Landfills and Surface Impoundments

SDWA MCLs were selected as compliance boundary groundwater performance standards for pentachlorophenol, arsenic, and chromium. MCLs have not changed since the 2005 ROD for these contaminants. Additional onsite groundwater performance standards for the protection of surface water were developed for pentachlorophenol, arsenic, and chromium based on Massachusetts ambient water quality criteria and dilution associated with groundwater and river discharge. The ambient water quality criteria for these contaminants have not changed since the 2005 ROD. Cleanup levels for soil were risk-based and EPA's 1998 OSWER *Directive Approach for Addressing Dioxin in Soil at CERCLA and RCRA Sites*, which is no longer in effect, was specifically used in setting the soil cleanup level for dioxin. Section 7.2.1 addresses the potential impacts of changes in EPA toxicity values and addition of an RfD for dioxin since the 2005 ROD.

Vapor intrusion was evaluated in the baseline human health risk assessment consistent with the EPA's 2002 Draft Guidance for Evaluating the Vapor Intrusion to Indoor Air Pathway from Groundwater and Soils. Any changes to the vapor intrusion guidance (once finalized) would be considered with respect to the institutional controls, as required by the ROD and ESD, and future building construction.

The requirements of many of the ARARs identified in the ROD were met during remedy construction.

7.3 Question C: Has any other information come to light that could call into question the protectiveness of the remedy?

No. There is no other information that calls into question the protectiveness of the remedy.

SECTION 8.0 ISSUES

Based on the activities conducted during this five-year review, the issues identified in Table 4 have been noted.

Table 4: Issues

Issue	Affects Protectiveness (Y/N)	
	Current	Future
Institutional controls restricting land uses that may impact the protectiveness of the remedy (including preventing the use of groundwater, protecting the consolidation area cover and other components of the remedy) need to be established. Also, an updated risk evaluation shows that the railroad right-of-way will also require institutional controls to protect workers who may contact soil in that area.	N	Y
The 2012 sediment sampling event included locations which were not collected at the historic sampling locations and the results showed lower contaminant concentrations than seen previously. As a result, it is uncertain whether the higher concentrations historically seen remain at the Site. If the historic concentrations are still present, recent changes to toxicity values and exposure parameters included in risk evaluation for sediment may result in a future change to the protectiveness determination with respect to sediment exposure.	N	Y
The fish tissue collection required by the ROD was not performed due to a lack of fish in the Rumford River. Also, surface water sampling required by the ROD was not performed due to EPA and MassDEP's agreement to continue discussions about the future operation and maintenance plan for the site.	N	Y
Determine whether a PCP detection above its MCL in a private groundwater supply well is site-related.	N	Y
Active irrigation wells have been identified approximately 300 feet beyond the compliance boundary. Irrigation wells are not expected to create enough drawdown to induce groundwater to flow to them from the compliance boundary. An on-site monitoring well just east (upgradient) of the compliance boundary does indicate the presence of contamination at concentrations above performance standards.	N	Y

SECTION 9.0 RECOMMENDATIONS AND FOLLOW-UP ACTIONS

In response to the issues noted in Section 8.0 it is recommended that the actions listed in Table 5 be taken:

Table 5: Recommendations and Follow-up Actions

Issue	Recommendations/ Follow-up Actions	Party Responsible	Oversight Agency	Milestone Date	Affects Protectiveness? (Y/N)	
					Current	Future
Institutional controls are not in place	Prepare documentation and record the AULs	EPA/ MassDEP	EPA	Aug 2019	N	Y
Sediment sampling coverage is limited	If accessible, collect sediment samples from locations which correspond to historical sampling locations and assess the new data.	MassDEP	EPA	Dec 2018	N	Y
Surface water and fish tissue not sampled	Review current site information, determine the need for and, if necessary, collect any additional data. Update/ document changes in the monitoring requirements accordingly.	EPA/ MassDEP	EPA	Dec 2018	N	Y
PCP detection in a private well	Perform evaluation which potentially includes the following: determine if detection is real (potential resampling); review well construction and any potential hydrogeologic connection to the site; and review nearby potential sources.	EPA	EPA	Dec 2016	N	Y
Active irrigation wells identified near compliance boundary.	Additional investigations should be conducted to confirm whether groundwater flow directions have been impacted by the irrigation wells.	EPA/ MassDEP	EPA	Dec 2015	N	Y

SECTION 10.0 PROTECTIVENESS STATEMENTS

The remedy at the Hatheway & Patterson Superfund Site currently protects human health and the environment because remediation of soil (soil removal and on-site consolidation) has been completed to cleanup levels that are considered protective for the anticipated future use of the property, and there is no current use of on-site groundwater which is classified as non-potable. However, in order for the remedy to be protective in the long-term, institutional controls need to be created and recorded to restrict inappropriate land uses (including use of groundwater) and protect the consolidation area cover. Operation and maintenance activities have been initiated and will ensure that the consolidation cell and associated components of the remedy (e.g., groundwater monitoring wells) remain in good condition. In addition, monitoring of groundwater will continue to assess the protectiveness of the remedy.

SECTION 11.0
NEXT FIVE-YEAR REVIEW

The next Five-Year Review for the Hatheway & Patterson Superfund Site is due in September 2019, five years from the signature date of this review.

APPENDIX A

FIGURES



SITE LOCATION MAP

Hatheway and Patterson
Superfund Site
35 County Street
Mansfield, MA

Location of Facility



FIGURE 1.1

★ Site Location



0 2,000 Feet



AMEC Earth and Environmental, Inc.
2 Robbins Road
Westford, MA 01886
(978) 692-9090





FIGURE B-1

SITE LAYOUT

HATHEWAY AND PATTERSON SITE
15 COUNTY ROAD
MANSFIELD, MASSACHUSETTS

M&E Metcalf & Eddy

TRC

South Mills South
East of John Street
Lowell, MA 01852
978-970-5600

TRC PROJ. NO.: 02136-0490-01X39

EPA CONTRACT NO.: 68-W6-0042

RAC SUBCONTRACTOR: 107061




Figure 2

OVERBURDEN GROUND WATER
ELEVATION MAP (APRIL 2004)
HATHWAY AND PATTERSON SITE
15 COUNTY ROAD
MANSFIELD, MASSACHUSETTS

M&E Metcalf & Eddy


TRC

Boott Mills South
Foot of John Street
Lowell, MA 01852
978-978-5600

TRC PROJ. NO.: 02136-0490-01X39

EPA CONTRACT NO.: 68-W6-0042

RAC SUBCONTRACT NO.: 107061



NOTE:
NS - NOT SURVEYED

0 75 150 225 300
SCALE IN FEET

Figure 3

BEDROCK GROUND WATER
ELEVATION MAP (APRIL 2004)
HATHEWAY AND PATTERSON SITE
15 COUNTY ROAD
MANSFIELD, MASSACHUSETTS

M&E Metcalf & Eddy


TRC

Boott Mills South
Foot of John Street
Lowell, MA 01852
978-870-5600

TRC PROJ. NO.: 02136-0490-01X39

EPA CONTRACT NO.: 68-W6-0042

RAC SUBCONTRACT NO.: 107061





-  Possible Private Well To Be Considered For Sampling
-  Possible Private Well

Figure 5. Possible Private Wells





FIGURE 6

**PRIVATE WELLS AND UNDERPASS
DEWATERING SYSTEMS**

● Well

▲ Underpass Dewatering System



APPENDIX B

LIST OF DOCUMENTS REVIEWED AND REFERENCES

AECOM. 2013. Hydrogeologic Conditions Report. Letter report addressed to Mr. David Lederer of EPA-New England, Region 1. March 29, 2013.

Blankenship, A. L., Kay, D. P., Zwiernik, M. J., Holem, R. R., Newsted, J. L., Hecker, M., & Giesy, J. P. 2008. *Toxicity reference values for mink exposed to 2, 3, 7, 8-tetrachlorodibenzo-p-dioxin (TCDD) equivalents (TEQs)*. *Ecotoxicology and Environmental Safety*, 69(3), 325-349.

Environmental Strategies & Management (ESM). 2012a. Field Work Reporting Memo – May 2012. Operations and Maintenance - Hatheway and Patterson, Mansfield, MA. July 25, 2012.

Environmental Strategies & Management (ESM). 2012b. Field Work Reporting Memo – October 2012. O&M Activities at the Hatheway and Patterson Superfund Site, Mansfield, MA. December 18, 2012.

Environmental Strategies & Management (ESM). 2013. Fish Survey Report. Hatheway and Patterson Site, Mansfield, MA. October 1, 2013.

Environmental Strategies & Management (ESM). 2014. Field Work Reporting Memo – November 2013. O&M Activities at the Hatheway and Patterson Superfund Site, Mansfield, MA. January 6, 2014.

Lockheed Martin Information Technologies. 2004. Baseline Ecological Risk Assessment. Hatheway & Patterson Superfund Site, Mansfield, Massachusetts. July 2004.

Metcalf & Eddy, Inc. (M&E). 2005. *Baseline Human Health Risk Assessment*. Hatheway & Patterson Superfund Site, Mansfield, Massachusetts. EPA Contract No. 68-W6-0042, Work Assignment No. 142-RICO-01X3. January 2005.

Moore, J. N., Zwiernik, M. J., Newsted, J. L., Fitzgerald, S. D., Link, J. E., Bradley, P. W., Kay, D., Budinsky, R., Giesy, J. P. and Bursian, S. J. (2012), *Effects of dietary exposure of mink (Mustela vison) to 2,3,7,8-tetrachlorodibenzo-p-dioxin, 2,3,4,7,8-pentachlorodibenzofuran, and 2,3,7,8-tetrachlorodibenzofuran on reproduction and offspring viability and growth*. *Environmental Toxicology and Chemistry*, 31: 360–369.

Sevenson Environmental Services, Inc. 2011. Final Remedial Action Completion Report. Hatheway and Patterson Superfund Site. Mansfield, Massachusetts. September 2011.

TRC Environmental Corporation (TRC), 2005. Interim Final Remedial Investigation Report, Hatheway & Patterson Superfund Site, Mansfield, Massachusetts. April 2005.

TRC Environmental Corporation (TRC), 2008. Construction Specifications, Hatheway & Patterson Superfund Site, Mansfield, Massachusetts. September 2008.

U.S. Environmental Protection Agency (USEPA). 2001. Comprehensive Five-Year Review Guidance. June 2001.

U.S. Environmental Protection Agency (USEPA). 2005. Record of Decision. Hatheway & Patterson Superfund Site, Mansfield-Foxborough, Massachusetts. September 30, 2005.

U.S. Environmental Protection Agency (USEPA). 2007. Aquatic Life Ambient Freshwater Quality Criteria – Copper. 2007 Revision. Office of Water. EPA-822-R-07-001. February 2007.

U.S. Environmental Protection Agency (USEPA). 2008. *Framework for Application of the Toxicity Equivalence Methodology for Polychlorinated Dioxins, Furans, and Biphenyls in Ecological Risk Assessment*. EPA/100/R-08/004.

U.S. Environmental Protection Agency (USEPA). 2011a. Declaration for the Explanation of Significant Differences. Hatheway & Patterson Superfund Site, Mansfield/Foxborough, Massachusetts. August 2011.

U.S. Environmental Protection Agency (USEPA). 2011b. Operations and Maintenance Manual. Hatheway and Patterson Superfund Site, Mansfield, Massachusetts. Version 1.0. September 2011.

U.S. Environmental Protection Agency (USEPA). 2012. Compilation and Review of Data on Relative Bioavailability of Arsenic in Soil and Recommendations for Default Value for Relative Bioavailability of Arsenic in Soil Documents. OSWER Directive 9200.1-113. December 31, 2012.

U.S. Environmental Protection Agency (USEPA). 2014a. Integrated Risk Information System. Available at <http://www.epa.gov/iris/>. May 2014.

U.S. Environmental Protection Agency (USEPA). 2014b. Human Health Evaluation Manual, Supplemental Guidance: Update of Standard Default Exposure Factors. OSWER Directive 9200.1-120. February 6, 2014.

APPENDIX C

ANALYTICAL RESULTS

GROUNDWATER ANALYTICAL RESULTS

**TABLE C-1. PENTACHLOROPHENOL (PCP), DIOXIN TEQ, ARSENIC, AND CHROMIUM CONCENTRATIONS
IN SELECT WELLS AT HATHEWAY & PATTERSON, 2001 TO 2012**

Well No.	Notes			Dec 2002 (unless footnoted)				May 2011				May 2012				Oct 2012				Apr 2013				Oct/Nov/Dec 2013			
				PCP	Dioxin TEQ	As	Cr	PCP	Dioxin TEQ	As	Cr	PCP	Dioxin TEQ	As	Cr	PCP	Dioxin TEQ	As	Cr	PCP	Dioxin TEQ	As	Cr	PCP	Dioxin TEQ	As	Cr
				ug/L	pg/L	ug/L	ug/L	ug/L	pg/L	ug/L	ug/L	ug/L	pg/L	ug/L	ug/L	ug/L	pg/L	ug/L	ug/L	ug/L	pg/L	ug/L	ug/L	ug/L	pg/L	ug/L	ug/L
MW-011	O	BK	LT	NA	NA	0.55 ⁽¹⁾	<2.5 ⁽¹⁾	<0.5	0.186	ND	ND	<11 ⁽²⁾	0.0126 ⁽³⁾	<8 ⁽²⁾	<50 ⁽²⁾	<11 ⁽²⁾	NCD ⁽²⁾	<8 ⁽²⁾	<50 ⁽²⁾	<1 ⁽²⁾	0.013 ⁽³⁾	<8 ⁽²⁾	<50 ⁽²⁾	<1 ⁽²⁾	0.38 ⁽³⁾	<8 ⁽²⁾	<50 ⁽²⁾
MW-111	O	ICB	LT					6.55	NCD	4.4	ND	<10	0.00336	<8	<50	<10	0.21	<8	<50	3	0.023	<8	<50	2	0.25	<8	<50
MW-113	O	ICB	LT					86.4	NCD	3.2	1.1	51	0.00269	<8	<50	130	NCD	<8	<50	110	NCD	<8	<50	110	0.16	<8	<50
RCA-9	O	ICB	LT	2.1 ⁽⁴⁾	NA	0.14 B ⁽⁴⁾	<2.5 ⁽⁴⁾	<0.5 ⁽²⁾	0.171 ⁽³⁾	ND	0.7 ⁽³⁾								<1	NCD	<8	<50	<1	0.59	<8	<50	
MW-111R	B	ICB	LT	4 ⁽⁵⁾	NA	3.6 ⁽⁵⁾	<2.5 ⁽⁵⁾	1270	0.0938	3.5	2.4	350	0.00399	<8	<50	1400	NCD	<8	<50	1200	0.081	15	<50	1200	0.38	<8	<50
MW-113R	B	ICB	LT					55.9	0.00363	1.6	2.3	70	0.003	<8	<50	200	7.66	<8	<50	140	NCD	<8	<50	<1	0.26	<8	<50
MW-107	O	BCB	LT					<0.5	0.00115	9	1.2	<11	NCD	10	<50	<10	NCD	8	<50	<1	NCD	<8	<50	<1	0.17	<8	<50
MW-107R	B	BCB	LT	<0.2 ⁽⁵⁾	NA	4.2 ⁽⁵⁾	<2.5 ⁽⁵⁾	<0.5	NCD	ND	0.6	<10	0.00579	<8	<50	<10	NCD	<8	<50	<1	NCD	<8	<50	<1	0.18	<8	<50
MW-109R	B	BCB	LT	<0.2 ⁽⁵⁾	NA	2.5 ⁽⁵⁾	<2.5 ⁽⁵⁾	<0.5	1.31	3.5	ND	<10	0.00513	<8	<50	<10	1.32	<8	<50	<1	0.011	<8	<50	<1	0.52	<8	<50
RCA-8	O	ICB		18 ⁽⁴⁾	NA	1.2 ⁽⁴⁾	NA					11	34.6	<8	<50	13	44.66	<8	<50								
Compliance Boundary Performance Standard				1	30	10	100	1	30	10	100	1	30	10	100	1	30	10	100	1	30	10	100	1	30	10	100
On-Site Performance Standard (Surface Water Protection)				1,792	None Established	17,924	1,314	1,792	None Established	17,924	1,314	1,792	None Established	17,924	1,314	1,792	None Established	17,924	1,314	1,792	None Established	17,924	1,314	1,792	None Established	17,924	1,314

1. Nov 2001

2. Sample and duplicate sample were analyzed. For non-detects, value reflects higher reporting limit (RL) if RLs were different.

3. Value is average of two (sample and duplicate) analyses

4. Dec 2003

5. Oct 2004

Column 2 Notes: O = Overburden Well; B = Bedrock Well; BK = Background Location; BCB = Beyond Compliance Boundary; ICB = Inside Compliance Boundary;

LT = Long-Term Monitoring Location, per Groundwater, Surface Water, and Sediment Sampling and Analysis Plan (SES, 2011)

Dioxin TEQ calculated using WHO 2005 TEFs (ND=0) except for Oct/Nov/Dec 2013, calculated using MassDEP 1995 TEFs (ND=0). Results using WHO TEFs would be less conservative and therefore still not exceed the performance standard.

ND = Not detected (reporting limit unknown)

NCD = No congeners detected, and no dioxin TEQ calculated

NA = Not analyzed

TEQ - Toxicity Equivalence

TEF - Toxicity Equivalence Factor

WHO - World Health Organization

Values in bold italic exceed performance criteria

"Less than" (<) values in bold = reporting limit is higher than performance standard

Light gray shading = well was not sampled

Dark gray shading = well did not exist

Sources: May 2011 results taken from Analytical Data Report prepared by Waste Stream Technology Inc, 06/09/11 (Note that concentrations are incorrectly reported in

Remedial Action Completion Report (SES, Sep 2011). May 2012 through Dec 2013 results taken from reports prepared by Environmental Strategies & Mgmt (Jul and

Dec 2012; Jan 2014). Pre-2011 results taken from Interim Final RI Report, Hatheway & Patterson Superfund Site (M&E/TRC, Apr 2005)

2014 PRIVATE WELL MONITORING

Table C-2. Hatheway & Patterson Private Well Sampling - June 2014

		18 Thomas Street 6/18/2014		136 Highland Ave 6/18/2014		46 Chauncy Street 6/18/2014		325 N Main Street 6/18/2014		Town 1 6/18/2014		Town 2 6/18/2014		132 Highland ave 6/18/2014		132 Highland ave (FD) 6/18/2014		Max Detect	MCL
		Conc.	RL	Conc.	RL	Conc.	RL	Conc.	RL	Conc.	RL	Conc.	RL	Conc.	RL	Conc.	RL		
Beryllium	ug/L	ND	0.2	0.2	0.2	ND	0.2	ND	0.2	ND	0.2	ND	0.2	ND	0.2	ND	0.2	0.2	4
Aluminum	ug/L	ND	5	59	5	ND	5	ND	5	ND	5	10	5	36	5	49	5	59	
Vanadium	ug/L	ND	0.2	ND	0.2	ND	0.2	ND	0.2	0.28	0.2	ND	0.2	ND	0.2	0.22	0.2	0.28	
Chromium	ug/L	1	0.5	ND	0.5	ND	0.5	ND	0.5	ND	0.5	ND	0.5	0.5	0.5	0.56	0.5	1	100
Manganese	ug/L	27	0.2	20	0.2	1600	0.2	2600	2	1.5	0.2	1400	0.2	11	0.2	11	0.2	2600	
Cobalt	ug/L	ND	0.2	ND	0.2	2.2	0.2	8.1	0.2	ND	0.2	5	0.2	ND	0.2	ND	0.2	8.1	
Nickel	ug/L	3.2	0.2	1.3	0.2	3.3	0.2	3.4	0.2	1.8	0.2	6.7	0.2	2.1	0.2	2.2	0.2	6.7	
Copper	ug/L	22	0.5	1.2	0.5	7.4	0.5	3.7	0.5	1.9	0.5	7.2	0.5	46	0.5	78	0.5	78	1300
Zinc	ug/L	13	5	88	5	590	5	18	5	19	5	39	5	17	5	24	5	590	
Arsenic	ug/L	ND	1	ND	1	4.1	1	ND	1	ND	1	ND	1	ND	1	ND	1	4.1	10
Selenium	ug/L	ND	1	ND	1	ND	1	ND	1	ND	1	ND	1	ND	1	ND	1	ND	50
Silver	ug/L	ND	0.2	ND	0.2	ND	0.2	ND	0.2	ND	0.2	ND	0.2	ND	0.2	ND	0.2	ND	
Cadmium	ug/L	ND	0.2	ND	0.2	ND	0.2	ND	0.2	ND	0.2	ND	0.2	ND	0.2	ND	0.2	ND	5
Molybdenum	ug/L	ND	1	ND	1	ND	1	ND	1	ND	1	ND	1	ND	1	ND	1	ND	
Antimony	ug/L	ND	0.5	ND	0.5	ND	0.5	ND	0.5	ND	0.5	ND	0.5	ND	0.5	ND	0.5	ND	6
Barium	ug/L	92	0.2	42	0.2	41	0.2	60	0.2	32	0.2	300	0.2	60	0.2	61	0.2	300	2000
Thallium	ug/L	ND	0.5	ND	0.5	ND	0.5	ND	0.5	ND	0.5	ND	0.5	ND	0.5	ND	0.5	ND	2
Lead	ug/L	1.3	0.2	ND	0.2	0.58	0.2	0.46	0.2	ND	0.2	0.74	0.2	3.5	0.2	7.6	0.2	7.6	15
Magnesium (mg/L)	mg/L	7.2	0.1	1.6	0.1	3.8	0.1	4.2	0.1	1.7	0.1	6.9	0.1	2.1	0.1	2.1	0.1	7.2	
Calcium (mg/L)	mg/L	67	0.2	15	0.2	59	0.2	33	0.2	18	0.2	57	2	24	0.2	24	0.2	67	
Iron	ug/L	ND	50	ND	50	3200	50	3100	50	ND	50	3500	50	340	50	940	50	3500	
Uranium	ug/L	ND	1	ND	1	ND	1	ND	1	ND	1	ND	1	ND	1	ND	1	ND	30
Pentachlorophenol	ug/L	ND	0.2	ND	0.2	ND	0.2	2.7 DB		ND	0.2	ND	0.2	ND	0.2	ND	0.2	2.7	1
Dioxin TEQ	pg/L	0.281		0.196		0.375		1.58		0.197		0.28		0.646		0.255		1.58	
	ug/L	2.81E-07		1.96E-07		3.75E-07		1.58E-06		1.97E-07		2.80E-07		6.46E-07		2.55E-07		1.58E-06	3.00E-05

Notes:
RL - Reporting Limit
ND - Not Detected
DB - Value reported is from a diluted sample and there was contamination associated with a laboratory blank
FD - Field Duplicate
TEQ - Toxicity Equivalency - based on WHO 2005 values



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION I

DATE: July 22, 2014

SUBJ: Hatheway and Patterson Ground water Sampling and Analysis – June 2014

FROM: Jerry Keefe, EIA Team Leader

TO: Kimberly White, RPM OSRR

I. Background Information

- A. Date of Sampling: Wednesday, June 18
- B. Weather Conditions: Mostly sunny, approximately 85 degrees F
- C. USEPA Representatives: Jerry Keefe
Mike Looney
- D. Samples Requested by: Kim White, RPM OSRR
- E. Address: Various locations within the town of Mansfield, Massachusetts

II. Purpose of Sampling

The sampling event was being done as part of a 5-year review to obtain additional information on potential contaminant migration in the site aquifer. The objective of the sampling event was to collect representative groundwater samples from private irrigation wells; all the properties are connected to a public water supply system for drinking water. Samples will be analyzed for dioxin/furans, PCP (pentachlorophenol), and metals. NERL will be analyzing samples for metals. The Dioxin and PCP samples will be analyzed at a CLP laboratory and is not discussed in this summary report.

III. Description of Sampling Locations

Sample locations and descriptions are shown in table 1.

Table 1

Sample Location/ Address	Owner/phone#	Map/Lot #	Time	Comments
Mansfield Fabric Care Center /18 Thomas St, Mansfield, MA	Billings Realty Trust Fontanini & Kennedy Trs 508-339-9057	Map 021, Lot 182	0935	Sampled at Spigot before filters. (Picture 1) Temperature – 14.0 C Conductivity – 1618 uS/cm pH – 6.19
Private Residence/ 136 Highland Ave, Mansfield, MA	John & Donna Harrington 508-339-8731	Map 018, Lot 460	1038	Sampled at pump head. (Picture 2) Temperature – 11.2 C Conductivity – 363.6 uS/cm pH – 5.53
Car Wash / 46 Chauncy St, Mansfield, MA	Nicks Realty Trust Nicholas & Steven Anagnos 508-339-9556	Map 022, Lot 008	1130	Sampled at top of system not thru hose. (Picture 3) Readings are grabs, flow was to high from system. Flushed system for 30 minutes. Temperature – 13.9 C Conductivity – 501 uS/cm pH – 7.14
Multi-tenant Residence/ 325 N Main Street, Mansfield, MA	Nicks Realty Trust Nicholas & Steven Anagnos 508-339-9556	Map 022, Lot 003	1215	Sampled at outside spigot – before treatment (Picture 4) Temperature – 13.1 C Conductivity – 886 uS/cm pH – 6.29
Town 1/ Underpass on N. Main St at Mansfield Ave, Mansfield, MA	Mark Cook 508-922-8388	Underpass	1419	Sample taken from seep in road. Mansfield Ave overpass on North Main Street. (Picture 5) Start purge at 1400 using peristaltic pump Temperature – 18 C Conductivity – 513.2 uS/cm pH – 6.53
Town 2/ Underpass on Chauncy St at Mansfield Ave, Mansfield, MA	Mark Cook 508-922-8388	Underpass	1500	Sample taken from storm sewer manhole on sidewalk. Overpass Route 106 and Chauncy Street. (Picture 6) Sample from 5 gallon pail dropped into manhole. No readings taken.
Private Residence/ 132 Highland Ave, Mansfield, MA	Kimberly Horstmann & Michael Mallon 774-406-1559	Map 018, Lot 459	1610	Sample taken from just after pump head. (Picture 7) Temperature – 15.6 C Conductivity – 98.6 uS/cm pH – 6.01

IV. Sampling Summary

On Wednesday, June 18, 2014, EPA investigators Jerry Keefe and Mike Looney conducted a Sampling Project at seven locations within the town of Mansfield, MA. Pre and post calibrations of field instruments were within acceptable limits. All locations sampled were completed according to sampling and analysis plan except for the Town 1 and Town 2 locations. These locations are stormwater and groundwater collections tanks for 2 town underpasses. Both holding tanks contain extensive debris (plastic cup/bottles, cigarette butts, etc) and were therefore not appropriate groundwater sample locations (Picture 8). Pipes with flowing groundwater were observed in the tanks but could not be sampled directly because of difficulty and safety concerns. The Town 1 location had breakouts of groundwater up-flowing into the street and then to the storm sewer. These groundwater up-flows appeared to be representative groundwater sampling locations. Picture 5 shows the sample location and the sample tubing. The peristaltic pump was pumping at approximately 400 ml/min with no draw down. Due to safety concerns the purging

was only for 20 minutes and the samples were collected along with field parameters. The Town 2 location was sampled from a manhole using a clean 5 gallon bucket from a 10" pipe flowing groundwater (according to Mark Cook) to the holding tank. The route 106 underpass is shown in Picture 6.

To ensure that data quality objectives were met and acceptable for decision making purposes the following was reviewed.

- 1) SAP – Hatheway and Patterson Well Sampling for Analysis of Dioxins, PCP, and metals.
- 2) Chain of Custody (COC)
- 3) Field duplicate comparison

Sampling and Analysis Plan

The SAP objectives were achieved and all locations were sampled accordingly. As stated above two sample locations Town 1 and Town 2 were sampled based upon the investigators' professional judgment and safety considerations. Although these sampling locations appeared representative and satisfactory, the locations have potential of being affected by other conditions that are not representative of actual ground water (stormwater, road debris).

Chain of Custody

All COC information as compared to field notes showed no issues. Sample delivery, preservation, and signage were acceptable.

Field Duplicate Comparison

A field duplicate is a collection of two or more samples collected at the same location side by side or one immediately after the other. This duplicate represents the precision of the whole method, site heterogeneity, field sampling and the laboratory analysis. Relative Percent Difference (RPD) was calculated for metals. The USEPA nationally has not set control criteria for field duplicates but the site SAP used 30 percent as a standard. Site contaminant of concern (chromium and arsenic) are within acceptable limits. Aluminum, copper, zinc, lead, and iron are above the 30 percent limit. In general water samples that are not filtered and/or collected at high flow rates may tend to have fluctuations in sample results due to the solubility of such compounds. The results show good correlation and field precision.

Overall Assessment


None of the data were qualified or rejected based upon this review and the quality of the data is acceptable. All data can be used for decision making purposes.

Table 2

	132 Highland Ave	132(d) Highland		RPD
Beryllium	ND	ND		0.0
Aluminum	36	49		30.6
Vanadium	ND	0.22		9.5
Chromium	0.5	0.56		11.3
Manganese	11	11		0.0
Cobalt	ND	ND		0.0
Nickel	2.1	2.2		4.7
Copper	46	78		51.6
Zinc	17	24		34.1
Arsenic	ND	ND		0.0
Selenium	ND	ND		0.0
Silver	ND	ND		0.0
Cadmium	ND	ND		0.0
Molybdenum	ND	ND		0.0
Antimony	ND	ND		0.0
Barium	60	61		1.7
Thallium	ND	ND		0.0
Lead	3.5	7.6		73.9
Magnesium (mg/L)	2.1	2.1		0.0
Calcium (mg/L)	24	24		0.0
Iron	340	940		93.8
Uranium	ND	ND		0.0

June 18, 2014

Picture 1 – 18 Thomas Street



Picture 2 – 136 Highland Ave



June 18, 2014


Picture 3 – 46 Chauncy Street



Picture 4 – 325 North Main Street



Picture 5 – Town 1



Picture 6 – Town 2



June 18, 2014

Picture 7



Picture 8 – Town 1 Debris in Holding Tank





Laboratory Report

July 17, 2014

Jerry Keefe - EIA / OEME
Kimberly White - Mail Code OSRR07-1
US EPA New England, Region 1
Kimberly White - Mail Code OSRR07-1

Project Number: 14060018
Project: Hatheway & Patterson Co - Mansfield, MA
Analysis: Total Recoverable Metals in Water
EPA Chemist: Michael Dowling

Date Samples Received by the Laboratory: 06/19/2014

Analytical Procedure:

All samples were received and logged in by the laboratory according to the USEPA New England Laboratory SOP for Sample Log-in.

Sample preparation and analysis was done following the EPA Region I SOP, EIASOP-INGICPMS5.

Samples were prepared following USEPA New England Sample Prep SOP: EIA-INGPREP8.SOP.

Samples were analyzed using a Perkin Elmer Elan 6000 inductively coupled plasma mass spectrometer. Preparation and analysis SOP's are based on Methods 200.2 and 200.8, respectively, as stated in "Methods for the Determination of Metals in Environmental Samples, Supplement I (EPA/600/R-94/111), Rev. 5.4, May 1994."

Data were reviewed in accordance with the internal verification procedures described in the EPA New England Quality Manual for NERL.

Results relate only to the items tested or to the samples as received by the Laboratory. This analytical report shall not be reproduced except in full, without written approval of the laboratory.

If you have any questions please call me at 617-918-8340 .

Sincerely,

14060018\$MTMSW

Qualifiers:

RL	Reporting limit
ND	Not Detected above reporting limit
NA	Not Applicable
NC	Not calculated since analyte concentration is ND
J1	Estimated value due to MS recovery outside acceptance criteria
J2	Estimated value due to LFB result outside acceptance criteria
J3	Estimated value due to RPD result outside acceptance criteria
J4	Estimated value due to LCS result outside acceptance criteria
B	Analyte is associated with the lab blank or trip blank contamination. Values are qualified when the observed concentration of the contamination in the sample extract is less than 10 times the concentration in the blank.
R	No recovery was calculated since the analyte concentration is greater than four times the spike level.

Comments: The pH values of all samples were approximately 1.9.

Hatheway & Patterson Co - Mansfield, MA

Total Recoverable Metals in Water

Client Sample ID: 18 Thomas Street
Date of Collection: 6/18/2014
Date of Preparation: 7/14/2014
Date of Analysis: 7/15/2014
Dry Weight Prepared: N/A
Wet Weight Prepared: N/A

Lab Sample ID: AB48954
Matrix: Water
Amount Prepared: 25 mL
Percent Solids: N/A
Extract Dilution: 1.01
pH: <2

CAS Number	Compound	Concentration ug/L	RL ug/L	Qualifier
7440-41-7	Beryllium	ND	0.20	
7429-90-5	Aluminum	ND	5.0	
7440-62-2	Vanadium	ND	0.20	
7440-47-3	Chromium	1.0	0.50	
7439-96-5	Manganese	27	0.20	
7440-48-4	Cobalt	ND	0.20	
7440-02-0	Nickel	3.2	0.20	
7440-50-8	Copper	22	0.50	
7440-66-6	Zinc	13	5.0	
7440-38-2	Arsenic	ND	1.0	
7782-49-2	Selenium	ND	1.0	
7440-22-4	Silver	ND	0.20	
7440-43-9	Cadmium	ND	0.20	
7439-98-7	Molybdenum	ND	1.0	
7440-36-0	Antimony	ND	0.50	
7440-39-3	Barium	92	0.20	
7440-28-0	Thallium	ND	0.50	
7439-92-1	Lead	1.3	0.20	
7439-95-4	Magnesium (mg/L)	7.2	0.10	
7440-70-2	Calcium (mg/L)	67	0.20	
7439-89-6	Iron	ND	50	
7440-61-1	Uranium	ND	1.0	

Comments:

Hatheway & Patterson Co - Mansfield, MA

Total Recoverable Metals in Water

Client Sample ID: 136 Highland Ave
Date of Collection: 6/18/2014
Date of Preparation: 7/14/2014
Date of Analysis: 7/15/2014
Dry Weight Prepared: N/A
Wet Weight Prepared: N/A

Lab Sample ID: AB48955
Matrix: Water
Amount Prepared: 25 mL
Percent Solids: N/A
Extract Dilution: 1.01
pH: <2

CAS Number	Compound	Concentration ug/L	RL ug/L	Qualifier
7440-41-7	Beryllium	0.20	0.20	
7429-90-5	Aluminum	59	5.0	
7440-62-2	Vanadium	ND	0.20	
7440-47-3	Chromium	ND	0.50	
7439-96-5	Manganese	20	0.20	
7440-48-4	Cobalt	ND	0.20	
7440-02-0	Nickel	1.3	0.20	
7440-50-8	Copper	1.2	0.50	
7440-66-6	Zinc	88	5.0	
7440-38-2	Arsenic	ND	1.0	
7782-49-2	Selenium	ND	1.0	
7440-22-4	Silver	ND	0.20	
7440-43-9	Cadmium	ND	0.20	
7439-98-7	Molybdenum	ND	1.0	
7440-36-0	Antimony	ND	0.50	
7440-39-3	Barium	42	0.20	
7440-28-0	Thallium	ND	0.50	
7439-92-1	Lead	ND	0.20	
7439-95-4	Magnesium (mg/L)	1.6	0.10	
7440-70-2	Calcium (mg/L)	15	0.20	
7439-89-6	Iron	ND	50	
7440-61-1	Uranium	ND	1.0	

Comments:

Hatheway & Patterson Co - Mansfield, MA

Total Recoverable Metals in Water

Client Sample ID: 46 Chauncy Street
Date of Collection: 6/18/2014
Date of Preparation: 7/14/2014
Date of Analysis: 7/15/2014
Dry Weight Prepared: N/A
Wet Weight Prepared: N/A

Lab Sample ID: AB48956
Matrix: Water
Amount Prepared: 25 mL
Percent Solids: N/A
Extract Dilution: 1.01
pH: <2

CAS Number	Compound	Concentration ug/L	RL ug/L	Qualifier
7440-41-7	Beryllium	ND	0.20	
7429-90-5	Aluminum	ND	5.0	
7440-62-2	Vanadium	ND	0.20	
7440-47-3	Chromium	ND	0.50	
7439-96-5	Manganese	1600	0.20	
7440-48-4	Cobalt	2.2	0.20	
7440-02-0	Nickel	3.3	0.20	
7440-50-8	Copper	7.4	0.50	
7440-66-6	Zinc	590	5.0	
7440-38-2	Arsenic	4.1	1.0	
7782-49-2	Selenium	ND	1.0	
7440-22-4	Silver	ND	0.20	
7440-43-9	Cadmium	ND	0.20	
7439-98-7	Molybdenum	ND	1.0	
7440-36-0	Antimony	ND	0.50	
7440-39-3	Barium	41	0.20	
7440-28-0	Thallium	ND	0.50	
7439-92-1	Lead	0.58	0.20	
7439-95-4	Magnesium (mg/L)	3.8	0.10	
7440-70-2	Calcium (mg/L)	59	0.20	
7439-89-6	Iron	3200	50	
7440-61-1	Uranium	ND	1.0	

Comments:

Hatheway & Patterson Co - Mansfield, MA

Total Recoverable Metals in Water

Client Sample ID: 325 N Main Street
Date of Collection: 6/18/2014
Date of Preparation: 7/14/2014
Date of Analysis: 7/15/2014
Dry Weight Prepared: N/A
Wet Weight Prepared: N/A

Lab Sample ID: AB48957
Matrix: Water
Amount Prepared: 25 mL
Percent Solids: N/A
Extract Dilution: 1.01
pH: <2

CAS Number	Compound	Concentration ug/L	RL ug/L	Qualifier
7440-41-7	Beryllium	ND	0.20	
7429-90-5	Aluminum	ND	5.0	
7440-62-2	Vanadium	ND	0.20	
7440-47-3	Chromium	ND	0.50	
7439-96-5	Manganese	2600	2.0	
7440-48-4	Cobalt	8.1	0.20	
7440-02-0	Nickel	3.4	0.20	
7440-50-8	Copper	3.7	0.50	
7440-66-6	Zinc	18	5.0	
7440-38-2	Arsenic	ND	1.0	
7782-49-2	Selenium	ND	1.0	
7440-22-4	Silver	ND	0.20	
7440-43-9	Cadmium	ND	0.20	
7439-98-7	Molybdenum	ND	1.0	
7440-36-0	Antimony	ND	0.50	
7440-39-3	Barium	60	0.20	
7440-28-0	Thallium	ND	0.50	
7439-92-1	Lead	0.46	0.20	
7439-95-4	Magnesium (mg/L)	4.2	0.10	
7440-70-2	Calcium (mg/L)	33	0.20	
7439-89-6	Iron	3100	50	
7440-61-1	Uranium	ND	1.0	

Comments: The manganese result is reported from a 10x dilution.

Hatheway & Patterson Co - Mansfield, MA

Total Recoverable Metals in Water

Client Sample ID:	Town 1	Lab Sample ID:	AB48958
Date of Collection:	6/18/2014	Matrix:	Water
Date of Preparation:	7/14/2014	Amount Prepared:	25 mL
Date of Analysis:	7/15/2014	Percent Solids:	N/A
Dry Weight Prepared:	N/A	Extract Dilution:	1.01
Wet Weight Prepared:	N/A	pH:	<2

CAS Number	Compound	Concentration ug/L	RL ug/L	Qualifier
7440-41-7	Beryllium	ND	0.20	
7429-90-5	Aluminum	ND	5.0	
7440-62-2	Vanadium	0.28	0.20	
7440-47-3	Chromium	ND	0.50	
7439-96-5	Manganese	1.5	0.20	
7440-48-4	Cobalt	ND	0.20	
7440-02-0	Nickel	1.8	0.20	
7440-50-8	Copper	1.9	0.50	
7440-66-6	Zinc	19	5.0	
7440-38-2	Arsenic	ND	1.0	
7782-49-2	Selenium	ND	1.0	
7440-22-4	Silver	ND	0.20	
7440-43-9	Cadmium	ND	0.20	
7439-98-7	Molybdenum	ND	1.0	
7440-36-0	Antimony	ND	0.50	
7440-39-3	Barium	32	0.20	
7440-28-0	Thallium	ND	0.50	
7439-92-1	Lead	ND	0.20	
7439-95-4	Magnesium (mg/L)	1.7	0.10	
7440-70-2	Calcium (mg/L)	18	0.20	
7439-89-6	Iron	ND	50	
7440-61-1	Uranium	ND	1.0	

Comments:

Hatheway & Patterson Co - Mansfield, MA

Total Recoverable Metals in Water

Client Sample ID:	Town 2	Lab Sample ID:	AB48959
Date of Collection:	6/18/2014	Matrix:	Water
Date of Preparation:	7/14/2014	Amount Prepared:	25 mL
Date of Analysis:	7/15/2014	Percent Solids:	N/A
Dry Weight Prepared:	N/A	Extract Dilution:	1.01
Wet Weight Prepared:	N/A	pH:	<2

CAS Number	Compound	Concentration ug/L	RL ug/L	Qualifier
7440-41-7	Beryllium	ND	0.20	
7429-90-5	Aluminum	10	5.0	
7440-62-2	Vanadium	ND	0.20	
7440-47-3	Chromium	ND	0.50	
7439-96-5	Manganese	1400	0.20	
7440-48-4	Cobalt	5.0	0.20	
7440-02-0	Nickel	6.7	0.20	
7440-50-8	Copper	7.2	0.50	
7440-66-6	Zinc	39	5.0	
7440-38-2	Arsenic	ND	1.0	
7782-49-2	Selenium	ND	1.0	
7440-22-4	Silver	ND	0.20	
7440-43-9	Cadmium	ND	0.20	
7439-98-7	Molybdenum	ND	1.0	
7440-36-0	Antimony	ND	0.50	
7440-39-3	Barium	300	0.20	
7440-28-0	Thallium	ND	0.50	
7439-92-1	Lead	0.74	0.20	
7439-95-4	Magnesium (mg/L)	6.9	0.10	
7440-70-2	Calcium (mg/L)	57	2.0	
7439-89-6	Iron	3500	50	
7440-61-1	Uranium	ND	1.0	

Comments: The calcium result is reported from a 10x dilution.

Hatheway & Patterson Co - Mansfield, MA

Total Recoverable Metals in Water

Client Sample ID: 132 Highland ave
Date of Collection: 6/18/2014
Date of Preparation: 7/14/2014
Date of Analysis: 7/15/2014
Dry Weight Prepared: N/A
Wet Weight Prepared: N/A

Lab Sample ID: AB48960
Matrix: Water
Amount Prepared: 25 mL
Percent Solids: N/A
Extract Dilution: 1.01
pH: <2

CAS Number	Compound	Concentration ug/L	RL ug/L	Qualifier
7440-41-7	Beryllium	ND	0.20	
7429-90-5	Aluminum	36	5.0	
7440-62-2	Vanadium	ND	0.20	
7440-47-3	Chromium	0.50	0.50	
7439-96-5	Manganese	11	0.20	
7440-48-4	Cobalt	ND	0.20	
7440-02-0	Nickel	2.1	0.20	
7440-50-8	Copper	46	0.50	
7440-66-6	Zinc	17	5.0	
7440-38-2	Arsenic	ND	1.0	
7782-49-2	Selenium	ND	1.0	
7440-22-4	Silver	ND	0.20	
7440-43-9	Cadmium	ND	0.20	
7439-98-7	Molybdenum	ND	1.0	
7440-36-0	Antimony	ND	0.50	
7440-39-3	Barium	60	0.20	
7440-28-0	Thallium	ND	0.50	
7439-92-1	Lead	3.5	0.20	
7439-95-4	Magnesium (mg/L)	2.1	0.10	
7440-70-2	Calcium (mg/L)	24	0.20	
7439-89-6	Iron	340	50	
7440-61-1	Uranium	ND	1.0	

Comments:

Hatheway & Patterson Co - Mansfield, MA

Total Recoverable Metals in Water

Client Sample ID: 132 (d) Highland ave
Date of Collection: 6/18/2014
Date of Preparation: 7/14/2014
Date of Analysis: 7/15/2014
Dry Weight Prepared: N/A
Wet Weight Prepared: N/A

Lab Sample ID: AB48961
Matrix: Water
Amount Prepared: 25 mL
Percent Solids: N/A
Extract Dilution: 1.01
pH: <2

CAS Number	Compound	Concentration ug/L	RL ug/L	Qualifier
7440-41-7	Beryllium	ND	0.20	
7429-90-5	Aluminum	49	5.0	
7440-62-2	Vanadium	0.22	0.20	
7440-47-3	Chromium	0.56	0.50	
7439-96-5	Manganese	11	0.20	
7440-48-4	Cobalt	ND	0.20	
7440-02-0	Nickel	2.2	0.20	
7440-50-8	Copper	78	0.50	
7440-66-6	Zinc	24	5.0	
7440-38-2	Arsenic	ND	1.0	
7782-49-2	Selenium	ND	1.0	
7440-22-4	Silver	ND	0.20	
7440-43-9	Cadmium	ND	0.20	
7439-98-7	Molybdenum	ND	1.0	
7440-36-0	Antimony	ND	0.50	
7440-39-3	Barium	61	0.20	
7440-28-0	Thallium	ND	0.50	
7439-92-1	Lead	7.6	0.20	
7439-95-4	Magnesium (mg/L)	2.1	0.10	
7440-70-2	Calcium (mg/L)	24	0.20	
7439-89-6	Iron	940	50	
7440-61-1	Uranium	ND	1.0	

Comments:

Hatheway & Patterson Co - Mansfield, MA

Laboratory Reagent Blank Result (ug/L)

Client Sample ID:	N/A	Lab Sample ID:	N/A
Date of Collection:	N/A	Matrix:	Water
Date of Preparation:	7/14/2014	Amount Prepared:	25 mL
Date of Analysis:	7/15/2014	Percent Solids:	N/A
Dry Weight Prepared:	N/A	Extract Dilution:	1.01
Wet Weight Prepared:	N/A	pH:	N/A

CAS Number	Compound	Concentration ug/L	RL ug/L	Qualifier
7440-41-7	Beryllium	ND	0.20	
7429-90-5	Aluminum	ND	5.0	
7440-62-2	Vanadium	ND	0.20	
7440-47-3	Chromium	ND	0.50	
7439-96-5	Manganese	ND	0.20	
7440-48-4	Cobalt	ND	0.20	
7440-02-0	Nickel	ND	0.20	
7440-50-8	Copper	ND	0.50	
7440-66-6	Zinc	ND	5.0	
7440-38-2	Arsenic	ND	1.0	
7782-49-2	Selenium	ND	1.0	
7440-22-4	Silver	ND	0.20	
7440-43-9	Cadmium	ND	0.20	
7439-98-7	Molybdenum	ND	1.0	
7440-36-0	Antimony	ND	0.50	
7440-39-3	Barium	ND	0.20	
7440-28-0	Thallium	ND	0.50	
7439-92-1	Lead	ND	0.20	
7439-95-4	Magnesium (mg/L)	ND	0.10	
7440-70-2	Calcium (mg/L)	ND	0.20	
7439-89-6	Iron	ND	50	
7440-61-1	Uranium	ND	1.0	

Comments:

Hatheway & Patterson Co - Mansfield, MA

MATRIX SPIKE (MS) RECOVERY

Sample ID: AB48957

PARAMETER	SPIKE ADDED ug/L	SAMPLE CONCENTRATION ug/L	MS CONCENTRATION ug/L	MS % REC	QC LIMITS (% REC)
Aluminum	40	ND	37.9	95	70 - 130
Antimony	40	ND	42.2	106	70 - 130
Arsenic	40	ND	44.2	110	70 - 130
Barium	40	60	97.2	93	70 - 130
Beryllium	40	ND	39.7	99	70 - 130
Cadmium	40	ND	39.5	99	70 - 130
Chromium	40	ND	38.6	97	70 - 130
Cobalt	40	8.1	47.1	98	70 - 130
Copper	40	3.7	40.9	93	70 - 130
Iron	440	3100	3480	R	70 - 130
Lead	40	0.46	42.1	104	70 - 130
Manganese	40	2600	2440	R	70 - 130
Molybdenum	40	ND	43.2	108	70 - 130
Nickel	40	3.4	40.6	93	70 - 130
Selenium	40	ND	40.3	101	70 - 130
Silver	40	ND	38.3	96	70 - 130
Thallium	40	ND	42.0	105	70 - 130
Uranium	40	ND	43.4	108	70 - 130
Vanadium	40	ND	41.2	103	70 - 130
Zinc	40	18	58.1	100	70 - 130

Hatheway & Patterson Co - Mansfield, MA

Laboratory Duplicate Results

Sample ID: AB48955

PARAMETER	SAMPLE RESULT ug/L	SAMPLE DUPLICATE RESULT ug/L	PRECISION RPD %	QC LIMITS
Aluminum	59	62	5.0	20
Antimony	ND	ND	NC	20
Arsenic	ND	ND	NC	20
Barium	42	42	0.0	20
Beryllium	0.20	ND	NC	20
Cadmium	ND	ND	NC	20
Calcium (mg/L)	15	15	0.0	20
Chromium	ND	ND	NC	20
Cobalt	ND	ND	NC	20
Copper	1.2	1.3	8.0	20
Iron	ND	ND	NC	20
Lead	ND	ND	NC	20
Magnesium (mg/L)	1.6	1.7	6.1	20
Manganese	20	21	4.9	20
Molybdenum	ND	ND	NC	20
Nickel	1.3	1.4	7.4	20
Selenium	ND	ND	NC	20
Silver	ND	ND	NC	20
Thallium	ND	ND	NC	20
Uranium	ND	ND	NC	20
Vanadium	ND	ND	NC	20
Zinc	88	92	4.4	20

Hatheway & Patterson Co - Mansfield, MA

Laboratory Fortified Blank (LFB) Results

PARAMETER	LFB AMOUNT SPIKED ug/L	LFB RESULT ug/L	LFB RECOVERY %	QC LIMITS %
Aluminum	40.0	39.2	98	85 - 115
Antimony	40.0	39.9	100	85 - 115
Arsenic	40.0	41.8	104	85 - 115
Barium	40.0	39.7	99	85 - 115
Beryllium	40.0	40.0	100	85 - 115
Cadmium	40.0	40.0	100	85 - 115
Calcium (mg/L)	8.00	7.58	95	85 - 115
Chromium	40.0	40.1	100	85 - 115
Cobalt	40.0	41.9	105	85 - 115
Copper	40.0	40.7	102	85 - 115
Iron	440	441	100	85 - 115
Lead	40.0	40.2	100	85 - 115
Magnesium (mg/L)	4.00	4.14	104	85 - 115
Manganese	40.0	40.0	100	85 - 115
Molybdenum	40.0	40.4	101	85 - 115
Nickel	40.0	40.7	102	85 - 115
Selenium	40.0	40.2	100	85 - 115
Silver	40.0	41.4	104	85 - 115
Thallium	40.0	41.1	103	85 - 115
Uranium	40.0	41.2	103	85 - 115
Vanadium	40.0	40.1	100	85 - 115
Zinc	40.0	42.8	107	85 - 115

Comments:

Samples in Batch: AB48954, AB48955, AB48956, AB48957, AB48958, AB48959, AB48960, AB48961



REGION 1

CHAIN OF CUSTODY RECORD

[illegible]

14060018\$MTMSW

1DFA - FORM I-HR CDD-1
CDD/CDF SAMPLE DATA SUMMARY
HIGH RESOLUTION

A0AA0

Lab Name: AGAT LABORATORIES

Contract: EP10W001067

Lab Code: AGATAB

Case No.: 44423

TO No.: 2134.2

SDG No.: A0AA0

Matrix: Water

Lab Sample ID: 5496756

Sample wt/vol: 970 mL

Lab File ID: 14M854568_5496756

Water Sample Prep: SEPF

Date Received: 06-23-2014

Concentrated Extract Volume: 20 uL

Date Extracted: 06-26-2014

Injection Volume: 1.0 uL % Solids/Lipids:

Date Analyzed: 07-02-2014

GC Column: DB-5

ID: 0.250 mm

Dilution Factor: 1.0

Concentration Units: pg/L

Target Analyte	Selected Ions	Peak RT	Ion Ratio #	Concentration	Q	EMPC/EDL
2378-TCDD	320/322				U	0.722
2378-TCDF	304/306	24.70	0.66	0.907	J	
12378-PeCDF	340/342	28.45	1.67	1.20	BJ	
12378-PeCDD	356/358				U	0.474
23478-PeCDF	340/342	29.19	1.24		*	0.722
123478-HxCDF	374/376	32.35	1.16	1.20	J	
123678-HxCDF	374/376	32.47	1.33	0.619	J	
123478-HxCDD	390/392				U	0.474
123678-HxCDD	390/392				U	0.515
123789-HxCDD	390/392				U	0.495
234678-HxCDF	374/376				U	0.392
123789-HxCDF	374/376	33.99	1.26	1.05	BJ	
1234678-HpCDF	408/410	35.85	1.13	0.722	J	
1234678-HpCDD	424/426				U	0.804
1234789-HpCDF	408/410	37.54	1.10	0.784	J	
OCDD	458/460	41.13	1.49		*	1.94
OCDF	442/444	41.35	0.90	2.60	J	

NOTE: Concentrations, Estimated Maximum Possible Concentrations (EMPCs), and Estimated Detection Levels (EDLs) for solid samples are calculated on a dry weight basis (except tissues, which are reported on a wet weight basis with % Lipids).

Labeled Compounds	Selected Ions	Peak RT	Ion Ratio #	Ion Ratio Limits	% Rec #	Recovery Limits
13C-2378-TCDD	332/334	25.30	0.82	0.65-0.89	65.2	25-164
13C-12378-PeCDD	368/370	29.54	1.56	1.32-1.78	88.3	25-181
13C-123478-HxCDD	402/404	33.23	1.30	1.05-1.43	84.1	32-141
13C-123678-HxCDD	402/404	33.32	1.32	1.05-1.43	77.1	28-130
13C-1234678-HpCDD	436/438	37.00	1.07	0.88-1.20	99.1	23-140
13C-OCDD	470/472	41.14	0.93	0.76-1.02	103.1	17-157
13C-2378-TCDF	316/318	24.68	0.84	0.65-0.89	72.4	24-169
13C-12378-PeCDF	352/354	28.43	1.60	1.32-1.78	79.6	24-185
13C-23478-PeCDF	352/354	29.18	1.62	1.32-1.78	88.1	21-178
13C-123478-HxCDF	384/386	32.35	0.53	0.43-0.59	78.7	26-152
13C-123678-HxCDF	384/386	32.47	0.53	0.43-0.59	74.9	26-123
13C-123789-HxCDF	384/386	33.96	0.53	0.43-0.59	78.9	29-147
13C-234678-HxCDF	384/386	33.08	0.53	0.43-0.59	84.6	28-136
13C-1234678-HpCDF	418/420	35.84	0.44	0.37-0.51	89.9	28-143
13C-1234789-HpCDF	418/420	37.52	0.45	0.37-0.51	99.1	26-138
37C1-2378-TCDD	328/NA	25.32	NA	NA	78.3	35-197

Column to be used to flag values outside QC limits.

1DFA - FORM I-HR CDD-1
CDD/CDF SAMPLE DATA SUMMARY
HIGH RESOLUTION

A0AA1

Lab Name: AGAT LABORATORIES

Contract: EP10W001067

Lab Code: AGATAB

Case No.: 44423

TO No.: 2134.2

SDG No.: A0AA0

Matrix: Water

Lab Sample ID: 5496758

Sample wt/vol: 1000 mL

Lab File ID: 14M854568_5496758

Water Sample Prep: SEPF

Date Received: 06-23-2014

Concentrated Extract Volume: 20 uL

Date Extracted: 06-26-2014

Injection Volume: 1.0 uL % Solids/Lipids:

Date Analyzed: 07-02-2014

GC Column: DB-5

ID: 0.250 mm

Dilution Factor: 1.0

Concentration Units: pg/L

Target Analyte	Selected Ions	Peak RT	Ion Ratio #	Concentration	Q	EMPC/EDL
2378-TCDD	320/322				U	0.880
2378-TCDF	304/306	24.70	0.82	0.740	J	
12378-PeCDF	340/342	28.44	1.43	1.10	BJ	
12378-PeCDD	356/358				U	0.560
23478-PeCDF	340/342				U	0.600
123478-HxCDF	374/376	32.36	1.31	0.880	J	
123678-HxCDF	374/376				U	0.360
123478-HxCDD	390/392				U	0.820
123678-HxCDD	390/392				U	0.800
123789-HxCDD	390/392				U	0.840
234678-HxCDF	374/376				U	0.380
123789-HxCDF	374/376				U	0.540
1234678-HpCDF	408/410				U	0.360
1234678-HpCDD	424/426				U	0.680
1234789-HpCDF	408/410				U	0.580
OCDD	458/460	41.14	0.92	1.52	J	
OCDF	442/444	41.34	0.90	3.20	J	

NOTE: Concentrations, Estimated Maximum Possible Concentrations (EMPCs), and Estimated Detection Levels (EDLs) for solid samples are calculated on a dry weight basis (except tissues, which are reported on a wet weight basis with % Lipids).

Labeled Compounds	Selected Ions	Peak RT	Ion Ratio #	Ion Ratio Limits	% Rec #	Recovery Limits
13C-2378-TCDD	332/334	25.30	0.82	0.65-0.89	44.6	25-164
13C-12378-PeCDD	368/370	29.55	1.60	1.32-1.78	68.4	25-181
13C-123478-HxCDD	402/404	33.23	1.31	1.05-1.43	69.8	32-141
13C-123678-HxCDD	402/404	33.32	1.31	1.05-1.43	68.8	28-130
13C-1234678-HpCDD	436/438	37.00	1.09	0.88-1.20	82.4	23-140
13C-OCDD	470/472	41.13	0.91	0.76-1.02	84.4	17-157
13C-2378-TCDF	316/318	24.68	0.83	0.65-0.89	44.0	24-169
13C-12378-PeCDF	352/354	28.44	1.62	1.32-1.78	56.2	24-185
13C-23478-PeCDF	352/354	29.18	1.64	1.32-1.78	58.6	21-178
13C-123478-HxCDF	384/386	32.35	0.52	0.43-0.59	67.7	26-152
13C-123678-HxCDF	384/386	32.47	0.54	0.43-0.59	62.1	26-123
13C-123789-HxCDF	384/386	33.96	0.52	0.43-0.59	68.3	29-147
13C-234678-HxCDF	384/386	33.08	0.53	0.43-0.59	66.4	28-136
13C-1234678-HpCDF	418/420	35.83	0.43	0.37-0.51	74.2	28-143
13C-1234789-HpCDF	418/420	37.52	0.45	0.37-0.51	80.9	26-138
37C1-2378-TCDD	328/NA	25.32	NA	NA	49.0	35-197

Column to be used to flag values outside QC limits.

1DFA - FORM I-HR CDD-1
CDD/CDF SAMPLE DATA SUMMARY
HIGH RESOLUTION

EPA Sample No.

A0AA2

Lab Name: AGAT LABORATORIES

Contract: EP10W001067

Lab Code: AGATAB

Case No.: 44423

TO No.: 2134.2

SDG No.: A0AA0

Matrix: Water

Lab Sample ID: 5496759

Sample wt/vol: 960 mL

Lab File ID: 14M854568_5496759

Water Sample Prep: SEPF

Date Received: 06-23-2014

Concentrated Extract Volume: 20 uL

Date Extracted: 06-26-2014

Injection Volume: 1.0 uL % Solids/Lipids:

Date Analyzed: 07-02-2014

GC Column: DB-5

ID: 0.250 mm

Dilution Factor: 1.0

Concentration Units: pg/L

Target Analyte	Selected Ions	Peak RT	Ion Ratio #	Concentration	Q	EMPC/EDL
2378-TCDD	320/322				U	0.688
2378-TCDF	304/306	24.68	0.83	0.958	J	
12378-PeCDF	340/342	28.44	1.26		*	0.792
12378-PeCDD	356/358				U	0.458
23478-PeCDF	340/342				U	0.396
123478-HxCDF	374/376	32.37	1.33	0.833	J	
123678-HxCDF	374/376				U	0.271
123478-HxCDD	390/392				U	0.521
123678-HxCDD	390/392				U	0.542
123789-HxCDD	390/392				U	0.542
234678-HxCDF	374/376				U	0.292
123789-HxCDF	374/376	33.95	1.13	0.667	BJ	
1234678-HpCDF	408/410	35.84	1.11	0.458	J	
1234678-HpCDD	424/426	37.00	1.00	0.625	J	
1234789-HpCDF	408/410				U	0.458
OCDD	458/460				U	0.729
OCDF	442/444	41.34	0.79	3.35	J	

NOTE: Concentrations, Estimated Maximum Possible Concentrations (EMPCs), and Estimated Detection Levels (EDLs) for solid samples are calculated on a dry weight basis (except tissues, which are reported on a wet weight basis with % Lipids)..

Labeled Compounds	Selected Ions	Peak RT	Ion Ratio #	Ion Ratio Limits	% Rec #	Recovery Limits
13C-2378-TCDD	332/334	25.30	0.79	0.65-0.89	69.4	25-164
13C-12378-PeCDD	368/370	29.54	1.64	1.32-1.78	85.7	25-181
13C-123478-HxCDD	402/404	33.21	1.30	1.05-1.43	87.5	32-141
13C-123678-HxCDD	402/404	33.31	1.29	1.05-1.43	75.3	28-130
13C-1234678-HpCDD	436/438	36.99	1.10	0.88-1.20	100.4	23-140
13C-OCDD	470/472	41.13	0.92	0.76-1.02	110.6	17-157
13C-2378-TCDF	316/318	24.68	0.83	0.65-0.89	74.8	24-169
13C-12378-PeCDF	352/354	28.43	1.63	1.32-1.78	81.7	24-185
13C-23478-PeCDF	352/354	29.18	1.63	1.32-1.78	84.5	21-178
13C-123478-HxCDF	384/386	32.35	0.51	0.43-0.59	83.5	26-152
13C-123678-HxCDF	384/386	32.47	0.53	0.43-0.59	73.4	26-123
13C-123789-HxCDF	384/386	33.95	0.53	0.43-0.59	85.5	29-147
13C-234678-HxCDF	384/386	33.07	0.54	0.43-0.59	80.9	28-136
13C-1234678-HpCDF	418/420	35.82	0.45	0.37-0.51	88.5	28-143
13C-1234789-HpCDF	418/420	37.51	0.46	0.37-0.51	102.5	26-138
37C1-2378-TCDD	328/NA	25.32	NA	NA	69.6	35-197

Column to be used to flag values outside QC limits.

1DFA - FORM I-HR CDD-1
CDD/CDF SAMPLE DATA SUMMARY
HIGH RESOLUTION

A0AA3

Lab Name: AGAT LABORATORIES

Contract: EP10W001067

Lab Code: AGATAB

Case No.: 44423

TO No.: 2134.2

SDG No.: A0AA0

Matrix: Water

Lab Sample ID: 5496760

Sample wt/vol: 990 mL

Lab File ID: 14M854568_5496760

Water Sample Prep: SEPF

Date Received: 06-23-2014

Concentrated Extract Volume: 20 uL

Date Extracted: 06-26-2014

Injection Volume: 1.0 uL % Solids/Lipids:

Date Analyzed: 07-04-2014

GC Column: DB-5

ID: 0.250 mm

Dilution Factor: 1.0

Concentration Units: pg/L

Target Analyte	Selected Ions	Peak RT	Ion Ratio #	Concentration	Q	EMPC/EDL
2378-TCDD	320/322				U	1.11
2378-TCDF	304/306	24.68	0,87	1.72	J	
12378-PeCDF	340/342	28.41	1,16		*	1.41
12378-PeCDD	356/358	29.56	1,72	0.869	BJ	
23478-PeCDF	340/342	29.19	1,38	0.949	BJ	
123478-HxCDF	374/376	32.35	1,27	1.94	J	
123678-HxCDF	374/376				U	0.768
123478-HxCDD	390/392				U	0.970
123678-HxCDD	390/392				U	1.01
123789-HxCDD	390/392				U	0.990
234678-HxCDF	374/376				U	0.808
123789-HxCDF	374/376				U	1.54
1234678-HpCDF	408/410	35.84	1,19	1.23	J	
1234678-HpCDD	424/426				U	1.03
1234789-HpCDF	408/410				U	0.808
OCDD	458/460	41.10	0,78	3.92	J	
OCDF	442/444	41.33	1,02	4.20	J	

NOTE: Concentrations, Estimated Maximum Possible Concentrations (EMPCs), and Estimated Detection Levels (EDLs) for solid samples are calculated on a dry weight basis (except tissues, which are reported on a wet weight basis with % Lipids).

Labeled Compounds	Selected Ions	Peak RT	Ion Ratio #	Ion Ratio Limits	% Rec #	Recovery Limits
13C-2378-TCDD	332/334	25.29	0,77	0.65-0.89	71,7	25-164
13C-12378-PeCDD	368/370	29.53	1,59	1.32-1.78	94,1	25-181
13C-123478-HxCDD	402/404	33.20	1,30	1.05-1.43	88,4	32-141
13C-123678-HxCDD	402/404	33.30	1,29	1.05-1.43	86,0	28-130
13C-1234678-HpCDD	436/438	37.00	1,08	0.88-1.20	111	23-140
13C-OCDD	470/472	41.11	0,91	0.76-1.02	95,0	17-157
13C-2378-TCDF	316/318	24.65	0,83	0.65-0.89	76,0	24-169
13C-12378-PeCDF	352/354	28.41	1,56	1.32-1.78	81,7	24-185
13C-23478-PeCDF	352/354	29.16	1,66	1.32-1.78	95,9	21-178
13C-123478-HxCDF	384/386	32.34	0,53	0.43-0.59	89,1	26-152
13C-123678-HxCDF	384/386	32.45	0,54	0.43-0.59	79,4	26-123
13C-123789-HxCDF	384/386	33.95	0,52	0.43-0.59	65,6	29-147
13C-234678-HxCDF	384/386	33.07	0,53	0.43-0.59	79,0	28-136
13C-1234678-HpCDF	418/420	35.83	0,44	0.37-0.51	93,4	28-143
13C-1234789-HpCDF	418/420	37.51	0,44	0.37-0.51	111	26-138
37C1-2378-TCDD	328/NA	25.30	NA	NA	72,6	35-197

Column to be used to flag values outside QC limits.

1DFA - FORM I-HR CDD-1
CDD/CDF SAMPLE DATA SUMMARY
HIGH RESOLUTION

A0AA4

Lab Name: AGAT LABORATORIES

Contract: EP10W001067

Lab Code: AGATAB

Case No.: 44423

TO No.: 2134.2

SDG No.: A0AA0

Matrix: Water

Lab Sample ID: 5496761

Sample wt/vol: 970 mL

Lab File ID: 14M854568_5496761

Water Sample Prep: SEPF

Date Received: 06-23-2014

Concentrated Extract Volume: 20 uL

Date Extracted: 06-26-2014

Injection Volume: 1.0 uL, % Solids/Lipids:

Date Analyzed: 07-02-2014

GC Column: DB-5

ID: 0.250 mm

Dilution Factor: 1.0

Concentration Units: pg/L

Target Analyte	Selected Ions	Peak RT	Ion Ratio #	Concentration	Q	EMPC/EDL
2378-TCDD	320/322				U	0.825
2378-TCDF	304/306	24.68	0.72	1.09	J	
12378-PeCDF	340/342	28.43	1.43	1.09	BJ	
12378-PeCDD	356/358				U	0.474
23478-PeCDF	340/342				U	0.619
123478-HxCDF	374/376	32.36	1.09	1.49	J	
123678-HxCDF	374/376				U	0.309
123478-HxCDD	390/392				U	0.495
123678-HxCDD	390/392				U	0.474
123789-HxCDD	390/392				U	0.495
234678-HxCDF	374/376				U	0.289
123789-HxCDF	374/376	33.95	1.20	0.742	BJ	
1234678-HpCDF	408/410	35.83	1.08	0.742	J	
1234678-HpCDD	424/426				U	0.845
1234789-HpCDF	408/410				U	0.412
OCDD	458/460	41.12	0.93	2.80	J	
OCDF	442/444	41.34	0.88	4.99	J	

NOTE: Concentrations, Estimated Maximum Possible Concentrations (EMPCs), and Estimated Detection Levels (EDLs) for solid samples are calculated on a dry weight basis (except tissues, which are reported on a wet weight basis with % Lipids).

Labeled Compounds	Selected Ions	Peak RT	Ion Ratio #	Ion Ratio Limits	% Rec #	Recovery Limits
13C-2378-TCDD	332/334	25.30	0.79	0.65-0.89	41.9	25-164
13C-12378-PeCDD	368/370	29.54	1.52	1.32-1.78	73.1	25-181
13C-123478-HxCDD	402/404	33.22	1.29	1.05-1.43	71.5	32-141
13C-123678-HxCDD	402/404	33.31	1.29	1.05-1.43	69.6	28-130
13C-1234678-HpCDD	436/438	36.99	1.08	0.88-1.20	90.3	23-140
13C-OCDD	470/472	41.13	0.92	0.76-1.02	73.0	17-157
13C-2378-TCDF	316/318	24.68	0.81	0.65-0.89	44.5	24-169
13C-12378-PeCDF	352/354	28.43	1.61	1.32-1.78	58.4	24-185
13C-23478-PeCDF	352/354	29.18	1.63	1.32-1.78	64.4	21-178
13C-123478-HxCDF	384/386	32.35	0.52	0.43-0.59	64.2	26-152
13C-123678-HxCDF	384/386	32.46	0.53	0.43-0.59	60.8	26-123
13C-123789-HxCDF	384/386	33.95	0.53	0.43-0.59	73.3	29-147
13C-234678-HxCDF	384/386	33.07	0.53	0.43-0.59	70.7	28-136
13C-1234678-HpCDF	418/420	35.82	0.45	0.37-0.51	70.3	28-143
13C-1234789-HpCDF	418/420	37.51	0.43	0.37-0.51	97.5	26-138
37C1-2378-TCDD	328/NA	25.32	NA	NA	47.7	35-197

Column to be used to flag values outside QC limits.

1DFA - FORM I-HR CDD-1
CDD/CDF SAMPLE DATA SUMMARY
HIGH RESOLUTION

A0AA5

Lab Name: AGAT LABORATORIES

Contract: EP10W001067

Lab Code: AGATAB

Case No.: 44423

TO No.: 2134.2

SDG No.: A0AA0

Matrix: Water

Lab Sample ID: 5496762

Sample wt/vol: 1000 mL

Lab File ID: 14M854568_5496762

Water Sample Prep: SEPF

Date Received: 06-23-2014

Concentrated Extract Volume: 20 uL

Date Extracted: 06-26-2014

Injection Volume: 1.0 uL % Solids/Lipids:

Date Analyzed: 07-03-2014

GC Column: DB-5

ID: 0.250 mm

Dilution Factor: 1.0

Concentration Units: pg/L

Target Analyte	Selected Ions	Peak RT	Ion Ratio #	Concentration	Q	EMPC/EDL
2378-TCDD	320/322				U	0.800
2378-TCDF	304/306	24.68	0.83	0.740	J	
12378-PeCDF	340/342	28.43	1.44	1.06	BJ	
12378-PeCDD	356/358				U	0.640
23478-PeCDF	340/342				U	0.520
123478-HxCDF	374/376	32.36	1.63		*	0.680
123678-HxCDF	374/376				U	0.400
123478-HxCDD	390/392				U	0.640
123678-HxCDD	390/392				U	0.620
123789-HxCDD	390/392				U	0.660
234678-HxCDF	374/376				U	0.420
123789-HxCDF	374/376				U	0.620
1234678-HpCDF	408/410	35.81	1.12	0.800	J	
1234678-HpCDD	424/426	36.99	0.97	1.32	J	
1234789-HpCDF	408/410				U	0.560
OCDD	458/460	41.11	0.81	3.72	J	
OCDF	442/444	41.33	0.79	3.16	J	

NOTE: Concentrations, Estimated Maximum Possible Concentrations (EMPCs), and Estimated Detection Levels (EDLs) for solid samples are calculated on a dry weight basis (except tissues, which are reported on a wet weight basis with % Lipids).

Labeled Compounds	Selected Ions	Peak RT	Ion Ratio #	Ion Ratio Limits	% Rec #	Recovery Limits
13C-2378-TCDD	332/334	25.29	0.81	0.65-0.89	66.2	25-164
13C-12378-PeCDD	368/370	29.53	1.61	1.32-1.78	83.7	25-181
13C-123478-HxCDD	402/404	33.20	1.31	1.05-1.43	83.2	32-141
13C-123678-HxCDD	402/404	33.30	1.30	1.05-1.43	77.3	28-130
13C-1234678-HpCDD	436/438	36.98	1.08	0.88-1.20	94.7	23-140
13C-OCDD	470/472	41.11	0.90	0.76-1.02	103.4	17-157
13C-2378-TCDF	316/318	24.66	0.83	0.65-0.89	67.3	24-169
13C-12378-PeCDF	352/354	28.41	1.65	1.32-1.78	77.1	24-185
13C-23478-PeCDF	352/354	29.17	1.64	1.32-1.78	77.7	21-178
13C-123478-HxCDF	384/386	32.34	0.52	0.43-0.59	78.1	26-152
13C-123678-HxCDF	384/386	32.45	0.54	0.43-0.59	77.5	26-123
13C-123789-HxCDF	384/386	33.94	0.52	0.43-0.59	81.7	29-147
13C-234678-HxCDF	384/386	33.06	0.55	0.43-0.59	80.4	28-136
13C-1234678-HpCDF	418/420	35.81	0.45	0.37-0.51	86.4	28-143
13C-1234789-HpCDF	418/420	37.49	0.45	0.37-0.51	94.8	26-138
37Cl-2378-TCDD	328/NA	25.30	NA	NA	63.4	35-197

Column to be used to flag values outside QC limits.

1DFA - FORM I-HR CDD-1
CDD/CDF SAMPLE DATA SUMMARY
HIGH RESOLUTION

EPA Sample No.

A0AA6

Lab Name: AGAT LABORATORIES

Contract: EP10W001067

Lab Code: AGATAB

Case No.: 44423

TO No.: 2134.2

SDG No.: A0AA0

Matrix: Water

Lab Sample ID: 5496763

Sample wt/vol: 990 mL

Lab File ID: 14M854568_5496763

Water Sample Prep: SEPF

Date Received: 06-23-2014

Concentrated Extract Volume: 20 uL

Date Extracted: 06-26-2014

Injection Volume: 1.0 uL % Solids/Lipids:

Date Analyzed: 07-03-2014

GC Column: DB-5

ID: 0.250 mm

Dilution Factor: 1.0

Concentration Units: pg/L

Target Analyte	Selected Ions	Peak RT	Ion Ratio #	Concentration	Q	EMPC/EDL
2378-TCDD	320/322				U	0.727
2378-TCDF	304/306	24.66	0.65		*	1.13
12378-PeCDF	340/342	28.44	1.35	0.869	BJ	
12378-PeCDD	356/358				U	0.444
23478-PeCDF	340/342				U	0.606
123478-HxCDF	374/376	32.34	1.12	1.13	J	
123678-HxCDF	374/376				U	0.364
123478-HxCDD	390/392				U	0.545
123678-HxCDD	390/392				U	0.525
123789-HxCDD	390/392				U	0.566
234678-HxCDF	374/376				U	0.364
123789-HxCDF	374/376				U	0.525
1234678-HpCDF	408/410	35.83	0.92	0.768	J	
1234678-HpCDD	424/426	36.99	1.11	1.64	J	
1234789-HpCDF	408/410				U	0.566
OCDD	458/460	41.11	0.98	6.73	J	
OCDF	442/444	41.31	0.84	5.46	J	

NOTE: Concentrations, Estimated Maximum Possible Concentrations (EMPCs), and Estimated Detection Levels (EDLs) for solid samples are calculated on a dry weight basis (except tissues, which are reported on a wet weight basis with % Lipids).

Labeled Compounds	Selected Ions	Peak RT	Ion Ratio #	Ion Ratio Limits	% Rec #	Recovery Limits
13C-2378-TCDD	332/334	25.29	0.81	0.65-0.89	47.8	25-164
13C-12378-PeCDD	368/370	29.53	1.56	1.32-1.78	79.6	25-181
13C-123478-HxCDD	402/404	33.20	1.30	1.05-1.43	72.9	32-141
13C-123678-HxCDD	402/404	33.30	1.29	1.05-1.43	73.1	28-130
13C-1234678-HpCDD	436/438	36.97	1.09	0.88-1.20	85.6	23-140
13C-OCDD	470/472	41.11	0.94	0.76-1.02	67.6	17-157
13C-2378-TCDF	316/318	24.66	0.82	0.65-0.89	49.0	24-169
13C-12378-PeCDF	352/354	28.41	1.62	1.32-1.78	63.5	24-185
13C-23478-PeCDF	352/354	29.17	1.65	1.32-1.78	68.4	21-178
13C-123478-HxCDF	384/386	32.33	0.52	0.43-0.59	66.7	26-152
13C-123678-HxCDF	384/386	32.45	0.53	0.43-0.59	62.9	26-123
13C-123789-HxCDF	384/386	33.94	0.53	0.43-0.59	75.3	29-147
13C-234678-HxCDF	384/386	33.06	0.54	0.43-0.59	71.9	28-136
13C-1234678-HpCDF	418/420	35.81	0.44	0.37-0.51	65.8	28-143
13C-1234789-HpCDF	418/420	37.48	0.45	0.37-0.51	94.0	26-138
37Cl-2378-TCDD	328/NA	25.30	NA	NA	46.8	35-197

Column to be used to flag values outside QC limits.

1DFA - FORM I-HR CDD-1
CDD/CDF SAMPLE DATA SUMMARY
HIGH RESOLUTION

A0AA8

Lab Name: AGAT LABORATORIES

Contract: EP10W001067

Lab Code: AGATAB

Case No.: 44423

TO No.: 2134.2

SDG No.: A0AA0

Matrix: Water

Lab Sample ID: 5496764

Sample wt/vol: 960 mL

Lab File ID: 14M854568_5496764

Water Sample Prep: SEPF

Date Received: 06-23-2014

Concentrated Extract Volume: 20 uL

Date Extracted: 06-26-2014

Injection Volume: 1.0 uL % Solids/Lipids:

Date Analyzed: 07-04-2014

GC Column: DB-5

ID: 0.250 mm

Dilution Factor: 1.0

Concentration Units: pg/L

Target Analyte	Selected Ions	Peak RT	Ion Ratio #	Concentration	Q	EMPC/EDL
2378-TCDD	320/322				U	1.15
2378-TCDF	304/306	24.68	0.87	0.875	J	
12378-PeCDF	340/342				U	0.917
12378-PeCDD	356/358				U	1.08
23478-PeCDF	340/342				U	0.750
123478-HxCDF	374/376	32.36	1.24	1.58	J	
123678-HxCDF	374/376				U	0.563
123478-HxCDD	390/392				U	1.06
123678-HxCDD	390/392				U	1.08
123789-HxCDD	390/392				U	1.08
234678-HxCDF	374/376				U	0.604
123789-HxCDF	374/376				U	1.15
1234678-HpCDF	408/410	35.83	1.13	0.708	J	
1234678-HpCDD	424/426				U	1.15
1234789-HpCDF	408/410				U	1.00
OCDD	458/460	41.13	0.78	2.94	J	
OCDF	442/444	41.32	0.89	4.58	J	

NOTE: Concentrations, Estimated Maximum Possible Concentrations (EMPCs), and Estimated Detection Levels (EDLs) for solid samples are calculated on a dry weight basis (except tissues, which are reported on a wet weight basis with % Lipids).

Labeled Compounds	Selected Ions	Peak RT	Ion Ratio #	Ion Ratio Limits	% Rec #	Recovery Limits
13C-2378-TCDD	332/334	25.29	0.83	0.65-0.89	69.3	25-164
13C-12378-PeCDD	368/370	29.53	1.66	1.32-1.78	93.1	25-181
13C-123478-HxCDD	402/404	33.22	1.29	1.05-1.43	89.7	32-141
13C-123678-HxCDD	402/404	33.31	1.29	1.05-1.43	89.6	28-130
13C-1234678-HpCDD	436/438	37.00	1.09	0.88-1.20	114.7	23-140
13C-OCDD	470/472	41.11	0.91	0.76-1.02	95.9	17-157
13C-2378-TCDF	316/318	24.66	0.82	0.65-0.89	76.2	24-169
13C-12378-PeCDF	352/354	28.41	1.60	1.32-1.78	80.0	24-185
13C-23478-PeCDF	352/354	29.17	1.66	1.32-1.78	93.5	21-178
13C-123478-HxCDF	384/386	32.34	0.52	0.43-0.59	91.5	26-152
13C-123678-HxCDF	384/386	32.45	0.53	0.43-0.59	77.8	26-123
13C-123789-HxCDF	384/386	33.95	0.54	0.43-0.59	70.2	29-147
13C-234678-HxCDF	384/386	33.07	0.53	0.43-0.59	80.8	28-136
13C-1234678-HpCDF	418/420	35.83	0.44	0.37-0.51	96.6	28-143
13C-1234789-HpCDF	418/420	37.51	0.46	0.37-0.51	114.7	26-138
37Cl-2378-TCDD	328/NA	25.30	NA	NA	80.5	35-197

Column to be used to flag values outside QC limits.

1DFA -- FORM I-HR CDD-1
CDD/CDF SAMPLE DATA SUMMARY
HIGH RESOLUTION

A0AB0

Lab Name: AGAT LABORATORIES

Contract: EP10W001067

Lab Code: AGATAB

Case No.: 44423

TO No.: 2134.2

SDG No.: A0AA0

Matrix: Water

Lab Sample ID: 5496768

Sample wt/vol: 855 ml (See case narrative)

Lab File ID: 14M854568_5496768

Water Sample Prep: SEPF

Date Received: 06-23-2014

Concentrated Extract Volume: 20 uL

Date Extracted: 06-26-2014

Injection Volume: 1.0 uL % Solids/Lipids:

Date Analyzed: 07-03-2014

GC Column: DB-5

ID: 0.250 mm

Dilution Factor: 1.0

Concentration Units: pg/L

Target Analyte	Selected Ions	Peak RT	Ion Ratio #	Concentration	Q	EMPC/EDL
2378-TCDD	320/322	25.30	0.88	186		
2378-TCDF	304/306	24.68	0.78	587		
12378-PeCDF	340/342	28.43	1.55	344	B	
12378-PeCDD	356/358	29.54	1.61	238	B	
23478-PeCDF	340/342	29.18	1.51	227	B	
123478-HxCDF	374/376	32.35	1.22	219		
123678-HxCDF	374/376	32.47	1.22	421		
123478-HxCDD	390/392	33.23	1.32	528	B	
123678-HxCDD	390/392	33.33	1.13	429		
123789-HxCDD	390/392	33.70	1.32	388	B	
234678-HxCDF	374/376	33.10	1.20	419		
123789-HxCDF	374/376	33.96	1.25	531	B	
1234678-HpCDF	408/410	35.85	0.98	234		
1234678-HpCDD	424/426	37.01	1.04	524		
1234789-HpCDF	408/410	37.52	1.04	527		
OCDD	458/460	41.12	0.94	809		
OCDF	442/444	41.31	0.90	979		

NOTE: Concentrations, Estimated Maximum Possible Concentrations (EMPCs), and Estimated Detection Levels (EDLs) for solid samples are calculated on a dry weight basis (except tissues, which are reported on a wet weight basis with % Lipids).

Labeled Compounds	Selected Ions	Peak RT	Ion Ratio #	Ion Ratio Limits	% Rec #	Recovery Limits
13C-2378-TCDD	332/334	25.27	0.81	0.65-0.89	73.7	25-164
13C-12378-PeCDD	368/370	29.53	1.54	1.32-1.78	93.2	25-181
13C-123478-HxCDD	402/404	33.22	1.30	1.05-1.43	101.8	32-141
13C-123678-HxCDD	402/404	33.31	1.30	1.05-1.43	81.6	28-130
13C-1234678-HpCDD	436/438	36.99	1.10	0.88-1.20	119.0	23-140
13C-OCDD	470/472	41.11	0.92	0.76-1.02	122.2	17-157
13C-2378-TCDF	316/318	24.65	0.81	0.65-0.89	75.9	24-169
13C-12378-PeCDF	352/354	28.40	1.62	1.32-1.78	86.0	24-185
13C-23478-PeCDF	352/354	29.16	1.65	1.32-1.78	92.2	21-178
13C-123478-HxCDF	384/386	32.34	0.52	0.43-0.59	94.5	26-152
13C-123678-HxCDF	384/386	32.45	0.53	0.43-0.59	81.2	26-123
13C-123789-HxCDF	384/386	33.95	0.53	0.43-0.59	72.8	29-147
13C-234678-HxCDF	384/386	33.07	0.52	0.43-0.59	87.0	28-136
13C-1234678-HpCDF	418/420	35.83	0.45	0.37-0.51	105.0	28-143
13C-1234789-HpCDF	418/420	37.51	0.45	0.37-0.51	119.0	26-138
37C1-2378-TCDD	328/NA	25.29	NA	NA	78.4	35-197

Column to be used to flag values outside QC limits.

1DFB - FORM I-HR CDD-2
CDD/CDF TOXICITY EQUIVALENCE SUMMARY
HIGH RESOLUTION

A0AA0

Lab Name: AGAT LABORATORIES

Contract: EP10W001067

Lab Code: AGATAB

Case No.: 44423

TO No.: 2134.2

SDG No.: A0AA0

Matrix: Water

Lab Sample ID: 5496756

Sample wt/vol: 970 mL

Lab File ID: 14M854568_5496756

Water Sample Prep: SEPF

Date Received: 06-23-2014

Concentrated Extract Volume: 20 uL

Date Extracted: 06-26-2014

Injection Volume: 1.0 uL % Solids/Lipids:

Date Analyzed: 07-02-2014

GC Column: DB-5

ID: 0.250 mm

Dilution Factor: 1.0

Concentration Units: pg/L

Target Analyte	Concentration	TEF*	TEF-Adjusted Concentration
2378-TCDD	0.0	x 1.0 =	0.0
2378-TCDF	0.907	x 0.1 =	0.0907
12378-PeCDF	1.20	x 0.03 =	0.0359
12378-PeCDD	0.0	x 1.0 =	0.0
23478-PeCDF	0.722	x 0.3 =	0.216
123478-HxCDF	1.20	x 0.1 =	0.120
123678-HxCDF	0.619	x 0.1 =	0.0619
123478-HxCDD	0.0	x 0.1 =	0.0
123678-HxCDD	0.0	x 0.1 =	0.0
123789-HxCDD	0.0	x 0.1 =	0.0
234678-HxCDF	0.0	x 0.1 =	0.0
123789-HxCDF	1.05	x 0.1 =	0.105
1234678-HpCDF	0.722	x 0.01 =	0.00722
1234678-HpCDD	0.0	x 0.01 =	0.0
1234789-HpCDF	0.784	x 0.01 =	0.00784
OCDD	1.94	x 0.0003 =	0.000581
OCDF	2.60	x 0.0003 =	0.000779
		Total =	0.646

* TEF - Toxicity Equivalent Factors from the World Health Organization (WHO), 2005.

1DFB - FORM I-HR CDD-2
CDD/CDF TOXICITY EQUIVALENCE SUMMARY
HIGH RESOLUTION

EPA Sample No.

A0AA1

Lab Name: AGAT LABORATORIES

Contract: EP10W001067

Lab Code: AGATAB

Case No.: 44423

TO No.: 2134.2

SDG No.: A0AA0

Matrix: Water

Lab Sample ID: 5496758

Sample wt/vol: 1000 mL

Lab File ID: 14M854568_5496758

Water Sample Prep: SEPF

Date Received: 06-23-2014

Concentrated Extract Volume: 20 uL

Date Extracted: 06-26-2014

Injection Volume: 1.0 uL % Solids/Lipids:

Date Analyzed: 07-02-2014

GC Column: DB-5

ID: 0.250 mm

Dilution Factor: 1.0

Concentration Units: pg/L

Target Analyte	Concentration	TEF*	TEF-Adjusted Concentration
2378-TCDD	0.0	x 1.0 =	0.0
2378-TCDF	0.740	x 0.1 =	0.0740
12378-PeCDF	1.10	x 0.03 =	0.0330
12378-PeCDD	0.0	x 1.0 =	0.0
23478-PeCDF	0.0	x 0.3 =	0.0
123478-HxCDF	0.880	x 0.1 =	0.0880
123678-HxCDF	0.0	x 0.1 =	0.0
123478-HxCDD	0.0	x 0.1 =	0.0
123678-HxCDD	0.0	x 0.1 =	0.0
123789-HxCDD	0.0	x 0.1 =	0.0
234678-HxCDF	0.0	x 0.1 =	0.0
123789-HxCDF	0.0	x 0.1 =	0.0
1234678-HpCDF	0.0	x 0.01 =	0.0
1234678-HpCDD	0.0	x 0.01 =	0.0
1234789-HpCDF	0.0	x 0.01 =	0.0
OCDD	1.52	x 0.0003 =	0.000456
OCDF	3.20	x 0.0003 =	0.000960
		Total =	0.196

* TEF - Toxicity Equivalent Factors from the World Health Organization (WHO), 2005.

1DFB - FORM I-HR CDD-2
CDD/CDF TOXICITY EQUIVALENCE SUMMARY
HIGH RESOLUTION

A0AA2

Lab Name: AGAT LABORATORIES

Contract: EP10W001067

Lab Code: AGATAB

Case No.: 44423

TO No.: 2134.2

SDG No.: A0AA0

Matrix: Water

Lab Sample ID: 5496759

Sample wt/vol: 960 mL

Lab File ID: 14M854568_5496759

Water Sample Prep: SEPF

Date Received: 06-23-2014

Concentrated Extract Volume: 20 uL

Date Extracted: 06-26-2014

Injection Volume: 1.0 uL % Solids/Lipids:

Date Analyzed: 07-02-2014

GC Column: DB-5

ID: 0.250 mm

Dilution Factor: 1.0

Concentration Units: pg/L

Target Analyte	Concentration	TEF*	TEF-Adjusted Concentration
2378-TCDD	0.0	x 1.0 =	0.0
2378-TCDF	0.958	x 0.1 =	0.0958
12378-PeCDF	0.792	x 0.03 =	0.0238
12378-PeCDD	0.0	x 1.0 =	0.0
23478-PeCDF	0.0	x 0.3 =	0.0
123478-HxCDF	0.833	x 0.1 =	0.0833
123678-HxCDF	0.0	x 0.1 =	0.0
123478-HxCDD	0.0	x 0.1 =	0.0
123678-HxCDD	0.0	x 0.1 =	0.0
123789-HxCDD	0.0	x 0.1 =	0.0
234678-HxCDF	0.0	x 0.1 =	0.0
123789-HxCDF	0.667	x 0.1 =	0.0667
1234678-HpCDF	0.458	x 0.01 =	0.00458
1234678-HpCDD	0.625	x 0.01 =	0.00625
1234789-HpCDF	0.0	x 0.01 =	0.0
OCDD	0.0	x 0.0003 =	0.0
OCDF	3.35	x 0.0003 =	0.00101
		Total =	0.281

* TEF - Toxicity Equivalent Factors from the World Health Organization (WHO), 2005.

1DFB - FORM I-HR CDD-2
CDD/CDF TOXICITY EQUIVALENCE SUMMARY
HIGH RESOLUTION

A0AA3

Lab Name: AGAT LABORATORIES

Contract: EP10W001067

Lab Code: AGATAB

Case No.: 44423

TO No.: 2134.2

SDG No.: A0AA0

Matrix: Water

Lab Sample ID: 5496760

Sample wt/vol: 990 mL

Lab File ID: 14M854568_5496760

Water Sample Prep: SEPF

Date Received: 06-23-2014

Concentrated Extract Volume: 20 uL

Date Extracted: 06-26-2014

Injection Volume: 1.0 uL % Solids/Lipids:

Date Analyzed: 07-04-2014

GC Column: DB-5

ID: 0.250 mm

Dilution Factor: 1.0

Concentration Units: pg/L

Target Analyte	Concentration	TEF*	TEF-Adjusted Concentration
2378-TCDD	0.0	x 1.0 =	0.0
2378-TCDF	1.72	x 0.1 =	0.172
12378-PeCDF	1.41	x 0.03 =	0.0424
12378-PeCDD	0.869	x 1.0 =	0.869
23478-PeCDF	0.949	x 0.3 =	0.285
123478-HxCDF	1.94	x 0.1 =	0.194
123678-HxCDF	0.0	x 0.1 =	0.0
123478-HxCDD	0.0	x 0.1 =	0.0
123678-HxCDD	0.0	x 0.1 =	0.0
123789-HxCDD	0.0	x 0.1 =	0.0
234678-HxCDF	0.0	x 0.1 =	0.0
123789-HxCDF	0.0	x 0.1 =	0.0
1234678-HpCDF	1.23	x 0.01 =	0.0123
1234678-HpCDD	0.0	x 0.01 =	0.0
1234789-HpCDF	0.0	x 0.01 =	0.0
OCDD	3.92	x 0.0003 =	0.00118
OCDF	4.20	x 0.0003 =	0.00126
		Total =	1.58

* TEF - Toxicity Equivalent Factors from the World Health Organization (WHO), 2005.

1DFB - FORM I-HR CDD-2
CDD/CDF TOXICITY EQUIVALENCE SUMMARY
HIGH RESOLUTION

EPA Sample No.

A0AA4

Lab Name: AGAT LABORATORIES Contract: EP10W001067
Lab Code: AGATAB Case No.: 44423 TO No.: 2134.2 SDG No.: A0AA0
Matrix: Water Lab Sample ID: 5496761
Sample wt/vol: 970 mL Lab File ID: 14M854568_5496761
Water Sample Prep: SEPF Date Received: 06-23-2014
Concentrated Extract Volume: 20 uL Date Extracted: 06-26-2014
Injection Volume: 1.0 uL % Solids/Lipids: Date Analyzed: 07-02-2014
GC Column: DB-5 ID: 0.250 mm Dilution Factor: 1.0
Concentration Units: pg/L

Target Analyte	Concentration	TEF*	TEF-Adjusted Concentration
2378-TCDD	0.0	x 1.0 =	0.0
2378-TCDF	1.09	x 0.1 =	0.109
12378-PeCDF	1.09	x 0.03 =	0.0328
12378-PeCDD	0.0	x 1.0 =	0.0
23478-PeCDF	0.0	x 0.3 =	0.0
123478-HxCDF	1.49	x 0.1 =	0.149
123678-HxCDF	0.0	x 0.1 =	0.0
123478-HxCDD	0.0	x 0.1 =	0.0
123678-HxCDD	0.0	x 0.1 =	0.0
123789-HxCDD	0.0	x 0.1 =	0.0
234678-HxCDF	0.0	x 0.1 =	0.0
123789-HxCDF	0.742	x 0.1 =	0.0742
1234678-HpCDF	0.742	x 0.01 =	0.00742
1234678-HpCDD	0.0	x 0.01 =	0.0
1234789-HpCDF	0.0	x 0.01 =	0.0
OCDD	2.80	x 0.0003 =	0.000841
OCDF	4.99	x 0.0003 =	0.00150
		Total =	0.375

* TEF - Toxicity Equivalent Factors from the World Health Organization (WHO), 2005.

1DFB - FORM I-HR CDD-2
CDD/CDF TOXICITY EQUIVALENCE SUMMARY
HIGH RESOLUTION

A0AA5

Lab Name: AGAT LABORATORIES

Contract: EP10W001067

Lab Code: AGATAB

Case No.: 44423

TO No.: 2134.2

SDG No.: A0AA0

Matrix: Water

Lab Sample ID: 5496762

Sample wt/vol: 1000 mL

Lab File ID: 14M854568_5496762

Water Sample Prep: SEPF

Date Received: 06-23-2014

Concentrated Extract Volume: 20 uL

Date Extracted: 06-26-2014

Injection Volume: 1.0 uL % Solids/Lipids:

Date Analyzed: 07-03-2014

GC Column: DB-5

ID: 0.250 mm

Dilution Factor: 1.0

Concentration Units: pg/L

Target Analyte	Concentration	TEF*	TEF-Adjusted Concentration
2378-TCDD	0.0	x 1.0 =	0.0
2378-TCDF	0.740	x 0.1 =	0.0740
12378-PeCDF	1.06	x 0.03 =	0.0318
12378-PeCDD	0.0	x 1.0 =	0.0
23478-PeCDF	0.0	x 0.3 =	0.0
123478-HxCDF	0.680	x 0.1 =	0.0680
123678-HxCDF	0.0	x 0.1 =	0.0
123478-HxCDD	0.0	x 0.1 =	0.0
123678-HxCDD	0.0	x 0.1 =	0.0
123789-HxCDD	0.0	x 0.1 =	0.0
234678-HxCDF	0.0	x 0.1 =	0.0
123789-HxCDF	0.0	x 0.1 =	0.0
1234678-HpCDF	0.800	x 0.01 =	0.00800
1234678-HpCDD	1.32	x 0.01 =	0.0132
1234789-HpCDF	0.0	x 0.01 =	0.0
OCDD	3.72	x 0.0003 =	0.00112
OCDF	3.16	x 0.0003 =	0.000948
		Total =	0.197

* TEF - Toxicity Equivalent Factors from the World Health Organization (WHO), 2005.

1DFB - FORM I-HR CDD-2
CDD/CDF TOXICITY EQUIVALENCE SUMMARY
HIGH RESOLUTION

EPA Sample No.

A0AA6

Lab Name: AGAT LABORATORIES

Contract: EP10W001067

Lab Code: AGATAB

Case No.: 44423

TO No.: 2134.2

SDG No.: A0AA0

Matrix: Water

Lab Sample ID: 5496763

Sample wt/vol: 990 mL

Lab File ID: 14M854568_5496763

Water Sample Prep: SEPF

Date Received: 06-23-2014

Concentrated Extract Volume: 20 uL

Date Extracted: 06-26-2014

Injection Volume: 1.0 uL % Solids/Lipids:

Date Analyzed: 07-03-2014

GC Column: DB-5

ID: 0.250 mm

Dilution Factor: 1.0

Concentration Units: pg/L

Target Analyte	Concentration	TEF*	TEF-Adjusted Concentration
2378-TCDD	0.0	x 1.0 =	0.0
2378-TCDF	1.13	x 0.1 =	0.113
12378-PeCDF	0.869	x 0.03 =	0.0261
12378-PeCDD	0.0	x 1.0 =	0.0
23478-PeCDF	0.0	x 0.3 =	0.0
123478-HxCDF	1.13	x 0.1 =	0.113
123678-HxCDF	0.0	x 0.1 =	0.0
123478-HxCDD	0.0	x 0.1 =	0.0
123678-HxCDD	0.0	x 0.1 =	0.0
123789-HxCDD	0.0	x 0.1 =	0.0
234678-HxCDF	0.0	x 0.1 =	0.0
123789-HxCDF	0.0	x 0.1 =	0.0
1234678-HpCDF	0.768	x 0.01 =	0.00768
1234678-HpCDD	1.64	x 0.01 =	0.0164
1234789-HpCDF	0.0	x 0.01 =	0.0
OCDD	6.73	x 0.0003 =	0.00202
OCDF	5.46	x 0.0003 =	0.00164
		Total =	0.280

* TEF - Toxicity Equivalent Factors from the World Health Organization (WHO), 2005.

1DFB - FORM I-HR CDD-2
CDD/CDF TOXICITY EQUIVALENCE SUMMARY
HIGH RESOLUTION

EPA Sample No.

A0AA8

Lab Name: AGAT LABORATORIES

Contract: EP10W001067

Lab Code: AGATAB

Case No.: 44423

TO No.: 2134.2

SDG No.: A0AA0

Matrix: Water

Lab Sample ID: 5496764

Sample wt/vol: 960 mL

Lab File ID: 14M854568_5496764

Water Sample Prep: SEPF

Date Received: 06-23-2014

Concentrated Extract Volume: 20 uL

Date Extracted: 06-26-2014

Injection Volume: 1.0 uL % Solids/Lipids:

Date Analyzed: 07-04-2014

GC Column: DB-5

ID: 0.250 mm

Dilution Factor: 1.0

Concentration Units: pg/L

Target Analyte	Concentration	TEF*	TEF-Adjusted Concentration
2378-TCDD	0.0	x 1.0 =	0.0
2378-TCDF	0.875	x 0.1 =	0.0875
12378-PeCDF	0.0	x 0.03 =	0.0
12378-PeCDD	0.0	x 1.0 =	0.0
23478-PeCDF	0.0	x 0.3 =	0.0
123478-HxCDF	1.58	x 0.1 =	0.158
123678-HxCDF	0.0	x 0.1 =	0.0
123478-HxCDD	0.0	x 0.1 =	0.0
123678-HxCDD	0.0	x 0.1 =	0.0
123789-HxCDD	0.0	x 0.1 =	0.0
234678-HxCDF	0.0	x 0.1 =	0.0
123789-HxCDF	0.0	x 0.1 =	0.0
1234678-HpCDF	0.708	x 0.01 =	0.00708
1234678-HpCDD	0.0	x 0.01 =	0.0
1234789-HpCDF	0.0	x 0.01 =	0.0
OCDD	2.94	x 0.0003 =	0.000881
OCDF	4.58	x 0.0003 =	0.00138
		Total =	0.255

* TEF - Toxicity Equivalent Factors from the World Health Organization (WHO), 2005.

1DFB - FORM I-HR CDD-2
CDD/CDF TOXICITY EQUIVALENCE SUMMARY
HIGH RESOLUTION

EPA Sample No.

A0AB0

Lab Name: AGAT LABORATORIES

Contract: EP10W001067

Lab Code: AGATAB

Case No.: 44423

TO No.: 2134.2

SDG No.: A0AA0

Matrix: Water

Lab Sample ID: 5496768

Sample wt/vol: 855 ml (See case narrative)

Lab File ID: 14M854568_5496768

Water Sample Prep: SEPF

Date Received: 06-23-2014

Concentrated Extract Volume: 20 uL

Date Extracted: 06-26-2014

Injection Volume: 1.0 uL % Solids/Lipids:

Date Analyzed: 07-03-2014

GC Column: DB-5

ID: 0.250 mm

Dilution Factor: 1.0

Concentration Units: pg/L

Target Analyte	Concentration	TEF*	TEF-Adjusted Concentration
2378-TCDD	186	x 1.0 =	186
2378-TCDF	587	x 0.1 =	58.7
12378-PeCDF	344	x 0.03 =	10.3
12378-PeCDD	238	x 1.0 =	238
23478-PeCDF	227	x 0.3 =	68.0
123478-HxCDF	219	x 0.1 =	21.9
123678-HxCDF	421	x 0.1 =	42.1
123478-HxCDD	528	x 0.1 =	52.8
123678-HxCDD	429	x 0.1 =	24.9
123789-HxCDD	388	x 0.1 =	38.8
234678-HxCDF	419	x 0.1 =	41.9
123789-HxCDF	531	x 0.1 =	53.1
1234678-HpCDF	234	x 0.01 =	2.34
1234678-HpCDD	524	x 0.01 =	5.24
1234789-HpCDF	527	x 0.01 =	4.27
OCDD	809	x 0.0003 =	0.153
OCDF	979	x 0.0003 =	0.294
		Total =	849

* TEF - Toxicity Equivalent Factors from the World Health Organization (WHO), 2005.

1F - FORM I SV-SIM
SEMIVOLATILE SIM ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

A0AA0

Lab Name: Shealy Environmental Services, Inc.

Contract: EP-W-11-035

Lab Code: SHEALY Case No.: 44423

Mod. Ref No.: 2110.4 SDG No.: A0AA0

Matrix: (SOIL/SED/WATER) Water

Lab Sample ID: PF20038-001

Sample wt/vol: 1000 (g/mL) mL

Lab File ID: 120708B10

Extraction: (Type) CONT

% Moisture: _____ Decanted: (Y/N) _____

Date Received: 06/20/2014

Concentrated Extract Volume: 1000 (uL)

Date Extracted: 06/24/2014

Injection Volume: 1.0 (uL) GPC Factor: 1.0

Date Analyzed: 07/08/2014

GPC Cleanup: (Y/N) N pH: _____

Dilution Factor: 1.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) <u>ug/L</u>	<u>Q</u>
87-86-5	Pentachlorophenol	0.20	U

1F - FORM I SV-SIM
SEMIVOLATILE SIM ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

A0AA1

Lab Name: Shealy Environmental Services, Inc.

Contract: EP-W-11-035

Lab Code: SHEALY Case No.: 44423

Mod. Ref No.: 2110.4 SDG No.: A0AA0

Matrix: (SOIL/SED/WATER) Water

Lab Sample ID: PF20038-002

Sample wt/vol: 1000 (g/mL) mL

Lab File ID: 120708B11

Extraction: (Type) CONT

% Moisture: _____ Decanted: (Y/N) _____

Date Received: 06/20/2014

Concentrated Extract Volume: 1000 (uL)

Date Extracted: 06/24/2014

Injection Volume: 1.0 (uL) GPC Factor: 1.0

Date Analyzed: 07/08/2014

GPC Cleanup: (Y/N) N pH: _____

Dilution Factor: 1.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) <u>ug/L</u>	Q
87-86-5	Pentachlorophenol	0.20	U

1F - FORM I SV-SIM
SEMIVOLATILE SIM ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

A0AA2

Lab Name: Shealy Environmental Services, Inc.

Contract: EP-W-11-035

Lab Code: SHEALY Case No.: 44423

Mod. Ref No.: 2110.4 SDG No.: A0AA0

Matrix: (SOIL/SED/WATER) Water

Lab Sample ID: PF20038-003

Sample wt/vol: 1000 (g/mL) mL

Lab File ID: 120708B12

Extraction: (Type) CONT

% Moisture: Decanted: (Y/N)

Date Received: 06/20/2014

Concentrated Extract Volume: 1000 (uL)

Date Extracted: 06/24/2014

Injection Volume: 1.0 (uL) GPC Factor: 1.0

Date Analyzed: 07/08/2014

GPC Cleanup: (Y/N) N pH:

Dilution Factor: 1.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) <u>ug/L</u>	<u>Q</u>
87-86-5	Pentachlorophenol	0.20	U

1F - FORM I SV-SIM
SEMIVOLATILE SIM ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

A0AA3

Lab Name: Shealy Environmental Services, Inc.

Contract: EP-W-11-035

Lab Code: SHEALY Case No.: 44423

Mod. Ref No.: 2110.4 SDG No.: A0AA0

Matrix: (SOIL/SED/WATER) Water

Lab Sample ID: PF20038-004

Sample wt/vol: 1000 (g/mL) mL

Lab File ID: 120708B13

Extraction: (Type) CONT

% Moisture: _____ Decanted: (Y/N) _____

Date Received: 06/20/2014

Concentrated Extract Volume: 1000 (uL)

Date Extracted: 06/24/2014

Injection Volume: 1.0 (uL) GPC Factor: 1.0

Date Analyzed: 07/08/2014

GPC Cleanup: (Y/N) N pH: _____

Dilution Factor: 1.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) <u>ug/L</u>	<u>Q</u>
87-86-5	Pentachlorophenol	3.3	EB

1F - FORM I SV-SIM
SEMIVOLATILE SIM ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

A0AA3DL

Lab Name: Shealy Environmental Services, Inc.

Contract: EP-W-11-035

Lab Code: SHEALY Case No.: 44423

Mod. Ref No.: 2110.4 SDG No.: A0AA0

Matrix: (SOIL/SED/WATER) Water

Lab Sample ID: PF20038-004

Sample wt/vol: 1000 (g/mL) mL

Lab File ID: 120708B18

Extraction: (Type) CONT

% Moisture: Decanted: (Y/N)

Date Received: 06/20/2014

Concentrated Extract Volume: 1000 (uL)

Date Extracted: 06/24/2014

Injection Volume: 1.0 (uL) GPC Factor: 1.0

Date Analyzed: 07/08/2014

GPC Cleanup: (Y/N) N pH:

Dilution Factor: 5.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) <u>ug/L</u>	<u>Q</u>
87-86-5	Pentachlorophenol	2.7	DB

1F - FORM I SV-SIM
SEMIVOLATILE SIM ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

A0AA4

Lab Name: Shealy Environmental Services, Inc.

Contract: EP-W-11-035

Lab Code: SHEALY Case No.: 44423

Mod. Ref No.: 2110.4 SDG No.: A0AA0

Matrix: (SOIL/SED/WATER) Water

Lab Sample ID: PF20038-005

Sample wt/vol: 1000 (g/mL) mL

Lab File ID: 120708B14

Extraction: (Type) CONT

% Moisture: _____ Decanted: (Y/N) _____

Date Received: 06/20/2014

Concentrated Extract Volume: 1000 (uL)

Date Extracted: 06/24/2014

Injection Volume: 1.0 (uL) GPC Factor: 1.0

Date Analyzed: 07/08/2014

GPC Cleanup: (Y/N) N pH: _____

Dilution Factor: 1.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) <u>ug/L</u>	<u>Q</u>
87-86-5	Pentachlorophenol	0.20	<u>U</u>

1F - FORM I SV-SIM
SEMIVOLATILE SIM ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

A0AA5

Lab Name: Shealy Environmental Services, Inc.

Contract: EP-W-11-035

Lab Code: SHEALY Case No.: 44423

Mod. Ref No.: 2110.4 SDG No.: A0AA0

Matrix: (SOIL/SED/WATER) Water

Lab Sample ID: PF20038-006

Sample wt/vol: 1000 (g/mL) mL

Lab File ID: 120708B15

Extraction: (Type) CONT

% Moisture: _____ Decanted: (Y/N) _____

Date Received: 06/20/2014

Concentrated Extract Volume: 1000 (uL)

Date Extracted: 06/24/2014

Injection Volume: 1.0 (uL) GPC Factor: 1.0

Date Analyzed: 07/08/2014

GPC Cleanup: (Y/N) N pH: _____

Dilution Factor: 1.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) <u>ug/L</u>	<u>Q</u>
87-86-5	Pentachlorophenol	0.20	<u>U</u>

1F - FORM I SV-SIM
SEMIVOLATILE SIM ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

A0AA6

Lab Name: Shealy Environmental Services, Inc.

Contract: EP-W-11-035

Lab Code: SHEALY Case No.: 44423

Mod. Ref No.: 2110.4 SDG No.: A0AA0

Matrix: (SOIL/SED/WATER) Water

Lab Sample ID: PF20038-007

Sample wt/vol: 1000 (g/mL) mL

Lab File ID: 120708B16

Extraction: (Type) CONT

% Moisture: _____ Decanted: (Y/N) _____

Date Received: 06/20/2014

Concentrated Extract Volume: 1000 (uL)

Date Extracted: 06/24/2014

Injection Volume: 1.0 (uL) GPC Factor: 1.0

Date Analyzed: 07/08/2014

GPC Cleanup: (Y/N) N pH: _____

Dilution Factor: 1.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) <u>ug/L</u>	<u>Q</u>
87-86-5	Pentachlorophenol	0.20	U

1F - FORM I SV-SIM
SEMIVOLATILE SIM ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

A0AA8

Lab Name: Shealy Environmental Services, Inc.

Contract: EP-W-11-035

Lab Code: SHEALY Case No.: 44423

Mod. Ref No.: 2110.4 SDG No.: A0AA0

Matrix: (SOIL/SED/WATER) Water

Lab Sample ID: PF20038-009

Sample wt/vol: 1000 (g/mL) mL

Lab File ID: 120708B17

Extraction: (Type) CONT

% Moisture: Decanted: (Y/N)

Date Received: 06/20/2014

Concentrated Extract Volume: 1000 (uL)

Date Extracted: 06/24/2014

Injection Volume: 1.0 (uL) GPC Factor: 1.0


Date Analyzed: 07/08/2014

GPC Cleanup: (Y/N) N pH:

Dilution Factor: 1.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) <u>ug/L</u>	<u>Q</u>
87-86-5	Pentachlorophenol	0.20	U

SEDIMENT ANALYTICAL RESULTS




● MONITORING WELL LOCATION
⊕ SEDIMENT SAMPLE LOCATION

--- APPROXIMATE PROPERTY LINE
+++++ RAILROAD TRACK
~ GENERAL TREE LINE

BASE MAP SOURCE: FIGURE 2, PREPARED BY
TRC, SEPTEMBER 2010

Environmental Strategies
& Management, Inc.

0 200 400
SCALE FEET

 **Environmental
Strategies
& Management**
273 West Main Street
Norton, MA 02766
(508) 226-1800
(508) 226-1811 fax
info@esm-inc.com

GAUGING DATE: NA	DRAWING DATE: 10/31/12	ACAD FILE: SARSS HATHEWAY
---------------------	---------------------------	------------------------------

MONITORING WELLS AND SEDIMENT SAMPLES

CLIENT:	MassDEP SARSS V	PM:	TS
LOCATION:	15 COUNTY STREET MANSFIELD, MASSACHUSETTS	LSP:	DH
RTN:	DWG:	PROJECT NO.:	FIGURE:
4-0571	DMR	2012-028	1

Table C-3. Hatheway & Patterson Superfund Site Sediment Sampling Results

		SED-1 5/16/2012	SED-2 5/16/2012	SED-3 5/16/2012	SED-4 5/16/2012	SED-4-FD 5/16/2012	Maximum Detection		Maximum Historical Detections HHRA	95% UCL HHRA	Maximum Historical Detections BERA	Geomean BERA
2,3,7,8-TCDD	mg/kg	7.02E-07	< 1.24E-06	< 1.13E-06	2.64E-06	1.37E-06	2.64E-06		NA	NA	3.29E-06	6.76E-07
1,2,3,7,8-PeCDD	mg/kg	6.05E-06	2.39E-06	3.11E-06	1.72E-05	3.64E-06	1.72E-05		NA	NA	4.91E-05	3.03E-06
1,2,3,4,7,8-HxCDD	mg/kg	2.34E-05	7.41E-06	7.59E-06	4.45E-05	5.73E-06	4.45E-05		NA	NA	2.15E-04	8.45E-06
1,2,3,6,7,8-HxCDD	mg/kg	2.31E-04	3.87E-05	4.60E-05	2.17E-04	2.99E-05	2.31E-04		NA	NA	1.82E-03	3.50E-05
1,2,3,7,8,9-HxCDD	mg/kg	7.04E-05	1.84E-05	1.80E-05	1.14E-04	1.91E-05	1.14E-04		NA	NA	6.15E-04	2.25E-05
1,2,3,4,6,7,8-HpCDD	mg/kg	8.72E-03	1.03E-03	1.44E-03	5.27E-03	8.17E-04	8.72E-03		NA	NA	5.90E-02	1.05E-03
OCDD	mg/kg	6.61E-02	6.57E-03	1.14E-02	3.66E-02	7.27E-03	6.61E-02		NA	NA	5.24E-01	7.09E-03
2,3,7,8-TCDF	mg/kg	< 1.24E-06	< 1.24E-06	< 1.13E-06	4.83E-06	2.46E-06	4.83E-06		NA	NA	2.81E-05	1.38E-06
1,2,3,7,8-PeCDF	mg/kg	1.84E-06	< 3.1E-06	7.10E-07	7.83E-06	1.62E-06	7.83E-06		NA	NA	3.60E-05	1.29E-06
2,3,4,7,8-PeCDF	mg/kg	1.72E-06	< 3.1E-06	5.87E-07	5.20E-06	1.56E-06	5.20E-06		NA	NA	2.89E-05	1.43E-06
1,2,3,4,7,8-HxCDF	mg/kg	3.16E-05	6.15E-06	7.39E-06	5.15E-05	7.87E-06	5.15E-05		NA	NA	2.79E-04	1.15E-05
1,2,3,6,7,8-HxCDF	mg/kg	1.24E-05	3.91E-06	5.27E-06	4.16E-05	6.44E-06	4.16E-05		NA	NA	1.37E-04	9.87E-06
2,3,4,6,7,8-HxCDF	mg/kg	< 3.1E-06	< 3.1E-06	1.73E-06	< 4.25E-06	< 3.57E-06	1.73E-06		NA	NA	1.38E-04	3.08E-06
1,2,3,7,8,9-HxCDF	mg/kg	2.51E-05	7.19E-06	1.03E-05	7.93E-05	1.16E-05	7.93E-05		NA	NA	3.31E-05	5.81E-07
1,2,3,4,6,7,8-HpCDF	mg/kg	1.50E-03	2.14E-04	2.89E-04	1.39E-03	2.02E-04	1.50E-03		NA	NA	9.12E-03	2.06E-04
1,2,3,4,7,8,9-HpCDF	mg/kg	9.86E-05	1.51E-05	2.78E-05	1.44E-04	1.97E-05	1.44E-04		NA	NA	8.15E-04	1.77E-05
OCDF	mg/kg	1.06E-02	7.58E-04	1.34E-03	4.32E-03	5.65E-04	1.06E-02		NA	NA	5.38E-02	6.28E-04
Dioxin TEQ ¹	mg/kg	1.73E-04	2.67E-05	3.49E-05	1.57E-04	2.68E-05	1.73E-04		2.27E-03	1.60E-03	NA	NA
Arsenic	mg/kg	26	1.7	4.8	20	6.2	26		65	18	65	2.77
Chromium	mg/kg	7	5	9	26	17	26		330	240	330	15.6
Pentachlorophenol	mg/kg	< 1	< 1	< 1	< 8	< 7	ND		690	81	24	0.438

Notes

1. Using 2005 WHO TEFs and non-detects equal to the 1/2 reporting limit.

NA - Not Applicable

ND - Not Detected

< - Not detected at the value reported

HHRA - 2005 Human Health Risk Assessment

BERA - 2004 Baseline Ecological Risk Assessment

UCL - Upper Confidence Limit

TABLE 2A
SUMMARY OF ANALYTICAL RESULTS IN SEDIMENT SAMPLES
DIOXINS

Hatheway Patterson Site RTN 4-571
15 County Street
Mansfield MA
(results in ng/kg)

Lab ID	Sample	Sample Type	Sample Date	2,3,7,8-Tetrachlorodibenzo-p-dioxin (TCDD)	1,2,3,7,8-Pentachlorodibenzo-p-dioxin (PeCDD)	1,2,3,4,7,8-Hexachlorodibenzo-p-dioxin (HxCDD)	1,2,3,6,7,8-Hexachlorodibenzo-p-dioxin (HxCDD)	1,2,3,7,8,9-Hexachlorodibenzo-p-dioxin (HxCDD)	1,2,3,4,6,7,8-Heptachlorodibenzo-p-dioxin (HpCDD)	Octachlorodibenzo-p-dioxin (OCDD)	2,3,7,8-Tetrachlorodibenzofuran (TCDF)	1,2,3,7,8-Pentachlorodibenzofuran (PeCDF)	2,3,4,7,8-Pentachlorodibenzofuran (PeCDF)	1,2,3,4,7,8-Hexachlorodibenzofuran (HxCDF)	1,2,3,6,7,8-Hexachlorodibenzofuran (HxCDF)	1,2,3,7,8,9-Hexachlorodibenzofuran (HxCDF)	2,3,4,6,7,8-Hexachlorodibenzofuran (HxCDF)
24087-13 (SED-1)	SED-1	Sample	5/16/2012	0.702 J	6.05	23.4	231	70.4	8720 E	66100 B,E	0.76 C,J	1.84 J	1.72 J	31.6	12.4 K	<3.1	25.1
24087-13 (SED-1)	SED-1	Re-analyzed TCDF	5/16/2012								<1.24						
24087-13 (SED-1)	SED-1	Diluted	5/16/2012	<24.8	<62.1	24.1 J,K	226	71.6	7620	68100 B	<24.8	<62.1	<62.1	23.5 J	<62.1	<62.1	<62.1
24087-13 (SED-1)	SED-1	Matrix Spike	5/16/2012	24.1	70.1	91.9		155	12900 E	94900 E	25.8	66.2	55.5	98.8	75.3	56.6	85.3
24087-13 (SED-1)	SED-1	Dup Matrix Spike	5/16/2012	25.6	67.5	92.3	347	173	10500 E	79600 E	26.3	66.7	52.6	90.4	74.6	58.5	84
24087-14 (SED-2)	SED-2	Sample	5/16/2012	<1.24	2.39 J	7.41	38.7	18.4	1030	6570 B,E	<1.24	<3.1	<3.1	6.15	3.91	<3.1	7.19
24087-15 (SED-3)	SED-3	Sample	5/16/2012	<1.13	3.11	7.59	46	18	1440	11400 B,E	<1.13	0.71 J	0.587 J	7.39	5.27	1.73 J,K	10.3
24087-16 (SED-4)	SED-4	Sample	5/16/2012	2.64	17.2	44.5	217	114	5270 E	36600 B,E	6.82 C	7.83	5.2 K	51.5	41.6	<4.25	79.3
24087-16 (SED-4)	SED-4	Re-analyzed TCDF	5/16/2012								4.83						
24087-16 (SED-4)	SED-4	Diluted	5/16/2012	<17	15.4 J	40.3 J,K	248	132	5190	39500 B	<17	<42.5	<42.5	46.8 K	42.1 J,K	<42.5	71.9
24087-17 (SED-4 Dup)	(SED-4 Dup)	Sample	5/16/2012	1.37 J	3.64	5.73 K	29.9	19.1	817	7270 B,E	3.69 C	1.62 J	1.56 J	7.87	6.44	<3.57	11.6
24087-17 (SED-4 Dup)	(SED-4 Dup)	Re-analyzed TCDF	5/16/2012								2.46						
Lab Control Sample	LCS	Sample	5/16/2012	17.8	45.4	45.6	48.3	48	43.9	78.1	18.5	49.3	45.8	42	45.8	43.3	44
Method Blank	MB	Method Blank	5/16/2012	<0.937	<2.34	<2.34	<2.34	<2.34	<2.34	1.55 J	<0.937	<2.34	<2.34	<2.34	<2.34	<2.34	<2.34

Notes:

List of flags and qualifiers is attached.

NA - not applicable

Results for non-detected compounds shown as less than (<) the laboratory reporting limit.

* EPA Fresh Water Screening Criterion

TABLE 2A
SUMMARY OF ANALYTICAL RESULTS IN SEDIMENT SAMPLES
DIOXINS

Hatheway Patterson Site RTN 4-571
15 County Street
Mansfield MA
(results in ng/kg)

Lab ID	Sample	Sample Type	Sample Date	1,2,3,4,6,7,8-Heptachlorodibenzofuran (HpCDF)	1,2,3,4,7,8,9-Heptachlorodibenzofuran (HpCDD)	Octachlorodibenzofuran (OCDF)	Tetrachlorodibenzo-p-dioxins (TCDD), Total	Pentachlorodibenzo-p-dioxin (PeCDD), Total	Hexachlorodibenzo-p-dioxins (HxCDD), Total	Heptachlorodibenzo-p-dioxins (HpCDD), Total	Tetrachlorodibenzofurans (TCDF), Total	Pentachlorodibenzofurans (PeCDF), Total	Hexachlorodibenzofurans (HxCDF), Total	Heptachlorodibenzofurans (HpCDF), Total	Total TCDD TEQ - 2005 WHO (ND = MRL)
24087-13 (SED-1)	SED-1	Sample	5/16/2012	1500 P	98.6	10600 E,P	12.2	55.7	839	13500	2.07	88.3	1090	1600	162
24087-13 (SED-1)	SED-1	Re-analyzed TCDF	5/16/2012												162
24087-13 (SED-1)	SED-1	Diluted	5/16/2012	1200	<62.1	9480									162
24087-13 (SED-1)	SED-1	Matrix Spike	5/16/2012	2220	193	14300 E	28.8	138	1380	20100	31.1	234	1780	10900	
24087-13 (SED-1)	SED-1	Dup Matrix Spike	5/16/2012	1860	166	12200 E	25.6	123	1270	16300	30.5	225	1540	8490	
24087-14 (SED-2)	SED-2	Sample	5/16/2012	214	15.1	758	<1.24	4.8	152	1600	<1.24	21.1	202	858	25.4
24087-15 (SED-3)	SED-3	Sample	5/16/2012	289	27.8	1340	<1.13	7.09	161	2190	<1.13	37.1	232	1260	34.3
24087-16 (SED-4)	SED-4	Sample	5/16/2012	1390	144	4320	22.4	81.7	1270	8850	64.7	298	1540	5050	157
24087-16 (SED-4)	SED-4	Re-analyzed TCDF	5/16/2012												157
24087-16 (SED-4)	SED-4	Diluted	5/16/2012	1250	117	4420									157
24087-17 (SED-4 Dup)	(SED-4 Dup)	Sample	5/16/2012	202	19.7	565	5.11	42.1	458	1740	25.1	55.5	210	706	26.6
24087-17 (SED-4 Dup)	(SED-4 Dup)	Re-analyzed TCDF	5/16/2012												26.6
Lab Control Sample	LCS	Sample	5/16/2012	46.4	48.9	75.5									
Method Blank	MB	Method Blank	5/16/2012	<2.34	<2.34	<4.68	<0.937	<2.34	<2.34	<2.34	<0.937	<2.34	<2.34	<2.34	

Notes:

List of flags and qualifiers is attached.

NA - not applicable

Results for non-detected compounds shown as less than (<) the laboratory

* EPA Fresh Water Screening Criterion

TABLE 2B
SUMMARY OF ANALYTICAL RESULTS IN SEDIMENT SAMPLES
As, Cr, and PCP

Hatheway Patterson Site RTN 4-571
15 County Street
Mansfield MA
(results in mg/kg)

		Sampled Date	Arsenic	Chromium	Pentachlorophenol
Field Samples	SED-1	5/16/2012	26	7	< 1
	SED-2	5/16/2012	1.7	5	< 1
	SED-3	5/16/2012	4.8	9	< 1
	SED-4	5/16/2012	20	26	< 8
	SED-4 Duplicate	5/16/2012	6.2	17	< 7

Notes:

List of flags and qualifiers is attached.

NA - not applicable

Results for non-detected compounds shown as less than (<) the laboratory reporting limit.

* EPA Fresh Water Screening Criterion

Data Qualifier Flags – Dioxin/Furans

- **B** Indicates the associated analyte is found in the method blank, as well as in the sample.
- **C** Confirmation of the TCDF compound: When 2378-TCDF is detected on the DB-5 column, confirmation analyses are performed on a second column (DB-225). The results from both the DB-5 column and the DB-225 column are included in this data package. The results from the DB-225 analyses should be used to evaluate the 2378-TCDF in the samples. The confirmed result should be used in determining the TEQ value for TCDF.
- **E** Indicates an estimated value – used when the analyte concentration exceeds the upper end of the linear calibration range.
- **J** Indicates an estimated value – used when the analyte concentration is below the method reporting limit (MRL) and above the estimated detection limit (EDL).
- **K** EMPC - When the ion abundance ratios associated with a particular compound are outside the QC limits, samples are flagged with a 'K' flag. A 'K' flag indicates an estimated maximum possible concentration for the associated compound.
- **U** Indicates the compound was analyzed and not detected.
- **Y** Samples that had recoveries of labeled standards outside the acceptance limits are flagged with 'Y'. In all cases, the signal-to-noise ratios are greater than 10:1, making these data acceptable.
- **ND** Indicates concentration is reported as 'Not Detected.'
- **S** Peak is saturated; data not reportable.
- **P** Indicates chlorodiphenyl ether interference present at the retention time of the target compound.
- **Q** Lock-mass interference by chlorodiphenyl ether compounds.

APPENDIX D

MANAGEMENT SYSTEM REVIEW

TECHNICAL MEMORANDUM
MANAGEMENT SYSTEM REVIEW AND TECHNICAL COMPLIANCE EVALUATION
HATHEWAY AND PATTERSON SUPERFUND SITE
MANSFIELD, MASSACHUSETTS
JULY 2014

As part of the Five-Year Review for the Hatheway and Patterson Superfund Site in Mansfield, MA, a Management System Review (MSR) has been performed which includes performance of a site inspection, review of the remedy, and a technical compliance evaluation in order to evaluate whether each element of the remedy is being maintained and operated in accordance with its intended function. This technical memorandum includes the completed inspection checklist from the site inspection performed on June 3, 2014, as well as annotated photographs of various site features taken on that date, and a technical assessment of physical features of the remedy. The portion of the review associated with risk standards was submitted under separate cover on June 9, 2014, in a memorandum entitled Assessment of Changes in Standards Memorandum.

Background

The Hatheway & Patterson Superfund Site is located at 35 County Street in Mansfield, Massachusetts (see Figure 1.1). Approximately 36 acres of the 38.17-acre site are located in the Town of Mansfield. The remaining 1.77 acres are located in the Town of Foxborough. The site is divided into four quadrants by the Rumford River, which runs north to south, and by a railroad right-of-way, which runs east to west. The northeast (NE) and northwest (NW) quadrants are referred to as the "Process Area" and are located north of the railroad tracks operated by CSX (see Figure 1.2). The southeast (SE) and southwest (SW) quadrants cover the area south of the railroad tracks. The "County Street area" lies north of the site fence in the northeast and northwest quadrants.

The majority of the historical operational areas and buildings were located on the northern portion of the property, north of the railroad tracks, and contained process buildings, drip pads, support buildings, an office, and a laboratory. With the exception of the office building, which was outside the remediation area, these structures have been demolished or removed (Sevenson, 2011).

The site and surrounding area are served by municipal drinking water. Groundwater underlying the site is designated as Class III (non-potable) by the Commonwealth of Massachusetts. The remedy outlined in the ROD was based on an assumption that groundwater at the site is not available for drinking water by future users of the site (USEPA, 2005).

History of Contamination

The land west of the Rumford River was owned by the Penn Central Railroad, who used it for bulk chemical transfer and storage of electric/utility poles and railroad ties, until the land was purchased by Hatheway & Patterson in 1978. The land south of the railroad tracks was purchased by Hatheway & Patterson in 1981 and was apparently not used between 1955 and 1971, but was reportedly used for coal storage prior to 1955 (USEPA, 2005).

Hatheway & Patterson reportedly began operations at the site in 1927, but did not begin wood treating until 1953. It is unknown what operations might have been conducted at the site between 1927 and 1953 (USEPA, 2005).

Wood treatment was accomplished by a variety of methods that changed over time. From 1953 through 1958, a solution of pentachlorophenol (PCP) in fuel oil, or creosote, was used for dipping lumber. After dipping, excess chemicals were allowed to drip off of the treated wood onto the ground surface. From 1958 through 1974, solutions of PCP in fuel oil and fluoro-chrome-arsenate-phenol (FCAP) salts in water were used in a pressure treatment process. From 1960 through 1984, PCP in mineral spirits was also used to pressure-treat lumber. From 1974 to 1984, operations incorporated PCP in fuel oil and chromated copper-arsenate (CCA) salts in water. From 1984 until operations ceased in 1993, solutions of CCA salts in water and PCP in water were utilized at the property. Wood was also infused with fire retardants, including Dricon™ (boric acid and anhydrous sodium tetraborate). The various wood-treating chemicals were stored in aboveground storage tanks (ASTs), underground storage tanks (USTs), and sumps located inside and outside of the former process buildings (USEPA, 2005). More detail on site history is provided in the Five Year Review Report.

Remedial Action Objectives

The EPA ROD for the site was signed on September 30, 2005. Remedial Action Objectives (RAOs) were developed for various media at the site based on the results of the RI and risk assessments. The RAOs were developed to aid in the development and screening of remedial alternatives.

The RAOs for the selected remedy for the site are:

- Surface Soil (Process Area) – Prevent current and future trespassers and future on-site residents (Foxborough parcel), commercial workers, town workers, and utility workers from ingestion of or dermal contact with Contaminants of Potential Concern (COPCs) (including arsenic, dioxin, and PCP) which would result in a cumulative excess cancer risk greater than 10^{-4} to 10^{-6} or HI=1;
- Subsurface Soil (Process Area) – Prevent future commercial workers and future on-site residents (Foxborough parcel) from ingestion of or dermal contact with COPCs (including arsenic, dioxin, and PCP) which would result in a cumulative risk greater than 10^{-4} to 10^{-6} or HI=1;
- Groundwater – Prevent discharge of pentachlorophenol and other COPCs from soil to groundwater and from groundwater to surface water at concentrations that would result in an in stream exceedence of the Ambient Water Quality Criteria (AWQCs) through source control. Prevent exposure to groundwater by future residents, recreational users, or commercial workers by monitoring extent of plume (to ensure it is remaining on-site) and implementing institutional controls to restrict groundwater use within the site boundary;
- Inter-Media Transfer – Eliminate or reduce potential for leaching through source control and inter-media transfer of COPCs from soil to groundwater and surface water;
- LNAPL – Minimize further contaminant transfer from LNAPL source material to groundwater by reducing LNAPL source material in soil excavation/treatment areas.

Minimize further migration of LNAPL free product to groundwater and surface water by removing free product “hotspots” to the extent feasible.

The primary components of the ROD included:

- Excavation of approximately 31,000 cubic yards of soil exceeding cleanup levels.
- Demolition of the buildings in and near Hatheway & Patterson’s former manufacturing area to allow excavation of underlying contaminated soils and replacement of the excavated soil with clean backfill.
- Excavation of soils containing PCP, SVOCs, and arsenic, testing for leachability and, if they fail, utilization of a stabilization/solidification agent(s). Consolidation of the stabilized/solidified soils on-site under a low-permeability cover.
- Off-site disposal of soils containing dioxin and oily material (LNAPL) at a licensed facility.
- Institutional controls to prohibit the use of site groundwater and restrict land uses in a manner that ensures the protectiveness of the remedy as described in this ROD, and ensures the integrity of the on-site low-permeability cover and other remedial components. Evaluation of risks from soil exposures within the area of the existing railroad right of way during design and implementation of appropriate action such as deed restrictions or other legal and administrative measures if necessary.
- Long term monitoring of groundwater, surface water, fish tissue and sediment.
- Five-year reviews, and operation and maintenance of remedial components, including the low permeability cover.

An ESD (USEPA, 2011), issued in August 2011, had three main purposes as summarized below.

- The remedy outlined in the ROD for the Foxborough parcel was based on future residential use of the parcel as the property was zoned for residential use in 2005. After the ROD was issued, the Town of Foxborough took ownership of the parcel through tax foreclosure with the intent of redeveloping the parcel as a parking lot. In connection with this plan, the town voted at the May 2008 Town Meeting to adopt a change in zoning of the lot from R-40 Residential and Agricultural District to “Limited Industrial.” The Town notified EPA of its intention to use the parcel as a parking facility for the nearby MBTA commuter rail station. Based on the change in zoning and intended reuse of the parcel, EPA and MassDEP determined that the Foxborough parcel should be remediated to a Reasonably Anticipated Future Use (RAMU) of commercial/open space and changed the cleanup level accordingly. EPA also determined that a consolidation area for soils in Foxborough contaminated with arsenic could be built on the Foxborough parcel and designed with an asphalt cover in order to facilitate reuse as a parking facility.
- EPA reevaluated the remedy for PCP and arsenic-contaminated soils excavated from the lots in the Mansfield portion of the site. The remedy chosen in the ROD called for on-site

consolidation of these soils, rather than disposal at an off-site facility. Subsequent to the signing of the ROD, the relative costs of off-site disposal decreased significantly. EPA reevaluated both options using criteria required under CERCLA to compare different remedial options. The criteria included overall protection, long-term effectiveness and permanence, community support, and cost. The remedy was changed since the costs were similar but the off-site disposal option offered the greatest overall protection, long-term protectiveness, and permanence.

- EPA clarified the extent of institutional controls to be placed on the site properties as called for in the ROD. Specifically, restrictions on future soil excavation, in the form of institutional controls, will be needed in the northeast quadrant of the site: 1) below the depth of the vertical extent of excavation reached during the remedial action (RA); and 2) at depths of two feet and below in a strip of land bordering the northeast quadrant and County Street to a distance about 5 feet laterally with the fence line. Institutional controls will also be necessary to protect the cover placed over the consolidated soils in the Foxborough parcel. In addition, institutional controls to eliminate on-site exposures to groundwater and to prevent residential use will be necessary on all four quadrants of the site property.

Site Inspection

On June 3, 2014, Kimberly White of the US EPA and Warren Diesl of AECOM performed an inspection of the Hatheway and Patterson site. Also present for part of the inspection was Garry Waldeck of MassDEP. The site inspection checklist and photos are included as Attachments 1 and 2, respectively.

As described above, the site is divided into four quadrants by two features: a wide (100 +/- feet) active railroad right-of-way, which is oriented NW-SE and divides the site into northern and southern sections, and by the Rumford River, which flows southwest (after entering the site in the NW Quadrant and flowing a short distance along County Road) and divides the site into eastern and western sections. The NE quadrant is a vegetated field except for the extreme eastern end, where the Town of Mansfield has its Emergency Management Agency building and a large storage building. The vegetation in the NE Quadrant is reportedly cut twice per year and was due to be cut shortly after the site inspection. The NW Quadrant is mostly covered with crushed rock except for a vegetated buffer along the Rumford River and a commuter parking lot for the Town of Foxborough in the extreme northwest corner. As described in the Site Inspection Checklist, the parking lot is well maintained, and the fencing and gates that surround the entire NW and NE Quadrants of the site are in good condition (except for very minor damage to the stockade fence on the northwest side of the commuter lot).

The monitoring wells that were observed were locked and appeared to be in good condition. The compliance boundary on the southwest side of the site is the backwash channel, which is in a vegetated marshy area which is difficult to traverse. Where observed near its confluence with the Rumford River, the amount of water in the backwash channel was miniscule, and no flow was observable. However, at the actual confluence, it was confirmed that the trickle of flow in the channel was moving northwest and discharging to the river. The wells along the compliance boundary had been sampled several weeks before the site inspection and were therefore not inspected.

Interviews

Representatives of the Town of Mansfield DPW and the Town of Foxborough, and the MassDEP Project Manager each responded to a request for an interview by providing written responses to a series of

interview questions. Attachment 3 includes a detailed summary of the interviews. In general, representatives from both towns were very pleased with the work conducted at the Site. The town representatives stated that they have been well informed throughout the process and that they have no concerns. The representative from the Town of Mansfield would like to see the institutional controls implemented so that the town can move forward with potential reuse of the property. Town of Mansfield personnel periodically inspect the Site. It was noted by the representative from Mansfield that, although vandalism has generally not been an issue at the Site, a few fence cuts in the deep woods have been found. The Project Manager for the MassDEP also stated that the project was a success, that he was well informed, and that he has no concerns.

Technical Compliance Evaluation of Remedy Components

The technical compliance evaluation is conducted to determine whether the individual components of the remedy are being maintained and operated in accordance with their intended functions.

Evaluation of Intended Function:

- The RAOs of preventing ingestion and dermal contact with surface and subsurface soils that would result in unacceptable risks have been achieved as a result of the remedial action. Institutional controls restricting inappropriate land uses and protecting the consolidation cell cover and other components of the remedy, as required by the 2011 ESD, need to be established to better ensure future protectiveness.
- The RAO of preventing discharge of pentachlorophenol and other COPCs from soil to groundwater and from groundwater to surface water at concentrations that would result in an in-stream exceedance of the Ambient Water Quality Criteria (AWQCs) was addressed via source control. The ROD and O&M Manual require annual surface water monitoring; however no surface water sampling has been conducted since the remedy was completed. Surface water sampling, in accordance with the ROD, is recommended in order to confirm that there are no in-stream exceedances of the AWQCs..
- The RAO of preventing exposure to groundwater by future residents, recreational users, or commercial workers by monitoring extent of plume (to ensure it is remaining on-site) is being addressed via the ongoing groundwater monitoring at existing monitoring wells. Institutional controls restricting the use of groundwater within the site boundary, as required by the 2011 ESD, need to be established to better ensure future protectiveness. Also, as recommended in the *Hydrogeologic Conditions Report* prepared by AECOM (2013), an expanded groundwater monitoring effort at private wells beyond the compliance boundary is also being implemented by EPA in response to the detection of contamination in monitoring wells at the boundary. Although not expected, if off-site plume migration is detected during monitoring of private wells, additional measures may be necessary to maintain protectiveness.
- The exposure pathways that were stated in the ROD and ESD are still valid. More detail is provided in the Assessment of Changes in Standards Memorandum.
- The zoning of the Foxborough Parcel was changed from Future Residential to “Limited Industrial”. This changed was addressed in the ESD, issued in 2011, and does not affect the protectiveness of the remedy.

References


AECOM. 2013. Hydrogeologic Conditions Report. Letter report addressed to Mr. David Lederer of EPA-New England, Region 1. March 29, 2013.

Sevenson Environmental Services, Inc. 2011. Final Remedial Action Completion Report. Hatheway and Patterson Superfund Site. Mansfield, Massachusetts. September 2011.

U.S. Environmental Protection Agency (USEPA). 2005. Record of Decision. Hatheway & Patterson Superfund Site, Mansfield-Foxborough, Massachusetts. September 30, 2005.

U.S. Environmental Protection Agency (USEPA). 2011. Declaration for the Explanation of Significant Differences. Hatheway & Patterson Superfund Site, Mansfield/Foxborough, Massachusetts. August 2011.

FIGURES



SITE LOCATION MAP

Hatheway and Patterson
Superfund Site
35 County Street
Mansfield, MA

Location of Facility



FIGURE 1.1

★ Site Location



0 2,000 Feet



AMEC Earth and Environmental, Inc.
2 Robbins Road
Westford, MA 01886
(978) 692-9090

ATTACHMENT 1

SITE INSPECTION CHECKLIST

Five-Year Review Site Inspection Checklist

(“N/A” refers to “not applicable.”)

I. SITE INFORMATION	
Site name: Hatheway & Patterson) Superfund Site	Date of inspection: June 3, 2014
Location and Region: Mansfield, MA; Region I	EPA ID: MAD001060805
Agency, office, or company leading the five-year review: USEPA/AECOM	Weather/temperature: Clear/80°F
Remedy Includes: (Check all that apply) <div style="display: flex; flex-wrap: wrap;"> <div style="width: 50%;"> <input type="checkbox"/> Landfill cover/containment <input checked="" type="checkbox"/> Access controls <input checked="" type="checkbox"/> Institutional controls <input type="checkbox"/> Groundwater pump and treatment <input type="checkbox"/> Surface water collection and treatment </div> <div style="width: 50%;"> <input type="checkbox"/> Monitored natural attenuation <input type="checkbox"/> Groundwater containment <input type="checkbox"/> Vertical barrier walls </div> </div> <p><input checked="" type="checkbox"/> Other <u>Monitoring of groundwater, surface water, sediment, and fish; asphalt-paved parking lot on Foxborough portion of NW Quadrant of site</u></p>	
Attachments: <input type="checkbox"/> Inspection team roster attached <input type="checkbox"/> Site map attached	
II. INTERVIEWS	
Interviews were performed by USEPA/AECOM and are included separately.	

III. ON-SITE DOCUMENTS & RECORDS VERIFIED (Check all that apply)				
1.	O&M Documents <input checked="" type="checkbox"/> O&M manual <input checked="" type="checkbox"/> As-built drawings <input checked="" type="checkbox"/> Maintenance logs	<input checked="" type="checkbox"/> Readily available <input checked="" type="checkbox"/> Readily available <input type="checkbox"/> Readily available	<input type="checkbox"/> Up to date <input type="checkbox"/> Up to date <input checked="" type="checkbox"/> Up to date	<input type="checkbox"/> N/A <input type="checkbox"/> N/A <input type="checkbox"/> N/A
Remarks: O&M manual was included RA Report, along with as-built drawings.				
2.	Site-Specific Health and Safety Plan <input type="checkbox"/> Contingency plan/emergency response plan	<input type="checkbox"/> Readily available <input type="checkbox"/> Readily available	<input type="checkbox"/> Up to date <input type="checkbox"/> Up to date	<input type="checkbox"/> N/A <input type="checkbox"/> N/A
Remarks: Not seen or reviewed – presumably available at office of contractor who performs monitoring and inspection.				
3.	O&M and OSHA Training Records	<input type="checkbox"/> Readily available	<input type="checkbox"/> Up to date	<input type="checkbox"/> N/A
Remarks: Not seen or reviewed – presumably available at office of contractor who performs monitoring and inspection.				
4.	Permits and Service Agreements <input type="checkbox"/> Air discharge permit <input type="checkbox"/> Effluent discharge <input type="checkbox"/> Waste disposal, POTW <input type="checkbox"/> Other permits _____	<input type="checkbox"/> Readily available <input type="checkbox"/> Readily available <input type="checkbox"/> Readily available <input type="checkbox"/> Readily available	<input type="checkbox"/> Up to date <input type="checkbox"/> Up to date <input type="checkbox"/> Up to date <input type="checkbox"/> Up to date	<input checked="" type="checkbox"/> N/A <input checked="" type="checkbox"/> N/A <input checked="" type="checkbox"/> N/A <input checked="" type="checkbox"/> N/A
Remarks:				
5.	Gas Generation Records	<input type="checkbox"/> Readily available	<input type="checkbox"/> Up to date	<input checked="" type="checkbox"/> N/A
Remarks:				
6.	Settlement Monument Records	<input type="checkbox"/> Readily available	<input type="checkbox"/> Up to date	<input checked="" type="checkbox"/> N/A
Remarks:				
7.	Groundwater Monitoring Records	<input checked="" type="checkbox"/> Readily available	<input checked="" type="checkbox"/> Up to date	<input type="checkbox"/> N/A
Remarks:				
8.	Leachate Extraction Records	<input type="checkbox"/> Readily available	<input type="checkbox"/> Up to date	<input checked="" type="checkbox"/> N/A
Remarks:				
9.	Discharge Compliance Records <input type="checkbox"/> Air <input type="checkbox"/> Water (effluent)	<input type="checkbox"/> Readily available <input type="checkbox"/> Readily available	<input type="checkbox"/> Up to date <input type="checkbox"/> Up to date	<input checked="" type="checkbox"/> N/A <input checked="" type="checkbox"/> N/A
10.	Daily Access/Security Logs	<input type="checkbox"/> Readily available	<input type="checkbox"/> Up to date	<input checked="" type="checkbox"/> N/A
Remarks:				

IV. O&M COSTS	
1.	O&M Organization <input type="checkbox"/> State in-house <input type="checkbox"/> PRP in-house <input type="checkbox"/> Federal Facility in-house <input type="checkbox"/> Other _____ <div style="text-align: right;"> <input checked="" type="checkbox"/> Contractor for State <input type="checkbox"/> Contractor for PRP <input type="checkbox"/> Contractor for Federal Facility </div>
2.	O&M Cost Records <div style="text-align: center;">Not Reviewed</div>
3.	Unanticipated or Unusually High O&M Costs During Review Period Describe costs and reasons: _____ _____ _____ _____
V. ACCESS AND INSTITUTIONAL CONTROLS <input checked="" type="checkbox"/> Applicable <input type="checkbox"/> N/A	
A. Fencing	
1.	Fencing damaged <input type="checkbox"/> Location shown on site map <input checked="" type="checkbox"/> Gates secured <input type="checkbox"/> N/A Remarks: <u>The cyclone fencing that surrounds most of the site appears to be in good condition. The two vehicle gates that provide access to the site off County Street are locked and in good condition, as are the two vehicle gates that isolate the site from the (active) railroad tracks that bisect the site and the vehicle gate that separates the Foxborough commuter parking lot from the rest of the NW Quadrant.</u>
B. Other Access Restrictions	
1.	Signs and other security measures <input type="checkbox"/> Location shown on site map <input checked="" type="checkbox"/> N/A Remarks _____ _____

C. Institutional Controls (ICs)				
1.	Implementation and enforcement			
	Site conditions imply ICs not properly implemented	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
	Site conditions imply ICs not being fully enforced	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
	Type of monitoring (e.g., self-reporting, drive by) _____			
	Frequency _____			
	Responsible party/agency _____			
	Contact _____			
	Name	Title	Date	Phone no.
	Reporting is up-to-date		<input type="checkbox"/> Yes	<input type="checkbox"/> No <input type="checkbox"/> N/A
	Reports are verified by the lead agency		<input type="checkbox"/> Yes	<input type="checkbox"/> No <input type="checkbox"/> N/A
	Specific requirements in deed or decision documents have been met		<input type="checkbox"/> Yes	<input type="checkbox"/> No <input type="checkbox"/> N/A
	Violations have been reported		<input type="checkbox"/> Yes	<input type="checkbox"/> No <input type="checkbox"/> N/A
	Other problems or suggestions: <input type="checkbox"/> Report attached			
	Remarks <u>ICs are not yet in place.</u>			

2.	Adequacy	<input type="checkbox"/> ICs are adequate	<input type="checkbox"/> ICs are inadequate	<input type="checkbox"/> N/A
	Remarks <u>ICs are not yet in place.</u>			
D. General				
1.	Vandalism/trespassing	<input type="checkbox"/> Location shown on site map	<input checked="" type="checkbox"/> No vandalism evident	
	Remarks _____			
2.	Land use changes on site	<input checked="" type="checkbox"/> N/A		
	Remarks _____			
3.	Land use changes off site	<input checked="" type="checkbox"/> N/A		
	Remarks _____			
VI. GENERAL SITE CONDITIONS				
A. Roads <input checked="" type="checkbox"/> Applicable <input type="checkbox"/> N/A				
1.	Roads damaged	<input type="checkbox"/> Location shown on site map	<input checked="" type="checkbox"/> Roads adequate	<input type="checkbox"/> N/A
	Remarks _____			

B. Other Site Conditions			
<p>Remarks <u>The NE Quadrant of the site is a vegetated field except for a small paved area at its eastern end, where the Town of Mansfield has its Emergency Management Building and a large storage facility. Vegetation is reportedly cut twice per year and was due to be cut shortly after the site inspection.</u></p> <p><u>The NW Quadrant of the site is covered with crushed rock, except for the buffer strip along the Rumford River and the commuter parking lot in the northwestern corner. The fencing that completely surrounds the NE and NW Quadrants of the site is in good condition, as are the two gates on County Street, the two gates at the railroad crossing, and the gate that isolates the commuter parking lot.</u></p>			
VII. LANDFILL COVERS <input type="checkbox"/> Applicable X N/A			
A. Landfill Surface			
1.	Settlement (Low spots) Areal extent _____ Depth _____ Remarks _____	<input type="checkbox"/> Location shown on site map Depth _____	<input type="checkbox"/> Settlement not evident
2.	Cracks Lengths _____ Remarks _____	<input type="checkbox"/> Location shown on site map Widths _____ Depths _____	<input type="checkbox"/> Cracking not evident
3.	Erosion Areal extent _____ Remarks _____	<input type="checkbox"/> Location shown on site map Depth _____	<input type="checkbox"/> Erosion not evident
4.	Holes Areal extent _____ Remarks _____	<input type="checkbox"/> Location shown on site map Depth _____	<input type="checkbox"/> Holes not evident
5.	Vegetative Cover <input type="checkbox"/> Grass <input type="checkbox"/> Cover properly established <input type="checkbox"/> No signs of stress <input type="checkbox"/> Trees/Shrubs (indicate size and locations on a diagram) Remarks _____		
6.	Alternative Cover (armored rock, concrete, etc.) <input type="checkbox"/> N/A Remarks _____		
7.	Bulges Areal extent _____ Remarks _____	<input type="checkbox"/> Location shown on site map Height _____	<input type="checkbox"/> Bulges not evident

8.	Wet Areas/Water Damage <input type="checkbox"/> Wet areas <input type="checkbox"/> Ponding <input type="checkbox"/> Seeps <input type="checkbox"/> Soft subgrade Remarks _____ _____	<input type="checkbox"/> Wet areas/water damage not evident <input type="checkbox"/> Location shown on site map Areal extent _____ <input type="checkbox"/> Location shown on site map Areal extent _____ <input type="checkbox"/> Location shown on site map Areal extent _____ <input type="checkbox"/> Location shown on site map Areal extent _____
9.	Slope Instability <input type="checkbox"/> Slides <input type="checkbox"/> Location shown on site map <input type="checkbox"/> No evidence of slope instability Areal extent _____ Remarks _____ _____	
B. Benches <input type="checkbox"/> Applicable <input type="checkbox"/> N/A (Horizontally constructed mounds of earth placed across a steep landfill side slope to interrupt the slope in order to slow down the velocity of surface runoff and intercept and convey the runoff to a lined channel.)		
1.	Flows Bypass Bench Remarks _____ _____	<input type="checkbox"/> Location shown on site map <input type="checkbox"/> N/A or okay
2.	Bench Breached Remarks _____ _____	<input type="checkbox"/> Location shown on site map <input type="checkbox"/> N/A or okay
3.	Bench Overtopped Remarks _____ _____	<input type="checkbox"/> Location shown on site map <input type="checkbox"/> N/A or okay
C. Letdown Channels <input type="checkbox"/> Applicable <input type="checkbox"/> N/A (Channel lined with erosion control mats, riprap, grout bags, or gabions that descend down the steep side slope of the cover and will allow the runoff water collected by the benches to move off of the landfill cover without creating erosion gullies.)		
1.	Settlement <input type="checkbox"/> Location shown on site map <input type="checkbox"/> No evidence of settlement Areal extent _____ Depth _____ Remarks _____ _____	
2.	Material Degradation <input type="checkbox"/> Location shown on site map <input type="checkbox"/> No evidence of degradation Material type _____ Areal extent _____ Remarks _____ _____	
3.	Erosion <input type="checkbox"/> Location shown on site map <input type="checkbox"/> No evidence of erosion Areal extent _____ Depth _____ Remarks _____ _____	

4.	Undercutting Areal extent _____ Depth _____ Remarks _____	<input type="checkbox"/> Location shown on site map <input type="checkbox"/> No evidence of undercutting	
5.	Obstructions Type _____ <input type="checkbox"/> Location shown on site map Areal extent _____ Size _____ Remarks _____	<input type="checkbox"/> No obstructions	
6.	Excessive Vegetative Growth Type _____ <input type="checkbox"/> No evidence of excessive growth <input type="checkbox"/> Vegetation in channels does not obstruct flow <input type="checkbox"/> Location shown on site map Areal extent _____ Remarks: _____		
D. Cover Penetrations <input type="checkbox"/> Applicable <input type="checkbox"/> N/A			
1.	Gas Vents <input type="checkbox"/> Active <input type="checkbox"/> Passive <input type="checkbox"/> Properly secured/locked <input type="checkbox"/> Functioning <input type="checkbox"/> Routinely sampled X Good condition <input type="checkbox"/> Evidence of leakage at penetration <input type="checkbox"/> Needs Maintenance <input type="checkbox"/> N/A Remarks:		
2.	Gas Monitoring Probes <input type="checkbox"/> Properly secured/locked <input type="checkbox"/> Functioning <input type="checkbox"/> Routinely sampled <input type="checkbox"/> Good condition <input type="checkbox"/> Evidence of leakage at penetration <input type="checkbox"/> Needs Maintenance <input type="checkbox"/> N/A Remarks:		
3.	Monitoring Wells (within surface area of landfill) <input type="checkbox"/> Properly secured/locked <input type="checkbox"/> Functioning <input type="checkbox"/> Routinely sampled <input type="checkbox"/> Good condition <input type="checkbox"/> Evidence of leakage at penetration <input type="checkbox"/> Needs Maintenance <input type="checkbox"/> N/A Remarks _____		
4.	Leachate Extraction Wells <input type="checkbox"/> Properly secured/locked <input type="checkbox"/> Functioning <input type="checkbox"/> Routinely sampled <input type="checkbox"/> Good condition <input type="checkbox"/> Evidence of leakage at penetration <input type="checkbox"/> Needs Maintenance <input type="checkbox"/> N/A Remarks _____		
5.	Settlement Monuments <input type="checkbox"/> Located <input type="checkbox"/> Routinely surveyed <input type="checkbox"/> N/A Remarks _____		

E. Gas Collection and Treatment		<input type="checkbox"/> Applicable	<input type="checkbox"/> N/A
1.	Gas Treatment Facilities <input type="checkbox"/> Flaring <input type="checkbox"/> Thermal destruction <input type="checkbox"/> Collection for reuse <input type="checkbox"/> Good condition <input type="checkbox"/> Needs Maintenance Remarks:		
2.	Gas Collection Wells, Manifolds and Piping <input type="checkbox"/> Good condition <input type="checkbox"/> Needs Maintenance Remarks:		
3.	Gas Monitoring Facilities (<i>e.g.</i> , gas monitoring of adjacent homes or buildings) <input type="checkbox"/> Good condition <input type="checkbox"/> Needs Maintenance <input type="checkbox"/> N/A Remarks _____ _____		
F. Cover Drainage Layer		<input type="checkbox"/> Applicable	<input type="checkbox"/> N/A
1.	Outlet Pipes Inspected <input type="checkbox"/> Functioning <input type="checkbox"/> N/A Remarks:		
2.	Outlet Rock Inspected <input type="checkbox"/> Functioning <input type="checkbox"/> N/A Remarks:		
G. Detention/Sedimentation Ponds		<input type="checkbox"/> Applicable	<input type="checkbox"/> N/A
1.	Siltation Areal extent _____ Depth _____ <input type="checkbox"/> N/A <input type="checkbox"/> Siltation not evident Remarks:		
2.	Erosion Areal extent _____ Depth _____ <input type="checkbox"/> Erosion not evident Remarks _____ _____		
3.	Outlet Works <input type="checkbox"/> Functioning <input type="checkbox"/> N/A Remarks _____ _____		
4.	Dam <input type="checkbox"/> Functioning <input type="checkbox"/> N/A Remarks _____ _____		

H. Retaining Walls		<input type="checkbox"/> Applicable	<input type="checkbox"/> N/A
1.	Deformations <input type="checkbox"/> Location shown on site map <input type="checkbox"/> Deformation not evident Horizontal displacement_____ Vertical displacement_____ Rotational displacement_____ Remarks_____		
2.	Degradation <input type="checkbox"/> Location shown on site map <input type="checkbox"/> Degradation not evident Remarks_____		
I. Perimeter Ditches/Off-Site Discharge		<input type="checkbox"/> Applicable	<input type="checkbox"/> N/A
1.	Siltation <input type="checkbox"/> Location shown on site map X Siltation not evident Areal extent_____ Depth_____ Remarks_____		
2.	Vegetative Growth <input type="checkbox"/> Location shown on site map <input type="checkbox"/> N/A <input type="checkbox"/> Vegetation does not impede flow Areal extent_____ Type_____ Remarks:		
3.	Erosion <input type="checkbox"/> Location shown on site map <input type="checkbox"/> Erosion not evident Areal extent_____ Depth_____ Remarks_____		
4.	Discharge Structure <input type="checkbox"/> Functioning <input type="checkbox"/> N/A Remarks:		
VIII. VERTICAL BARRIER WALLS		<input type="checkbox"/> Applicable	X N/A
1.	Settlement <input type="checkbox"/> Location shown on site map <input type="checkbox"/> Settlement not evident Areal extent_____ Depth_____ Remarks_____		
2.	Performance Monitoring Type of monitoring_____ <input type="checkbox"/> Performance not monitored Frequency_____ <input type="checkbox"/> Evidence of breaching Head differential_____ Remarks_____		

IX. GROUNDWATER/SURFACE WATER REMEDIES <input type="checkbox"/> Applicable <input checked="" type="checkbox"/> N/A			
A. Groundwater Extraction Wells, Pumps, and Pipelines <input type="checkbox"/> Applicable <input type="checkbox"/> N/A			
1.	Pumps, Wellhead Plumbing, and Electrical <input type="checkbox"/> Good condition <input type="checkbox"/> All required wells properly operating <input type="checkbox"/> Needs Maintenance <input type="checkbox"/> N/A Remarks:		
2.	Extraction System Pipelines, Valves, Valve Boxes, and Other Appurtenances <input type="checkbox"/> Good condition <input type="checkbox"/> Needs Maintenance Remarks:		
3.	Spare Parts and Equipment <input type="checkbox"/> Readily available <input type="checkbox"/> Good condition <input type="checkbox"/> Requires upgrade <input type="checkbox"/> Needs to be provided Remarks:		
B. Surface Water Collection Structures, Pumps, and Pipelines <input type="checkbox"/> Applicable <input type="checkbox"/> N/A			
1.	Collection Structures, Pumps, and Electrical <input type="checkbox"/> Good condition <input type="checkbox"/> Needs Maintenance Remarks_____		
2.	Surface Water Collection System Pipelines, Valves, Valve Boxes, and Other Appurtenances <input type="checkbox"/> Good condition <input type="checkbox"/> Needs Maintenance Remarks_____		
3.	Spare Parts and Equipment <input type="checkbox"/> Readily available <input type="checkbox"/> Good condition <input type="checkbox"/> Requires upgrade <input type="checkbox"/> Needs to be provided Remarks_____		

C. Treatment System		<input type="checkbox"/> Applicable	<input type="checkbox"/> N/A
1.	Treatment Train (Check components that apply) <input type="checkbox"/> Metals removal <input type="checkbox"/> Oil/water separation <input type="checkbox"/> Bioremediation <input type="checkbox"/> Air stripping <input type="checkbox"/> Carbon adsorbers <input type="checkbox"/> Filters: microfiltration and filter presses <input type="checkbox"/> Additive (<i>e.g.</i> , chelation agent, flocculent) _____ <input type="checkbox"/> Others _____ <input type="checkbox"/> Good condition <input type="checkbox"/> Needs Maintenance <input type="checkbox"/> Sampling ports properly marked and functional <input type="checkbox"/> Sampling/maintenance log displayed and up to date <input type="checkbox"/> Equipment properly identified <input type="checkbox"/> Quantity of groundwater treated annually _____ <input type="checkbox"/> Quantity of surface water treated annually _____ Remarks _____ _____		
2.	Electrical Enclosures and Panels (properly rated and functional) <input type="checkbox"/> N/A <input type="checkbox"/> Good condition <input type="checkbox"/> Needs Maintenance Remarks _____ _____		
3.	Tanks, Vaults, Storage Vessels <input type="checkbox"/> N/A <input type="checkbox"/> Good condition <input type="checkbox"/> Proper secondary containment <input type="checkbox"/> Needs Maintenance Remarks _____ _____		
4.	Discharge Structure and Appurtenances <input type="checkbox"/> N/A <input type="checkbox"/> Good condition <input type="checkbox"/> Needs Maintenance Remarks _____ _____		
5.	Treatment Building(s) <input type="checkbox"/> N/A <input type="checkbox"/> Good condition (esp. roof and doorways) <input type="checkbox"/> Needs repair <input type="checkbox"/> Chemicals and equipment properly stored Remarks _____ _____		
6.	Monitoring Wells (pump and treatment remedy) <input type="checkbox"/> Properly secured/locked <input type="checkbox"/> Functioning X Routinely sampled <input type="checkbox"/> Good condition <input type="checkbox"/> All required wells located <input type="checkbox"/> Needs Maintenance <input type="checkbox"/> N/A Remarks: _____ _____		
D. Monitoring Data:			
1.	Monitoring Data <input type="checkbox"/> Is routinely submitted on time <input type="checkbox"/> Is of acceptable quality		
2.	Monitoring data suggests: <input type="checkbox"/> Groundwater plume is effectively contained <input type="checkbox"/> Contaminant concentrations are declining		

D. Monitored Natural Attenuation			
1.	Monitoring Wells (natural attenuation remedy) <input type="checkbox"/> Properly secured/locked <input type="checkbox"/> Functioning <input type="checkbox"/> Routinely sampled <input type="checkbox"/> Good condition <input type="checkbox"/> All required wells located <input type="checkbox"/> Needs Maintenance <input type="checkbox"/> N/A Remarks:		
X. OTHER REMEDIES			
<p><u>Bituminous Asphalt Cover.</u> The portion of the NW Quadrant of the site that is within the Town of Foxborough was paved to create a commuter parking lot. The pavement appears to be in very good condition, with only minor cracks along joints in the pavement and near the southern corner of the lot. No settlement was observed. Silt fence at the outlet of the storm drainage system (possibly a relic from construction) is breached, and minor repairs are needed at two locations along the stockade fence that borders the northwest side of the lot. However, the overall condition of the lot is very good.</p> <p><u>Monitoring Wells.</u> The monitoring wells that were observed were locked and appeared to be in good condition. None were marked, but the markings may be under the protective covers. A monitoring round had been conducted a few weeks prior to the site inspection, and no deficiencies in the well network had been reported.</p>			
XI. OVERALL OBSERVATIONS			
A. Implementation of the Remedy			
The remedy is effective and functioning as designed. Access to the site is restricted. Institutional controls are not yet in place, but the site is inaccessible (except for along the railroad tracks) for activities that would involve excavation or drilling. Monitoring of groundwater, surface water, sediment, and fish are ongoing.			
B. Adequacy of O&M			
Other than maintenance of the fencing that surrounds most of the site, little O&M is required. The vegetation at the site is cut twice per year, and the portion of the site that is a commuter parking lot is in good condition.			
C. Early Indicators of Potential Remedy Problems			
Describe issues and observations such as unexpected changes in the cost or scope of O&M or a high frequency of unscheduled repairs that suggest that the protectiveness of the remedy may be compromised in the future.			
None			

D.	Opportunities for Optimization
	Describe possible opportunities for optimization in monitoring tasks or the operation of the remedy.
	None

ATTACHMENT 2

SITE PHOTOS

HATHEWAY AND PATTERSON SUPERFUND SITE
June 3, 2014 - SITE INSPECTION PHOTOGRAPHS



Photo #1. Easternmost Gate to Site off County Road



Photo #2. Looking Southeast across NE Quadrant of Site



Photo #3. Looking Southeast Across NW Quadrant of Site (NE Quadrant in distance)



Photo #4. Looking Southeast along Railroad Tracks that Bisect Site



Photo #5. Gates at RR Crossing Between Northern and Southern Quadrants of Site



**Photo #6. Rumford River Flowing Southwest in Channel Between NW and NE Quadrants of Site
(Railroad Bridges Across River in Background)**



Photo #7. Rumford River Downstream of Railroad Bridges and Upstream of Confluence with Backwash Channel



Photo #8. Backwash Channel Flowing (<<1 gpm, from left to right, in rivulet that crosses mud-filled channel) into Rumford River



Photo #9. Commuter Parking Lot on Foxborough Portion of Site (Note minor crack in pavement in foreground along painted line)



Photo #10. Gate Separating Commuter Lot from NW Quadrant of Site (note flush-mount monitoring well along fence, with road box painted white)

ATTACHMENT 3

INTERVIEW RECORDS

INTERVIEW RECORD

Site Name: Hatheway and Patterson Superfund Site (Mansfield, MA)		EPA ID No.: MAD001060805	
Subject: Five Year Review		Time:	Date:
Type: <input type="checkbox"/> Telephone <input type="checkbox"/> Visit <input type="checkbox"/> Other Location of Visit:		<input type="checkbox"/> Incoming <input type="checkbox"/> Outgoing	
Contact Made By:			
Name:	Title:	Organization: AECOM	
Individual Contacted:			
Name: Mike Ahern	Title: Department of Public Works	Organization: Town of Mansfield	
Telephone No: (508) 261-7335 Fax No: (508) 261-7452 E-Mail: mahern@mansfieldma.com	Street Address: 6 Park Row, Mansfield, MA 02048		

1. **What is your overall impression of the project? (general sentiment)**
 - *Project went very well. Town was very happy.*

2. **Do you feel well informed about site activities and progress?**
 - *Yes, the Town was kept very well informed throughout the process and was invited to attend various project meetings to stay current with job progress.*

3. **What are the current uses of the property?**
 - *Presently part of the property is used for Mansfield Emergency Management Agency and the rest is presently grassed areas and gravel parking.*

4. **What are the planned future uses of the property (if different from current uses)?**
 - *Town is looking at the property for future uses including business development and other potential uses.*

5. **Is there evidence or sightings of trespassers on the property? If yes, how often and what type of activities do they engage in?**
 - *Generally no, although there has been a few, mainly hunters only. Whereas the site has Emergency Management on site they constantly look at the site.*

6. **Have there been any events of vandalism at the property?**
 - *Generally no, except for few fence cuts in deep woods.*

7. Have there been any unusual or unexpected activities or events at the site (e.g., flooding)? If so, what if anything was done to address these issues?

- *In existing parking area there has been small ponding, but it is being addressed by the Town. (No issue)*

8. Have any problems been encountered or changes in the site conditions that affect the current operations at the site?

- *No.*

9. Has the site been the subject of any community complaints (e.g., odor, noise, health, etc.)?

- *No.*

10. Are you aware of any community concerns regarding the site or remedial actions performed? If so, please provide details.

- *No.*

11. Have there been routine communications or activities (site visits, inspections, reporting activities, etc.) conducted by your office regarding the site? If so, please give purpose and results.

- *We do general inspections and as stated in question 5, Mansfield Emergency Management watches the site.*

12. Do you have any comments, suggestions, or recommendations regarding site management or operation?

- *Generally no, everything is going well. The only thing would be the completion of the site specific activity use limitations so we can move forward with the potential uses of the property.*

13. Is there any other information that you wish to share that might be of use?

- *Overall, the project went very well. It was great working with the staff of the EPA and the Army Corps of Engineers. Dave Lenderer from the EPA, Chris Turek of the Army Corps of Engineers and Gary Waldeck from Mass DEP were all exceptional to work with.*

INTERVIEW RECORD

Site Name: Hatheway and Patterson Superfund Site (Mansfield, MA)		EPA ID No.: MAD001060805	
Subject: Five Year Review		Time: 2:40pm	Date: 6/25/2014
Type: <input type="checkbox"/> Telephone <input type="checkbox"/> Visit <input checked="" type="checkbox"/> Other Location of Visit:		<input type="checkbox"/> Incoming <input checked="" type="checkbox"/> Outgoing	
Contact Made By:			
Name:	Title:	Organization: AECOM	
Individual Contacted:			
Name: William R. Scollins, III	Title: Finance Director	Organization: Town of Foxborough	
Telephone No: 508-543-1218 Fax No: 508-543-6278 E-Mail: rscollins@town.foxborough.ma.us	Street Address: 40 South Street, Foxborough, MA 02035		

1. What is your overall impression of the project? (general sentiment)

We are very pleased with the result. To have a long standing hazardous waste site cleaned up in a residential neighborhood and then repurposed for the benefit of the Foxborough residents is incredibly positive for all.

2. Do you feel well informed about site activities and progress?

Yes. During the cleanup and reconstruction of the property, the project managers maintained a website that was kept updated with all activities and progress. When there were critical decisions to be made appropriate meetings were held with Town officials.

3. What are the current uses of the property?

A dedicated free commuter parking lot for Foxborough residents only who take the commuter rail from Mansfield, as per the site conditions.

4. What are the planned future uses of the property (if different from current uses)?

The Town is prohibited from changing the use from a parking lot to anything else, as per the conditions of the funding award.

5. Is there evidence or sightings of trespassers on the property? If yes, how often and what type of activities do they engage in?

The local police patrol all areas of the Town including this parking lot. No trespassers have been reported. The property is well lit and signed.

6. Have there been any events of vandalism at the property?

None have been reported.

7. Have there been any unusual or unexpected activities or events at the site (e.g., flooding)? If so, what if anything was done to address these issues?

None have been reported.

8. Have any problems been encountered or changes in the site conditions that affect the current operations at the site?

None.

9. Has the site been the subject of any community complaints (e.g., odor, noise, health, etc.)?

None.

10. Are you aware of any community concerns regarding the site or remedial actions performed? If so, please provide details.

No concerns, other than a preference for a dedicated pathway from the parking lot to the Mansfield commuter rail station, which is a half mile away. This would require a level of funding that Foxborough would find quite difficult to absorb. Further, the pathway would be primarily on property in the Town of Mansfield.

11. Have there been routine communications or activities (site visits, inspections, reporting activities, etc.) conducted by your office regarding the site? If so, please give purpose and results.

We have actively promoted the site to residents at the Foxborough Town Hall & website, as well as the Mansfield train station. The police dept patrols the site routinely as part of their rounds. The highway dept maintains the light fixtures, signage, fencing, and grounds, including plowing and striping.

12. Do you have any comments, suggestions, or recommendations regarding site management or operation?

None at this time.

13. Is there any other information that you wish to share that might be of use?

We are grateful that this site was chosen to be remediated. The neighbors are pleased and the commuters are also pleased to have this lot as an option.

INTERVIEW RECORD

Site Name: Hatheway and Patterson Superfund Site (Mansfield, MA)		EPA ID No.: MAD001060805	
Subject: Five Year Review		Time:	Date:
Type: <input type="checkbox"/> Telephone <input type="checkbox"/> Visit <input type="checkbox"/> Other Location of Visit:		<input type="checkbox"/> Incoming <input type="checkbox"/> Outgoing	
Contact Made By:			
Name:	Title:	Organization: AECOM	
Individual Contacted:			
Name: Garry Waldeck	Title: State Remedial Project manager	Organization: MassDEP	
Telephone No: (617) 348-4017 Fax No: E-Mail Address: garry.waldeck@state.ma.us	Street Address: 1 Winter Street Boston, MA 02108		

1. **What is your overall impression of the project? (general sentiment)**
 The construction of the remedy is complete and the project was a success.

2. **Have there been routine communications or activities (site visits, inspections, reporting, etc.) conducted by your office at the site? If so, please give purpose and results.**
 Yes, MassDEP has been performing the O and M for the site, including groundwater and sediment sampling.

3. **Have there been any complaints, violations, or other incidents related to the site requiring response by your office? If so, please give details of the events and results of the responses.**
 No.

4. **Do you feel well informed about site activities and progress?**
 Yes

5. Do you have any comments, suggestions, or recommendations regarding the site's management or operation?

No

6. Are you aware of any problems or issues that will affect the progress or implementability of the proposed institutional controls?

No

7. Is there evidence or sightings of trespassers on the property, or evidence of vandalism? If yes, how often and what type of activities do they engage in?

No

8. Have there been any unusual or unexpected activities or events at the site (e.g., flooding)? If so, has this resulted in any damage or had an impact on operations at the site?

No

9. Has the site been the subject of any community complaints (e.g., odor, noise, health, etc.)?

No

10. Is there any other information that you wish to share that might be of use?

No

11. What are the annual system operation/O&M costs for OU-1 since the RA was completed? Please provide in the following format:

Dates		Total Cost (rounded to nearest \$1,000)
From	To	
4/1/12	6/6/14	\$111,000

APPENDIX E
INTERVIEW RECORD FORMS

INTERVIEW RECORD

Site Name: Hatheway and Patterson Superfund Site (Mansfield, MA)	EPA ID No.: MAD001060805
---	---------------------------------

Subject: Five Year Review	Time:	Date:
----------------------------------	--------------	--------------

Type: <input type="checkbox"/> Telephone <input type="checkbox"/> Visit <input checked="" type="checkbox"/> Other Location of Visit: by email	<input type="checkbox"/> Incoming <input type="checkbox"/> Outgoing
--	---

Contact Made By:

Name: Cinthia McLane	Title: Project Manager	Organization: AECOM
-----------------------------	-------------------------------	----------------------------

Individual Contacted:

Name: Garry Waldeck	Title: State Remedial Project manager	Organization: MassDEP
----------------------------	--	------------------------------

Telephone No: (617) 348-4017 Fax No: E-Mail Address: garry.waldeck@state.ma.us	Street Address: 1 Winter Street Boston, MA 02108
---	---

1. **What is your overall impression of the project? (general sentiment)**
 The construction of the remedy is complete and the project was a success.

2. **Have there been routine communications or activities (site visits, inspections, reporting, etc.) conducted by your office at the site? If so, please give purpose and results.**
 Yes, MassDEP has been performing the O and M for the site, including groundwater and sediment sampling.

3. **Have there been any complaints, violations, or other incidents related to the site requiring response by your office? If so, please give details of the events and results of the responses.**
 No.

4. **Do you feel well informed about site activities and progress?**
 Yes

5. Do you have any comments, suggestions, or recommendations regarding the site's management or operation?

No

6. Are you aware of any problems or issues that will affect the progress or implementability of the proposed institutional controls?

No

7. Is there evidence or sightings of trespassers on the property, or evidence of vandalism? If yes, how often and what type of activities do they engage in?

No

8. Have there been any unusual or unexpected activities or events at the site (e.g., flooding)? If so, has this resulted in any damage or had an impact on operations at the site?

No

9. Has the site been the subject of any community complaints (e.g., odor, noise, health, etc.)?

No

10. Is there any other information that you wish to share that might be of use?

No

11. What are the annual system operation/O&M costs for OU-1 since the RA was completed? Please provide in the following format:

Dates		Total Cost (rounded to nearest \$1,000)
From	To	
4/1/12	6/6/14	\$111,000

INTERVIEW RECORD

Site Name: Hatheway and Patterson Superfund Site (Mansfield, MA)		EPA ID No.: MAD001060805	
Subject: Five Year Review		Time: 2:40pm	Date: 6/25/2014
Type: <input type="checkbox"/> Telephone <input type="checkbox"/> Visit <input checked="" type="checkbox"/> Other Location of Visit:		<input type="checkbox"/> Incoming <input checked="" type="checkbox"/> Outgoing	
Contact Made By:			
Name: Cinthia McLane	Title: Project Manager	Organization: AECOM	
Individual Contacted:			
Name: William R. Scollins, III	Title: Finance Director	Organization: Town of Foxborough	
Telephone No: 508-543-1218 Fax No: 508-543-6278 E-Mail: rscollins@town.foxborough.ma.us	Street Address: 40 South Street, Foxborough, MA 02035		

1. What is your overall impression of the project? (general sentiment)

We are very pleased with the result. To have a long standing hazardous waste site cleaned up in a residential neighborhood and then repurposed for the benefit of the Foxborough residents is incredibly positive for all.

2. Do you feel well informed about site activities and progress?

Yes. During the cleanup and reconstruction of the property, the project managers maintained a website that was kept updated with all activities and progress. When there were critical decisions to be made appropriate meetings were held with Town officials.

3. What are the current uses of the property?

A dedicated free commuter parking lot for Foxborough residents only who take the commuter rail from Mansfield, as per the site conditions.

4. What are the planned future uses of the property (if different from current uses)?

The Town is prohibited from changing the use from a parking lot to anything else, as per the conditions of the funding award.

5. Is there evidence or sightings of trespassers on the property? If yes, how often and what type of activities do they engage in?

The local police patrol all areas of the Town including this parking lot. No trespassers have been reported. The property is well lit and signed.

6. Have there been any events of vandalism at the property?

None have been reported.

7. Have there been any unusual or unexpected activities or events at the site (e.g., flooding)? If so, what if anything was done to address these issues?

None have been reported.

8. Have any problems been encountered or changes in the site conditions that affect the current operations at the site?

None.

9. Has the site been the subject of any community complaints (e.g., odor, noise, health, etc.)?

None.

10. Are you aware of any community concerns regarding the site or remedial actions performed? If so, please provide details.

No concerns, other than a preference for a dedicated pathway from the parking lot to the Mansfield commuter rail station, which is a half mile away. This would require a level of funding that Foxborough would find quite difficult to absorb. Further, the pathway would be primarily on property in the Town of Mansfield.

11. Have there been routine communications or activities (site visits, inspections, reporting activities, etc.) conducted by your office regarding the site? If so, please give purpose and results.

We have actively promoted the site to residents at the Foxborough Town Hall & website, as well as the Mansfield train station. The police dept patrols the site routinely as part of their rounds. The highway dept maintains the light fixtures, signage, fencing, and grounds, including plowing and striping.

12. Do you have any comments, suggestions, or recommendations regarding site management or operation?

None at this time.

13. Is there any other information that you wish to share that might be of use?

We are grateful that this site was chosen to be remediated. The neighbors are pleased and the commuters are also pleased to have this lot as an option.

INTERVIEW RECORD

Site Name: Hatheway and Patterson Superfund Site (Mansfield, MA)		EPA ID No.: MAD001060805	
Subject: Five Year Review		Time:	Date:
Type: <input type="checkbox"/> Telephone <input type="checkbox"/> Visit <input type="checkbox"/> Other Location of Visit:		<input type="checkbox"/> Incoming <input type="checkbox"/> Outgoing	
Contact Made By:			
Name:	Title:	Organization: AECOM	
Individual Contacted:			
Name: Mike Ahern		Title: Department of Public Works	Organization: Town of Mansfield
Telephone No: (508) 261-7335 Fax No: (508) 261-7452 E-Mail: mahern@mansfieldma.com		Street Address: 6 Park Row, Mansfield, MA 02048	

1. **What is your overall impression of the project? (general sentiment)**
 - *Project went very well. Town was very happy.*

2. **Do you feel well informed about site activities and progress?**
 - *Yes, the Town was kept very well informed throughout the process and was invited to attend various project meetings to stay current with job progress.*

3. **What are the current uses of the property?**
 - *Presently part of the property is used for Mansfield Emergency Management Agency and the rest is presently grassed areas and gravel parking.*

4. **What are the planned future uses of the property (if different from current uses)?**
 - *Town is looking at the property for future uses including business development and other potential uses.*

5. **Is there evidence or sightings of trespassers on the property? If yes, how often and what type of activities do they engage in?**
 - *Generally no, although there has been a few, mainly hunters only. Whereas the site has Emergency Management on site they constantly look at the site.*

6. **Have there been any events of vandalism at the property?**
 - *Generally no, except for few fence cuts in deep woods.*

7. Have there been any unusual or unexpected activities or events at the site (e.g., flooding)? If so, what if anything was done to address these issues?

- *In existing parking area there has been small ponding, but it is being addressed by the Town. (No issue)*

8. Have any problems been encountered or changes in the site conditions that affect the current operations at the site?

- *No.*

9. Has the site been the subject of any community complaints (e.g., odor, noise, health, etc.)?

- *No.*

10. Are you aware of any community concerns regarding the site or remedial actions performed? If so, please provide details.

- *No.*

11. Have there been routine communications or activities (site visits, inspections, reporting activities, etc.) conducted by your office regarding the site? If so, please give purpose and results.

- *We do general inspections and as stated in question 5, Mansfield Emergency Management watches the site.*

12. Do you have any comments, suggestions, or recommendations regarding site management or operation?

- *Generally no, everything is going well. The only thing would be the completion of the site specific activity use limitations so we can move forward with the potential uses of the property.*

13. Is there any other information that you wish to share that might be of use?

- *Overall, the project went very well. It was great working with the staff of the EPA and the Army Corps of Engineers. Dave Lenderer from the EPA, Chris Turek of the Army Corps of Engineers and Gary Waldeck from Mass DEP were all exceptional to work with.*

APPENDIX F
RISK CALCULATIONS



Post-Excavation
Soil Sample Locations

Hatheway and Patterson
Superfund Site
35 County Street
Mansfield, MA

Legend

- Confirmatory Soil Sample Location (Hatheway-Patterson Site)
- Post Excavation Soil Sample Location (CSX Right of Way)
- Limit of Excavation



FIGURE 4.1

0 115
Feet

amec

AMEC Environment & Infrastructure, Inc.
2 Robbins Road
Westford, MA 01886
(978) 692-9090



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Region 1

5 Post Office Square, Suite 100

BOSTON, MA 02109-3912

Date: June 18, 2014

From: Chau Vu, Human Health Risk Assessor, Technical & Enforcement Support Section

To: Kimberly White, RPM, MA Superfund Section

Subject: Update on Risks from Railroad Right-of-Way Exposures, Hatheway and Patterson Superfund Site

The purpose of this memorandum is to update Margaret McDonough's May 24, 2007 and March 31, 2011 memoranda on risk evaluation for the railroad right-of-way exposures at the Hatheway and Patterson Superfund Site (Appendix L of the September 2011 Final Remedial Action Completion Report for the Hatheway and Patterson Superfund Site). This update is performed to reflect the new release of the OSWER Directive 9200.1-120 dated February 6, 2014 on the Update of Standard Default Exposure Factors and the finalization of dioxin non-cancer oral reference dose (RfD) in February 2012 on EPA Integrated Risk Information System (IRIS). Prior to the final dioxin RfD value on IRIS, non-cancer health effects from exposures to dioxin were not usually evaluated due to the lack of a non-cancer toxicity value. This memorandum also includes the use of the default relative bioavailability value of 60% or 0.6 of arsenic in soil according to the December 2012 OSWER Directive 9200.1-113 Recommendations for Default Value for Relative Bioavailability of Arsenic in Soil. Due to the changes of standard default exposure factors, relative bioavailability for arsenic, and new dioxin RfD value, risk estimates for receptors exposed to contaminated subsurface soils at the railroad right-of-way on the Site have changed.

Similar to the 2007 and 2011 memos, risk screening and risk evaluation are performed in this memorandum using the maximum detected concentrations of pentachlorophenol (PCP), dioxin, and arsenic presented in the September 2011 Final Remedial Action Completion Report. The maximum detected concentrations are used from the 2010 dataset for post-excavation soil from the Report because these are soils closest to the railroad tracks and there are no samples collected from the railroad tracks themselves. Although there are five samples, including a duplicate sample, from the adjacent Northeast quadrant, and four samples from the Northwest quadrant, there are not sufficient samples to calculate a statistically significant 95th upper confidence limit (95% UCL) value for exposure point concentration. In this situation, it is EPA's practice to use the maximum detected concentration in the dataset to be conservative.

Risks are calculated for utility workers who are assumed to conduct repairs and maintenance at the railroad right-of-way area and exposed to contaminated subsurface soils via incidental

ingestion and dermal contact pathways. Table 1 below presents the default exposure factors for utility worker previously used in the 2007 and 2011 memos along with the currently recommended values from the 2012 and 2014 OSWER Directives and the 2012 dioxin IRIS update. For those exposure values not currently recommended, the values are kept the same as those used in previous memos.

Table 1 – Utility Worker Exposure Factors and Toxicity Values

Exposure Factors and Toxicity Values (units)	Symbol	Previous Default Value	Currently Recommended Value
Soil/sediment ingestion rate – intense contact (mg/day)	IR _{worker}	200	200
Default relative bioavailability for arsenic (%)	RBA _{arsenic}	100	60
Exposure frequency (days/year)	EF	66	66
Body weight (kg)	BW _{worker}	70	80
Skin surface area (cm ²)	SA _{worker}	3300	3470
Adherence factor (mg/cm ²) – utility worker	AF	0.2	0.12
Absorption factor for PCP (unitless)	ABS _{PCP}	0.13	0.25
Absorption factor for dioxin (unitless)	ABS _{dioxin}	0.13	0.03
Absorption factor for arsenic (unitless)	ABS _{arsenic}	0.13	0.03
Cancer slope factor for PCP (mg/kg-day) ⁻¹	CSF _{PCP}	0.4	0.4
Reference dose for PCP (mg/kg-day)	RfD _{PCP}	5E-03	5E-03
Cancer slope factor for dioxin (mg/kg-day) ⁻¹	CSF _{dioxin}	1.5E+05	1.5E+05
Reference dose for dioxin (mg/kg-day)	RfD _{dioxin}	Not Available	7E-10
Cancer slope factor for arsenic (mg/kg-day) ⁻¹	CSF _{arsenic}	1.5	1.5
Reference dose for arsenic (mg/kg-day)	RfD _{arsenic}	3E-04	3E-04
Averaging time for cancer risk (year)	AT _{cancer}	70	70
Averaging time for non-cancer risk – utility worker (year)	AT _{noncancer}	1	1

Bold text represents the exposure values changed since 2011.

Risk screening for 2010 subsurface soil data

Following EPA's risk assessment practice, the maximum detected concentrations of the 2010 dataset for post-excavation soil from the 2011 Final Remedial Action Completion Report are used to screen against the risk-based screening levels. Table 2 below presents the maximum concentrations and screening levels.

Table 2 – Maximum Concentrations near Railroad Right-of-Way Compared to EPA Risk-Based Screening Levels

Maximum Detected PCP (mg/kg)	EPA PCP Screening Level (mg/kg)	Maximum Detected Dioxin (mg/kg)	EPA Dioxin Screening Level (mg/kg)	Maximum Detected Arsenic (mg/kg)	EPA Arsenic Screening Level (mg/kg)
152	4 (1E-06 risk)	6.76E-03	2.2E-05 (1E-06 risk)	309	3 (1E-06 risk)

The EPA screening levels are developed based on a target cancer risk level of 1E-06 or an HI of 0.1 for each contaminant for commercial/industrial exposure scenario, using the standard EPA risk methodology. These chemical-specific values are selected from the May 2014 EPA Regional Screening Levels (RSLs) available at <http://www.epa.gov/reg3hwmd/risk/human/rb-concentration-table/>. Since the maximum detected concentrations of PCP, dioxin, and arsenic in subsurface soils near the railroad right-of-way exceed their respective screening levels, further risk evaluation is performed for these detected subsurface soil levels for utility worker and construction worker.

Risk evaluation for utility worker

The following equations are used to estimate cancer risks and non-cancer hazards for utility worker exposed to PCP, dioxin, and arsenic in subsurface soils at the railroad right-of-way area. Please refer to Table 1 above for more detailed descriptions of the values used in the equations.

Ingestion Pathway

Equation 1

$$\text{Cancer Risk} = \frac{\text{CSF} \times \text{RBA} \times \text{C} \times 10^{-6} \text{ kg/mg} \times \text{IR} \times \text{ED} \times \text{EF}}{\text{BW} \times \text{AT}_{\text{cancer}} \times 365 \text{ days/year}}$$

Where:

CSF = cancer slope factor
RBA = default relative bioavailability for arsenic
C = maximum detected concentration
IR = ingestion rate
ED = exposure duration
EF = exposure frequency
BW = body weight
AT_{cancer} = averaging time for cancer

Equation 2

$$\text{Hazard Index} = \frac{\text{C} \times \text{RBA} \times 10^{-6} \text{ kg/mg} \times \text{IR} \times \text{ED} \times \text{EF}}{\text{RfD} \times \text{BW} \times \text{AT}_{\text{noncancer}} \times 365 \text{ days/year}}$$

Where:

C	= maximum detected concentration
RBA	= default relative bioavailability for arsenic
IR	= ingestion rate
ED	= exposure duration
EF	= exposure frequency
RfD	= reference dose
BW	= body weight
AT _{noncancer}	= averaging time for non-cancer

Dermal Pathway

Equation 3

Cancer risk =

$$\text{CSF} \times \text{RBA} \times \text{C} \times 10^{-6} \text{ kg/mg} \times \text{ED} \times \text{EF} \times \text{ABS} \times \text{AF} \times \text{SA}$$

$$\text{BW} \times \text{AT}_{\text{cancer}} \times 365 \text{ days/year}$$

Where:

CSF	= cancer slope factor
RBA	= default relative bioavailability for arsenic
C	= maximum detected concentration
ED	= exposure duration
EF	= exposure frequency
ABS	= absorption factor
AF	= adherence factor
SA	= skin surface area
BW	= body weight
AT _{cancer}	= averaging time for cancer

Equation 4

$$\text{Hazard Index} = \frac{\text{C} \times \text{RBA} \times 10^{-6} \text{ kg/mg} \times \text{ED} \times \text{EF} \times \text{ABS} \times \text{AF} \times \text{SA}}{\text{RfD} \times \text{BW} \times \text{AT}_{\text{noncancer}} \times 365 \text{ days/year}}$$

Where:

C	= maximum detected concentration
RBA	= default relative bioavailability for arsenic
ED	= exposure duration
EF	= exposure frequency
ABS	= absorption factor
AF	= adherence factor
SA	= skin surface area
RfD	= reference dose

BW = body weight
 $AT_{\text{noncancer}}$ = averaging time for non-cancer

Similar to the 2007 and 2011 memos, utility workers are assumed to be exposed to contaminated subsurface soils at the railroad right-of-way area via incidental ingestion and dermal exposure pathways. Inhalation of subsurface soils is not considered an exposure pathway for this receptor.

Equation 5

Total Cancer Risk = Ingestion Risk + Dermal Risk

Equation 6

Total Hazard Index = Ingestion HI + Dermal HI

Applying the values from Tables 1 and 2 to these equations, the risk and hazard estimates for utility worker exposed to pentachlorophenol, dioxin, and arsenic in subsurface soils at the railroad right-of-way area are presented in Table 3 below.

Table 3 – Utility Worker Estimated Cancer Risk and Hazard Index

Subsurface Soil Contaminant	Maximum Concentration in Subsurface Soil (mg/kg)	Cancer Risk for Utility Worker	Hazard Index for Utility Worker
Pentachlorophenol	152	5E-07	0.02
Dioxin	6.76E-03	7E-06	4.7
Arsenic	309	2E-06	0.3
Total		1E-05	5.0

Table 3 shows that by using the updated exposure values and toxicity values with the 2010 subsurface soil data, total cancer risk estimate for utility workers from exposures to maximum detected concentrations of PCP, dioxin, and arsenic in subsurface soil is similar to the total cancer risk of 1E-05 calculated in the previous memo and is within EPA's acceptable risk range of 10⁻⁴ to 10⁻⁶. However, the non-cancer total hazard index of 5.0 would exceed the acceptable hazard index level of 1, mainly due to dioxin in soil.

Risk evaluation for construction worker

The 2007 memo stated that a construction worker scenario is unlikely because it is based on the assumption that the railroad tracks will be removed in the future. However, risks are still estimated for a construction worker. Similar to the 2007 memo, a construction worker is assumed to be exposed to contaminated soil on the railroad right-of-way for about 180 days or 6 months, approximately 3 times longer than assumed for the utility worker. Thus, the total risks for construction worker would be 3 times greater than those estimated for utility worker presented in Table 3 above. These risk estimates are shown in Table 4 below.

Table 4 – Construction Worker Estimated Cancer Risk and Hazard Index

Subsurface Soil Contaminant	Maximum Concentration in Subsurface Soil (mg/kg)	Cancer Risk for Construction Worker	Hazard Index for Construction Worker
Pentachlorophenol	152	2E-06	0.06
Dioxin	6.76E-03	2E-05	14.1
Arsenic	309	6E-06	0.9
Total		3E-05	15.0

Table 4 shows that the total cancer risk estimate of 3E-05 for construction worker scenario is within EPA's acceptable risk range of 10-4 to 10-6. However, the non-cancer total hazard index of 15.0 would exceed the acceptable hazard index level of 1, mainly due to dioxin in soil.

Conclusion

The potential estimated non-cancer hazard to a utility worker, the most likely scenario in the railroad right-of-way, exceeds the acceptable level of 1 for hazard index based on the assumption that concentrations bordering the tracks are representative of this exposure. The potential estimated non-cancer hazard to a construction worker is higher, but the construction worker scenario is considered unlikely to occur at the railroad right-of-way.

APPENDIX G

ARARs REVIEW TABLES

Chemical-Specific ARARs				
Media/Authority	Requirements and Status	Requirement Synopsis	Action to Attain ARAR	Five Year Review
All Media				
Federal Criteria, Advisories, and Guidance	American Conference of Governmental Industrial Hygienists Threshold Limit Values (TLVs) ROD Status: To Be Considered (TBC) 5-Yr Status: Not ARAR	Health-based guidelines for exposure limit represented in terms of exposure over a workday (8 hours) or a work week (40 hours). These standards were issued as consensus standards for controlling air quality in work place environments.	TLVs will be used for assessing site inhalation risks for site remediation workers.	These guidelines were To Be Considered (TBC) for air monitoring during active phases of the remedial construction. No further land disturbing activities are anticipated, thus these guidelines are no longer ARAR unless further land disturbing activities are conducted. This ARAR is more appropriate as an Action-Specific ARAR.
	EPA Risk Reference Dose (RfDs) and EPA Carcinogen Assessment Group Potency Factors ROD Status: TBC 5-Yr Status: TBC	Reference dose is an estimate of a daily oral exposure to human populations that is likely to be without an appreciable risk of non-cancer effects. The Cancer Group Potency factors are used as qualitative weight-of-evidence judgment as to the likelihood of a chemical being a carcinogen.	Risks due to carcinogens and noncarcinogens with EPA RfDs and carcinogens with Cancer Potency factors were used to develop target cleanup levels and evaluate remedial alternatives.	These values were used in the risk assessment and development of soil cleanup levels and any future risk calculations are expected to use these values.
	EPA Carcinogenicity Slope Factors ROD Status: TBC 5-Yr Status: TBC	Slope factors are developed by EPA from health effects assessments. Carcinogenic effects present the most up-to-date information on cancer risk.	Risks due to carcinogens as assessed with slope factors were used to develop target cleanup levels and evaluate remedial alternatives.	These values were used in the risk assessment and development of soil cleanup levels and any future risk calculations are expected to use these values.
	OSWER Draft Guidance for Evaluating the Vapor Intrusion to Indoor Air Pathway from Groundwater and Soils ROD Status: TBC 5-Yr Status: TBC	This draft guidance establishes a methodology for assessing indoor air risks to human health.	Risks associated with future residential exposure to indoor air were evaluated consistent with this guidance.	Vapor intrusion was evaluated in the risk assessment consistent with the draft guidance. This guidance has not yet been finalized. Once finalized, potential impacts related to the institutional controls (not yet implemented) should be evaluated.
	US EPA Guidance: Approach for Addressing Dioxin in Soil at CERCLA and RCRA Sites ROD Status: TBC 5-Yr Status: Not ARAR	Recommends PRG's or points of departure for cleanup levels for dioxin in soils and sediments at CERCLA sites. Recommended cleanup levels are based on direct exposure pathway.	This guidance was used in setting cleanup levels for dioxin-contaminated soils.	The cleanup level for dioxin in soil was based on the recommended level in this 1998 EPA guidance. Since the 2005 ROD, an RfD was developed for dioxin and is now the recommended toxicity value "to be considered" in developing dioxin cleanup levels under CERCLA. Refer to the response to "Question B" in the five-year review text for the discussion of the potential impacts of the change.

Chemical-Specific ARARs				
Media/Authority	Requirements and Status	Requirement Synopsis	Action to Attain ARAR	Five Year Review
Other Guidance	<p>Ontario Ministry of Environment and Energy (OMEE) Lowest and Severe Effect Levels (LELs and SELs) for Freshwater Sediments (Persaud <i>et al.</i>, 1993)</p> <p>ROD Status: TBC 5-Yr Status: TBC</p>	The LEL value is the concentration at which the majority of the sediment-dwelling organisms are not affected.	The LEL value was used for selecting Chemicals of Potential Concern and for characterizing ecological effects for all alternatives and to assist in setting soil/sediment cleanup levels.	These values were used as screening values for the baseline ecological risk assessment and any future risk calculations are expected to use these values. Note that no cleanup levels were developed for sediment and these sediment criteria were not used in setting soil cleanup levels.

Location-Specific ARARs				
Media/Authority	Requirements	Requirement Synopsis	Action to Attain ARAR	Five-Year Review
All Media				
Federal Regulatory Requirements	Executive Order 11990; "Protection of Wetlands" (40 CFR Part 6, Appendix A) ROD Status: Applicable 5-Yr Status: Applicable	Under this requirement, no activity that adversely affects a wetland shall be permitted if a practicable alternative with lesser effects is available. Action to avoid, whenever possible, the long-and short-term impacts on wetlands and to preserve and enhance wetlands. If activity takes place, impacts must be minimized to the maximum extent.	Wetlands have been identified on the site and excavation, consolidation and installation of monitoring wells occur in or around wetlands. Because high levels of contamination exist in or near wetlands areas, there is no practicable alternative to excavating or consolidating in these areas. All practicable means will be used to minimize harm to the wetlands. Wetlands disturbed by remedial activities will be mitigated, restored, or preserved. The Proposed Plan will solicit specific comments on this work.	Buffer zone adjacent to the Rumford River was impacted by the remedial construction and subsequently restored by grading and replanting with native species, followed by a one-year monitoring period that resulted in some additional replanting in 2011. This requirement remains applicable to any future activities, such as installation of monitoring wells, if determined to be needed in or around wetlands.
	Fish and Wildlife Coordination Act (16 U.S.C. §661 et seq.); Fish and wildlife protection (40 CFR §6.302(g)) ROD Status: Applicable 5-Yr Status: Not ARAR	Any modification of a body of water requires consultation with the U.S. Fish and Wildlife Services and the appropriate state wildlife agency to develop measures to prevent, mitigate or compensate for losses of fish and wildlife.	The Site includes streams and rivers. These alternatives may require discharge of treated water into Rumford River resulting from dewatering activities. Consultation will be undertaken with appropriate agencies in this case.	During remedial construction, no discharge of treated water occurred into the Rumford River. Some treated water was discharged to the ground on-site.
	Executive Order 11988; "Floodplain Management" (40 CFR Part 6, Appendix A) ROD Status: Applicable 5-Yr Status: Applicable	Actions will avoid, whenever possible, the long- and short-term impacts associated with the occupancy and modifications of floodplains development, wherever there is a practical alternative. Promotes the preservation and restoration of floodplains so that their natural and beneficial value can be realized.	The Site includes areas defined to be within the 100-year floodplain. These alternatives all involve installation of monitoring wells, some include excavation, and/or consolidation and cap construction possibly in the floodplain areas. All practicable means will be followed to minimize harm and avoid adverse effects as much as possible. Actions will be taken to restore and preserve the natural and beneficial values of the floodplain.	This requirement would be applicable to any future activities, such as installation of monitoring wells, if determined to be needed within the 100-year floodplain.

Location-Specific ARARs				
Media/Authority	Requirements	Requirement Synopsis	Action to Attain ARAR	Five-Year Review
Federal Regulatory Requirements (continued)	Standards for Owners and Operators Of RCRA Hazardous Waste Treatment, Storage, and Disposal Facilities, 40 C.F.R. Part 264.18(b)k General Facility Standards, Subpart B ROD Status: Applicable 5-Yr Status: Not ARAR	Requires that hazardous waste treatment, storage, or disposal facilities within a 100-year floodplain must be designed, constructed, operated, and maintained to prevent washout unless an alternative demonstration is made to the Regional Administrator.	The Site includes areas defined to be within the 100-year floodplain. Consolidation and capping will be designed, constructed and maintained to prevent washout by a 100-year flood.	The on-site consolidation area that was originally envisioned in the 2005 ROD for arsenic and pentachlorophenol contaminated soils from the Mansfield parcel was not constructed and these soils were disposed off-site. A low permeability asphalt cover was placed across the majority of the Foxboro parcel.
	Endangered Species Act, 16 U.S.C. 1531 et seq.; 50 C.F.R. Parts 17.11-12 ROD Status: Applicable 5-Yr Status: Applicable	Requires site action to be conducted in a manner that avoids harming threatened or endangered species or their habitat.	Transient bald eagles have been sited. Work will be conducted to avoid harming the bald eagle or its habitat.	The requirement remains applicable.
State Regulatory Requirements	Wetlands Protection Act (Mass. Gen. Laws ch. 131, §40); Wetlands Protection Regulations (310 CMR §10.00) ROD Status: Applicable 5-Yr Status: Applicable	Sets performance standards for dredging, filling, altering of inland wetlands and within 100 feet of a wetland. The requirement also defines wetlands based on vegetation type and requires that effects on wetlands be mitigated. Resource areas at the site covered by the regulations include banks, bordering vegetated wetlands, land under bodies of water, land subject to flooding, riverfront, and estimated habitats of rare wildlife. Under this requirement available alternatives must be considered that minimize the extent of adverse impacts and mitigation including restoration and/or replication are required.	Wetlands have been identified on the site and excavation, consolidation and installation of monitoring wells occur in or around wetlands and the 100 foot buffer zone. Because high levels of contamination exist in or near wetlands areas, there is no practicable alternative to excavating or consolidating in these areas. All practicable means will be used to minimize harm to the wetlands including erosion and sedimentations controls and stormwater management. Wetlands disturbed by remedial activities will be mitigated, restored, or preserved.	Buffer zone adjacent to the Rumford River was impacted by the remedial construction and subsequently restored by grading and replanting with native species, followed by a one-year monitoring period that resulted in some additional replanting in 2011. This requirement remains applicable to any future activities, such as installation of monitoring wells, if determined to be needed in or around wetlands.

Location-Specific ARARs				
Media/Authority	Requirements	Requirement Synopsis	Action to Attain ARAR	Five-Year Review
	<p>Massachusetts Endangered Species Act (Mass. Gen. Laws ch. 131 §40); Massachusetts Endangered Species Act Regulations, Part III: Alteration of Significant Habitat (321 CMR §§10.30-10.43)</p> <p>ROD Status: Applicable 5-Yr Status: Applicable</p>	<p>The MESA establishes State's list of threatened and endangered species and species of special concern. Habitat of such species is protected by the regulations promulgated under the MA Wetlands Protection Act.</p>	<p>The Site is noted as being near the habitat of "species of special concern" (see letter in Appendix B); further review will be conducted to determine applicability of this requirement. Should endangered or threatened species or species of special concern be determined to be present at the site, the substantive requirements of this regulation will be met.</p>	<p>The requirement remains applicable.</p>
Federal Criteria, Advisories and Guidance	<p>Policy on Floodplains and Wetland Assessments for CERCLA Actions (EPA OSWER, 8/8/1985)</p> <p>ROD Status: TBC 5-Yr Status: TBC</p>	<p>Floodplain and wetlands assessments must be incorporated into analysis conducted during planning of remedial action; public participation requirements must also be met.</p> <p>Restates requirement that remedial action may only be located in wetlands if no practicable alternative exists. Potential harm or adverse effects to wetlands or floodplains must be minimized and/or mitigated as required by law/regulation</p>	<p>Floodplain and wetlands assessments and associated considerations were incorporated into RI/FS process.</p> <p>Public participation requirements were met through Proposed Plan.</p> <p>Substantive requirements for decision-making will be met when selecting and designing remedy.</p>	<p>The substantive requirements of this policy were met.</p>

Action-Specific ARARs				
Media/Authority	Requirements	Requirement Synopsis	Action to be Taken to Attain ARAR	Five-Year Review
Surface Water, Wetlands				
Federal Regulatory Requirements	Clean Water Act (33 U.S.C. §1251 <i>et seq.</i>); Section 404(b)(1) Guidelines for Specification of Disposal Sites for Dredged or Fill Material (40 CFR Part 230, 231 and 33 CFR Parts 320-323) ROD Status: Applicable 5-Yr Status: Applicable	Under this requirement, no activity that adversely affects a wetland shall be permitted if a practicable alternative with lesser effects is available. If activity takes place, impacts must be minimized to the maximum extent. Controls discharges of dredged or fill material to protect aquatic ecosystems.	Wetlands have been identified on the site coincident with contamination. Excavation, consolidation, and installation of monitoring wells will occur in and around the site wetlands. These actions will be designed to minimize adverse effects and to preserve, mitigate, and restore disturbed areas.	Buffer zone adjacent to the Rumford River was impacted by the remedial construction and subsequently restored by grading and replanting with native species, followed by a one-year monitoring period that resulted in some additional replanting in 2011. This requirement remains applicable to any future activities, such as installation of monitoring wells, if determined to be needed in or around wetlands.
	Rivers and Harbors Act of 1899 (33 U.S.C. §401 <i>et seq.</i>); (33 CFR Part 320) ROD Status: Applicable 5-Yr Status: Not ARAR	Protects navigable rivers from unauthorized discharges or from unauthorized obstruction or alteration.	Discharges to the Rumford River resulting from dewatering activities, if any, will occur via a piping system that will not obstruction or alter the River.	During remedial construction, no discharge of treated water occurred into the Rumford River. Some treated water was discharged to the ground on-site.
	Clean Water Act, Section 402, National Pollutant Discharge Elimination System (NPDES), 33 USC 1342 (4- CFR 122-125, 131) ROD Status: Applicable 5-Yr Status: Not ARAR	These standards govern discharge of water into surface waters.	Groundwater resulting from dewatering activities, if any, will be treated to the required standards before discharge to the Rumford River.	During remedial construction, no discharge of treated water occurred into the Rumford River. Some treated water was discharged to the ground on-site.
State Regulatory Requirements	Massachusetts Surface Water Quality Standards – Vernal Pools, 314 CMR §4.06(1)(d)(11) and 314 CMR 9.08 (variance) ROD Status: Relevant and Appropriate 5-Yr Status: Relevant and Appropriate	Prohibits discharge of dredged or fill material to a vernal pool certified by the Massachusetts of Division of Fisheries and Wildlife, unless a variance is granted under 314 CMR <u>9.08</u> .(11) – Vernal Pools	Wetland features exist, which, although not officially classified, may be characteristic of vernal pools. If further studies indicate an ecological risk exists, it will be considered an overriding public interest to address the risk. Dredging and/or filling activities will be conducted to avoid, minimize and mitigate adverse effects and restoration/replication will be conducted.	Vernal pools were not filled as part of the remedial construction. This requirement remains relevant and appropriate to any future activities, such as installation of monitoring wells, if determined to be needed in or around vernal pools.

Action-Specific ARARs				
Media/Authority	Requirements	Requirement Synopsis	Action to be Taken to Attain ARAR	Five-Year Review
	Surface Water Quality Standards (314 CMR 4.00) ROD Status: Applicable 5-Yr Status: Applicable	Surface water in the vicinity of the Site are classified as Class B and designated as habitat for fish, other aquatic and wildlife, and for primary and secondary contact recreation. The state surface water minimum criteria for Class B waters are consistent with federal AWQC.	Surface water standards will be used as performance criteria to measure the effectiveness of the Site remedy at preventing degradation of surface water below these standards.	AWQC for pentachlorophenol, arsenic, and chromium were used in calculating onsite groundwater performance standards for protection of surface water. The AWQC for these compounds have not changed since the ROD. Groundwater monitoring results are compared to these performance standards.
	401 Water Quality Certification for Discharge of Dredged or Fill Material, 314 CMR 9.00 ROD Status: Applicable 5-Yr Status: Applicable	Under this requirement, no activity that adversely affects a wetland shall be permitted if a practicable alternative with lesser effects is available. If activity takes place, adverse impacts must be minimized. Controls discharges of dredged or fill material to protect aquatic ecosystems.	Wetlands have been identified on the site coincident with contamination. Excavation, consolidation, and installation of monitoring wells will occur in and around site wetlands. These actions will be designed to minimize adverse effects and to preserve, mitigate, and restore disturbed areas.	Buffer zone adjacent to the Rumford River was impacted by the remedial construction and subsequently restored by grading and replanting with native species, followed by a one-year monitoring period that resulted in some additional replanting in 2011. This requirement remains applicable to any future activities, such as installation of monitoring wells, if determined to be needed in or around wetlands.
	Massachusetts DEP Surface Water Discharge Permit Program (314 CMR 3) ROD Status: Applicable 5-Yr Status: Not ARAR	These standards govern discharge of water into surface waters.	Groundwater resulting from dewatering activities, if any, will be treated to the required standards before discharge to the Rumford River.	During remedial construction, no discharge of treated water occurred into the Rumford River. Some treated water was discharged to the ground on-site.
Groundwater				
Federal Regulatory Requirements	Federal Safe Drinking Water Act – Maximum Contaminant Levels (MCLs) and non-zero MCLs 40 CFR 141 ROD Status: Relevant and Appropriate 5-Yr Status: Relevant and Appropriate	These levels regulate the concentration of contaminants in public drinking water supplies but may also be considered appropriate for groundwater aquifers potentially used for drinking water.	These standards will be used during groundwater monitoring to measure the performance of the remedy to ensure that groundwater migrating off the Site does not exceed MCLs and non-zero MCLs.	These standards remain relevant and appropriate. The MCLs for pentachlorophenol, arsenic, and chromium are used as performance standards for long-term monitoring of groundwater beyond the compliance boundary.

Action-Specific ARARs				
Media/Authority	Requirements	Requirement Synopsis	Action to be Taken to Attain ARAR	Five-Year Review
	Resource Conservation and Recovery Act (42 U.S.C. §6901 <i>et seq.</i>);(40 CFR 264.94 and 95) Subpart F ROD Status: Relevant and Appropriate 5-Yr Status: Relevant and Appropriate	Establishes maximum concentration limits for RCRA groundwater monitoring and response requirements for solid waste management units. Standards for 14 toxic compounds have been adopted as part of RCRA groundwater protection standards.	These standards will be used during groundwater monitoring to measure the performance of the remedy to ensure that groundwater migrating off the Site does not exceed RCRA groundwater concentration levels for Site contaminants. Compliance boundary is south of the Rumford River and will be established more specifically during remedial design.	These requirements remain relevant and appropriate. Arsenic and chromium groundwater monitoring results for wells located beyond the compliance boundary should be compared to these standards. Note that the limit for arsenic (0.05 mg/l) is higher than the MCL (0.01 mg/l); however, the limit from chromium (0.05 mg/l) is lower than the MCL (0.1 mg/l). Long-term monitoring results for 2011, 2012, and 2013 met these standards.
	Resource Conservation and Recovery Act (42 U.S.C. §6901 <i>et seq.</i>);(40 CFR 264.100) Subpart F ROD Status: Relevant and Appropriate 5-Yr Status: Relevant and Appropriate	Requires that corrective action be taken in the event groundwater is migrating offsite in excess of RCRA groundwater concentration levels set out in 40 CFR 264.94.	Corrective action will be taken should offsite monitoring wells demonstrate that groundwater is migrating offsite in excess of RCRA groundwater concentration levels.	These requirements remain relevant and appropriate.
State Regulatory Requirements	Massachusetts Ground Water Quality Standards (314 CMR §6.00) ROD Status: Applicable 5-Yr Status: Not ARAR	Establishes groundwater quality criteria necessary to sustain the designated uses, and regulations necessary to achieve the designated uses or maintain the existing groundwater quality. Groundwater at the site is classified as Class II and III, non-potable uses.	These standards will be used during groundwater monitoring to measure the performance of the remedy to ensure that groundwater migrating off the Site does not exceed MCLs and non-zero MCLs that are more stringent than federal standards for Site contaminants.	These regulations were rescinded after the 2005 ROD and are no longer applicable. Federal SDWA MCLs for pentachlorophenol, arsenic, and chromium are used as performance standards for long-term monitoring of groundwater beyond the compliance boundary.
Air				
Federal Regulatory Requirements	National Emission Standards for Hazardous Air Pollutants (NESHAPs) 40 CFR Part 61 Subparts H&I ROD Status: Relevant and Appropriate 5-Yr Status: Not ARAR	Regulates air emissions of VOCs from regulated source categories.	VOC emission levels will be met during soil treatment processes through carbon filtering and/or other engineering controls.	No soil treatment was performed during remedial construction and no activities are anticipated that would trigger this requirement.

Action-Specific ARARs				
Media/Authority	Requirements	Requirement Synopsis	Action to be Taken to Attain ARAR	Five-Year Review
	RCRA Air Emissions Standards for Process Vents (40 CFR Part 264, Subpart AA) ROD Status: Relevant and Appropriate if threshold concentrations are met 5-Yr Status: Not ARAR	Contains air pollutant emission standards applying to solvent extraction and air stripping facilities that treat RCRA wastes with total organics concentrations of 10 parts per million by weight or greater.	Treatment components treating wastes with regulated levels of organic constituents will be designed to meet the criteria set forth in this subpart if threshold levels are met.	No treatment was performed during remedial construction and no activities are anticipated that would trigger this requirement.
	RCRA Air Emissions Standards for Equipment Leaks (40 CFR Part 264, Subpart BB) ROD Status: Relevant and Appropriate if treatment involves groundwater with organics at concentrations of at least 10% by weight 5-Yr Status: Not ARAR	Sets emission standards for equipment that contains or contacts RCRA wastes with organic concentrations of at least 10% by weight.	Treatment components treating wastes with regulated levels of VOCs will be designed to meet the criteria set forth in this subpart if threshold levels are met.	No treatment was performed during remedial construction and no activities are anticipated that would trigger this requirement.
	RCRA Air Emissions Standards for Tanks and containers (40 CFR Part 264, Subpart CC) ROD Status: Relevant and Appropriate if threshold levels are met 5-Yr Status: Not ARAR	Requires specific organic emissions controls on tanks and containers having VOC concentrations equal to or greater than 500 parts per million by weight.	Treatment facility components treating wastes with regulated levels of VOCs will be designed to meet the criteria set forth in this subpart if threshold levels are met.	No treatment was performed during remedial construction and no activities are anticipated that would trigger this requirement.
State Regulatory Requirements	Ambient Air Quality Standards (310 CMR 6.00) ROD Status: Applicable 5-Yr Status: Not ARAR	Sets primary and secondary standards for emissions of Sulfur Oxides, particulate matter, CO, ozone, Nitrogen Dioxide, and Lead.	Remedies will be designed, constructed, and operated in accordance with these rules. No air emissions from remedial treatment will cause ambient air quality standards to be exceeded. Dust standards will be complied with during any and all excavation of materials at the Site.	No treatment was performed during remedial construction. A Perimeter Air Monitoring and Emissions Control Plan was developed and air monitoring for fugitive dust, VOCs, and hydrogen sulfide was performed during active phases of the remedial construction. No further land disturbing activities are anticipated, thus these requirements are no longer ARAR unless further land disturbing activities are conducted.

Action-Specific ARARs				
Media/Authority	Requirements	Requirement Synopsis	Action to be Taken to Attain ARAR	Five-Year Review
	Massachusetts DEP Air Pollution Control Regulations (310 CMR 7.00) ROD Status: Applicable 5-Yr Status: Not ARAR	Regulates dust, particulates and fugitive emissions. Establishes emissions limitations for various processes and regions within the state.	Excavation and treatment processes will be designed, constructed, and operated in accordance with these rules. Air monitoring will be conducted to ensure levels are met.	No treatment was performed during remedial construction. A Perimeter Air Monitoring and Emissions Control Plan was developed and air monitoring for fugitive dust, VOCs, and hydrogen sulfide was performed during active phases of the remedial construction. No further land disturbing activities are anticipated, thus these requirements are no longer ARAR unless further land disturbing activities are conducted.
Massachusetts Criteria, Advisories, and Guidance	Massachusetts Threshold Effects Exposure Levels (TELs) and Allowable Ambient Limits (AALs) for Air (December 1995) ROD Status: To Be Considered 5-Yr Status: Not ARAR	Establishes exposure concentrations for air contaminants developed and recommended by the Office of Research and Standards to protect public health.	Evaluation of air emissions will consider AALs and TELs.	A Perimeter Air Monitoring and Emissions Control Plan was developed and air monitoring for fugitive dust, VOCs, and hydrogen sulfide was performed during active phases of the remedial construction. No further land disturbing activities are anticipated, thus these guidelines are no longer ARAR unless further land disturbing activities are conducted.
Soil				
Federal Regulatory Requirements RCRA program has been delegated to Massachusetts; therefore, only State references appear as ARARs unless particular provision not contained in State program.				
State Regulatory Requirements	RCRA Hazardous Waste Management – Identification and Listing of Hazardous Waste (310 CMR 30.100) ROD Status: Applicable 5-Yr Status: Not ARAR	Establishes standards for identifying and listing hazardous waste.	Testing as appropriate will assess whether hazardous wastes are present in excavated soil, sediments (if any) and groundwater generated during remedial activities.	This ARAR has been met. Pre-excavation waste characterization was performed on the contaminated soils to be disposed off-site and the soil was determined to be non-characteristic under RCRA. Some wastes generated during remedial construction, including liquid and solid contents of certain USTs, were characterized and disposed as RCRA characteristic waste.

Action-Specific ARARs				
Media/Authority	Requirements	Requirement Synopsis	Action to be Taken to Attain ARAR	Five-Year Review
	Hazardous Waste Management – Requirements for Generators of Hazardous Waste (310 CMR 30.300) ROD Status: Applicable to any action that generates hazardous waste 5-Yr Status: Not ARAR	Generator requirements outline waste characterization, management of containers, packaging, labeling, and manifesting. Generator requirements apply to contaminated substances meeting the definition of hazardous under 310 CMR 100.	Waste generated during excavation, treatment processes and well drilling that are characteristic waste will be managed in accordance with the substantive requirements of this regulation.	This ARAR has been met. RCRA characteristic wastes generated during remedial construction were characterized and managed in accordance with these requirements.
	Hazardous Waste Management – Landfill Closure and Post Closure Care (310 CMR, 30.633(1)(a-d), 2(a), (d), (e)) ROD Status: Relevant and Appropriate 5-Yr Status: Relevant and Appropriate	Establishes performance standards for low permeability covers and for post closure care and for groundwater monitoring.	Consolidated waste will be covered on-site with a low permeability cover that meets these standards. Post-closure care of cover will meet these standards.	This ARAR remains relevant and appropriate and is being complied with. An asphalt parking lot was constructed on the Foxboro parcel to provide a low permeability cover over contaminated soils. Long-term inspection and maintenance of the asphalt cover as well as long-term groundwater monitoring are being conducted in accordance with the O&M Manual (EPA Region 1, September 2011).
	Hazardous Waste Management – Closure and Post Closure (310 CMR 30.582, 30.585, 30.592) ROD Status: Relevant and Appropriate 5-Yr Status: Relevant and Appropriate	Establishes performance standards for closure and post closure care and groundwater monitoring	All equipment, structures, and soil will be properly decontaminated and disposed of during the remedial action. Post closure care will meet substantive standards as determined by EPA.	This ARAR remains relevant and appropriate. Long-term inspection and maintenance of the asphalt cover as well as long-term groundwater monitoring are being conducted in accordance with the O&M Manual (EPA Region 1, September 2011).
	Hazardous Waste Management – General Requirements for ignitable, reactive, or incompatible waste (310 CMR 30.560) ROD Status: Applicable 5-Yr Status: Not ARAR	General requirement for handling hazardous waste	Hazardous wastes will be handled in accordance with these requirements.	No ignitable, reactive, or incompatible wastes were encountered during remedial construction.

Action-Specific ARARs				
Media/Authority	Requirements	Requirement Synopsis	Action to be Taken to Attain ARAR	Five-Year Review
	Hazardous Waste Management – Tanks (310 CMR 30.343) ROD Status: Applicable 5-Yr Status: Not ARAR	Establishes management procedures tanks uses to store hazardous waste.	Any hazardous waste stored in containers will meet substantive requirements of this subpart, including condition and management of containers.	Hazardous wastes were not stored in tanks during remedial construction.
	Hazardous Waste Management – Containers (310 CMR 30.342) ROD Status: Applicable 5-Yr Status: Not ARAR	Specifies conditions under which hazardous waste may be stored in containers.	Any hazardous waste stored in containers will meet substantive requirements of this subpart, including condition and management of containers.	Hazardous wastes were not stored in containers during remedial construction.
Federal Criteria, Advisories and Guidance	Revised Alternative Cap Design Guidance Proposed for Unlined, Hazardous Waste Landfills in the EPA Region 1 (EPA OSRR 2/5/01). ROD Status: TBC 5-Yr Status: Not TBC USEPA Technical Guidance Document: Final Covers on Hazardous Waste Landfills and Surface Impoundments (EPA/530-SW-89-047) ROD Status: TBC 5-Yr Status: Not TBC	Provides guidance for landfill cap design for unlined, hazardous waste landfills at Superfund landfill sites in EPA Region 1. Presents technical specifications for the design of multi-barrier covers for landfills at which hazardous wastes were disposed.	Guidance will be considered when designing low permeability cover for consolidated material on-site. Technical specifications in guidance will be considered when designing low permeability cover for consolidated material on-site.	These guidance documents would have been considered during design the asphalt cover on the Foxboro parcel, but are no longer to be considered for the on-going operation, maintenance, and monitoring activities.