Public Input on General Electric's Road Assessment Work Plan, dated June 26, 2025

June 2025 - July 2025

Public Input ended on July 30, 2025



CITY OF PITTSFIELD

Department of Public Works – Engineering Division

70 Allen Street Pittsfield, MA (413) 499-9327

To: U.S. Environmental Protection Agency, New England Region

From: The City of Pittsfield Department of Public Works

Date: July 30, 2025

Re: Housatonic Rest of River (GECD850) Road Assessment Work Plan

Comments on the Road Assessment Work Plan

Below are the City's comments pertaining to the contents in the road assessment work plan developed by Arcadis for General Electric Company dated June 2025.

- 1. In the interest of transparency, The City of Pittsfield is making it know to the U.S. Environmental Protection Agency and General Electric Company that the city has and is continuing contracted services with citylogix (f/k/a StreetScan) for road data collection which includes pavement condition indexes for city streets.
- 2. Specifically, what is being included under "Infrastructure" for the assessments (bridges, culverts, utility structures, etc.)?
 - a. The city would like to be present for the inspection of the small culverts on Holmes Road and East New Lenox Road.
- 3. The Massachusetts Department of Transportation owns the railroad bridge on Holmes Road in Pittsfield; they should receive the pre and post condition assessment for that structure.
- 4. Will preconstruction assessments be delayed or advanced if there are changes to the timing of a construction phase? The schedule included in the report is not rigid, but the anticipated schedule.

Comments on Condition of Infrastructure in Pittsfield

- 1. Pomeroy Avenue (Preston to Holmes Road)
 - a. Single segment PCI 84
- 2. Pomeroy Avenue City Bridge P-10-023 (Between Preston Avenue and Holmes Road)
 - a. Last inspected by DOT on 10-24-2023
 - b. Deck Condition: Good
 - c. Superstructure: Good
 - d. Substructure: Good
 - e. Channel and Channel Protection: Good
- 3. Holmes Road (Pomeroy to Lenox TL)
 - a. Pomeroy to R.R. Bridge ~ 0.7 miles
 - i. Paved in 2024
 - b. From R.R. Bridge to Lenox TL ~ 1.1 miles
 - i. PCI range 50-70
- 4. Utility Drive
 - a. Not included in Road Data Collection
 - b. Poor condition with deep ruts along the length
 - c. Private rail crossing, owned by the city, has view obscured by wooden ties looking north and overgrowth to the south.
 - d. Road subbase is potentially unsuitable for increase in heavy construction vehicles.
 - i. Based on record drawings road is 2.5" 3" HMA, 3" crushed stone base, and 12" gravel subbase, over sandy loam native soils.
- 5. East New Lenox Road
 - a. Crack and fog sealed in 2024
 - b. PCI ranges 80-95
- 6. P-10-055 Sackett Brook Culvert
 - a. Last inspected 02-28-2024
 - b. New construction completed in Summer 2024
 - i. Excellent condition
- 7. Small drainage culverts
 - a. 3 Holmes Road
 - b. 3 East New Lenox Road

2-DIST B.I.N. **01 01 R**

STRUCTURES INSPECTION FIELD REPORT ROUTINE INSPECTION

BR. DEPT. NO. **P-10-023**

CITY/TOWN PITTSFIELD			8ST	RUCTURE NO. P10023-01	R-MU	N-NBI			. POINT 0.000	A:OPEN				P. DATE 2023
07-FACILITY CARRIED HWY POMEROY A	WE		•	MEMORIAL NAMI	E/LOCAL	NAME		1	R BUILT 1936	106-YR REBUILT 1993	YR R		OOO	ON 106)
06-FEATURES INTERSECTED				26-FUNCTIONAL (CLASS		DIST. B	RIDGE	INSPECTI	ON ENGINEER	L. A. I	Briggs		
WATER E BR HOU	SATO	NIC R		Urban Collec	tor			A	1. B.	161				
43-STRUCTURE TYPE 302: Steel Stringe	r/Gird	ler		22-OWNER City/ Municipal Highway A		lunicipal			R. R. Mance	ari Cari				
107-DECK TYPE 1 : Concrete Cast-i	n-Pla	се		weather Sunny	TEMP. (a	air) 1°C		MEMB	ERS					
ITEM 58	_		ITE	M 59			1		ITEM	60				
DECK	7	DEF		ERSTRUCTUI	RE	7	DE			RUCTURE		7		DEF
1.Wearing Surface	7	-	1.Stri	ngers		N	-		1. Abutı	nents	Dive	Cur	7	
2.Deck Condition	7	-	2.Flo	orbeams		N	-		a. Pedes		N	N		-
3.Stay in place forms	8	-	3.Flo	or System Braci	ng	N	-		b. Bridge c. Backw		N	7		- M-P
4.Curbs	7	-	4.Gird	ders or Beams		7	-		d. Breast		N	7		-
5.Median	N	_	5.Tru	sses - General		N	-		e. Wingw		N	7		-
6.Sidewalks	7	_	а.	Upper Chords		N	-		f. Slope g. Pointir	Paving/Rip-Rap	N	8 N	-	-
			b. 1	Lower Chords		N	-		h. Footin		N	Н		-
7. Parapets	N	-	c.	Web Members		N	-		i. Piles		N	Н		-
8.Railing	6	-	d. I	Lateral Bracing		N	-		j. Scour k. Settler	nont	N	8 7	-	-
9.Anti Missile Fence	N	-	е.	Sway Bracings		N	-		I.	nent	N	N	-	-
10.Drainage System	N	-	f.	Portals		N	-		m.		N	N		-
11.Lighting Standards	N	-	a. I	End Posts		N	-		2. Piers	or Bents			N	
12.Utilities	6	-		& Hangers		N	1 -		a. Pedesi b. Caps	tals	N	N		-
13.Deck Joints	6	-	7.Cor	nn Plt's, Gussets	s & Ang	les 8	╢-		c. Colum	ns	N	N		-
14.	N	_	8.Cov	ver Plates		8	╢.		d. Stems	/Webs/Pierwalls	N	N		-
15.			9.Bea	ring Devices		8	╫-		e. Pointin	•	N N	N		-
	N	-	10. Di	aphragms/Cross	s Frame	es 8	╢-		f. Footin g. Piles	9	N	N	-	
16.	N	-		vets & Bolts		8	╢-		h. Scour		N	N		-
ı	N	s	12. W			7	-		i. Settler	nent	N	N	-	-
CURB REVEAL (In millimeters)	90	160		ends ember Alignmen	.+	8	╟╌		j. k.		N	N		-
(III IIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIII				int/Coating		7	├		3. Pile F	Bents			N	_
APPROACHES		DEF		inivCoating		N N	-		a. Pile Ca	aps	N	N		-
a. Appr. Pavement Condition	7	-	15.			- 14	<u> </u>		b. Piles		N	N		-
b. Appr. Roadway Settlement	8	-	Year	Painted	19	93				nal Bracing Intal Bracing	N	N N		-
c. Appr. Sidewalk Settlement	6	M-P	COLLI	ISION DAMAGE:	Please e	xplain			e. Faster		N	N		-
d.	N	-	None	e(X) Minor()	Moderat	te () Se	evere ()	UNDERM	INING (Y/N) If YE	ES ple	ase e	xplain	N
OVERHEAD SIGNS (Attached to bridge)	(Y/N)	N	None	e(X) Minor()	Moderat	te () Se	vere ()		ON DAMAGE:	oderat	e () Sev	ere ()
	+	DEF				te () Se	evere ()	-	Please explain		-		. ,
a. Condition of Welds	N	-	<u> </u>					\dashv	1	Minor () Mo	oderat	e () Sev	ere ()
b. Condition of Bolts	N	-	Any F	racture Critical	Membe	r: (Y/N)	N		I-60 (Dive	e Report):	<i>I</i> -60) (This	Repor	t): 7
c. Condition of Signs	N	_	Any C	Cracks: (Y/N)	N				028 11/1	W (DIVE) Insp		በበ/	00/00	000
									33D-U/V	v (DIVE) IIISP		301	30/00	
V-UNIKNO				NOT ADDI IO										

CITY/	/TOW	N	_		B.I.1	N.	BR. DEPT. NO. 8.	STRU	JCTUI	RE NO.		INSPECTION	ON D	ATE
	SFIEL				011		1			IR-MUN-NE	ВІ	OCT 2		
TI NI	EM 61		—	—		TET	TEM 36 TRAFFIC SAF	FTY			ACCESSI			N/P)
				,	7			36	COND	DEF	ACCESSI	DILIT	Needed	,
	INNE.	EL & EL PROTECTION	. A .7	•		A. !	. Bridge Railing	0	6	-	Lift Bucket		N	N
CHA	.IVIVE.	LPKUIECIIO	.V			B	Transitions	0	8	-	Ladder	•	N	N
l			Dive	Cur	DEF	, <u> C.</u> /	. Approach Guardrail	0	7	-	Boat		N	N
1.Ch	annel	Scour	N	7		<u> </u> <u>D.</u> /	. Approach Guardrail Ends	0	8		Waders		N	N
2.Em	ıbankı	ment Erosion	N	8	_	WE	EIGHT POSTING	Not Ap	pplical	ble X	Inspector	50	Y	Υ
3.Del	bris		N	8	-		Н	3 3	3S2 S	Single	Rigging		N	N
4.Vec	getatio	on	N	8	T -	Ac	ctual Posting N	N	N	N	Staging		N	N
l	ilities		N	N		∣ _{Re}	ecommended Posting N	N	N	N	Traffic Cor		Y	Υ
		Slane Brotoction	+	8		1					RR Flagge	r	N	N
		/Slope Protection	N	+ -		Wai		JDMT Da		00/00/0000	Police		Y	Υ
 	gradat		N	8	-	Sic	gns In Place E	w	Other	er Advance W	Other:		<u> </u>	
8.Fer	nder S	System	N	N	<u> - </u>	(Y=	=Yes,N=No, R=NotRequired)	-					N	N
			\perp	<u> </u> '		Leg	egibility/			<u> </u>	TOTAL H	IOURS		8
		,		'		Visi	sibility							
		-				CLF		N .		S	PLANS	(Y/I	N):	Υ
<u> </u>			_			No		in	ft	in meter				=
STRE	EAM FL	LOW VELOCITY:					ctual Field Measurement	0	.	0	(V.C.R.)	(Y/N):	N	
Tidal () Hig	gh () Moderate () L	Low()	X) Nor	ne ()	Pos	osted Clearance	0	Δ	0 o		_		
						Sig	gns In Place At bridge	S	N	Advance S	TAPE#:			
ITEM 61	1 (Dive R	Report): N ITEM 61	i (This	Repor	ort): 7	(Y=	(=Yes,N=No, R=Not Required)				List of field	tests performed	d:	
93b-l	II/W IN	NSP. DATE: 00	 n/no/	/0000	<u></u>	Leg	egibility/			7 /		-		
						Vis	sibility							
RATI Rating		ort (Y/N): Y			,	1					S please give			
					,	Reco	commend for Rating or Rerat	ing (Y/I	N):	N HIG	3H () MEDIUI	IM () LOW ()	
Date:		10/01/2002			,	REA	ASON:							
	•	ion data at time of e		•	•	1								
I 58: 8	3 159	9: 8 160: 7 Da	ıte :1	0/10	0/2001	1	<u> </u>							
							CONDITION RAT	TING	4 GUI	IDIB (For	Items 58, 59, 6	30 and 61)		
	CODE	CONDITION	\Box				DEFECTS			,	10	0 4.14 2 . ,		
 	N	NOT APPLICABLE	+											
G	9	EXCELLENT	_	xceller	nt condition.									
G	8	VERY GOOD	_		olem noted.									
G	7	GOOD	_		ninor problem	 ms.								
F	6	SATISFACTORY					some minor deterioration.							
F	5	FAIR					nents are sound but may have minor secti	ion loss, c	cracking,	. spalling or scour.				
P	4	POOR	_		-		eterioration, spalling or scour.			<u></u>				
P	3	SERIOUS	Lo	oss of s	section, dete	terioratio	ion, spalling or scour have seriously affect concrete may be present.	cted prima	ary struct	tural components. I	Local failures are	possible. Fatigue c	racks	
			Ad	Advance	ed deteriorat	ation of p	primary structural elements. Fatigue crac							
С	2	CRITICAL	re	removed	d substructur	ire suppo	port. Unless closely monitored it may be	necessary	ry to close	se the bridge until co	orrective action is t	taken.		
С	1	"IMMINENT" FAILURE					tion loss present in critical structural comp out corrective action may put it back in lig			s vertical or horizon	tal movement and	cting structure star	olility.	_
	0	FAILED	c	Out of s	ervice - bey	ond cor	prrective action.							
		IAILL				<i></i>			YC (S141131A				
DEEL	ICIENC	CY: A defect in a stru		that re	iree corre	ative a	DEFICIENCY REPO	<u>)Kun</u>	<u> </u>	AUIDA				
						Clive ac	ction.							
		Deficiency Deficiencies			in nature, gr	orally d	1. and impose the structural integrity of the bridg	and could	ilv he r	ind Evamples incl		-t Challed concrete	*Ainor no	٠.
NI= IV	1inor 1	Jeficiency - Deliciences holes, Minor	r corrosi	ion of ste	el, Minor scor	uring, Clo	do not impact the structural integrity of the bridge logged drainage, etc.	and could c	easily be in	еранец. Ехантрієв под	JOE DUL are not mines	J to: Spalled concrete,	Millioi por	•
S= Se	evere/N	Iajor Deficiency - De cc	eficienci orroded	ies which rebars,	n are more ext Considerable	ensive in settlemer	in nature and need more planning and effort to re ent, Considerable scouring or undermining, Mode	∌pair. Examp erate to ext€	ples includ ensive corr	de but are not limited to: rosion to structural stee'	Moderate to major do with measurable los	eterioration in concrete s of section, etc.	, Exposed	d and
C-S=	Critic	al Structural Deficie	ency	_ A def	iciency in a str	ructural e	element of a bridge that poses an extreme unsaf	ie condition	due to the	e failure or imminent fail	ure of the element wh	nich will affect the struc	tural integ	grity
		cal Hazard Deficienc	cv -	of the A deficie	e bridge. iency in a comp	ponent or	or element of a bridge that poses an extreme haz	zard or unsaf	afe condition	on to the public, but does	es not impair the struct	ctural integrity of the brid	idge. Exam	mples
~	· · · · ·	al linear w &	· i	include b etc.	out are not limi	ited to: Lo	Loose concrete hanging down over traffic or pede	astrians, A h	hole in a sig	idewalk that may cause	injuries to pedestrian	s, Missing section of b	ridge railin	ng,
UPG	ENCY	OF REPAIR:					,	-						
UNG														
	nmediate	, ,	-		-		n Engineer (DBIE) to report the Deficiency and to Engineer or the Responsible Party (if not a State							

CITY/TOWN	B.I.N.	BR. DEPT. NO.	8STRUCTURE NO.	INSPECTION DATE
PITTSFIELD	01R	P-10-023	P10023-01R-MUN-NBI	OCT 24, 2023

REMARKS

BRIDGE ORIENTATION

Pomeroy Avenue travels west and east. The East Branch of the Housatonic River flows from north to south. This single span structure consists of seven weathering steel beams with welded cover plates supporting a reinforced concrete deck with an asphalt wearing surface. The beams and bays are numbered from north to south, upstream to downstream, in accordance with the plans. See photos 1 & 2.

ITEM 58 - DECK

Item 58.1 - Wearing Surface

At the east deck joint, the wearing surface is pulling away from the armor, with cracking and patches. See photo 3.

Item 58.2 - Deck Condition

Both deck overhangs have randomly spaced transverse hairline cracks with efflorescence that extend up the fascias.

All bays have stay in place forms. See photo 2.

<u>Item 58.4 - Curbs</u>

In the south curb, all of the masonry joints have minor vegetation.

In the north curb, between the curb and sidewalk, there is a moderate amount of vegetation. See photo 4.

The southwest and northeast approach curbs are tipped toward the roadway, up to 2".

Item 58.6 - Sidewalks

The both sidewalks have longitudinal and transverse hairline cracks.

The north sidewalk, adjacent to the curb, has scaled areas, full length x up to 2" wide x 1" deep, with light vegetation growth. See photo 4.

Both sidewalk fascias have vertical hairline cracks that line up with cracks in the deck overhangs.

Item 58.8 - Railing

North Railing

The top rail has several minor dents, full length.

The 4th panel from the west has several balusters with minor damage.

The east end post, around the bottom rail, has a scaled area, 10" wide x 6" high x 2" deep.

South Railing

The 6th panel from the west has balusters that are not fully secured.

Item 58.12 - Utilities

In bay 1, the second bracket from the west is severely rusted with holes throughout the web. The utility is located directly under a set of deck weeps. See photo 5.

In bay 1, the water main insulation has been repaired.

CITY/TOWN	B.I.N.	BR. DEPT. NO.	8STRUCTURE NO.	INSPECTION DATE
PITTSFIELD	01R	P-10-023	P10023-01R-MUN-NBI	OCT 24, 2023

REMARKS

Item 58.13 - Deck Joints

The east deck joint is filled with sand and debris. See photo 3.

At the east deck joint, the steel headers have minor gouges, up to 4" wide x 1/2" deep, due to plow damage.

APPROACHES

Approaches a - Appr. Pavement Condition

At the east deck joint, the approach pavement is pulling away from the armor, with cracking and patches. See photo 3.

Approaches c - Appr. Sidewalk Settlement

The southeast corner is settled, 2".

The southwest corner is settled, 2". The approach walkway in this area is dirt / grass. See photo 6.

ITEM 59 - SUPERSTRUCTURE

Item 59.4 - Girders or Beams

Beam 1, at the east end, has minor laminating rust in the painted section near the bottom flange, 6' long. See photo 7.

Beams 1 & 2, at the west end, have laminated rust on the bottom flanges, up to 5' long, due to leakage from the deck weeps.

Item 59.9 - Bearing Devices

At the east abutment, the sliding plate bearings are in expansion toward the backwall, approximately 1" past center.

<u>Item 59.12 - Welds</u>

At the east end of beam 1, the cover plate welds have rust with delamination. See photo 7.

Item 59.13 - Member Alignment

Refer to Item 59.9 - Bearing Devices.

Item 59.14 - Paint/Coating

The weathering steel beams have regular dark patina.

The beam ends are painted.

Beam 1, at the east end, mostly along the bottom of the web, has peeling in the paint and patina failure, 6' long. See photo 7.

ITEM 60 - SUBSTRUCTURE

Item 60.1 - Abutments

Item 60.1.b - Bridge Seats

The west seat, at the north end, has a large amount of standing water and active leakage.

Refer to Item 60.1.d - Breastwalls.

CITY/TOWN	B.I.N.	BR. DEPT. NO.	8STRUCTURE NO.	INSPECTION DATE
PITTSFIELD	01R	P-10-023	P10023-01R-MUN-NBI	OCT 24, 2023

REMARKS

Item 60.1.c - Backwalls

At both backwalls, in bay 1 around the utility pipe, the bricks and mortar are deteriorated. Fill from below the approach sidewalks is spilling through in these areas. See photo 5.

East Backwall

In bays 2 - 4 & 6, there are full height vertical hairline cracks with efflorescence.

Bay 4 has a full height vertical crack, 1/16" wide.

Bay 5 has two vertical hairline cracks.

West Backwall

Bays 2, 3, 5, & 6 have full height vertical hairline cracks with efflorescence.

Bay 4 has two vertical hairline cracks with efflorescence.

Item 60.1.d - Breastwalls

Both sides, in all bays, have vertical cracks in the newer sections, 1/16" wide x 3' high. These cracks are near the steps in the seats.

The east breastwall, near the south drain pipe, has a scaled area, 1' diameter x 1" deep.

The east breastwall, at the north end, has a full length horizontal hairline crack with efflorescence at the pour joint and hairline mapcracking, 12' long.

Item 60.1.e - Wingwalls

The northeast wingwall has moderate mapcracking with efflorescence. At the end of the wingwall, the top is scaled 8' long x full width x 4" deep.

The southeast wingwall is scaled at the top, 4' long x 18" high x 1" deep, 6' from the breastwall.

Item 60.1.h - Footings

The footings are hidden by design.

Item 60.1.i - Piles

The piles are hidden by design.

TRAFFIC SAFETY

Item 36a - Bridge Railing

The bridge railings consist of type AL-3 aluminum rails, with balusters, tied into the tapered concrete end posts and mounted on the sidewalks. Refer to Item 58.8 - Railing.

Item 36b - Transitions

The transitions consist of nested steel W-beam panels tied into the concrete end posts and mounted on steel posts with steel blockouts, spaced at 3'.

Item 36c - Approach Guardrail

The approach guardrails consist of single steel W-beam panels mounted on steel posts with steel blockouts, spaced at 6'.

PAGE 6 OF 12

CITY/TOWN	B.I.N.	BR. DEPT. NO.	8STRUCTURE NO.	INSPECTION DATE
PITTSFIELD	01R	P-10-023	P10023-01R-MUN-NBI	OCT 24, 2023

REMARKS

The northeast approach guardrail has minor damage to one panel.

Item 36d - Approach Guardrail Ends

The southwest and northeast approach guardrails have buried ends, swept from traffic.

The southeast and northwest approach guardrails have steel terminal ends, swept from traffic.

Sketch / Chart / Photo Log

Sketch 1: Framing plan.

Chart 1: Channel profile readings.
Photo 1: General topside, looking west.
Photo 2: Typical underside, looking east.

Photo 3: East deck joint filled with sand and debris. Note the approach pavement pulling away from the

armor and patches.

Photo 4: Vegetation growing between the north sidewalk and curb.


Photo 5: Rusted utility support at the west end of bay 1. Also, note the fill spilling through the utility bay

in the backwall.

Photo 6: Approach sidewalk settlement at the west end of the south sidewalk.

Photo 7: Rusting with delamination at the east end of beam 1. Also, note the delamination in the cover

plate and the associated welds.



CHARTS

				D01006	Channel Profi	le Readings				
		S	outh Fasci	ia			N	orth Fasc	cia	
DATE	West Abutment	1/4 span	1/2 span	3/4 span	East Abutment	West Abutment	1/4 span	1/2 span	3/4 span	East Abutment
10/5/23	8.8	15.8	18.0	18.0	11.3	10.0	15.3	18.0	16.3	12.0

NOTES:

*All readings in decimal feet.




Chart 1: Channel profile readings.




Photo 1: General topside, looking west.



Photo 2: Typical underside, looking east.



Photo 3: East deck joint filled with sand and debris. Note the approach pavement pulling away from the armor and patches.



Photo 4: Vegetation growing between the north sidewalk and curb.



Photo 5: Rusted utility support at the west end of bay 1. Also, note the fill spilling through the utility bay in the backwall.



Photo 6: Approach sidewalk settlement at the west end of the south sidewalk.

CITY/TOWN
PITTSFIELD
B.I.N. BR. DEPT. NO. 8.-STRUCTURE NO. P10023-01R-MUN-NBI INSPECTION DATE OCT 24, 2023



Photo 7: Rusting with delamination at the east end of beam 1. Also, note the delamination in the cover plate and the associated welds.

2-DIST B.I.N. **C53**

STRUCTURES INSPECTION FIELD REPORT ROUTINE INSPECTION

BR. DEPT. NO. **P-10-055**

CITY/TOWN PITTSFIELD			8ST	RUCTURE NO. P10055-C5	3-MUI	N-DES			o. POINT 0.000	D:OPEN				P. DATE 2024
07-FACILITY CARRIED HWY E NEW LEN	ОХ		'	MEMORIAL NAMI	E/LOCAL	NAME		1	R BUILT 2023	106-YR REBUILT 0000	YR R		0000 (NC	ON 106)
06-FEATURES INTERSECTED				26-FUNCTIONAL O	CLASS		DIST. B	RIDG	E INSPECTI			Briggs		
WATER SACKETT	BRO	OK		Urban Loca	al		Mich	rae	l PE M	<i>Cabe</i> for	LA	В		
43-STRUCTURE TYPE 506: Prestressed Concrete B or Spread	ox Bean	n or Girders	- Single	22-OWNER City/ Municipal Highway A	21-MAIN City/ M Highwa	unicipal			ER R. Manc					
107-DECK TYPE 1 : Concrete Cast-i	n-Pla	ce		weather Rain	TEMP. (a)	rC	TEAM I	AN	ZONI	Ranzoni				
ITEM 58			ITE	M 59			1		ITEM					
DECK	9	DEF		ERSTRUCTUR	RE	9	DE	F	SUBST	RUCTURE		9		DEF
1.Wearing Surface	9	_		ngers		N	1 -		1. Abutı		Dive	Cur	9	
2.Deck Condition	9			orbeams		N	 		a. Pedes	tals	N	N		-
	9		3.Flo	or System Braci	na	N	<u> </u>		b. Bridge		N	N		-
3.Stay in Place Forms	9			ders or Beams	9	9	ऻ ॒		c. Backw d. Breast		N	N 9		-
4.Curbs	_	-		sses - General		N	 		e. Wingw		N	9		-
5.Median	N	-		Upper Chords		N	' <u> </u>		· ·	Paving/Rip-Rap	N	9	-	-
6.Sidewalks	N	-	-	Lower Chords		N	_		g. Pointii h. Footin		N	N H	-	
7.Parapets	N	-		Web Members		N	<u> </u>		i. Piles	ys	N	Н.		-
8.Railing	9	-		Lateral Bracing		N			j. Scour		N	9		-
9.Anti Missile Fence	N	-		Sway Bracings		N	-		k. Settler	nent	N	9		-
10.Drainage System	N	-				N	-		m.		N N	N N		-
11.Lighting Standards	N	-		Portals		N	-		2. Piers	or Bents			N	
12.Utilities	9	_		End Posts & Hangers		N	1 -		a. Pedes	tals	N	N		-
13.Deck Joints	N	_		n Pit's, Gussets	o P Anal		<u> </u>		b. Caps c. Colum		N	N	-	-
				er Plates	a Aliyi	es N	├			/Webs/Pierwalls	N	N		
14.	N	-	0.00				-		e. Pointii		N	N		-
15.	N	-		ring Devices		N	<u> </u>		f. Footin	g	N	N		
16.	N	-		aphragms/Cross	s Frame		-		g. Piles h. Scour		N	N		-
	E	w		vets & Bolts		N	-		i. Settler	nent	N	N		-
CURB REVEAL	<u>,</u> [200	12. W	elds		N	-		j.		N	N		-
(In millimeters)	'	200	13. Me	ember Alignmen	ıt	N	-		k. 3. Pile I	Panta	N	N		-
APPROACHES		DEF	14. Pa	int/Coating		N	-		a. Pile Ca		N	N	N	
a. Appr. Pavement Condition	9		15.			N	-		b. Piles	ips	N	N		-
b. Appr. Roadway Settlement	9		Year	Painted	N	 I	1		c. Diagoi	nal Bracing	N	N		-
, ,		-		I					d. Horizo e. Faster	ntal Bracing	N	N	-	-
c. Appr. Sidewalk Settlement	N	-		SION DAMAGE:	Please ex Moderate		vere (e. raster	lers	IN	IN	L	-
d.	N	-		. , , ,	Please ex		vere (UNDERM	INING (Y/N) If YE	ES ple	ase e	xplain	N
OVERHEAD SIGNS (Attached to bridge)	(Y/N)	N	None	e(X) Minor()	Moderate	e()Se	vere ()		ON DAMAGE:	oderat	e () Sev	ere ()
		DEF			Please ex Moderate	kpıaın e() Se	vere ()	l 	Please explain		`		- 、 /
a. Condition of Welds	N	-						\dashv			oderat	e () Sev	ere ()
b. Condition of Bolts	N	-	Any F	racture Critical	Member	: (Y/N)	N		I-60 (Div	e Report): N	<i>I</i> -60	0 (This	Repor	t): 9
c. Condition of Signs	N		Any C	Cracks: (Y/N)	N			_		. ,				
									93B-U/V	V (DIVE) Insp		00/	00/00	JUU
V-UNIKNO				NOT ADDI IO										OVED

CITY/	TOW	N	_		B.I.1	N.	BR. DEPT. NO. 8	STR	UCTU!	RE NO.			INSPECTIO)N Di	ATE
PITTS					C5					53-MUN-D	E:		FEB 28		
	EM 61	<u> </u>	—	—	_	T	TEM 36 TRAFFIC SAF	ETY			П	ACCESSIB	ILITY	, (Y/N	V/P)
	INNE			,	9			36	COND	DEF		TICCE COL		Needed	
		L & L PROTECTION	N				. Bridge Railing	0	9			Lift Bucket		N	N
C111 -	1 11 1	LI NOILCIIC.					. Transitions	0	N	-		Ladder		N	N
 			1	Cur	DEF	1 I 🗀	. Approach Guardrail	0	N	-		Boat		N	N
1.Ch	annel	Scour	N	9	<u> </u>	<u> D.</u> /	. Approach Guardrail Ends	0	N		- 1 ⊦	Waders		Р	N
2.Em	ıbankı	ment Erosion	N	9	-	WE	EIGHT POSTING	Not A	\pplical	ble X	- 1 ⊢	Inspector 50		N	N
3.Deb	bris_		N	9		1	H	3	3S2 5	Single	- 1 ⊢	Rigging		N	N
4.Veç	getatio	on	N	9	-	Ac	ctual Posting N	N	N	N	11	Staging		N	N
5.Util	lities	-	N	N	-	Re	ecommended Posting N	N	N	N	- 1 ⊢	Traffic Contr	ol	N	N
6.Rir	o-Rap/	Slope Protection	N	9	-	∣ _{Wa}	aived Date: 00/00/0000 E.	JDMT D	nate: (00/00/0000		RR Flagger		N N	N
	grada	-	N	9	_	'	At bridge			er Advance	Ή	Police		N	N
·		System	N	N	-		igns In Place N	S	N	S	.] }	Other:		\vdash	
0.1-61	luei o	ystem	IN		- -	(Y=	′=Yes,N=No, R=NotRequired)				L				<u></u>
 			+	+			egibility/ isibility			7[/		TOTAL HO	URS		8
 			—	<u> </u> '			,	<u></u>		W	十			\vdash	二
				'		No		in	ft	in meter	.	PLANS	(Y/N	1):	Υ
CTD							ctual Field Measurement	0		0		GIOD)			
		LOW VELOCITY:		₩ \ No	, ,		osted Clearance	0		0	" "	(V.C.R.)	(Y/N):	N	
lidai () Hig	gh () Moderate () L	_ow (/	Noi	1e ()		At bridge			dvance	1	TAPE#:			
ITEM 61	l (Dive F	Report): N ITEM 61	1 (This	s Repo	ort): 9	(Y=	igns In Place E '=Yes,N=No,	W	E	W	\vdash				
						NR:	R=Not Required)				1	List of field tes	ts performea:		
93b-L	J/W IN	ISP. DATE: 00)/00/	/0000	J		egibility/ isibility								
RATI	NG					\vdash				If YI	ES	please give pri	iority:		
Rating	Repc و	ort (Y/N): N			,	Rec	commend for Rating or Rera	ting (Y	′/N):			() MEDIUM ()	
Date:		00/00/0000			,		_	-	· _						
		ion data at time of e	existi	ina ra	ıtina	REA	ASON:				_				
	•			•	0/0000	1					_				
├──							CONDITION DA	TUNI			_				
 			\neg				CONDITION RA	IIIN	<u> </u>	(For	r Ite	ems 58, 59, 60 a	and 61)		
 '	CODE	00112111011	+				DEFECTS								
	N	NOT APPLICABLE	_		· dition						_				
G	9	EXCELLENT	_		nt condition.										
G	8	VERY GOOD	_		olem noted. ninor problem						_				
G F	6	GOOD					some minor deterioration.								
F	5	FAIR					nents are sound but may have minor sec	tion loss.	cracking	spalling or scour.					
P	4	POOR	_		-		eterioration, spalling or scour.	1011 1000,	Cracking,	Spailing or Joou					
P	3	SERIOUS	Lo	oss of s	section, dete	erioratio	tion, spalling or scour have seriously affe	cted prin	nary struc	tural components.	Loc	cal failures are pos	sible. Fatigue cra	acks	
	-	SEKIOUS					concrete may be present. f primary structural elements. Fatigue cra	acke in et	ool or she	or cracks in concre	oto I	may be present or	coour may have		
С	2	CRITICAL	re	removed	d substructur	ire supp	poort. Unless closely monitored it may be	e necessa	ary to close	se the bridge until co	corre	ective action is take	en.		
С	1	"IMMINENT" FAILURE					tion loss present in critical structural com but corrective action may put it back in lig			s vertical or horizon	ntal	movement affectir	ng structure stabl	ility.	
	0	FAILED	+	Out of s	envice - bev	ond cor	prrective action.				_				
		FAILED				ли сс		2-D/D	770 (
	O'EN/	A defect in a str	- churo	that re	iron corr		DEFICIENCY REPO	<u>DRTI</u>	<u>ing (</u>	SOIDE					
	CIENC				quires corre	ctive au	action.								
		IES OF DEFICIENC			- i- acture or	rolly d	the act increase the atmosphere integrity of the bride	ad coul	' ha	Evernoles inc	-l-ıde	- total and limited to	Carllad concrete N	ti-or not	
M= M	1inor 1)eficiency - Deliciences holes, Minor	r corrosi	ion of ste	el, Minor scou	uring, Clo	do not impact the structural integrity of the bridg clogged drainage, etc.	anu coun	1 easily ue i	repaired. Examples inc	Juue	3 but are not immed to.	Spalled concrete, is	linoi poi	
S= Se	vere/N	Iajor Deficiency - Deficiency - Co	eficienci orroded	ies which rebars,	n are more ext Considerable	ensive in settlemer	in nature and need more planning and effort to rent, Considerable scouring or undermining, Mod	epair. Exar erate to ex	nples includatensive con	de but are not limited to rosion to structural stee	o: Mo el wi	oderate to major deter ith measurable loss of	ioration in concrete, section, etc.	Exposed	l and
C-S=	Critic	al Structural Deficie	ency -	_ A def	iciency in a str	uctural e	element of a bridge that poses an extreme unsa	fe conditio	n due to the	e failure or imminent fai	ilure	of the element which	will affect the structu	ural integr	rity
		cal Hazard Deficienc	cv -	of the A deficie	e bridge. iency in a comp	ponent or	or element of a bridge that poses an extreme ha	zard or uns	safe conditio	on to the public, but doe	es n	not impair the structural	I integrity of the bridg	ge. Exam	nples
	_		•	include b etc.	out are not limi	ted to: Lo	Loose concrete hanging down over traffic or peo	estrians, A	hole in a si	idewalk that may cause	e inj	uries to pedestrians, iv	fissing section of bit	dge railiri	ıg,
		OF REPAIR:									_				
	ımediate	,	-		-		n Engineer (DBIE) to report the Deficiency and to			=	٦,	-			
A = AS P = Pri							Engineer or the Responsible Party (if not a State ne Responsible Party (if not a State owned bridge								

REMARKS

BRIDGE ORIENTATION

East New Lenox Road travels north and south. Sackett Brook flows from east to west. This single span bridge is still under construction. The beams and bays are numbered from west to east, downstream to upstream, in accordance with the plans. See photos 1 & 2 and sketch 1.

GENERAL REMARKS

This structure is still under construction and many items are hidden by form work or not yet completed. The condition ratings are based on what is currently visible and carrying traffic. Temporary construction items will not be rated. Beams 1 & 2 are open to traffic. Beams 3-5 are still under construction.

ITEM 60 - SUBSTRUCTURE

<u>Item 60.1 - Abutments</u> <u>Item 60.1.h - Footings</u>

The footings are hidden by design.

Item 60.1.i - Piles

The piles are hidden by design.

TRAFFIC SAFETY

Item 36a - Bridge Railing

The completed west portion of bridge railing consists of S3-TL4 type railing bolted to the reinforced concrete rail base. The temporary east railing consists of Jersey Barriers. Refer to item 59.9 - Railing.

Item 36b - Transitions

The permanent transitions are not built yet.

Item 36c - Approach Guardrail

The permanent approach guardrails are not built yet.

Item 36d - Approach Guardrail Ends

The permanent approach guardrail ends are not built yet.

Sketch / Photo Log

Sketch 1: Framing plan.

Photo 1: General topside, looking south.
Photo 2: General underside, looking south.






Photo 1: General topside, looking south.



Photo 2: General underside, looking south.

National Bridge Element Inspection

BDEP1#	P-10-055					Date	02/28/20	24	
B.I.N.	C53			District B	ridge Ins	spection Eng'r	Laurie A	. Briggs	
Item 8	P10055-C53-MUN-DES				Inspe	ecting Agency	Mass. Hi	ghway Dept.	
Span Group	1					Team Leader	Reed Ma	ıncari	
Town	Pittsfield					Team		Ranzoni	
District	1					Member(s)			
El#	Element Name	Units	Env.	Total Q.	% or Q	State 1	State 2	State 3	State 4
12	Re Concrete Deck	sq feet	2	531.000	\ \ \ \ \ \ \ \ \ \ \ 	531.000			
Notes:	•	-							
104	Pre Clsd Box Girder	feet	2	89.000	%	89.000			
Notes:	•	•			•				
215	Re Conc Abutment	feet	2	14.000	\ \ \ \ \ \ \	14.000			
Notes:	•	-							
310	Elastomeric Bearing	each	2	10	%	10			
Notes:	·								
330	Metal Bridge Railing	feet	2	64.000	\ \ \ \ \ \ \ \ \ \ \ \ \ \	64.000			

Notes:

	State Information			Classification	Code
BDEPT#= P10055	A	gency Br.No.	(112) NBIS Bridge Length		N
Town= Pittsfield		L.O.	(104) Highway System		N
B.I.N= C53		AASHTO= 000.0	(20) 1 41104101141 01400	Urban Local	19
RANK= 0 H.I.=	Identification	FHWA Select List= N (6/21/17	, , , , , , , , , , , , , , , , , , , ,		0
(8) Structure Number		P10055C53MUNDES			N
(5) Inventory Route		151000000		2-way traffic	1 lane for 2 way ²
2) State Highway Department Di	strict		(103) Temporary Structure		N
3) County Code 003	(4) Place code	53960	(105) Federal Lands Highways		0
6) Features Intersected		WATER SACKETT BROOF	(110) Designated National Network	<	N
7) Facility Carried		HWY E NEW LENOX	• •		3
9) Location		.7 MI S OF WILLIAM S		nicipal Highway A	04
(11) Kilometerpoint		0000.000	(22) Owner - City/Mun	nicipal Highway A	04
12) Base Highway Network		1	(37) Historical Significance	- "	
13) LRS Inventory Route & Subr	oute		(70) 5	Condition	Code
16) Latitude		42 DEG 25 MIN 28.25 SEC	(58) Deck		9
17) Longitude		73 DEG 13 MIN 30.97 SEC	(59) Superstructure (60) Substructure		9
98) Border Bridge State Code		Share %	(61) Channel & Channel Protection		9
99) Border Bridge Structure No.	#		(62) Culverts		9
	icture Type and Mat			d Rating and Posting	Code
	Prestressed C			HL-93	A
Box Beam - Spread	Jointless I	bridge type: Not -app licable	(62) Operating Pating Method		
44) Structure Type Appr:		INTEGRAL (weak a	(64) Operating Rating		0
		Code	(65) Inventory Rating Method -		
45) Number of spans in main un	it	1 -000	(66) Inventory Rating		0
46) Number of approach spans		0000	(70) Bridge Posting		0
107) Deck Structure Type -	Concrete Ca	st-in-Place Code 1	(41) Structure -	Open with shorin	
108) Wearing Surface / Protectiv	e System:		(CZ) Church and Fredrich	Appraisal	Code
A) Type of wearing surface -		Code 6	(67) Structural Evaluation (68) Deck Geometry		-0 3
B) Type of membrane -		Code 3	(69) Underclearances, vert. and hor	ri 7	-N 2
C) Type of deck protection -		Code 1	(71) Waterway adequacy	112.	
	Age and Service	<u> </u>	(72) Approach Roadway Alignment		7
27) Year Built		2023 0000	(36) Traffic Safety Features		7
106) Year Reconstructed		0000		124	0 0 0 0
42) Type of Service: On -	Highway		3 2/20	1/24 Inspections	
Under - Waterway		Code 15	(90) Inspection Date 00/ 00/ 0	00 (91) Fr	equency 24 00 MO
28) Lanes: On Structure	00	Under structure 00			(93) CFI DATE
29) Average Daily Traffic		003621	(A) Fracture Critical Detail	**	MO A) 00/00/00
30) Year of ADT	2017 (109) Truck A	ADT 06 %	(B) Underwater Inspection	**	MO B) 00/00/00
19) Bypass, detour length		012 KM	(C) Other Special Inspection		MO C) 00/00/00
	■ Geometric Data	40.5	(*) Other Inspection (Lane width)		MO *) 11/ 06/ 23 <mark>0</mark> 0
48) Length of maximum span		13.5 0 000. 0 M	(*) Closed Bridge		MO *) 00/00/00
49) Structure Length		14.6 00 000. 0 M	(*) UW Special Inspection		MO *) 00/00/00
50) Curb or sidewalk:	Left 00.0	3	(*) Damage Inspection	Rating Loads	MO *) 00/00/00
51) Bridge Roadway Width Curb	to Curb	3.3 0 00.0 M	Report Date 00/00/00	H20 Type 3	Type 3S2 Type HS
52) Deck Width Out to Out		4.2 0 00.0 M	Operating	0.0 0.0	0.0 0.0
32) Approach Roadway Width (w	u/shoulders)	3.3 _{000.0} M	Inventory	0.0 0.0	0.0 0.0
33) Bridge Median -		Code		Field Posting	
34) Skew 00 DEG	(35) Structure		Status	Posting [Date 00/00/00
10) Inventory Route MIN Vert Cl		99.9 00.00M	2 Axle	3 Axle 5 A	xle Single
47) Inventory Route Total Horiz	Clear	3.3 00.0 M	Actual		
53) Min Vert Clear Over Bridge R	Rdwy	99.9 0 0.00 M	Recommended		
54) Min Vert Underclear ref		00.00 M	Missing Signs N	Misc.	
55) Min Lat Underclear RT ref		00.0 M	Bridge Name	1 11001	
56) Min Lat Underclear LT		00.0 M		Acrow Panel	N Jointless Bridge
	Navigation Data		Freeze/Thaw	and	Johnsess Bridge
, -	navigation control or	•	•	iir Owner(s)	
111) Pier Protection		Code	=	sibility (Needed/Used)	
39) Navigation Vertical Clearance		000.0 M		N Rigging	Other
116) Vert-lift Bridge Nav Min Vert		M	12.	N Staging	Oute
40) Navigation Horizontal Clearar	nce	0000.0 M	N Boat	N Traffic Control	
· -			IV Doar	I W ITATIO CONTUO	
				N RR Flagperson	Inspection Hours: 000 6

Report Date: October 1, 2024 State Information Classification • ode BDFPT#= P10055 Agency Br.No. (112) NBIS Bridge Length L.O. Town= Pittsfield Ν (104) Highway System AASHTO= B.I.N= C53 007.0 (26) Functional Class -19 Urban Local RANK= 0 FHWA Select List= N (6/21/17) 100.0 % (100) Defense Highway n Identification N (101) Parallel Structure P10055C53MUNDES (8) Structure Number 3 151000000 (102) Direction of Traffic -One lane for 2-way traffic (5) Inventory Route Ν (103) Temporary Structure 01 (2) State Highway Department District (4) Place code 53960 (105) Federal Lands Highways 0 003 (3) County Code Ν WATER SACKETT BROOK (110) Designated National Network (6) Features Intersected (7) Facility Carried **HWY E NEW LENOX** (20) Toll -On free road 3 .7 MI S OF WILLIAM ST (9) Location (21) Maintain -City/Municipal Highway A 04 (22) Owner -(11) Kilometerpoint 0000.000 City/Municipal Highway A 04 (12) Base Highway Network (37) Historical Significance Condition . Code (13) LRS Inventory Route & Subroute (58) Deck 9 42 DEG 25 MIN 28.25 SEC (16) Latitude (59) Superstructure 9 73 DEG 13 MIN 30.97 SEC (17) Longitude (60) Substructure 9 (98) Border Bridge State Code Share % (61) Channel & Channel Protection 9 (99) Border Bridge Structure No. # N (62) Culverts Structure Type and Material Load Rating and Posting Prestressed Concrete Code 506 (43) Structure Type Main: (31) Design Load -HL 93 INTEGRAL (weak a Box Beam or Girders - Single or Spread Jointless bridge type: (63) Operating Rating Method (44) Structure Type Appr: (64) Operating Rating Code (65) Inventory Rating Method -(45) Number of spans in main unit (66) Inventory Rating 0 0000 (46) Number of approach spans (70) Bridge Posting 0 (41) Structure -Open with shoring D (107) Deck Structure Type -Concrete Cast-in-Place Code 1 Appraisal Code (108) Wearing Surface / Protective System: (67) Structural Evaluation 3 Bituminous Code 6 A) Type of wearing surface -(68) Deck Geometry 2 B) Type of membrane -Code 3 **Epoxy** (69) Underclearances, vert. and horiz. N 1 C) Type of deck protection -**Epoxy Coated Reinforcing** Code (71) Waterway adequacy 7 Age and Service (72) Approach Roadway Alignment 7 2023 (27) Year Built 0 0 0 0 (36) Traffic Safety Features (106) Year Reconstructed 0000 (113) Scour Critical Bridges (42) Type of Service: On -Highway Inspections (90) Inspection Date 02/28/24 (91) Frequency 24 MO Under -Waterway Code 15 (92) Critical Feature Inspection: (93) CFI DATE 01 00 (28) Lanes: On Structure Under structure MO A) 00/00/00 (A) Fracture Critical Detail 00 (29) Average Daily Traffic 003621 Ν 00/00/00 (B) Underwater Inspection 00 MO B) Ν (30) Year of ADT 2017 (109) Truck ADT 06 % (C) Other Special Inspection 00 MO C) 00/00/00 Ν 012 KM (19) Bypass, detour length Geometric Data 00 MO *) 00/00/00 (*) Other Inspection () N (48) Length of maximum span 0013.5 M (*) Closed Bridge 00 MO *) 00/00/00 Ν 00014.6 M (49) Structure Length (*) UW Special Inspection 00 MO *) 00/00/00 00.0 M $00.3\,\mathrm{M}$ MO *) 00/00/00 (50) Curb or sidewalk: Right (*) Damage Inspection Rating Loads (51) Bridge Roadway Width Curb to Curb 003.3 M Report Date 00/00/00 Type 3 Type 3S2 Type HS H20 (52) Deck Width Out to Out 004.2 M Operating 0.0 0.0 0.0 0.0 003.3 M (32) Approach Roadway Width (w/shoulders) 0.0 Inventory 0.0 0.0 0.0 (33) Bridge Median -No median Code n Field Posting (34) Skew 00 DEG (35) Structure Flared Ν Posting Date 00/00/00 Status (10) Inventory Route MIN Vert Clear 99.99 M Single 2 Axle 3 Axle 5 Axle Actual (47) Inventory Route Total Horiz Clear $03.3 \, M$ Recommended 99.99 M (53) Min Vert Clear Over Bridge Rdwy Missing Signs Ν (54) Min Vert Underclear ref M 00.00 Misc. N $00.0\,\mathrm{M}$ (55) Min Lat Underclear RT ref Bridge Name (56) Min Lat Underclear LT 00.0 M N Anti-missile fence Acrow Panel Y Jointless Bridge Navigation Data Freeze/Thaw (38) Navigation Control -Code No navigation control on waterway 0 # Stairs On/Adjacent Stair Owner(s) (111) Pier Protection Code Accessibility (Needed/Used) (39) Navigation Vertical Clearance 000.0 MN / N Liftbucket N/N Rigging Other (116) Vert-lift Bridge Nav Min Vert Clear Μ N/NLadder N/N Staging 0000.0 M (40) Navigation Horizontal Clearance Traffic Control N/NBoat N/NInspection P/NWader N / N RR Flagperson 008 Hours: N/NInspector 50 N / N Police



TOWN OF LEE 32 Main Street, Lee, MA 01238 www.lee.ma.us

R. Christopher Brittain, Town Administrator

July 29, 2025

Mr. Josh Fontaine EPA New England 10 Lyman Street, Suite 2 Pittsfield, MA 01201

Dear Mr. Fontaine:

Please find comments from the Town of Lee regarding the <u>Road Assessment Work</u> <u>Plan</u>:


Table 1 of the work plan lists several roads in the Town of Lee. The Town requests further details on the following:

The previously presented transportation plan indicated that reach 7 materials would be moved by hydraulic dredging. Please provide the proposed use of Columbia, Center and Bradley Streets for 7 B and C if materials are moved hydraulically. Also please indicate how Columbia, Center and Bradly Street will be used for UDF Construction with out the use of other roads in town in order to connect to a major highway. For example, if equipment or materials for the UDF need to connect to Interstate 90 through Center or Columbia Street they would also need to pass through Main Street and Housatonic Street in Lee.

Table 1 also indicated Orchard and Greylock as "included for background information – not anticipated to be used". Please clarify why these roads are being evaluated if they are not being used. The Town of Lee is particularly concerned about potential use of these roads, especially for reach 7 materials, as they are a populated residential area and include 3 schools (Lee High School, Lee Elementary School and St. Mary's School).

Sincerely

R. Christopher Brittain *Town Administrator*



Mr. Josh Fontaine Remedial Project Manager Rest of River 5 Post Office Sq. Suite 100 Boston, MA 02109-3912

Re: Town of Lenox Comments on Road Assessment Work Plan

Dear Mr. Fontaine and EPA staff:

The Town of Lenox submits this letter to communicate its concerns and comments regarding the proposed Road Assessment Work Plan (hereinafter, work plan) by General Electric (GE) for roads identified and associated with the construction of the Upland Disposal Facility (UDF) and Rest of River (ROR) cleanup operations. Lenox will be impacted by GE trucking activity and other associated vehicular traffic during the construction of the UDF and ROR remediation work. This type of activity will affect the quality of life for our residents and businesses that live on, near and use these public ways.


The work plan indicates that some roads are not in sufficient condition to stand up to the loads that GE needs to put on them. It is assumed that GE will be responsible for the construction of new roads, the improvement of existing roads and maintaining affected roads in a state of good repair during ROR operations and at the conclusion of the ROR project. However, these responsibilities appear vague. Lenox requests that these expectations and responsibilities be clearly spelled out in order to assess accountability and responsibility.

Frequency & Type of Vehicles Anticipated to be Used

Notwithstanding the assessment methodology and scope as discussed below, Lenox requests that GE provide EPA and Lenox estimates on the number of truck trips it anticipates daily during UDF construction and identify the type of vehicles reasonably anticipated to be used for hauling UDF construction materials. Estimated weight and frequencies will help Lenox assess road construction methodologies as proposed by GE and anticipate potential road and infrastructure damage in addition to any assessment work performed by GE. Similarly, Lenox requests the same data for those vehicles proposed to be used for moving materials to the UDF from the Woods Pond rail transfer yard during the clean-up phase of work. Should rail transportation not be feasible at any given time during cleanup operations as discussed in EPA's Conditional Approval of the Transportation and Disposal Plan, these trucks will be using roadways identified as alternative routes in the Transportation and Disposal Plan to move material from work sites to the UDF.

Hours of Operation & Public Communication

Lenox also has concerns as to when truck traffic will be present on routes associated with UDF construction and cleanup operations as this will directly impact quality of life. Lenox is requesting that EPA set reasonable hours of operation and require GE to provide information on how it plans to mobilize equipment and



materials for construction of the UDF. This information will assist the Town of Lenox in setting expectations, communicating to its residents and monitoring and responding to quality-of-life issues around truck traffic. Similarly, Lenox is requesting that GE provide weekly public notices via media channels and directly to municipalities on reasonably anticipated trucking activities or transportation changes during UDF construction and cleanup operations.

Comments & Concerns in Section 1 Introduction and Background

The Work Plan includes assessment of planned primary and alternative routes for trucking during the ROR project. Lenox is seeking clarity in the work plan that the same schedule of assessments be performed on alternative routes should those routes be used and notice provided to Lenox if those routes become active. The work plan should also include what controls, accountability and assessment will be put in place should non-authorized routes be used. Lenox requests that EPA and/or GE establish a method to directly receive resident/community concerns regarding ROR transportation activities.

The Town of Lenox requests that GE make a commitment to meet with municipalities regularly regarding changes to trucking routes as they are identified prior to publishing them in future design documents. Our community is very concerned about the impact to the community infrastructure and quality of life from trucking during the performance of the project. Lenox wants to be sure GE and EPA effectively communicate to its residents the where, when, why and how trucks and other traffic will be moving through their neighborhoods.

Comments & Concerns in Section 2.1 Paved Roads


The assessment methods for paved roads as proposed are considered to be insufficient to assess the totality of impact of ROR activities on the roadways, especially within the subgrade. Consistent with its previous request and contained in the Settlement Agreement, Lenox is requesting that ground penetrating radar (GPR) be used during all phases of assessment to determine if subgrade materials and/or infrastructure has been affected. Surface treatment via overlay will not address and may mask underlying failures that will eventually degrade the road.

In addition to GPR, Lenox is requesting that mobile LiDAR be used during all phases of assessment in addition to the proposed methods to document the existing and post activity surface for evaluation of rutting and shoving, which are typical roadway failure modes from heavy truck traffic, that may result from the ROR project-related transportation.

Should GE install new pavement down on a road, the proposed assessment methods will not be sufficient to evaluate damage to the road and/or subbase. Lenox is requesting the use of LiDAR to give elevation information that can better assess potential future failure.

Comments & Concerns in Section 2.3 Infrastructure

This section is unclear in what specific infrastructure will be assessed. Lenox is requesting that infrastructure such as drainage structures, culverts and manholes be clearly identified as requiring assessment. All assessments should include video inspection with internal measurements due to the potential of structural



failure of these structures being exposed to the significantly high volume of heavy truck traffic. GE should research and consult with the municipalities to obtain any existing data as to the number, location, size, and material of any of these structures. A survey should be completed for the identified and agreed upon infrastructure to determine if settlement is occurring using accepted engineering practices, such as LiDAR, GPR, etc.

Assessment of infrastructure should also include other roadway infrastructure that may be present and affected such as guide railing, signs, drainage ditches, traffic control devices, curbing, sidewalks, sidewalk ramps, etc.

Underground utilities that serve businesses and residents may be affected by overhead truck traffic. Lenox is requesting that GE identify and inventory utility services such as lateral sewer connections and water service connections and identify an assessment methodology to identify any impact and that GE be responsible for the repair and restoration of such underground utility services.

Comments & Concerns in Section 3 Schedule, Data Evaluation, and Reporting

The proposed work plan states that "If a notable trend divergence occurs on a road or road segment subject to ROR project transportation activities, GE will conduct additional analysis to assess whether the increased rate of road degradation can be attributed to the ROR project or some other factor." The term "notable" is vague and should be further defined with clear metrics. Furthermore, "additional analysis" should also be defined. The responsibility for determining what is a "notable trend" or if the additional analysis is sufficient should be made clear. Acceptability criteria and the opportunity for municipalities to evaluate should be established.

The proposed work plan provides that by February 15 of each year of the ROR project, "GE will submit to EPA, with copies to the pertinent municipalities, an annual report summarizing the road assessment and associated evaluations performed during the prior year. In accordance with Paragraph VI.A.3 of the February 2020 Settlement Agreement, such report will include photographic documentation of the condition of assessed infrastructure and roads for review by the affected municipality as appropriate." The Town of Lenox is requesting that all data assessments, data collected, analysis and/or computations made, conclusions, results, and reports be provided to the municipality with adequate time for comment prior to acceptance. And lastly, throughout the proposed work plan, there are references that "further details will be included in future reports and communications with effected municipalities in future meetings." This language is vague and more detail and expectations should be set.

Thank you for the opportunity to comment and for your attention to these concerns.

Respectfully submitted,

Jay K. Green, J.D. Town Manager