AECOM 100 S. Wacker Drive, Suite 500 Chicago, Illinois 60606 312-939-1000 tel 312-939-4198 fax

August 21, 2017

960630

Mr. Christopher J. Seibel John Burns Construction Company 17601 SW Highway, Orland Park, IL 60467

RE: Radiological Survey of Right-of-Way Utility Excavation Permit No.: DOT836709 Permit Address: 50 E. Ohio St., Chicago, IL AECOM Project No. 60537484.800

Dear Mr. Seibel:

Pursuant to conditions specified in the Chicago Department of Public Health (CDPH) radiation monitoring was required to be performed at the above referenced site. AECOM Technical Services, Inc. (AECOM) provided the required radiation monitoring on August 9, 10, and 11, 2017, to screen exposed fill material during removal of existing light base, installation of a cellular light base and the associated utility trench excavations.

Gamma radiation surveying was conducted at the above referenced address during the concrete/asphalt removal and trench excavation in the sidewalk and roadway Right-of-Way (ROW). The excavation consisted of removal of existing light pole base, concrete sidewalk, roadway as well as disturbance of the fill material during these activities. The work area is located along the north side of E. Ohio St., west of the intersection of E. Ohio St. and N. Rush St. (refer to sketch). The trench excavations were approximately 40-feet long, 3 to 5-feet wide. The excavation disturbed fill to depths of 0.5 to 8.5-feet below ground surface (bgs).

The U.S. Environmental Protection Agency (USEPA) removal action level for Chicago's Streeterville area is 7.1 picocuries per gram (pCi/g) total radium (Ra-226 + Ra-228). Gamma radiation count measurements for the project were made using a Ludlum Model 2221 survey meter (SN# 176944) and an unshielded 2 x 2 inch sodium iodide (Nal) probe Model 44-10. For the instruments used, the gamma count indicative of the USEPA removal action level of 7.1 pCi/g were 17,270 counts per minute (cpm) unshielded and 6,175 cpm shielded.

The field instrument gamma background of the area was recorded at a 2,500 com (shielded) at a ground level planter in close proximity to the excavations. Although none were observed for this project, field gamma measurements greater than twice the field background represent potential anomalous results that require more cautious and frequent field screening, but are not necessarily indications of the presence of thorium contaminated fill soil.

The field gamma measurements within the excavation area and of the spoil materials generated during the excavation process did not exceed the field instrument threshold equivalent to the USEPA removal action level and ranged from a minimum of 900 cpm to a maximum of 3,100 cpm shielded. Thus, there was no indication of the presence of radiologically-contaminated fill soil and/or an exceedance of the USEPA removal action level of 7.1 pCi/g total radium.

To fulfill the requirement of the CPDH permit this letter has been forwarded via email to:

Chicago Department of Public Health Attn: Mr. Terry Sheahan 333 South State Street, Rm. 200 Chicago, Illinois 60604 Permit No.: DOT836709 Permit Address: 50 E. Ohio St. Page 2

Please contact us with any questions you have regarding this letter or the reported results.

Regards,

Andrew Kozak Geologist

cc: Verneta Simon, USEPA Robert Wilson, Mobilitie

Attachments: CDPH Permit Sketch

Steven C. Kornder, Ph.D. Senior Project Geochemist

PERMIT



DEPARTMENT OF PUBLIC HEALTH

CITY OF CHICAGO

(STREETERVILLE Right-of-Way)

Notice is hereby given that the site you have requested a permit for is recorded with the City of Chicago Department of Public Health (CDPH) as potentially having environmental contamination on the site and adjacent right-of way. This environmental contamination could present a threat to human health and safety in connection with work performed at the site, or in the adjacent right-of-way, if proper safeguards are not employed.

A file containing detailed information regarding the aforementioned environmental contamination is available for review at CDPH at 333 S. State St., Room 200, Chicago, Illinois 60604 during normal business hours (8:30AM-4:30PM, Monday through Friday). Contact (312) 745-3152 for an appointment. This file must be reviewed and the remainder of this form completed before the permit can be issued if the ground is exposed or excavated. Please note that for some locations, additional health and safety procedures may be required by law.

Please complete the following:

I have reviewed and understand the documents, maintained by CDPH, regarding environmental contamination of the site and adjacent right-ofway. Further, I will ensure that all work at the subject site and adjacent right-of-way, and any monitoring required including but not limited to radiation monitoring, will be performed in a manner that is protective of human health and the environment and in compliance with all applicable local, state, and federal laws, rules, and regulations, especially those pertaining to worker safety and waste management. I will ensure that the results of any radiation monitoring and/or surveying conducted shall be provided to the CDPH and the United States Environmental Protection Agency within two (2) weeks of their completion. If any elevated levels of radioactive material are detected, I will immediately contact the United States Environmental Protection Agency at (800) 424-8802.

Applicant Name (print): Robert Wilson

Signature:

Site Address and Work Location (Describe exact site location and attach map):

50 E. Ohio Street (see attached construction drawings)

Nature of Work: Attach small cell wireless equipment to replacement light pole.

Company Name, Address, Phone No.: Mobilitie, LLC, 120 S. Riverside Plaza, Suite 1800, Chicago, IL, 60606, (312) 343-4882

General / Prime Contractor Name, Address, Phone No.: John Burns Construction Co., Chris Seibel, 17601 Southwest Hwy, Orland Park Include subcontractor information if applicable) IL, 60467, 708 326 3350 (office); 708 670 6733 (mobile) Safety Officer / Phone No.

Radiation Contractor / Phone No. and email address (if applicable) AECOM, Steve Kornder, 262 515-7700

Check if City Department Work Department Name:

CDOT Permit No.: DOT836709

Today's Date: 07/26/2017 Expected Start Date: 8/10/2017

CDPH Approval / Date

Please return this completed form to the Chicago Department of Transportation, Division of Infrastructure Management, Public Way Permit Office, City Hall – Room 905, 121 N. LaSalle St., Chicago, Illinois 60602 during normal business hours (8:30 AM - 4:30 PM, Monday through Friday)

For CDPH Use Only

333 SOUTH STATE STREET, ROOM 200, CHICAGO, ILLINOIS 60604

		REGIONAL MAP	WORK ORDER NO. 1 11617010	
mob	ilitie	Chicago	Marshall Marshall AMC 600 North Michigar 9	mobilitie
intelligent infrastructu	re	nordale Californ Pizza Big Bowl Kitchen at Why freed		EELTAAT UM ENGINEERING, INC.
<u>Site</u> Dasc_ch9 <u>Site A(</u> 42ND Ward -	<u>ID</u> DXSGNBC DDRESS 50 F. OHIO ST.	Diseage Pizzerio Uno Pizzerio Via Pizzerio V	a Ch	PROFESSIONAL LICENSURE
INDEX OF SHEETS	PROJECT INFORMATION	VICINITY MAP		
SHEET HOL SHEET TITLE I COVERSHEET COVERSHEET 2 CODE MATRIX STORE STATUS 3 PORE ELEVATIONS - STORE VIEW PORE ELEVATIONS - FRONT VIEW 4 PORE ELEVATIONS - FRONT VIEW ECOURDENT DETAILS 5 & LOADING DETAILS PORETAILS 7 CROUNDING DETAILS PORETAILS 8 GEREPARL NOTES 10 10 GEREPARL NOTES 11 11 STEE PLANT PLANT 12 PROFILES COOT STANDARDS 14 COOT STANDARDS ELEVANDARDS 15 COOT STANDARDS ELEVANDARDS 16 TRAFFIC CONTINGL FILE MO, 2016-73355	ADDRESS/CROSS STI SD E, OHIO ST, COUNTY, CORE COUNTY UTILITIESI PORE COUNTY CREE COUNTY AND COUNTY PROPERTY OWNERS APPLICANT, MODIFIELD Dig Chicago? Balarow, NOS dig, Ford State State County APPLICANT, MODIFIELD			IT IS A VIOLATION OF THE LAW FOR ANY PERSON, DELSS THEY NOT ACTING UNDERAL EXEMPLE. IN A LTG THE DECEMBER IN THE DELST AND A LTG THE DECEMBER. REVISIONS
PERMITTING	PROJECT CONTACTS	COORDINATES	N	PROJECT INFORMATION
JURISDICTION 1 COOT	MOBILITIE: PROJECT MANAGER ROBERT WILSON CONTACT: 120 S. RIVERSIDE PLAZA, CHICAGO, IL 60606 PHONE. 31(2):32-4092	LATITUDE: 41' 53'33,28"N (41.892578)		Сизин Вл. NRJ Сисоко вл. NKR Багса 04-27-2017
PROJECT SUMMARY END USER PROPOSES TO INSTALL EQUIPAENT ON EXISTING ALLMINNUM LIGHT POR UNITIAN NA EXISTING AND AND AND AND AND AND CONSIST OF THE FOLLOWING - INSTALL PROPOSED SWALL CELL COLPACINT	EJM ENGINEERING, INC.) ENGINEER 411 S. WELLS ST., CONTACT: SUITE 1000 CHICAGO, IL 60607 PHONE: 312-922-1700	LONGITUDE: 87 37'34.83"W (~87.626341)		Deliziti * CHIOXISCHIC (DOC IM# 2016-23335), (DUC EFF# 2017-300) (Titti COVERSHEET Skilz, 7482, 1 16

SKETCH

AECOM

JOBTITLE JBCC. SO E. Ohio St. Vireless Equipment Installation REVIEWER S. Kornder DATE 8/14/17 SCALE Isquere = Sleet SHEET NO. 1 OF 1

Sarvey Ludlu Probe	Equipu n 2221 2×2 NaI unshie shii backgro person	s/N: S/N: S/N: elded: eldel: sound: nurel:	1769 RN21 171,2 6,17 2,50 A.Ko	187 187 Sopm Sopm Do com zak			
		*		S	fore front	2	- Curr
	-10'		sil	3 1/01 2	5' 4		
Carb				curb	S I I		
	F		E. Oh	10 St. —	in sto	ielt base	
						~75'	
				Survey	Readings.		
C 0.	Daville		cD 14 (d selled	C. Do	D. //.	course (1)
D	Olconcre	te)		weded)	(2)	O" (corcrele)	(pm(shielded)
-	6" (sub-bu	.e) 1,3	500-2,2	200		6" (sab-bale)	1,300-2,000
B	24"	l.	100-1.	450	B	24"	1,500-2,300
	72 581	[i ^c	100 - 1/c	00 Emo	9	(concrete)	1/00-1700
	76"	L.	600-21	000		6 (IUS-Sove)	11400 111700
	84"	li	700-2	las	Ð	O" (concrete)	
						6" (sab - bas	1,500-2,300
						24"	1,500-3,100
					\bigcirc	O'logente	
						16"	900-1,160
						27"	1,500-2,100
		_			_		

Grid: 5x5 = 1 in