


# Pike Hill Copper Mine Superfund Site Information Update - July 2022





# Pike Hill Copper Mine - Introduction

- The Pike Hill Copper Mine Superfund Site (Site) was placed on the EPA National Priorities List (NPL), also known as the Superfund list, in 2004
- The Pike Hill Copper Mine Superfund Site includes three separate mines along with the impacted areas of Pike Hill Brook and a tributary to Cookville Brook including downstream wetland areas.
- The Site is considered eligible for the National Register of Historic Places triggering the requirements of the National Historic Preservation Act.
  - Mining activities from 1846-1919.
  - Material brought to Elizabeth Mine in 1940s and 1950s.
- The Site hosts the largest known concentration of state-threatened eastern small-footed bats in Vermont and is historic habitat for the federally threatened northern long-eared bat.




# Pike Hill Copper Mine Superfund Site



## Site Description

The Pike Hill Copper Mine Superfund Site contains three sub-areas.

- Eureka Mine and Union Mine:
  - Drain to Pike Hill Brook watershed.
  - About 81,000 cubic yards of mine waste material extending over about 13 acres.
  - Underground workings (shafts and adits) and old foundations.
  - The section of Pike Hill Brook immediately downstream of the waste rock piles contains mine waste.
- Smith Mine:
  - Drains to a tributary of Cookville Brook.
  - About 0.5 miles south of the other mines.
  - There are three small waste piles over about 1 acre containing about 4,000 cubic yards of waste material.
  - Underground workings (shaft and adit).










Pike Hill Brook below waste piles



Tailings Piles below Eureka Mine







**Red and Pink line show stream segments that are list as impaired waters by the VT DEC**

**Red line:**


- contaminant concentrations consistently exceed standards,
- the water is acutely toxic to fish, and
- the benthic and fish communities are severely depleted and fails state criteria.

**Pink line:**

- contaminant concentrations periodically exceed standards, and
- the benthic and fish communities are less healthy when compared to reference locations and fails state criteria.

#### Legend

- ▲ Sampling Locations
- Extent of Severe Impairment
- Extent of Variable Impairment
- ⚒ Mine





## Pike Hill Copper Mine Superfund Site– Cleanup Objectives

- EPA is developing an Engineering Evaluation and Cost Analysis (EE/CA) to identify cleanup actions to address the impacts to Pike Hill Brook and a tributary of Cookville Brook.
- The objectives of the cleanup are listed below (updated since June presentation):
  - Control/reduce the release of MIW from mine waste to improve the composition and density of the aquatic community and reduce toxicity to the biota in Pike Hill Brook, the tributary to Cookville Brook, and associated wetlands.
  - Control/reduce the release of MIW from mine waste to reduce the loading of copper into Pike Hill Brook and the tributary to Cookville Brook and to lessen the area exceeding surface water quality standards.
  - Control the erosion of mine waste into Pike Hill Brook to reduce the transport of contaminants into Pike Hill Brook, reduce toxicity to biota, and improve the composition and density of the aquatic community in Pike Hill Brook.
  - Implement the response action in a manner that will minimize, to the extent practicable, impacts to federal and state threatened and endangered bats.
  - Implement the response action in a manner that will minimize, to the extent practicable, impacts to historic resources at the Site.



To accomplish the Removal Action Objectives, the EE/CA will evaluate two options:

- Alternative 1: Excavation and on-site consolidation/capping of mine waste in one or more containment cells, with in-place (referred to as "in-situ") stabilization of select areas of mine waste.
- Alternative 2: Excavation and off-site disposal of mine waste with in-situ stabilization of select areas of mine waste.
- Both alternatives would require some degree of long-term inspections and maintenance, known as Post-Removal Site Control.



## Pike Hill Copper Mine Superfund Site – Cleanup Alternatives

### Activities that are included in both Alternative 1 and Alternative 2:

- Survey and layout.
- Historic resource documentation and data recovery.
- Clearing, staging areas and erosion controls/stormwater management features.
- On-site access road construction (1.5 miles of on-site roads to widen and stabilize).
- Off-site (Town Road) improvements (safety improvements for 2 miles of narrow town roads).
- Excavation of approximately 65,000 cubic yards of mine waste.
- In-situ stabilization of mine waste in close proximity to the bat habitat (adding organic and alkalinity to buried waste material)
- Confirmation soil sampling.
- Restoration of areas disturbed by the cleanup, including wetland creation and the restoration of the segment of Pike Hill Brook that will be excavated.



Alternative 1: Excavation and on-site consolidation/capping of mine waste with in-situ stabilization of select areas of mine waste


Activities that are unique to Alternative 1:

- Installation of cover system over the containment cell (about 3-4 acres).
  - Bedding layer
  - Geomembrane
  - Drainage net
  - Protective soil or stone layer
  - Topsoil, is soil cover
- 2-3 years for implementation.
- An estimated 5,000 truck loads would be necessary to implement Alternative 1.
- \$18 million.

Alternative 2: Excavation and off-site disposal of mine waste with in-situ stabilization of select areas of mine waste

- Activities that are unique to Alternative 2:
- Transportation of 65,000 cubic yards of mines waste to an off-site disposal facility.
- 2-3 years for implementation.
- An estimated 6,700 truck loads would be necessary to implement Alternative 2.
- \$28 million






CONCEPTUAL  
EE/CA DRAWINGS

PIKE HILL COPPER  
MINE

SUPERFUND SITE  
CORINTH, VERMONT

NO.	DATE	DESCRIPTION
REVISIONS		




DATE:	JULY 2022
NOBIS PROJECT NO.	93201.18
DRAWN BY:	ATB
CHECKED BY:	BJK
CAD DRAWING FILE:	93201.18 SITE.dwg

SHEET TITLE

WASTE  
EXCAVATION  
AND CLEARING  
AREAS

FIGURE

2





nobis

Nobis Group® - 18 Chenell Drive  
Concord, NH 03301 - (603) 224-4182  
www.nobis-group.com

CONCEPTUAL  
EE/CA DRAWINGS

PIKE HILL COPPER  
MINE

SUPERFUND SITE  
CORINTH, VERMONT

NO.	DATE	DESCRIPTION
REVISIONS		

0 80' 160'  
GRAPHIC SCALE


DATE: JULY 2022  
NOBIS PROJECT NO. 93201.18  
DRAWN BY: ATB  
CHECKED BY: BJK  
CAD DRAWING FILE:  
93201.18\_SITE.dwg

SHEET TITLE

PRELIMINARY  
WASTE  
CONTAINMENT CELL  
AND STAGING  
AREAS

FIGURE


3



LEGEND







	SHAFT LOCATION		EPHEMERAL STREAM
	ADIT LOCATION		EXISTING TREE LINE (APPROXIMATE)
	SEEP LOCATION		PROPERTY LINE
	MINE OPENING		PROPOSED TREE LINE
	TRENCH		CLEARING AREA
	OPEN CUT		APPROXIMATE LOCATION OF UNDERGROUND WORKINGS
	PERENNIAL STREAM		





## Waste Cell

- 67,000 cubic yards of waste
- 3 -acre surface area for cover
- Geomembrane cover
  - Soil or stone on top of geomembrane





## Example of waste rock excavation





## Example Cover System Installation








## Before and After Waste Pile Removal at a mine site










PIKE HILL COPPER MINE  
POTENTIAL HAUL ROUTE

## Road Access to Mine for Truck Traffic

- Most likely route is RT25 – Brook Road – Richardson Road.
- Traffic Plan will be developed.
- Major focus will be safety and minimizing inconvenience to locals.
- EPA will work with Town officials and local residents to address any road improvements required in advance of the hauling and make repairs that may be necessary during and after hauling.





## EE/CA Criteria Evaluation – Effectiveness and Cost

Alternative 1: Excavation and on-site consolidation/capping of mine waste with in-situ stabilization of select areas of mine waste.

- Achieve Removal Action Objectives:
  - Isolates the mine waste from water and oxygen to prevent the release of MIW.
  - Reduce impacts to Pike Hill Brook and a tributary of Cookville Brook.
  - Improves habitat for endangered species.
- Achieve federal and state regulations (ARARs).
- Less short-term impacts to community from truck hauling (5,000 truck loads).
- \$18 million.

Alternative 2: Excavation and off-site disposal of mine waste with in-situ stabilization of select areas of mine waste.

- Achieve Removal Action Objectives
  - Isolates the mine waste from water and oxygen to prevent the release of MIW.
  - Reduce impacts to Pike Hill Brook and a tributary of Cookville Brook.
  - Improves habitat for endangered species.
- Achieve federal and state regulations (ARARs).
- More short-term impacts to community from truck hauling (6,700 truck loads).
- Less historic resource impacts.
- \$28 million.



## EE/CA Criteria Evaluation - Implementability

Alternative 1: Excavation and on-site consolidation/capping of mine waste with in-situ stabilization of select areas of mine waste.

- Greater implementability:
  - Containment cell standard for mine waste (Elizabeth Mine, Ely Mine, Callahan Mine).
  - Less off-site transportation.
  - Schedule may be extended due to endangered species protections.

Alternative 2: Excavation and off-site disposal of mine waste with in-situ stabilization of select areas of mine waste.

- Less implementability:
  - Available capacity at a disposal facility (non-haz) and distance to a facility would be a major uncertainty.
  - Additional truck traffic increases potential community concerns.
  - Schedule may be extended due to endangered species protections.



## Pike Hill Copper Mine Superfund Site – Recommended Cleanup Alternative

- Why does EPA recommend implementing Alternative 1?
  - The Site represents a severe ongoing ecological threat as documented by multiple lines of evidence (surface water concentrations, benthic community studies, fish community studies, and toxicity testing).
  - The proposed Alternative 1 cleanup action would:
    - Greatly reduce acute impacts to aquatic organisms;
    - Reduce contaminant loading to downstream wetlands area;
    - Be the Least Environmentally Damaging Practicable Alternative to protect wetland and aquatic resources (as required under the federal Clean Water Act), and
    - Advance the source control cleanup while EPA continues the investigations to determine whether additional cleanup actions are needed for the groundwater, underground workings, stream sediments, or downstream waters (wetlands and streams) are being completed.
  - Alternative 1 was determined to be the most cost-effective cleanup approach to achieve the Removal Action Objectives.
  - A similar cleanup approach was successful at Elizabeth Mine and has been designed for the Ely Copper Mine.



## Pike Hill Copper Mine Superfund Site – Next Steps

- **Public Comment:**

- 30-day public comment period for the EE/CA, fact sheet and administrative record will begin August 3, 2022 and extend to September 2, 2022.
- A public hearing will be held August 23, 2022.
- You can provide comments at the hearing or email/mail comments to EPA prior to the end of the comment period.
  - Email: [hathaway.ed@epa.gov](mailto:hathaway.ed@epa.gov) or
  - mail: Edward Hathaway, Project Manager, USEPA Region 1, 5 Post Office Square, Suite 100, Mailcode: 07-1, Boston, MA 02109
- After EPA reviews and considers all of the comments received, an Action Memorandum will be developed to document the cleanup approach, which will include EPA's written responses to all of the substantive comments received.
- Following the Action Memorandum, EPA would develop a detailed design for the cleanup. The design phase could require 1-2 years. The actual cleanup work may not begin until 2024/2025 or later.



### Other Activities:

- Maintenance and inspections of the engineered cover system and other components of the NTCRA will be performed by the State of Vermont as Post-Removal Site Control.
  - The estimated annual cost is \$41,000/year.
  - The Post-Removal Site Control will be included in the Site-wide long-term monitoring, maintenance, and inspections once a final remedial action is selected for the Site.
- EPA will also continue the investigations to assess other areas of the Site, including: Underground Workings, groundwater, stream sediments, and downstream wetland areas.
- EPA will select a final remedy for the site to address any remaining contamination issues not addressed by this NTCRA.



# Pike Hill Mine Superfund Site- Site Contact Information

## US EPA Contacts:

Edward Hathaway, Project Manager  
USEPA Region 1  
5 Post Office Square, Suite 100  
Mailcode: HBT  
Boston, MA 02109  
(617) 918-1372  
[Hathaway.ed@epa.gov](mailto:Hathaway.ed@epa.gov)

Darriel Swatts, Public Affairs Specialist / Community  
Involvement Coordinator  
US EPA, Region 1  
5 Post Office Sq. Suite 100  
Mail Code: ORA01-3  
Boston, MA 02109-3912  
Office: 617-918-1065  
Cell: 857-329-3740  
Fax: 617-918-0617  
Email: [swatts.darriel@epa.gov](mailto:swatts.darriel@epa.gov)

## Vermont ANR Contacts:

John Schmeltzer, Co-Site Project Manager  
Sites Management Section  
VT DEC  
103 South Main Street, West Office Building  
Waterbury, VT 05671-0404  
tel: 802-241-5620  
[john.schmeltzer@vermont.gov](mailto:john.schmeltzer@vermont.gov)

Graham Bradley, PhD, Co-Site Project Manager  
Sites Management Section  
VTDEC  
103 South Main Street, West Office Building  
Waterbury, VT 05671-0404  
tel: 802-622-4129  
[grahame.Bradley@vermont.gov](mailto:grahame.Bradley@vermont.gov)