

#### **Kevin Mooney**

Senior Project Manager Global Operations - Environment, Health & Safety

General Electric Company 1 Plastics Ave. Pittsfield, MA 01201

T (413) 553-6610 kevin.mooney@ge.com

Via Electronc Mail

February 19, 2024

Mr. Christopher Smith EPA Project Manager U.S. Environmental Protection Agency New England Region Five Post Office Square, Suite 100 Boston, MA 02109

Re: GE-Pittsfield/Housatonic River Site

**Rest of River (GECD850)** 

**Revised Reach 5A Baseline Restoration Assessment Report** 

Dear Mr. Smith:

In accordance with December 21, 2023 conditional approval letter for a prior version of this report, enclosed for EPA's review and approval is GE's *Revised Housatonic River Reach 5A Baseline Restoration Assessment Report*, prepared for GE by AECOM.

Please let me know if you have any questions about the enclosed report.

Very truly yours,

Kevin G. Mooney

Senior Project Manager - Environmental Remediation

**Enclosure** 

Cc: (via electronic mail)

Dean Tagliaferro, EPA
Anni Loughlin, EPA
Tim Conway, EPA
John Kilborn, EPA
Richard Fisher, EPA
Joshua Fontaine, EPA
Christopher Ferry, ASRC Federal

Thomas Czelusniak, HDR Inc.

Scott Campbell, Taconic Ridge Environmental

Izabella Zapisek, Taconic Ridge Environmental

Michael Gorski, MassDEP

John Ziegler, MassDEP

Ben Guidi, MassDEP

Michelle Craddock, MassDEP

Jeffrey Mickelson, MassDEP

Mark Tisa, MassDFW

Jonathan Regosin, MassDFW

Betsy Harper, MA AG

Traci lott, CT DEEP

Susan Peterson, CT DEEP

Graham Stevens, CT DEEP

Carol Papp, CT DEEP

Lori DiBella, CT AG

Molly Sperduto, USFWS

Mark Barash, US DOI

Diane Evers, NOAA

James McGrath, City of Pittsfield

Andrew Cambi, City of Pittsfield

Michael Coakley, PEDA

Melissa Provencher, BRPC

Christopher Ketchen, Town of Lenox

R. Christopher Brittain, Town of Lee

Town Manager, Great Barrington

Town Administrator, Stockbridge

Town Administrator, Sheffield

Jim Wilusz, Tri Town Health Department

Andrew Silfer, GE

Andrew Thomas, GE

Matthew Calacone, GE

Dennis Lowry, AECOM

Michael Werth, Anchor QEA

Adam Ayers, Arcadis

James Bieke, Sidley Austin

Public Information Repository at David M. Hunt Library in Falls Village, CT

**GE Internal Repository** 



# Revised Housatonic River Reach 5A Baseline Restoration Assessment Report

Pittsfield, Massachusetts

February 2024

Prepared for General Electric Company Pittsfield, Massachusetts

# Revised Housatonic River Reach 5A Baseline Restoration Assessment Report

Pittsfield, Massachusetts

February 2024

Prepared for
General Electric Company
1 Plastics Avenue
Pittsfield, Massachusetts 01201

Prepared by
AECOM
500 Enterprise Drive
Rocky Hill, Connecticut 06067



# TABLE OF CONTENTS

1.0	Introduction and Objectives1					
	1.1	Background				
	1.2	Restor	ration Performance Standards	2		
	1.3	Reach	5A BRA Objectives	2		
	1.4	Reach	Reach 5A BRA Requirements			
	1.5	Reach	5A BRA Organization	4		
2.0	Ove	view o	of Approach for Reach 5A BRA	5		
3.0	Reach 5A BRA of Riverine Habitats					
	3.1	Background Ecological Information				
		3.1.1	Woodlot Ecological Characterization (2002)	7		
		3.1.2	RCRA Facility Investigation Report (2003)	8		
		3.1.3	EPA Modeling (2006)	9		
		3.1.4	Corrective Measures Study Reports (2008-2010)	9		
		3.1.5	Stantec Bank Studies (2009)	10		
		3.1.6	Example Area Evaluations (2010)	11		
		3.1.7	Natural Heritage Information (2000-2022)	12		
		3.1.8	Pre-Design Investigations of Reach 5A 1			
		3.1.9	3.1.9 Other Existing Information14			
	3.2	2022 Riverine Habitat Investigations				
		3.2.1	Overview of Approach and Methods	15		
		3.2.2	RBP Physical Habitat Survey	16		
			3.2.2.1 Methods	16		
			3.2.2.2 Results	16		
		3.2.3	Benthic Macroinvertebrate Survey	18		
			3.2.3.1 Methods	18		
			3.2.3.2 Results	20		
		3.2.4	Assessment of Fish Species	22		
			3.2.4.1 Methods	22		
			3.2.4.2 Results	23		
		3.2.5	Incidental Direct Wildlife Observations	24		
		3.2.6	Aquatic Plant and Invasive Species Observations	25		
	3.3	Descri	ption of Reach 5A Riverine Habitats	25		



		3.3.1	Habitat	Types Within the Riverine Environment	25
		3.3.2	Hydrolo	gy and Physical Features	26
		3.3.3	Biologic	al Communities	28
	3.4	Reach	5A Riveri	ne Habitat Functional Assessment	30
4.0	Read	h 5A B	RA of R	Riverbank Habitats	35
	4.1	Backgr	ound Eco	ological Information	35
		4.1.1	Woodlo	ot Ecological Characterization (2002)	35
		4.1.2	RCRA F	acility Investigation Report (2003)	36
		4.1.3	EPA's M	lodeling (2006)	36
		4.1.4	Correcti	37	
		4.1.5	Stantec Bank Studies (2009)		38
		4.1.6	•	e Area Evaluations (2010)	
		4.1.7	Natural Heritage Information (2000-2022)		
		4.1.8		ign Investigations of Reach 5A	
	4.2	2022 Riverbank Habitat Investigations			
		4.2.1		ls	
		4.2.2			
			4.2.2.1	Physical Characterization	
			4.2.2.2	Bordering Habitats	
			4.2.2.3	Hydrologic Characterization	
			4.2.2.4	Plant Community Composition	44
			4.2.2.5	Other Habitat Features	45
			4.2.2.6	Incidental Direct Wildlife Observations	46
			4.2.2.7	Rare Species Habitat	46
	4.3	Description of Reach 5A Riverbank Habitats		47	
		4.3.1	Physical	Description	47
		4.3.2	Biologic	cal Communities	47
	4.4	Reach	5A Riverk	oank Habitat Functional Assessment	48
5.0	Read	ch 5A B	RA of B	Backwater Habitats	51
	5.1	Backgr	ound Eco	ological Information	51
		5.1.1		et Ecological Characterization (2002)	
		5.1.2	RCRA F	acility Investigation Report (2003)	52
		5.1.3	Correcti	ve Measures Study Reports (2008-2010)	52
		5.1.4	Example	e Area Evaluations (2010)	52



		5.1.5	Natural	Heritage Information (2000-2022)	52	
		5.1.6	Pre-Des	sign Investigations of Reach 5A	53	
	5.2	2022-2023 Backwater Habitat Investigations				
		5.2.1	Method	ds	54	
		5.2.2	Overvie	ew of Reach 5A Backwaters	55	
		5.2.3	Results.	57		
			5.2.3.1	Physical Characterization	57	
			5.2.3.2	Bordering Habitats	57	
			5.2.3.3	Hydrologic Characterization	57	
			5.2.3.4	Plant Community Composition	58	
			5.2.3.5	Other Habitat Features	59	
			5.2.3.6	Incidental Wildlife Observations	59	
			5.2.3.7	Rare Species Habitat	60	
			5.2.3.8	Water Quality	60	
	5.3	Description of Reach 5A Backwater Habitats				
	5.4	Reach 5A Backwater Habitat Functional Assessment				
6.0	Rea	each 5A BRA of Floodplain Habitats (excluding Vernal Pools)				
5.0	6.1	Background Ecological Information				
		6.1.1				
		6.1.2		acility Investigation Report (2003)		
		6.1.3	Corrective Measures Study Reports (2008-2010)			
		6.1.4		e Area Evaluations (2010)		
		6.1.5	Natural	Heritage Information (2000-2022)	66	
		6.1.6	Pre-Des	sign Investigations of Reach 5A Floodplain	67	
	6.2	Baseline Mapping and Classification of Floodplain Habitats			68	
		6.2.1	Method	ds	68	
		6.2.2	Results.		71	
	6.3	2022 Floodplain Wetland Habitat Investigations			74	
		6.3.1	Method	ds	74	
		6.3.2	Results.		76	
			6.3.2.1	Plant Community Composition	76	
			6.3.2.2	NRCS Soils	77	
			6.3.2.3	Other Habitat Features	79	
			6.3.2.4	Incidental Direct Wildlife Observations	79	



			6.3.2.5	Rare Species Habitat in Wetland Floodplains	80	
		6.3.3	Descrip	tion of Reach 5A Floodplain Wetland Habitats	80	
		6.3.4	Reach 5A Floodplain Wetland Functional Assessment8			
	6.4	2022 Floodplain Upland Habitat Investigations			89	
		6.4.1	Method	ds	89	
		6.4.2	Results.		90	
			6.4.2.1	Plant Community Composition	90	
			6.4.2.2	Other Habitat Features	91	
			6.4.2.3	Incidental Direct Wildlife Observations	91	
			6.4.2.4	Rare Species	91	
		6.4.3	Descrip	tion of Reach 5A Floodplain Upland Habitats	91	
		6.4.4	Reach 5	5A Floodplain Upland Habitat Functional Assessment	93	
	6.5	Exposi	ure Area	10 (Canoe Meadows) Base Mapping	94	
7.0	Reach 5A BRA of Vernal Pool Habitats					
	7.1	2018-2	2020 Read	ch 5A Vernal Pool Investigations	96	
	7.2		2022-2023 Reach 5A Vernal Pool Investigations			
		7.2.1	Method	ds	97	
		7.2.2	Results.		101	
			7.2.2.1	Plant Community Composition	101	
			7.2.2.2	Pool Physical and Chemical Characteristics	102	
			7.2.2.3	Habitat Characteristics in the Adjacent Landscape	105	
	7.3	Descri	ption of F	Reach 5A Vernal Pool Habitat	105	
	7.4	Reach	5A Verna	al Pool Functional Assessment	106	
8.0	Reac	h 5A A	Assessm	ent of Rare Species	107	
	8.1	Metho	ds		107	
		8.1.1	Federal	ly Listed Species	107	
		8.1.2	State-Li	isted Species	107	
	8.2	Result	s		108	
		8.2.1	Federal	ly Listed Species	108	
		8.2.2	State-Li	isted Species and Reach 5A Core Habitats	109	
9.0	Reac	h 5A I	nvasive	Species	115	
	9.1	Metho	1ethods			
	92	Results				



10.0Pre	eliminary Identification of Degraded Habitats and Restoration Oppo	ortunities
in I	Reach 5A	119
10.1	1 Identification of Disturbed or Degraded Habitats	119
10.2	2 Identification of Restoration Opportunities	121
11.0 Տսլ	oplemental BRA Activities and Anticipated Schedule	123
12.0Ref	ferences	125



#### LIST OF TABLES

- Table 3-1: Reach 5A Riverine Habitat Characterization
- Table 3-2: RBP Riverine Parameters Collected
- Table 3-3: RPB Results Instream Features and Large Woody Debris (LWD) Coverage
- Table 3-4: RPB Results Aquatic Vegetation and Substrate Characteristics
- Table 3-5: RBP Habitat Assessment Parameters
- Table 3-6: Macroinvertebrate Survey Results Compiled by Order
- Table 3-7: Macroinvertebrate Survey Results- Taxa Measures
- Table 3-8: Small Fish Species Trapping Results
- Table 3-9: Fish Composition Results from Electrofishing in Lower Reach 5A
- Table 3-10: Wildlife Observations Made During the 2022 Riverine Survey
- Table 3-11: State-Listed Rare Species Associated with the Aquatic Riverine Habitats of Reach 5A
- Table 3-12: Reach 5A Riverine Function Assessment Factors
- Table 4-1: Reach 5A Riverbank Habitat Characterization
- Table 4-2: Reach 5A Riverbank Summary Data
- Table 4-3: Reach 5A Riverbank Sediment/Substrate Composition
- Table 4-4: Reach 5A Riverbank Hydrology Ratings: Channel Gradient, Incisement, and Floodplain Connectivity
- Table 4-5: Reach 5A Riverbank Bordering Habitat Types
- Table 4-6: Reach 5A Riverbank Biotic Habitat Features
- Table 4-7: Reach 5A Riverbank Habitat—Physical Bank Habitat Features
- Table 4-8: Reach 5A Riverbank Plant Species Summary Data
- Table 4-9: Reach 5A Riverbank Plant Community Inventory Left Bank
- Table 4-10: Reach 5A Riverbank Plant Community Inventory Right Bank
- Table 4-11: Reach 5A Riverbank Plant Community Inventory Riparian Vegetation Cover
- Table 4-12: Reach 5A Riverbanks: Other Wildlife Habitat Features
- Table 4-13: Incidental Direct Wildlife Observations at Bank Survey Stations
- Table 4-14: Reach 5A Riverbank MNHESP Rare Species and Core Area Habitat Designation
- Table 4-15: Reach 5A Riverbank Function Assessment Factors
- Table 4-16: Reach 5A Riverbank Restoration Opportunities
- Table 5-1: Reach 5A Backwater Habitat Characteristics
- Table 5-2: Reach 5A Backwater Plant Species Summary Data
- Table 5-3: Reach 5A Backwaters Biotic Habitat Features
- Table 5-4: Reach 5A Backwaters: Summary of Biotic Habitat Features
- Table 5-5: State-Listed Rare Species Potentially Associated with Backwater Habitats of Reach 5A
- Table 5-6: Reach 5A Backwater Function Assessment Factors
- Table 5-7: Water Chemistry of Backwater Habitats of Reach 5A



- Table 6-1: Reach 5A Wetland Community Types
- Table 6-2: Reach 5A Upland Community Types
- Table 6-3: Comparison of Natural Community Cover Types Mapped Between 2002 and 2023
- Table 6-4: Reach 5A Floodplain Wetland Habitat Characterization
- Table 6-5: Reach 5A Floodplain Plant Species Summary Data
- Table 6-6: Percent Cover of Trees, Shrubs, Woody Vines, Herbs and Mosses Estimated Within Each Floodplain Natural Community Cover Type
- Table 6-7: Reach 5A NRCS Soil Series Mapping
- Table 6-8: Reach 5A Floodplain Natural Communities: Biotic Habitat Features
- Table 6-9: Reach 5A Floodplain Natural Communities: Summary of Biotic Habitat Features
- Table 6-10: Wildlife Observations Made During the 2022 Floodplain Surveys
- Table 6-11: State-Listed Rare Species Potentially Associated with Floodplain Wetland Habitats in Reach 5A
- Table 6-12: Reach 5A Floodplain Wetland Function Assessment Factors
- Table 6-13: Reach 5A Floodplain Upland Habitat Characterization
- Table 6-14: Reach 5A Plant Species in Upland Natural Communities Summary Data
- Table 6-15: Percent Cover of Trees, Shrubs, Woody Vines, Herbs, and Mosses Estimated within Upland Natural Community Cover Types
- Table 6-16: Reach 5A Upland Natural Communities: Biotic Habitat Features
- Table 6-17: Reach 5A Upland Natural Communities: Summary of Biotic Habitat Features
- Table 6-18: State-Listed Rare Species Potentially Associated with Floodplain Upland Habitats in Reach 5A
- Table 6-19: Reach 5A Floodplain Upland Function Assessment Factors
- Table 6-20: Canoe Meadows Bird Observations
- Table 7-1: Data Collected in 2018-2019 on Vernal Pools in Reach 5A
- Table 7-2: Habitat Characteristics within Reach 5A Vernal Pools and the Adjacent Landscape
- Table 7-3: Summary Statistics of Vernal Pool Vegetation Cover, In-Pool Physical Structure, and the Adjacent Landscape
- Table 7-4: Reach 5A Plant Species Summary Data for Certified Vernal Pools
- Table 7-5: Soil and Water Chemistry within 15 Randomly Selected Vernal Pools
- Table 7-6: State-Listed Rare Species Potentially Associated with Vernal Pool Habitats in Reach 5A
- Table 7-7: Reach 5A Vernal Pool Tier Ratings
- Table 8-1: State-Listed Species with Species Habitat Mapping Overlapping Reach 5A as shown on MNHESP Data Provided in October 2022
- Table 10-1: Reach 5A BRA Form H: Site Degradation/Disturbance Evaluation Criteria

vii



#### LIST OF FIGURES

Figure 1-1: Reaches 5-8 Housatonic River – Pittsfield, MA

Figure 1-2: Reach 5A of the Rest of River

Figures 3-1a – 3-1d: Reach 5A Riverine Habitat Investigations

Figure 3-2: Riverine Inorganic Substrate Components of Reach 5A

Figures 4-1a – 4-1d: Reach 5A Riverbank Habitat Investigations

Figure 5-1: Reach 5A Backwaters and Natural Communities

Figure 6-1: Example Areas within Floodplain Habitats

Figures 6-2a – 6-2e: Reach 5A Natural Communities

Figures 6-3a – 6-3e: Reach 5A Surface Hydrology and Drainage Features

Figure 6-4: Wetland Functional Units in Reach 5A

Figure 6-5: NRCS Mapped Soils in Reach 5A

Figure 6-6: Typical Cross-Section Through Riverine and Floodplain Habitats in Reach 5A

Figure 6-7: Canoe Meadows (EA 10) Existing Conditions Map

Figure 7-1: Reach 5A MNHESP Certifiable Vernal Pools

Figure 7-2a – 7-2e: Soil and Water Chemistry; Measures of Central Tendency and Boxplots

Figure 8-1: NHESP Priority Habitats

Figure 8-2: Reach 5A NHESP Core Areas

Figures 10-1a – 10-1e: Reach 5A Disturbed Areas



#### LIST OF APPENDICES

- A. Riverine Habitat Information
  - 1a. RBP Physical Data Sheets
  - 1b. Incidental Wildlife Observations
  - 2. Benthic Macroinvertebrate Results and Field Data Sheets
  - 3. Fisheries Photo Log
- B. Riverbank Habitat Inventory Forms
- C. Backwater Habitat Inventory Forms
- D. Floodplain Habitat Information
  - 1. Floodplain Habitat Photo Log
  - 2. Form FP-1 (Blank)
  - 3. Incidental Wildlife Observations During Floodplain Surveys
- E. Wetland Function and Value Assessment
- F. Vernal Pool Information
  - 1. Vernal Pool Photo Log (2018-2019)
  - 2. Form VP-1 (Blank)
- G. Rare Species Information
- H. Invasive Species Information
  - 1. Identification of Invasive Plant Species in Reach 5A
  - 2. General Information on Primary Invasive Species Identified



#### **ABBREVIATIONS**

BANCS Bank Assessment for Non-Point Source Consequences of Sediment

BEHI Bank Erosion Hazard Index

BRA Baseline Restoration Assessment

CD Consent Decree

cfs cubic feet per second

CMS Corrective Measures Study

dbh diameter at breast height (of trees)

EA Exposure Area

EFDC Environmental Fluid Dynamics Code
EPA U.S. Environmental Protection Agency

FEMA FIS Federal Emergency Management Agency Flood Insurance Study

Final Accessibility Report Final Morphology and Accessibility Survey Report Final Revised SOW Final Revised Rest of River Statement of Work

GE General Electric Company
GPS global positioning system

HEC-RAS Hydrologic Engineering Center River Analysis System (USACE)

HHA Hydrologic/Hydraulic Analysis

IPaC Information for Planning and Consultation (USFWS)

IPANE Invasive Plant Atlas of New England

LGS Low Gradient Stream

LiDAR Light Detection and Ranging

LWD Large Woody Debris

Massachusetts Division of Fisheries and Wildlife

mg/kg milligram per kilogram
MGS Medium-gradient Stream

MIPAG Massachusetts Invasive Plant Advisory Group

MNHESP Massachusetts Natural Heritage and Endangered Species Program

NBS Near-Bank Stress

PCBs polychlorinated biphenyls
PDI pre-design investigation
PSA Primary Study Area

RBP EPA Rapid Bioassessment Protocol

RCRA Resource Conservation and Recovery Act

RCMS Revised Corrective Measures Study for Housatonic Rest of River

RD/RA Remedial Design/Remedial Action

Revised Permit Revised Final RCRA Permit Modification

RFI RCRA Facility Investigation

RMS Red Maple Swamp



ROR Rest of River
RU Remediation Unit

SOP Standard Operating Procedure

SOW Statement of Work

UAV Unoccupied aerial vehicle
USACE U.S. Army Corps of Engineers

USDA NRCS U.S. Department of Agriculture Natural Resource Conservation Service

USFWS U.S. Fish and Wildlife Service

USGS U.S. Geological Survey
WMA Wildlife Management Area

Woodlot Woodlot Alternatives, Inc (now Stantec)
WWTF/P Wastewater Treatment Facility/Plant

YSI Yellow Springs Instrument

February 2024



# 1.0 Introduction and Objectives

### 1.1 Background

On December 16, 2020, pursuant to the 2000 Consent Decree (CD) for the GE Pittsfield/Housatonic River Site (EPA and GE 2000), the U.S. Environmental Protection Agency (EPA) issued to the General Electric Company (GE) a final revised modification of GE's Resource Conservation and Recovery Act (RCRA) Corrective Action Permit (Revised Permit) for the Housatonic Rest of River (ROR) (EPA 2020). The ROR is defined as that portion of the Housatonic River and its backwaters and floodplain (excluding Actual/Potential Lawns as defined in the CD) downstream of the confluence of the East and West Branches of the Housatonic River (the Confluence) in Pittsfield, Massachusetts. The ROR is shown on Figure 1-1, including river reach designations established by EPA within it, as well as the Housatonic River contributing watershed above Rising Pond (Reach 8). The Revised Final Permit set forth a Remedial Action selected by EPA to address polychlorinated biphenyls (PCBs) in the ROR.

The Revised Final Permit required GE to develop and submit a Statement of Work (SOW) specifying the deliverables and activities that GE will conduct to design and implement the ROR Remedial Action. In accordance with that requirement, after receipt of EPA's comments on an earlier version, GE submitted a Final Revised Rest of River Statement of Work on September 14, 2021 (Final Revised SOW; Anchor QEA et al. 2021), and EPA approved it on September 16, 2021.

Section II.B.1.c.(2)(a) of the Revised Permit requires GE to conduct a Baseline Restoration Assessment (BRA) of areas that will be affected by the ROR Remedial Action. Sections 4.2.1.4 and 4.2.1.5 of the Final Revised SOW describe the work plan for and report on the BRA in more detail.

Pursuant to the Revised Permit requirement, on December 22, 2021, GE submitted a *Baseline Restoration Assessment Work Plan* (initial BRA Work Plan) to meet those requirements. On March 31, 2022, EPA issued a conditional approval letter for that initial BRA Work Plan. Among other conditions, that letter required GE to submit a focused BRA Work Plan for Reach 5A of the ROR – the first ROR area to be addressed under the Revised Permit – in advance of revising the overall BRA Work Plan to cover other areas of the ROR. Reach 5A is shown in more detail on Figure 1-2. On May 16, 2022, GE submitted a Reach 5A BRA Work Plan. On June 29, 2022, EPA issued a conditional approval letter for that work plan, requiring several modifications to be incorporated in a revised work plan. On July 14, 2022, GE submitted a Revised Reach 5A BRA Work Plan (the "Revised Reach 5A BRA Work Plan" or "Revised Work Plan"; AECOM 2022). The Revised Work Plan presented the processes and activities that GE planned to conduct to identify and document the existing ecological conditions and functions in Reach 5A. On July 18, 2022, EPA approved the Revised Reach 5A BRA Work Plan. GE subsequently initiated data collection for the Reach 5A BRA, which was conducted from July 2022 through June 14, 2023.



As prescribed in the Revised Permit, the Final Revised SOW, and the Revised Reach 5A BRA Work Plan, following implementation of the studies outlined in the Revised Work Plan, GE was to prepare a BRA Report to present the results. That report was initially submitted to EPA on August 25, 2023, providing for Reach 5A a description and assessment of the pre-remediation conditions, functions, and values of river bottom, riverbank, backwater, floodplain, impoundment, and vernal pool habitats, as well as the identified occurrence of federal or state-listed threatened or endangered species or other state-listed species and any invasive species in the areas affected by the remediation. EPA conditionally approved that report by letter dated December 21, 2023, which directed GE to submit a revised report addressing the conditions in EPA's letter. This document constitutes that Revised Reach 5A BRA Report.

#### 1.2 Restoration Performance Standards

The Performance Standards for restoration of disturbed areas in the ROR, as provided in Section II.B.1.c.(1) of the Revised Permit and summarized in Section 2.1.3 of the Final Revised SOW, are to: (1) implement a comprehensive program of restoration measures to address the impacts of the Corrective Measures on affected ecological resources, species, and habitats, including, but not limited to, riverbanks, riverbed, floodplain, wetland habitat, and the occurrence of threatened, endangered, or other state-listed species and their habitats; and (2) return areas disturbed by remediation activities to pre-remediation conditions (e.g., the functions, values, characteristics, vegetation, habitat, species use, and other attributes) to the extent feasible and consistent with the remediation requirements. Under Section II.B.1.c.(2) of the Revised Permit, these Performance Standards will be achieved through a program designed to address the potential impacts of remediation, which will be specified in the following series of documents: (1) a BRA Work Plan; (2) a Restoration Performance Objectives and Evaluation Criteria Report; (3) Restoration Corrective Measures Coordination Plans; and (4) Restoration Plans. Each of those documents was described further in the Final Revised SOW. The Final Revised SOW also specified that following the BRA for each Remediation Unit (RU), a BRA Report would be submitted for that RU. As noted above, this document constitutes a revised BRA report for Reach 5A.<sup>1</sup>

## 1.3 Reach 5A BRA Objectives

The Reach 5A BRA is intended to provide a detailed baseline ecological inventory and assessment of pre-remediation conditions and functions of the affected habitats within Reach 5A and thus to serve as the foundation for meeting the restoration Performance Standards set forth in Section II.B.1.c.(1) of the Revised Permit as applicable to this reach. The conditions and features identified in this BRA

<sup>&</sup>lt;sup>1</sup> In addition, GE prepared the required Restoration Performance Objectives and Evaluation Criteria Report on a site-wide basis. That report was initially submitted on August 25, 2023, and was conditionally approved by EPA by letter dated January 29, 2024, which required GE to revise and resubmit that report within 75 days.



Report are also to be used in concert with engineering considerations in an effort to site access roads and staging areas in areas with lower habitat values where practicable. That information was also taken into account in GE's Conceptual Remedial Design/Remedial Action (RD/RA) Work Plan for Reach 5A (Anchor QEA et al. 2023), which was submitted on September 28, 2023 and is currently under review by EPA.

#### 1.4 Reach 5A BRA Requirements

Section II.B.1.c.(2)(a) of the Revised Permit and Section 4.2.1.4 of the Final Revised SOW set forth the requirements for the BRA Work Plan. Those requirements and the requirements in Section 4.2.1.5 of the Final Revised SOW indicate that the BRA for each subject area in the ROR, including Reach 5A, is to include the following elements:

- Identification of the presence and location of specific habitat types, including delineation of existing wetlands;
- Identification of the presence, location, abundance, and condition of federal or state-listed threatened or endangered species or other state-listed species and their habitats, as well as other representative species;
- Identification of the presence, location, abundance, and condition of invasive species;
- Evaluation of vernal pool locations, hydrology, and species use; and
- Characterization of physical/biological attributes of affected habitats (e.g., substrate characteristics, water depth, velocity, temperature, elevation/bathymetry, species composition, density, percent cover, and structural components).

In addition, EPA's March 31 and June 29, 2022 conditional approval letters set forth a number of specific requirements that were addressed in the Revised Reach 5A BRA Work Plan and are thus required to be part of the BRA; and EPA's December 21, 2023 conditional approval letter for the initial Reach 5A BRA Report specified a number of items to be addressed in this Revised Reach 5A BRA Report.

The Revised Reach 5A BRA Work Plan noted that, following the submission of the Reach 5A BRA Report, supplemental BRA activities will be necessary after the footprint of the remediation has been developed and support areas (access roads and staging areas) have been identified, as specified in the Conceptual RD/RA Work Plan for Reach 5A, and that those supplemental BRA activities would be identified in the Reach 5A BRA Report or the Conceptual RD/RA Work Plan.<sup>2</sup> It notes further that

\_

<sup>&</sup>lt;sup>2</sup> In fact, as discussed in Section 11, the supplemental BRA activities were proposed in Section 5 of GE's Supplemental Data Collection Work Plan, which was attached to the Conceptual RD/RA Work Plan for Reach 5A, submitted on September 28, 2023.



other supplemental BRA activities will be conducted as necessary to complete the BRA, and that the results of the supplemental BRA activities will be reported in an addendum to the Reach 5A BRA Report.

#### 1.5 Reach 5A BRA Organization

Consistent with Revised Reach 5A Work Plan, this Revised Reach 5A BRA Report is organized according to the major habitat types which occur in Reach 5A. Section 2 provides an overview of the approach taken for this report. Sections 3 through 7 provide baseline ecological descriptions of the riverine, riverbank, backwater, floodplain wetland, floodplain upland, and vernal pool habitats in Reach 5A, respectively. Following those habitat assessments, Section 8 presents information on federally listed and state-listed species in Reach 5A, and Section 9 addresses invasive species identified in the different habitats. Section 10 presents information obtained during the BRA on: (a) floodplain areas with disturbed or degraded habitats that could be considered candidates for access roads and staging areas for the Reach 5A remediation; and (b) potential restoration opportunities in Reach 5A. Finally, Section 11 describes anticipated scheduling and supplemental BRA activities.



# 2.0 Overview of Approach for Reach 5A BRA

The general approach for conducting the BRA for each major habitat type in Reach 5A has been consistent among the habitats. For each habitat type, the initial step was to consolidate and summarize prior reports and investigations that included characterization of that habitat and ecological conditions of or applicable to Reach 5A. The relevant prior investigations through 2020 were described in Section 2 of the Revised Reach 5A BRA Work Plan. In addition, consideration was given to relevant information from the pre-design investigation (PDI) conducted in Reach 5A from December 2021 through July 2023 in accordance with GE's Revised Pre-Design Investigation Work Plan for Reach 5A Sediment and Riverbanks (Revised Reach 5A Sediment/Bank PDI Work Plan; Anchor QEA and AECOM 2022), submitted on May 2, 2022 and approved by EPA on June 1, 2022, as well as other existing information from other sources. This information was supplemented with the results of the specific habitat investigations conducted in 2022 and 2023 in accordance with the Revised Reach 5A BRA Work Plan.

Each of the habitat-specific sections of this Revised BRA Report begins by presenting the pertinent information relating to the subject habitat from the prior sources described in Section 2 of the Revised Reach 5A BRA Work Plan, as well as pertinent information from the Reach 5A PDI and other existing sources. It next presents the results of the specific BRA investigations conducted for the subject habitat, and it then describes the subject habitat based upon the collective information assembled from all sources and the functions provided by that habitat. This Revised BRA Report addresses the conditions in EPA's December 21, 2023 conditional approval letter for a prior version of this report and provides other updating.



#### 3.0 Reach 5A BRA of Riverine Habitats

Numerous protocols have been developed pertaining to the collection of field data for evaluating the ecological conditions, functions, and values of rivers and streams. From a site-wide perspective, investigations of the ROR over the past 20-25 years have encompassed many of the parameters incorporated into such protocols. Accordingly, consolidating pre-existing information on the relevant riverine habitats in Reach 5A was the first step in the BRA for that reach. In addition, the assessment of the riverine habitat incorporated information on key parameters from the field work conducted under the Revised Reach 5A Sediment/Bank PDI Work Plan and from additional field survey work in the Reach 5A river channel. These activities have collectively provided a comprehensive description of the riverine characteristics in Reach 5A. This approach recognizes that parameters encompassing the physical, hydrologic, and structural characteristics of the riverine system are linked to ecological functions and values. Physical processes form habitat in a stream channel. For example, importation of woody debris, movement of sediment over a range of flows, formation of scour and depositional features due to channel morphology and flow variability, and changes on dynamic riverbanks all establish habitat features. Combined with chemical constituents and biological interactions, physical habitat determines biological productivity and diversity, and drives the aquatic ecosystem.

Table 3-1 provides a summary of the parameters that were incorporated into the assessment of baseline riverine habitat conditions in Reach 5A. These include a broad range of riverine characteristics related to riverine geomorphology, hydrology, floodplain connectivity, riverbank conditions, in-stream habitat, aquatic biota, and bordering vegetative conditions.

The riverine habitat inventory process for Reach 5A included consolidating and incorporating existing information on riverine habitats that are specific or applicable to Reach 5A. The riverine habitat characterization for Reach 5A also included site-specific inventories and data collection, including a physical riverine habitat survey, a benthic macroinvertebrate survey, and a fish community survey, as described below. During these riverine surveys, information was also collected on the presence of aquatic plants and use of the riverine habitat by wildlife observed incidental to the data collection.

## 3.1 Background Ecological Information

As noted in Table 3-1, some of the riverine assessment parameters were based on information consolidated from the sources cited previously in Section 2 of the Revised Reach 5A BRA Work Plan. In other cases, the parameters were based on information drawn from other tasks or steps in the remedial investigation process, notably the Reach 5A PDI. Still other information, such as hydrologic/hydraulic data, was obtained from other available sources, as also noted in Table 3-1.



#### 3.1.1 Woodlot Ecological Characterization (2002)

On behalf of EPA, Woodlot Alternatives, Inc (Woodlot, now Stantec) conducted an ecological characterization of the Housatonic River and presented its findings in two documents (Woodlot 2002a, 2002b). The first document (Woodlot 2002a) includes information covering Reach 5A and is summarized below.

The ecological characterization study carried out by Woodlot included a variety of biological investigations which addressed rare plants, natural communities, dragonflies, freshwater mussels, reptiles, amphibians, raptors, waterfowl, forest birds, marsh, wading birds, small mammals, river otter, mink, and bats. In this section of the BRA Report, only findings from Woodlot's study which pertain specifically to the riverine habitat in Reach 5A will be discussed.

The Woodlot ecological characterization included a discussion of hydrologic influences in Reach 5A. Woodlot stated that "the main stem of the Housatonic River in this section has moderately fast water with pool, riffle, and run habitat. The channel walls are vertically cut and bottom substrate is often gravel and sand" (Woodlot 2002a, page III-1-6). Woodlot noted that the volume of water resources in the Primary Study Area (PSA), which consists of Reaches 5-6, was affected by industrial and municipal discharges that contributed significant flow quantities to the Housatonic River. Specific to Reach 5A, the Pittsfield Wastewater Treatment Facility (WWTF), which discharges its effluent at the downstream end of Reach 5A (near the midpoint of the PSA), contributes an average flow of 0.5 cms to the Housatonic River, representing approximately 17% of the local flow of the river.

Woodlot classified the Housatonic River from the Confluence to Holmes Road as medium-gradient stream (MGS), and south of Holmes Road as a low-gradient steam (LGS) with slow-moving water that may have abundant submerged aquatic plants. During its surveys, Woodlot found that riverine point bar and beaches occurred occasionally along the Housatonic River, including in Reach 5A, primarily near bends in the channel, while mud flats of limited size began to appear later in the season as the water levels declined and exposed previously flooded substrate. Channel banks were described as vertically cut and a number of mucky sand beaches and accretion bars were located that often harbored the rare mudflat spikesedge (*Eleocharis intermedia*).

During Woodlot's freshwater mussel surveys, only the triangle floater (*Alasmidonta undulata*) was found in Reach 5A. Woodlot noted in the discussion of mussel survey results that there are large areas of suitable habitat in the PSA that are uninhabited by mussels and that definitive reasons for the lack of mussels in these areas are unknown. It also noted that, during dragonfly surveys, a total of 38 Odonate species were recorded within the Housatonic River, one of which, riffle snaketail (*Ophiogomphus carolus*), was a state-listed rare species.



Fish populations were qualitatively and quantitatively sampled by Woodlot within the PSA during 1998-2000. Woodlot characterized the results of the fish species collected by feeding strategies (predator species, bottom feeders, forage fish). Fourteen species of fish were captured in Reach 5A during the 2000 biomass sampling events. White sucker (*Catostomus commersonii*), a bottom feeder, and largemouth bass (*Micropterus salmoides*), a predator, accounted for over 75% of the biomass in the samples from Reach 5A. Bluegill (*Lepomis macrochirus*), pumpkinseed (*Lepomis gibbosus*), cyprinids (Order *Cypriniformes*), and rock bass (*Ambloplites rupestris*) shared dominance of the forage fish group in Reach 5A. No rare, threatened, or endangered fish species were confirmed to exist in the PSA.

In an extensive listing of wildlife species associated with the various classified habitats, Woodlot specifically broke out medium-gradient and low-gradient stream habitat as distinct classes, and listed wildlife species associated with these habitats. However, the species compositions for these habitat classes did not specify those found in Reach 5A, but rather were more broadly listed for the entire PSA.

### 3.1.2 RCRA Facility Investigation Report (2003)

GE's 2003 RCRA Facility Investigation Report (RFI Report; BBL and QEA 2003) provided substantial information characterizing ecological resources in the ROR area, including the riverine habitats in Reach 5A. The focus of the RFI Report was on documenting the extent of PCBs in the river, which will not be summarized herein. However, in depicting PCB distribution, some relevant riverine habitat information was provided. For example, the RFI Report characterized the Reach 5A conditions as follows: "[B]etween the Confluence and the WWTF (Reach 5A), the River is relatively shallow and fast-flowing, due in large part to the relatively steep slope of the channel. This flow regime results in a high energy environment and a coarse sediment bed, both of with affect the transport of constituents that are bound to particulate matter" (RFI Report, page 8-4).

The RFI Report documented previous biota sampling activities that involved fish, plants, invertebrates, reptiles, amphibians, birds, and small mammals, providing ancillary information on faunal and floral species composition. The RFI Report noted that, with respect to the fish fauna, the cyprinids, such as dace, darters, and other minnows, are common in the upstream portion of Reach 5A. In summarizing water quality data, the RFI Report indicated that phytoplankton biomass in Reach 5A is relatively low (chlorophyll-*a* concentration of about 2 µg/L), but that nutrient levels in Reach 5A do support a well-defined community of periphyton. It explained that benthic invertebrate abundance increased in the downstream direction, which was consistent with riverbed characteristics in Reach 5A. The RFI Report also indicated that total abundance of benthic invertebrates (counts per ponar grab sample) in the 1999-2000 EPA data was relatively low in Reach 5A with counts that were typically 1.5 to two per sample as compared to five to six per sample downstream in Woods Pond.



#### 3.1.3 EPA Modeling (2006)

EPA's documentation of its modeling efforts for the ROR (EPA 2006), notably its hydrodynamic, sediment transport, and contaminant fate modeling using the Environmental Fluid Dynamics Code (EFDC), provides information on specific functions, such as riverine hydrodynamics, that can be used in characterizing riverine ecological functions, at least partially applicable to Reach 5A.

The EFDC modeling conducted by EPA provided calculations about the Housatonic River's continuous time series of flow, water depths, shear stresses, water surface elevations, and velocities, all of which affect habitat suitability to varying degrees. During the study, the movement of largemouth bass was assessed in Reach 5A. Fish movement was found to be limited but still sufficient to support spawning resident fish. Additionally, the study concluded that Reach 5A had a small amount of over-wintering largemouth bass habitat compared its downstream counterparts. It noted that free-flowing riverine habitat in the medium grade portions is generally made up of coarse substrates and affected by higher flow velocity. Periphyton in Reach 5A "attaches to coarse particles and to the soft bottom of open pools and slow-moving reaches. Periphyton cover in the free-flowing areas of Reaches 5 and 6 consists primarily of algae attached to the substrate, and the associated microorganisms found with the algae" (EPA 2006, page 2.4-11). It noted further that, due to less suitable conditions such as swift water velocity and scouring, macrophytes tend to be less common in Reach 5A. It indicated that, in free-flowing habitats like Reach 5A, white sucker dominated the fish community and feed on epifauna, while benthic communities mainly consist of the larvae of true flies (order *Diptera*).

# 3.1.4 Corrective Measures Study Reports (2008-2010)

In 2008, GE issued a Corrective Measures Study (CMS) Report, which provided detailed evaluations of remedial alternatives for the ROR (Arcadis and QEA 2008). During those evaluations, the CMS Report presented substantial information on ecological baseline conditions in the ROR, including Reach 5A riverine habitat conditions. In October 2010, GE issued a Revised Corrective Measures Study (RCMS) Report, which included additional remedial alternatives, provided an updated evaluation of the remedial alternatives, and responded to comments on the 2008 CMS Report (Arcadis et al. 2010). The RCMS Report included a substantially expanded description of the affected habitats in the ROR, including Reach 5A riverine habitats, and the ecological impacts and potential for restoration associated with the remedial alternatives.

With regard to the riverine habitat of Reach 5A, the RCMS Report described the habitat as including both medium-gradient stream areas from the Confluence to the Holmes Road Bridge and low-gradient stream areas throughout the entirety of the rest of Reach 5A. It noted that the transition is somewhat gradual with a boundary that is difficult to define. Additionally, riverine point pars were



noted to exist throughout Reach 5A along with mud flats in the lower water late summer months, but the extent of these mud flats was not quantified since it is dependent on river flow.

The RCMS Report discussed physical features within these habitat types in Reach 5A, describing the medium-gradient areas as having moderate water velocities with substrate dominated by coarse sand, gravel, and cobble, with small amounts of boulder and silt present. Depth in these areas was listed at 1.5 to five feet in the main channel, with most of the run habitat including some areas of riffle and pool. Riverine point bars were noted, but they only comprised approximately one acre of the entirety of the PSA.

Features within the low-gradient areas were described to include substrate dominated by silts, organic muck, and fine sand, with little gravel, cobble and boulder components; and it was noted that this area has considerable meanders throughout. Woody debris was described as being a major visual component of the medium-gradient areas and as present throughout Reach 5A, but often submerged in the low-gradient areas.

Biological communities within Reach 5A were also described in the RCMS Report, including aquatic vegetation, aquatic invertebrates, fish, and rare species habitats. It noted that the riverine habitat in Reach 5A hosts only sparse aquatic vegetation due to the sand and gravel substrate and high water velocity. Fisheries information on Reach 5A reported in the RCMS was primarily taken from Woodlot (2002a). More generally, the RCMS noted that "the Housatonic River is the major migration and dispersal corridor in the PSA. It provides opportunity for aquatic and semi-aquatic organisms, including numerous fish species, wood turtles (*Glyptemys insculpta*), beaver (*Castor canadensis*), and muskrat (*Ondatra zibethicus*), to seek out and navigate into suitable habitat. It also allows for transport of nutrients, sediment, and food items from upstream terrestrial and aquatic communities to downstream areas" (RCMS Report, page 5-16). Finally, the RCMS Report provided extensive detail on state-listed species mapping and habitats in Reach 5A, including many that use riverine habitats, at least for certain life cycle requirements.

## 3.1.5 Stantec Bank Studies (2009)

On EPA'S behalf, Stantec Consulting Services, Inc (Stantec) conducted an evaluation of riverbank erosion in Reaches 5A and 5B. Stantec used field surveys to determine Bank Erosion Hazard Index (BEHI) and Near-Bank Stress (NBS) ratings. This evaluation was presented in a report entitled *A Study of Bank Erosion Rates within Selected Reaches of the Housatonic River* (Stantec 2009). In Reaches 5A and 5B, data were collected in May of 2009 from approximately 41,000 linear feet of stream channel and 82,000 feet of streambank (both banks were surveyed). Riverine habitat conditions in Reach 5A were not specifically discussed in detail in this report, but riverbank conditions are closely related to and affect riverine conditions and habitat. Stantec described the areas of high bank erosion as being out of phase with the form of the river, with many areas of high and extreme erosion located



upstream of point bars and inside banks, indicating active channel migration and horizontal instability. However, no specific habitat factors were addressed in relation to this analysis.

### 3.1.6 Example Area Evaluations (2010)

In February 2010, GE submitted a Supplement to Interim Response presenting detailed evaluations of six Example Areas within Reaches 5A to 5C that were selected by EPA, four of which were located within Reach 5A (AECOM 2010). Those evaluations contain considerable information on the existing ecological conditions and functions in the selected Example Areas, as well as the impacts of remedial alternatives on those conditions and functions. Example Areas #1 and #2 both include sections of the Housatonic River within Reach 5A, and habitat descriptions of both were provided. These two Example Areas are shown on Figures 3-1a and 3-1b (also discussed in Section 3.2). (The other two Example Areas in Reach 5A consisted only of floodplain habitat and are discussed in Section 6.1.4.)

Example Area #1 contains approximately 1,600 linear feet (2.4 acres) of riverine habitat, characterized by a channel 40 to 60 feet in width and one to five feet in depth, a primarily sand substrate with smaller components of gravel or cobble, and substantial amounts of large woody debris. This section of river includes two sharp bends and one broad bend with sections of pool and riffle habitat as well as two depositional point bars. Example Area #2 contains approximately 1,650 linear feet of riverine habitat, and also has a sand substrate with significant gravel components in the upstream portion and significant silt components in the downstream portion. Like Example Area #1, there was large woody debris in Example Area #2, primarily in the downstream portion.

The Example Area evaluations provide considerable detail on the riverine habitats in both sections of the river in Reach 5A. In-stream habitat is described for each area, including substrate composition, riffle/run/pool distribution, aquatic vegetation, woody debris, and depositional features such as point bars. Descriptions are provided of the habitat use of these different features, including habitat for a range of aquatic invertebrates and fish, as well as overwintering habitat for turtles. Point bars present in these sections provide foraging grounds for mammals and birds, and emergent plant habitat for amphibian, invertebrate, and fish larvae (AECOM, 2010). The following points summarize the riverine habitat descriptions provided about Example Areas #1 and #2:

- Example Area #1 consists of 1,600 linear feet of medium gradient stream (MGS), whereas the similarly sized riverine habitat in Example Area #2 transitions from MGS in the upper portion to low gradient stream (LGS) in the downstream.
- Sand and gravel is the dominant substrate in MGS areas, whereas sand and silt is dominant in LGS areas. Very limited areas of cobble occur where increased water velocity transports the sand downstream.



- On an aerial basis, in-stream habitat in both Example Areas is dominated by run habitat, which is estimated at nearly 90% of the river. Pool habitat accounts for approximately 8-9% of the total habitat in these example areas, and riffle habitat is limited to only 1-2%. Most pool habitat in both Example Areas is associated with outside bends or downstream of large woody debris collection points.
- Large woody debris is substantial within both Example Areas, adding considerable structure
  and complex micro-habitats to the River. These natural structures alter sediment transport
  and impact flow patterns and erosive forces, creating variation in depth and substrate
  texture.
- Aquatic vegetation in this portion of the Housatonic River is limited to small patches in sandy areas, and the invasive curly-leaf pondweed (*Potamogeton crispus*) is the most abundant aquatic species in both Example Areas. Other aquatic plant species in this section of the river include Eurasian watermilfoil (*Myriophyllum spicatum*) and water celery (*Vallisneria americana*). Algal growths are generally limited by water velocity, but blue-green and green algal mats are present in a few areas, and diatoms coat many of the rocks.

## 3.1.7 Natural Heritage Information (2000-2022)

Investigations, data, mapping, and reports from the Massachusetts Natural Heritage and Endangered Species Program (MNHESP) of the Massachusetts Division of Fisheries and Wildlife (MassDFW) have been ongoing for at least the last two decades. These efforts included designation of Priority Habitats of rare species. This information described habitat conditions of state-wide significance and detailed the state-listed rare species (i.e., threatened, endangered, and special concern species) that were documented within the Priority Habitat limits delineated. In 2008-2009, MNHESP conducted rare species field surveys over thousands of hours to identify populations of state-listed rare species within the Upper Housatonic River Valley (MNHESP, 2010). As of 2010, this research confirmed the presence of at least 20 state-listed species in Reach 5A and resulted in the preparation of updated Priority Habitat mapping for each of these species, which was included in the 2010 RCMS Report. Many of these state-listed species are associated with riverine habitat in the Housatonic River, at least during some of the species' life stages. MNHESP also published two documents summarizing much of its investigations (MNHESP 2010, 2011).

The 2010 MNHESP report described rare species and natural community surveys in the Housatonic Watershed. Riverine habitats in Reach 5A were not specifically discussed; however, summaries were provided of riverine investigations documenting rare species with habitat requirements found within Reach 5A riverine habitat and included in the Priority Habitat mapping discussed above (MNHESP, 2010). The 2011 MNHESP report did note that one of the state's best populations of triangle floater mussels was documented in the Housatonic River in Pittsfield (2011, page 6); at the time, this was a



state-listed species, but it has since been de-listed. MNHESP concluded that "the project saw the updating of records and the discovery of many new occurrences of rare species and priority natural communities that were recently or historically known from the watershed, and also included the identification of several rare species never before documented in the watershed. There does not appear to have been a significant decline in the number of species or priority natural community types despite the long history of human influence in the watershed, although some have declined in abundance and distribution (population or occurrence quality)." (MNHESP 2011, pages 30-31.)

In July 2012, MassDFW issued a letter to EPA reporting on the designation of Core Habitat Areas within the ROR that were based upon the MNHESP state-listed species data and analyses (MassDFW 2012). This letter, which was attached to the Revised Permit, included maps depicting the locations of the different types of Core Areas, designated Core Area 1, 2, and 3, and presented the criteria for the designations.<sup>3</sup> All three types of Core Areas include some riverine habitats. There are four specific sections of the Housatonic River from the Confluence to Canoe Meadows where riverine habitat (and possibly riverbank habitat) is included in Core Area 1; it is noted that one of the species included in the MNHESP listing of Core Area 1 species is the triangle floater, which is no longer a state-listed species. However, one of the Core Area 1 plant species, the wapato (*Sagittaria cuneata*), may potentially be found in Reach 5A riverine habitat.

In October 2022, MNHESP provided GE with updated digital information that included Species Habitat mapping of the state-listed species in the ROR, including Reach 5A.<sup>4</sup> As described in Section 3.3 and further in Section 8, at least ten of these species utilize habitats consistent with those present in the Reach 5A riverine habitat and have mapped Species Habitat that includes the Reach 5A river channel.

# 3.1.8 Pre-Design Investigations of Reach 5A

The PDI conducted in Reach 5A collected a range of information on riverine conditions that contribute to habitat characteristics.<sup>5</sup> The PDI included detailed topographic and bathymetric surveys of the river, riverbanks, and floodplain to support the remedial design. All survey work was

<sup>&</sup>lt;sup>3</sup> Cores Areas 1, 2, and 3 are defined in Section 6.1.5 of this report. Section 8 of this report provides further information on the Core Habitat designations by MNHESP.

<sup>&</sup>lt;sup>4</sup> As discussed further in Section 8, Species Habitat Maps are species-specific maps prepared by MNHESP using the "best scientific evidence available," examining individual occurrence records and other set criteria to delineate the anticipated habitat area for an individual state-listed species. MNHESP also provides on-line, publicly available mapping of Priority Habitats of state-listed species, which is a regulatory layer consisting of combined Species Habitat Maps with "supporting habitat" added, where applicable.

<sup>&</sup>lt;sup>5</sup> The PDI of the sediments and riverbanks in Reach 5A was described in GE's *Pre-Design Investigation Summary Report for Reach 5A Sediments and Riverbanks* (Anchor QEA and AECOM 2023a), which was submitted to EPA on September 28, 2023 along with the Conceptual RD/RA Work Plan for Reach 5A.



conducted by Spicer Group, Inc., between December 2021 and May 2022 using a combination of methods and technologies, some of which pertain to the riverine habitat of Reach 5A, including the following:

- An aerial Light Detection and Ranging (LiDAR) survey was conducted in December 2021 over the entire length of Reaches 5 and 6 (i.e., from the Confluence to Woods Pond Dam).
- A bathymetry survey was conducted through the main channel and backwaters within Reaches 5 and 6. Data collected in Reach 5A were obtained using conventional survey methods. Specifically, within the main channel, bathymetric survey cross-sections were completed every 100 feet along the centerline of the river and at every main channel sediment sampling transect spaced 250 feet apart along the centerline of the river. Top-ofwater elevations were measured on both the left and right bank at every other transect.
- Water surface elevations and river current velocities were measured at various locations
  throughout Reach 5 to support development of a hydraulic model. Current velocities were
  measured at six cross-sections within Reach 5 using an acoustic Doppler current profiler.
  These six cross-sections included three locations in Reach 5A (Holmes Road bridge, adjacent
  to Joseph Drive, and near the Pittsfield WWTF). Additionally, this effort included the
  deployment of water level loggers at two locations (one of which was within Reach 5A) to
  continuously monitor water surface elevation.

Using the topography and bathymetry data sets described above, Spicer Group generated a contiguous digital elevation model (DEM) which indicates that the majority of the Reach 5A riverine habitat falls between 948 and 959 feet (NAVD88), with pockets that fall between 858 and 947 feet (mostly occurring in the southernmost stretches of Reach 5A).

The PDI also included a characterization of the riverine habitat in 5A. The PDI showed that the Reach 5A river is free-flowing, contains numerous meanders, and has riverbanks that are subject to erosion in places. The width of the river in this reach ranges from approximately 40 to 120 feet, and bankfull water depth ranges from approximately two to 10 feet. Additional surface water monitoring conducted in 2022 provided supplementary updated information on river stage, surface water elevations, and calculated flows, as described in GE's *Interim Baseline Surface Water Monitoring Report* (Anchor QEA and Arcadis 2023a).

# 3.1.9 Other Existing Information

A United States Geological Survey (USGS) gauge station (USGS 01197000) is present upstream on the East Branch of the Housatonic River at Coltsville. This gauge is about 5.4 miles upstream of the Confluence (i.e., the start of Reach 5A). The Coltsville gauge station provides substantial data on



water quantity and quality in the East Branch dating back to 1936. In particular, flow quantity and stage data from this station are used in defining the hydrologic and hydraulic conditions within Reach 5A of the Housatonic River. However, data from this station need to be qualified, since the station represents a watershed drainage area of 57.6 square miles, whereas the watershed drainage area above the Confluence is 134 square miles and includes the West Branch of the Housatonic River as well as the remaining watershed of the East Branch downstream of the Coltsville gauge station. Adjusting the Coltsville gauge station database to account for these watershed conditions, as done with various hydrologic models, provides hydrologic data for Reach 5A (e.g., bankfull flows), which strongly influence riverine habitat conditions. The method used for this adjustment followed the standard practice of relating such gauge station hydrologic data to various watershed locations as described in the Hydrologic/Hydraulic Analysis (HHA) included as Appendix G to the Reach 5A Conceptual RD/RA Work Plan. As described there, flow increment ratios (or drainage area ratios) are developed to relate measured flow at the USGS gauge to other downstream locations, adjusted to account for differences in land use and soil conditions in the subwatersheds. Flow ratios between the East and West Branches of the Housatonic were calculated using flows measured during GE's interim baseline surface water monitoring program (Anchor QEA and Arcadis 2023). These comparisons were used as an empirical baseline to support estimation of relative flow volumes in each branch. Those measurements were also used to develop a relationship between flows measured at the Confluence and flows recorded at the USGS Coltsville gauge. The HHA provides a full hydrological analysis of Reach 5A (as well as all of Reaches 5 and 6) to evaluate the statistical characteristics of flows within these portions of the ROR.

## 3.2 2022 Riverine Habitat Investigations

## 3.2.1 Overview of Approach and Methods

The consolidation and assimilation of the information described above were supplemented by additional field surveys of the baseline riverine habitat conditions in Reach 5A in August and September of 2022. Those surveys utilized the Habitat Assessment and Physiochemical Parameters methods from the EPA's Rapid Bioassessment Protocols (RBP) (Barbour et al. 1999), focusing on the structural parameters of the riverine habitat. Specifically, the physical characterization protocol of the RBP was implemented to document the riverine habitat conditions in Reach 5A, the macroinvertebrate sampling protocol for multi-habitat conditions was implemented, and additional fisheries surveys were also conducted, as described below. The RBP provided for an integrated assessment, comparing habitat (e.g., physical structure, flow regime), water quality, and biological measures. Use of the RBP provides for a systematic documentation of baseline conditions which could serve as a reference for post-remediation restoration assessment. As noted in the RBP, "the habitat quality evaluation can be accomplished by characterizing selected physicochemical



parameters in conjunction with a systematic assessment of physical structure. Through this approach, key features can be rated or scored to provide a useful assessment of habitat quality" (RBP, page 5-1).

### 3.2.2 RBP Physical Habitat Survey

#### 3.2.2.1 Methods

Use of the RBP employed the standard inventory forms for the physical characterization and habitat assessment. Those forms were completed for 18 riverine stations in Reach 5A and are provided in Appendix A-1a The forms include standard measures for documenting a variety of watershed, riparian, bank, and in-stream features. Included in the characterization are in-stream physical measures, aquatic vegetation, large woody debris, basic water quality parameters, sediment/substrate conditions, epifaunal habitat, flow regime, channel conditions, bank stability, and vegetative cover, as well as incidental wildlife observations. Details for each parameter collected are provided in Table 3-2. Substrate type areas were derived from visual observations of surficial sediments (aided by view tubes), sediment grab texture observations, and observations using intrusions in the sediment with steel poles in deep areas that were too deep to be observed. Estimates of habitat areas were provided in square feet, and then calculated in proportion to the overall area.

The 18 stations at which RBP assessments were conducted were distributed between the Confluence and the downstream end of Reach 5A, as shown on Figures 3-1a through 3-1d. These segments were set based on field evaluations of stream morphology patterns by AECOM scientists. The use of segments based on representative reaches following repetitive patterns in stream morphology allowed for evaluation of the entirety of the subject river habitat without the potential error associated with subsampling small portions of the river. Each station was selected to encompass an approximately proportionate amount of each river habitat feature type (run, riffle, pool) based on the river morphology as depicted on high-resolution aerial imagery. River habitat features are often correlated with the river morphology. For example, pools are typically located in meander bends and riffles and runs are typically found in straight sections. The field team recorded qualitative and quantitative habitat parameters in this pattern. Drought conditions and low water occurred during the field effort in August and September 2022. However, flow-dependent parameters were recorded as though the flow was in its normal condition using bank and bottom indicators to approximate normal flow.

#### 3.2.2.2 Results

The entirety of the resulting field data from the RPB data collection is provided in the completed forms in Appendix A-1a. The results for the RBP are summarized in Tables 3-3, 3-4, and 3-5.



Observations from the 18 stations provide a comprehensive evaluation of riverine habitat in the entire Reach 5A. The key findings are as follows:

- River morphology is a top-level indicator of habitat in both flow regime and substrate.
   Overall river morphology proportions observed in Reach 5A are Pool 53%, Run 41%, and
   Riffle 6%. Proportions of riffle and run were higher upstream and decrease downstream into a lower gradient regime.
- Substrate is the foundation of riverine habitat and creates habitat for the forage base of the biological community. Overall substrate proportions are as follows: Sand 42%, Gravel 21%, Silt 20%, Clay 8%, Cobble 7%, Boulder 2%, and Bedrock 0%. See Figure 3-2 (three sheets) and Table 3-4. These data were derived from recorded visual observations in accordance with the RBP protocols.
- Rocky substrate generally decreased from upstream to downstream.
- Overall organic substrate distributions are as follows: Detritus (leaves, small wood, and other organic matter) 9.5%, and Muck-Mud 2.6%. See Table 3-4.
- Large woody debris (LWD) was a consistent habitat component and the density is estimated at 33.1 m<sup>2</sup>/km<sup>2</sup> of riverine habitat across all stations, ranging from 7 to 122.8 m<sup>2</sup>/km<sup>2</sup>. Large, embedded root wads and trees demonstrably entrapped other large woody debris in the flow and created substrate for epifauna and cover for fish and other aquatic organisms, as well as suitable basking habitat for reptiles and perching sites for birds.
- Overall submerged aquatic vegetation cover was sparse (4.3%). Periphyton algae was the main cover type, followed by the invasive curly-leaf pondweed.
- The qualitative habitat assessment parameters for the overall area (see Table 3-5) ranked from highest (optimal) to lowest (marginal) weighted scores are:
  - 1. Riparian Vegetative Zone Width- 17.32,
  - 2. Channel Alteration-17.29,
  - 3. Pool Variability- 13.74,
  - 4. Channel Flow Status- 13.01,
  - 5. Pool Substrate Characterization- 12.66,
  - Vegetative Protection 12.53,
  - 7. Available Cover- 11.34,
  - 8. Channel Sinuosity- 11.28,



- 9. Bank Stability- 10.09, and
- 10. Sediment deposition- 9.41.

Riparian vegetative zone width and channel alteration had the highest scores because most of Reach 5A has not been armored or dredged and there is a large riparian buffer. Bank stability and sediment deposition were observed to be in poor condition as banks erode and unconsolidated sediments move through the river. Although there are higher gradient flows in the upper sections of the reach, there was no concurrent trend in habitat quality.

- The dominant riparian vegetation type was trees, and the dominant species was silver maple (*Acer saccharinum*), with the invasive Japanese knotweed (*Fallopia japonica*) in the understory.
- Average water depth was 1.3 meters and average surface velocity was 0.5 m/s.
- Pool habitats were usually found in outside bends, as is common in rivers dominated by soft substrate. Many of these pool habitats also featured large woody debris and undercut banks that provide habitat for forage fish, larger fish, turtles, muskrat, and other wildlife.

### 3.2.3 Benthic Macroinvertebrate Survey

Benthic macroinvertebrate surveys can play a useful role in assessing aquatic habitat quality. Benthic macroinvertebrates (small aquatic animals and the aquatic larval stages of insects) can provide valuable insights into the health and quality of an aquatic habitat. They are sensitive to pollution and changes in their habitats, have a relatively long life cycle, and are indicators of water quality over a period of time. Their presence, diversity, and abundance can help to assess the overall health of the aquatic ecosystem.

#### 3.2.3.1 Methods

A survey of the benthic macroinvertebrate community was conducted in Reach 5A in August and September 2022. A total of five sampling stations were sampled within Reach 5A concurrently with the physical riverine habitat survey. The sampling stations are shown on Figures 3-1a-d highlighted in yellow. The objective of the macroinvertebrate sampling was to obtain updated information on the general species composition and relative abundance in the main benthic habitats in Reach 5A. The sampling method was carried out as follows:

1. Approximately 300-foot-long sampling areas were selected based upon the physical habitat inventory, to include representative benthic substrates and flow regimes while considering potential influence from nearby anthropogenic factors. These sampling areas are shown on Figures 3-1a-d. They were selected primarily based on their representation of benthic substrates and flow regimes in Reach 5A. There were limited areas available that presented



the variety of depth, flow, and substrates representative of this section of this medium-gradient reach. Based on field conditions, a determination was made to include the area downstream from Pomeroy Avenue Bridge. It was determined that influence from roadway stormwater runoff and other anthropogenic factors were minimal at this location because the immediate area is not densely developed and runoff from the roadway does not discharge directly to the river here. The Holmes Road Bridge is downstream from the sampling area, so it has minimal effect on the macroinvertebrate community. The area around this bridge also has minimal anthropogenic factors, other than scour protection around the abutments, which are well downstream of the sampling area.

- Field documentation worksheets were completed, and a sketch map of the sampling area was prepared, including in-stream attributes, flow direction, and approximate station designation.
- 3. Benthic macroinvertebrates were collected systematically by utilizing two methods, kicking the substrate and jabbing it with a dip net. When the kicking approach was used, a D-shaped dip net was positioned and held stationary on the substrate at the downstream end of the sampling area while the substrate immediately upstream of the net is disturbed by kicking. When the jabbing approach was used, the dip net was forcefully thrust into the substrate multiple times. Epifauna on rocks and wood were manually removed (by hand rolling and cleaning rocks, woody debris, etc. as necessary) and added to the samples during the sampling. These methods continued until 20 individual substrate samples were collected. The distribution of the 20 samples were collected to represent the proportion of each of the substrate types (sand, gravel, cobble, wood, aquatic plants) in that sampling area.
- 4. Upon completion of each round of kicking or jabbing, the net was removed from the water column, allowed to drain free of water, and inspected for the presence of macroinvertebrates. Large debris (leaves, sticks, rocks, etc.) were removed from the net, and the remaining contents transferred to a labeled sample jar (continuing to fill the same jar after each round) and preserved using ethanol.
- 5. This process was repeated by moving upstream across the sampling area until 20 individual samples were collected from the sampling area. The individual samples collected by kicking or jabbing from the multiple habitats and placed into the sample jar were composited to obtain a single homogeneous sample for the sample area. The process was then repeated at each of the remaining sampling areas.



Each composite sample was labeled with sampling date and collection location to be sent to a laboratory for taxonomic identification (to species level where possible).<sup>6</sup> A total of five composite samples, plus a duplicate sample from one of the sample areas, were sent to the laboratory for such identification.

The analysis of water quality and riverine habitat from the macroinvertebrate data was performed with assistance by Lotic Inc. (Lotic)<sup>7</sup> in a manner that is consistent with previous monitoring of restoration efforts on the 1½-Mile Reach situated upstream from Reach 5A (e.g., GE 2017). Given the lack of a reference site for this effort, many of the metrics in the RBP manual cannot be used, since the RBP uses comparisons with the reference condition to make evaluations of benthic communities. However, Lotic has developed an in-house model based on 23 years of aggregated benthic community data that is further bolstered by its consistency with Maine Department of Environmental Protection's linear discriminant model (Davies and Tsomides, 2014). The Lotic model is designed for similar habitats and macroinvertebrate communities in western Massachusetts, and, as noted above, was used in previous macroinvertebrate surveys in the 1½-Mile Reach.

#### 3.2.3.2 Results

As described above, the benthic macroinvertebrate community assessment involved the collection and taxonomic identification of six composite samples (including one duplicate sample). Table 3-6 presents the taxonomic identification results of the samples collected at all stations to the nearest order. The full results of the benthic macroinvertebrate sampling are provided in Appendix A-2. It should be recognized that this sampling was conducted during drought conditions. Drought causes some decrease in macroinvertebrate abundance due to loss of available habitat and some decrease in richness due to a loss in habitat diversity, as less of the channel is submerged. The water quality may also be impacted as the temperature is typically warmer than normal and dissolved oxygen is also typically lower. Thus, any comparison using these data as a baseline should consider these factors.

The goal for each subsample for laboratory processing was 300-500 organisms; however, two of the six samples did not reach that organism count. Station 1 located at the top of Reach 5A and Station 2 located just upstream of Canoe Meadows totaled only 243 and 139 organisms, respectively.

Across sampling stations, a total of 1,673 individuals were given a final identification after lab processing. Among those individuals there was high species richness, including 117 different species. These species were representative of 41 different families, from 17 distinct orders. This high species richness is typical of a suitable water quality and substrate for diverse aquatic organisms.

-

<sup>&</sup>lt;sup>6</sup> Cole Ecological, Inc. in Greenfield, MA provided taxonomic identification of macroinvertebrates.

<sup>&</sup>lt;sup>7</sup> Lotic Inc. (now part of Haley Ward, Inc.), Belfast, Maine.



In aggregate across the stations, the family-level taxon *Hydropsychidae* (net-spinning caddisflies) under the order *Trichoptera* was the most common, making up over 33% of the sampled community with 563 individuals. This family as a group is considered moderately pollution-tolerant, although the individual species have a variety of tolerances to pollution and disturbance. The next highest abundance was a diverse group in the order *Diptera*, with most individuals in the family *Chironomidae* (non-biting midges). This order made up 37% of the sampled community with 626 individuals. The highest count of an individual identified species found in the samples belonged to *Hydropsyche betteni* (the common net spinner caddisfly), which made up about 13% of the total sampled community at 216 individuals and is also moderately tolerant of pollution.

Table 3-7 presents the taxa measures from each station. The Lotic model described above assigns the following classifications based on benthic community structure to aid in interpretation of the data in comparison to other similar streams in New England:

- 1. Class A- High quality; aquatic life as naturally occurs,
- 2. Class B- Good quality; no detrimental changes to the biological community,
- 3. Class C- Fair quality, some changes to aquatic life; maintains the structure and function of the resident biological community,
- 4. Non-attainment (NA)- Does not attain Class A, B or C classifications.

Capital letters in the table following the richness and dominant organism metrics indicate the estimated water quality classification based on the Lotic model. All samples attained a classification in this system with fair or higher indicators of quality.

The average taxa (genus) richness of 36 is indicative of good water quality with no detrimental effects to the biological community. The dominant organism and its proportional presence in each sample was also evaluated. Species with higher water quality requirements translate to higher classifications for aquatic habitat quality. EPT Richness refers to the relative abundance of three major orders of stream insects: Ephemeroptera (mayflies), Plecoptera (stoneflies), and Trichoptera (caddisflies). These insects are very sensitive to many pollutants in the stream environment, and thus their presence or absence can be used as an indicator of water quality. A large proportion of EPT taxa indicates high water quality (Lenat and Penrose 1996). In this survey, the EPT ranged from 9 to 15 with an average of 11. This EPT proportion is an indicator of fair to good water quality. The general lack of stoneflies is an indicator of potentially poor water quality in these results, but the other two orders are fairly representative. Stoneflies are particularly sensitive to low dissolved oxygen, which may be a consequence of the drought conditions during sampling.

Large numbers of pollution-tolerant chironomids often indicate poor water quality conditions. These species have a substance similar to hemoglobin in their blood, which allows them to survive in places



where the oxygen has become depleted. However, the Chironomidae family incorporates taxa with a large ecological and physiological diversity and different sensitivity to impairment. Therefore, while some species are tolerant of pollution and can thrive in degraded sites, others may be more sensitive (Saether 1975). In this survey, the Chironomidae richness average ranged from 5 to 15, with an average of 13.33. The abundance was also distributed among these genera without one strongly dominant genus. This is indicative of good water quality, especially when considering the long drought season.

Overall, this high species richness and other taxa measures are indicative of sufficient long-term water quality, the diverse microhabitats available in the Reach 5A channel, the abundant vegetation/habitat in riparian zone for adult emergent insects, and the soft sediment that provides forage and habitat for macroinvertebrates. It should also be considered that the proportions and total numbers of macroinvertebrates may represent metrics that are skewed towards indicators of below-average water quality because of the extensive drought that occurred in the spring and summer before and during the sampling.

Crayfish were also found and are discussed in the small fish assessment section below.

### 3.2.4 Assessment of Fish Species

#### 3.2.4.1 Methods

Small fish traps (known as minnow traps) were deployed in August 2022 upstream of the electrofishing station in Reach 5A in shallower habitat to obtain information on small fish species that may not be affected or observed while electrofishing. The traps were deployed at three locations in Reach 5A, which were distributed to account for diversity in habitat and location, as shown on Figures 3-1a-d. See the Small Fish Photo Log in Appendix A-3 for pictures of the sites and the equipment setup. Each location had four traps divided into two sets of two traps distributed in prime small fish habitat representative of Reach 5A.

As noted above and shown on Figures 3-1a-d, the three locations of the trap sets were evenly distributed along Reach 5A. The northern set of traps was deployed on either side of a meander near Holmes Road upstream from Canoe Meadows. The middle set was deployed downstream of Holmes Road at the confluence of Sykes Brook, in riffle habitat adjacent to Nobles Farm. The southern set was deployed downstream of Sykes Brook adjacent to East New Lenox Road. At each of those three locations, four baited traps (baited with white bread and canned fish-based cat food) were deployed in the morning, checked late in the afternoon, and then pulled from the water the next morning, so that each trap was in place for approximately 22-26 hours. At both the late afternoon check and the final pull, the small fish species (and other species) present in the traps were identified and total length was measured by a senior AECOM fisheries scientist.



In addition, in accordance with Section 3.1.1.3 of the Revised BRA Work Plan, a fish community composition sampling event was performed on September 29, 2023 in lower Reach 5A using an electrofishing boat along with the first round of fish tissue sampling in the baseline monitoring program. This sampling occurred by boat for 33 minutes along each side of approximately 1,700 feet of river length in Reach 5A. The transect started 500 feet upstream from the Pittsfield Wastewater Treatment Plant outfall and proceeded upstream in the vicinity of the Electric Power Research Institute facility. The sampling occurred following rain during a wet late summer/fall period and flows were high with approximately 3-4 feet of visibility, but the high flows allowed for boat access in areas that might otherwise be limited. Navigation was limited by fallen trees across the river and sampling proceeded as far upstream as the boat could safely pass on the day of sampling. The high flow sampling conditions complimented the low flow sampling conditions during the trap sampling described above. Habitat within the sampling area was sand/clay/mud bottom with deep river bends and LWD interspersed in aggregation. There were two small meanders and one long sweeping meander in the transect. There was little to no submerged aquatic vegetation present. Surrounding land consisted of farmland on one side on the east and forest on the west. The majority of the banks were steep on either side. Species, age class and any apparent diseases or deformities were recorded for each fish by a senior AECOM fish scientist as the fish were captured.

#### 3.2.4.2 Results

The results of the August 2022 small fish trapping effort are presented in Table 3-8. The diversity of habitats represented areas that are typically suitable habitat for small fish species. There were no diseases or deformities observed in any of the sampled fish. Results of the overall trapping effort showed that the biomass of juvenile fish species (crayfish excluded) was more proportionally dominant than that of small fish species (e.g., minnows such as shiner and dace). This is especially notable when the usual relative abundance and biomass of those species' guilds are considered. Biomass and numbers of forage species such as minnows are typically higher than that of juvenile species of predatory and bottom-feeding fish. Forage species population numbers are typically orders of magnitude more abundant than larger predatory fish. In Reach 5A, although there are some areas of LWD that provide cover, there is a lack of habitat for small fish species. Most small fish species prefer cover habitats such as submerged vegetation, non-embedded rocky substrates, and bottom roughness that is higher than sandy unconsolidated substrates provide. Although the sampling locations were chosen that fit these preferences, there is likely not enough of the preferred habitat to support abundant small fish.

Species that are moderately tolerant of pollution and soft unconsolidated substrates, such as adult spottail shiner (*Notropis hudsonius*) and juvenile white sucker (*Catostomus commersonii*) (see Grabarkiewicz and Davis 2008), comprised a majority of the catch. A few juvenile rock bass were also



captured. They are a non-native species that typically prefer habitat with abundant cover, but, like many non-native species, they are adaptable and competitive for resources.

The low representative catch numbers and habitats that the species represent may have been influenced by the drought conditions during the time of the fish capture effort in the late summer of 2022. The drought conditions brought low water and relatively warm water conditions. The low water limited the habitat available to fish in volume because of less submerged substrate and woody debris available. It also allowed more sunlight penetration and reduced the cover from birds and other predators that hunt above the water. Moreover, warm water conditions are not ideal for many cold or cool water-adapted fish. Fish in small rivers are known to migrate to find suitable conditions. Although the trap locations in this study included relatively deep areas, many fish may have migrated to deeper, cooler waters or found refugia in groundwater outputs, like those that have been documented throughout Reach 5A.

Many common crayfish (*Cambarus bartonii*) were captured in the fish traps. They are generally regarded as moderately tolerant of polluted and disturbed environments. The lengths obtained for this species in Table 3-8 are carapace length, which is the large segment of their shell measured dorsally from the eye socket to the junction with the tail. Because of the low detrital input to the stream during the drought, they were likely on low reserves and were willing to travel farther than usual distances to obtain the bait in the trap. This was corroborated by observations of uncharacteristic mid-day conspicuous feeding behavior. The presence of these crayfish in the traps may have discouraged fish from entering them. The crayfish may have also captured and eaten some of the captured fish while they were in the trap.

The results of the electrofishing sampling catches in the lower Reach 5A in September 2023 are summarized in Table 3-9. Although there were some potential confounding factors listed above, those results are generally consistent with the trap sampling data. Spottail shiners were the most numerous followed by white sucker, yellow perch, and rock bass. White suckers comprised the highest fish biomass. This is consistent with this species' habitat preference for medium to fast flowing waters with fine sediment. While these data may not be representative of the whole reach, the composition of species found in this survey is typical of a transitional area from MGS to LGS. There were no diseases or deformities observed in any of the sampled fish.

# 3.2.5 Incidental Direct Wildlife Observations

During the course of the riverine habitat surveys, field observers recorded all direct observations of wildlife species (including evidence of species presence, such as tracks or scat). Table 3-10 provides a summary of these observations. Overall, a total of 41 species (or evidence of their use) were observed in or around the river in Reach 5A. These include 19 bird species, seven species of herpetofauna, three mammal species, 10 invertebrate species, and two fish species, as shown in



Table 3-10. In addition to this listing, Appendix A-1b provides a comprehensive listing of wildlife species recorded or potentially occurring (based on habitat conditions) in Reach 5A.

# 3.2.6 Aquatic Plant and Invasive Species Observations

Submerged aquatic plant cover is generally sparse in the riverine environment in Reach 5A. Periphyton algae covers some rocks, woody debris, and shallow silty/clayey bottoms. Curly-leaf pondweed, an invasive species, was sparsely located in areas with full sun and nutrient rich soil. The invasive Eurasian watermilfoil was also found during the riverine investigations along an outside bend adjacent to an open field on the south end of RBP-12 (Figure 3-1c; between Joseph Drive and New Lenox Road). This accessible location and the presence of colored aquarium substrate on the bank suggest introduction by aquarium dumping. Watermilfoil was also found in a small patch in RBP 17. Other species of aquatic plants found include water celery, burr-reed species (*Sparganium* spp.), macrophyte algae, yellow iris (*Iris pseudacorus*, an invasive species) and blue flag iris (*Iris virginica*). Other than the three invasive species noted above, no other invasive species (plant or animal) was observed during the in-river surveys.

# 3.3 Description of Reach 5A Riverine Habitats

### 3.3.1 Habitat Types Within the Riverine Environment

The Housatonic River in Reach 5A includes two primary flowing water habitat designations, as defined by MNHESP (Swain and Kearsley 2000): medium-gradient stream (MGS) and low-gradient stream (LGS). Extending approximately 4.6 river miles, the total riverine habitat in Reach 5A is approximately 45 acres. Based upon current findings, approximately 29 acres of MGS occurs in Reach 5A, with 16 acres of LGS. While Woodlot (2002a) classified only nine acres of MGS in Reach 5A (running from the Confluence to approximately the Holmes Road Bridge), with the remainder being LGS, the 2022 field survey interpreted conditions to be more variable than the Woodlot classification. For example, while most of Reach 5A above Holmes Road provides MGS habitat, some areas of slack water were present, which is more consistent with LGS habitat. Similarly, habitat conditions from Holmes Road to the downstream end of Reach 5A remain variable, with segments of MGS interspersed with LGS in fairly equal proportions (although the boundary between these two habitats is not well defined). LGS does become progressively more abundant in the lower portions of Reach 5A. Reach 5A includes significantly more pool (53%) and run (41%) habitat than riffle (6%) across the entirety of the reach; and while riffle habitat does appear in the lower stretches of Reach 5A, this habitat is more prevalent in the upstream MGS dominant stretches.

Two other aquatic habitats are distinguished from the stream itself by MNHESP (Swain and Kearsley 2000) – riverine point bars and mud flats. Riverine point bars include deposits of coarse material near the edge of the river, typically at an inner bend, and are spread throughout Reach 5A. Figures



3-1a-d show the location of many of the point bars located in Reach 5A (along with other habitat features such as accumulations of large woody debris); and since these are transitional features between the river and riverbank, they are also shown on Figures 4-1a-d and discussed in Section 4 on riverbanks. Mud flats are composed of finer material deposits, usually of higher organic content, also along the river edge. The extent of mud flats has not been quantified, but they are noted as a seasonally available habitat, associated with low late summer and early autumn water levels.

Several other waterbodies occur along Reach 5A that contribute flow and sediment to the riverine habitat. One notable waterbody is a small tributary stream named Wampenum Brook that flows into the Housatonic River from Morewood Lake, which is located just outside of the Reach 5A limits. The stream is six to eight feet wide and has an average depth of six inches. The total substrate within the stream channel is composed of 80% sand/gravel and 20% silt. The banks range from one to two feet in height and contain small animal burrows and woody debris (AECOM 2010).

Two other small tributary streams, Sackett Brook and Sykes Brook, feed into Reach 5A on the eastern side of the river (along station RBP 7). The brooks are similar and are approximately eight to 10 feet wide with depths ranging from 0.5 to one foot with coarse sand and gravel substrate. Small point bars, woody debris, and sandy deposits are present at many of the bends in the brooks. The banks range in height from two to four feet (AECOM 2010). Two other waterbodies are of note, although neither provides "riverine" habitat. The first is an intermittently flowing side channel that extends off the main channel just below the Confluence and runs along the east side of the Housatonic River. The second is West Pond in Canoe Meadows and the small tributary that connects this pond with the Housatonic River just downstream of the Holmes Road Bridge.

# 3.3.2 Hydrology and Physical Features

Hydrologic and hydraulic conditions in the Housatonic River in Reach 5A ultimately determine the physical and biological conditions. Streams carry the water and sediment supplied by their watershed. The resulting hydrology and hydraulic processes provide the foundation for all other functions that streams provide. The relationships among precipitation, runoff, infiltration, and groundwater flow determine the amount of water that the stream carries at any given time, the energy of the water to move sediment, the physicochemical processes that affect water quality, and the biological processes that the stream will support. In this respect, the watershed setting of Reach 5A is a critical factor determining its form and function. Reach 5A starts at the Confluence, with a combined watershed area of approximately 130 square miles (almost equally distributed between the two sub-watersheds: 69 acres for the East Branch and 61 acres for the West Branch). The general character of both sub-watersheds is also somewhat similar, consisting of very rural wooded hills draining into and through developed urban landscapes. This setting can lead to a fairly "flashy" hydrologic setting, with flow stages and volumes reacting quickly and with substantial magnitude to



storm events. Further, this headwater setting can lead to low flow conditions where minimal flow is available. Low flow conditions in Reach 5A typically drop below 20 cubic feet per second (cfs), with water levels commonly less than a foot deep and both bars and mud flats prominent along the river margins.

In contrast, storm events increase flows in Reach 5A dramatically, and these conditions strongly affect the physical conditions of the river channel and banks, which in turn affect the biological communities which comprise the riverine habitats. As reported in the recently completed HHA in Appendix G to the Reach 5A Conceptual RD/RA Work Plan, a one-year storm event generates flow at the Confluence of just over 1,000 cfs, while the 100-year storm event flow is roughly 13 times higher (13,390 cfs). Further, the HHA notes that recent analyses indicate that these storm flows have increased in magnitude; for example, the 1987 FEMA 100-year (or 1% annual chance flood) flow of 12,386 cfs has increased to 13,390 cfs based on the updated HHA. The HHA indicates that bankfull flows in the upper part of Reach 5A are on the order of 2,000-3,000 cfs, reflecting the stage of overbank flooding into the adjacent floodplain which may occur every 1.5 to two years, with water levels more on the order five to six feet deep. More detailed hydrologic analysis is anticipated as the HHA is expanded for final remedial design, and is anticipated to contribute further to the understanding of habitat conditions related to hydrology and hydraulics. For example, the current 1D HHA model will be expanded to a two-dimensional (2D) model to support the final design of the Reach 5A remediation. A 2D model will more effectively evaluate flow patterns and velocities at locations with complex stream and floodplain geometry, aiding in the assessment of relationships between flow parameters and habitat conditions.

The Housatonic River within Reach 5A transitions from moderate to low channel slope. Stream gradient generally declines downstream and a transition to more LGS occurs along the length of Reach 5A; however, as noted above, the change is quite gradual and even intermittent. Elevational gradient along the river length is a primary factor in establishing the features of the riverine environment and the associated habitat types. Water velocity, channel depth, river width, substrate, and bank slope are all affected by stream gradient. In the MGS areas, water velocities are at least moderate and the substrate is dominated by coarse sand to gravel or even cobble, with some boulders present and very little silt. Maximum (non-flood) water depths in MGS areas are typically two to four feet in the main channel, with some pools and riffles but mostly run habitat (moderate to rapid non-turbulent flow with little exposed substrate). Banks are high in most MGS area, but there are sufficient cuts in the bank to provide functional linkage with the adjacent floodplain. During lower flow periods, the water level in MGS areas is often less than one foot, with features such as mid-channel bars exposed a foot or more above the water surface. Maximum water depths in Reach 5A LGS areas during "normal" (i.e., non-flood/non-drought) conditions in Reach 5A may approach four to five feet in the main channel, but LGS areas in Reach 5A are more typically two to three feet deep.



Riverine bar habitat is formed at points where higher water velocities transition to lower velocities as a function of channel changes, usually on the inside of a river bend, but where velocities are rarely high enough to wash away accumulated sediment. Typically, bars have a gentle slope and are often submerged during flood events and periods of high water. These river features accumulate downed woody material and other debris during times of high water levels, and are important for the emergence of insect larvae and for providing access between terrestrial and aquatic habitats for a variety of wildlife. While riverine bar habitat occupies only small portions of the overall riverine habitat, they are not uncommon features within Reach 5A. Figures 3-1a-d show the location of 55 riverine bars identified during the 2022 field surveys.

Progressing downstream in the Reach 5A river channel, the substrate typically becomes more frequently dominated by silts, organic muck, and fine sand in the LGS areas. Some gravel, cobble, or boulders may be present even in LGS areas of Reach 5A, particularly along the margins, but are not a major component of the submerged substrate. Mud flats may form as water levels decline during prolonged periods of low flow, particularly along protected lee edges of LGS areas.

Dead trees and branches, or LWD, that fall into the river create habitat features that provide physical structure, localized flow pattern, substrate features, and overall habitat value for many species. Such LWD is a consistent visual aspect of MGS and much of the transition zone to LGS. Woody debris is present but often submerged in LGS. While such debris may not be visible, it adds structure and affects depositional patterns, even within the LGS. Woody debris creates variation in habitat over space and time in the river; old debris eventually decays, crumbles, and moves downstream, while newer debris replaces it, although not at a uniform rate and often not in the same locations. Figures 3-1a-d indicate the location of the major LWD accumulation zones in Reach 5A identified during the bank and floodplain surveys, noting that such locations are temporary and subject to change from fluvial processes. Larger aggregations of LWD containing multiple large trunks, limbs, and/or root wads were thoroughly mapped. Disparate and small areas of exposed LWD that likely have minor effects on the river morphology and habitat were not mapped. However, even some of these more minor LWD areas would be accounted for in the riverine and riverbank qualitative ratings (as indicated in the riverine forms in forms in Appendix A-1a and the bank forms in Appendix B).

# 3.3.3 Biological Communities

The biological communities in the riverine habitat in Reach 5A are interrelated with the surrounding habitats. The river serves as a pathway for nutrients, forage, and animals themselves. Observations of wildlife during the riverine habitat effort, which are summarized in Table 3-10 and shown in detail in Appendix A-1b, contain a variety of signs and direct observations of wildlife using the river. Many species of birds, dragonflies, reptiles, amphibians, and mammals were observed using this habitat.



The Reach 5A channel hosts only sparse aquatic vegetation due to the unconsolidated sand and gravel substrate and high water velocity. The primary aquatic plant species identified in Reach 5A were various periphyton algae, Eurasian watermilfoil, curly-leaf pondweed, American bur-reed (*Sparganium americanum*), and giant bur-reed (*Sparganium eurycarpum*). The watermilfoil and curly-leaf pondweed are invasive species and are found in sparse patches in riverine areas in Reach 5A. Shading by shoreline trees and shrubs occurs, restricting light and limiting temperature rise, and thus further controlling aquatic plant growth. Aquatic vegetation is limited to small patches in sandy areas in Reach 5A. Cover and overall habitat structure are more often associated with woody debris in this reach.

A wide range of aquatic invertebrates utilize the Housatonic River within the PSA (Woodlot, 2002a), including a number of state-listed species. The state-listed species include six species of dragonflies - brook snaketail (Ophiogomphus aspersus), riffle snaketail (Ophiogomphus carolus), arrow clubtail (Stylurus spiniceps), rapids clubtail (Phanogomphus quadricolor), spine-crowned clubtail (Hylogomphus abbreviates), and ocellated darner (Boyeria grafiana)). The snaketails are restricted to MGS habitat and the transition zone to LGS within Reach 5A, preferring gravelly substrates (although gravel is not a prevalent substrate in Reach 5A). The clubtail dragonflies can be found throughout the reach in sandy or silty sediments. Other invertebrates commonly found in Reach 5A include other dragonfly species, damselflies, a variety of true bugs (Hemiptera), beetles, caddisflies, a wide range of true flies (Diptera), freshwater shrimp (Amphipoda), two native species of crayfish, and three species of mussels (the formerly state-listed triangle floater, the eastern floater [Anodonta cataracta], and the eastern elliptio [Elliptio complanata]). Three species of fingernail clam (Sphaeriidae family) also inhabit the river. The dragonfly species and other insect species live in the river in a larval form, morphing into a flying adult stage during spring and/or summer, although with long-lived larval stages or multiple generations in a year, the river is never without invertebrates. A few species, like mussels and some true bugs and beetles, never leave the stream in any life form. The adult stages of many aquatic invertebrates utilize the adjacent riverbanks and floodplain, as do many terrestrial insects. Several of the above-listed species were observed during riverine surveys and macroinvertebrate surveys within Reach 5A: a full list can be found in Table 3-6 and Table 3-10.

Fish in the overall PSA are mostly warmwater species, with 25 species detected in surveys from 1998-2000, including sunfish species (genus *Leopomis*), yellow perch (*Perca flavescens*), various minnow species (Order *Cypriniformes*), sucker species (Family *Catostomidae*), largemouth bass, eastern chain pickerel (*Esox niger*), northern pike (*Esox lucius*), brown bullhead (*Ameiurus nebulosus*), goldfish (*Carassius auratus*), and common carp (*Cyprinus carpio*). Three cold water trout species – brook trout (*Salvelinus fontinalis*), brown trout (*Salmo trutta*), and rainbow trout (*Oncorhynchus mykiss*) – have been found in surveys since 1998, but are not abundant and only brook trout is native. In 2000, the most abundant fish species in Reach 5A was the white sucker, at 65% of the biomass, but other commonly occurring species included largemouth and rock bass, yellow perch, and various minnow



species (Woodlot 2002a). The recent surveys in 2022-2023 are consistent with these previous findings.

The point bars and other side and mid-river bars in Reach 5A provide access between the river and floodplain for wading birds and small and large mammals. They also serve as emergence habitat for amphibian and invertebrate larvae, including some dragonflies. The higher, more gravelly portions of the point bars provide potential nesting habitat for the state-listed wood turtle.

There are 10 state-listed plant and animal species that have MNHESP-mapped Species Habitat within the river channel in Reach 5A and that could be found in the aquatic riverine habitat in this reach (based upon habitat requirements). The list consists of dragonflies (described above), emergent vegetation, wading birds, and a reptile. There are no fish or other species that are solely dependent on the riverine environment. These state-listed species are listed in Table 3-11 and are discussed further in Section 8. Further, as noted previously, riverine habitat in Reach 5A is included in portions of Core Areas 1-3 as designated by MNHESP (Mass DFW 2012).

### 3.4 Reach 5A Riverine Habitat Functional Assessment

This section presents an assessment of the ecological functions and services of the riverine habitat in Reach 5A. As stated above, assessment of the existing functions and services is based primarily on the information consolidated and collected on measurable and observable structural parameters that are known to give rise to the functions of the relevant habitat.

The consolidation of existing and PDI information along with the results of the EPA RBP and the other field surveys described in Section 3.2 have served as the basis for the riverine functional assessment in Reach 5A, focusing on the measurable and observable structural parameters derived from those activities. Riverine functions are also qualitatively described in terms of the functional categories described in Table 3-12 using the parameters or factors listed in that table for each functional category. The Stream Functions Pyramid developed by Harman (2009) and Harman and Starr (2011) provides an approach that organizes stream functions in a pyramid form to illustrate goal setting for restoration assessments. These functions (listed from bottom to top) are: hydrologic/hydraulic, geomorphological, physiochemical, and biological. Within this hierarchical framework, higher-level functions are supported by lower-level functions. For example, hydraulic functions cannot occur without hydrologic functions, and these "water-based" functions drive stream geomorphology, which in concert determine physicochemical conditions, and the collective association of these foundational functions determine stream biology. Table 3-12 is adapted from this approach, in which the functional categories have been modified from Fischenich (2006) to more closely match functions with parameters that are commonly used in the fields of hydrology, hydraulics, geomorphology, physiochemistry, and ecology. These functional relationships are



summarized below, drawing from guidance from EPA's A Function-Based Framework for Stream Assessment and Restoration Projects (EPA 2012).

The intent of the assessment process is to use the inventoried structural parameters to describe the overall function of each category. Table 3-12 shows, for each function, the parameters from Table 3-1 that have been used to describe and assess that function. These parameters are primarily observable structural or physical measures, although some are actual functions (e.g., flood storage). Through the inventory and data collection process before remedial design, baseline conditions are incorporated into the design process to address means and measures to maintain riverine functions under post-restoration conditions. Restoration success largely depends on addressing these functions from bottom to top in the order of the hierarchy through restoring the structural and physical parameters that give rise to those functions. The following summarizes the Reach 5A riverine functions using the functional categories presented in Table 3-12.

### **Hydrologic Support Function**

As a general matter, a stream reach and its watershed comprise a dynamic balance where the floodplain, channel, and streambed evolve through natural processes that erode, transport, sort, and deposit sediments. The hydrology of the reach is fundamentally defined by the transport of water from the watershed through the channel. The hydrologic processes (precipitation, infiltration, runoff, and evaporation) that occur at the watershed level influence the character and functions of the stream reach. Hydrologic support functions include water conveyance and transport, watershed connectivity, floodwater dynamics (flood flow amelioration, flood storage and desynchronization, and peak rate control), base flow maintenance (groundwater discharge and recharge), and the broader ecological function as a migration and dispersal corridor.

Streams carry the water supplied by their watershed. The resulting hydrology and hydraulic processes provide the basic foundation for all other functions that streams provide. The relationships among precipitation, runoff, infiltration, and groundwater flow determine the amount of water that the stream carries at any given time, the energy of the water to move sediment, the physicochemical processes that affect water quality, and the biological processes that the stream will support. Stream channels like Reach 5A are connected with their floodplains, attenuate flood pulses, and spread nutrients and organic matter during flooding events. Streamflows rise and fall with precipitation and snowmelt events, resulting in a dynamic range of flows. This range of flow defines the channel form and creates the basic structure on which many other processes and functions rely. The sinuous channel form and steps (vertical profile changes) also aid in attenuation and suppression of floodwater and stream flow forces. Groundwater is also both recharged and discharged along the Reach 5A channel, providing another hydrologic link between the stream channel and the landscape.



The hydrologic and hydraulic conditions prevailing in the riverine habitat in Reach 5A create a dynamic environment that provides the characteristic elements described above to support hydrologic functions. Water conveyance and transport are apparent relative to the range in flow conditions, and this hydrologic regime also reflects a watershed connectivity function, particularly given the setting at the Confluence. The transport of water and sediment is also reflected in the instream features that are formed within the stream channel. Transport of sediment and nutrients is demonstrated by the unconsolidated sediment and point bars found throughout Reach 5A. Hydraulic factors also affect many functions because they determine the amount of force and power that is exerted by the water on aquatic habitats. Despite signs of instability and disturbance to the desired equilibrium of sediment transport (discussed below), the Reach 5A river channel maintains sufficient connectivity with the floodplain to promote flood storage and peak flow/stage desynchronization, particularly during storms less intense than the two-year storm event.

#### **Geomorphology Functions**

The geomorphology functional category includes the following functions: channel formation and maintenance, floodplain connectivity, transport of organic and mineral sediment material, transport of woody debris, and transport of nutrients and food sources. The Reach 5A channel form (dimension, pattern, and profile) is variable and somewhat complex due to the watershed and hydrologic factors described above, with highly sinuous meandering sections interspersed with straighter runs. While again indicative of some instability, these conditions also contribute to aquatic habitat diversity. As noted above, the transport of water and sediment is reflected in the bed features that are formed within a stream channel. Similarly, a key geomorphologic function is the transport of wood to create diverse flow conditions, which affects sediment transport/deposition and resulting aquatic habitat such as bed forms. Reach 5A has a relatively consistent amount of LWD in and along the stream channel which both reflects and contributes to flow diversity and channel geomorphologic variability.

The Reach 5A river channel contains sequences of riffles and pools or steps and pools that maintain channel slope and stability and contribute to aquatic habitat diversity. Riffles and pools in this reach, as well as other bed features such as runs and glides, form a diversity of aquatic habitats and provide the foundation for many of the biological and water quality functions that the Reach 5A riverine habitat provides. Macroinvertebrate benthic organisms cling to rocks and coarse substrates in riffle areas, filtering food from the flowing water and thriving on the oxygen-rich water. The oxygen in riffles and the increased flow allow a higher rate of contact with the water supporting all aquatic life and especially species and life stages that require access to high levels of dissolved oxygen. Early life forms of fish and macroinvertebrates use the fast-flowing water and higher oxygen levels in the accelerated growth of their early development.



Pools at the meanders create diverse habitats. Large woody debris and undercut banks are often associated with these pools. Many fish species utilize meander pool areas due to the cover provided for protection and ambush and for cooler water temperatures afforded by the deeper water environment. Even within a single meander pool, there are aquatic organisms that prefer to live at varying water depths and locations within the pool.

#### **Physicochemical Functions**

Physicochemical functions include water quality maintenance, temperature and oxygen regulation, and processing of organic matter and nutrients. These functions are closely associated with, and largely determined by, the hydrologic and geomorphologic conditions. For example, riffles and deep pools (bed form diversity), along with shade and a wide buffer, help regulate stream temperature. Trees and shrubs along the riverbanks regulate water temperatures through shading and provide organic matter to the system, which is stored and transported forming the energy web that supports aquatic life and diversity.

#### **Biological Functions**

Biology is located at the top of the Stream Functions Pyramid because the biological functions are dependent on all the underlying functions. Specific biological functions include biodiversity and sustaining life stages of aquatic and riparian life, habitat for aquatic and other water-using biota, and rare species habitat.

The Housatonic River in Reach 5A provides diverse habitat for aquatic organisms. Due to the range of substrate types, vegetative cover, and depth features, this area provides a range of functional uses for many fish and invertebrate species. Fish found in this reach are primarily warmwater species, including sunfish, various minnow species, and bass. These species forage throughout the river in this reach, taking advantage of complex habitat features to locate food resources and shelter, and providing a food source for piscivorous (fish-eating) mammals and birds. A wide range of aquatic invertebrates also utilizes this area. These include several freshwater mussels (e.g., the previously state-listed triangle floater) and several state-listed rare dragonfly species – the brook snaketail, riffle snaketail, rapids clubtail, and spine-crowned clubtail dragonflies – as well as the ocellated darner. The snaketail dragonflies and triangle floater are largely restricted to MGS habitat and prefer the gravelly substrates present in Reach 5A. The invertebrates (including the state-listed dragonflies and previously listed mussel species) rely on foraging, shelter, and emergence habitat provided by the river.

Many areas within Reach 5A contain abundant coarse and fine woody debris, which is both embedded in the river bottom and free floating. This woody debris both above and below the water line provides structure for invertebrates, fish, amphibians, turtles, and several small mammals.



Invertebrates seek out woody debris for shelter and for its linkage to food sources. Predatory fish seek out the same structures for food and shelter, particularly bass and sunfish. Pools created because of large woody debris offer shade and deeper, cooler water during summer months. Most fish species will seek out this cooler water during summer months if it is available. Pool habitat in the Housatonic River in Reach 5A provides aquatic organisms with refuge from high velocities during flood and storm events, as well as thermal refuge during droughts and hot summer months. The ability to seek shelter in pool habitat to avoid high velocity flows or elevated temperature is energetically beneficial to fish and other aquatic organisms which might otherwise be washed downstream or metabolically stressed.

Finally, the Housatonic River, including in Reach 5A, is the major migration corridor in the watershed. It provides opportunity for aquatic and semi-aquatic organisms to seek out and navigate into suitable habitat, and allows for transport of nutrients, sediment, and food items from upstream terrestrial and aquatic communities to downstream areas.



### 4.0 Reach 5A BRA of Riverbank Habitats

Riverbank conditions in the ROR have been included in numerous investigations over the past 20+ years along with other work, particularly in the PSA, including Reach 5A. As with the riverine BRA approach, the BRA of riverbanks within Reach 5A initially drew from these previous investigations and also incorporated the riverbank data collected under the Revised Reach 5A Sediment/Bank PDI Work Plan, as well as additional field surveys.<sup>8</sup> As with the riverine inventory and assessment, and as directed in EPA's March 31, 2022 conditional approval letter, information on riverbank structural parameters was obtained for all riverbanks in Reach 5A, with data collection applied within discrete bank segments that have similar characteristics.

Table 4-1 provides a summary of the parameters that have been incorporated into the assessment of riverbank habitat conditions in Reach 5A. Those parameters collectively contribute to the formation of habitat functions, including hydrologic conditions, floodplain connectivity, stability/erosional status, and specific habitat features such as large woody debris, cut banks, and vegetative cover.

### 4.1 Background Ecological Information

As noted in Table 4-1, some of the riverbank habitat assessment parameters were based on information consolidated from the sources cited previously in Section 2 of the Revised Reach 5A BRA Work Plan. In other cases, the parameters were based on information drawn from other tasks or steps in the remedial investigation process, notably the Reach 5A PDI. Still other information, such as hydrologic/hydraulic data pertinent to riverbank conditions, was obtained from available sources (as also noted in Table 4-1), as well as updated data presented in the HHA in Appendix G to the Reach 5A Conceptual RD/RA Work Plan.

# 4.1.1 Woodlot Ecological Characterization (2002)

The Woodlot Ecological Characterization of the PSA (Woodlot 2022a) included some information on the riverbanks in Reach 5A. In describing the Reach 5A area, Woodlot stated that "the main stem of the Housatonic River in this section has moderately fast water with pool, riffle, and run habitat. The

<sup>8</sup> 

<sup>&</sup>lt;sup>8</sup> The Revised Reach 5A BRA Work Plan used the same definition of riverbanks presented in the approved Revised Reach 5A Sediment/Bank PDI Work Plan, which was based on the Massachusetts Wetlands Protection Act regulations (310 CMR 10.54(2)(c)) definition, in which the toe is "the mean annual low flow level" and the top-of bank is "the first observable break in the slope or the mean annual flood level, whichever is lower." In fact, for the Reach 5A PDI, the toe of bank was defined based on the water surface elevation observed during the April 2022 topographic survey (with a river flow rate between 130-150 cfs) and the top-of-bank was the first observable break in slope based on the LiDAR survey data collected in 2021 and 2022, but no higher than the elevation of the adjacent 1 mg/kg PCB isopleth. This Revised BRA Report follows that same definition, which is also consistent with the definition used in the conceptual design for Reach 5A, included in the September 2023 Conceptual RD/RA Work Plan.



channel walls are vertically cut and bottom substrate is often gravel and sand" (Woodlot 2002a, page III-1-6). As the river slows and widens somewhat moving downstream, Woodlot noted that, "though the stream banks are generally vertically cut, a number of sand beaches were found" (id., page 1-11).

In its extensive listing of wildlife species associated with the various classified habitats, Woodlot did not specifically break out riverbank habitat as a distinct class. However, it did list wildlife species associated with riverine point bar and beach habitat, both of which may fall within riverbank areas to some degree. However, the species break-downs for these habitat classes do not specify those found in Reach 5A, but rather are more broadly listed for the entire PSA.

### 4.1.2 RCRA Facility Investigation Report (2003)

GE's 2003 RFI Report provides substantial information characterizing ecological resources in the ROR area, including riverbank habitats in Reach 5A. Although the focus of that report was on documenting the extent of PCBs in the river, some relevant Reach 5A riverbank information is provided (e.g., total organic carbon content of riverbank soils). Minimal specific Reach 5A bank habitat characterization was provided, but rather conditions in the overall Reach 5 were typically referred to. The RFI Report summarized bank erosion investigations conducted by EPA in 2000-2002, which included the use of toe pins in Reach 5A to measure bank elevations over a 20-month period as well as bank migration measurements at 11 locations in Reach 5A. An overall bank erosion rate of -0.7 ft/yr was determined by these studies. The RFI Report noted that these values are not necessarily representative of Reach 5A as a whole because specific bends where bank erosion is more likely to occur were targeted in the surveys.

# 4.1.3 EPA's Modeling (2006)

EPA's documentation of its modeling efforts for the ROR, notably its use of the EFDC, included extensive descriptions of riverbank conditions, some of which can be attributed to conditions in Reach 5A. As part of the field data collection for the EFDC modeling, detailed test pits were conducted along the riverbanks, including at six locations in Reach 5A. These test pits defined the soil/substrate profile to depths approaching six feet below the surface. The test pits were excavated to measure soil horizon depths, colors, and texture. Sampling locations were chosen such that results provide an estimate of rates and locations of sediment deposition during flood events. They were excavated either at the bank edge or approximately 50 feet from the bank. The observed soil profiles were reported as indicative of repeated flooding and associated sediment deposition. This was noted by the presence of alternating A horizons (a pedogenic or biologically active surface layer) with C horizons (not affected by pedogenic processes); the C horizons were considered indicative of flood deposition events, followed by non-flood years in which A horizons develop.



In addition, these investigations characterized sediment grain size on riverbank soils collected from all the locations studied in Reach 5A. Riverbank soils generally consisted of a lower layer of silt loam to loam that was overlaid by a loamy sand. The silt loam generally extended from the water surface to two to six feet up the riverbank. Riverbank heights (annual high-water line to top-of-bank) averaged five to six feet. The loamy sand surface that was present above this layer averaged two to four feet in thickness and was observed on about 50% to 75% of the erosion sites. At low flow, resistant silt loam benches were observed below the high-water line. Riverbank erosion may be initiated where these benches meet the riverbank. At those points, the toe of the riverbank is undermined and riverbanks subsequently fail and the river is able to move laterally.

### 4.1.4 Corrective Measures Study Reports (2008-2010)

GE's 2008 CMS Report presented substantial information on ecological baseline conditions in the ROR, including Reach 5A riverbank habitat conditions. Its 2010 RCMS Report included a substantially expanded description of the affected habitats in the ROR, including Reach 5A riverbank habitats, and the ecological impacts of the remedial alternatives.

Section 5.0 of the RCMS Report provided the following summary of the Reach 5A riverbanks:

"Riverbanks in Reach 5A, the upper portion of the PSA, generally range in height from 2 to 5 feet, with areas of high vertical banks ranging from 8 to 12 feet. Banks consist of silts and sands with a range of physical attributes, including sloped and vegetated banks, vertical and exposed banks, erosional banks with slumping, and erosional but vegetated banks. Vertical and exposed banks lack vegetative cover but provide important habitat functions discussed in more detail below. Undercut banks are an important habitat component of the riverbanks in Reach 5A and are more prevalent in Reach 5A than anywhere else in the PSA. Mature trees overhanging the river and dense herbaceous and shrub communities are also prevalent on the banks in Reach 5A and provide shading to the river and foraging opportunities for wildlife." (RCMS Report, page 5-28.)

Additional descriptive information on the Reach 5A riverbanks from the RCMS Report includes the following regarding Reach 5A:

- Vegetation along the riverbanks consists mostly of trees in Reach 5A. Silver maple, red maple (*Acer rubrum*), eastern cottonwood (*Populus deltoides*), and box elder (*Acer negundo*) form much of the canopy in that reach, while the subcanopy, shrub, and herbaceous layers are minimized by light limitation.
- Exposed vertical banks in Reach 5A provide suitable nesting habitat for two species of bank nesting birds, the belted kingfisher (*Megaceryle alcyon*) and the bank swallow (*Riparia*



*riparia*). The vertical banks also provide potential nesting sites for several turtle species, including the state-listed wood turtle. The riverbanks in Reach 5A provide lodging habitat and slides for beaver and muskrat and foraging habitats for birds and mammals, including American mink (*Neovison vison*) and raccoons (*Procyon lotor*). In particular, beaver activity along the banks is common in many places, with frequently occurring burrows evident. Undercut banks and woody accumulations offer hibernacula sites for wood turtles to overwinter.

• Large overhanging trees in this area provide shaded microhabitats and variability in water temperature within the river for fish, invertebrates, and shade-tolerant plant species, as well as foraging and perching sites for piscivorous and insectivorous birds.

In addition, Appendix G of the RCMS provided an assessment of riverbank stabilization techniques that could be applied under a range of remedial alternatives, including options that may be applicable in Reach 5A. These were based on an initial visual assessment of bank conditions, as well as review of other existing information, to evaluate geomorphic characteristics and hydraulics affecting particular bank sections.

### 4.1.5 Stantec Bank Studies (2009)

As discussed in Section 3.1.5, EPA's consultants at Stantec conducted an evaluation of erosion from the ROR riverbanks, using the BEHI and NBS ratings (Stantec 2009). In Reaches 5A and 5B, data were collected in May of 2009 from approximately 41,000 linear feet of stream channel and 82,000 feet of streambank (both banks were surveyed). As also noted in Section 3.1.5, Stantec described the areas of high bank erosion as being out of phase with the form of the river, with many areas of high and extreme erosion located upstream of point bars and inside banks, indicating active channel migration and horizontal instability; no specific habitat factors were addressed in relation to this analysis.

# 4.1.6 Example Area Evaluations (2010)

As discussed in Section 3.1.6, GE's February 2010 Supplement to Interim Response presented detailed evaluations of six Example Areas in Reaches 5A to 5C, four of which were located within Reach 5A (AECOM 2010). Only two of those Example Areas encompassed riverbank habitat – Example Areas #1 and #2, shown on Figures 3-1a and 3-1b. The descriptions provided of riverbank habitat conditions within those Example Areas included the following:

 Riverbank conditions consist predominantly of mature woodland, with severely eroded sections of bank in places, notably on the outside banks of the prominent bends in the upstream and downstream portions.



- Low slope areas of riparian banks, often occurring at the locations of point bars, provide connectivity with the floodplain. They allow for movements of aquatic invertebrates and amphibians and their larvae between in-stream and floodplain habitats. They also serve as hunting and feeding grounds for small mammals and wading birds, and are prominent access points to the river for larger mammals such as white-tailed deer (*Odocoileus virginianus*) and black bear (*Ursus americanus*).
- Riverbanks within these Example Areas are quite variable. In some areas, such as the outside of meander bends, they are vertical and exposed (no vegetation), while in other locations they are sloped at 30 to 50 degrees and are covered in vegetation. In general, the banks are composed of silts and sands and are three to five feet in height above normal flow, but can be as much as 12 feet high. The riverbanks are typically well vegetated, although on much of them only the upper portion is vegetated while the lower portion is bare. Undercut banks are common and occur in both the exposed and the vegetated portions. Vegetated banks consist of a dense intertwining mass of fine roots and woody debris within sandy soils. Where woody shrubs and trees overhang the river, they provide perching and nesting sites above the water and provide shade over the bank and river.
- The riverbanks in Example Area #2 provide lodging habitat and slides for beavers and foraging habitat for birds and mammals, including mink and raccoons. Along the portions of the river in this area where the banks are exposed and/or undercut, the riverbank habitat provides potential nesting sites for bank swallows and belted kingfishers and hibernation habitat for the state-listed wood turtle. Nesting sites for kingfishers and swallows are limited to exposed areas of the riverbank well above the height of normal water level fluctuations.

# 4.1.7 Natural Heritage Information (2000-2022)

As described in Section 3.1.7, MNHESP conducted extensive investigations from 2000 to 2010 in the Housatonic River watershed, including the Reach 5A river, riverbank, and floodplain habitats. The results of these investigations were summarized in two reports (MNHESP 2010, 2011), and also resulted in updated designation of Priority Habitats of rare species. The 2010 and 2011 MNHESP reports provided exhaustive summaries of target species, but did not distinguish occurrences in riverbank habitats from other occurrences in the floodplain. However, the reports listed occurrences of invertebrate, turtle, and amphibian target species that may be encountered in riverbank habitats at certain stages of life. The tables provided in the reports do not specify wildlife specifically found in Reach 5A, and there were no specific descriptions of the riverbanks in Reach 5A. Similarly, while the Core Area designations by MNHESP in 2012 encompass riverbanks in Reach 5A, they do not specifically cite this habitat.



As also noted in Section 3.1.7, in October 2022, MNHESP provided GE with updated digital information that includes Species Habitat mapping of the state-listed species in the ROR, including Reach 5A. As described in Section 4.2.2.7 and Section 8, at least 13 of these species utilize habitats consistent with those present on the Reach 5A riverbanks and have mapped Species Habitat overlapping Reach 5A riverbanks.

## 4.1.8 Pre-Design Investigations of Reach 5A

The PDI of Reach 5A collected a range of information on riverbank conditions that apply to habitat characteristics of the banks. That information provided a definition for determining the toe and top-of-bank to allow differentiation of river sediment from bank substrate and to define the inner edge of the floodplain.<sup>9</sup> It also included the 2022 focused survey of the riverbanks using a mobile LiDAR system to provide detailed information on bank morphology. Further, it included a bank erodibility assessment conducted following the methodology outlined in *Watershed Assessment of River Stability and Sediment Supply* (WARSSS; Rosgen 2006). A total of 50,033 linear feet of riverbank in Reach 5A were assessed for BEHI and NBS rating. The results of these activities were presented in GE's *Pre-Design Investigation Summary Report for Reach 5A Sediments and Riverbanks* (PDI Summary Report for Reach 5A Sediments and Riverbanks (PDI Summary Report for Reach 5A Sediments and Riverbanks (PDI Summary Report for Reach 5A. That report also describes the Bank Assessment for Non-Point Source Consequences of Sediment (BANCS) model calibration survey that is ongoing to correlate various BEHI/NBS conditions to estimates of the annual amount of sediment eroding from the riverbank (Rosgen 2006).

# 4.2 2022 Riverbank Habitat Investigations

### 4.2.1 Methods

In addition to the background information discussed above, field surveys were conducted in 2022 to further document the physical/structural and biological conditions of the riverbank areas in Reach 5A. In accordance with the Revised BRA Work Plan, bank characteristics documented in the 2022 field surveys included bank morphology (height, slope, sinuosity, etc.), bank stability, soil/substrate composition, and vegetative composition. Based on an evaluation of apparent changes in riverbank morphology conditions in Reach 5A, the field bank habitat assessments occurred at approximately 34 stations in Reach 5A, distributed between the Confluence and the downstream end of Reach 5A. Those stations are shown on Figures 4-1a through 4-1d. The stations were established in a stratified random manner to encompass a range of riverbank morphologic conditions (e.g., some straight runs, different bends, etc.) along the entire span of Reach 5A. In each case, "stations" were not discrete

-

<sup>&</sup>lt;sup>9</sup> See note 7 in Section 4 above.



transects across the river, but rather encompassed a 200-400 foot length of riverbank on both sides of the river to better characterize the range of conditions observed. Reach 5A bank field surveys were conducted from August through October of 2022.

This habitat characterization of the Reach 5A riverbanks included, at each of the 34 stations, completion of Form RB-1 (provided in Appendix B), which is adapted from Table 4-1 for documenting the riverbank characteristics. Form RB-1 provides for detailed documentation of the following conditions on the banks: physical metrics, soil/substrate composition, bank stability, hydrologic indicators (e.g., bankfull), floodplain connectivity, vegetative cover, bordering habitats, corridor connectivity capacity, and habitat degradation (e.g., invasive species), as well as incidental wildlife observations. These investigations also included the identification of special habitat features on the Reach 5A banks – e.g., cut banks, turtle hibernacula or observed nesting sites, kingfisher or bank swallow nest sites (which consist of vertical sandy banks), otter slides, rock basking sites, beaver bank dens, burrows, and tree cavities. For most characteristics, the documentation of bank conditions includes the overall characterization on both the left and right banks for each station length; for a few characteristics, such as vegetative composition, data are distinguished between the left and right banks (based on verbal direction from EPA representatives in August of 2022). Finally, during the course of the field surveys, riverbank restoration opportunities were assessed. This included noting the presence of potential restoration resources that may be considered in the bank/river restoration design, such as the presence of boulders, large trees or woody debris, root wad material, or plant propagation source materials.

Some of the characteristics provided in Form RB-1 required review of other source information followed by completion in the office. For example, the overlap of each bank station with Core Areas and Species Habitat mapping provided by MNHESP was determined in the office, with the information added to each form as applicable. Further, field survey data obtained from riverbank PDI investigations and from the floodplain habitat investigations were consulted during completion of the riverbank forms to ensure consistency between these findings. These included estimates of bankfull conditions, bank slopes, and riparian zone vegetative composition. Finally, Form RB-1 at each of the 34 riverbank stations was completed by adding an aerial photograph of the bank station location as well as photographs of the station.

### 4.2.2 Results

Appendix B contains the completed riverbank Form RB-1 for each of the 34 stations within Reach 5A. As noted above, these station locations are shown on Figures 4-1a-d, and they are also shown on an aerial photograph section at the end of each completed form. Summary data obtained from consolidating the information from all 34 RB-1 forms are provided in tabular form in Tables 4-2 through 4-14. That field survey information is described in the following subsections.



#### 4.2.2.1 Physical Characterization

The 34 riverbank stations surveyed within Reach 5A encompass a total of 8,300 linear feet of the total reach, or 16.6% of the roughly 50,500 total linear feet of riverbank in this reach (counting both sides of the river). The stratified random selection of bank segments included in the survey area resulted in various morphological settings being surveyed, including eight relatively straight runs, six segments with right bends and seven with left bends, three segments with a straight run leading to a left bend and two with a straight run leading to a right bend, and six segments including both right and left bends. Physical characterization of the Reach 5A riverbanks included bank height, slope, substrate composition, stability/erosional condition, and degree of channel incision. Table 4-2 summarizes the physical characterization data obtained for riverbanks in Reach 5A, with additional details on bank substrate conditions provided in Table 4-3; some of this characterization pertains more broadly to the river channel at the location of each of the riverbank stations, which is included in Table 4-4. Some of the key physical characteristics of the Reach 5A riverbanks summarized in Tables 4-2 through 4-7 are as follows:

- The average height of the riverbanks in Reach 5A was estimated to be 6.2 feet (range of four to 10 feet).
- The average slope of the riverbanks in Reach 5A was estimated to be 66% (range of 25-105%).
- Riverbank substrate surveys recorded a relatively even distribution of sand and silt material (both approximately 42% of the area surveyed), with 13% cover of gravel/cobble material and minimal other substrate material.
- Stream channel widths at the bank stations ranged from 60 to 90 feet.
- Stream gradient at the 34 stations included both mid-gradient (65%) and low-gradient conditions (35%), based primarily on visible flow characteristics at low water.
- The degree of channel incisement at the survey stations was most often rated as somewhat incised (50%) or moderately incised (35%), with the remainder being not incised (no segments were rated as deeply incised or entrenched).

In addition to these physical characteristics, the bank stability and observed erosional condition at each station was generally characterized and described on Form RB-1, along with the location of the thalweg, where observable.



#### 4.2.2.2 Bordering Habitats

The habitats bordering each riverbank station were recorded using the natural community cover types described for the floodplain in Section 6.2.1 (as adapted from Woodlot 2002a). In general, for a habitat to be considered as "bordering" a riverbank station, the habitat is either directly adjacent to the bank or in sufficient proximity and with no encumbrances for wildlife to readily access the river from the habitat unit. These are separated into wetland or upland categories. Wetland habitat types include four forested wetland cover types – shrub swamp, shallow or deep marsh, wetland meadow, and vernal pool. Upland habitat types include five forested cover types, cultural or agricultural fields, or developed/disturbed cover types. Table 4-5 summarizes the bordering habitat conditions at each of the 34 riverbank survey stations. The following points summarize the key points related to these bordering habitat conditions:

- Transitional floodplain forest habitat borders all 34 riverbank stations to some extent.
- Other wetland habitats that border the riverbank stations include shallow emergent marsh (30% of stations), shrub swamp (20%), and deep emergent marshes (10%).
- Vernal pool habitat borders 32% of the riverbank stations.
- Upland habitats border 70% of the riverbank stations, with upland forest occurring at 56% of the stations, followed by upland fields (38%) and disturbed/developed conditions (15%).

### 4.2.2.3 Hydrologic Characterization

Hydrologic characterization at each bank station encompasses conditions in the channel between the riverbanks as well on the banks themselves. These include an estimate of the stream gradient (primarily based on flow conditions), degree of channel incision and connectivity with the floodplain, bankfull indicators, and other field-derived indicators of hydrologic/flow conditions. Hydrologic characteristics at the 34 riverbank stations in Reach 5A are summarized in Table 4-4, with key points as follows:

- Stream channel widths at the bank stations ranged from 60 to 90 feet.
- Stream gradient at the 34 stations included both mid-gradient (65%) and low-gradient conditions (based primarily on visible flow characteristics at low water).
- Most (91%) of the bank survey segments contain some topographic break which could contribute flow into the adjacent floodplain, and 65% of the bank stations bordered floodplain with high-flow channels which could function to disperse flood waters through the floodplain.



- The degree of channel incisement at the survey stations was most often rated as somewhat incised (50%) or moderately incised (35%), with the remainder being not incised (no segments were rated as deeply incised or entrenched).
- Bankfull indicators on the riverbank segments averaged a height of three feet (range of two
  to five feet) above the field-estimated mean low water level, although it is noted that actual
  bankfull flows will be determined by hydrologic references and subsequent field
  assessments.

### 4.2.2.4 Plant Community Composition

Riverbank plant community composition data obtained include estimates of vegetative cover from bank vegetation, overhanging vegetation, and riparian vegetation, with data collected for each strata (i.e., tree, shrub, liana/vines, herb); these data were collected separately for each side of the riverbank. Plant species composition was recorded overall for each bank station, including designation of any invasive species (no rare species were observed). Tables 4-8 through 4-11 provide summary data on the plant community composition surveyed at the Reach 5A riverbank stations. The data reflect relatively diverse tree and herbaceous communities along the banks in Reach 5A, with less diverse but still significant coverage at the shrub and vine/liana strata. Invasive species are prevalent in the shrub and vine strata, and to a lesser degree in the herbaceous stratum. The following points summarize the vegetative community composition along the riverbanks within the surveyed segments:

- Overall vegetative cover along the surveyed bank segments is estimated at 75% (range of 30-100%). Overhanging vegetation covers an estimated 60% of the bank surface area.
- Riverbank vegetative cover by the tree strata averages 40% (range of 0-90%), 45% by the shrub strata (range of 0-80%), 55% by the herbaceous strata (range of 0-90%), and 30% by vines (range of 0-70%).
- Riparian zone vegetative cover along the riverbank segments is an estimated 90% overall (range of 60-100%). This consists of 58% average cover by the tree strata (range of 10-80%), 65% by the shrub strata (range of 20-85%), 68% by the herb strata (range of 40-90%), and 25% by vines (range of 10-35%).
- A total of 118 different plant species occur in the 34 bank survey segments in Reach 5A.
   These include 23 tree species, 11 shrub species, eight species of vines, and 76 herbaceous species (including two aquatic species along the lower margins of the banks). Sixteen different invasive species were recorded (no invasive tree species, four invasive shrub species, one invasive vine species, and 11 invasive herb species).



- Box elder is the most common tree species, occurring in 60% of the survey segments, followed by silver maple (44%) and American elm (*Ulmus americana*) (24%). Other tree species occurring in 7-10% of the survey segments are green ash (*Fraxinus pennsylvanica*), sugar maple (*Acer saccharum*), ironwood (*Ostrya virginiana*), eastern cottonwood, American linden (*Tilia americana*), and eastern hemlock (*Tsuga canadensis*). Fourteen other tree species occur less frequently (Table 4-8).
- Of the 11 shrub species, red-osier dogwood (*Cornus sericea*) is the most prevalent (30% frequency), followed by the invasive common or European buckthorn (*Rhamnus cathartica*) (29%) and Morrow's honeysuckle (*Lonicera morrowii*) (22%). All other shrub species occur in less than 5% of the survey segments.
- The invasive vine Asian bittersweet (*Celastrus orbiculatus*) is the most common vine (59% frequency), followed by river grape (*Vitis riparia*) (37%) and wild cucumber (*Echinocystis lobata*) (15%).
- Six herbaceous species occur in more than 25% of the survey segments; the most common herbaceous species are pale smartweed (*Persicaria lapathifolia*) (56%), nodding beggar-ticks (*Bidens cernua*) (48%), and the invasive Japanese knotweed (48%). Slightly less prevalent herbaceous species include blue vervain (*Verbena hastata*) (32%), ostrich fern (*Matteuccia struthiopteris*) (30%), and water purslane (*Ludwigia palustris*) (26%). Thirteen other herbaceous species occur with more than 10% frequency (Table 4-8).
- The most prevalent invasive species are Asian bittersweet (59% frequency), Japanese knotweed (48%), common buckthorn (29%), Morrow's honeysuckle (22%), water forget-menot (*Myosotis scorpioides*) (18%), purple loosestrife (*Lythrum salicaria*) (12%), and bishop's goutweed (*Aegopodium podagraria*) (10%). Invasive species are discussed further in Section 9 of this BRA Report.

Tables 4-9 through 4-11 provide additional data summarizing the plant community along the surveyed bank segments. These include differentiation of the plant communities on the right bank and the left bank to provide an assessment of whether conditions noticeably vary between sides of the river. In general, there are no distinct trends indicating consistent differences between the left and right banks. Also, in reviewing the riverbank data from the Confluence to the downstream end of Reach 5A, there are no discernible or significant trends or differentiation of the conditions apparent in progressing down the reach.

#### 4.2.2.5 Other Habitat Features

Form RB-1 includes a broad selection of other habitat features that were recorded for each riverbank station. These include wildlife food plants; a variety of cover, perching, basking, denning, and



nesting habitat features; and specific features such as vertical sandy banks, undercut banks, and nesting sites for bank-specific species such as bank swallows. The connectivity of each bank station with adjoining natural habitats was also classified. These habitat features are shown in Table 4-12 and summarized as follows:

- Nearly all (97%) bank segments contain wetland and upland plants that provide food sources for wildlife.
- Most (74%) of the bank segments contain large (>30" diameter at breast height [dbh]) live or dead standing trees, and most (88%) contain cavities in the tree trunks or limbs. In addition, live or dead tall standing trees near water offering visibility for avifauna were abundant at 68% of the bank stations or present at 32% of the stations.
- Habitat features for small mammals and herpetofauna occur at most of the bank segments, including burrows (100%), dense herbaceous cover (97%), undercut or overhanging banks, and rocks/logs/crevices (97%).
- Vertical sandy banks offering habitat for bank swallows or kingfisher nesting occur at 18% of the bank survey segments, and bank swallow nesting colonies are present at 12% of the bank stations.

#### 4.2.2.6 Incidental Direct Wildlife Observations

During the course of the riverbank surveys, field observers recorded all direct observations of wildlife species (including evidence of species presence, such as tracks or scat). Table 4-13 provides a summary of these observations. Overall, a total of 30 species (or evidence of their use) were observed along the riverbanks. These include 22 bird species, three species of herpetofauna, two mammal species, and three invertebrates or fish species.

### 4.2.2.7 Rare Species Habitat

Both federal and state-listed rare species habitats have been assessed for each of the 34 riverbank stations in Reach 5A. The Core Area designations from MNHESP (MassDFW 2012) were overlain on the riverbank station mapping to determine whether the riverbank stations occur within any of the Core Areas. Further, the Species Habitat mapping provided by MNHESP was reviewed to record each state-listed species that has such mapping within any of the bank stations. Thirteen state-listed species have such Species Habitat mapping across the 34 riverbank stations, with potentially suitable habitat for each of these species observed within the riverbanks. Table 4-14 lists both the Core Area designations which apply at each bank station and the state-listed species that have mapped habitat overlaying each bank station. Review of the U.S. Fish and Wildlife Service (USFWS) on-line Information, Planning, and Consultation System (IpaC) for identification of federally listed rare species (USFWS 2023) resulted in the identification of habitat for only one such species within Reach



5A; habitat for the northern long-eared bat (*Myotis septentrionalis*) is mapped within the entirety of Reach 5A, and potential habitat for this species occurs along all riverbank stations. Rare species are further addressed in Section 8 of this BRA Report.

# 4.3 Description of Reach 5A Riverbank Habitats

# 4.3.1 Physical Description

The riverbanks of the Housatonic River in Reach 5 have substantial variability in physical appearance and function. The slope and height of these riverbanks vary, with height generally decreasing from the Confluence to Woods Pond. Riverbanks in Reach 5A are more consistent but still variable, generally ranging in height from three to seven feet (average of 6.2 feet among the surveyed stations), with areas of higher vertical banks ranging from eight to 12 feet high (some of these extending above the bank as defined herein, and/or above the 1 mg/kg PCB isopleth). Banks consist of silts and sands with a range of physical attributes, including sloped and vegetated banks, vertical and exposed banks, erosional banks with slumping, and erosional but vegetated banks. Vertical and exposed banks generally lack vegetative cover but provide habitat functions discussed in more detail below. Undercut banks are a common habitat component of the riverbanks in Reach 5A and are prevalent in Reach 5A, occurring in 97% of the surveyed bank stations. Mature trees overhanging the river and dense herbaceous and shrub communities are also prevalent on the banks in Reach 5A and provide shading to the river and foraging opportunities for wildlife.

Transitional between the river and the riverbanks are features such as point bars. Point bars are depositional features formed as the secondary flow of the stream sweeps and rolls sand, gravel, and small stones laterally across the floor of the stream, depositing that material on the inside bend due to slow river velocities so as to form a bar. Typically, point bars have a gentle slope and are often submerged during flood events and periods of high water. These river features accumulate downed woody material and other debris during times of high water levels, and allow for the emergence of insect larvae and for providing access between terrestrial and aquatic habitats for a variety of wildlife. Other riverine bar formations in the center of the channel and along the sides also serve similar functions.

# 4.3.2 Biological Communities

While the overall character of the Reach 5A riverbanks is primarily mature woodland, specific vegetative composition varies considerably based on factors such as location across the bank section (e.g., bank toe versus top of bank), hydrology, bank slope, and substrate. In general, the upper portions of the Reach 5A banks consists predominantly of trees, with interspersed sections being a shrub-dominated mix with some trees, vines, and herbaceous growths. Box elder, silver maple, and American elm form much of the bank canopy in Reach 5A, while the subcanopy, shrub and



herbaceous layers are variable based upon factors such as light (from shading) and elevation relative to river water stages and flooding. A variety of shrubs are abundant, most commonly red-osier dogwood and several invasive species (Morrow's honeysuckle and common buckthorn in particular). Asian bittersweet and Japanese knotweed are the most abundant invasive species on and near to the riverbanks in Reach 5A. Herbaceous species composition is a diverse mix of perennials and annuals, with the presence and distribution of the annuals expected to vary considerably between years based on river water levels and flows. Lower portions of the Reach 5A banks often support dense herbaceous growth which develop annually as the water levels recede.

The riverbanks within Reach 5A are an integral part of the overall riverine habitat in that reach. These banks provide a variety of functions for a range of wildlife species. Exposed vertical banks in Reach 5A provide suitable nesting habitat for two species of bank nesting birds – the belted kingfisher and the bank swallow. Belted kingfisher nest burrows have been documented within the 8- to 12-foot high portion of the right bank in the upper portion of Reach 5A (AECOM 2010), and bank swallow nesting cavities have also been noted in several of the higher sandy banks within Reach 5A. The vertical banks also provide potential nesting sites for several turtle species, including the state-listed wood turtle. The riverbanks in Reach 5A provide lodging habitat and slides for beaver and muskrat and foraging habitats for birds and mammals, including mink and raccoons. In particular, beaver activity along the banks is common in many places, with frequently occurring burrows evident. Undercut banks and woody accumulations offer hibernacula sites for wood turtles to overwinter. Large overhanging trees in this area provide shaded microhabitats and variability in water temperature within the river for fish, invertebrates, and shade-tolerant plant species, as well as foraging and perching sites for piscivorous and insectivorous birds.

Low slope areas of riparian banks, often occurring at the locations of point bars, are likely to provide better connectivity with the floodplain, including during smaller but higher frequency flood events (2- to 5-year flood frequencies). These low-lying slope zones are important for movements of aquatic invertebrates and amphibians and their larvae between in-stream and floodplain habitats. They also serve as hunting and feeding grounds for small mammals and wading birds and are prominent access points to the river for larger mammals such as deer and bear.

A total of 13 state-listed plant and animal species have NHESP-mapped Species Habitat that encompass the riverbanks in Reach 5A and could utilize those bank habitats based upon habitat requirements of each species and the riverbank habitats documented in these areas. These species are listed in Table 4-14 and discussed further in Section 8.

### 4.4 Reach 5A Riverbank Habitat Functional Assessment

Table 4-15 lists the applicable functional categories for the riverbank assessment, summarizes the primary bank functions that will be assessed, and lists, for each, the inventoried parameters from



Table 4-1 that contribute to developing the functional assessment. While the functional categories of riverbanks are the same as those assessed for riverine functions, the specific functions and parameters considered in assessing the functions vary between riverbank and riverine habitats. In addition to the hydrologic and geomorphologic functions, the bank assessment focused on the ecological and wildlife habitat functions that have been recognized in past investigations and that are related to specific habitat features such as vertical sandy banks and cut banks. The assessment of riverbank functions in Reach 5A has drawn from the information documented for that reach on Form RB-1, and addresses the functions and considerations presented in Table 4-15 to qualitatively relate the physical/structural conditions of the riverbank to the listed functions.

### Hydrologic/Hydraulic Functions

Riverbank hydrologic support functions, as used here, include water conveyance and transport, watershed connectivity, and floodwater dynamics (flood flow amelioration, flood storage and desynchronization, and peak rate control). The hydrologic and hydraulic functions of the river were discussed in Section 3.4, and the riverbank is inseparable from the river in terms of these functions, with the bank conditions often reflecting the stream hydrology in terms of flow conveyance energy and sediment dynamics (transport, erosion, deposition). A key function of the Reach 5A riverbanks is the role they play in affecting floodwater dynamics between the river channel and the floodplain. The channel-forming flow, or bankfull discharge or flow, which transports the majority of the flow and sediment over time, forms and maintains the river channel. While the Reach 5A riverbank conditions indicate some instability (e.g., tight meander bends with eroding outer banks, poor point bar development), the bankfull flow parameters generally indicate only slight stream incision, such that overbank flooding into the floodplain appears to generally occur during flows generated by the 1.5- to two-year storm events (i.e., a normal flooding regime). Based on the recent HHA results, this equates to a flow range of roughly 2,000-3,000 cfs at the Confluence.

### **Geomorphology Functions**

The geomorphology functional category includes the following functions: supply of organic and mineral sediment material, supply/processing of woody debris, effects on flow, and role in determining stream planform and geomorphic diversity. As described in Section 3.4, the riverbank is subject to and indicative of the same geomorphologic factors as the river channel. The Reach 5A riverbanks reflect and affect the geomorphic diversity and functions driven by the hydrologic factors. Bank erosion and deposition of sediment, vegetative conditions (including woody debris transport and deposition), and overall channel form (dimension, pattern, and profile) collectively reflect riverbank geomorphologic functions.



### **Physiochemical Functions**

Physicochemical functions of the riverbanks include water quality maintenance and water temperature and oxygen regulation for in-stream habitat. A key factor in the Reach 5A riverbank provision of this function is the extent of overhanging mature vegetation. This vegetative cover contributes to temperature moderation, which in turn aids in oxygen regulation. In addition, the variation in flow regime from woody debris and other bed features (riffles/runs/pools) also contribute to water quality maintenance for in-stream habitat.

### **Biological Functions**

Section 4.3.2 above describes many of the diverse biological functions provided by the Reach 5A riverbanks. These riverbanks provide lodging habitat and slides for beavers and foraging habitat for birds and mammals, including mink and raccoons. The exposed and/or undercut banks along portions of the river in this area provide potential nesting sites for belted kingfishers, bank swallows, and several turtle species, including the state-listed wood turtle. Woody debris accumulation along the cut riverbanks may provide hibernacula for the wood turtle. Along a substantial proportion of the Reach 5A riverbanks, the overhanging mature trees and other dense riparian vegetation also provide shaded microhabitats and variability in water temperature within the river for fish, invertebrates, and shade-tolerant plant species, as well as foraging and perching sites for piscivorous and insectivorous birds.



### 5.0 Reach 5A BRA of Backwater Habitats

The Revised Permit defines "backwaters" as "areas that are typically inundated or open water adjacent to the main channel of the river in Reaches 5, 6, and 7" (page 1). EPA's earlier *Final Supplemental Investigation Work Plan* (EPA 2000) provided a more refined definition: "Backwater areas are quiescent areas adjacent to the main river channel that maintain a hydraulic connection to the river channel" (page 5-8). Similarly, *GE's Supplement to Response to EPA's Interim Comments on CMS Report* (GE 2010) noted that, "[f]or remediation purposes, backwaters are generally addressed by the sediment (rather than floodplain) remedial alternatives, reflecting the fact that they generally have a direct surface water connection to the river" (page IN-3).

Backwaters refer more to a hydrologic condition than a distinct habitat type, encompass both riverine and floodplain natural community types, and generally have a direct surface water connection to the river. However, from the perspective of habitat, backwaters are predominantly deep marshes with either shallow (i.e., less than six feet deep) open water and/or floating and/or submerged aquatic vegetation. These areas have open surface water connections to the Housatonic River that allow unimpeded backwater flow from the river into them annually, and that backwater flow is the primary hydrologic input (versus other surface water inputs). Each backwater area is typically accessible to fish annually, which can occur much of the year. Backwaters were not a mapped community type in the Woodlot 2002 Ecological Characterization.

Table 5-1 provides a summary of the parameters that were incorporated into the assessment of backwater habitat in Reach 5A. The habitat inventory process for backwaters in Reach 5A first incorporated pre-existing information consolidated from sources listed in Section 2 of the Revised BRA Work Plan where applicable to Reach 5A. In addition, information on physical conditions within each confirmed backwater in Reach 5A was generated from the updated LiDAR mapping and associated topographic/bathymetric mapping and data conducted for the PSA under the Revised Reach 5A Sediment/Bank PDI Work Plan. This information was then supplemented by a more detailed field inventory and characterization of the habitat within each of the Reach 5A backwaters in 2022 and 2023.

# 5.1 Background Ecological Information

# 5.1.1 Woodlot Ecological Characterization (2002)

Although, as noted above, the Woodlot ecological characterization of the PSA (Woodlot 2002a) did not map backwaters as a distinct community type, it did contain numerous references to backwaters and the associated deep marsh habitat. However, virtually all the discussion and information on backwaters in that report pertain to the main backwater areas just north of Woods Pond (most of



which are in Reach 5C, but some extend north on New Lenox Road into Reach 5B). No specific references to backwaters in Reach 5A were noted.

## 5.1.2 RCRA Facility Investigation Report (2003)

The RFI Report included several references to backwaters (e.g., Section 8.8.2), separating those that are hydraulically connected to the main channel from those that are disconnected (including vernal pools). However, the focus of the RFI Report discussions was on PCB fate and transport rather than on habitat. No specific reference to backwater habitats in Reach 5A was noted in the RFI Report.

## 5.1.3 Corrective Measures Study Reports (2008-2010)

Section 5.3.6 of the RCMS Report summarized information on backwater habitats, noting that they are considered in the same category as deep marshes from a habitat standpoint. A preliminary identification of backwaters in Reaches 5 through 7 was depicted on Figure 3-17 of the RCMS Report. That mapping indicated four areas that were mapped as backwaters within Reach 5A; however, specific discussion of the habitat conditions within each of these was not provided.

### 5.1.4 Example Area Evaluations (2010)

As noted previously, the Example Area evaluations conducted by GE (GE 2010) included four areas within Reach 5A. Only one of these Example Areas (Example Area #2, within Canoe Meadows; see Figure 3-1b) contained a backwater area. This backwater, now identified as BW 5A-1, was described as follows:

"The floodplain also contains a large backwater, which retains flood waters and functions as a deep emergent marsh. This backwater provides habitat for reptiles (including the state-listed wood turtle), amphibians, and a variety of bird species (including the state-listed American bittern [Botaurus lentiginosus]), as well as numerous plant species (including two state-listed species – intermediate spike sedge and wapato). In addition, while this backwater was not listed by Woodlot as a vernal pool, evidence of wood frog breeding activity has been observed in this area, indicating that at least portions of the backwater may function as vernal pool breeding habitat." (GE 2010, page 13.)

# 5.1.5 Natural Heritage Information (2000-2022)

As with other habitats in the 2010 and 2011 reports, MNHESP also included these areas in its designation of Priority Habitats of rare species, without distinguishing occurrences within backwaters from those within the riverine and floodplain environments. However, the reports listed occurrences of mussel, fish, turtle, and amphibian target species, which may be encountered in backwater habitats at certain stages of life. The tables provided in the reports do not specify target species



found in Reach 5A backwaters, and the figures are provided for larger general regions which include Reach 5A. There were no specific descriptions of the conditions of backwaters in Reach 5A.

As noted In Section 3.1.7, MassDFW's July 2012 letter to EPA, which was attached to the Revised Permit, included maps depicting the locations of the different types of Core Areas, designated Core Area 1, 2, and 3, and presented the criteria for the designations. All three types of Core Areas include some backwater habitats. These are discussed further in Section 5.2.3.7.

As also previously noted, the updated digital information that MNHESP provided to GE in October 2022 included Species Habitat mapping of the state-listed species in the ROR, including Reach 5A. As described in Section 5.2.2.7 and further in Section 8, at least 11 of those species utilize habitats consistent with those present in the Reach 5A backwaters and have mapped Species Habitat overlapping Reach 5A backwaters.

## 5.1.6 Pre-Design Investigations of Reach 5A

Backwaters in Reach 5A were subject to further survey and identification in the 2018-2019 morphology and vernal pool investigations, and those changes have been carried forward into this current backwaters assessment process.

In 2018 through 2019, GE conducted investigations in Reach 5A in accordance with a Floodplain PDI Work Plan that was conditionally approved by EPA (Anchor QEA and AECOM 2017). Part of that work involved the classification of waterbodies in Reach 5A, including whether they are to be considered vernal pools, backwaters, or other waterbodies. The 2018-2019 field investigations and subsequent data analyses identified which waterbodies met the MNHESP criteria for vernal pool certification, and also identified which non-vernal pool areas met the criteria as "backwaters" as defined in the Revised Permit. That information was presented in 2020 reports to EPA (AECOM 2020; AECOM and Anchor QEA 2020). As reported therein, only two of the Reach 5A backwater areas identified in the RCMS met the backwater criteria, but four other areas identified and mapped within Reach 5A were determined to meet the criteria for backwaters, resulting in a total of six backwaters in Reach 5A. Accordingly, as provided in the Revised Reach 5A BRA Work Plan, the BRA for Reach 5A backwaters was conducted in those six backwaters. Those backwaters are shown on Figure 5-1 and described in Section 5.2.2.

Backwater investigations were also included as part of the Reach 5A PDI activities. As part of these investigations, a bathymetric survey was conducted throughout the main channel and backwaters

53

<sup>&</sup>lt;sup>10</sup> As also noted above, Cores Areas 1, 2, and 3 are defined in Section 6.1.5 of this report; and Section 8 provides further information on the Core Habitat designations by MNHESP.



within Reaches 5 and 6. This survey was conducted in late April and early May 2022, and was used with LiDAR survey to generate updated topographic/bathymetric mapping.

Sampling of the six backwaters within Reach 5A (BW5A-1 through BW5A-6) was conducted on a 50-foot grid as prescribed in the Revised Sediment/Bank PDI Work Plan. At each location, water depth was measured, and a 0.5-inch-diameter (or less) steel probe was used to determine the sediment composition and to determine if advancement of a sediment sampler to the target depth of 5 feet in the backwaters was possible. A total of 484 samples (including 461 environmental samples and 23 field duplicates) were collected from all 127 target locations in the Reach 5A backwaters and sent for analysis of PCBs as Aroclors using EPA Method 8082 and total organic carbon. In addition, porewater PCB concentrations were measured at 20 locations within the main channel and backwaters of Reach 5A. The results of these sampling activities were presented in the September 28, 2023 PDI Summary Report for Reach 5A Sediments and Riverbanks.

The updated topographic/bathymetric mapping and sediment sampling of the Reach 5A backwaters contribute to the documentation and understanding of backwater habitat conditions.

## 5.2 2022-2023 Backwater Habitat Investigations

### 5.2.1 Methods

In addition to the information described in Section 5.1, a more detailed field inventory and characterization of the habitats within the six Reach 5A backwaters was conducted during field surveys in 2022 and 2023. Table 5-1 provides a summary of the parameters that were incorporated in the assessment of backwater habitats in Reach 5A. The parameters inventoried are documented on Form BW-1 (provided in Appendix C), which includes documentation of physical connectivity with the river, sediment composition, aquatic biota, rare species habitat, and invasive species presence, as well as incidental wildlife observations. That form was completed for each backwater within Reach 5A.

GE also collected water quality data from the backwaters during the 2023 growing season (due to the lack of sufficient surface water during the 2022 field surveys). A Yellow Springs Instrument (YSI) Pro Dss Sonde 4M and data logger was used to collect information on water quality, and a YSI EXO Sonde and data-logger was used to collect chlorophyll and phycocyanin (total algae) data at three discrete point locations within each of the six backwaters in Reach 5A. These data were collected three times in each backwater during the 2023 growing season.

The Pro Dss Sonde 4M YSI was calibrated for each parameter prior to use daily. Deploying both the Pro Dss and EXO YSIs was conducted by lowering the sensors into the water column to a depth that allowed each sensor to be submerged but not disturb the pool bottom. The optical sensors



remained in the water column until the parameter sensor readings stabilized, approximately 10 minutes, then the readings were documented before removal. The YSI sonde and sensors were rinsed with clean water between each deployment to ensure accurate measurements. YSIs were cleaned and stored in provided cases at the end of each day. The resulting water quality data are recorded on Form BW-1, which includes a section to record those data.

### 5.2.2 Overview of Reach 5A Backwaters

Before presenting the results of the 2022-2023 field investigations, this section provides an overview of each of the six backwaters in Reach 5A (as shown on Figure 5-1), including location, setting, and general description of each area, based both on previous pre-design investigations (including the updated LiDAR mapping) and on the 2022-2023 field surveys.

#### **BW 5A-1**

This backwater is situated along the eastern side of the Housatonic River between Stations 73 and 86 (as used in the riverine and riverbank habitat assessments). BW 5A-1 covers approximately two acres within Canoe Meadows and is connected hydrologically to the Housatonic River by a well-defined swale which extends northeast off the main channel of the river near Station 86. The swale is approximately three feet wide at its bottom elevation and extends for a distance of roughly 50 feet between the river and the backwater. This connecting swale typically runs dry during low flow periods. In addition, there is another high-flow channel that allows surface waters to be conveyed from the backwater to the southeast directly to Sackett Brook during larger flooding conditions.

While classified as a deep marsh, this backwater is subject to extreme variations in water depth, with depths of at least four feet during spring flooding followed by near complete draw-down during summer low flow periods. This backwater has formed in what is likely a remnant meander scar of the Housatonic River and is bounded by steep upland forested slopes on the northern and eastern sides, and floodplain forest along the western and southern sides.

#### BW 5A-2

This backwater is situated along the western side of the Housatonic River between Stations 117 and 120 in the northern portion of the George L. Darey Housatonic Valley Wildlife Management Area (WMA). Based on its geomorphology, this backwater appears to be a remnant oxbow channel of the river. It is approximately 460 feet in length and 26-44 feet wide and covers an area of 0.38 acre. It is connected hydrologically to the river at the southern end with a low, broad channel, and at high water (likely at bankfull) on the northern end with a higher elevation opening. This backwater is largely deep marsh habitat and is likely flooded throughout the growing season in most years.



BW 5A-2 is bordered by floodplain forest in the northern and southern portions, and by wet meadow floodplain in the central portion.

#### **BW 5A-3 and BW 5A-4**

These two backwaters occur in close proximity to each other along the western side of the River between Stations 126 and 128 in the northern portion of the George L. Darey Housatonic Valley WMA and southwest of BW 5A-2. The primary connection for both of these backwaters to the river is at their southernmost points; however, during high water stages, flow from the river discharges over the floodplain to the northern ends of these backwaters. These are relatively small backwater pools, ranging in size from 0.04 to 0.16 acre. The connecting channels between these backwaters and the river range in length from 60 to 80 feet in width and from two to three feet deep, and typically remain with standing water one to two feet deep even at low flow periods. Both of these areas primarily provide shallow marsh habitat, and BW 5A-3 also contains some deep marsh habitat. BW 5A-3 is bordered on the western side by upland forest (with a sewer utility line in close proximity) and on the eastern side by floodplain forest. BW 5A-4 is bordered by a combination of floodplain forest and floodplain wet meadow.

#### **BW 5A-5**

This backwater is situated along the southern/western side of the Housatonic River between Stations 143 and 150 in the southern portion of the George L. Darey Housatonic Valley WMA. It is a long, linear depression (1,020 feet long by 25-70 feet wide), covering approximately 1.6 acres, that runs along the base of a steep upland slope on its eastern side, and is bordered on the western side by an extensive marsh which discharges surface water into the southwestern end of BW 5A-5. The northern end of this backwater is connected to the river at high water by a low-lying marsh roughly 100 feet wide, but during lower flow periods, only two narrow channels through the marsh provide a hydrologic connection. BW 5A-5 is classified as a deep marsh and is likely flooded throughout the growing season in most years.

### **BW 5A-6**

This backwater is situated along the western side of the Housatonic River at the downstream end of Reach 5A, and it receives the discharge from the Pittsfield WWTF along its southwestern edge. This backwater is approximately 0.33 acre in size and classified as deep marsh habitat. The surface water connection to the river along the eastern side of this backwater is approximately 130 feet long; however, at low water, only a small (25 foot long) section of this remains with flowing water open to the river (to allow the WWTF effluent to discharge).



### 5.2.3 Results

The data collected during the 2022-2023 field surveys of the six backwaters were recorded on Form BW-1. The completed forms for all six backwaters are provided in Appendix C. Based upon information in those forms, the following subsections provide an overall characterization of the Reach 5A backwater habitats.

### 5.2.3.1 Physical Characterization

The physical characteristics of the Reach 5A backwaters are important in assessing the habitat functions that these areas may support. These backwaters are relatively small, ranging in size from 0.04 to two acres in area, and in all but one case are linear features which extend out from bends in the river into the surrounding floodplain (with upland forest also bordering three of the six backwaters along one side). Based on inspection of soil profiles taken during characterization of the backwaters, substrates in all the backwaters typically consist of relatively high organic silty muck soils, consistent with the deep marsh habitats which comprise most of these areas. There were no signs of instability or erosion at any of the backwaters, consistent with the slack water that these areas generally receive during backwater flooding events.

### 5.2.3.2 Bordering Habitats

Figure 5-1 includes the habitat cover types which border the Reach 5A backwaters. As is typical for much of the Reach 5A area, the most common bordering habitat condition for the six backwaters is transitional floodplain forest, although wet meadow floodplain habitat also borders three of the backwaters and upland forested habitat also borders portions of three of the backwaters.

### 5.2.3.3 Hydrologic Characterization

Integral to the definition of backwater areas, all six of the Reach 5A backwaters share a similar hydrologic regime based upon ephemeral surface water connections to the river. While the physical dimensions of the surface water connections between these six backwaters and the river vary (as described above), each affords surface water backflooding from the river during river water levels more frequent than the annual flood level. In general, the elevation of the swales that connect these backwaters to the river appear to be at least two to three feet below bankfull level. In several of the backwaters, there are also other surface water connections between the backwater and other wetlands or surface waters, which also affect the hydrologic conditions in and around the backwater. In all cases, the backwater connections to the river result in flooding of the backwaters during high flow periods (often several feet deep), followed by very shallow water or near dry conditions during summer low flow periods. Despite the drought conditions observed during the 2022 field investigations, the hydrologic conditions within the Reach 5A backwaters were adequately characterized based on hydrologic indicators (e.g., high water marks on trees) and vegetative composition. Hydrologic characterizations of the backwaters were also augmented by reviews of



these areas during water quality sampling in May and June of 2023. Further, all Reach 5A backwaters were reviewed intensively during the 2018-2020 PDI field surveys as presented in 2020 reports to EPA (AECOM 2020; AECOM and Anchor QEA 2020), contributing to the understanding of hydrologic regimes in these backwater habitats.

## 5.2.3.4 Plant Community Composition

During the 2022 surveys, a total of 55 plant species were documented within the six backwater habitats in Reach 5A. These plant species are listed in Table 5-2. They include 49 herbaceous species (including submerged, emergent, and floating-leaved aquatics), one shrub, four trees, and one woody vine. The most frequently occurring species were nodding beggar-ticks and rice cutgrass (*Leersia oryzoides*), with both occurring in all six backwaters. Silver maple occurred in five backwaters and dotted smartweed (*Persicaria punctata*) occurred in four backwaters. In addition, 14 plant species occurred in three backwaters, 15 plant species occurred in two backwaters, and 22 plant species occurred in one backwater (see Table 5-2).

A total of seven invasive herbaceous plant species were observed in the backwater habitats, as shown in Table 5-2. These include two aquatic plants, Eurasian watermilfoil and water chestnut (*Trapa natans*). No invasive shrubs, trees, or vines were observed in the backwaters. Three of the invasive herbaceous species were observed in three backwaters, two were observed in two backwaters, and the remaining two were observed in one backwater. In addition, one non-native (but not invasive) plant species was observed in BW 5A-2. The backwater observed to have the most species of invasive plants was BW 5A-2 with five invasive plant species, followed by BW 5A-3 with four invasive plant species, and then BW 5A-1, 5A-4, 5A-5, and 5A-6, each with two invasive plant species.

During the 2022 surveys, western Massachusetts was in a moderate to severe drought and backwater habitats were observed to be dry or nearly dry. These conditions likely affected the species composition and total cover of floating-leaved versus aquatic submergent and emergent cover types observed. In 2022, the dominant cover type was emergent marsh and submerged aquatic plant species, with an average cover of 84.3% (range 63.0%-98.0%). Floating-leaved plants such as the yellow pond lily (*Nuphar variegata*) exhibited comparatively low cover and were observed only in BW 5A-1. Tree cover was also relatively low, with an average of 16.7% cover and a range from zero (BW 5A-2) to 38.0% (BW 5A-1 and 5A-4).

Plant community composition in backwaters can change dramatically with hydrologic variability and with seasonality, particularly in the herbaceous layer. Although the 2022 surveys were conducted at a time of low water, the organic and mucky substrates remained mostly saturated and retained the floating-leaved and submerged aquatic plant community indicative of more aquatic conditions, while also indicating what is present in the seed bank of these systems (in the form of colonizing



herbaceous plants). As water levels drop, species intolerant of flooding germinate from the existing seedbank, but species that grow in flooded conditions are still visible, thereby providing a more comprehensive picture of the plant community in these systems compared to conducting plant surveys during flooded conditions (see representative photographs in Appendix C).

All six backwaters were re-visited in May and June of 2023 to collect data on water chemistry. Water levels at this time were generally higher than during the 2022 inspections. Although no additional data on plant species composition were collected in 2023, representative photographs show that a much higher diversity of plant species was present during low-water conditions as observed in 2022 than during the higher water levels in 2023. However, GE will revisit each backwater once in 2024 during mid- to late-spring to verify species occurrences and check for aquatic submergent, emergent, and floating-leaved plants that may not have been observed in 2022.

#### 5.2.3.5 Other Habitat Features

Form BW1 included a broad selection of other habitat features that were recorded for each backwater. These include wildlife food plants; a variety of cover, perching, basking, denning, and nesting habitat features; and specific features such as turtle nesting sites, undercut banks and habitats specific to bank swallows, wading birds and waterfowl. These data are presented by observation plot in Table 5-3 and summarized in Table 5-4 and as follows:

- Wetland and/or aquatic food plants were present or abundant in all backwaters.
- Structural features, such as cavities in trunks or limbs of live trees, large woody debris, root
  wads, dense herb cover, or hummocks that provide for perching, breeding, nesting and/or
  escape cover, were also found in all the backwaters.
- No open sandy to gravelly soils with sparse vegetation suitable for turtle nesting or vertical sandy banks typically used by kingfishers and bank swallows for nesting were observed.

#### 5.2.3.6 Incidental Wildlife Observations

During field surveys in the six backwaters in Reach 5A, observations were recorded on the backwater form to document wildlife use of these areas (see Appendix C). Among the wildlife observations were eight species of birds: great blue heron (*Ardea herodias*), belted kingfisher, blue jay (*Cyanocitta cristata*), gray catbird (*Dumetella carolinensis*), cedar waxwing (*Bombycilla cedrorum*), goldfinch (*Carduelis carduelis*), tufted titmouse (*Baeolophus bicolor*), and yellow warbler (*Setophaga coronate*). Herpetofauna observed included snapping turtle (*Chelydra serpentina*), pickerel frog (*Lithobates palustris*), green frog (*Lithobates clamitans*), American toad (*Anaxyrus americanus*), and garter snake (*Thamnophis sirtalis*). Mammal signs included tracks or scats of raccoon, white-tailed deer, coyote (*Canis latrans*), and black bear.



#### 5.2.3.7 Rare Species Habitat

There are 11 state-listed plant and animal species that have MNHESP-mapped Species Habitat within the backwater habitats of Reach 5A and that could utilize those habitats based upon habitat requirements of each species and the backwater habitat conditions documented to occur there. The species with mapped habitat that overlays 5A backwaters are listed in Table 5-5 and are further discussed in Section 8. As noted previously, all three Core Areas designated by MNHESP include backwater areas. Two backwaters (BW 5A-1 and 5A-2) fall within Core Areas 1, 2, and 3, and three backwaters (BW 5A-3, 5A-4, and 5A-5) fall within Core Areas 2 and 3. The backwater near the Pittsfield WWTF discharge (BW 5A-6) does not fall with any Core Area.

## 5.2.3.8 Water Quality

Baseline water chemistry was collected from the backwaters in 2023, using a YSI meter, three times during the early growing season – May 9, June 6, and June 14, 2023 – in backwaters BW 5A-1 through BW 5A-5. In BW 5A-6, no water was present in the backwater for the two June inspections and therefore only one round of sampling was completed.

Each sample collection event included sampling in three locations equally spaced throughout the pooled/submerged portions of the backwater. Sample readings occurred at the same location during each event. Parameters measured included pH, Temperature °C, Specific Conductivity, Dissolved Oxygen (% and mg/l), and Chlorophyll-a (mg/l). Results are presented in Table 5-7. The backwaters generally have pH (7.69 average) and specific conductivity (463 average) levels that indicate the influence of calcareous groundwater discharge. Chlorphyll-a readings were generally within the normal range (1-3 mg/l) of surface waters in non-eutrophic lotic habitats, with one high reading (40 mg/l) found in BW 5A-6 where the Pittsfield WWTF discharge likely influenced the level.

To develop a more representative baseline of water chemistry in backwater habitats, and as directed in EPA's December 21, 2023 conditional approval letter, GE will conduct two additional rounds of sampling in each of the six backwaters during mid- to late summer in 2024 if water is available for sampling in these backwaters.

# **5.3 Description of Reach 5A Backwater Habitats**

The six designated backwaters in Reach 5A consist generally of deep marsh habitat occurring on saturated, mucky mineral soils that are seasonally inundated and permanently saturated. The substrate is flooded by waters that are not subject to significant wave action, with water depths ranging from six inches to six feet. Water levels fluctuate seasonally, but the substrate is rarely dry, and there is usually some standing water throughout the year. The vegetation in deep marshes is quite variable. It may be co-dominated by a mixture of species or have a single dominant species. In Reach 5A, dominant plant species within backwaters are nodding beggar-ticks and rice cut-grass,



both of which occurred in all six backwaters, plus silver maple and dotted smartweed. Reach 5A contains approximately 3.91 total acres of backwaters areas, with individual backwaters ranging in area from 0.04 to 2 acres.

The presence of fish in the Reach 5A backwaters likely varies considerably from that in the backwaters and deep marshes within the remaining portions of the PSA. The key feature of backwaters and deep emergent marshes that drives the wildlife function of these habitats is the hydrologic connection to the Housatonic River. During periods of high water when these areas are connected to the Housatonic River, fish can migrate between the backwater habitat and mainstem of the river. In smaller backwater areas of Reach 5A, as the high water recedes, fish would be expected to return to the river, although some may be trapped within the backwaters. By contrast, the larger backwater areas in the vicinity of Woods Pond contain open water year-round and provide suitable habitat for fish, including brown bullhead, common carp, goldfish, bluegill, largemouth bass, yellow perch, and white sucker. The fisheries habitat of the Reach 5A backwaters is quite different and much more seasonal in use.

The Reach 5A backwater areas and associated deep emergent marshes are also utilized by a range of bird, mammal, amphibian, and reptile species that rely on these areas for foraging, shelter, and breeding. These backwater and marsh habitats can be used for nesting and foraging for a variety of bird species, including the state-listed American bittern, the state-listed common gallinule (Gallinula galeata), wood duck (Aix sponsa), mallard duck (Anas platyrhynchos), great blue heron, and green heron (Butorides virescens). Wading birds prefer these backwater and emergent marsh areas of open water with minimal current for foraging. Species presence may vary among years depending upon the hydrologic conditions of the backwater and marsh habitats. Amphibian and reptile species also use these habitats for foraging, breeding, and thermal regulation, including northern leopard frog (Lithobates pipiens), green frog, snapping turtle, spotted turtle (Clemmys guttata), eastern painted turtle (Chrysemys picta picta), eastern garter snake, northern water snake (Nerodia sipedon) and the state-listed wood turtle. In addition, during years when standing water exists through the amphibian breeding season, obligate vernal pool species such as wood frog (Lithobates sylvaticus) and spotted salamander (Ambystoma maculatum) may use portions of these areas for breeding. Although other amphibian species will often prey on obligate vernal pool species, the diversity of micro-habitats within certain backwaters, particularly BW-5A-1, may allow for some coexistence between obligate species and those that normally prey on these species – e.g., by providing secluded areas in dense vegetation and organic debris for egg masses and developing larvae of the obligate species.

## 5.4 Reach 5A Backwater Habitat Functional Assessment

Key functions of backwater areas within Reach 5A consist of wildlife habitat, fisheries habitat, flood storage, and water quality functions, as shown in Table 5-6. These are described qualitatively in this



Reach 5A BRA Report, using the data obtained during the 2022-2023 field surveys, with a focus on describing key characteristics and parameters to be considered in restoration plans for the affected backwaters. The site-specific information collected for each backwater as documented on Form BW-1 has been used in the functional assessment, considering the physical and hydrologic characteristics, substrate conditions, specific habitat features, connectivity with surrounding habitats, and the presence of both rare and invasive species habitats.

#### Wildlife Habitat Function

As described in the previous section, Reach 5A backwater areas and associated deep emergent marshes provide habitat for a variety of bird, mammal, amphibian, and reptile species that rely on these areas for foraging, shelter, and breeding. Of the six individual backwater areas, BW 5A-1 in Canoe Meadows provides the highest quality habitat, despite it having the most ephemeral surface water connection to the river, due to its secluded setting among mature floodplain and upland forested area, diversity of vegetative cover resulting from variable hydrologic conditions, and a secondary overflow swale connection to Sackett Brook to the southeast of the backwater.

#### **Fisheries Habitat Function**

As described in the previous section, during periods of high water when the backwaters are connected to the Housatonic River, fish can migrate between the backwater habitat and mainstem of the River. In smaller backwater areas of Reach 5A, as the high water recedes, fish would be expected to return to the river, although some may be trapped within the backwaters. Given the relatively small total area of backwater habitat in Reach 5A, those backwaters would not provide much overall fisheries habitat; but during specific hydrologic conditions such as major storms, these habitats may provide refuge habitat, particularly for smaller fish. In some cases, the backwaters may be "sinks" for fish, where they are trapped internally as water levels recede and succumb to lack of surface water during low flow periods. This is especially true of BW 5A-1 in Canoe Meadows, because it has the most ephemeral surface water connection to the River and is the most likely to draw down to a dry surface during the summer.

#### Flood Storage Function

Backwaters contribute to flood storage functions given that they tend to be accessible to overbank flooding by more frequent storm events. The surface water connections between all six backwaters in Reach 5A and the river appear to be at least two feet below the bankfull stage, such that floodwaters can flow into these storage basins several times per year. Given the overall small area of these backwaters, the significance of this storage function by itself is not likely to be high. However, the depressional storage provided by the backwaters along with the continuity they provide for



floodflows across the floodplain contribute to the net storage and flood peak desynchronization function of the floodplain in Reach 5A.

## **Water Quality Function**

Water quality functions of the backwaters in Reach 5A include the capacity to settle suspended solids as backwater flooding is dispersed into the quiescent waters of these areas during flood events, along with associated removals/settling of adsorbed constituents which could impair surface water quality. BW 5A-6 is in a particularly relevant setting to improve water quality in the discharge from the Pittsfield WWTF, which discharges into the southwestern corner of this backwater and is dispersed across the area to the main stem of the river.



# 6.0 Reach 5A BRA of Floodplain Habitats (excluding Vernal Pools)

Reach 5A includes approximately 365 acres of floodplain habitat between the riverbanks and the 1 mg/kg PCB isopleth (which approximates the 10-year floodplain). Since the Housatonic River itself comprises approximately 45 acres, there are a total of approximately 410 acres within the 1 mg/kg isopleth. The BRA of the floodplain in Reach 5A involved: (1) review and consolidation of background ecological information from other sources; (2) generation of base mapping and classification of the habitats within the floodplain; (3) field assessment of baseline conditions in the floodplain wetland habitats; and (4) field assessment of baseline conditions in floodplain upland habitats. It also included, as required by the Final Revised SOW, a survey of features in the area designated in the Revised Permit as expanded Exposure Area (EA) 10, which is in Canoe Meadows and is owned by the Massachusetts Audubon Society (Mass Audubon)

# 6.1 Background Ecological Information

The floodplain habitat inventory process for Reach 5A was initiated by incorporating information from the sources referenced in Section 2 of the Revised Reach 5A BRA Work Plan (where applicable to the Reach 5A floodplain), as well as from the Reach 5A floodplain PDI. A summary of information on floodplain habitats in Reach 5A from those investigations is provided below.

# 6.1.1 Woodlot Ecological Characterization (2002)

As described in Section 3.1.1, the ecological characterization carried out by Woodlot for the PSA included a variety of biological investigations (Woodlot 2002a). In the Woodlot report, specific references to floodplain conditions within Reach 5A are infrequent. However, in the overall mapping of community types, Woodlot provided a baseline of the aerial distribution and extent of different floodplain habitat types that occur in Reach 5A. For example, the Woodlot mapping includes 361 acres of floodplain habitat in Reach 5A, with most of it (84%) consisting of wetland habitat, and most of the wetland habitat (40%) consisting of transitional floodplain forest. Comparison of the Woodlot mapping with the current habitat mapping, as provided in the following sections, is useful to assess successional patterns and habitat changes in Reach 5A.

Specific to Reach 5A, Woodlot notes that "beginning from the confluence of the East Branch and West Branch Housatonic River, the floodplain is relatively narrow (ca. 100 – 250 m) and less structurally diverse compared to downstream portions of the PSA. Where the natural communities are intact, the upstream region is primarily vegetated by riparian forests that receive over bank flow during high-water events. Herb- and shrub-dominated, seasonally flooded depressions occurred in this area and were found to be utilized by breeding amphibians" (Woodlot 2002a, page III-1-6).



# 6.1.2 RCRA Facility Investigation Report (2003)

Although, as previously noted, GE's 2003 RFI Report was focused on documenting the extent of PCBs in the river, it did provide some relevant floodplain habitat information, some of it specific to Reach 5A. In general, however, the RFI Report referred to the depiction of habitat conditions provided by Woodlot (2002a). For example, Figure 2-14 of the RFI Report provided mapping of floodplain vegetation that includes Reach 5A, and the depicted community types are based on those presented in the Woodlot ecological characterization.

# 6.1.3 Corrective Measures Study Reports (2008-2010)

GE's 2008 CMS Report presented substantial information on ecological baseline conditions in the PSA, including the Reach 5A floodplain; and the 2010 RCMS Report included a substantially expanded description of the affected habitats. In particular, Section 5 of the RCMS Report described the habitat characteristics of each of the floodplain habitats in the overall PSA, including those in Reach 5A. Other than describing potential impacts from remedial alternatives, however, there are few details provided specific to Reach 5A, such as descriptions of floodplain habitat conditions which apply directly or only to this reach of the PSA.

# 6.1.4 Example Area Evaluations (2010)

As discussed in Section 3.1.6, GE's February 2010 Supplement to Interim Response presented detailed evaluations of six Example Areas in Reaches 5A to 5C (AECOM 2010). Four of those Example Areas included portions of the floodplain in Reach 5A. Those example areas are shown on Figure 6-1. Those evaluations contain considerable information on the existing ecological conditions and functions in the selected Example Areas, as well as the impacts of remedial alternatives on those conditions and functions.

The four Example Areas in Reach 5A contain a variety of floodplain habitats, including transitional floodplain forest, high terrace floodplain forest, shrub swamp, shallow and deep marshes, wet meadow, and vernal pools. These habitats were subject to detailed field investigations and reporting on the ecological conditions found there, including detailed discussions of the wildlife species present or anticipated to use each area (including state-listed species). Detailed mapping of the existing habitat features were created for each area. The following points summarize the floodplain habitats described for these four Example Areas:

• The floodplain bordering the river in Example Area #1 consists predominantly of transitional floodplain forest, and includes swales, depressions, former river meanders, and complex microtopography. Dense herbaceous and shrub vegetation, numerous mature largediameter trees, and abundant coarse woody debris and dead tree snags are present in this



area. The transitional floodplain forest connects other natural communities in this area, which include shallow and deep emergent marsh, shrub swamp, and wet meadow. These habitats are periodically flooded and contain varied soil textures typical of such wetlands. This Example Area also contains several depressions that were at that time confirmed or potential vernal pools. The transitional floodplain forest around these pools provides non-breeding habitat for the vernal pool amphibians.

- The floodplain in Example Area #2 is also dominated by transitional floodplain forest, with abundant large woody debris and standing dead snags and dense herbaceous cover. The floodplain also contains a large backwater, which retains flood waters and functions as a deep emergent marsh and may also provide breeding habitat for vernal pool species. The surrounding forested areas would provide non-breeding habitat for the vernal pool species.
- The floodplain in Example Area #3 is dominated by transitional floodplain forest, which has a dense tree canopy, a sparse shrub layer, a dense herbaceous layer, and abundant large woody debris. The floodplain in this area also contains red maple swamp a forested habitat consisting of a fairly open canopy, a dense shrub layer, and little herbaceous vegetation. Example Area #3 also contains several types of non-forested wetlands. These include: (a) three areas of shallow emergent marsh, which are dominated by invasive plant species such as purple loosestrife and/or reed canary grass (*Phalaris arundinaceae*); (b) a deep emergent marsh; and (c) a wet meadow, which is maintained as part of a natural gas pipeline right-of-way.
- The floodplain in Example Area #4 consists predominantly of high terrace floodplain forest, shrub swamp/emergent marsh, and former agricultural fields. Overbank flooding and deposition has formed swales, deep depressions, levees, and complex microtopography through the floodplain. The high terrace floodplain forest, which is a relatively uncommon habitat type in the PSA, is characterized by rich calcareous (derived from calcium-rich bedrock) soils and supports large-diameter canopy trees, dead tree snags, and large woody debris, along with dense herbaceous cover. In the central portion of the example area, a large shrub swamp/emergent marsh complex receives surface water supply from a broad shallow swale to the north and is semi-permanently flooded as a result of an active beaver dam within a deep swale draining toward the Housatonic River to the south. Five vernal pools designated by Woodlot (2002) were present in Example Area 4.

# 6.1.5 Natural Heritage Information (2000-2022)

The MNHESP investigations, data, mapping, and reports on the Housatonic River watershed (described in Section 3.1.7) encompassed the habitats of the Reach 5A floodplain (MNHESP 2010, 2011). These efforts included targeted surveys to provide updated information on state-listed



species within the floodplain habitats, as well as designation of Priority Habitats of rare species. As noted in Section 3.1.7, as of 2010, this research confirmed the presence of at least 20 state-listed species in Reach 5A and resulted in the preparation of updated Priority Habitat mapping for each of these species, which was included in the 2010 RCMS Report. Many of these state-listed species are associated with floodplain habitat in the Housatonic River, at least during some of the species' life stages.

The 2011 MNHESP report did not specifically describe the conditions of Reach 5A but did characterize the "Upper Housatonic River Valley area at the lower ends of the East and West Branches" as containing "extensive floodplain wetlands and forests, and high-quality headwater streams that drain the western slopes of October Mountain" (page 11). The report listed occurrences of state-listed turtle and amphibian target species, which may be encountered in Reach 5A floodplain habitats at certain stages of life.

As also discussed previously, MassDFW's July 2012 letter to EPA, which was attached to the Revised Permit, included maps depicting the locations of the different types of Core Habitat Areas, along with the criteria for the designations. Core Areas 1, 2, and 3 include floodplain habitats in Reach 5A. Core Area 1, which MNHESP classifies as the highest quality habitat for species that are most likely to be adversely impacted by PCB remediation activities, comprises 59 acres in Reach 5A and includes seven state-listed species with mapped Species Habitat in the Reach 5A floodplain; and it also includes a floodplain forest community type (the high terrace floodplain forest) which occurs in Reach 5A. Core Area 2 (classified by MNHESP as the highest quality habitat for more mobile species that may be less vulnerable to remediation impacts, species where the habitat is likely to be somewhat more easily restored, and listed species that may be more of somewhat lower conservation concern, given their state-wide distribution) comprises 263 acres in Reach 5A and includes four state-listed species with mapped Species Habitat in the Reach 5A floodplain. Core Area 3 consists of areas where Species Habitat mapping of at least eight state-listed species overlap and comprises 105 acres in Reach 5A.

Further, as previously noted, the updated digital information that MNHESP provided to GE in October 2022 included Species Habitat mapping of the state-listed species in the ROR, including Reach 5A. As described in Section 6.3 and further in Section 8, at least 21 of these species utilize habitats consistent with those present in the Reach 5A floodplain and have mapped Species Habitat in the Reach 5A floodplain.

# 6.1.6 Pre-Design Investigations of Reach 5A Floodplain

Floodplains in Reach 5A were subject to further survey and identification in the 2018-2019 morphology and vernal pool investigations, and those changes have been carried forward into this current floodplain assessment process. Specifically, in 2018 and 2019, GE conducted investigations in Reach 5A in accordance with its 2017 Floodplain PDI Work Plan (Anchor QEA and AECOM 2017).



Part of that work pertained to identifying changes in floodplain cover types that could affect "super habitat" delineations and accessibility categories. In particular, in its January 25, 2018 conditional approval letter for that work plan, EPA directed GE to identify "any visually apparent changes in morphology that have occurred since the Woodlot (2002) survey or other appropriate baseline survey of topographic features and that could affect property boundaries, super habitat boundaries, (and) application of accessibility factors." The resulting information was obtained and presented in 2020 reports to EPA (AECOM 2020; AECOM and Anchor QEA 2020), and has been taken into account in this BRA, as discussed further in Section 6.2.1.

# 6.2 Baseline Mapping and Classification of Floodplain Habitats

## 6.2.1 Methods

In addition to consolidating information from the sources described in Section 6.1, updated base mapping of the Reach 5A floodplain was generated, including classification of floodplain natural communities, wildlife habitat features, and dense monoculture stands of invasive plant species. For this purpose, floodplain habitats have been divided generally into wetland habitats and upland habitats. In addition, the Reach 5A floodplain was mapped by drainage class as described in a *Classification of Wetlands and Deepwater Habitats of the United States* (FGDC 2013). Vernal pools in the floodplain are discussed separately in Section 7.

Characterization of floodplain habitats and natural communities along the Housatonic River in the PSA was originally performed by Woodlot and presented in its ecological characterization report (Woodlot 2002a). As part of that characterization, ecological community type mapping was produced for the PSA, including all floodplain habitats, and that work was incorporated into updated mapping of Reach 5A. Updated floodplain community cover mapping conducted in Reach 5A during the 2018-2019 morphology surveys was also incorporated into the floodplain classification and mapping process. As documented in GE's 2020 Final Accessibility Report for Reach 5A (GE 2020), portions of the floodplain within that reach showed significant changes in habitat boundaries since the 2002 Woodlot survey (primarily resulting from changes in hydrologic conditions and small shifts in channel morphology of the Housatonic River).

The Woodlot 2002 ecological characterization followed natural communities as described in Swain and Kearsley's 2000 *Classification of Natural Communities of Massachusetts* (2000) and referred to wetland habitats as "palustrine communities" and to upland habitats as "terrestrial communities." Tables 6-1 and 6-2 describe, respectively, the wetland and upland natural community types present in Reach 5A, as characterized by Woodlot (2002a). Palustrine communities described in Table 6-1 included cover types ranging from deep emergent marsh habitats to open wet meadow, shrub swamp, and forested habitats. Moderately alkaline ponds in the floodplain were classified as a



lacustrine community with the Housatonic River and tributaries classified as low, medium, and high-gradient streams, as described by Weatherbee and Crow (1992). Upland habitats included several forest types as well as "cultural grasslands," which included hay fields, former agricultural areas, and residential lawns (Table 6-2).

For purposes of the Reach 5A BRA, the updated natural community mapping was generally consistent with the Woodlot 2002 ecological characterization, except that several palustrine habitats (mud flats, black ash-red maple-tamarack calcareous seepage swamp, calcareous seepage marsh, and woodland vernal pools) are not included as wetland classes in the updated floodplain mapping, as they either do not occur within Reach 5A or are encompassed within other habitat assessments. The 2022 field surveys and floodplain mapping for the BRA also included a review of the recently updated *Classification of Natural Communities of Massachusetts* (Swain 2020).

As discussed in the Revised Reach 5A BRA Work Plan, although the BRA divided the floodplain into wetland and upland habitats, it did not include an effort to delineate wetlands from a regulatory jurisdictional standpoint or to classify and delineate specific individual resource area types within the floodplain under the Massachusetts Wetlands Protection Act regulations (310 CMR 10.00). This is because the entire floodplain is recognized to be a resource area subject to these regulations, and the remedial work is classified as a limited project pursuant to these regulations. Further, Woodlot classified more than 80% of the Reach 5A floodplain as palustrine wetland, and nearly 33% of the floodplain in Reach 5A was mapped as transitional floodplain forest, which is an extremely complex community relative to wetland regulatory criteria due to many factors, including varied microtopography, diverse floodplain soils, intermittent flooding, and differential surface water conveyance through the forest based on microrelief. See Section 6.2.1 of the Revised Reach 5A BRA Work Plan for further discussion of this issue.

Nevertheless, understanding conditions on the floodplain relative to wetland versus upland conditions is important for identifying suitable access roads and staging areas during restoration and maintaining floodwater conveyance and hydrologic conditions in wetlands and vernal pools across the floodplain. Therefore, the Reach 5A floodplain was mapped by flooding regimes used to describe non-tidal parts of palustrine, lacustrine, and riverine systems (FGDC 2013) to help differentiate areas that are regularly flooded and consistently exhibit wetland conditions (hydric soils and hydrophytic vegetation) from areas that may be a mix of wetland and upland. In addition, swales across the floodplain that connect wetlands to each other and to the river were identified and mapped.

To prepare the updated mapping including the wetlands and natural community/cover types as described above, a combination of desktop analyses and field surveys, followed by aerial photographic-interpretation and heads-up digitizing in ArcGIS, was performed. In addition, these



activities identified and mapped areas with 25% or greater invasive plant species cover and included an assessment of degraded habitats as potential areas for access roads and staging areas in the floodplain. Data layers compiled for the desktop analyses and subsequent mapping updates include:

- Existing community type classification mapping from the Woodlot 2002 ecological characterization;
- Mapping and photographs from Example Area characterizations conducted for the RCMS (2010);
- Vernal pool surveys, mapping, and classification and morphology surveys conducted in 2018-2019;
- Low-altitude aerial photography flown across Reach 5A by GE in 2018, using an unoccupied aerial vehicle (UAV);
- Aerial photography (from 2021 and earlier years) and related imagery (e.g., bare earth Digital Elevation Model imagery, which are particularly useful for delineating wetter areas of the floodplain based on microrelief) available from MassGIS, and other publicly available GIS data sources, as needed; and
- Surface topography generated from the LiDAR and other surveys conducted of the river and floodplain in the PSA in December 2021 and April-May 2022.<sup>11</sup>

Prior to conducting field surveys, the above-listed mapping data were compiled and overlain to produce preliminary resource mapping and aerial images that include the natural community cover types, vernal pools, delineated hydrologic zones, and other features. The updated LiDAR mapping and 2021 MassGIS aerials were the primary baseline field resource maps with these other data layers added. These resource maps then had a 100-meter grid overlain across the limits of the Reach 5A floodplain for use in the field surveys of the floodplain.

Field surveys were conducted by walking transects along the 100-meter grid lines across the floodplain habitats in Reach 5A; these surveys occurred from August 1 to September 28, 2022. Transect locations along with the resource base mapping were uploaded to ArcGIS Online and viewed in the field using the ArcGIS Collector application. When used in conjunction with an Arrow-

2018 aerial photographs were sufficient to supplement these detailed field surveys with aerial views.

<sup>&</sup>lt;sup>11</sup> As directed in EPA's March 31, 2022 conditional approval letter, GE also considered utilizing recent advances in UAV technology, including review of a document cited by EPA on UAV applications, to support field resource surveys. As noted in the Revised Reach 5A BRA Work Plan, GE concluded that additional use of UAVs (beyond the 2018 aerial photography produced from UAV flights) was not warranted at the present time. The on-ground field surveys and mapping described herein were sufficient to achieve the detailed mapping and classification of habitat types, and the



100 GPS unit (capable of one-foot accuracy), real-time tracking of location and collection of highly accurate GPS data points were conducted. In addition, the lateral extent of certain features that are visible on the aerial photographs in ArcGIS Collector (e.g., dense stands of scrub-shrub habitat and a large patch of Japanese knotweed) were interpreted, field-verified, and digitized while in the field from one vantage point, as opposed to surveying individual points by GPS and connecting them later in GIS. This approach provided efficient field efforts and post-processing of field data. Representative photographs of different community types in Reach 5A are provided in Appendix D-1.

#### 6.2.2 Results

Upon completion of the field surveys, surveyed GPS data points, polygons, and polylines were overlayed with existing site data in GIS for post-processing and mapping. The new ArcGIS data layers produced for Reach 5A are as follows:

- An updated version of the natural community mapping originally prepared as part of the Woodlot 2002 ecological characterization, including vernal pools, as shown on Figures 6-2a through 6-2e;
- A polygon data layer estimating the flooding regimes (FGDC 2013) within the floodplain based on inspection of LIDAR data, aerial photograph interpretation and field verification (including wetter areas such as vernal pools, other depressions, swales, and ditches), as shown on Figures 6-3a through 6-3e;<sup>12</sup>
- A polygon data layer showing areas with 25% or greater cover of invasive plant species, with polygons identified with species observed (discussed further in Section 9); and
- A polygon data layer showing areas of disturbed or degraded habitats that could be used for access roads or staging areas during remediation and restoration stages of the project (discussed further in Section 10.1).

Natural community mapping based on the 2022 field surveys and other recent investigations conducted in Reach 5A is presented on Figures 6-2a-e. There were some notable differences between the Woodlot natural community mapping and the latest (2023) mapping (i.e., changes in community type and spatial juxtaposition). Major changes are identified in Table 6-3 and described

<sup>&</sup>lt;sup>12</sup> To identify these wetter areas, the aerial photograph interpretation included identification and delineation of "wetness signatures," as defined in the 2012 USACE Regional Wetland Manual. These wetter zones are clearly noted on bare earth Digital Elevation Model imagery. They have also been noted preliminarily to correlate with areas of lower elevations on the 2021-2022 LiDAR mapping (see Figures 6-3a-e).



further below.<sup>13</sup> In the latest field survey, a total of 504 individual polygons representing 15 natural community and cover types were mapped over the approximately 410-acre Reach 5A survey area. They include:

- Two open water categories totaling 56.8 acres;
- Two open field / early successional categories totaling 30.6 acres;
- Five wetland categories totaling 154.2 acres;
- Five forested categories totaling 167.7 acres;
- One developed/disturbed category totaling 0.6 acres, and
- Riverine point bar and beach, which are identified on Figures 6-2a-e as point locations because these areas were too narrow to map as a polygon feature and be represented effectively on scaled drawings.

Woodlot originally mapped the upper portion of the Housatonic River from the Confluence down to Holmes Road as MGS, with the rest of Reach 5A mapped as LGS. Based on observations made during the 2022 field investigations, river conditions were determined to be more complex and variable than that. Therefore, the 2023 mapping identifies the Housatonic River within Reach 5A as a "Stream." See Section 3 for more discussion on stream characteristics and morphology in that reach. As described there, based upon current findings, approximately 29 acres of MGS occurs in Reach 5A, with 16 acres of LGS.

As with the mapping effort conducted by Woodlot in 2002, transitional floodplain forest remains the dominant cover type mapped within Reach 5A (Table 6-3). The 2023 mapping includes approximately 21 more acres of transitional floodplain forest than what was originally mapped. Much of this difference can be attributed to areas that have matured substantially over the last 20 years or have been impacted by beaver activity and undergone retrogressive succession (i.e., reverted to scrub-shrub or marsh habitats). However, some areas that differ are likely due to interpretation of conditions on the ground and/or during the remote mapping exercise.

The cover type that has changed the most within Reach 5A is a significant decrease in areas mapped as red maple swamp, with a commensurate increase in wet meadow, shallow emergent marsh and shrub swamp. Since 2002, the amount of area identified as red maple swamp has decreased by approximately 39 acres, while the other three cover types have increased by a total of approximately

<sup>&</sup>lt;sup>13</sup> As discussed below in this section, it is unlikely that the comparison of natural communities between the Woodlot 2002 ecological characterization and the updated community mapping in 2022 was significantly affected by the fact that the latter was conducted during abnormally dry conditions.



41 acres. Nearly all these changes occurred in Canoe Meadows and directly across the river from the Sackett Brook confluence, where heavy beaver activity has increased water levels by one to two feet (and possibly more in some areas of Canoe Meadows), causing tree species to die off and shrub and emergent marsh species to become more dominant. These changes were addressed in the morphology investigations conducted in 2018-2019 (AECOM and Anchor QEA 2020).

Finally, the only other cover type with a notable change was agricultural field. This cover type has decreased by approximately 14 acres since the 2002 mapping effort. These changes are evident southwest of Joseph Drive and northeast of the Pittsfield WWTF on Massachusetts Department of Fish and Game (Wildlife Management Area) lands where agricultural field areas have gone fallow and are growing in with dense shrub and tree cover. These areas are now mapped primarily as cultural grasslands, with approximately 1.5 acres southwest of Joseph Drive that is now mapped as wet meadow and transitional floodplain forest.

Although the 2022 surveys were conducted during a period of drought conditions, the natural plant communities mapped are broad cover types and one season of drought would not alter a particular area sufficiently to change it from one community type to another. Communities most likely to appear different during periods of low water would be shallow emergent marsh, and deep emergent marsh. As water levels drop, species intolerant of flooding germinate from the existing seedbank, giving the appearance of a wet meadow habitat. However, mapping is not based strictly on the plant community that was observed at that time. Incorporated into the designation of community type are previous knowledge of the floodplain habitats (based on observations made during other seasons and under different hydrologic conditions), the shape and size of depressions, water marks on trees and other vegetation, micro-topographic relief, and soil conditions. For these reasons, it is unlikely that the cover types identified during the surveys conducted during abnormally dry conditions in 2022 would be significantly different from those present under normal hydrologic conditions.

Flooding regimes in the Reach 5A floodplain (FGDC 2013) are presented on Figures 6-3a-e. Areas mapped as seasonally flooded or wetter (i.e., seasonally flooded/saturated, semi-permanently flooded) would generally meet the criteria for a state or federal jurisdictional wetland. Areas mapped as temporarily or intermittently flooded generally do not exhibit hydric soils and would not meet the definition of a jurisdictional wetland, but may have some wetland inclusions due to the complex nature of this natural community cover type.

Floodplain areas between the riverbank and the 1 mg/kg isopleth within Reach 5A include approximately 230 acres of habitats that are mapped as seasonally flooded or wetter (63.2% of the total floodplain area). These include approximately 2.8 acres of area functioning as floodplain channels and swales, which typically have poorly to very poorly drained soils. The remaining approximately 134 acres of floodplain (36.8%) are mapped as intermittently or temporarily flooded.



These areas tend to have moderately to excessively drained soils, with water tables that can be up to several feet below the ground surface for much of the growing season. However, these areas may also contain wetland inclusions or other features (e.g., floodplain channels and swales).

# 6.3 2022 Floodplain Wetland Habitat Investigations

In addition to the consolidation of existing information and the mapping and classification of floodplain habitats, an inventory was conducted of the floodplain wetland habitats, as described in this section.

## 6.3.1 Methods

The Reach 5A floodplain wetland habitat inventory characterization consolidated and incorporated information on a broad range of floodplain wetland parameters that collectively contribute to wetland functional capacity. These parameters consisted of wetland hydrology, vegetative conditions, soils, rare species habitat, invasive species, surrounding habitats, and juxtaposition with other wetland and surface water systems. Table 6-4 summarizes the floodplain wetland parameters that were included in this characterization.

As described above for the baseline mapping procedures, field surveys were conducted by walking transects along the 100-meter grid lines across the floodplain habitats in Reach 5A; these surveys occurred from August 1 to September 28, 2022. As noted, field surveys consisted of walking each transect and surveying points using GPS at changes in community/cover types, wetland and vernal pool edges, wetter/lower zones such as swales and depressions, and areas that are dominated by invasive plant species or are heavily disturbed/degraded. In addition, representative points along wetland edges between the transect lines were surveyed by GPS in areas where this boundary was difficult to photo-interpret, such as boundaries located under a coniferous tree canopy. At each 100-meter grid point (with possible adjustments where appropriate), a Floodplain Habitat Inventory Form (Form FP-1, which was provided in Appendix D to the Revised BRA Work Plan and a blank version of which is provided in Appendix D-2 hereto) was completed in the field. The form has eight sections (i.e., Section I through VIII) and provides site-specific information on wetland hydrology, soils, vegetation, specific wildlife habitat features (wolf trees, tree cavities, standing dead trees, large woody debris, mammal burrows, connectivity/juxtaposition with other habitat, signs of degradation, etc.), and the presence of or habitat for listed rare species for each wetland cover type unit.

The first two sections (Sections I and II) were completed to document the conditions listed in those sections, including natural community types, plant inventory, estimates of percent vegetation cover,

<sup>&</sup>lt;sup>14</sup> Due to the large number of survey points and the digital collection of information on the forms, the completed forms are not themselves included in this report, but the resulting information is presented in tabular form, as discussed in Section 6.3.2.



hydrology, and characterization of soils. In general, community cover type patches distinguished for mapping/data collection were greater than 0.5 acre in size (or roughly 25% of one grid in the 100-meter grid), except for previously delineated vernal pools, which were mapped independently of this size threshold.

The remaining sections of Form FP-1 (Sections III-VIII) were completed, along with a compiled summary of the information collected for Sections I and II, at the 100-meter grid points within each wetland cover type unit larger than 0.5 acre. The habitat features listed in Section III of Form FP-1 were recorded by the field observers for each wetland cover type unit during the traversing of the grid lines and were used in the characterization of the overall cover type unit. In addition, as part of this assessment, the presence of Core Area 1, Core Area 2, and Core Area 3 habitats (as designated by MNHESP) in the Reach 5A floodplain wetland areas was incorporated into the mapping and inventory, as was the presence of any other designated habitat for any federally listed or state-listed rare species; and any direct observation of a federal or state-listed rare species was documented and surveyed by GPS. Form FP-1 contains a section (Section V) to document these observations. Further, other incidental direct wildlife observations were recorded, as provided in Section VI of Form FP-1.

In addition to the above data collection and survey procedures, other available information on habitat and wildlife observations was incorporated into the Reach 5A wetland assessments. This included information from Mass Audubon on bird observations at Canoe Meadows), as well as data from Cornell's ebird web site for Canoe Meadows (<a href="https://ebird.org">https://ebird.org</a>), as described in Section 6.4.4. As discussed further in Section 10, the field survey activities included the identification of degraded habitats that could potentially be used for access roads and/or staging areas, and observations were also recorded on restoration opportunities that may be integrated with the remedial design and implementation. Sections VII and VIII of Form FP-1 provided for the documentation of such observations.

In addition to the characterization of wetlands by community type and physical and biological parameters, the Reach 5A floodplain wetlands were assessed by grouping the wetland systems into three general wetland functional units, shown on Figure 6-4, which consist of:

- Wetlands in Reach 5A from the Confluence to Holmes Road;
- Wetlands of Canoe Meadows (including the association with Sackett Brook/Sykes Brook and other surface waters); and
- Wetlands in the remainder of Reach 5A.

Functional units consider functional and spatial relationships of habitats, both surface and subsurface hydrological connections and wildlife habitat to provide context for the network of wetlands. This grouping also facilitated the functions and values functional assessment described in Section 6.3.4.



## 6.3.2 Results

The following text and Tables 6-5 through 6-10 provide a summary of field data collected during the 2022 Reach 5A floodplain surveys using Form FP-1. Due to the large number of observation plots (201), most of the information on Form FP-1 was collected digitally and is presented in tabular form rather than in a collection of completed forms. The following sections include discussion on plant community composition including invasive species, soil types mapped by the NRCS and observed in the field, physical features needed to support wildlife habitat (including access to food sources and suitable habitats for nesting, breeding, and escape cover), incidental wildlife observations, and rare species habitat.

## 6.3.2.1 Plant Community Composition

A total of 240 plant species were documented from 201 plots surveyed on the floodplains within Reach 5A, as shown in Table 6-5. These included 166 species of herbs, forbs, and grasses, 30 shrubs, 35 trees, five woody vines, and four mosses. The frequency of species occurrence ranged considerably among each plant stratum. Observations of herbaceous species ranged from the identification of 66 species of herbs, forbs, and grasses in one plot to the identification of only one herbaceous species in 58 plots. The most frequently encountered herbaceous species were purple loosestrife, sensitive fern (Onoclea sensibilis), jewelweed (Impatiens capensis), moneywort (Lysimachia nummularia), and ostrich fern. Six species of woody shrubs occurred in only one plot while one species occurred in 80 plots. The most frequently encountered shrub species were silky dogwood (Cornus amomum), common buckthorn and Morrow's honeysuckle. Seven species of trees occurred only in one plot, while one tree species occurred in 35 plots. The most frequently encountered tree species were boxelder maple, silver maple, red maple, and eastern cottonwood. Finally, the observations of woody vine species occurred in varying number of plots depending on the species, ranging from seven plots for one species (virgin's-bower [Clematis virginiana]) to 41 plots for another species (river grape). In addition to river grape, the invasive woody vine Asian bittersweet was observed with a relatively high frequency and documented in 30 plots.

Data were collected on invasive species presence at the 201 plot locations across the floodplain. Invasive plant species were observed at 179 of these plots (89%). Out of the 22 plots where no invasive plants were observed, nine of them were clustered in an area between Eric Drive east of the river and Palomino Drive west of the river on state lands (the George L. Darey Housatonic Valley WMA). As shown in Table 5-5, a total of 21 species listed as invasive or likely invasive were observed growing in the floodplain plots that contained such species (11 herbs, eight shrubs, one tree, and one woody vine). Invasive plants were included in the list of most frequently encountered for the herbaceous, shrub, and vine layers, as described above. These consisted of purple loosestrife and moneywort in the herbaceous layer, common buckthorn and Morrow's honeysuckle in the shrub layer, and Asian bittersweet in the woody vine layer. Only one invasive tree species, Norway maple



(*Acer platanoides*), was observed on the floodplain and occurred in only two plots. In addition, species considered non-native but not listed as invasive or likely invasive in Massachusetts were observed at 36 of these plots (18%). There were 30 such non-native species (28 herbs, one shrub, and one tree). A total of 188 native plants (126 herbs, 21 shrubs, 33 trees, and four woody vines) were observed on the floodplain. Mosses included two plants identified to species and two generalized groups (i.e., *Sphagnum spp.* and *Bryophytes*), all considered to be native.

Percent cover of mosses, herbs, shrubs, woody vines, and trees was also estimated at all 201 plot locations across the floodplain. Total vegetation cover within plots ranged from 5.9% to 72% percent, with herbs representing the most cover on average (72%). Average cover of trees and shrubs was similar with 36.6% and 38.5% cover, respectively. Woody vines and mosses represented a smaller proportion of the total cover on average, with 7.1% cover for each.

The percent cover results are presented in Table 6-6 for each cover type. As would be expected, tree cover on average was generally low or non-existent in deep emergent marsh, shallow emergent marsh, wet meadow and cultural grassland habitats. Tree cover in forested natural communities ranged from approximately 38% to 93% cover on average, with the highest tree cover observed in high-terrace floodplain forest and northern hardwoods-hemlock-white pine forest. On average, shrub cover was highest in shrub swamp, with forested community types ranging from approximately 14% to 53% cover on average. Average cover of woody vines ranged from approximately 3% to 21% in forested community types and were generally lower in open community types including deep emergent marsh, shallow emergent marsh, wet meadow and shrub swamp. Herbaceous species cover was generally high among all community types with the exception of northern hardwoods-hemlock-white pine forest and successional northern hardwoods. This is to be expected because communities with greater cover of coniferous trees (i.e., hemlock and white pine) and those that are in successional stages with dense shrub and tree layers typically have lower densities of herbs due to the effects of shading.

#### 6.3.2.2 NRCS Soils

The Natural Resources Conservation Service (NRCS) soil survey has mapped 16 different soil series in Reach 5A, plus three mapping units that represent disturbed conditions. These soil types are listed in Table 6-7 and depicted on Figure 6-5. Approximately 295 acres of Reach 5A (72%) contain soils that have formed in alluvial deposited sediments (i.e., on floodplains) and consist of very fine sandy loam (Winooski) to loamy (Limerick) and silty alluvium (Saco and Hadley). Limerick and Saco series soils are poorly drained and very poorly drained soils, respectively, and indicate true wetland conditions. In addition, both the Natchaug and Catden soils are very poorly drained organic mucks that form in depressions on floodplains and typically exhibit 10 (Natchaug) to 60 (Catden) inches of organic accumulation (USDA NRCS 2023).



Approximately 44 acres of Reach 5A (11% of the total floodplain area) consist of soils that were formed in glaciofluvial (water-deposited) materials (Copake, Groton, Hinckley, Hero. Hoosic and Merrimac series) or deposited in place as glacial till (Berkshire and Marlow series). One soil series (Oakville) is formed in sandy eolian (i.e., wind-blown) post-glacial deposits (approximately one acre within Reach 5A). The remaining approximately 21 acres of Reach 5A consist of mapping units that represent disturbed conditions (urban land, pits, gravel, and udorthents [man-altered soil units]). These areas are typically moderately well drained to excessively drained and have been disturbed by cutting, filling, or smoothing, or by buildings and pavement. They are typically sandy to gravelly textured and exhibit no evidence of soil profile development.

During the 2022 floodplain surveys, soils were inspected to depths up to 48 inches (range = 8-48 inches, mean = 20.8 inches). Hydric soil conditions were documented in 131 of the 222 locations and included soils with low chroma matrices, redoximorphic features, gleyed soils, and soils with mucky mineral and organic layers at the surface. Soils exhibiting organic and mucky mineral soils at the surface were documented at 83 locations and were 10.9 inches thick on average (range = 2-48 inches thick). At 38 of these locations, depths of mucky mineral soils and organic accumulation were greater than 14 inches thick. In addition, buried organic layers were documented at three locations, which is not uncommon in a floodplain setting. The texture of subsoils typically ranged from silt loam to fine sandy loam in soils meeting hydric criteria (NEIWPCC 2018).

The remaining 91 soil sample locations from the floodplain were moderately well drained to well drained and would not be considered hydric. Soil texture ranged from silt loam to very fine and fine sandy loams in upper portions of the soil solum, with some coarser textured material at depth (e.g., loamy fine sand). In general, field conditions were comparable to those mapped by the NRCS. However, the information collected to describe soils and other components of the NRCS soil mapping units were collected at scales ranging from 1:12,000 to 1:63,360 (USDA NRCS 2023). Floodplain surveys in 2022 inspected and described soil profiles at 222 locations on the floodplain, including samples collected in all 59 certified vernal pools. Mapping of natural communities and flooding regime was conducted at 1:400 using aerial photography and 2018-2019 LiDAR data. Therefore, discrepancies are to be expected when comparing the NRCS data to the observations of the detailed field investigation performed for the Reach 5A BRA. The largest discrepancies were observed at three locations, which are described below.

The first location, located south of Revilla Terrace and west of Pomeroy Avenue, is an approximately 9.4-acre area mapped as udorthents. A total of 13 soil profiles were inspected within that area, including from seven vernal pools. Aside from the east-west running sewer line that bisects this area and some recent restoration efforts along the northern edge by 5A-VP-13, no evidence of past disturbance was observed. Soils within the vernal pools are poorly drained to very poorly drained



mucky mineral over fine sandy loam and silt loam soils (e.g., Limerick and Saco series), and areas of the adjacent floodplain are moderately well drained and similar to the Winooski silt loam soil series.

The second area is located within Canoe Meadows. A large proportion of this area, approximately 52 acres, is mapped by the NRCS as a moderately well drained Winooski silt loam. However, based on field observations from 27 sample points and mapping of flooding regime using aerial photographs and LiDAR data, only about 10 acres of this area can be described as having moderately well drained soils. The remaining 42 acres exhibit poorly and very poorly drained soils, with other channels and ponded areas that are semi-permanently to permanently flooded. Portions of these 42 acres exhibited very deep organic soils (greater than 30 inches) and would fall into the Natchaug-Catden complex, while other areas are dominated by silt loam throughout the soil solum and match more closely the description for Saco or Limerick series.

Finally, an approximately three-acre area located just east of the Pittsfield WWTF is mapped as a Groton gravelly sandy loam. This area is actually an old gravel pit that has been excavated to within 12-18 inches of the water table. Soils were extremely gravelly, sandy loam with a thin A-horizon developing at the surface (approximately six inches thick). Based on the LiDAR topographic data, this area was excavated approximately 14-27 feet down from the adjacent landscape.

#### 6.3.2.3 Other Habitat Features

Form FP-1 includes a broad selection of other habitat features that were recorded for each plot location. These include wildlife food plants; a variety of cover, perching, basking, denning, and nesting habitat features; and specific features such as four-toed salamander (*Hemidactylium scutatum*) habitat, presence of vernal pools, and habitats specific to wading birds and waterfowl. These data are presented by observation plot in Table 6-8 and summarized in Table 6-9.

In general, all plot locations contain wetland, upland, or some combination of wetland and upland food plants that provide food sources for wildlife. Other habitat features that were encountered with high frequency included shrub and herbaceous vegetation suitable for bird nesting (86%) and dense herb cover suitable for small mammals, amphibians, and reptiles (85%). Habitat structures, such as standing dead or live trees with cavities and perches, large woody debris on the ground, rocks, crevices, logs or roots at the water's edge and areas with standing water at least part of the growing season, were all present in or near half or more of the plots (range = 47%-59%).

#### 6.3.2.4 Incidental Direct Wildlife Observations

During the course of the floodplain surveys, field observers recorded all direct observations of wildlife species (including evidence of species presence, such as tracks or scat). Table 6-10 provides a listing of these observations. Overall, a total of 80 species (or evidence of their use) were observed on the floodplain. These include 52 bird species, 12 species of herpetofauna, eight mammal species,



and eight invertebrates. A detailed listing of the incidental wildlife observations is provided in Appendix D-3.

## 6.3.2.5 Rare Species Habitat in Wetland Floodplains

A total of 21 state-listed plant and animal species have MNHESP-mapped Species Habitat that encompass the floodplain wetlands in Reach 5A and that could utilize those habitats based upon habitat requirements of each species and the floodplain habitat conditions documented to occur there. These species are listed Table 6-11 and are further discussed in Section 8.

# 6.3.3 Description of Reach 5A Floodplain Wetland Habitats

Floodplain wetlands in Reach 5A are composed of seven different plant community cover types and one open water community type. Several forested wetland types comprise the greatest area of these floodplain habitats, followed by shrub swamp, shallow marsh, wet meadow, and deep marsh. These habitats are described below. The relationship between these different habitats in the floodplain and the river is shown graphically in Figure 6-6, which is a schematic cross-section of habitats typically present in Reach 5A.

## Floodplain Wetland Forest Habitats

Based upon the 2022-2023 community type mapping described herein, approximately 163 acres of forested wetland floodplains occur within Reach 5A. Three different natural community types are represented within these forested wetlands – transitional floodplain forest (144 acres), red maple swamp (8.8acres), and high terrace floodplain forest (10.3 acres).

Transitional floodplain forest is the dominant matrix habitat connecting all other intervening floodplain natural communities (e.g., vernal pools, shrub swamps, emergent marsh, etc.) within Reach 5A, and accounts for approximately 35% of the total Reach 5A floodplain area. Topography within this habitat is complex, involving fluvial swales, depressions, and meander scars that are often connected directly to the river by deep, narrow swales, beaver slides and burrows through the riverbanks, and other microtopographic features. The complexity of this system is enhanced by debris dams and sediment deposition, which can modify these flow paths on a seasonal basis. As a result, these swales and other lower-lying areas are typically flooded more frequently (i.e., seasonally) than the rest of the floodplain forest (which is only temporarily flooded), creating intervening habitats with different soil conditions, hydrologic regimes, plant communities, and wildlife functions, as detailed in the following paragraphs.

Due to slightly higher ground surface elevations, the majority of the transitional floodplain forest is temporarily flooded during seasonal high water and periodic flood events when the river overtops its banks; but during much of the growing season, the groundwater lies well below the surface. Soil



textures range from very fine loamy sands to sandy loams with variations in coloring below 18 inches in depth reflecting the groundwater table.

The hydrologic regime and soil textures present in the transitional floodplain forest result in a vegetation community dominated by facultative plant species that occur as dense herbaceous stands, shrub thickets, and large diameter trees, including silver maple, box elder, and cottonwood. Dominant herbaceous species are ostrich fern, green-headed coneflower (Rudbeckia laciniata), and wood nettle (Laportea canadensis). However, due to the dynamic nature of floodplain habitats and transport of non-native plants and seeds down the river, a number of invasive species are present in this habitat, including dames rocket (Hesperis matronalis), bishop's goutweed, moneywort, forgetme-nots (Myosotis spp.), Japanese knotweed, garlic mustard (Allaria petiolata), spotted knapweed (Centaurea stoebe), Japanese barberry (Berberis thunbergii), Morrow's honeysuckle, common buckthorn, glossy buckthorn (Rhamnus frangula), and Asian bittersweet. In many cases, invasive species are most prevalent (i.e., occur at greater densities) along or near to the utility corridors, reflecting the influence of anthropogenic (human-caused) factors in the spread of such species. For example, significant portions of the floodplain between the river and the powerline easement just downstream from the Confluence exhibit large patches of Japanese knotweed that likely took hold during ground-disturbing activities associated with the powerline easement and the sewer line easement that also crosses through that area.

Woody debris is abundant throughout the transitional floodplain forest habitats in Reach 5A. This debris is variable in length, width, and ground surface coverage, and is in various stages of decomposition. Standing dead snags with numerous cavities of variable sizes occur throughout the transitional floodplain forest and large diameter trees (over 30" dbh) are common. Silver maples in this habitat tend to grow in large clumps often with seven to 10 and as many as 15 primary trunks ranging in size from 12" to 36" dbh.

When the Housatonic River overtops its banks, coarse bedload sediments are deposited directly adjacent to the river, forming banks that are typically two to three feet higher than elevations of the adjacent floodplain forest. Such levees are prevalent in Reach 5A along the bank edges adjacent to the floodplain forests. Tunnels and slides created by beavers and other semi-aquatic mammals are common along the bank of the river adjacent to the floodplain forest. These features also serve as conduits for the river water to flood the floodplain forest during lower stage flood events without having to rise the additional two to three feet to crest the bank. Through the digging of dens and channels, beavers affect not only the flow patterns and thus the hydrology of the area, but also riverbank dynamics, since the washing-out and collapsing of their dens alter the shape and character of the riverbank. Beaver foraging also affects vegetation growth patterns both by altering hydrology and by the cutting and removal of trees and branches for food. As a result of this repeated cutting or "coppicing" of the trees, the beavers create low dense shrub habitats preferred by other wildlife.



Selective foraging of certain tree species while allowing other species to grow changes the vegetative succession of the forested community.

The two other wetland forests which occur within the Reach 5A floodplain – high terrace floodplain forest and red maple swamp – may have similar characteristics to those described above for the transitional floodplain forest, but typically vary slightly in hydrology, soils, and vegetative composition. High terrace floodplain forest occurs slightly higher in the floodplain, typically above the two-year floodplain, and is therefore drier and better drained. In contrast, red maple swamp typically is more often seasonally flooded to saturated and associated with higher organic content soils derived from groundwater.

High terrace floodplain forests occur on raised banks adjacent to rivers and streams, on steep banks bordering high-gradient rivers, on high alluvial terraces, and on raised areas within floodplain forests. They are river-influenced and mesic (i.e., characterized by organic-rich moist soils), but they typically are not flooded annually, as indicated by the presence of a distinct surface soil organic layer. Soils are typically silt loams. The canopy is a mixture of floodplain taxa, such as red and silver maple and mesic deciduous hardwoods. The shrub layer varies from sparse to well-developed, and the herbaceous layer is a mixture of the characteristic floodplain forest ferns. High-terrace floodplain forests can contain low wet depressions that function as vernal pools.

Red maple swamp habitats often occur in groundwater depressions within the floodplain or areas which are more poorly drained than transitional floodplain forest areas. Along with the dominant red maple canopy coverage, other tree species in this habitat can include silver maple, American elm, box elder, and black willow (*Salix nigra*). Red maple swamp areas often have a dense shrub understory; in Reach 5A, the more common shrubs in this habitat are silky dogwood and the invasive Morrow's honeysuckle. Herbaceous vegetation comprises most commonly ferns such as ostrich fern, sensitive fern, and cinnamon fern (*Osmundastrom cinnamomeum*).

#### **Shrub Swamp Habitats**

After transitional floodplain forest, shrub swamp is the most prevalent cover type mapped in the Reach 5A floodplain and accounts for approximately 16% (64 acres) of the total area. Shrub swamps in Reach 5A occur in small discrete patches within fluvial swales, isolated depressions, and vernal pools surrounded by transitional floodplain forest, and as broad seasonally flooded to seasonally flooded/saturated wetland systems that cover extensive portions of the floodplain (see Figure 6-2). Shrub swamp habitat situated within the smaller isolated depressions and vernal pools ranges in size from 0.06 to 0.72 acre, with a few larger depressions containing up to four acres of shrub swamp habitat. Soils in the smaller depressions are typically hydric and consist of mineral or mucky-mineral textures at the surface underlain by silt loam, fine sandy loam and loamy sand soils; however, there are a few vernal pools with thicker organic layers at the surface. Larger shrub swamp systems occur



in Canoe Meadows east of the river and on state lands to the west (i.e., George L. Darey Housatonic Valley WMA located northeast of Palomino Drive). Canoe Meadows contains approximately 21 acre of shrub swamp, and wetland areas on the WMA to the west have up to nine acres of shrub swamp. These larger systems tend to have much deeper mucky mineral and organic soil horizons associated with them.

Variations in topography, soil texture, and hydroperiod in the shrub swamp habitat have resulted in a vegetation community dominated by dense shrub thickets and herbaceous cover that are, in many cases, associated with medium to large openings in the tree canopy. The most frequently encountered species in these systems was silky dogwood, with lesser amounts of pussy willow (*Salix discolor*), speckled alder (*Alnus incana*), white meadowsweet (*Spirea alba*) and elderberry (*Sambucus canadensis*). Invasive species such as glossy buckthorn, multiflora rose (*Rosa multiflora*), and Morrow's honeysuckle were often observed around the periphery of the shrub swamps, and occasionally in drier inclusions (e.g., on hummocks or other topographic features above the water table). Moneywort was very common in shallowly flooded basins and vernal pools with shorter hydroperiods and greater canopy cover, and purple loosestrife and water forget-me-not were observed in wetter open canopy habitats.

## **Shallow Emergent Marsh Habitats**

Shallow emergent marshes in Reach 5A are primarily associated with large, flooded areas on the floodplain and occur in a mosaic with shrub swamp and deep emergent marsh habitats, although this habitat does occur in some small depressions and vernal pools as well. Shallow emergent marsh habitat is the third most prevalent natural community mapped on the floodplain in Reach 5A and accounts for approximately 11% of the total area (46.3 acres).

The largest areas of shallow emergent marsh habitat are in Canoe Meadows, the WMA lands northeast of Palomino Drive, and just north of the Pittsfield WWTF (see Figures 6-2b, 6-2c, and 6-2d). Soils are variable but tend to exhibit thicker mucky mineral and organic soils than observed in shrub swamp or transitional floodplain forest. Shallow marshes are often found in shallow depressions in the floodplain or in areas affected by beaver impoundments. The most frequently encountered species in the shallow emergent marsh habitats were purple loosestrife, a variety of sedges and smartweeds, American bur-reed (Sparganium americanum), broad-leaved cattails (Typha latifolia), jewelweed, marsh bedstraw (Galium palustre), reed canary grass, woolgrass (Scirpus cyperinus), and rice cutgrass.

#### **Deep Emergent Marsh Habitats**

The deep emergent marsh habitat occupies approximately 12.6 acres (3.1%) of the Reach 5A floodplain. Deep emergent marshes are composed of herbaceous vegetation and form in saturated,



mucky mineral soils that are seasonally inundated and permanently saturated. The substrate is flooded by waters that are not subject to wave action and with water depths ranging from six inches to six feet. Water levels may fluctuate seasonally, but the substrate is rarely dry, and there is usually standing water throughout the year. Deep emergent marsh habitats are quite variable. They may be co-dominated by a mixture of species or have a single dominant species. In Reach 5A, dominant plant species within this natural community include sedges, rushes, purple loosestrife, smartweeds, floating pondweed (*Potamogetan natans*), arrowhead (*Sagittaria latifolia*), soft-stemmed bulrush (*Schoenoplectus tabernaemontani*), American bur-reed, and great bur-reed (*Sparganium eurycarpum*). Deep emergent marshes are closely associated with open backwater habitats in Reach 5A.

#### **Wet Meadow Habitats**

Wet meadow habitat occupies approximately 22 acres (5.4%) of the Reach 5A floodplain. Wet meadows are wetlands that often resemble grasslands and are typically drier than other marshes except during periods of seasonal high water. For most of the year, wet meadows are devoid of standing water, although a high-water table allows the soil to remain saturated. The wetland substrate consists of mineral soils with redoximorphic features, sometimes with a surface layer of well decomposed organic material. A variety of water-loving grasses, sedges, rushes, and wetland wildflowers proliferate in the fertile soil of wet meadow habitat. In Reach 5A, dominant plant species within this natural community include several invasive species (reed canary grass, moneywort, and purple loosestrife), plus jewelweed, spotted joe-pye weed (*Eutrochium maculatum*), stinging nettle (*Urticadioica*), marsh bedstraw, ostrich fern, and silky dogwood. Wet meadows are located throughout theCanoe Meadows area and in scattered locations across the floodplain.

#### Moderately Alkaline Lake/Pond (Open Water) Habitats

Dispersed among the Reach 5A floodplain are a number of smaller open-water habitats, also called moderately alkaline lake/pond (following Woodlot 2002 terminology). Collectively these areas comprise 8.5 acres (2.1%) of the Reach 5A floodplain. These are typically depressions in the floodplain, and often areas where beaver activity has resulted in impounding surface drainage in combination with deepening the ponded area forming behind dam by on-going digging of the organic soils. This habitat type is most common in the Canoe Meadows area where beaver impoundments of Sackett Brook and other tributaries have long been active.

# 6.3.4 Reach 5A Floodplain Wetland Functional Assessment

This section presents an assessment of the ecological functions and values of the floodplain wetlands in Reach 5A. This functional assessment utilized the information obtained in the wetland inventory described above. The assessment of the existing functions was based primarily on the consolidation



and collection of data on measurable and observable structural parameters that are known to give rise to the functions of the wetland habitats.

The floodplain wetland functional assessment draws upon the criteria and functions described in the USACE New England District's *The Highway Methodology Workbook Supplement, Wetland Functions and Values, A Descriptive Approach* (USACE Wetland Workbook Supplement; USACE New England District 1995). This approach is a multi-disciplinary assessment of wetland functions, including the following: groundwater recharge/discharge; floodflow alteration; fish and shellfish habitat; sediment, toxicant, and pathogen retention; nutrient removal, retention, and transformation; production export; sediment and shoreline stabilization; wildlife habitat; recreation; education and scientific value; uniqueness and heritage; visual quality and aesthetics; and threatened or endangered species habitat. The assessment is a qualitative description of the physical characteristics of the wetlands, including a determination of the principal functions exhibited. This method is not based on quantitative metrics, but rather provides criteria for assessing whether a wetland's characteristics could contribute to providing the functions listed above.

Table 6-12, which has been developed and adapted from the USACE Wetland Workbook Supplement cited above, lists the functions assessed in this process. In addition to a description of each function, that table lists the characteristics or criteria from Table 6-4 used in assessing the function. This functional assessment was conducted for each of the three functional wetland units described above (shown on Figure 6-4). For each such functional unit, the functional assessment process was documented on a Wetland Function Form (Form FP-2). This form lists each function and records the criteria considered in documenting the wetland characteristics that contributed to the functional assessment of the particular wetland functional unit.

The results of the floodplain wetland functional assessment are summarized in tabular form in Appendix E, which also includes the completed Form FP-2 for each of the three wetland evaluation units. The results are discussed below. Although these results are discussed in this floodplain wetland section, the combined assemblage of the Reach 5A riverine, riverbank, floodplain, and vernal pool habitats has been incorporated into the functional assessment.

#### **Groundwater Recharge/Discharge**

Based upon landscape setting, soil conditions, and surficial geologic conditions, the floodplain wetlands in Reach 5A provide conditions suitable for interactions between ground and surface waters. Much of the transitional floodplain forest, which comprises a majority of the area, contains floodplain soils that are sufficiently sandy to afford vertical and horizontal movement of surface and ground waters. Overbank flooding that is stored in the floodplain is at least partially infiltrated to the shallow groundwater table and moves laterally to discharge in the river. At other times, groundwater flow from the adjacent highlands may intersect the land surface within the floodplain of Reach 5A



(especially along the margins of vernal pools and other lower depressions) and discharge to the surface, contributing to base flow. The Housatonic River is a reflection of the regional groundwater table, and groundwater discharge to it provides base flow. Recent seepage meter results from the Reach 5A PDI indicate that both groundwater discharge to and recharge from the river occurs within the Reach 5A floodplain.

#### Floodflow Alteration

Given the location and characteristics of Reach 5A within the 10-year floodplain of the Housatonic River, this area provides floodflow alteration functions. These include not only the general provision of flood storage capacity, but also the function of providing temporary attenuation of the floodwaters, followed by a delayed and gradual release of the floodwaters draining back into the river. The characteristics within the floodplain wetlands that contribute to the latter floodflow alteration function include the surface topography and varied microtopographic surface features, the sinuous surface flow paths, the presence of dense herbaceous cover and shrubs in some pockets, and the dense mature woody vegetation that produces coarse woody debris. For example, vegetation impedes surface water flow and reduces the energy of storm runoff, causing water to deposit sediment and debris. Heavy vegetation, including dense areas of herbaceous and shrub species and mixed age classes of trees, slows flow and provides areas of slack water, allowing more water to seep down through soil and be stored as groundwater. Microtopographic complexity increases the tortuosity of flow pathways, reduces average velocity, and increases the gradient of moisture conditions. Coarse woody debris, derived from large trees, blocks flows and modifies flow patterns. These characteristics create naturally produced roughness, which increases flow resistance on the floodplain. This flow resistance, in turn, enhances retention of floodwaters, reduces erosion, increases infiltration, increases retention of inorganic sediments and organic particulates, and diversifies both moisture gradients and microhabitats for biota.

## Water Quality Maintenance, Nutrient Processing, and Production Export

The separate but related functions of water quality maintenance, nutrient processing, and production export are generally related to the cumulative effects of hydrology, sediment transport and deposition, and plant productivity. Sediment is transported into and through the Reach 5A from upstream sources, and bank erosion within this reach contributes further to this sediment load. When overbank or backwater flooding occurs from the main stem of the Housatonic River into the adjacent floodplains, inorganic sediment carried by the river is deposited within the floodplain, and adsorbed constituents (such as nutrients) settle out with the sediment; some sediment also settles within the quiescent pools of the river itself. This function maintains surface water quality by removing sediments, nutrients, and other pollutants from the water column. In addition, nutrients are processed within the floodplain as primary plant productivity converts inorganic forms into



organic forms of nutrients. The floodplain then serves as a source of organic forms of nutrients back to the river, either during further flood flows or by direct deposition of leaves and related vegetative parts, and these contribute to sustaining the base food chain in the river and ultimately the entire biotic community. This is the production export function.

#### Wildlife Habitat

The Reach 5A floodplain wetland consists of varied wetland cover types interspersed throughout the floodplain; the specific cover type in a particular area is typically first and foremost related to the surface hydrology. The wildlife habitat value of the floodplain wetlands is ultimately related to the collective contribution of the habitat features in each cover type, discussed below.

The transitional floodplain forest habitat in Reach 5A contains numerous dead tree snags of varying diameter and height, which have resulted from periodic flooding, sediment deposition, and beaver activity. Standing dead timber provides foraging habitats for all the woodpecker species and provides summer roosting sites for bats such as the big brown bat (Eptesicus fuscus), northern longeared bat (Myotis septentrionalis), and little brown bat (Myotis lucifugus). Abundant live trees with greater than 12-inch dbh are also present. Many of these trees are greater than 30 inches dbh. Both the dead standing trees and large living trees contain cavities ranging in size from less than six inches to 18 inches or larger and are used during the breeding season for nesting and as escape cover by a wide variety of birds such as wood duck, woodpeckers, tree swallow (Tachycineta bicolor), owls, bluebird (Sialia sialis), black-capped chickadee (Poecile atricapillus), hooded merganser (Lophodytes cucullatus), and common merganser (Mergus merganser). These cavities also provide habitat for several mammals, including mink, fisher (Pekania pennanti), raccoon, porcupine (Erethizon dorsatum, black bear, Virginia opossum (Didelphis virginiana) and flying squirrels. Larger live trees in the forest can be as tall as 100 feet with a fairly open understory, which can provide suitable foraging and nesting habitat for raptors such as the great horned owl (Bubo virginianus) and red-shouldered hawk (Buteo lineatus).

The dense herbaceous cover and other characteristic features of the transitional floodplain forest also play a role in providing non-breeding habitat for amphibians around the vernal pools in this area (the in-pool habitat functions of these vernal pools themselves are discussed further below). Amphibian species, such as the wood frog and northern spring peeper (*Pseudacris crucifer*), rely on the shade, deep litter, and woody debris in forested areas immediately surrounding the pools. Such areas within 100 feet from a vernal pool's edge, sometimes referred to as the vernal pool protection zone or envelope, protect the vernal pool amphibians, especially juveniles, from dessication and predation, protect the water quality in the pools from runoff and sedimentation, and provide shade and litter for the pool ecosystem.



In many parts of the Reach 5A floodplain, a system of fluvial worked swales, depressions, and meander scars directs flood flows across the floodplain and reduce water velocities, allowing the accumulation of very fine silt loams and formation of organic muck soils that perch and retain surface waters for extended periods. As a result, these areas have developed a carpet of herbaceous vegetation, including ostrich fern and wood nettle, and shrub swamp thickets of silky dogwood and nannyberry (*Viburnum lentago*), which can be used for a variety of foraging and nesting birds. Shrub swamp habitat also provides suitable conditions for earthworms and insects which are preyed upon by birds, small mammals, and bat species including the big brown bat and little brown bat.

Shallow and deep emergent marsh habitats of the type present in the Reach 5A floodplain are typically used for early season forage by several reptile species and as breeding habitat for several amphibian species. Reptiles also often use these moist habitats to regulate body temperatures and rehydrate during the summer. Wet meadow associated with the utility right-of way provides open and edge habitat used by birds such as the scarlet tanager (*Piranga olivaceae*), common yellowthroat, yellow warbler, and ruby-throated hummingbird (*Archilochus colubris*).

Finally, the Reach 5A wetland areas provide habitat for rare species, as described in detail in Section 8 and Appendix G of this report. Reach 5A is documented to support habitat for 21 statelisted species, one of which is also a federally listed species.

#### **Other Functions and Values**

As described in Appendix E, other principal functions and values of the Reach 5A wetlands, as indicated by the evaluation process, include recreation, educational/scientific, uniqueness/heritage, and visual quality/aesthetics.

#### Comparison with Earlier Functional Assessment

An earlier wetland functional assessment was conducted that included Reach 5A as well as areas upstream and downstream of this reach (TechLaw 1998). That effort also employed the ACOE Highway Method as well as other methods in use at the time. Reach 5A was incorporated into "Section Two" of the evaluation, which encompassed the Housatonic River from Confluence to below New Lenox Road (approximating what is now Reach 5A and 5B). TechLaw assessed the principal wetland functions and values to include: floodflow alteration, wildlife habitat, sediment/toxicant retention, sediment/shoreline stabilization, fish and shellfish habitat, production export, uniqueness/heritage, educational/scientific value, recreation, and visual/aesthetics. The only difference between that earlier wetland assessment and the current one is that the current one also found groundwater recharge/discharge to be a principal function.



# 6.4 2022 Floodplain Upland Habitat Investigations

As noted in the Woodlot 2002 ecological characterization report

"[V]ery little terrestrial or upland habitat is found in the PSA. Red oak–sugar maple transition forests are located in a few widely scattered locations. Cultural grasslands, which are open, upland habitats periodically disturbed by mowing or grazing, do occur near New Lenox Road. A few upland inclusions of northern hardwoods–hemlock–white pine forest also occur north of Yokum Brook. Most of the upland habitats occur adjacent to the PSA as cultural grassland, northern hardwoods–hemlock–white pine forest, and rich mesic forest." (Woodlot 2002a, page II-15.)

The 2002 Woodlot community type delineations indicated that less than 20% of the Reach 5A floodplain consisted of upland habitats. As described in Section 6.2, the updated floodplain habitat mapping and classification process identified these upland floodplain habitats. Agricultural fields were considered a subset of cultural grasslands and developed/disturbed parts of the floodplain were also distinguished in the mapping and classification. In addition, as with the floodplain wetland habitats, an inventory was conducted of the floodplain upland habitats, as described below.

## 6.4.1 Methods

The methods employed to survey conditions in the floodplain uplands of Reach 5A followed the same procedures as those described above for the wetland areas and were implemented along with those wetland surveys. The 100-meter grid described in Section 6.2 extended across the floodplain habitats, including both upland and wetland community cover types. Field observers traversed the grid lines using GPS location tracking and characterize/document conditions.

Table 6-13 summarizes the parameters considered in characterizing the floodplain upland habitats and indicates the information sources from which such information has been drawn. The relevant information includes information on flood frequency and depth, soil composition, vegetation, wildlife habitat features, identified rare species habitat, invasive species, and juxtaposition with surrounding habitats. That information was obtained from existing data sources (as specified in Table 6-13), supplemented by field surveys, again using the Floodplain Habitat Inventory Form (Form FP-1 in Appendix D-2). As described in Section 6.2, Sections I and II of Form FP-1 were completed as part of the natural community mapping at roughly 100-meter points in the Reach 5A floodplain (with adjustments as appropriate). For each discrete upland cover type unit larger than 0.5 acre, the remaining sections of Form FP-1 (Sections III-VIII) were completed, along with a compiled summary of the information collected for Sections I and II at the 100-meter grid points within that same cover type unit. As with the floodplain wetland assessment, the habitat features listed in Section III of Form



FP-1 were noted and recorded by the field observers for each upland cover type unit during the traversing of the grid lines and were used in the characterization of the overall cover type unit.

In addition to the collection of this information, the same additional inventory information described in Section 6.3 for floodplain wetland habitats was collected in the floodplain upland habitats. This included the presence of Core Area habitats (as designated by MNHESP) or other designated habitats for federal or state-listed rare species, any observation of a listed rare species, information from Mass Audubon and from Cornell's ebird web site on bird observations at Canoe Meadows, incidental wildlife observations, identification of degraded habitats that could potentially be used for access roads and/or staging areas, and identification of items that could potentially be used in restoration.

#### 6.4.2 Results

The Reach 5A floodplain within the 1 mg/kg isopleth includes 44.2 acres of upland consisting of five natural community types, two of which of which are fields and three are forests. Cultural grassland is by far the most extensive cover type in these upland floodplains, comprising 26.1 acres (59%) of the area. Agricultural fields add another 4.4 acres (10%) of the upland floodplain. Three upland forest cover types make up 13.7 acres (31%) of the upland area, with northern hardwoods-hemlock-white pine forest the most prevalent (7.4 acres/16.7%), followed by successional northern hardwood forest (3.7 acres/8.4%) and red oak-sugar maple transition forest (2.6 acres/5.9%). Developed or disturbed cover within the floodplain upland comprises only 0.6 acre.

As might be expected, these upland habitats are generally situated along the outer margins of the floodplain area (see Figure 1-2 for a simplified view). Upstream of Pomeroy Avenue, there are only minor fringe upland habitats along the outer portion of the floodplain. Between Pomeroy Avenue and Holmes Road and downstream along Canoe Meadows, the upland floodplains are generally associated with either open fields (some mowed) or utility lines, with some upland forests in the outer perimeter areas both east and west of the River. In the central portion of Reach 5A, there are several larger areas of floodplain uplands with both open and forested cover mixed; these occur primarily in the Joseph Road area and then west of the River towards the Pittsfield WWTF. Finally, there are upland agricultural fields toward the downstream end of Reach 5A.

The following summarizes the floodplain upland habitat surveys from data collected in 2022-2023.

# 6.4.2.1 Plant Community Composition

Table 6-14 provides a list of plants recorded in the upland natural communities with the frequency of occurrence. The upland forests contain a diversity of tree species (28 species). The most common tree species observed were American hornbeam (*Carpinus caroliniana*), American linden, black cherry (*Prunus serotina*), white pine (*Pinus strobus*), and sugar maple. A total of 16 shrub species were



recorded in the upland habitats, with Morrow's honeysuckle and silky dogwood the most common. Woody vines were quite abundant in many of the upland communities, with Asian bittersweet, poison ivy (*Toxicodendron radicans*), and river grape the most common species. Only a few herbaceous species appeared in more than several of the 26 upland plots, with Canada goldenrod, sensitive fern, and ostrich fern the most common. Table 6-15 provides additional summary data of the vegetative cover in the different upland floodplain plant communities.

## 6.4.2.2 Other Habitat Features

A summary of the data on recorded biotic habitat features for the upland floodplain natural community cover types is provided in Tables 6-16 and 6-17. The most commonly occurring biotic habitat features in these areas consisted of upland plant food sources, shrub thickets for earthworm habitat, standing dead trees with cavities and perches, shrubs and/or herbs for bird nesting, and large woody debris.

#### 6.4.2.3 Incidental Direct Wildlife Observations

Since the floodplain upland habitat surveys were integrated with the floodplain wetland surveys, wildlife observations incidental to the floodplain surveys are incorporated into the species listing in Table 6-10 and the detailed documentation in Appendix D-3. However, tracking of specific wildlife observed within or while on the upland portions of the floodplain resulted in the identification of 13 species of birds, <sup>15</sup> one amphibian (wood frog), and one insect (monarch butterfly; *Danaus plexippus*).

#### 6.4.2.4 Rare Species

A total of 11 state-listed plant and animal species have MNHESP-mapped Species Habitat that encompass the floodplain upland habitats in Reach 5A and could utilize these habitats based upon habitat requirements and the habitat characteristics identified during these surveys. These species are listed in Table 6-18 and further discussed in Section 8.

# 6.4.3 Description of Reach 5A Floodplain Upland Habitats

Based upon the updated community type mapping conducted in 2022-2023, five different natural community cover types comprise the floodplain upland habitat areas in Reach 5A. These are listed below along with a brief summary of each cover type and the area each comprises within the Reach 5A floodplain.

<sup>&</sup>lt;sup>15</sup> These were the cedar waxwing, red-tailed hawk (*Buteo jamaicensis*), northern cardinal (*Cardinalis cardinalis*), yellow-shafted flicker, American crow (*Corvus brachyrhynchos*), gray catbird, bald eagle (*Haliaeetus leucocephalus*), Baltimore oriole (*Icterus galbula*), hairy woodpecker, belted kingfisher, black capped chickadee, American robin (*Turdus migratorius*), and mourning dove (*Zenaida macroura*).



#### **Successional Northern Hardwoods**

This upland forest type comprises 3.7 acres within the Reach 5A floodplain (1% of the floodplain). Successional northern hardwood forests are limited in Reach 5A to small areas mostly around borrow pits and other disturbed areas and near residential lots or abandoned fields. Typical species include quaking aspen (*Populus tremuloides*), gray birch (*Betula populifolia*), and white pine. These forests tend to be younger and less developed in plant community structural diversity and organic composition.

## **Red-Oak Sugar Maple Transition Forest**

This upland forest type comprises 2.6 acres within the Reach 5A floodplain (0.6% of the floodplain). The red oak-sugar maple transition forests are relatively level to sloping upland forests dominated by larger canopy trees of red oak (*Quercus rubra*), white ash (*Fraxinus americana*), sugar maple, American beech (*Fagus grandifolia*), eastern hemlock and black birch (*Betula lenta*). This forest type typically includes a sparse subcanopy of American hornbeam as well as a sparse shrub layer of maple-leaved viburnum (*Viburnum acerifolium*) and witch-hazel (*Hamamelis virginiana*). The herbaceous layer is generally dominated by New York fern (*Parathelypteris noveboracensis*), white wood aster (*Eurybia divaricate*), and wild sarsaparilla (*Aralia nudicaulis*).

#### Northern Hardwoods-Hemlock-White Pine Forest

This upland forest type comprises 7.4 acres within the Reach 5A floodplain (1.8% of the floodplain). The northern hardwoods-hemlock-white pine upland forests are situated on relatively level to uneven ground vegetated with a mixture of broad-leaved and needle-leaved trees. Typically, the canopy layer is dominated by red oak, eastern hemlock, white pine, and sugar maple, and a poorly developed subcanopy is dominated by eastern hemlock and American beech. Shrub layer plants generally include hobblebush (*Viburnum lantanoides*), striped maple (*Acer spicatum*), and mountain maple. The herbaceous layer, which is variable and dependent on canopy dominants, can include Christmas fern (*Polystichum acrostichoides*), shining firmoss (*Huperzia lucidula*), evergreen woodfern (*Dryopteris intermedia*), Canada mayflower (*Maianthemum canadense*), bracken fern (*Pteridium aquilinum*, wintergreen (*Ilex verticillata*), southern ground cedar (*Diphasiastrum digitatum*, and partridge berry (*Mitchella ripens*).

#### **Agricultural Fields**

There are 4.4 acres of active upland agricultural fields within the Reach 5A floodplain (1.1% of the floodplain). Agricultural upland fields are open fields typically situated on level ground within floodplains of actively farmed areas and include crop cultivation and/or grazing. Because of their proximity to rivers and streams, agricultural fields typically contain fertile soils.



#### **Cultural Grasslands**

Cultural grasslands comprise 26.1 acres of upland area within the Reach 5A floodplain (6.4% of the floodplain). Cultural grasslands are open, upland fields dominated by grass-like herbs that are periodically disturbed, generally by mowing practices. Situated on relatively level ground, this community type lacks a canopy and subcanopy; however, it may include sparse patches of stunted shrubs that are often confined to dense colonies along the grassland edges. Typical shrubs found within this community include pussy willow, beaked willow (*Salix bebbiana*), red-osier dogwood, and staghorn sumac (*Rhus hirta*). Herbaceous vegetation is usually dense and can include red fescue (*Festuca rubra*), common Timothy (*Phleum pratense*), Kentucky blue-grass (*Poa pratensis*), poverty grass (*Danthonia spicata*), little bluestem (*Schizachyrium scoparium*), tall goldenrod (*Solidago altissima*), common milkweed (*Asclepias syriaca*), wild carrot (*Daucas carota*), common evening primrose (*Oenothera biennis*), and spreading dogbane (*Apocynum androsaemifolium*).

## Other Developed/Disturbed Areas

Other developed/disturbed areas are present within the Reach 5A floodplain upland areas, but make up only a small portion of those areas (0.6 acre, 0.2% of the floodplain). These consist of areas that have been impacted by historical disturbances such as filling, former sand and gravel mining operations, and existing structures (specifically, two buildings and a small portion of a tennis court).

# 6.4.4 Reach 5A Floodplain Upland Habitat Functional Assessment

The information obtained for the inventory and characterization of floodplain upland habitats in Reach 5A has been incorporated into a qualitative assessment of the ecological functions that these habitats contribute to. In general, the floodplain uplands provide similar functions as those in the floodplain wetlands. Functions which have been assessed in this qualitative process are groundwater recharge, flood storage, wildlife habitat, rare species habitat, buffer capacity, and corridor connectivity, as listed in Table 6-19. The impact of invasive species in the floodplain upland habitats was also considered. The site-specific information collected for each floodplain upland in Reach 5A, as documented on Form FP-1, forms the basis of the functional assessment, again considering the physical and hydrologic characteristics, substrate conditions, specific habitat features, connectivity with surrounding habitats, and the presence of both rare and invasive species habitats.

#### **Groundwater Recharge**

Based upon landscape setting, soil conditions, and surficial geologic conditions, the floodplain uplands in Reach 5A provide conditions suitable for interactions between ground and surface waters. Much of the upland floodplain forest contains floodplain soils that are sufficiently sandy to afford vertical and horizontal movement of surface and ground waters. As in the wetlands, overbank



flooding that is stored in the floodplain is at least partially infiltrated to the shallow groundwater table and moves laterally to discharge in the river. Due to the greater differential vertical distance between the land surface and the water table in upland areas versus wetlands, the upland portions of the floodplain may actually have more significance for groundwater recharge than wetland areas. Groundwater flow from these uplands typically moves laterally to intersect the land surface within lower portions of the floodplain of Reach 5A (especially along the margins of vernal pools and other lower depressions) or along the river's edge and discharges to the surface, contributing to base flow.

#### Flood Storage and Floodflow Alteration

As with floodplain wetlands, the location and characteristics of Reach 5A uplands within the 10-year floodplain of the Housatonic River provide floodflow alteration functions. These include not only the general provision of flood storage capacity, but also the function of providing temporary attenuation of the floodwaters, followed by a delayed and gradual release of the floodwaters draining back into the river. Given their higher elevation and less frequent flooding than floodplain wetlands, the floodplain uplands would be expected to have an overall lesser floodplain function; however, they do provide storage and flood peak desynchronization functions during major flood events. As in the wetlands, the characteristics within the floodplain uplands that contribute to the latter floodflow alteration function include the surface topography and varied microtopographic surface features, the sinuous surface flow paths, the presence of dense herbaceous cover and shrubs in some pockets, and the dense mature woody vegetation that produces coarse woody debris.

#### Wildlife Habitat

The structural components of the floodplain upland community cover types in Reach 5A are generally similar to those of the floodplain wetland community cover types, and therefore many of the wildlife species and functions provided are similar across the floodplain, whether wetland or upland. There are obviously some species which may be drawn to a slightly drier condition that the upland areas provide. For example, the upland habitat may provide sandier soils for turtle nesting, and the area is less prone to flooding of the nests of ground-nesting species. There tends to be greater diversity in the tree stratum in the upland forest than in the wetland forest, so additional food sources and nesting opportunities may be available. However, the overall significance of the upland floodplain for wildlife habitat is not greatly different from that of the wetland areas in Reach 5A.

# 6.5 Exposure Area 10 (Canoe Meadows) Base Mapping

In accordance with Section 4.2.1.4 of the Final Revised SOW, the BRA assessment of Reach 5A included a survey of the trails, signage, boardwalk, and access areas in the expanded Exposure Area (EA) 10, owned by the Massachusetts Audubon Society. This consisted of an existing conditions



survey using GPS instrumentation, with documentation of the location and photographs of these features on an aerial photographic base. Specifically, during field surveys in August-October of 2022, GPS instrumentation was used to locate the features listed above within the Canoe Meadows property encompassing EA 10 on a base map. Figure 6-7 presents that base map.

In accordance with the Revised Reach 5A Work Plan, direct observations of bird species recorded at Canoe Meadows have been consolidated in a separate table (Table 6-20). This list has been generated from Canoe Meadows information provided on the MAS website, as well as the listing for Canoe Meadows observations provided at "ebird.org": Canoe Meadows Wildlife Sanctuary, Pittsfield, Berkshire County, MA, US - eBird Hotspot. This listing indicates that over 180 species of birds have been observed within Canoe Meadows, much of which is located in Reach 5A.



## 7.0 Reach 5A BRA of Vernal Pool Habitats

Extensive investigations on vernal pool habitats have been conducted in Reach 5A over the past 25 years to develop a comprehensive mapping and classification of these habitats as well as to provide a detailed inventory of their characteristics. Detailed vernal pool investigations were initially conducted as part of the Woodlot ecological characterization of the PSA (Woodlot 2002a). Vernal pool investigations in Reach 5A also occurred during preparation of the RCMS, as reported by AECOM (2010) and Arcadis et al. (2010). Subsequently, GE conducted additional investigations on the identification and evaluation of vernal pools in the Reach 5A floodplain from 2018 to 2020 and presented the results to EPA in various reports, most notably those in 2020 and 2021 (AECOM 2020; GE 2021). Those reports included the identification of the pools in Reach 5A that met the MNHESP biological and physical criteria for vernal pools, as well as providing information on the hydrology of the pools and the faunal species observed in those pools (specifically, invertebrates, amphibians, reptiles, and fish). Those investigations are further described in Section 7.1 below. In addition, more recent investigations of the vernal pools in Reach 5A were conducted in 2022 and 2023 in accordance with the Revised Reach 5A BRA Work Plan. Those investigations are described in Section 7.2.

## 7.1 2018-2020 Reach 5A Vernal Pool Investigations

As discussed above, GE completed an identification and evaluation of vernal pools in the Reach 5A floodplain in 2018 and 2019, with some follow-up surveys in 2020. This work included field surveys of a total of 99 potential vernal pools. The final results, presented to EPA in the 2020 and 2021 reports noted above, included information collected historically and during the 2018-2020 investigations, along with observations on physical parameters. Specifically, the data presented included the obligate, facultative, and other species observed (if any), as well as presence of fish, habitat class, waterbody permanence, presence of a permanently flowing outlet, and evidence regarding an established fish population. A photographic log of the 2018-2019 investigations is provided in Appendix F-1.

These activities resulted in the identification of 59 pools in Reach 5A that met the MNHESP biological and physical criteria for certification as vernal pools and were thus subject to this BRA.<sup>17</sup> Those

<sup>&</sup>lt;sup>16</sup> That information was also presented to the MNHESP, which certified the vernal pools that it concluded met its criteria, although the Revised Permit does not require such certification for pools to be considered as vernal pools, only that they meet the MNHESP criteria for vernal pools.

<sup>&</sup>lt;sup>17</sup> In addition to these vernal pools, EPA's June 16, 2020 conditional approval letter for GE's November 2019 vernal pool report noted that there is a certified vernal pool southeast of pool 5A-VP-24 and east of sample location F0435006, located outside of but near the floodplain boundary: and it directed GE to investigate that vernal pool. GE inspected that pool in the spring of 2022 and confirmed that it meets the applicable vernal pool criteria. That pool



vernal pools are shown on Figure 7-1. The biological and physical data collected historically (Woodlot 2002a) and during the 2018-2020 investigations and used to show that those 59 vernal pools met the criteria for vernal pool certification are presented in Table 7-1. The data shown in this table include the obligate, facultative, and other species observed (if any), including the presence of fish, as well as the permanence of water in the pool and the presence of a permanently flowing outlet.

The species used as evidence to show that the pools meet the applicable criteria were wood frog, spotted salamander, and fairy shrimp (*Eubranchipus vernalis*). Wood frogs were the most frequently encountered species in Reach 5A vernal pools and were observed in 48 of the pools. Spotted salamanders were observed in only 11 pools and were only found in one pool without other obligate vernal pool species (e.g., wood frogs or fairy shrimp). Fairy shrimp were observed in 29 pools, and in four pools, they were the only obligate species observed. No state-listed species (e.g., Jefferson salamander complex) were observed during these vernal pool surveys.

During the course of the 2018-2019 investigations, some additional information was also obtained, but not reported, on other aspects of the vernal pools in Reach 5A. While that information is relevant and was considered in the Reach 5A BRA (as described below), it was not a systematic or comprehensive collection of such data to meet the current BRA objectives (since it was not necessary to determine whether the pools met the MNHESP vernal pools criteria). Therefore, additional surveys and data collection described in the Revised Work Plan were conducted in the Reach 5A vernal pools in 2022 and 2023.

# 7.2 2022-2023 Reach 5A Vernal Pool Investigations

### 7.2.1 Methods

For the vernal pools in Reach 5A, the additional characterization activities in 2022 and 2023 consisted of the following, as provided in the Revised Reach 5A BRA Work Plan: (1) compiling the existing information collected during the 2018-2019 surveys on other relevant attributes of those vernal pools – namely, flora, topography, bottom sediment/soil composition, in-pool physical structure, surrounding land use, and relationship/proximity to other vernal pools; and (2) collecting additional information on those relevant attributes, as well as data on the general water and soil chemistry of the vernal pools, as described below. A Vernal Pool Characterization Form (Form VP-1, which was provided in Appendix F to the Revised Work Plan and a blank version of which is provided in

was then subject to updated PCB sampling in 2022. That sampling showed the presence of PCBs within that vernal pool to be less than 1 mg/kg. Therefore, no further evaluation of this vernal pool has been or will be conducted.



Appendix F-2 hereto) was completed for each certifiable vernal pool, with the data from this form presented in tabular form herein (Tables 7-2 and 7-3), along with other data as described below.

To estimate percent cover of tree canopy, woody shrubs, herbaceous plants (including sedges, rushes, and grasses), and woody vines within each vernal pool, a line-intercept sampling procedure was implemented in most pools. This involved stretching a 100-foot tape across the pool from shoreline to shoreline and tallying the total length of each cover type that projects through that plane over the line. Percent cover was then calculated as a function of total length of a particular cover type divided by the total length of the transect. Two to three transects were measured across each pool and the dominant plant species within each of the various plant strata recorded, including observations of any invasive plant. In general, pools less than 0.2 acre in size had two transects, and pools between 0.2 and one acre had three transects. For pools that were too big (i.e., larger than one acre) or too deep, contained soft organic sediments that could not support the weight of a person, or were too thick with woody shrubs to penetrate in a straight line from shoreline to shoreline with a tape measure, the percent cover of tree canopy and woody shrubs was estimated by in-field observations along with inspection of the 2018 high-resolution UAV aerial photography for Reach 5A.

A comprehensive list of plant species observed within each pool was collected and plant species were identified using accepted current taxonomic references (e.g., Native Plant Trust (Gobotany.nativeplanttrust.org); the USDA NRCS Plants Data Base (<u>USDA Plants Database</u>) for the Massachusetts region (USDA NRCS 2022).

In accordance with the Revised Reach 5A BRA Work Plan, water depths (or evidence of water depths depending upon the seasonal conditions) were measured or determined at two- to five-foot intervals (depending on how flat or steep the topography was) along the vegetation transect from shoreline to shoreline to map the relative topography within each pool. The start and stop location of each transect was surveyed by GPS and points with corresponding water depths plotted along that line in GIS. For pools that were too big (i.e., larger than one acre) or too deep, contained soft organic sediments that could not support the weight of a person, or were too thick with woody shrubs to penetrate in a straight line from shoreline to shoreline with a tape measure, data on water depth were collected up to approximately three feet. Significant topographic or physical features within the pool (e.g., large hummocks or windthrown trees) that were not intercepted by the transect were characterized and located by GPS.

Vernal pool sediment/soil composition was categorized in the field using a hand auger and/or tile spade shovel and generally inspected to a depth of 18-24 inches. One profile description per pool was documented between the outer edge and deepest part of the pool. The information collected for each soil profile included soil horizons, depth, texture, color, and the presence or absence of



redoximorphic features (mottles and other features). Colors of the soil matrix and mottles were identified using Munsell Soil Color Charts (USGS 2014). Hydric soil determinations were based on criteria established in *Field Indicators for Identifying Hydric Soils in New England* (NEIWPCC, 2018) and guidance in the 2012 USACE Regional Wetland Manual.

In-pool physical structure other than the plants measured during the line-intercept sampling described above was quantified within each pool. Observations of coarse woody debris, large boulders, or exposed root wads were located via GPS during the pool inspection with the approximate length, width, and/or diameter recorded in inches. Fine woody debris was estimated as a total percent cover of the entire pool area.

The hydrologic regime, or hydroperiod of each vernal pool had been assessed during the 2018-2020 field surveys as temporary or permanently flooded. However, using observations of pool hydrology made during the 2022 surveys along with detailed mapping of flooding regime as described in Section 6.2.2 and presented on Figures 6-3a-e, pool hydrology was updated and classified on a continuum from shortest to longest hydroperiod as seasonally flooded, seasonally flooded/saturated, or semi-permanently flooded.

The habitat and land use conditions in the immediate vicinity of each vernal pool were characterized in the field, and percent of total area consisting of forest, development, open space, and scrub/shrub habitats in the broader landscape was quantified in GIS. These four habitat cover types are from Calhoun and Klemens (2002) and were quantified within both the 100-foot buffer around the vernal pool (the vernal pool envelope) and the 100-750 foot zone (the critical terrestrial habitat) using the MassGIS 2016 Land Cover/Land Use data-layer. The landscape setting of the pool was also characterized, noting whether it is a discrete depression in the floodplain or part of a larger wetland, and also the juxtaposition with other vernal pools to assess the potential for vernal pool network factors.

In addition, data were collected on the general water and soil chemistry data of the vernal pools, other than PCB concentrations, which were previously determined separately.<sup>18</sup> The collection of the general water and soil chemistry data occurred in May of 2023 and was conducted in a stratified random selection of the 59 certifiable vernal pools in Reach 5A to obtain data from 25% (15) of these pools. To select those pools, the 59 certifiable vernal pools were spatially stratified from north to

in GE' Pre-Design Investigation Summary Report for Reach 5A Non-Residential Floodplain Exposure Areas (Anchor QEA and Arcadis 2023b), submitted on September 28, 2023 and approved by EPA on January 30, 2024.

<sup>&</sup>lt;sup>18</sup> Specifically, the PCB concentrations in the Reach 5A vernal pools were determined through 2022 sampling conducted under the Second Revised Pre-Design Investigation Work Plan for Reach 5A Non-Residential Floodplain Exposure Areas (Anchor QEA 2021). The results have been reported in GE's Revised Vernal Pool Pilot Study Work Plan (Anchor QEA and AECOM 2023b), submitted on November 13, 2023 and approved by EPA on December 5, 2023, and in GE' Pre-Design Investigation Summary Report for Reach 5A Non-Residential Floodplain Exposure Areas (Anchor QEA)



south into three groups of 19-20 pools, and five pools were randomly selected within each group using a random number generator.

A Yellow Springs Instrument (YSI) Pro Dss Sonde 4M and data logger was used to collect general water chemistry from the 15 randomly selected vernal pools in Reach 5A. Water chemistry data were collected at one location within each of the selected vernal pools once during the growing season. Parameters collected were temperature, dissolved oxygen (DO), specific conductivity (SC), and pH. The Pro Dss Sonde 4M YSI was calibrated for each parameter prior to use daily. Deploying the meter was conducted by lowering the sensors into the water column to a depth that allowed each sensor to be submerged but not disturb the pool bottom. The optical sensors remained in the water column until the parameter sensor readings stabilized, approximately 10 minutes, then the readings were documented before removal. The YSI sonde and sensors were rinsed with clean water between each deployment to ensure accurate measurements. YSIs were cleaned and stored in cases at the end of each day.

Composite soil samples were also collected within each of the 15 randomly selected vernal pools. Each pool was visually divided into three quadrants from which a single sample was collected and combined into the one composite sample. Using a clean hand-held Edelman Auger, samples were collected at depths up to eight inches below the soil surface. Soil from the three locations were placed into a clean stainless-steel bowl and stirred with a clean stainless-steel spoon until homogenized then placed in four-ounce amber jars provided by the laboratory. The stainless-steel bowl and spoon were rinsed with clean water between each pool and then rinsed again with pool sample-specific water. Sample jars were labeled and placed on ice.

The Revised Reach 5A BRA Work Plan provided that: (1) if the data from these selected pools show significant spatial variability in one or more of the measured parameters, water quality measurements will be made and/or soil samples will be collected in additional vernal pools, selected in consultation with EPA, for determination of those parameters; and (2) in any case, after a determination has been made as to which vernal pools in Reach 5A require remediation, any such pools requiring remediation that have not already been subject to the collection of soil samples for analysis of pH and organic content will be sampled for those parameters as part of supplemental BRA activities. GE has subsequently identified the vernal pools that require remediation under the criteria in the Revised Permit. There are 48 such vernal pools. During the BRA, soil and water quality data were collected from 11 of those 48 vernal pools. As discussed in Section 7.2.2.2, GE has evaluated whether these data show significant spatial variability; and it proposes to collect soil samples from the remaining 37 vernal pools requiring remediation, as well as water quality data from six additional vernal pools, as part of supplemental BRA activities.



## 7.2.2 Results

This section describes results of the 2022-2023 field surveys conducted within the 59 vernal pools in Reach 5A. These include the within-pool parameters and habitat characteristics of the adjacent landscape, as described in Section 7.2.1. These results are also presented by pool in Table 7-2, with summary statistics in Table 7-3.

## 7.2.2.1 Plant Community Composition

As shown in Table 7-2, cover types within the vernal pools occur along a gradient from wetter to drier conditions – i.e., from deep and shallow emergent marsh to shrub swamp and transitional floodplain forest – which typically correlate well with pool maximum depth and hydroperiod. Most pools exhibited multiple cover types within their estimated flooding limits. However, 12 pools located within the floodplain were characterized as transitional floodplain forest. These pools tended to be smaller, 0.15 acre on average, as opposed to pools with multiple cover types (mean = 0.4 acre), and tended to have relatively high canopy cover (average of 73.2%, with a range of 32.6% to 100%).

Percent cover of vegetation layers, as measured from line-intercept transects across each vernal pool (n = 49) and estimated for those with restricted access across the pool (n = 10), is also presented in Table 7-2 and summarized in Table 7-3. Vegetation cover in the vernal pools varied with herbaceous and tree cover being relatively high on average compared to other cover types (i.e., woody vines, shrubs, and mosses). As would be expected, tree canopy cover is negatively correlated with the total percent cover of shrubs and observed in the pools. Estimates of fine and coarse woody debris were generally low, ranging from 3.7% to 8.2% on average. In addition, windthrown trees and exposed root wads were infrequently encountered. Hummocks composed of tussock forming grasses and sedges or woody shrubs were also generally low, although two pools were estimated to have greater than 38% of these features (5A-VP-1B and 5A-VP-77).

Data were collected on species presence at all 59 vernal pools in Reach 5A. The species found are listed in Table 7-4. A total of 132 plant species were documented within the 59 certified vernal pools in Reach 5A.<sup>19</sup> These included 19 species of trees, 18 shrubs, four woody vines and 91 herbs. A total of 41 species (three trees, five shrubs, one woody vine, and 32 herbs) were encountered in only one pool. The most frequently encountered trees were silver maple, boxelder maple, red maple, and American elm. Shrubs included silky dogwood, Morrow's honeysuckle, and common buckthorn and woody vines included river grape. The most frequently encountered herbs were sensitive fern,

101

<sup>&</sup>lt;sup>19</sup> As noted in EPA's December 21, 2023 conditional approval letter, although 48 of the 59 vernal pools require remediation, the species occurrence in all 59 pools, including the 11 pools that do not require remediation, will be considered part of baseline conditions.



moneywort, and purple loosestrife. Moneywort, sensitive fern, silky dogwood, and silver maple were all encountered in more than 30 pools.

As shown in Table 7-4, a total of 14 species listed as invasive or likely invasive were observed growing in vernal pools (six herbs, seven shrubs, and one woody vine). Invasive plants were included in the list of most frequently encountered for the herb, shrub, and vine layers as described above. This included purple loosestrife and moneywort in the herb layer, common buckthorn and Morrow's honeysuckle in the shrub layer, and Asian bittersweet in the woody vine layer. No invasive tree species were observed in the vernal pools. In addition, four species (all herbaceous) were identified as non-native but are not listed as invasive in Massachusetts. A total of 113 native plants (80 herbs, 11 shrubs, 19 trees and three woody vines) were observed in the pools.

#### 7.2.2.2 Pool Physical and Chemical Characteristics

As shown in Table 7-2, of the 59 total vernal pools, 45 pools were characterized as discrete depressions in the floodplain and 14 pools were part of a larger wetland system. Further, 32 pools were truly isolated with no inlet or outlet observed and 27 pools had inlets and/or outlets that were estimated to be either seasonally or temporarily flowing. No pools were documented to have a permanently flowing outlet. Estimated hydroperiod of most vernal pools ranged from seasonally flooded (n = 29) to seasonally flooded/saturated (n = 26). These are pools that likely dry out in late June to early July (seasonally flooded), or dry in July into early August but remain saturated at the surface or with small shallow pooled areas (seasonally flooded/saturated). Three pools were characterized as semi-permanently flooded. These pools retain some surface water in most years. One pool (5A-VP-1) is a large, flooded depression that has a deep and semi-permanently flooded section at the southern end, while the northern portions are more shallow and seasonally flooded.

The 2022 field surveys were conducted in August during a period of moderate to severe drought in western Massachusetts and hence most pools contained little or no water. Therefore, a second round of visits to each pool was conducted during the spring of 2023 to map the relative shape of each basin by measuring water depths at intervals along transects within each pool. Except for one flooding event that occurred near the end of April 2023, water levels were generally quite low for most of the spring 2023 survey period. This is apparent when looking at the transect data that were collected. Among all pools surveyed, maximum depths ranged from four to 37 inches (mean = 17.2 inches), not including three pools that were dry during the survey period. Average depths within each pool ranged from approximately 1.8 to 19.9 inches. The flooding event began April 23, 2023, when approximately 1.58 inches of rain fell over a 24-hour period (as reported at the Pittsfield Municipal Airport Weather Station), resulting in an increase in river flows from approximately 61.3 to 798 cfs at the Coltsville, MA USGS staff gage. During this time, pools that were connected to the river were then back-flooded through channels and/or overtopping of the bank, with some pools becoming three to four feet deep or more.



On average, soils within each vernal pool were inspected to 19.9 inches on average (range of 12-32 inches) below the ground surface. Most of the pools (n = 45) exhibited a mineral or mucky mineral surface horizon underlain by silt loam, very fine to fine sandy loam, and at two locations (i.e., 5A-VP-20 and 5A-VP-22) by a loamy sand. Eleven pools exhibited organic horizons overlying mineral soils ranging from silt loam to loamy sand in texture, and three pools exhibited deep organic soils with no underlying mineral soil encountered. In addition, in three pools (5A-VP-21, 5A-VP-22 and 5A-VP-80), organic horizons buried beneath mineral soil deposits were observed. The depth of organic surface horizons (including both organic and mucky mineral soils) ranged from approximately two to 32 inches and were 13.1 inches thick on average.

The results of the soil and water quality sampling in the 15 randomly selected Reach 5A vernal pools are provided in Table 7-5.<sup>20</sup> As required by EPA's December 21, 2023 conditional approval letter, GE has reevaluated these data in terms of spatial variability, as discussed in the following paragraphs.

Abiotic parameters in the surface water and soil of wetlands and vernal pools typically exhibit interand intra-specific variability. That is, within a single pool, measured parameters such as pH, SC, and DO can exhibit variability over time, and these parameters may also vary significantly among pools. For example, studies have documented significant variations in pH seasonally within pools and among vernal pools in Maine (Kifner 2017) and among vernal pools in Massachusetts (Coburn 2004). Similarly, in both of these studies, seasonal fluctuations in DO were documented over time and were significantly different among pools. Rowe and Dunson (1993), looking at relationships between abiotic parameters and breeding effort by amphibians, found that vernal pools are rather heterogeneous in their abiotic characteristics with significant variability within and among pools sampled for a wide variety of chemical parameters. Ayayee et al. (2020) also observed seasonal and spatial variability in soil percent organic carbon (%OC) and soil pH within and among vernal pools, respectively.

The variability in measured water chemistry and soil %OC derives from both within-pool and landscape-level effects. In-pool factors affecting these parameters may include pool size, depth, substrate and soil type, plant community composition, canopy closure, and source of hydrologic input (i.e., precipitation, surface runoff, groundwater exchange) (Rowe and Dunson 1993, Korfel et al. 2009, Herve et al. 2020). Landscape-level effects may include proximity to roads and development (Forman and Alexander 1998, Forman and Deblinger 2000, Karraker et al, 2008) and the landscape position of the pool (e.g., whether the pool is isolated or part of a larger wetland complex with surface water inlets or outlets).

-

<sup>&</sup>lt;sup>20</sup> A surface water sample from one of the selected vernal pools (5A-VP-27) was not obtainable due to lack of surface water.



Among the 15 vernal pools sampled in 2023 in Reach 5A, results of the soil and water chemistry were variable. However, even with this relatively small sample size, the variability was correlated with both within-pond and landscape level characteristics. For example, using a Spearman rank correlation test ( $s_r$ ), the amount of development within the critical terrestrial habitats (0-100 feet from the pool edge) was correlated with DO ( $s_r$ =0.57, T=2.39, p = 0.034) and SC ( $s_r$ =0.64, T=2.88, p = 0.014), and soil %OC was correlated with cover of herbaceous vegetation within the pool ( $s_r$ =0.63, T=2.79, p = 0.016).

Although the sample results exhibited variability, most of those results were within the 25th to 75th percentile range, with a few data-points that were mathematical outliers (e.g., %OC and pH in soils), as shown on Figures 7-2a through 7-2e. In addition, the standard error of the mean suggests that variability may not be as high as first apparent when considering the numerical spread between minimum, maximum and outlier values only. For example, although the %OC in soil ranged from 1.5 to 11%, the standard error of the mean (4% OC) was only 0.74%. When looking at characteristics of the individual pools, the observed variability can also be explained qualitatively. For example, VP-3, with primarily a sandy substrate and no surface organic layers documented, had only 1.5% OC, while the pool with 11% OC was VP-72, which has deep (approximately 24 inches) organic/muck soils. Similarly, pools with the highest SC were closer to roads and had development within 100 feet of the pool edge. VP-18, which is approximately 22 feet from the edge of Pomeroy Ave, exhibited the highest SC out of any pool (1578  $\mu$ S/cm) (see Figure 7-2d).

Based on these considerations, the observed variability in the soil and water chemistry data in the 15 vernal pools sampled would be expected and is consistent with previous studies as well as the range of within-pond and landscape-level factors that may contribute to such variability. None of the results is beyond typical ranges of soil and water quality parameters anticipated in this floodplain setting, particularly with proximity to roads and development. Accordingly, GE has concluded that the data do not represent the type of "significant spatial variability" that would warrant additional sampling of these parameters. Indeed, additional sampling of Reach 5A vernal pools would still not be expected to provide a complete picture of abiotic variability within and among the pools in Reach 5A. Further, these abiotic data do not appear to provide significant information contributing to the vernal pool breeding habitat functions.

However, since soil sampling has not been conducted in 37 of the 48 vernal pools requiring remediation, soil samples will be collected from those 37 pools for analysis of pH and organic carbon (or organic matter) content as part of supplemental BRA activities. In addition, to comply with EPA's December 21, 2023 conditional approval letter, GE will collect water quality data from six additional vernal pools during this soil sampling. Those pools are 5A-VP-7, VP-10, VP-32, VP-57, VP-59A, and VP-60, which have been selected using the same spatial stratification approach described above in Section 7.2.1, as well as stratified by the amount of development within 750 feet of the pool (in order to sample pools from both developed and undeveloped portions of the landscape). These additional



data will further indicate the range of soil and water chemistry conditions within Reach 5A vernal pools.

#### 7.2.2.3 Habitat Characteristics in the Adjacent Landscape

As shown in Tables 7-2 and 7-3, the vernal pool envelope (0-100 feet from the pool edge) around 58 of the 59 vernal pools is composed mainly (over 99% on average) of forest, scrub-shrub, and other open space habitats, with little or no development in that envelope. The one exception is 5A-VP-18, where the vernal pool envelope is 23.2% developed by residential homes and paved areas associated with Pomeroy Avenue, which is directly adjacent to this pool. Extending further out into the adjacent landscape, the critical terrestrial habitats (100-750 feet from the pool edge) are only slightly more developed. with approximately 91% of that total area composed of forest, scrub-shrub, and other open space habitats. Seven of the eight pools with the most developed critical terrestrial habitat are located north of Holmes Road and west of Pomeroy Avenue, with a range of 21.4% (5A-VP-6) to 39% (5A-VP-18) developed. Seventeen pools have less than 1% of their critical terrestrial habitat developed, and 36 pools have less than 10% of that habitat developed.

On average, each pool has 6.3 vernal pools within 1000 feet, with a range of one to 11 pools within that distance. The largest cluster of pools is located upstream of Pomeroy Avenue, with 20 pools located within approximately 57.4 acres of contiguous floodplain habitats. The remaining vernal pools are distributed throughout the Reach 5A floodplain habitats downstream of Holmes Road, with 32 pools along the western side of the Housatonic River, and seven pools located east of the river in Canoe Meadows (two pools), west and south of Joseph Drive (three pools), and at the southern end of Reach 5A (two pools).

A total of 12 state-listed plant and animal species have MNHESP-mapped Species Habitat that encompasses the vernal pools in Reach 5A and could utilize those vernal pool habitats based upon habitat requirements of these species and the habitat conditions documented in these vernal pools. These species are listed in Table 7-6.

## 7.3 Description of Reach 5A Vernal Pool Habitat

The vernal pools in Reach 5A consist of depressions in the wetland floodplain habitats which are capable of holding standing water through at least a portion of the amphibian breeding season. These depressions function as vernal pool breeding habitat for obligate vernal pool species, such as wood frog, spotted salamander, and fairy shrimp, as well as breeding, foraging, and rehydration/thermoregulation habitat for other amphibians and reptiles, including northern spring peeper, northern leopard frog, green frog, snapping turtle, painted turtle, garter snake, American toad, and bullfrog, all of which have been documented in the Reach 5A vernal pools. In addition, ribbon snakes (*Thamnophis sauritus*), wood turtles, and spotted turtles frequently forage and estivate in riparian pools.



#### 7.4 Reach 5A Vernal Pool Functional Assessment

For the vernal pools in Reach 5A, their functional assessment is based primarily on their status as vernal pools that meet the applicable MNHESP criteria. In short, since each of the 59 vernal pools in Reach 5A meets the biological and physical criteria for vernal pools, the primary function performed by each of these pools is to function as a vernal pool. More specifically, these vernal pools function to provide suitable breeding habitat for obligate vernal pool species, the most common being wood frogs, fairy shrimp, and spotted salamander, and/or they provide breeding habitat for at least two facultative vernal pool species. In addition, these pools collectively provide a network of vernal pools within the context of the overall floodplain system.<sup>21</sup>

To further evaluate the relative ecological value of each of the vernal pools in Reach 5A, a tier ranking system developed by Calhoun and Klemens (2002) may be utilized, using Form VP-2 (which was provided in Appendix G to the Revised Work Plan). Table 7-7 summarizes the results of the vernal pool tier ranking, as provided by Form V-2. This is a rating system designed strictly as a planning tool to determine the relative ecological value of pools in a community (Calhoun and Klemens 2002). According to Calhoun and Klemens, pools with a Tier I rating denote exemplary pools. Most of the pools in Reach 5A (32 of 59) met criteria of having two or more indicator species and/or greater than 25 egg masses, with very little development in the adjacent vernal pool envelope or critical terrestrial habitat, and therefore are classified as Tier I. The remaining 27 pools did not have two or more indicator species breeding in the pool, nor were more than 25 egg masses encountered; therefore, these pools fall into the Tier III category. No pools were rated as Tier II.

<sup>-</sup>

<sup>&</sup>lt;sup>21</sup> While vernal pools may function as singular aquatic systems, they more often occur in clusters due to their geologic setting. Juvenile amphibians disperse among the pools, maintaining a balance between local extinctions and colonization (Gibbs and Read 2008) – that is, when the hydrologic or other factors of a pool are not sufficient during a given year to allow breeding, or a given species is otherwise temporarily lost from a particular breeding pool, that pool may be recolonized by individuals from adjacent pools when adequate breeding conditions return. It is the proximity of vernal pools with slightly differing, but suitable, characteristics which can provide the necessary network to keep the local population of a species intact. In addition, part of the reproductive success for a vernal pool population is predicated upon having opportunities for occasional exchange of genetic material among individuals from different subpopulations (Gibbs and Read 2008).



# 8.0 Reach 5A Assessment of Rare Species

This section provides an assessment of the presence of federal and state-listed rare species and their associated habitats in Reach 5A. Federally listed rare species are those determined to be endangered or threatened under the Endangered Species Act (ESA: 16 U.S.C 1531 et seq.); "candidate species" under consideration for listing are also noted herein. State-listed species are those identified under the Massachusetts Endangered Species Act (MESA; M.G.L. c. 131A) and its implementing regulations (321 CMR 10.00) as endangered, threatened, or of special concern. Under MESA, a particular species may be identified and listed as "endangered" (in danger of extinction throughout all or a significant portion of its range or in danger of extirpation), "threatened" (likely to become Endangered within the foreseeable future), or of "special concern" (a species which has suffered a decline that could threaten the species if allowed to continue unchecked, or that occurs in such small numbers or with such a restricted distribution or specialized habitat requirements that it could become threatened within Massachusetts) (321 CMR 10.03(6)). Both the federally listed and state-listed species encompassed by these definitions are collectively referred to as rare species herein.

## 8.1 Methods

## 8.1.1 Federally Listed Species

The occurrence of any federally listed threatened or endangered species or their habitat in Reach 5A has been identified based on the USFWS IPaC. The IPaC online mapping tool was consulted in August 2023 to document the potential presence of federally listed rare species under the ESA within Reach 5A (including candidate species). In addition, the habitat requirements for such listed species were researched using appropriate source material, primarily that available from the USFWS (ECOS: Home (fws.gov) as well as MNHESP (List of Endangered, Threatened, and Special Concern species | Mass.gov). These habitat requirements were then assessed relative to the documented conditions in the Reach 5A habitats.

# 8.1.2 State-Listed Species

State-listed species and their habitats in Reach 5A have been determined based primarily on information provided by MNHESP. In October 2022, MNHESP provided GE with digital information presenting its delineation of state-listed species habitats in Reaches 5 through 8 of the ROR. These individual species maps are referred to as Species Habitat Maps. These maps are prepared by MNHESP using the "best scientific evidence available," examining individual occurrence records in the context of species listing status and applying a set of specified criteria. These criteria include the nature and/or significance of the occurrence as it relates to the conservation and protection of the



species, including, but not limited to, evidence of breeding, persistence, life stages present, number of individuals, extent of necessary supporting habitat, and proximity to other occurrences (321 CMR 10.12 (2)). Species observations in close proximity, grouped into occurrences (also known as "element occurrences"), indicate the geographic location presumably inhabited by a population of that species. MNHESP has advised GE that it will not allow presentation of the Species Habitat Maps by individual species, but that GE may show the overall area in Reach 5A mapped for all state-listed species collectively, may report the overall acreage in Reach 5A mapped for each state-listed species individually, and may generally describe that area.

MNHESP also provides on-line, publicly available mapping of Priority Habitats of state-listed species. Priority Habitat mapping is a regulatory layer which consists of combined Species Habitat Maps with "supporting habitat" added, where applicable, and may exclude certain Species Habitat mapping of low-ranked occurrences, Species Habitats based on historic occurrence sources, and Species Habitats for listed species that are not regulated.

## 8.2 Results

## 8.2.1 Federally Listed Species

Based upon the IPaC review, the northern long-eared bat (Myotis septentrionalis) is the only federally listed species indicated to potentially occur within the limits of Reach 5A. Another candidate species (under consideration for federal listing), the monarch butterfly (Danaus plexippus), is also indicated to potentially occur within Reach 5A. A brief summary of the habitat requirements for these two species is provided below, and Appendix G provides more extensive information on these two species and the potential for their habitat requirements to be met in all or portions of Reach 5A. This information will be used as guidance in the remedial design process to minimize impacts on habitats of federally listed species to the extent practicable.

**Northern Long-Eared Bat (Endangered):** This is a small, brown bat with unique large, long ears that distinguish it from other species in Massachusetts. The northern long-eared bat is found in forested habitats in the warm months of the year where it roosts in trees and forages. Although found in other tree roosts, it prefers roosts in large, tall cavities of large, live or dead trees in clustered hardwood stands. Northern long-eared bat populations, once common in the northern United States, have been devastated by the spread of the white-nose syndrome fungus. Infected hibernacula in caves in the Northeast have caused catastrophic population losses of 90-100%. The USFWS IPaC consultation indicates that potential habitat for northern long-eared bat occurs throughout all of Reach 5A.

**Monarch Butterfly (Candidate):** The monarch butterfly migrates each year from as far as Canada and across the United States to a few forested overwintering sites in the mountains of central Mexico



and coastal California (USFWS 2022). Over the last two decades, numbers have declined, and therefore this species is a candidate for listing by the USFWS. Primary threats to this species appear to be conversion of grasslands to agriculture, urban development, widespread use of herbicides, logging/thinning at overwintering sites in Mexico, unsuitable management of overwintering groves in California, drought, continued exposure to insecticides, and effects of climate change (USFWS 2022). The monarch butterfly is not currently a state-listed species in Massachusetts. Open meadows (both wetland and upland) in Reach 5A provide potentially suitable habitat for monarch butterflies. These habitats support several milkweed species which serve as the larval host plants for monarch butterflies.

# 8.2.2 State-Listed Species and Reach 5A Core Habitats

Based upon information provided by MNHESP in October of 2022, a total of 20 state-listed plant and animal species have MNHESP-mapped Species Habitat that encompass the various habitats in Reach 5A. An additional species (the northern long-eared bat), which is both state- and federally listed, also potentially occurs within Reach 5A (based upon IPaC results), but MNHESP did not include that species in its Species Habitat mapping. All 21 species are listed in Table 8-1, along with the acreage of mapped habitat for each species, the MESA status of each, and the taxonomic group that each species belongs in. Included in the list of state-listed species are 10 plants, seven invertebrates, two birds, one reptile, and one mammal. Since MNHESP did not provide a Species Habitat Map for the northern long-eared bat, the entire Reach 5A area is included as that species' habitat based upon the IPaC results.

As noted above, MNHESP has advised GE that it will not allow presentation of the Species Habitat Maps by individual species. The overall area mapped for all state-listed species collectively in Reach 5A encompasses all of Reach 5A.

Figure 8-1 shows the limit of the latest Priority Habitat mapping from MNHESP in the Reach 5A area (along with certified vernal pools for informational purposes). As noted above, this is generated from publicly available mapping of Priority Habitats of state-listed species. As shown on Figure 8-1, the Priority Habitat in Reach 5A extends upstream and downstream as well as laterally beyond the isopleth bounds that define the limits of Reach 5A. Figure 8-1 shows that virtually all of Reach 5A falls within Priority Habitat, with only one small area along East New Lenox Road in the southeastern part of Reach 5A extending outside of mapped Priority Habitat.



As previously discussed, MassDFW's July 2012 letter to EPA, which was attached to the Revised Permit, included maps depicting the locations of the different types of Core Habitat areas. Figure 8-2 shows the areas in Reach 5A that were designated as Core Area 1, Core Area 2, and Core Area 3.<sup>22</sup>

Each of the state-listed species with mapped habitat in Reach 5A, along with its habitat requirements, the extent (acreage) of its mapped Species Habitat in Reach 5A, and a general description of that area, are summarized briefly below, with more information provided in Appendix G. The general information on each species is largely taken from species-specific fact sheets prepared by MNHESP, as available on its website at <u>List of Endangered, Threatened, and Special Concern species | Mass.gov</u>, with additional information for some species based upon historical information and published literature. The extent of mapped Species Habitat for each species is taken from the Species Habitat maps provided by MNHESP.

American Bittern (*Botaurus lentiginosus*; Endangered): The American bittern is a wading bird that inhabits freshwater wetlands, spending most of its time secretly dwelling in marshland emergent vegetation. According to the 2022 MNHESP maps, Species Habitat for the American bittern in Reach 5A totals 164 acres covering three general areas, all of which contain suitable marsh habitat along the Housatonic River.

**Bristly Buttercup** (*Ranunculus pensylvanicus; Special Concern*): Bristly buttercup is an annual or short-lived perennial member of the buttercup family. Suitable habitats for colonization have open to filtered light and wet to periodically flooded conditions, including marshes, bogs, moist clearings, wet woods, stream banks, and ditches. Bristly buttercup may often inhabit disturbed riverbanks and managed wetland communities in utility corridors, as well as other disturbed areas. Massachusetts populations have been documented in marsh edges, vernal pools, seasonally flooded riverbanks, wet swales, drawn down glacial kettle holes, shrub swamps, and edges of or openings in floodplain forests. According to the 2022 MNHESP maps, the Species Habitat of the bristly buttercup occurs in one area of Reach 5A, approximately 29 acres in size in the central portion of Reach 5A to the west of the Housatonic River.

**Brook Snaketail (***Ophiogomphus asperus; Special Concern***)** is a dragonfly member of the Gomphidae family known as the clubtails. The nymphs of the brook snaketail prefer sandy substrates in clear running water. Adults may live out the rest of the summer far from the stream, often in dense woodland or shrubland. In Massachusetts, the flight period of the adult is mid-May through August. Mapped Species Habitat of the brook snaketail occurs in 240.65 acres within Reach 5A, extending from the Confluence downstream for approximately two miles.

<sup>&</sup>lt;sup>22</sup> The definitions of those Core Areas are provided in Section 6.1.5 above.



**Common Gallinule (***Gallinula galeata; Special Concern***):** Formerly known as the common moorhen, the gallinule is a duck-like swimming bird that inhabits large freshwater or brackish marshes and water bodies with cattails and other emergent vegetation. According to the 2022 MNHESP maps, the Species Habitat of the common gallinule occurs in two small areas in Reach 5A, both in marshes north of the Pittsfield WWTF on the western side of the Housatonic River. The mapped Species Habitat for this species in Reach 5A comprises 16.23 acres.

**Culver's-root** (*Veronicastrum virginicum; Threatened*): This is an herbaceous perennial wildflower of tall stature (2.6-6.5 ft) with showy arrays of dense pink or white flowers on several candelabra-like terminal spikes. Species Habitat of the culver's-root occurs within one small (0.12 acre) area of Reach 5A, located near the Confluence to the east of the Housatonic River.

**Frank's lovegrass (***Eragrostis frankii; Special Concern***):** Also known as sandbar lovegrass, Frank's lovegrass is an annual grass species identified by its repeatedly branching clusters on straight stems from about four inches up to a foot high. This species prefers sandy substrate within or at edges of the river channel. In Massachusetts, Frank's lovegrass occurs on sandbars and sandy riverbanks found only along the Housatonic and Connecticut Rivers. The Reach 5A mapped Species Habitat for Frank's lovegrass consists of river channel, including sandbars within the river, riverbank, and some floodplain habitat, and totals approximately 25.90 acres in size along a roughly 2.5-mile stretch of the Housatonic River in the downstream end of Reach 5A.

**Gray's Sedge** *(Carex grayi; Threatened)* is a perennial member of the sedge family (Cyperaceae) that is a clump-forming plant with an identifying striking "spiked-ball looking" flower. Gray's sedge is found in rich, mesic soils of forests, calcareous seepage Swamps. marshes, banks, and wet meadows, usually within riparian systems. In Massachusetts, Gray's sedge inhabits the moist alluvial soils of floodplain forests and adjacent meadow edges of large rivers. The Species Habitat for Gray's sedge within Reach 5A occurs in 27.5 acres of floodplain wetland along a roughly one-mile section of the river north of the Pittsfield WWTF.

**Great Laurel** (*Rhododendron maximum; Threatened*) is an evergreen shrub or small tree that grows up to 33 feet high belonging to the Ericaceae or Heath family. Great laurel grows best in filtered light in moist woods, swamps, and pond edges. The mapped Species Habitat for great laurel occurs within a single small area (1.72 acres) of Canoe Meadows east of the river in Reach 5A.

Hairy Wild Rye (*Elymus villosus; Endangered*) is a native perennial, tufted grass in the family Poaceae. distinguished by its bristly, white pubescent "bottle-brush" inflorescence. Hairy wild rye is found in floodplain forests, rich moist thickets, and rocky woodlands. In Massachusetts, hairy wild rye inhabits high terrace floodplain forests with moist alluvial soils, and moist to dry, rich, rocky open woods and thickets. Mapped Species Habitat of hairy wild rye comprises 18.9 acres in the central portion of Reach 5A northeast of the Pittsfield WWTF on the western side of the Housatonic River.



**Matted Spike-sedge** (*Eleocharis intermedia; Threatened*), formerly known as the intermediate spike-sedge, is an annual herb belonging to the sedge family. The matted spike-sedge is typically found in marshes, freshwater mudflats, or in other wet areas with muddy substrates. Mapped Species Habitat of the matted spike-sedge extends from the Confluence south through all of Reach 5A, covering 116.8 acres.

**Mustard White (butterfly)** (*Pieris oleraceae; Endangered*) is a medium-sized, white butterfly member of the Pieridae family. The mustard white is typically found in moist, rich, (mesic) openings in woodlands and riparian floodplains, edges of fens, marshes and streams, and open wet meadows, fields, and pastures. Two herbaceous woodland plants are essential larval hosts: the native two-leaved toothwort (*Cardamine diphylla*), and introduced cuckoo-flower from Eurasia (*Cardamine pratensis*) growing in forests, floodplains, and meadows. Other larval hosts may include several species of the mustard family, as well as the invasive garlic mustard. The mapped Species Habitat of the mustard white butterfly in Reach 5A extends south contiguously through the southern two-thirds of Reach 5A below the Holmes Road bridge, covering 327.4 acres.

Northern Long-eared Bat (Myotis septentrionalis; Endangered--both state and federal): Discussed above,

**Ocellated Darner** (*Boyeria grafiana; Special Concern*) is an insect member of the dragonflies (Order Odonata, Suborder Anisoptera) in the Aeshnidae family known as the darners. It is known to inhabit clear, shallow, swift-flowing streams and large, rocky, poorly vegetated lakes. In Massachusetts, it has been observed only in shaded, clear, cold, rocky streams and rivers. The mapped Species Habitat of the ocellated darner in Reach 5A occurs from the Confluence through to the southern extent of the Pittsfield WWTF, covering 276.78 acres.

**Ostrich Fern Borer** (*Papaipema sp.2 near pterisii; Special Concern*) is a noctuid moth from the Noctuidae (owelet moth) family associated with mature floodplain forests and wooded swamps with stands of ostrich rern (*Matteucia struthiopteris*). The ostrich fern oorer moth inhabits mature floodplain forests and wooded swamps where ostrich fern grows in moderate to dense stands, preferably in a shaded or partially shaded microhabitat. Mapped Species Habitat of the ostrich fern borer moth comprises 171.26 acres in the north-central portion of Reach 5A, just downstream of the Holmes Road Bridge.

**Rapids Clubtail** (*Phanogomphus quadricolor; Endangered*) is an insect member of the dragonflies (Order Odonata, Suborder Anisoptera) in the Gomphidae family, specifically clubtails, which are typically burrowers and predators. The rapids clubtail inhabits clear, cold streams and rivers with intermittent sections of rocks and rapids. Mapped Species Habitat of the rapids clubtail comprises 55 acres in the southern portion of Reach 5A.



**Riffle Snaketail (***Ophiogomphous carolus; Threatened***)**, is a large and stocky insect member of the dragonflies (Order Odonata, Suborder Anisoptera) in the Gomphidae family or clubtails. The riffle snaketail inhabits clear, cold, rocky streams that are fast flowing with few pools and fine gravel or sand sediment. During maturation, riffle snaketail adults wander from woodland to forest clearings and fields, feeding on small aerial insects such as flies and mosquitos. The mapped Species Habitat of the riffle snaketail comprises 192 acres in the upstream portion of Reach 5A, from the Confluence to a point just upstream of the Joseph Road area.

**Spine-crowned Clubtail** (*Hylogomphus abbrevi*ates; **Special Concern**) is a large insect member of the dragonflies (Order Odonata, Suborder Anisoptera) in the Gomphidae family, the clubtails. In Massachusetts, spine-crowned clubtails have been found on the Connecticut River and other medium to large rivers that have silty and sandy bottoms. During maturation, spine-crowned clubtail adults fly from woodland to forest clearings and fields, feeding on small aerial insects such as flies and mosquitos. They are rarely observed during this time and thought to spend much of this stage in tree tops. Mapped Species Habitat of the spine-crowned clubtail in Reach 5A occurs from the Confluence to the southern extent of the Pittsfield WWTF, comprising 256 acres.

**Tuckerman's sedge (***Carex tuckermanii; Endangered***)** is a perennial herbaceous wetland sedge (family Cyperaceae) that grows in loose clumps up to a meter tall in habitats including river and lake shores, swamps, and vernal pools. In Massachusetts, Tuckerman's sedge inhabits the rich soils of lowland river floodplain habitats such as oxbows adjacent to river channels, low depressions, forests, meadows, swales, and vernal pools in the western and central part of the state. Mapped Species Habitat of Tuckerman's sedge occurs in the central portion of Reach 5A northeast of the Pittsfield WWTF on the western side of the Housatonic River, covering less than one acre in area.

**Wapato** (*Sagittaria cuneata; Threatened*) is an aquatic herbaceous perennial of the water-plantain or arrowhead family (Alismataceae), found in nearly neutral to slightly basic, open-water habitats. In Massachusetts, wapato is found in very slow-moving or stagnant waters of riverine floodplain habitats in alkaline backwaters, oxbow ponds, small shallow depressions with muddy substrate, and a few occurrences on pond shores. Wapato displays high variability in its growth form as an emergent and emersed plant, a floating plant, or entirely submerged plant depending on its growth conditions. Mapped Species Habitat of wapato in Reach 5A extends from the Confluence south along the river corridor through Reach 5A, comprising 171 acres.



White Adder's-mouth (*Malaxis monophyllos var. brachypoda; Endangered*) is a single-leaved orchid member of the family Orchidaceae found in small, shaded, calcareous wetland habitats. White-adder's mouth prefers habitats with accumulations of incompletely decomposed organic material, or peat, dominated by coniferous trees and influenced by highly calcareous water. Mapped Species Habitat for white adder's-mouth occurs in the northern section of Reach 5A, comprising approximately 1.62 acres.



# 9.0 Reach 5A Invasive Species

Assessment of invasive species in Reach 5A was initiated by establishing a definition of "invasive species," including the plant and animal species that will be considered invasive. For plants, the definition of invasive species included those listed by the Massachusetts Invasive Plant Advisory Group (MIPAG) as "invasive" or "likely invasive" (MIPAG 2005; https://www.massnrc.org/mipag), those listed by the USACE New England District in its focused list of invasive species to be controlled at wetland mitigation sites, and those listed as invasive by the Invasive Plant Atlas of New England (IPANE 2007).<sup>23</sup>

For animals, to implement EPA's directive in Condition 9 of its March 31, 2022 conditional approval letter to evaluate "invasive aquatic animals," guidance on what aquatic species are considered invasive was obtained from both the Massachusetts Department of Conservation and Recreation (e.g., List of Current and Potential Aquatic Invasive Species | Mass.gov) and the U.S. Geological Survey (e.g., Nonindigenous Aquatic Species (usgs.gov)). In this determination, it is important to distinguish "exotic invasives" from other non-native species (which may or may not be invasive).<sup>24</sup> Based on this assessment, the zebra mussel (*Dreissena polymorpha*) and Asian clam (*Corbicula fluminca*) have been identified as exotic aquatic invasive animals which could potentially occur in the Reach 5A area. Non-native fish species documented in Reach 5A are addressed in this BRA, but are not treated as invasive species. This is consistent with both the state and federal guidance referenced above.

## 9.1 Methods

The initial effort in identifying invasive species involved consolidating available information on the general occurrence of each invasive species in Reach 5A. As with the habitat inventories described above, the identification and location of invasive species were then conducted using site base mapping and aerial photographs in combination with field verification. This work was conducted in conjunction with the associated surveys in the riverine, riverbank, backwater, and floodplain habitats as described previously.

For Reach 5A, as described in Section 6.2.1, an aerial photograph overlay provided an initial depiction of known areas of invasive species based on the available information and aerial photographic interpretation. This baseline information was also transferred on to the 2022 LiDAR topo-bathymetry mapping. The aerial photographic base mapping was then used during field surveys to document

<sup>&</sup>lt;sup>23</sup> It should be noted that the USACE New England District's list of invasive plant species to be controlled does not include any species that are not listed as invasive or likely invasive by MIPAG or IPANE.

<sup>&</sup>lt;sup>24</sup> Under the federal definition, "invasive" species "cause significant economic harm, ecological harm, or harm to human health. 'Native species' means, with respect to a particular ecosystem, a species that, other than as a result of an introduction, historically occurred or currently occurs in that ecosystem" (Executive Order 13112).



the location and extent of invasive species. For the purposes of this documentation, invasive plant species occurrence was ranked by relative abundance of foliage cover in a given plant stratum (e.g., canopy, understory, ground layer) on a scale of 0-5%, 5-25%, 25-50%, 50-75%, or >75%. For instances of invasive plant species exceeding 50% cover in discrete contiguous units, GPS instrumentation was used to document their location. An exception to this procedure applies to extensive areas of ground cover foliage such as moneywort or garlic mustard, which are impractical to map across the floodplain forest floor; in such cases, the presence of the species was documented in the data collection form for the subject habitat. Aquatic invasive species (both plant and animal) in the river and backwaters were documented during the field surveys for each of those habitats, including location references in the base mapping.

## 9.2 Results

Data on the occurrences of invasive species were recorded in all habitats (riverine, riverbanks, backwaters, floodplain wetlands, floodplain uplands, and vernal pools) during the field investigations dating back to 2018, but in particular during the more recent surveys in 2022-2023. The results were reported in the above sections of this report addressing each of those habitats. However, for completeness, the primary findings on invasive species are summarized again in this section, as discussed below. Additional information on the field assessment of invasive species in Reach 5A is provided in Appendix H-1, and general information regarding the primary invasive species identified in Reach 5A is provided in Appendix H-2.

Overall, among the Reach 5A habitats surveyed, only one invasive tree species was observed (Norway maple). Eight invasive shrub species, one woody vine, and fourteen herbaceous species were observed. In terms of "invasive aquatic animals," only one such potential species was observed, as described below. The following summarizes the primary findings on invasive species for each of the habitats.

#### Riverine Invasive Species

- Eurasian milfoil and curly-leaf pondweed were detected on small patches throughout Reach
   5A; and the invasive yellow iris was observed along the river edge.
- Asian clams are suspected to be present in Reach 5A based on observation of small clam shells, but identification could not be verified.
- No invasive fish or any other potential invasive animal species such as zebra mussels were detected.



#### **Riverbank Invasive Species**

- Sixteen different invasive species were recorded (no invasive tree species, four invasive shrub species, one invasive vine species, and 11 invasive herbaceous species).
- The invasive vine Asian bittersweet was the most common vine (59% frequency).
- The most prevalent invasive species on the riverbanks were Asian bittersweet (59% frequency), Japanese knotweed (48%), common buckthorn (29%), Morrow's honeysuckle (22%), water forget-me-not (18%), purple loosestrife (12%), and bishop's goutweed (10%).

#### **Backwater Invasive Species**

- A total of seven invasive plant species were observed in the six Reach 5A backwater habitats.
- No invasive shrubs, trees, or vines were observed in the backwaters, only invasive herbaceous species, including two aquatic plants.
- Invasive plant species in the backwaters included five herbaceous species: yellow iris, moneywort, purple loosestrife, water forget-me-knot, reed canary grass. Two aquatic species were also observed: Eurasian watermilfoil and water chestnut
- Three of the invasive species were observed in three backwaters, two of the invasive species
  were observed in two backwaters, and the remaining two invasive species were observed in
  one backwater.
- The backwater observed to have the most species of invasive plants was BW5A-2 with five invasive plant species, followed by BW-3 with four invasive plant species, and then BW-1, BW-4, BW-5 and BW-6, each with two invasive plant species.

### Floodplain Invasive Species (including Vernal Pools)

- Invasive plant species were observed at 179 of 201 floodplain plots (89%).
- A total of 21 species listed as invasive or likely invasive were observed growing in floodplain habitats (11 herbs, eight shrubs, one tree, and one woody vine).
- Only one invasive tree species (Norway maple) was recorded in the observation plots, and occurred in only 1% of the plots.
- The most common invasive shrub species were Morrow's honeysuckle (25.2%), common buckthorn (26.2%), and multiflora rose (7.4%).



- The most prevalent invasive herbaceous species encountered were purple loosestrife (28.7%) and moneywort (23.7%), followed by reed canary grass (7.9%), bishop's goutweed (6.9%), garlic mustard (4%), and Japanese knotweed (3.5%).
- A total of 14 species listed as invasive or likely invasive were observed growing in vernal pools (six herbs, seven shrubs, and one woody vine).
- Invasive plants in vernal pools were included in the list of most frequently encountered for
  the herb, shrub and vine layers. This included purple loosestrife and moneywort in the herb
  layer, common buckthorn and Morrow's honeysuckle in the shrub layer, and Asian
  bittersweet in the woody vine layer. No invasive tree species were observed in the vernal
  pools.

In addition to the overall data summary provided above on invasive species in Reach 5A, three species of invasive plants within Reach 5A have developed discrete areas of dominance in the floodplain that are large enough in area to map (i.e., >0.5 acre). These three species include Japanese knotweed, reed canary grass, and phragmites (or common reed). The limits of the discrete areas of dominance by these species were therefore mapped, as shown on Figures 10-1a through 10-1e (discussed in Section 10.1), and were incorporated into the assessment of degraded or disturbed areas to be considered in the layout of access roads and staging areas, as further described in Section 10.1. The other areas of invasive species do not present such discrete areas of dominance that afford an ability to map specific zones.



# 10.0 Preliminary Identification of Degraded Habitats and Restoration Opportunities in Reach 5A

The Revised Reach 5A BRA Work provided that, during the course of the BRA activities in floodplain areas, disturbed or degraded habitats would be identified that could be suitable for access roads or staging areas during remediation and restoration stages of the project with the objective of minimizing ecological impacts. It also provided that, during BRA activities, GE would evaluate restoration opportunities. GE conducted these activities during the BRA of Reach 5A. Those activities and their results are described in this section.

## 10.1 Identification of Disturbed or Degraded Habitats

To assist in identifying disturbed or degraded floodplain habitat areas that could be suitable for access roads or staging areas, Form FP-1 included a section (Section VII) for the recording of observations pertaining to habitat degradation. These included evidence of significant levels of dumping or of significant erosion or sedimentation, the relative abundance of invasive species, disturbance from roads or highway, evidence of fire, and evidence of other human disturbances. In addition, in accordance with EPA's June 29, 2022 conditional approval letter, GE developed a Site Degradation/Disturbance Evaluation Form, provided in Appendix H of the Revised Work Plan, to qualitatively assess the level of degradation in each wetland or upland cover type unit for which Form FP-1 is completed. The information used for this form was to be generated from the floodplain site inventories described previously. This form includes ratings for eight factors or evaluation criteria which relate to the level of disturbance or habitat degradation. Each factor has an assigned significance coefficient (from 1 to 3), which is multiplied by the rating assigned to each condition that the factor is recorded as having. The product of these values yields a score that provides a relative measure of the level of disturbance/degradation for the area assessed.

In applying the Site Degradation/Disturbance Form to the more than 400 acres of floodplain habitat that comprises Reach 5A, it was determined that developing a degradation/disturbance score for each wetland or upland cover type for which Form FP-1 was completed would not be a constructive or useful procedure for identifying discrete areas of the floodplain where degradation could be defined for the purposes of aiding in assessing the locations of access and/or staging areas. For example, the contiguous area of transitional floodplain forest comprising much of the floodplain area upstream of Pomeroy Road is one cover type unit, but the sewer utility line within this cover type is not distinctly shown due to the growth of floodplain forest that has developed over this utility line corridor. Therefore, providing a degradation score for this floodplain forest cover type unit would not be sufficiently refined to delineate areas of greater degradation.



Site Degradation/Disturbance Evaluation Forms and associated scores were completed for the more broadly defined wetland functional units (Areas 5A-1, 5A-2, and 5A-3 on Figure 6-3, as well as a separate form for the western side of 5A-1) to assess the overall relative level of degradation of these sections of the Reach 5A floodplain. The results are compiled for each such area in Table 10-1. This table consolidates the criteria and scoring from the Site Degradation/Disturbance Evaluation Forms in one table for clarity and ease of comparison among the four units evaluated. While the results provide some differentiation among evaluation units (e.g., showing the area west of the Confluence as the least degraded/disturbed), the use of even these broader forms remains too general to provide useful information to identify discrete disturbed or degraded areas of the floodplain that could be considered for access roads and staging areas.

As an alternative to the use of these forms to assess levels of degradation and the types of disturbance factors that occur within Reach 5A and which may be useful in defining access and staging areas, four types of disturbance conditions have been identified that are distinct from less disturbed floodplain areas. They are: (1) areas where utility lines have been constructed through the floodplain; (2) areas that have a strong dominance of invasive plant species; (3) other areas that are influenced by ongoing land uses such as mowing or similar land management uses; and (4). areas that have been impacted by historical disturbances. Accordingly, these four disturbance conditions were delineated on Reach 5A cover maps. Figures 10-1a through 10-1e show the resulting delineation of those portions of the Reach 5A floodplain that contain degraded or disturbed conditions. These are summarized as follows:

- <u>Utility lines</u>: Three types of utility lines traverse the Reach 5A floodplain in various areas. An electric transmission line crosses the Housatonic River from the western side of Miss Hall's School upstream of Pomeroy Avenue and extends north through the Reach 5A floodplain to the eastern side of the Confluence. Sewer utility line corridors also extend across this portion of the floodplain extending west from Pomeroy Avenue, and this line continues south along the western side of the River to the Pittsfield WWTF; this sewer line also crosses the floodplain from the Joseph/Eric Drive area. Finally, a gas transmission line extends across the floodplain from the Palomino Drive area to northwest of Eric Drive at Anita Drive. All of these utility lines have infrastructure installed which have affected the subsoils, soils, topography, and vegetative growth within the corridors to various extents, and therefore are classified as disturbed/degraded habitat.
- Areas that have a strong dominance of invasive plant species: As discussed in Section 9.2, three species of invasive plants within Reach 5A have developed discrete areas of dominance in the floodplain that are large enough in area to map (i.e., >0.5 acre). These three species are Japanese knotweed, reed canary grass, and phragmites (or common reed). The discrete areas of dominance by these species are shown on Figures 10-1a-e. Note that, as also



stated in Section 9.2, other areas of invasive species do not present such discrete areas of dominance that afford an ability to delineate specific zones as are shown on those figures.

- <u>Disturbed open space land uses</u>: This category consists of areas that are subject to ongoing land uses such as agriculture, mowing, or similar land management uses (i.e., cultural grasslands).
- Areas impacted by historical disturbances: This category consists of areas that have been
  impacted by historical disturbances such as filling, former sand and gravel mining operations,
  and existing structures (specifically, two buildings, a small portion of a tennis court, and the
  concrete outfall channel from the WWTF).

These delineated areas of specific degradation/disturbance were considered in the preliminary selection of access roads and staging areas presented in the Reach 5A Conceptual RD/RA Work Plan, with the objective of minimizing ecological impact from those activities.

## **10.2 Identification of Restoration Opportunities**

In accordance with the Revised BRA Work Plan, during the BRA activities, GE has also evaluated potential restoration opportunities within the various Reach 5A habitats in the course of surveying the ecological conditions. These considerations included the following:

- Identification of plant species and locations that may be used as propagation material;
- Identification of other features/materials that may be used for post-remediation restoration (e.g., trees, root wads, coarse woody debris, boulders, other rock material);
- Tracking of areas where invasive species dominance may warrant management efforts even if
  off the target of remedial activities (to impede invasive species growth post-remediation);
- The identification of species that may warrant collection/preservation or re-location prior to remediation; and
- Evaluation of data needed for avoidance and/or mitigative measures to be optimized.

For the riverine and riverbank areas, the field surveys included noting the presence of potential restoration resources that may be considered in the bank/river restoration design, such as the presence of boulders, large trees or woody debris, root wad material, or plant propagation source materials. For the riverbanks, these are listed in Form RB-1 (in Appendix B) for each bank station and summarized in Table 4-16. Other noted potential restoration resources included coarse woody debris at all 34 bank stations, rock material (cobbles to boulders) at 88% of the stations, large trees at 60% of the stations, and root wads at 50% of the stations.



Other restoration opportunities listed for each bank survey segment are those considered as potential stabilization/restoration measures appropriate for each bank station, based upon the assessment provided in Appendix G of the RCMS Report and consistent with Natural Channel Design options. Bank stabilization/restoration opportunities based upon this assessment include measures such as coir matting, reshaping point bars, compartmentalized fill, log or rock vanes, and vegetated riprap. These were noted on Form RB-1 for each station (in Appendix B); however, these opportunities were not based on design assessments and are independent of potential bank stabilization/restoration measures that may be ultimately incorporated into the Reach 5A riverbank remediation/restoration design.

For the Reach 5A floodplain, vernal pool, and backwater areas, restoration opportunities tracked during the surveys included identification of the following: fill or other debris that could be removed; features/materials that may be used for restoration (e.g., trees, root wads, coarse woody debris, rock material); the presence and extent (where possible) of invasive plant species to consider for pre- or post-remediation control efforts; and the location of specific plant resources which may warrant consideration in use for post-remediation re-vegetation efforts. The documentation of these floodplain restoration opportunities has been tracked on spreadsheets using the observation plot identifiers for future consideration in the remedial design and restoration process. Any such restoration measures will be described further in the Restoration Corrective Measures Coordination Plan and the Restoration Plan for Reach 5A.



# 11.0 Supplemental BRA Activities and Anticipated Schedule

Supplemental BRA activities will be conducted to take into account in greater detail the actual extent of remediation in Reach 5A and the access roads and staging areas identified in the September 2023 Conceptual RD/RA Work Plan after that work plan is approved by EPA. These activities were proposed in Section 5 of the Supplemental Data Collection Work Plan attached to the Conceptual RD/RA Work Plan. They include the following surveys (as described in that plan) in specific areas that will be affected by remediation and support activities:

- Supplemental riverbank habitat surveys;
- Supplemental backwater habitat surveys;
- Habitat surveys in the Reach 5A hydrographic features that do not constitute backwaters (referred to as Other Waterbodies); and
- Supplemental floodplain habitat surveys.

In addition, as noted in Section 1.4 of the Supplemental Data Collection Work Plan, there were certain previously proposed and approved BRA activities that had not been conducted at that time. These included the fish community survey proposed in Section 3.1.1.3 of the Revised BRA Work Plan, which was subsequently conducted in late September 2023, as described in Section 3.2.4 of this Revised BRA Report. Other supplemental BRA activities that were either previously proposed or added in this Revised BRA Report in response to conditions in EPA's December 21, 2023 conditional approval letter include the following:

- As discussed in Section 5.2.3.4, GE will revisit each backwater in Reach 5A once in 2024 during mid- to late spring to verify species occurrences and check for aquatic plants that may not have been observed in 2022.
- As discussed in Section 5.2.3.8, GE will conduct two additional rounds of water quality sampling in each backwater during mid- to late summer in 2024 if water is available for sampling.
- As described in Section 7.2.2.2, GE will collect soil samples for pH and organic content
  analysis from the 37 vernal pools subject to remediation that have not already been sampled
  for those parameters, and will also collect water quality data from six additional vernal pools.



The results of the above-described supplemental BRA activities will be reported in an addendum to this Reach 5A BRA Report (or other appropriate deliverable) following the completion of those activities and prior to development of the Final RD/RA Work Plan for Reach 5A. Further, as noted in Section 10.2, restoration measures will be described further in the Restoration Corrective Measures Coordination Plan and the Restoration Plan for Reach 5A.



## 12.0 References

- AECOM, 2010. Supplement to Response to EPA's Interim Comments on CMS Report: Evaluation of Example Areas, Housatonic River Rest of River. Prepared for General Electric Company. February 2010.
- AECOM, 2020. Housatonic River Rest of River, Reach 5A Floodplain Pre-Design Investigations:

  Summer/Fall 2019 and Final Report on Potential Vernal Pool Investigations. Prepared for
  General Electric Company. Originally submitted November 18, 2019; revised July 16, 2020.
- AECOM, 2022. Revised Research 5A Baseline Restoration Assessment Work Plan. Prepared for General Electric Company. Submitted July 2022.
- AECOM and Anchor QEA, 2020. Housatonic River Rest of River, Reach 5A Floodplain Pre-Design Investigations: Final Morphology and Accessibility Survey Report. Prepared for General Electric Company. Revised July 16, 2020.
- Anchor QEA and AECOM, 2017. Floodplain Pre-Design Investigation Work Plan Reach 5A. Prepared for General Electric Company. October 2017.
- Anchor QEA and AECOM, 2022. Revised Pre-Design Investigation Work Plan for Reach 5A Sediment and Riverbanks. Housatonic River Rest of River. Prepared for General Electric Company. May 2, 2022.
- Anchor QEA and AECOM, 2023a. *Pre-Design Investigation Summary Report for Reach 5A Sediments and Riverbanks*. Prepared for General Electric Company. September 2023.
- Anchor QEA and AECOM, 2023b. *Revised Vernal Pool Pilot Study Work Plan*. Prepared for General Electric Company. November, 2023.
- Anchor QEA, AECOM, and Arcadis, 2021. *Final Revised Rest of River Statement of Work*. Prepared for the General Electric Company. September 2021.
- Anchor QEA and Arcadis, 2023a. *Interim Baseline Surface Water Monitoring Report. Housatonic Rest of River.* Prepared for the General Electric Company. March 2023.
- Anchor QEA and Arcadis, 2023b. *Pre-Design Investigation Summary Report for Reach 5A Non-Residential Floodplain Exposure Areas*. Prepared for the General Electric Company. September 2023.
- Anchor QEA, Arcadis and AECOM, 2023. *Conceptual Remedial Design/Remedial Action Work Plan for Reach 5A*. Prepared for the General Electric Company. September 2023.



- Arcadis, Anchor QEA, and AECOM, 2010. *Housatonic River Rest of River, Revised Corrective Measures Study Report*. Prepared for the General Electric Company. October 2010.
- Arcadis and QEA, 2008. *Housatonic River Rest of River Corrective Measures Study Report*, Prepared for General Electric Company, Pittsfield, MA, March 2008.
- Ayayee, P.A. 2020. Patterns of denitrification and methanogenesis rates from vernal pools in a temperate forest driven by seasonal, microbial, functional gene abundances, and soil chemistry. Wetlands (2020) 40:721–731.
- Barbour, M.T., J. Gerritsen, B.D. Snyder, and J.B. Striblin, 1999. *Rapid Bioassessment Protocols for Use in Streams and Wadeable Rivers: Periphyton, Benthic Macroinvertebrates and Fish, Second Edition*. EPA 841-B-99-002. U.S. Environmental Protection Agency; Office of Water; Washington, D.C.
- BBL and QEA, 2003. *Housatonic River Rest of River, RCRA Facility Investigation Report* (RFI Report). Prepared for General Electric Company, Pittsfield, Massachusetts. September 2003.
- Calhoun, A. J. K., and M. W. Klemens, 2002. Best development practices: Conserving pool-breeding amphibians in residential and commercial developments in the northeastern United States. MCA Technical Paper No. 5, Metropolitan Conservation Alliance, Wildlife Conservation Society, Bronx, New York.
- Colburn, E.A. 2004. *Vernal Pools: Natural History and Conservation*. McDonald and Woodward Publishing Company.
- Cornell's ebird web site (<a href="https://ebird.org">https://ebird.org</a>) ebird.org: <a href="mailto:Canoe Meadows Wildlife Sanctuary">Canoe Meadows Wildlife Sanctuary</a>, <a href="Pittsfield">Pittsfield</a>, <a href="mailto:Berkshire County">Berkshire County</a>, <a href="mailto:MA, US eBird Hotspot">MA, US eBird Hotspot</a>
- Davies, S.P. and Tsomides, L., 2014. *Methods for biological sampling and analysis of Maine's rivers and streams*. Maine Department of Environmental Protection, Bureau of Land and Water Quality, Division of Environmental Assessment.
- EPA (U.S. Environmental Protection Agency), 2000. Supplemental Investigation Work Plan for the Lower Housatonic River. Prepared by Roy F. Weston, Inc., Manchester, New Hampshire. February 2000.
- EPA, 2006. Final Model Documentation Report (FMDR): Modeling Study of PCB Contamination in the Housatonic River. Prepared by Weston Solutions, Inc., West Chester, PA, for the U.S. Army Corps of Engineers, New England District, and the U.S. Environmental Protection Agency, New England Region. November 2006.



- EPA, 2012. A Function-Based Framework for Stream Assessment and Restoration Projects. EPA 843-K-12-006.
- EPA, 2020. Revised Final Permit Modification to the 2016 Reissued RCRA Permit and Selection of CERCLA Remedial Action and Operation & Maintenance for Rest of River. December 2020.
- EPA and GE (General Electric Company), 2000. Consent Decree (CD) in *United States of America, State of Connecticut, and Commonwealth of Massachusetts v. General Electric Company*, Civil Action Nos. 99-30225, 99-30226, 99-30227-MAP, entered by the United States District Court for the District of Massachusetts. October 27, 2000.
- FGDC (Federal Geographic Data Committee), 2013. *Classification of Wetlands and Deepwater Habitats of the United States*. FGDC-STD-004-2013. Second Edition. Wetlands Subcommittee, Federal Geographic Data Committee and U.S. Fish and Wildlife Service, Washington, DC.
- Fischenich, J. C., 2006. *Functional Objectives for Stream Restoration*. USAE Research and Development Center, Vicksburg, MS. ERDC TN-EMRRP SR-52. September 2006.
- Forman, T.T., and R.D. Deblinger. 2000. The ecological road-effect zone of a Massachusetts (USA) suburban highway. Conservation Biology, 14 (1): 36-46.
- Forman, T.T., and L.E. Alexander. 1998. Roads and their major ecological effects. Annu. Rev. Ecol. Syst. 29:207-231.
- GE, 2010. Supplement to Response to EPA's Interim Comments on CMS Report. Prepared by General Electric Company, Pittsfield, Massachusetts. February 2010.
- GE, 2017. GE-Pittsfield/Housatonic River Site. 1½ Mile Reach of Housatonic River. 2017 Aquatic Macroinvertebrate Sampling Report. Submitted to EPA on November 21, 2017.
- GE, 2021. GE-Pittsfield/Housatonic River Site. Rest of River (GECD850). Further Evaluation Regarding Vernal Pools in Reach 5A. Letter from Kevin Mooney, GE, to Christopher Smith, EPA. February 4, 2012.
- Gibbs, J. P., and J. M. Reed, 2008. Population and genetic linkages of vernal pool associated amphibians. A. J. K. Calhoun, P. G. deMaynadier, editors, Science and Conservation of Vernal Pools in Northeastern North America. 149-167.
- Grabarkiewicz, Jeffrey D., and Wayne S. Davis, 2008. An introduction to freshwater fishes as biological indicators. US Environmental Protection Agency, Office of Environmental, 2008.
- Harman, W., and R. Starr, 2011. Natural Channel Design Review Checklist. US Fish and Wildlife Service, Chesapeake Bay Field Office, Annapolis, MD.



- Harman, W.A., 2009. The Functional Lift Pyramid (Presentation). Mid-Atlantic Stream Restoration Conference. Morgantown, WV.
- Herve, P., S. Grellier, S.D. Tiegs, K.M. Wantzen, and F. Isselin-Nondedeu. 2020. Monitoring organic-matter decomposition and environmental drivers in restored vernal pools. Wetlands Ecol. Manage. 28: 937-952.
- IPANE (Invasive Pla Atlas of New England), 2007. European Buckthorn. Department of Ecology and Evolutionary Biology. University of Connecticut. Storrs, CT, USA. Available: <a href="https://www.invasive.org/weedcd/html/ipane.html">https://www.invasive.org/weedcd/html/ipane.html</a>.
- Karraker, N.E., J.P. Gibbs, and J.R. Vonesh. 2008. Impacts of road deicing salt on the demography of vernal pool-breeding amphibians. Ecological Applications 18 (3): 724-734.
- Kifner, L.H. 2017. Water chemistry dynamics in four vernal pools in Maine, USA. Electronic Theses and Dissertations. 2802. <a href="https://digitalcommons.library.umaine.edu/etd/2802">https://digitalcommons.library.umaine.edu/etd/2802</a>.
- Lenat D. R. and D. L. Penrose. 1996. History of the EPT taxa richness metric. Bulletin of North American Benthological Soc. 13: 305-307. Massachusetts Department of Conservation and Recreation, <u>List of Current and Potential Aquatic Invasive Species | Mass.gov.</u>
- MassDFW (Massachusetts Division of Fisheries and Wildlife), 2012. Core Habitat Area figures for Housatonic River Primary Study Area (PSA), and July 31, 2012 letter from Mass DFW. Attachment B to EPA's Final Revised Permit.
- MassGIS, 2021-2023. Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services. <a href="MassGIS">MassGIS</a> (Bureau of Geographic Information) | Mass.gov.
- MIPAG, 2005. The Evaluation of Non-Native Plant Species for Invasiveness in Massachusetts (with annotated list). Massachusetts Invasive Plant Advisory Group. April 1, 2005. Updates on-line at: MIPAG Massachusetts Invasive Plant Advisory Group (massnrc.org)
- MNHESP (Massachusetts Natural Heritage and Endangered Species Program), 2010. Rare Species and Natural Community Surveys in the Housatonic River Watershed of Western Massachusetts. Prepared for Trustee Sub-Council for Massachusetts Natural Resource Trustees for the GE/Housatonic River in partial completion of Proposal 18: "Rare Species Recovery on the Housatonic River." Natural Heritage and Endangered Species Program, Massachusetts Division of Fisheries and Wildlife. July 2010.
- MNHESP, 2011. Conserving Biodiversity in the Housatonic River Watershed of Western Massachusetts.

  Mass Division of Fisheries & Wildlife/Natural Heritage & Endangered Species Program.



- MNHESP, 2020. List of Endangered, Threatened, and Special Concern species | Mass.gov
- Native Plant Trust. Gobotany.nativeplanttrust.org
- NEIWPCC, 2018. Field Indicators for Identifying Hydric Soils in New England, Version 4, written by the New England Hydric Soils Technical Committee.
- Rosgen, D.L., 2006. Watershed Assessment of River Stability and Sediment Supply (WARSSS). Wildland Hydrology Books. Fort Collins, CO. 648 pp.
- Rowe, L.R., and W.A. Dunson. 1993. Relationships among abiotic parameters and breeding effort by three amphibians in temporary wetlands of central Pennsylvania. Wetlands 13 (4): 237-246.
- Saether, O., 1975. Chironomid communities as water quality indicators. Holarctic Ecology 2: 65-74.
- Stantec, 2009. A Study of Bank Erosion Rates within Selected Reaches of the Housatonic River. Stantec 2009). Stantec Consulting, Topsham, ME.
- Swain, P. C. 2020. Classification of the Natural Communities of Massachusetts. Massachusetts Division of Fisheries and Wildlife, Westborough, MA.
- Swain, P.C., and J.B. Kearsley, 2000. Classification of the Natural Communities of Massachusetts.

  Massachusetts Natural Heritage and Endangered Species Program, Westborough, MA.
- TechLaw, Inc., 1998. Preliminary Report: Wetland Characterization and Function-Value Assessment, Housatonic River from Newell Street to Woods Pond. TechLaw, Inc., Boston, MA.
- USACE (U.S. Army Corps of Engineers), New England Division), 1995. *The Highway Methodology Workbook Supplement, Wetland Functions and Values, A Descriptive Approach*, NEDEP-360-1-30a.
- USACE (U.S. Army Corps of Engineers), Engineer Research and Development Center, 2012. Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Northcentral and Northeast Region (Version 2.0). ERDC/EL TR-12-1.
- USDA NRCS. 2023. Soil Survey Geographic Database (SSURGO) database. Available URL: https://www.nrcs.usda.gov/resources/data-and-reports/soil-survey-geographic-database-ssurgo#:~:text=The%20map%20units%20describe%20soils,a%20scale%20of%201%3A63%2C 360.
- USDA NRCS. 2022. The PLANTS Database (http://plants.usda.gov, 07/11/2022). National Plant Data Team, Greensboro, NC USA.



- USFWS (U.S. Fish and Wildlife Service, 2022. Monarchs. Available URL: <a href="https://www.fws.gov/initiative/pollinators/monarchs">https://www.fws.gov/initiative/pollinators/monarchs</a>. [Accessed 08/11/2023].
- USFWS (U.S. Fish and Wildlife Service), 2023. Information, Planning, and Consultation System (IPaC). Available on-line at: <a href="https://ecos.fws.gov/ipac">https://ecos.fws.gov/ipac</a>.
- USFWS. Available URL: ECOS: Home (fws.gov).
- USGS (U.S. Geological Survey), 2014. Available URL: http://pubsdata.usgs.gov/pubs/of/2006/1195/htmldocs/munsellcode.htm
- Weatherbee, P,B., and G.E. Crow, 1992. Natural plant communities of Berkshire County, Massachusetts. Rhodora, 94 (878): 171-209.
- Woodlot (Woodlot Alternatives, Inc.), 2002a. *Ecological Characterization of the Housatonic River*.

  Prepared for EPA Region 1, Boston. Contract No. DACW33-94-D-0009/032. September 2002.
- Woodlot (Woodlot Alternatives, Inc), 2002b. *Ecological Characterization of the Housatonic River Downstream of Woods Pond*. Prepared for EPA Region 1, Boston. Contract No. DACW33-94-D-0009/032.



# **Tables**

Table 3-1: Reach 5A Riverine Habitat Characterization

Description of Parameter	Reach 5A Inventory Approach*					
Mapping of physical location and limits; high gradient/mid- gradient/low gradient	Updated LiDAR and bathymetric mapping; consolidate existing information (from sources below); 2022 site reconnaissance and RBP field surveys					
Flooding and flow characteristics (volume/velocity from peak to base flow, bankfull discharge); hydrologic indicators (mean low water, mean high water, bankfull stage)	Consolidate existing information from prior hydrologic modeling, USGS gauge data, and other relevant sources below; discharge volume of 1.5-2 yr flood flow in channel cross-section; field indicators via site reconnaissance and updated LiDAR and bathymetric mapping					
Channel form (type)/sinuosity; channel-forming flow; physical dimensions (length, area, depth, width, thalweg); floodplain connectivity (entrenchment status; side channel connections); stream bedform variability (riffle/pool/run)	Sinuosity (stream length/valley length) and other morphology to be measured from updated LiDAR and bathymetric mapping; consolidate existing information (from sources below); 2022 site reconnaissance and RBP field surveys					
Range in observed bank heights relative to mean low water, mean high water, and bankfull stages; substrate composition; vegetative cover; stability/erosiveness	BEHI/NBS information from Stantec 2009 evaluation, 2010 Example Area evaluations, and PDI of Reach 5A banks (including updated BEHI/NBS assessment); consolidate other bank-related information (from sources below); 2022 site reconnaissance and field surveys using Form RB-1					
Sediment/substrate composition (% clay/silt/sand, gravel/cobble; boulder/bedrock; organic matter); sediment depositional/erosion features (bars, benches, fans, cut banks); riffle/pool/run presence; large woody debris	Consolidate existing information (from sources below); 2022 site reconnaissance and RBP surveys					
Temperature, pH, TSS, turbidity, clarity, dissolved oxygen	Consolidate existing information (from sources below); 2022 RBP field surveys					
Species composition and relative abundance of aquatic macrophytes, fish, benthic habitat/organisms, and other water-using biota; presence/abundance of invasive plant and animal species	Review of invasive plant species lists from USACE New England District and MIPAG and invasive aquatic animal species guidance from MassDCR and USGS; consolidate existing information (from sources below); 2022 site reconnaissance and RBP field surveys; benthic macroinvertebrate and fish community surveys; incidental wildlife observations.					
Priority Habitat/Core Area Habitat mapping; IPaC results from USFWS on-line data base	MNHESP investigations and designations (including updated outreach to MNHESP); IPaC results; direct observations during 2022 RBP field surveys and other site investigations					
Riparian vegetative cover; overhanging vegetation; rare species habitat; invasive species	Consolidate existing information (from sources below); aerial photography; site reconnaissance and 2022 field surveys (RBP, bank, and floodplain inventories)					
	Mapping of physical location and limits; high gradient/midgradient/low gradient  Flooding and flow characteristics (volume/velocity from peak to base flow, bankfull discharge); hydrologic indicators (mean low water, mean high water, bankfull stage)  Channel form (type)/sinuosity; channel-forming flow; physical dimensions (length, area, depth, width, thalweg); floodplain connectivity (entrenchment status; side channel connections); stream bedform variability (riffle/pool/run)  Range in observed bank heights relative to mean low water, mean high water, and bankfull stages; substrate composition; vegetative cover; stability/erosiveness  Sediment/substrate composition (% clay/silt/sand, gravel/cobble; boulder/bedrock; organic matter); sediment depositional/erosion features (bars, benches, fans, cut banks); riffle/pool/run presence; large woody debris  Temperature, pH, TSS, turbidity, clarity, dissolved oxygen  Species composition and relative abundance of aquatic macrophytes, fish, benthic habitat/organisms, and other water-using biota; presence/abundance of invasive plant and animal species  Priority Habitat/Core Area Habitat mapping; IPaC results from USFWS on-line data base  Riparian vegetative cover; overhanging vegetation; rare					

<sup>\*</sup> The existing information used for the Reach 5A riverine habitat characterization included information from the following sources: the 2002 Woodlot Ecological Characterization reports, the 2003 RFI Report, the 2010 Example Area evaluations and RCMS Report, the MNHESP investigations of state-listed species through 2012, and the Final Accessibility Report – all described and referenced in Section 2 of the Reach 5A BRA Work Plan – as well as USGS gauge data and previous hydrologic modeling (e.g., EFDC model) referenced in Section 3.1.1 of the Work Plan.

**Table 3-2: RBP Riverine Parameters Collected** 

Category	Name	Parameter Details		
	Reach Length (m)	Reach length measured along river centerline		
	Stream Width (m)	Estimated average width of river		
	Sampling Reach Area (m <sup>2</sup> )	Calculated in GIS using delineated reach polygons		
	Depth (m)	Average estimated depth of all riverine areas		
INSTREAM	Surface Velocity (m/sec)	Average estimated surface velocity		
FEATURES	High Water Mark (m)	Average distance from normal water level to high water mark		
	Canopy Cover	Open, Partly open, Partly shaded, or Shaded		
	% Riffle			
	% Pool	% of river reach in each stream morphology type		
	% Run			
LWD	Large Woody Debris (LWD; m <sup>2</sup> )	Total area of LWD		
LVVD	Density of LWD (m <sup>2</sup> /km <sup>2</sup> )	Area of LWD/ Sampling reach area		
Riparian	Dominant Riparian Vegetation	Vegetation Type (e.g Trees, Shrubs, Herbs)		
Vegetation	Dominant Riparian Species	1-4 dominant riparian vegetation species		
	Dominant Aquatic Veg	1-4 dominant aquatic vegetation species		
Aquatic Vegetation	% Aquatic Vegetation	% coverage of aquatic vegetation species (including algae)		
	Water Temp (deg C)			
	Specific Conductance (ms/cm)	Collected by water quality sonde		
	DO (mg/L)			
Water Quality	рН			
	Turbidity	_		
	Odor	Observations		
	Oils			
	Bedrock %	_		
	Boulder %	_		
Outlineturet	Cobble %	— 0/		
Substrate (Inorganic)	Gravel %	<ul> <li>% coverage of each inorganic substrate type, totals to</li> <li>100%</li> </ul>		
(9)	Sand %	_		
	Silt %	_		
	Clay %			
Onlysterite	Detritus %	= 0/		
Substrate (Organic)	Muck-Mud %	<ul> <li>% coverage of organic substrate. Does not total to 100%,</li> <li>detritus includes fine wood cover</li> </ul>		
	Marl %			

Table 3-2: RBP Riverine Parameters Collected (continued)

Category	Name	Parameter Details			
	Epifauna; Substrate/ Available Cover				
	Pool Substrate Characterization	_			
	Pool Variability	_			
	Sediment Deposition	_			
	Channel Flow Status	_			
	Channel Alteration	_			
HABITAT	Channel Sinuosity	<ul> <li>Rating of each characteristic, following guidance for rating</li> <li>of each parameter. (Each Scored 0-20, 0=Poor and</li> </ul>			
ASSESSMENT	Bank Stability (LB)	20=Optimal)			
PARAMETERS	Bank Stability (RB)	_			
	Vegetative Protection (LB)	_			
	Vegetative Protection (RB)	_			
	Riparian Vegetative Zone Width (LB)	_			
	Riparian Vegetative Zone Width (RB)				
	Total Score	Sum of ratings above			

Table 3-3: RBP Results – Instream Features and Large Woody Debris (LWD) Coverage

			II.	NSTREAM F	EATURES					LWD
RBP Station #	Reach Length (m)	Stream Width (m)	Sampling Reach Area (Sq. Meter)	Depth (m)	Surface Velocity (m/sec)	% Riffle	% Pool	% Run	LWD (m <sup>2</sup> )	Density of LWD (m²/km²)
1	154.4	27	2,753	1.5	0.5	20	60	20	50	18.2
2	200	17	3,535	1	0.5	5	25	70	200	56.6
3	365	25	7,701	1	0.5	25	10	65	150	19.5
4	500	25	8,872	1.5	0.5	10	20	70	500	56.4
5	490	25	10,404	0.75	0.25	15	30	55	200	19.2
6	975	25	19,568	1.5	0.25	5	65	30	500	25.6
7	550	20	10,658	1.5	0.25	10	45	45	700	65.7
8	400	18	8,180	1.5	0.3	2	28	70	350	42.8
9	579	28	14,001	1	0.75	16	32	52	1000	71.4
10	500	20	10,429	1.5	0.3	2	60	38	200	19.2
11	180	25	4,985	0.5	0.25	0	10	90	100	20.1
12	518	25	12,030	1	0.3	0	35	65	75	6.2
13	450	30	14,004	1.25	2	2	13	85	125	8.9
14	610	28	14,201	1	0.4	0	50	50	100	7.0
15	300	30	7,764	1	0.3	0	10	90	150	19.3
16	280	25	6,899	1	0.5	15	50	35	400	58.0
17	200	20	4,070	2	0.2	0	65	35	500	122.8
18	533	30	12,122	2	0.125	0	88	12	400	33.0
Area Weighted Average	432.5	24.6	9,565	1.3	0.5	6%	41%	53%	316.7	33.1

Table 3-4: RBP Results – Aquatic Vegetation and Substrate Characteristics

	Aquatic Vegetation	n			Substr	ate (Inorga	ınic)			Subs	trate (Orga	ınic)
RBP Station #	Dominant Aquatic Veg	% Aquatic Vegetation	Bedrock %	Boulder %	Cobble %	Gravel %	Sand %	Silt %	Clay %	Detritus %	Muck- Mud %	Marl %
1	Potamogeton crispus	3	0	2	15	20	5	48	10	10	5	0
2	Algae	0.5	0	0	15	15	40	20	10	20	5	0
3	Potamogeton crispus	2	0	0	10	30	25	25	10	7	1	0
4	Potamogeton crispus	2	0	0	10	25	40	20	5	10	0	0
5	Potamogeton crispus	2	0	6	2	30	30	29	3	5	3	0
6	Potamogeton crispus, algae	20	0	3	3	32	32	20	10	5	0	0
7	Potamogeton crispus, water celery, blue flag iris	1	0	2	5	25	35	30	3	5	0	0
8	Yellow flag iris, algae	0.5	0	5	10	25	30	25	5	15	0	0
9	Algae	15	0	1	2	30	40	17	10	10	1	0
10	Potamogeton crispus, sparse macrophyte algae	15	0	0.5	10	10	50	20	10	10	0	0
11	Water celery	0.5	0	5	10	20	35	20	10	10	0	0
12	Water celery, algae, Eurasian milfoil	2	0	5	20	20	47	5	3	8	5	0
13	Bur-reed	5	0	0	15	10	50	20	5	15	0	0
14	Grasses	4	0	1	2	20	65	10	2	10	10	0
15	Bur-reed, macrophyte algae	2	0	0	0	20	55	20	5	15	5	0
16	Burr reed, algae	0.5	0	0	5	20	35	20	20	10	0	0
17	Bur-reed, Eurasian milfoil	2	0	0	0	20	60	10	10	15	5	0
18	Burr-reed	1	0	2	2	5	50	30	11	6	8	0
Area Weighted Average		4.3%	0.0%	1.9%	6.9%	21.5%	41.9%	20.4%	7.3%	9.5%	2.6%	0.0%

Table 3-5: RBP Habitat Assessment Parameters. Each Scored 0-20; 0-5=Poor, 6-10=Marginal (red), 11-15=Sub-optimal (yellow/orange), 16-20=Optimal (green)

RBP Station #	Epifauna; Substrate/ Available Cover	Pool Substrate Characterization	Pool Variability	Sediment Deposition	Channel Flow Status	Channel Alteration	Channel Sinuosity	Bank Stability	Vegetative Protection	Riparian Vegetative Zone Width	Total Score
1	14	12	17	11	14	19	17	8	9	18	139
2	13	16	16	12	15	19	14	11	10	20	146
3	10	10	16	9	12	17	6	11	12	16	119
4	16	10	13	11	14	17	12	9	10	20	132
5	10	11	14	8	9	13	8	8	12	14	107
6	12	12	11	8	10	13	6	10	12	14	108
7	15	12	12	9	13	19	13	10	12	18	133
8	11	13	15	9	15	20	8	12	16	20	139
9	8	15	16	7	13	18	8	8	10	18	121
10	12	14	15	7	15	20	16	6	10	20	135
11	10	10	6	10	14	20	8	16	18	20	132
12	13	19	15	12	14	19	10	10	12	20	144
13	13	14	18	12	13	17	10	16	18	20	151
14	10	13	17	9	14	18	15	9	14	18	137
15	11	13	6	13	15	18	13	14	14	14	131
16	9	11	12	12	11	16	15	14	16	16	132
17	12	10	13	13	18	20	18	6	7	15	132
18	8	9	12	6	13	17	18	6	10	14	113
Area Weighted Average	11.34	12.66	13.74	9.41	13.01	17.29	11.28	10.09	12.53	17.32	128.67

Table 3-6: Macroinvertebrate Survey Results Compiled by Order

				Stat	ion Numbe	(from N to	S)		_ Total by
Phylum	Class	Order	1	2	3	4	5	6	Order
Annelida	Clitellata	Lumbriculida		1					1
		Tubificida			4	5	29	4	42
Arthropoda	Arachnida	Trombidiformes	1						1
	Insecta	Coleoptera	14		17	28	6	4	69
		Diptera	7	24	65	166	129	235	626
		Ephemeroptera	14	69	77	24	42	16	242
		Hemiptera				4			4
		Megaloptera					1		1
		Odonata	2	1	5	4	4		16
		Plecoptera				2			2
		Trichoptera	202	39	156	85	62	60	604
	Malocostraca	Amphipoda			1	1	4		6
		Decapoda		2	1	1	4	0	8
		Isopoda				1	21	1	23
Mollusca	Bivalvia	Sphaeriida				1	4		5
		Unionoida			1				1
	Gastropoda	Basommatophora	2	1	5	2	5	1	16
Nematoda			1	2		2			5
Plathyhelminthes	Trepaxonemata					1			1
Grand Total			243	139	332	327	311	321	1673

Table 3-7: Macroinvertebrate Survey Results- Taxa Measures and Benthic Community Classifications (A, B, C)

Station	Taxa Richness	Abundance	EPT Richness	Dominant Organism	Chironomidae Richness
1	21 C	243	9 C	Hydropsyche betteni (35.0%) B	5 A
2	23 C	139	9 C	Iswaeon anoka (27.3%) A	9 A/B
3	45 B	332	14 B	Hydropsyche betteni (26.8%) B	17 B
4	51 B	327	15 B	Tanytarsus sp. (27.5%) C	18 B
5	46 B	311	12 C	Cheumatopsyche sp. (12.5%) B	16 B
6	32 C	321	9 C	Simulium sp. (40.5%) C	15 A/B
Average	36	286	11		13.33

#### Notes:

- 1. Richness metrics were summed at the genus level per the Lotic Inc. model used to evaluate water quality and habitat. Richness calculated at the species level would be higher.
- 2. The Lotic Inc. classification model used above assigns the following classifications based on benthic community structure to aid in interpretation of the data in comparison to other similar streams in New England:
  - Class A- High quality; aquatic life as naturally occurs,
  - Class B- Good quality; no detrimental changes to the biological community,
  - Class C- Fair quality, some changes to aquatic life; maintains the structure and function of the resident biological community,
  - Non-attainment (NA)- Does not attain Class A, B or C classifications (not present in these samples).

## **Table 3-8: Small Fish Species Trapping Results**

# Northern 5A – Upstream of Canoe Meadows

# N1- Located on the edge of a pool in LWD, 2 ft depth

N2- Located in gravel bar with LWD in 1 ft depth

Species	Life stage	Length (mm)	Species	Life stage	Length (mm)
crayfish	adult	51	crayfish	adult	34
crayfish	adult	57	crayfish	adult	29
crayfish	adult	35	crayfish	adult	40
crayfish	adult	34	rock bass	juvenile	39
crayfish	adult	31	spottail shiner	adult	34
crayfish	adult	42			
crayfish	adult	41			
crayfish	adult	38			

## Middle 5A- Near East New Lenox Road

#### M1- Located downstream of falls in 1.5 ft depth

## M2- Located in large boulders in 1.5 ft depth

Species	Life stage	Length (mm)	Species	Life stage	Length (mm)			
spottail shiner	adult	33	crayfish	adult	34			
spottail shiner	adult	33	crayfish	adult	29			
spottail shiner	adult	41	crayfish	adult	40			
rock bass	adult	171	crayfish	adult	31			
crayfish	adult	37	parts from 2 other eaten of	rayfish				
crayfish	adult	28						
crayfish	adult	33						
crayfish	adult	38						
crayfish	adult	22						
•	•	•	·	<u>-</u>	<u> </u>			

# Southern 5A- Near East New Lenox Road

# S1- Located in milfoil bed in 1 ft depth

# S2- Located in LWD in 2.5 ft depth

Species	Life stage	Length (mm)	Species	Life stage	Length (mm)		
yellow perch	juvenile	71	spottail shiner	adult	56		
rock bass	juvenile	27	crayfish	adult	35		
rock bass	juvenile	42	crayfish	adult	32		
white sucker	juvenile	88	crayfish	adult	38		
white sucker	juvenile	82	crayfish	adult	32		
white sucker	juvenile	68	Note: a 4"v4" bala w	as found in each tran ofto	or the night (2nd) est		
finescaled dace	adult	56	Note: a 4"x4" hole was found in each trap after the night (2nd) set.				

Table 3-9: Fish Composition Results from Electrofishing in Lower Reach 5A from September 29, 2023 showing life stages and total of each species. (Note YOY= Young of Year)

Species	YOY	Juvenile	Adult	Large adult	Total
Black crappie	1				1
Bluntnose minnow			1		1
Bluegill	2				2
Pickerel		2			2
Fallfish	1	1	2		4
Smallmouth bass		4	1		5
Largemouth bass	5	1			6
Pumpkinseed	8				8
Rock bass			10		10
Yellow perch	12	5	2	1	20
White sucker		4	25		29
Spottail shiner			36		36
<b>Grand Total</b>	29	17	77	1	124

Table 3-10: Summary of Wildlife Observations Made During the 2022 Riverine Surveys

Common Name	Scientific Name	Common Name	Scientific Name
Amphibia	ns and Reptiles	Bi	rds
American Toad	Anaxyrus americanus	American goldfinch	Spinus tristis
Common snapping turtle	Chelydra serpentina	Belted kingfisher	Megaceryle alcyon
Green frog	Lithobates clamitans	Blue jay	Cyanocitta cristata
Green tree frog	Hyla cinerea	Canada goose	Branta canadensis
Painted turtle	Chrysemys picta	Cedar waxwing	Bombycilla cedrorum
Pickerel Frog	Lithobates palustris	Common grackle	Quiscalus quiscula
Red eared slider	Trachemys scripta elegans	Cooper's hawk	Accipiter cooperii
		Common yellow throat warbler	Geothlypis trichas
Inve	ertebrates	Gray catbird	Dumetella carolinensis
Bumblebee	Bombus spp.	Great Blue Heron	Ardea herodias
Caddisflies	Order Trichoptera	Hummingbird	Trochilidae spp.
Freshwater Clams	Family Veneridae	Killdeer	Charadrius vociferus
Common water strider	Aquarius remigis	Mallard	Anas platyrynchos
Crayfish	Cambarus spp.	Red bellied woodpecker	Melanerpes carolinus
Damselflies	Order Zygoptera	Red-tailed hawk	Buteo jamaicensis
Dragonflies	Order Anisoptera	Redwing blackbird	Agelaius phoeniceus
Eastern Elliptio	Elliptio complanata	Sandpiper	Scolopacidae
Honeybee	Apis mellifera	White-breasted nuthatch	Sitta carolinensis
Whirligig beetles	Family <i>Gyrinidae</i>	Wood duck	Aix sponsa
M	ammals	Yellow warbler	Setophaga petechia
American Beaver	Castor canadensis	F	ish
Racoon	Procyon lotor	Bluegill	Lepomis macrochirus
White-tailed deer	Odocoileus virginianus	Brook trout	Salvelinus fontinalis

Table 3-11: State-Listed Rare Species Associated with the Aquatic Riverine Habitats of Reach 5A

Scientific Name	Common Name	State Status
Botaurus lentiginosus	American Bittern	Endangered
Ophiogomphus aspersus	Brook Snaketail	Special Concern
Gallinula galeata	Common Gallinule	Special Concern
Eleocharis intermedia	Matted Spike-sedge	Threatened
Boyeria grafiana	Ocellated Darner	Special Concern
Phanogomphus quadricolor	Rapids Clubtail	Endangered
Ophiogomphus carolus	Riffle Snaketail	Threatened
Hylogomphus abbreviatus	Spine-crowned Clubtail	Special Concern
Sagittaria cuneata	Wapato	Threatened
Glyptemys insculpta	Wood Turtle	Special Concern

**Table 3-12: Reach 5A Riverine Function Assessment Factors** 

Functional Category	Description of Functions	Parameters Considered in Assessing Function (see Table 3-1)
Hydrologic Support	Water conveyance and transport; watershed connectivity; floodwater dynamics (flood flow amelioration, flood storage and desynchronization, peak rate control); base flow maintenance (groundwater discharge); migration and dispersal corridor	Hydrology; geomorphology; bank characteristics
Geomorphology	Channel formation and maintenance; floodplain connectivity; transport of organic and mineral sediment material; transport of woody debris; transport of nutrients and food sources	Hydrology; geomorphology; bank characteristics; in-stream habitat features
Physicochemical	Water quality maintenance; temperature and oxygen regulation; processing of organic matter and nutrients	Hydrology; in-stream habitat features; water quality; aquatic biota habitat
Biological	Biodiversity and sustaining life stages of aquatic and riparian life; habitat for aquatic and other water-using biota; rare species habitat	Hydrology; geomorphology; bank characteristics; in-stream habitat features; water quality; habitat for aquatic and other water-using biota; riparian zone conditions; rare species habitat (mapped Priority Habitat and Core Area habitat and IPaC results); connectivity; invasive plant and animal species; benthic macroinvertebrate and fish community surveys; incidental wildlife observations

Table 4-1: Reach 5A Riverbank Habitat Characterization

Parameter	Description of Parameter	Reach 5A Inventory Approach <sup>1</sup>
Mapping and physical measures	Mapping of physical location and limits; length, depth, slope	Updated LiDAR and bathymetric mapping.
Bank height (relative to water stage); bankfull stage/discharge	Range in observed bank heights relative to mean low water, mean high water, and bankfull stages.	Consolidate existing information (from sources below); updated LiDAR and bathymetric mapping; 2022 field surveys using Form RB-1; discharge volume of 1.5-2 yr flood flow in channel cross-sections
Floodplain connectivity	Hydrologic connection between the river and floodplain; degree of river incisement/entrenchment along with breaks in the bank or conduits for floodwater dispersement into the floodplain	Consolidate existing information (from sources below); 2022 field surveys using Form RB-1
Soil/substrate composition	Relative % clay/silt/sand and gravel/cobble; boulder/bedrock presence; organic matter	Consolidate existing information (from sources below); PDI of Reach 5A banks (including updated BEHI/NBS assessment); 2022 field surveys using Form RB-1
Bank stability and migration	Observed erosional conditions; documentation of river channel/bank migration	BEHI/NBS information from Stantec 2009 evaluation; 2010 Example Area evaluations, and PDI of Reach 5A banks (including updated BEHI/NBS assessment); consolidate other bank-related information (from sources below); 2022 field surveys using Form RB-1
Large woody debris (LWD)	Density of LWD; woody debris on the bank	Consolidate existing information (from sources below); 2022 field surveys using Form RB-1
Vegetation, including on- bank, overhanging, and riparian vegetation	Species composition and relative abundance; presence/abundance of invasive species	Review of invasive plant species lists from USACE New England District and MIPAG; consolidate existing information (from sources below); aerial photography; 2022 field surveys using Form RB-1
General wildlife habitat	Species composition and relative abundance of riverbank and riparian wildlife	Consolidate existing information (from sources below); 2022 field surveys using Form RB-1; incidental wildlife observations
Rare species habitat	Priority Habitat/Core Area Habitat mapping; IPaC results from USFWS on-line data base	MNHESP investigations and designations (including updated outreach to MNHESP); IPaC results; 2022 field surveys using Form RB-1
Unique habitat features	Cut banks; turtle hibernacula or nesting sites, kingfisher or bank swallow nest sites (vertical sandy banks); otter slides; rock basking sites; beaver bank dens; burrows; tree cavities; bars and benches	Consolidate existing information (from sources below); 2022 field surveys using Form RB-1

<sup>&</sup>lt;sup>1</sup> The existing information used for the Reach 5A riverbank habitat characterization includes information from the following sources: the 2002 Woodlot Ecological Characterization, the Stantec 2009 bank erosion evaluation, the 2003 RFI Report, the 2010 Example Area evaluations and RCMS Report, the MNHESP investigations of state-listed species through 2012, the Final Accessibility Report – all described and referenced in Section 2 of the Reach 5A BRA Work Plan.

Table 4-2: Reach 5A Riverbank Summary Data\*

Parameter		Average	Range	
Bank Height		6.2 ft	4-10 ft	
Bank Slope		66%	25-105%	
Bankfull Indicators		2.97 ft	2-5 ft	
Bank Substrate	Sand	41.8%	30-50%	
	Silt	42.4%	30-50%	
_	Clay	0%	N/A	
_	Gravel/Cobble	12.9%	0-30%	
_	Boulder/Bedrock	2.6%	0-20%	
_	Organic	1%	0-5%	
Stream Gradient	Low	35%		
_	Mid	65%		
Total Vegetative Cover	Bank	75%	30-100%	
	Overhanging	60%	10-100%	
	Riparian	90%	60-100%	
Vegetative Cover by Strata	Tree	40%	0-90%	
_	Shrub	45%	0-80%	
_	Herb	55%	0-90%	
_	Vine	30%	0-70%	
	Moss	0%	0%	
Riparian Zone Vegetative Cover	Tree	58%	10-80%	
by Strata	Shrub	65%	20-85%	
_	Herb	68%	40-90%	
_	Vine	25%	10-35%	
_	Moss	1%	0-5%	

<sup>\*</sup>Data summarized from 34 riverbank stations ranging from 100-400 feet in length (8,300 lf in total), combining both left and right bank data

Table 4-3: Reach 5A Riverbank Sediment/Substrate Composition

Bank Station	%Sand	%Silt	%Clay	%Gravel/ Cobble	%Boulder/ Bedrock	%Organic Matter
1	50	40	0	10	0	5
2	50	50	0	0	0	5
3	50	50	0	0	0	5
4	40	30	0	30	0	3
5	50	50	0	0	0	5
6	40	50	0	10	0	0
7	40	40	0	20	0	3
8	30	50	0	20	0	0
9	45	45	0	10	0	0
10	45	45	0	10	0	0
11	40	40	0	20	0	0
12	30	30	0	20	20	0
13	40	50	0	10	0	0
14	40	40	0	20	0	0
15	40	50	0	10	0	0
16	40	30	0	20	10	0
17	30	30	0	20	20	0
18	45	45	0	10	0	0
19	40	50	0	10	0	0
20	50	35	0	15	0	0
21	30	30	0	20	20	0
22	45	45	0	10	0	0
23	40	40	0	20	0	0
24	30	30	0	30	10	0
25	40	40	0	0	10	5
26	45	45	0	10	0	0
27	45	50	0	5	0	0
28	45	45	0	10	0	0
29	45	45	0	10	0	0
30	40	40	0	20	0	0
31	45	45	0	10	0	0
32	45	45	0	10	0	0
33	40	40	0	20	0	0
34	50	50	0	0	0	0

Table 4-4: Reach 5A Riverbank Hydrology Ratings: Channel Gradient, Incisement, and Floodplain Connectivity

**Floodplain Connectivity High-flow Channels** Topographic **Incisement Rating** in Floodplain **Breaks in Bank Bank Station** Stream Gradient Mid-gradient 1 Somewhat incised  $\sqrt{}$  $\sqrt{}$ 2 Low-gradient Moderately incised  $\sqrt{}$ 3 Mid-gradient Moderately incised 4 Mid-gradient Moderately incised  $\sqrt{}$  $\sqrt{}$ Mid-gradient Somewhat incised 5  $\sqrt{}$  $\sqrt{}$ 6 Mid-gradient Moderately incised 7  $\sqrt{}$ Mid-gradient Moderately incised  $\sqrt{}$ 8 Mid-gradient Somewhat incised 9  $\sqrt{}$ Mid-gradient Somewhat incised  $\sqrt{}$ 10 Somewhat incised Mid-gradient 11 Low-gradient Not incised 12 Low-gradient Somewhat incised 13 Low-gradient Somewhat incised Mid-gradient  $\sqrt{}$ 14 Moderately incised  $\sqrt{}$ 15 Mid-gradient Moderately incised Somewhat incised  $\sqrt{}$  $\sqrt{}$ 16 Mid-gradient  $\sqrt{}$ 17 Mid-gradient Not incised  $\sqrt{}$  $\sqrt{}$ Somewhat incised 18 Low-gradient  $\sqrt{}$  $\sqrt{}$ 19 Low-gradient Moderately incised  $\sqrt{}$  $\sqrt{}$ 20 Mid-gradient Not incised  $\sqrt{}$  $\sqrt{}$ 21 Mid-gradient Somewhat incised  $\sqrt{}$  $\sqrt{}$ 22 Low-gradient Not incised 23  $\sqrt{}$ Mid-gradient Somewhat incised 24 Mid-gradient Moderately incised 25 Mid-gradient Somewhat incised  $\sqrt{}$  $\sqrt{}$ 26 Mid-gradient Moderately incised  $\sqrt{}$ 27 Somewhat incised Low-gradient  $\sqrt{}$ 28 Mid-gradient Not incised  $\sqrt{}$ 29 Mid-gradient Somewhat incised 30 Mid-gradient Somewhat incised  $\sqrt{}$ 31 Low-gradient Somewhat incised 32 Low-gradient Moderately incised  $\sqrt{}$ 33 Low-gradient Moderately incised 34 Low-gradient Somewhat incised

Table 4-5: Reach 5A Riverbank Bordering Habitat Types

			Bordering	Borde	ing Upland I	-labitats <sup>2</sup>				
<b>Bank Station</b>	TFF	SS	SEM	DEM	VP	RMS	HTF	HPF	GG-AF	DD
1			V	$\sqrt{}$						
2	<b>√</b>									
3	V									
4	<b>√</b>									
5	$\sqrt{}$		$\sqrt{}$	$\sqrt{}$						
6	$\sqrt{}$									
7										$\sqrt{}$
8	<b>√</b>							V		
9	<b>√</b>	V						V		
10	<b>√</b>	V						V		
11	<b>√</b>								V	
12	$\sqrt{}$								V	
13										
14				V						
15									V	
16									V	$\sqrt{}$
17					√					
18		V			$\sqrt{}$					
19	$\sqrt{}$	V	V							
20	$\sqrt{}$	V	V					V		
21									V	
22		V							V	
23	$\sqrt{}$						V	V		
24										
25	$\sqrt{}$	V				$\sqrt{}$				
26	$\sqrt{}$							V		
27										
28	√		V						V	
29	√							V	V	
30	$\sqrt{}$		V					V	V	
31	V		V					V	V	
32	V		V		<b>V</b>			V	V	
33	<b>√</b>		V		V			V	V	
34	$\sqrt{}$		V	V				V	V	

<sup>1</sup>TFF: Transitional Floodplain Forest; SS: Shrub Swamp; SEM: Shallow Emergent Marsh: DEM: Deep Emergent Marsh; VP: Vernal Pool; RMS: Red Maple Swamp; HTF: High Terrace Floodplain Forest

<sup>2</sup>HPF: Hardwoods/Hemlock/Pine Forest; CG-AF: Cultural Grassland-Agricultural Field; DD: Disturbed/Developed

Table 4-6: Reach 5A Riverbank –Biotic Habitat Features

Wildlife Food Cover/Perches/Basking/Denning/Nesting Habitat Rocks. **Rock Piles.** Live or Dead Standing **Small** Crevices, Tall Veg. Live or **Dense** Large **OH**<sup>+</sup> Branches Crevices, Wetland and **Upland Dead Trees** Dead Tree **Mammal** Herb Woody Logs, Roots at ≤ 1 m to Water or Hollow OH/Near Water Edge<sup>3</sup> Bank # **Aquatic Food** Food >30" DBH **Trees Cavities Burrows** Cover<sup>1</sup> Debris<sup>2</sup> Surface<sup>4</sup> Logs<sup>5</sup> Water<sup>6</sup>  $\sqrt{}$ 1 Ø Ø 2 Ø \* \* 3 Ø Ø \* \*  $\sqrt{}$ 4 Ø \* \* \* 5 6 \* 7 Ø  $\sqrt{}$  $\sqrt{}$ 8 Ø \* \* \* 9 \* 10 Ø Ø Ø  $\sqrt{}$ 11 Ø Ø Ø Ø 12  $\sqrt{}$ 13 14 Ø 15  $\sqrt{}$ \* \*  $\sqrt{}$  $\sqrt{}$ \* \* 16 \* 17 \*  $\sqrt{}$ 18 19 Ø Ø  $\sqrt{}$ 20  $\sqrt{}$ 21  $\sqrt{}$ 22 Ø Ø Ø Ø Ø 23 Ø Ø 24 \* 25  $\sqrt{}$  $\sqrt{}$  $\sqrt{}$ 26

Table 4-6: Reach 5A Riverbank –Biotic Habitat Features (continued)

Wildlife Food

Cover/Perches/Basking/Denning/Nesting Habitat

Bank #	Wetland and Aquatic Food	Upland Food	Live or Dead Trees >30" DBH	Standing Dead Trees	Tree Cavities	Small Mammal Burrows	Dense Herb Cover <sup>1</sup>	Large Woody Debris <sup>2</sup>	Rocks, Crevices, Logs, Roots at Water Edge <sup>3</sup>	OH⁺ Branches ≤ 1 m to Water Surface⁴	Rock Piles, Crevices, or Hollow Logs <sup>5</sup>	Live or Dead Tall Veg. OH/Near Water <sup>6</sup>
27	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	$\checkmark$	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	$\checkmark$	$\checkmark$	*
28	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	√	V	√	$\sqrt{}$	V	√	$\sqrt{}$	√	*
29	$\sqrt{}$	V	$\sqrt{}$	$\sqrt{}$	V	$\sqrt{}$	<b>V</b>	V	V	$\sqrt{}$	$\sqrt{}$	*
30	$\sqrt{}$	V	$\sqrt{}$	$\sqrt{}$	V	$\sqrt{}$	<b>V</b>	V	V	$\sqrt{}$	$\sqrt{}$	*
31	$\sqrt{}$	$\sqrt{}$	Ø	Ø	Ø	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$			Ø	$\sqrt{}$
32	V	√	Ø	$\sqrt{}$	V	√	√	<b>√</b>	V	V	$\sqrt{}$	$\sqrt{}$
33	√	$\sqrt{}$	√	√	$\sqrt{}$	√	*	V	√	√	√	$\sqrt{}$
34	V	V	Ø	$\sqrt{}$	$\sqrt{}$	$\checkmark$	V	$\checkmark$	V	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$

<sup>\*=</sup>Abundant; √=Present; Ø=Absent

<sup>\*</sup>OH: Overhanging

<sup>&</sup>lt;sup>1</sup>Habitat suitable for voles, small mammals, amphibians and reptiles

<sup>&</sup>lt;sup>2</sup>Habitat suitable for small mammals, mink, amphibians and reptiles

<sup>&</sup>lt;sup>3</sup>Habitat suitable for turtles, snakes, frogs

<sup>&</sup>lt;sup>4</sup>Habitat suitable for turtles, snakes, frogs, wading birds, wood duck, mink, raccoon

<sup>&</sup>lt;sup>5</sup>Habitat suitable for various mammals, e.g., otter, mink, porcupine, raccoon

<sup>&</sup>lt;sup>6</sup>Habitat offering good visibility of open water for, e.g., osprey, kingfisher, flycatchers, cedar waxwings

Table 4-7: Reach 5A Riverbank Habitat—Physical Bank Habitat Features

		Wildlife Dens/Nests					
Bank #	Underwater Banks Fine silt and/or clay <sup>1</sup>	Undercut or OH+ banks <sup>2</sup>	Vertical Sandy Banks <sup>3</sup>	Mud Flats	Exposed, Well-Drained, Sandy Areas <sup>4</sup>	Turtle Nesting Sites <sup>5</sup>	Bank Swallow Colonies
1	$\sqrt{}$	$\checkmark$	Ø	$\sqrt{}$	$\sqrt{}$	Ø	Ø
2	$\sqrt{}$	$\checkmark$	Ø	$\sqrt{}$	$\sqrt{}$	Ø	Ø
3	$\sqrt{}$	$\sqrt{}$	Ø	$\sqrt{}$	Ø	Ø	Ø
4	$\sqrt{}$	$\sqrt{}$	Ø	$\sqrt{}$	Ø	Ø	Ø
5	$\checkmark$	$\checkmark$	*	$\sqrt{}$	$\checkmark$	Ø	$\checkmark$
6	√		Ø	V	Ø	Ø	Ø
7	√	√	Ø	V	Ø	Ø	Ø
8	V	√	V	V	V	Ø	V
9	√	√	V	V	<b>V</b>	Ø	Ø
10	$\sqrt{}$	$\sqrt{}$	Ø	V	Ø	Ø	Ø
11	V	√	Ø	V	Ø	Ø	Ø
12	$\sqrt{}$	$\sqrt{}$	Ø	V	Ø	Ø	Ø
13	$\sqrt{}$	$\sqrt{}$	Ø	V	Ø	Ø	Ø
14	√	√	Ø	V	Ø	Ø	Ø
15	$\sqrt{}$	$\sqrt{}$	V	V	$\sqrt{}$	Ø	Ø
16	$\sqrt{}$	$\sqrt{}$	V	V	$\sqrt{}$	Ø	$\sqrt{}$
17	$\sqrt{}$	$\sqrt{}$	Ø	V	$\sqrt{}$	Ø	Ø
18	$\sqrt{}$	$\sqrt{}$	Ø	V	$\sqrt{}$	Ø	Ø
19	*	$\checkmark$	Ø	$\sqrt{}$	$\sqrt{}$	Ø	Ø
20	V	$\sqrt{}$	Ø	V	V	Ø	Ø
21	V	$\sqrt{}$	Ø	V	V	Ø	Ø
22	√	Ø	Ø	V	Ø	Ø	Ø
23	√		Ø	V	√	Ø	Ø
24	√	√	Ø	V	Ø	Ø	Ø
25	√	√	Ø	V	Ø	Ø	Ø
26	√	√	Ø	V	Ø	V	Ø
27	*	√	Ø	*	Ø	Ø	Ø
28	V	$\sqrt{}$	Ø	V	Ø	Ø	Ø
29		V	Ø	V	Ø	Ø	Ø
30	$\sqrt{}$	$\sqrt{}$	Ø	V		Ø	Ø
31	$\sqrt{}$	$\sqrt{}$	Ø	V		Ø	Ø
32	V	V	Ø	V	V	Ø	Ø
33	*	√	*	V	√	Ø	V
34	V	√ ·	Ø	√	Ø	Ø	Ø

<sup>+</sup>OH: Overhanging; \*=Abundant; √=Present; Ø=Absent

<sup>&</sup>lt;sup>1</sup>Features suitable for beaver, muskrat, otter

<sup>&</sup>lt;sup>2</sup>Features suitable for small mammals, mink, weasels, turtles

<sup>&</sup>lt;sup>3</sup>Features suitable for bank swallow, kingfisher

<sup>&</sup>lt;sup>4</sup>Features suitable for turtle nesting

<sup>&</sup>lt;sup>5</sup>Only applies to any actual observed turtle nesting sites, not potential nesting sites

Table 4-8: Reach 5A Riverbank Plant Species Summary Data

	Common Name	Scientific Name	Status¹	Occurrence (Number of Survey Segments N=68) <sup>2</sup>
Tree	boxelder	Acer negundo	Native	41
Species	striped maple	Acer pensylvanicum	Native	1
-	red maple	Acer rubrum	Native	1
-	silver maple	Acer saccharinum	Native	30
-	sugar maple	Acer saccharum	Native	6
-	yellow birch	Betula alleghaniensis	Native	3
-	paper birch	Betula papyrifera	Native	1
=	river birch	Betula nigra	Native	1
-	ironwood	Carpinus caroliniana	Native	7
-	northern catalpa	Catalpa speciosa	Non-native	1
-	Dotted hawthorn	Crataegus punctata	Native	3
-	American beech	Fagus grandifolia	Native	1
-	white ash	Fraxinus americana	Native	1
-	green ash	Fraxinus pennsylvanica	Native	6
-	black walnut	Juglans nigra	Non-native	3
-	American sycamore	Platanus occidentalis	Native	3
-	eastern cottonwood	Populus deltoides	Native	6
=	northern red oak	Quercus rubra	Native	2
_	black oak	Quercus velutina	Native	
-	black willow	Salix nigra	Native	1
-	American linden	Tilia americana	Native	5
-	eastern hemlock	Tsuga canadensis	Native	8
-	American elm	Ulmus americana	Native	16
Shrub	silky dogwood	Cornus amomum	Native	3
Species	red-osier dogwood	Cornus sericea	Native	21
-	burning bush	Euonymus alatus	Invasive <sup>A,B,C</sup>	1
-	European spindle-tree	Euonymus europaeus	Non-native	1
-	American witch hazel	Hamamelis virginiana	Native	2
-	border privet	Ligustrum obtusifolium	Invaisve <sup>D</sup>	2
-	Morrow's honeysuckle	Lonicera morrowii	Invasive <sup>A,B</sup>	15
-	Atlantic ninebark	Physocarpus opulifolius	Non-native	1
-	common buckthorn	Rhamnus cathartica	Invasive <sup>A,B,C</sup>	20
-	eastern black currant	Ribes americanum	Native	1
-	red raspberry	Rubus idaeus	Native	1
Vine	Asian bittersweet	Celastrus orbiculatus	Invasive <sup>A,B,C</sup>	40
Species	virgin's-bower	Clematis virginiana	Native	1
-	hedge bindweed	Convolvulus sepium	Native	 1
-	wild cucumber	Echinocystis lobata	Native	10
-	climbing bindweed	Fallopia scandens	Native	1
-	Virginia-creeper	Parthenocissus quinquefolia	Native	5
	J 2. 20P 0.			<del>-</del>

Table 4-8: Reach 5A Riverbank Plant Species Summary Data (continued)

**Occurrence** (Number of Survey **Common Name Scientific Name** Status<sup>1</sup> Segments N=68)<sup>2</sup> poison-ivy Toxicodendron radicans Native 2 Vitis riparia Native 25 river grape Herb Achillea millefolium 0 Native yarrow Species Invasive<sup>A,B</sup> 7 bishop's goutweed Aegopodium podagraria Alisma triviale Native 1 northern water-plantain Invasive<sup>A,B</sup> Alliaria petiolata 1 garlic-mustard Ambrosia artemisiifolia Native 1 common ragweed 2 swamp milkweed Asclepias incarnata Native nodding beggar-ticks Bidens cernua Native 33 purple-stemmed beggar-ticks Bidens connata Native 1 Bidens frondosa Native 8 Devil's beggar-ticks 1 small-spiked false-nettle Boehmeria cylindrica Native black mustard Non-native 8 Brassica nigra 1 lurid sedge Carex Iurida Native awl-fruited sedge Carex stipata Native 1 1 tussock sedge Carex stricta Native white turtlehead Chelone glabra Native 2 water hemlock Cicuta bulbifera Native 1 1 wood-reed grass Cinna arundinacea Native Native 1 red-root flatsedge Cyperus erythrorhizos 2 Native umbrella sedge Cyperus strigosus crested wood fern Native 1 Dryopteris cristata 1 spike rush Eleocharis sp Native eastern willow-herb Epilobium coloratum Native 3 field horsetail Equisetum arvense Native 1 7 spotted Joe-Pye weed Eupatorium maculatum Native Invasive<sup>A,B,C</sup> Japanese knotweed 33 Fallopia japonica 1 American burnweed Erechtites hieraciifolius Native Geranium maculatum Native 0 spotted crane's-bill Glechoma hederacea Invasive<sup>B</sup> 0 Gill-over-the-ground Native 1 American manna grass Glyceria grandis Invasive<sup>A,B,C</sup> dame's-rocket Hesperis matronalis 1 jewelweed Impatiens capensis Native 6 Invasive<sup>A,B</sup> yellow iris Iris pseudacorus 6 1 common soft rush Juncus effusus Native 1 Canada wood nettle Laportea canadensis Native Native Leersia oryzoides 6 rice cut-grass lance-leaved tiger-lily Lilium lancifolium Non-native 1 yellow-seeded false pimpernel Lindernia dubia Native 3 common water-purslane Ludwigia palustris Native 18

Table 4-8: Reach 5A Riverbank Plant Species Summary Data (continued)

**Occurrence** (Number of Survey **Scientific Name** Status<sup>1</sup> Segments N=68)<sup>2</sup> **Common Name** Virginia water-horehound Lycopus virginicus Native Lythrum salicaria Invasive<sup>A,B,C</sup> 8 purple loosestrife ostrich fern Matteuccia struthiopteris Native 21 American wild mint Mentha canadensis Native 1 Allegheny monkeyflower Mimulus ringens Native 9 Invasive<sup>A,B,C</sup> 1 Eurasian water-milfoil Myriophyllum spicatum Invasive<sup>D</sup> water forget-me-not Myosotis scorpioides 12 1 giant chickweed Myosoton aquaticum Non-native common evening primrose Oenothera biennis Native 1 sensitive fern Onoclea sensibilis Native 8 cinnamon fern Osmunda cinnamomea Native 2 2 ditch-stonecrop Penthorum sedoides Native water-pepper smartweed Persicaria hydropiper Native 8 2 Persicaria hydropiperoides Native false water-pepper smartweed 38 pale smartweed Persicaria lapathifolia Native Persicaria maculosa Native 2 lady's-thumb smartweed arrow-leaved tearthumb Persicaria sagittata Native 1 Persicaria virginiana Native 4 jumpseed reed canary grass Phalaris arundinacea Invasive<sup>A,B,C</sup> 3 Canada clearweed Pilea pumila Native 9 Pontederia cordata Native 1 pickerelweed Invasive<sup>A,B</sup> 0 curly pondweed Potamogeton crispus creeping yellow-cress Rorippa sylvestris Non-native 1 green-headed coneflower Rudbeckia laciniata Native 13 Non-native curly dock Rumex crispus 1 common arrowhead Sagittaria latifolia Native 1 Saponaria officinalis Non-native 1 common soapwort Native dark-green bulrush Scirpus atrovirens 1 American bur-reed Sparganium americanum Native 10 giant bur-reed Sparganium eurycarpum Native 0 lance-leaved American aster Symphyotrichum lanceolatum 1 Native 1 small white aster Symphyotrichum racemosum Native marsh fern Thelypteris palustris Native 1 stinging nettle Urtica dioica Native 6 common mullein Verbascum thapsus Native 1 22 blue vervain Verbena hastata Native American speedwell Veronica americana Native 4 rough cocklebur Xanthium strumarium Non-native 8

<sup>&</sup>lt;sup>1</sup>Invasive Ratings: A= MIPAG Invasive; B=IPANE Invasive; C=ACOE Invasive; D=MIPAG Likely Invasive

<sup>&</sup>lt;sup>2</sup>Data are from 34 riverbank stations in Reach 5A, with surveys of both left and right banks tabulated separately for total number of observation points of 68.

Table 4-9: Reach 5A Riverbank Plant Community Inventory – Left Bank

Bank	Total	OH+	Riparian	OH Tree	OH Shrub	OH Vine	<b>OH Moss</b>	OH Herb
Station	% Cover	% Cover	% Cover	% Cover	% Cover	% Cover	% Cover	% Cover
1	50	75	100	50	60	30	0	40
2	75	50	90	30	30	25	0	75
3	75	20	100	25	50	25	0	75
4	60	70	90	50	40	60	0	50
5	90	75	100	60	50	50	0	50
6	60	60	90	75	75	50	0	25
7	70	60	90	75	50	25	0	25
8	75	50	100	50	30	20	0	50
9	80	30	90	20	50	30	0	70
10	70	10	90	10	50	25	0	80
11	80	60	80	20	60	25	0	75
12	80	60	70	70	80	30	0	30
13	90	80	100	50	50	30	0	90
14	70	100	100	20	80	60	0	50
15	80	70	100	80	60	50	0	40
16	60	90	100	80	40	20	0	70
17	80	80	100	70	70	50	0	20
18	70	80	100	30	50	30	0	70
19	60	10	100	10	10	10	0	60
20	90	80	90	0	75	40	0	20
21	60	50	80	50	30	20	0	80
22	80	10	70	0	80	10	0	80
23	60	70	100	70	20	0	0	10
24	70	80	90	80	40	50	0	10
25	75	50	90	50	70	40	0	70
26	50	80	100	80	10	10	0	10
27	90	75	80	90	50	70	0	0
28	90	70	75	20	60	30	0	70
29	75	50	80	10	0	0	0	90
30	80	60	80	30	30	10	0	60
31	80	30	80	20	40	20	0	70
32	60	80	60	40	60	30	0	60
33	60	20	90	10	30	20	0	60
34	80	30	90	20	50	30	0	70

+OH: Overhanging

Table 4-10: Reach 5A Riverbank Plant Community Inventory – Right Bank

Bank#	Total % Cover	OH⁺ % Cover	Riparian % Cover	OH Tree % Cover	OH Shrub % Cover	OH Vine % Cover	OH Moss % Cover	OH Herb % Cover
1	75	50	100	50	40	30	0	75
2	30	70	100	50	40	30	0	30
3	50	80	90	60	40	30	0	25
4	60	70	90	50	40	50	0	50
5	80	50	100	60	40	30	0	75
6	75	75	100	50	25	25	0	75
7	80	40	90	60	50	30	0	75
8	60	50	100	40	60	20	0	20
9	80	60	100	40	40	10	0	70
10	90	80	100	70	75	30	0	50
11	75	60	70	60	50	20	0	25
12	80	50	80	30	60	30	0	70
13	30	100	100	50	70	75	0	10
14	100	80	100	10	10	10	0	90
15	90	75	100	50	10	10	0	70
16	90	80	100	60	30	10	0	80
17	90	75	100	30	0	0	0	90
18	100	25	100	20	20	20	0	90
19	100	10	100	10	10	10	0	90
20	80	60	80	60	20	20	0	60
21	70	50	90	80	50	50	0	10
22	80	30	100	10	10	10	0	80
23	80	60	90	70	70	30	0	50
24	70	60	100	40	50	30	0	70
25	80	60	100	50	60	40	0	60
26	80	50	90	50	40	0	0	60
27	75	60	90	10	20	10	0	90
28	80	60	100	60	40	20	0	30
29	80	60	100	30	70	20	0	70
30	80	60	90	80	10	10	0	80
31	80	80	90	20	70	20	0	40
32	50	30	80	30	70	70	0	10
33	90	25	90	20	50	30	0	70
34	70	60	90	40	70	30	0	70

<sup>+</sup>OH: Overhanging

Table 4-11: Reach 5A Riverbank Plant Community Inventory – Riparian Vegetation Cover

Bank Station         % Cover         % Cover         % Cover         % Cover         % Cover           1         60         70         30         3         75           2         50         70         30         3         75           3         50         70         30         3         75           4         70         70         30         3         75           5         40         70         30         3         75           6         70         70         30         3         75           7         70         70         25         0         75           8         75         75         30         0         60           9         75         60         25         3         75           10         65         70         30         0         70           11         10         20         10         0         80           12         60         60         20         0         70           13         75         85         35         0         70           14         75         85         35 </th <th></th> <th>Tree</th> <th>Shrub</th> <th>Vine</th> <th>Moss</th> <th>Herb</th>		Tree	Shrub	Vine	Moss	Herb
2         50         70         30         3         75           3         50         70         30         3         75           4         70         70         30         3         55           5         40         70         30         0         75           6         70         70         30         3         75           7         70         70         25         0         75           8         75         75         30         0         60           9         75         60         25         3         75           10         65         70         30         0         70           11         10         20         10         0         80           12         60         60         20         0         70           13         75         80         30         5         75           14         75         85         35         0         70           15         80         80         30         0         60           16         50         60         20         0	Bank Station	% Cover	% Cover	% Cover		% Cover
3         50         70         30         3         75           4         70         70         30         3         55           5         40         70         30         0         75           6         70         70         30         3         75           7         70         70         25         0         75           8         75         75         30         0         60           9         75         60         25         3         75           10         65         70         30         0         70           11         10         20         10         0         80           12         60         60         20         0         70           13         75         85         35         0         70           14         75         85         35         0         70           15         80         80         30         0         60           16         50         60         20         0         90           17         80         70         30         0 <td< td=""><td>-</td><td>60</td><td>70</td><td>30</td><td>3</td><td>75</td></td<>	-	60	70	30	3	75
4         70         70         30         3         55           5         40         70         30         0         75           6         70         70         30         3         75           7         70         70         25         0         75           8         75         75         30         0         60           9         75         60         25         3         75           10         65         70         30         0         70           11         10         20         10         0         80           12         60         60         20         0         70           13         75         85         35         0         70           13         75         80         30         5         75           14         75         85         35         0         70           15         80         80         30         0         60           16         50         60         20         0         90           17         80         70         30         0 <t< td=""><td>2</td><td>50</td><td>70</td><td>30</td><td>3</td><td>75</td></t<>	2	50	70	30	3	75
5         40         70         30         0         75           6         70         70         30         3         75           7         70         70         25         0         75           8         75         75         30         0         60           9         75         60         25         3         75           10         65         70         30         0         70           11         10         20         10         0         80           12         60         60         20         0         70           13         75         80         30         5         75           14         75         85         35         0         70           15         80         80         30         0         60           16         50         60         20         0         90           17         80         70         30         0         60           18         60         80         20         0         75           19         40         70         25         0         <	3	50	70	30	3	75
6         70         70         30         3         75           7         70         70         25         0         75           8         75         75         30         0         60           9         75         60         25         3         75           10         65         70         30         0         70           11         10         20         10         0         80           12         60         60         20         0         70           13         75         80         30         5         75           14         75         85         35         0         70           15         80         80         30         0         60           16         50         60         20         0         90           17         80         70         30         0         60           18         60         80         20         0         75           19         40         70         25         0         80           20         50         75         20         0	4	70	70	30	3	55
7         70         70         25         0         75           8         75         75         30         0         60           9         75         60         25         3         75           10         65         70         30         0         70           11         10         20         10         0         80           12         60         60         20         0         70           13         75         80         30         5         75           14         75         85         35         0         70           15         80         80         30         0         60           16         50         60         20         0         90           17         80         70         30         0         60           18         60         80         20         0         75           19         40         70         25         0         80           20         50         75         20         0         90           21         70         60         20         0	5	40	70	30	0	75
8         75         75         30         0         60           9         75         60         25         3         75           10         65         70         30         0         70           11         10         20         10         0         80           12         60         60         20         0         70           13         75         80         30         5         75           14         75         85         35         0         70           15         80         80         30         0         60           16         50         60         20         0         90           17         80         70         30         0         60           18         60         80         20         0         75           19         40         70         25         0         80           20         50         75         20         0         90           21         70         60         20         0         40           22         10         80         10         0	6	70	70	30	3	75
9         75         60         25         3         75           10         65         70         30         0         70           11         10         20         10         0         80           12         60         60         20         0         70           13         75         80         30         5         75           14         75         85         35         0         70           15         80         80         30         0         60           16         50         60         20         0         90           17         80         70         30         0         60           18         60         80         20         0         75           19         40         70         25         0         80           20         50         75         20         0         90           21         70         60         20         0         40           22         10         80         10         0         80           23         80         60         20         0	7	70	70	25	0	75
10         65         70         30         0         70           11         10         20         10         0         80           12         60         60         20         0         70           13         75         80         30         5         75           14         75         85         35         0         70           15         80         80         30         0         60           16         50         60         20         0         90           17         80         70         30         0         60           18         60         80         20         0         75           19         40         70         25         0         80           20         50         75         20         0         90           21         70         60         20         0         40           22         10         80         10         0         80           23         80         60         20         0         60           24         70         60         30         0	8	75	75	30	0	60
11         10         20         10         0         80           12         60         60         20         0         70           13         75         80         30         5         75           14         75         85         35         0         70           15         80         80         30         0         60           16         50         60         20         0         90           17         80         70         30         0         60           18         60         80         20         0         75           19         40         70         25         0         80           20         50         75         20         0         90           21         70         60         20         0         40           22         10         80         10         0         80           23         80         60         20         0         60           24         70         60         30         0         60           25         80         60         30         0	9	75	60	25	3	75
12         60         60         20         0         70           13         75         80         30         5         75           14         75         85         35         0         70           15         80         80         30         0         60           16         50         60         20         0         90           17         80         70         30         0         60           18         60         80         20         0         75           19         40         70         25         0         80           20         50         75         20         0         90           21         70         60         20         0         40           22         10         80         10         0         80           23         80         60         20         0         60           24         70         60         30         0         60           25         80         60         30         0         50           26         70         40         10         0	10	65	70	30	0	70
13         75         80         30         5         75           14         75         85         35         0         70           15         80         80         30         0         60           16         50         60         20         0         90           17         80         70         30         0         60           18         60         80         20         0         75           19         40         70         25         0         80           20         50         75         20         0         90           21         70         60         20         0         40           22         10         80         10         0         80           23         80         60         20         0         60           24         70         60         30         0         60           25         80         60         30         0         50           26         70         40         10         0         50           27         70         60         20         0	11	10	20	10	0	80
14       75       85       35       0       70         15       80       80       30       0       60         16       50       60       20       0       90         17       80       70       30       0       60         18       60       80       20       0       75         19       40       70       25       0       80         20       50       75       20       0       90         21       70       60       20       0       40         22       10       80       10       0       80         23       80       60       20       0       60         24       70       60       30       0       60         25       80       60       30       0       50         26       70       40       10       0       50         26       70       40       10       0       50         27       70       60       20       0       60         28       50       50       25       0       60 <td< td=""><td>12</td><td>60</td><td>60</td><td>20</td><td>0</td><td>70</td></td<>	12	60	60	20	0	70
15       80       80       30       0       60         16       50       60       20       0       90         17       80       70       30       0       60         18       60       80       20       0       75         19       40       70       25       0       80         20       50       75       20       0       90         21       70       60       20       0       40         22       10       80       10       0       80         23       80       60       20       0       60         24       70       60       30       0       60         25       80       60       30       0       50         26       70       40       10       0       50         27       70       60       20       0       60         28       50       50       25       0       60         29       70       75       25       0       70         30       40       70       30       0       60 <td< td=""><td>13</td><td>75</td><td>80</td><td>30</td><td>5</td><td>75</td></td<>	13	75	80	30	5	75
16         50         60         20         0         90           17         80         70         30         0         60           18         60         80         20         0         75           19         40         70         25         0         80           20         50         75         20         0         90           21         70         60         20         0         40           22         10         80         10         0         80           23         80         60         20         0         60           24         70         60         30         0         60           25         80         60         30         0         50           26         70         40         10         0         50           27         70         60         20         0         60           28         50         50         25         0         60           28         50         50         25         0         60           29         70         75         25         0	14	75	85	35	0	70
17       80       70       30       0       60         18       60       80       20       0       75         19       40       70       25       0       80         20       50       75       20       0       90         21       70       60       20       0       40         22       10       80       10       0       80         23       80       60       20       0       60         24       70       60       30       0       60         25       80       60       30       0       50         26       70       40       10       0       50         27       70       60       20       0       60         28       50       50       25       0       60         29       70       75       25       0       70         30       40       70       30       0       60         31       40       60       30       0       70         32       40       60       20       0       60 <td< td=""><td>15</td><td>80</td><td>80</td><td>30</td><td>0</td><td>60</td></td<>	15	80	80	30	0	60
18       60       80       20       0       75         19       40       70       25       0       80         20       50       75       20       0       90         21       70       60       20       0       40         22       10       80       10       0       80         23       80       60       20       0       60         24       70       60       30       0       60         25       80       60       30       0       50         26       70       40       10       0       50         27       70       60       20       0       60         28       50       50       25       0       60         29       70       75       25       0       70         30       40       70       30       0       60         31       40       60       30       0       70         32       40       60       20       0       60         33       50       50       50       30       0       80	16	50	60	20	0	90
19       40       70       25       0       80         20       50       75       20       0       90         21       70       60       20       0       40         22       10       80       10       0       80         23       80       60       20       0       60         24       70       60       30       0       60         25       80       60       30       0       50         26       70       40       10       0       50         27       70       60       20       0       60         28       50       50       25       0       60         29       70       75       25       0       70         30       40       70       30       0       60         31       40       60       30       0       60         32       40       60       20       0       60         33       50       50       30       0       80	17	80	70	30	0	60
20         50         75         20         0         90           21         70         60         20         0         40           22         10         80         10         0         80           23         80         60         20         0         60           24         70         60         30         0         60           25         80         60         30         0         50           26         70         40         10         0         50           27         70         60         20         0         60           28         50         50         25         0         60           29         70         75         25         0         70           30         40         70         30         0         60           31         40         60         30         0         70           32         40         60         20         0         60           33         50         50         30         0         80	18	60	80	20	0	75
21         70         60         20         0         40           22         10         80         10         0         80           23         80         60         20         0         60           24         70         60         30         0         60           25         80         60         30         0         50           26         70         40         10         0         50           27         70         60         20         0         60           28         50         50         25         0         60           29         70         75         25         0         70           30         40         70         30         0         60           31         40         60         30         0         70           32         40         60         20         0         60           33         50         50         30         0         80	19	40	70	25	0	80
22       10       80       10       0       80         23       80       60       20       0       60         24       70       60       30       0       60         25       80       60       30       0       50         26       70       40       10       0       50         27       70       60       20       0       60         28       50       50       25       0       60         29       70       75       25       0       70         30       40       70       30       0       60         31       40       60       30       0       70         32       40       60       20       0       60         33       50       50       30       0       80	20	50	75	20	0	90
23       80       60       20       0       60         24       70       60       30       0       60         25       80       60       30       0       50         26       70       40       10       0       50         27       70       60       20       0       60         28       50       50       25       0       60         29       70       75       25       0       70         30       40       70       30       0       60         31       40       60       30       0       70         32       40       60       20       0       60         33       50       50       30       0       80	21	70	60	20	0	40
24       70       60       30       0       60         25       80       60       30       0       50         26       70       40       10       0       50         27       70       60       20       0       60         28       50       50       25       0       60         29       70       75       25       0       70         30       40       70       30       0       60         31       40       60       30       0       70         32       40       60       20       0       60         33       50       50       30       0       80	22	10	80	10	0	80
25       80       60       30       0       50         26       70       40       10       0       50         27       70       60       20       0       60         28       50       50       25       0       60         29       70       75       25       0       70         30       40       70       30       0       60         31       40       60       30       0       70         32       40       60       20       0       60         33       50       50       30       0       80	23	80	60	20	0	60
26       70       40       10       0       50         27       70       60       20       0       60         28       50       50       25       0       60         29       70       75       25       0       70         30       40       70       30       0       60         31       40       60       30       0       70         32       40       60       20       0       60         33       50       50       30       0       80	24	70	60	30	0	60
27     70     60     20     0     60       28     50     50     25     0     60       29     70     75     25     0     70       30     40     70     30     0     60       31     40     60     30     0     70       32     40     60     20     0     60       33     50     50     30     0     80	25	80	60	30	0	50
28     50     50     25     0     60       29     70     75     25     0     70       30     40     70     30     0     60       31     40     60     30     0     70       32     40     60     20     0     60       33     50     50     30     0     80	26	70	40	10	0	50
29     70     75     25     0     70       30     40     70     30     0     60       31     40     60     30     0     70       32     40     60     20     0     60       33     50     50     30     0     80	27	70	60	20	0	60
30     40     70     30     0     60       31     40     60     30     0     70       32     40     60     20     0     60       33     50     50     30     0     80	28	50	50	25	0	60
31     40     60     30     0     70       32     40     60     20     0     60       33     50     50     30     0     80	29	70	75	25	0	70
32     40     60     20     0     60       33     50     50     30     0     80	30	40	70	30	0	60
33 50 50 30 0 80	31	40	60	30	0	70
	32	40	60	20	0	60
34 30 50 30 0 60	33	50	50	30	0	80
	34	30	50	30	0	60

Table 4-12: Reach 5A Riverbanks: Other Wildlife Habitat Features\*

Habitat Feature         Wildlife Use         Abundant         Present         Absent           Imp. Wetland/Aquatic Food Plants         Overall food         0         97         3           Imp. Upland Food Plants         Overall food         0         100         0           Trees (live or dead) >30" DBH         Cover/perching/nesting         0         85         15           Standing Dead Trees         Cavities/perching/nesting         0         88         12           Small Mammal Burrows         Nesting/escape/cover         0         100         0           Small Mammal Burrows         Nesting/escape/cover         0         100         0           Dense Herbaceous Cover         Voles, small mammals, amphibians, reptiles         18         79         3           Large Woody Debris on Ground         Small mammals, amphibians, reptiles         26         71         3           Large Woody Debris on Ground         Turtles, snakes, frogs, among protective emergence         26         71         3           Rocks, Crevices. Logs, Tree Roots, or Hummocks Under or at Water's Edge         Turtles, snakes, frogs, wading pirds, wood duck, mink, raccoon         6         91         3           Rock Piles, Crevices, Hollow         Mammals: otter, mink, praccoon         3         73         24			% of Stations	% of Stations	% of Stations
Plants         Imp. Upland Food Plants         Overall food         0         100         0           Trees (live or dead) >30" DBH         Cover/perching/nesting         0         74         26           Standing Dead Trees         Cavities/perching/nesting         0         85         15           Tree Cavities in Trunks or Limbs         Cavities/perching/nesting         0         88         12           Small Mammal Burrows         Nesting/escape/cover         0         100         0           Dense Herbaceous Cover         Voles, small mammals, amphibians, reptiles         18         79         3           Large Woody Debris on Ground Pobris on Ground Smith Image and phides, invertebrate emergence         Small mammals, amphibians, reptiles         26         71         3           Rocks, Crevices. Logs, Tree Roots, or Hummocks Under or at Water's Edge         Turtles, snakes, frogs, wading birds, wood duck, mink, raccoon         6         91         3           OH Branches ≤ 1M above Water Logs         Turtles, snakes, frogs, wading birds, wood duck, mink, raccoon         6         91         3           Live or Dead Tall Standing Veg. OH or Near Water Offering Visibility         Perching (Osprey Kingfisher, Flycatchers, Cedar Waxwings)         0         68         32           Undercut or OH Banks         Small mammals (Mink, Weasels), Turtles	Habitat Feature	Wildlife Use	Abundant	Present	Absent
Trees (live or dead) >30" DBH     Cover/perching/nesting     0     74     26       Standing Dead Trees     Cavities/perching/nesting     0     85     15       Tree Cavities in Trunks or Limbs     Cavities/perching/nesting     0     88     12       Small Mammal Burrows     Nesting/escape/cover     0     100     0       Dense Herbaceous Cover     Voles, small mammals, amphibians, reptiles     18     79     3       Large Woody Debris on Ground     Small mammals, amphibians, reptiles     26     71     3       Rocks, Crevices. Logs, Tree Roots, or Hummocks Under or at Water's Edge     Turtles, snakes, frogs, invertebrate emergence     26     71     3       OH Branches ≤ 1M above Water Water Sedge     Turtles, snakes, frogs, wading birds, wood duck, mink, raccoon     6     91     3       Rock Piles, Crevices, Hollow Live or Dead Tall Standing Veg. OH or Near Water Offering Visibility     Perching (Osprey Kingfisher, Flycatchers, Cedar Waxwings)     0     68     32       Undercut or OH Banks     Small mammals (Mink, Weasels), Turtles     9     91     0       Undercut or OH Banks     Small mammals (Mink, Weasels), Turtles     0     97     3       Vertical Sandy Banks     Nesting bank swallows and kingfishers; Turtles     6     12     83       Wettal Sandy Banks     Peeding sites for birds, small mammals, herps		Overall food	0	97	3
Standing Dead Trees       Cavities/perching/nesting       0       85       15         Tree Cavities in Trunks or Limbs       Cavities/perching/nesting       0       88       12         Small Mammal Burrows       Nesting/escape/cover       0       100       0         Dense Herbaceous Cover       Voles, small mammals, amphibians, reptiles       18       79       3         Large Woody Debris on Ground       Small mammals, amphibians, reptiles       26       71       3         Rocks, Crevices. Logs, Tree Roots, or Hummocks Under or at Water's Edge       Turtles, snakes, frogs, invertebrate emergence       26       71       3         OH Branches ≤ 1M above Water Water's Edge       Turtles, snakes, frogs, wading birds, wood duck, mink, raccoon       6       91       3         Rock Piles, Crevices, Hollow Logs       Mammals: otter, mink, porcupine, raccoon       3       73       24         Live or Dead Tall Standing Veg. OH or Near Water Offering Visibility       Perching (Osprey Kingfisher, Flycatchers, Cedar Waxwings)       0       68       32         Undercut or OH Banks       Small mammals (Mink, Weasels), Turtles       9       91       0         Vertical Sandy Banks       Nesting bank swallows and kingfishers; Turtles       6       12       83         Wet start the start particles       Feeding sites for	Imp. Upland Food Plants	Overall food	0	100	0
Tree Cavities in Trunks or Limbs       Cavities/perching/nesting       0       88       12         Small Mammal Burrows       Nesting/escape/cover       0       100       0         Dense Herbaceous Cover       Voles, small mammals, amphibians, reptiles       18       79       3         Large Woody Debris on Ground       Small mammals, amphibians, reptiles       26       71       3         Rocks, Crevices. Logs, Tree Roots, or Hummocks Under or at Water's Edge       Turtles, snakes, frogs, rogs, invertebrate emergence       26       71       3         OH Branches ≤ 1M above Water Vater's Edge       Turtles, snakes, frogs, wading birds, wood duck, mink, raccoon       6       91       3         Rock Piles, Crevices, Hollow Logs       Mammals: otter, mink, porcupine, raccoon       3       73       24         Live or Dead Tall Standing Veg. OH or Near Water Offering Visibility       Perching (Osprey Kingfisher, Flycatchers, Cedar Waxwings)       0       68       32         Undercut or OH Banks       Small mammals (Mink, Weasels), Turtles       9       91       0         Vertical Sandy Banks       Nesting bank swallows and kingfishers; Turtles       6       12       83         Mud Flats       Feeding sites for birds, small mammals, herps       3       97       0         Exposed well drained soil       Turtle	Trees (live or dead) >30" DBH	Cover/perching/nesting	0	74	26
Small Mammal Burrows       Nesting/escape/cover       0       100       0         Dense Herbaceous Cover       Voles, small mammals, amphibians, reptiles       18       79       3         Large Woody Debris on Ground       Small mammals, amphibians, reptiles       26       71       3         Rocks, Crevices. Logs, Tree       Turtles, snakes, frogs, snakes, frogs, snakes, frogs, wading birds, wood duck, mink, raccoon       26       71       3         Roots, or Hummocks Under or at Water's Edge       Turtles, snakes, frogs, wading birds, wood duck, mink, raccoon       6       91       3         Rock Piles, Crevices, Hollow Logs       Mammals: otter, mink, porcupine, raccoon       3       73       24         Live or Dead Tall Standing Veg. OH or Near Water Offering Visibility       Perching (Osprey Kingfisher, Flycatchers, Cedar Waxwings)       0       68       32         Underwater Banks of Fine Silt and/or Clay       Beaver, Muskrat, Otter       9       91       0         Undercut or OH Banks       Small mammals (Mink, Weasels), Turtles       0       97       3         Vertical Sandy Banks       Nesting bank swallows and kingfishers; Turtles       6       12       83         Mud Flats       Feeding sites for birds, small mammals, herps       3       97       0         Exposed well drained soil       Tur	Standing Dead Trees	Cavities/perching/nesting	0	85	15
Dense Herbaceous Cover       Voles, small mammals, amphibians, reptiles       18       79       3         Large Woody Debris on Ground       Small mammals, amphibians, reptiles       26       71       3         Rocks, Crevices. Logs, Tree Roots, or Hummocks Under or at Water's Edge       Turtles, snakes, frogs, invertebrate emergence       26       71       3         OH Branches ≤1M above Water Water's Edge       Turtles, snakes, frogs, wading birds, wood duck, mink, raccoon       6       91       3         Rock Piles, Crevices, Hollow Logs       Mammals: otter, mink, porcupine, raccoon       3       73       24         Live or Dead Tall Standing Veg. OH or Near Water Offering Visibility       Perching (Osprey Kingfisher, Plycatchers, Cedar Waxwings)       0       68       32         Underwater Banks of Fine Silt and/or Clay       Beaver, Muskrat, Otter       9       91       0         Undercut or OH Banks       Small mammals (Mink, Weasels), Turtles       0       97       3         Vertical Sandy Banks       Nesting bank swallows and kingfishers; Turtles       6       12       83         Mud Flats       Feeding sites for birds, small mammals, herps       3       97       0         Exposed well drained soil       Turtle nesting       0       3       97	Tree Cavities in Trunks or Limbs	Cavities/perching/nesting	0	88	12
Large Woody Debris on Ground Large Woody Debris on Ground Provided BranchesSmall mammals, amphibians, reptiles, invertebrate emergence26713Rocks, Crevices. Logs, Tree Roots, or Hummocks Under or at Water's EdgeTurtles, snakes, frogs, invertebrate emergence26713OH Branches ≤1M above Water Water's EdgeTurtles, snakes, frogs, wading birds, wood duck, mink, raccoon6913Rock Piles, Crevices, Hollow LogsMammals: otter, mink, porcupine, raccoon37324Live or Dead Tall Standing Veg. OH or Near Water Offering VisibilityPerching (Osprey Kingfisher, Flycatchers, Cedar Waxwings)06832Underwater Banks of Fine Silt and/or ClayBeaver, Muskrat, Otter9910Undercut or OH BanksSmall mammals (Mink, Weasels), Turtles0973Vertical Sandy BanksNesting bank swallows and kingfishers; Turtles61283Mud FlatsFeeding sites for birds, small mammals, herps3970Exposed well drained soilTurtle nesting05050Turtle nesting sites observedTurtle nesting0397	Small Mammal Burrows	Nesting/escape/cover	0	100	0
Rocks, Crevices. Logs, Tree Roots, or Hummocks Under or at Water's Edge  OH Branches ≤1M above Water Clive or Dead Tall Standing Veg. OH or Near Water Offering Visibility  Undercut or OH Banks  Vertical Sandy Banks  Nesting bank swallows and kingfishers; Turtles  Nesting bank swallows and kingfishers; Turtles  Exposed well drained soil  Turtle nesting sites observed  Turtles, snakes, frogs, wading invertebrate emergence  Turtles, snakes, frogs, wading obirds, wood duck, mink, raccoon  Turtles, snakes, frogs, wading obirds, wading obirds, wood duck, mink, raccoon  Turtles, snakes, frogs, wading obirds, snakes, frogs, wading obirds, wading obirds, wading obirds, wading obirds, wading obirds, snakes, frogs, wading obirds, snakes, frogs, wading obirds, snakes, frogs, wading objects  Turtle nesting sites observed  Turtle nesting  Zef Turtles, snakes, frogs, wading obirds, snakes, frogs, wading objects  Purtles, snakes, frogs, wading objects  Purtles, snakes, frogs, wading objects  And Sef Turtle nesting objects  Sef Turtle nesting objects  Turtle nes	Dense Herbaceous Cover		18	79	3
Roots, or Hummocks Under or at Water's Edgeinvertebrate emergenceOH Branches ≤1M above Water Water's EdgeTurtles, snakes, frogs, wading birds, wood duck, mink, raccoon6913Rock Piles, Crevices, Hollow LogsMammals: otter, mink, porcupine, raccoon37324Live or Dead Tall Standing Veg. OH or Near Water Offering VisibilityPerching (Osprey Kingfisher, Flycatchers, Cedar Waxwings)06832Underwater Banks of Fine Silt and/or ClayBeaver, Muskrat, Otter9910Undercut or OH BanksSmall mammals (Mink, Weasels), Turtles0973Vertical Sandy BanksNesting bank swallows and kingfishers; Turtles61283Mud FlatsFeeding sites for birds, small mammals, herps3970Exposed well drained soilTurtle nesting05050Turtle nesting sites observedTurtle nesting0397	Large Woody Debris on Ground		26	71	3
Birds, wood duck, mink, raccoon  Rock Piles, Crevices, Hollow Logs  Live or Dead Tall Standing Veg. OH or Near Water Offering Visibility  Underwater Banks of Fine Silt and/or Clay  Undercut or OH Banks  Vertical Sandy Banks  Nesting bank swallows and kingfishers; Turtles  Mud Flats  Exposed well drained soil  Nammals: otter, mink, and and and a porcupine, raccoon  Perching (Osprey Kingfisher, and a porcupine, raccoon)  Perching (Osprey Kingfisher, and a porcupine, raccoon)  Perching (Osprey Kingfisher, and a porcupine, raccoon)  Beaver, Muskrat, Otter  9 91 0  97 3  Weasels), Turtles  Nesting bank swallows and	Roots, or Hummocks Under or at		26	71	3
Logsporcupine, raccoonLive or Dead Tall Standing Veg. OH or Near Water Offering VisibilityPerching (Osprey Kingfisher, Flycatchers, Cedar Waxwings)06832Underwater Banks of Fine Silt and/or ClayBeaver, Muskrat, Otter9910Undercut or OH BanksSmall mammals (Mink, Weasels), Turtles0973Vertical Sandy BanksNesting bank swallows and kingfishers; Turtles61283Mud FlatsFeeding sites for birds, small mammals, herps3970Exposed well drained soilTurtle nesting05050Turtle nesting sites observedTurtle nesting0397	OH Branches ≤ 1M above Water		6	91	3
OH or Near Water Offering Visibility  Underwater Banks of Fine Silt and/or Clay  Undercut or OH Banks  Vertical Sandy Banks  Mud Flats  Feeding sites for birds, small mammals, herps  Exposed well drained soil  Flycatchers, Cedar Waxwings)  Flycatchers, Cedar Waxwings)  Beaver, Muskrat, Otter  9 91 0  97 3  Weasels), Turtles  Nesting bank swallows and 6 12 83  kingfishers; Turtles  Feeding sites for birds, small 3 97 0  mammals, herps  Exposed well drained soil  Turtle nesting  0 50 50  Turtle nesting sites observed	_		3	73	24
Undercut or OH Banks Small mammals (Mink, Weasels), Turtles  Vertical Sandy Banks Nesting bank swallows and kingfishers; Turtles  Mud Flats Feeding sites for birds, small mammals, herps  Exposed well drained soil Turtle nesting Turtle nesting 0 3 97 0 50 7 10 11 12 12 13 13 15 15 16 17 18 18 18 18 18 18 18 18 18 18 18 18 18	OH or Near Water Offering		0	68	32
Weasels), TurtlesVertical Sandy BanksNesting bank swallows and kingfishers; Turtles61283Mud FlatsFeeding sites for birds, small mammals, herps3970Exposed well drained soilTurtle nesting05050Turtle nesting sites observedTurtle nesting0397		Beaver, Muskrat, Otter	9	91	0
kingfishers; TurtlesMud FlatsFeeding sites for birds, small mammals, herps3970Exposed well drained soilTurtle nesting05050Turtle nesting sites observedTurtle nesting0397	Undercut or OH Banks		0	97	3
mammals, herps  Exposed well drained soil Turtle nesting 0 50 50  Turtle nesting sites observed Turtle nesting 0 3 97	Vertical Sandy Banks		6	12	83
Turtle nesting sites observed Turtle nesting 0 3 97	Mud Flats		3	97	0
·	Exposed well drained soil	Turtle nesting	0	50	50
Bank Swallow colony observed Bank swallow nesting 0 12 88	Turtle nesting sites observed	Turtle nesting	0	3	97
	Bank Swallow colony observed	Bank swallow nesting	0	12	88

<sup>\*</sup>Data summarized from 34 riverbank stations ranging from 100-400 feet in length (8,300 lf in total)

Table 4-13: Incidental Direct Wildlife Observations at Bank Survey Stations

Bank Station	Incidental Direct Wildlife Observations
1	Catbird, Cardinal, Raccoon Tracks
2	Catbird; Great blue heron; Raccoon tracks; Spotted sandpiper; Song sparrow; Green frog; Dragonflies
3	Green frog; Raccoon tracks; Spotted sandpiper
4	
5	Kingfisher; Deer tracks; Raccoon tracks; Spotted sandpiper; Song sparrow; Green frog; Wood pewee
6	Great blue heron; Deer tracks; Raccoon tracks; Spotted sandpiper; Mussels (Elliptio or Eastern Lampmussel; Green frog; Dragonflies
7	Green frogs; Raccoon tracks
8	Green heron; Spotted sandpiper; Mallards; Catbird; Cardinal; Tennessee warbler; Green frogs
9	Raccoon tracks; Catbird
10	
11	
12	Spotted sandpiper
13	Deer; Green heron; Kingfisher; Painted turtle
14	Mallards; Deer; Catbird; Painted turtle
15	Green heron; Black-capped chickadee; Wood pewee
16	Kingfisher; Red-bellied woodpecker; Crow; Raccoon tracks; Deer tracks; Painted turtle
17	Kingfisher
18	Canada geese; Great blue heron; Painted turtle; Titmouse; Goldfinch;
19	
20	Kingfisher; Wood pewee; Phoebe; Painted turtle
21	
22	Spotted sandpiper; Red-tailed hawk; Green frog; Raccoon tracks; Deer
23	Kingfisher; Veery
24	
25	Dragonflies; Phoebe; Great crested flycatcher; Titmouse
26	Great blue heron; Red tail hawk; Redstart; Pheobe; Painted turtle
27	Creek chub
28	
29	
30	Spotted sandpiper
31	Spotted sandpiper; Canada geese
32	Deer tracks; Raccoon tracks; Goldfinch
33	Painted turtle; Bull frog; Green frog; Song sparrow; Robin; Catbird; Veery; Bank swallow nesting cavities
34	Spotted sandpiper

Table 4-14: Reach 5A Riverbank – MNHESP Rare Species and Core Area Habitat Designation<sup>1</sup>

<b>Bank Station</b>	MNHESP Core Area	State-Listed Species Habitat <sup>2</sup>		
1	Core Area 1	American Bittern, Brook Snaketail, Matted Spike-sedge, Ocellated Darner, Riffle Snaketail, Spine-crowned		
	Core Area 2	Clubtail, Wapato, Wood Turtle		
2	Core Area 1	American Bittern, Brook Snaketail, Matted Spike-sedge, Ocellated Darner, Riffle Snaketail, Spine-crowned		
	Core Area 2	Clubtail, Wapato, Wood Turtle		
3	Core Area 2	American Bittern, Brook Snaketail, Matted Spike-sedge, Ocellated Darner, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle		
4	Core Area 2	American Bittern, Brook Snaketail, Matted Spike-sedge, Ocellated Darner, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle		
5	Core Area 2	American Bittern, Brook Snaketail, Matted Spike-sedge, Ocellated Darner, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle		
6	Core Area 2	Brook Snaketail, Matted Spike-sedge, Ocellated Darner, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle		
7	Core Area 2	Brook Snaketail, Matted Spike-sedge, Ocellated Darner, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle		
8	Core Area 2	Brook Snaketail, Matted Spike-sedge, Ocellated Darner, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle		
9		Brook Snaketail, Matted Spike-sedge, Ocellated Darner, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle		
10		Brook Snaketail, Matted Spike-sedge, Ocellated Darner, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle		
11		Brook Snaketail, Matted Spike-sedge, Ocellated Darner, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle		
12		Brook Snaketail, Matted Spike-sedge, Ocellated Darner, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle		
13	Core Area 2	Brook Snaketail, Matted Spike-sedge, Mustard White, Ocellated Darner, Ostrich Fern Borer Moth, Riffle		
	Core Area 3	Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle		
14	Core Area 2	Bristly Buttercup; Brook Snaketail, Matted Spike-sedge, Mustard White, Ocellated Darner, Ostrich Fern Borer		
	Core Area 3	Moth, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle		
15	Core Area 2	American Bittern, Bristly Buttercup; Brook Snaketail, Matted Spike-sedge, Mustard White, Ocellated Darner,		
	Core Area 3	Ostrich Fern Borer Moth, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle		
16	Core Area 1; Core Area 2; Core Area 3	American Bittern, Bristly Buttercup; Brook Snaketail, Matted Spike-sedge, Mustard White, Ocellated Darner, Ostrich Fern Borer Moth, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle		

Table 4-14: Reach 5A Riverbank – MNHESP Rare Species and Core Area Habitat Designation<sup>1</sup> (continued)

Bank Station	MNHESP Core Area	State-Listed Species Habitat <sup>2</sup>
17	Core Area 1; Core Area 2; Core Area 3	American Bittern, Bristly Buttercup; Brook Snaketail, Matted Spike-sedge, Mustard White, Ocellated Darner, Ostrich Fern Borer Moth, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle
18	Core Area 1; Core Area 2; Core Area 3	American Bittern, Brook Snaketail, Frank's Lovegrass, Matted Spike-sedge, Mustard White, Ocellated Darner, Ostrich Fern Borer Moth, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle
19	Core Area 1; Core Area 2; Core Area 3	American Bittern, Brook Snaketail, Frank's Lovegrass, Hairy Wild Rye; Matted Spike-sedge, Mustard White, Ocellated Darner, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle
20	Core Area 2 Core Area 3	Brook Snaketail, Frank's Lovegrass, Hairy Wild Rye, Matted Spike-sedge, Mustard White, Ocellated Darner, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle
21	Core Area 2 Core Area 3	Brook Snaketail, Frank's Lovegrass, Hairy Wild Rye, Matted Spike-sedge, Mustard White, Ocellated Darner, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle
22	Core Area 2; Core Area 3; Core Area 4	Brook Snaketail, Frank's Lovegrass, Hairy Wild Rye, Matted Spike-sedge, Mustard White, Ocellated Darner, Spine-crowned Clubtail, Wapato, Wood Turtle
23	Core Area 2 Core Area 3	Brook Snaketail, Frank's Lovegrass, Hairy Wild Rye, Matted Spike-sedge, Mustard White, Ocellated Darner, Spine-crowned Clubtail, Wapato, Wood Turtle
24	Core Area 2 Core Area 3	Brook Snaketail, Frank's Lovegrass, Hairy Wild Rye, Matted Spike-sedge, Mustard White, Ocellated Darner, Rapids Clubtail, Spine-crowned Clubtail, Wapato, Wood Turtle
25	Core 3	Brook Snaketail, Frank's Lovegrass, Hairy Wild Rye, Matted Spike-sedge, Mustard White, Ocellated Darner, Rapids Clubtail, Spine-crowned Clubtail, Wapato, Wood Turtle
26		Brook Snaketail, Frank's Lovegrass, Hairy Wild Rye, Matted Spike-sedge, Mustard White, Rapids Clubtail, Spine-crowned Clubtail, Wapato, Wood Turtle
27		Brook Snaketail, Frank's Lovegrass, Matted Spike-sedge, Mustard White, Rapids Clubtail, Spine-crowned Clubtail, Wapato, Wood Turtle
28		Brook Snaketail, Frank's Lovegrass, Matted Spike-sedge, Mustard White, Ocellated Darner, Rapids Clubtail, Spine-crowned Clubtail, Wapato, Wood Turtle
29		Brook Snaketail, Frank's Lovegrass, Matted Spike-sedge, Mustard White, Ocellated Darner, Rapids Clubtail, Spine-crowned Clubtail, Wapato, Wood Turtle
30		Brook Snaketail, Frank's Lovegrass, Matted Spike-sedge, Mustard White, Ocellated Darner, Rapids Clubtail, Spine-crowned Clubtail, Wapato, Wood Turtle
31		Brook Snaketail, Frank's Lovegrass, Matted Spike-sedge, Mustard White, Rapids Clubtail, Spine-crowned Clubtail, Wapato, Wood Turtle
32		Brook Snaketail, Frank's Lovegrass, Matted Spike-sedge, Mustard White, Rapids Clubtail, Spine-crowned Clubtail, Wapato, Wood Turtle

Table 4-14: Reach 5A Riverbank – MNHESP Rare Species and Core Area Habitat Designation<sup>1</sup> (continued)

<b>Bank Station</b>	MNHESP Core Area	State-Listed Species Habitat <sup>2</sup>
33		Brook Snaketail, Frank's Lovegrass, Matted Spike-sedge, Mustard White, Rapids Clubtail, Spine-crowned Clubtail, Wapato, Wood Turtle
34		Frank's Lovegrass, Matted Spike-sedge, Mustard White, Rapids Clubtail; Spine-crowned Clubtail, Wapato, Wood Turtle

<sup>&</sup>lt;sup>1</sup>Core Habitat Areas as designated by MNHESP, July 2012

<sup>&</sup>lt;sup>2</sup>State-Listed Species habitats as mapped by MNHESP, provided October 2022

Table 4-15: Reach 5A Riverbank Function Assessment Factors

Functional Category	Description of Functions	Parameters/Factors Considered in Assessing Function (see Table 4-1)
Hydrology/hydraulic	Water conveyance and transport; floodwater dynamics (flood flow distribution, flood storage and desynchronization, peak rate control)	Bank height; bank vegetation; bank stability/migration; floodplain connectivity
Geomorphology	Supply of organic and mineral sediment material; supply/processing of woody debris; effects on flow and role in determining stream planform and geomorphic diversity	Bank stability; substrate composition; large woody debris supply; bank stability/migration; bank vegetation
Physicochemical	Water quality maintenance; temperature and oxygen regulation for in-stream habitat	Vegetation (bank, overhanging, riparian); bank stability/migration
Biological	Biodiversity and sustaining aquatic and riparian life; migration and dispersal corridor; river access; rare species habitat	Bank stability/migration; vegetation (on-bank, overhanging, and riparian); large woody debris; general wildlife habitat; presence of unique habitat features; rare species habitat (mapped Priority Habitat and Core Area habitat and IPaC results); floodplain connectivity; invasive species; incidental wildlife observations

**Table 4-16: Reach 5A Riverbank Restoration Opportunities** 

<b>Bank Station</b>	Potential Restoration Resources Present
1	Coarse woody debris; Cobbles
2	Coarse woody debris
3	Coarse woody debris; Large trees; Root wads
4	Coarse woody debris; Cobbles
5	Coarse woody debris; Large trees; Root wads
6	Coarse woody debris; Large trees; Cobbles
7	Coarse woody debris; Large trees: Cobbles
8	Coarse woody debris; Large trees; Cobble
9	Coarse woody debris; Root wads; Large trees; Cobbles
10	Coarse woody debris; Large trees; Cobbles
11	Coarse woody debris; Large trees; Cobbles
12	Coarse woody debris; Large trees; Cobbles; Boulders
13	Coarse woody debris; Large trees; Cobbles
14	Coarse woody debris; Large trees; Cobbles
15	Coarse woody debris; Large trees; Root wads; Cobbles
16	Coarse woody debris; Large trees; Root wads; Cobbles; Boulders
17	Coarse woody debris; Root wads; Boulders; Cobbles
18	Coarse woody debris; Large trees Root wads; Cobbles
19	Coarse woody debris; Large trees; Cobbles
20	Coarse woody debris; Cobbles
21	Coarse woody debris; Large trees; Root wads; Cobbles; Boulders
22	Coarse woody debris; Cobbles
23	Coarse woody debris; Large trees; Root wads; Cobbles
24	Coarse woody; Large trees; Root wads; Cobbles; Boulders
25	Coarse woody debris; Large trees; Root wads; Boulders
26	Coarse woody debris; Large trees; Root wads; Cobbles
27	Coarse woody debris; Large trees; Root wads; Cobbles
28	Coarse woody debris; Large trees; Root wads; Cobbles
29	Coarse woody debris; Large trees; Cobbles
30	Coarse woody debris; Large trees; Root wads; Cobbles
31	Coarse woody debris; Large trees; Cobbles
32	Coarse woody debris, Large trees; Root wads; Cobbles
33	Coarse woody debris; Large trees; Root wads; Cobbles
34	Coarse woody debris; Large trees; Root wads

Table 5-1: Reach 5A Backwater Habitat Characterization

Parameter	Description of Parameter	Reach 5A Inventory Approach*
Mapping and classification	Mapping of physical location and limits	Updated LiDAR and bathymetric mapping
Physical dimensions	Length, width, area, depth, and volume	Updated LiDAR and bathymetric mapping; 2022 field surveys using Form BW-1
Hydrology and connectivity to river	Flow dynamics; depth; water level fluctuation; mean low water; mean high water; hydrologic connection with river; other surface water inputs	Consolidate existing information (from sources below); 2022 field surveys using Form BW-1
Sediment composition	Relative % clay/silt/sand/gravel/cobble; boulder/bedrock; organic matter	Consolidate existing information (from sources below); 2022 field surveys using Form BW-1
Aquatic plant community	Species composition and relative abundance; rare species habitat; invasive species	Consolidate existing information (from sources below); 2022 field surveys using Form BW-1
Bordering habitat types	Species composition and relative abundance; rare species habitat; standing dead timber	2022 field surveys using Form BW-1; rare species habitat from MNHESP investigations/designations and IPaC results
Large woody debris (LWD)	Size, relative abundance and density of LWD above and below water	Consolidate existing information (from sources below); 2022 field surveys using Form BW-1
Water quality	Temperature, pH, TSS, turbidity, clarity, dissolved oxygen	Consolidate existing information (from sources below); collection of basic water quality data with field meter during field surveys
Habitat for aquatic and other water-using biota	Species composition and relative abundance of aquatic macrophytes, fish, benthic habitat/organisms, and other water-using biota	Consolidate existing information (from sources below); 2022 field surveys using Form BW-1; incidental wildlife observations
Rare species habitat	Priority Habitat/Core Area Habitat mapping; IPaC results from USFWS on-line data base	MNHESP investigations and designations (including updated outreach to MNHESP); IPaC results; 2022 field surveys using Form BW-1
Invasive species	Presence/relative abundance of invasive plant and animal species	Review of invasive plant species lists from USACE New England District and MIPAG and invasive aquatic animal species guidance from MassDCR and USGS; consolidate existing information (from sources below); 2022 field surveys using Form BW-1
Presence of special habitat features	Tree cavities; beaver/muskrat dens; otter slides	Consolidate existing information (from sources below); 2022 field surveys using Form BW-1

<sup>\*</sup> The existing information used for the Reach 5A backwater habitat characterization includes information from the following sources: the 2002 Woodlot Ecological Characterization, the 2003 RFI Report, the 2010 Example Area evaluations and RCMS Report, the MNHESP investigations of state-listed species through 2012, and the 2019 Final Accessibility Report – all described and referenced in Section 2 of the Reach 5A BRA Work Plan.

Table 5-2: Reach 5A Backwater Plant Species Summary Data

Layer	Common Name	Scientific Name	Status <sup>1</sup>	Backwaters Where Identified	Total Occurrences
Tree Species	Boxelder maple	Acer negundo	Native	BW3, BW4	2
·	Red maple	Acer rubrum	Native	BW5	1
	Silver maple	Acer saccharinum	Native	BW1, BW3, BW4, BW5, BW6	5
	American sycamore	Platanus occidentalis	Native	BW3	1
Shrub Species	Silky dogwood	Cornus amomum	Native	BW1, BW3	2
Woody Vine Species	River grape	Vitis riparia	Native	BW3	1
Herbs, forbs,	Sweetflag	Acorus calamus	Native	BW5	1
grasses and aquatic plants	Northern water-plantain	Alisma triviale	Native	BW3, BW4	2
aquatio piarito	Swamp milkweed	Asclepias incarnata	Native	BW2	1
	Nodding beggar-ticks	Bidens cernua	Native	BW1, BW2, BW3, BW4, BW5, BW6	6
	Devil's beggar-tick	Bidens frondosa	Native	BW2, BW4, BW5	3
	Small-spiked false nettle	Boehmeria cylindrica	Native	BW1, BW2, BW3	3
	Wild calla	Calla palustris	Native	BW6	1
	Water-starwort	Callitriche palustris	Native	BW2, BW3, BW4	3
	Hop sedge	Carex lupulina	Native	BW2	1
	Spotted water-hemlock	Cicuta maculata	Native	BW4	1
	Common dodder	Cuscuta gronovii	Native	BW2, BW3, BW4	3
	Needle spikesedge	Eleocharis acicularis	Native	BW2	1
	Spikerush	Eleocharis sp.	Native	BW6	1
	Willow-herb	Epilobium coloratum	Native	BW3, BW4	2
	Spotted joe-pye weed	Eutrochium maculatum	Native	BW2	1
	Marsh bedstraw	Galium palustre	Native	BW1, BW2, BW3	3
	Jewelweed	Impatiens capensis	Native	BW3, BW4, BW5	3
	Pale jewelweed	Impatiens pallida	Native	BW5	1
	Yellow iris	Iris pseudacorus	Invasive <sup>A,B</sup>	BW2, BW3, BW4	3
	Canada wood nettle	Laportea canadensis	Native	BW1, BW3	2

Table 5-2: Reach 5A Backwater Plant Species Summary Data (continued)

Layer	Common Name	Scientific Name	Status <sup>1</sup>	Backwaters Where Identified	Total Occurrences
	Rice cut-grass	Leersia oryzoides	Native	BW1, BW2, BW3, BW4, BW5, BW6	6
	False pimpernel	Lindernia dubia	Native	BW6	1
	Common water-primrose	Ludwigia palustris	Native	BW2	1
	Northern water-horehound	Lycopus uniflorus	Native	BW1, BW4	2
	Moneywort	Lysimachia nummularia	Invasive <sup>A</sup>	BW1, BW2	2
	Purple loosestrife	Lythrum salicaria	Invasive <sup>ABC</sup>	BW2, BW3, BW6	3
	Wild mint	Mentha canadensis	Native	BW3, BW4	2
	Monkey-flower	Mimulus ringens	Native	BW2, BW4	2
	Water forget-me-not	Myosotis scorpioides	Invasive <sup>D</sup>	BW2, BW3, BW4	3
	Eurasian water-milfoil	Myriophyllum spicatum	Invasive <sup>ABC</sup>	BW2	1
	Yellow pond-lily	Nuphar variegata	Native	BW1	1
	Sensitive fern	Onoclea sensibilis	Native	BW1, BW2, BW5	3
	Ditch-stonecrop	Penthorum sedoides	Native	BW2, BW3	2
	False water-pepper	Persicaria hydropiperoides	Native	BW3, BW4	2
	Dock-leaved smartweed	Persicaria lapathifolia	Native	BW3, BW6	2
	Dotted Smartweed	Persicaria punctata	Native	BW1, BW3, BW5, BW6	4
	Arrow-leaved tearthumb	Persicaria sagittata	Native	BW1, BW2, BW4	3
	Reed canary grass	Phalaris arundinacea	Invasive <sup>ABC</sup>	BW3, BW5	2
	Obedient false dragonhead	Physostegia virginiana	Non-native	BW2	1
	Pickerelweed	Pontederia cordata	Native	BW1	1
	Green-headed coneflower	Rudbeckia laciniata	Native	BW2, BW3, BW4	3
	Common arrowhead	Sagittaria latifolia	Native	BW2, BW5, BW6	3
	Woolgrass	Scirpus cyperinus	Native	BW1	1
	Water parsnip	Sium suave	Native	BW3, BW5	2
	p F	<del>-</del>		- / = · · · <del>·</del>	_

Table 5-2: Reach 5A Backwater Plant Species Summary Data (continued)

Layer	Common Name	Scientific Name	Status¹	Backwaters Where Identified	Total Occurrences
	American bur-reed	Sparganium americanum	Native	BW1	1
	Water-chestnut	Trapa natans	Invasive <sup>ABC</sup>	BW1	1
	Stinging nettle	Urtica dioica	Native	BW6	1
	Blue vervain	Verbena hastata	Native	BW2, BW4	2
	Water speedwell	Veronica catenata	Native	BW2, BW4, BW6	3

<sup>&</sup>lt;sup>1</sup>Invasive Ratings: A= MIPAG Invasive; B=IPANE Invasive; C=ACOE Invasive; D=MIPAG Likely Invasive

Table 5-3: Reach 5A Backwaters –Biotic Habitat Features

Wildlife Food<sup>1</sup>

Cover/Perches/Basking/Denning/Nesting Habitat<sup>1</sup>

Backwater ID	Wetland and Aquatic Food	Live or Dead Trees >30" DBH	Standing dead trees with cavities and perches	Cavities in trunks or limbs of Live Trees	Small mammal burrows on banks	Dense herb cover on banks	Large woody debris in contact with water	Rocks, crevices, logs, roots, hummocks under water surface	Rock, crevices, logs, branches, hummocks at or within 1 m above water	Live or Dead Tall Veg over/nea r water	Flat rocks or logs on banks or in exposed areas of backwater	Underwater banks of fine silt and/or clay	Undercut or overhanging banks	Mud flats	Vertical Sandy Banks	Open sandy to gravelly soils with sparse vegetation	Emergent wetlands
BW-1	$\sqrt{}$	$\checkmark$	$\sqrt{}$	$\sqrt{}$	$\checkmark$	*	$\checkmark$	$\sqrt{}$	$\checkmark$	$\checkmark$	$\checkmark$	$\checkmark$	$\sqrt{}$	$\sqrt{}$	Ø	Ø	V
BW-2	$\sqrt{}$	Ø	Ø	$\sqrt{}$	$\checkmark$	*	$\checkmark$	$\checkmark$	$\checkmark$	$\checkmark$	$\checkmark$	Ø	$\sqrt{}$	$\checkmark$	Ø	Ø	$\checkmark$
BW-3	*	$\checkmark$	$\sqrt{}$	$\sqrt{}$	Ø	*	$\sqrt{}$	$\sqrt{}$	$\checkmark$	<b>V</b>	$\checkmark$	Ø	$\sqrt{}$	√	Ø	Ø	
BW-4	$\sqrt{}$	$\checkmark$	$\sqrt{}$	$\sqrt{}$	Ø	*	$\sqrt{}$	$\sqrt{}$	$\checkmark$	<b>V</b>	$\checkmark$	Ø	$\sqrt{}$	√	Ø	Ø	
BW-5	√	√	√	√	V	*	*	√	√	√	<b>√</b>	√	√	√	Ø	Ø	√
BW-6	*	√	√	√	Ø	*	V	V	√	<b>V</b>	V	Ø	√	√	Ø	Ø	√

<sup>&</sup>lt;sup>1</sup>See Table 5-4 for wildlife associations with listed habitat features

Table 5-4: Reach 5A Backwaters: Summary of Biotic Habitat Features (N=6)

Habitat Feature	Wildlife Use	% of Stations Abundant	% of Stations Present	% of Stations Absent
Wetland and Aquatic Food	Overall food	33	67	0
Live or Dead Trees >30" DBH	Cover/perching/nesting	0	83	17
Standing dead trees with cavities and perches	Cavities/perching/breeding/nesting/feeding	0	83	17
Cavities in trunks or limbs of Live Trees	Cavities/perching/breeding/nesting	0	100	0
Small mammal burrows on banks	Hibernation/breeding/nesting/escape/cover	0	50	50
Dense herb cover on banks	Voles, small mammals, amphibians, reptiles	100	0	0
Large woody debris in contact with water	Small mammals, amphibians, reptiles, invertebrate emergence	17	83	0
Rocks, crevices, logs, roots, hummocks under water surface	Turtles, snakes, frogs, invertebrate emergence	0	100	0
Rock, crevices, logs, branches, hummocks at or within 1 m above water	Turtles, snakes, frogs, wading birds, wood duck, mink, raccoon	0	100	0
Live or Dead Tall Veg over/near water	Habitat offering good visibility of open water for, e.g., osprey, kingfisher, flycatchers, cedar waxwings. Vegetation closer to ground for turtles, snakes, frogs, wading birds, wood duck, mink, raccoon	0	100	0
Flat rocks or logs on banks or in exposed areas of backwater	Cover and basking for herpetofauna	0	100	0
Underwater banks of fine silt and/or clay	Beaver, muskrat, otter	0	33	67
Undercut or overhanging banks	Small mammals, mink, weasels, turtles	0	100	0
Mud flats	Feeding sites for birds, small mammals, herps	0	100	0
Vertical Sandy Banks	Nesting bank swallows and kingfishers; Turtles	0	0	100
Open sandy to gravelly soils with sparse vegetation	Turtle nesting habitat	0	0	100
Emergent wetlands	Habitat for common snipe, spotted sandpiper, sedge wren, least bittern, common moorhen (Flooded > 5cm) and pied-billed grebe (Flooded > 25cm)	0	100	0

Table 5-5: State-Listed Rare Species Potentially Associated with Backwater Habitats of Reach 5A

Scientific Name	<b>Common Name</b>	State Status
Botaurus lentiginosus	American Bittern	Endangered
Ophiogomphus aspersus	Brook Snaketail	Special Concern
Gallinula galeata	Common Gallinule	Special Concern
Eleocharis intermedia	Matted Spike-Sedge	Threatened
Boyeria grafiana	Ocellated Darner	Special Concern
Papaipema sp. 2	Ostrich Fern Borer	Special Concern
Phanogomphus quadricolor	Rapids Clubtail	Endangered
Ophiogomphus carolus	Riffle Snaketail	Threatened
Hylogomphus abbreviatus	Spine-Crowned Clubtail	Endangered
Sagittaria cuneata	Wapato	Threatened
Glyptemys insculpta	Wood Turtle	Special Concern

Table 5-6: Reach 5A Backwater Function Assessment Factors

Functional Category	Description of Functions	Parameters/Factors Considered in Assessing Function (see Table 5-1)		
Hydrology/hydraulic	Floodwater dynamics (flood flow amelioration, flood storage and desynchronization, peak rate control)	Physical dimensions; hydrology and connectivity to river		
Geomorphology	Deposition and storage of organic and mineral sediment material	Hydrology and connectivity to river; sediment composition; aquatic plant community; large woody debris; aquatic biota		
Physicochemical	Water quality maintenance; temperature and oxygen regulation; processing of organic matter and nutrients	Hydrology and connectivity to river; water quality; aquatic plant community; aquatic biota habitat		
Biological	Biodiversity and sustaining life stages of fish and other aquatic biota; habitat for aquatic and other water-using biota; rare species habitat	Hydrology and connectivity to river; aquatic plant community; bordering habitat types; large woody debris; water quality; habitat for aquatic and other water-using biota; rare species habitat (mapped Priority Habitat and Core Area habitat and IPaC results); invasive plant and animal species; presence of special habitat features; incidental wildlife observations		

Table 5-7: Water Chemistry of Backwater Habitats of Reach 5A

Dissolved Oxygen

					Oxygen		<del>-</del>
Date	Sample Location ID	рН	Temperature °C	Specific Conductivity	%	mg/l	Chlorophyll-a mg/l
			BW	R5A-1			
	1	7.63	20.7	458.3	105	9.44	3
5/9/2023	2	7.5	20.3	477	89.4	7.93	1
	3	7.51	19.1	487.8	87	7.88	1
	1	7.53	17.9	514	129.7	12.27	1
6/6/2023	2	7.71	18.	504	137	12.94	0.7
	3	7.81	18.8	513	145.9	13.55	1
	1	7.64	15.4	618	99.4	9.85	0.6
6/14/2023	2	7.72	15.7	518	106.4	10.55	1.2
	3	7.91	15.5	522	120.6	11.98	2
Total	Average	7.66	17.9	512.5	113.4	10.71	1.3
			BW	R5A-2			
	1	7.72	11.6	432.8	134	14.62	1
5/9/2023	2	7.3	11.1	404	74.3	8.15	1.8
	3	8.28	16	413.3	158.6	15.46	1
	1	7.32	14.8	561	67.2	6.78	1.6
6/6/2023	2	7.4	12.1	476.5	96.9	10.4	4.7
	3	7.55	16.8	431.3	71.8	6.95	2.5
	1	7.47	14.8	499	81.2	8.25	1.5
6/14/2023	2	7.24	12.8	509	79.4	8.32	1.9
	3	7.5	19	449	60	5.53	2
Total Average		7.53	14.3	464.0	91.5	9.38	2.0

Table 5-7: Water Chemistry of Backwater Habitats of Reach 5A (continued)

**Dissolved** Oxygen Sample **Temperature Specific** Chlorophyll-a **Location ID** Conductivity % **Date** pН °C mg/l mg/l **BW R5A-3** 1 7.23 22.4 393.5 74.5 6.47 1 5/9/2023 2 7.32 19.6 381.2 77.6 7.04 1 3 7.38 17.5 412.9 8.13 86.9 1 1 439.1 80.1 6.99 7.19 22 1.9 2 469.2 1.5 6/6/2023 7.47 19.9 10.2 112.1 7.34 456.6 8.75 3 19.4 92.5 1 1 21.9 524 4.45 7.21 51 1.6 6/14/2023 9.3 2 7.6 19.5 482.7 101.8 1 3 7.81 19.6 465 10.6 1.1 116.6 **Total Average** 20.2 447.1 1.2 7.39 88.1 7.99 **BW R5A-4** 7.48 17.4 470.7 6.84 0.5 1 73.3 5/9/2023 7.38 18 482.4 58.6 5.48 0.5 2 7.48 17 7.04 0.5 3 492.4 73.6 1 7.85 17.9 449.4 11.5 1 119.8 6/6/2023 2 7.53 17.8 471.7 97.3 9.24 1 3 7.72 18.3 457 7.8 1.3 83.2 7.72 18.3 457 83.2 7.8 1.3 1 6/14/2023 2 17.5 148.7 14.17 2.2 8.29 423.7 3 7.8 1.7 17.4 462 88 8.41 **Total Average** 7.69 462.9 17.7 91.7 8.70 1.1

Table 5-7: Water Chemistry of Backwater Habitats of Reach 5A (continued)

**Dissolved** Oxygen Sample **Temperature** Sp Chlorophyll-a Location ID °C Conductivity % **Date** рΗ mg/l mg/l **BW R5A-5** 1 7.61 17.8 585 98.4 9.24 4 5/9/2023 2 7.47 17.0 572 84.8 8.09 2 3 7.36 19.1 603 79.7 7.34 2 1 7.74 20.5 676 107.5 9.33 2.5 6/6/2023 2 7.45 17.6 694 72.9 7.23 6 3 7.49 18.7 709 9.36 2.2 100.5 1 7.88 19.3 672 94.6 8.6 3.6 6/14/2023 2 7.66 6.7 2.3 18.3 686 71.8 3 7.48 18.5 694 60.9 5.67 1.2 **Total Average** 7.57 18.5 654.6 85.7 7.95 2.9 **BW R5A-6** 1 8.01 18.4 478.2 193.4 15.07 40 5/9/2023 2 7.53 25.1 477.8 94.6 7.56 4 3 7.46 25.1 472.7 83.2 6.86 3 **Total Average** 7.67 15.7 22.9 476.2 123.7 9.83

Table 6-1: Reach 5A Wetland Community Types\*

Community Type	Description
Wet Meadow	Herbaceous emergent wetlands that are periodically disturbed by mowing or grazing or possibly sustained by hydrologic factors.
Shallow Emergent Marsh	Herb-dominated wetland community with saturated soils or inundated at some locations. Vegetation diverse, but lacking robust, grass-like herbs characteristic of deep emergent marshes.
Deep Emergent Marsh	Herb-dominated wetland community that often remains inundated with water through the growing season. Dominated by robust graminoids grass-like plants or aquatic, broad-leaved herbs.
Shrub Swamp	Hydric shrublands lacking a closed canopy.
Red Maple Swamp	Hydric forests dominated by red maple.
Transitional Floodplain Forest	Riparian forests dominated by silver maple, box-elder, and American elm.
High-terrace Floodplain Forest	Riparian forests with a mixture of trees from wetter sites (e.g., silver maple, American elm) and trees from rich, upland sites (e.g., sugar maple, white ash, basswood). Herb layer with characteristic species of high-nutrient forests.
Black ash-red maple-tamarack calcareous seepage swamp	Hydric forests dominated by red maple, black ash, and bur oak. Occur in high pH groundwater discharge areas.
Moderately alkaline lake/pond	Ponds located in the central valley region with calcareous bedrock underneath.

<sup>\*</sup> Adapted From Woodlot (2002a) Ecological Characterization

Table 6-2: Reach 5A Upland Community Types\*

Community Type	Description
Successional Northern Hardwood Forests	Early successional forests growing on formerly disturbed sites (fire, silvicultural, agricultural) well drained upland mineral soils. Dominant plants include quaking aspen, white pine, white birch, gray birch, and black birch in the canopy with willows, goldenrods, clovers beneath.
Red Oak-Sugar Maple Transition Forest	Upland forest with well drained upland mineral soils. Species are transitional between southern and northern types and include red oak, white ash, sugar maple, American beech, eastern hemlock, black birch in the canopy with maple-leaved viburnum, witch hazel, Christmas fern, and wild sarsaparilla beneath.
Northern Hardwoods–Hemlock–White Pine Forest	Upland forest with well drained upland mineral soils. Plant species are a mixture of broad-leaved and needle-leaved trees including red oak, eastern hemlock, white pine, and sugar maple. Other species may include hobblebush, striped maple, Christmas fern, Canada mayflower, bracken fern, princess-pine, and partridge berry.
Cultural Grasslands	Includes open, upland fields dominated by grass-like herbs that are periodically disturbed (mowed) but may include sparse and stunted shrubs in unmanaged areas. Typical vegetation includes reed fescue, Timothy, Kentucky blue-grass, poverty grass, little bluestem, goldenrods, common milkweed, wild carrot, common evening primrose, spreading dogbane, common flat-topped goldenrod, and spotted knapweed. Shrubs may include willows, dogwoods, staghorn sumac, buckthorn. Upland mineral Soils are well drained.

<sup>\*</sup> Adapted From Woodlot (2002a) Ecological Characterization

Table 6-3: Comparison of natural community cover types mapped between 2002 and 2023

Natural Community / Cover Type	Woodlot 2002 (Acres) <sup>1</sup>	Natural Community / Cover Type	AECOM 2023 (Acres) <sup>2</sup>
Moderately alkaline lake/pond	14.3	Moderately alkaline lake/pond	8.5
Low gradient stream	35.4	Chrom	40.2
Medium-gradient stream	8.3	Stream	48.3
Wet meadow	14.7	Wet meadow	22.4
Shallow emergent marsh	23.2	Shallow emergent marsh	46.2
Deep emergent marsh	15.6	Deep emergent marsh	12.6
Shrub swamp	54.8	Shrub swamp	64.0
Red maple swamp	47.8	Red maple swamp	8.9
Transitional floodplain forest	121.8	Transitional floodplain forest	143.8
High-terrace floodplain forest	9.8	High-terrace floodplain forest	10.3
Successional northern hardwoods	4.1	Successional Northern Hardwoods	3.7
Red oak-sugar maple transition forest	2.2	Red oak-sugar maple transition forest	2.6
Northern hardwoods-hemlock-white pine forest	9.1	Northern hardwoods-hemlock-white pine forest	7.4
Agricultural Field	18.3	Agricultural Field	4.4
Cultural grasslands	25.4	Cultural grasslands	26.1
Riverine pointbar and beach	0.8	Riverine pointbar and beach	0.0
Developed / Disturbed	0.0	Developed / Disturbed	0.6
SUM:	405.5	SUM:	409.8

<sup>1.</sup> Natural community mapping based on Woodlot 2002 ecological characterization.

<sup>2.</sup> Natural community mapping based on AECOM 2022-2023 field surveys, and interpretation of available aerial photography and LiDAR data.

Table 6-4: Reach 5A Floodplain Wetland Habitat Characterization

Parameter	<b>Description of Parameter</b>	Reach 5A Inventory Approach*					
Mapping and classification; watershed setting/factors	Mapping of physical location and limits; natural community cover type classification and delineation; wetlandwatershed relationships (position in watershed; size of wetland relative to watershed; watershed factors)	Woodlot 2002 Ecological Characterization mapping and classification in Reach 5A (updated during 2018-2019 morphology surveys); aerial photograph interpretation and updated LiDAR mapping; 2022 field surveys to confirm mapping and obtain data for Form FP-1					
Hydrogeologic setting	Surficial geology	USGS surficial geology information; U.S. Department of Agriculture (USDA) Natural Resource Conservation Service (NRCS) soil survey mapping					
Hydrology	Degree of surface flooding; connectivity to river or other surface water flow; water regime (mean water level, fluctuation/maximum water depth to lowest water level). Evidence of groundwater discharge (springs/seeps, etc.)	Consolidate existing information (from sources below); Federal Emergency Management Agency Flood (FEMA) Flood Insurance Study (FIS); 2022 field surveys to obtain data for Form FP-1					
Soil composition and characteristics	Soil profile description; soils series as mapped by the USDA NRCS	Consolidate existing information (from sources below); 2022 field surveys to obtain data for Form FP-1					
Plant community	Plant species by community type	Consolidate existing information (from sources below); 2022 field surveys to obtain data for Form FP-1					
Overall wildlife habitat/use	Wildlife use; habitat suitability; surrounding land uses; corridor connectivity	Consolidate existing information (from sources below); 2022 field surveys to obtain data for Form FP-1					
Special habitat features	Wolf trees; standing dead timber; tree cavities; large woody debris; turtle hibernacula or nesting sites	Consolidate existing information (from sources below); 2022 field surveys to obtain data for Form FP-1					
Rare species habitat	Priority Habitat/Core Area Habitat mapping; IPaC results from USFWS on-line data base	MNHESP investigations and designations (including updated outreach to MNHESP); IPaC results; 2022 field surveys to confirm mapping and obtain data for Form FP-1					
Invasive species	Invasive plant species as designated by ACOE New England District or MIPAG	Review of invasive plant species lists from USACE New England District and MIPAG; consolidate existing information (from sources below); 2022 field surveys to map invasive species and obtain data for Form FP-1					

<sup>\*</sup> The existing information used for the Reach 5A floodplain wetland habitat characterization includes information from the following sources: the 2002 Woodlot Ecological Characterization reports, the 2003 RFI Report, the 2010 example area evaluations and RCMS Report, the MNHESP investigations of state-listed species through 2012, the Reach 5A vernal pool investigations; and the Final Accessibility Report – all described and referenced in Section 2 of the Reach 5A BRA Work Plan – as well as the USDA NRCS soil surveys, USGS surficial geology mapping, and FEMA FIS.

Table 6-5: Reach 5A Floodplain Wetland Plant Species Summary Data

(Number of **Plots** Layer **Common Name** Scientific Name Status<sup>1</sup> N=202)Tree Boxelder maple Acer negundo Native 65 **Species** Invasive<sup>A,B</sup> Acer platanoides 2 Norway maple Native 24 Red maple Acer rubrum 47 Silver maple Acer saccharinum Native Acer saccharum Native 10 Sugar maple Yellow birch Betula alleghaniensis Native 3 3 Sweet birch Betula lenta Native Paper birch Betula papyrifera Native 1 Gray birch Betula populifolia Native 4 American hornbeam Carpinus caroliniana 12 Native 2 Bitternut hickory Carya cordiformis Native 2 Shagbark hickory Native Carya sp. 3 Celtis occidentalis Common hackberry Native Dotted hawthorn Crataegus punctata Native 13 5 American beech Fagus grandifolia Native White ash Native 10 Fraxinus americana Black ash Fraxinus nigra Native 1 Green ash Fraxinus pennsylvanica Native 6 Butternut Juglans cinerea Native 1 5 Hop-hornbeam Ostrya virginiana Native 1 Native Red pine Pinus resinosa Pinus strobus 10 Eastern white pine Native 4 Platanus occidentalis Native American sycamore Eastern cottonwood Populus deltoides 21 Native Populus tremuloides Quaking aspen Native 5 8 Black cherry Prunus serotina Native Northern red oak Quercus rubra Native 4 White willow Salix alba Non-native 1 Black willow Salix nigra Native 19 American bladdernut Staphylea trifolia Native 2 1 American yew Taxus canadensis Native American linden Tilia americana 17 Native 4 Eastern hemlock Tsuga canadensis Native

Occurrence

Table 6-5: Reach 5A Floodplain Wetland Plant Species Summary Data (continued).

	American elm	Ulmus americana	Native	21
	Slippery elm	Ulmus rubra	Native	1
Shrub	Speckled alder	Alnus incana	Native	18
Species	Canada serviceberry	Amelanchier canadensis	Native	1
	Japanese barberry	Berberis thunbergii	Invasive <sup>A,B,C</sup>	9
	Buttonbush	Cephalanthus occidentalis	Native	4
	Silky dogwood	Cornus amomum	Native	80
	American hazelnut	Corylus americana	Native	1
	Autumn olive	Elaeagnus umbellata	Invasive <sup>A,B,C</sup>	3
	Burning bush	Euonymus alatus	Invasive <sup>A,B,C</sup>	7
	European spindle	Euonymus europaeus	Non-native	2
	Glossy buckthorn	Frangula alnus	Invasive <sup>A,B,C</sup>	1
	American witch hazel	Hamamelis virginiana	Native	2
	Winterberry	llex verticillata	Native	4
	Border privet	Ligustrum obtusifolium	Invasive <sup>D</sup>	7
	Spicebush	Lindera bensoin	Native	1
	Morrow's honeysuckle	Lonicera morrowii	Invasive <sup>A,B</sup>	51
	Maleberry	Lyonia ligustrina	Native	1
	European buckthorn	Rhamnus cathartica	Invasive <sup>A,B,C</sup>	53
	Eastern black current	Ribes americanum	Native	3
	Multiflora rose	Rosa multiflora	Invasive <sup>A,B,C</sup>	15
	Swamp rose	Rosa palustris	Native	4
	Blackberry	Rubus allegheniensis	Native	2
	Red raspberry	Rubus idaeus	Native	3
	Dwarf raspberry	Rubus pubescens	Native	1
	Pussy willow	Salix disolor	Native	8
	Willow	Salix sp.	Native	14
	Elderberry	Sambucus canadensis	Native	6
	White meadowsweet	Spiraea alba	Native	9
	Meadowsweet	Spiraea latifolia	Native	8
	Arrowwood	Viburnum dentatum	Native	7
	Nannyberry	Viburnum lentago	Native	2
Woody	Asian bittersweet	Celastrus orbiculatus	Invasive <sup>A,B,C</sup>	30
Vine Species	Virgin's-bower	Clematis virginiana	Native	7
Species	Virginia creeper	Parthenocissus quinquefolia	Native	14
	Poison ivy	Toxicodendron radicans	Native	12

Table 6-5: Reach 5A Floodplain Wetland Plant Species Summary Data (continued).

	River grape	Vitis riparia	Native	41
Herb, Forb	Sweetflag	Acorus calamus	Native	3
and Grass Species	Northern maidenhair fern	Adiantum pedatum	Native	1
	Bishop's goutweed	Aegopodium podagraria	Invasive <sup>A,B</sup>	14
	Northern water-plantain	Alisma triviale	Native	5
	Garlic mustard	Alliara petiolata	Invasive <sup>A,B</sup>	8
	Ramps	Allium tricoccum	Native	1
	Hemp dogbane	Apocynum cannabinum	Native	1
	Jack-in-the-pulpit	Arisaema triphyllum	Native	1
	Swamp milkweed	Asclepias incarnata	Native	1
	Common milkweed	Asclepias syriaca	Native	2
	Aster	Aster sp.	Native	1
	Lady fern	Athyrium angustum	Native	1
	Nodding beggar-ticks	Bidens cernua	Native	12
	Devil's beggar-tick	Bidens frondosa	Native	12
	Small-spiked false nettle	Boehmeria cylindrica	Native	7
	Black mustard	Brassica nigra	Non-native	5
<del>-</del>	Smooth brome	Bromus inermis	Non-native	1
	Wild calla	Calla palustris	Native	1
	Water-starwort	Callitriche palustris	Native	4
	Hedge bindweed	Calystegia sepium	Native	1
	Hairy bitter-cress	Cardamine hirsuta	Non-native	1
	Eastern woodland sedge	Carex blanda	Native	1
	Bearded sedge	Carex comosa	Native	1
	Fringed sedge	Carex crinita	Native	1
	Bladder sedge	Carex intumescens	Native	1
	Hop sedge	Carex lupulina	Native	1
	Pennsylvania sedge	Carex pensylvanica	Native	2
	Sedge	Carex sp.	Native	7
	Tussock sedge	Carex stricta	Native	12
	Blue cohosh	Caulophyllum thalictroides	Native	4
	Brown knapweed	Centaurea jacea	Non-native	1
	Chickweed	Cerastium arvense	Non-native	1
	White turtlehead	Chelone glabra	Native	2
	Bulblet-bearing water-hemlock	Cicuta bulbifera	Native	10
	Spotted water-hemlock	Cicuta maculata	Native	1

Table 6-5: Reach 5A Floodplain Wetland Plant Species Summary Data (continued).

Sweet wood-reed	Cinna arundinacea	Native	3
Enchanter's-nightshade	Circaea canadensis	Native	3
Creeping thistle	Cirsium arvense	Non-native	1
Field bindweed	Convolvulus arvensis	Non-native	1
Three-leaved goldthread	Coptis trifolia	Native	1
Common dodder	Cuscuta gronovii	Native	7
Queen Anne's Lace	Daucus carota	Non-native	1
Swamp-loosestrife	Decodon verticillatus	Native	1
Tree-clubmoss	Dendrolycopodium obscurum	Native	1
Tufted hairgrass	Deschampsia cespitosa	Non-native	5
Woodfern	Dryopteris carthusiana	Native	5
Barnyard grass	Echinochloa crus-galli	Non-native	2
Wild cucumber	Echinocystis lobata	Native	1
Needle spikesedge	Eleocharis acicularis	Native	2
Spikerush	Eleocharis sp.	Native	7
Purple-leaved willowherb	Epilobium ciliatum	Native	4
Willow-herb	Epilobium coloratum	Native	3
Purple willow-herb	Epilobium sp.	Native	3
River horsetail	Equisetum fluviatile	Native	1
Tall scouring-rush	Equisetum hyemale	Native	3
Meadow horsetail	Equisetum pratense	Native	3
Branched scouring-rush	Equisetum scirpoides	Native	2
Burnweed	Erechtites hieraciifolius	Native	2
Boneset	Eupatorium perfoliatum	Native	1
Grass-leaved-goldenrod	Euthamia graminifolia	Native	3
Spotted joe-pye weed	Eutrochium maculatum	Native	15
Black bindweed	Fallopia convolvulus	Non-native	1
Japanese knotweed	Fallopia japonica	Invasive <sup>A,B,C</sup>	7
Climbing bindweed	Fallopia scandens	Native	2
Common Strawberry	Fragaria virginiana	Native	2
Hemp-nettle	Galeopsis bifida	Non-native	1
Bedstraw	Galium aparine	Native	3
Rough bedstraw	Galium asprellum	Native	2
Whorled bedstraw	Galium mollugo	Native	1
Marsh bedstraw	Galium palustre	Native	21
Yellow avens	Geum aleppicum	Native	5

Table 6-5: Reach 5A Floodplain Wetland Plant Species Summary Data (continued).

White avens	Geum canadense	Native	9
Avens	Geum sp.	Native	2
Rattlesnake grass	Glyceria canadensis	Native	1
Tuberous sunflower	Helianthus tuberosus	Non-native	1
American cow-parsnip	Heracleum maximum	Native	2
Dame's-rocket	Hesperis matronalis	Invasive <sup>A,B</sup>	5
Common St. John's-wort	Hypericum perforatum	Native	1
Jewelweed	Impatiens capensis	Native	52
Pale jewelweed	Impatiens pallida	Native	1
Morning-glory	Ipomoea purpurea	Non-native	1
Yellow iris	Iris pseudacorus	Invasive <sup>A,B</sup>	4
Soft rush	Juncus effusus	Native	9
Path rush	Juncus tenuis	Native	2
Canada wood nettle	Laportea canadensis	Native	22
Rice cut-grass	Leersia oryzoides	Native	12
Common duckweed	Lemna minor	Native	1
False pimpernel	Lindernia dubia	Native	1
Common water-primrose	Ludwigia palustris	Native	9
Northern water-horehound	Lycopus uniflorus	Native	4
Fringed yellow-loosestrife	Lysimachia ciliata	Native	7
Moneywort	Lysimachia nummularia	Invasive <sup>A</sup>	48
Whorled loosestrife	Lysimachia quadrifolia	Native	1
Swamp candle	Lysimachia terrestris	Native	1
Yellow loosestrife	Lysimachia vulgaris	Native	4
Purple loosestrife	Lythrum salicaria	Invasive <sup>A,B,C</sup>	58
Fasle Soloman's seal	Maianthemum racemosum	Native	2
Ostrich fern	Matteuccia struthiopteris	Native	40
Wild mint	Mentha canadensis	Native	2
Monkey-flower	Mimulus ringens	Native	2
Partridge berry	Mitchella repens	Native	1
Water forget-me-not	Myosotis scorpioides	Invasive <sup>D</sup>	10
Eurasian water-milfoil	Myriophyllum spicatum	Invasive <sup>A,B</sup>	1
Sensitive fern	Onoclea sensibilis	Native	57
Cinnamon fern	Osmunda cinnamomea	Native	2
Royal fern	Osmunda regalis	Native	4
Slender yellow wood sorrel	Oxalis dillenii	Native	1

Table 6-5: Reach 5A Floodplain Wetland Plant Species Summary Data (continued).

Common yellow wood sorrel	Oxalis stricta	Native	1
Japanese mountain-spurge	Pachysandra terminalis	Non-native	1
New York Fern	Parathelypteris noveboracensis	Native	1
Massachusetts fern	Parathelypteris simulata	Native	2
Green arrow-arum	Peltandra virginica	Native	1
Ditch-stonecrop	Penthorum sedoides	Native	4
Water-pepper smartweed	Persicaria hydropiper	Native	11
False water-pepper	Persicaria hydropiperoides	Native	7
Dock-leaved smartweed	Persicaria lapathifolia	Native	4
Pennsylvania smartweed	Persicaria pensylvanica	Native	4
Dotted Smartweed	Persicaria punctata	Native	8
Arrow-leaved tearthumb	Persicaria sagittata	Native	25
Smartweed	Persicaria sp.	Native	3
Jumpseed	Persicaria virginiana	Native	18
Reed canary grass	Phalaris arundinacea	Invasive <sup>A,B,C</sup>	16
Common reed	Phragmites australis	Invasive <sup>A,B,C</sup>	3
Obedient false dragonhead	Physostegia virginiana	Non-native	1
Clearweed	Pilea pumila	Native	9
Narrow leaf plantain	Plantago lanceolata	Non-native	1
Fowl blue grass	Poa palustris	Native	1
Solomon's seal	Polygonatum sp.	Native	1
Christmas fern	Polystichum acrostichoides	Native	1
Pickerelweed	Pontederia cordata	Native	1
Floating pondweed	Potamogeton natans	Native	1
Creeping buttercup	Ranunculus repens	Non-native	1
Green-headed coneflower	Rudbeckia laciniata	Native	25
Curly dock	Rumex crispus	Non-native	6
Common arrowhead	Sagittaria latifolia	Native	9
Soapwort	Saponaria officinalis	Non-native	1
Soft-stemmed bulrush	Schoenoplectus tabernaemontani	Native	3
Woolgrass	Scirpus cyperinus	Native	15
Hooded skullcap	Scutellaria galericulata	Native	1
Purple crown-vetch	Securigera varia	Non-native	1
One-seeded burr-cucumber	Sicyos angulatus	Native	1

Table 6-5: Reach 5A Floodplain Wetland Plant Species Summary Data (continued).

	Bladder campion	Silene vulgaris	Non-native	1
	Water parsnip	Sium suave	Native	4
	Climbing nightshade	Solanum dulcamara	Non-native	1
	Canada goldenrod	Solidago canadensis	Native	20
	Smooth goldenrod	Solidago gigantea	Native	2
	Wrinkled-leaved goldenrod	Solidago rugosa	Native	8
	Goldenrod	Solidago sp.	Native	3
	American bur-reed	Sparganium americanum	Native	12
	Great bur-reed	Sparganium eurycarpum	Native	2
	American aster	Symphyotrichum lateriflorum	Native	2
	Purple-stemmed aster	Symphyotrichum puniceum	Native	3
	Skunk cabbage	Symplocarpus foetidus	Native	7
	Common dandelion	Taraxacum officinale	Non-native	1
	Tall meadow-rue	Thalictrum pubescens	Native	1
	Marsh fern	Thelypteris palustris	Native	4
	White clover	Trifolium repens	Non-native	1
	Narrow-leaved cattail	Typha angustifolia	Non-native	6
	Broad-leaved cattail	Typha latifolia	Native	7
	Stinging nettle	Urtica dioica	Native	12
	Blue vervain	Verbena hastata	Native	4
	White vervain	Verbena urticifolia	Native	1
	Water speedwell	Veronica catenata	Native	3
	Germander speedwell	Veronica chamaedrys	Non-native	1
	Violet	Viola sp.	Native	3
	Rough cocklebur	Xanthium strumarium	Non-native	2
Bryophytes	Mosses	Bryophyta	Native	1
	American cliamacium moss	Climacium americanum	Native	1
	Haircap moss	Polytrichum commune	Native	1

<sup>&</sup>lt;sup>1</sup>Invasive Ratings: A= MIPAG Invasive; B=IPANE Invasive; C=ACOE Invasive; D=MIPAG Likely Invasive

Table 6-6: Percent Cover of Trees, Shrubs, Woody Vines, Herbs, and Mosses Estimated within each Floodplain Natural Community Cover Type

		Deep emergent marsh	Shallow emergent marsh	Wet meadow	Shrub swamp	Red maple swamp	Transitional floodplain forest	High-terrace floodplain forest	
	Count	3	27	17	36	3	74	8	
Trees	Min	0.0	0.0	0.0	0.0	38.0	0.0	85.5	
_	Max	0.0	85.5	20.5	63.0	63.0	98.0	98.0	
-	Mean	0.0	11.2	3.7	9.9	46.3	64.2	93.3	
-	±SE	0.0	4.3	1.5	3.1	8.3	3.0	2.3	
Shrubs	Min	0.0	0.0	0.0	3.0	20.5	0.0	3.0	
-	Max	3.0	85.5	63.0	98.0	98.0	98.0	85.5	
-	Mean	1.0	13.0	11.1	74.5	46.3	43.3	27.4	
_	±SE	1.0	3.8	4.5	4.7	25.8	4.0	9.6	
Woody	Min	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Vines	Max	0.0	10.5	20.5	38.0	10.5	98.0	20.5	
-	Mean	0.0	0.4	2.0	2.4	3.5	12.3	10.1	
-	±SE	0.0	0.4	1.3	1.2	3.5	2.3	3.2	
Herbs	Min	85.5	63.0	63.0	0.0	10.5	3.0	10.5	
-	Max	98.0	98.0	98.0	98.0	98.0	98.0	63.0	
-	Mean	93.8	94.5	94.5	57.3	68.8	70.7	43.6	
-	±SE	4.2	1.9	2.2	6.1	29.2	3.4	8.2	
Mosses	Min	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
-	Max	0.0	98.0	10.5	98.0	0.0	85.5	0.0	
-	Mean	0.0	12.1	1.0	12.6	0.0	3.8	0.0	
-	±SE	0.0	5.6	0.6	4.5	0.0	1.5	0.0	

Table 6-7: Reach 5A NRCS Soil Series Mapping

Code <sup>1</sup>	Series <sup>2</sup>	Area (Acres)	Percent of Reach 5A
901E	Berkshire-Marlow association	0.15	0.0
267A,B,D	Copake fine sandy loam	7.44	1.8
632C	Copake-Urban land complex	3.92	1.0
34A	Fredon fine sandy loam	3.48	0.8
298E	Groton and Hinckley soils	1.10	0.3
269B,C,D	Groton gravelly sandy loam	23.89	5.8
96A	*Hadley silt loam	21.29	5.2
270A	Hero loam	0.04	0.0
242D	Hinckley loamy sand	0.28	0.1
272C	Hoosic gravelly fine sandy loam	0.59	0.1
8A	*Limerick silt loam	117.26	28.6
254A,B	Merrimac fine sandy loam	2.93	0.7
58A	*Natchaug and Catden mucks	23.77	5.8
273A,B	Oakville loamy sand	0.95	0.2
600	Pits, gravel	7.32	1.8
5A	*Saco silt loam	4.38	1.1
651	Udorthents, smoothed	9.98	2.4
602	Urban land	3.40	0.8
1	water	49.21	12.0
98A	*Winooski silt loam	128.47	31.3
		409.84	100.0

<sup>1.</sup> Letters refer to percent slope of the mapping unit; A=0-3%, B=3-8%, C=8-15%, D=15-25%

<sup>2.</sup> Floodplain soils are indicated by an asterisk (\*)

Table 6-8: Reach 5A Floodplain Natural Communities –Biotic Habitat Features

	W	/ildlife Foo	d¹						Cover/Pero	:hes/Basking/[	enning/N	esting Ha	bitat <sup>1</sup>						
Plot_ID	Wetland and Aquatic Food	Upland Food	Shrub thickets with earthworm habitat	Live or Dead Trees >30" DBH	Standing Dead Trees with Cavities and Perches	Cavities in trunks or limbs of Live Trees	Small Mammal Burrows	Shrubs and/or Herbs for bird nesting	Sandy soils suitable for turtle nesting	Other Wildlife Dens/Nests	Dense Herb Cover	Large Woody Debris	Rocks, Crevices, Logs, Roots at Water Edge	Live or Dead Tall Veg. OH/Near Water	Persistent emergent wetland vegetation	Fine-leaved emergent vegetation	Depressions serving as vernal pools	Standing water Present at least part of the growing season	Four -toed salamander habitat
1	V	N/A	*	Ø	*	*	Ø	V	Ø	Ø	√	*	Ø	$\sqrt{}$	Ø	Ø	√	<b>√</b>	Ø
2	$\sqrt{}$	V	V	√	N/A	Ø	Ø	$\sqrt{}$	Ø	Ø	*	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	Ø	Ø
3	$\sqrt{}$	V	Ø	√	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	*	*	Ø	*	Ø	Ø	Ø	Ø	Ø
4	$\sqrt{}$	$\sqrt{}$	Ø	Ø	$\sqrt{}$	Ø	Ø	*	Ø	Ø	*	Ø	Ø	*	Ø	Ø	Ø	V	Ø
6	<b>V</b>	N/A	N/A	<b>V</b>	Ø	$\sqrt{}$	Ø	*	Ø	Ø	*	√	Ø	*	Flooded >25cm	Flooded >25cm	√	*	Ø
7	V	V	V	Ø	Ø	√	Ø	V	Ø	Ø	V	Ø	Ø	*	Ø	Ø	Ø	V	Ø
8	V	V	N/A	Ø	Ø	$\sqrt{}$	V	V	Ø	Ø	Ø	Ø	Ø	N/A	Ø	Ø	Ø	$\sqrt{}$	Ø
9	*	N/A	N/A	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	$\sqrt{}$	V	Flooded >25cm	Flooded >25cm	Ø	$\checkmark$	Ø
10	$\sqrt{}$	V	N/A	Ø	*	$\checkmark$	Ø	Ø	Ø	Ø	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	*	Ø	Ø	Ø	*	Ø
11	√	V	Ø	Ø	V	$\sqrt{}$	Ø	*	Ø	Ø	√	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	Ø	Ø
12	V	V	Ø	V	V	*	Ø	V	Ø	V	Ø	V	V	Ø	Ø	Ø	Ø	Ø	Ø
13	√	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø
14	√	V	Ø	Ø	Ø	*	Ø	*	Ø	Ø	√	*	√	Ø	Ø	Ø	Ø	$\sqrt{}$	Ø
15	V	V	Ø	Ø	Ø	Ø	Ø	V	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	V	Ø
16	$\checkmark$	$\sqrt{}$	Ø	$\sqrt{}$	$\sqrt{}$	Ø	Ø	*	Ø	Ø	*	Ø	Ø	$\checkmark$	Ø	Ø	Ø	$\sqrt{}$	Ø
17	$\checkmark$	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	Ø	$\sqrt{}$	Ø	V	Ø	Ø	$\sqrt{}$	$\sqrt{}$	Ø	$\sqrt{}$	Ø	Ø	Ø	√	Ø
19	√	√	Ø	√	$\checkmark$	√	Ø	*	Ø	Ø	√	Ø	Ø	$\sqrt{}$	Ø	Ø	Ø	√	√
20	$\checkmark$	N/A	Ø	Ø	$\sqrt{}$	$\checkmark$	Ø	*	Ø	Ø	*	$\sqrt{}$	Ø	$\sqrt{}$	Ø	Ø	$\checkmark$	$\checkmark$	Ø
21	$\checkmark$	$\sqrt{}$	Ø	*	Ø	$\checkmark$	Ø	Ø	Ø	Ø	Ø	$\sqrt{}$	$\checkmark$	$\checkmark$	Ø	Ø	$\sqrt{}$	$\sqrt{}$	Ø
22	$\sqrt{}$	V	V	Ø	√	Ø	Ø	$\sqrt{}$	Ø	Ø	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø
23	*	N/A	Ø	Ø	Ø	Ø	Ø	*	Ø	Ø	√	√	Ø	Ø	Ø	Ø	Ø	√	Ø
24	√ 	√ 	√ 	Ø	Ø	Ø	√	√	Ø	Ø	√	√	Ø	Ø	Ø	Ø	Ø	Ø	Ø
25		√ 	√ 	Ø	√ 	Ø	Ø	√	Ø	Ø	√ 	√	Ø	Ø	Ø	Ø	Ø	Ø	Ø
26	*	√ 	√ 	√ 	√ 	√ 	Ø	*	Ø	√ 	√ /	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø
27		$\frac{}{}$	√ √	√ •	√ √	Ø	Ø	*	Ø	Ø	√ √	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø
28	V			Ø	V	Ø	Ø	*	Ø	Ø	- V	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø
29	*	N/A	Ø	Ø	√ 	√ 	Ø		Ø	Ø	*	√ 	√	√	Flooded >25cm	Ø	√	√	Ø
30	√	√ 	Ø	*	√	√	Ø	√ 	Ø	√	Ø	√	Ø	*	Ø	Ø	Ø	Ø	Ø
37	$\sqrt{}$	N/A	Ø	Ø	√	$\sqrt{}$	Ø	*	Ø	Ø	$\checkmark$	Ø	$\checkmark$	*	Flooded >25cm	Ø	Ø	$\checkmark$	Ø
38	$\checkmark$	N/A	Ø	Ø	$\sqrt{}$	Ø	Ø	*	Ø	Ø	*	Ø	*	*	Flooded >5cm	Ø	Ø	$\checkmark$	Ø

Table 6-8: Reach 5A Floodplain Natural Communities –Biotic Habitat Features (continued)

	V	/ildlife Foo	d <sup>1</sup>						Cover/Pero	ches/Basking/[	Denning/N	lesting Ha	bitat <sup>1</sup>						
Plot_ID	Wetland and Aquatic Food	Upland Food	Shrub thickets with earthworm habitat	Live or Dead Trees >30" DBH	Standing Dead Trees with Cavities and Perches	Cavities in trunks or limbs of Live Trees	Small Mammal Burrows	Shrubs and/or Herbs for bird nesting	Sandy soils suitable for turtle nesting	Other Wildlife Dens/Nests	Dense Herb Cover	Large Woody Debris	Rocks, Crevices, Logs, Roots at Water Edge	Live or Dead Tall Veg. OH/Near Water	Persistent emergent wetland vegetation	Fine-leaved emergent vegetation	Depressions serving as vernal pools	Standing water Present at least part of the growing season	Four -toed salamander habitat
39	*	N/A	Ø	Ø	V	Ø	Ø	*	Ø	V	*	√	*	*	Ø	Ø	Ø	√	Ø
40	$\sqrt{}$	N/A	Ø	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	*	*	Flooded >5cm	Flooded >5cm	Ø	$\sqrt{}$	Ø
41	V	V	V	Ø	V	Ø	Ø	√	Ø	Ø	Ø	Ø	Ø	√	Ø	Ø	Ø	Ø	Ø
42	$\checkmark$	$\checkmark$	Ø	Ø	Ø	Ø	Ø	*	Ø	$\checkmark$	*	Ø	Ø	*	Flooded >25cm	Flooded >25cm	Ø	$\checkmark$	Ø
43	V	V	V	√	V	$\sqrt{}$	Ø	*	Ø	Ø	*	√	Ø	*	Ø	Ø	Ø	Ø	Ø
44	$\checkmark$	N/A	N/A	Ø	*	Ø	Ø	*	Ø	Ø	*	Ø	$\checkmark$	Ø	Flooded >25cm	Flooded >25cm	Ø	$\sqrt{}$	Ø
45	V	N/A	N/A	Ø	V	Ø	Ø	*	Ø	Ø	*	√	*	Ø	Ø	Ø	Ø	V	V
46	V	N/A	Ø	Ø	V	V	Ø	*	Ø	Ø	*	√	Ø	Ø	Ø	Ø	Ø	Ø	Ø
47	V	N/A	N/A	Ø	V	Ø	Ø	*	Ø	Ø	*	√	Ø	Ø	Ø	Ø	Ø	V	Ø
48	V	N/A	Ø	Ø	√	Ø	Ø	*	Ø	Ø	*	Ø	<b>V</b>	*	Flooded >25cm	Flooded >25cm	Ø	*	Ø
49	*	N/A	N/A	Ø	V	Ø	Ø	*	Ø	Ø	*	√	Ø	Ø	Ø	Ø	Ø	*	Ø
50	V	N/A	N/A	Ø	√	Ø	Ø	*	Ø	Ø	*	Ø	√	Ø	Flooded >25cm	Flooded >25cm	Ø	*	Ø
51	*	N/A	Ø	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	Ø	Ø	Flooded >25cm	Flooded >25cm	Ø	$\sqrt{}$	Ø
52	*	N/A	N/A	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	V	*	Ø	Ø	Ø	√	Ø
53	*	N/A	N/A	Ø	V	Ø	Ø	*	Ø	Ø	Ø	√	$\checkmark$	Ø	Ø	Ø	Ø	*	Ø
54	*	N/A	N/A	Ø	Ø	Ø	Ø	*	Ø	Ø	Ø	Ø	*	Ø	Ø	Ø	Ø	*	Ø
55	$\sqrt{}$	N/A	N/A	Ø	Ø	Ø	Ø	*	Ø	Ø	$\sqrt{}$	$\sqrt{}$	*	Ø	Ø	Ø	Ø	*	<b>V</b>
56	*	N/A	N/A	Ø	Ø	Ø	Ø	*	Ø	$\checkmark$	*	Ø	*	Ø	Flooded >25cm	Flooded >25cm	Ø	*	Ø
57	$\checkmark$	N/A	N/A	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	*	Ø	Flooded >5cm	Flooded >5cm	Ø	*	Ø
58	*	N/A	N/A	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	*	Ø	Flooded >25cm	Flooded >25cm	Ø	*	Ø
59	V	V	V	V	Ø	Ø	Ø	√	Ø	Ø	V	Ø	Ø	Ø	Ø	Ø	Ø	V	Ø
60	<b>V</b>	N/A	N/A	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	√	Ø	Flooded >25cm	Ø	Ø	*	Ø
61	<b>√</b>	N/A	N/A	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	*	Ø	Flooded >25cm	Ø	Ø	*	Ø
62	V	N/A	N/A	$\sqrt{}$	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	*	$\sqrt{}$	√	Ø	Ø	Ø	*	*	Ø
64	*	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	$\sqrt{}$	Ø	Ø	*	Ø	Ø	*	Ø	Ø	$\sqrt{}$	Ø	Ø
65	V	$\sqrt{}$	V	V	Ø	V	Ø	*	Ø	V	*	√	Ø	Ø	Ø	Ø	Ø	Ø	Ø

Table 6-8: Reach 5A Floodplain Natural Communities –Biotic Habitat Features (continued)

	V	Vildlife Foo	od <sup>1</sup>						Cover/Perc	:hes/Basking/[	Denning/N	lesting Ha	bitat <sup>1</sup>						
Plot_ID	Wetland and Aquatic Food	Upland Food	Shrub thickets with earthworm habitat	Live or Dead Trees >30" DBH	Standing Dead Trees with Cavities and Perches	Cavities in trunks or limbs of Live Trees	Small Mammal Burrows	Shrubs and/or Herbs for bird nesting	Sandy soils suitable for turtle nesting	Other Wildlife Dens/Nests	Dense Herb Cover	Large Woody Debris	Rocks, Crevices, Logs, Roots at Water Edge	Live or Dead Tall Veg. OH/Near Water	Persistent emergent wetland vegetation	Fine-leaved emergent vegetation	Depressions serving as vernal pools	Standing water Present at least part of the growing season	Four -toed salamander habitat
66	*	N/A	Ø	Ø	$\checkmark$	Ø	Ø	*	Ø	Ø	*	$\sqrt{}$	Ø	$\sqrt{}$	Ø	Ø	Ø	*	Ø
67	V	V	<b>V</b>	*	Ø	V	Ø	*	Ø	Ø	*	√	Ø	Ø	Ø	Ø	Ø	Ø	Ø
68	V	$\sqrt{}$	$\sqrt{}$	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø
69	V	<b>V</b>	V	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	Ø	*	Ø	Ø	Ø	Ø	Ø
70	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	Ø	V	$\sqrt{}$	Ø	*	Ø	Ø	*	$\sqrt{}$	Ø	*	Ø	Ø	Ø	Ø	Ø
71	V	V	Ø	Ø	V	Ø	Ø	*	Ø	Ø	*	Ø	Ø	Ø	Ø	Ø	Ø	*	Ø
72	V	V	Ø	V	*	*	Ø	*	Ø	V	√	√	V	Ø	Ø	Ø	Ø	Ø	Ø
73	*	$\sqrt{}$	Ø	$\sqrt{}$	Ø	V	$\sqrt{}$	*	Ø	Ø	*	Ø	$\sqrt{}$	Ø	Ø	Ø	Ø	V	Ø
74	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	Ø	Ø	$\sqrt{}$	$\checkmark$	*	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø
75	*	N/A	Ø	Ø	V	Ø	Ø	*	Ø	Ø	*	Ø	Ø	Ø	Ø	Ø	Ø	*	Ø
79	V	$\sqrt{}$	V	$\sqrt{}$	V	V	Ø	$\sqrt{}$	Ø	Ø	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	*	Ø	Ø	Ø	Ø	Ø
81	*	N/A	Ø	Ø	Ø	Ø	Ø	*	Ø	Ø	Ø	Ø	$\sqrt{}$	Ø	Ø	Ø	V	*	Ø
82	V	V	Ø	Ø	V	V	√	V	Ø	√	$\sqrt{}$	√	*	V	Flooded >5cm	Flooded >5cm	<b>√</b>	*	
83	*	N/A	Ø	Ø	Ø	V	Ø	*	Ø	Ø	V	V	*	Ø	Ø	Ø	V	V	√
84	*	N/A	Ø	Ø	V	V	Ø	*	Ø	Ø	√	√	√	Ø	Ø	Ø	√	*	V
85	*	√	V	Ø	Ø	Ø	√	√	Ø	Ø	Ø	√	Ø	*	Ø	Ø	Ø	Ø	Ø
86	V	V	V	Ø	Ø	V	Ø	$\sqrt{}$	Ø	Ø	Ø	V	Ø	Ø	Ø	Ø	Ø	Ø	Ø
87	$\sqrt{}$	N/A	V	Ø	Ø	Ø	Ø	*	Ø	Ø	$\sqrt{}$	Ø	$\sqrt{}$	*	Ø	Ø	Ø	$\sqrt{}$	Ø
88	V	<b>V</b>	<b>V</b>	Ø	V	V	Ø	*	Ø	Ø	*	√	*	*	Ø	Ø	Ø	V	Ø
90	V	N/A	√	Ø	Ø	Ø	√	*	Ø	Ø	*	Ø	Ø	*	Flooded >25cm	Flooded >25cm	Ø	*	Ø
91	V	√	Ø	Ø	Ø	Ø	Ø	√	V	V	*	√	V	Ø	Ø	Ø	Ø	Ø	Ø
92	V	√	Ø	Ø	V	Ø	√	*	Ø	Ø	*	√	V	Ø	Ø	Ø	Ø	Ø	Ø
94	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	Ø	Ø	Ø	Ø	$\sqrt{}$	Ø	Ø	*	Ø	$\sqrt{}$	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø
95	V	√	Ø	√	V	V	Ø	Ø	Ø	Ø	Ø	*	V	Ø	Ø	Ø	√	V	Ø
96	V	√	√	√	Ø	V	√	√	Ø	Ø	*	√	V	√	Ø	Ø	Ø	Ø	Ø
97	V	√	V	$\sqrt{}$	Ø	Ø	Ø	*	Ø	Ø	V	$\sqrt{}$	$\sqrt{}$	Ø	Ø	Ø	Ø	V	Ø
99	V	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	V	$\sqrt{}$	Ø	$\sqrt{}$	Ø	Ø	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	Ø
100	V	N/A	V	$\sqrt{}$	V	Ø	Ø	$\sqrt{}$	Ø	Ø	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	Ø
101	√	√	*	Ø	Ø	Ø	V	√	Ø	Ø	Ø	√	√	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø
102	√ 	√	√ 	<b>√</b>	√ 	√ 	Ø	√ 	Ø	Ø	√ 	√ 	<b>√</b>	Ø	Ø	Ø	Ø	Ø	Ø
103	<u> </u>	N/A	√ 	√ 	√ 	√ 	Ø	√ 	Ø	Ø	√ 	√ 	√ 	Ø	Ø	Ø	Ø	√	Ø
104	V	√	*	√	V	V	Ø	*	Ø	Ø	√	V	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	Ø

Table 6-8: Reach 5A Floodplain Natural Communities –Biotic Habitat Features (continued)

	V	Vildlife Foo	od <sup>1</sup>						Cover/Pero	ches/Basking/E	Denning/N	lesting Ha	bitat <sup>1</sup>						
Plot_ID	Wetland and Aquatic Food	Upland Food	Shrub thickets with earthworm habitat	Live or Dead Trees >30" DBH	Standing Dead Trees with Cavities and Perches	Cavities in trunks or limbs of Live Trees	Small Mammal Burrows	Shrubs and/or Herbs for bird nesting	Sandy soils suitable for turtle nesting	Other Wildlife Dens/Nests	Dense Herb Cover	Large Woody Debris	Rocks, Crevices, Logs, Roots at Water Edge	Live or Dead Tall Veg. OH/Near Water	Persistent emergent wetland vegetation	Fine-leaved emergent vegetation	Depressions serving as vernal pools	Standing water Present at least part of the growing season	Four -toed salamander habitat
105	V	√	Ø	√	√	V	Ø	$\sqrt{}$	Ø	Ø	*	√	√	√	Ø	Ø	Ø	Ø	Ø
106	<b>√</b>	$\sqrt{}$	Ø	V	Ø	$\sqrt{}$	Ø	Ø	$\sqrt{}$	Ø	*	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	Ø	Ø	$\sqrt{}$	$\sqrt{}$	Ø
107	<b>√</b>	$\sqrt{}$	Ø	Ø	Ø	$\sqrt{}$	Ø	$\sqrt{}$	Ø	Ø	$\sqrt{}$	*	$\sqrt{}$	N/A	Ø	Ø	Ø	$\sqrt{}$	Ø
108	*	V	Ø	Ø	√	V	Ø	*	Ø	Ø	√	$\checkmark$	$\sqrt{}$	N/A	Flooded >5cm	Flooded >5cm	Ø	√	Ø
109	√	$\sqrt{}$	√	V	Ø	V	√	V	Ø	Ø	*	√	$\sqrt{}$	*	Ø	Ø	Ø	Ø	Ø
110	<b>√</b>	N/A	√	Ø	√	V	Ø	V	Ø	Ø	√	Ø	Ø	Ø	Flooded >25cm	Flooded >25cm	*	√	Ø
111	<b>√</b>	V	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	*	Ø	Ø	$\sqrt{}$	Flooded > 5cm	Flooded >5cm	Ø	$\checkmark$	Ø
112	V	√	Ø	$\sqrt{}$	Ø	Ø	Ø	N/A	Ø	Ø	√	√	Ø	Ø	Ø	Ø	Ø	<b>V</b>	Ø
113	$\sqrt{}$	√	Ø	V	Ø	Ø	Ø	$\sqrt{}$	Ø	Ø	$\sqrt{}$	Ø	Ø	√	Ø	Ø	Ø	Ø	Ø
114	V	√	√	V	$\sqrt{}$	√	Ø	√	Ø	Ø	Ø	√	Ø	Ø	Ø	Ø	Ø	Ø	Ø
115	$\sqrt{}$	*	*	Ø	$\checkmark$	Ø	Ø	$\sqrt{}$	Ø	Ø	$\sqrt{}$	Ø	Ø	N/A	Ø	Ø	N/A	N/A	Ø
116	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	Ø	Ø	Ø	Ø	$\sqrt{}$	Ø	Ø	$\sqrt{}$	Ø	Ø	N/A	Ø	Ø	N/A	$\checkmark$	Ø
117	N/A	Ø	Ø	$\sqrt{}$	√	Ø	Ø	Ø	Ø	Ø	Ø	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	N/A	N/A
118	V	√	$\sqrt{}$	Ø	Ø	Ø	Ø	$\sqrt{}$	Ø	Ø	V	Ø	Ø	Ø	Ø	Ø	√	√	Ø
119	$\sqrt{}$	$\sqrt{}$	*	$\sqrt{}$	$\checkmark$	$\sqrt{}$	Ø	$\sqrt{}$	Ø	Ø	*	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø
120	$\sqrt{}$	$\checkmark$	$\sqrt{}$	$\checkmark$	$\sqrt{}$	$\sqrt{}$	Ø	$\checkmark$	Ø	Ø	Ø	$\sqrt{}$	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	Ø
121	$\sqrt{}$	$\checkmark$	*	$\sqrt{}$	Ø	$\sqrt{}$	Ø	$\sqrt{}$	Ø	Ø	*	Ø	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	Ø
122	V	√	*	Ø	√	Ø	Ø	√	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø
123	V	$\sqrt{}$	$\sqrt{}$	√	Ø	Ø	Ø	$\sqrt{}$	Ø	Ø	*	Ø	√	Ø	Ø	Ø	√	Ø	Ø
124	V	√	V	Ø	$\checkmark$	V	Ø	V	Ø	Ø	*	$\sqrt{}$	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	Ø
125	V	N/A	*	V	V	V	Ø	*	Ø	Ø	*		$\sqrt{}$	Ø	Ø	Ø	$\sqrt{}$	Ø	Ø
126	V	√	√	Ø	V	V	Ø	V	Ø	Ø	Ø	V	Ø	Ø	Ø	Ø	Ø	Ø	Ø
127	V	N/A	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	*	Ø	Ø	Ø	Ø	Ø	*	$\checkmark$	Ø
128	$\sqrt{}$	N/A	*	Ø	Ø	Ø	Ø	V	Ø	Ø	*	Ø	$\sqrt{}$	Ø	Ø	Ø	$\sqrt{}$	Ø	Ø
129	<b>√</b>	$\sqrt{}$	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	Ø	Ø	*	Ø	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	Ø
130	V	V	V	Ø	Ø	Ø	Ø	V	Ø	Ø	V	V	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	Ø
131	V	N/A	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	*	√	√	Ø	Ø	Ø	Ø	V	N/A
132	<b>√</b>	N/A	*	Ø	Ø	Ø	Ø	*	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø
134	<b>√</b>	√	V	V	V	V	√	V	Ø	Ø	√	√	√	Ø	Ø	Ø	Ø	Ø	Ø
136	V	N/A	*	Ø	$\sqrt{}$	V	Ø	$\sqrt{}$	Ø	Ø	V	Ø	$\checkmark$	$\checkmark$	Ø	Ø	$\sqrt{}$	V	Ø
137	*	N/A	*	Ø	√	V	$\sqrt{}$	*	Ø	√	*	Ø	$\sqrt{}$	$\sqrt{}$	Flooded >25cm	Flooded >25cm	$\checkmark$	*	Ø

Table 6-8: Reach 5A Floodplain Natural Communities –Biotic Habitat Features (continued)

	V	Vildlife Foo	od <sup>1</sup>						Cover/Pero	ches/Basking/[	Denning/N	lesting Ha	bitat <sup>1</sup>						
Plot_ID	Wetland and Aquatic Food	Upland Food	Shrub thickets with earthworm habitat	Live or Dead Trees >30" DBH	Standing Dead Trees with Cavities and Perches	Cavities in trunks or limbs of Live Trees	Small Mammal Burrows	Shrubs and/or Herbs for bird nesting	Sandy soils suitable for turtle nesting	Other Wildlife Dens/Nests	Dense Herb Cover	Large Woody Debris	Rocks, Crevices, Logs, Roots at Water Edge	Live or Dead Tall Veg. OH/Near Water	Persistent emergent wetland vegetation	Fine-leaved emergent vegetation	Depressions serving as vernal pools	Standing water Present at least part of the growing season	Four -toed salamander habitat
138	√	N/A	*	Ø	V	√	Ø	*	Ø	Ø	√	Ø	√	Ø	Ø	Ø	Ø	√	Ø
139	$\checkmark$	N/A	Ø	Ø	Ø	Ø	Ø	Ø	Ø	$\checkmark$	$\checkmark$	Ø	$\sqrt{}$	$\sqrt{}$	Flooded >25cm	Flooded >25cm	Ø	$\sqrt{}$	N/A
140	$\checkmark$	N/A	Ø	Ø	Ø	$\checkmark$	$\checkmark$	$\sqrt{}$	Ø	$\sqrt{}$	*	Ø	$\checkmark$	$\sqrt{}$	Flooded >25cm	Flooded >25cm	Ø	$\checkmark$	N/A
141	V	N/A	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	*	Ø	Ø	Ø	Flooded >25cm	Flooded >25cm	Ø	√	Ø
142	V	N/A	*	Ø	Ø	Ø	Ø	*	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	V	Ø
143	√	N/A	*	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	Ø	Ø	Ø	Ø	Ø	<b>V</b>	Ø
144	V	N/A	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	*	Ø	Ø	Ø	Flooded >25cm	Flooded >25cm	Ø	√	N/A
146	V	$\sqrt{}$	$\sqrt{}$	Ø	Ø	V	Ø	$\sqrt{}$	Ø	Ø	*	Ø	V	√	Ø	Ø	Ø	Ø	Ø
147	V	$\sqrt{}$	*	Ø	Ø	V	Ø	$\sqrt{}$	Ø	Ø	√	Ø	V	Ø	Ø	Ø	Ø	√	Ø
148	$\sqrt{}$	V	$\sqrt{}$	V	$\sqrt{}$	V	Ø	$\sqrt{}$	Ø	Ø	V	V	V	V	Ø	Ø	Ø	$\sqrt{}$	Ø
149	$\sqrt{}$	√	Ø	V	$\checkmark$	$\sqrt{}$	Ø	Ø	Ø	Ø	*	$\sqrt{}$	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	Ø
150	V	V	Ø	Ø	√	V	Ø	V	Ø	Ø	V	Ø	√	Ø	Flooded >25cm	Flooded >25cm	Ø	√	Ø
151	√	N/A	*	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø
152	√	N/A	*	Ø	V	V	Ø	*	Ø	Ø	*	Ø	√	Ø	Ø	Ø	√	V	Ø
153	V	N/A	*	Ø	V	V	Ø	*	Ø	Ø	*	Ø	V	√	Ø	Ø	Ø	√	Ø
155	*	N/A	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	*	Ø	Ø	Ø	Flooded >25cm	Flooded >25cm	Ø	√	Ø
156	*	N/A	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	*	Ø	Ø	Ø	Ø	Flooded >25cm	Ø	Ø	Ø
157	<b>√</b>	N/A	$\checkmark$	Ø	Ø	Ø	Ø	$\sqrt{}$	Ø	Ø	*	$\checkmark$	$\sqrt{}$	Ø	Ø	Flooded >25cm	Ø	$\checkmark$	Ø
158	$\checkmark$	N/A	*	Ø	Ø	Ø	Ø	*	Ø	Ø	$\checkmark$	Ø	Ø	Ø	Flooded >25cm	Flooded >25cm	Ø	Ø	Ø
159	$\sqrt{}$	N/A	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	V	Ø	Ø	$\sqrt{}$	Ø	Ø	Ø	$\checkmark$	V
160	<b>√</b>	N/A	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	*	Ø	Ø	Ø	Flooded >25cm	Flooded >25cm	Ø	$\checkmark$	Ø
161	$\sqrt{}$	N/A	*	Ø	Ø	$\sqrt{}$	Ø	*	Ø	Ø	Ø	Ø	$\checkmark$	Ø	Ø	Ø	Ø	$\sqrt{}$	Ø
162	√	√	Ø	√	Ø	√	√	√	Ø	Ø	√	√	<b>V</b>	Ø	Ø	Ø	Ø	√	Ø
163	√ 	√ /	√	√	√ 	√ /	<u>√</u>	<b>√</b>	Ø	Ø	√	√ 	√ 	Ø	Ø	Ø	Ø	√	Ø
164	√ 	√ 	*	Ø	√ 	√ 	√	<b>√</b>	Ø	Ø	*	√ 	<u>√</u>	Ø	Ø	Ø	Ø	Ø	Ø
165	√ 	√ 	√ 	√ 	√ 	√ 	√ 	√ 	Ø	Ø	√ 	√ 	√ 	√ 	Ø	Ø	Ø	Ø	Ø
168	√ 	N/A	√	Ø	V	√	٧	٧	Ø	Ø	√	√	√ 	√	Ø	Ø	Ø	√	Ø

Table 6-8: Reach 5A Floodplain Natural Communities –Biotic Habitat Features (continued)

	W	/ildlife Foo	d <sup>1</sup>						Cover/Pero	:hes/Basking/[	enning/N	esting Ha	bitat <sup>1</sup>						
Plot_ID	Wetland and Aquatic Food	Upland Food	Shrub thickets with earthworm habitat	Live or Dead Trees >30" DBH	Standing Dead Trees with Cavities and Perches	Cavities in trunks or limbs of Live Trees	Small Mammal Burrows	Shrubs and/or Herbs for bird nesting	Sandy soils suitable for turtle nesting	Other Wildlife Dens/Nests	Dense Herb Cover	Large Woody Debris	Rocks, Crevices, Logs, Roots at Water Edge	Live or Dead Tall Veg. OH/Near Water	Persistent emergent wetland vegetation	Fine-leaved emergent vegetation	Depressions serving as vernal pools	Standing water Present at least part of the growing season	Four -toed salamander habitat
169	$\sqrt{}$	N/A	*	Ø	$\sqrt{}$	$\sqrt{}$	Ø	$\sqrt{}$	Ø	Ø	*	$\sqrt{}$	$\sqrt{}$	Ø	Ø	Ø	Ø	$\sqrt{}$	Ø
170	$\sqrt{}$	N/A	Ø	Ø	√	<b>√</b>	Ø	Ø	Ø	Ø	*	Ø	$\sqrt{}$	<b>√</b>	Ø	Flooded >25cm	V	√	Ø

<sup>&</sup>lt;sup>1</sup>See Table 6-9 for wildlife associations with listed habitat features

<sup>\*=</sup>Abundant; √=Present; Ø=Absent

Table 6-9: Reach 5A Floodplain Natural Communities: Summary of Biotic Habitat Features

Habitat Feature	Wildlife Use	% of Stations Abundant	% of Stations Present	% of Stations Absent
Wetland and Aquatic Food	Overall food	16	83	0
Upland Food	Overall food	1	55	1
Shrub thickets with earthworm habitat	Game foraging habitat (e.g., American woodcock)	16	33	39
Live or Dead Trees >30" DBH	Cover/perching/nesting	2	28	70
Standing Dead Trees with Cavities and Perches	Cavities/perching/breeding/nesting/feeding	3	47	50
Cavities in trunks or limbs of Live Trees	Cavities/perching/breeding/nesting	3	44	53
Small Mammal Burrows	Hibernation/breeding/nesting/escape/cover	0	13	87
Shrub and/or herbaceous vegetation	Suitable for birds such as veery nesting	46	40	14
Open sandy to gravelly soils with sparse vegetation	Turtle nesting habitat	0	1	99
Other Wildlife Dens/Nests	Hibernation/breeding/nesting/escape/cover	0	9	91
Dense Herb Cover	Voles, small mammals, amphibians, reptiles	51	34	15
Large Woody Debris on the ground	Small mammals, amphibians, reptiles, invertebrate emergence	3	45	51
Rocks, Crevices, Logs, Roots at Water Edge	Turtles, snakes, frogs, invertebrate emergence	9	46	45
Live or dead vegetation overhanging and/or near water	Habitat offering good visibility of open water for, e.g., osprey, kingfisher, flycatchers, cedar waxwings. Vegetation closer to ground for turtles, snakes, frogs, wading birds, wood duck, mink, raccoon	16	20	61
Persistent emergent wetland vegetation at least seasonally flooded during the growing season	Habitat for American bittern, wood duck, green heron, black-crowned night heron, rails (sora, king, Virginia), moorhen, coot, pie-billed grebe, etc.	14	7	80
Fine-leaved emergent vegetation (Grasses and sedges) at least seasonally flooded during the growing season	Habitat for common snipe, spotted sandpiper, sedge wren, least bittern, common moorhen	11	8	81
Depressions serving as vernal pools	Turtles, snakes, frogs, invertebrate emergence	2	14	83
Standing water present at least part of the growing season	Amphibians, turtles, foraging waterfowl, non-breeding amphibians and reptiles (foraging, re-hydration)	15	44	40
Sphagnum hummocks or mats, moss-covered logs or saturated logs, overhanging or directly adjacent to pools of standing water in spring	Habitat for four-toed salamander	0	5	92

Table 6-10. Wildlife Observations Made During the 2022 Floodplain Surveys

Common Name	Scientific Name	Common Name	Scientific Name
Amphibians	and Reptiles	Birds	s (cont.)
American toad	Anaxyrus americanus	Northern cardinal	Cardinalis cardinalis
Bullfrog	Lithobates catesbeiana	Northern harrier	Circus hudsonius
Common snapping turtle	Chelydra serpentina	Marsh wren	Cistothorus palustris
Eastern garter snake	Thamnophis sirtalis	Yellow shafted flicker	Colaptes auratus
Greenfrog	Lithobates clamitans	Eastern wood-pewee	Contopus virens
Grey tree frog	Dryophytes versicolor	American crow	Corvus brachyrhynchos
Northern leopard frog	Lithobates pipiens	Fish crow	Corvus ossifragus
Painted turtle	Chrysemys picta	Blue Jay	Cyanocitta cristata
Pickerel frog	Lithobates palustris	Downy woodpecker	Dryobates pubescens
Spring peeper	Pseudacris crucifer	Pileated woodpecker	Dryocopus pileatus
Wood frog	Lithobates sylvaticus	Gray catbird	Dumetella carolinensis
Spotted salamander	Ambystoma maculatum	American kestrel	Falco sparverius
Invert	ebrates	Common yellow throat	Geothypis trichas
Damselfly	O: Odonata S: Zygoptera	Bald eagle	Haliaeetus leucocephalus
Caddisfly	F: Limnephilidae	Baltimore oriole	lcterus galbula
Darners	O: Odonata F: Aeshnidae	Hairy woodpecker	Leuconotopicus villosus
Ruby Meadowhawk	Sympetrum rubicundulum	Belted kingfisher	Megaceryle alcyon
Isopods	O: Isopoda	Red bellied woodpecker	Melanerpes carolinus
Monarch butterfly	Danaus plexippus	Wild turkey	Meleagris gallopave
Stonefly	O: Plecoptera	Song sparrow	Melospiza melodia
Tiger swallowtail	Papilio glaucus	Great-crested Flycatcher	Myiarchus crinitus
Man	nmals	Osprey	Pandion haliaetus
Beaver	Castor canadensis	Small sparrow	Passer domesticus
Black bear	Ursus americanus	Chestnut warbler	Phylloscopus castaniceps
Chipmunk	Tamias striatus	Eastern towhee	Pipilo erythrophthalmus
Coyote	Canis latrans	Black capped chickadee	Poecile atricapillus

Table 6-10. Wildlife Observations Made During the 2022 Floodplain Surveys (continued)

Common Name	Scientific Name	Common Name	Scientific Name
Eastern cottontail	Sylvilagus floridanus	Common grackle	Quiscalus quiscula
Muskrat	Ondatra zibethicus	American Woodcock	Scolopax minor
Racoon	Procyon lotor	Yellow warbler	Setophaga petechia
White-tailed deer	Odocoileus virginianus	American redstart	Setophaga ruticilla
Bir	ds	Eastern bluebird	Sialia sialis
Red-winged blackbird	Agelaius phoeniceus	American goldfinch	Spinus tristis
Wood duck	Aix sponsa	Field sparrow	Spizella pusilla
Mallard	Anas platyrhynchos	House wren	Troglodytes aedon
Ruby-throated hummingbird	Archilochus colubris	American robin	Turdus migratorius
Great blue heron	Ardea herodias	Red-eyed vireo	Vireo olivaceus
Tufted titmouse	Baeolophus bicolor	Mourning dove	Zenaida macroura
Red-tailed hawk	Beteo jamaicensis	Veery	Catharus fuscescens
Cedar waxwing	Bombycilla cedrorum	Wood thrush	Hylocichla mustelina
Ruffed grouse	Bonasa umbellus	Common moorhen	Gallinula chloropus
Canada geese	Branta canadensis	Northern waterthrush	Parkesia noveboracensis
Green heron	Butorides virescens		

Table 6-11: State-Listed Rare Species Potentially Associated with Floodplain Wetland Habitats in Reach 5A

Scientific Name	Common Name	State Status
Botaurus lentiginosus	American Bittern	Endangered
Ranunculus pensylvanicus	Bristly Buttercup	Special Concern
Ophiogomphus aspersus	Brook Snaketail	Special Concern
Gallinula galeata	Common Gallinule	Special Concern
Veronicastrum virginicum	Culver's-root	Threatened
Eragrostis frankii	Frank's Lovegrass	Special Concern
Carex grayi	Gray's Sedge	Threatened
Rhododendron maximum	Great Laurel	Threatened
Elymus villosus	Hairy Wild Rye	Endangered
Eleocharis intermedia	Matted Spike-sedge	Threatened
Pieris oleracea	Mustard White	Threatened
Boyeria grafiana	Ocellated Darner	Special Concern
Papaipema sp. 2	Ostrich Fern Borer	Special Concern
Phanogomphus quadricolor	Rapids Clubtail	Endangered
Ophiogomphus carolus	Riffle Snaketail	Threatened
Hylogomphus abbreviatus	Spine-crowned Clubtail	Endangered
Carex tuckermanii	Tuckerman's Sedge	Endangered
Sagittaria cuneata	Wapato	Threatened
Malaxis monophyllos ssp. brachypoda	White Adder's-mouth	Endangered
Myotis septentrionalis	Northern Long-eared Bat	Endangered
Glyptemys insculpta	Wood Turtle	Special Concern

Table 6-12: Reach 5A Floodplain Wetland Function Assessment Factors\* (Functional Assessment Documented on Form FP-2).

Function	Description of Function	Parameters Considered in Assessing Function
Groundwater recharge/discharge	This function considers the potential for a wetland to serve as a groundwater recharge and/or discharge area. Recharge relates to the potential for the wetland to contribute water to an aquifer. Discharge relates to the potential for the wetland to serve as an area where groundwater can be discharged to the surface.	Hydrogeologic setting; soil composition and characteristics
Floodflow alteration (storage & desynchronization)	This function considers the effectiveness of the wetland in reducing flood damage by attenuation of floodwaters for prolonged periods following precipitation events.	Watershed setting/factors; hydrology; soil composition and characteristics; plant community
Sediment, toxicant, and pathogen retention	This function reduces or prevents degradation of water quality. It relates to the effectiveness of the wetland as a trap for sediments, toxicants, or pathogens.	Watershed setting/factors; hydrology; soil composition and characteristics; plant community
Nutrient removal, retention, and transformation	This function relates to the effectiveness of the wetland to prevent adverse effects of excess nutrients entering aquifers or surface waters such as ponds, lakes, streams, rivers, or estuaries.	Watershed setting/factors; hydrology; soil composition and characteristics; plant community
Production export (nutrient)	This function relates to the effectiveness of the wetland to produce food or usable products for humans or other living organisms.	Watershed setting/factors; hydrology; soil composition and characteristics; plant community; overall wildlife habitat/use
Sediment/shoreline stabilization	This function relates to the effectiveness of a wetland to stabilize streambanks and shorelines against erosion.	Watershed setting/factors; hydrology; soil composition and characteristics; plant community
Wildlife habitat	This function considers the effectiveness of the wetland to provide habitat for various types and populations of animals typically associated with wetlands and the wetland edge. Both resident and/or migrating species must be considered. Species lists of observed and potential animals should be included in the wetland assessment report.	Watershed setting/factors; hydrology; soil composition and characteristics; plant community; special habitat features; overall wildlife habitat/use; rare species habitat; invasive species; incidental wildlife observations
Fish and shellfish habitat	This function considers the effectiveness of seasonal or permanent waterbodies associated with the wetland in question for fish and shellfish habitat.	Watershed setting/factors; hydrology; soil composition and characteristics; plant community; special habitat features; overall wildlife habitat; rare species habitat; invasive species
Rare species habitat	This value relates to the effectiveness of the wetland or associated waterbodies to support threatened, endangered, or other rare species.	Rare species habitat (mapped Priority Habitat and Core Area habitat and IPaC results)

<sup>\*</sup> Generally adapted from USACE New England District, 1995: The Highway Methodology Workbook Supplement, Wetland Functions and Values, A Descriptive Approach, NEDEP-360-1-30a

Table 6-13: Reach 5A Floodplain Upland Habitat Characterization

Parameter	Description of Parameter	Reach 5A Inventory Approach*
Mapping and classification	Mapping of physical location and limits; natural community cover type classification and delineation	Woodlot 2002 Ecological Characterization mapping and classification in Reach 5A; aerial photograph interpretation and updated LiDAR mapping; 2022 field surveys to confirm mapping and obtain data for Form FP-1
Hydrogeologic setting	Surficial geology	USGS surficial geology information; U.S. Department of Agriculture (USDA) Natural Resource Conservation Service (NRCS) soil survey mapping
Hydrology/drainage characteristics	Degree of surface flooding; connectivity to adjacent wetlands, river or other surface water flow	Consolidate existing information (from sources below); Federal Emergency Management Agency Flood (FEMA) Flood Insurance Study (FIS); 2022 field surveys to obtain data for Form FP-1
Soil composition and characteristics	Soil profile description; soils series as mapped by the USDA NRCS.	USDA NRCS soil survey mapping; consolidate other existing information (from sources below); 2022 field surveys to obtain data for Form FP-1
Plant community	Plant species by community type; density/diversity and interspersion of plant community cover types	Consolidate existing information (from sources below); 2022 field surveys to obtain data for Form FP-1
Overall wildlife habitat/use	Wildlife use; habitat suitability	Consolidate existing information (from sources below); 2022 field surveys to obtain data for Form FP-1; incidental wildlife observations
Special habitat features	Wolf trees; standing dead timber; tree cavities; large woody debris; turtle hibernacula or nesting sites	Consolidate existing information (from sources below); 2022 field surveys to obtain data for Form FP-1
Rare species habitat	Priority Habitat/Core Area Habitat mapping; IPaC results from USFWS on-line data base	MNHESP investigations and designations (including updated outreach to MNHESP; IPaC results; 2022 field surveys to obtain data for Form FP-1
Invasive species	Invasive plant species as designated by ACOE New England District or MIPAG	Review of invasive plant species lists from USACE New England District and MIPAG; consolidate existing information (from sources below); 2022 field surveys to map invasive species and obtain data for Form FP-1

<sup>\*</sup> The existing information used for the Reach 5A floodplain upland habitat characterization includes information from the following sources: the 2002 Woodlot Ecological Characterization reports, the 2003 RFI Report, the 2010 example area evaluations and RCMS Report, the MNHESP investigations of state-listed species through 2012, the Reach 5A vernal pool investigations; and the Final Accessibility Report – all described and referenced in Section 2 of the Reach 5A BRA Work Plan – as well as the USDA NRCS soil surveys, USGS surficial geology mapping, and; FEMA FIS.

Table 6-14: Reach 5A Plant Species in Upland Natural Communities Summary Data

Layer	Common Name	Scientific Name	Status¹	Occurrence (Number of Plots N=26)
Tree	American beech	Fagus grandifolia	Native	3
Species	American bladdernut	Staphylea trifolia	Native	1
	American elm	Ulmus americana	Native	2
	American hornbeam	Carpinus caroliniana	Native	10
	American linden	Tilia americana	Native	8
	American yew	Taxus canadensis	Native	1
	Bitternut hickory	Carya cordiformis	Native	1
	Black cherry	Prunus serotina	Native	5
	Boxelder maple	Acer negundo	Native	2
	Butternut	Juglans cinerea	Native	1
	Common hackberry	Celtis occidentalis	Native	1
	Eastern cottonwood	Populus deltoides	Native	3
	Eastern hemlock	Tsuga canadensis	Native	2
	Eastern white pine	Pinus strobus	Native	6
	Gray birch	Betula populifolia	Native	1
	Green ash	Fraxinus pennsylvanica	Native	1
	Hickory	Carya sp.	Native	2
	Hop-hornbeam	Ostrya virginiana	Native	4
	Northern red oak	Quercus rubra	Native	4
	Paper birch	Betula papyrifera	Native	1
	Quaking aspen	Populus tremuloides	Native	2
	Red maple	Acer rubrum	Native	3
	Silver maple	Acer saccharinum	Native	1
	Slippery elm	Ulmus rubra	Native	1
	Sugar maple	Acer saccharum	Native	5
	Sweet birch	Betula lenta	Native	3
	White ash	Fraxinus americana	Native	4
	Yellow birch	Betula alleghaniensis	Native	1
Shrub	American hazelnut	Corylus americana	Native	1
Species	American witch hazel	Hamamelis virginiana	Native	2
	Autumn olive	Elaeagnus umbellata	Invasive <sup>A,B,C</sup>	3
	Blackberry	Rubus allegheniensis	Native	1
	Burning bush	Euonymus alatus	Invasive <sup>A,B,C</sup>	3
	Canada serviceberry	Amelanchier canadensis	Native	1
	European buckthorn	Rhamnus cathartica	Invasive <sup>A,B,C</sup>	7
	Japanese barberry	Berberis thunbergii	Invasive <sup>A,B,C</sup>	2
	Morrow's honeysuckle	Lonicera morrowii	Invasive <sup>A,B</sup>	10

Table 6-14: Reach 5A Plant Species in Upland Natural Communities Summary Data (continued)

Layer	Common Name	Scientific Name	Status¹	Occurrence (Number of Plots N=26)
<u> Layo.</u>	Multiflora rose	Rosa multiflora	Invasive <sup>A,B,C</sup>	1
	Pussy willow	Salix disolor	Native	2
	Red raspberry	Rubus idaeus	Native	1
	Silky dogwood	Cornus amomum	Native	6
	Speckled alder	Alnus incana	Native	1
	Spicebush	Lindera bensoin	Native	1
	Swamp rose	Rosa palustris	Native	 1
Woody Vine	Asian bittersweet	Celastrus orbiculatus	Invasive <sup>A,B,C</sup>	9
Species	Poison ivy	Toxicodendron radicans	Native	6
	River grape	Vitis riparia	Native	8
	Virginia creeper	Parthenocissus quinquefolia	Native	5
	Virgin's-bower	Clematis virginiana	Native	2
Herb, Forb	Avens	Geum sp.	Native	 1
and Grass	Bedstraw	Galium aparine	Native	3
Species	Bedstraw	Galium sp.	Native	1
	Bladder campion	Silene vulgaris	Non-native	1
	Bladder sedge	Carex intumescens	Native	1
	Blue cohosh	Caulophyllum thalictroides	Native	4
	Branched scouring-rush	Equisetum scirpoides	Native	1
	Brown knapweed	Centaurea jacea	Non-native	1
	Canada goldenrod	Solidago canadensis	Native	9
	Canada wood nettle	Laportea canadensis	Native	1
	Chickweed	Cerastium arvense	Non-native	1
	Christmas fern	Polystichum acrostichoides	Native	1
	Common dandelion	Taraxacum officinale	Non-native	1
	Common milkweed	Asclepias syriaca	Native	2
	Common St. John's-wort	Hypericum perforatum	Native	1
	Common Strawberry	Fragaria virginiana	Native	2
	Eastern woodland sedge	Carex blanda	Native	1
	Enchanter's-nightshade	Circaea canadensis	Native	1
	Germander speedwell	Veronica chamaedrys	Non-native	1
	Grass-leaved-goldenrod	Euthamia graminifolia	Native	1
	Green-headed coneflower	Rudbeckia laciniata	Native	1
	Hedge bindweed	Calystegia sepium	Native	1
	Hemp dogbane	Apocynum cannabinum	Native	1
	Hemp-nettle	Galeopsis bifida	Non-native	1
	Jewelweed	Impatiens capensis	Native	3

Table 6-14: Reach 5A Plant Species in Upland Natural Communities Summary Data (continued)

Layer	Common Name	Scientific Name	Status¹	Occurrence (Number of Plots N=26)
	Jumpseed	Persicaria virginiana	Native	3
	Marsh bedstraw	Galium palustre	Native	2
	Meadow horsetail	Equisetum pratense	Native	2
	Moneywort	Lysimachia nummularia	Invasive <sup>A</sup>	1
	Morning-glory	Ipomoea purpurea	Non-native	1
	Narrow leaf plantain	Plantago lanceolata Parathelypteris	Non-native	1
	New York Fern	noveboracensis	Native	1
	Northern maidenhair fern	Adiantum pedatum	Native	1
	Ostrich fern	Matteuccia struthiopteris	Native	4
	Partridge berry	Mitchella repens	Native	1
	Path rush	Juncus tenuis	Native	2
	Pennsylvania sedge	Carex pensylvanica	Native	2
	Purple loosestrife	Lythrum salicaria	Invasive <sup>A,B,C</sup>	1
	Purple-stemmed aster	Symphyotrichum puniceum	Native	1
	Queen Anne's Lace	Daucus carota	Non-native	1
	Reed canary grass	Phalaris arundinacea	Invasive <sup>A,B,C</sup>	2
	Rough bedstraw	Galium asprellum	Native	2
	Sensitive fern	Onoclea sensibilis	Native	6
	Skunk cabbage	Symplocarpus foetidus	Native	2
	Slender yellow wood sorrel	Oxalis dillenii	Native	1
	Soapwort	Saponaria officinalis	Non-native	1
	Solomon's seal	Polygonatum sp.	Native	1
	Stinging nettle	Urtica dioica	Native	1
	Sweet wood-reed	Cinna arundinacea	Native	1
	Three-leaved goldthread	Coptis trifolia	Native	1
	Tree-clubmoss	Dendrolycopodium obscurum	Native	1
	Violet	Viola sp.	Native	1
	White avens	Geum canadense	Native	1
	Whorled bedstraw	Galium mollugo	Native	1
	Woodfern	Dryopteris carthusiana	Native	1
	Wrinkled-leaved goldenrod	Solidago rugosa	Native	2
Bryophytes	Haircap moss	Polytrichum commune Invasive: C=ACOE Invasive: D=MIF	Native	1

<sup>&</sup>lt;sup>1</sup>Invasive Ratings: A= MIPAG Invasive; B=IPANE Invasive; C=ACOE Invasive; D=MIPAG Likely Invasive

Table 6-15: Percent Cover of Trees, Shrubs, Woody Vines, Herbs, and Mosses Estimated within Upland Natural Community Cover Types

		Northern hardwoods- hemlock-white pine forest	Red oak-sugar maple transition forest	Successional Northern Hardwoods	Cultural grasslands/ Agriculture
	Count	3	2	3	10
Trees	Min	63.0	38.0	63.0	0.0
_	Max	98.0	38.0	85.5	20.5
	Mean	86.3	38.0	78.0	5.2
	±SE	11.7	0.0	7.5	2.8
Shrubs	Min	10.5	20.5	10.5	0.0
_	Max	20.5	85.5	63.0	85.5
_	Mean	13.8	53.0	45.5	22.4
<del>-</del>	±SE	3.3	32.5	17.5	9.6
Woody	Min	0.0	3.0	20.5	0.0
/ines	Max	63.0	3.0	20.5	38.0
_	Mean	21.0	3.0	20.5	7.8
	±SE	21.0	0.0	0.0	3.9
Herbs	Min	3.0	20.5	0.0	10.5
_	Max	38.0	63.0	10.5	98.0
_	Mean	20.5	41.8	4.5	84.3
	±SE	10.1	21.3	3.1	8.4
Mosses	Min	0.0	0.0	0.0	0.0
_	Max	38.0	0.0	10.5	3.0
_	Mean	12.7	0.0	3.5	0.6
·-	±SE	12.7	0.0	3.5	0.4

Table 6-16: Reach 5A Upland Natural Communities –Biotic Habitat Features

	V	Vildlife Foo	od <sup>1</sup>						Cover/Pero	ches/Basking/[	enning/N	lesting Ha	bitat <sup>1</sup>						
Plot_ID	Wetland and Aquatic Food	Upland Food	Shrub thickets with earthworm habitat	Live or Dead Trees >30" DBH	Standing Dead Trees with Cavities and Perches	Cavities in trunks or limbs of Live Trees	Small Mammal Burrows	Shrubs and/or Herbs for bird nesting	Sandy soils suitable for turtle nesting	Other Wildlife Dens/Nests	Dense Herb Cover	Large Woody Debris	Rocks, Crevices, Logs, Roots at Water Edge	Live or Dead Tall Veg. OH/Near Water	Persistent emergent wetland vegetation	Fine-leaved emergent vegetation	Depressions serving as vernal pools	Standing water Present at least part of the growing season	Four -toed salamander habitat
5	N/A	$\sqrt{}$	Ø	√	V	V	Ø	Ø	Ø	Ø	Ø	V	Ø	N/A	Ø	Ø	N/A	N/A	N/A
18	N/A	*	Ø	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	Ø	Ø	Ø	Ø	Ø	N/A	N/A
31	N/A	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	N/A
32	N/A	$\sqrt{}$	V	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	Ø	Ø	Ø	Ø	Ø	N/A	N/A
33	N/A	$\sqrt{}$	V	Ø	Ø	Ø	$\sqrt{}$		Ø	V	*	Ø	Ø	Ø	Ø	Ø	Ø	N/A	N/A
34	N/A	*	V	Ø	V	V	V		Ø	V	V	V	Ø	V	Ø	Ø	Ø	N/A	N/A
35	N/A	V	V	Ø	V	V	V		Ø	Ø	Ø	V	V	V	Ø	Ø	Ø	N/A	N/A
36	N/A	$\sqrt{}$	V	Ø	Ø	Ø	Ø		Ø	Ø	V	Ø	Ø	Ø	Ø	Ø	Ø	N/A	N/A
63	N/A	$\sqrt{}$	V	Ø	Ø	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	Ø	Ø	V	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	N/A	N/A
76	N/A	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	Ø	Ø	Ø	Ø	Ø	N/A	N/A
77	N/A	Ø	Ø	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	Ø	Ø	Ø	Ø	Ø	N/A	N/A
78	N/A	V	Ø	Ø	Ø	Ø	Ø	*	Ø	Ø	*	Ø	Ø	*	Ø	Ø	Ø	N/A	N/A
80	N/A	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	Ø	N/A	N/A
89	N/A	$\sqrt{}$	V	Ø	V	V	Ø	Ø	Ø	Ø	Ø	V		Ø	Ø	Ø	Ø	Ø	N/A
93	N/A	$\sqrt{}$	V	Ø	Ø	Ø	Ø	*	Ø	Ø	*	V		Ø	Ø	Ø	Ø	N/A	N/A
98	N/A	$\sqrt{}$	V	Ø	V	Ø	Ø		Ø	Ø	Ø	V		Ø	Ø	Ø			N/A
133	N/A	$\sqrt{}$	Ø	Ø	$\sqrt{}$	$\sqrt{}$	Ø	$\sqrt{}$	Ø	Ø	Ø	$\sqrt{}$	$\sqrt{}$	Ø	Ø	Ø	Ø	N/A	N/A
135	N/A	$\sqrt{}$	V	Ø	V	$\sqrt{}$	$\sqrt{}$	√	Ø	Ø	V	Ø	$\sqrt{}$	$\sqrt{}$	Ø	Ø	Ø	N/A	N/A
145	N/A	$\sqrt{}$	Ø	Ø	Ø	Ø	Ø	V	Ø	Ø	*	Ø	Ø	Ø	Ø	Ø	Ø	N/A	N/A
154	N/A	$\sqrt{}$	Ø	$\checkmark$	V	$\sqrt{}$	Ø	V	Ø	Ø	Ø	$\sqrt{}$	V	$\sqrt{}$	Ø	Ø	Ø	N/A	N/A
166	N/A	$\sqrt{}$	$\sqrt{}$	Ø	Ø	Ø	Ø	$\sqrt{}$	Ø	Ø	*	Ø	Ø	Ø	Ø	Ø	Ø	N/A	N/A
167	N/A	$\sqrt{}$	V	Ø	Ø	V	$\sqrt{}$		Ø	Ø	*	V		Ø	Ø	Ø	Ø	N/A	N/A

<sup>&</sup>lt;sup>1</sup>See Table 6-17 for wildlife associations with listed habitat features

<sup>\*=</sup>Abundant; √=Present; Ø=Absent

Table 6-17: Reach 5A Upland Natural Communities: Summary of Biotic Habitat Features

Habitat Feature	Wildlife Use	% of Stations Abundant	% of Stations Present	% of Stations Absent
Wetland and Aquatic Food	Overall food	0	0	0
Upland Food	Overall food	9	82	9
Shrub thickets with earthworm habitat	Game foraging habitat (e.g., American woodcock)	0	55	45
Live or Dead Trees >30" DBH	Cover/perching/nesting	0	9	91
Standing Dead Trees with Cavities and Perches	Cavities/perching/breeding/nesting/feeding	0	36	64
Cavities in trunks or limbs of Live Trees	Cavities/perching/breeding/nesting	0	41	59
Small Mammal Burrows	Hibernation/breeding/nesting/escape/cover	0	27	73
Shrub and/or herbaceous vegetation	Suitable for birds such as veery nesting	27	59	14
Open sandy to gravelly soils with sparse vegetation	Turtle nesting habitat	0	0	100
Other Wildlife Dens/Nests	Hibernation/breeding/nesting/escape/cover	0	9	91
Dense Herb Cover	Voles, small mammals, amphibians, reptiles	45	18	36
Large Woody Debris on the ground	Small mammals, amphibians, reptiles, invertebrate emergence	0	45	55
Rocks, Crevices, Logs, Roots at Water Edge	Turtles, snakes, frogs, invertebrate emergence	0	36	64
Live or dead vegetation overhanging and/or near water	Habitat offering good visibility of open water for, e.g., osprey, kingfisher, flycatchers, cedar waxwings. Vegetation closer to ground for turtles, snakes, frogs, wading birds, wood duck, mink, raccoon	5	18	73
Persistent emergent wetland vegetation at least seasonally flooded during the growing season	Habitat for American bittern, wood duck, green heron, black-crowned night heron, rails (sora, king, Virginia), moorhen, coot, pie-billed grebe, etc.	0	0	100
Fine-leaved emergent vegetation (Grasses and sedges) at least seasonally flooded during the growing season	Habitat for common snipe, spotted sandpiper, sedge wren, least bittern, common moorhen	0	0	100
Depressions serving as vernal pools	Turtles, snakes, frogs, invertebrate emergence	0	5	91
Standing water present at least part of the growing season	Amphibians, turtles, foraging waterfowl, non-breeding amphibians and reptiles (foraging, re-hydration)	0	5	9
Sphagnum hummocks or mats, moss-covered logs or saturated logs, overhanging or directly adjacent to pools of standing water in spring	Habitat for four-toed salamander	0	0	0

Table 6-18: State-Listed Rare Species Potentially Associated with Floodplain Upland Habitats in Reach 5A

Scientific Name	Common Name	State Status
Ranunculus pensylvanicus	Bristly Buttercup	Special Concern
Veronicastrum virginicum	Culver's-Root	Threatened
Eragrostis frankii	Frank's Lovegrass	Special Concern
Carex grayi	Gray's Sedge	Threatened
Rhododendron maximum	Great Laurel	Threatened
Elymus villosus	Hairy Wild Rye	Endangered
Pieris oleracea	Mustard White	Threatened
Papaipema sp. 2	Ostrich Fern Borer	Special Concern
Malaxis monophyllos ssp. brachypoda	White Adder's-Mouth	Endangered
Glyptemys insculpta	Wood Turtle	Special Concern
Myotis septentrionalis	Northern Long-Eared Bat	Endangered

Table 6-19: Reach 5A Floodplain Upland Function Assessment Factors

Function	Description of Function	Parameters Considered in Assessing Function
Groundwater recharge	Infiltration/recharge of surface water to groundwater, especially during flood or high runoff events	Hydrogeologic setting; soil composition and characteristics; hydrology/drainage characteristics; plant community
Flood storage and desynchronization	Floodwater dynamics (flood flow amelioration, flood storage and desynchronization, peak rate control)	Hydrology/drainage characteristics; plant community
Corridor ecological connectivity	Capacity to contribute to ecological corridor connectivity along the riparian zone	Mapping and classification; plant community; overall wildlife habitat/use; rare species habitat
Buffer capacity	Capacity to buffer adjacent wetland and water habitats from nearby development	Soil composition and characteristics; plant community
Overall wildlife habitat	Habitat suitability for diverse wildlife at various trophic levels and all life stages	Plant community; presence of special habitat features; overall wildlife habitat/use; rare species habitat; invasive species; incidental wildlife observations
Rare species habitat	Designated rare species habitat per MNHESP and USFWS	Rare species habitat (mapped Priority Habitat and Core Area habitat and IPaC results)

#### **Table 6-20: Canoe Meadows Bird Observations**

This list has been generated from Canoe Meadows information provided on the MAS website as well as the listing for Canoe Meadows observations provided at "ebird.org": <u>Canoe Meadows Wildlife Sanctuary</u>, <u>Pittsfield, Berkshire County, MA, US - eBird Hotspot</u>. This listing indicates over 180 species of birds that have directly been observed within Canoe Meadows, much of which is located within Reach 5A.

Scolopax minor         American woodcock           Haliaeetus leucocephalus         Bald eagle           Icterus galbula         Baltimore oriole           Riparia riparia         Bank swallow           Hirundo rustica         Barn swallow           Strix varia         Barred owl           Megaceryle alcyon         Belted kingfisher           Mniotilta varia         Black-and-white warbler           Coccyzus erythropthalmus         Black-billed cuckoo           Setophaga fusca         Black-billed cuckoo           Setophaga fusca         Black-billed cuckoo           Setophaga fusca         Black-capped chickadee           Nycticorax nycticorax         Black-capped chickadee           Nycticorax nycticorax         Black-crowned night heron           Setophaga striata         Black-poll warbler           Setophaga caerulescens         Black-throated blue warbler           Setophaga virens         Black-throated preen warbler           Cyanocitta cristata         Blue jay           Polioptila carulea         Blue-jaray gnatcatcher           Vireo solitarius         Blue-jaray gnatcatcher           Vireo solitarius         Blue-winged warbler           Dolichonyx onyzivorus         Bobolink           Bute- winged warbler	Scientific Name	Common Name
Icterus galbula   Baltimore oriole   Riparia riparia   Bank swallow   Hirundo rustica   Barn swallow   Strix varia   Barred owl   Megaceryle alcyon   Belted kingfisher   Mniotilta varia   Black-and-white warbler   Coccyzus erythropthalmus   Black-billed cuckoo   Setophaga fusca   Black-capped chickadee   Nycticorax nycticorax   Black-crowned night heron   Setophaga striata   Black-throated blue warbler   Setophaga virens   Black-throated green warbler   Cyanocitta cristata   Blue-gray gnatcatcher   Vireo solitarius   Blue-headed vireo   Spatula discors   Blue-winged warbler   Blue-winged warbler   Dolichonyx oryzivorus   Broad-winged hawk   Certhia americana   Brown creeper   Toxostoma rufum   Brown thrasher   Brown-headed cowbird   Brombycilla cedrorum   Cedar waxwing   Setophaga pensylvanica   Chestnut-sided warbler   Chaetura pelagica   Chimney swift   Spizella passerina   Chipping sparrow   Petrochelidon pyrrhonota   Cumon goldeneye   Common g	Scolopax minor	American woodcock
Riparia riparia Bank swallow  Hirundo rustica Barn swallow  Strix varia Barred owl  Megaceryle alcyon Belted kingfisher  Mniotilta varia Black-and-white warbler  Coccyzus erythropthalmus Black-billed cuckoo  Setophaga fusca Blackburnian warbler  Poecile atricapillus Black-capped chickadee  Nycticorax nycticorax Black-crowned night heron  Setophaga striata Blackpoll warbler  Setophaga virens Black-throated blue warbler  Cyanocitta cristata Blue jay  Polioptila caerulea Blue-gray gnatcatcher  Vireo solitarius Blue-winged teal  Vermivora cyanoptera Blue-winged warbler  Dolichonyx oryzivorus Bobolink  Buteo platypterus Broad-winged hawk  Certhia americana Brown creeper  Toxostoma rufum Brown thrasher  Molothrus ater Brown-headed cowbird  Branta canadensis Canada goose  Cardellina canadensis Canada warbler  Betophaga cerulea Cerulean warbler  Setophaga pensylvanica Chestnut-sided warbler  Chaetura pelagica Chimney swift  Spizella passerina Ciliff swallow  Tyto alba Common goldeneye	Haliaeetus leucocephalus	Bald eagle
Hirundo rustica Barn swallow  Strix varia Barred owl  Megaceryle alcyon Belted kingfisher  Mniotilta varia Black-and-white warbler  Coccyzus erythropthalmus Black-billed cuckoo  Setophaga fusca Blackburnian warbler  Poecile atricapillus Black-capped chickadee  Nycticorax nycticorax Black-crowned night heron  Setophaga striata Blackpoll warbler  Setophaga caerulescens Black-throated blue warbler  Setophaga virens Black-throated green warbler  Cyanocitta cristata Blue jay  Polioptila caerulea Blue-gray gnatcatcher  Vireo solitarius Blue-winged teal  Vermivora cyanoptera Blue-winged warbler  Dolichonyx oryzivorus Bobolink  Buteo platypterus Broad-winged hawk  Certhia americana Brown creeper  Toxostoma rufum Brown thrasher  Molothrus ater Brown-headed cowbird  Branta canadensis Canada goose  Cardellina canadensis Canada warbler  Bombycilla cedrorum Cedar waxwing  Setophaga pensylvanica Chestnut-sided warbler  Chaetura pelagica Chimney swift  Spizella passerina Ciliff swallow  Tyto alba Common goldeneye	Icterus galbula	Baltimore oriole
Strix varia         Barred owl           Megaceryle alcyon         Belted kingfisher           Mniotilta varia         Black-and-white warbler           Coccyzus erythropthalmus         Black-billed cuckoo           Setophaga fusca         Black-billed cuckoo           Poecile atricapillus         Black-capped chickadee           Nycticorax nycticorax         Black-crowned night heron           Setophaga striata         Black-poll warbler           Setophaga caerulescens         Black-throated blue warbler           Setophaga virens         Black-throated green warbler           Cyanocitta cristata         Blue jay           Polioptila caerulea         Blue-gray gnatcatcher           Vireo solitarius         Blue-headed vireo           Spatula discors         Blue-winged teal           Vermivora cyanoptera         Blue-winged warbler           Dolichonyx oryzivorus         Bobolink           Buteo platypterus         Broad-winged hawk           Certhia americana         Brown creeper           Toxostoma rufum         Brown thrasher           Molothrus ater         Brown-headed cowbird           Branta canadensis         Canada warbler           Cardellina canadensis         Canada warbler           Setophaga pensylvanica	Riparia riparia	Bank swallow
Megaceryle alcyon         Belted kingfisher           Mniotilta varia         Black-and-white warbler           Coccyzus erythropthalmus         Black-billed cuckoo           Setophaga fusca         Blackburnian warbler           Poecile atricapillus         Black-capped chickadee           Nycticorax nycticorax         Black-crowned night heron           Setophaga striata         Black-poll warbler           Setophaga caerulescens         Black-throated blue warbler           Setophaga virens         Blue-kethroated green warbler           Cyanocitta cristata         Blue jay           Polioptila caerulea         Blue-gray gnatcatcher           Vireo solitarius         Blue-headed vireo           Spatula discors         Blue-winged teal           Vermivora cyanoptera         Blue-winged warbler           Dolichonyx oryzivorus         Bobolink           Buteo platypterus         Broad-winged hawk           Certhia americana         Brown thrasher           Molothrus ater         Brown thrasher           Molothrus ater         Brown-headed cowbird           Branta canadensis         Canada goose           Cardellina canadensis         Canada warbler           Bombycilla cedrorum         Cedar waxwing           Setophaga pensylvanica </td <td>Hirundo rustica</td> <td>Barn swallow</td>	Hirundo rustica	Barn swallow
Mniotilta varia         Black-and-white warbler           Coccyzus erythropthalmus         Black-billed cuckoo           Setophaga fusca         Black-capped chickadee           Poecile atricapillus         Black-capped chickadee           Nycticorax nycticorax         Black-crowned night heron           Setophaga striata         Black-poll warbler           Setophaga caerulescens         Black-throated blue warbler           Setophaga virens         Black-throated green warbler           Cyanocitta cristata         Blue jay           Polioptila caerulea         Blue-gray gnatcatcher           Vireo solitarius         Blue-gray gnatcatcher           Vireo solitarius         Blue-minged teal           Vermivora cyanoptera         Blue-winged warbler           Spatula discors         Blue-winged warbler           Dolichonyx oryzivorus         Bobolink           Buteo platypterus         Broad-winged hawk           Certhia americana         Brown creeper           Toxostoma rufum         Brown thrasher           Molothrus ater         Brown-headed cowbird           Branta canadensis         Canada goose           Cardellina canadensis         Canada warbler           Bombycilla cedrorum         Cedar waxwing           Setophaga pensylva	Strix varia	Barred owl
Setophaga fusca Black-billed cuckoo Setophaga fusca Blackburnian warbler Poecile atricapillus Black-capped chickadee Nycticorax nycticorax Black-crowned night heron Setophaga striata Blackpoll warbler Setophaga caerulescens Black-throated blue warbler Setophaga virens Black-throated green warbler Cyanocitta cristata Blue jay Polioptila caerulea Blue-gray gnatcatcher Vireo solitarius Blue-headed vireo Spatula discors Blue-winged teal Vermivora cyanoptera Blue-winged warbler Dolichonyx oryzivorus Bobolink Buteo platypterus Broad-winged hawk Certhia americana Brown creeper Toxostoma rufum Brown thrasher Molothrus ater Brown-headed cowbird Branta canadensis Canada goose Cardellina canadensis Canada warbler Bombycilla cedrorum Cedar waxwing Setophaga cerulea Cerulean warbler Setophaga pensylvanica Chestnut-sided warbler Chaetura pelagica Chimney swift Tyto alba Common goldeneye	Megaceryle alcyon	Belted kingfisher
Setophaga fusca Poecile atricapillus Black-capped chickadee Nycticorax nycticorax Black-crowned night heron Setophaga striata Black-pll warbler Setophaga caerulescens Black-throated blue warbler Setophaga virens Black-throated green warbler Cyanocitta cristata Blue jay Polioptila caerulea Blue-gray gnatcatcher Vireo solitarius Blue-headed vireo Spatula discors Blue-winged teal Vermivora cyanoptera Blue-winged warbler Dolichonyx onyzivorus Bobolink Buteo platypterus Broad-winged hawk Certhia americana Brown creeper Toxostoma rufum Brown thrasher Molothrus ater Branta canadensis Canada goose Cardellina canadensis Canada warbler Bombycilla cedrorum Cedar waxwing Setophaga cerulea Setophaga pensylvanica Chimney swift Spizella passerina Chipping sparrow Petrochelidon pyrrhonota Tyto alba Common goldeneye	Mniotilta varia	Black-and-white warbler
Poecile atricapillus  Nycticorax nycticorax  Black-crowned night heron  Setophaga striata  Blackpoll warbler  Setophaga caerulescens  Black-throated blue warbler  Setophaga virens  Cyanocitta cristata  Blue jay  Polioptila caerulea  Nycticorax  Blue-gray gnatcatcher  Setophaga virens  Blue-headed vireo  Spatula discors  Blue-winged teal  Vermivora cyanoptera  Blue-winged warbler  Dolichonyx oryzivorus  Bobolink  Buteo platypterus  Brown creeper  Toxostoma rufum  Brown thrasher  Molothrus ater  Brown-headed cowbird  Branta canadensis  Canada goose  Cardellina canadensis  Canada warbler  Setophaga cerulea  Setophaga pensylvanica  Chaetura pelagica  Chimney swift  Spizella passerina  Petrochelidon pyrrhonota  Tyto alba  Common goldeneye	Coccyzus erythropthalmus	Black-billed cuckoo
Nycticorax nycticorax         Black-crowned night heron           Setophaga striata         Blackpoll warbler           Setophaga caerulescens         Black-throated blue warbler           Setophaga virens         Black-throated green warbler           Cyanocitta cristata         Blue jay           Polioptila caerulea         Blue-gray gnatcatcher           Vireo solitarius         Blue-headed vireo           Spatula discors         Blue-winged teal           Vermivora cyanoptera         Blue-winged warbler           Dolichonyx oryzivorus         Bobolink           Buteo platypterus         Broad-winged hawk           Certhia americana         Brown creeper           Toxostoma rufum         Brown thrasher           Molothrus ater         Brown-headed cowbird           Branta canadensis         Canada goose           Cardellina canadensis         Canada warbler           Bombycilla cedrorum         Cedar waxwing           Setophaga cerulea         Cerulean warbler           Setophaga pensylvanica         Chestnut-sided warbler           Chaetura pelagica         Chimney swift           Spizella passerina         Chipping sparrow           Petrochelidon pyrrhonota         Cliff swallow           Tyto alba         Common barn o	Setophaga fusca	Blackburnian warbler
Setophaga striataBlackpoll warblerSetophaga caerulescensBlack-throated blue warblerSetophaga virensBlack-throated green warblerCyanocitta cristataBlue jayPolioptila caeruleaBlue-gray gnatcatcherVireo solitariusBlue-headed vireoSpatula discorsBlue-winged tealVermivora cyanopteraBlue-winged warblerDolichonyx oryzivorusBobolinkButeo platypterusBroad-winged hawkCerthia americanaBrown creeperToxostoma rufumBrown thrasherMolothrus aterBrown-headed cowbirdBranta canadensisCanada gooseCardellina canadensisCanada warblerBombycilla cedrorumCedar waxwingSetophaga ceruleaCerulean warblerSetophaga pensylvanicaChestnut-sided warblerChaetura pelagicaChimney swiftSpizella passerinaChipping sparrowPetrochelidon pyrrhonotaCliff swallowTyto albaCommon barn owlBucephala clangulaCommon goldeneye	Poecile atricapillus	Black-capped chickadee
Setophaga caerulescensBlack-throated blue warblerSetophaga virensBlack-throated green warblerCyanocitta cristataBlue jayPolioptila caeruleaBlue-gray gnatcatcherVireo solitariusBlue-headed vireoSpatula discorsBlue-winged tealVermivora cyanopteraBlue-winged warblerDolichonyx oryzivorusBobolinkButeo platypterusBroad-winged hawkCerthia americanaBrown creeperToxostoma rufumBrown thrasherMolothrus aterBrown-headed cowbirdBranta canadensisCanada gooseCardellina canadensisCanada warblerBombycilla cedrorumCedar waxwingSetophaga ceruleaCerulean warblerSetophaga pensylvanicaChestnut-sided warblerChaetura pelagicaChimney swiftSpizella passerinaChipping sparrowPetrochelidon pyrrhonotaCliff swallowTyto albaCommon barn owlBucephala clangulaCommon goldeneye	Nycticorax nycticorax	Black-crowned night heron
Setophaga virens Cyanocitta cristata Blue jay  Polioptila caerulea Blue-gray gnatcatcher Vireo solitarius Blue-headed vireo Spatula discors Blue-winged teal Vermivora cyanoptera Blue-winged warbler Dolichonyx oryzivorus Bobolink Buteo platypterus Broad-winged hawk Certhia americana Brown creeper Toxostoma rufum Brown thrasher Molothrus ater Brown-headed cowbird Branta canadensis Canada goose Cardellina canadensis Canada warbler Bombycilla cedrorum Cedar waxwing Setophaga cerulea Cerulean warbler Chaetura pelagica Chimney swift Spizella passerina Petrochelidon pyrrhonota Common barn owl Bucephala clangula Common goldeneye	Setophaga striata	Blackpoll warbler
Cyanocitta cristata       Blue jay         Polioptila caerulea       Blue-gray gnatcatcher         Vireo solitarius       Blue-headed vireo         Spatula discors       Blue-winged teal         Vermivora cyanoptera       Blue-winged warbler         Dolichonyx oryzivorus       Bobolink         Buteo platypterus       Broad-winged hawk         Certhia americana       Brown creeper         Toxostoma rufum       Brown thrasher         Molothrus ater       Brown-headed cowbird         Branta canadensis       Canada goose         Cardellina canadensis       Canada warbler         Bombycilla cedrorum       Cedar waxwing         Setophaga cerulea       Cerulean warbler         Setophaga pensylvanica       Chestnut-sided warbler         Chaetura pelagica       Chimney swift         Spizella passerina       Chipping sparrow         Petrochelidon pyrrhonota       Cliff swallow         Tyto alba       Common barn owl         Bucephala clangula       Common goldeneye	Setophaga caerulescens	Black-throated blue warbler
Polioptila caerulea  Vireo solitarius  Blue-headed vireo  Spatula discors  Blue-winged teal  Vermivora cyanoptera  Blue-winged warbler  Dolichonyx oryzivorus  Bobolink  Buteo platypterus  Broad-winged hawk  Certhia americana  Brown creeper  Toxostoma rufum  Brown-headed cowbird  Branta canadensis  Canada goose  Cardellina canadensis  Canada warbler  Bombycilla cedrorum  Cedar waxwing  Setophaga cerulea  Setophaga pensylvanica  Chestnut-sided warbler  Chaetura pelagica  Spizella passerina  Cemmon barn owl  Bucephala clangula  Common goldeneye	Setophaga virens	Black-throated green warbler
Vireo solitariusBlue-headed vireoSpatula discorsBlue-winged tealVermivora cyanopteraBlue-winged warblerDolichonyx oryzivorusBobolinkButeo platypterusBroad-winged hawkCerthia americanaBrown creeperToxostoma rufumBrown thrasherMolothrus aterBrown-headed cowbirdBranta canadensisCanada gooseCardellina canadensisCanada warblerBombycilla cedrorumCedar waxwingSetophaga ceruleaCerulean warblerSetophaga pensylvanicaChestnut-sided warblerChaetura pelagicaChimney swiftSpizella passerinaChipping sparrowPetrochelidon pyrrhonotaCliff swallowTyto albaCommon barn owlBucephala clangulaCommon goldeneye	Cyanocitta cristata	Blue jay
Spatula discorsBlue-winged tealVermivora cyanopteraBlue-winged warblerDolichonyx oryzivorusBobolinkButeo platypterusBroad-winged hawkCerthia americanaBrown creeperToxostoma rufumBrown thrasherMolothrus aterBrown-headed cowbirdBranta canadensisCanada gooseCardellina canadensisCanada warblerBombycilla cedrorumCedar waxwingSetophaga ceruleaCerulean warblerSetophaga pensylvanicaChestnut-sided warblerChaetura pelagicaChimney swiftSpizella passerinaChipping sparrowPetrochelidon pyrrhonotaCliff swallowTyto albaCommon barn owlBucephala clangulaCommon goldeneye	Polioptila caerulea	Blue-gray gnatcatcher
Vermivora cyanopteraBlue-winged warblerDolichonyx oryzivorusBobolinkButeo platypterusBroad-winged hawkCerthia americanaBrown creeperToxostoma rufumBrown thrasherMolothrus aterBrown-headed cowbirdBranta canadensisCanada gooseCardellina canadensisCanada warblerBombycilla cedrorumCedar waxwingSetophaga ceruleaCerulean warblerSetophaga pensylvanicaChestnut-sided warblerChaetura pelagicaChimney swiftSpizella passerinaChipping sparrowPetrochelidon pyrrhonotaCliff swallowTyto albaCommon barn owlBucephala clangulaCommon goldeneye	Vireo solitarius	Blue-headed vireo
Dolichonyx oryzivorusBobolinkButeo platypterusBroad-winged hawkCerthia americanaBrown creeperToxostoma rufumBrown thrasherMolothrus aterBrown-headed cowbirdBranta canadensisCanada gooseCardellina canadensisCanada warblerBombycilla cedrorumCedar waxwingSetophaga ceruleaCerulean warblerSetophaga pensylvanicaChestnut-sided warblerChaetura pelagicaChimney swiftSpizella passerinaChipping sparrowPetrochelidon pyrrhonotaCliff swallowTyto albaCommon barn owlBucephala clangulaCommon goldeneye	Spatula discors	Blue-winged teal
Buteo platypterusBroad-winged hawkCerthia americanaBrown creeperToxostoma rufumBrown thrasherMolothrus aterBrown-headed cowbirdBranta canadensisCanada gooseCardellina canadensisCanada warblerBombycilla cedrorumCedar waxwingSetophaga ceruleaCerulean warblerSetophaga pensylvanicaChestnut-sided warblerChaetura pelagicaChimney swiftSpizella passerinaChipping sparrowPetrochelidon pyrrhonotaCliff swallowTyto albaCommon barn owlBucephala clangulaCommon goldeneye	Vermivora cyanoptera	Blue-winged warbler
Certhia americanaBrown creeperToxostoma rufumBrown thrasherMolothrus aterBrown-headed cowbirdBranta canadensisCanada gooseCardellina canadensisCanada warblerBombycilla cedrorumCedar waxwingSetophaga ceruleaCerulean warblerSetophaga pensylvanicaChestnut-sided warblerChaetura pelagicaChimney swiftSpizella passerinaChipping sparrowPetrochelidon pyrrhonotaCliff swallowTyto albaCommon barn owlBucephala clangulaCommon goldeneye	Dolichonyx oryzivorus	Bobolink
Toxostoma rufum  Brown thrasher  Molothrus ater  Brown-headed cowbird  Branta canadensis  Canada goose  Cardellina canadensis  Canada warbler  Bombycilla cedrorum  Cedar waxwing  Setophaga cerulea  Cerulean warbler  Setophaga pensylvanica  Chestnut-sided warbler  Chaetura pelagica  Chimney swift  Spizella passerina  Chipping sparrow  Petrochelidon pyrrhonota  Common barn owl  Bucephala clangula  Common goldeneye	Buteo platypterus	Broad-winged hawk
Molothrus aterBrown-headed cowbirdBranta canadensisCanada gooseCardellina canadensisCanada warblerBombycilla cedrorumCedar waxwingSetophaga ceruleaCerulean warblerSetophaga pensylvanicaChestnut-sided warblerChaetura pelagicaChimney swiftSpizella passerinaChipping sparrowPetrochelidon pyrrhonotaCliff swallowTyto albaCommon barn owlBucephala clangulaCommon goldeneye	Certhia americana	Brown creeper
Branta canadensisCanada gooseCardellina canadensisCanada warblerBombycilla cedrorumCedar waxwingSetophaga ceruleaCerulean warblerSetophaga pensylvanicaChestnut-sided warblerChaetura pelagicaChimney swiftSpizella passerinaChipping sparrowPetrochelidon pyrrhonotaCliff swallowTyto albaCommon barn owlBucephala clangulaCommon goldeneye	Toxostoma rufum	Brown thrasher
Cardellina canadensis       Canada warbler         Bombycilla cedrorum       Cedar waxwing         Setophaga cerulea       Cerulean warbler         Setophaga pensylvanica       Chestnut-sided warbler         Chaetura pelagica       Chimney swift         Spizella passerina       Chipping sparrow         Petrochelidon pyrrhonota       Cliff swallow         Tyto alba       Common barn owl         Bucephala clangula       Common goldeneye	Molothrus ater	Brown-headed cowbird
Bombycilla cedrorum       Cedar waxwing         Setophaga cerulea       Cerulean warbler         Setophaga pensylvanica       Chestnut-sided warbler         Chaetura pelagica       Chimney swift         Spizella passerina       Chipping sparrow         Petrochelidon pyrrhonota       Cliff swallow         Tyto alba       Common barn owl         Bucephala clangula       Common goldeneye	Branta canadensis	Canada goose
Setophaga cerulea       Cerulean warbler         Setophaga pensylvanica       Chestnut-sided warbler         Chaetura pelagica       Chimney swift         Spizella passerina       Chipping sparrow         Petrochelidon pyrrhonota       Cliff swallow         Tyto alba       Common barn owl         Bucephala clangula       Common goldeneye	Cardellina canadensis	Canada warbler
Setophaga pensylvanica Chaetura pelagica Chimney swift Spizella passerina Chipping sparrow Petrochelidon pyrrhonota Cliff swallow Tyto alba Common barn owl Bucephala clangula Common goldeneye	Bombycilla cedrorum	Cedar waxwing
Chaetura pelagica       Chimney swift         Spizella passerina       Chipping sparrow         Petrochelidon pyrrhonota       Cliff swallow         Tyto alba       Common barn owl         Bucephala clangula       Common goldeneye	Setophaga cerulea	Cerulean warbler
Spizella passerina       Chipping sparrow         Petrochelidon pyrrhonota       Cliff swallow         Tyto alba       Common barn owl         Bucephala clangula       Common goldeneye	Setophaga pensylvanica	Chestnut-sided warbler
Petrochelidon pyrrhonota  Cliff swallow  Tyto alba  Common barn owl  Bucephala clangula  Common goldeneye	Chaetura pelagica	Chimney swift
Tyto alba Common barn owl  Bucephala clangula Common goldeneye	Spizella passerina	Chipping sparrow
Bucephala clangula Common goldeneye	Petrochelidon pyrrhonota	Cliff swallow
	Tyto alba	Common barn owl
Quiscalus quiscula Common grackle	Bucephala clangula	Common goldeneye
	Quiscalus quiscula	Common grackle

Table 6-20: Canoe Meadows Bird Observations (continued)

Scientific Name	Common Name
Mergus merganser	Common merganser
Gallinula chloropus	Common moorhen
Chordeiles minor	Common nighthawk
Corvus corax	Common raven
Acanthis flammea	Common redpoll
Gallinago gallinago	Common snipe
Geothlypis trichas	Common yellowthroat
Accipiter cooperii	Cooper's hawk
Junco hyemalis	Dark-eyed junco
Phalacrocorax auritus	Double-crested cormorant
Dryobates pubescens	Downy woodpecker
Sialia sialis	Eastern bluebird
Tyrannus tyrannus	Eastern kingbird
Sturnella magna	Eastern meadowlark
Sayornis phoebe	Eastern phoebe
Megascops asio	Eastern screech owl
Pipilo erythrophthalmus	Eastern towhee
Contopus virens	Eastern wood-pewee
Sturnus vulgaris	European starling
Hesperiphona vespertinus	Evening grosbeak
Spizella pusilla	Field sparrow
Regulus satrapa	Golden-crowned kinglet
Vermivora chrysoptera	Golden-winged warbler
Dumetella carolinensis	Gray catbird
Ardea herodias	Great blue heron
Myiarchus crinitus	Great crested flycatcher
Bubo virginianus	Great horned owl
Butorides virescens	Green heron
Anas carolinensis	Green-winged teal
Leuconotopicus villosus	Hairy woodpecker
Ammodramus henslowii	Henslow's sparrow
Catharus guttatus	Hermit thrush
Larus argentatus	Herring gull
Lophodytes cucullatus	Hooded merganser
Eremophila alpestris	Horned lark
Haemorhous mexicanus	House finch
Passer domesticus	House sparrow
Troglodytes aedon	House wren
Passerina cyanea	Indigo bunting
Charadrius vociferus	Killdeer
Rallus elegans	King rail

Table 6-20: Canoe Meadows Bird Observations (continued)

Scientific Name	Common Name
Calcarius Iapponicus	Lapland longspur
Ixobrychus exilis	Least bittern
Empidonax minimus	Least flycatcher
Calidris minutilla	Least sandpiper
Asio otus	Long-eared owl
Parkesia motacilla	Louisiana waterthrush
Setophaga magnolia	Magnolia warbler
Anas platyrhynchos	Mallard
Cistothorus palustris	Marsh wren
Zenaida macroura	Mourning dove
Geothlypis philadelphia	Mourning warbler
Leiothlypis ruficapilla	Nashville warbler
Colinus virginianus	Northern bobwhite
Cardinalis cardinalis	Northern cardinal
Colaptes auratus	Northern flicker
Accipiter gentilis	Northern goshawk
Circus hudsonius	Northern harrier
Mimus polyglottos	Northern mockingbird
Setophaga americana	Northern parula
Stelgidopteryx serripennis	Northern rough-winged swallow
Aegolius acadicus	Northern saw-whet owl
Lanius borealis	Northern shrike
Parkesia noveboracensis	Northern waterthrush
Contopus cooperi	Olive-sided flycatcher
Pandion haliaetus	Osprey
Seiurus aurocapillus	Ovenbird
Setophaga palmarum	Palm warbler
Falco peregrinus	Peregrine falcon
Podilymbus podiceps	Pied-billed grebe
Dryocopus pileatus	Pileated woodpecker
Pinicola enucleator	Pine grosbeak
Spinus pinus	Pine siskin
Setophaga pinus	Pine warbler
Setophaga discolor	Prairie warbler
Haemorhous purpureus	Purple finch
Progne subis	Purple martin
Melanerpes carolinus	Red-bellied woodpecker
Sitta canadensis	Red-breasted nuthatch
Vireo olivaceus	Red-eyed vireo
Melanerpes erythrocephalus	Red-headed woodpecker
Buteo lineatus	Red-shouldered hawk

Table 6-20: Canoe Meadows Bird Observations (continued)

Buteo jamaicensis         Red-tailed hawk           Agelaius phoeniceus         Red-winged blackbird           Larus delawarensis         Ring-billed gull           Aythya collaris         Ring-necked duck           Phasianus colchicus         Ring-necked pheasant           Columba livia         Rock dove           Pheucticus ludovicianus         Rose-breasted grosbeak           Buteo lagopus         Rough-legged hawk           Regulus calendula         Ruby-crowned kinglet           Archilochus colubris         Ruby-throated hummingbird           Bonasa umbellus         Ruffed grouse           Euphagus carolinus         Rusty blackbird           Passerculus sandwichensis         Savannah sparrow           Piranga olivacea         Scarlet tanager           Cistothorus stellaris         Sedge wren           Calidris pusilla         Semipalmated sandpiper           Accipiter striatus         Sharp-shinned hawk           Plectrophenax nivalis         Snow bunting           Anser caerulescens         Snow goose           Tringa solitaria         Solitary sandpiper           Melospiza melodia         Song sparrow           Porzana carolina         Sora           Actitis macularia         Spotted sandpiper	Scientific Name	Common Name
Larus delawarensis         Ring-billed gull           Aythya collaris         Ring-necked duck           Phasianus colchicus         Ring-necked pheasant           Columba livia         Rock dove           Pheucticus ludovicianus         Rose-breasted grosbeak           Buteo lagopus         Rough-legged hawk           Regulus calendula         Ruby-crowned kinglet           Archilochus colubris         Ruby-throated hummingbird           Bonasa umbellus         Ruffed grouse           Euphagus carolinus         Rusty blackbird           Passerculus sandwichensis         Savannah sparrow           Piranga olivacea         Scarlet tanager           Cistothorus stellaris         Sedge wren           Calidris pusilla         Semipalmated sandpiper           Accipiter striatus         Sharp-shinned hawk           Plectrophenax nivalis         Snow bunting           Anser caerulescens         Snow goose           Tringa solitaria         Solitary sandpiper           Melospiza melodia         Song sparrow           Porzana carolina         Sora           Actitis macularia         Spotted sandpiper           Melospiza georgiana         Swamp sparrow           Leiothlypis peregrina         Tennessee warbler	Buteo jamaicensis	Red-tailed hawk
Aythya collaris Ring-necked duck Phasianus colchicus Ring-necked pheasant Columba livia Rock dove Pheucticus ludovicianus Rose-breasted grosbeak Buteo lagopus Rough-legged hawk Regulus calendula Ruby-crowned kinglet Archilochus colubris Ruby-throated hummingbird Bonasa umbellus Ruffed grouse Euphagus carolinus Rusty blackbird Passerculus sandwichensis Savannah sparrow Piranga olivacea Scarlet tanager Cistothorus stellaris Sedge wren Calidris pusilla Semipalmated sandpiper Accipiter striatus Sharp-shinned hawk Plectrophenax nivalis Snow bunting Anser caerulescens Snow goose Tringa solitaria Solitary sandpiper Melospiza melodia Song sparrow Porzana carolina Sora Actitis macularia Spotted sandpiper Melospiza georgiana Swamp sparrow Leiothlypis peregrina Tennessee warbler Tachycineta bicolor Tree swallow Baeolophus bicolor Tufted titmouse Cathartes aura Turkey vulture Catharus fuscescens Weery Rallus limicola Virginia rail Vireo gilvus Warbling vireo Antrostomus vociferus Whip-poor-will Sitta carolinensis White-breasted nuthatch Zonotrichia albicollis White-throated sparrow Meleagris gallopavo Wild turkey Empidonax traillii Willow flycatcher Troglodytes hiemalis Wood duck Hylocichla mustelina Wood thrush Setophaga coronata Yellow warbler	Agelaius phoeniceus	Red-winged blackbird
Phasianus colchicus Columba livia Rock dove Pheucticus ludovicianus Rose-breasted grosbeak Buteo lagopus Rough-legged hawk Regulus calendula Ruby-crowned kinglet Archilochus colubris Rusty blackbird Passerculus sandwichensis Savannah sparrow Piranga olivacea Cistothorus stellaris Sedge wren Calidris pusilla Anser caerulescens Tringa solitaria Sora Actitis macularia Melospiza georgiana Leiothlypis peregrina Tachycineta bicolor Tufted titmouse Cathartes aura Vireo gilvus Rundy Melospiza gallopavo Wild turkey Empidonax traillii Vireo gilvus kieplamalis Neodo thrush Wood thrush Veltophaga coronata Neodo thrush Veltophaga coronata Roughaga Roughaga Roughaga Roughaga Coronata Roughaga Roughaga Roughaga Andrushaga Roughaga Coronata Roughaga Roughaga Andrushaga Roughaga Coronata Roughaga Coronata Roughaga Roughaga Anser Candartes Andrushaga Roughaga Coronata Roughaga Roughaga Anser Candartes Andrushaga Roughaga Coronata Roughaga Roug	Larus delawarensis	Ring-billed gull
Columba livia Rock dove Pheucticus ludovicianus Rose-breasted grosbeak Buteo lagopus Rough-legged hawk Regulus calendula Ruby-crowned kinglet Archilochus colubris Ruby-throated hummingbird Bonasa umbellus Ruffed grouse Euphagus carolinus Rusty blackbird Passerculus sandwichensis Savannah sparrow Piranga olivacea Scarlet tanager Cistothorus stellaris Sedge wren Calidris pusilla Semipalmated sandpiper Accipiter striatus Sharp-shinned hawk Plectrophenax nivalis Snow bunting Anser caerulescens Snow goose Tringa solitaria Solitary sandpiper Melospiza melodia Song sparrow Porzana carolina Sora Actitis macularia Spotted sandpiper Melospiza georgiana Swamp sparrow Leiothlypis peregrina Tennessee warbler Tachycineta bicolor Tree swallow Baeolophus bicolor Tufted titmouse Cathartes aura Turkey vulture Catharus fuscescens Veery Rallus limicola Virginia rail Vireo gilvus Warbling vireo Antrostomus vociferus Whip-poor-will Sitta carolinensis White-breasted nuthatch Zonotrichia albicollis White-throated sparrow Meleagris gallopavo Wild turkey Empidonax traillii Willow flycatcher Troglodytes hiemalis Wood duck Hylocichla mustelina Wood thrush Setophaga coronata Yellow warbler	Aythya collaris	Ring-necked duck
Pheucticus Iudovicianus         Rose-breasted grosbeak           Buteo lagopus         Rough-legged hawk           Regulus calendula         Ruby-crowned kinglet           Archilochus colubris         Ruby-throated hummingbird           Bonasa umbellus         Ruffed grouse           Euphagus carolinus         Rusty blackbird           Passerculus sandwichensis         Savannah sparrow           Piranga olivacea         Scarlet tanager           Cistothorus stellaris         Sedge wren           Calidris pusilla         Semipalmated sandpiper           Accipiter striatus         Sharp-shinned hawk           Plectrophenax nivalis         Snow bunting           Anser caerulescens         Snow goose           Tringa solitaria         Solitary sandpiper           Melospiza melodia         Song sparrow           Porzana carolina         Sora           Actitis macularia         Spotted sandpiper           Melospiza georgiana         Swamp sparrow           Leiothlypis peregrina         Tennessee warbler           Tachycineta bicolor         Tree swallow           Baeolophus bicolor         Tufted titmouse           Cathartes aura         Turkey vulture           Catharus fuscescens         Veery <th< td=""><td>Phasianus colchicus</td><td>Ring-necked pheasant</td></th<>	Phasianus colchicus	Ring-necked pheasant
Buteo lagopus Rough-legged hawk Regulus calendula Ruby-crowned kinglet Archilochus colubris Ruffed grouse Euphagus carolinus Rusty blackbird Passerculus sandwichensis Savannah sparrow Piranga olivacea Scarlet tanager Cistothorus stellaris Sedge wren Calidris pusilla Semipalmated sandpiper Accipiter striatus Sharp-shinned hawk Plectrophenax nivalis Sonow bunting Anser caerulescens Sonow goose Tringa solitaria Solitary sandpiper Melospiza melodia Song sparrow Porzana carolina Sora Actitis macularia Spotted sandpiper Melospiza georgiana Swamp sparrow Leiothlypis peregrina Tennessee warbler Tachycineta bicolor Tree swallow Baeolophus bicolor Tufted titmouse Cathartes aura Turkey vulture Catharus fuscescens Veery Rallus limicola Virginia rail Vireo gilvus Warbling vireo Antrostomus vociferus Whip-poor-will Sitta carolinensis White-breasted nuthatch Zonotrichia albicollis White-throated sparrow Meleggris gallopavo Wild turkey Empidonax traillii Winter wren Aix sponsa Wood duck Hylocichla mustelina Setophaga coronata	Columba livia	Rock dove
Regulus calendula Archilochus colubris Bonasa umbellus Buphagus carolinus Rusty blackbird Passerculus sandwichensis Savannah sparrow Piranga olivacea Cistothorus stellaris Calidris pusilla Anser caerulescens Tringa solitaria Melospiza georgiana Leiothlypis peregrina Tachycineta bicolor Baeolophus bicolor Catharus fuscescens Veery Rallus limicola Vireo gilvus Anterstendus Siney sunder Rusty blackbird Savannah sparrow Sedge wren Calidris pusilla Semipalmated sandpiper Sharp-shinned hawk Plectrophenax nivalis Snow bunting Anser caerulescens Snow goose Tringa solitaria Sonow sparrow Sora Actitis macularia Sora Actitis macularia Spotted sandpiper Melospiza georgiana Swamp sparrow Leiothlypis peregrina Tennessee warbler Tree swallow Baeolophus bicolor Tufted titmouse Cathartes aura Turkey vulture Catharus fuscescens Veery Rallus limicola Vireg gilvus Warbling vireo Antrostomus vociferus Whip-poor-will Sitta carolinensis White-breasted nuthatch Zonotrichia albicollis White-throated sparrow Meleagris gallopavo Wild turkey Empidonax traillii Willow flycatcher Troglodytes hiemalis Winter wren Aix sponsa Wood duck Hylocichla mustelina Setophaga coronata	Pheucticus Iudovicianus	Rose-breasted grosbeak
Regulus calendula         Ruby-crowned kinglet           Archilochus colubris         Ruby-throated hummingbird           Bonasa umbellus         Ruffed grouse           Euphagus carolinus         Rusty blackbird           Passerculus sandwichensis         Savannah sparrow           Piranga olivacea         Scarlet tanager           Cistothorus stellaris         Sedge wren           Calidris pusilla         Semipalmated sandpiper           Accipiter striatus         Sharp-shinned hawk           Plectrophenax nivalis         Snow bunting           Anser caerulescens         Snow goose           Tringa solitaria         Solitary sandpiper           Melospiza melodia         Song sparrow           Porzana carolina         Sora           Actitis macularia         Spotted sandpiper           Melospiza georgiana         Swamp sparrow           Leiothlypis peregrina         Tennessee warbler           Tachycineta bicolor         Tree swallow           Baeolophus bicolor         Tufted titmouse           Cathartes aura         Turkey vulture           Cathartes aura         Turkey vulture           Cathartes aura         Virginia rail           Vireo gilvus         Warbling vireo           Antrostomus vocif	Buteo lagopus	Rough-legged hawk
Bonasa umbellus         Ruffed grouse           Euphagus carolinus         Rusty blackbird           Passerculus sandwichensis         Savannah sparrow           Piranga olivacea         Scarlet tanager           Cistothorus stellaris         Sedge wren           Calidris pusilla         Semipalmated sandpiper           Accipiter striatus         Sharp-shinned hawk           Plectrophenax nivalis         Snow bunting           Anser caerulescens         Snow goose           Tringa solitaria         Solitary sandpiper           Melospiza melodia         Song sparrow           Porzana carolina         Sora           Actitis macularia         Spotted sandpiper           Melospiza georgiana         Swamp sparrow           Leiothlypis peregrina         Tennessee warbler           Tachycineta bicolor         Tree swallow           Baeolophus bicolor         Tufted titmouse           Cathartes aura         Turkey vulture           Catharus fuscescens         Veery           Rallus limicola         Virginia rail           Vireo gilvus         Warbling vireo           Antrostomus vociferus         Whip-poor-will           Sitta carolinensis         White-breasted nuthatch           Zonotrichia albicollis <td>·</td> <td>Ruby-crowned kinglet</td>	·	Ruby-crowned kinglet
Bonasa umbellus         Ruffed grouse           Euphagus carolinus         Rusty blackbird           Passerculus sandwichensis         Savannah sparrow           Piranga olivacea         Scarlet tanager           Cistothorus stellaris         Sedge wren           Calidris pusilla         Semipalmated sandpiper           Accipiter striatus         Sharp-shinned hawk           Plectrophenax nivalis         Snow bunting           Anser caerulescens         Snow goose           Tringa solitaria         Solitary sandpiper           Melospiza melodia         Song sparrow           Porzana carolina         Sora           Actitis macularia         Spotted sandpiper           Melospiza georgiana         Swamp sparrow           Leiothlypis peregrina         Tennessee warbler           Tachycineta bicolor         Tree swallow           Baeolophus bicolor         Tufted titmouse           Cathartes aura         Turkey vulture           Catharus fuscescens         Veery           Rallus limicola         Virginia rail           Vireo gilvus         Warbling vireo           Antrostomus vociferus         Whip-poor-will           Sitta carolinensis         White-breasted nuthatch           Zonotrichia albicollis <td>Archilochus colubris</td> <td>Ruby-throated hummingbird</td>	Archilochus colubris	Ruby-throated hummingbird
Euphagus carolinus Passerculus sandwichensis Savannah sparrow Piranga olivacea Scarlet tanager Cistothorus stellaris Sedge wren Calidris pusilla Semipalmated sandpiper Accipiter striatus Sharp-shinned hawk Plectrophenax nivalis Snow bunting Anser caerulescens Snow goose Tringa solitaria Solitary sandpiper Melospiza melodia Sora Actitis macularia Spotted sandpiper Melospiza georgiana Leiothlypis peregrina Tennessee warbler Tachycineta bicolor Tree swallow Baeolophus bicolor Cathartes aura Turkey vulture Catharus fuscescens Veery Rallus limicola Virginia rail Vireo gilvus Meleagris gallopavo Wild turkey Empidonax traillii Willow flycatcher Troglodytes hiemalis Wood duck Hylocichla mustelina Veelog warbler Sedge wren Savannah sparrow Tinge wren Savale tanager Savannah sparrow Veren Savale tanager Savannah sparrow Veren Savale wren Savannah sparrow Veren Savale tanager Savannah sparrow Veren Savannah sparrow Veren	Bonasa umbellus	<u> </u>
Passerculus sandwichensis         Savannah sparrow           Piranga olivacea         Scarlet tanager           Cistothorus stellaris         Sedge wren           Calidris pusilla         Semipalmated sandpiper           Accipiter striatus         Sharp-shinned hawk           Plectrophenax nivalis         Snow bunting           Anser caerulescens         Snow goose           Tringa solitaria         Solitary sandpiper           Melospiza melodia         Song sparrow           Porzana carolina         Sora           Actitis macularia         Spotted sandpiper           Melospiza georgiana         Swamp sparrow           Leiothlypis peregrina         Tennessee warbler           Tachycineta bicolor         Tree swallow           Baeolophus bicolor         Tufted titmouse           Cathartes aura         Turkey vulture           Cathartes aura         Veery           Rallus limicola         Virginia rail           Vireo gilvus         Warbling vireo           Antrostomus vociferus         Whip-poor-will           Sitta carolinensis         White-throated sparrow           Meleagris gallopavo         Wild turkey           Empidonax traillii         Willow flycatcher           Troglodytes hiemalis	Euphagus carolinus	
Piranga olivacea         Scarlet tanager           Cistothorus stellaris         Sedge wren           Calidris pusilla         Semipalmated sandpiper           Accipiter striatus         Sharp-shinned hawk           Plectrophenax nivalis         Snow bunting           Anser caerulescens         Snow goose           Tringa solitaria         Solitary sandpiper           Melospiza melodia         Song sparrow           Porzana carolina         Sora           Actitis macularia         Spotted sandpiper           Melospiza georgiana         Swamp sparrow           Leiothlypis peregrina         Tennessee warbler           Tachycineta bicolor         Tree swallow           Baeolophus bicolor         Tufted titmouse           Cathartes aura         Turkey vulture           Cathartes aura         Veery           Rallus limicola         Virginia rail           Vireo gilvus         Warbling vireo           Antrostomus vociferus         Whip-poor-will           Sitta carolinensis         White-breasted nuthatch           Zonotrichia albicollis         White-throated sparrow           Meleagris gallopavo         Wild turkey           Empidonax traillii         Wildow flycatcher           Troglodytes hiemalis <td></td> <td><u> </u></td>		<u> </u>
Calidris pusilla Semipalmated sandpiper Accipiter striatus Sharp-shinned hawk Plectrophenax nivalis Snow bunting Anser caerulescens Tringa solitaria Solitary sandpiper Melospiza melodia Porzana carolina Sora Actitis macularia Spotted sandpiper Melospiza georgiana Leiothlypis peregrina Tennessee warbler Tachycineta bicolor Tree swallow Baeolophus bicolor Tufted titmouse Cathartes aura Turkey vulture Catharus fuscescens Veery Rallus limicola Vireo gilvus Antrostomus vociferus White-breasted nuthatch Zonotrichia albicollis White-throated sparrow Melospirs gallopavo Empidonax traillii Willow flycatcher Troglodytes hiemalis Wood duck Hylocichla mustelina Setophaga coronata Semipalmated sandpiper Sharp-shinned hawk Senow banks Senow bunting Sonw bunting Sonw bunting Sonw bunting And sandpiper Sharp-shinned hawk Senow bunting Sharp-shinned hawk Senow bunting Sonw bunting Sharp-shinned hawk Senow bunting Sharp-shinned hawk Sharp-shinned Solitary sandpiper Sharp-shinned Solitary sandpiper Sharp-sharper Sharper Sharp-sharper Sharp-sharper Sharp-sharper Sharp-sharper Sharper Sharp-sharper Sharper	Piranga olivacea	Scarlet tanager
Calidris pusillaSemipalmated sandpiperAccipiter striatusSharp-shinned hawkPlectrophenax nivalisSnow buntingAnser caerulescensSnow gooseTringa solitariaSolitary sandpiperMelospiza melodiaSong sparrowPorzana carolinaSoraActitis maculariaSpotted sandpiperMelospiza georgianaSwamp sparrowLeiothlypis peregrinaTennessee warblerTachycineta bicolorTree swallowBaeolophus bicolorTufted titmouseCathartes auraTurkey vultureCatharus fuscescensVeeryRallus limicolaVirginia railVireo gilvusWarbling vireoAntrostomus vociferusWhip-poor-willSitta carolinensisWhite-breasted nuthatchZonotrichia albicollisWhite-throated sparrowMeleagris gallopavoWild turkeyEmpidonax trailliiWillow flycatcherTroglodytes hiemalisWinter wrenAix sponsaWood duckHylocichla mustelinaYellow warbler	Cistothorus stellaris	Sedge wren
Accipiter striatus Plectrophenax nivalis Anser caerulescens Snow goose Tringa solitaria Solitary sandpiper Melospiza melodia Porzana carolina Actitis macularia Spotted sandpiper Melospiza georgiana Leiothlypis peregrina Tachycineta bicolor Baeolophus bicolor Tufted titmouse Cathartes aura Turkey vulture Catharus fuscescens Veery Rallus limicola Vireo gilvus Antrostomus vociferus Sitta carolinensis White-breasted nuthatch Zonotrichia albicollis Melospiza georgiana United titmouse Warbling vireo Antrostomus vociferus Whip-poor-will Sitta carolinensis White-throated sparrow Meleagris gallopavo Wild turkey Empidonax traillii Willow flycatcher Troglodytes hiemalis Aix sponsa Wood duck Hylocichla mustelina Setophaga coronata Yellow warbler	Calidris pusilla	
Plectrophenax nivalisSnow buntingAnser caerulescensSnow gooseTringa solitariaSolitary sandpiperMelospiza melodiaSong sparrowPorzana carolinaSoraActitis maculariaSpotted sandpiperMelospiza georgianaSwamp sparrowLeiothlypis peregrinaTennessee warblerTachycineta bicolorTree swallowBaeolophus bicolorTufted titmouseCathartes auraTurkey vultureCatharus fuscescensVeeryRallus limicolaVirginia railVireo gilvusWarbling vireoAntrostomus vociferusWhip-poor-willSitta carolinensisWhite-breasted nuthatchZonotrichia albicollisWhite-throated sparrowMeleagris gallopavoWild turkeyEmpidonax trailliiWillow flycatcherTroglodytes hiemalisWinter wrenAix sponsaWood duckHylocichla mustelinaWood thrushSetophaga coronataYellow warbler	· · · · · · · · · · · · · · · · · · ·	
Tringa solitaria Solitary sandpiper  Melospiza melodia Song sparrow  Porzana carolina Sora  Actitis macularia Spotted sandpiper  Melospiza georgiana Swamp sparrow  Leiothlypis peregrina Tennessee warbler  Tachycineta bicolor Tree swallow  Baeolophus bicolor Tufted titmouse  Cathartes aura Turkey vulture  Catharus fuscescens Veery  Rallus limicola Virginia rail  Vireo gilvus Warbling vireo  Antrostomus vociferus Whip-poor-will  Sitta carolinensis White-breasted nuthatch  Zonotrichia albicollis White-throated sparrow  Meleagris gallopavo Wild turkey  Empidonax traillii Willow flycatcher  Troglodytes hiemalis Wood duck  Hylocichla mustelina Wood thrush  Setophaga coronata Yellow warbler	Plectrophenax nivalis	Snow bunting
Melospiza melodiaSong sparrowPorzana carolinaSoraActitis maculariaSpotted sandpiperMelospiza georgianaSwamp sparrowLeiothlypis peregrinaTennessee warblerTachycineta bicolorTree swallowBaeolophus bicolorTufted titmouseCathartes auraTurkey vultureCatharus fuscescensVeeryRallus limicolaVirginia railVireo gilvusWarbling vireoAntrostomus vociferusWhip-poor-willSitta carolinensisWhite-breasted nuthatchZonotrichia albicollisWhite-throated sparrowMeleagris gallopavoWild turkeyEmpidonax trailliiWillow flycatcherTroglodytes hiemalisWinter wrenAix sponsaWood duckHylocichla mustelinaWood thrushSetophaga coronataYellow warbler	Anser caerulescens	Snow goose
Melospiza melodiaSong sparrowPorzana carolinaSoraActitis maculariaSpotted sandpiperMelospiza georgianaSwamp sparrowLeiothlypis peregrinaTennessee warblerTachycineta bicolorTree swallowBaeolophus bicolorTufted titmouseCathartes auraTurkey vultureCatharus fuscescensVeeryRallus limicolaVirginia railVireo gilvusWarbling vireoAntrostomus vociferusWhip-poor-willSitta carolinensisWhite-breasted nuthatchZonotrichia albicollisWhite-throated sparrowMeleagris gallopavoWild turkeyEmpidonax trailliiWillow flycatcherTroglodytes hiemalisWinter wrenAix sponsaWood duckHylocichla mustelinaWood thrushSetophaga coronataYellow warbler	Tringa solitaria	Solitary sandpiper
Actitis maculariaSpotted sandpiperMelospiza georgianaSwamp sparrowLeiothlypis peregrinaTennessee warblerTachycineta bicolorTree swallowBaeolophus bicolorTufted titmouseCathartes auraTurkey vultureCatharus fuscescensVeeryRallus limicolaVirginia railVireo gilvusWarbling vireoAntrostomus vociferusWhip-poor-willSitta carolinensisWhite-breasted nuthatchZonotrichia albicollisWhite-throated sparrowMeleagris gallopavoWild turkeyEmpidonax trailliiWillow flycatcherTroglodytes hiemalisWinter wrenAix sponsaWood duckHylocichla mustelinaWood thrushSetophaga coronataYellow warbler	Melospiza melodia	Song sparrow
Melospiza georgianaSwamp sparrowLeiothlypis peregrinaTennessee warblerTachycineta bicolorTree swallowBaeolophus bicolorTufted titmouseCathartes auraTurkey vultureCatharus fuscescensVeeryRallus limicolaVirginia railVireo gilvusWarbling vireoAntrostomus vociferusWhip-poor-willSitta carolinensisWhite-breasted nuthatchZonotrichia albicollisWhite-throated sparrowMeleagris gallopavoWild turkeyEmpidonax trailliiWillow flycatcherTroglodytes hiemalisWinter wrenAix sponsaWood duckHylocichla mustelinaWood thrushSetophaga coronataYellow warbler	Porzana carolina	Sora
Leiothlypis peregrinaTennessee warblerTachycineta bicolorTree swallowBaeolophus bicolorTufted titmouseCathartes auraTurkey vultureCatharus fuscescensVeeryRallus limicolaVirginia railVireo gilvusWarbling vireoAntrostomus vociferusWhip-poor-willSitta carolinensisWhite-breasted nuthatchZonotrichia albicollisWhite-throated sparrowMeleagris gallopavoWild turkeyEmpidonax trailliiWillow flycatcherTroglodytes hiemalisWinter wrenAix sponsaWood duckHylocichla mustelinaWood thrushSetophaga coronataYellow warbler	Actitis macularia	Spotted sandpiper
Tachycineta bicolor  Baeolophus bicolor  Cathartes aura  Turkey vulture  Catharus fuscescens  Rallus limicola  Vireo gilvus  Antrostomus vociferus  Sitta carolinensis  White-breasted nuthatch  Zonotrichia albicollis  Meleagris gallopavo  Empidonax traillii  Troglodytes hiemalis  Aix sponsa  Westling vireo  Whip-poor-will  White-throated sparrow  Wild turkey  Empidonax traillii  Willow flycatcher  Troglodytes hiemalis  Wood duck  Hylocichla mustelina  Wellow warbler	Melospiza georgiana	Swamp sparrow
Baeolophus bicolor Cathartes aura Turkey vulture Catharus fuscescens Veery Rallus limicola Vireo gilvus Warbling vireo Antrostomus vociferus White-breasted nuthatch Zonotrichia albicollis White-throated sparrow Meleagris gallopavo Empidonax traillii Winter wren Aix sponsa Wood duck Hylocichla mustelina Veery Warbling vireo Warbling vireo White-breasted nuthatch White-throated sparrow Wild turkey Willow flycatcher Troglodytes hiemalis Wood duck Hylocichla mustelina Wood thrush Setophaga coronata	Leiothlypis peregrina	Tennessee warbler
Cathartes auraTurkey vultureCatharus fuscescensVeeryRallus limicolaVirginia railVireo gilvusWarbling vireoAntrostomus vociferusWhip-poor-willSitta carolinensisWhite-breasted nuthatchZonotrichia albicollisWhite-throated sparrowMeleagris gallopavoWild turkeyEmpidonax trailliiWillow flycatcherTroglodytes hiemalisWinter wrenAix sponsaWood duckHylocichla mustelinaWood thrushSetophaga coronataYellow warbler	Tachycineta bicolor	Tree swallow
Catharus fuscescens       Veery         Rallus limicola       Virginia rail         Vireo gilvus       Warbling vireo         Antrostomus vociferus       Whip-poor-will         Sitta carolinensis       White-breasted nuthatch         Zonotrichia albicollis       White-throated sparrow         Meleagris gallopavo       Wild turkey         Empidonax traillii       Willow flycatcher         Troglodytes hiemalis       Winter wren         Aix sponsa       Wood duck         Hylocichla mustelina       Wood thrush         Setophaga coronata       Yellow warbler	Baeolophus bicolor	Tufted titmouse
Rallus limicolaVirginia railVireo gilvusWarbling vireoAntrostomus vociferusWhip-poor-willSitta carolinensisWhite-breasted nuthatchZonotrichia albicollisWhite-throated sparrowMeleagris gallopavoWild turkeyEmpidonax trailliiWillow flycatcherTroglodytes hiemalisWinter wrenAix sponsaWood duckHylocichla mustelinaWood thrushSetophaga coronataYellow warbler	Cathartes aura	Turkey vulture
Vireo gilvus  Antrostomus vociferus  Whip-poor-will  Sitta carolinensis  White-breasted nuthatch  Zonotrichia albicollis  White-throated sparrow  Meleagris gallopavo  Wild turkey  Empidonax traillii  Willow flycatcher  Troglodytes hiemalis  Winter wren  Aix sponsa  Wood duck  Hylocichla mustelina  Wellow warbler	Catharus fuscescens	Veery
Antrostomus vociferus  Sitta carolinensis  White-breasted nuthatch  Zonotrichia albicollis  White-throated sparrow  Meleagris gallopavo  Wild turkey  Empidonax traillii  Willow flycatcher  Troglodytes hiemalis  Winter wren  Aix sponsa  Wood duck  Hylocichla mustelina  Wellow warbler	Rallus limicola	Virginia rail
Sitta carolinensis  White-breasted nuthatch  Zonotrichia albicollis  White-throated sparrow  Meleagris gallopavo  Wild turkey  Empidonax traillii  Willow flycatcher  Troglodytes hiemalis  Winter wren  Aix sponsa  Wood duck  Hylocichla mustelina  Wellow warbler	Vireo gilvus	Warbling vireo
Zonotrichia albicollis  Meleagris gallopavo  Wild turkey  Empidonax traillii  Willow flycatcher  Troglodytes hiemalis  Minter wren  Aix sponsa  Wood duck  Hylocichla mustelina  Setophaga coronata  White-throated sparrow  Wild turkey  Wood duck  Hylocichla mustelina  Yellow warbler	Antrostomus vociferus	Whip-poor-will
Meleagris gallopavo       Wild turkey         Empidonax traillii       Willow flycatcher         Troglodytes hiemalis       Winter wren         Aix sponsa       Wood duck         Hylocichla mustelina       Wood thrush         Setophaga coronata       Yellow warbler	Sitta carolinensis	White-breasted nuthatch
Empidonax traillii Willow flycatcher  Troglodytes hiemalis Winter wren  Aix sponsa Wood duck  Hylocichla mustelina Wood thrush  Setophaga coronata Yellow warbler	Zonotrichia albicollis	White-throated sparrow
Troglodytes hiemalis  Aix sponsa  Wood duck  Hylocichla mustelina  Setophaga coronata  Winter wren  Wood thrush  Yellow warbler	Meleagris gallopavo	Wild turkey
Aix sponsa Wood duck  Hylocichla mustelina Wood thrush  Setophaga coronata Yellow warbler	Empidonax traillii	Willow flycatcher
Hylocichla mustelina Wood thrush Setophaga coronata Yellow warbler	Troglodytes hiemalis	Winter wren
Setophaga coronata Yellow warbler	Aix sponsa	Wood duck
	Hylocichla mustelina	Wood thrush
Sphyrapicus varius Yellow-bellied sapsucker	Setophaga coronata	Yellow warbler
	Sphyrapicus varius	Yellow-bellied sapsucker

Table 6-20: Canoe Meadows Bird Observations (continued)

Scientific Name	Common Name
Coccyzus americanus	Yellow-billed cuckoo
Icteria virens	Yellow-breasted chat
Setophaga coronata	Yellow-rumped warbler
Vireo flavifrons	Yellow-throated vireo

Table 7-1: Data Collected in 2018-2019 on Vernal Pool inspections in Reach 5A

	Hi	storical Data		2	018 Biological	Data			2019 Biologica	I Data		Physical Dat 2019	
Pool_ID	Obligate Species <sup>1,3</sup>	Facultative Species <sup>1</sup>	Permanency <sup>2</sup>	Obligate Species (egg mass counts) <sup>1,3</sup>	Facultative Species <sup>1</sup>	Other Species <sup>1</sup>	Fish Presence	Obligate Species (egg mass counts) <sup>1,3</sup>	Facultative Species <sup>1</sup>	Other Species <sup>1</sup>	Fish Presence	Permanency <sup>2</sup>	Perm Flowing Outlet?
5A-VP-1A	FS		Т	SS (1), WF (1)		GF, ST		WF (1), WF Larvae		ST, GF (adult)		Ta	No
5A-VP-1B				,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		,		SS(4), WF(3), WF Larvae		, , ,		T <sup>a</sup>	No
5A-VP-1	None	ST, WT, AT, SP, NLF, GF	Р	SS (13), WF (Adult)		WT, PT, ST, GF	Yes	SS(9), WF(1)		GF (larvae), PF GF, PT, ST		NA	No
5A-VP-2	None			SS (5), WF (1) Spermatophores	SP			SS(25), WF(13), Spermatophores			Yes	T <sup>a</sup>	No
5A-VP-3	None			WF (Adult)		GF		WF Larvae				T <sup>a</sup>	No
5A-VP-4	WF, FS		Т	WF (2), FS				WF(10)				T <sup>a</sup>	No
5A-VP-5	SS, WF,FS		Р	WF (250-300), FS				, ,	Not Subject to Ins	spection		T <sup>a</sup>	No
5A-VP-6	FS		T	WF (6), FS					Not Subject to Ins			T <sup>a</sup>	No
5A-VP-7	WF <sup>1</sup>	GF	Т	WF (35-40), FS, WF Chorusing				SS(2), WF(50+)	•			Ta	No
5A-VP-8	None			FS				WF(15)				Ta	No
5A-VP-9	WF, FS	ST, PT, SP, NLF, GF	Т	WF (1), WF (Adult), FS, WF Chorusing				WF (30)				T <sup>a</sup>	No
5A-VP-10	None	,		WF (15-20), FS				WF (> 100)				Ta	No
5A-VP-12	None			WF (23)				WF(2), SS(1)		ST, GF(larvae, adults)		NA	No
5A-VP-13	None			WF (9)			Yes	None		GF larvae		Р	No
5A-VP-14	None			None				WF Larvae				T <sup>a</sup>	No
5A-VP-15	None			WF (20-25), FS				WF Larvae		GF larvae		T <sup>a</sup>	No
5A-VP-15A	None			FS				WF(3)				Ta	No
5A-VP-16	None			FS				WF(25)				Ta	No
5A-VP-18	None			None		GF		WF(9)				T <sup>a</sup>	No
5A-VP-18A	None			None		GF		WF Larvae			Yes	T <sup>a</sup>	No
5A-VP-19	None			None	GTF	GF, ST		WF (5)				T⁵	No
5A-VP-20	None			WF (4), FS	SP			WF(7)		GF (larvae)		T⁵	No
5A-VP-21	SS, WF, FS	RSN, SP,NLF, PF, GF	Т	WF (250-300), FS	SP			None				Tb	No
5A-VP-22	WF, FS	SP, NLF, GF	Т	WF (170), FS				WF(4)	GTF (calling) SP (calling)			Tb	No
5A-VP-24	None			WF (10), SS (14)					Not Subject to Ins	spection		NA	No
5A-VP-26	None			FS				None				Tb	
5A-VP-27	None			FS				FS				T <sup>a</sup>	No
5A-VP-28A								WF (2, Larvae)	AT			Ta	No
5A-VP-32	None		Т	WF (1), FS				WF (4), FS				T <sup>a</sup>	No
5A-VP-33	WF, FS		T	WF (Adult), FS				WF (10), FS	AT (calling)			T <sup>a</sup> No	No
5A-VP-35	None			FS				WF (6)	AT (breeding/eggs)			Tb	No
5A-VP-36	WF <sup>1</sup>		Т	WF (6)	SP				Not Subject to Ins			T <sup>b</sup>	
5A-VP-40	WF	PT, NLF, GF	Р	WF (1), FS					Not Subject to Ins	spection		T <sup>b</sup>	
5A-VP-42	None			WF (Adult)				WF (5), WF Larvae				Tb	
5A-VP-49A	None			None		GF, NLF		WF (1), WF Larvae		GF		Tb	No
5A-VP-50	None			None		GF		WF Larvae	AT eggs			T⁵No	No
5A-VP-52	None			None	SP, GTF	NLF, GF		WF(1), WF larvae		<u> </u>		T⁵No	No

Table 7-1: Data Collected in 2018-2019 on Vernal Pool inspections in Reach 5A (continued).

	His	storical Data		2	018 Biological	Data			2019 Biological	Data		Physical Dat 2019	
Pool_ID	Obligate Species <sup>1,3</sup>	Facultative Species <sup>1</sup>	Permanency <sup>2</sup>	Obligate Species (egg mass counts) <sup>1,3</sup>	Facultative Species <sup>1</sup>	Other Species <sup>1</sup>	Fish Presence	Obligate Species (egg mass counts) <sup>1,3</sup>	Facultative Species <sup>1</sup>	Other Species <sup>1</sup>	Fish Presence	Permanency <sup>2</sup>	Perm Flowing Outlet?
5A-VP-54	None			None	SP, GTF	GF		WF(1), WF larvae		GF (larvae)		T <sup>a</sup>	No
5A-VP-55	None		T	WF (2)	SP, GTF	GF		WF(1), WF Larvae	SP larvae	GF (larvae)		T <sup>a</sup>	No
5A-VP-57	None		Т	None	SP, GTF	ST		WF(20), WF Larvae				T <sup>a</sup>	No
5A-VP-59A	None			WF (adults)		NLF		WF(3), WF Larvae		GF		T <sup>a</sup>	No
5A-VP-60	WF	GF	T	WF (9), FS				, ,:	Not Subject to Insp	pection		T <sup>a</sup>	No
5A-VP-61	FS, WF	GF	T	WF (70), FS					Not Subject to Insp	pection		T <sup>a</sup>	No
5A-VP-62	FS, WF	GF	T	WF (7), FS					Not Subject to Insp	pection		T <sup>a</sup>	No
5A-VP-63	FS	GTF, GF	Т	WF (1), FS					Not Subject to Insp			T <sup>a</sup>	No
5A-VP-64	None			None	GTF, AT	NLF, GF, ST,	Yes	WF (4)	AT Tadpoles	GF (larvae)		Ta	No
5A-VP-65	None			WF (1)	GTF	ST	Yes	WF(6), WF Larvae				Ta	No
5A-VP-69	WF, FS	ST, PT, SP, NLF,GF	Т	WF (6)	SP				Not Subject to Insp	pection		Ta	No
5A-VP-70	WF, FS	PT, SP, NLF, GF	Т	WF (65), FS					Not Subject to Insp	pection		Tª	No
5A-VP-71	None	ST, PT, GF	Р	SS(2), WF(2)	GTF	GF, RSN, PT, carp, perch	Yes	WF (8)		PF (2), RSN, GF (larvae)		NA	No
5A-VP-72	WF	PT, NLF, GF	Р	SS(6)	GTF	PF, dead carp and perch	Yes		Not Subject to Insp	pection		NA	No
5A-VP-73	SS, WF	RSN, SP,NLF	Т	SS(13), WF(+200)		GF, BF, PT, ST	Yes		Not Subject to Insp	pection		NA	No
5A-VP-73A	None			FS, WF(5)		BF, GF, PT			Not Subject to Insp	pection		Tb	No
5A-VP-74	SS, FS	GF	Т	FS, WF(23)		, - , -	Yes		Not Subject to Inst			Ta	No
5A-VP-77	None	-		WF (6), SS (18)	SP	GF, NLF	Yes		Not Subject to Ins			NA	No
5A-VP-79	FS		Т	FS		ĞF			Not Subject to Inst			T♭	
5A-VP-80	FS	SP	Т	FS				None				T♭	
5A-VP-81	None			FS				None				Ta	No
5A-VP-83	None			None		GF		WF Larvae	AT (breeding/eggs)			T <sup>b</sup> No	No

Table 7-1: Data Collected in 2018-2019 on Vernal Pool inspections in Reach 5A (Keys to Table Abbreviations).

## 1. Species abbreviations:

Code	Meaning	Code	Meaning
(	Obligate Species		Other Species
WF	Wood Frog	BF	Bull Frog
SS	Spotted Salamander	GF	Green Frog
JS	Jefferson Salamander	NLF	Northern Leopard Frog
FS	Fairy Shrimp	PF	Pickerel Frog
Fa	acultative Species	PT	Painted Turtle
AT	American Toad	RSN	Red Spotted Newt
GTF	Gray Tree Frog	ST	Snapping Turtle
SP	Spring Peeper	WT	Wood Turtle

### 2. Hydrologic Code:

Code	Meaning
T <sup>a</sup>	Temporary pool, observed with no surface water
Tb	Temporary pool, observed nearly dry in late spring, expected to dry out entirely during summer of a normal hydrological year
Р	Expected to be permanently flooded
NA	Not applicable because pool has already been determined to meet vernal pool criteria under obligate species method based on 2018 data

<sup>3.</sup> Obligate species listed consist of egg masses for amphibians except where adults and/or larvae are noted, or fairy shrimp.



Table 7-2: Habitat Characteristics within Reach 5A Vernal Pools and the Adjacent Landscape

Surrounding Land Use (Percent of total area from edge of pool)<sup>5</sup>

																						(Perc	ent or t	otal are	a iroiii	euge o	poor	
								G	eneral	Vernal Pool Characteris	stics		Vegeta	ition Cov	ver (%) <sup>4</sup>		In-l		sical Ha	bitat	All F	orest	Deve	loped	Open	Space	Scrub	o/Shrub
Pool_ID		Discrete Depression in floodplain	Pool part of larger wetland	Number of Pools within 1000 feet	Cover Types <sup>1</sup>	Substrate Type <sup>2</sup>	Area (Acres)	Max Depth (inches)	Average Depth (inches)	√ Pool Hydrology³	Inlet/Outlet	Tree Canopy Cover	Shrubs	Herbs	Mosses	Woody Vines	FWD	CWD	Windthrown Trees / Root Wads	Hummocks (Sedge/Grass/shrub)	VPE 0-100	CTH 100-750						
5A-VP-1A	08/02/22		Υ	4	SS / SEM	Mucky Mineral/SiL	0.15	13	5.0	Seasonally Flooded	N	59.7	28.6	56.8	0.0	7.5	10.5	3	0	0	27.8	61.3	0.0	0.2	72.2	36.7	0.0	1.8
5A-VP-1B	08/02/22		Υ	4	SEM / SS	Mucky Mineral/SiL	0.13	8	4.1	Seasonally Flooded	N	9.4	52.6	94.1	0.0	0.0	0	0	0	63	27.8	63.4	0.0	0.0	72.2	34.6	0.0	2.0
5A-VP-1	08/02/22		Y	5	POW / DEM / SEM / SS	Mucky Mineral/SiL	0.82	33	15.6	Seasonally to Semi- Perm Flooded	Seasonal	21.1	21.7	23.9	0.0	0.0	3	0	0	10.5	65.8	75.3	0.0	0.3	34.2	23.0	0.0	1.3
5A-VP-2	08/02/22	Υ		6	SEM / SS / TFF	Deep Organic Muck	0.23	Dry	0.0	Seasonally Flooded/Saturated	Seasonal	27.1	21.4	97.6	0.0	0.0	3	10.5	0	20.5	62.2	77.5	0.0	0.8	37.8	20.8	0.0	0.9
5A-VP-3	08/01/22	Υ		8	SS / TFF	Mineral/VFSL	0.39	6	2.6	Seasonally Flooded	N	86.1	26.2	51.0	0.0	0.0	10.5	3	3	0	100.0	74.2	0.0	12.7	0.0	12.4	0.0	0.6
5A-VP-4	08/01/22	Υ		7	SS / TFF	Mineral/SiL	0.23	18	7.6	Seasonally Flooded/Saturated	N	49.0	35.8	83.0	0.0	0.0	20.5	3	0	3	94.5	77.1	5.5	15.8	0.0	6.7	0.0	0.4
5A-VP-5	08/03/22		Υ	8	SEM / SS	Mucky Mineral/VFSL	0.33	17	9.6	Seasonally Flooded/Saturated	N	49.2	49.5	54.1	8.5	3.6	3	0	0	0	100.0	70.5	0.0	24.6	0.0	3.8	0.0	1.1
5A-VP-6	08/03/22		Υ	9	TFF	Mucky Mineral/VFSL	0.05	18	10.1	Seasonally Flooded	N	73.0	7.3	22.1	5.4	0.0	10.5	0	3	0	100.0	72.3	0.0	21.4	0.0	4.7	0.0	1.7
5A-VP-7	08/03/22	Υ		9	SS / TFF	Mineral/VFSL	0.41	18	8.8	Seasonally Flooded	Temporary	77.0	27.2	36.8	0.0	10.4	10.5	3	3	0	81.9	84.8	0.0	0.7	18.1	13.4	0.0	1.1
5A-VP-8	08/03/22	Υ		9	SS / TFF	Mineral/SiL	0.07	18	8.5	Seasonally Flooded	Temporary	17.5	74.5	55.9	0.0	10.9	0	3	0	0	100.0	87.9	0.0	1.4	0.0	9.1	0.0	1.6
5A-VP-9	08/03/22		Υ	9	SEM/SS/ TFF	Mineral/FSL	0.60	16	5.6	Seasonally Flooded	N	3.0	98.0	20.5	0.0	3.0	10.5	3	10.5	3	90.0	80.3	0.0	9.3	5.4	10.0	4.6	0.4
5A-VP-10	08/03/22		Υ	11	SS / TFF	Mineral/VFSL	0.17	13	5.8	Seasonally Flooded	N	100.0	16.1	8.1	0.0	0.0	20.5	10.5	0	0	100.0	76.0	0.0	16.3	0.0	6.1	0.0	1.5
5A-VP-12	08/03/22	Υ		8	DEM / TFF	Mucky Mineral/SiL	0.27	24	13.7	Seasonally Flooded/Saturated	Seasonal	44.6	15.4	95.1	0.0	0.0	3	10.5	0	0	90.6	77.8	0.8	6.8	8.6	13.8	0.0	1.5
5A-VP-13	08/02/22	Υ		11	DEM / TFF	Mucky Mineral/VFSL	0.40	21	11.7	Semi-permanently Flooded	Seasonal	49.3	1.7	78.4	0.0	0.0	3	3	3	0	85.0	75.7	0.2	12.1	8.8	11.2	6.0	1.1
5A-VP-14	08/02/22	Υ		9	SS / TFF	Mucky Mineral/VFSL	0.03	5	2.5	Seasonally Flooded/Saturated	N	21.9	0.0	100.0	0.0	0.0	3	0	0	0	66.6	69.8	0.0	17.5	33.4	12.3	0.0	0.5
5A-VP-15	08/02/22	Υ		9	DEM / SEM / TFF	Mucky Mineral/FSL	0.37	18	7.8	Semi-permanently Flooded	Seasonal	52.7	0.6	100.0	0.0	0.0	3	10.5	0	0	93.1	65.6	0.5	22.4	6.4	11.1	0.0	0.9
5A-VP-15A	08/02/22	Υ		6	TFF	Mucky Mineral/FSL	0.04	15	7.4	Seasonally Flooded/Saturated	N	100.0	0.0	41.5	0.0	0.0	10.5	10.5	0	0	83.9	63.8	0.0	26.6	16.1	9.3	0.0	0.3
5A-VP-16	08/03/22	Υ		7	TFF	Mucky Mineral/FSL	0.04	23	10.3	Seasonally Flooded	N	54.8	50.6	68.3	0.0	0.0	20.5	10.5	0	3	100.0	62.2	0.0	29.1	0.0	8.3	0.0	0.5
5A-VP-18	08/03/22	Υ		6	SEM / SS /TFF	Mucky Mineral/FSL	0.15			Seasonally Flooded	Temporary	68.6	30.2	29.4	0.0	0.0	20.5	3	0	3	76.8	55.3	23.2	39.0	0.0	5.5	0.0	0.1
5A-VP-18A	08/03/22	Υ		6	DEM / TFF	Mucky Mineral/FSL	0.04	24	11.2	Seasonally Flooded/Saturated	Seasonal	22.5	42.5	92.5	0.0	0.0	10.5	0	0	0	96.9	61.9	0.0	31.9	3.1	6.1	0.0	0.1
5A-VP-19	08/05/22	Υ		1	SEM	Mineral/SiL	0.14	9	4.5	Seasonally Flooded	N	3.0	3.0	98.0	0.0	0.0	3	0	0	3	38.6	31.5	0.0	11.7	42.8	50.0	18.5	6.7
5A-VP-20	08/04/22		Υ	3	SEM/SS/ TFF	Mucky Mineral/LS	0.33	16	6.2	Seasonally Flooded/Saturated	N	10.7	51.6	53.9	0.0	0.0	3	0	0	20.5	76.9	51.4	0.1	16.5	5.3	23.1	17.8	9.0
5A-VP-21	08/05/22		Υ	4	DEM / SEM / SS	Deep Organic Muck	1.65	23	13.6	Seasonally Flooded/Saturated	N	3.0	85.5	38.0	3.0	10.5	10.5	10.5	3	0	56.4	58.7	8.1	22.5	18.6	13.7	16.9	5.0
5A-VP-22	08/05/22		Υ	4	DEM / SS / TFF	Mucky Mineral/LS	0.82	27	12.6	Seasonally Flooded/Saturated	N	60.5	18.3	64.2	0.0	0.0	3	3	0	10.5	56.4	65.9	0.0	7.4	3.8	21.1	39.8	5.5
5A-VP-24	08/04/22	Υ		1	RMS	Mucky Mineral/FSL	0.10	12	5.7	Seasonally Flooded	N	85.5	20.5	10.5	0.0	0.0	20.5	3	3	10.5	89.6	64.5	0.0	0.0	10.4	22.7	0.0	12.8

Table 7-2: Habitat Characteristics within Reach 5A Vernal Pools and the Adjacent Landscape (continued)

Surrounding Land Use (Percent of total area from edge of pool)<sup>5</sup>

								G	eneral \	/ernal Pool Characteris	tics		Vegeta	tion Cov	er (%) <sup>4</sup>		In-l	Pool Phy Stru	sical Hal	bitat	All F		Deve	loped	Open			o/Shrub
Pool_ID	Date	Discrete Depression in floodplain	Pool part of larger wetland	Number of Pools within 1000 feet	Cover Types <sup>1</sup>	Substrate Type <sup>2</sup>	Area (Acres)	Max Depth (inches)	Average Depth (inches)	Pool Hydrology³	Inlet/Outlet	Tree Canopy Cover	Shrubs	Herbs	Mosses	Woody Vines	FWD	CWD	Windthrown Trees / Root Wads	Hummocks (Sedge/Grass/shrub)	VPE 0-100	CTH 100-750	VPE 0-100	CTH 100-750	VPE 0-100	CTH 100-750	VPE 0-100	CTH 100-750
5A-VP-26	08/04/22	Υ		4	SS/TFF	Mucky Mineral/FSL	0.08	15	7.5	Seasonally Flooded	Temporary	0.0	58.3	73.3	0.0	29.9	3	10.5	0	0	82.2	66.2	1.7	10.6	0.7	9.3	15.4	13.9
5A-VP-27	08/04/22	Υ		6	TFF	Mineral/FSL	0.08	Dry	0.0	Seasonally Flooded	N	32.6	42.3	31.0	0.0	0.0	3	0	0	0	91.6	67.0	0.0	7.0	0.2	11.0	8.2	15.0
5A-VP-28A	08/04/22	Υ		6	SS/TFF	Mucky Mineral/SL	0.03			Seasonally Flooded/Saturated	Temporary	0.0	4.5	100.0	0.0	0.0	20.5	10.5	10.5	0	96.6	62.7	0.0	0.0	3.4	17.8	0.0	19.6
5A-VP-32	08/08/22	Υ		7	SS / RMS	Organic/VFSL	0.08	18	11.8	Seasonally Flooded/Saturated	Temporary	76.7	31.3	59.4	0.0	13.1	10.5	3	3	0	76.2	50.0	0.0	0.0	1.8	22.9	22.0	27.1
5A-VP-33	08/08/22	Υ		7	DEM / SS / TFF	Mineral/VFSL	0.53	15	7.3	Seasonally Flooded/Saturated	Temporary	11.9	12.6	100.0	0.0	0.0	3	0	0	10.5	93.6	49.9	0.0	0.0	3.8	27.0	2.6	23.1
5A-VP-35	08/08/22	Υ		6	SS / TFF	Mucky Mineral/FSL	0.30	4	1.8	Seasonally Flooded/Saturated	Temporary	19.8	31.7	82.3	0.0	0.0	3	3	10.5	3	68.5	47.7	0.0	0.0	3.1	33.0	28.4	19.3
5A-VP-36	08/08/22	Υ		6	SEM / SS / TFF	Mineral/VFSL	0.30	12	6.4	Seasonally Flooded/Saturated	N	65.7	53.6	64.4	0.0	0.0	3	0	0	0	54.0	47.7	0.0	0.0	11.3	27.9	34.7	24.4
5A-VP-40	08/08/22	Υ		5	SEM / TFF	Mucky Mineral/FSL	0.12	15	7.4	Seasonally Flooded/Saturated	Temporary	60.7	15.7	70.4	0.0	0.0	3	3	0	0	84.9	47.5	0.0	0.2	14.6	36.7	0.6	15.6
5A-VP-42	08/08/22	Υ		5	SEM / TFF	Mucky Mineral/FSL	0.13	8	4.3	Seasonally Flooded/Saturated	Temporary	85.6	0.0	87.9	0.0	0.0	3	10.5	0	0	87.5	43.2	0.0	3.8	12.5	42.8	0.0	10.2
5A-VP-49A	08/08/22	Υ		5	SS / TFF	Mineral/VFSL	0.03	28	13.6	Seasonally Flooded	N	93.8	18.8	100.0	0.0	0.0	3	0	0	0	64.9	29.6	0.0	6.2	35.1	55.6	0.0	8.5
5A-VP-50	08/25/22	Υ		5	SEM / TFF	Mineral/VFSL	0.06	12	6.0	Seasonally Flooded/Saturated	Temporary	56.3	0.0	100.0	0.0	0.0	10.5	0	0	0	72.1	34.5	0.0	7.6	27.1	50.4	0.8	7.5
5A-VP-52	08/09/22	Υ		7	SEM/SS	Mucky Mineral/VFSL	0.06	11	5.3	Seasonally Flooded	Temporary	30.0	8.6	100.0	0.0	0.0	3	0	0	3	16.2	38.3	0.0	13.8	27.6	39.4	56.2	8.6
5A-VP-54	08/09/22	Υ		7	SEM/SS	Mucky Mineral/VFSL	0.09	5	2.9	Seasonally Flooded/Saturated	N	0.0	38.0	98.0	0.0	0.0	10.5	0	0	3	13.2	37.7	0.0	10.5	25.4	43.1	61.5	8.6
5A-VP-55	08/09/22	Υ		7	SEM/SS	Organic/VFSL	0.25	17	8.8	Seasonally Flooded/Saturated	Temporary	0.0	13.6	98.5	0.0	0.0	3	10.5	0	0	41.5	36.2	0.0	8.3	24.1		34.4	11.0
5A-VP-57	08/09/22	Υ		5	TFF	Mineral/VFSL	0.49	37	19.9	Seasonally Flooded	Temporary	85.5	3.0	10.5	0.0	10.5	20.5	10.5	10.5	0	57.7	31.0	0.0	4.8	30.7	47.6	11.5	16.6
5A-VP-59A	08/31/22	Y		6	TFF	Mucky Mineral/VFSL	0.06	12	5.2	Seasonally Flooded/Saturated	N	94.5	12.3	37.2	0.0	5.7	10.5	0	0	0	76.0	36.5	0.0	10.1	24.0	49.4	0.0	4.0
5A-VP-60	08/11/22	Y		6	TFF	Organic/LFS	0.08	16	9.1	Seasonally Flooded	N	81.9	5.5	59.2	0.0	0.0	3	10.5	0	0	99.7	46.8	0.0	20.0	0.3	31.4	0.0	1.9
5A-VP-61	08/11/22	Y		9	TFF	Mineral/VFSL	0.26	17	9.1	Seasonally Flooded	N N	66.9	21.2	76.6	0.0	0.0	20.5	10.5	3	0	97.1	47.3	0.0	14.4	2.9	34.8	0.0	3.4
5A-VP-62 5A-VP-63	08/11/22 08/10/22	Y		9	TFF TFF	Organic/VFSL Mineral/VFSL	0.22	20 17	9.7	Seasonally Flooded Seasonally Flooded	N N	86.7 45.5	0.0	23.9 43.2	0.0	0.0 5.5	10.5	0	0	0	80.4 75.4	51.5 55.2	0.0	10.8 2.5	19.6 24.6	34.7 37.4	0.0	2.9 4.8
5A-VP-64	08/10/22	Y		6	SEM / SS / WM	Mucky Mineral/VFSL	1.00		19.8	Seasonally Flooded/Saturated	Temporary	0.0	2.1	98.6	0.0	0.0	10.5	0	0	20.5	38.8	38.8	0.0	0.5	39.6	46.4		14.3
5A-VP-65	08/10/22	Υ		7	SEM	Mineral/VFSL	0.11	28	13.5	Seasonally Flooded/Saturated	Temporary	50.0	25.8	100.0	0.0	0.0	3	3	0	0	54.9	41.5	0.0	0.5	32.5	40.6	12.6	17.4
5A-VP-69	08/10/22	Υ		8	SEM / SS	Organic/LS	0.34	14	6.4	Seasonally Flooded	N	48.2	22.3	57.6	12.5	0.0	10.5	0	0	0	89.9	48.5	1.1	4.4	8.4	39.5	0.6	7.5
5A-VP-70	08/10/22	Υ		11	SEM / SS	Organic/LS	0.78	27	10.6	Seasonally Flooded	N	60.3	56.0	52.8	19.7	2.0	20.5	0	0	3	86.0	42.7	3.9	4.0	10.0	44.9	0.0	8.4
5A-VP-71	08/11/22		Υ	10	DEM/SEM/ SS	Organic/FSL	0.47	19	14.0	Seasonally Flooded/Saturated	Temporary	0.0	20.5	100.0	0.0	0.0	3	0	0	10.5	17.2	50.4	0.0	0.5	44.7	42.6	38.0	6.6
5A-VP-72	08/11/22		Υ	9	DEM/SEM/ SS	Organic/FSL	1.26			Semi-permanently Flooded	Temporary	0.0	38.0	98.0	0.0	0.0	3	0	0	20.5	17.8	47.1	0.0	5.0	28.7	44.0	53.4	3.9
5A-VP-73	08/11/22		Υ	5	SS / TFF	Organic/FSL	0.48	19	9.7	Seasonally Flooded/Saturated	Temporary	22.3	30.7	91.8	1.3	0.0	3	0	0	10.5	58.8	41.5	0.0	10.9	13.6	42.5	27.6	5.1

Table 7-2: Habitat Characteristics within Reach 5A Vernal Pools and the Adjacent Landscape (continued)

### Surrounding Land Use (Percent of total area from edge of pool)<sup>5</sup>

								G	eneral '	Vernal Pool Characteris	stics		Vegeta	ation Cov	ver (%) <sup>4</sup>		In-		sical Ha	bitat	All F	orest	Deve	loped	Open	Space	Scrub	o/Shrub
Pool_ID	Date	Discrete Depression in floodplain	Pool part of larger wetland	Number of Pools within 1000 feet	Cover Types <sup>1</sup>	Substrate Type <sup>2</sup>	Area (Acres)	Max Depth (inches)	Average Depth (inches)	Pool Hydrology <sup>3</sup>	Inlet/Outlet	Tree Canopy Cover	Shrubs	Herbs	Mosses	Woody Vines	FWD	CWD	Windthrown Trees / Root Wads	Hummocks (Sedge/Grass/shrub)	VPE 0-100	CTH 100-750						
5A-VP-73A	08/11/22	Υ		4	SS/TFF	Mucky Mineral/FSL	0.15	11	5.2	Seasonally Flooded	N	100.0	39.6	66.6	0.0	6.3	10.5	0	0	0	64.7	38.0	0.0	5.3	35.3	50.2	0.0	6.4
5A-VP-74	08/11/22	Υ		7	TFF	Organic/LFS	0.26	24	9.6	Seasonally Flooded	N	76.6	10.4	32.1	0.0	8.6	10.5	10.5	0	0	93.5	42.1	0.0	6.5	6.5	43.5	0.0	7.8
5A-VP-77	09/15/22		Υ	1	SEM/SS/ TFF	Deep Organic Muck	3.93	Dry	0.0	Seasonally Flooded	Seasonal	3.0	85.5	63.0	20.5	0.0	10.5	3	3	38	85.2	58.0	9.4	9.7	5.0	31.9	0.4	0.4
5A-VP-79	08/24/22	Υ		3	SS/TFF	Organic/VFSL	0.08	12	6.9	Seasonally Flooded	N	49.0	18.9	93.0	0.0	18.3	10.5	0	0	0	92.3	46.4	0.0	1.1	4.6	49.7	3.1	2.9
5A-VP-80	08/24/22	Υ		3	SS/TFF	Mucky Mineral/FSL	0.83	15	8.8	Seasonally Flooded/Saturated	Temporary	50.4	20.1	100.0	0.0	0.0	10.5	0	0	0	94.6	39.2	0.0	2.8	5.4	55.7	0.0	2.3
5A-VP-81	08/24/22	Υ		3	TFF	Mucky Mineral/SL	0.09	16	9.7	Seasonally Flooded	N	80.8	0.0	79.2	0.0	0.0	3	10.5	0	0	92.4	48.8	0.0	0.2	3.7	48.4	3.9	2.5
5A-VP-83	08/25/22	Υ		3	SEM	Mineral/SL	0.05	17	10.4	Seasonally Flooded	N	3.0	0.0	98.0	0.0	0.0	3	0	0	0	25.7	39.8	1.7	0.1	72.7	58.6	0.0	1.5

<sup>1.</sup> SS = Shrub Swamp, SEM = Shallow Emergent Marsh, DEM = Deep Emergent Marsh, TFF = Transitional Floodplain Forest, RMS = Red Maple Swamp, POW = Palustrine Open Water

<sup>2.</sup> Surface horizon / sub-surface soil textures

<sup>3.</sup> Hydrologic Regimes from FGDC (2013)

<sup>4.</sup> Percent cover of vegetation layers as measured from line-intercept transects across each vernal pool (n = 49) or as estimated in pools larger than one acre or pools with high shrub densities and/or deep water that restricted access across the pool (n = 10).

<sup>5.</sup> Percent cover of select habitats within the VPE = Vernal Pool Envelope (0-100 feet) and CTH = Critical Terrestrial Habitat (100-750 feet) from the edge of the pool. Landscape cover metrics based on MassGIS Land Cover/Land Use data (2016).

Table 7-3. Summary Statistics of Vernal Pool Vegetation Cover, In-pool Physical Structure, and the Adjacent Landscape

#### Surrounding Land Use (Percent of total area from edge of pool)<sup>1</sup>

Nin   0.0   0.0   8.1   0.0																			
Nin   0.0   0.0   8.1   0.0			Veget	ation Cov	ver (%)		In-			oitat	All F	orest	Deve	loped	Open	Space	Scrub	)/Shrub	
Max         100.0         98.0         100.0         20.5         29.9         20.5         10.5         10.5         63.0         100.0         87.9         23.2         39.0         72.7         58.6         61.5         27.1           Mean         45.5         25.8         68.1         1.2         2.5         8.2         3.7         1.2         4.6         72.9         55.2         1.0         9.0         17.0         29.2         9.2         6.6           Count         59 <t< th=""><th></th><th>Tree Canopy Cover</th><th>Shrubs</th><th>Herbs</th><th>Mosses</th><th>dy Vi</th><th>FWD</th><th>CWD</th><th>/indthi oot W</th><th>ımmocks edge/Grass/shru</th><th>-6</th><th>-1</th><th>0-1</th><th>-1</th><th></th><th>-75</th><th>0</th><th>Н 100-7</th><th>Number of Pools within 1000 feet</th></t<>		Tree Canopy Cover	Shrubs	Herbs	Mosses	dy Vi	FWD	CWD	/indthi oot W	ımmocks edge/Grass/shru	-6	-1	0-1	-1		-75	0	Н 100-7	Number of Pools within 1000 feet
Mean     45.5     25.8     68.1     1.2     2.5     8.2     3.7     1.2     4.6     72.9     55.2     1.0     9.0     17.0     29.2     9.2     6.6       Count     59     59     59     59     59     59     59     59     59     59     59     59	Min	0.0	0.0	8.1	0.0	0.0	0.0	0.0	0.0	0.0	13.2	29.6	0.0	0.0	0.0	3.8	0.0	0.1	1
Count 59 59 59 59 59 59 59 59 59 59 59 59 59	Max	100.0	98.0	100.0	20.5	29.9	20.5	10.5	10.5	63.0	100.0	87.9	23.2	39.0	72.7	58.6	61.5	27.1	11
	Mean	45.5	25.8	68.1	1.2	2.5	8.2	3.7	1.2	4.6	72.9	55.2	1.0	9.0	17.0	29.2	9.2	6.6	6.3
SE 4.3 3.1 3.8 0.5 0.7 0.8 0.6 0.4 1.4 3.3 2.0 0.4 1.2 2.4 2.1 2.1 0.9	Count	59	59	59	59	59	59	59	59	59	59	59	59	59	59	59	59	59	59
	SE	4.3	3.1	3.8	0.5	0.7	0.8	0.6	0.4	1.4	3.3	2.0	0.4	1.2	2.4	2.1	2.1	0.9	0.3

<sup>1.</sup> VPE = Vernal Pool Envelope, landscape within 0-100 feet from pool edge CTH = Critical Terrestrial Habitat, landscape within 100-750 feet from pool edge

Table 7-4. Reach 5A Plant Species Summary Data for Certified Vernal Pools

Layer	Common Name	Scientific Name	Status	(Number of Pools N=59)
Tree Species	Boxelder maple	Acer negundo	Native	19
	Red maple	Acer rubrum	Native	13
	Silver maple	Acer saccharinum	Native	33
	Sugar maple	Acer saccharum	Native	3
	Yellow birch	Betula alleghaniensis	Native	2
	American hornbeam	Carpinus caroliniana	Native	7
	Common hackberry	Celtis occidentalis	Native	1
	Dotted hawthorn	Crataegus punctata	Native	7
	American beech	Fagus grandifolia	Native	1
	Green ash	Fraxinus pennsylvanica	Native	2
	Butternut	Juglans cinerea	Native	2
	Quaking aspen	Populus tremuloides	Native	2
	Pin cherry	Prunus pensylvanica	Native	1
	Black cherry	Prunus serotina	Native	3
	Eastern cottonwood	Pupulus deltoides	Native	6
	Black willow	Salix nigra	Native	8
	American linden	Tilia americana	Native	4
	Eastern hemlock	Tsuga canadensis	Native	2
	American elm	Ulmus americana	Native	13

Occurrence

Table 7-4. Reach 5A Plant Species Summary Data for Certified Vernal Pools (continued)

Layer	Common Name	Scientific Name	Status	(Number of Pools N=59)
Shrub	Speckled alder	Alnus incana	Native	3
Species	Japanese barberry	Berberis thunbergii	Invasive <sup>A,B,C</sup>	1
	Buttonbush	Cephalanthus occidentalis	Native	3
	Silky dogwood	Cornus amomum	Native	39
	American hazelnut	Corylus americana	Native	1
	Burning bush	Euonymus alatus	Invasive <sup>A,B,C</sup>	1
	Glossy buckthorn	Frangula alnus	Invasive <sup>A,B,C</sup>	1
	Winterberry	llex verticillata	Native	2
	Border privet	Ligustrum obtusifolium	Invasive <sup>D</sup>	2
	Morrow's honeysuckle	Lonicera morrowii	Invasive <sup>A,B</sup>	12
	Dock-leaved smartweed	Persicaria lapathifolia	Native	1
	European buckthorn	Rhamnus cathartica	Invasive <sup>A,B,C</sup>	9
	Multiflora rose	Rosa multiflora	ABC	8
	Pussy willow	Salix discolor	Native	3
	Willow	Salix sp.	Native	6
	Elderberry	Sambucus canadensis	Native	2
	White Meadowsweet	Spiraea alba	Native	3
	Arrowwood	Viburnum dentatum	Native	2
Woody Vines	Asian bittersweet	Celastrus orbiculatus	Invasive <sup>A,B,C</sup>	2
	Virginia creeper	Parthenocisus quiquefolia	Native	1
	Poison ivy	Toxicodendron radicans	Native	5
	River grape	Vitis riparia	Native	17

Occurrence

Table 7-4. Reach 5A Plant Species Summary Data for Certified Vernal Pools (continued)

(Number of Pools **Common Name Scientific Name** N=59) Layer **Status** Herb, Forb Sweet flag Acorus americanus Native 1 and Grass Snakeroot Ageratina altissima Native Species Northern water-plantain Alisma triviale Native Hemp dogbane Apocynum cannabinum Native 1 Swamp milkweed Native Asclepias incarnata 1 Lady fern Athyrium angustum Native<sub>4</sub> 1 Nodding beggar-ticks 3 Bidens cernua Native<sub>17</sub> Devil's beggar-tick Bidens frondosa Native 14 Small-spiked false nettle Boehmeria cylindrica 5 Native Black mustard Brassica nigra Non-native 4 Water starwort Callitriche palustris Native 2 Fringed sedge Carex crinita Native 5 Greater bladder sedge Carex intumescens Native 3 Hop sedge Carex lupulina Native Lurid sedge Carex Iurida Native 1 Sedge Carex sp. Native 11 Tussock sedge Carex stricta Native 2 Chamerion angustifolium 3 Fireweed Native Chelone glabra White turtlehead Native 1 Cicuta bulbifera 2 Bulblet-bearing water-hemlock Native Sweet wood-reed Cinna arundinacea Native Enchanter's-nightshade Circaea canadensis Native Common dodder Cuscuta gronovii 8 Native

Occurrence

Table 7-4. Reach 5A Plant Species Summary Data for Certified Vernal Pools (continued)

Layer	Common Name	Scientific Name	Status¹	Occurrence (Number of Pools N=59)
	Tufted hairgrass	Deschampsia cespitosa	Non-native	1
	Barnyard grass	Echinochloa crus-galli	Non-native	2
	Needle spikesedge	Eleocharis acicularis	Native	2
	Spikerush	Eleocharis sp.	Native	6
	Purple-leaved willowherb	Epilobium ciliatum	Native	1
	Tall scouring-rush	Equisetum hyemale	Native	2
	Burnweed	Erechtites hieraciifolius	Native	4
	Spotted joe-pye weed	Eutrochium maculatum	Native	3
	Marsh bedstraw	Galium palustre	Native	12
	White avens	Geum canadense	Native	2
	Rattlesnake grass	Glyceria canadensis	Native	2
	Jewelweed	Impatiens capensis	Native	23
	Yellow iris	Iris pseudacorus	Invasive <sup>A,B</sup>	8
	Blueflag	Iris versicolor	Native	1
	Canadian rush	Juncus canadensis	Native	1
	Soft rush	Juncus effusus	Native	1
	Canada wood nettle	Laportea canadensis	Native	3
	Rice cut-grass	Leersia oryzoides	Native	8
	Common duckweed	Lemna minor	Native	1
	Common water-primrose	Ludwigia palustris	Native	4
	Northern water-horehound	Lycopus uniflorus	Native	3
	Fringed yellow-loosestrife	Lysimachia ciliata	Native	2
	Moneywort	Lysimachia nummularia	Invasive <sup>A,C</sup>	31

Table 7-4. Reach 5A Plant Species Summary Data for Certified Vernal Pools (continued)

Layer	Common Name	Scientific Name	Status	Occurrence (Number of Pools N=59)
	Swamp candles	Lysimachia terrestris	Native	1
	Yellow loosestrife	Lysimachia vulgaris	Native	1
	Purple loosetrife	Lythrum salicaria	Invasive <sup>A,B,C</sup>	29
	Ostrich fern	Matteuccia struthiopteris	Native	2
	Wild mint	Mentha canadensis	Native	1
	Monkey-flower	Mimulus ringens	Native	1
	Water forget-me-not	Myosotis scorpioides	Invasive <sup>D</sup>	15
	Sensitive fern	Onoclea sensibilis	Native	34
	Interrupted fern	Osmunda claytoniana	Native	2
	Royal fern	Osmunda regalis	Native	2
	Royal fern	Osumnda regalis	Native	2
	New York fern	Parathelypteris noveboracensis	Native	1
	Ditch-stonecrop	Penthorum sedoides	Native	9
	Halberd-leaved tearthumb	Persicaria arifolia	Native	1
	Water-pepper smartweed	Persicaria hydropiper	Native	6
	False water-pepper	Persicaria hydropiperoides	Native	8
	Pennsylvania smartweed	Persicaria pensylvanica	Native	8
	Dotted smartweed	Persicaria punctata	Native	10
	Arrow-leaved tearthumb	Persicaria sagittata	Native	11
	Smartweed	Persicaria sp.	Native	9
	Jumpseed	Persicaria virginiana	Native	4
	Reed canary grass	Phalaris arundinacea	Invasive <sup>A,B,C</sup>	14
	Common reed	Phragmites austrails	Invasive <sup>A,B,C</sup>	3

Table 7-4. Reach 5A Plant Species Summary Data for Certified Vernal Pools (continued)

Occurrence (Number of Pools **Common Name Scientific Name** N=59) Layer **Status** Clearweed Pilea pumila Native Pickerelweed Pontederia cordata 1 Native Bristly buttercup Ranunculus hispidus Native 1 Blisterwort Ranunculus recurvatus Native 1 Green-headed coneflower Rudbeckia laciniata Native 6 Common arrowhead Sagittaria latifolia Native 5 Soft-stemmed bulrush Schoenoplectus tabernaemontani Native 1 Woolgrass Scirpus cyperinus Native 10 Mad dog skullcap Scutellaria lateriflora Native 1 One-seeded burr-cucumber Sicyos angulatus Native 1 Water parsnip Sium suave Native 5 Climbing nightshade Solanum dulcamara Non-native 4 American bur-reed Sparganium americanum Native 3 5 Bur-reed Sparganium sp. Native Symphyotrichum sp. Native 1 Aster Skunk cabbage Symplocarpus foetidus Native 4 Marsh fern Thelypteris palustris Native 4 Thelypteris simulata Massachusetts fern Native 1 2 Stinging nettle Urtica dioica Native Blue vervain Verbena hastata Native 1 Narrow-leaved speedwell Veronica scutellata Native 1 Rough cocklebur Xanthium strumarium Non-native 6

<sup>&</sup>lt;sup>1</sup>Invasive Ratings: A= MIPAG Invasive; B=IPANE Invasive; C=ACOE Invasive; D=MIPAG Likely Invasive

Table 7-5: Soil and Water Chemistry within the 15 Randomly Selected Vernal Pools

_		Sc	Water Chemistry									
		Total Organic	Carbon					Dissolve	d Oxygen			
Vernal Pool ID	Organic Carbon mg/Kg <sup>1</sup>	% Organic Carbon Dry Weight <sup>2</sup>	% Moisture	% Solids	pH (SU)	Date	Temperature °C	%	mg/L	Specific Conductivity	pН	Date
5AVP3	15000	1.5	31.8	68.2	6.1	5/17/23	13.9	33.6	3.47	143.2	6.45	4/26/23
5AVP5	33000	3.3	41.1	58.9	5.7	5/17/23	10.4	27.4	3.95	112.4	6.22	4/26/23
5AVP12	61000	6.1	56.9	43.1	6.1	5/17/23	11.1	57.3	6.31	225.2	6.96	4/26/23
5AVP16	33000	3.3	40.0	60.0	6.0	5/17/23	11.7	43.4	4.70	228.7	6.82	4/26/23
5AVP18	18000	1.8	28.3	71.7	6.3	5/17/23	18.0	153.9	14.51	1578	7.18	4/26/23
5AVP20	27000	2.7	31.6	68.4	6.1	5/18/23	11.4	70.3	7.33	421.7	6.52	4/26/23
5AVP22	24000	2.4	38.8	61.2	6.2	5/17/23	11.7	17.5	1.90	192.5	6.62	4/26/23
5AVP27	18000	1.8	32.6	67.4	5.9	5/17/23			Dry			4/26/23
5AVP40	51000	5.1	45.9	54.1	5.9	5/17/23	14.4	11.7	1.19	231.8	6.64	4/21/23
5AVP50	32000	3.2	41.4	58.6	6.9	5/17/23	14.8	76.3	7.72	287.0	7.32	4/25/23
5AVP63	50000	5	44.6	55.4	6.1	5/17/23	10.8	19.6	2.05	101.6	6.14	4/25/23
5AVP69	17000	1.7	36.6	63.4	6.3	5/17/23	7.3	57.6	6.92	309	7.27	4/25/23
5AVP72	110000	11	60.9	39.1	5.6	5/17/23	11.7	74.6	8.09	167.8	6.54	4/25/23
5AVP79	27000	2.7	42.4	57.6	5.7	5/18/23	7.7	29.5	3.52	100.6	6.02	4/26/23
5AVP80	91000	9.1	59.1	40.9	6.4	5/18/23	8.4	21.1	2.47	278.5	6.83	4/26/23

<sup>1.</sup> Method: EPA-Lloyd Kahn, 9045D, Prep type: Total/NA Soluble

<sup>2.</sup> Percent Organic Carbon Dry Weight of each sample was determined by dividing each Organic Carbon value by 10,000 (1% of the analysis unit where 1 ppm = 1 mg/K or 10,000).

Table 7-6: State-Listed Rare Species Potentially Associated with Vernal Pool Habitats in Reach 5A

Scientific Name	<b>Common Name</b>	State Status
Botaurus lentiginosus	American Bittern	Endangered
Ranunculus pensylvanicus	Bristly Buttercup	Special Concern
Gallinula galeata	Common Gallinule	Special Concern
Veronicastrum virginicum	Culver's-Root	Threatened
Carex grayi	Gray's Sedge	Threatened
Eleocharis intermedia	Matted Spike-Sedge	Threatened
Pieris oleracea	Mustard White	Threatened
Papaipema sp. 2	Ostrich Fern Borer	Special Concern
Carex tuckermanii	Tuckerman's Sedge	Endangered
Sagittaria cuneata	Wapato	Threatened
Malaxis monophyllos ssp. brachypoda	White Adder's-Mouth	Endangered
Glyptemys insculpta	Wood Turtle	Special Concern

Table 7-7: Reach 5A Vernal Pool Tier Ratings\*

	(	Category A		Category B					
Pool_ID	State-listed Species Present or Breeding in CVP	2 or more VP Indicator Species	> 25 Egg Masses Counted	Score	>75% VPE Undvlp	>50% CTH Undvlp	Score	Tier Rating	
5A-VP-1A	N	Υ	N	1	Υ	Υ	2	Tier I	
5A-VP-1B	N	N	N	0	Υ	Υ	2	Tier III	
5A-VP-1	N	Υ	N	1	Υ	Υ	2	Tier I	
5A-VP-2	N	Υ	Υ	2	Υ	Υ	2	Tier I	
5A-VP-3	N	N	N	0	Υ	Υ	2	Tier III	
5A-VP-4	N	Υ	N	1	Υ	Υ	2	Tier I	
5A-VP-5	N	Υ	Υ	2	Υ	Υ	2	Tier I	
5A-VP-6	N	Υ	N	1	Υ	Υ	2	Tier I	
5A-VP-7	N	Υ	Υ	2	Υ	Υ	2	Tier I	
5A-VP-8	N	N	N	0	Υ	Υ	2	Tier III	
5A-VP-9	N	Υ	Υ	2	Υ	Υ	2	Tier I	
5A-VP-10	N	Υ	Υ	2	Υ	Υ	2	Tier I	
5A-VP-12	N	Υ	N	1	Υ	Υ	2	Tier I	
5A-VP-13	N	N	N	0	Υ	Υ	2	Tier III	
5A-VP-14	N	N	N	0	Υ	Υ	2	Tier III	
5A-VP-15	N	Υ	Υ	2	Υ	Υ	2	Tier I	
5A-VP-15A	N	Υ	N	1	Υ	Υ	2	Tier I	
5A-VP-16	N	Υ	Υ	2	Υ	Υ	2	Tier I	
5A-VP-18	N	N	N	0	Υ	Υ	2	Tier III	
5A-VP-18A	N	N	N	0	Υ	Υ	2	Tier III	
5A-VP-19	N	N	N	0	Υ	Υ	2	Tier III	
5A-VP-20	N	Υ	N	1	Υ	Υ	2	Tier I	
5A-VP-21	N	Υ	Υ	2	Υ	Υ	2	Tier I	
5A-VP-22	N	Υ	Υ	2	Υ	Υ	2	Tier I	

Table 7-7: Reach 5A Vernal Pool Tier Ratings (continued)\*

	(							
Pool_ID	State-listed Species Present or Breeding in CVP	2 or more VP Indicator Species	> 25 Egg Masses Counted	Score	>75% VPE Undvlp	>50% CTH Undvlp	Score	Tier Rating
5A-VP-24	N	Υ	Υ	2	Υ	Υ	2	Tier I
5A-VP-26	N	N	N	0	Υ	Υ	2	Tier III
5A-VP-27	N	N	N	0	Υ	Υ	2	Tier III
5A-VP-28A	N	N	N	0	Υ	Υ	2	Tier III
5A-VP-32	N	Υ	N	1	Υ	Υ	2	Tier I
5A-VP-33	N	Υ	N	1	Υ	Υ	2	Tier I
5A-VP-35	N	Υ	N	1	Υ	Υ	2	Tier I
5A-VP-36	N	N	N	0	Υ	Υ	2	Tier III
5A-VP-40	N	Υ	N	1	Υ	Υ	2	Tier I
5A-VP-42	N	N	N	0	Υ	Υ	2	Tier III
5A-VP-49A	N	N	N	0	Υ	Υ	2	Tier III
5A-VP-50	N	Υ	N	1	Υ	Υ	2	Tier I
5A-VP-52	N	N	N	0	Υ	Υ	2	Tier III
5A-VP-54	N	N	N	0	Υ	Υ	2	Tier III
5A-VP-55	N	N	N	0	Υ	Υ	2	Tier III
5A-VP-57	N	N	N	0	Υ	Υ	2	Tier III
5A-VP-59A	N	N	N	0	Υ	Υ	2	Tier III
5A-VP-60	N	Υ	N	1	Υ	Υ	2	Tier I
5A-VP-61	N	Υ	Υ	2	Υ	Υ	2	Tier I
5A-VP-62	N	Υ	N	1	Υ	Υ	2	Tier I
5A-VP-63	N	Υ	N	1	Υ	Υ	2	Tier I
5A-VP-64	N	N	N	0	Υ	Υ	2	Tier III
5A-VP-65	N	N	N	0	Υ	Υ	2	Tier III
5A-VP-69	N	N	N	0	Υ	Υ	2	Tier III

Table 7-7: Reach 5A Vernal Pool Tier Ratings (continued)\*

	(	Category A			Category B				
Pool_ID	State-listed Species Present or Breeding in CVP	2 or more VP Indicator Species	> 25 Egg Masses Counted	Score	>75% VPE Undvlp	>50% CTH Undvlp	Score	Tier Rating	
5A-VP-70	N	Υ	Υ	2	Υ	Υ	2	Tier I	
5A-VP-71	N	Υ	N	1	Υ	Υ	2	Tier I	
5A-VP-72	N	N	N	0	Υ	Υ	2	Tier III	
5A-VP-73	N	Υ	Υ	2	Υ	Υ	2	Tier I	
5A-VP-73A	N	Υ	N	1	Υ	Υ	2	Tier I	
5A-VP-74	Υ	Υ	N	2	Υ	Υ	2	Tier I	
5A-VP-77	N	Υ	N	1	Υ	Υ	2	Tier I	
5A-VP-79	N	N	N	0	Υ	Υ	2	Tier III	
5A-VP-80	N	N	N	0	Υ	Υ	2	Tier III	
5A-VP-81	N	N	N	0	Υ	Υ	2	Tier III	
5A-VP-83	N	N	N	0	Υ	Υ	2	Tier III	

<sup>\*</sup>Based upon the Tier Rating System of Calhoun and Klemens (2002)

Table 8-1: State-Listed Species with Species Habitat Mapping Overlapping Reach 5A as shown on MNHESP Data Provided in October 2022

		State	Area in 5A	
Scientific Name	Common Name	Status	(Acres)	Taxonomic Group
Botaurus lentiginosus	American Bittern	Е	164.0	Bird
Ranunculus pensylvanicus	Bristly Buttercup	SC	29.4	Plant
Ophiogomphus aspersus	Brook Snaketail	SC	240.6	Invertebrate
Gallinula galeata	Common Gallinule	SC	16.2	Bird
Veronicastrum virginicum	Culver's-Root	Т	0.1	Plant
Eragrostis frankii	Frank's Lovegrass	SC	25.9	Plant
Carex grayi	Gray's Sedge	Т	27.5	Plant
Rhododendron maximum	Great Laurel	Т	1.7	Plant
Elymus villosus	Hairy Wild Rye	Е	18.9	Plant
Eleocharis intermedia	Matted Spike-Eedge	Т	116.8	Plant
Pieris oleracea	Mustard White	Т	327.4	Invertebrate
Boyeria grafiana	Ocellated Darner	SC	276.8	Invertebrate
Papaipema sp. 2	Ostrich Fern Borer	SC	171.3	Invertebrate
Phanogomphus quadricolor	Rapids Clubtail	Е	55.0	Invertebrate
Ophiogomphus carolus	Riffle Snaketail	Т	191.7	Invertebrate
Hylogomphus abbreviatus	Spine-Crowned Clubtail	S	256.2	Invertebrate
Carex tuckermanii	Tuckerman's Sedge	Е	0.9	Plant
Sagittaria cuneata	Wapato	Т	171.2	Plant
Malaxis monophyllos ssp. brachypoda	White Adder's-Mouth	E	1.6	Plant
Glyptemys insculpta	Wood Turtle	SC	396.3	Reptile
Myotis septentrionalis	Northern Long-eared Bat	Е	409.8*	Mammal

<sup>\*</sup>The acreage of the Northern Long-Eared Bat is derived from the IPaC data, since no Species Habitat Map for this species was provided by MNHESP.

Table 10-1: R5A BRA Form H: Site Degradation/Disturbance Evaluation Criteria

Area of Review <sup>1</sup>	Evaluation Criteria	SC*	Description/Rationale	Condition	Rating	Score
	invasive Species	3	Relative abundance of invasive plant species	Invasive species present but not dominant in most strata	3	9
	Site Stability	2	Level of erosion or sedimentation	Low level or none	1	2
	Soil Profile Integrity	2	Evidence of disturbed soil profile	Moderate	2	4
Aroo	Fill Disturbance	3	Evidence of filling	Moderate	2	6
Area 5A-1 East Side of	Surface Degradation	3	Evidence of dumping or other disturbance	Dumping or other physical disturbance evident	3	9
the River	Land Use Juxtaposition	1	Proximity and accessibility to land uses which may contribute to disturbance of the site.	Proximate and accessible to developed land use	3	3
	Size	1	Area of the evaluation unit	Large (>2 acres)	3	3
	Accessibility	1	Likelihood of the site being used for access or staging due to location	Highly likely	5	3
					Total Score:	39
	invasive Species	3	Relative abundance of invasive plant species	Minor presence of invasive plant species	1	3
	Site Stability	2	Level of erosion or sedimentation	Low level or none	1	2
Area 5.4.4	Soil Profile Integrity	2	Evidence of disturbed soil profile	Low level or none	1	2
	Fill Disturbance	3	Evidence of filling	Low level or none	1	3
Area 5A-1 West Side of	Surface Degradation	3	Evidence of dumping or other disturbance	Dumping or other physical disturbance evident	3	9
River	Land Use Juxtaposition	1	Proximity and accessibility to land uses which may contribute to disturbance of the site.	Remote and isolated from developed land use	1	1
	Size	1	Area of the evaluation unit	Large (>2 acres)	3	3
	Accessibility	1	Likelihood of the site being used for access or staging due to location	Unlikely	1	1
					Total Score:	24
	invasive Species	3	Relative abundance of invasive plant species	Invasive species present but not dominant in most strata	3	9
	Site Stability	2	Level of erosion or sedimentation	Low level or none	1	2
	Soil Profile Integrity	2	Evidence of disturbed soil profile	Low level or none	1	2
	Fill Disturbance	3	Evidence of filling	Low level or none	1	3
Area 5A-2	Surface Degradation	3	Evidence of dumping or other disturbance	Dumping or other physical disturbance evident	3	9
	Land Use Juxtaposition	1	Proximity and accessibility to land uses which may contribute to disturbance of the site.	Moderate juxtaposition	2	2
	Size	1	Area of the evaluation unit	Large (>2 acres)	3	3
	Accessibility	1	Likelihood of the site being used for access or staging due to location	Highly likely	5	3
					<b>Total Score:</b>	33


Table 10-1: R5A BRA Form H: Site Degradation/Disturbance Evaluation Criteria (continued)


Area of Review <sup>1</sup>	Evaluation Criteria	SC*	Description/Rationale	Condition	Rating	Score
	invasive Species	3	Relative abundance of invasive plant species	Invasive species present but not dominant in most strata	3	9
	Site Stability	2	Level of erosion or sedimentation	Low level or none	1	2
	Soil Profile Integrity	2	Evidence of disturbed soil profile	Moderate	2	4
	Fill Disturbance	3	Evidence of filling	Low level or none	1	3
Area 5A-3	Surface Degradation	3	Evidence of dumping or other disturbance	Dumping or other physical disturbance evident	3	9
	Land Use Juxtaposition	1	Proximity and accessibility to land uses which may contribute to disturbance of the site.	Moderate juxtaposition	2	2
	Size	1	Area of the evaluation unit	Large (>2 acres)	3	3
	Accessibility	1	Likelihood of the site being used for access or staging due to location	Highly likely	5	3
					Total Score:	35


<sup>1.</sup> Refer to Figure 6-3 for limits of Functional Units





# **Figures**














**Figure 3-2: Inorganic Substrate Components** 

## **Substrate Components for Overall Reach 5A**




Figure 3-2: (Continued)

## **Inorganic Substrate Components by RBP (1-9)**








Figure 3-2: (Continued)


## **Inorganic Substrate Components by RBP (10-18)**

























































## Typical Cross-Section Through Riverine and Floodplain Habitats in Reach 5A Housatonic River - Pittsfield, MA

SCALE	DATE	PROJECT NO.
N/A	8/18/2023	60670015



Figure 6-6






Figure 7-2a. Percent organic carbon by dry weight.

Metric	% oc	
Min	1.5	
Max	11.0	VP-72
Mean	4.0	
SE	0.73	
$IQR^1$	3.3	Includes 10 out of 15 Samples
Outlier Limit	10.1	Includes 1 out of 15 Samples

<sup>1.</sup> Interquartile Range, includes all samples from 25th to 75th percentile.




Figure 7-2b. Soil pH.

Metric	рН	
Min	5.6	
Max	6.9	VP-50
Mean	6.1	
SE	0.08	
$IQR^1$	0.4	Includes 10 out of 15 Samples
Outlier Limit	6.9	Includes 1 out of 15 Samples

 $<sup>{\</sup>bf 1.} \ {\bf Interquartile} \ {\bf Range, includes \ all \ samples \ from \ 25th \ to \ 75th \ percentile.}$ 




Figure 7-2c. Dissolved oxygen in water.

DO (mg/L)	
1.2	
14.5	
5.3	
0.94	
	Includes 8 out of 14
5.1	Samples
	No outliers in this dataset
	1.2 14.5 5.3 0.94

<sup>1.</sup> Interquartile Range, includes all samples from 25th to 75th percentile.




Figure 7-2d. Specific conductivity in water

	Specific	
Metric	Conductivity	
Min	100.6	
Max	1578.0	VP-18
Mean	312.7	
SE	100.27	
IQR <sup>1</sup>	157.0	Includes 8 out of 14 Samples
<b>Outlier Limit</b>	528.0	Includes 1 out of 14 Samples
1 Internuertile De	ع المعمل معربا معرب	amples from 25th to 75th

<sup>1.</sup> Interquartile Range, includes all samples from 25th to 75th percentile.








Figure 7-2e. Water pH.


Metric	Water pH	
Min	6.0	
Max	7.3	
Mean	6.7	
SE	0.11	
IQR <sup>1</sup>	0.6	Includes 8 out of 14 Samples
Outlier Limit		No outliers in this dataset
1. Interquartile Range, includes all samples from 25th to 75th percentile.		






















## Appendix A Riverine Habitat Information

- 1a. RBP Physical Data Sheets
- 1b. Incidental Wildlife Observations
- 2. Benthic Macroinvertebrate Results, Field Data Sheets and Notes
- 3. Fisheries Photo Log



# A-1a RBP Physical Data Sheets (and Incidental Wildlife Observations)

### PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

STREAM NAME House	tonic River	LOCATION Station 0+00 - 5+00		
STATION # RBP 0-1 R	VERMILE N/A	STREAM CLASS E (Rosgen)		
LAT 42.433205 LC	NG -73.251625	RIVER BASIN Housatonic		
STORET # N/A		AGENCY N/A		
INVESTIGATORS SM, 7	W, KVN, NC			
FORM COMPLETED BY		DATE 08/23/22	REASON FOR SURVEY	
SM		TIME 0920 VAM PM	Reach 5A BRA	
WEATHER CONDITIONS	Now	Past 24	Has there been a heavy rain in the last 7 days?  ☑Yes □No	
CONDITIONS	storm	(heavy rain) hours	Air Temperature 21 0 C	
	showers	steady rain) s (intermittent)	Other	
		loud cover 100 % ear/sunny	Other	
SITE LOCATION/MAP	Draw a man of the sit	and indicate the areas same	oled (or attach a photograph)	
SITE LOCATION/MAP	Draw a map of the sit	e and indicate the areas samp	ned (or attach a photograph)	
			Mary Laure	
			Macro Invert Sampling Station	
		Macro Invert	1 End	
		Sampling Station		
		1 Start		
		18 0 O		
		RBP 0-1	To the second se	
		(Confluence - BA-1)		
			Bland	
		/ (D	RBP 2-4 A-2 - BA-5)	
		So le	(A-Z-1BA-3)	
		War and the second		
	2000年	MONEY AS	5	
	Additional photo	graphs attached belov	N.	
STREAM CHARACTERIZATION	Stream Subsystem Perennial Inte	ermittent Tidal	Stream Type Coldwater Warmwater	
	Stream Origin	_	Catchment Area 339.3 km <sup>2</sup>	
	Glacial Non-glacial montane	Spring-fed  Mixture of origins	<del></del>	
	Swamp and bog	Other		

### PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERS FEATURI		Predom  ☐ Fores  ☐ Field/ ☐ Agric ☐ Resid	Pasture Industrultural Other	ercial	□ No ev □Obvid —	ous sources Vatershed Erosi	e potential sources
RIPARIA VEGETA (18 meter	TION	✓ l'rees	e the dominant type an	Shrubs	Grasses	s present He	rbaceous
INSTREA FEATURI		Estimat Samplin Area in Estimat	km² (m²x1000)  red Stream Depth  Velocity  0.5	m 53.4 m² 2.75 km²	Proport	v open Partl vater Mark 0 tion of Reach R tology Types 120 %  tology W tology H tolo	y shaded Shaded  5 m  epresented by Stream    Run 20 %
LARGE V DEBRIS	VOODY	LWD Density	50 m <sup>2</sup> of LWD 12.15	m²/km² ( <b>LWD</b> /	reach area)		
AQUATION VEGETA		Indicate the dominant type and record the dominant species present  Rooted emergent Floating Algae  dominant species present  Potamogeton Crispis  Portion of the reach with aquatic vegetation 3 %				Free floating	
WATER (	QUALITY	Temperature 19.8 ° C Specific Conductance 0.563 Dissolved Oxygen 7.45 mg/L pH 8.18 Turbidity WQ Instrument Used YSI 650			□Petrol □Fishy  Water S □Slick □None  Turbidi □ Clear	aal/None Sewa leum Surface Oils Sheen Other	Chemical Other
SEDIMEN SUBSTRA					☐ ☐Relief	ge	Paper fiber Sand Other Sand/Mud h are not deeply embedded, k in color?
INORGANIC SUBSTRATE COMPONENTS (should add up to 100%)					SUBSTRATE C		
Substrate Type	te Diameter % Composition in Sampling Reach		Substrate Type	Chara	acteristic	% Composition in Sampling Area	
Bedrock Boulder	> 256 mm (10")	> 256 mm (10") 2		Detritus	sticks, wood, materials (CP		10
Cobble Gravel	64-256 mm (2.5	64-256 mm (2.5"-10")		Muck-Mud	black, very fir (FPOM)	ne organic	5
Sand Silt Clay	0.06-2mm (gritty)		Marl	grey, shell fra	gments	0	

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION 0+00 - 5+00
STATION # RBP 0-1 RIVERMILE N/A	STREAM CLASS E (Rosgen)
LAT 42.433205 LONG -73.251625	RIVER BASIN Housatonic
STORET # N/A	AGENCY N/A
INVESTIGATORS SM, TW, KVN, NC	
FORM COMPLETED BY	DATE 08/23/22 REASON FOR SURVEY
SM	TIME O920 PM Reach 5A BRA

	Habitat	Condition Category				
	Parameter	Optimal	Suboptimal	Marginal	Poor	
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.	
eac	SCORE 14	20 19 18 17 16	15 (14) 13 12 11	10 9 8 7 6	5 4 3 2 1 0	
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization	Mixture of substrate materials, with gravel and firm sand prevalent; root mats and submerged vegetation common.	Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.	
nate	SCORE 12	20 19 18 17 16	15 14 13 (12) 11	10 9 8 7 6	5 4 3 2 1 0	
ers to be eval	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large- deep; very few shallow.	Shallow pools much more prevalent than deep pools.	Majority of pools small-shallow or pools absent.	
mete	SCORE 17	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0	
Para	4. Sediment Deposition  Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.		Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.	
	SCORE 11	20 19 18 17 16	15 14 13 12 (1)	10 9 8 7 6	5 4 3 2 1 0	
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.	
	SCORE 14	20 19 18 17 16	15 (14) 13 12 11	10 9 8 7 6	5 4 3 2 1 0	

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat	Condition Category				
	Parameter	Optimal	Suboptimal	Marginal	Poor	
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.	
	SCORE 19	20 (19) 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0	
ling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.	
ı san	SCORE 17	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0	
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.	
eva	SCORE 4 (LB)	Left Bank 10 9	8 7 6	5 (4) 3	2 1 0	
to be	SCORE 4 (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0	
Parameters	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.	
	SCORE 4 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0	
	SCORE 5 (RB)	Right Bank 10 9	8 7 6	<b>5</b> 4 3	2 1 0	
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.	
	SCORE (LB)	Left Bank 10 <b>9</b>	8 7 6	5 4 3	2 1 0	
	SCORE (RB)	Right Bank 10 <b>9</b>	8 7 6	5 4 3	2 1 0	

Total Score 139

Incidental Direct Wildlife Observations	
American toad	
Beaver sign	

### **AECOM** Imagine it. Delivered.

#### PHOTOGRAPHIC LOG

Client Name:

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

**Date:** 08/23/22

Direction Photo Taken: North

Description:

Station RBP 0-1 looking upstream contains a short run. The shoreline consists of grassy vegetation along with large bushes and trees. The banks have slight signs of erosion and bits of woody debris.

Substrate is largely composed of silt with smaller percentages of gravel, cobble, and clay.




Photo No.

**Date:** 8/23/22

Direction Photo Taken: South

Description:

RBP 0-1 looking downstream. This section of the river consisted of a pool around five feet deep. There is little to no woody debris and the partly overhanging canopy is made up of silver and red maple trees.





### **PHOTOGRAPHIC LOG**

Client Name:Site Location:Project No.GEReach 5A Housatonic River60689453

Photo No. Date: 8/23/22

Direction Photo Taken: Southeast

Description:
RBP 0-1 looking
downstream. This section
of RBP 0-1 was
dominated by a pool
environment with slight
shoreline erosion. Similar
to the previous image, the
pool is around five feet
deep and there is a partly
overhanging canopy.



### PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

STREAM NAME Housatonic River		LOCATION Station 5+00 - 11+00		
STATION # RBP 2-4 R	VERMILE N/A	STREAM CLASS E (Rose	gen)	
LAT 42.432825 LC	ONG -73.250741	RIVER BASIN Housatoni	С	
STORET # N/A		AGENCY N/A		
INVESTIGATORS SM, 7	W, KVN, NC			
FORM COMPLETED BY	_	DATE 08/23/22	REASON FOR SURVEY	
KVN		TIME 1024 VAM PM	Reach 5A BRA	
WEATHER CONDITIONS	rain (  showers  y  %  w  %cl	(heavy rain) (steady rain) (s (intermittent) loud cover ear/sunny	Has there been a heavy rain in the last 7 days?  Yes No  Air Temperature 21 ° C  Other	
SITE LOCATION/MAP	RBP 0-1	E R		
STREAM CHARACTERIZATION	Stream Subsystem Perennial Inte Stream Origin Glacial Non-glacial montane Swamp and bog	ermittent ☐Tidal  Spring-fed  Mixture of origins  Other  Other	Stream Type  ☐ Coldwater ✓ Warmwater  Catchment Area ☐ km²	

### PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERSHED FEATURES		l/Pasture ☐ Industri cultural ☐ Other	rcial	Local Watershed NPS  □ No evidence □ Som □ Obvious sources □ Local Watershed Eros □ None □ Moderate	e potential sources
RIPARIAN VEGETATION (18 meter buffer)	✓ l`ree	te the dominant type and s S ant species present Box	nrubs	Grasses THO	erbaceous
INSTREAM FEATURES	Estima Sampl Area i Estima		m m m s m s m m m m m m m m m m m m m m	Morphology Types	ly shaded □Shaded □m  tepresented by Stream Run 70
LARGE WOODY DEBRIS	LWD Densit	200 m <sup>2</sup> y of LWD 58.8 n	n <sup>2</sup> /km <sup>2</sup> (LWD/	reach area)	
AQUATIC VEGETATION	□Roo □Floa domin	Indicate the dominant type and record the dominant species present  Rooted emergent  Floating Algae  dominant species present  Very sparse  Portion of the reach with aquatic vegetation 0.5 %			
WATER QUALITY	Specif Dissolp H 8.	<del></del>	ms/cm	Water Odors  □ Normal/None □ Sew □ Petroleum □ Fishy  Water Surface Oils □ Slick □ Sheen □ None □ Other □ Turbidity (if not meas □ Clear □ Slightly to □ Opaque □ Stained	Chemical Other Globs Flecks
SEDIMENT/ SUBSTRATE	Otho Oils	nical Anaerobic	Petroleum None	Looking at stones which	Paper fiber Sand Other Sand/Mud ch are not deeply embedded, ck in color?
	INORGANIC SUBSTRATE COMPONENTS (should add up to 100%)			ORGANIC SUBSTRATE ( (does not necessarily add	
Substrate Type D	e Diameter % Composition in Sampling Reach		Substrate Type	Characteristic	% Composition in Sampling Area
Bedrock Boulder > 256 mm	(10")	0	Detritus	sticks, wood, coarse plant materials (CPOM)	20
Cobble 64-256 m	64-256 mm (2.5"-10")		Muck-Mud	black, very fine organic (FPOM)	5
Silt 0.004-0.0	0.06-2mm (gritty) 40 0.004-0.06 mm 20 < 0.004 mm (slick) 10		Marl	grey, shell fragments	0

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION Station 5+00 - 11+00
STATION # RBP 2-4 RIVERMILE N/A	STREAM CLASS E (Rosgen)
LAT 42.432825 LONG -73.250741	RIVER BASIN Housatonic
STORET # N/A	AGENCY N/A
INVESTIGATORS SM, TW, KVN, NC	
FORM COMPLETED BY	DATE 08/23/22 REASON FOR SURVEY
KVN	TIME 1024 ✓ ✓ ✓ PM Reach 5A BRA

	Habitat	Condition Category				
	Parameter	Optimal	Suboptimal	Marginal	Poor	
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.	
each	SCORE 13	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0	
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization  Mixture of substrate materials, with gravel an firm sand prevalent; root mats and submerged vegetation common.		Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.	
nate	SCORE 16	20 19 18 17 (6)	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0	
rs to be eval	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large- deep; very few shallow.	Shallow pools much more prevalent than deep pools.	Majority of pools small-shallow or pools absent.	
mete	SCORE 16	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0	
Para	4. Sediment Deposition  Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.		Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.	
	SCORE 12	20 19 18 17 16	15 14 13 (12) 11	10 9 8 7 6	5 4 3 2 1 0	
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.	
	SCORE 15	20 19 18 17 16	(15) 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0	

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat	Condition Category			
	Parameter	Optimal	Suboptimal	Marginal	Poor
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.
	SCORE 19	20 (19) 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
oling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.
ı sar	SCORE 14	20 19 18 17 16	15 (14) 13 12 11	10 9 8 7 6	5 4 3 2 1 0
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.
e eva	SCORE 8 (LB)	Left Bank 10 9	<b>(8)</b> 7 6	5 4 3	2 1 0
to be	SCORE (RB)	Right Bank 10 9	8 7 6	5 4 ③	2 1 0
Parameters	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.
	SCORE 5 (LB)	Left Bank 10 9	8 7 6	<b>5</b> 4 3	2 1 0
	SCORE 5 (RB)	Right Bank 10 9	8 7 6	<b>5</b> 4 3	2 1 0
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.
	SCORE (LB)	Left Bank (10) 9	8 7 6	5 4 3	2 1 0
	SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0

Total Score 146

Incidental Direct Wildlife Observations	
painted turtle	
green frog	
2 unidentified fish aprox 12"	
hummingbird	
water strider	
belted kingfisher	
pollinators (honeybee, yellow jacket)	
	·



#### **PHOTOGRAPHIC LOG**

Client Name:

GΕ

Site Location:

Reach 5A Housatonic River

Project No.

60689453

Photo No.

Date: 8/23/22

**Direction Photo** 

Taken:

East

**Description:**RBP 2-4 looking
downstream. This section of pool/run contained a moderate number of woody debris including fallen logs. A dead tree overhanging the river may provide another source of woody debris in the future. The shoreline consists of many trees.




Photo No.

Date: 8/23/22

**Direction Photo** 

Taken:

West

**Description:** 

RBP 2-4 looking upstream shows a run with large cluster of woody debris in the middle of the river and smaller clumps closer to the shoreline.



Photo No. 3

Date: 8/23/22

**Direction Photo** 

Taken: South

**Description:** Further downstream in RBP 2-4 looking downstream. This section contains a shallow riffle/run with a sand/gravel bar and woody debris piled on top. The left side of the image shows erosion and slope failure, leading to multiple trees leaning over the river.



### PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

STREAM NAME Housatonic River		LOCATION Station 11+00 - 24+00		
STATION # RBP 5-6 R	VERMILE N/A	STREAM CLASS	(Rosgen)	
LAT 42.430558 LC	NG -73.249828	RIVER BASIN Hou	satonic	
STORET # N/A		AGENCY N/A		
INVESTIGATORS SM, 7	W, KVN, NC			
FORM COMPLETED BY		DATE 08/23/22		FOR SURVEY
SM		TIME 1030	<sup>AM□PM</sup> Reach	5A BRA
WEATHER CONDITIONS	Now	Pas hor		een a heavy rain in the last 7 days? No
CONDITIONS	storm	(heavy rain)		ature 22 C
	✓ showers	s (intermittent)	Othor	C
	100 %	oud cover sar/sunny	<u> </u>	
SITE LOCATION/MAP	Draw a map of the site	•	as sampled (or attach	ı a photograph)
	Draw a map of ene six		o sumpreu (or uccuer	a photograph)
				<b>""和""等。</b>
				WATER CO.
	A PROPERTY OF	RBP	5-6	是多数性的高点
		(BA-6-)	BA-7)	<b>这些人的</b>
				心理的。27 会对为
	To the			
	THE WAY			
	A PAN			<b>人</b> 中国 医多罗
				ALCE A.
				R
	4		11	(BA
	1000			Cha
	Additional photo	aranhe attachad	helow	
		grapiis attacileu	DEIUW.	
STREAM CHARACTERIZATION	Stream Subsystem  Perennial Inte	ermittent Tidal	Stream Typ Coldwater	e Warmwater
CIMMICI EMEATION	Stream Origin		Catchment A	
	Glacial Non-glacial montane	Spring-fed Mixture of original		<del></del>
	Swamp and bog	Other		

### PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERS FEATURI		Predom  ☐ Forest ☐ Field/ ☐ Agric ☐ Resid	Pasture Indus Utural Other	nercial trial	Local Watershed NPS  □ No evidence □ Som □ Obvious sources  Local Watershed Eros □ None □ Moderate	e potential sources
RIPARIAI VEGETAT (18 meter	TION	✓ I rees	e the dominant type a v nt species present	Shrubs		erbaceous
INSTREA FEATURE		Estimat Samplin Area in Estimat	red Stream Depth 1.:  Velocity 0.5	m 01m² 7.7km²	High Water Mark 1 Proportion of Reach R Morphology Types	ly shaded ☐ Shaded  .5m  tepresented by Stream  Run 65%  ☑No ☑No
LARGE V DEBRIS	VOODY	LWD Density	150 m <sup>2</sup> of LWD 16.44	]m²/km² (LWD/	reach area)	
AQUATIO VEGETA		☐Roote ☐Floati domina	ed emergent	Rooted submerge Attached Algae otamogeton	crispis	Free floating
WATER (	QUALITY	Temper Specific Dissolve pH 8.09	ature 19.6 ° C Conductance 0.597 ed Oxygen 6.53 mg/L	☐ms/cm	Water Odors  ☑Normal/None ☐Sew ☐Petroleum ☐Fishy  Water Surface Oils	Chemical Other  Globs Flecks
SEDIMEN SUBSTRA		Odors Norm Chem Other Oils	ical Anaerobic	Petroleum None	Looking at stones which	Paper fiber Sand Other Sand/Mud ch are not deeply embedded, ck in color?
INORGANIC SUBSTRATE COMPONENTS (should add up to 100%)				ORGANIC SUBSTRATE (		
Substrate Type	Diamete	Diameter % Composition in Sampling Reach		Substrate Type	Characteristic	% Composition in Sampling Area
Bedrock Boulder	> 256 mm (10")	0 0		Detritus	sticks, wood, coarse plant materials (CPOM)	7
Cobble Gravel	64-256 mm (2.5 2-64 mm (0.1"-2	5"-10") 10		Muck-Mud	black, very fine organic (FPOM)	1
Sand Silt Clay	0.06-2mm (gritty 0.004-0.06 mm < 0.004 mm (slie	y) 25 25		Marl	grey, shell fragments	0

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION Station 11+00 - 24+00		
STATION # RBP 5-6 RIVERMILE N/A	STREAM CLASS E (Rosgen)		
LAT <u>42.430558</u> LONG <u>-73.249828</u>	RIVER BASIN Housatonic		
STORET # N/A	AGENCY N/A		
INVESTIGATORS SM, TW, KVN, NC			
FORM COMPLETED BY	DATE 08/23/22 REASON FOR SURVEY		
SM	TIME 1030 ✓ ✓ ✓ PM Reach 5A BRA		

	Habitat		Condition	Category	
	Parameter	Optimal	Suboptimal	Marginal	Poor
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.
each.	SCORE 10	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization	Mixture of substrate materials, with gravel and firm sand prevalent; root mats and submerged vegetation common.	Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.
uate	SCORE 10	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
ers to be eval	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large- deep; very few shallow.	Shallow pools much more prevalent than deep pools.	Majority of pools small-shallow or pools absent.
mete	SCORE 16	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
Para	4. Sediment Deposition	Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.
	SCORE 09	20 19 18 17 16	15 14 13 12 11	10 (9) 8 7 6	5 4 3 2 1 0
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.
	SCORE 12	20 19 18 17 16	15 14 13 (12) 11	10 9 8 7 6	5 4 3 2 1 0

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat		Condition	. Category	
	Parameter	Optimal	Suboptimal	Marginal	Poor
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.
	SCORE 17	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
npling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.
ı sar	SCORE 6	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.
eva	SCORE 6 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
to be	SCORE 5 (RB)	Right Bank 10 9	8 7 6	<b>⑤</b> 4 3	2 1 0
Parameters	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.
	SCORE 6 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
	SCORE 6 (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.
	SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
	SCORE (RB)	Right Bank 10 9	<b>8</b> 7 6	5 4 3	2 1 0

Total Score 119

Incidental Direct Wildlife Observations	
crayfish	
mussels- eliptio	
great blue heron	
frogs	
deer tracks	
beaver slide	
racoon tracks & scat	
	•



### **PHOTOGRAPHIC LOG**

Client Name:

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.


**Date:** 8/23/22

**Direction Photo** 

Taken: Southwest

**Description:** 

RBP 5-6 looking downstream. Maple trees provide a partial canopy over the river's run. Erosion is affecting the shoreline on the right side which is covered in shrubs and trees. Grassy vegetation and shrubs cover the left shoreline.



## PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

STREAM NAME Housatonic River		LOCATION Station 24+00 - 38+00		
STATION # RBP 7-9 RI	VERMILE N/A	STREAM CLASS E (Rosgen)		
LAT 42.429998 LC	NG -73.246600	RIVER BASIN Housatonic		
STORET # N/A		AGENCY N/A	\	
INVESTIGATORS SM, T	W, KVN, NC			
FORM COMPLETED BY KVN		DATE 08/23/22 TIME 1510	☐ ☐AM <b>☑</b> PM	REASON FOR SURVEY Reach 5A BRA
WEATHER CONDITIONS	rain (s showers 40 % v %clo	(heavy rain) steady rain) (intermittent) oud cover ar/sunny	Past 24 hours	Has there been a heavy rain in the last 7 days?  Yes No  Air Temperature 22 C
SITE LOCATION/MAP	Draw a map of the site	and indicate the	e areas samp	led (or attach a photograph)
	_		-	•
				RBP,10-11 (BA-11-BA-12)
	Additional photog	graprio attaci	i ieu beiow	v.
STREAM CHARACTERIZATION	Stream Subsystem  ✓ Perennial Interest Perennial Stream Origin  ☐ Glacial Non-glacial montane ☐ Swamp and bog	rmittent Tida  Spring-fec  Mixture o  Other	1	Stream Type  Coldwater  ✓ Warmwater  Catchment Area  km²

### PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERSHED FEATURES	✓ Fores	Pasture Industricultural Other	ercial	Local Watershed NPS  □ No evidence □ Som □ Obvious sources  □ Local Watershed Eros □ None □ Moderate	e potential sources
RIPARIAN VEGETATION (18 meter buffer)	✓ l'rees	e the dominant type and Silvent species present	hrubs		erbaceous
INSTREAM FEATURES	Estimate Samplin Area in Estimate	ted Stream Depth 1.5  Velocity 0.5 n	m m 72 m² .8 km² m	Morphology Types	ly shaded Shaded m  tepresented by Stream Run 70 %  No
LARGE WOODY DEBRIS	LWD Density	500 m <sup>2</sup> of LWD 40 r	m²/km² ( <b>LWD</b> /	reach area)	
AQUATIC VEGETATION	□Roote □Float	ed emergent $\square$ R	ooted submerge ttached Algae tamogeton	crispis	Free floating
WATER QUALITY				Water Odors  ☑ Normal/None ☐ Sew ☐ Petroleum ☐ Fishy  Water Surface Oils ☐ Slick ☐ Sheen ☑ None ☐ Other ☐ Turbidity (if not meas) ☐ Clear ☑ Slightly to ☐ Opaque ☐ Stanned	Chemical Other  Globs Flecks
SEDIMENT/ SUBSTRATE					Paper fiber Sand Other Sand/Mud ch are not deeply embedded, ck in color?
INORGANIC SUBSTRATE COMPONENTS (should add up to 100%)				ORGANIC SUBSTRATE ( (does not necessarily add	
Substrate Type Diame	Diameter % Composition i Sampling Reach		Substrate Type	Characteristic	% Composition in Sampling Area
Bedrock Boulder > 256 mm (10	")	0	Detritus	sticks, wood, coarse plant materials (CPOM)	10
Cobble 64-256 mm (2 Gravel 2-64 mm (0.1"	5"-10")	5 20	Muck-Mud	black, very fine organic (FPOM)	0
Sand 0.06-2mm (gri Silt 0.004-0.06 mm	2-64 mm (0.1"-2.5") [20 0.06-2mm (gritty) [45 0.004-0.06 mm [25] < 0.004 mm (slick) [5]		Marl	grey, shell fragments	0

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION Station 24+00 - 38+00				
STATION # RBP 7-9 RIVERMILE N/A	STREAM CLASS E (Rosgen)				
LAT 42.429998 LONG -73.246600	RIVER BASIN Housatonic				
STORET # N/A	AGENCY N/A				
INVESTIGATORS SM, TW, KVN, NC					
FORM COMPLETED BY KVN	DATE 08/23/22 REASON FOR SURVEY Reach 5A BRA				

	Habitat	Condition Category					
	Parameter	Optimal	Suboptimal	Marginal	Poor		
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.		
eac	SCORE 16	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization	Mixture of substrate materials, with gravel and firm sand prevalent; root mats and submerged vegetation common.	Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.		
nate	SCORE 10	20 19 18 17 16	15 14 13 12 11	0 9 8 7 6	5 4 3 2 1 0		
ers to be eval	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large-deep; very few shallow.	Shallow pools much more prevalent than deep pools.	Majority of pools small-shallow or pools absent.		
mete	SCORE 13	20 19 18 17 16	15 14 🔞 12 11	10 9 8 7 6	5 4 3 2 1 0		
Para	4. Sediment Deposition	Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.		
	SCORE 11	20 19 18 17 16	15 14 13 12 (1)	10 9 8 7 6	5 4 3 2 1 0		
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.		
	SCORE 14	20 19 18 17 16	15 (4) 13 12 11	10 9 8 7 6	5 4 3 2 1 0		

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat		Condition	. Category	
	Parameter	Optimal	Suboptimal	Marginal	Poor
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.
	SCORE 17	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
npling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.
ı san	SCORE 12	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.
e eva	SCORE 4 (LB)	Left Bank 10 9	8 7 6	5 (4) 3	2 1 0
to be	SCORE 5 (RB)	Right Bank 10 9	8 7 6	<b>5</b> 4 3	2 1 0
Parameters	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.
	SCORE 5 (LB)	Left Bank 10 9	8 7 6	<u>§</u> 4 3	2 1 0
	SCORE 5 (RB)	Right Bank 10 9	8 7 6	<b>3</b> 4 3	2 1 0
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.
	SCORE (LB)	Left Bank 0 9	8 7 6	5 4 3	2 1 0
	SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0

Total Score 132

Incidental Direct Wildlife Observations	
pickerel frog	
killdeer	
dragonfly	
unidentified fish	
bluejay	
catbird (2x)	
whirligig beetles	
pollinators (honeybee, yellowjacket)	



### **PHOTOGRAPHIC LOG**

Client Name:Site Location:Project No.GEReach 5A Housatonic River60689453


Photo No. Date: 8/23/22

Direction Photo Taken:

West

#### **Description:**

RBP 7-9 looking upstream. This run contains many groups of woody debris along both shorelines, resulting in good cover for epifaunal organisms and fish. This section of RBP 7-9 had slight erosion, but other parts had more moderate erosion issues.



### PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

STREAM NAME Housatonic River		LOCATION Station 38+00 - 56+00				
STATION # RBP 10-11 R	STREAM CLASS E (Rosgen)					
LAT 42.429839 LC	RIVER BASIN Housatonic					
STORET # N/A	AGENCY N/A	1				
INVESTIGATORS SM, 7	INVESTIGATORS SM, TW, KVN, NC					
FORM COMPLETED BY	_	DATE 08/23/22	<u></u>	REASON FOR SURVEY		
SM		TIME 1445	AM ✓ PM	Reach 5A BRA		
WEATHER CONDITIONS	rain (: showers 100 %   rain (: showers	(heavy rain) steady rain) s (intermittent) oud cover ear/sunny	hours	Has there been a heavy rain in the last 7 days?  Yes No  Air Temperature 22 0 C  Other		
SITE LOCATION/MAP	Draw a map of the site of the		(BA-1)	Macro Invert Sampling Station 2 End Station		
STREAM CHARACTERIZATION	Stream Subsystem Perennial Inte Stream Origin Glacial Non-glacial montane Swamp and bog	ermittent Tida Spring-fed Mixture of Other	ı	Stream Type  ☐Coldwater ☑Warmwater  Catchment Area ☐ km²		

### PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERS FEATURI		Predom  ☐ Fores ☐ Field/ ☐ Agric ☐ Resid	Pasture Industrul Other	ercial	— L	Local Watershed NPS Pollution  ☐ No evidence ☐ Some potential sources ☐ Obvious sources  Local Watershed Erosion ☐ None ☐ Moderate ☐ Heavy	
RIPARIAI VEGETAT (18 meter	TION	Indicate the dominant type and record the dominant species present   Trees					
INSTREA FEATURE		Estimat Samplin Area in Estimat	ted Stream Depth 0.7	m 04 m² 0.4 km²	H P N V	Canopy Cover Partly open Partly High Water Mark 2 Proportion of Reach Re Morphology Types Riffle 15 %  Pool 30 %  Channelized Yes  Oam Present Yes	m
LARGE W DEBRIS	VOODY	LWD 200 m²  Density of LWD 16.33 m²/km² (LWD/ reach area)					
AQUATIC VEGETA		Indicate the dominant type and record the dominant species present  Rooted emergent Floating Algae  dominant species present  Potamogeton crispis  Portion of the reach with aquatic vegetation 2 %					
WATER QUALITY  Temperature 20.2 ° C Specific Conductance 0.594 Dissolved Oxygen 7.47 mg/L pH 8.36 Turbidity WQ Instrument Used YS1 650				L V L	Fishy Water Surface Oils	Chemical Other Globs Flecks red)	
SEDIMENT/ SUBSTRATE  Odors  Normal Chemical Other  Oils  Absent Sewage Chemical Sewage Chemical Normal Anaerobic Modera			∏Petroleum ∏None			Paper fiber Sand Other Sand/Mud n are not deeply embedded, k in color?	
INORGANIC SUBSTRATE COMPONENTS (should add up to 100%)					ANIC SUBSTRATE Co		
Substrate Type	Diamete	er	% Composition in Sampling Reach	Substrate Type		Characteristic	% Composition in Sampling Area
Bedrock Boulder	> 256 mm (10")		6	Detritus		wood, coarse plant als (CPOM)	5
Cobble Gravel	64-256 mm (2.5"-10") 2-64 mm (0.1"-2.5")		30	Muck-Mud	black, (FPOM	very fine organic M)	3
Sand Silt Clay	0.06-2mm (gritty) 0.004-0.06 mm < 0.004 mm (slick)		30 29 3	Marl	grey, si	shell fragments	0

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION Station 38+00 - 56+00			
STATION # RBP 10-11 RIVERMILE N/A	STREAM CLASS E (Rosgen)			
LAT 42.429839 LONG -73.241568	RIVER BASIN Housatonic			
STORET # N/A	AGENCY N/A			
INVESTIGATORS SM, TW, KVN, NC				
FORM COMPLETED BY	DATE 08/23/22 REASON FOR SURVEY			
SM	TIME [1445			

	Habitat	Condition Category				
	Parameter	Optimal	Suboptimal	Marginal	Poor	
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.	
each	SCORE 10	20 19 18 17 16	15 14 13 12 11	9 8 7 6	5 4 3 2 1 0	
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization	Mixture of substrate materials, with gravel and firm sand prevalent; root mats and submerged vegetation common.	Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.	
	SCORE 11	20 19 18 17 16	15 14 13 12 (1)	10 9 8 7 6	5 4 3 2 1 0	
	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large- deep; very few shallow.	Shallow pools much more prevalent than deep pools.	Majority of pools small-shallow or pools absent.	
mete	SCORE 14	20 19 18 17 16	15 (14) 13 12 11	10 9 8 7 6	5 4 3 2 1 0	
Para	4. Sediment Deposition	Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.	
	SCORE 8	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0	
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.	
	SCORE 9	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0	

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat				
	Parameter	Optimal	Suboptimal	Marginal	Poor
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.
	SCORE 13	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
pling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.
ı sar	SCORE 8	20 19 18 17 16	15 14 13 12 11	10 9 🚷 7 6	5 4 3 2 1 0
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.
eva	SCORE 4 (LB)	Left Bank 10 9	8 7 6	5 (4) 3	2 1 0
to be	SCORE 4 (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0
Parameters t	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.
	SCORE 6 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
	SCORE 6 (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.
	SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
	SCORE (RB)	Right Bank 10 9	<b>③</b> 7 6	5 4 3	2 1 0

Total Score 107

Incidental Direct Wildlife Observations				
clams				
green frogs				
racoon scat				
minnows				
eliptio mussels				



Client Name:

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

**Date:** 8/23/22

Direction Photo Taken:

Southwest

Description:

RBP 10-11 looking upstream near Pomeroy Ave Bridge. A shallow run flows underneath the bridge and past a deposited sand bar on both sides. Litter is scattered on the riverbed.



Photo No.

**Date:** 8/23/22

Direction Photo Taken:

East

Description:

RBP 10-11 looking downstream. This section contains a short riffle that cuts through the sand bar. The rest of the stream in this section is a shallow run. Dense vegetation on both shorelines. Cobble covers the slope on the right shoreline.





**Client Name:** 

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No. 3

Date:


8/23/22

#### **Direction Photo** Taken:

Northeast

### Description:

RBP 11 outer bend. The outer bend of RBP 11 contains rip rap to prevent shoreline erosion near houses. The water also gets deeper on the outer bend and changes from a run to a pool.



# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

STREAM NAME Housatonic River		LOCATION Station 56+00 - 88+00			
STATION # RBP 12-13 R	VERMILE N/A	STREAM CLASS E (Rosgen)			
LAT 42.426141 LC	ONG -73.238070	RIVER BASIN Housatonic			
STORET # N/A		AGENCY N/A			
INVESTIGATORS SM, T	W, KVN, NC				
FORM COMPLETED BY		DATE 08/23/22 TIME 1545 AM PA	REASON FOR SURVEY		
SM		THVIE 1043 AMP-PM	Reach 5A BRA		
	Г				
WEATHER CONDITIONS	Now	Past 24 hours	Has there been a heavy rain in the last 7 days?  ☑Yes □No		
	storm	(heavy rain) (steady rain)	Air Temperature 22 C		
	showers	s (intermittent)	Other		
	70 % V %cl	loud cover			
SITE LOCATION/MAP	Draw a man of the site	e and indicate the areas sam	pled (or attach a photograph)		
22220111010111111	Page Invert	and the tree of same	r ( protog-up")		
	Station 2 Start	Trail or 1	ZERN N		
	RBP 1041 Sympling				
	(BA-11 BA-12) Station 2 End				
	4/ 2				
			Though the same		
	4	17 Car 17 - A			
		1/61 1000			
		(BA-13 - BA-14)			
	COMPANY NO		100		
	(一) 學(一) 近	- Kende	Contract of the Contract of th		
			ana di di		
	Additional photo	graphs attached belo	W.		
STREAM	Stream Subsystem Perennial Inte	To a Province	Stream Type		
CHARACTERIZATION		ermittent Tidal	Coldwater Warmwater		
	Stream Origin	Spring-fed	Catchment Area km²		
	Non-glacial montane Swamp and bog	Mixture of origins Other			

# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERS FEATURI		Predon  ☐ Fores ☐ Field ☐ Agric ☐ Resid	Pasture Indust ultural Other	ercial	Local Watershet □ No evidence [ □ Obvious source  Local Watershet □ None □ Mod	Some potential sources  Erosion	
RIPARIAI VEGETAT (18 meter	TION	✓ l'rees	e the dominant type an	Shrubs	minant species present Grasses	Herbaceous	
INSTREA FEATURE		Estimat Samplin Area in Estimat	red Stream Depth 1.5 Velocity 0.25	m 668 m² 9.5 km²	High Water Mar  Proportion of Re Morphology Typ Riffle 5 9 Pool 65 9 Channelized	ach Represented by Stream les  " Run 30 %	
LARGE W DEBRIS	VOODY	LWD Density	500 m <sup>2</sup> of LWD 20.5	m²/km² (LWD/	reach area)		
AQUATIC VEGETA		☐Roote ☐Floati	ng Algae	Rooted submerge Attached Algae otamogeton	mogeton crispis + algae		
WATER QUALITY  Temperature 20.83 ° C  Specific Conductance 0.582  Dissolved Oxygen 7.41 mg/L  pH 8.57  Turbidity			_	Water Odors  ✓ Normal/None [  ─ Petroleum  ☐ Fishy  Water Surface O  ☐ Slick ☐ She  ☐ None ☐ Oth  Turbidity (if not  ☐ Clear ☐ Slig  ✓ Opaque ✓ Star	ils en Globs Flecks er measured) htly turbid Turbid		
SEDIMENT/ SUBSTRATE  Odors  Normal Chemical Anaerobic Other  Oils  Absent Sewage Chemical Anaerobic Other  Oils			□Petroleum □None  ate □Profu	are the undersid	dust Paper fiber Sand Other Sand/Mud  s which are not deeply embedded, es black in color?		
INORGANIC SUBSTRATE COMPONENTS (should add up to 100%)				ORGANIC SUBSTRA	ATE COMPONENTS y add up to 100%)		
Substrate Type	e Diameter		% Composition in Sampling Reach	Substrate Type	Characteristic	% Composition in Sampling Area	
Bedrock Boulder	> 256 mm (10")		3	Detritus	sticks, wood, coarse pla materials (CPOM)	nt 5	
Cobble Gravel	64-256 mm (2.5 2-64 mm (0.1"-2	"-10")	3	Muck-Mud	black, very fine organic (FPOM)	0	
Sand Silt Clay	0.06-2mm (gritty) 0.004-0.06 mm < 0.004 mm (slick)		32 20 10	Marl	grey, shell fragments	0	

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION Station 56+00 - 88+00		
STATION # RBP 12-13 RIVERMILE N/A	STREAM CLASS E (Rosgen)		
LAT 42.426141 LONG -73.238070	RIVER BASIN Housatonic		
STORET # N/A	AGENCY N/A		
INVESTIGATORS SM, TW, KVN, NC			
FORM COMPLETED BY SM	DATE 08/23/22 REASON FOR SURVEY TIME 1545 PAM PPM Reach 5A BRA		

	Habitat	Condition Category					
	Parameter	Optimal	Suboptimal	Marginal	Poor		
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.		
each	SCORE 12	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization	Mixture of substrate materials, with gravel and firm sand prevalent; root mats and submerged vegetation common.	Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.		
uate	SCORE 12	20 19 18 17 16	15 14 13 (2) 11	10 9 8 7 6	5 4 3 2 1 0		
rs to be eval	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large-deep; very few shallow.	Shallow pools much more prevalent than deep pools.	Majority of pools small-shallow or pools absent.		
mete	SCORE 11	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		
Para	4. Sediment Deposition	Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.		
	SCORE 8	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.		
	SCORE 10	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat		Condition	. Category		
	Parameter	Optimal	Suboptimal	Marginal	Poor	
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.	
	SCORE 13	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0	
npling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.	
ı sar	SCORE 6	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0	
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.	
eva	SCORE 5 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0	
to be	SCORE 5 (RB)	Right Bank 10 9	8 7 6	<b>5</b> 4 3	2 1 0	
Parameters	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.	
	SCORE 6 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0	
	SCORE 6 (RB)	Right Bank 10 9	8 7 🜀	5 4 3	2 1 0	
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.	
	SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0	
	SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0	

Total Score 108

Incidental Direct Wildlife Observations				
Deer tracks				
Eastern elliptio mussels				
racoon sign				



**Client Name:** 

**Site Location:** 

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No. 1

Date: 8/23/22

**Direction Photo** Taken:

South

**Description:** 

Beginning of RBP 12 looking downstream. Silver maple trees and shrubs cover the shorelines. This section contains many deep pools and sections of run. Woody debris piles can be found on the shorelines.



Photo No. 2

Date: 8/23/22

**Direction Photo** Taken:

North

Description:

Lower half of RBP 12 looking upstream. Woody debris is scattered along the shorelines. In this section, there is a slight riffle, but mainly a run with a pool at the outer bend. Silver maple trees make up the majority of riparian vegetation.





**Client Name:** 

**Site Location:** 

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

3

Date: 8/23/22

#### **Direction Photo** Taken:

South

### Description:

Lower half of RBP 12 looking downstream. This shallow section of RBP 12 contains riffles near the sand bars and runs near the left shoreline.



Photo No. 4

Date: 8/23/22

#### **Direction Photo** Taken:

North

Description:
Beginning of RBP 13
looking upstream. This section contains a large pool on the outer bend with overhanging maple trees. Erosion can also be seen on the outer bend's shoreline.





**Client Name:** 

**Site Location:** 

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

**Date:** 8/23/22

### Direction Photo Taken:

Southeast

### **Description:**

RBP 13 has large woody debris that provides good cover/habitat for underwater organisms. Floating debris is also being caught on the branches in this pool area. The shoreline is experiencing moderate erosion.



Photo No.

**Date:** 8/23/22

### Direction Photo Taken:

East

### Description:

Downstream of RBP 13 has branches and other woody debris. The shorelines have slight erosion in this pool area. Silver maples and shrubs make up the riparian vegetation.



# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

STREAM NAME Housa	tonic River	LOCATION Station 88+00 - 104+00				
STATION # RBP 14 R	VERMILE N/A	STREAM CLASS E (Rosgen)				
LAT 42.25222 LO	NG <u>-73.14145</u>	RIVER BASIN Housatonic				
STORET # N/A		AGENCY N/A				
INVESTIGATORS SM, T	W, KVN, NC					
FORM COMPLETED BY		DATE 08/23/22 TIME 1710 AM	REASON FOR SURVEY			
KVN			Reach 5A BRA			
WEATHER CONDITIONS	Now	Past 24 hours	Has there been a heavy rain in the last 7 days?  ✓ Yes No			
CONDITIONS	storm	(heavy rain)	Air Temperature 22.7 °C			
	showers	s (intermittent)	Other			
	50 % ✓ %cl	loud cover 2 100 % ear/sunny	out			
SITE LOCATION/MAP			pled (or attach a photograph)			
SHE LOCATION MAR	Draw a map of the stu	c and mulcate the areas sall	picu (vi attacii a piivtogi apii)			
	A ACCURATE		Mana			
	10/1/5					
	1					
			BERMA			
			(BÁ-15)			
			Macro Invert Sampling Station			
			A CONTRACTOR OF THE PROPERTY O			
		740 科基下	Mintow Trap M1			
		10000000000000000000000000000000000000	Trap M2			
			Macro Invert			
			© Sampling Station 3 Start			
			esets.			
	The Lates of the L					
	Additional photo	graphs attached belo	W.			
STREAM CHARACTERIZATION	Stream Subsystem  ✓ Perennial ☐ Inte	ermittent   Tidal	Stream Type Coldwater Warmwater			
	Stream Origin	_	Catchment Area km²			
	Glacial Non-glacial montane	☐ Spring-fed ☐ Mixture of origins	<del></del>			
	Swamp and bog	Other				

# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERS FEATURI		Predom  ☐ Fores ☐ Field/ ☐ Agric ☐ Resid	Pasture Industrultural Other	ercial	□ No evid □Obvious — Local Wa		e potential sources
RIPARIAI VEGETAT (18 meter	TION	✓ I rees	e the dominant type and S nt species present	hrubs	Grasses	oresent He	rbaceous
INSTREA FEATURE		Estimated Reach Length 550 m  Estimated Stream Width 20 m  Sampling Reach Area 10658 m²  Area in km² (m²x1000) 11 km²  Estimated Stream Depth 1.5 m  Surface Velocity 0.25 m/sec (at thalweg)			High Wat Proportio Morpholo	pen Partler Partler Mark 2 n of Reach Rogy Types 10 %  and Yes 2 ced Yes	y shaded Shaded m epresented by Stream Run 45 %  No
LARGE W DEBRIS	VOODY	LWD Density	700 m <sup>2</sup> of LWD 63.6 n	m²/km² (LWD/	reach area)		
dominant species present Pot			ooted submerge ttached Algae	crispis, wate	d floating [	Free floating	
Dissolved Oxyg pH 8.51 Turbidity			ed Oxygen 8.88 mg/L		☐ Petroleu☐ Fishy  Water Su☐ Slick☐ None  Turbidity☐ Clear	None Sewa	Chemical Other Globs Flecks ured)
SEDIMENT/ SUBSTRATE  Odors    Normal			Petroleum None	Looking a	_	Paper fiber Sand Other Sand/Mud h are not deeply embedded, k in color?	
INORGANIC SUBSTRATE COMPONENTS (should add up to 100%)					BSTRATE C	OMPONENTS up to 100%)	
Substrate Type			% Composition in Sampling Reach	Substrate Type	Charact	eristic	% Composition in Sampling Area
Bedrock Boulder	> 256 mm (10")		0	Detritus	sticks, wood, comaterials (CPO)		5
Cobble Gravel	64-256 mm (2.5"-10") 2-64 mm (0.1"-2.5")		5 25	Muck-Mud	black, very fine (FPOM)	organic	0
Sand Silt Clay	0.06-2mm (gritty) 0.004-0.06 mm < 0.004 mm (slick)		35 30 3	Marl	grey, shell fragm	nents	0

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION Station 88+00 - 104+00			
STATION # RBP 14 RIVERMILE N/A	STREAM CLASS E (Rosgen)			
LAT 42.25222 LONG -73.14145	RIVER BASIN Housatonic			
STORET # N/A	AGENCY N/A			
INVESTIGATORS SM, TW, KVN, NC				
FORM COMPLETED BY	DATE 08/23/22 REASON FOR SURVEY			
KVN	TIME 1710 AM PM Reach 5A BRA			

	Habitat	Condition Category					
	Parameter	Optimal	Suboptimal	Marginal	Poor		
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.		
each	SCORE 15	20 19 18 17 16	(15) 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization	Mixture of substrate materials, with gravel and firm sand prevalent; root mats and submerged vegetation common.	Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.		
nate	SCORE 12	20 19 18 17 16	15 14 13 (2) 11	10 9 8 7 6	5 4 3 2 1 0		
ers to be eval	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large- deep; very few shallow.	Majority of pools small-shallow or pools absent.			
mete	SCORE 12	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		
Para	4. Sediment Deposition	Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.		
	SCORE 9	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.		
	SCORE 13	20 19 18 17 16	15 14 (13) 12 11	10 9 8 7 6	5 4 3 2 1 0		

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat		Condition	. Category		
	Parameter	Optimal	Suboptimal	Marginal	Poor	
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.	
	SCORE 19	20 (19) 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0	
npling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.	
ı sar	SCORE 13	20 19 18 17 16	15 14 (13) 12 11	10 9 8 7 6	5 4 3 2 1 0	
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.	
e eva	SCORE 5 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0	
to be	SCORE 5 (RB)	Right Bank 10 9	8 7 6	<b>5</b> 4 3	2 1 0	
Parameters	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.	
	SCORE 6 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0	
	SCORE 6 (RB)	Right Bank 10 9	8 7 🜀	5 4 3	2 1 0	
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.	
	SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0	
	SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0	

Total Score 133

Incidental Direct Wildlife Observations				
Whirligig beetle				
Killdeer				
Unidentified fish				
Beaver				
deer tracks				
Damselfly				
Dragonflies				
Rusty crayfish				



**Client Name:** 

GE

**Site Location:** 

Reach 5A Housatonic River

Project No.

60689453

Photo No.

1

Date: 8/23/22

**Direction Photo** Taken:

East

Description:

Beginning of RBP 14 with woody debris. The far side of the image contains a pool and the left side is a run.



Photo No. 2

Date: 8/24/22

**Direction Photo** Taken:

South

**Description:**Beginning of RBP 14
looking downstream. On the outer bend, there are cobble deposits and woody debris. The sand bar on the inner part of the bend has grassy vegetation before a steep slope.





Client Name:

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

**Date:** 8/23/22

Direction Photo Taken:

Southeast

Description:

RBP 14 looking downstream is a run. Woody debris stretches across the river, creating a blockage near the sand bar. Riparian trees hang over the river. A pile of cobble was deposited on the far right side.




Photo No.

4

**Date:** 8/23/22

Direction Photo Taken:

Southeast

Description:

Further downstream of RBP 14, woody debris is collected on the shorelines. A small bar has formed on the right side. Shrubs and maple trees make up the riparian vegetation. There are also pools on the outer bends of the river.



### **AECOM** Imagine it. Delivered.

### **PHOTOGRAPHIC LOG**

**Client Name:** 

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

**Date:** 08/23/22

Direction Photo Taken: North



### Description:

Eroded bank in RBP 14. Vegetation's roots are exposed, and bank stability is low. This section has shallow areas and sunken woody debris.

Photo No.

**Date:** 8/24/22

Direction Photo Taken:

Northwest



Looking upstream in RBP-14. Due to the drought during these pictures, some parts of this section appear as riffles. Woody debris around the sand bar dams part of the stream. More shrubs and grassy vegetation line these shores.





# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

STREAM NAME Housatonic River		LOCATION Station 104+00 - 115+00				
STATION # RBP 15-16 R	VERMILE N/A	STREAM CLASS E (Rosgen)				
LAT 42.25226 LO	NG <u>-73.14156</u>	RIVER BASIN Housatonic				
STORET # N/A		AGENCY N/	'A			
INVESTIGATORS SM, T	W, KVN, NC					
FORM COMPLETED BY		DATE 08/24/22 TIME 1050	☐ ☑AM□PM	REASON FOR SURVEY		
KVN		TIME TOO	VAMPM	Reach 5A BRA		
WEATHER CONDITIONS	rain (s	(heavy rain) steady rain) (intermittent)	hours [	Has there been a heavy rain in the last 7 days?  Yes No  Air Temperature 24 0 C  Other		
	70 % <b>Ľ</b> %cle	oud cover ar/sunny	<u>√</u> 80 %			
SITE LOCATION/MAP	Draw a man of the site	and indicate the	areas sample	ed (or attach a photograph)		
		RBP11 (BA-16-F	5-16 BA17)	Macro Invert. Sampling Station 3 Start  RANGE  AND  AND  AND  AND  AND  AND  AND  AN		
	Additional photog	J. 3P.13 G.(GO)				
STREAM CHARACTERIZATION	Stream Subsystem ✓ Perennial Inte	rmittent Tida	ıl [	Stream Type □Coldwater   ✓Warmwater		
	Stream Origin  Glacial  Non-glacial montane  Swamp and bog	Spring-fed Mixture of Other	l f origins	Catchment Area km²		

# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERS FEATURI		Predon  ☑ Fores  ☑ Field  ☑ Agric  ☐ Resid	Pasture Industrultural Other	ercial	□ No □Ob — Loca	al Watershed NPS of evidence □Some ovious sources al Watershed Erosione □Moderate	e potential sources
RIPARIAI VEGETAT (18 meter	TION	✓ l'rees	e the dominant type an S nt species present	hrubs	Grasse	cies present es He	rbaceous
INSTREA FEATURE		Estimat Samplin Area in Estimat		m	High Prop Morj VRii Po Char	Water Mark 1 ortion of Reach Rophology Types	y shaded Shaded m epresented by Stream Run 60 %  No
LARGE V DEBRIS	VOODY	LWD Density	350 m <sup>2</sup> of LWD 48.6	m²/km² (LWD/	reach area)		
AQUATIC VEGETA		☑ Roote ☐ Floati  domina	ed emergent Ring Algae VA	tooted submerge attached Algae ellow flag iri	ow flag iris, algae		
			Conductance 0.535 ed Oxygen 7.15 mg/L 5		☑No □Pe □Fis Wate □Sli ☑No Turb	shy er Surface Oils ick ☐Sheen ☐	Chemical Other
SEDIMENT/ SUBSTRATE  Odors  Normal Sewage Chemical Anaerobic Other  Oils  Absent Slight Modera			□ Petroleum □ None	□ □ Re Look are the	udge Sawdust elict shells which king at stones which he undersides blac	Paper fiber Sand Other Sand/Mud h are not deeply embedded, k in color?	
INORGANIC SUBSTRATE COMPONENTS (should add up to 100%)						C SUBSTRATE Co	
Substrate Type	Diameter % Composition Sampling Re		% Composition in Sampling Reach	Substrate Type	Cha	aracteristic	% Composition in Sampling Area
Bedrock Boulder	> 256 mm (10")		5	Detritus	sticks, woo materials (	od, coarse plant CPOM)	15
Cobble Gravel	64-256 mm (2.5"-10") 2-64 mm (0.1"-2.5")		10 25	Muck-Mud	black, very (FPOM)	fine organic	0
Sand Silt Clay	0.06-2mm (gritty) 0.004-0.06 mm < 0.004 mm (slick)		30 25 5	Marl	grey, shell	fragments	0

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION Station 104+00 - 115+00			
STATION # RBP 15-16 RIVERMILE N/A	STREAM CLASS E (Rosgen)			
LAT 42.25226 LONG -73.14156	RIVER BASIN Housatonic			
STORET # N/A	AGENCY N/A			
INVESTIGATORS SM, TW, KVN, NC				
FORM COMPLETED BY	DATE 08/24/22 REASON FOR SURVEY			
KVN	TIME 1050 PM Reach 5A BRA			

	Habitat	····					
	Parameter	Optimal	Suboptimal	Marginal	Poor		
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.		
each	SCORE 11	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization	Mixture of substrate materials, with gravel and firm sand prevalent; root mats and submerged vegetation common.	Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.		
nate	SCORE 13	20 19 18 17 16	15 14 (13) 12 11	10 9 8 7 6	5 4 3 2 1 0		
rs to be eval	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large-deep; very few shallow.	Shallow pools much more prevalent than deep pools.	Majority of pools small- shallow or pools absent.		
mete	SCORE 15	20 19 18 17 16	<b>(</b> 5) 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		
Para	4. Sediment Deposition	Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.		
	SCORE 9	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.		
	SCORE 15	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat		Condition	ı Category	
	Parameter	Optimal	Suboptimal	Marginal	Poor
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.
	SCORE 20	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
npling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.
ı san	SCORE 8	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.
eva	SCORE 6 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
to b	SCORE 6 (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0
Parameters	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.
	SCORE 8 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
	SCORE 8 (RB)	Right Bank 10 9	<b>③</b> 7 6	5 4 3	2 1 0
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.
	SCORE (LB)	Left Bank (10) 9	8 7 6	5 4 3	2 1 0
	SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0

Total Score 139

Incidental Direct Wildlife Observations				
Whirligig beetle				
Rusty crayfish (6)				
Green treefrog (3)				
Songbirds				
Cooper's hawk (2)				
Painted turtle (2)				
Eastern elliptio mussel				
White breasted nuthatch				
Bumblebees				
Honeybees				

### **AECOM** Imagine it. Delivered.

### **PHOTOGRAPHIC LOG**

Client Name:

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No. 1

Date: 8/24/22

**Direction Photo** Taken: East

### Description:

RBP 15-16 looking upstream. This section is a run with little woody debris.



Photo No. 2

Date: 8/24/22

**Direction Photo** 

Taken: South

### Description:

RBP 15 looking downstream. This section of the river is a pool with woody debris. Houses and private property reside over the bank's slope. Erosion is visible on the slope in areas lacking vegetation.



### **AECOM** Imagine it. Delivered.

### **PHOTOGRAPHIC LOG**

Client Name:

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.


**Date:** 8/24/22

Direction Photo Taken: North



### Description:

RBP 15-16 looking upstream. In the middle of the stream is a deposited island with a fallen tree. This section of the stream is a run.



Direction Photo Taken: West

### Description:

RBP 15-16 looking downstream. In this section, there is a cobble bar and sand bar. In between these two deposits is a riffle. A run leads to a pool on the left where a large collection of woody debris resides.



# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

STREAM NAME Housatonic River		LOCATION Station 115+00 - 135+00			
STATION # RBP 17 R	IVERMILE N/A	STREAM CLASS E (Rosgen)			
LAT 42.416992 LC	NG <u>-73.240999</u>	RIVER BASIN Housa	tonic		
STORET # N/A		AGENCY N/A			
INVESTIGATORS SM, T	W, KVN, NC				
FORM COMPLETED BY		DATE 08/24/22 TIME 1217 AM	REASON FOR SURVEY		
SM		TIME 1217 AM	Reach 5A BRA		
WEATHER CONDITIONS	Now	Past 2			
CONDITIONS	storm	(heavy rain) hours	Air Temperature 23 0 C		
	showers	steady rain)	Other		
	50 %	loud cover 60 car/sunny	9% Other		
SITE LOCATION/MAP		•	sampled (or attach a photograph)		
SHE LOCATION/MAP	_	e and indicate the areas	sampieu (or attacii a piiotograpii)		
	Shelland Drive	West of the second	(BAYGBA17)		
			(BA+16-BATI)		
	1 0 1				
	The Late				
	The same				
	Plan				
	Pluto Drive	1			
	TO A SEE				
		DRD 47			
		(BA-18)			
		7			
	1 2 2 1				
	The state of				
			REP 19		
			(BA-20)		
	1	Cap			
	Additional phata	aranha attached L	olow		
	Additional prioto	graphs attached b	SIUW.		
STREAM CHARACTERIZATION	Stream Subsystem ✓ Perennial ☐ Inte	ermittent   Tidal	Stream Type ☐Coldwater		
CHARACTERIZATION	Stream Origin		Catchment Area km <sup>2</sup>		
	Glacial Sontane  Non-glacial montane	Spring-fed  Mixture of origins	<del></del>		
	Swamp and bog	Other	1		

# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERS FEATURI		Predom  ☐ Fores ☐ Field/ ☐ Agric ☐ Resid	Pasture Indusultural Other	nercial trial		Local Watershed NPS I  No evidence ☑Some ☑Obvious sources  Local Watershed Erosi ☑ None ☑Moderate	potential sources
RIPARIA VEGETA (18 meter	TION	✓ l'rees	e the dominant type a nt species present	Shrubs	ominant G	t species present Grasses He	rbaceous
INSTREA FEATURI		Estimat Samplir Area in Estimat Surface	Estimated Reach Length 579 m  Estimated Stream Width 28 m  Sampling Reach Area 14001 m²  Area in km² (m²x1000) 14.0 km²  Estimated Stream Depth 1 m  Surface Velocity 0.75 m/sec (at thalweg)			Canopy Cover Partly open Partly shaded Shaded  High Water Mark 1.5 m  Proportion of Reach Represented by Stream Morphology Types Riffle 16 % Run 52 % Pool 32 %  Channelized Yes No  Dam Present Yes No	
LARGE V DEBRIS	VOODY	LWD Density	1000 m <sup>2</sup> of LWD 61.7	]m <sup>2</sup> /km <sup>2</sup> (LWD/	reach a	area)	
AQUATIO VEGETA		☐Roote ☐Floati domina	ed emergent	Rooted submerge Attached Algae Igae	ached Algae		
WATER QUALITY  Temperature 21.1  Specific Conductance Dissolved Oxygen 7. pH 8.48  Turbidity WQ Instrument Used			Conductance 0.56: ed Oxygen 7.04 mg/L 8		[ ] [ ]	☐Fishy <u>Water Surface Oils</u>	Chemical Other Globs Flecks red)
SEDIMENT/ SUBSTRATE  Odors  Normal Sewage Chemical Anaerobic Other  Oils  Absent Slight Modera			Petroleum None			Paper fiber Sand Other Sand/Mud  n are not deeply embedded, k in color?	
INORGANIC SUBSTRATE COMPONENTS (should add up to 100%)						ANIC SUBSTRATE Copes not necessarily add	
Substrate Type	e Diameter % Composition in Sampling Reach		Substrate Type		Characteristic	% Composition in Sampling Area	
Bedrock Boulder	> 256 mm (10")	256 mm (10") 1		Detritus		, wood, coarse plant rials (CPOM)	10
Cobble Gravel	64-256 mm (2.5"-10") 2-64 mm (0.1"-2.5")		30	Muck-Mud	black, (FPO	, very fine organic M)	1
Sand Silt Clay	0.06-2mm (gritty) 0.004-0.06 mm < 0.004 mm (slick)		[40 [17 [10	Marl	grey,	shell fragments	0

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION Station 115+00 - 135+00		
STATION # RBP 17 RIVERMILE N/A	STREAM CLASS E (Rosgen)		
LAT 42.416992 LONG -73.240999	RIVER BASIN Housatonic		
STORET # N/A	AGENCY N/A		
INVESTIGATORS SM, TW, KVN, NC			
FORM COMPLETED BY	DATE 08/24/22 REASON FOR SURVEY		
SM	TIME 1217 AM PM Reach 5A BRA		

	Habitat	Condition Category						
	Parameter	Optimal	Suboptimal	Marginal	Poor			
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.			
reac	SCORE 8	20 19 18 17 16	15 14 13 12 11	10 9 (8) 7 6	5 4 3 2 1 0			
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization	Mixture of substrate materials, with gravel and firm sand prevalent; root mats and submerged vegetation common.	Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.			
nate	SCORE 15	20 19 18 17 16	(5) 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0			
ers to be eval	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large- deep; very few shallow.	Shallow pools much more prevalent than deep pools.	Majority of pools small-shallow or pools absent.			
mete	SCORE 16	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0			
Para	4. Sediment Deposition	Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.			
	SCORE 7	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0			
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.			
	SCORE 13	20 19 18 17 16	15 14 (13) 12 11	10 9 8 7 6	5 4 3 2 1 0			

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat		Condition	. Category	
	Parameter	Optimal	Suboptimal	Marginal	Poor
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.
	SCORE 18	20 19 (18) 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
npling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.
ı sar	SCORE 8	20 19 18 17 16	15 14 13 12 11	10 9 🚷 7 6	5 4 3 2 1 0
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.
eva	SCORE 4 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
to be	SCORE 4 (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0
Parameters	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.
	SCORE 5 (LB)	Left Bank 10 9	8 7 6	<b>3</b> 4 3	2 1 0
	SCORE 5 (RB)	Right Bank 10 9	8 7 6	<b>5</b> 4 3	2 1 0
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.
	SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
	SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0

Total Score 121

Incidental Direct Wildlife Observations					
Goldfinches					
Beaver tracks					
Goose scat					
Hummingbirds					



**Client Name:** 

GE

Site Location:

Reach 5A Housatonic River

Project No.

60689453

Photo No.

1

**Date:** 8/24/22

### Direction Photo Taken:

Southwest

### **Description:**

Beginning of RBP 17 looking downstream. The water depth is shallow in this area and a riffle is present. Large rocks/cobble deposits are near the riffle. The shoreline has contains gravel and a mix of shrubs.



Photo No.

**Date:** 8/24/22

Direction Photo Taken:

South

### **Description:**

RBP 17 looking downstream. This section is a run, and the left bank has slight erosion. There is a fallen log and other woody debris. A sand bar and riffle can be seen in the distance.



# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

STREAM NAME Housatonic River		LOCATION Station 135+00 - 150+00			
STATION # RBP 18 R	STREAM CLASS E (Rosgen)				
LAT 42.414557 LC	RIVER BASIN Housatonic				
STORET # N/A	AGENCY N/A	4			
INVESTIGATORS SM, 7	TW, KVN, NC				
FORM COMPLETED BY		DATE 08/24/22		REASON FOR SURVEY	
KVN		TIME 1235	■AM <b>∠</b> PM	Reach 5A BRA	
WEATHER CONDITIONS	Now		Past 24	Has there been a heavy rain in the last 7 days?  ☑Yes ☐No	
CONDITIONS	storm	(heavy rain)	hours	Air Temperature 23 O C	
	rain (	steady rain) s (intermittent)	H	Other	
	50 % v %c	loud cover ear/sunny	<u>₹</u> 80 %	Other	
aven v o a l = 100 v o c		•			
SITE LOCATION/MAP	Draw a map of the sit	e and indicate th	e areas samp	led (or attach a photograph)	
	to the			RBP	
			22		
	A BELLEVILLE		<b>6</b> 0		
		E STATE OF			
	<b>原</b> 图 第				
	<b>多。為於經濟</b>		1		
	di antigra	E THE	RBP 18		
			(BA-19)		
	The second second				
	22				
			No. Market		
	A LEG				
	Additional photo	graphs attac	ned below	<i>.</i>	
STREAM	Stream Subsystem Perennial Inte			Stream Type	
CHARACTERIZATION		ermittent Tid	ai	Coldwater Warmwater	
	Stream Origin	Spring-fe	d	Catchment Areakm <sup>2</sup>	
	☐ Non-glacial montane ☐ Swamp and bog	Mixture of Other	of origins		
	Ī				

# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERSI FEATURE		Predom ☐Fores ☑Field/ ☐ Agric ☐ Resid	Pasture Industrultural Other	ercial			
RIPARIAN VEGETAT (18 meter l	ΓΙΟΝ	Indicate the dominant type and record the dominant species present  ☐ Irees ☐ Shrubs ☐ Grasses  dominant species present  silver maple, sycamore, knotweed					
INSTREA FEATURE		Estimat Samplin Area in Estimat		m 29 m²	Hi Pr M V C	orphology Types	
LARGE W DEBRIS	VOODY	LWD 200 m²  Density of LWD 20 m²/km² (LWD/ reach area)					
AQUATIC VEGETAT		Indicate the dominant type and record the dominant species present  Rooted emergent Rooted submergent Rooted floating Free floating Attached Algae  dominant species present  Potamogeton crispis, sparse macrophyte algae  Portion of the reach with aquatic vegetation 15 %				<b>_</b>	
Dissolved Oxy pH 8.25 Turbidity			ed Oxygen 8.46 mg/L		W D	Fishy  [ater Surface Oils	Chemical Other Globs Flecks red)
SEDIMENT/ SUBSTRATE  Odors  Normal Sewage Chemical Anaerobic Other  Oils Absent Slight Modern			Petroleum None	$\sqsupset \ \ rac{\Box}{\operatorname*{Lo}}$		Paper fiber Sand Other Sand/Mud h are not deeply embedded, k in color?	
INORGANIC SUBSTRATE COMPONENTS (should add up to 100%)				ORGANIC SUBSTRATE COMPONENTS (does not necessarily add up to 100%)			
Substrate Type	Diamete	er	% Composition in Sampling Reach	Substrate Type	(	Characteristic	% Composition in Sampling Area
Bedrock Boulder	> 256 mm (10")		0 <1	Detritus		vood, coarse plant ls (CPOM)	10
Cobble Gravel	64-256 mm (2.5"-10") 2-64 mm (0.1"-2.5")		10	Muck-Mud	black, ve (FPOM)	ery fine organic	0
Sand Silt Clay	0.06-2mm (gritty) 0.004-0.06 mm < 0.004 mm (slick)		50 20 10	Marl	grey, she	ell fragments	0

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION Station 135+00 - 150+00		
STATION # RBP 18 RIVERMILE N/A	STREAM CLASS E (Rosgen)		
LAT 42.414557 LONG -73.238682	RIVER BASIN Housatonic		
STORET # N/A	AGENCY N/A		
INVESTIGATORS SM, TW, KVN, NC			
FORM COMPLETED BY KVN	DATE 08/24/22 REASON FOR SURVEY TIME 1235 PAM PPM Reach 5A BRA		

	Habitat	Condition Category			
	Parameter	Optimal	Suboptimal	Marginal	Poor
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.
each	SCORE 12	20 19 18 17 16	15 14 13 (12) 11	10 9 8 7 6	5 4 3 2 1 0
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization	Mixture of substrate materials, with gravel and firm sand prevalent; root mats and submerged vegetation common.	Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.
uate	SCORE 14	20 19 18 17 16	15 (14) 13 12 11	10 9 8 7 6	5 4 3 2 1 0
rs to be eval	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large- deep; very few shallow.	Shallow pools much more prevalent than deep pools.	Majority of pools small-shallow or pools absent.
mete	SCORE 15	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
Para	4. Sediment Deposition	Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.
	SCORE 7	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.
	SCORE 15	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat				
	Parameter	Optimal	Suboptimal	Marginal	Poor
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.
	SCORE 20	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
pling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.
ı san	SCORE 16	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.
e eva	SCORE 3 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
to be	SCORE (RB)	Right Bank 10 9	8 7 6	5 4 ③	2 1 0
Parameters	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.
	SCORE 5 (LB)	Left Bank 10 9	8 7 6	<b>3</b> 4 3	2 1 0
	SCORE 5 (RB)	Right Bank 10 9	8 7 6	<b>5</b> 4 3	2 1 0
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.
	SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
	SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0

Total Score 135

In airdental Direct Wildlife Observations	
Incidental Direct Wildlife Observations	
Goldfinches	
Eastern elliptio mussel	
Kingfisher	
Unidentified fishes	
Painted turtles	
Green frog	
Grackle	
Great blue heron	
Canada goose	
Yellow warbler	
Red-tailed hawks	
Common snapping turtle	



Client Name:

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

**Date:** 8/24/22

Direction Photo Taken: South

Description:

RBP 18 looking downstream. From this spot, wood debris is prevalent. A sand bar has formed on the inner bend of the river.



Photo No.


**Date:** 8/24/22

Direction Photo Taken:

East

Description:

RBP 18 looking downstream, a small sand bar has formed around the bend of the river.



# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

STREAM NAME Housatonic River		LOCATION Station 150+00 - 156+00			
STATION # RBP 19 R	IVERMILE N/A	STREAM CLASS E (Rosgen)			
LAT 42.415515 LC	NG <u>-73.236849</u>	RIVER BASIN	Housatonic		
STORET # N/A		AGENCY N/A	1		
INVESTIGATORS SM, 7	TW, KVN, NC				
FORM COMPLETED BY	_	DATE 08/24/22	<u></u>	REASON FOR SURVEY	
KVN		TIME 1430	AM PM	Reach 5A BRA	
WEATHER CONDITIONS	Now		Past 24	Has there been a heavy rain in the last 7 days?  □Yes □No	
CONDITIONS	storm	(heavy rain)	hours	Air Temperature 25.8 C	
	showers	steady rain) (intermittent)	占	Other	
	50 % v %cl	oud cover ar/sunny	<u>v</u> 100 %	Other	
CYPER Y O C + PYONY R + P		-			
SITE LOCATION/MAP	Draw a map of the site	and indicate the	areas samp	led (or attach a photograph)	
	WAR TO A				
				THE TAXABLE	
				<b>B</b>	
		<b>发表</b> 7.4	RBP19		
			(BA-20		
				A. T. Parket	
		1		ALL STATES	
		02			
		70% .			
		1			
	Additional photo	graphs attach	ned below	I.	
CUDE AM	Starrage Co. 1			Stream True	
STREAM CHARACTERIZATION	Stream Subsystem ✓ Perennial ☐ Inte	rmittent Tida	1	Stream Type Coldwater Warmwater	
	Stream Origin	По	ı	Catchment Area km²	
	Glacial Non-glacial montane	Spring-fed Mixture of	forigins		
	Swamp and bog	Other_			

# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERSHED FEATURES	☑Fore □Field	l/Pasture ☐ Industri cultural ☐ Other	ercial	Local Watershed NPS  □ No evidence □ Som □ Obvious sources  □ Local Watershed Eros □ None □ Moderate	e potential sources	
RIPARIAN VEGETATION (18 meter buffer)	✓ l`ree	Indicate the dominant type and record the dominant species present    Grasses				
INSTREAM FEATURES	Estima Sampli Area ii Estima		m m 5 m² km² m n/sec	Canopy Cover Partly open Partl High Water Mark 2  Proportion of Reach R Morphology Types Riffle % Pool 10 %  Channelized Yes  Dam Present Yes	m	
LARGE WOODY DEBRIS	LWD Densit	100 m² y of LWD 22.2 r	m²/km² ( <b>LWD</b> /	reach area)		
AQUATIC VEGETATION	□Root □Floa domin	Indicate the dominant type and record the dominant species present  Rooted emergent Floating Algae Attached Algae  dominant species present  Vallisneria  Portion of the reach with aquatic vegetation 1 %				
WATER QUALITY  Temperature 22 ° C Specific Conductance 0.506 Dissolved Oxygen 8.89 mg/L pH 8.35 Turbidity WQ Instrument Used YSI 650				<u>Water Surface Oils</u>	Chemical Other Globs Flecks	
SEDIMENT/ SUBSTRATE					Paper fiber Sand Other Sand/Mud  th are not deeply embedded, ck in color?	
INORGANIC SUBSTRATE COMPONENTS (should add up to 100%)				ORGANIC SUBSTRATE C (does not necessarily add		
Substrate Type	e Diameter % Composition in Sampling Reach		Substrate Type	Characteristic	% Composition in Sampling Area	
Bedrock Boulder > 256 mr	n (10")	5	Detritus	sticks, wood, coarse plant materials (CPOM)	10	
Cobble 64-256 n	m (2.5"-10") (0.1"-2.5")	10	Muck-Mud	black, very fine organic (FPOM)	0	
Sand 0.06-2mr Silt 0.004-0.0 Clay < 0.004 r	(6 7)	35 20 10	Marl	grey, shell fragments	0	

# HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION Station 150+00 - 156+00		
STATION # RBP 19 RIVERMILE N/A	STREAM CLASS E (Rosgen)		
LAT 42.415515 LONG -73.236849	RIVER BASIN Housatonic		
STORET # N/A	AGENCY N/A		
INVESTIGATORS SM, TW, KVN, NC			
FORM COMPLETED BY	DATE 08/24/22 REASON FOR SURVEY		
KVN	TIME 1430		

	Habitat	Condition Category					
	Parameter	Optimal	Suboptimal	Marginal	Poor		
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.		
each	SCORE 10	20 19 18 17 16	15 14 13 12 11	0 9 8 7 6	5 4 3 2 1 0		
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization	Mixture of substrate materials, with gravel and firm sand prevalent; root mats and submerged vegetation common.	Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.		
nate	SCORE 10	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		
ers to be eval	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large-deep; very few shallow.	Shallow pools much more prevalent than deep pools.	Majority of pools small-shallow or pools absent.		
mete	SCORE 6	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		
Para	4. Sediment Deposition	Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.		
	SCORE 10	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.		
	SCORE 14	20 19 18 17 16	15 (4) 13 12 11	10 9 8 7 6	5 4 3 2 1 0		

# HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat	Condition Category						
	Parameter	Optimal	Suboptimal	Marginal	Poor			
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.			
	SCORE 20	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0			
npling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.			
San	SCORE 8	20 19 18 17 16	15 14 13 12 11	10 9 🚷 7 6	5 4 3 2 1 0			
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.			
e eva	SCORE 10 (LB)	Left Bank (10) 9	8 7 6	5 4 3	2 1 0			
to be	SCORE 6 (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0			
Parameters	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.			
	SCORE 9 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0			
	SCORE 9 (RB)	Right Bank 10 1	8 7 6	5 4 3	2 1 0			
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.			
	SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0			
	SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0			

Total Score 132

Incidental Direct Wildlife Observations				
Cedar waxwing				
Red bellied woodpecker				
Sandpiper				
Eastern elliptio mussel				
Painted turtles				
Green frog				
Red-tailed hawk				



Client Name:

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

**Date:** 8/24/22

**Direction Photo Taken:** Northeast (Left)
Northwest (Right)



### **Description:**

RBP-19. First photo taken looking downstream, second photo taken after the bend looking back upstream. In both images, a run is present. The outer bend has moderate erosion, while the inner bend has a sand bar with grassy vegetation.

Photo No.


**Date:** 8/24/22

Direction Photo Taken:

Northeast

### **Description:**

RBP-19 looking downstream. This section is a pool with branches and underwater woody debris. It later converts into a run with a few small riffles for the rest of RBP 19.



# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

STREAM NAME Housatonic River		LOCATION Station 156+00 - 172+00				
STATION # RBP 20-22 R	VERMILE N/A	STREAM CLASS E (Rosgen)				
LAT 42.414430 LO	NG <u>-73.234158</u>	RIVER BASIN Housatonic				
STORET # N/A		AGENCY N/A				
INVESTIGATORS SM, T	W, KVN, NC					
FORM COMPLETED BY		DATE 08/24/22		REASON FOR SURVEY		
SM		TIME 1520	■AM☑PM	Reach 5A BRA		
WEATHER CONDITIONS	Now		Past 24 Hours	las there been a heavy rain in the last 7 days? ∏Yes ∏No		
CONDITIONS	storm	(heavy rain)	ī	Air Temperature 29 C		
	showers	steady rain) (intermittent)	j ,	Other		
	25 % ✓ %cl	oud cover ar/sunny	80 %	, their		
SITE LOCATION/MAP		•	roge comple	d (or attach a photograph)		
SITE LOCATION/MAP	Draw a map of the site	and indicate the al		.0		
		6	Joseph			
				The State of the s		
	To the second		6			
	<b>1</b>					
	* All Control					
	N. A. S. A.					
			1			
	5					
			RBP 20-22			
		No.	RBP 20-22 (BA-21 - BA-2	<mark>2)</mark>		
				Minnow		
				Trap S1		
				EARL		
		V. N				
		THE PERSON		Nag 1		
				<del></del>		
	Additional photo	graphs attache	d below.			
STREAM	Stream Subsystem  ☑ Perennial ☐ Inte	rmittent Tidal	S	Stream Type Coldwater		
CHARACTERIZATION	Stream Origin	annucht 🔲 Huai	_	Catchment Area km <sup>2</sup>		
	Glacial Non-glacial montane	Spring-fed Mixture of or		Accument AreaNIII		
	Swamp and bog	Other				

# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERS FEATURI		Predom  ☐ Fores ☐ Field/ ☐ Agric ☐ Resid	Pasture Industri	rcial	Local Watershed NPS  □ No evidence □Som □Obvious sources  Local Watershed Eros □ None □Moderate	e potential sources
RIPARIAI VEGETAT (18 meter	TION	Indicate the dominant type and record the dominant species present  ☐ Frees ☐ Shrubs ☐ Grasses  dominant species present  Tulip poplar				
INSTREA FEATURE		Estimat Samplin Area in Estimat			Proportion of Reach R Morphology Types	.5 m
LARGE W DEBRIS	VOODY	LWD Density	75 m <sup>2</sup> of LWD 5.8 m	n²/km² <b>(LWD</b> / 1	reach area)	
AQUATIO VEGETA		☐Roote ☐Floati domina	e the dominant type and ded emergent Reng Algae Algae Was of the reach with aquat	+ algae	Free floating	
WATER QUALITY  Temperature 21.1 ° C Specific Conductance 0.563  Dissolved Oxygen 7.04 mg/L pH 8.48  Turbidity WQ Instrument Used YSI 650			ms/cm	Fishy Water Surface Oils	Chemical Other Globs Flecks	
SEDIMEN SUBSTRA				Petroleum None	Looking at stones which	Paper fiber Sand Other Sand/Mud ch are not deeply embedded, ck in color?
INORGANIC SUBSTRATE COMPONENTS (should add up to 100%)				ORGANIC SUBSTRATE (		
Substrate Type			Substrate Type	Characteristic	% Composition in Sampling Area	
Bedrock Boulder	> 256 mm (10")	0 5		Detritus	sticks, wood, coarse plant materials (CPOM)	8
Cobble Gravel	ole 64-256 mm (2.5"-10")		20	Muck-Mud	black, very fine organic (FPOM)	5
Sand Silt Clay	0.06-2mm (gritty 0.004-0.06 mm < 0.004 mm (slie	ritty) 47 nm 5		Marl	grey, shell fragments	0

# HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION Station 156+00 - 172+00		
STATION # RBP 20-22 RIVERMILE N/A	STREAM CLASS E (Rosgen)		
LAT 42.414430 LONG -73.234158	RIVER BASIN Housatonic		
STORET # N/A	AGENCY N/A		
INVESTIGATORS SM, TW, KVN, NC			
FORM COMPLETED BY SM	DATE 08/24/22 REASON FOR SURVEY TIME 1520 AMPPM Reach 5A BRA		

	Habitat	Condition Category					
	Parameter	Optimal	Suboptimal	Marginal	Poor		
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.		
eac	SCORE 13	20 19 18 17 16	15 14 (13) 12 11	10 9 8 7 6	5 4 3 2 1 0		
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization	Mixture of substrate materials, with gravel and firm sand prevalent; root mats and submerged vegetation common.	Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.		
nate	SCORE 19	20 (19) 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		
ers to be eval	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large- deep; very few shallow.	Shallow pools much more prevalent than deep pools.	Majority of pools small-shallow or pools absent.		
mete	SCORE 15	20 19 18 17 16	13 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		
Para	4. Sediment Deposition	Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.		
	SCORE 12	20 19 18 17 16	15 14 13 (12) 11	10 9 8 7 6	5 4 3 2 1 0		
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.		
	SCORE 14	20 19 18 17 16	15 (14) 13 12 11	10 9 8 7 6	5 4 3 2 1 0		

# HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat	Condition Category						
	Parameter	Optimal	Suboptimal	Marginal	Poor			
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.			
	SCORE 19	20 (19) 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0			
npling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.			
ı san	SCORE 10	20 19 18 17 16	15 14 13 12 11	9 8 7 6	5 4 3 2 1 0			
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.			
eva	SCORE 5 (LB)	Left Bank 10 9	8 7 6	<b>5</b> 4 3	2 1 0			
to be	SCORE 5 (RB)	Right Bank 10 9	8 7 6	<b>5</b> 4 3	2 1 0			
Parameters	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.			
	SCORE 6 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0			
	SCORE 6 (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0			
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.			
	SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0			
	SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0			

Total Score 144

Incidental Direct Wildlife Observations				
Crawfish				
Great Blue Heron				
Mussels				
Beaver sign				
Mallard				
Goldfinches				



Client Name:

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

**Date:** 8/24/22

Direction Photo Taken:

Northwest

**Description:** 

End of RBP 20 looking upstream contains cobble bars and shoreline. A run reaches the cobble area and turns into a riffle.



Photo No.

**Date:** 8/24/22

Direction Photo Taken: Southeast

**Description:** 

RBP 20-21 looking downstream. Large woody debris has fallen into the river. The bank is more stable on the left side and contains cobble, while the bank on the right is eroded and has lost stability. This section is a run.





**Client Name:** 

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

3

Date: 8/24/22

# **Direction Photo**

Taken:

Southeast

Description:
End of RBP 21 looking downstream. Coontail is the dominant aquatic vegetation. This area is a run with pockets of pool.



Photo No. 4

Date: 8/24/22

**Direction Photo** Taken:

Southeast

**Description:** RBP 22 looking downstream. This section also contains predominantly coontail. At the far bank, there is cobble/rip rap to prevent erosion.



# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

nic River LOCATION Station 172+00 - 188+00	LOCATION   Station 172+00 - 188+00		
ERMILEN/A STREAM CLASS E (Rosgen)	Ī		
G -73.233352 RIVER BASIN Housatonic	ĵ		
AGENCY N/A	j		
/, KVN, NC	]		
DATE 08/24/22 REASON FOR SURVEY	7		
Reach 5A BRA			
	_		
Now Past 24 Has there been a heavy rain in the last 7 days?			
storm (heavy rain)			
showers (intermittent)			
clear/sunny			
Draw a map of the site and indicate the areas sampled (or attach a photograph)			
O Trap S1			
e Carib			
Minnow			
Trap S2			
Macro Invert Sampling			
Station 4 End 🕤			
(BA-23 - BA-25)			
Additional photographs attached below			
Additional photographs attached below.			
Stream Subsystem Stream Type			
Stream Subsystem Perennial Intermittent Tidal Stream Type Coldwater Warmwater			
Stream Subsystem Stream Type			
	RIVER BASIN Housatonic  AGENCY N/A  AGENCY N/A  DATE 08/24/22 TIME 1600 AMDPM REASON FOR SURVEY Reach 5A BRA  Now Past 24 Hours No Air Temperature 29 ° C  Other  Draw a map of the site and indicate the areas sampled (or attach a photograph)		

# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERS FEATURI		Predon  ☐ Fores ☐ Field ☐ Agric ☐ Resid	Pasture Industri	rcial	_	ocal Watershed NPS I No evidence ☑Some Obvious sources ocal Watershed Erosi None ☑Moderate	e potential sources
RIPARIAI VEGETAT (18 meter	TION	✓ l'rees	e the dominant type and SI nt species present	record the donrubs	<b>minant s</b> ∐Gra	species present He	rbaceous
INSTREA FEATURE		Estimat Samplin Area in Estimat		km <sup>2</sup>	Hi Pr M V CI	orphology Types	<u> </u>
LARGE W DEBRIS	VOODY	LWD Density	125 m <sup>2</sup> of LWD 9.26 n	n²/km² ( <b>LWD</b> / 1	reach are	ea)	
VEGETATION  ☐ Rooted emergent ☐ Floating Algae  dominant species pres				ooted submerge ttached Algae nerican bur	r-reed	Rooted floating	Free floating
WATER (	QUALITY	Specific Dissolve pH 8.4 Turbidi				Fishy  [ater Surface Oils	Chemical Other Globs Flecks red)
SEDIMEN SUBSTRA		Odors Norm Chem Other Oils	nical Anaerobic	Petroleum None  The Profus	⊐ ☐		Paper fiber Sand Other Sand/Mud n are not deeply embedded, k in color?
INORGANIC SUBSTRATE COMPONENTS (should add up to 100%)						NIC SUBSTRATE Cos not necessarily add	
Substrate Type			% Composition in Sampling Reach	Substrate Type	(	Characteristic	% Composition in Sampling Area
Bedrock Boulder	> 256 mm (10")		0	Detritus		vood, coarse plant ls (CPOM)	15
Cobble Gravel	64-256 mm (2.5"-10") 2-64 mm (0.1"-2.5")		15	Muck-Mud	black, v (FPOM)	ery fine organic	0
Sand Silt Clay	0.06-2mm (gritty) 0.004-0.06 mm < 0.004 mm (slick)		50 20 5	Marl	grey, sh	ell fragments	0

# HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION Station 172+00 - 188+00				
STATION # RBP 23-24 RIVERMILE N/A	STREAM CLASS E (Rosgen)				
LAT 42.411755 LONG -73.233352	RIVER BASIN Housatonic				
STORET # N/A	AGENCY N/A				
INVESTIGATORS SM, TW, KVN, NC					
FORM COMPLETED BY SM	DATE 08/24/22 REASON FOR SURVEY TIME 1600 DAM PM Reach 5A BRA				

	Habitat		Condition	Category	
	Parameter	Optimal	Suboptimal	Marginal	Poor
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.
eac	SCORE 13	20 19 18 17 16	15 14 (13) 12 11	10 9 8 7 6	5 4 3 2 1 0
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization	Mixture of substrate materials, with gravel and firm sand prevalent; root mats and submerged vegetation common.	Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.
nate	SCORE 14	20 19 18 17 16	15 (14) 13 12 11	10 9 8 7 6	5 4 3 2 1 0
ers to be eval	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large-deep; very few shallow.	Shallow pools much more prevalent than deep pools.	Majority of pools small-shallow or pools absent.
mete	SCORE 18	20 19 (18) 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
Para	4. Sediment Deposition	Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.
	SCORE 12	20 19 18 17 16	15 14 13 (12) 11	10 9 8 7 6	5 4 3 2 1 0
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.
	SCORE 13	20 19 18 17 16	15 14 (13) 12 11	10 9 8 7 6	5 4 3 2 1 0

# HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat		Condition	. Category	
	Parameter	Optimal	Suboptimal	Marginal	Poor
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.
	SCORE 17	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
npling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.
ı san	SCORE 10	20 19 18 17 16	15 14 13 12 11	9 8 7 6	5 4 3 2 1 0
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.
eva	SCORE 8 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
to be	SCORE 8 (RB)	Right Bank 10 9	<b>③</b> 7 6	5 4 3	2 1 0
Parameters	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.
	SCORE 9 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
	SCORE 9 (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.
	SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
	SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0

Total Score 151

Incidental Direct Wildlife Observations	
Whirligig beatles	
Great Blue Heron	
Eastern elliptio mussel	
Raptor nest - not ID'ed	
Unidentified fish	
Brook trout	
Green frogs	



Client Name:

Site Location:

Project No.

GE

Reach 5A Housatonic River

Photo No. Date:

8/24/22

**Direction Photo** Taken: South

**Description:** RPB 23-24 looking downstream at a run. Cobble is present on the left bank along with woody debris on both sides.



# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

STREAM NAME Housa	tonic River	LOCATION	Station 188	+00 - 209+00		
STATION # RBP 25-26 R	VERMILE N/A	STREAM CLASS E (Rosgen)				
LAT 42.405314 LO	NG -73.235891	RIVER BASIN	Housatonic			
STORET # N/A		AGENCY N/A	ı			
INVESTIGATORS SM, T	W, KVN, NC					
FORM COMPLETED BY		DATE 08/24/22 TIME 1622		REASON FOR SURVEY		
SM		TIME 1022	AMPPM	Reach 5A BRA		
WEATHER CONDITIONS	Now		Past 24 hours	Has there been a heavy rain in the last 7 days?  ☑Yes ☐No		
	storm (	(heavy rain) steady rain)		Air Temperature 29 C		
	showers	(intermittent)		Other		
		oud cover ar/sunny	<u>70</u> %			
SITE LOCATION/MAP	Draw a map of the site	and indicate the	e areas sampl	ed (or attach a photograph)		
		- Tiles				
	3 1/2 (3)					
	16. 4		1			
	* HISTORY					
	Macro Invert					
	Sampling Station 5 Start	RBP 25-26 (BA-26 - BA-27)	AN			
	RBP 27-28	(DA-26-) DA-21)		Tag No.		
				W LET		
				IN THE STATE OF TH		
	ampling on 5 End	-		ood		
			L. Car			
				ALL WIT		
		11				
	BA+27 €3	8	Te			
	Additional photog	aranhe attacl	had halow			
	Additional prioto(	graprio attaci	IEU DEIUW			
STREAM CHARACTERIZATION	Stream Subsystem Perennial Inter	rmittent   Tida	n1	Stream Type  □Coldwater  □Warmwater		
CIMINIC PENIZATION	Stream Origin	_		Catchment Area km²		
	Glacial Non-glacial montane	Spring-fee	l f origins			
	Swamp and bog	Other				

# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERSHED FEATURES	)	Predom  ☐ Forest ☐ Field/ ☐ Agric ☐ Resid	Pasture Indusultural Other	nercial strial		Local Watershed NPS I  No evidence  Some Obvious sources  Local Watershed Erosi  None  Moderate	e potential sources
RIPARIAN VEGETATION (18 meter buffe		✓ l'rees	e the dominant type a	Shrubs		int species present Grasses He	rbaceous
INSTREAM FEATURES		Estimat Samplin Area in Estimat	km² (m²x1000)  ed Stream Depth  Velocity  0.4	3 m 1201 m <sup>2</sup> 14.2 km <sup>2</sup>		Canopy Cover Partly open Partly High Water Mark 1.  Proportion of Reach Remorphology Types Riffle % Pool 50 %  Channelized Yes  Dam Present Yes	0 m
LARGE WOO DEBRIS	DDY	LWD Density	100 m <sup>2</sup> of LWD 5.85	m²/km² (LWD	' reach	ı area)	
AQUATIC VEGETATION	N	✓ Roote ☐ Floati		Rooted submerg Attached Algae rasses	ent	nnt species present Rooted floating  %	Free floating
WATER QUAI	LITY	Specific Dissolve pH 8.43 Turbidi				Fishy Water Surface Oils	Chemical Other Globs Flecks red)
SEDIMENT/ SUBSTRATE  Odors Normal Chemica Other Oils Pabsent			ical Anaerobic	Petroleum None  Prof			Paper fiber Sand Other Sand/Mud h are not deeply embedded, k in color?
INORGANIC SUBSTRATE COMPONENTS (should add up to 100%)						GANIC SUBSTRATE Co	
Substrate Type			% Composition in Sampling Reach	Substrate Type		Characteristic	% Composition in Sampling Area
Bedrock Boulder > 25	> 256 mm (10")		0	Detritus		ks, wood, coarse plant erials (CPOM)	10
Cobble 64-2	64-256 mm (2.5"-10") 2-64 mm (0.1"-2.5")		20	Muck-Mud		ek, very fine organic OM)	10
Silt 0.00	0.06-2mm (gritty) 0.004-0.06 mm < 0.004 mm (slick)		65 10 2	Marl	grey	, shell fragments	0

# HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION Station 188+00 - 209+00					
STATION # RBP 25-26 RIVERMILE N/A	STREAM CLASS E (Rosgen)					
LAT 42.405314 LONG -73.235891	RIVER BASIN Housatonic					
STORET # N/A	AGENCY N/A	ENCY N/A				
INVESTIGATORS SM, TW, KVN, NC						
FORM COMPLETED BY SM	DATE 08/24/22 TIME 1622 □AM PM	REASON FOR SURVEY Reach 5A BRA				

	Habitat	Condition Category								
	Parameter	Optimal	Suboptimal	Marginal	Poor					
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.					
eac <sub>t</sub>	SCORE 10	20 19 18 17 16	15 14 13 12 11	0 9 8 7 6	5 4 3 2 1 0					
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization	Mixture of substrate materials, with gravel and firm sand prevalent; root mats and submerged vegetation common.	Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.					
nate	SCORE 13	20 19 18 17 16	15 14 (13) 12 11	10 9 8 7 6	5 4 3 2 1 0					
ers to be eval	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large- deep; very few shallow.	Shallow pools much more prevalent than deep pools.	Majority of pools small-shallow or pools absent.					
mete	SCORE 17	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0					
Para	4. Sediment Deposition	Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.					
	SCORE 9	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0					
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.					
	SCORE 14	20 19 18 17 16	15 (14) 13 12 11	10 9 8 7 6	5 4 3 2 1 0					

# HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat		Condition	Category	
	Parameter	Optimal	Suboptimal	Marginal	Poor
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.
	SCORE 18	20 19 (18) 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
npling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.
ı san	SCORE 15	20 19 18 17 16	<b>(</b> 5) 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.
e eva	SCORE 4 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
to be	SCORE 5 (RB)	Right Bank 10 9	8 7 6	<b>⑤</b> 4 3	2 1 0
Parameters	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.
	SCORE 7 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
	SCORE 7 (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.
	SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
	SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0

Total Score 137

Incidental Direct Wildlife Observations					
Red eared slider turtles					
Bluegill					
Crayfish					
Kingfisher					
)					



Client Name:

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

**Date:** 8/24/22

Direction Photo Taken:

South

### **Description:**

RBP 25 looking downstream. Maples and sunflowers occupy the banks. The water depth is shallow in this area and contains scattered pieces of woody debris. Some edges of the stream drop off into a pool.



Photo No.

**Date:** 8/24/22

Direction Photo Taken: Northwest

### **Description:**

RBP 26 looking downstream. The river is predominantly a pool and contains waterlogged woody debris. Maples overhang the river and provide partial cover.



# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

STREAM NAME House	atonic River LOCATION Station 209+00 - 219+00
STATION # RBP 27-28 R	IVERMILE N/A STREAM CLASS E (Rosgen)
LAT 42.40690 LC	ONG -73.23662 RIVER BASIN Housatonic
STORET # N/A	AGENCY N/A
INVESTIGATORS SM, T	TW, KVN, NC
FORM COMPLETED BY	DATE 08/25/22 REASON FOR SURVEY TIME 1010 PAM PM Reach 54 RRA
KVN	TIME 1010 PM Reach 5A BRA
WEATHER CONDITIONS	Now Past 24 Has there been a heavy rain in the last 7 days?  hours ✓ Yes ✓ No
001,21101,5	storm (heavy rain)
	showers (intermittent)
	5 % W %cloud cover 150 % Other Clear/sunny
SITE LOCATION/MAP	Draw a map of the site and indicate the areas sampled (or attach a photograph)
SHE LOCATION/MAP	Draw a map of the site and indicate the areas sampled (of attach a photograph)
	Macro Invert Sampling Station
	6 Start (BA-26 - BA-27)
	RBP 27-28 (BA-28 - BA-29)
	Macro Invert    P 29-30-31   Sampling    -30 - BA-32   Station 5 End
	30 - BA-32) Station 5 End
	DA47
	RBP/32 (BA-33)
	Additional photographs attached below.
STREAM	Stream Subsystem Stream Type
CHARACTERIZATION	Perennial ☐Intermittent ☐Tidal ☐Coldwater ☐Warmwater
	Stream Origin Catchment Area km²  Glacial Spring-fed
	Non-glacial montane Mixture of origins Swamp and bog Other Other

# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERSI FEATURE		Predom ☐Fores ☑Field/ ☐ Agric ☐ Resid	Pasture Industri ultural Other	ercial	Local Watershed NI  □ No evidence □ So □ Obvious sources  Local Watershed En □ None □ Modera	ome potential sources osion
RIPARIAN VEGETAT (18 meter l	ΓΙΟΝ	✓ l'rees	e the dominant type and S nt species present Silv	hrubs		Herbaceous
INSTREAL FEATURE		Estimat Samplin Area in Estimat		m m m km² km² m m sn/sec	High Water Mark	
LARGE W DEBRIS	OODY	LWD Density	150 m <sup>2</sup> of LWD 16.7 r	m²/km² ( <b>LWD</b> /	reach area)	
AQUATIC VEGETAT		☑Roote □Floati domina	ed emergent Ring Algae Algae	record the dominant species present oted submergent Rooted floating Free floating ached Algae  reed, macrophyte algae		
WATER Q	QUALITY	Temperature 19.4			Globs Flecks  Sasured) turbid Turbid	
SEDIMEN SUBSTRA		Odors Norm Chem Othen Othen	nical Anaerobic	Petroleum None	are the undersides b	Other Sand/Mud nich are not deeply embedded,
INORGANIC SUBSTRATE COMPONENTS (should add up to 100%)					ORGANIC SUBSTRATE	
Substrate Type			% Composition in Sampling Reach	Substrate Type	Characteristic	% Composition in Sampling Area
Bedrock Boulder	> 256 mm (10")		0	Detritus	sticks, wood, coarse plant materials (CPOM)	15
Cobble	obble 64-256 mm (2.5"-10")		20	Muck-Mud	black, very fine organic (FPOM)	5
Sand Silt Clay	Sand 0.06-2mm (gritty) Silt 0.004-0.06 mm		55 20 5	Marl	grey, shell fragments	0

# HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION Station 188+00 - 209+00		
STATION # RBP 27-28 RIVERMILE N/A	STREAM CLASS E (Rosgen)		
LAT 42.40690 LONG -73.23662	RIVER BASIN Housatonic		
STORET # N/A	AGENCY N/A		
INVESTIGATORS SM, TW, KVN, NC			
FORM COMPLETED BY KVN	DATE 08/25/22 REASON FOR SURVEY Reach 5A BRA		

	Habitat		Condition	Category	Condition Category								
	Parameter	Optimal	Suboptimal	Marginal	Poor								
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.								
each	SCORE 11	20 19 18 17 16	15 14 13 12 (1)	10 9 8 7 6	5 4 3 2 1 0								
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization	Mixture of substrate materials, with gravel and firm sand prevalent; root mats and submerged vegetation common.	Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.								
nate	SCORE 13	20 19 18 17 16	15 14 (13) 12 11	10 9 8 7 6	5 4 3 2 1 0								
ers to be eval	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large- deep; very few shallow.	Shallow pools much more prevalent than deep pools.	Majority of pools small-shallow or pools absent.								
mete	SCORE 6	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0								
Parar	4. Sediment Deposition	Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.								
	SCORE 13	20 19 18 17 16	15 14 (13) 12 11	10 9 8 7 6	5 4 3 2 1 0								
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.								
	SCORE 15	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0								

# HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat						
	Parameter	Optimal	Suboptimal	Marginal	Poor		
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.		
	SCORE 18	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		
npling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.		
ı san	SCORE 13	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0		
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.		
eva	SCORE 8 (LB)	Left Bank 10 9	8) 7 6	5 4 3	2 1 0		
to be	SCORE 6 (RB)	Right Bank 10 9	8 7 🔞	5 4 3	2 1 0		
Parameters	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.		
	SCORE 7 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0		
	SCORE 7 (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0		
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.		
	SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0		
	SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0		

Total Score 131

Incidental Direct Wildlife Observations				
Gray catbird				
Unidentified waterfowl				
Whirligig beatles				
Water striders				
Redwing blackbird				
Unidentified minnows				
Painted turtles				
Blue heron tracks				



Client Name:

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453


Photo No.

Date: 8/25/22

**Direction Photo** Taken:

Northeast

Description:
RBP 28 looking upstream.
A large pool with slight to
moderate erosion on the
right bank. Large logs have accumulated and dammed a part of the river.



# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

STREAM NAME House	atonic River LOCATION 209+00 - 219+00
	IVERMILE NA STREAM CLASS E (Rosgen)
LAT 42.40734 LC	ONG -73.23855 RIVER BASIN Housatonic
STORET # N/A	AGENCY N/A
INVESTIGATORS SM, 7	TW, KVN, NC
FORM COMPLETED BY	DATE 08/25/22 REASON FOR SURVEY
SM	TIME 1115 PM Reach 5A BRA
WEATHER CONDITIONS	Now Past 24 Has there been a heavy rain in the last 7 days? hours □ Yes □ No
00110110110	storm (heavy rain)
	showers (intermittent)
	% % % % % % % % Other
SITE LOCATION/MAP	Draw a map of the site and indicate the areas sampled (or attach a photograph)
SHE LOCATION/MAP	Draw a map of the site and indicate the areas sampled (of attach a photograph)
	Macro Invert Sampling Station
	5 Start
	S PROGRAM
	RBP 27-28 (BA-28 - BA-29)
	(a) (DY-20-0P-E)
	Macro Invert
	RBP 29-30-31 Sampling (BA-30 - BA-32) Station 5 End
	(BA-3U-BA-3Z)
	8
	S S
	Additional photographs attached below.
	Additional priotographic ditachica polow.
STREAM CHARACTERIZATION	Stream Subsystem Stream Type  ☑ Perennial ☐ Intermittent ☐ Tidal ☐ Coldwater ☑ Warmwater
CHARACTERIZATION	Stream Origin Catchment Areakm <sup>2</sup>
	☐ Glacial ☐ Spring-fed ☐ Mixture of origins
	Swamp and bog Other

# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERS FEATURI		Predom  ☑ Fores  ☑ Field/ ☑ Agric ☑ Resid	Pasture Industri ultural Other	ercial	Local Water □ No eviden □ Obvious so □ Local Water □ None	ce Some ources	e potential sources
RIPARIA VEGETA (18 meter	TION	Indicate the dominant type and record the dominant species present  ☐ Irees ☐ Shrubs ☐ Grasses ☐ Herbaceous  dominant species present ☐ Box elder, Silver & Red maple, Knotweed					rbaceous
INSTREA FEATURI		Estimate Samplin Area in Estimate		m m m m m m m m m m m m m m m m m m m	Canopy Cov Partly ope: High Water Proportion Morphology VRiffle 15 V Pool 50 Channelized	Mark 1  of Reach Ro y Types  y W  y Types  y Y  y Y  y Y  y Y  y Y  y Y  y Y  y	y shaded Shaded m mepresented by Stream Run 55 %  No
LARGE W DEBRIS	VOODY	LWD Density	400 m <sup>2</sup> of LWD 57.14 m	n²/km² (LWD/	reach area)		
AQUATIC VEGETATION  Indicate the dominant type and record the dominant species present Rooted emergent Acoted submergent Indicate the dominant species present Indicate the dominant type and record the dominant species present Indicate the dominant species present Indicate the dominant type and record the dominant species present Indicate the dominant type and record the dominant species present Indicate the dominant type and record the dominant species present Indicate the dominant type and record the dominant species present Indicate the dominant type and record the dominant species present Indicate the dominant type and record the dominant species present Indicate the dominant species present Indicate the dominant type and record the dominant species present Indicate the Indi					Free floating		
WATER (	QUALITY	Specific Dissolve pH 8.1 Turbidi		ms/cm	Water Odoi  ✓ Normal/No  — Petroleum  — Fishy  Water Surfa  — Slick  ✓ None  Turbidity (i	one Sewa	Chemical Other Globs Flecks red)
SEDIMENT/ SUBSTRATE  Odors Normal Chemical Other Oils Plasent			ical Anaerobic	Petroleum None	are the unde	is visiones which	Paper fiber Sand Other Sand/Mud h are not deeply embedded, k in color?
INORGANIC SUBSTRATE COMPONENTS (should add up to 100%)					ORGANIC SUBS		
Substrate Type			% Composition in Sampling Reach	Substrate Type	Character	istic	% Composition in Sampling Area
Bedrock Boulder	> 256 mm (10")		0	Detritus	sticks, wood, coars materials (CPOM)		10
Cobble Gravel	ble 64-256 mm (2.5"-10")		5 20	Muck-Mud	black, very fine or (FPOM)	ganic	0
Sand Silt Clay	0.004-0.06 mm		35 20 20	Marl	grey, shell fragmer	nts	0

# HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION 219+00 - 227+00		
STATION # RBP 29-31 RIVERMILE N/A	STREAM CLASS E (Rosgen)		
LAT 42.40734 LONG -73.23855	RIVER BASIN Housatonic		
STORET # N/A	AGENCY N/A		
INVESTIGATORS SM, TW, KVN, NC			
FORM COMPLETED BY	DATE 08/25/22 REASON FOR SURVEY		
SM	TIME LI115 PM Reach 5A BRA		

	Habitat		Condition	Category	
	Parameter	Optimal	Suboptimal	Marginal	Poor
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.
each	SCORE 9	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization	Mixture of substrate materials, with gravel and firm sand prevalent; root mats and submerged vegetation common.	Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.
nate	SCORE 11	20 19 18 17 16	15 14 13 12 (1)	10 9 8 7 6	5 4 3 2 1 0
rs to be eval	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large-deep; very few shallow.	Shallow pools much more prevalent than deep pools.	Majority of pools small-shallow or pools absent.
mete	SCORE 12	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
Parar	4. Sediment Deposition	Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.
	SCORE 12	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.
	SCORE 11	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0

# HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat	Condition Category							
	Parameter	Optimal	Suboptimal	Marginal	Poor				
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.				
	SCORE 16	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0				
npling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.				
ı sar	SCORE 15	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0				
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.				
e eve	SCORE 7 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0				
to be	SCORE 7 (RB)	Right Bank 10 9	8 ⑦ 6	5 4 3	2 1 0				
Parameters	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.				
	SCORE 8 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0				
	SCORE (RB)	Right Bank 10 9	3 7 6	5 4 3	2 1 0				
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.				
	SCORE (LB)	Left Bank 10 9	8 7 <b>6</b>	5 4 3	2 1 0				
	SCORE (RB)	Right Bank <b>①</b> 9	8 7 6	5 4 3	2 1 0				

Total Score 132

Incidental Direct Wildlife Observations						
Caddisfly exoskeleton						
Honeybee						
Dragonflies (green & blue)						
Unidentified fishes						
Whirligig beetles						



### **PHOTOGRAPHIC LOG**

**Client Name:** 

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

Date: 8/25/22

**Direction Photo** Taken:

Southwest

Description: RBP 29 looking downstream. The right side of the river is a large pool, while the left side is mainly a run. Woody debris has settled in the deep pool areas.



Photo No. 2

Date: 8/25/22

**Direction Photo** Taken:

Southwest

Description:

RBP 29 looking downstream. The right side of the river is a large pool, while the left side is mainly a run. Woody debris has settled in the deep pool areas.





### **PHOTOGRAPHIC LOG**

Client Name:

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

**Date:** 8/25/22

## Direction Photo Taken:

South/Southeast

### Description:

RBP 30-31 looking downstream at bend. A large deep pool makes up this area. Mature silver and red maples line the right bank. Erosion is visible on the outer bend and woody debris is present.



# PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

STREAM NAME Housatonic River		LOCATION 227+00 - 234+00		
	VERMILE N/A	STREAM CLASS E (Rosgen)		
LAT 42.40581 LC	NG -73.23732	RIVER BASIN Housatonic		
STORET # N/A		AGENCY N/A		
INVESTIGATORS SM, 7	W, KVN, NC			
FORM COMPLETED BY KVN		DATE 08/25/22 TIME 1330 AM	REASON FOR SURVEY Reach 5A BRA	
WEATHER CONDITIONS	rain ( showers  5 % v %cl	Past 2- hours  (heavy rain) steady rain) s (intermittent) loud cover aar/sunny	✓ Yes No  Air Temperature 28 ° C	
SITE LOCATION/MAP	Draw a map of the site	e and indicate the areas s	impled (or attach a photograph)	
	29-30-31 0-BA-32)	RBP3 (BA-3)	Station 5 End  EA-27	
STREAM CHARACTERIZATION	Stream Subsystem Perennial Inte Stream Origin Glacial Non-glacial montane Swamp and bog	ermittent	Stream Type Coldwater Warmwater Catchment Area km²	

## PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERS FEATURI		Predom  ✓ Forest  ✓ Field/ ✓ Agric  ✓ Resid	Pasture Industri	ercial		Local Watershed NPS I  No evidence  Obvious sources  Local Watershed Erosic  None  Moderate	potential sources
RIPARIA VEGETA (18 meter	TION	Trees	e the dominant type and S  nt species present  Kno	hrubs		Grasses Hei	baceous
INSTREA FEATURI		Estimated Reach Length 200 m  Estimated Stream Width 20 m  Sampling Reach Area 4070 m²  Area in km² (m²x1000) 4 km²  Estimated Stream Depth 2 m  Surface Velocity 0.2 m/sec (at thalweg)				Canopy Cover Partly open Partly High Water Mark 2  Proportion of Reach Re Morphology Types Riffle % V Pool 65 %  Channelized Yes  Dam Present Yes	
LARGE W DEBRIS	VOODY	LWD Density	500 m <sup>2</sup> of LWD 125 m	m²/km² <b>(LWD</b> / 1	reach	area)	
AQUATIO VEGETA		Indicate the dominant type and record the dominant species present  ☐ Rooted emergent ☐ Rooted submergent ☐ Floating Algae ☐ Attached Algae  dominant species present ☐ Burr reed, milfoil  Portion of the reach with aquatic vegetation 2 %					Free floating
WATER QUALITY  Temperature 21.9 ° C  Specific Conductance 0.521 ms/cm  Dissolved Oxygen 8.94 mg/L  pH 8.38  Turbidity			l		☐Fishy ☐ Water Surface Oils	Chemical Other Globs Flecks red)	
SEDIMEN SUBSTRA		Odors Norm Chem Other Oils	nical Anaerobic	Petroleum None  Profu	□ se		Paper fiber Sand Other Sand/Mud n are not deeply embedded, k in color?
INC		STRATE (	COMPONENTS			GANIC SUBSTRATE Co	
Substrate Type	Diamete	er	% Composition in Sampling Reach	Substrate Type		Characteristic	% Composition in Sampling Area
Bedrock Boulder	> 256 mm (10")	0 nm (10")				ss, wood, coarse plant erials (CPOM)	15
Cobble Gravel	( /			Muck-Mud	black (FPC	k, very fine organic OM)	5
Sand Silt Clay				Marl	grey	, shell fragments	0

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION 227+00- 234+00			
STATION # RBP 32 RIVERMILE N/A	STREAM CLASS E (Rosgen)			
LAT 42.40581 LONG -73.23732	RIVER BASIN Housatonic			
STORET # N/A	AGENCY N/A			
INVESTIGATORS SM, TW, KVN, NC				
FORM COMPLETED BY	DATE 08/25/22 REASON FOR SURVEY			
KVN	TIME 1330 AMDPM Reach 5A BRA			

	Habitat	Condition Category						
	Parameter	Optimal	Suboptimal	Marginal	Poor			
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.			
each.	SCORE 12	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0			
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization	Mixture of substrate materials, with gravel and firm sand prevalent; root mats and submerged vegetation common.	Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.			
nate	SCORE 10	20 19 18 17 16	15 14 13 12 11	0 9 8 7 6	5 4 3 2 1 0			
rs to be eval	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large-deep; very few shallow.	Shallow pools much more prevalent than deep pools.	Majority of pools small-shallow or pools absent.			
mete	SCORE 13	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0			
Para	4. Sediment Deposition	Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.			
	SCORE 13	20 19 18 17 16	15 14 (13) 12 11	10 9 8 7 6	5 4 3 2 1 0			
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.			
	SCORE 18	20 19 (18) 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0			

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat					
	Parameter	Optimal	Suboptimal	Marginal	Poor	
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.	
	SCORE 20	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0	
npling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.	
ı san	SCORE 18	20 19 (8) 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0	
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.	
eva	SCORE 2 (LB)	Left Bank 10 9	8 7 6	5 4 3	2) 1 0	
to be	SCORE 4 (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0	
Parameters	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.	
	SCORE 2 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0	
	SCORE 5 (RB)	Right Bank 10 9	8 7 6	<b>⑤</b> 4 3	2 1 0	
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.	
	SCORE (LB)	Left Bank 10 9	8 7 6	<b>③</b> 4 3	2 1 0	
	SCORE (RB)	Right Bank 0 9	8 7 6	5 4 3	2 1 0	

Total Score 132

Incidental Direct Wildlife Observations					
Belted kingfisher					
Dragonflies					
Crickets					
Various field insects					
Green tree frog					
Water strider					
Catbird					
Beaver sign					



### PHOTOGRAPHIC LOG

**Client Name:** 

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.


**Date:** 8/25/22

Direction Photo Taken:

South

### Description:

RBP 32 looking downstream. The outer bend is a pool with large clumps of woody debris and erosion. The inner bend is shallower and is a run. Moderate erosion has occurred at the outer bank and has shrubs growing on top of the slope.



## PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (FRONT)

STREAM NAME Housatonic River		LOCATION 234+00 - 247+00		
	IVERMILE N/A	STREAM CLASS E (Rosgen)		
LAT 42.40385 LC	NG -73.23812	RIVER BASIN Housatonic		
STORET # N/A		AGENCY N/A		
INVESTIGATORS SM, 7	ΓW, KVN, NC			
FORM COMPLETED BY		DATE 08/25/22 TIME 1341	REASON FOR SURVEY	
SM		TIME <b>1341</b> □ AM	Reach 5A BRA	
WEATHER CONDITIONS	Now	Past 2		
CONDITIONS	storm	(heavy rain) hours	Air Temperature 32 C	
	showers	steady rain)	Other	
	25 % V %cl	oud cover  ar/sunny	% Other	
CITE I OCLETOWAL S		•		
SITE LOCATION/MAP	Draw a map of the site	e and indicate the areas s	ampled (or attach a photograph)	
			(BA-33)	
			B	
		7. E		
	- F			
	RBP3	3		
	(BA-34			
		THE REAL PROPERTY.		
		We have the second		
		A WARRY		
			ATT FOR	
	Additional photo	graphs attached be	elow.	
STREAM	Stream Subsystem  ✓ Perennial ☐ Inte	To a Post of	Stream Type	
CHARACTERIZATION		ermittent Tidal	□Coldwater □Warmwater	
	Stream Origin	Spring-fed	Catchment Area km²	
	Non-glacial montane Swamp and bog	Mixture of origins Other	l	
	I —			

## PHYSICAL CHARACTERIZATION/WATER QUALITY FIELD DATA SHEET (BACK)

WATERSHED FEATURES	✓ Fores	/Pasture	ercial	Local Watershed NPS  No evidence Obvious sources  Local Watershed Eros None	e potential sources
RIPARIAN VEGETATION (18 meter buffer)	✓ l'rees	e the dominant type and S unt species present Kno	hrubs	Grasses THO	erbaceous
INSTREAM FEATURES	Estima Sampli Area in Estima			Proportion of Reach R Morphology Types	.5 m
LARGE WOODY DEBRIS	LWD Density	400 m <sup>2</sup> 7 <b>of LWD</b> 25 r	m²/km² ( <b>LWD</b> /	reach area)	
AQUATIC VEGETATION	☑Root □Float domina	Indicate the dominant type and record the dominant species present  ☐ Rooted emergent ☐ Rooted submergent ☐ Rooted floating ☐ Free floating  ☐ dominant species present ☐ Burr weed ☐ Portion of the reach with aquatic vegetation ☐ 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			
WATER QUALITY  Temperature 21.6 ° C  Specific Conductance 0.522 ms/cm  Dissolved Oxygen 8.6 mg/L  pH 8.38  Turbidity				<u>W</u> ater Sur <u>face</u> Oils	Chemical Other Globs Flecks
SEDIMENT/ SUBSTRATE	Odors Norn Chen Othe	nical Anaerobic	Petroleum None	Looking at stones which are the undersides black	Paper fiber Sand Other Sand/Mud ch are not deeply embedded, ck in color?
	BSTRATE I add up to	COMPONENTS 100%)		ORGANIC SUBSTRATE ( (does not necessarily add	
Substrate Type Dian	te Diameter % Composition in Sampling Reach			Characteristic	% Composition in Sampling Area
Bedrock Boulder > 256 mm (1	> 256 mm (10") 2			sticks, wood, coarse plant materials (CPOM)	6
Cobble 64-256 mm ( Gravel 2-64 mm (0	2.5"-10")	5	Muck-Mud	black, very fine organic (FPOM)	8
Sand 0.06-2mm (g Silt 0.004-0.06 m Clay < 0.004 mm	[50] [30] [11]	Marl	grey, shell fragments	0	

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (FRONT)

STREAM NAME Housatonic River	LOCATION 234+00 - 247+00			
STATION # RBP 33 RIVERMILE N/A	STREAM CLASS E (Rosgen)			
LAT 42.40385 LONG -73.23812	RIVER BASIN Housatonic			
STORET # N/A	AGENCY N/A			
INVESTIGATORS SM, TW, KVN, NC				
FORM COMPLETED BY	DATE 08/25/22 REASON FOR SURVEY			
SM	TIME 1341 Reach 5A BRA			

	Habitat	Condition Category						
	Parameter	Optimal	Suboptimal	Marginal	Poor			
	1. Epifaunal Substrate/ Available Cover	Greater than 50% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	30-50% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	10-30% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 10% stable habitat; lack of habitat is obvious; substrate unstable or lacking.			
eac <sub>t</sub>	SCORE 8	20 19 18 17 16	15 14 13 12 11	10 9 (8) 7 6	5 4 3 2 1 0			
Parameters to be evaluated in sampling reach	2. Pool Substrate Characterization	Mixture of substrate materials, with gravel and firm sand prevalent; root mats and submerged vegetation common.	Mixture of soft sand, mud, or clay; mud may be dominant; some root mats and submerged vegetation present.	All mud or clay or sand bottom; little or no root mat; no submerged vegetation.	Hard-pan clay or bedrock; no root mat or vegetation.			
nate	SCORE 9	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0			
rs to be eval	3. Pool Variability	Even mix of large- shallow, large-deep, small-shallow, small-deep pools present.	Majority of pools large-deep; very few shallow.	Shallow pools much more prevalent than deep pools.	Majority of pools small-shallow or pools absent.			
mete	SCORE 12	20 19 18 17 16	15 14 13 (12) 11	10 9 8 7 6	5 4 3 2 1 0			
Para	4. Sediment Deposition	Little or no enlargement of islands or point bars and less than <20% of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 20-50% of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 50-80% of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 80% of the bottom changing frequently; pools almost absent due to substantial sediment deposition.			
	SCORE 6	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0			
	5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.			
	SCORE 13	20 19 18 17 16	15 14 (13) 12 11	10 9 8 7 6	5 4 3 2 1 0			

### HABITAT ASSESSMENT FIELD DATA SHEET—LOW GRADIENT STREAMS (BACK)

	Habitat				
	Parameter	Optimal	Suboptimal	Marginal	Poor
	6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.
	SCORE 17	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
npling reach	7. Channel Sinuosity	The bends in the stream increase the stream length 3 to 4 times longer than if it was in a straight line. (Note - channel braiding is considered normal in coastal plains and other low-lying areas. This parameter is not easily rated in these areas.)	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	The bends in the stream increase the stream length 1 to 2 times longer than if it was in a straight line.	Channel straight; waterway has been channelized for a long distance.
ı sar	SCORE 18	20 19 (8) 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
Parameters to be evaluated broader than sampling reach	8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.
eva	SCORE 3 (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
to be	SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0
Parameters	9. Vegetative Protection (score each bank)  Note: determine left or right side by facing downstream.	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.
	SCORE 5 (LB)	Left Bank 10 9	8 7 6	<b>3</b> 4 3	2 1 0
	SCORE 5 (RB)	Right Bank 10 9	8 7 6	<b>5</b> 4 3	2 1 0
	10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12- 18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6- 12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters: little or no riparian vegetation due to human activities.
	SCORE (LB)	Left Bank 10 9	8 🔿 6	5 4 3	2 1 0
	SCORE (RB)	Right Bank 10 9	8 ⑦ 6	5 4 3	2 1 0

Total Score 113

Incidental Direct Wildlife Observations	
Kingfisher	
Wood Duck	
Pickerel Frog	
Beaver sign	



### PHOTOGRAPHIC LOG

**Client Name:** 

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

**Date:** 8/25/22

Direction Photo Taken: South



### **Description:**

RBP 33-34 looking downstream. One of the deeper RBPs in our survey. The large pool's water depth is approximately six and a half feet. Woody debris clusters can be seen in the distance.

# Photo No. Date: 8/25/22

Direction Photo Taken:

North

Description:

RBP 33-34 looking upstream. Most of this section is a pool with large amounts of woody debris. The substrate is predominantly sand with some silt.





## A-1b Wildlife Forms

### **WILDLIFE FIELD OBSERVATIONS**

Date:08/23/2022

Time:0920

Weather: Showers

Team member(s): SM, TW, KVN, NC

Detail	S OI Observati	ons.		Details of Observations.									
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u>	Species Observed <sup>3</sup>	Location <sup>4</sup>	<u>Faunal</u>	<b>Observation</b>	Behavior/Condition Description/Habitat Type <sup>6</sup>						
		Collected:2			<u>Type⁵</u>	Type <sup>6</sup>							
0920	Amphibian	No	American Toad  Anaxyrus americanus	RBP 0-1 42.433205, -73.251625	Amphibian	Animal	Individual						
0920	Small mammal	No	American Beaver Castor canadensis	RBP 0-1 42.433205, -73.251625	Small mammal	Track							

### **WILDLIFE FIELD OBSERVATIONS**

Date: 08/23/2022 Time: 1024

Weather: Showers

Team member(s): SM, TW, KV, NC

<u>Time</u>	Observation <sup>1</sup>	Data Collected: <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	Faunal Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
1024	Reptile	No	Painted turtle Chrysemys picta	RBP 2-4 42.432825, -73.250741	Reptile	Animal	Individual Adult
1024	Amphibian	No	Green frog Lithobates clamitans	RBP 2-4 42.432825, -73.250741	Amphibian	Animal	Individual Adult
1024	Fish	No	Unknown	RBP 2-4 42.432825, -73.250741	Fish	Animal	2 individuals approximately 12" in length
1024	Bird	No	Hummingbird Trochilidae	RBP 2-4 42.432825, -73.250741	Bird	Animal	Individual
1024	Invertebrate	No	Common water strider Aquarius remigis	RBP 2-4 42.432825, -73.250741	Invertebrate	Animal	Multiple individuals
1024	Bird	No	Belted kingfisher Megaceryle alcyon	RBP 2-4 42.432825, -73.250741	Bird	Animal	1 individual

### **WILDLIFE FIELD OBSERVATIONS**

Date: 08/23/2022

**Time:** 1030

Weather: Showers

Team member(s): SM, TW, KVN, NC

שכומוו	is of Observati	uiia.	1		1	1	
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u>	Species Observed <sup>3</sup>	Location <sup>4</sup>	<u>Faunal</u>	<u>Observation</u>	Behavior/Condition Description/Habitat Type <sup>6</sup>
		Collected:2			<u>Type⁵</u>	Type <sup>6</sup>	
1030	Invertebrate	No	Crayfish Cambarus	RBP 5-6 42.430558, -73.249828	Invertebrate	Animal	Individual
1030	Invertebrate	No	Eastern Elliptio Elliptio complanata	RBP 5-6 42.430558, -73.249828	Invertebrate	Animal	Multiple individuals
1030	Bird	No	Great blue heron Ardea herodias	RBP 5-6 42.430558, -73.249828	Bird	Animal	Individual
1030	Small mammal	No	American Beaver Castor canadensis	RBP 5-6 42.430558, -73.249828	Small mammal	Track	
1030	Large mammal	No	White-tailed deer Odocoileus virginianus	RBP 5-6 42.430558, -73.249828	Large mammal	Track	
1030	Small mammal	No	Racoon Procyon lotor	RBP 5-6 42.430558, -73.249828	Small mammal	Track	

### **WILDLIFE FIELD OBSERVATIONS**

Date: 08/23/2022

**Time:** 1510

Weather: Showers

Team member(s): SM, TW, KVN, NC

<u>Time</u>	Observation <sup>1</sup>	Data Collected: <sup>2</sup>	Species Observed <sup>3</sup>	Location <sup>4</sup>	Faunal Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
1510	Amphibian	No No	Pickerel Frog Lithobates palustris	RBP 7-9 42.429998, -73.246600	Amphibian	Animal	Individual
1510	Bird	No	Killdeer Charadrius vociferus	RBP 7-9 42.429998, -73.246600	Bird	Animal	Individual
1510	Invertebrate	No	Dragonfly Anisoptera	RBP 7-9 42.429998, -73.246600	Invertebrate	Animal	Individual
1510	Bird	No	Bluejay Cyanocitta cristata	RBP 7-9 42.429998, -73.246600	Bird	Animal	Individual
1510	Bird	No	Gray catbird  Dumetella carolinensis	RBP 7-9 42.429998, -73.246600	Bird	Animal	2 individuals
1510	Invertebrate	No	Whirligig beetles Gyrinidae	RBP 7-9 42.429998, -73.246600	Invertebrate	Animal	Multiple individuals

### WILDLIFE FIELD OBSERVATIONS

Date: 08/23/2022

Time:1445 Weather: Showers

Team member(s): SM, TW, KVN, NC

Time	Observation <sup>1</sup>	Data	Species Observed <sup>3</sup>	Location <sup>4</sup>	Faunal	Observation	Behavior/Condition Description/Habitat Type <sup>6</sup>
		Collected:2			Type <sup>5</sup>	Type <sup>6</sup>	
1445	Invertebrate	No	Clam Bivalvia	RBP 10-11 42.429839, -73.241568	Invertebrate	Animal	Multiple individuals
1445	Amphibian	No	Green Frog Rana clamitans	RBP 10-11 42.429839, -73.241568	Amphibian	Animal	Multiple individuals
1445	Small mammal	No	Racoon Procyon lotor	RBP 10-11 42.429839, -73.241568	Small mammal	Scat	
1445	Fish	No	Minnow Small fish	RBP 10-11 42.429839, -73.241568	Fish	Animal	Multiple individuals
1445	Invertebrate	No	Eastern Elliptio Elliptio complanata	RBP 10-11 42.429839, -73.241568	Invertebrate	Animal	Multiple individuals

### **WILDLIFE FIELD OBSERVATIONS**

Date: 08/23/2022 **Time:** 1545

Weather: Showers

Team member(s): SM, NC, KVN, TW

<u>Time</u>	Observation <sup>1</sup>	<u>Data</u>	Species Observed <sup>3</sup>	Location <sup>4</sup>	<u>Faunal</u>	Observation	Behavior/Condition Description/Habitat Type <sup>6</sup>
		Collected:2			<u>Type⁵</u>	<u>Type<sup>6</sup></u>	
1545	Large	No	White-tailed deer	RBP 12-13	Large	Track	
	mammal		Odocoileus virginianus	42.426141,	Mammal		
				-73.238070			
1545	Invertebrate	No	Eastern Elliptio Elliptio complanata	RBP 12-13 42.426141, -73.238070	Invertebrate	Animal	Multiple individuals
1545	Small mammal	No	Racoon Procyon lotor	RBP 12-13 42.426141, -73.238070	Small mammal	Track	

### **WILDLIFE FIELD OBSERVATIONS**

Date: 08/23/2022 **Time:**1710

Weather: Cloudy

Team member(s): SM, KVN, TW, NC

<u>Time</u>	Observation <sup>1</sup>	Data Collected: <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	<u>Faunal</u> <u>Type⁵</u>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
1710	Invertebrate	No	Whirligig beetles Gyrinidae	RBP 14 42.25222, -73.14145	Invertebrate	Animal	Multiple individuals
1710	Bird	No	Killdeer Charadrius vociferus	RBP 14 42.25222, -73.14145	Bird	Animal	Individual
1710	Small mammal	No	American Beaver Castor canadensis	RBP 14 42.25222, -73.14145	Small mammal	Animal	Individual
1710	Large mammal	No	White-tailed deer Odocoileus virginianus	RBP 14 42.25222, -73.14145	Large Mammal	Tracks	
1710	Invertebrate	No	Damselfly Zygoptera	RBP 14 42.25222, -73.14145	Invertebrate	Animal	Individual
1710	Invertebrate	No	Dragonfly Anisoptera	RBP 14 42.25222, -73.14145	Invertebrate	Animal	Multiple individuals
1710	Invertebrate	No	Crayfish Cambarus	RBP 14 42.25222, -73.14145	Invertebrate	Animal	Individual

### **WILDLIFE FIELD OBSERVATIONS**

Date:08/24/22 Time:1050

Weather:Cloudy

Team member(s): SM, KVN, TW, NC

Time	Observation <sup>1</sup>	Data	Species Observed <sup>3</sup>	<b>Location</b> ⁴	Faunal	Observation	Behavior/Condition Description/Habitat Type <sup>6</sup>
		Collected:2			Type <sup>5</sup>	Type <sup>6</sup>	
<u>1050</u>	Invertebrate	No	Whirligig beetles Gyrinidae	RBP 15-16, 42.25226, -73.14156	Invertebrate	Animal	Multiple individuals
<u>1050</u>	Invertebrate	No	Crayfish Cambarus	RBP 15-16, 42.25226, -73.14156	Invertebrate	Animal	6 individuals
1050	Amphibian	No	Green tree frog Hyla cinerea	RBP 15-16, 42.25226, -73.14156	Amphibian	Animal	3 individuals
1050	<u>Bird</u>	No	Cooper's hawk Accipiter cooperii	RBP 15-16, 42.25226, -73.14156	Bird	Animal	2 individuals
1050	Reptile	No	Painted turtle Chrysemys picta	RBP 15-16, 42.25226, -73.14156	Reptile	Animal	2 individuals
1050	Invertebrate	No	Eastern Elliptio Elliptio complanata	RBP 15-16, 42.25226, -73.14156	Invertebrate	Animal	Individual
1050	<u>Bird</u>	No	White-breasted nuthatch Sitta carolinensis	RBP 15-16, 42.25226, -73.14156	Bird	Animal	Individual
1050	Invertebrate	No	Bumblebee Bombus	RBP 15-16, 42.25226, -73.14156	Invertebrate	Animal	Multiple individuals
<u>1050</u>	Invertebrate	No	<u>Honeybee</u> <u>Apis mellifera</u>	RBP 15-16, 42.25226, -73.14156	Invertebrate	Animal	Multiple individuals

### **WILDLIFE FIELD OBSERVATIONS**

Date:08/24/2022

Time:1217

Weather: Partly Cloudy

Team member(s): SM, KVN, TW, NC

Time	Observation <sup>1</sup>	Data	Species Observed <sup>3</sup>	Location <sup>4</sup>	Faunal	Observation	Behavior/Condition Description/Habitat Type <sup>6</sup>
		Collected:2	_		Type <sup>5</sup>	Type <sup>6</sup>	
1217	Bird	No	American goldfinch Spinus tristis	RBP 17 42.416992, -73.240999	Bird	Animal	Multiple individuals
1217	Small mammal	No	American Beaver Castor canadensis	RBP 17 42.416992, -73.240999	Small mammal	Track	
1217	Bird	No	Canada goose Branta canadensis	RBP 17 42.416992, -73.240999	Bird	Scat	
1217	Bird	No	Hummingbird Trochilidae	RBP 17 42.416992, -73.240999	Bird	Animal	Multiple individuals

### WILDLIFE FIELD OBSERVATIONS

Date:08/24/22 Time:1235

Weather: Partly Cloudy

Team member(s): SM, KVN, TW, NC

<u>Time</u>	Observation <sup>1</sup>	<u>Data</u>	Species Observed <sup>3</sup>	Location <sup>4</sup>	<u>Faunal</u>	Observation	Behavior/Condition Description/Habitat Type <sup>6</sup>
		Collected:2			<u>Type⁵</u>	<u>Type<sup>6</sup></u>	
1235	Bird	No	American goldfinch Spinus tristis	RBP 18 42.414557, -73.238682	Bird	Animal	Multiple individuals
1235	Invertebrate	No	Eastern Elliptio Elliptio complanata	RBP 18 42.414557, -73.238682	Invertebrate	Animal	Individual
1235	Bird	No	Belted kingfisher Megaceryle alcyon	RBP 18 42.414557, -73.238682	Bird	Animal	Individual
1235	Reptile	No	Painted turtle Chrysemys picta	RBP 18 42.414557, -73.238682	Reptile	Animal	Multiple individuals
1235	Amphibian	No	Green Frog Rana clamitans	RBP 18 42.414557, -73.238682	Amphibian	Animal	Individual
1235	Bird	No	Common grackle Quiscalus quiscula	RBP 18 42.414557, -73.238682	Bird	Animal	Individual
1235	Bird	No	Great blue heron Ardea herodias	RBP 18 42.414557, -73.238682	Bird	Animal	Individual
1235	Bird	No	Canada goose Branta canadensis	RBP 18 42.414557, -73.238682	Bird	Animal	Individual
1235	Bird	No	Yellow warbler Setophaga petechia	RBP 18 42.414557, -73.238682	Bird	Animal	Individual
1235	Bird	No	Red-tailed hawk Buteo jamaicensis	RBP 18 42.414557, -73.238682	Bird	Animal	Multiple individuals
1235	Reptile	No	Common snapping turtle Chelydra serpentina	RBP 18 42.414557, -73.238682	Reptile	Animal	Individual

### WILDLIFE FIELD OBSERVATIONS

Date:08/24/2022

**Time:**1430

Weather: Partly Cloudy

Team member(s): SM, KVN, TW, NC

Time	Observation <sup>1</sup>	<u>Data</u>	Species Observed <sup>3</sup>	Location <sup>4</sup>	<u>Faunal</u>	Observation	Behavior/Condition Description/Habitat Type <sup>6</sup>
		Collected:2			<u>Type⁵</u>	<u>Type<sup>6</sup></u>	
1430	Bird	No	Cedar waxwing Bombycilla cedrorum	RBP 19 42.415515, -73.236849	Bird	Animal	Individual
1430	Bird	No	Red bellied woodpecker Melanerpes carolinus	RBP 19 42.415515, -73.236849	Bird	Animal	Individual
1430	Bird	No	Sandpiper Scolopacidae	RBP 19 42.415515, -73.236849	Bird	Animal	Individual
1430	Invertebrate	No	Eastern Elliptio Elliptio complanata	RBP 19 42.415515, -73.236849	Invertebrate	Animal	Individual
1430	Reptile	No	Painted turtle Chrysemys picta	RBP 19 42.415515, -73.236849	Reptile	Animal	Multiple individuals
1430	Amphibian	No	Green frog Lithobates clamitans	RBP 19 42.415515, -73.236849	Amphibian	Animal	Individual
1430	Bird	No	Red-tailed hawk Buteo jamaicensis	RBP 19 42.415515, -73.236849	Bird	Animal	Individual

### WILDLIFE FIELD OBSERVATIONS

Date:08/24/2022

Time:1520

Weather: Partly Cloudy

Team member(s): SM, KVN, TW, NC

<u>Time</u>	Observation <sup>1</sup>	Data Collected: <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	Faunal Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
1520	Invertebrate	No	Crayfish Cambarus	RBP 20-22 42.414430, -73.234158	Invertebrate	Animal	Individual
1520	Bird	No	Great blue heron Ardea herodias	RBP 20-22 42.414430, -73.234158	Bird	Animal	Individual
1520	Small mammal	No	American Beaver Castor canadensis	RBP 20-22 42.414430, -73.234158	Small mammal	Sign	
1520	Bird	No	Mallard Anas platyrhynchos	RBP 20-22 42.414430, -73.234158	Bird	Animal	Individual
1520	Bird	No	American goldfinch Spinus tristis	RBP 20-22 42.414430, -73.234158	Bird	Animal	Multiple individuals

### WILDLIFE FIELD OBSERVATIONS

Date:08/24/22 Time:1600

Weather: Partly Cloudy

Team member(s): SM, KVN, TW, NC

<u>Time</u>	Observation <sup>1</sup>	Data Collected: <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	<u>Faunal</u> Type⁵	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
1600	Invertebrate	No	Whirligig beetles Gyrinidae	RBP 23-24 42.411755, -73.233352	Invertebrate	Animal	Multiple individuals
1600	Bird	No	Great blue heron Ardea herodias	RBP 23-24 42.411755, -73.233352	Bird	Animal	Individual
1600	Invertebrate	No	Eastern Elliptio Elliptio complanata	RBP 23-24 42.411755, -73.233352	Invertebrate	Animal	Multiple individuals
1600	Fish	No	Brook trout Salvelinus fontinalis	RBP 23-24 42.411755, -73.233352	Fish	Animal	Individual
1600	Amphibian	No	Green frog Lithobates clamitans	RBP 23-24 42.411755, -73.233352	Amphibian	Animal	Multiple individuals

### **WILDLIFE FIELD OBSERVATIONS**

Date:08/24/2022

Time:1622

Weather: Partly Cloudy

Team member(s): SM, KVN, TW, NC

<u>Time</u>	Observation <sup>1</sup>	Data Collected: <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	Faunal Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
1622	Reptile	No	Red eared slider turtle Trachemys scripta elegans	RBP 25-26 42.405314, -73.235891	Reptile	Animal	Individual
1622	Fish	No	Bluegill Lepomis macrochirus	RBP 25-26 42.405314, -73.235891	Fish	Animal	Individual
1622	Invertebrate	No	Crayfish Cambarus	RBP 25-26 42.405314, -73.235891	Invertebrate	Animal	Individual
1622	Bird	No	Belted kingfisher Megaceryle alcyon	RBP 25-26 42.405314, -73.235891	Bird	Animal	Individual

### **WILDLIFE FIELD OBSERVATIONS**

Date:08/25/2022 Time:1010

Weather: Sunny

Team member(s): SM, KVN, TW, NC

Time	Observation <sup>1</sup>	Data	Species Observed <sup>3</sup>	Location <sup>4</sup>	Faunal	Observation	Behavior/Condition Description/Habitat Type <sup>6</sup>
		Collected:2			<u>Type⁵</u>	Type <sup>6</sup>	
1010	Bird	No	Gray catbird  Dumetella carolinensis	RBP 27-28 42.40690, -73.23662	Bird	Animal	Individual
1010	Bird	No	Unidentified waterfowl	RBP 27-28 42.40690, -73.23662	Bird	Animal	Individual
1010	Invertebrate	No	Whirligig beetles Gyrinidae	RBP 27-28 42.40690, -73.23662	Invertebrate	Animal	Multiple individuals
1010	Invertebrate	No	Common water strider Aquarius remigis	RBP 27-28 42.40690, -73.23662	Invertebrate	Animal	Multiple individuals
1010	Bird	No	Redwing blackbird Agelaius phoeniceus	RBP 27-28 42.40690, -73.23662	Bird	Animal	Individual
1010	Fish	No	Minnow Small fish	RBP 27-28 42.40690, -73.23662	Fish	Animal	Multiple individuals
1010	Reptile	No	Painted turtle Chrysemys picta	RBP 27-28 42.40690, -73.23662	Reptile	Animal	Individual
1010	Bird	No	Great blue heron Ardea herodias	RBP 27-28 42.40690, -73.23662	Bird	Track	

### **WILDLIFE FIELD OBSERVATIONS**

Date:08/25/2022 Time:1115

Weather: Sunny

Team member(s): SM, KVN, TW, NC

<u>Time</u>	Observation <sup>1</sup>	<u>Data</u>	Species Observed <sup>3</sup>	Location <sup>4</sup>	<u>Faunal</u>	<u>Observation</u>	Behavior/Condition Description/Habitat Type <sup>6</sup>
		Collected:2			<u>Type⁵</u>	<u>Type<sup>6</sup></u>	
1115	Invertebrate	No	Caddisfly	RBP 29-31	Invertebrate	Animal	Exoskeleton
			Trichoptera	42.40734,			
				-73.23855			
1115	Invertebrate	No	<u>Honeybee</u>	RBP 29-31	Invertebrate	Animal	Multiple individuals
			<u>Apis mellifera</u>	42.40734,			
				-73.23855			
1115	Invertebrate	No	Dragonfly	RBP 29-31	Invertebrate	Animal	Individual
			Anisoptera	42.40734,			
				-73.23855			
1115	Invertebrate	No	Whirligig beetles	RBP 29-31	Invertebrate	Animal	Multiple individuals
			Gyrinidae	42.40734,			
				-73.23855			

### **WILDLIFE FIELD OBSERVATIONS**

Date:08/25/2022

Time:1330 Weather: Sunny

Team member(s): SM, KVN, TW, NC

<u>Time</u>	Observation <sup>1</sup>	Data Collected: <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	Faunal Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
1330	Bird	No	Belted kingfisher Megaceryle alcyon	RBP 32 42.40581, -73.23732	Bird	Animal	Individual
1330	Invertebrate	No	Dragonfly Anisoptera	RBP 32 42.40581, -73.23732	Invertebrate	Animal	Multiple individuals
1330	Amphibian	No	Green tree frog Hyla cinerea	RBP 32 42.40581, -73.23732	Amphibian	Animal	Individual
1330	Invertebrate	No	Common water strider Aquarius remigis	RBP 32 42.40581, -73.23732	Invertebrate	Animal	Multiple individuals
1330	Bird	No	Gray Catbird  Dumetella carolinensis	RBP 32 42.40581, -73.23732	Bird	Animal	Individual
1330	Small mammal	No	American Beaver Castor canadensis	RBP 32 42.40581, -73.23732	Small mammal	Sign	

### **WILDLIFE FIELD OBSERVATIONS**

Date:08/25/2022 Time:1341

Weather: Sunny

Team member(s): SM, KVN, TW, NC

Time	Observation <sup>1</sup>	<u>Data</u>	Species Observed <sup>3</sup>	Location <sup>4</sup>	<u>Faunal</u>	Observation	Behavior/Condition Description/Habitat Type <sup>6</sup>
		Collected:2			<u>Type⁵</u>	Type <sup>6</sup>	
1341	Bird	No	Wood duck Aix sponsa	RBP 33 42.40385, -73.23812	Bird	Animal	Individual
1341	Amphibian	No	Pickerel Frog Lithobates palustris	RBP 33 42.40385, -73.23812	Amphibian	Animal	Individual
1341	Small mammal	No	American Beaver Castor canadensis	RBP 33 42.40385, -73.23812	Small mammal	Sign	
1341	Bird	No	Belted kingfisher Megaceryle alcyon	RBP 33 42.40385, -73.23812	Bird	Animal	Individual



# A-2 Benthic Macroinvertebrate Results, Field Data Sheets and Notes

## Appendix A-2- Reach 5A Macroinvertebrate Sampling Full Identification List

Dhydrige	Class	Ordor	Camily	Final ID	4			orth to South)			TOTAL
Phylum	Class	Order	Family	Final ID	1	2	3	4	5	6	TOTAL
Annelida	Clitellata	Lumbriculida	Lumbriculidae	Lumbriculidae	<del>.</del>	1	•		•	•	1
		Tubificida	Naididae	Aulodrilus pluriseta					3		3
				Limnodrilus hoffmeisteri			2				2
				Nais bretscheri			1				1
				Tubificoid Naididae w capilliform setae				2	6		8
			-	Tubificoid Naididae w/out capilliform setae	<del>.</del>		1	3	20	4	28
rthropoda	Arachnida	Trombidiformes	Hygrobatidae	Hygrobates sp.	. 1		•	•	•	•	1
	Insecta	Coleoptera	Elmidae	Ancyronyx variegatus				2	1	1	4
				Dubiraphia sp.				1		1	2
				Macronychus glabratus			11	16	4	2	33
				Optioservus elegans group				1			1
				Optioservus fastiditus group			1				1
				Stenelmis crenata	1			3	1		5
				Stenelmis sp.			1	2			3
			Gyrinidae	Dineutus sp.				1		0	1
			Hydrophilidae	Berosus sp.				2			2
			Psephenidae	Psephenus herricki	13		4				17
		Diptera	Ceratopogonidae	Ceratopogoninae			•	•	2	1	3
		·	Chironomidae	Ablabesmyia sp.		1	1	5	3	1	11
				Chironomus sp.	1	2	5	2	5		15
				Cladotanytarsus sp.				1		2	3
				Cricotopus bicinctus	1	1				3	5
				Cricotopus sp.	•	3	1	1		3	8
				Cricotopus/Orthocladius sp.			·	2			2
				Cryptochironomus sp.			1	1			2
				Dicrotendipes sp.			·	1	2		3
				Eukiefferiella sp.				•	1		1
				Kribiodorum perpulchrum				1	·		1
				Microtendipes pedellus group			2	1	2	1	6
							2	1	1	1	11
				Nanocladius sp.			3	4	ļ	I	1
				Nilotanypus fimbriatus			1				2
				Orthocladius sp.			4				1
				Parametriocnemus sp.			1				2
				Paratendipes sp.			_		2		2
				Pentaneura sp.			1		1		2
				Pentaneurini		_		_	_	1	1
				Phaenopsectra obedians group		1		1	1		3
				Polypedilum flavum	1	3		4	4	10	22
				Polypedilum halterale group				1		2	3
				Polypedilum illinoense group		1		1	4	2	8
				Polypedilum laetum		1					1

Station # (North to South)

							Station # (No	orui to Soutil)			
Class	ss	Order	Family	Final ID	1	2	3	4	5	6	TOTAL
				Polypedilum scalaenum group	1				2		3
				Potthastia gaedii group					1		1
				Procladius sp.				2	7		9
				Rheocricotopus sp.		1	10	1	4	6	22
				Rheotanytarsus exiguus group	2		6	5	10	19	42
				Rheotanytarsus sp.			1			1	2
				Saetheria tylus				1			1
				Stenochironomus sp.			1				1
				Tanypodinae			1	4			5
				Tanytarsus sp.		7	11	90	36	28	172
				Thienemanniella sp.						2	2
				Thienemannimyia group	1	2	9	33	21	21	87
				Tvetenia tshernovskii			3				3
			Empididae	Hemerodromia sp.		1	1	4	2	1	9
			Limoniidae	Antocha sp.			1				1
			Simuliidae	Simulium sp.					17	130	147
			Tipulidae	Tipula sp.			1		1		2
		Ephemeroptera	Baetidae	Baetidae		1		1	1		3
		r		Baetis flavistriga complex		3	8	1			12
				Baetis intercalaris	3	2	1			1	7
				Baetis sp.	-	_	1			·	1
				Iswaeon anoka	2	38	19	4	4	4	71
				Labiobaetis sp.	_	00	26	•	6	7	39
				Plauditus punctiventris		14	20		1	,	15
			Baetiscidae	Baetisca sp.		14			3	2	5
			Heptageniidae	Maccaffertium modestum	5	2	5	1	3	2	13
			Пертаденниае	Maccaffertium sp.	3	2	4	3		2	9
					2		0	3	19	2	32
				Stenacron interpunctatum Stenacron sp.	2		O	1	19		2
			loonyohiidoo		2	0	2	1	1		19
			Isonychiidae	Isonychia sp.	2	9	3	'	4		1
			Leptophlebiidae	Leptophlebia sp.			1	0	0		13
		Haminton	Carividae	Leptophlebiidae			1	9	3		4
		Hemiptera	Corixidae	Corixidae				4			
		Megaloptera	Sialidae	Sialis sp.					1		1
		Odonata	Aeshnidae	Basiaeschna janata				1			1
				Boyeria vinosa				2			2
			Coenagrionidae	Ischnura sp.				1			1
			Gomphidae	Gomphidae	2						2
				Hylogomphus sp.					1		1
				Ophiogomphus sp.		1	2				3
				Phanogomphus sp.			2				2
				Stylurus scudderi					2		2
				Stylurus spiniceps			1		1		2

Station #	(North to South)	1
-----------	------------------	---


								orth to South)			
Phylum	Class	Order	Family	Final ID	1	2	3	4	5	6	TOTAL
		Plecoptera	Perlidae	Paragnetina media				1			1
				Perlesta sp.				1			1
		Trichoptera	Brachycentridae	Brachycentrus numerosus				9	2	3	14
			Hydropsychidae	Cheumatopsyche sp.	14	6	49	59	39	44	211
				Hydropsyche betteni	85	16	89	4	11	11	216
				Hydropsyche bronta	49	10	4		3		66
				Hydropsyche morosa	21		7				28
				Hydropsyche morosa group			2		1		3
				Hydropsyche sparna	28	1		1	5	1	36
				Hydropsychidae	1			1	1		3
			Hydroptilidae	Hydroptila sp.		3	1	2			6
				Hydroptilidae		2		2		1	5
				Leucotrichia pictipes	1						1
			Limnephilidae	Pycnopsyche sp.			1				1
			Philopotamidae	Chimarra aterrima		1					1
				Chimarra obscura	2						2
			Polycentropodidae	Polycentropodidae				2			2
				Polycentropus sensu lato complex				2			2
			Psychomyiidae	Lype diversa			2	3			5
			Thremmatidae	Neophylax sp.	1		1				2
	Malocostraca	Amphipoda	Crangonyctidae	Crangonyx sp.				1	4		5
			Hyalellidae	Hyalella sp.			1				1
		Decapoda	Cambaridae	Faxonius sp.		2	1	1	4	0	8
		Isopoda	Asellidae	Caecidotea racovitzai racovitzai				1	11		12
				Caecidotea sp.					10	1	11
Mollusca	Bivalvia	Sphaeriida	Sphaeriidae	Pisidium sp.					2		2
		·	•	Sphaeriidae					1		1
				Sphaerium sp.				1	1		2
		Unionoida	Unionidae	Elliptio complanata			1				1
	Gastropoda	Basommatophora	Lymnaeidae	Lymnaeidae			1				1
	•	,	Physidae	Physella sp.					3		3
			Planorbidae	Ferrissia sp.	2	1	4	2	2	1	12
Nematoda				Nematoda		2		2			5
Plathyhelminthes	Trepaxonemata			Trepaxonemata	<u> </u>						1
Grand Total				F - December 2	243	139	332	327	311	321	1673

#### BENTHIC MACROINVERTEBRATE FIELD DATA SHEET

STREAM NAME		LOCAT	LOCATION										
STATION #	RIVERMI	LE	STREA	STREAM CLASS									
LAT	LONG		_ RIVER	BASIN									
STORET#			AGENC	ĽΥ									
INVESTIGATORS						LOT	NUMBER						
FORM COMPLETED	) BY		DATE TIME	(A)	м) рм	REAS	SON FOR SURVEY						
HABITAT TYPES	☑ Cobble	% \(\overline{\infty}	e of each hab		etated B		% \( \times \text{Sand}\)						
SAMPLE COLLECTION	How were t	the samples	collected? f jabs/kicks ta	☑ wading	Other _ fabitat t	from ban	k 📮 from bo	– at					
	☑ Cobble ☑ Submero	⊵ ed Macroph	snagsvtes	□ Veg	etated B Other (	sanks							
GENERAL COMMENTS													
QUALITATIVE I Indicate estimated Dominant		$:  0 = \mathbf{A}\mathbf{b}\mathbf{s}$	sent/Not Ob	served, 1 =		2 = C	ommon, 3= Abur						
Periphyton			2 3 4		imes			_		2			
Filamentous Algae		•	2 3 4			vertebr	ates	0	1		3		
Macrophytes		0 (1	2 3 4	E					$\sim$				
				1.	ish				(1)	2	3	4	
FIELD OBSERVA Indicate estimated		: 0 = Ab organi	sent/Not Ol sms), 3= Ab	bserved, 1 =	= Rare	(1-3 or	rganisms), 2 = Co , 4 = Dominant (>	0 ommoi	n (3	.9			
		: 0 = Ab organi	sent/Not Ol sms), 3= Ab	bserved, 1 =	= Rare 0 orga	(1-3 or	rganisms), 2 = Co , 4 = Dominant (x Chironomidae	0 ommoi	n (3	.9			
Indicate estimated	0 1 2 0 1 2	3 4 A 3 4 Z	sent/Not Ol	bserved, 1 = oundant (>1	= Rare 0 orga	3 4 3 4	rganisms), 2 = Co	0 ommor >50 or	n (3 rgar	- <b>9</b> nism 2 2	ns)	4	
Porifera Hydrozoa Platyhelminthes	0 1 2 0 1 2 0 1 2 0 1 2	3 4 A 3 4 Z 3 4 H	sent/Not Ol sms), 3= Ab anisoptera dygoptera demiptera	bserved, 1 = oundant (>1 0 1 0 1 0 1	= Rare 0 orga 2 2 2	(1-3 or nisms)	rganisms), 2 = Co , 4 = Dominant (x Chironomidae Ephemeroptera Trichoptera	0 0 0 0 0 0	n (3 rgar	2 2 2	3 3 3	4 4 4	
Porifera Hydrozoa Platyhelminthes Turbellaria	0 1 2 0 1 2	3 4 A 3 4 Z 3 4 H	ssent/Not Ol sms), 3= Ab anisoptera	bserved, 1 = oundant (>1 0 1 0 1	= Rare 0 orga 2 2 2	3 4 3 4	rganisms), 2 = Co , 4 = Dominant (> Chironomidae Ephemeroptera	0 0 0 0 0	n (3-rgar	- <b>9</b> nism 2 2	3 3	4 4	
Porifera Hydrozoa Platyhelminthes Turbellaria Hirudinea Oligochaeta Isopoda	0 1 2 0 1 2 0 1 2 0 1 2 10 1 2	3 4 A 3 4 Z 3 4 H 3 4 C	Anisoptera Evygoptera Lemiptera Coleoptera ONS WER	0 1 0 1 0 1 0 1	Rare 0 orga	3 4 3 4 3 4 3 4 3 4	rganisms), 2 = Co , 4 = Dominant (x Chironomidae Ephemeroptera Trichoptera	0 50 on 0 0 0	n (3-rgar	2 2 2	3 3 3	4 4 4	
Porifera Hydrozoa Platyhelminthes Turbellaria Hirudinea Oligochaeta Isopoda Amphipoda	0 1 2 0 1 2 0 1 2 1 2 1 2 1 2 1 2 1 2 1	3 4 A 3 4 Z 3 4 H 3 4 C  DSERVATI	anisoptera (ygoptera Lemiptera Coleoptera ONS WERG	bserved, 1 = bundant (>10	Rare 0 orga	3 4 3 4 3 4 3 4 3 4 3 4 3 4 3 4 3 4 3 4	rganisms), 2 = Co , 4 = Dominant (2 Chironomidae Ephemeroptera Trichoptera Other	0 50 on 0 0 0	n (3-rgar	2 2 2	3 3 3	4 4 4	
Porifera Hydrozoa Platyhelminthes Turbellaria Hirudinea Oligochaeta Isopoda Amphipoda Decapoda	0 1 2 0 1 2 0 1 2 0 1 2 0 1 2 lo field ok	3 4 A 3 4 Z 3 4 B 3 4 C 3 4 T 3 4 E	sent/Not Olsms), 3= Alsonisoptera Elemiptera Coleoptera Coleoptera Cipulidae Cipulidae Compididae	0 1 0 1 0 1 0 1 0 1 0 1 0 1 0 1 0 1 0 1	= Rare 0 orga	3 4 3 4 3 4 3 4 3 4 3 4 3 4 3 4 3 4 3 4	rganisms), 2 = Co , 4 = Dominant (2 Chironomidae Ephemeroptera Trichoptera Other	0 50 on 0 0 0	n (3-rgar	2 2 2	3 3 3	4 4 4	
Porifera Hydrozoa Platyhelminthes Turbellaria Hirudinea Oligochaeta Isopoda Amphipoda	0 1 2 0 1 2 0 1 2 1 2 1 2 1 2 1 2 1 2 1	3 4 A 3 4 C 3 4 C 3 4 C 3 4 C 3 4 C 3 4 C 3 4 C 3 4 C 3 4 C 3 4 C 3 4 C 3 4 C 3 4 C 3 4 C	anisoptera (ygoptera Lemiptera Coleoptera ONS WERG	bserved, 1 = pundant (>10	= Rare 0 orga	3 4 3 4 3 4 3 4 3 4 3 4 3 4 3 4 3 4 3 4	rganisms), 2 = Co , 4 = Dominant (2 Chironomidae Ephemeroptera Trichoptera Other	0 50 on 0 0 0	n (3-rgar	2 2 2	3 3 3	4 4 4	

#### BENTHIC MACROINVERTEBRATE FIELD DATA SHEET

	ousatonic	LOCATION	LOCATION RBP 10-11									
STATION #_1	RIVERMILE RBP 1,2	STREAM CL	LASS									
LAT 42.43033	LONG 73.24048	RIVER BASI	IN Housatonic									
STORET#		AGENCY [	AECOM / EPA									
INVESTIGATORS T	W, NC			LOT	NUMBER R5A-MI-S2	2 (2 Bot	tles)					
FORM COMPLETED	BY TW	DATE 08/26	6/22	REAS	ON FOR SURVEY							
	1 77	TIME 1030	AM PM		ch 5A BERA							
	1											
HABITAT TYPES	Indicate the percent				<b>7</b> 0/ <b>8</b> 0 1							
	<ul><li> ☑ Cobble 5</li></ul>	☑ Snags 15 %  ohytes %	☐ Vegetated Ba☐ Other (		% ⊠ Sand <sub>.∞</sub>	%						
CAMDI E	Gear used 🛛 D-fra		Other C			1						
SAMPLE COLLECTION	Gear used 🚨 D-irai	me	☐ Other			_						
	How were the sampl	es collected?	wading	rom ban	k	at						
	Indicate the number		in each habitat ty	pe.								
	☑ Cobble ☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐	☑ Snags 5	☐ Vegetated Ba		☐ ☑ Sand 15							
	a submerged waerop	mytes <u>.                                    </u>	G Other ([		//				_			
GENERAL COMMENTS												
	LISTING OF AQUA											
Indicate estimated Dominant	1 abundance: 0 = A	bsent/Not Observ	yed, 1 = Rare,	2 = C	ommon, 3= Abun	dant,	4 =					
Dominant												
Periphyton		1 2 3 4	Slimes				1 2	2				
Filamentous Algae	•	1 2 3 1				(0)	1 /	- 3	4			
I mame mous i mgae	0	1 2 3 4		vertebr	ates	0			4			
Macrophytes	0	1 2 3 4 1 2 3 4	Macroinv	vertebr	ates	0 (	① 2	3	4 4 4			
Macrophytes				vertebr	ates	0 (		3	4			
	© 0 ATIONS OF MACR	1 2 3 4	Macroinv	vertebr	ates	0 (	① 2	3	4			
FIELD OBSERVA	ATIONS OF MACR	1 2 3 4  COBENTHOS Absent/Not Obser	Macroinv Fish ved, 1 = Rare	(1-3 oı	ganisms), 2 = Co	0 ( 0	1) 2 (1) 2	3 3	4			
FIELD OBSERVA	ATIONS OF MACR	1 2 3 4  COBENTHOS	Macroinv Fish ved, 1 = Rare	(1-3 oı	ganisms), 2 = Co	0 ( 0	1) 2 (1) 2	3 3	4			
FIELD OBSERVA Indicate estimated	ATIONS OF MACR d abundance: 0 = A orga	1 2 3 4  COBENTHOS  Absent/Not Obsernisms), 3= Abund	Macroinv Fish ved, 1 = Rare lant (>10 organ	(1-3 or	rganisms), 2 = Co 4 = Dominant (>	0 ( 0 mmon 50 or	(3-9 ganisi	3 3 ms)	4 4			
FIELD OBSERVA Indicate estimated	ATIONS OF MACR labundance: 0 = A orga	2 3 4  COBENTHOS  Absent/Not Obser nisms), 3= Abund  Anisoptera	Macroinv Fish  ved, 1 = Rare elant (>10 organ  0 1 2 3	(1-3 or nisms),	rganisms), 2 = Co 4 = Dominant (> Chironomidae	0 (0 0 mmon 50 or;	(3-9 ganisi	3 3 ms)	4 4			
FIELD OBSERVA Indicate estimated Porifera Hydrozoa	ATIONS OF MACR dabundance: 0 = A orga	2 3 4  COBENTHOS  Absent/Not Obser nisms), 3= Abund  Anisoptera  Zygoptera	Macroinv Fish  ved, 1 = Rare elant (>10 organ  0 1 2 3 0 1 2 3	(1-3 or nisms),	rganisms), 2 = Co 4 = Dominant (> Chironomidae Ephemeroptera	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	(3-9 ganisi 1 2 1 2	3 3 ms)	4 4 4			
FIELD OBSERVA Indicate estimated Porifera Hydrozoa Platyhelminthes	0 1 2 3 4 0 1 2 3 4 0 1 2 3 4	1 2 3 4  COBENTHOS Absent/Not Obsernisms), 3= Abund  Anisoptera Zygoptera Hemiptera	Macroinv Fish  ved, 1 = Rare of lant (>10 organ  0 1 2 3 0 1 2 3 0 1 2 3	(1-3 or nisms),	rganisms), 2 = Co 4 = Dominant (> Chironomidae Ephemeroptera Trichoptera	0 (0 0 mmon 50 or;	(3-9 ganisi  1 2 1 2 1 2	3 3 ms)	4 4 4 4			
Porifera Hydrozoa Platyhelminthes Turbellaria	ATIONS OF MACR dabundance: 0 = A orga	Anisoptera Zygoptera Hemiptera Coleoptera	Macroinv Fish  ved, 1 = Rare ( lant (>10 organ  0 1 2 3  0 1 2 3  0 1 2 3  0 1 2 3	(1-3 or nisms),	rganisms), 2 = Co 4 = Dominant (> Chironomidae Ephemeroptera	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	(3-9 ganisi 1 2 1 2	3 3 ms)	4 4 4			
Porifera Hydrozoa Platyhelminthes Turbellaria Hirudinea	0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4	Anisoptera Zygoptera Hemiptera Coleoptera Lepidoptera	Macroinv Fish  ved, 1 = Rare of lant (>10 organ  0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3	(1-3 or nisms),	rganisms), 2 = Co 4 = Dominant (>  Chironomidae Ephemeroptera Trichoptera Other	0 (0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	(3-9 ganisi  1 2 1 2 1 2	3 3 ms)	4 4 4 4			
Porifera Hydrozoa Platyhelminthes Turbellaria Hirudinea	0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4	Anisoptera Zygoptera Hemiptera Coleoptera Lepidoptera	Macroinv Fish  ved, 1 = Rare of lant (>10 organ  0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3	(1-3 or nisms),	rganisms), 2 = Co 4 = Dominant (>  Chironomidae Ephemeroptera Trichoptera Other	0 (0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	(3-9 ganisi  1 2 1 2 1 2	3 3 ms)	4 4 4 4			
Porifera Hydrozoa Platyhelminthes Turbellaria Hirudinea Oligochaeta	0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4	Anisoptera Zygoptera Hemiptera Coleoptera Lepidoptera	Macroiny Fish  ved, 1 = Rare elant (>10 organ  0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3 ken- pull fr	(1-3 or nisms),	rganisms), 2 = Co 4 = Dominant (>  Chironomidae Ephemeroptera Trichoptera Other	0 (0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	(3-9 ganisi  1 2 1 2 1 2	3 3 ms)	4 4 4 4			
Porifera Hydrozoa Platyhelminthes Turbellaria Hirudinea Oligochaeta Isopoda Amphipoda Decapoda	0 1 2 3 4 0 1 2	Anisoptera Zygoptera Hemiptera Coleoptera Lepidoptera Ations Were ta	Macroiny Fish  ved, 1 = Rare ( lant (>10 organ  0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3 ken- pull fr	(1-3 or nisms), 3 4 3 4 3 4 3 4 7 rom	rganisms), 2 = Co 4 = Dominant (>  Chironomidae Ephemeroptera Trichoptera Other	0 (0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	(3-9 ganisi  1 2 1 2 1 2	3 3 ms)	4 4 4 4			
Porifera Hydrozoa Platyhelminthes Turbellaria Hirudinea Oligochaeta Isopoda Amphipoda Decapoda Gastropoda	0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4	Anisoptera Zygoptera Hemiptera Coleoptera Lepidoptera tions were ta	Macroiny Fish  ved, 1 = Rare elant (>10 organ  0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3 Aken- pull fr	(1-3 or nisms),  3  4  3  4  3  4  4  3  4  4  3  4  4  3  4  4	rganisms), 2 = Co 4 = Dominant (>  Chironomidae Ephemeroptera Trichoptera Other	0 (0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	(3-9 ganisi  1 2 1 2 1 2	3 3 ms)	4 4 4 4			
Porifera Hydrozoa Platyhelminthes Turbellaria Hirudinea Oligochaeta Isopoda Amphipoda Decapoda	0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4 0 1 2 3 4	Anisoptera Zygoptera Hemiptera Coleoptera Lepidoptera Ations Were ta	Macroiny Fish  ved, 1 = Rare elant (>10 organ  0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3 0 1 2 3	(1-3 or nisms),  3 4 3 4 3 4 3 4 3 4 3 4 3 4 3 4	rganisms), 2 = Co 4 = Dominant (>  Chironomidae Ephemeroptera Trichoptera Other	0 (0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	(3-9 ganisi  1 2 1 2 1 2	3 3 ms)	4 4 4 4			



OF reach of Macrolnusmy Data Sample ? RSA-MI-SZ (25 ample) Sample I R.SA-MI-SI (2 Somple) 5 tary station 46+00 DS@ 10:30 Starts starion 3+00 DS 8140 Samples TW, NC Samplers NC, TW tabital - 00%, colbe, 30% Sand, Ot. Veg banks Habitas - 5% coople, 80% sond, O'll veg banks 15%. 5mays, 0% sub Mac 10%. snags, 5% sub mal Jabs - I cobble, 15 Sond, 5 snags samples connected wading w DNet samples collected wading w/ Dhet Jabs: 5 in sand, 10 in colle, 3 in snagg, 2 La protection de la constante in 54 mac Abundance: Agranic Biota Abundance: Agresic Biota Periphyton: I periphyton; o Fil. Algae: O Fil. Algae: 0 Macrophytes: 1 Macrophyty:0 Slimes: 0 Shimes: 0 Macro Invents. 3 Macro mets:1 Fish: 1 Fish: 1 Field Observations of macrobinens TBD Field Obs of Macrobenthas TBD based on lab results based on lab results

#### BENTHIC MACROINVERTEBRATE FIELD DATA SHEET

STREAM CLASS REVENUE STORES RIVER BASIN MOUSE TORE AGENCY ACCOUNTING STORET# AGENCY ACCOUNTING THE RESON FOR SURVEY REASON FOR SURVEY REAS	STREAM NAME	BUSLIONIE	LOCATION PBP	14
AGENCY   A			STREAM CLASS Per	ind
DOT NUMBER RSA - NI - S3 2 be   FORM COMPLETED BY   N   S   DATE   S   2   Z   Z   REASON FOR SURVEY   C   C   C   C   C   C   C   C   C	LAT SE REW	LONG	RIVER BASIN Hous	Line
DATE S   2   2   2   2   3   4   5   5   5   5   5   5   5   5   5	STORET#		AGENCY A	/epa
DATE S   2   2   2   2   3   4   5   5   5   5   5   5   5   5   5	INVESTIGATORS 1	EN SM	140	LOT NUMBER REA-NI-SE DI
Cobble   %   Sangs   %   Vegetated Banks   %   Sand   5 %     Submerged Macrophytes   6 %   Other   Submerged Macrophytes   Other   Sangs   Sand   6 %   Sand   6 %   Sand   6 %   Sand   6 %   Submerged Macrophytes   Other   Other   Submerged Macrophytes   Other   Ot				REASON FOR SURVEY
Gear used Doframe kick-net Other How were the samples collected? Wading from bank from boat  Indicate the number of jabs/kicks taken in each habitat type.  Gobble Snags Divegetated Banks   Grand Ban	HABITAT TYPES	Cobble_15_%	Snags 7 % Uvegetated I	Banks 5 % D Sand 45 %
QUALITATIVE LISTING OF AQUATIC BIOTA Indicate estimated abundance: 0 = Absent/Not Observed, 1 = Rare, 2 = Common, 3 = Abundant, 4 =  Periphyton  Periphyton  Olivinary  Olivinar	SAMPLE COLLECTION	How were the samples of indicate the number o	ollected? Swading on abs/kicks taken in each habitat to Snags	from bank
Indicate estimated abundance: 0 = Absent/Not Observed, 1 = Rare, 2 = Common, 3 = Abundant, 4 = Dominant  Periphyton 0 1 2 3 4 Slimes 0 1 2 3 4  Filamentous Algae 0 1 2 3 4 Macroinvertebrates 0 1 2 3 4  Macrophytes 0 1 2 3 4 Fish 0 1 2 3 4  FIELD OBSERVATIONS OF MACROBENTHOS Indicate estimated abundance: 0 = Absent/Not Observed, 1 = Rare (1-3 organisms), 2 = Common (3-9 organisms), 3 = Abundant (>10 organisms), 4 = Dominant (>50 organisms)	GENERAL COMMENTS			ween Sudfarel IsiH
Indicate estimated abundance: 0 = Absent/Not Observed, 1 = Rare (1-3 organisms), 2 = Common (3-9 organisms), 3 = Abundant (>10 organisms), 4 = Dominant (>50 organisms)	Indicate estimated Dominant Periphyton Filamentous Algae	abundance: 0 = Abse	2 3 4 Slimes 2 3 4 Macroin	@1 2 3
	Macrophytec	0 1	2 3 4 Fish	0 1 2 3
Platyhelminthes (0) 1 2 3 4 Hemiptera 0 1 2 3 4 Trichoptera 0 1 2 (3) 4	FIELD OBSERVA Indicate estimated	0 1 2 3 4 And 1 2 3 4 Zyg	ent/Not Observed, 1 = Rare ns), 3= Abundant (>10 orga isoptera 0 1 2 goptera 0 1 2	3 4 Chironomidae 0 1 2 3 Ephemeroptera 0 1 2 3

Porifera	0 1	2	3	4	Anisoptera	0 (1)	2	3	4	Chironomidae	6)	1	2 3	4
Hydrozoa	01	2	3	4	Zygoptera	04	21	3)	4	Ephemeroptera	0	1 (	Ø (	0 4
Platyhelminthes"	(0)1	2	3	4	Hemiptera	0 1	(2)	3	4	Trichoptera	0	1	50	0 4
Turbellaria	(0) 1	2	3	4	Coleoptera	0 1	21	3)	4	Other	0	1	2 3	4
Hirudinea	(0)_1	2	3	4	Lepidoptera	(0)1	2	3	4					
Oligochaeta	Service of the servic	2	3	4	Sialidae	0 1	(2)	3	4					
Isopoda	0 Q	2	3	4	Corydalidae	0 1	(2)	3	4					
Amphipoda	0 D	2	3	4	Tipulidae	0 1	2	3	4					
Decapoda	00	72	3	4	Empididae	(0 1	2	3	4					is
Gastropoda	0 (1)	2	3	4	Simuliidae	@ 1	2	3	4					V.
Bivalvia	0 0	2	3	4	Tabinidae	@ 1	2	3	4					
					Culcidae	@ 1	2	3	4					1

RBP BONTHIC INJECTS 8/31/22 N42°25.70 W75 H.171 98100 Sundy J Field Colost 10/100 N 4225.222 W 73/4,1491 #= CWD 0

#### BENTHIC MACROINVERTEBRATE FIELD DATA SHEET

	RIVERMILE COP ZIZZ	STREAM CLASS	→ 173+ 50	
		Tanama a vane () 1	. 0	
	- RONG	RIVER BASIN Hausata	and Affirmation and Affirmatio	
STORET#		AGENCY Account	-c/A	M: 2 . 15 1
INVESTIGATORS	SM RVN		LOT NUMBER RSA -	MI-54 184
FORM COMPLETED SIN KU		TIME 11:00 AP PM	REASON FOR SURVEY	R5A-11-S
HABITAT TYPES	Indicate the percentage of Coubble 8 % US	of each habitat type present Snags 5 % 2 Vegetated I es 1 % 2 Other (	Banks I Sand C	0 % pare/(box)
SAMPLE COLLECTION	☐ Cobble ☐ ☐ S ☐ Submerged Macrophyte	abs/kicks taken in each habitat to Snags Vegetated I	Banks   Sand	at 2 th gravel 3
GENERAL COMMENTS	20.3° C.Wa			
	LISTING OF AQUATION Absent	C BIOTA nt/Not Observed, 1 = Rare,	2 = Common, 3= Abun	dant, 4 =
Dominant	0 17	(2) 3 4 Slimes		0 (1) 2 3 4
Periphyton	0 17		vertebrates	
Dominant Periphyton Filamentous Algae Macrophytes	0 17		evertebrates	
Periphyton Filamentous Algae Macrophytes FIELD OBSERV Indicate estimated Porifera Hydrozoa	O 1 (0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	2 3 4 Macroin 2 3 4 Fish  ENTHOS ent/Not Observed, 1 = Rare ns), 3 = Abundant (>10 organisoptera goptera 0 1 2 2 2	(1-3 organisms), 2 = Conisms), 4 = Dominant (>  3  4   Chironomidae 3  4   Ephemeroptera	0 1 ② 3 4 0 1 ② 3 4 mmon (3-9 50 organisms)
Periphyton Filamentous Algae Macrophytes FIELD OBSERV Indicate estimated Porifera Hydrozoa Platyhelminthes	O 1 (0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	2 3 4 Macroin 2 3 4 Fish  ENTHOS ent/Not Observed, 1 = Rare ns), 3= Abundant (>10 orga  isoptera 0 1 2  goptera 0 1 2	(1-3 organisms), 2 = Conisms), 4 = Dominant (>  Chironomidae Ephemeroptera Trichoptera	0 1 2 3 4 0 1 2 3 4 mmon (3-9 50 organisms)  0 1 2 3 4 0 1 2 3 4 0 1 2 3 4
Periphyton Filamentous Algae Macrophytes FIELD OBSERV Indicate estimated Porifera Hydrozoa Platyhelminthes Furbellaria	0 1 0 0 1 0 0 1 0 0 1 0 0 1 0 0 0 0 0 0	2 3 4 Macroin 2 3 4 Fish  ENTHOS ent/Not Observed, 1 = Rare ns), 3= Abundant (>10 orga  isoptera 0 1 2 miptera 0 1 2 miptera 0 1 2 eoptera 0 1 2	(1-3 organisms), 2 = Conisms), 4 = Dominant (>  3     4	0 1 2 3 4 0 1 2 3 4 mmon (3-9 50 organisms)
Periphyton Filamentous Algae Macrophytes FIELD OBSERV Indicate estimated Porifera Hydrozoa Platyhelminthes Furbellaria Hirudinea	0 1 (0 0 1) 0 1) 0 1) 0 1) 0 1) 0 1) 0 1 2 3 4 Ani 0 1 2 3 4 Zyg 0 1 2 3 4 Her 0 1 2 3 4 Col 0 1 2 3 4 Lep	2 3 4 Macroin 2 3 4 Fish  ENTHOS ent/Not Observed, 1 = Rare ns), 3= Abundant (>10 orga  isoptera 0 1 2 miptera 0 1 2 miptera 0 1 2 deoptera 0 1 2 miptera 0 1 2	(1-3 organisms), 2 = Conisms), 4 = Dominant (>  Chironomidae Ephemeroptera Trichoptera	0 1 2 3 4 0 1 2 3 4 mmon (3-9 -50 organisms)
Periphyton Filamentous Algae Macrophytes FIELD OBSERV Indicate estimated Porifera Hydrozoa Platyhelminthes Furbellaria Hirudinea Dligochaeta	0 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	2 3 4 Macroin 2 3 4 Fish  ENTHOS ent/Not Observed, 1 = Rare ns), 3 = Abundant (>10 orga  isoptera 0 1 2 miptera 0 1 2 deoptera 0 1 2	(1-3 organisms), 2 = Conisms), 4 = Dominant (>  Chironomidae Ephemeroptera Trichoptera Other  Other	0 1 2 3 4 0 1 2 3 4 mmon (3-9 -50 organisms)
Periphyton Filamentous Algae Macrophytes FIELD OBSERV Indicate estimated Porifera Hydrozoa Platyhelminthes	0 1 0 0 1 0 0 1 0 0 1 0 0 1 0 0 0 0 0 0	2 3 4 Macroin 2 3 4 Fish  ENTHOS ent/Not Observed, 1 = Rare ns), 3= Abundant (>10 orga  isoptera 0 1 2 miptera 0 1 2 miptera 0 1 2 deoptera 0 1 2 miptera 0 1 2	(1-3 organisms), 2 = Conisms), 4 = Dominant (>  3     4	0 1 2 3 4 0 1 2 3 4 mmon (3-9 -50 organisms)

Simuliidae

Tabinidae

3

2 3

3

Gastropoda

Bivalvia

MACROINCE + STATION # 4 + Diplomber SB6-51+55 170+00 170+50A 42,4/12/187 -73°,233C150 Algoe on surfee of Sand in many locations 172+00 FOROSTOD BANK (APPROK.) 800c 42010296°N 73.23470808

### BENTHIC MACROINVERTEBRATE FIELD DATA SHEET

STREAM NAME	love ATON = P.	LOCATI	ON 281	7	8	1 STATON	213+00	TO.
	RIVERMILE CA Z	STREAM	1 CLASS	-				7
LAT See Re	~~ EONG @	RIVER	BASIN LL	151	70-	ve	24	
STORET#		AGENC				7	eric LA	
INVESTIGATORS	KIN SM	9		T	LOT	NUMBER PSA		5
FORM COMPLETE	DBY KN	DATE	9(1/22 1600 AM (		RE/	ASON FOR SURVEY	_	7
HABITAT TYPES	Indicate the percentag  Cobble % Submerged Macrophy	Snags \ O %	tat type present		nk42	>_% □ Sanet		ty /
SAMPLE COLLECTION	☐ Submerged Macrophy	rollected?	□ Vegetate □ Oth	of from the front front front from the front front front front from the front fro	e. iks_	Sand_	15	V
GENERAL COMMENTS	Perm HA Before Bottom Spondic	Rung	Rua Brute	( -	516	1 1	sols Sand) -	المنهاد المنهاد
Indicate estimated Dominant	LISTING OF AQUAT I abundance: 0 = Abs	TC BIOTA ent/Not Obs	erved, 1 = Ra	re, 2	= (	Common, 3= Abu	ndant, 4=	
Periphyton Filamentous Algae Macrophytes		② 3 4 2 3 4 2 3 4	Slime Macro Fish	200	rteb	rates	0 2	国
	ATIONS OF MACRO I abundance: θ = Aborder organis	ent/Not Obs	served, 1 = Ra indant (>10 or	re (1 ganis	-3 o	rganisms), 2 = Co	ommon (3-9 >50 organism	is)
Porifera		nisoptera	① 1 2	3	4	Chironomidae	0 1 (2)	3_4
Hydrozoa		goptera	<b>1</b> 2	1	4	Ephemeroptera	( 12	200
Platyhelminthes		emiptera	(F) 1 2		4	Trichoptera	TO S	4
Furbellaria Hirudinea	ALC: A	oleoptera	Ø 1 2		4	Other	@ 1 2	3 4
	Photo.	pidoptera	P 1 2		4	The state of		
Oligochaeta Isopoda		alidae	1 2		4			
Amphipoda	Total Control of the	rydalidae	(9) 1 2 (70) 1 2		4			
Amphipoda Decapoda		pulidae	(0) 1 2		4			
Gastropoda		npididae	0 1 2 0 1 2		4	1.4		
		muliidae bisidas			4	- 15 Maria		
Jivaivia	(0 1 2 3 4 Ta	binidae	0 1 2	3	4			

Housasone R REACH SA BERA 76. 2372394 Pool Agustic Veg 42,4069299N - curly pondured -7-3.2367056E - Bur Reed - Eurasia M. Ifail

# = B CWD

NTS



# A-3 Fisheries Photo Log

### **AECOM** Imagine it. Delivered.

#### **PHOTOGRAPHIC LOG**

Client Name:

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

**Date:** 08/26/22

**Direction Photo** 

Taken:

N/A

Description:

A juvenile rock bass caught in one of three fish net locations throughout the reach.



Photo No.

**Date:** 8/25/22

Direction Photo Taken: South

**Description:** 

Location of one set of fishtraps at our northernmost fish trap area, within RBP 12 looking downstream. Fish nets were secured to the pictured woody debris.





#### PHOTOGRAPHIC LOG

Client Name:

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

**Date:** 8/25/22

Direction Photo
Taken: Northwest



#### **Description:**

Location of one set of fishtraps at our northernmost fish trap area, within RBP 12 looking upstream. Fish nets were secured to the pictured woody debris along the western bank.


Photo No. 6

**Date:** 8/26/22

**Direction Photo Taken:** N/A

#### **Description:**

Crayfish collected from fishnet traps at one of three sampling locations along the reach.





### **PHOTOGRAPHIC LOG**

**Client Name:** 

Chem Name

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

**Date:** 8/25/22

Direction Photo Taken: North



One of two fishtrap sets located within RBP 14 looking upstream. Fish nets were secured to the pictured boulders along the eastern bank.



Photo No.

Date:

8/25/22

Direction Photo Taken: South (Left)

North (Right)

#### Description:

An upstream and downstream look at ne of two fishtrap sets located within RBP 14. Fish nets were secured to the pictured logs which sit in the middle of the channel.





#### PHOTOGRAPHIC LOG

Client Name:

Site Location:

Project No.

GE

Reach 5A Housatonic River

60689453

Photo No.

**Date:** 8/25/22

Direction Photo
Taken: Southwest



Location of one set of fish traps at the southernmost fishtrap location located within RBP 22 looking downstream. Fish nets were secured to the handing branches pictured over the western bank.



Photo No.

**Date:** 8/25/22

Direction Photo Taken: Northwest

#### **Description:**

Location of one set of fish traps at the southernmost fishtrap location within RBP 22 looking upstream. Fishnets were secured using wooden sticks as planks amongst the submerged aquatic vegetation on the eastern bank.





### **AECOM** Imagine it. Delivered.

#### PHOTOGRAPHIC LOG

Client Name:

Site Location:

Project No.

GE


Reach 5A Housatonic River

60689453

Photo No.

**Date:** 8/26/22

Direction Photo Taken: N/A



#### **Description:**

A juvenile rock bass being measured after catch in one of three fish net locations throughout the reach.

Photo No.

**Date:** 8/25/22

Direction Photo Taken: N/A

#### Description:


Example on the bank of how fish nets are set up in water. Baiting with bread and catfood is used to lure fish through holes in the nets and the traps themselves are secured to submerged woody debris upstream.








# Appendix B Riverbank Habitat Inventory Forms

with figures showing riverbank stations surveyed









I.	General Info	ormation			
		OR R5A Bank 1 d Evaluation Segment			
	Bank 1: Statio	•	ream of Confluence. 300-ft s	tretch	before tight left bend.
	8/3/22 Date(s) of Site	Visit(s) and Data Collec	ction		
	Sunny, warm				
	AECOM	forming Evaluation			8/3/22  Date this form was completed
II.	Site Descrip	otion			
A.	Bank Charac	terization			
Phy	ysical Dimens	ions (ft):			
Ler	ngth 300'	Width: 60'	Bank Height: 6-7'		Slope: R 30% L 90%
Sed	diment / Subs	trate composition:			
% \$	Sand: 50	% Silt 40	% Clay 0		% Gravel/cobble 10
% E	Boulder/Bedro	ock 0	% Organic matter 5		
Bar	Left bank is r			tree ro	oot system. Roots appear to stabilize the bank.
В.	Bordering Ha	bitat Types			
We	tland		U	pland	
		nal floodplain forest			Northern Hardwoods-Hemlock-White Pine Forest
	☐ High terr	ace floodplain forest			Rich mesic forest
	☐ Red map	ole swamp			Red Oak-Sugar Maple Transition Forest
	☐ Vernal p	ool			Agricultural fields
	☐ Black as swamp	h-red maple-tamarack	calcareous seepage		Cultural grassland
	☐ Deep em	nergent marsh			Successional northern hardwoods
	Shallow	emergent marsh			Spruce-fir-northern hardwood forest
	☐ Shrub sv	vamp			Developed/disturbed cover types
	☐ Wet mea	adow			Other
	Other				

No	tes:							
C.	Hydrology							
Str	eam gradient:	☐ Low Gra	idient [	⊠ Mid-Gra	dient		☐ High-Gradient	
De	gree of overbank f	looding potentia	al / floodplain	connectivity	′			
	☐ High-flow cha	annels present i	n adjacent flo	odplain	$\boxtimes$	Торо	graphic breaks present	in the riverbank
	☐ Channel is de	eeply incised	☐ Modera	ately incised	l	$\boxtimes$	Somewhat incised	☐ Not incised
De	gree of Water leve	el fluctuation (es	timated vertic	al differenc	e fron	n mea	n low water to):	
	Bankfull indicator	rs: 3 ft	Top of banl	k slope: 6-7	ft	Flo	odplain surface: 6-7 ft	
Fie	ld-Derived Eviden	ce of Hydrologic	Conditions					
		line impressed	on bank		$\boxtimes$	Chan	ges in character of soil	
	⊠ Bed and ban	ks				Wate	r staining	
	Shelving				$\boxtimes$	Vege	tation matted down, ber	nt or absent
		litter and debris	)		$\boxtimes$	Chan	ge in plant community	
		Deposition				Destr	ruction of terrestrial vege	etation
	☐ Line of mud of	or silt on tree tru	nks/vegetatio	n		Debri	s stuck on overhanging	tree limbs
	Other							
Fie	ld-Derived Eviden	ce of Bankfull S	tage/Dischar	ge Water				
						Rece	nt changes to river bend	ds/meanders
	□ Depositional	bench (active c	hannel)		$\boxtimes$	Unde	rcuts	
	☐ Depositional	point bar				Stain	ing of rocks	
	Depositional	island				Торс	of point bars	
	☐ Middle bench	n for braided rive	ers		$\boxtimes$	Lowe	r limits in perennial vege	etation
	□ Break in slop	e of banks (floo	dplain break)					
	Other:							
D.	Inventory (Plant 0	Community)						
Rig	jht Bank							
	Total % Cover:	75 Bank Vegetat		0 Overhanging Ve	egetati	on	100 Riparian Vegetation	_
	Percent Cover of	f Bank and Ove	rhanging Stre	am Vegetat	ion b	y Strat	ta	
	50 Trees (> 20')	40 Shrubs (< 20')	30 Woody	y vines	0 Mo	sses	75 Herbaceous	_

### **General Electric Housatonic Rest of River**

Form RB-1: Riverbank Habitat Inventory Form Left Bank 50 100 75 Total % Cover: Bank Vegetation Overhanging Vegetation Riparian Vegetation Percent Cover of Bank and Overhanging Stream Vegetation by Strata 30 40 Trees (> 20') Shrubs (< 20') Herbaceous Woody vines Mosses Percent Cover of Riparian Vegetation by Strata 60% 75% Woody vines Mosses Herbaceous Trees (> 20') Bank and overhanging vegetation plant list (species that comprise 10% or more of the vegetative cover in each strata, or any amount of an invasive plant species; "\*" designates a dominant plant species for the strata): Plant Species Plant Species Strata Strata Forget me not (Myosotis scorpioides)\* Riverbank grape (Vitis riparia)\* Herb Vine Japanese knotweed (Polygonum Box elder (Acer negundo) Herb Tree cuspidatum)\* Shrub Red osier dogwood (Cornus sericea)\* Tree Silver maple (Acer saccharinum)\* Riparian vegetation plant list (species that comprise 10% or more of the vegetative cover in each strata, or any amount of an invasive plant species; "\*" designates a dominant plant species for the strata): Herb Ostrich fern (Matteuccia struthiopteris)\* Vine Bittersweet (Celastrus orbiculatus) Herb Coneflower (Rudbeckia laciniata) Sapling Common buckthorn (Rhamnus cathartica) Morrow's honeysuckle (Lonicera morrowil) Tree Silver maple (Acer saccharinum)\* Shrub Strata: T=Tree, S=Shrub, L=Liana (vine), H=Herb (Includes grasses, herbs, pterophytes [ferns], lichens, woody seedlings, and mosses) Notes: See attached tables for plant species lists. III. Important Habitat Features Wildlife Food Important wetland/aquatic food plants Abundant Present Absent Not Applicable Important upland food plants (hard mast and fruit/berry producers) ☐ Abundant □ Present □ Absent Not Applicable

#### Cover/Perches/Basking/Denning/Nesting Habitat

Trees (live or dead) > 30" DBH

Abundant □ Present Absent Not Applicable

Standing dead trees (potential for cavities and perches)

Abundant	□ Present	☐ Absent	□ Not Applicable
Tree cavities in trunks or lin	nbs		
Abundant	☐ Present		☐ Not Applicable
Small mammal burrows:			
Abundant	□ Present	Absent	☐ Not Applicable
Dense herbaceous cover (v	oles, small mammals, ar	mphibians & reptiles)	
	☐ Present	☐ Absent	☐ Not Applicable
Large woody debris on the	ground (small mammals,	mink, amphibians & rep	tiles)
Abundant	□ Present	Absent	☐ Not Applicable
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)
Abundant	□ Present	Absent	□ Not Applicable
Overhanging branches at o duck, mink, raccoon)	r within 1 m above the wa	ater's surface (turtles, sr	nakes, frogs, wading birds, wood
	☐ Present	Absent	☐ Not Applicable
Rock piles, crevices, or holl	ow logs suitable for vario	ous mammals (otter, min	k, porcupine, racoon):
Abundant	☐ Present		☐ Not Applicable
Live or dead tall standing ve osprey, kingfisher, flycatche		near water offering goo	d visibility of open water (e.g.,
	Present	Absent	☐ Not Applicable
Other Important Habitat C	haracteristics:		
Underwater banks of fine si	lt and/or clay (beaver, m	uskrat, otter)	
☐ Abundant	□ Present	Absent	☐ Not Applicable
Undercut or overhanging ba	anks (small mammals, m	ink, weasels, turtles)	
Abundant	□ Present	☐ Absent	☐ Not Applicable
Vertical sandy banks (bank	swallow, kingfisher)		
☐ Abundant	☐ Present		□ Not Applicable
Mud flats			
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable
Exposed areas of well-drain	ned, sandy soil suitable fo	or turtle nesting	
☐ Abundant	□ Present	Absent	□ Not Applicable

#### Wildlife Dens/Nests (if observed)

	Turtle nesting sites								
	☐ Abundant ☐ Present ☐			☐ Not Applicable					
	Bank swallow colony(ies)								
	Abundant	☐ Present		☐ Not Applicable					
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron					
	Den(s) present of	☐ Otter	☐ Mink	☐ Beaver					
	Other nests or dens (identify	y species):							
IV.	Connectivity with Adjoining Natural Habitats								
	☐ No direct connections to adjacent areas of wildlife habitat (little connectivity function)								
	☐ Limited number of conr	nectors to adjacent areas	of habitat (some	ewhat important for connectivity function)					
	Riverbank is embedded connectivity function)	in a large area of natura	al habitat with ur	nimpeded connection to other habitats (high					
٧.	Rare Species and MNHES	SP Core Area Habitat De	esignation						
	Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat								
	State-listed species habitat (including species with known overlapping Priority Habitat):								
	Brook Snaketail, Matted Sp	oike Sedge, Riffle Snaket	tail, Spine-crown	ed Clubtail, Wapato, Wood Turtle					
	Rare species direct observa	ations during current field	surveys:						
VI.	Incidental Direct Wildlife								
	Catbird								
	Cardinal								
	Raccoon tracks								
	raccoon tracks								

	Form RB-1: Riverbank Habitat Inventory Form						
VII.	VII. Habitat Degradation (identify specific location on bank segr	nent if applicable)					
	Evidence of significant levels of dumping						
	Evidence of significant erosion or sedimentation problems						
	Occurrence of invasive plants:  Japanese knotweed (prevalent on both banks above bankfull); bittersweet common on both banks at upper levels as well as in floodplain; Morrow's honeysuckle, common buckthorn, yellow iris, forget-me-nots also present						
	Evidence of other human disturbance; describe: Left bank a	t upstream end has apparent earth fill					
VIII	VIII.Restoration Opportunities						
	□ Presence of potential restoration resources (e.g., boulders, bank stabilization or hibernacula, plant propagation source mate Coarse woody debris along left bank, Cobbles						
	R: Coir matting						
	L: Vegetated Riprap with bank spurs						
	Invasive species control						
	Revegetation						

Bank 1 Plant Species					
Left Bank	Right Bank				
boxelder   Acer negundo   tree	boxelder   Acer negundo   tree				
silver maple   Acer saccharinum   tree	silver maple   Acer saccharinum   tree				
Devil's beggar-ticks   Bidens frondosa   herb	Devil's beggar-ticks   Bidens frondosa   herb				
black mustard   Brassica nigra   herb	black mustard   Brassica nigra   herb				
Asian bittersweet   Celastrus orbiculatus   vine/liana   *	Asian bittersweet   Celastrus orbiculatus   vine/liana   *				
silky dogwood   Cornus amomum   shrub	red-osier dogwood   Cornus sericea   shrub				
red-osier dogwood   Cornus sericea   shrub	hawthorn   Crataegus spp.   shrub/tree				
Japanese knotweed   Fallopia japonica   herb   *	Japanese knotweed   Fallopia japonica   herb   *				
jewelweed   Impatiens capensis   herb	green ash   Fraxinus pennsylvanica   tree				
Morrow's honeysuckle   Lonicera morrowii   shrub   *	American burnweed   Erechtites hieraciifolius   herb				
common water-purslane   Ludwigia palustris   herb	jewelweed   Impatiens capensis   herb				
ostrich fern   Matteuccia struthiopteris   herb	yellow iris   Iris pseudacorus   herb   *				
water forget-me-not   Myosotis scorpioides   herb   *	Morrow's honeysuckle   Lonicera morrowii   shrub   *				
common buckthorn   Rhamnus cathartica   herb   *	common water-purslane   Ludwigia palustris   herb				
green-headed coneflower   Rudbeckia laciniata   herb	ostrich fern   Matteuccia struthiopteris   herb				
stinging nettle   Urtica dioica   herb	Allegheny monkeyflower   Mimulus ringens   herb				
river grape   Vitis riparia   vine/liana	water forget-me-not   Myosotis scorpioides   herb   *				
	sensitive fern   Onoclea sensibilis   herb				
	water-pepper smartweed   Persicaria hydropiper   herb				
	false water-pepper smartweed   Persicaria hydropiperoides   herb				
	pale smartweed   Persicaria lapathifolia   herb				
	Canada clearweed   Pilea pumila   herb				
	common buckthorn   Rhamnus cathartica   herb   *				
	green-headed coneflower   Rudbeckia laciniata   herb				
	curly dock   Rumex crispus   herb				
	black willow   Salix nigra   tree				
	American bur-reed   Sparganium americanum   herb				
American elm   Ulmus americana   tree					
	stinging nettle   Urtica dioica   herb				
	river grape   Vitis riparia   vine/liana				

<sup>\*</sup>Invasive species

#### **Bank 1 Floodplain Plant Species**

Japanese Knotweed	Fallopia japonica	Н
false Soloman's seal	Maianthemum racemosum	Н
Morrow's honeysuckle	Lonicera morrowii	S
white ash	Fraxinus americana	Τ
boxelder	Acer negundo	Τ
American linden	Tilia americana	Τ
river grape	Vitis riparia	V
stinging nettle	Urtica dioica	Н
bishop's goutweed	Aegopodium podagraria	Н
garlic-mustard	Alliara petiolata	Н
ostrich fern	Matteuccia struthiopteris	Н
Asian bittersweet	Celastrus orbiculatus	V
common buckthorn	Rhamnus cathartica	S
Virginia creeper	Parthenocissus quinquefolia	V
American elm	Ulmus americana	T
sensitive fern	Onoclea sensibilis	Н
moneywort	Lysimachia nummularia	Н
skunk-cabbage	Symplocarpus foetidus	Н
silky dogwood	Cornus amomum	S
silver maple	Acer saccharinum	Τ
American elm	Ulmus americana	Τ




Bank 1: Stations 0-3. 300-ft of straight channel below the confluence

Photos of Bank 1 Area. August 3, 2022.









Views of left bank showing cut bank, largely vegetated

I.	Gener	al Informat	tion				
	Housatonic ROR R5A Bank 2						
	Site Name and Evaluation Segment  Bank 2: Stations 3-5. 300-500 ft downstream of Confluence along tight left bend.						
	Location/Physical Description						
	8/3/22 Date(s)		(s) and Data Colle	action			
	Sunny,	warm (85 de	egrees)	Solion			
			During Site Visit				0/0/00
	AECOM Field Staff Performing Evaluation						8/3/22  Date this form was completed
II.	Site D	escription					
Α. Ι	Bank C	Characteriza	tion				
Phy	sical D	imensions (	(ft):				
Len	gth: 20	00'	Width: 60'	Bank Height: R 8	s'; L 5'	Slope: R 90°	%; L 40%
Sec	liment /	/ Substrate	composition:				
% S	Sand 50	)	% Silt 50	% Clay 0		% Gravel/cobble 0	
% E	Boulder	/Bedrock 0		% Organic matter 5			
Bank stability / Observed erosional conditions: Right bank is mostly vertical, with some undercutting beneath roots and significant slumping. Thalweg is along right.							
В. І	Border	ing Habitat <sup>-</sup>	Types				
Wet	tland				Upland		
	⊠ Tr	ansitional flo	oodplain forest			Northern Hardwoo Forest	ds-Hemlock-White Pine
	☐ Hi	gh terrace f	loodplain forest			Rich mesic forest	
	☐ Re	ed maple sw	vamp			Red Oak-Sugar M	aple Transition Forest
	□ Ve	ernal pool				Agricultural fields	
		ack ash-red vamp	maple-tamarac	k calcareous seepage		Cultural grassland	
	⊠ De	eep emerge	nt marsh			Successional north	nern hardwoods
	⊠ Sh	nallow emer	gent marsh			Spruce-fir-northern	n hardwood forest
	☐ Sh	nrub swamp	1			Developed/disturb	ed cover types
	☐ Wet meadow ☐ Other						
	Other						
Not	tes: Erosional channel cuts from right bank through to marsh/open water to the southwest.						

	Trees (> 20')	Shrubs (< 20')	Woody		osses	Herbaceous	<del></del>		
	50	40	30	iiii vegetation 0	•	30			
	Total % Cover:  Percent Cover of	Bank Vegetation Bank and Overl		verhanging Vegeta um Vegetation		Riparian Vegetation			
Rig	tht Bank	30	70			100			
D.	D. Inventory (Plant Community)								
	Other:								
		oe of banks (flood	dplain break)						
	☐ Middle bench for braided rivers			$\boxtimes$	] Lov	Lower limits in perennial vegetation			
	☐ Depositional island			$\boxtimes$	] Top	Top of point bars			
	□ Depositional point bar				] Sta	Staining of rocks			
	□ Depositional bench (active channel)				] Und	Undercuts			
					] Red	cent changes to river ber	nds/meanders		
Fie	ld-Derived Evider	nce of Bankfull St	age/Discharg	e Water					
	Other								
	☐ Line of mud	or silt on tree trur	nks/vegetatior	n [	] Del	Debris stuck on overhanging tree limbs			
	Scour and/or Deposition     ■ Scour and Scour a				] Des	Destruction of terrestrial vegetation			
	☐ Wrack lines	(litter and debris)		$\boxtimes$	] Cha	Change in plant community			
	Shelving			$\boxtimes$	] Ve	Vegetation matted down, bent or absent			
	⊠ Bed and bar	nks			] Wa	Water staining			
		I line impressed	on bank	$\boxtimes$	] Cha	Changes in character of soil			
Fie	ld-Derived Evider	nce of Hydrologic	Conditions						
	Bankfull indicators: 3 ft Top of bank slope: 5-8 ft Floodplain surface: 6-8 ft								
Degree of Water level fluctuation (estimated vertical difference from mean low water to):									
	☐ Channel is deeply incised ☐ Moderately incised ☐ Somewhat incised ☐ Not incise								
							t in the riverbank		
Degree of overbank flooding potential / floodplain connectivity									
Stre	eam gradient:		dient [	] Mid-Gradier	t	☐ High-Gradient			
C.	Hydrology								

Left Bank 90 75 50 Total % Cover: Bank Vegetation Overhanging Vegetation Riparian Vegetation Percent Cover of Bank and Overhanging Stream Vegetation by Strata 75 Trees (> 20') Shrubs (< 20') Woody vines Mosses Herbaceous Percent Cover of Riparian Vegetation by Strata 50% <5% 70% 75% Shrubs (< 20') Trees (> 20') Woody vines Mosses Herbaceous Bank and overhanging vegetation plant list (species that comprise 10% or more of the vegetative cover in each strata, or any amount of an invasive plant species; "\*" designates a dominant plant species for the strata): Strata Plant Species Strata Plant Species Stinging nettle (Urtica dioica) Vine Bittersweet (Celastrus orbiculatus) Herb Clear weed (Pilea pumila) Box elder (Acer negundo) Herb Tree Shrub Red osier dogwood (Cornus sericea) Tree Silver maple (Acer saccharinum) Riparian vegetation plant list (species that comprise 10% or more of the vegetative cover in each strata, or any amount of an invasive plant species; "\*" designates a dominant plant species for the strata): Ostrich fern (Matteuccia struthiopteris)\* Vine Bittersweet (Celastrus orbiculatus) Herb Common buckthorn (Rhamnus cathartica) Herb Coneflower (Rudbeckia laciniata) Sapling Shrub Morrow's honeysuckle (Lonicera morrowil) Box elder (Acer negundo) Tree Strata: T=Tree, S=Shrub, L=Liana (vine), H=Herb (Includes grasses, herbs, pterophytes [ferns], lichens, woody seedlings, and mosses) Notes: See attached tables for plant species lists. III. Important Habitat Features **Wildlife Food** Important wetland/aquatic food plants Abundant □ Present Not Applicable | | Absent Important upland food plants (hard mast and fruit/berry producers) Abundant Present Absent ■ Not Applicable Cover/Perches/Basking/Denning/Nesting Habitat Trees (live or dead) > 30" DBH Abundant  $\boxtimes$ Absent ■ Not Applicable Present Standing dead trees (potential for cavities and perches) □ Present Abundant Absent Not Applicable

Tree cavities in trunks or limbs								
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable					
Small mammal burrows:	Small mammal burrows:							
Abundant	□ Present	☐ Absent	☐ Not Applicable					
Dense herbaceous cover (	voles, small mammals, ar	mphibians & reptiles)						
Abundant	□ Present	☐ Absent	☐ Not Applicable					
Large woody debris on the	ground (small mammals	, mink, amphibians & rep	otiles)					
Abundant		Absent	☐ Not Applicable					
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)					
Abundant	□ Present	Absent	☐ Not Applicable					
Overhanging branches at o duck, mink, raccoon)	or within 1 m above the w	ater's surface (turtles, sr	nakes, frogs, wading birds, wood					
Abundant	□ Present	Absent	☐ Not Applicable					
Rock piles, crevices, or ho	llow logs suitable for vario	ous mammals (otter, min	k, porcupine, racoon):					
Abundant	☐ Present		☐ Not Applicable					
Live or dead tall standing vosprey, kingfisher, flycatch		near water offering goo	d visibility of open water (e.g.,					
Abundant	□ Present	☐ Absent	☐ Not Applicable					
Other Important Habitat	Characteristics:							
Underwater banks of fine s	silt and/or clay (beaver, m	uskrat, otter)						
Abundant		☐ Absent	□ Not Applicable					
Undercut or overhanging b	oanks (small mammals, m	ink, weasels, turtles)						
Abundant		Absent	☐ Not Applicable					
Vertical sandy banks (bank	swallow, kingfisher)							
Abundant	Present		Not Applicable					
Mud flats								
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable					
Exposed areas of well-drain	ned, sandy soil suitable f	or turtle nesting						
Abundant		Absent	☐ Not Applicable					

Wildlife Dens/Nests (if observed)

	Turtle nesting sites							
	Abundant	☐ Present		☐ Not Applicable				
	Bank swallow colony(ies)							
	Abundant	☐ Present		☐ Not Applicable				
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron				
	Den(s) present of	☐ Otter	☐ Mink	☐ Beaver				
	Other nests or dens (identify	y species):						
IV.	Connectivity with Adjoining	ng Natural Habitats						
	☐ No direct connections to	o adjacent areas of wildli	fe habitat (little o	connectivity function)				
	☐ Limited number of conn	nectors to adjacent areas	of habitat (some	ewhat important for connectivity function)				
	Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with un	impeded connection to other habitats (high				
٧.	Rare Species and MNHES	SP Core Area Habitat De	esignation					
		re Area 2 🔲 Core A	rea 3 🔲 Cor	e Area 4				
	Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat							
	State-listed species ha	bitat (including species v	vith known overla	apping Priority Habitat):				
Wo	American Bittern, Brook Si od Turtle	naketail, Matted Spike Se	edge, Riffle Snal	ketail, Spine-crowned Clubtail, Wapato,				
	Rare species direct observa	ations during current field	surveys:					
VI.	Incidental Direct Wildlife	Observations						
	Catbird							
	Great blue heron							
	Raccoon tracks							
	Spotted sandpiper							
	Song sparrow							
	Green frog							

Dragonflies	
VII. Habitat Degradation (identify specific location on b	ank segment if applicable)
Evidence of significant levels of dumping	
Evidence of significant erosion or sedimentation pr	oblems
☑ Occurrence of invasive plants: bittersweet common on both banks at upper levels as buckthorn, Japanese knotweed, forget-me-not	well as in floodplain; Morrow's honeysuckle, common
Evidence of other human disturbance; describe:	
VIII.Restoration Opportunities	
Presence of potential restoration resources (e.g., beank stabilization or hibernacula, plant propagation so Coarse woody debris along both banks.	oulders, large trees or woody debris, root wad material for urce material). Identify specific items:
R: Vegetated riprap; Log or rock vanes	
L: Coir matting	
Invasive species control	
Revegetation	

Bank 2 Plant Species				
<u>Left bank</u>	Right bank			
boxelder   Acer negundo   tree	boxelder   Acer negundo   tree			
silver maple   Acer saccharinum   tree	silver maple   Acer saccharinum   tree			
Asian bittersweet   Celastrus orbiculatus   vine/liana   *	Asian bittersweet   Celastrus orbiculatus   vine/liana   *			
red-osier dogwood   Cornus sericea   shrub	silky dogwood   Cornus amomum   shrub			
Japanese knotweed   Fallopia japonica   herb   *	red-osier dogwood   Cornus sericea   shrub			
green ash   Fraxinus pennsylvanica   tree	Japanese knotweed   Fallopia japonica   herb   *			
common water-purslane   Ludwigia palustris   herb	green ash   Fraxinus pennsylvanica   tree			
water forget-me-not   Myosotis scorpioides   herb   *	Morrow's honeysuckle   Lonicera morrowii   shrub   *			
pale smartweed   Persicaria lapathifolia   herb	ostrich fern   Matteuccia struthiopteris   herb			
common buckthorn   Rhamnus cathartica   herb   *	common buckthorn   Rhamnus cathartica   herb   *			
stinging nettle   Urtica dioica   herb	stinging nettle   Urtica dioica   herb			

<sup>\*</sup>Invasive species


#### **Bank 2 Floodplain Plant Species**

stinging nettle	Urtica dioica	Н
bishop's goutweed	Aegopodium podagraria	Н
garlic-mustard	Alliara petiolata	Н
ostrich fern	Matteuccia struthiopteris	Н
Asian bittersweet	Celastrus orbiculatus	V
Morrow's honeysuckle	Lonicera morrowii	S
common buckthorn	Rhamnus cathartica	S
boxelder	Acer negundo	S/T
Virginia creeper	Parthenocissus quinquefolia	V
American elm	Ulmus americana	T



Bank 2: Stations 3-5. 200 ft of sharp left bend. Vertical cut bank on outer bend. Gentle bank on inside with point bar development.

Photos of Bank 2 Area, August 3, 2023





I.	Gei	neral Informa	tion				
		satonic ROR R	5A Bank 3 Iuation Segment				
	Bank 3: Stations 5+50 to 7+50; 550-ft downstream of Confluence; 200-ft long straight stretch between tight bends						
	Loc 8/3/	ation/Physical D	escription				
			(s) and Data Collection	on		_	
		ny, warm (85 deather Conditions	egrees) s During Site Visit				
	AEC	СОМ	•			8/3/22	
	Fiel	d Staff Performi	ng Evaluation			Date this form was completed	
II.	Site	e Description					
A.	Ban	k Characteriza	ation				
Phy	/sica	al Dimensions	(ft):				
Ler	gth:	200'	Width: 60'	Bank Height: R 8	3' L 5'	Slope: R 90% L 40%	
Sec	dime	ent / Substrate	composition:				
% \$	Sanc	1 50	% Silt 50	% Clay 0		% Gravel/cobble 0	
% E	3oul	der/Bedrock	%	Organic matter 5			
Bar	Rigl	ht bank is mos			eath root	ts and some slumping; moderate – high BEHI.	
В.	Bord	dering Habitat	Types				
We	tland	d			Upland		
	$\boxtimes$	Transitional fl	oodplain forest			Northern Hardwoods-Hemlock-White Pine Forest	
		High terrace f	loodplain forest			Rich mesic forest	
		Red maple sv	vamp			Red Oak-Sugar Maple Transition Forest	
		Vernal pool				Agricultural fields	
		Black ash-red swamp	l maple-tamarack o	calcareous seepage		Cultural grassland	
		Deep emerge	ent marsh			Successional northern hardwoods	
		Shallow emer	gent marsh			Spruce-fir-northern hardwood forest	
		Shrub swamp	)			Developed/disturbed cover types	
		Wet meadow				Other	
		Other					
Not	es:						

C.	Hydrology						
Stre	eam gradient:	☐ Low Gra	dient 🛛 Mid-G	Gradient	☐ High-Gradient		
De	regree of overbank flooding potential / floodplain connectivity						
	☐ High-flow cha	annels present ir	n adjacent floodplain	$\boxtimes$	Topographic breaks present in	the riverbank	
	☐ Channel is de	eeply incised		sed	☐ Somewhat incised	☐ Not incised	
De	gree of Water leve	I fluctuation (est	imated vertical differe	nce from	mean low water to):		
	Bankfull indicator	s: 3 ft	Top of bank slope: 5	5-8 ft	Floodplain surface: 6-8 ft		
Fie	d-Derived Evidend	ce of Hydrologic	Conditions				
		line impressed	on bank		Changes in character of soil		
	Bed and bank	ks			Water staining		
	Shelving				Vegetation matted down, bent	or absent	
	☐ Wrack lines (	litter and debris)			Change in plant community		
	Scour and/or     Scour and/or	Deposition			Destruction of terrestrial veget	ation	
	Line of mud o	or silt on tree tru	nks/vegetation		Debris stuck on overhanging to	ree limbs	
	☐ Other						
Fie	d-Derived Evidend	ce of Bankfull St	age/Discharge Water				
	Scour line				Recent changes to river bends	s/meanders	
	□ Depositional	bench (active ch	nannel)	$\boxtimes$	Undercuts		
	Depositional	point bar			Staining of rocks		
	Depositional	island			Top of point bars		
	☐ Middle bench	for braided rive	ers		Lower limits in perennial veget	ation	
	□ Break in slope     □ Break in slope	e of banks (flood	dplain break)				
	Other: good b	oankfull bench o	n left bank				
D.	Inventory (Plant C	Community)					
Rig	ht Bank						
		50	80		90		
	Total % Cover: Bank Vegetation Overhanging Vegetation Riparian Vegetation						
	Total % Cover:  Percent Cover of	Bank Vegetation			·		

**General Electric Housatonic Rest of River** Form RB-1: Riverbank Habitat Inventory Form Left Bank 20 100 75 Total % Cover: Bank Vegetation Overhanging Vegetation Riparian Vegetation Percent Cover of Bank and Overhanging Stream Vegetation by Strata 75 Trees (> 20') Shrubs (< 20') Herbaceous Woody vines Mosses Percent Cover of Riparian Vegetation by Strata Trees (> 20') Woody vines Mosses Herbaceous Bank and overhanging vegetation plant list (species that comprise 10% or more of the vegetative cover in each strata, or any amount of an invasive plant species; "\*" designates a dominant plant species for the strata): Strata Plant Species Strata Plant Species Japanese knotweed (Polygonum cuspidat) Bittersweet (Celastrus orbiculatus) Herb Vine Herb Clear weed (Pilea pumila) Tree Box elder (Acer negundo) Shrub Red osier dogwood (Cornus sericea) Tree American elm (Ulmus americana) Riparian vegetation plant list (species that comprise 10% or more of the vegetative cover in each strata, or any amount of an invasive plant species; "\*" designates a dominant plant species for the strata): Ostrich fern (Matteuccia struthiopteris)\* Bittersweet (Celastrus orbiculatus) Herb Vine Herb Japanese knotweed (Polygonum Sapling Common buckthorn (Rhamnus cathartica) cuspidatum) Morrow's honeysuckle (Lonicera morrowil) Box elder (Acer negundo) Shrub Tree Strata: T=Tree, S=Shrub, L=Liana (vine), H=Herb (Includes grasses, herbs, pterophytes [ferns], lichens, woody seedlings, and mosses) Notes: See attached tables for plant species lists. III. Important Habitat Features Wildlife Food Important wetland/aquatic food plants ☐ Absent Abundant Present Not Applicable

#### Cover/Perches/Basking/Denning/Nesting Habitat

Important upland food plants (hard mast and fruit/berry producers)

□ Present

Trees (live or dead) > 30" DBH

Abundant

Abundant Absent Not Applicable Present

☐ Absent

Not Applicable

Standing dead trees (potential for cavities and perches)							
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable				
Tree cavities in trunks or limbs							
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable				
Small mammal burrows:							
☐ Abundant	□ Present	☐ Absent	□ Not Applicable				
Dense herbaceous cover (v	voles, small mammals, a	mphibians & reptiles)					
Abundant	□ Ab     □ Ab	sent	ot Applicable				
Large woody debris on the	ground (small mammals	, mink, amphibians & rep	otiles)				
	☐ Present	Absent	□ Not Applicable				
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wat	er's surface (turtles, snakes, frogs)				
	Present	Absent	□ Not Applicable				
Overhanging branches at o duck, mink, raccoon)	or within 1 m above the w	rater's surface (turtles, sr	nakes, frogs, wading birds, wood				
Abundant	□ Present	☐ Absent	☐ Not Applicable				
Rock piles, crevices, or hol	low logs suitable for vari	ous mammals (otter, min	nk, porcupine, racoon):				
Abundant	☐ Present		☐ Not Applicable				
Live or dead tall standing v osprey, kingfisher, flycatche		r near water offering goo	d visibility of open water (e.g.,				
Abundant	□ Present	☐ Absent	☐ Not Applicable				
Other Important Habitat C	Characteristics:						
Underwater banks of fine s	ilt and/or clay (beaver, m	uskrat, otter)					
Abundant	□ Present	Absent	□ Not Applicable				
Undercut or overhanging be	anks (small mammals, m	nink, weasels, turtles)					
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable				
Vertical sandy banks (bank	swallow, kingfisher)						
☐ Abundant	☐ Present		Not Applicable				
Mud flats							
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable				
Exposed areas of well-drained, sandy soil suitable for turtle nesting							

#### **General Electric Housatonic Rest of River** Form RB-1: Riverbank Habitat Inventory Form Abundant Present ☐ Not Applicable Wildlife Dens/Nests (if observed) Turtle nesting sites ☐ Abundant ☐ Present Not Applicable Bank swallow colony(ies) Abundant Present ☐ Not Applicable Nest(s) present of ☐ Bald Eagle Osprey ☐ Great Blue Heron ☐ Mink Den(s) present of Otter Beaver Other nests or dens (identify species): \_\_ IV. Connectivity with Adjoining Natural Habitats No direct connections to adjacent areas of wildlife habitat (little connectivity function) Limited number of connectors to adjacent areas of habitat (somewhat important for connectivity function) Riverbank is embedded in a large area of natural habitat with unimpeded connection to other habitats (high connectivity function) V. Rare Species and MNHESP Core Area Habitat Designation ☐ Core Area 1 ☐ Core Area 2 Core Area 3 Core Area 4 Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat State-listed species habitat (including species with known overlapping Priority Habitat): Brook Snaketail, Matted Spike-sedge, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle Rare species direct observations during current field surveys: VI. Incidental Direct Wildlife Observations Green frog Raccoon tracks

Spotted sandpiper

	General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form							
VII.	VII. Habitat Degradation (identify specific location on bank seg	ment if applicable)						
	☐ Evidence of significant levels of dumping							
	Evidence of significant erosion or sedimentation problems							
	Evidence of other human disturbance; describe:							
VIII	VIII.Restoration Opportunities							
	☑ Presence of potential restoration resources (e.g., boulders, bank stabilization or hibernacula, plant propagation source mate Coarse woody debris; large trees; root wads							
	R: Compartmentalized fill							
	L: Grade bank/Coir matting							
	Invasive species control							
	Revegetation							

Bank 3 Plant Species List			
Left bank	Right bank		
boxelder   Acer negundo   tree	boxelder   Acer negundo   tree		
Asian bittersweet   Celastrus orbiculatus   vine/liana   *	Asian bittersweet   Celastrus orbiculatus   vine/liana   *		
red-osier dogwood   Cornus sericea   shrub	red-osier dogwood   Cornus sericea   shrub		
Japanese knotweed   Fallopia japonica   herb   *	Japanese knotweed   Fallopia japonica   herb   *		
	American elm   Ulmus americana   tree		

<sup>\*</sup>Invasive species

#### **Bank 3 Floodplain Plant Species**

Japonese knotweed	Fallopia japonica	Н
false Soloman's seal	Maianthemum racemosum	Н
Morrow's honeysuckle	Lonicera morrowii	S
white ash	Fraxinus americana	T
boxelder	Acer negundo	T
American linden	Tilia americana	T
river grape	Vitis riparia	V



Bank 3 Stations 5.5 - 7.5. 550-ft downstream of Confluence. 200-ft long straight stretch between tight bends

Photos of Bank 3 Area, August 3, 2023 Left bank Right bank (to left), left bank to right, looking upstream Right bank, looking upstream

I.	Gei	neral Informat	tion					
	Housatonic ROR R5A Bank 4 Site Name and Evaluation Segment							
		Bank 4: Stations 9-11. 900-ft downstream of Confluence. After sharp right bend and covering 200 ft of slight right curve in						
	river.  Location/Physical Description							
	8/3/	· ·	occupación de la comparion de					
		` '	(s) and Data Collectio	n				
		iny, warm (85 de ather Conditions	egrees) During Site Visit					
		COM d Staff Performi	ng Evaluation			8/3/22  Date this form was complete		
	riei	u Stall Fellollilli	ng Evaluation			Date this form was complete	u	
II.	Site	e Description						
A.	Ban	k Characteriza	ition					
Phy	/sica	al Dimensions	(ft):					
Ler	ngth:	200'	Width: 60'	Bank Height: R	7' L 8'	Slope: R 60% L 40%		
Sed	dime	ent / Substrate	composition:					
% \$	Sand	i 40	% Silt 30	% Clay 0		% Gravel/cobble: 30		
% E	3oul	der/Bedrock 0	%	Organic matter <5				
	_eft k	oank high BEH				ith left bank near station 10+00 and has erode	ed	
В.	Bord	dering Habitat	Types					
We	tland	d			Upland			
		Transitional flo	oodplain forest			Northern Hardwoods-Hemlock-White Pine Forest		
		High terrace f	loodplain forest			Rich mesic forest		
		Red maple sv	vamp			Red Oak-Sugar Maple Transition Forest		
		Vernal pool				Agricultural fields		
		Black ash-red swamp	l maple-tamarack ca	alcareous seepage		Cultural grassland		
		Deep emerge	nt marsh			Successional northern hardwoods		
		Shallow emer	gent marsh			Spruce-fir-northern hardwood forest		
		Shrub swamp				Developed/disturbed cover types		
		Wet meadow				Other		
		Other						
Not	tes:							

C.	Hydrology						
Str	eam gradient:	☐ Low Gra	dient 🖂	Mid-Gradient	[	☐ High-Gradient	
De	gree of overbank f	looding potentia	l / floodplain cor	nnectivity			
	☐ High-flow cha	annels present ir	adjacent flood	plain 🖂	Topogra	aphic breaks present	in the riverbank
	☐ Channel is de	eeply incised		ly incised	☐ S	omewhat incised	☐ Not incised
De	Degree of Water level fluctuation (estimated vertical difference from mean low water to):						
	Bankfull indicator	s: 3 ft	Top of bank s	lope: 7-8 ft	Flood	plain surface: 7-8 ft	
Fie	ld-Derived Eviden	ce of Hydrologic	Conditions				
		line impressed	on bank	$\boxtimes$	Change	s in character of soil	
	⊠ Bed and bank	ks			Water s	taining	
	Shelving			$\boxtimes$	Vegetat	ion matted down, be	nt or absent
	☐ Wrack lines (	litter and debris)		$\boxtimes$	Change	in plant community	
	Scour and/or     Scour and/or	Deposition			Destruc	tion of terrestrial veg	etation
	Line of mud of	or silt on tree tru	nks/vegetation		Debris s	stuck on overhanging	tree limbs
	Other						
Fie	ld-Derived Eviden	ce of Bankfull St	age/Discharge	Water			
					Recent	changes to river ben	ds/meanders
	□ Depositional	bench (active ch	nannel)		Undercu	uts	
	☐ Depositional	point bar			Staining	of rocks	
	☐ Depositional	island			Top of p	point bars	
	☐ Middle bench	for braided rive	rs		Lower li	mits in perennial veg	etation
		e of banks (flood	dplain break)				
	Other:						
D.	Inventory (Plant 0	Community)					
Rig	ıht Bank						
	Total % Cover:	60 Bank Vegetation	on 70 Over	hanging Vegetation		00 Riparian Vegetation	_
	Percent Cover of	Bank and Over	hanging Stream	vegetation by	y Strata		
	50 Trees (> 20')	40 Shrubs (< 20')	50 Woody vir	nes 0	sses	50 Herbaceous	

Left Bank 60 90 70 Total % Cover: Bank Vegetation Overhanging Vegetation Riparian Vegetation Percent Cover of Bank and Overhanging Stream Vegetation by Strata 60 50 Trees (> 20') Shrubs (< 20') Woody vines Mosses Herbaceous Percent Cover of Riparian Vegetation by Strata Shrubs (< 20') Trees (> 20') Woody vines Mosses Herbaceous Bank and overhanging vegetation plant list (species that comprise 10% or more of the vegetative cover in each strata, or any amount of an invasive plant species; "\*" designates a dominant plant species for the strata): Strata Plant Species Strata Plant Species Pale Smartweed (Persicaria lapathifolia) Vine Bittersweet (Celastrus orbiculatus) Herb Japanese knotweed (Polygonum cusp.) Box elder (Acer negundo) Herb Tree Vine Riverbank grape (Vitis riparia) Tree Silver maple (Acer saccharinum) Riparian vegetation plant list (species that comprise 10% or more of the vegetative cover in each strata, or any amount of an invasive plant species; "\*" designates a dominant plant species for the strata): Ostrich fern (Matteuccia struthiopteris)\* Vine Bittersweet (Celastrus orbiculatus) Herb Common buckthorn (Rhamnus cathartica) Herb Stinging nettle (Urtica dioica) Sapling Shrub Morrow's honeysuckle (Lonicera morrowil) Tree Box elder (Acer negundo) Strata: T=Tree, S=Shrub, L=Liana (vine), H=Herb (Includes grasses, herbs, pterophytes [ferns], lichens, woody seedlings, and mosses) Notes: See attached tables for plant species lists. III. Important Habitat Features **Wildlife Food** Important wetland/aquatic food plants Abundant □ Present Absent Not Applicable Important upland food plants (hard mast and fruit/berry producers) Abundant Present Absent ■ Not Applicable Cover/Perches/Basking/Denning/Nesting Habitat Trees (live or dead) > 30" DBH Abundant Absent ■ Not Applicable Present Standing dead trees (potential for cavities and perches) □ Present Abundant Absent Not Applicable

Tree cavities in trunks or limbs				
☐ Abundant		☐ Absent	☐ Not Applicable	
Small mammal burrows:				
☐ Abundant		☐ Absent	☐ Not Applicable	
Dense herbaceous cover (	voles, small mammals, a	mphibians & reptiles)		
☐ Abundant		Absent	☐ Not Applicable	
Large woody debris on the	ground (small mammals	, mink, amphibians & re	ptiles)	
	☐ Present	Absent	☐ Not Applicable	
Rocks, crevices, logs, tree	roots or hummocks at w	ater's edge or under wa	ter's surface (turtles, snakes, frogs)	
	Present	Absent	□ Not Applicable	
Overhanging branches at o duck, mink, raccoon)	or within 1 m above the w	/ater's surface (turtles, s	nakes, frogs, wading birds, wood	
Abundant	□ Present	☐ Absent	☐ Not Applicable	
Rock piles, crevices, or hol	llow logs suitable for vari	ous mammals (otter, mi	nk, porcupine, racoon):	
Abundant		☐ Absent	□ Not Applicable	
Live or dead tall standing vosprey, kingfisher, flycatch		r near water offering god	od visibility of open water (e.g.,	
Abundant		☐ Absent	□ Not Applicable	
Other Important Habitat (	Characteristics:			
Underwater banks of fine s	silt and/or clay (beaver, m	nuskrat, otter)		
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable	
Undercut or overhanging b	anks (small mammals, m	nink, weasels, turtles)		
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable	
Vertical sandy banks (bank	swallow, kingfisher)			
Abundant	☐ Present		Not Applicable	
Mud flats				
☐ Abundant		☐ Absent	☐ Not Applicable	
Exposed areas of well-drai	ned, sandy soil suitable f	or turtle nesting		
☐ Abundant	☐ Present		☐ Not Applicable	

Wildlife Dens/Nests (if observed)

	Turtle nesting sites			
	Abundant	Present		□ Not Applicable
	Bank swallow colony(ies)			
	☐ Abundant	☐ Present		☐ Not Applicable
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron
	Den(s) present of	☐ Otter	Mink	Beaver
	Other nests or dens (identify	y species):		
IV.	Connectivity with Adjoini	ng Natural Habitats		
	☐ No direct connections to	o adjacent areas of wildli	fe habitat (little c	connectivity function)
	☐ Limited number of conr	nectors to adjacent areas	of habitat (some	ewhat important for connectivity function)
	Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with un	nimpeded connection to other habitats (high
٧.	Rare Species and MNHES	SP Core Area Habitat De	esignation	
	☐ Core Area 1 ☐ Core	Area 2	a 3 🔲 Core A	Area 4
	Federally listed threate habitat): Northern long-ear		ies habitat (inclu	uding species with known overlapping
	State-listed species ha	bitat (including species v	vith known overla	apping Priority Habitat):
	Brook Snaketail, Matted Sp	oike-sedge, Riffle Snaket	ail, Spine-crown	ed Clubtail, Wapato, Wood Turtle
	Rare species direct observa	ations during current field	surveys:	
VI.	Incidental Direct Wildlife	Observations		
		-		

VII.	Habitat Degradation (identify specific location on bank segment if applicable)
	☐ Evidence of significant levels of dumping
	Evidence of significant erosion or sedimentation problems: side channel eroding into left bank
	Occurrence of invasive plants:  Bittersweet, Japanese knotweed
	Evidence of other human disturbance; describe:
VIII	Restoration Opportunities
	Presence of potential restoration resources:  Coarse woody debris along both banks; good cobble and gravel material for stream and bank restoration/habitat enhancement
	☐ Other restoration opportunities:
	R: Reshape point bar
	L: Log or rock vanes
	Invasive species control
	Revegetation

Bank 4 Plant Species List				
Left bank	Right bank			
boxelder   Acer negundo   tree	boxelder   Acer negundo   tree			
silver maple   Acer saccharinum   tree	silver maple   Acer saccharinum   tree			
Asian bittersweet   Celastrus orbiculatus   vine/liana   *	Asian bittersweet   Celastrus orbiculatus   vine/liana   *			
Japanese knotweed   Fallopia japonica   herb   *	Japanese knotweed   Fallopia japonica   herb   *			
common water-purslane   Ludwigia palustris   herb	Morrow's honeysuckle   Lonicera morrowii   shrub   *			
pale smartweed   Persicaria lapathifolia   herb	pale smartweed   Persicaria lapathifolia   herb			
river grape   Vitis riparia   vine/liana	river grape   Vitis riparia   vine/liana			

<sup>\*</sup>Invasive species


#### **Bank 4 Floodplain Plant Species**

Japanese knotweed	Fallopia japonica	Н
false Soloman's seal	Maianthemum racemosum	Н
Morrow's honeysuckle	Lonicera morrowii	S
white ash	Fraxinus americana	T
boxelder	Acer negundo	T
American elm	Tilia americana	T
river grape	Vitis riparia	V
bishop's goutweed	Aegopodium podagraria	Н
common buckthorn	Rhamnus cathartica	S
privet	Ligustrum vulgare	S
silver maple	Acer saccharinum	T



Bank 4 Stations 9-11. 900-ft downstream of Confluence. After sharp right bend and covering 200 ft of slight right curve in river.

Photos of Bank 4 Area. August 3, 2022







Right bank views, looking downstream

Right bank, Japanese knotweed




Photo in floodplain along left bank near Station 10+00, where side channel that comes from left bank near the Confluence has eroded into the left river bank (main flow channel of side channel stays left and continues to Station 15+00).

	Housatonic ROR R5A Bank 5 Site Name and Evaluation Segment					
	Bank 5: Stations 11-14. 1100-ft downstream of Confluence. 300-ft stretch from Stations 11-14 along left bend Location/Physical Description					
	8/3/22					
		e(s) of Site Visit iny, warm (85 d	t(s) and Data Colle	ction		
			s During Site Visit			
		COM				8/3/22
	Fiel	d Staff Performi	ing Evaluation			Date this form was completed
II.	Site	e Description				
A.	Ban	k Characteriza	ation			
Phy	/sica	al Dimensions	(ft):			
Len	ngth:	300'	Width: 60'	Bank Height:	L 8' R 5'	Slope: L 90% R 40%
Sec	dime	nt / Substrate	composition:			
% 5	Sand	I 50	% Silt 50	% Clay 0		% Gravel/cobble 0
% E	Boul	der/Bedrock 0		% Organic matter 5		
Bar	Do alo	wnstream end		near vertical sandy ba		n, but lower parts are more stable. Thalweg is point bar development. High BEHI and NBS along
B.	Bord	dering Habitat	Types			
We	tland	d			Upland	
	$\boxtimes$	Transitional f	loodplain forest			Northern Hardwoods-Hemlock-White Pine Forest
		High terrace	floodplain forest			Rich mesic forest
		Red maple sv	wamp			Red Oak-Sugar Maple Transition Forest
		Vernal pool				Agricultural fields
		Black ash-red swamp	d maple-tamarac	k calcareous seepage		Cultural grassland
	$\boxtimes$	Deep emerge	ent marsh			Successional northern hardwoods
	$\boxtimes$	Shallow eme	rgent marsh			Spruce-fir-northern hardwood forest
		Shrub swamp	)			Developed/disturbed cover types
		Wet meadow				Other
		Other				
Not	es:	Ero	sional channel c	uts from right bank the	rough to m	narsh/open water to the northwest.

C.	Hydrology								
Stre	eam gradient:	☐ Low Gra	dient	⊠ Mid-Grad	dient		☐ High-Gr	adient	
Deg	gree of overbank fl	looding potentia	l / floodpla	in connectivity					
		annels present ir	n adjacent	floodplain	$\boxtimes$	Topog	graphic break	s present in	the riverbank
	☐ Channel is de	eeply incised	☐ Mode	erately incised		$\boxtimes$	Somewhat in	cised	☐ Not incised
Deg	gree of Water leve	I fluctuation (est	imated ver	tical difference	fror	n mear	n low water to	):	
	Bankfull indicator	s: 3 ft	Top of ba	ank slope: 5-8	ft	Floo	odplain surfac	e: 6-8 ft	
Fie	ld-Derived Evidend	ce of Hydrologic	: Condition:	S					
		line impressed	on bank		$\boxtimes$	Chan	ges in charact	ter of soil	
	⊠ Bed and bank	KS				Water	staining		
	Shelving				$\boxtimes$	Veget	ation matted	down, bent	or absent
		litter and debris)	)		$\boxtimes$	Chang	ge in plant co	mmunity	
	Scour and/or     Scour and/or	Deposition			$\boxtimes$	Des	truction of ter	restrial vege	etation
	☐ Line of mud o	or silt on tree tru	nks/vegeta	tion		Debris	s stuck on ove	erhanging tr	ee limbs
	Other								
Fie	ld-Derived Evidend	ce of Bankfull St	tage/Disch	arge Water					
	Scour line					Recer	nt changes to	river bends	/meanders
	□ Depositional	bench (active ch	nannel)		$\boxtimes$	Under	rcuts		
	□ Depositional	point bar				Staini	ng of rocks		
	☐ Depositional	island			$\boxtimes$	Top o	f point bars		
	☐ Middle bench	for braided rive	ers		$\boxtimes$	Lower	r limits in pere	ennial vegeta	ation
	□ Break in slope	e of banks (floo	dplain brea	ık)					
	Other:								
D.	Inventory (Plant C	Community)							
Rig	ht Bank								
	Total % Cover:	80 Bank Vegetation	on	50 Overhanging Ve	getati	on	100 Riparian Veget	ation	
	Percent Cover of	Bank and Over	hanging St	ream Vegetat	on b	y Strat	a		
	60 Trees (> 20')	40 Shrubs (< 20')	<u>30</u>	ndy vines	0 Mo	sses	<u>75</u> Herba	aceous	_

Left Bank 90 100 75 Total % Cover: Bank Vegetation Overhanging Vegetation Riparian Vegetation Percent Cover of Bank and Overhanging Stream Vegetation by Strata 50 50 Herbaceous Trees (> 20') Shrubs (< 20') Woody vines Mosses Percent Cover of Riparian Vegetation by Strata Shrubs (< 20') Trees (> 20') Woody vines Mosses Herbaceous Bank and overhanging vegetation plant list (species that comprise 10% or more of the vegetative cover in each strata, or any amount of an invasive plant species; "\*" designates a dominant plant species for the strata): Strata Plant Species Strata Plant Species Japanese knotweed (P. cuspidatum) Vine Bittersweet (Celastrus scandens) Herb Cocklebur (Xanthium orientale) Box elder (Acer negundo) Herb Tree Shrub Red osier dogwood (Cornus sericea) Tree Silver maple (Acer saccharinum) Riparian vegetation plant list (species that comprise 10% or more of the vegetative cover in each strata, or any amount of an invasive plant species; "\*" designates a dominant plant species for the strata): Ostrich fern (Matteuccia struthiopteris)\* Vine Bittersweet (Celastrus scandens) Herb Common buckthorn (Rhamnus cathartica) Herb Coneflower (Rudbeckia laciniata) Sapling Shrub Morrow's honeysuckle (Lonicera morrowil) Tree Box elder (Acer negundo) Strata: T=Tree, S=Shrub, L=Liana (vine), H=Herb (Includes grasses, herbs, pterophytes [ferns], lichens, woody seedlings, and mosses) Notes: See attached tables for plant species lists. Notes: Right bank and adjacent vegetation varies as it runs along marsh and then steep upland forest at bend. Multistem silver maple at Station 11+80 crosses from left bank to right bank and is significant habitat feature III. Important Habitat Features Wildlife Food Important wetland/aquatic food plants □ Present Abundant Absent Not Applicable Important upland food plants (hard mast and fruit/berry producers) Present | Abundant Absent Not Applicable Cover/Perches/Basking/Denning/Nesting Habitat Trees (live or dead) > 30" DBH Abundant  $\square$ Present Absent Not Applicable

Standing dead trees (potential for cavities and perches)

☐ Abundant	□ Present	☐ Absent	□ Not Applicable
Tree cavities in trunks or lin	nbs		
Abundant	□ Present	☐ Absent	☐ Not Applicable
Small mammal burrows:			
Abundant	□ Present	☐ Absent	☐ Not Applicable
Dense herbaceous cover (v	voles, small mammals, a	mphibians & reptiles)	
Abundant	□ Aba	sent	t Applicable
Large woody debris on the	ground (small mammals	, mink, amphibians & rep	otiles)
	Present	☐ Absent	□ Not Applicable
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)
	Present	☐ Absent	□ Not Applicable
Overhanging branches at o duck, mink, raccoon)	or within 1 m above the w	ater's surface (turtles, sr	nakes, frogs, wading birds, wood
☐ Abundant	□ Present	Absent	□ Not Applicable
Rock piles, crevices, or hol	low logs suitable for vario	ous mammals (otter, min	k, porcupine, racoon):
Abundant	□ Present	□Absent	□ Not Applicable
Live or dead tall standing voosprey, kingfisher, flycatche		near water offering goo	d visibility of open water (e.g.,
	Present	Absent	□ Not Applicable
Other Important Habitat C	Characteristics:		
Underwater banks of fine si	ilt and/or clay (beaver, m	uskrat, otter)	
Abundant	□ Present	☐ Absent	□ Not Applicable
Undercut or overhanging ba	anks (small mammals, m	ink, weasels, turtles)	
Abundant	□ Present	☐ Absent	□ Not Applicable
Vertical sandy banks (bank	swallow, kingfisher)		
	Present	☐ Absent ☐	Not Applicable
Mud flats			
Abundant	□ Present	☐ Absent	☐ Not Applicable
Exposed areas of well-drain	ned, sandy soil suitable f	or turtle nesting	
Abundant		☐ Absent	□ Not Applicable

#### Wildlife Dens/Nests (if observed)

	Turtle nesting sites			
	Abundant	☐ Present		□ Not Applicable
	Bank swallow colony(ies)			
	Abundant	□ Present	☐ Absent	☐ Not Applicable
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron
	Den(s) present of	☐ Otter	Mink	Beaver
	Other nests or dens (identify	y species): 3'x2' cavern	in right bank nea	ar Station 13+00
IV.	Connectivity with Adjoining	ng Natural Habitats		
	☐ No direct connections to	o adjacent areas of wildli	ife habitat (little d	connectivity function)
	Limited number of conr	nectors to adjacent areas	of habitat (some	ewhat important for connectivity function)
	□ Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with ur	nimpeded connection to other habitats (high
٧.	Rare Species and MNHES	SP Core Area Habitat De	esignation	
	☐ Core Area 1 ⊠ Core	Area 2	a 3 🔲 Core A	Area 4
	□ Federally listed threate habitat): Northern long-ear		cies habitat (inclu	uding species with known overlapping
	<u> </u>	abitat (including species v		, , , , , , , , , , , , , , , , , , ,
	American Bittern, Brook Sn Turtle	naketail, Matted Spike-se	dge, Riffle Snak	etail, Spine-crowned Clubtail, Wapato, Wood
	Rare species direct observa	ations during current field	l surveys:	
VI.	Incidental Direct Wildlife			
	Belted kingfisher			
	Deer tracks			
	Raccoon tracks			
	Spotted sandpiper			
	Song sparrow			

	Green frog				
	Wood pewee				
VII.	Habitat Degradation (identify specific location on b	ank segment if applicable)			
	☐ Evidence of significant levels of dumping				
		oblems			
	○ Occurrence of invasive plants:   Japanese knotweed, Morrow's honeysuckle, bishop's goutweed				
	Evidence of other human disturbance; describe:				
VIII	Restoration Opportunities				
	Presence of potential restoration resources (e.g., boulders, large trees or woody debris, root wad material for bank stabilization or hibernacula, plant propagation source material). Identify specific items:  Coarse woody debris along both banks, including root wads				
	Other restoration opportunities:				
	R: Compartmentalized Fill; Vegetated riprap; Log or	rock vanes; Root wads			
	L: Compartmentalized Fill; Reshape point bar				
	Invasive species control				
	Revegetation				

Bank 5 Plant	Species List
<u>Left bank</u>	Right bank
boxelder   Acer negundo   tree	boxelder   Acer negundo   tree
silver maple   Acer saccharinum   tree	silver maple   Acer saccharinum   tree
bishop's goutweed   Aegopodium podagraria   herb   *	Devil's beggar-ticks   Bidens frondosa   herb
red-osier dogwood   Cornus sericea   shrub	red-osier dogwood   Cornus sericea   shrub
Japanese knotweed   Fallopia japonica   herb   *	Japanese knotweed   Fallopia japonica   herb   *
green ash   Fraxinus pennsylvanica   tree	common water-purslane   Ludwigia palustris   herb
Morrow's honeysuckle   Lonicera morrowii   shrub   *	ostrich fern   Matteuccia struthiopteris   herb
common water-purslane   Ludwigia palustris   herb	pale smartweed   Persicaria lapathifolia   herb
common buckthorn   Rhamnus cathartica   herb   *	blue vervain   Verbena hastata   herb
	rough cocklebur   Xanthium strumarium   herb


<sup>\*</sup>Invasive species

#### Bank 5 Floodplain Plant Species

bishop's goutweed	Aegopodium podagraria	Н
common buckthorn	Rhamnus cathartica	S
privet	Ligustrum vulgare	S
silver maple	Acer saccharinum	T
boxelder	Acer negundo	T



Bank 5: Stations 11-14. 1100-ft downstream of Confluence. 300-ft stretch from Stations 11-14 along sharp left bend





I.	Ge	neral Informat	tion					
	Housatonic ROR R5A Bank 6 Site Name and Evaluation Segment							
	Bank 6: Stations 15-19. 1500-ft downstream of Confluence. 400-ft stretch below multiple meanders and inflow from side channel.							
	Location/Physical Description							
	8/3/ Dat		(s) and Data Collection					
	Sun	ny, warm (85 de	egrees)					
		ather Conditions COM	During Site Visit				8/3/22	
		d Staff Performi	ng Evaluation				Date this form was comple	ted
II.	Site	e Description						
A.	Ban	k Characteriza	ation					
Phy	/sica	al Dimensions	(ft):					
Ler	ngth:	400'	Width: 60-70'	Bank Height: R	4' L 6'	Slope: L 90-	-120% R 30%	
Sed	dime	ent / Substrate	composition:					
% \$	Sano	1 40	% Silt 50	% Clay 0		% Gravel/cobble 1	0	
% E	3oul	der/Bedrock 0	% Oı	rganic matter				
Bar	Left	bank is mostly	ved erosional condition y vertical, with some use mostly low – modera	indercutting benea			g. Thalweg is along left b nannel bar at 18+50.	oank.
B.	Bord	dering Habitat	Types					
We	tland	d			Upland			
	$\boxtimes$	Transitional fl	oodplain forest			Northern Hardwoo Forest	ds-Hemlock-White Pine	
		High terrace f	loodplain forest			Rich mesic forest		
		Red maple sv	vamp			Red Oak-Sugar Ma	aple Transition Forest	
		Vernal pool				Agricultural fields		
		Black ash-red swamp	l maple-tamarack calc	areous seepage		Cultural grassland		
		Deep emerge	ent marsh			Successional north	nern hardwoods	
		Shallow emer	gent marsh			Spruce-fir-northern	h hardwood forest	
		Shrub swamp				Developed/disturbe	ed cover types	
		Wet meadow				Other		
		Other						
Not	es:	Stee	ep upland hillside bord	ders right bank. T	FF along	left bank.		

C.	Hydrology						
Stre	eam gradient:	☐ Low Gra	dient 🛛 Mid-C	Gradient	☐ High-Gradie	ent	
Deg	gree of overbank	flooding potentia	/ floodplain connecti	vity: Lov	v hydrologic connectiv	ity here	
	⊠ High-flow ch	annels present in	adjacent floodplain	⊠ 7	Topographic breaks pro	esent in the riverbank (right)	
	☐ Channel is o	deeply incised		sed	☐ Somewhat incise	d Not incised	
Deg	gree of Water lev	el fluctuation (est	imated vertical differe	ence from	mean low water to):		
	Bankfull indicate	ors: 3 ft	Top of bank slope:	5-6 ft	Floodplain surface: 6	-8 ft	
Fiel	d-Derived Evide	nce of Hydrologic	Conditions				
		al line impressed	on bank	$\boxtimes$ (	Changes in character of	of soil	
	Bed and ba	nks		□ V	Vater staining		
	Shelving				/egetation matted dow	n, bent or absent	
	☐ Wrack lines	(litter and debris)		$\boxtimes$ (	Change in plant comm	unity	
	Scour and/c     Scour	or Deposition			Destruction of terrestria	al vegetation	
	☐ Line of mud	or silt on tree tru	nks/vegetation		Debris stuck on overha	nging tree limbs	
	Other						
Fiel	d-Derived Evide	nce of Bankfull St	age/Discharge Water	r			
				□ F	Recent changes to rive	r bends/meanders	
	□ Depositiona	ıl bench (active ch	annel)	⊠ ι	Indercuts		
	□ Depositiona	l point bar			Staining of rocks		
	□ Depositiona	ıl island		⊠ 7	Top of point bars		
	☐ Middle bend	ch for braided rive	rs	⊠ L	ower limits in perennia	al vegetation	
		pe of banks (flood	dplain break)				
	Other						
D.	Inventory (Plant	Community)					
Rig	ht Bank						
	Total % Cover:	75 Bank Vegetation	on 75 Overhangin	g Vegetatior	100 Riparian Vegetation		
	Percent Cover of	of Bank and Over	hanging Stream Vege	etation by	Strata		
	50 Trees (> 20')	25 Shrubs (< 20')	25 Woody vines	<u>0</u>	75 Herbaceo	us	

Left Bank 60 90 60 Total % Cover: Bank Vegetation Overhanging Vegetation Riparian Vegetation Percent Cover of Bank and Overhanging Stream Vegetation by Strata 50 25 Trees (> 20') Shrubs (< 20') Woody vines Mosses Herbaceous Percent Cover of Riparian Vegetation by Strata Shrubs (< 20') Trees (> 20') Woody vines Mosses Herbaceous Bank and overhanging vegetation plant list (species that comprise 10% or more of the vegetative cover in each strata, or any amount of an invasive plant species; "\*" designates a dominant plant species for the strata): Strata Plant Species Strata Plant Species Water-pepper (Persicaria hydropiper) Vine Riverbank grape (Vitis riparia) Herb Forget-me-not (Myosotis scorpioides) Box elder (Acer negundo) Herb Tree Shrub Morrow's honeysuckle (Lonicera morrowii) Tree Silver maple (Acer saccharinum) Riparian vegetation plant list (species that comprise 10% or more of the vegetative cover in each strata, or any amount of an invasive plant species; "\*" designates a dominant plant species for the strata): Ostrich fern (Matteuccia struthiopteris)\* Vine Bittersweet (Celastrus scandens) Herb Common buckthorn (Rhamnus cathartica) Herb Coneflower (Rudbeckia laciniata) Sapling Shrub Morrow's honeysuckle (Lonicera morrowii) Box elder (Acer negundo) Tree Strata: T=Tree, S=Shrub, L=Liana (vine), H=Herb (Includes grasses, herbs, pterophytes [ferns], lichens, woody seedlings, and mosses) Notes: See attached tables for plant species lists. III. Important Habitat Features **Wildlife Food** Important wetland/aquatic food plants Abundant □ Present Absent Not Applicable Important upland food plants (hard mast and fruit/berry producers) Abundant Present Absent ■ Not Applicable Cover/Perches/Basking/Denning/Nesting Habitat Trees (live or dead) > 30" DBH Abundant  $\boxtimes$ Absent ■ Not Applicable Present Standing dead trees (potential for cavities and perches) □ Present Abundant Absent Not Applicable

Wildlife Dens/Nests (if observed)

Tree cavities in trunks or lin	nbs					
Abundant	□ Present	□Absent	□ Not Applicable			
Small mammal burrows:						
Abundant	□ Present	☐ Absent	☐ Not Applicable			
Dense herbaceous cover (v	voles, small mammals, a	mphibians & reptiles)				
Abundant	□ Ab     □ Ab	sent	ot Applicable			
Large woody debris on the	ground (small mammals	, mink, amphibians & re	ptiles)			
Abundant	□ Present	☐ Absent	☐ Not Applicable			
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wat	er's surface (turtles, snakes, frogs)			
Abundant	□ Present	☐ Absent	☐ Not Applicable			
Overhanging branches at o duck, mink, raccoon)	r within 1 m above the w	rater's surface (turtles, s	nakes, frogs, wading birds, wood			
Abundant	□ Present	☐ Absent	□ Not Applicable			
Rock piles, crevices, or hollow logs suitable for various mammals (otter, mink, porcupine, racoon):						
Abundant	□ Present	☐ Absent	☐ Not Applicable			
Live or dead tall standing voosprey, kingfisher, flycatche		r near water offering goo	od visibility of open water (e.g.,			
	Present	☐ Absent	□ Not Applicable			
Other Important Habitat C	Characteristics:					
Underwater banks of fine si	ilt and/or clay (beaver, m	uskrat, otter)				
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable			
Undercut or overhanging ba	anks (small mammals, m	nink, weasels, turtles)				
Abundant	□ Present	☐ Absent	☐ Not Applicable			
Vertical sandy banks (bank swallow, kingfisher)						
Abundant	☐ Present		Not Applicable			
Mud flats						
Abundant	□ Present	☐ Absent	☐ Not Applicable			
Exposed areas of well-drained, sandy soil suitable for turtle nesting						
Abundant	Present		□ Not Applicable			

	Turtle nesting sites						
	☐ Abundant	☐ Present		□ Not Applicable			
	Bank swallow colony(ies)						
	Abundant	☐ Present		☐ Not Applicable			
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron			
	Den(s) present of	☐ Otter	☐ Mink	☐ Beaver			
	Other nests or dens (identify	y species):					
IV.	Connectivity with Adjoini	ng Natural Habitats					
	☐ No direct connections to	o adjacent areas of wildli	fe habitat (little o	connectivity function)			
	☐ Limited number of conr	nectors to adjacent areas	of habitat (some	ewhat important for connectivity function)			
	Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with un	impeded connection to other habitats (high			
٧.	Rare Species and MNHES	SP Core Area Habitat De	esignation				
	☐ Core Area 1 ☐ Core Area 2 ☐ Core Area 3 ☐ Core Area 4						
	☐ Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat						
	, 3						
	State-listed species ha	ubitat (including species v	vith known overla	apping Priority Habitat):			
	Brook Snaketail, Matted Sp	oike-sedge, Riffle Snaket	ail, Spine-crown	ed Clubtail, Wapato, Wood Turtle			
	Rare species direct observa	ations during current field	surveys:				
VI.	Incidental Direct Wildlife	Observations					
	Great blue heron						
	Deer tracks						
	Raccoon tracks						
	Spotted sandpiper						
	Mussels (Elliptio or Eastern	ı Lampmussel)					
	Green frog						

Dragonflies						
VII. Habitat Degradation (identify specific location on b	ank segment if applicable)					
Evidence of significant levels of dumping	Evidence of significant levels of dumping					
Evidence of significant erosion or sedimentation problems						
○ Occurrence of invasive plants:   Bittersweet common on both banks at upper levels as well as in floodplain; Morrow's honeysuckle, common buckthorn, Japanese knotweed, bishop's goutweed, forget-me-knots						
Evidence of other human disturbance; describe:						
VIII.Restoration Opportunities						
☑ Presence of potential restoration resources (e.g., beank stabilization or hibernacula, plant propagation so Coarse woody debris along both banks, large trees, continuous.						
R: Coir matting;						
L: Grade bank/Coir matting; Bank spurs; Compartme	entalized fill					
Invasive species control						
Revegetation						

Bank 6 Plant Species List			
<u>Left bank</u>	Right bank		
bishop's goutweed   Aegopodium podagraria   herb   *	boxelder   Acer negundo   tree		
Asian bittersweet   Celastrus orbiculatus   vine/liana   *	Devil's beggar-ticks   Bidens frondosa   herb		
Japanese knotweed   Fallopia japonica   herb   *	northern catalpa   Catalpa speciosa   tree		
Morrow's honeysuckle   Lonicera morrowii   shrub   *	Asian bittersweet   Celastrus orbiculatus   vine/liana   *		
ostrich fern   Matteuccia struthiopteris   herb	red-osier dogwood   Cornus sericea   shrub		
common buckthorn   Rhamnus cathartica   herb   *	Japanese knotweed   Fallopia japonica   herb   *		
American elm   Ulmus americana   tree	Canada wood nettle   Laportea canadensis   herb		
river grape   Vitis riparia   vine/liana	rice cut-grass   Leersia oryzoides   herb		
	ostrich fern   Matteuccia struthiopteris   herb		
	water forget-me-not   Myosotis scorpioides   herb   *		
	sensitive fern   Onoclea sensibilis   herb		
	water-pepper smartweed   Persicaria hydropiper   herb		
	pale smartweed   Persicaria lapathifolia   herb		
	northern red oak   Quercus rubra   tree		
	green-headed coneflower   Rudbeckia laciniata   herb		
	blue vervain   Verbena hastata   herb		
	river grape   Vitis riparia   vine/liana		
	rough cocklebur   Xanthium strumarium   herb		

<sup>\*</sup>Invasive species

### **Bank 6 Floodplain Plant Species**

bishop's goutweed	Aegopodium podagraria	Н
common buckthorn	Rhamnus cathartica	S
privet	Ligustrum vulgare	S
silver maple	Acer saccharinum	T
boxelder	Acer negundo	Т
ostrich fern	Matteuccia struthiopteris	Н
Morrow's honeysuckle	Lonicera morrowii	S
Eastern cottonwood	Populus deltoides	T
American elm	Ulmus americana	Т
dame's-rocket	Hesperis matronalis	Н
green-headed coneflower	Rudbeckia laciniata	Н
enchanter's-nightshade	Circaea canadensis	Н
jumpseed	Persicaria virginiana	Н
Virginia creeper	Parthenocissus quinquefolia	V
virgin's-bower	Clematis virginiana	V



Bank 6 area: Station 15-19. 400' along Right bend at inflow from overflow channel on left bank followed by straight run.





Left bank, looking at location where overflow channel discharges into river at Station 15+00



Looking downstream through Bank 6 at mid-bar



Left bank



Left bank: undercut tree root system



Right bank at Station 17+00; red oaks

I.	General Information						
	Housatonic ROR R5A Bank 7 Site Name and Evaluation Segment						
	Bank 7: Stations 22-24; 2200 feet below Confluence; 200-ft straight run before sharp left bend just above Morewood Lake tributary confluence.  Location/Physical Description						
	8/4/22 Date(s) of Site Visit(s) and Data Collection						
	Weather Conditions During Site Visit AECOM						
		d Staff Performi	ng Evaluation			Date	e this form was completed
II.	Site	Description					
A.	Banl	k Characteriza	ation				
Phy	/sica	l Dimensions	(ft):				
Len	gth:	200'	Width: 70'	Bank Height: R	4-5' L 6	Slope: R 50%	L 90-100%
Sec	dime	nt / Substrate	composition:				
% 5	Sand	40	% Silt 40	% Clay		% Gravel/cobble 20	
% E	Bould	der/Bedrock	9	% Organic matter <5			
	Som	ne cut bank an				ow - moderate BEHI and	d NBS). Right bank has
B.	Bord	lering Habitat	Types				
We	tland	i			Upland		
		Transitional fl	oodplain forest			Northern Hardwoods-Forest	Hemlock-White Pine
		High terrace f	loodplain forest			Rich mesic forest	
		Red maple sv	vamp			Red Oak-Sugar Maple	Transition Forest
		Vernal pool				Agricultural fields	
		Black ash-red swamp	l maple-tamarack	calcareous seepage		Cultural grassland	
		Deep emerge	ent marsh			Successional northern	hardwoods
		Shallow emer	gent marsh			Spruce-fir-northern har	rdwood forest
		Shrub swamp	)		$\boxtimes$	Developed/disturbed of	over types
		Wet meadow				Other	
		Other					
Not	es:						

C.	Hydrology							
Stre	eam gradient:	☐ Low Gra	dient	⊠ Mid-Grad	dient		☐ High-Gradient	
Deg	gree of overbank f	looding potentia	l / floodplain	connectivity	•			
		annels present ir	n adjacent flo	oodplain		Topog	raphic breaks preser	nt in the riverbank
	☐ Channel is de	eeply incised	⊠ Moder	rately incised			Somewhat incised	☐ Not incised
Deg	gree of Water leve	I fluctuation (est	imated verti	cal difference	e fron	n mean	low water to):	
	Bankfull indicators: 3 ft Top of bank slope: 4-6 ft Floodplain surface: 4-6 ft							ft
Fiel	Field-Derived Evidence of Hydrologic Conditions							
		line impressed	on bank		$\boxtimes$	Chang	ges in character of so	pil
	Bed and banl	ks				Water	staining	
	Shelving				$\boxtimes$	Vegeta	ation matted down, b	pent or absent
		litter and debris)	1		$\boxtimes$	Change in plant community		
	Scour and/or     Scour and/or	Deposition				Destru	iction of terrestrial ve	egetation
	Line of mud of	or silt on tree tru	nks/vegetati	on		Debris	stuck on overhangir	ng tree limbs
	Other							
Fiel	d-Derived Eviden	ce of Bankfull St	age/Discha	rge Water				
	Scour line					Recen	t changes to river be	ends/meanders
	□ Depositional	bench (active ch	nannel)		$\boxtimes$	Undercuts		
	□ Depositional	point bar				Staining of rocks		
	☐ Depositional	island				Top of	point bars	
	☐ Middle bench	for braided rive	rs			Lower	limits in perennial ve	egetation
		e of banks (flood	dplain break	)				
	Other							
D.	Inventory (Plant 0	Community)						
Rig	ht Bank							
	Total % Cover:	80 Bank Vegetation		40 Overhanging Ve	egetati	 on	90 Riparian Vegetation	
	Percent Cover of	Bank and Over	hanging Str	eam Vegetat	ion b	y Strata	а	
	60 Trees (> 20')	50 Shrubs (< 20')	<u>30</u>	dv vines	0 Mo	sses	75 Herbaceous	

Left Bank

Total % Cover:	70	60		90
	Bank Vegetation			
	of Bank and Overhang	•	•	
75 Trees (> 20')	50 Shrubs (< 20')	25 Woody vines	0 Mosses	<u>25</u> Herbaceous
, ,	parian Vegetation by S			
70 Trees (> 20')	70 Shrubs (< 20')	25 Woody vines	0 Mosses	<u>75</u> Herbaceous
Bank and overhangi	ing vegetation plant lis	t (species that cor	nprise 10% o	or more of the vegetative cover in each dominant plant species for the strata):
Strata Plar	nt Species		Strata	Plant Species
Riparian vegeta	tion plant list (species	that comprise 10%	 % or more of	the vegetative cover in each strata, or any
amount of an in	vasive plant species; "	*" designates a do	minant plant	t species for the strata):
Strata: T=Tree, S=S seedlings, and r		H=Herb (Includes	grasses, he	rbs, pterophytes [ferns], lichens, woody
	d tables for plant spec	ies lists		
Notes: Steep upland	d wooded slope above	e right bank.		
III. Important Habi	tat Features			
Wildlife Food				
Important wetlar	nd/aquatic food plants			
•		. –	<b>A.</b> 1	
☐ Abundant	⊠ Prese	ent	Absent	☐ Not Applicable
Important upland	d food plants (hard ma	st and fruit/berry p	oroducers)	
☐ Abundant	⊠ Prese	ent 🗌	Absent	□ Not Applicable
Cover/Perches	/Basking/Denning/Ne	esting Habitat		
Trees (live or de	ead) > 30" DBH			
☐ Abundant	∑ Prese	ent $\square$	Absent	□ Not Applicable
_	rees (notential for cavi	_		

☐ Abundant	☐ Present		□ Not Applicable					
Tree cavities in trunks or lin	nbs							
Abundant	□ Present	☐ Absent	☐ Not Applicable					
Small mammal burrows:	Small mammal burrows:							
Abundant	□ Present	☐ Absent	☐ Not Applicable					
Dense herbaceous cover (v	voles, small mammals, ar	mphibians & reptiles)						
Abundant	□ Present	Absent	☐ Not Applicable					
Large woody debris on the	ground (small mammals	, mink, amphibians & rep	otiles)					
Abundant	□ Present	Absent	□ Not Applicable					
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)					
Abundant	□ Present	Absent	□ Not Applicable					
Overhanging branches at or within 1 m above the water's surface (turtles, snakes, frogs, wading birds, wood duck, mink, raccoon)								
Abundant	□ Present	Absent	☐ Not Applicable					
Rock piles, crevices, or holl	low logs suitable for vario	ous mammals (otter, min	k, porcupine, racoon):					
Abundant	□ Present	Absent	□ Not Applicable					
Live or dead tall standing veosprey, kingfisher, flycatche		near water offering goo	d visibility of open water (e.g.,					
	Present	Absent	□ Not Applicable					
Other Important Habitat C	Characteristics:							
Underwater banks of fine si	ilt and/or clay (beaver, m	uskrat, otter)						
Abundant	□ Present	Absent	□ Not Applicable					
Undercut or overhanging banks (small mammals, mink, weasels, turtles)								
Abundant	□ Present	Absent	□ Not Applicable					
Vertical sandy banks (bank swallow, kingfisher)								
Abundant	Present		Not Applicable					
Mud flats								
Abundant	□ Present	Absent	☐ Not Applicable					
Exposed areas of well-drain	Exposed areas of well-drained, sandy soil suitable for turtle nesting							
☐ Abundant	☐ Present		□ Not Applicable					

### Wildlife Dens/Nests (if observed)

	Turtle nesting sites						
	Abundant	Present		☐ Not Applicable			
	Bank swallow colony(ies)						
	☐ Abundant	☐ Present		☐ Not Applicable			
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron			
	Den(s) present of	☐ Otter	☐ Mink	☐ Beaver			
	Other nests or dens (identify	y species):					
IV.	V. Connectivity with Adjoining Natural Habitats						
	☐ No direct connections to adjacent areas of wildlife habitat (little connectivity function)						
	☐ Limited number of connectors to adjacent areas of habitat (somewhat important for connectivity function)						
	⊠ Riverbank is embedded in a large area of natural habitat with unimpeded connection to other habitats (high connectivity function)						
V.	Rare Species and MNHES	SP Core Area Habitat De	esignation				
	☐ Core Area 1 ☐ Core	Area 2	a 3 🔲 Core A	Area 4			
	$\boxtimes$ Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat						
	•	bitat (including species v		· · · · · · · · · · · · · · · · · · ·			
	Brook Snaketail, Matted Sp	oike-sedge, Riffle Snaket	ail, Spine-crown	ed Clubtail, Wapato, Wood Turtle			
	Rare species direct observa	ations during current field	surveys:				
VI.	Incidental Direct Wildlife	Observations					
	Green frogs						
	Racoon tracks						

	eral Electric Housatonic Rest of River n RB-1: Riverbank Habitat Inventory Form					
VII. I	Habitat Degradation (identify specific location on b	ank segment if applicable)				
[	Evidence of significant levels of dumping					
[	Evidence of significant erosion or sedimentation pr	roblems				
	○ Occurrence of invasive plants:     Japanese knotweed, bittersweet, common buckthorn, forget-me-not					
	⊠ Evidence of other human disturbance; describe: Potential	ower line right-of-way crosses between Stations 23 - 24.				
VIII.F	Restoration Opportunities					
k	Presence of potential restoration resources (e.g., boank stabilization or hibernacula, plant propagation sources woody debris, Large trees, Cobbles	ooulders, large trees or woody debris, root wad material for urce material). Identify specific items:				
[	Other restoration opportunities:					
	R: Grade bank/Coir matting; Compartmentalized fill; I	Bank spurs				
	L: Grade bank/Coir matting; Compartmentalized fill; F	Reshape point bar				
	Invasive species control					
	Revegetation					

Bank 7 Plant Species List					
Left bank	Right bank				
boxelder   Acer negundo   tree	yellow birch   Betula alleghaniensis   tree				
rice cut-grass   Leersia oryzoides   herb	river birch   Betula nigra   tree				
ostrich fern   Matteuccia struthiopteris   herb	Devil's beggar-ticks   Bidens frondosa   herb				
sensitive fern   Onoclea sensibilis   herb	Asian bittersweet   Celastrus orbiculatus   vine/liana   *				
cinnamon fern   Osmunda cinnamomea   herb	spotted Joe-Pye weed   Eupatorium maculatum   herb				
common buckthorn   Rhamnus cathartica   herb   *	Japanese knotweed   Fallopia japonica   herb   *				
poison-ivy   Toxicodendron radicans   liana/vine	ostrich fern   Matteuccia struthiopteris   herb				
stinging nettle   Urtica dioica   herb	water forget-me-not   Myosotis scorpioides   herb   *				
river grape   Vitis riparia   vine/liana	sensitive fern   Onoclea sensibilis   herb				
	cinnamon fern   Osmunda cinnamomea   herb				
	Virgini-creeper   Parthenocissus quinquefolia   vine/liana				
	false water-pepper smartweed   Persicaria hydropiperoides   herb				
	black oak   Quercus velutina   tree				
	eastern hemlock   Tsuga canadensis   tree				
	American elm   Ulmus americana   tree				

<sup>\*</sup>Invasive species

**Bank 7 Floodplain Plant Species** 

ostrich fern	Matteuccia struthioptera	Н
Virginia creeper	Parthenocissus quinquefolia	V
spotted Joe-Pye weed	Eupatorium maculatum	Н
bishop's goutweed	Aegopodium podagraria	Н
Jerusalem artichoke	Helianthus tuberosus	Н
Canada goldenrod	Solidago canadensis	Н
Morrow's honeysuckle	Lonicera morrowii	S
silver maple	Acer saccharinum	Т
American linden	Tilia americana	Т
virgin's bower	Clematis virginiana	Н
common buckthorn	Rhamnus cathartica	S
boxelder	Acer negundo	S
cinnamon fern	Osmunda cinnamomea	Н
jumpseed	Persicaria virginiana	Н
Asian bittersweet	Celastrus orbiculatus	V



Bank 7: Stations 22-24. 200-ft Straight run before left bend

Photos of Bank 7 area. August 4, 2022. Left bank Left bank Left bank (left side) to right bank. Right bank CONT. N. W. Right bank at Station 24+20; inlet from Morewood Lake Right bank

I.	Gei	neral Informat	tion							
	Housatonic ROR R5A Bank 8 Site Name and Evaluation Segment									
	Bank 8: Stations 25-28: 300-ft stretch at left bend below Morewood Lake tributary into straight run Location/Physical Description									
	8/4/22 Date(s) of Site Visit(s) and Data Collection									
	Weather Conditions During Site Visit									
		COM d Staff Performi	ng Evaluation			Date this form was completed				
	0:4	. D								
		e Description								
A.	Ban	k Characteriza	ition							
Phy	/sica	al Dimensions	(ft):							
Len	gth:	300'	Width: 70'	Bank Height: R 6	6' L 4-5'	Slope: R 90% L 50%				
Sec	dime	nt / Substrate	composition:							
% 5	Sanc	I 30	% Silt 50	% Clay 0		% Gravel/cobble 20				
% E	Boul	der/Bedrock	0	% Organic matter						
Bar	Rigl higl	nt bank starts	3S). Left bank is s	slumping bank with sar		ding embankment above floodplain (moderate – erate BEHI and NBS). Thalweg moves to right				
B.	Bord	dering Habitat	Types							
We	tland	t			Upland					
	$\boxtimes$	Transitional fl	oodplain forest			Northern Hardwoods-Hemlock-White Pine Forest				
		High terrace f	loodplain forest			Rich mesic forest				
		Red maple sv	vamp			Red Oak-Sugar Maple Transition Forest				
	$\boxtimes$	Vernal pool				Agricultural fields				
		Black ash-red swamp	l maple-tamarack	calcareous seepage		Cultural grassland				
	☐ Deep emergent marsh			Successional northern hardwoods						
		Shallow emer	gent marsh			Spruce-fir-northern hardwood forest				
		Shrub swamp	)			Developed/disturbed cover types				
		Wet meadow				Other				
		Other								
Not	es.									

C.	Hydrology							
Stre	Stream gradient:							
Deg	gree of overbank f	looding potentia	l / floodplain conne	ectivity				
	☐ High-flow cha	annels present ir	n adjacent floodpla	in 🖂	Topog	graphic breaks present	in the riverbank	
	☐ Channel is de	eeply incised	☐ Moderately in	ncised	$\boxtimes$	Somewhat incised	☐ Not incised	
De	Degree of Water level fluctuation (estimated vertical difference from mean low water to):							
	Bankfull indicators: 3ft Top of bank slope: 4-6ft Floodplain surface: 4-6ft							
Fie	ld-Derived Eviden	ce of Hydrologic	Conditions					
		line impressed	on bank	$\boxtimes$	Chan	ges in character of soil		
		ks			Water	staining		
	Shelving			$\boxtimes$	Veget	ation matted down, be	nt or absent	
		litter and debris)	)	$\boxtimes$	Chan	ge in plant community		
	Scour and/or     Scour and/or	Deposition			Destru	uction of terrestrial veg	getation	
	☐ Line of mud o	or silt on tree tru	nks/vegetation		Debris	s stuck on overhanging	g tree limbs	
	Other							
Fie	ld-Derived Eviden	ce of Bankfull St	age/Discharge Wa	ater				
					Recer	nt changes to river ber	nds/meanders	
	□ Depositional	bench (active ch	nannel)		Under	cuts		
	□ Depositional	point bar			Staini	ng of rocks		
	☐ Depositional	island			Top o	f point bars		
	☐ Middle bench	for braided rive	rs	$\boxtimes$	Lower	· limits in perennial veg	getation	
		e of banks (floo	dplain break)					
	Other							
D.	Inventory (Plant 0	Community)						
Rig	ıht Bank							
	Total % Cover:	60 Bank Vegetation	on 50 Overhar	nging Vegetation	on	100 Riparian Vegetation		
	Percent Cover of	Bank and Over	hanging Stream V	egetation by	y Strat	a		
	40 Trees (> 20')	60 Shrubs (< 20')	20 Woody vines	0 	sses	20 Herbaceous		

Left Bank

	Total % Cover:	75 Bank Vegetation	50 Overhanging	g Vegetation	100 Riparian Vegetation					
	Percent Cover of	of Bank and Overhang	ging Stream Vege	tation by Stra	ata					
	50	30 Shrubs (< 20')	20	0 Mosses	50					
	Trees (> 20')	Shrubs (< 20')	Woody vines	Mosses	Herbaceous					
Per	cent Cover of Rip	parian Vegetation by	Strata							
	75	75 Shrubs (< 20')	30	0 Mosses	60					
			•		Herbaceous					
Baı					or more of the vegetative cover in each dominant plant species for the strata):					
	•	nt Species	nam opooloo,	Strata	Plant Species					
	Sirata Fiai	it Species		Silaia	Flant Species					
				<del></del>						
				<del></del>						
					the vegetative cover in each strata, or any t species for the strata):					
	amount of an in	racivo piant opocios,	accignates a c	iorimiant pian	t openior for the endia).					
				<del></del>						
				·						
Stra	ata:  T=Tree, S=\$ seedlings, and r		H=Herb (Include	s grasses, he	erbs, pterophytes [ferns], lichens, woody					
Not		d tables for plant spec	cies lists							
		a tables for plant oper	noo noto.							
III.	Important Habi	tat Features								
	Wildlife Food									
	Important wetlar	Important wetland/aquatic food plants								
	important wettar	id/aquatic food plants								
	☐ Abundant	⊠ Prese	ent [	Absent	☐ Not Applicable					
	Important upland food plants (hard mast and fruit/berry producers)									
	☐ Abundant	⊠ Prese	ent [	Absent	☐ Not Applicable					
	_			-						
		<u>/Basking/Denning/N</u>	esung nabitat							
	Trees (live or de	ead) > 30" DBH								
	☐ Abundant	⊠ Prese	ent [	Absent	☐ Not Applicable					
	Standing dead to	rees (potential for cav	ities and perches	)						

Abundant	□ Present	☐ Absent	□ Not Applicable						
Tree cavities in trunks or lin	mbs								
☐ Abundant	□ Present	☐ Absent	□ Not Applicable						
Small mammal burrows:									
☐ Abundant	□ Present	☐ Absent	□ Not Applicable						
Dense herbaceous cover (voles, small mammals, amphibians & reptiles)									
Abundant		Absent	☐ Not Applicable						
Large woody debris on the	ground (small mammals	, mink, amphibians & rep	otiles)						
☐ Abundant		Absent	☐ Not Applicable						
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)						
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable						
Overhanging branches at o duck, mink, raccoon)	or within 1 m above the w	rater's surface (turtles, sr	nakes, frogs, wading birds, wood						
☐ Abundant		☐ Absent	☐ Not Applicable						
Rock piles, crevices, or ho	llow logs suitable for vario	ous mammals (otter, min	k, porcupine, racoon):						
Abundant	☐ Present		☐ Not Applicable						
Live or dead tall standing vosprey, kingfisher, flycatch		r near water offering goo	d visibility of open water (e.g.,						
	Present	Absent	□ Not Applicable						
Other Important Habitat (	Characteristics:								
Underwater banks of fine s	silt and/or clay (beaver, m	uskrat, otter)							
Abundant	□ Present	☐ Absent	☐ Not Applicable						
Undercut or overhanging b	anks (small mammals, m	nink, weasels, turtles)							
Abundant	□ Present	☐ Absent	☐ Not Applicable						
Vertical sandy banks (bank swallow, kingfisher)									
Abundant		☐ Absent ☐	Not Applicable						
Mud flats									
Abundant		Absent	☐ Not Applicable						
Exposed areas of well-drained, sandy soil suitable for turtle nesting									
☐ Abundant	□ Present	Absent	□ Not Applicable						

### Wildlife Dens/Nests (if observed)

	Turtle nesting sites			
	Abundant	Present		☐ Not Applicable
	Bank swallow colony(ies)			
	Abundant	□ Present	Absent	□ Not Applicable
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron
	Den(s) present of	☐ Otter	☐ Mink	Beaver
	Other nests or dens (identif	y species):		
IV.	Connectivity with Adjoini	ng Natural Habitats		
	☐ No direct connections t	o adjacent areas of wildl	ife habitat (little	connectivity function)
	Limited number of conr	nectors to adjacent areas	s of habitat (som	ewhat important for connectivity function)
	Riverbank is embedded connectivity function)	d in a large area of natur	al habitat with u	nimpeded connection to other habitats (high
٧.	Rare Species and MNHES	SP Core Area Habitat De	esignation	
	☐ Core Area 1 ☐ Core	Area 2	a 3 🔲 Core	Area 4
	Federally listed threate habitat): Northern long-ear		cies habitat (incl	uding species with known overlapping
	State-listed species ha	abitat (including species v	with known over	lapping Priority Habitat):
	Brook Snaketail, Matted Sp	oike-sedge, Riffle Snaket	tail, Spine-crowr	ned Clubtail, Wapato, Wood Turtle
	Rare species direct observa	ations during current field	d surveys:	
VI.	Incidental Direct Wildlife	Observations		
	Green heron			
	Spotted sandpiper			
	Mallards			
	Catbird			
	Cardinal			

Tennessee warbler	
Green frogs	
VII. Habitat Degradation (identify specific location on ba	ank segment if applicable)
☐ Evidence of significant levels of dumping	
Evidence of significant erosion or sedimentation pro	oblems
○ Occurrence of invasive plants:     Bittersweet, Japanese knotweed, Morrow's honeysuc     □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □	kle
Evidence of other human disturbance; describe:	
VIII.Restoration Opportunities	
☑ Presence of potential restoration resources (e.g., both bank stabilization or hibernacula, plant propagation sour Coarse woody debris, large trees, cobbles	oulders, large trees or woody debris, root wad material for arce material). Identify specific items:
○ Other restoration opportunities:	
R: Vegetated riprap; Log or rock vanes; Grade bank/0	Coir matting
L: Reshape point bar	
Invasive species control	
Revegetation	

Bank 8 Plant Species List						
<u>Left bank</u>	Right bank					
boxelder   Acer negundo   tree	Asian bittersweet   Celastrus orbiculatus   vine/liana   *					
Japanese knotweed   Fallopia japonica   herb   *	hawthorn   Crataegus spp.   shrub/tree					
rice cut-grass   Leersia oryzoides   herb	Morrow's honeysuckle   Lonicera morrowii   shrub   *					
water-pepper smartweed   Persicaria hydropiper   herb						
rough cocklebur   Xanthium strumarium   herb						

<sup>\*</sup>Invasive species


**Bank 8 Floodplain Plant Species** 

Bank of rocapiant riant openes				
European privet	Ligustrum vulgare	S		
river grape	Vitis riparia	V		
moneywort	Lysimachia nummularia	Н		
silky dogwood	Cornus amomum	S		
black ash	Fraxinus nigra	Т		
white ash	Fraxinus americana	Т		
virgin's-bower	Clematis virginiana	Н		
multiflora rose	Rosa multiflora	S		
goldenrod sp.	Solidago sp.	Н		
white avens	Geum canadensis	Н		
red raspberry	Rubus idaeus	S		
jewelweed	Impatiens capensis	Н		
Boxelder	Acer negundo	Т		
Green ash	Fraxinus pennsylvanica	Т		
Boxelder	Acer negundo	S		
Sensitive fern	Onoclea sensibilis	Н		
Burnweed	Erechtites hieraciifolius	Н		
Cinnamon fern	Osmunda cinnamomea	Н		



Bank 8: Stations 25-28. 300-ft stretch at left bend below Morewood Lake tributary into straight run.

Photos of Bank 8 Area. August 4, 2022 Right bank just below Morewood tributary Right bank at Station 26 Left bank at Station 26 Left bank at Station 25 Right bank from left bank Right bank



I.	General Informa	ntion							
	Housatonic ROR R5A Bank 9								
	Site Name and Evaluation Segment  Bank 9: Stations 36-38. 200-ft stretch along a moderate left bend from Station 36-38.  Location/Physical Description  8/4/22								
	Date(s) of Site Visit(s) and Data Collection								
	Weather Condition	s During Site Visit							
	AECOM Field Staff Perform	ing Evaluation				Date this form was completed			
II.	Site Description	1							
A.	Bank Characteriza	ation							
Phy	sical Dimensions	(ft):							
Ler	ngth: 200'	Width: 70'	Bank Height: I	R 6'	L5'	Slope: R 90% L 25%			
Sec	diment / Substrate	composition:							
% 5	Sand 45	% Silt 45	% Clay 0			% Gravel/cobble 10			
% E	Boulder/Bedrock	% C	rganic matter						
Bar		rved erosional condition ively stable. Large he		ave fa	ıllen	across the right bank into river. Thalweg along			
В.	Bordering Habitat	Types							
We	tland			Up	land				
		loodplain forest				Northern Hardwoods-Hemlock-White Pine Forest			
	☐ High terrace	floodplain forest				Rich mesic forest			
	☐ Red maple s	wamp				Red Oak-Sugar Maple Transition Forest			
	✓ Vernal pool					Agricultural fields			
	Black ash-red swamp	d maple-tamarack cal	careous seepage	)		Cultural grassland			
	☐ Deep emergent marsh ☐ Successional northern hardwoods					Successional northern hardwoods			
	☐ Shallow emergent marsh ☐ Spruce-fir-northern hardwood forest					Spruce-fir-northern hardwood forest			
	Shrub swam     Shrub swam	р				Developed/disturbed cover types			
	☐ Wet meadow	I				Other			
	Other								
Not	otes: Steep upland forested hillside along right bank.								

C.	Hydrology						
Stream gradient:							
Deg	Degree of overbank flooding potential / floodplain connectivity						
		annels present ir	n adjacent floodplain		Topographic breaks present in the riverbank		
	☐ Channel is de	eeply incised	☐ Moderately incise	d			
Deg	gree of Water leve	I fluctuation (est	timated vertical difference	e fron	om mean low water to):		
	Bankfull indicator	s: 3ft	Top of bank slope: 5-	6ft	Floodplain surface: 5-6ft		
Fie	ld-Derived Eviden	ce of Hydrologic	Conditions				
		line impressed	on bank	$\boxtimes$	Changes in character of soil		
	⊠ Bed and banl	ks			] Water staining		
	Shelving			$\boxtimes$	Vegetation matted down, bent or absent		
		litter and debris)	)	$\boxtimes$	Change in plant community		
	Scour and/or     Scour and/or	Deposition			Destruction of terrestrial vegetation		
	Line of mud o	or silt on tree tru	nks/vegetation		Debris stuck on overhanging tree limbs		
	Other						
Fie	ld-Derived Eviden	ce of Bankfull St	tage/Discharge Water				
	Scour line				Recent changes to river bends/meanders		
	<ul> <li>☑ Depositional bench (active channel)</li> <li>☑ Depositional point bar</li> <li>☑ Depositional island</li> <li>☐ Middle bench for braided rivers</li> </ul>			$\boxtimes$	Undercuts		
					Staining of rocks		
				$\boxtimes$	Top of point bars		
				$\boxtimes$	Lower limits in perennial vegetation		
	□ Break in slope of banks (floodplain break)						
	Other						
D.	Inventory (Plant 0	Community)					
Rig	Right Bank						
	Total % Cover:	80 Bank Vegetation	on 60 Overhanging V	/egetati	ation Riparian Vegetation		
	Percent Cover of Bank and Overhanging Stream Vegetation by Strata						
	40 Trees (> 20')	40 Shrubs (< 20')	10 Woody vines	0 Mos	) 70 Mosses Herbaceous		

Left Bank

Total % Cove	<sub>r.</sub> 80	30		90
Total % Cove	Bank Vegetation	Overhanging	Vegetation	Riparian Vegetation
Percent Cove	er of Bank and Overhang	ging Stream Veget	ation by Stra	ıta
20 Trees (> 20')	50 Shrubs (< 20')	30 Woody vines	0 Mosses	70 Herbaceous
, ,	Riparian Vegetation by	•	Wiodoco	Holodocodo
75 Trees (> 20')		25 Woody vines	<5 Mosses	<u>75</u> Herbaceous
				or more of the vegetative cover in each dominant plant species for the strata):
_	lant Species	mant species, u	Strata	Plant Species
Ottata 1	iant opecies		Ottata	riant opecies
Riparian vege	etation plant list (species	that comprise 10	% or more of	the vegetative cover in each strata, or any
amount of an	invasive plant species; '	designates a d	ominant pian	t species for the strata):
	Church I Liana (vina)			also attack to the second links and a second
seedlings, and		H=Herb (includes	s grasses, ne	erbs, pterophytes [ferns], lichens, woody
Notes: See attach	ned tables for plant spec	cies lists.		
III. Important Ha	bitat Features			
Wildlife Food	<u>l</u>			
Important wet	land/aquatic food plants			
·				
☐ Abundant	⊠ Prese	ent	Absent	☐ Not Applicable
Important upla	and food plants (hard ma	ast and fruit/berry	producers)	
☐ Abundant	⊠ Prese	ent	Absent	☐ Not Applicable
Cover/Perch	es/Basking/Denning/Ne	esting Habitat		
Trees (live or	dead) > 30" DBH			
☐ Abundant	⊠ Prese	ent _	Absent	☐ Not Applicable
Standing dead	Literature Control Collins	:::		
	d trees (potential for cav	ities and perches)		

Tree cavities in trunks or limbs							
☐ Abundant		☐ Absent	□ Not Applicable				
Small mammal burrows:							
☐ Abundant		☐ Absent	□ Not Applicable				
Dense herbaceous cover (	voles, small mammals, a	mphibians & reptiles)					
☐ Abundant		☐ Absent	□ Not Applicable				
Large woody debris on the	ground (small mammals	, mink, amphibians & re	otiles)				
	☐ Present	☐ Absent	□ Not Applicable				
Rocks, crevices, logs, tree	roots or hummocks at w	ater's edge or under wat	er's surface (turtles, snakes, frogs)				
	Present	☐ Absent	☐ Not Applicable				
Overhanging branches at or within 1 m above the water's surface (turtles, snakes, frogs, wading birds, wood duck, mink, raccoon)							
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable				
Rock piles, crevices, or hol	Rock piles, crevices, or hollow logs suitable for various mammals (otter, mink, porcupine, racoon):						
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable				
Live or dead tall standing vegetation overhanging or near water offering good visibility of open water (e.g., osprey, kingfisher, flycatchers, cedar waxwings)							
	Present	☐ Absent	☐ Not Applicable				
Other Important Habitat Characteristics:							
Underwater banks of fine s	silt and/or clay (beaver, m	nuskrat, otter)					
☐ Abundant	□ Present	☐ Absent	□ Not Applicable				
Undercut or overhanging banks (small mammals, mink, weasels, turtles)							
☐ Abundant		☐ Absent	□ Not Applicable				
Vertical sandy banks (bank swallow, kingfisher)							
Abundant		☐ Absent ☐	Not Applicable				
Mud flats							
☐ Abundant		☐ Absent	□ Not Applicable				
Exposed areas of well-drained, sandy soil suitable for turtle nesting							
☐ Abundant		☐ Absent	□ Not Applicable				

Wildlife Dens/Nests (if observed)

	Turtle nesting sites						
	Abundant	☐ Present		□ Not Applicable			
	Bank swallow colony(ies)						
	☐ Abundant	☐ Present		☐ Not Applicable			
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron			
	Den(s) present of	☐ Otter	☐ Mink	☐ Beaver			
	Other nests or dens (identify	y species):					
IV.	Connectivity with Adjoini	ng Natural Habitats					
	☐ No direct connections t	o adjacent areas of wildli	fe habitat (little d	connectivity function)			
	☐ Limited number of connectors to adjacent areas of habitat (somewhat important for connectivity function)						
con	Riverbank is embedded in a large area of natural habitat with unimpeded connection to other habitats (high onnectivity function)						
٧.	Rare Species and MNHES	SP Core Area Habitat De	esignation				
	☐ Core Area 1 ☐ Core Area 2 ☐ Core Area 3 ☐ Core Area 4						
	Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat						
	State-listed species habitat (including species with known overlapping Priority Habitat):						
	Brook Snaketail, Matted Spike-sedge, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle						
	Rare species direct observations during current field surveys:						
VI.	I. Incidental Direct Wildlife Observations						
	Raccoon tracks						
	Catbird						

	l Electric Housatonic Rest of River B-1: Riverbank Habitat Inventory Form			
VII. Hab	oitat Degradation (identify specific location on bank segment if applicable)			
	Evidence of significant levels of dumping			
	Evidence of significant erosion or sedimentation problems			
	○ Occurrence of invasive plants:     Bittersweet, Japanese knotweed, bishop's goutweed, purple loosestrife			
	Evidence of other human disturbance; describe:			
VIII.Res	storation Opportunities			
ban	Presence of potential restoration resources (e.g., boulders, large trees or woody debris, root wad material for k stabilization or hibernacula, plant propagation source material). Identify specific items: parse woody debris, root wads, large trees, cobbles			
	Other restoration opportunities:			
R:	Root wads; Log or rock vanes; Vegetated riprap			
L: I	Reshape point bar			
Inva	asive species control			
Rev	vegetation			

Bank 9 Plant Species List		
<u>Left bank</u>	Right bank	
nodding beggar-ticks   Bidens cernua   herb	sugar maple   Acer saccharum   tree	
Devil's beggar-ticks   Bidens frondosa   herb	bishop's goutweed   Aegopodium podagraria   herb   *	
black mustard   Brassica nigra   herb	yellow birch   Betula alleghaniensis   tree	
tussock sedge   Carex stricta   herb	nodding beggar-ticks   Bidens cernua   herb	
spotted Joe-Pye weed   Eupatorium maculatum   herb	Asian bittersweet   Celastrus orbiculatus   vine/liana   *	
Japanese knotweed   Fallopia japonica   herb   *	red-osier dogwood   Cornus sericea   shrub	
jewelweed   Impatiens capensis   herb	rice cut-grass   Leersia oryzoides   herb	
purple loosestrife   Lythrum salicaria   herb   *	ostrich fern   Matteuccia struthiopteris   herb	
pale smartweed   Persicaria lapathifolia   herb	Virgini-creeper   Parthenocissus quinquefolia   vine/liana	
green-headed coneflower   Rudbeckia laciniata   herb	pale smartweed   Persicaria lapathifolia   herb	
dark-green bulrush   Scirpus atrovirens   herb	northern red oak   Quercus rubra   tree	
stinging nettle   Urtica dioica   herb	eastern hemlock   Tsuga canadensis   tree	
blue vervain   Verbena hastata   herb	American elm   Ulmus americana   tree	
rough cocklebur   Xanthium strumarium   herb		

<sup>\*</sup>Invasive species

### **Bank 9 Floodplain Plant Species**

Eastern hemlock	Tsuga canadensis	T
silver maple	Acer saccharinum	T
boxelder	Acer negundo	S
Japenese knotweed	Fallopia japonica	Н



Bank 9: Stations 36-38. 200-ft stretch along a moderate left bend from Station 36-38

bank is on the right.



I.	Ge	neral Informa	tion						
Housatonic ROR R5A Bank 10									
	Site Name and Evaluation Segment  Bank 10: Stations 39-41. 200-ft stretch along a moderate right bend from Station 39-41								
Location/Physical Description 8/4/22									
			(s) and Data Collect	tion					
	Wea	ather Conditions	During Site Visit						
		COM d Staff Performi	ng Evaluation					Date th	nis form was completed
II.	Site	e Description							
A.	Ban	k Characteriza	ation						
Phy	/sica	al Dimensions	(ft):						
Ler	gth:	200'	Width: 80'	Bank Height:	R 6'L	_ 3-4	ļ'	Slope: R 80% L 5	50%
Sec	dime	nt / Substrate	composition:						
% 5	Sanc	l 45	% Silt 45	% Clay 0			% G	ravel/cobble 10	
% E	Boul	der/Bedrock	C	% Organic matter					
Bank stability / Observed erosional conditions: Both banks relatively stable, no major erosional issues. Thalweg along the right bank.									
В.	Bord	dering Habitat	Types						
We	tland	d			Upl	and			
	$\boxtimes$	Transitional fl	oodplain forest			_	Nort Fore	hern Hardwoods-Her est	mlock-White Pine
		High terrace f	loodplain forest				Rich	mesic forest	
		Red maple sv	vamp				Red	Oak-Sugar Maple Tr	ansition Forest
	$\boxtimes$	Vernal pool					Agri	cultural fields	
		Black ash-red swamp	l maple-tamarack	calcareous seepage	е		Cult	ural grassland	
		Deep emerge	ent marsh				Suc	cessional northern ha	ardwoods
		Shallow emer	gent marsh				Spru	uce-fir-northern hardw	vood forest
		Shrub swamp	)				Dev	eloped/disturbed cov	er types
		Wet meadow					Othe	er	
		Other							
Not	es:	Rig	ght bank bordered	I by steep upland fo	rest.				

C.	Hydrology							
Stre	Stream gradient:							
Deg	Degree of overbank flooding potential / floodplain connectivity							
		nnels present ir	n adjacent floodpla	in 🖂	Topog	graphic breaks present	in the riverbank	
	☐ Channel is de	eeply incised	☐ Moderately i	ncised	$\boxtimes$	Somewhat incised	☐ Not incised	
Deg	gree of Water leve	I fluctuation (est	imated vertical diff	erence fron	n mear	n low water to):		
	Bankfull indicator	s: 3 ft	Top of bank slop	e: 4-6 ft	Floo	odplain surface: 4-6 ft		
Fie	ld-Derived Evidend	ce of Hydrologic	Conditions					
		line impressed	on bank	$\boxtimes$	Chang	ges in character of soil		
		<b>KS</b>			Water	staining		
	Shelving			$\boxtimes$	Veget	ation matted down, be	nt or absent	
		litter and debris)	)	$\boxtimes$	Change in plant community			
	Scour and/or     Scour and/or	Deposition			Destruction of terrestrial vegetation			
	Line of mud o	or silt on tree tru	nks/vegetation		Debris stuck on overhanging tree limbs			
	Other							
Fie	ld-Derived Evidend	ce of Bankfull St	age/Discharge Wa	ater				
					Recer	nt changes to river ber	nds/meanders	
	□ Depositional	bench (active ch	nannel)		Undercuts			
	□ Depositional	point bar			Staining of rocks			
	□ Depositional	island			Top of point bars			
	☐ Middle bench	for braided rive	rs		Lower limits in perennial vegetation			
	□ Break in slope	e of banks (flood	dplain break)					
	Other							
D.	Inventory (Plant C	Community)						
Rig	ht Bank							
	Total % Cover:	90 Bank Vegetation	on 80 Overhar	nging Vegetation	on .	100 Riparian Vegetation	_	
	Percent Cover of	Bank and Over	hanging Stream V	egetation by	y Strata	a		
	70 Trees (> 20')	75 Shrubs (< 20')	30 Woody vines	0 Mos	sses	50 Herbaceous		

Left Bank

	Fotal % Cover: $\frac{70}{\text{Bank Vegetation}}$ $\frac{10}{\text{Overhanging}}$		g Vegetation	90 Riparian Vegetation					
	Percent Cover of	of Bank and Overhang	ging Stream Vege	tation by Stra	ıta				
	10 Trees (> 20')	50 Shrubs (< 20')	25 Woody vines	0 Mosses	80				
	, ,	, ,	•	Mosses	Herbaceous				
Per	cent Cover of Rip	parian Vegetation by S	Strata						
	65	70 Shrubs (< 20')	30	0	70				
	, ,	, ,	•						
Bar	nk and overhangi strata. or anv ar	ng vegetation plant lis nount of an invasive p	st (species that co plant species: "*" o	omprise 10% ( designates a d	or more of the vegetative cover in each dominant plant species for the strata):				
	•	nt Species	, , , , , , , , , , , , , , , , , , , ,	Strata	Plant Species				
	Circia Fiai	пореслез		Otrata	Tant oposios				
				<del></del>					
				<u>-</u> :					
	Diparian yagata	tion plant list (species	that comprise 10	10/ or more of	the vegetative cover in each strata, or any				
					t species for the strata):				
				<u> </u>					
				<del></del>					
Stra	ata: T=Tree.S=S	Shrub. L=Liana (vine).	H=Herb (Include	s grasses, he	erbs, pterophytes [ferns], lichens, woody				
	seedlings, and n								
Not	es: See attache	d tables for plant spec	cies lists.						
		4-4 <b>F</b> 4							
III.	Important Habi	tat reatures							
	Wildlife Food								
	Important wetland/aquatic food plants								
	☐ Abundant	⊠ Prese	ent [	Absent	□ Not Applicable				
	Important upland food plants (hard mast and fruit/berry producers)								
	ітіропані иріані	a 1000 piants (naid ma	ast and multiperry	producers)					
	☐ Abundant	⊠ Prese	ent	Absent	□ Not Applicable				
	Cover/Perches/	/Basking/Denning/Ne	esting Habitat						
	Trees (live or dead) > 30" DBH								
	☐ Abundant	∑ Prese	ent 🗆	Absent	□ Not Applicable				
	Standing dead to	rees (potential for cav	ities and perches	)					

Abundant		☐ Absent	☐ Not Applicable
Tree cavities in trunks or lin	nbs		
☐ Abundant	□ Present	Absent	☐ Not Applicable
Small mammal burrows:			
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable
Dense herbaceous cover (v	voles, small mammals, ar	mphibians & reptiles)	
	☐ Present	☐ Absent	☐ Not Applicable
Large woody debris on the	ground (small mammals,	mink, amphibians & rep	tiles)
Abundant	☐ Present		☐ Not Applicable
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)
☐ Abundant	☐ Present		□ Not Applicable
Overhanging branches at o duck, mink, raccoon)	r within 1 m above the w	ater's surface (turtles, sn	akes, frogs, wading birds, wood
☐ Abundant	□ Present	Absent	☐ Not Applicable
Rock piles, crevices, or hol	low logs suitable for vario	ous mammals (otter, min	k, porcupine, racoon):
☐ Abundant	☐ Present		□ Not Applicable
Live or dead tall standing v osprey, kingfisher, flycatche		near water offering good	d visibility of open water (e.g.,
	☐ Present	☐ Absent	☐ Not Applicable
Other Important Habitat C	Characteristics:		
Underwater banks of fine s	ilt and/or clay (beaver, m	uskrat, otter)	
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable
Undercut or overhanging ba	anks (small mammals, m	ink, weasels, turtles)	
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable
Vertical sandy banks (bank	swallow, kingfisher)		
☐ Abundant	☐ Present		Not Applicable
Mud flats			
☐ Abundant	□ Present	☐ Absent	□ Not Applicable
Exposed areas of well-drain	ned, sandy soil suitable fo	or turtle nesting	
☐ Abundant	Present		□ Not Applicable

### Wildlife Dens/Nests (if observed)

	Turtle nesting sites				
	☐ Abundant	☐ Present		□ Not Applicable	
	Bank swallow colony(ies)				
	☐ Abundant	☐ Present		☐ Not Applicable	
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron	
	Den(s) present of	☐ Otter	☐ Mink	☐ Beaver	
	Other nests or dens (identif	y species):			
IV.	Connectivity with Adjoini	ng Natural Habitats			
	☐ No direct connections t	to adjacent areas of wildl	ife habitat (little	connectivity function)	
	Limited number of con	nectors to adjacent areas	s of habitat (som	ewhat important for connectivity function)	
	Riverbank is embedded connectivity function)	d in a large area of natur	al habitat with ur	nimpeded connection to other habitats (high	
٧.	Rare Species and MNHES	SP Core Area Habitat Do	esignation		
☐ Core Area 1 ☐ Core Area 2 ☐ Core Area 3 ☐ Core Area 4					
	Federally listed threate habitat): Northern long-ear		cies habitat (incl	uding species with known overlapping	
	<u> </u>	abitat (including species v		<u> </u>	
	Brook Snaketail, Matted Sp	pike-sedge, Riffle Snaket	tail, Spine-crown	ed Clubtail, Wapato, Wood Turtle	
	Rare species direct observa	ations during current field	d surveys:		
VI.	Incidental Direct Wildlife	Observations			
	-				
	-				

General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form	
VII. Habitat Degradation (identify specific location on b	ank segment if applicable)
☐ Evidence of significant levels of dumping	
Evidence of significant erosion or sedimentation pr	oblems
○ Occurrence of invasive plants:     Japanese knotweed, bittersweet, purple loosestrife	
Evidence of other human disturbance; describe:	
VIII.Restoration Opportunities	
☑ Presence of potential restoration resources (e.g., beank stabilization or hibernacula, plant propagation sour Coarse woody debris, large trees, cobbles	oulders, large trees or woody debris, root wad material for urce material). Identify specific items:
○ Other restoration opportunities:	
R: Vegetated riprap	
L: Grade bank/Coir matting	
Invasive species control	
Revegetation	

Bank 10 Plant Species List					
<u>Left bank</u>	Right bank				
rice cut-grass   Leersia oryzoides   herb	Asian bittersweet   Celastrus orbiculatus   vine/liana   *				
common water-purslane   Ludwigia palustris   herb	Japanese knotweed   Fallopia japonica   herb   *				
purple loosestrife   Lythrum salicaria   herb   *	ostrich fern   Matteuccia struthiopteris   herb				
Allegheny monkeyflower   Mimulus ringens   herb	Virgini-creeper   Parthenocissus quinquefolia   vine/liana				
pale smartweed   Persicaria lapathifolia   herb	American linden   Tilia americana   tree				
blue vervain   Verbena hastata   herb					

<sup>\*</sup>Invasive species

#### **Bank 10 Flooplain Plant Species**

Canada wood nettle	Laportea canadensis	Н
ostrich fern	Matteuccia struthiopteris	Н
green-headed coneflower	Rudbeckia laciniata	Н
stinging nettle	Urtica dioica	Н
boxelder	Acer negundo	S
boxelder	Acer negundo	Т



Bank 10: 200-ft stretch along a moderate right bend from Station 39-41.





I.	General Information						
	Housatonic ROR R5A Bank 11						
	Site Name and Evaluation Segment  Bank 11: Stations 51-53. 200-ft stretch along a straight run from Station 51-53  Location/Physical Description  8/4/22						
	Date(s) of Site Vi	sit(s) and Data Coll	ection				
		ons During Site Visit			_		
	AECOM Field Staff Perfor	ming Evaluation			Date this form was completed		
II.	Site Description	n					
A.	Bank Characteri	zation					
Phy	rsical Dimension	s (ft):					
Len	gth: 200'	Width: 80'	Bank Height: R 8'	L 6'	Slope: R 80% L 60%		
Sec	liment / Substrat	te composition:					
% 5	Sand 40	% Silt 40	% Clay 0		% Gravel/cobble 20		
% E	Boulder/Bedrock		% Organic matter				
		erved erosional cong on Right bank.	onditions: Left bank is stable. Thalw	eg mo	ves from right to left side.		
В.	Bordering Habita	at Types					
We	tland		U	lpland			
		I floodplain forest			Northern Hardwoods-Hemlock-White Pine Forest		
	☐ High terrace	e floodplain forest	i e		Rich mesic forest		
	☐ Red maple	swamp			Red Oak-Sugar Maple Transition Forest		
	☐ Vernal pool				Agricultural fields		
	☐ Black ash-r swamp	ed maple-tamarad	ck calcareous seepage	$\boxtimes$	Cultural grassland		
	☐ Deep emer	gent marsh			Successional northern hardwoods		
	☐ Shallow em	ergent marsh			Spruce-fir-northern hardwood forest		
	☐ Shrub swar	np		$\boxtimes$	Developed/disturbed cover types		
	☐ Wet meado	W			Other		
	Other						
Not	es:						

C. H	ydrology								
Strea	Stream gradient:								
Degr	Degree of overbank flooding potential / floodplain connectivity								
	☐ High-flow cha	annels present ir	adjacent flo	odplain	$\boxtimes$	Topo	graphic breaks present	in the ri	verbank
	☐ Channel is deeply incised ☐ Moderately incised ☐ Somewhat incised ☐ Not incised								Not incised
Degr	ee of Water leve	I fluctuation (est	imated vertic	al difference	fron	n mea	n low water to):		
В	Bankfull indicators: 3 ft Top of bank slope: 6-8 ft Floodplain surface: 6-8 ft								
Field-Derived Evidence of Hydrologic Conditions									
	Clear natural	line impressed	on bank		$\boxtimes$	Chan	ges in character of soil		
	Bed and ban	ks				Wate	r staining		
	Shelving					Vege	tation matted down, ber	nt or ab	sent
	☑ Wrack lines (	litter and debris)			$\boxtimes$	Change in plant community			
	Scour and/or	Deposition				Destruction of terrestrial vegetation			
	Line of mud o	or silt on tree trur	nks/vegetatio	n		Debris stuck on overhanging tree limbs			nbs
	Other								
Field-	-Derived Eviden	ce of Bankfull St	age/Discharç	ge Water					
	Scour line					Rece	nt changes to river bend	ds/mear	nders
	Depositional	bench (active ch	annel)		$\boxtimes$	Undercuts			
	Depositional	point bar				Staining of rocks			
	Depositional	island			$\boxtimes$	Top of point bars			
	☐ Middle bench	n for braided rive	rs		$\boxtimes$	Lower limits in perennial vegetation			
	Break in slop	e of banks (flood	dplain break)						
	Other								
D. Ir	nventory (Plant (	Community)							
Right	Bank								
Т	otal % Cover:	75 Bank Vegetation	on 6	0 Verhanging Ve	getatio	on	70 Riparian Vegetation	_	
F	Percent Cover of	Bank and Overl	nanging Stre	am Vegetatio	on b	y Strat	ta		
	0 rees (> 20')	50 Shrubs (< 20')	<u>20</u> Woody	vines	0 Mos	sses	25 Herbaceous		

Left Bank

	Total % Cover:	80 Bank Vegetation	60 Overhangin	g Vegetation	80 Riparian Vegetation				
	Percent Cover of Bank and Overhanging Stream Vegeta		etation by Stra	ıta					
	20	60 Shrubs (< 20')	25	0 Mosses	75 Herbaceous				
	Trees (> 20')		Woody vines	Mosses	Herbaceous				
Per	cent Cover of Rip	parian Vegetation by S	Strata						
	10	20 Shrubs (< 20')	10	0 Mosses	80				
			-		Herbaceous				
Bar	nk and overhangi strata. or anv an	ng vegetation plant lis	st (species that co plant species: "*" o	omprise 10% d designates a d	or more of the vegetative cover in each dominant plant species for the strata):				
	•	nt Species	орослос,	Strata	Plant Species				
	Circia Fiai	поросно		Otrata	Tan opened				
	Diparian vagata	tion plant list (species	that comprise 10	00/ or more of	the vegetative cover in each strata, or any				
					t species for the strata):				
Stra	ata: T=Tree, S=S	Shrub, L=Liana (vine),	H=Herb (Include	es grasses, he	erbs, pterophytes [ferns], lichens, woody				
	seedlings, and n	nosses)	<u> </u>						
Not	es: See attached	d tables for plant spec	cies lists.						
<u>—</u>	Important Habi	tat Foatures							
••••	•	iai i caiaics							
	Wildlife Food								
	Important wetlar	nd/aquatic food plants							
	☐ Abundant	⊠ Prese	ent [	Absent	☐ Not Applicable				
	Important upland food plants (hard mast and fruit/berry producers)								
	_	. ,			_				
	☐ Abundant	⊠ Prese	ent L	Absent	☐ Not Applicable				
	Cover/Perches/	<u>/Basking/Denning/Ne</u>	esting Habitat						
	Trees (live or dead) > 30" DBH								
	☐ Abundant	☐ Prese	ent D	Absent	□ Not Applicable				
	_	_		_					
	Standing dead trees (potential for cavities and perches)								

Abundant	☐ Present		☐ Not Applicable					
Tree cavities in trunks	or limbs							
Abundant	☐ Present		□ Not Applicable					
Small mammal burrow	rs:							
Abundant		☐ Absent	□ Not Applicable					
Dense herbaceous co	ver (voles, small mamma	als, amphibians & reptile	es)					
Abundant		☐ Absent	☐ Not Applicable					
Large woody debris or	n the ground (small mam	mals, mink, amphibians	s & reptiles)					
Abundant		☐ Absent	□ Not Applicable					
Rocks, crevices, logs,	tree roots or hummocks	at water's edge or under	er water's surface (turtles, snakes, frogs)					
Abundant		☐ Absent	□ Not Applicable					
Overhanging brancheduck, mink, raccoon)	Overhanging branches at or within 1 m above the water's surface (turtles, snakes, frogs, wading birds, wood duck, mink, raccoon)							
Abundant		Absent	☐ Not Applicable					
Rock piles, crevices, c	or hollow logs suitable for	r various mammals (otte	er, mink, porcupine, racoon):					
Abundant	☐ Present		☐ Not Applicable					
	ing vegetation overhang atchers, cedar waxwings		ng good visibility of open water (e.g.,					
Abundant		☐ Absent	□ Not Applicable					
Other Important Hab	itat Characteristics:							
Underwater banks of f	ine silt and/or clay (beav	er, muskrat, otter)						
Abundant		☐ Absent	□ Not Applicable					
Undercut or overhang	ing banks (small mamma	als, mink, weasels, turtle	es)					
Abundant		☐ Absent	□ Not Applicable					
Vertical sandy banks (	bank swallow, kingfisher	·)						
Abundant	☐ Present		☐ Not Applicable					
Mud flats								
Abundant		☐ Absent	□ Not Applicable					
Exposed areas of well	-drained, sandy soil suita	able for turtle nesting						
Abundant	☐ Present		☐ Not Applicable					

### Wildlife Dens/Nests (if observed)

	Turtle nesting sites			
	Abundant	Present		□ Not Applicable
	Bank swallow colony(ies)			
	Abundant	☐ Present		☐ Not Applicable
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron
	Den(s) present of	☐ Otter	Mink	☐ Beaver
	Other nests or dens (identif	y species):		
IV.	Connectivity with Adjoini	ng Natural Habitats		
		o adjacent areas of wildli	fe habitat (little c	connectivity function)
	☐ Limited number of conr	nectors to adjacent areas	of habitat (some	ewhat important for connectivity function)
	Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with un	nimpeded connection to other habitats (high
٧.	Rare Species and MNHES	SP Core Area Habitat De	esignation	
	☐ Core Area 1 ☐ Core	Area 2	a 3 🔲 Core A	Area 4
	☐ Federally listed threate habitat): Northern long-ear		ies habitat (inclu	uding species with known overlapping
	<u> </u>	bitat (including species v		· · · · · · · · · · · · · · · · · · ·
	Brook Snaketail, Matted Sp	oike-sedge, Riffle Snaket	ail, Spine-crown	ed Clubtail, Wapato, Wood Turtle
	Rare species direct observa	ations during current field	surveys:	
VI.	Incidental Direct Wildlife	Observations		

General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form	
/II. Habitat Degradation (identify specific location on b	ank segment if applicable)
☐ Evidence of significant levels of dumping	
Evidence of significant erosion or sedimentation process.	oblems
Occurrence of invasive plants: Bittersweet, common buckthorn, Morrow's honeys	uckle, hedge bindweed
⊠ Evidence of other human disturbance; describe: A	ctive mowed lawns along river
/III.Restoration Opportunities	
☑ Presence of potential restoration resources (e.g., bank stabilization or hibernacula, plant propagation so Coarse woody debris, large trees, cobbles	ooulders, large trees or woody debris, root wad material for urce material). Identify specific items:
○ Other restoration opportunities:	
R: Compartmentalized fill	
L: Grade bank/Coir matting; Log or rock vanes	
Invasive species control	
Revegetation	

Bank 11 Plant Species List				
<u>Left bank</u>	Right bank			
red maple   Acer rubrum   tree	ironwood   Carpinus caroliniana   tree			
common ragweed   Ambrosia artemisiifolia   herb	Asian bittersweet   Celastrus orbiculatus   vine/liana   *			
swamp milkweed   Asclepias incarnata   herb	hedge bindweed   Convolvulus sepium   vine   *			
Devil's beggar-ticks   Bidens frondosa   herb	American witch hazel   Hamamelis virginiana   shrub			
red-osier dogwood   Cornus sericea   shrub	Morrow's honeysuckle   Lonicera morrowii   shrub   *			
spotted Joe-Pye weed   Eupatorium maculatum   herb	common buckthorn   Rhamnus cathartica   herb   *			
lance-leaved tiger-lily   Lilium lancifolium   herb	poison-ivy   Toxicodendron radicans   Iiana/vine			
Allegheny monkeyflower   Mimulus ringens   herb				
pale smartweed   Persicaria lapathifolia   herb				
green-headed coneflower   Rudbeckia laciniata   herb				
American bur-reed   Sparganium americanum   herb				
river grape   Vitis riparia   vine/liana				

<sup>\*</sup>Invasive species

### Bank 11 Floodplain Plant Species

ostrich fern	Matteuccia struthiopteris	Н
bishop's goutweed	Aegopodium podagraria	Н
boxelder maple	Acer negundo	T/S
weeping willow	Salix babylonica	T
Asian bittersweet	Celastrus orbiculatus	V
river grape	Vitis riparia	V



Bank 11: Stations 51-53. 200-ft stretch along a straight run from Station 51-53



I.	Ge	neral Informat	tion				
		usatonic ROR R					
			luation Segment				
				etch along a sharp right	bend fro	om Station 54-56	
		ation/Physical D 4/22	escription				
			(s) and Data Colle	ection			
		ather Conditions	During Site Visit				
		d Staff Performi	ng Evaluation				Date this form was completed
II.	Site	e Description					
A.	Ban	k Characteriza	ation				
Phy	/sica	al Dimensions	(ft):				
Ler	ngth:	200'	Width: 60'	Bank Height: R 6	6' L 8'	Slope: R 30%	% L 80-90%
Sed	dime	ent / Substrate	composition:				
% \$	Sand	30	% Silt 30	% Clay 0		% Gravel/cobble 2	0
% E	Boul	der/Bedrock 20	0	% Organic matter			
Bar	Left				k has hi	gh NBS. Both bank	s stable. Right bank has point
В.	Bor	dering Habitat	Types				
We	tlan	d			Upland		
	$\boxtimes$	Transitional fl	oodplain forest			Northern Hardwood Forest	ds-Hemlock-White Pine
		High terrace f	loodplain forest			Rich mesic forest	
		Red maple sv	vamp			Red Oak-Sugar Ma	aple Transition Forest
		Vernal pool				Agricultural fields	
		Black ash-red swamp	l maple-tamarac	k calcareous seepage	$\boxtimes$	Cultural grassland	
		Deep emerge	ent marsh			Successional north	ern hardwoods
		Shallow emer	gent marsh			Spruce-fir-northern	hardwood forest
		Shrub swamp	)			Developed/disturbe	ed cover types
		Wet meadow				Other	
		Other					
Not							

C.	Hydrology										
Stre	Stream gradient:										
Deg	gree of overbank f	looding potentia	l / floodplain	connectivity							
	☐ High-flow cha	annels present ir	n adjacent flo	odplain	$\boxtimes$	Торо	graphic br	eaks prese	ent in t	he riverba	nk
	☐ Channel is de	eeply incised	☐ Modera	ately incised		$\boxtimes$	Somewh	at incised		☐ Not in	ncised
Deg	gree of Water leve	I fluctuation (est	imated verti	cal difference	e fron	n mea	n low wate	er to):			
	Bankfull indicator	s: 3' ft	Top of ban	k slope: 6-8	ft	Floo	odplain su	ırface: 6-8	ft		
Fie	ld-Derived Eviden	ce of Hydrologic	Conditions								
		line impressed	on bank		$\boxtimes$	Chan	ges in cha	aracter of s	oil		
	⊠ Bed and banl	ks				Water	r staining				
	Shelving					Veget	tation mat	ted down,	bent o	r absent	
	☐ Wrack lines (	litter and debris)	)		$\boxtimes$	Chan	ge in plan	t communi	ty		
	Scour and/or     Scour and/or	Deposition				Destr	uction of t	errestrial v	egetat	ion	
	Line of mud o	or silt on tree tru	nks/vegetation	on		Debri	s stuck or	overhangi	ing tre	e limbs	
	Other										
Fie	ld-Derived Eviden	ce of Bankfull St	age/Dischar	ge Water							
	Scour line					Recei	nt change	s to river b	ends/r	neanders	
	□ Depositional	bench (active ch	nannel)		$\boxtimes$	Unde	rcuts				
	□ Depositional	point bar				Staini	ng of rock	(S			
	Depositional	island			$\boxtimes$	Тор о	of point ba	rs			
	☐ Middle bench	for braided rive	ers		$\boxtimes$	Lowe	r limits in	perennial v	egetat	tion	
		e of banks (floo	dplain break)	)							
	Other										
D.	Inventory (Plant 0	Community)									
Rig	ht Bank										
	Total % Cover:	80 Bank Vegetation	on (	50 Overhanging Ve	getati	on	80 Riparian \	egetation			
	Percent Cover of	Bank and Over	hanging Stre	am Vegetati	on b	y Strat	ta				
	30 Trees (> 20')	60 Shrubs (< 20')	<u>30</u>	ly vines	0 Mos	sses		70 Herbaceous			

Left Bank

	Total % Cover:	80	60		70	
		Bank Vegetation	Overhanging	•	Riparian Vegetation	
		f Bank and Overhang		ation by Stra		
	70 Trees (> 20')	80 Shrubs (< 20')	30 Woody vines	0 Mosses	30 Herbaceous	
Per	,	parian Vegetation by	•			
	60			0	70	
	Trees (> 20')	60 Shrubs (< 20')	20 Woody vines	Mosses	Herbaceous	
Baı	strata, or any an	nount of an invasive p		esignates a	or more of the vegetative cover in each dominant plant species for the strata):	
	Strata Plan	t Species		Strata	Plant Species	
	Diporion vegetate	ion plant list (openion	that appropriate 100		the vegetative cover in each strate or a	
					the vegetative cover in each strata, or a t species for the strata):	ny
	seedlings, and m		`	s grasses, he	erbs, pterophytes [ferns], lichens, woody	
— III.	Important Habit	at Features				
	Wildlife Food					
	Important wetlan	d/aquatic food plants				
	☐ Abundant	□ Prese	ent 🗵	Absent	□ Not Applicable	
	Important upland	I food plants (hard ma	ast and fruit/berry	producers)		
	☐ Abundant	⊠ Prese	ent	Absent	□ Not Applicable	
	Cover/Perches/	Basking/Denning/No	esting Habitat			
	Trees (live or de	ad) > 30" DBH				
	☐ Abundant	⊠ Prese	ent _	Absent	□ Not Applicable	
	Standing dead tr	ees (potential for cav	ities and perches)			
	☐ Abundant	⊠ Prese	ent	Absent	☐ Not Applicable	

Tree cavities in trunks or lin	Tree cavities in trunks or limbs						
Abundant	□ Present	☐ Absent	□ Not Applicable				
Small mammal burrows:							
Abundant	□ Present	☐ Absent	☐ Not Applicable				
Dense herbaceous cover (v	voles, small mammals, a	mphibians & reptiles)					
Abundant	□ Present	☐ Absent	□ Not Applicable				
Large woody debris on the	ground (small mammals	, mink, amphibians & rep	otiles)				
Abundant	□ Present	☐ Absent	□ Not Applicable				
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wat	er's surface (turtles, snakes, frogs)				
Abundant	□ Present	☐ Absent	☐ Not Applicable				
Overhanging branches at o duck, mink, raccoon)	r within 1 m above the w	ater's surface (turtles, sr	nakes, frogs, wading birds, wood				
Abundant	□ Present	Absent	☐ Not Applicable				
Rock piles, crevices, or hol	low logs suitable for vario	ous mammals (otter, min	ık, porcupine, racoon):				
Abundant	□ Present	Absent	☐ Not Applicable				
Live or dead tall standing vosprey, kingfisher, flycatche		r near water offering goo	d visibility of open water (e.g.,				
Abundant	□ Present	☐ Absent	□ Not Applicable				
Other Important Habitat C	Characteristics:						
Underwater banks of fine s	ilt and/or clay (beaver, m	uskrat, otter)					
Abundant	□ Present	☐ Absent	□ Not Applicable				
Undercut or overhanging ba	anks (small mammals, m	ink, weasels, turtles)					
Abundant	□ Present	☐ Absent	☐ Not Applicable				
Vertical sandy banks (bank	swallow, kingfisher)						
Abundant	☐ Present		Not Applicable				
Mud flats							
Abundant	□ Present	☐ Absent	□ Not Applicable				
Exposed areas of well-drain	Exposed areas of well-drained, sandy soil suitable for turtle nesting						
Abundant	☐ Present		☐ Not Applicable				

Wildlife Dens/Nests (if observed)

	Turtle nesting sites			
	Abundant	Present		□ Not Applicable
	Bank swallow colony(ies)			
	☐ Abundant	☐ Present		☐ Not Applicable
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron
	Den(s) present of	☐ Otter	Mink	Beaver
	Other nests or dens (identify	y species):		
IV.	Connectivity with Adjoini	ng Natural Habitats		
	☐ No direct connections to	o adjacent areas of wildli	fe habitat (little c	connectivity function)
		nectors to adjacent areas	of habitat (some	ewhat important for connectivity function)
	Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with un	nimpeded connection to other habitats (high
٧.	Rare Species and MNHES	SP Core Area Habitat De	esignation	
	☐ Core Area 1 ☐ Core	Area 2	a 3 🔲 Core A	Area 4
	☐ Federally listed threate habitat): Northern long-ear		ies habitat (inclu	uding species with known overlapping
	State-listed species ha	bitat (including species v	vith known overla	apping Priority Habitat):
	Brook Snaketail, Matted Sp	oike-sedge, Riffle Snaket	ail, Spine-crown	ed Clubtail, Wapato, Wood Turtle
	Rare species direct observa	ations during current field	surveys:	
VI.	Incidental Direct Wildlife	Observations	_	
	Spotted sandpiper			

	m RB-1: Riverbank Habitat Inventory Form
VII.	Habitat Degradation (identify specific location on bank segment if applicable)
	☐ Evidence of significant levels of dumping
	Evidence of significant erosion or sedimentation problems
	○ Occurrence of invasive plants:     Japanese knotweed, Morrow"s honeysuckle
	Evidence of other human disturbance; describe:
VIII.	Restoration Opportunities
	Presence of potential restoration resources (e.g., boulders, large trees or woody debris, root wad material for bank stabilization or hibernacula, plant propagation source material). Identify specific items:  Coarse woody debris, large trees, cobbles, boulders
	○ Other restoration opportunities:
	R: Reshape point bar; Grade bank/Coir matting
	L: Vegetated riprap; Log or rock vanes
	Invasive species control
	Revegetation

Bank 12 Plant Species List				
<u>Lef bank</u>	Right bank			
boxelder   Acer negundo   tree	silver maple   Acer saccharinum   tree			
Devil's beggar-ticks   Bidens frondosa   herb	nodding beggar-ticks   Bidens cernua   herb			
Morrow's honeysuckle   Lonicera morrowii   shrub   *	Japanese knotweed   Fallopia japonica   herb   *			
eastern cottonwood   Populus deltoides   tree	rice cut-grass   Leersia oryzoides   herb			
	pale smartweed   Persicaria lapathifolia   herb			
	Canada clearweed   Pilea pumila   herb			

<sup>\*</sup>Invasive species

### **Bank 12 Floodplain Plant Species**

ostrich fern	Matteuccia struthiopteris	Н
bishop's goutweed	Aegopodium podagraria	Н
boxelder	Acer negundo	T/S
weeping willow	Salix babylonica	T
Asian bittersweet	Celastrus orbiculatus	V
river grape	Vitis riparia	V



Bank 12: Stations 54-56. 200-ft stretch along a straight run from Station 54-56

Left bank at Station 54+50

Photos of Bank 12 Area. August 4, 2022 Right bank from Station 55 looking downstream Right bank at Station 54 Left bank at Station 55 Left bank at Station 55-56

Right bank (right) to left bank from Station 54

I.	General Information						
	Housatonic ROR R5A Bank 13 Site Name and Evaluation Segment						
	Site Name and Evaluation Segment  Bank 13: Stations 78-81. 300-ft stretch along a mild left bend from Station 78-81.  Location/Physical Description						
	9/15/22 Date(s) of Site Visit	c(s) and Data Collection					
	Weather Conditions	s During Site Visit					
	AECOM Field Staff Performi	ing Evaluation			Da	ate this form was completed	
II.	Site Description						
A.	Bank Characteriza	ation					
Phy	vsical Dimensions	(ft):					
Len	igth: 300'	Width: 60'	Bank Height R: 7'	L: 5'	Slope: R 90%	L 30%	
Sec	diment / Substrate	composition:					
% 5	Sand 40	% Silt 50	% Clay		% Gravel/cobble 10		
% E	Boulder/Bedrock	% O	rganic matter				
Е	Bank stability / Observed erosional conditions:  Both banks relatively stable. Right bank largely vertical with undercuts. High – very high NBS on right bank. Thalweg along right side.						
В.	B. Bordering Habitat Types						
Wetland Upland							
		loodplain forest			Northern Hardwoods- Forest	-Hemlock-White Pine	
	☐ High terrace f	floodplain forest			Rich mesic forest		
	☐ Red maple swamp				Red Oak-Sugar Mapl	e Transition Forest	
	☐ Vernal pool				Agricultural fields		
	☐ Black ash-red maple-tamarack calca swamp		areous seepage		Cultural grassland		
	☐ Deep emergent marsh				Successional norther	n hardwoods	
	☐ Shallow eme	rgent marsh			Spruce-fir-northern ha	ardwood forest	
	☐ Shrub swamp	)			Developed/disturbed	cover types	
	☐ Wet meadow				Other		
	☐ Other						
Not	es:						

C.	Hydrology								
Stream gradient:   Low Gradient   Mid-Gradient   High-Gradient									
Deg	Degree of overbank flooding potential / floodplain connectivity								
		nnels present ir	n adjacent	floodplain	$\boxtimes$	Topo	graphic breaks	present in	the riverbank
	☐ Channel is de	eeply incised	☐ Mode	erately incised		$\boxtimes$	Somewhat inci	sed	☐ Not incised
Deg	gree of Water leve	I fluctuation (est	imated ver	tical difference	e fron	n mea	n low water to):		
	Bankfull indicators	s: 2'	Top of ba	ank slope: 5-7'		Flo	odplain surface:	: 5-7'	
Fie	ld-Derived Evidend	ce of Hydrologic	Conditions	3					
		line impressed	on bank		$\boxtimes$	Chan	ges in characte	r of soil	
		<b>KS</b>				Wate	r staining		
	Shelving				$\boxtimes$	Vege	tation matted do	own, bent	or absent
	☐ Wrack lines (I	litter and debris)	)		$\boxtimes$	Chan	ge in plant com	munity	
	Scour and/or     Scour and/or	Deposition				Destr	uction of terrest	trial vegeta	ation
	Line of mud o	or silt on tree tru	nks/vegeta	tion		Debri	s stuck on over	hanging tr	ee limbs
	Other								
Fie	Field-Derived Evidence of Bankfull Stage/Discharge Water								
	☐ Scour line					Rece	nt changes to ri	ver bends.	/meanders
	□ Depositional	bench (active ch	nannel)		$\boxtimes$	Unde	rcuts		
	□ Depositional	point bar				Staini	ing of rocks		
	☐ Depositional	island			$\boxtimes$	Тор с	of point bars		
	☐ Middle bench	for braided rive	ers		$\boxtimes$	Lowe	r limits in peren	nial vegeta	ation
	⊠ Break in slope	e of banks (floo	dplain brea	k)					
	Other								
D.	Inventory (Plant C	Community)							
Rig	ıht Bank								
	Total % Cover:	30 Bank Vegetation	on	100 Overhanging Ve	getati	on .	100 Riparian Vegetati	ion	
	Percent Cover of	Bank and Over	hanging St	ream Vegetat	ion b	y Strat	ta		
	50 Trees (> 20')	70 Shrubs (< 20')	75 Woo	ody vines	0 Mo	sses	10 Herbac	eous	_

#### Left Bank

	Total % Cover:	90 Bank Vegetation	80 Overhangir	ng Vegetation	100 Riparian Vegetation			
Percent Cover		of Bank and Overhanging Stream Vegetation by Strata						
	50	50 Shrubs (< 20')	30	<u>0</u>	90			
				Mosses	Herbaceous			
Per	cent Cover of Rip	parian Vegetation by	Strata					
	75	80 Shrubs (< 20')	30	5	75			
			•					
Baı					or more of the vegetative cover in each dominant plant species for the strata):			
	•	nt Species	ла. п орослос,	Strata	Plant Species			
	Otrata Fiai	п оросноз		Ottata	Tant openies			
	Rinarian vegeta	tion plant list (species	that comprise 1	0% or more of	the vegetative cover in each strata, or any			
					t species for the strata):			
Stra	ata: T=Tree, S=S	Shrub, L=Liana (vine),	H=Herb (Includ	es grasses, he	erbs, pterophytes [ferns], lichens, woody			
	seedlings, and n	nosses)						
Not	tes: See attached	d tables for plant spec	cies lists.					
 !!!	Important Habi	tat Foaturos						
••••	-	at i catales						
	Wildlife Food							
	Important wetland/aquatic food plants							
	☐ Abundant	⊠ Pres	ent [	Absent	☐ Not Applicable			
	Important unland	d food plants (hard ma	ast and fruit/herr	v producers)				
	_	a 100a pianto (nara mi		y producers,	_			
	☐ Abundant	_			Not Applicable			
	Cover/Perches/Basking/Denning/Nesting Habitat							
	Cover/Perches/	⊠ Preso		Absent	☐ Not Applicable			
	Cover/Perches/	Basking/Denning/N		Absent	□ Not Applicable			
		Basking/Denning/N	esting Habitat	☐ Absent ☐ Absent	☐ Not Applicable			

Abundant	□ Present	☐ Absent	☐ Not Applicable			
Tree cavities in trunks or limbs						
Abundant		☐ Absent	☐ Not Applicable			
Small mammal burrow	vs:					
Abundant		☐ Absent	☐ Not Applicable			
Dense herbaceous co	ver (voles, small mamma	als, amphibians & reptile	es)			
Abundant		☐ Absent	☐ Not Applicable			
Large woody debris of	n the ground (small mam	mals, mink, amphibians	s & reptiles)			
Abundant		☐ Absent	☐ Not Applicable			
Rocks, crevices, logs,	tree roots or hummocks	at water's edge or unde	er water's surface (turtles, snakes, frogs)			
Abundant		☐ Absent	□ Not Applicable			
Overhanging branche duck, mink, raccoon)	s at or within 1 m above	the water's surface (turt	tles, snakes, frogs, wading birds, wood			
Abundant		☐ Absent	□ Not Applicable			
Rock piles, crevices, o	or hollow logs suitable for	various mammals (otte	er, mink, porcupine, racoon):			
Abundant		☐ Absent	□ Not Applicable			
	ling vegetation overhang catchers, cedar waxwing		ng good visibility of open water (e.g.,			
	☐ Present	☐ Absent	□ Not Applicable			
Other Important Hab	itat Characteristics:					
Underwater banks of t	fine silt and/or clay (beav	er, muskrat, otter)				
Abundant		☐ Absent	☐ Not Applicable			
Undercut or overhanging banks (small mammals, mink, weasels, turtles)						
Abundant		☐ Absent	□ Not Applicable			
Vertical sandy banks (bank swallow, kingfisher)						
Abundant	☐ Present		☐ Not Applicable			
Mud flats						
Abundant		☐ Absent	☐ Not Applicable			
Exposed areas of well-drained, sandy soil suitable for turtle nesting						
☐ Abundant	☐ Present		☐ Not Applicable			

### Wildlife Dens/Nests (if observed)

	Turtle nesting sites						
	☐ Abundant	☐ Present		□ Not Applicable			
	Bank swallow colony(ies)						
	☐ Abundant	☐ Present		☐ Not Applicable			
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron			
	Den(s) present of	☐ Otter	Mink	☐ Beaver			
	Other nests or dens (identif	y species):					
IV.	Connectivity with Adjoini	ng Natural Habitats					
	☐ No direct connections t	o adjacent areas of wildli	fe habitat (little o	connectivity function)			
	Limited number of conr	nectors to adjacent areas	of habitat (some	ewhat important for connectivity function)			
	□ Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with un	nimpeded connection to other habitats (high			
V.	Rare Species and MNHES	SP Core Area Habitat De	esignation				
	☐ Core Area 1 ⊠ Core	Area 2 🔀 Core Area	a 3 🔲 Core A	Area 4			
	Federally listed threate habitat): Northern long-ea		cies habitat (inclu	uding species with known overlapping			
	State-listed species ha	ıbitat (including species v	vith known overl	apping Priority Habitat):			
	Brook Snaketail, Matted Spike-sedge, Mustard White, Ostrich Fern Borer Moth, Riffle Snaketail, Spine-crowned Clubtail, Wapato, Wood Turtle						
	Rare species direct observa	ations during current field	surveys:				
VI.	Incidental Direct Wildlife	Observations					
	Deer						
	Green heron						
	Kingfisher						
	Painted turtle						

General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form				
VII. Habitat Degradation (identify specific location on b	pank segment if applicable)			
Evidence of significant levels of dumping				
Evidence of significant erosion or sedimentation p	roblems			
○ Occurrence of invasive plants:     Bittersweet, common buckthorn, Morrow's honeysuckle, Japanese knotweed, purple loosestrife, yellow iris, forget-me-not				
Evidence of other human disturbance; describe:				
VIII.Restoration Opportunities				
Presence of potential restoration resources (e.g., boulders, large trees or woody debris, root wad material for bank stabilization or hibernacula, plant propagation source material). Identify specific items:  Coarse woody debris, large trees, cobble				
R: Vegetated riprap; Log or rock vanes				
L: Reshape point bar				
Invasive species control				
Revegetation				

Bank 13 Plant Species List					
<u>Left</u>	<u>Right</u>				
boxelder   Acer negundo   tree	silver maple   Acer saccharinum   tree				
silver maple   Acer saccharinum   tree	sugar maple   Acer saccharum   tree				
nodding beggar-ticks   Bidens cernua   herb	Asian bittersweet   Celastrus orbiculatus   vine/liana   *				
awl-fruited sedge   Carex stipata   herb	black walnut   Juglans nigra   tree				
Asian bittersweet   Celastrus orbiculatus   vine/liana   *	Morrow's honeysuckle   Lonicera morrowii   shrub   *				
wild cucumber   Echinocystis lobata   vine	American elm   Ulmus americana   tree				
spike rush   Eleocharis sp   herb	river grape   Vitis riparia   vine/liana				
spotted Joe-Pye weed   Eupatorium maculatum   herb					
Japanese knotweed   Fallopia japonica   herb   *					
American manna grass   Glyceria grandis   herb					
yellow iris   Iris pseudacorus   herb   *					
common water-purslane   Ludwigia palustris   herb					
purple loosestrife   Lythrum salicaria   herb   *					
ostrich fern   Matteuccia struthiopteris   herb					
Allegheny monkeyflower   Mimulus ringens   herb					
water forget-me-not   Myosotis scorpioides   herb   *					
lady's-thumb smartweed   Persicaria maculosa   herb					
jumpseed   Persicaria virginiana   herb					
Canada clearweed   Pilea pumila   herb					
pickerelweed   Pontederia cordata   herb					
common buckthorn   Rhamnus cathartica   herb   *					
lance-leaved American aster   Symphyotrichum lanceolatum   herb					
small white aster   Symphyotrichum racemosum   herb					
marsh fern   Thelypteris palustris   herb					
blue vervain   Verbena hastata   herb					
*Invasive species					

#### Bank 13 Floodplain Plant Species

black cherry	Prunus serotina	T
boxelder	Acer negundo	T
common buckthorn	Rhamnus cathartica	S
Morrow's honeysuckle	Lonicera morrowii	S
Japanese barberry	Berberis thunbergii	S
American bittersweet	Celastrus orbiculatus	V
river grape	Vitis riparia	V
moneywort	Lysimachia nummularia	Н
Canada wood nettle	Laportea canadensis	Н

(B-60)



Bank 13: 300-ft stretch along a mild left bend from Station 78-81

Photos of Bank 13 on September 15, 2022: 300-ft stretch along a mild left bend from Station 78-81 Station 78 left bank (right) to right bank looking upstream Station 78 right bank Station 79 right bank Station 79 left bank Station 80 left bank Station 80 right bank



.l.	General Informa	ation				
	Housatonic ROR R					=
	Bank 14: Stations 8	85-88. 300-ft stretch	along a sharp right bei	nd fror	om Station 85-88.	_
	Location/Physical I 9/15/22	Description				
	Date(s) of Site Visit(s) and Data Collection					=
	Weather Condition	s During Site Visit				-
	AECOM Field Staff Perform	ning Evaluation			Date this form was completed	-
II.	Site Description	1				
A.	Bank Characteriza	ation				
Ph	ysical Dimensions	(ft):				
Le	ngth: 300'	Width: 80'	Bank Height: R: 6'	L 7'	Slope: R 60% L 90%	
Se	diment / Substrate	composition:				
%	Sand 40	% Silt 40	% Clay 0		% Gravel/cobble 20	
%	Boulder/Bedrock	% (	Organic matter			
Ва				. Left	t bank is shear cut bank. Right bank is stable wi	th
В.	Bordering Habitat	: Types				
We	etland		U	pland	d	
		floodplain forest			Northern Hardwoods-Hemlock-White Pine Forest	
	☐ High terrace	floodplain forest			Rich mesic forest	
	☐ Red maple s	wamp			Red Oak-Sugar Maple Transition Forest	
	☐ Vernal pool				Agricultural fields	
	☐ Black ash-red swamp	d maple-tamarack ca	lcareous seepage		Cultural grassland	
	□ Deep emerge	ent marsh			Successional northern hardwoods	
	☐ Shallow eme	ergent marsh			Spruce-fir-northern hardwood forest	
	☐ Shrub swam	р			Developed/disturbed cover types	
	☐ Wet meadow	ı			Other	
	Othor					

Notes: C. Hydrology Low Gradient Mid-Gradient ☐ High-Gradient Stream gradient: Degree of overbank flooding potential / floodplain connectivity High-flow channels present in adjacent floodplain ☐ Topographic breaks present in the riverbank Channel is deeply incised Moderately incised Somewhat incised Not incised Degree of Water level fluctuation (estimated vertical difference from mean low water to): Bankfull indicators: 3 ft Top of bank slope: 5-7 ft Floodplain surface: 5-7 ft Field-Derived Evidence of Hydrologic Conditions Clear natural line impressed on bank Changes in character of soil Bed and banks ☐ Water staining Vegetation matted down, bent or absent Shelving Wrack lines (litter and debris) □ Change in plant community Scour and/or Deposition Destruction of terrestrial vegetation Line of mud or silt on tree trunks/vegetation Debris stuck on overhanging tree limbs Other Field-Derived Evidence of Bankfull Stage/Discharge Water ☐ Scour line ☐ Recent changes to river bends/meanders □ Undercuts Depositional bench (active channel) Depositional point bar Staining of rocks Depositional island Break in slope of banks (floodplain break) Other D. Inventory (Plant Community) Right Bank Total % Cover: Overhanging Vegetation Bank Vegetation Riparian Vegetation Percent Cover of Bank and Overhanging Stream Vegetation by Strata Trees (> 20') Shrubs (< 20') Herbaceous Woody vines Mosses

Left Bank

	Total % Cover:	70 Bank Vegetation	100 Overhangir	ng Vegetation	100 Riparian Vegetation
	Percent Cover of Bank and Overhanging Stream Vege		etation by Stra	nta	
	20	80	60	0 Mosses	50
	Trees (> 20')	Shrubs (< 20')	Woody vines	Mosses	Herbaceous
Per	cent Cover of Rip	parian Vegetation by	Strata		
	75	85 Shrubs (< 20')	35 Woody vines	0 Mosses	70
					Herbaceous
Baı					or more of the vegetative cover in each dominant plant species for the strata):
	·	nt Species	nam opooloo,	Strata	Plant Species
	Strata Flat	it opecies		Strata	Fiant Species
					-
					the vegetative cover in each strata, or any t species for the strata):
	amount or arr in	raciro piant opocios,	accignates a	aorimiani pian	t openior for the original.
Stra	ata:  1=1ree, S=8 seedlings, and r		H=Herb (Include	es grasses, he	erbs, pterophytes [ferns], lichens, woody
Not		d tables for plant spec	cies lists		
-		a tables for plant spec	neo noto.		
III.	Important Habi	tat Features			
	Wildlife Food				
		- d/o av otio fo o d mlo mto			
	important wettar	nd/aquatic food plants	•		
	☐ Abundant	⊠ Prese	ent [	Absent	☐ Not Applicable
	Important upland	d food plants (hard ma	ast and fruit/berry	y producers)	
	☐ Abundant	⊠ Prese	ent Γ	Absent	□ Not Applicable
	Cover/Perches	/Basking/Denning/N	estina Hahitat	_	
			ooding Habitat		
	Trees (live or de	:au) > 30 DBH			
	☐ Abundant	☐ Prese	ent [	Absent	□ Not Applicable
	Standing dead t	rees (potential for cav	ities and perche	s)	

Abundant	□ Present	Absent	☐ Not Applicable
Tree cavities in trunks or li	mbs		
☐ Abundant	□ Present	☐ Absent	□ Not Applicable
Small mammal burrows:			
Abundant	□ Present	Absent	☐ Not Applicable
Dense herbaceous cover (	voles, small mammals, a	mphibians & reptiles)	
Abundant	□ Present	Absent	□ Not Applicable
Large woody debris on the	ground (small mammals	, mink, amphibians & rep	otiles)
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wat	er's surface (turtles, snakes, frogs)
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable
Overhanging branches at o duck, mink, raccoon)	or within 1 m above the w	vater's surface (turtles, sr	nakes, frogs, wading birds, wood
Abundant	□ Present	☐ Absent	☐ Not Applicable
Rock piles, crevices, or ho	llow logs suitable for vari	ous mammals (otter, min	k, porcupine, racoon):
Abundant	□ Present	☐ Absent	☐ Not Applicable
Live or dead tall standing vosprey, kingfisher, flycatch		r near water offering goo	d visibility of open water (e.g.,
	☐ Present	Absent	☐ Not Applicable
Other Important Habitat	Characteristics:		
Underwater banks of fine s	silt and/or clay (beaver, m	nuskrat, otter)	
Abundant		☐ Absent	☐ Not Applicable
Undercut or overhanging b	oanks (small mammals, m	nink, weasels, turtles)	
Abundant		☐ Absent	☐ Not Applicable
Vertical sandy banks (bank	swallow, kingfisher)		
Abundant	☐ Present		Not Applicable
Mud flats			
☐ Abundant	□ Present	Absent	☐ Not Applicable
Exposed areas of well-drain	ned, sandy soil suitable f	or turtle nesting	
☐ Abundant	Present		□ Not Applicable

#### Wildlife Dens/Nests (if observed)

	Turtle nesting sites			
	☐ Abundant	☐ Present		□ Not Applicable
	Bank swallow colony(ies)			
	☐ Abundant	☐ Present		☐ Not Applicable
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron
	Den(s) present of	☐ Otter	Mink	☐ Beaver
	Other nests or dens (identify	y species):		
IV.	Connectivity with Adjoini	ng Natural Habitats		
	☐ No direct connections t	o adjacent areas of wildli	fe habitat (little c	connectivity function)
	☐ Limited number of conr	nectors to adjacent areas	of habitat (some	ewhat important for connectivity function)
	☐ Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with un	impeded connection to other habitats (high
V.	Rare Species and MNHES	SP Core Area Habitat De	esignation	
	☐ Core Area 1 ☐ Core	Area 2 🔀 Core Area	a 3 🔲 Core A	Area 4
	Federally listed threate habitat): Northern long-ear		ies habitat (inclu	uding species with known overlapping
	<u> </u>	bitat (including species v		······································
	Bristly Buttercup, Brook Sn crowned Clubtail, Wapato,		dge, Ostrich Fer	n Borer Moth, Riffle Snaketail, Spine-
	Rare species direct observa	ations during current field	surveys:	
VI.	Incidental Direct Wildlife	Observations		
	Mallards			
	Deer			
	Catbird			
	Painted turtle			

General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form	
VII. Habitat Degradation (identify specific location on b	pank segment if applicable)
☐ Evidence of significant levels of dumping	
Evidence of significant erosion or sedimentation p	roblems
○ Occurrence of invasive plants:     Bittersweet, common buckthorn, Morrow's honeysuck goutweed	kle, Japanese knotweed, purple loosestrife, bishop's
Evidence of other human disturbance; describe:	
VIII.Restoration Opportunities	
□ Presence of potential restoration resources (e.g., bank stabilization or hibernacula, plant propagation so Coarse woody debris, large trees, cobble	boulders, large trees or woody debris, root wad material for ource material). Identify specific items:
○ Other restoration opportunities:	
R: Reshape point bar	
L: Log or rock vanes; Root wads; Vegetated riprap	
Invasive species control	
Revegetation	

Species List
<u>Right</u>
boxelder   Acer negundo   tree   nodding beggar-ticks   Bidens cernua   herb   water hemlock   Cicuta bulbifera   herb   wild cucumber   Echinocystis lobata   vine   Japanese knotweed   Fallopia japonica   herb   * pale smartweed   Persicaria lapathifolia   herb   jumpseed   Persicaria virginiana   herb   blue vervain   Verbena hastata   herb

#### **Bank 14 Floodplain Plant Species**

silver maple	Acer saccharinum	T
boxelder	Acer negundo	T
boxelder	Acer negundo	S
silky dogwood	Cornus amomum	S
Canada wood nettle	Laportea canadensis	Н
ostrich fern	Matteuccia struthiopteris	Н
bishop's goutweed	Aegopodium podagraria	Н

(B-60)



Bank 14: Stations 85-88. 300-ft stretch along a sharp right bend from Station 85-88

Station 87-88, right bank

Photos of Bank 14 Area. September 15, 2022. Station 85-86 right bank, looking upstream Station 86 left bank Outlet from backwater at Station 86, left bank Swale from backwater to left bank at Station 86

Station 88 left bank



ı	l.	. General Information						
		Housatonic ROR R5A Bank 15						
		Site Name and Evaluation Segment  Bank 15: Stations 102-104. 200-ft stretch with bend to right, then left, with mid-channel bar						
		Bank 15: Stations 1 Location/Physical D		with bend to right, the	nen le	ft, with mid-channel bar		
		8/30/22	rescription					
		Date(s) of Site Visit(s) and Data Collection						
		Weather Conditions	s During Site Visit					
		AECOM						
		Field Staff Performi	ng Evaluation			Date this form was completed		
II.	Sit	e Description						
A.	Bar	nk Characterization	n					
Phy	/sic	al Dimensions (ft):	:					
Ler	gth	: 200'	Width: 70'	Bank Height: R 5'	L 6'	Slope: R 30%, 90% L 90-120%		
Sec	dime	ent / Substrate cor	mposition:					
% \$	San	d 40	% Silt 50	% Clay		% Gravel/cobble 10		
% E	3ou	lder/Bedrock	% O	rganic matter				
Ve	ry v	ariable conditions	d erosional conditions: . Upper right bank ver y root cover. Mid-cha	y gentle and stable.		r right cut steep but stable. Left bank steep th banks.		
B.	Bor	dering Habitat Typ	pes					
We	tlan	d		U	pland			
	$\boxtimes$	Transitional floor	dplain forest			Northern Hardwoods-Hemlock-White Pine Forest		
		High terrace floo	dplain forest			Rich mesic forest		
		Red maple swan	np			Red Oak-Sugar Maple Transition Forest		
		Vernal pool			$\boxtimes$	Agricultural fields		
		Black ash-red ma swamp	aple-tamarack calcare	ous seepage		Cultural grassland		
		Deep emergent i	marsh			Successional northern hardwoods		
		Shallow emerger	nt marsh			Spruce-fir-northern hardwood forest		
		Shrub swamp				Developed/disturbed cover types		
		Wet meadow				Other		
		Other						
Not	ъс.							

C.	Hydrology						
Stre	eam gradient:	☐ Low Grad	dient		ient	nt High-Gradient	
Deg	gree of overbank flood	ling potential / fl	oodplain co	onnectivity			
		els present in ac	ljacent floo	dplain	$\boxtimes$	Topographic breaks present in the riverbank	
	☐ Channel is deeply	y incised	⊠ Mode	rately incised		☐ Somewhat incised ☐ Not incised	
Deg	Degree of Water level fluctuation (estimated vertical difference from mean low water to):						
	Bankfull indicators: 2	2 ft	Top of ba	nk slope: 5-6 f	t	Floodplain surface: 5-6 ft	
Fiel	d-Derived Evidence o	of Hydrologic Co	nditions				
		impressed on t	oank		$\boxtimes$	Changes in character of soil	
	Bed and banks					] Water staining	
	Shelving					Vegetation matted down, bent or absent	
	☐ Wrack lines (litter	r and debris)			$\boxtimes$	Change in plant community	
	Scour and/or Dep	oosition				Destruction of terrestrial vegetation	
	☐ Line of mud or sil	It on tree trunks	/vegetation			Debris stuck on overhanging tree limbs	
	Other						
Fiel	d-Derived Evidence o	f Bankfull Stage	e/Discharge	e Water			
	☐ Scour line					Recent changes to river bends/meanders	
	□ Depositional benefit	ch (active chani	nel)		$\boxtimes$	Undercuts	
	☐ Depositional poin	nt bar				Staining of rocks	
	□ Depositional islar	nd			$\boxtimes$	Top of point bars	
	☐ Middle bench for	braided rivers			$\boxtimes$	Lower limits in perennial vegetation	
	□ Break in slope of	banks (floodpla	ain break)				
	Other						
D.	Inventory (Plant Com	munity)					
Rig	ht Bank						
J	Total % Cover:	90 Bank Vegetation	on .	75 Overhanging Ve	getati	ation The state of	
	Percent Cover of Bar	nk and Overhan	nging Strea	m Vegetation	by S	Strata	
	50 Trees (> 20')	10 Shrubs (< 20')	10	ody vines	0 Mo	losses 70 Herbaceous	

#### Left Bank

	Total % Cover:	80 Bank Vegetation	70 Overhanging	Vegetation	100 Riparian Vegetation	
	Percent Cover o	of Bank and Overhanging		-	Ripanan vegetation	
	80	60	50	0	40	
	Trees (> 20')	Shrubs (< 20')	Woody vines	Mosses	Herbaceous	_
Pei	cent Cover of Rip	parian Vegetation by Strat	ta			
	80	80	30	0	60	_
	Trees (> 20')	Shrubs (< 20')	Woody vines	Mosses	Herbaceous	
Baı	nk and overhangi or any amount o	ng vegetation plant list (sp f an invasive plant specie	pecies that comp s; "*" designates	rise 10% or n a dominant p	nore of the vegetative covo plant species for the strata	er in each strata, ):
	Strata F	Plant Species		Strata	Plant Species	
		ion plant list (species that vasive plant species; "*" d			e vegetative cover in each ecies for the strata):	strata, or any
Stra	ata: T=Tree, S=S seedlings, and n		Herb (Includes gr	asses, herbs	, pterophytes [ferns], liche	ens, woody
Not	tes: See attached	d tables for plant species	lists.			
III.	Important Habi	tat Features				
	Wildlife Food					
	Important wetlar	nd/aquatic food plants				
	☐ Abundant	□ Present	□ A	bsent	☐ Not Applicable	
	Important upland	d food plants (hard mast a	and fruit/berry pro	ducers)		
	☐ Abundant	□ Present		Absent	☐ Not Applicable	
	Cover/Perches/	Basking/Denning/Nesti	ng Habitat			
	Trees (live or de	ad) > 30" DBH				
	☐ Abundant	□ Present	□ A	bsent	☐ Not Applicable	
	Standing dead to	rees (potential for cavities	and perches)			

#### **General Electric Housatonic Rest of River** Form RB-1: Riverbank Habitat Inventory Form ☐ Not Applicable Abundant Present Absent Tree cavities in trunks or limbs ■ Not Applicable Abundant Present Absent Small mammal burrows: Abundant □ Present Absent ☐ Not Applicable Dense herbaceous cover (voles, small mammals, amphibians & reptiles) □ Present ☐ Not Applicable Abundant Absent Large woody debris on the ground (small mammals, mink, amphibians & reptiles) ☐ Present ☐ Absent ☐ Not Applicable Rocks, crevices, logs, tree roots or hummocks at water's edge or under water's surface (turtles, snakes, frogs) Present Abundant Absent ☐ Not Applicable Overhanging branches at or within 1 m above the water's surface (turtles, snakes, frogs, wading birds, wood duck, mink, raccoon) Present Abundant Absent Not Applicable Rock piles, crevices, or hollow logs suitable for various mammals (otter, mink, porcupine, racoon): Present ☐ Absent Abundant Not Applicable Live or dead tall standing vegetation overhanging or near water offering good visibility of open water (e.g., osprey, kingfisher, flycatchers, cedar waxwings) Abundant Present Absent Not Applicable Other Important Habitat Characteristics: Underwater banks of fine silt and/or clay (beaver, muskrat, otter) □ Present Abundant Absent Not Applicable Undercut or overhanging banks (small mammals, mink, weasels, turtles) Abundant Present Absent ☐ Not Applicable Vertical sandy banks (bank swallow, kingfisher) Abundant Present Absent Not Applicable

Present

Exposed areas of well-drained, sandy soil suitable for turtle nesting

Mud flats

Abundant

Abundant

Absent

Not Applicable

Not Applicable

#### Wildlife Dens/Nests (if observed)

	Turtle nesting sites			
	Abundant	☐ Present		□ Not Applicable
	Bank swallow colony(ies)			
	Abundant	Present		☐ Not Applicable
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron
	Den(s) present of	Otter	☐ Mink	Beaver
	Other nests or dens (identify	y species):		
٧.	Connectivity with Adjoining	ng Natural Habitats		
	☐ No direct connections to	o adjacent areas of wildli	fe habitat (little	connectivity function)
	☐ Limited number of conn	ectors to adjacent areas	of habitat (som	ewhat important for connectivity function)
	Riverbank is embedded connectivity function)	I in a large area of natura	al habitat with ur	nimpeded connection to other habitats (high
<b>/</b> .	Rare Species and MNHES	P Core Area Habitat De	esignation	
	☐ Core Area 1 ☐ Core	Area 2 🔀 Core Area	a 3 🔲 Core	Area 4
	□ Federally listed threate     Northern long-eared bat	ned or endangered spec	ies habitat (incl	uding species with known overlapping habitat):
	State-listed species ha	bitat (including species w	vith known overl	apping Priority Habitat):
	Bristly Buttercup, Brook Sn. Spine-crowned Clubtail, Wa		dge, Mustard W	hite, Ostrich Fern Borer Moth, Riffle Snaketail,
	Rare species direct observa	ations during current field	surveys:	
/I.	Incidental Direct Wildlife	Observations		
	Green heron			
	Black-capped chickad	dee		
	Wood pewee			
	·			

General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form	
VII. Habitat Degradation (identify specific location on	bank segment if applicable)
Evidence of significant levels of dumping	
Evidence of significant erosion or sedimentation p	problems
<ul> <li>Occurrence of invasive plants:</li> <li>Common buckthorn, bittersweet, Japanese knotw</li> </ul>	eed, forget-me-not
Evidence of other human disturbance; describe: _	
VIII.Restoration Opportunities	
Presence of potential restoration resources (e.g., bank stabilization or hibernacula, plant propagation so Coarse woody debris, large trees, root wads, cobb	
○ Other restoration opportunities:	
R: Compartmentalized fill; Grade bank/Coir matting	
L: Grade bank/Coir matting	
Invasive species control	
Revegetation	

Bank 15 Plant Species List			
<u>Left bank</u>	Right bank		
silver maple   Acer saccharinum   tree	boxelder   Acer negundo   tree		
nodding beggar-ticks   Bidens cernua   herb	silver maple   Acer saccharinum   tree		
Asian bittersweet   Celastrus orbiculatus   vine/liana   *	nodding beggar-ticks   Bidens cernua   herb		
silky dogwood   Cornus amomum   shrub	Japanese knotweed   Fallopia japonica   herb   *		
red-osier dogwood   Cornus sericea   shrub	common water-purslane   Ludwigia palustris   herb		
spotted Joe-Pye weed   Eupatorium maculatum   herb	water forget-me-not   Myosotis scorpioides   herb   *		
jewelweed   Impatiens capensis   herb	pale smartweed   Persicaria lapathifolia   herb		
ostrich fern   Matteuccia struthiopteris   herb	blue vervain   Verbena hastata   herb		
common buckthorn   Rhamnus cathartica   herb   *			
American elm   Ulmus americana   tree			

<sup>\*</sup>Invasive species


#### Bank 15 Floodpain Plant Species

silver maple	Acer saccharinum	T
common buckthorn	Rhamnus cathartica	S
Japanese knotweed	Fallopia japonica	Н
ostrich fern	Matteuccia struthiopteris	Н
stinging nettle	Urtica dioica	Н
bishop's goutweed	Aegopodium podagraria	Н



Bank 15: Stations 102-104. 200-ft bend to right and then left with large mid-channel bar at Station 103.

Photos of Bank 15 Area, August 30, 2022 Looking upstream from Station102. Right bank is on left side. Right bank at Station 102 Looking downstream at left bank (left) to right bank (right) Right bank looking downstream toward Station 103 toward Station 103 Right bank at Station 104 Right bank at Station 104





Left bank at upstream side of Station 103



Left bank (right side) at downstream side of Station 103. Midchannel bar is to the left. Looking upstream.



Looking upstream at downstream end of mid-channel bar. From Station 103+50



Looking upstream from Station 105. Mid-channel bar in view at Station 103.

I.	General Informa	ition						
	Housatonic ROR R5A Bank 16							
	Site Name and Evaluation Segment							
	Bank 16: Stations 106-110. 400-ft sharp left and right bend, then back to left  Location/Physical Description							
	8/30/22							
	Date(s) of Site Visi	t(s) and Data Col	lection					
	Weather Condition	s During Site Visi	t					
	AECOM Field Staff Perform	ing Evaluation			Date this form was completed			
	Tiola Gian Follonin	mig Evaldation			Date and form was completed			
II.	Site Description	1						
A.	Bank Characteriza	ation						
Phy	sical Dimensions	(ft):						
Len	gth: 400'	Width: 70'	Bank Height: R 4-5	5' L 10' Slope: R 45	% L 90%			
Sec	liment / Substrate	composition:						
% 5	Sand 40	% Silt 30	% Clay	% Gravel/cobble	20			
% E	Boulder/Bedrock 1	0	% Organic matter					
Bar	nk stability / Obsei	rved erosional c	onditions:					
			h BEHI and extreme NBS	on left bank. Right bank i	s relatively stable. Thalweg is			
	slightly left of cer	nter.						
B.	Bordering Habitat	Types						
We	tland		L	Ipland				
		loodplain forest			ods-Hemlock-White Pine			
	☐ High terrace	floodplain fores	<del>t</del>	Forest  Rich mesic forest				
		·	•					
	Red maple s	wamp		☐ Red Oak-Sugar N	laple Transition Forest			
	☐ Vernal pool			Agricultural fields				
	☐ Black ash-ree swamp	d maple-tamara	ck calcareous seepage		i			
	☐ Deep emerge	ent marsh		☐ Successional nort	hern hardwoods			
	☐ Shallow eme	rgent marsh		☐ Spruce-fir-norther	n hardwood forest			
	☐ Shrub swam	р		□ Developed/disturb	ped cover types			
	☐ Wet meadow	1		Other				
	Other							
Not	001							

C.	Hydrology							
Stre	eam gradient:	☐ Low Gr	adient	⊠ Mid-Gra	dient		☐ High-Gradient	
Deg	egree of overbank flooding potential / floodplain connectivity							
		nnels present	in adjacen	t floodplain	$\boxtimes$	Торо	graphic breaks preser	nt in the riverbank
	☐ Channel is de	eply incised	□ Мо	derately incised		$\boxtimes$	Somewhat incised	☐ Not incised
Deg	gree of Water level	fluctuation (e	stimated v	ertical differenc	e fror	n mea	n low water to):	
	Bankfull indicators	s: 2-4 ft	Top of bar	nk slope: 4-10 f		Flood	olain surface: 4-10 ft	
Fiel	d-Derived Evidend	e of Hydrolog	ic Conditio	ns				
		line impressed	d on bank			Chan	ges in character of so	il
	⊠ Bed and bank	is .				Wate	r staining	
	Shelving					Vege	tation matted down, b	ent or absent
	☐ Wrack lines (I	itter and debri	s)		$\boxtimes$	Chan	ge in plant community	′
	Scour and/or	Deposition				Destr	uction of terrestrial ve	getation
	☐ Line of mud o	r silt on tree tr	unks/veae	tation		Debri	s stuck on overhangir	na tree limbs
	_		unite, rege	lation	ш	200	J	3
	Other		_	lation				
Fiel	_							
Fiel	Other						nt changes to river be	
Fiel	Other	e of Bankfull S	Stage/Disc				nt changes to river be	
Fiel	☐ Otherd-Derived Evidence☐ Scour line	ee of Bankfull S	Stage/Disc			Rece	nt changes to river be	
Fiel	☐ Other  d-Derived Evidence ☐ Scour line ☐ Depositional b	ee of Bankfull Spench (active opench bar	Stage/Disc			Rece Unde Stain	nt changes to river be	
Fiel	Other  d-Derived Evidence  Scour line  Depositional because of the control	ee of Bankfull Spench (active opench bar	Stage/Disc			Rece Unde Stain Top o	nt changes to river be rcuts ing of rocks	nds/meanders
Fiel	Other  d-Derived Evidence  Scour line  Depositional because of the control	ee of Bankfull spench (active opench bar sland for braided riverse	Stage/Disc channel) vers	harge Water		Rece Unde Stain Top o	nt changes to river be rcuts ing of rocks of point bars	nds/meanders
Fiel	Other	ee of Bankfull spench (active opench bar sland for braided rive of banks (flood	Stage/Disc channel) /ers odplain bre	harge Water		Rece Unde Stain Top o	nt changes to river be rcuts ing of rocks of point bars	nds/meanders
	Other	ee of Bankfull spench (active opench (active opench spench	Stage/Disc channel) /ers odplain bre	harge Water		Rece Unde Stain Top o	nt changes to river be rcuts ing of rocks of point bars	nds/meanders
D.	Other	ee of Bankfull spench (active opench (active opench spench	Stage/Disc channel) /ers odplain bre	harge Water		Rece Unde Stain Top o	nt changes to river be rcuts ing of rocks of point bars	nds/meanders
D.	☐ Other	ee of Bankfull spench (active opench (active opench spench	Stage/Disc channel) vers	harge Water		Rece Unde Stain Top o	nt changes to river be rcuts ing of rocks of point bars	nds/meanders
D.	Other	ee of Bankfull Spench (active opench (active opench spench	Stage/Disconnel)  vers odplain breation	harge Water eak)	□ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □	Rece Unde Stain Top o Lowe	nt changes to river be rcuts ing of rocks of point bars r limits in perennial ve	nds/meanders

Left Bank

Total %	6 Cover:	60	90		100	
		Bank Vegetation	ŭ	ng Vegetation	Riparian Vegetation	
	it Cover o	f Bank and Overhang		etation by Stra		
80 Trees (>	20')	40 Shrubs (< 20')	20 Woody vines	0 Mosses		
`	,	parian Vegetation by S	•			
50	·	60	20	0	90	
Trees (>	20')	Shrubs (< 20')	Woody vines	Mosses	Herbaceous	
Bank and o strata, Strata	or any an	ng vegetation plant lis nount of an invasive p t Species	st (species that of lant species; "*"	comprise 10% o designates a c Strata	or more of the vegetative cover dominant plant species for the Plant Species	er in each e strata):
					the vegetative cover in each to species for the strata):	strata, or any
seedlin Notes: See	gs, and m		•	es grasses, he	rbs, pterophytes [ferns], liche	ns, woody
Wildlife	e Food					
		d/aquatic food plants				
	undant	⊠ Prese		Absent	☐ Not Applicable	
Importa	ant upland	I food plants (hard ma	ast and fruit/berr	y producers)		
☐ Ab	undant	□ Prese	ent [	Absent	☐ Not Applicable	
Cover/	Perches/	Basking/Denning/Ne	esting Habitat			
Trees (	(live or de	ad) > 30" DBH				
☐ Ab	undant	⊠ Prese	ent [	Absent	☐ Not Applicable	
Standir	ng dead tr	ees (potential for cavi	ities and perche	s)		

☐ Abundant	□ Present	☐ Absent	□ Not Applicable
Tree cavities in trunks or lin	nbs		
Abundant	□ Present	☐ Absent	☐ Not Applicable
Small mammal burrows:			
Abundant	□ Present	Absent	☐ Not Applicable
Dense herbaceous cover (v	voles, small mammals, ar	mphibians & reptiles)	
Abundant	□ Present	Absent	□ Not Applicable
Large woody debris on the	ground (small mammals	, mink, amphibians & rep	tiles)
	☐ Present	Absent	□ Not Applicable
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)
	☐ Present	Absent	□ Not Applicable
Overhanging branches at o duck, mink, raccoon)	r within 1 m above the w	ater's surface (turtles, sr	nakes, frogs, wading birds, wood
	☐ Present	Absent	□ Not Applicable
Rock piles, crevices, or hol	low logs suitable for vario	ous mammals (otter, min	k, porcupine, racoon):
Abundant	□ Present	Absent	☐ Not Applicable
Live or dead tall standing voosprey, kingfisher, flycatche		near water offering goo	d visibility of open water (e.g.,
	☐ Present	Absent	□ Not Applicable
Other Important Habitat C	Characteristics:		
Underwater banks of fine si	ilt and/or clay (beaver, m	uskrat, otter)	
Abundant	□ Present	Absent	□ Not Applicable
Undercut or overhanging ba	anks (small mammals, m	ink, weasels, turtles)	
Abundant	□ Present	Absent	□ Not Applicable
Vertical sandy banks (bank	swallow, kingfisher)		
Abundant	□ Present	Absent	Not Applicable
Mud flats			
Abundant	□ Present	Absent	☐ Not Applicable
Exposed areas of well-drain	ned, sandy soil suitable f	or turtle nesting	
Abundant		Absent	□ Not Applicable

#### Wildlife Dens/Nests (if observed)

	Turtle nesting sites			
	☐ Abundant	Present		☐ Not Applicable
	Bank swallow colony(ies)			
	Abundant	□ Present	☐ Absent	□ Not Applicable
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron
	Den(s) present of	Otter	☐ Mink	Beaver
	Other nests or dens (identify	y species):		
IV.	Connectivity with Adjoini	ng Natural Habitats		
	☐ No direct connections t	to adjacent areas of wildli	ife habitat (little d	connectivity function)
	Limited number of conr	nectors to adjacent areas	of habitat (some	ewhat important for connectivity function)
	☐ Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with ur	nimpeded connection to other habitats (high
V.	Rare Species and MNHES	SP Core Area Habitat De	esignation	
		Area 2 🔀 Core Area	a 3 🔲 Core /	Area 4
	☐ Federally listed threate habitat): Northern long-ear		cies habitat (inclu	uding species with known overlapping
	<u> </u>	abitat (including species v		
	American Bittern, Bristly Bu Moth, Spine-crowned Clubt			sedge, Mustard White, Ostrich Fern Borer
	Rare species direct observa	ations during current field	surveys:	
VI.	Incidental Direct Wildlife	Observations		
	Kingfisher			_
	Red-bellied woodped	cker		
	Crow			
	Raccoon tracks			
	Deer tracks			


Painted turtle	
VII. Habitat Degradation (identify specific location on b	ank segment if applicable)
☐ Evidence of significant levels of dumping	
⊠ Evidence of significant erosion or sedimentation pro	oblems
○ Occurrence of invasive plants:     Common buckthorn, Japanese knotweed, bittersweet, forget-me-not	Morrow's honeysuckle, yellow iris, bishop's goutweed,
Evidence of other human disturbance; describe:	
VIII.Restoration Opportunities	
☑ Presence of potential restoration resources (e.g., b bank stabilization or hibernacula, plant propagation sou Coarse woody debris, large trees, root wads, cobbl	
Other restoration opportunities:	
R: Reshape point bar; Vegetated riprap	
L: Vegetated riprap; Grade bank/Coir matting	
Invasive species control	
Revegetation	

Bank 16 Plant	t Species List
<u>Left bank</u>	Righ bank
silver maple   Acer saccharinum   tree	boxelder   Acer negundo   tree
bishop's goutweed   Aegopodium podagraria   herb   *	silver maple   Acer saccharinum   tree
Asian bittersweet   Celastrus orbiculatus   vine/liana   *	nodding beggar-ticks   Bidens cernua   herb
white turtlehead   Chelone glabra   herb	small-spiked false-nettle   Boehmeria cylindrica   herb
Japanese knotweed   Fallopia japonica   herb   *	wild cucumber   Echinocystis lobata   vine
green ash   Fraxinus pennsylvanica   tree	Japanese knotweed   Fallopia japonica   herb   *
yellow iris   Iris pseudacorus   herb   *	common water-purslane   Ludwigia palustris   herb
Morrow's honeysuckle   Lonicera morrowii   shrub   *	water forget-me-not   Myosotis scorpioides   herb   *
ostrich fern   Matteuccia struthiopteris   herb	common buckthorn   Rhamnus cathartica   herb   *
sensitive fern   Onoclea sensibilis   herb	blue vervain   Verbena hastata   herb
eastern cottonwood   Populus deltoides   tree	
common buckthorn   Rhamnus cathartica   herb   *	
American elm   Ulmus americana   tree	
river grape   Vitis riparia   vine/liana	

<sup>\*</sup>Invasive species

Bank 16 Floodplain Plant Species

silver maple	Acer saccharinum	T
hawthorn	Crataegus spp.	T
ostrich fern	Matteuccia struthiopteris	Н
stinging nettle	Urtica dioica	Н



Photos of Bank 16 Area. August 30, 2022.





I.	General Inform	ation					
	Housatonic ROR						
Site Name and Evaluation Segment							
	Bank 17: Stations Location/Physical		along left bend at sewer li	line crossing			
	8/30/22	Description					
	Date(s) of Site Vis	sit(s) and Data Co	llection				
	Weather Condition	ns During Site Vis	it				
	AECOM Field Staff Perform	ning Evaluation		Date this form was complete	ed		
II.	Site Description	n					
A.	Bank Characteriz	zation					
Phy	ysical Dimensions	s (ft):					
Ler	ngth: 200'	Width: 70'	Bank Height: R s	5-6' L 5-6' Slope: R 90% L 70%			
Sec	diment / Substrate	e composition:					
% 5	Sand 30	% Silt 30	% Clay	% Gravel/cobble 20			
% E	Boulder/Bedrock	20	% Organic matter				
Bar	nk stability / Obse Both banks relat bank. Thalweg	ively stable; bar		nk; large down trees at upper end divert lower flows to	o left		
В.	Bordering Habita	t Types					
We	tland			Upland			
		floodplain fores	t	<ul><li>Northern Hardwoods-Hemlock-White Pine Forest</li></ul>			
	☐ High terrace	floodplain fores	st	☐ Rich mesic forest			
	☐ Red maple s	swamp		Red Oak-Sugar Maple Transition Forest			
	∀ Vernal pool			Agricultural fields			
	☐ Black ash-re swamp	ed maple-tamara	ack calcareous seepage	☐ Cultural grassland			
	□ Deep emerged	gent marsh		☐ Successional northern hardwoods			
	☐ Shallow eme	ergent marsh		Spruce-fir-northern hardwood forest			
	☐ Shrub swam	np		□ Developed/disturbed cover types			
	☐ Wet meadov	N		Other <u>sewer line crossing</u>			
	Other		_				
Not	toe						

C.	Hydrology								
Stre	eam gradient:	☐ Low Grad	dient	⊠ Mid-Grad	ient		☐ High-Gradier	nt	
Deg	Degree of overbank flooding potential / floodplain connectivity								
		annels present ir	adjacent flo	oodplain	$\boxtimes$	Topogr	raphic breaks pres	sent in t	he riverbank
	☐ Channel is de	eeply incised	☐ Moder	ately incised			Somewhat incised	I	Not incised
Deg	gree of Water leve	I fluctuation (est	imated verti	cal difference	fron	n mean	low water to):		
	Bankfull indicator	s: 2.5 ft	Top of ban	k slope: 5-6 f	t	Floor	dplain surface: 5-6	6 ft	
Fie	ld-Derived Eviden	ce of Hydrologic	Conditions						
		line impressed	on bank		$\boxtimes$	Change	es in character of	soil	
	Bed and banl	ks				Water	staining		
	Shelving					Vegeta	ition matted down	, bent o	r absent
	☐ Wrack lines (	litter and debris)			$\boxtimes$	Change	e in plant commu	nity	
	Scour and/or     Scour and/or	Deposition				Destru	ction of terrestrial	vegeta	tion
	☐ Line of mud of	or silt on tree trui	nks/vegetati	on		Debris	stuck on overhan	iging tre	e limbs
	Other								
Fie	ld-Derived Eviden	ce of Bankfull St	age/Dischar	ge Water					
	☐ Scour line					Recent	t changes to river	bends/ı	meanders
	□ Depositional	bench (active ch	nannel)		$\boxtimes$	Undercuts			
	□ Depositional	point bar				Staining of rocks			
	□ Depositional	island			$\boxtimes$	Top of	point bars		
	☐ Middle bench	for braided rive	rs		$\boxtimes$	Lower	limits in perennial	vegeta	tion
		e of banks (flood	dplain break	)					
	Other								
D.	Inventory (Plant C	Community)							
Rig	ht Bank								
	Total % Cover:	90 Bank Vegetation		75 Overhanging Ve	getati	on .	100 Riparian Vegetation		
	Percent Cover of	Bank and Over	hanging Stre	eam Vegetati	on b	y Strata			
	30 Trees (> 20')	0 Shrubs (< 20')	0 	ly vines	0 Mo:	sses	90 Herbaceous	2	

Left Bank

	Total % Cover:	80	80		100			
		Bank Vegetation Overhanging V			Riparian Vegetation			
	Percent Cover of	f Bank and Overhang		etation by Stra	trata			
	70 Trees (> 20')	70 Shrubs (< 20')	50 Woody vines	<u>0</u> 	20 Herbaceous			
Do	,	parian Vegetation by S		WOODCO	Holbaccous			
rei	cent Cover of Kip	anan vegetation by s	Siraia					
	80 Trees (> 20')	70 Shrubs (< 20')	30 Woody vines	0 Mosses	60 Herbaceous			
Ba	nk and overhangi	ng vegetation plant lis	st (species that o	comprise 10%	or more of the vegetative cover dominant plant species for the s	in each trata):		
	Strata Plar	t Species		Strata	Plant Species			
					the vegetative cover in each strata):	ata, or any		
Not	seedlings, and n	nosses) I tables for plant spec		es grasses, he	rbs, pterophytes [ferns], lichens	, woody		
	Wildlife Food							
	Important wetland/aquatic food plants							
	☐ Abundant	⊠ Prese		Absent	☐ Not Applicable			
	Important upland	I food plants (hard ma	ast and fruit/berr	y producers)				
	☐ Abundant	⊠ Prese	ent [	Absent	☐ Not Applicable			
	Cover/Perches/	Basking/Denning/Ne	esting Habitat					
	Trees (live or dead) > 30" DBH							
	☐ Abundant	□ Prese	ent [	Absent	☐ Not Applicable			
	Standing dead tr	ees (potential for cav	ities and perche	s)				

Abundant	□ Present	☐ Absent	☐ Not Applicable				
Tree cavities in trunks or lin	nbs						
Abundant	□ Present	Absent	☐ Not Applicable				
Small mammal burrows:							
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable				
Dense herbaceous cover (v	voles, small mammals, ar	mphibians & reptiles)					
Abundant	□ Present	Absent	☐ Not Applicable				
Large woody debris on the	ground (small mammals,	, mink, amphibians & rep	tiles)				
	☐ Present	Absent	☐ Not Applicable				
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)				
	☐ Present	Absent	□ Not Applicable				
Overhanging branches at or within 1 m above the water's surface (turtles, snakes, frogs, wading birds, wood duck, mink, raccoon)							
☐ Abundant	□ Present	Absent	□ Not Applicable				
Rock piles, crevices, or hol	low logs suitable for vario	ous mammals (otter, min	k, porcupine, racoon):				
☐ Abundant	□ Present	Absent	□ Not Applicable				
Live or dead tall standing voosprey, kingfisher, flycatche		near water offering goo	d visibility of open water (e.g.,				
	☐ Present	Absent	☐ Not Applicable				
Other Important Habitat C	Characteristics:						
Underwater banks of fine si	ilt and/or clay (beaver, m	uskrat, otter)					
☐ Abundant	□ Present	Absent	☐ Not Applicable				
Undercut or overhanging ba	anks (small mammals, m	ink, weasels, turtles)					
☐ Abundant	□ Present	Absent	☐ Not Applicable				
Vertical sandy banks (bank swallow, kingfisher)							
☐ Abundant	☐ Present		Not Applicable				
Mud flats							
☐ Abundant	□ Present	Absent	☐ Not Applicable				
Exposed areas of well-drained, sandy soil suitable for turtle nesting							
☐ Abundant		Absent	□ Not Applicable				

#### Wildlife Dens/Nests (if observed)

	Turtle nesting sites						
	☐ Abundant	☐ Present		☐ Not Applicable			
	Bank swallow colony(ies)						
	Abundant	☐ Present		□ Not Applicable			
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron			
	Den(s) present of	☐ Otter	Mink	☐ Beaver			
	Other nests or dens (identify	y species):					
IV.	Connectivity with Adjoini	ng Natural Habitats					
	☐ No direct connections t	to adjacent areas of wildli	ife habitat (little o	connectivity function)			
	Limited number of conr	nectors to adjacent areas	of habitat (som	ewhat important for connectivity function)			
	☐ Riverbank is embedded connectivity function)	in a large area of natura	al habitat with ur	nimpeded connection to other habitats (high			
V.							
		Area 2 🛛 Core Area	a 3 🔲 Core /	Area 4			
	Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat						
	•	abitat (including species v					
	American Bittern, Bristly Bu Moth, Spine-crowned Clubt			sedge, Mustard White, Ostrich Fern Borer			
	Rare species direct observa	ations during current field	l surveys:				
VI.	Incidental Direct Wildlife	Observations					
	Kingfisher			_			

General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form					
VII. Habitat Degradation (identify specific location on b	ank segment if applicable)				
☐ Evidence of significant levels of dumping					
☐ Evidence of significant erosion or sedimentation pr	oblems				
□ Occurrence of invasive plants (e.g., purple loosestrife, <i>Phragmites</i> , glossy buckthorn); identify plants and estimate approximate percent coverage:     □ Bittersweet, reed canary grass					
	ewer line crossing				
VIII.Restoration Opportunities					
☑ Presence of potential restoration resources (e.g., beank stabilization or hibernacula, plant propagation sources woody debris, root wads, boulders, cobblete.)					
R: Root wads; Log or rock vanes					
L: Reshape point bar					
Invasive species control					
Revegetation					

Bank 17 Plant Species List				
<u>Left bank</u>	Right bank			
boxelder   Acer negundo   tree	silver maple   Acer saccharinum   tree			
silver maple   Acer saccharinum   tree	nodding beggar-ticks   Bidens cernua   herb			
nodding beggar-ticks   Bidens cernua   herb	spotted Joe-Pye weed   Eupatorium maculatum   herb			
Asian bittersweet   Celastrus orbiculatus   vine/liana   *	green ash   Fraxinus pennsylvanica   tree			
red-osier dogwood   Cornus sericea   shrub	common soft rush   Juncus effusus   herb			
jewelweed   Impatiens capensis   herb	Allegheny monkeyflower   Mimulus ringens   herb			
pale smartweed   Persicaria lapathifolia   herb	sensitive fern   Onoclea sensibilis   herb			
Canada clearweed   Pilea pumila   herb	ditch-stonecrop   Penthorum sedoides   herb			
river grape   Vitis riparia   vine/liana	pale smartweed   Persicaria lapathifolia   herb			
	reed canary grass   Phalaris arundinacea   herb   *			
	Canada clearweed   Pilea pumila   herb			
	green-headed coneflower   Rudbeckia laciniata   herb			

<sup>\*</sup>Invasive species


#### Bank 17 Floodplain Plant Species d Populus deltoides

Eastern cottonwood	Populus deltoides	T
silver maple	Acer saccharinum	T
green ash	Fraxinus pennsylvanica	T
common buckthorn	Rhamnus cathartica	S
American elm	Ulmus americana	S
Asian bittersweet	Celastrus orbiculatus	V
stinging nettle	Urtica dioica	Н
Pennsylvania smartweed	Persicaria pensylvanica	Н
black mustard	Brassica nigra	Н
water forget-me-not	Myosotis scorpioides	Н
reed canary grass	Phalaris arundinacea	Н



Photos of Bank 17 Area, August 30, 2022





I.	Ge	neral Informat	tion					
	Housatonic ROR R5A Bank 18							
	Site Name and Evaluation Segment  Bank 18: Stations 135-138. 300-ft stretch of sharp bends							
	Location/Physical Description							
		5/22 e(s) of Site Visit	(s) and Data Collection	า				
	We	ather Conditions	s During Site Visit					
	AE(	СОМ	-					
	Fiel	d Staff Performi	ng Evaluation				Date this form was completed	
II.	Site	e Description						
A.	Ban	k Characteriza	ation					
Phy	/sica	al Dimensions	(ft):					
Len	gth:	300'	Width: 70'	Bank Height: R 6	6-7' L 7	<b>'-</b> 8'	Slope: R 60% L 90-100%	
Sec	dime	ent / Substrate	composition:					
% 5	Sand	d 45	% Silt 45	% Clay		% G	ravel/cobble 10	
% E	3oul	der/Bedrock	%	Organic matter				
Left	t bar elop	nk is steep and oment in upper		ollowed by bar deve eep cut with mature	tree roc		nd the bend. Right bank is gentle with bar n lower part around the bend. Right bank	
В.		dering Habitat			g			
	tland	_			Unland	ı		
vve	liani	u			Upland		hern Hardwoods-Hemlock-White Pine	
		Transitional fl	oodplain forest			Fore		
		High terrace f	loodplain forest			Rich	mesic forest	
		Red maple sv	vamp			Red	Oak-Sugar Maple Transition Forest	
	$\boxtimes$	Vernal pool				Agri	cultural fields	
		Black ash-red swamp	l maple-tamarack ca	llcareous seepage		Cult	ural grassland	
	☐ Deep emergent marsh				Suc	cessional northern hardwoods		
	Shallow emergent marsh			Spru	uce-fir-northern hardwood forest			
		Shrub swamp	)			Dev	eloped/disturbed cover types	
		Wet meadow				Othe	er	
		Other						
Not	-Δς.							

C.	Hydrology							
Stre	Stream gradient:							
De	Degree of overbank flooding potential / floodplain connectivity							
		annels present ir	n adjacent f	loodplain	$\boxtimes$	Торо	graphic breaks prese	nt in the riverbank
	☐ Channel is de	eeply incised	☐ Mode	rately incised	i	$\boxtimes$	Somewhat incised	☐ Not incised
De	gree of Water leve	I fluctuation (est	imated vert	ical differenc	e fron	n mea	n low water to):	
	Bankfull indicator	s: 3 ft	Top of ba	nk slope: 6-8	ft	Flo	odplain surface: 6-8 f	t
Fie	ld-Derived Evidend	ce of Hydrologic	Conditions	;				
		line impressed	on bank		$\boxtimes$	Chan	ges in character of so	oil
	⊠ Bed and bank	ks				Wate	r staining	
	Shelving					Vege	tation matted down, b	pent or absent
	☐ Wrack lines (	litter and debris)	)		$\boxtimes$	Change in plant community		
		Deposition				Destr	uction of terrestrial ve	egetation
	Line of mud o	or silt on tree tru	nks/vegetat	tion		Debri	s stuck on overhangi	ng tree limbs
	Other							
Fie	ld-Derived Evidend	ce of Bankfull St	age/Discha	ırge Water				
	☐ Scour line					Rece	nt changes to river be	ends/meanders
	□ Depositional	bench (active ch	nannel)		$\boxtimes$	Undercuts		
	□ Depositional	point bar				Staining of rocks		
	Depositional	island			$\boxtimes$	Top of point bars		
	☐ Middle bench	for braided rive	ers		$\boxtimes$	Lowe	r limits in perennial v	egetation
	□ Break in slope	e of banks (flood	dplain breal	k)				
	Other							
D.	Inventory (Plant C	Community)						
Rig	ıht Bank							
	Total % Cover:	100 Bank Vegetation	on .	25 Overhanging V	egetati	on	100 Riparian Vegetation	
	Percent Cover of	Bank and Over	hanging Stı	ream Vegeta	tion b	y Strat	ta	
	20 Trees (> 20')	20 Shrubs (< 20')	<u>20</u>	ody vines	<u>0</u>	sses	90 Herbaceous	

Left Bank

	Total % Cover:	70	80		100			
		Bank Vegetation Overhanging V			Riparian Vegetation			
		f Bank and Overhang		etation by Stra				
	30 Trees (> 20')	50 Shrubs (< 20')	30 Woody vines	0 Mosses	<u>70</u> Herbaceous			
Per	,	parian Vegetation by S	-					
	·			•				
	60 Trees (> 20')	80 Shrubs (< 20')	20 Woody vines	<del>0</del> Mosses				
Baı	strata, or any am	ng vegetation plant lis nount of an invasive p nt Species	st (species that co lant species; "*" (	omprise 10% designates a d	or more of the vegetative cover dominant plant species for the s Plant Species	in each trata):		
					the vegetative cover in each st species for the strata):	rata, or any		
Not	seedlings, and m	nosses) I tables for plant spec		es grasses, he	erbs, pterophytes [ferns], lichens	s, woody		
	Wildlife Food							
	Important wetlan	d/aquatic food plants						
	☐ Abundant	□ Prese	ent [	Absent	□ Not Applicable			
	Important upland	I food plants (hard ma	ast and fruit/berry	producers)				
	☐ Abundant	□ Prese	ent [	Absent	☐ Not Applicable			
	Cover/Perches/	Basking/Denning/Ne	esting Habitat					
	Trees (live or dead) > 30" DBH							
	☐ Abundant	∑ Prese	ent [	Absent				
	Standing dead tr	ees (potential for cav	ities and nerches	:)				

Abundant	□ Present	☐ Absent	□ Not Applicable						
Tree cavities in trunks or lin	nbs								
☐ Abundant	□ Present	Absent	☐ Not Applicable						
Small mammal burrows:									
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable						
Dense herbaceous cover (v	voles, small mammals, ar	mphibians & reptiles)							
	Present	Absent	☐ Not Applicable						
Large woody debris on the	ground (small mammals,	, mink, amphibians & rep	tiles)						
Abundant	□ Present	Absent	☐ Not Applicable						
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)						
Abundant	□ Present	Absent	□ Not Applicable						
Overhanging branches at or within 1 m above the water's surface (turtles, snakes, frogs, wading birds, wood duck, mink, raccoon)									
☐ Abundant	□ Present	Absent	☐ Not Applicable						
Rock piles, crevices, or hol	Rock piles, crevices, or hollow logs suitable for various mammals (otter, mink, porcupine, racoon):								
☐ Abundant	□ Present	Absent	□ Not Applicable						
Live or dead tall standing voosprey, kingfisher, flycatche		near water offering goo	d visibility of open water (e.g.,						
	Present	Absent	☐ Not Applicable						
Other Important Habitat C	Characteristics:								
Underwater banks of fine si	ilt and/or clay (beaver, m	uskrat, otter)							
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable						
Undercut or overhanging ba	anks (small mammals, m	ink, weasels, turtles)							
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable						
Vertical sandy banks (bank swallow, kingfisher)									
☐ Abundant	Present		Not Applicable						
Mud flats									
☐ Abundant	□ Present	Absent	☐ Not Applicable						
Exposed areas of well-drained, sandy soil suitable for turtle nesting									
☐ Abundant		☐ Absent	□ Not Applicable						

#### Wildlife Dens/Nests (if observed)

	Turtle nesting sites								
	☐ Abundant	☐ Present		□ Not Applicable					
	Bank swallow colony(ies)								
	☐ Abundant	☐ Present		☐ Not Applicable					
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron					
	Den(s) present of	☐ Otter	Mink	☐ Beaver					
	Other nests or dens (identif	y species):							
IV.	Connectivity with Adjoini	ng Natural Habitats							
	☐ No direct connections t	o adjacent areas of wildli	ife habitat (little d	connectivity function)					
	Limited number of conr	nectors to adjacent areas	of habitat (some	ewhat important for connectivity function)					
	Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with ur	impeded connection to other habitats (high					
٧.									
		Area 2 🔀 Core Are	a 3 🔲 Core A	Area 4					
	Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat								
	<u> </u>	abitat (including species v		··· · · · · · · · · · · · · · · · · ·					
	American Bittern, Brook Sr crowned Clubtail, Wapato,		dge, Mustard W	hite, Ostrich Fern Borer Moth, Spine-					
	Rare species direct observa	ations during current field	surveys:						
VI.	Incidental Direct Wildlife	Observations							
	Canada geese								
	Great blue heron								
	Painted turtle								
	Titmouse								
	Goldfinch								

General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form				
VII. Habitat Degradation (identify specific location on b	ank segment if applicable)			
Evidence of significant levels of dumping				
Evidence of significant erosion or sedimentation pr	oblems			
Occurrence of invasive plants: Bittersweet, Japanese knotweed, common buckthorn, dame's-rocket, purple loosestrife				
Evidence of other human disturbance; describe:				
VIII.Restoration Opportunities				
□ Presence of potential restoration resources (e.g., beank stabilization or hibernacula, plant propagation so Coarse woody debris, large trees, root wads, cobb				
○ Other restoration opportunities:				
R: Log or rock vanes; Vegetated riprap; Root wads				
L: Reshape point bar				
Invasive species control				
Revegetation				

Bank 18 Plant Species List				
<u>Left bank</u>	Right bank			
boxelder   Acer negundo   tree	boxelder   Acer negundo   tree			
silver maple   Acer saccharinum   tree	silver maple   Acer saccharinum   tree			
nodding beggar-ticks   Bidens cernua   herb	nodding beggar-ticks   Bidens cernua   herb			
Asian bittersweet   Celastrus orbiculatus   vine/liana   *	Asian bittersweet   Celastrus orbiculatus   vine/liana   *			
white turtlehead   Chelone glabra   herb	crested wood fern   Dryopteris cristata   herb			
virgin's-bower   Clematis virginiana   vine	Japanese knotweed   Fallopia japonica   herb   *			
Japanese knotweed   Fallopia japonica   herb   *	purple loosestrife   Lythrum salicaria   herb   *			
dame's-rocket   Hesperis matronalis   herb   *	pale smartweed   Persicaria lapathifolia   herb			
common water-purslane   Ludwigia palustris   herb	Atlantic ninebark   Physocarpus opulifolius   shrub			
ostrich fern   Matteuccia struthiopteris   herb	American sycamore   Platanus occidentalis   tree			
giant chickweed   Myosoton aquaticum   herb	blue vervain   Verbena hastata   herb			
pale smartweed   Persicaria lapathifolia   herb				
common buckthorn   Rhamnus cathartica   herb   *				
eastern black currant   Ribes americanum   shrub				
green-headed coneflower   Rudbeckia laciniata   herb				
river grape   Vitis riparia   vine/liana				

<sup>\*</sup>Invasive species

#### **Bank 18 Floodplain Plant Species**


boxelder Acer negundo		T
boxelder	Acer negundo	S
American sycamore	Platanus occidentalis	T
dotted smartweed	Persicaria punctata	Н
black mustard	Brassica nigra	Н
common cocklebur	Xanthium strumarium	Н



Left bank looking downstream from Station 135 +50



Left bank looking upstream from Station 136





Left bank looking downstream from Station 136+50. Overhanging silver maple.

Right bank (right) to left bank (left) looking downstream from Station 137

l.	Gei	neral Informa	tion				
	Housatonic ROR R5A Bank 19						
	Site Name and Evaluation Segment						
	Bank 19: Stations 147-150. 300-ft along sharp right bend Location/Physical Description						
	8/25	5/22	·				
	Date	e(s) of Site Visit	(s) and Data Collec	tion			
	Wea	ather Conditions	s During Site Visit				
		COM					
	Field	d Staff Performi	ing Evaluation			Date this form was completed	
II.	Site	e Description					
A.	Ban	k Characteriza	ation				
Ph	ysica	al Dimensions	(ft):				
Ler	nath:	300'	Width: 80'	Bank Height: R 7	" L 5-7'	Slope: R 40% L 30% upstream,	
	Ū			3		90% downstream	
Se	dime	nt / Substrate	composition:				
% \$	Sand	I 40	% Silt 50	% Clay		% Gravel/cobble 10	
% I	Boul	der/Bedrock		% Organic matter			
Bai	nk st	ability / Obser	ved erosional con	ditions: Very variable	on both	banks.	
	eft b	ank around be	end is slumping (E	Extreme BEHI and mod	erate NI	BS). Right bank also with some slumping but	
	mos	stly moderate	BEHI and low NB	S. Thalweg moves righ	ht to left		
В.	Boro	dering Habitat	Types				
We	etland	d			Upland		
	$\boxtimes$	Transitional fl	loodplain forest			Northern Hardwoods-Hemlock-White Pine	
			•		_	Forest	
	Ш	High terrace f	floodplain forest			Rich mesic forest	
		Red maple sv	wamp			Red Oak-Sugar Maple Transition Forest	
		Vernal pool				Agricultural fields	
		Black ash-red swamp	d maple-tamarack	calcareous seepage		Cultural grassland	
		Deep emerge	ent marsh			Successional northern hardwoods	
	$\boxtimes$	Shallow emer	rgent marsh			Spruce-fir-northern hardwood forest	
	$\boxtimes$	Shrub swamp	)			Developed/disturbed cover types	
		Wet meadow				Other	
		Other					

Note	es:								
C.	Hydro	ology							
Stre	am g	gradient:	□ Low Grade     □	dient	☐ Mid-Gra	dient		☐ High-Gradient	
Deg	ree o	of overbank fl	ooding potential	/ floodpl	ain connectivit	y			
	⊠ I	High-flow cha	innels present in	adjacen	t floodplain	$\boxtimes$	Торо	graphic breaks present i	n the riverbank
		Channel is de	eply incised	⊠ Mod	derately incised	b		Somewhat incised	□ Not incised
Deg	ree o	of Water level	I fluctuation (est	mated ve	ertical differenc	e fron	n meai	n low water to):	
	Bank	kfull indicators	s: 3-4' ft	Top of b	oank slope: 5-7	ft ft	Floo	odplain surface: 5-7 ft	
Fiel	d-De	rived Evidend	ce of Hydrologic	Conditio	ns				
		Clear natural	line impressed o	on bank		$\boxtimes$	Chan	ges in character of soil	
	⊠ I	Bed and bank	(S				Water	staining	
	$\boxtimes$ :	Shelving					Veget	ation matted down, ben	t or absent
	□ \	Wrack lines (I	itter and debris)			$\boxtimes$	Chan	ge in plant community	
	$\boxtimes$ :	Scour and/or	Deposition				Destr	uction of terrestrial vege	etation
	I	Line of mud o	or silt on tree trur	nks/veget	ation		Debris	s stuck on overhanging	tree limbs
		Other							
Fiel	d-De	rived Evidenc	ce of Bankfull St	age/Disc	harge Water				
		Scour line					Recei	nt changes to river bend	ls/meanders
	□ Depositional bench (active channel)			$\boxtimes$	Unde	rcuts			
	□ Depositional point bar				Staini	ng of rocks			
		Depositional i	sland			$\boxtimes$	Тор о	f point bars	
		·	for braided rive	rs		$\boxtimes$		· r limits in perennial vege	etation
			e of banks (flood		ak)			, ,	
			,						
D.		ntory (Plant C							
	ht Ba	• `	, , , , , , , , , , , , , , , , , , , ,						
9		ıl % Cover:	100 Bank Vegetation	on .	10 Overhanging V	'egetatio	on .	100 Riparian Vegetation	-
	Perd	cent Cover of	Bank and Overl	nanging S	Stream Vegeta	tion b	y Strat	a	
	10 Trees	s (> 20')	10 Shrubs (< 20')	$\frac{10}{\text{W}}$	oody vines	0 Mos	sses	90 Herbaceous	_

Left Bank

	Total % Cover:	60	10		100	
		Bank Vegetation Overhanging \		•	Riparian Vegetation	
		of Bank and Overhang		etation by Stra		
	10 Trees (> 20')	10 Shrubs (< 20')	10 Woody vines	<del>0</del> Mosses	<u>60</u> Herbaceous	
Per	,	parian Vegetation by S				
	·			0	00	
	40 Trees (> 20')	70 Shrubs (< 20')	25 Woody vines	<del>U</del> Mosses	Herbaceous	
Bar	strata, or any am	ng vegetation plant lis nount of an invasive p nt Species	et (species that co	omprise 10% o designates a o Strata	or more of the vegetative cover in dominant plant species for the strange Plant Species	each ata):
					the vegetative cover in each strats species for the strata):	ta, or any
Not	seedlings, and m	nosses) I tables for plant spec		es grasses, he	rbs, pterophytes [ferns], lichens, v	woody
	Wildlife Food					
		nd/aquatic food plants				
	_	_		7		
	☐ Abundant	⊠ Prese	ent L	Absent	☐ Not Applicable	
	Important upland	d food plants (hard ma	ast and fruit/berry	producers)		
	☐ Abundant	⊠ Prese	ent [	Absent	□ Not Applicable	
	Cover/Perches/	Basking/Denning/Ne	esting Habitat			
	Trees (live or de					
		_		7. Abacat	Nea Accident	
	☐ Abundant	☐ Prese	ent 🕑	Absent	☐ Not Applicable	
	Standing dead tr	ees (potential for cavi	ities and perches	)		

☐ Abundant	Present		□ Not Applicable		
Tree cavities in trunks or lin	nbs				
Abundant	□ Present	☐ Absent	☐ Not Applicable		
Small mammal burrows:					
Abundant	□ Present	Absent	☐ Not Applicable		
Dense herbaceous cover (v	voles, small mammals, ar	mphibians & reptiles)			
	☐ Present	Absent	☐ Not Applicable		
Large woody debris on the	ground (small mammals	, mink, amphibians & rep	tiles)		
Abundant	□ Present	Absent	□ Not Applicable		
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)		
Abundant	□ Present	Absent	□ Not Applicable		
Overhanging branches at o duck, mink, raccoon)	r within 1 m above the w	ater's surface (turtles, sr	nakes, frogs, wading birds, wood		
☐ Abundant	□ Present	Absent	□ Not Applicable		
Rock piles, crevices, or holl	low logs suitable for vario	ous mammals (otter, min	k, porcupine, racoon):		
Abundant	□ Present	Absent	□ Not Applicable		
Live or dead tall standing voosprey, kingfisher, flycatche		near water offering goo	d visibility of open water (e.g.,		
Abundant	□ Present	Absent	□ Not Applicable		
Other Important Habitat C	Characteristics:				
Underwater banks of fine si	ilt and/or clay (beaver, m	uskrat, otter)			
	☐ Present	Absent	□ Not Applicable		
Undercut or overhanging ba	anks (small mammals, m	ink, weasels, turtles)			
Abundant	□ Present	Absent	□ Not Applicable		
Vertical sandy banks (bank	swallow, kingfisher)				
Abundant	Present		Not Applicable		
Mud flats					
Abundant	□ Present	Absent	□ Not Applicable		
Exposed areas of well-drained, sandy soil suitable for turtle nesting					
☐ Abundant	□ Present	Absent	□ Not Applicable		

#### Wildlife Dens/Nests (if observed)

	Turtle nesting sites						
	☐ Abundant	☐ Present		□ Not Applicable			
	Bank swallow colony(ies)						
	☐ Abundant	☐ Present		☐ Not Applicable			
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron			
	Den(s) present of	☐ Otter	☐ Mink	☐ Beaver			
	Other nests or dens (identif	y species):					
IV.	Connectivity with Adjoini	ng Natural Habitats					
	☐ No direct connections t	o adjacent areas of wildli	fe habitat (little d	connectivity function)			
	☐ Limited number of conr	nectors to adjacent areas	of habitat (some	ewhat important for connectivity function)			
	Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with un	nimpeded connection to other habitats (high			
٧.	Rare Species and MNHES	SP Core Area Habitat De	esignation				
	□ Core Area 1    □ Core	Area 2 🔀 Core Area	a 3 🔲 Core A	Area 4			
	☐ Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat						
	State-listed species ha	ubitat (including species v	vith known overl	apping Priority Habitat):			
	American Bittern, Hairy Wild Rye, Matted Spike-sedge, Mustard White, Spine-crowned Clubtail, Wapato, Wood Turtle						
	Rare species direct observa	ations during current field	surveys:				
VI.	Incidental Direct Wildlife	Observations					

General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form				
VII. Habitat Degradation (identify specific location on b	ank segment if applicable)			
Evidence of significant levels of dumping				
	oblems: Slumping along left bank			
○ Occurrence of invasive plants:     Japanese knotweed				
Evidence of other human disturbance; describe:				
VIII.Restoration Opportunities				
□ Presence of potential restoration resources (e.g., beank stabilization or hibernacula, plant propagation so Coarse woody debris, large trees, cobbles	ooulders, large trees or woody debris, root wad material for urce material). Identify specific items:			
○ Other restoration opportunities:				
R: Grade bank/Coir matting; Reshape point bar				
L: Log or rock vanes; Vegetated riprap; Root wads				
Invasive species control				
Revegetation				

Bank 19 Plant Species List				
Left bank	Right bank			
nodding beggar-ticks   Bidens cernua   herb	boxelder   Acer negundo   tree			
Japanese knotweed   Fallopia japonica   herb   *	silver maple   Acer saccharinum   tree			
pale smartweed   Persicaria lapathifolia   herb	nodding beggar-ticks   Bidens cernua   herb			
green-headed coneflower   Rudbeckia laciniata   herb	Japanese knotweed   Fallopia japonica   herb   *			
American bur-reed   Sparganium americanum   herb	yellow-seeded false pimpernel   Lindernia dubia   herb			
blue vervain   Verbena hastata   herb	pale smartweed   Persicaria lapathifolia   herb			
	green-headed coneflower   Rudbeckia laciniata   herb			
	blue vervain   Verbena hastata   herb			

<sup>\*</sup>Invasive species

#### **Bank 19 Floodplain Plant Species**

silver maple	Acer saccharinum	T
Canadian nettle	Laportea canadensis	Н
garlic-mustard	Alliara petiolata	Н
ostrich fern	Matteuccia struthiopteris	Н
white avens	Geum canadense	Н



Bank 19: Station 147-150. 300-ft tight bend to right

Photos of Bank 19 Area. August 25, 2022



Right bank (right) to left bank (left) looking downstream from Station 146 +50



Right bank at Station 147.



Right bank below Station 147 looking downstream. Bar formation with sandy material in higher elevations with siltier material lower down.



Right bank at Station 148 looking downstream, bar transitions to bankfull marsh in right cove. Trees to rear are near Station150 as river bends left



Left bank looking downstream from Station 147



Left bank from right bank at Station 148



Left bank from right bank at Station 149



Left bank from right bank looking upstream from Station 149



Bankfull marsh between Stations 149-150

Notes:

#### **General Information** Housatonic ROR R5A Bank 20 Site Name and Evaluation Segment Bank 20: Stations 154-156. 200-ft stretch along straight run Location/Physical Description 8/16/22 Date(s) of Site Visit(s) and Data Collection Weather Conditions During Site Visit Field Staff Performing Evaluation Date this form was completed Site Description A. Bank Characterization Physical Dimensions (ft): Length: 200' Width: 80' Bank Height: R 5' L 4' Slope: R 50% L 30% Sediment / Substrate composition: % Sand 50% % Silt 35% % Gravel/cobble 15% % Clay % Boulder/Bedrock % Organic matter Bank stability / Observed erosional conditions: Both banks relatively stable. Both banks have low NBS and moderate BEHI. Thalweg runs along center. B. Bordering Habitat Types Wetland Upland Northern Hardwoods-Hemlock-White Pine Forest ☐ High terrace floodplain forest Rich mesic forest Red maple swamp Red Oak-Sugar Maple Transition Forest Vernal pool Agricultural fields Black ash-red maple-tamarack calcareous seepage Cultural grassland swamp Successional northern hardwoods Deep emergent marsh Shallow emergent marsh Spruce-fir-northern hardwood forest Developed/disturbed cover types Wet meadow Other \_\_\_\_\_ Other

1

C.	Hydrology					
Stre	am gradient:		High-Gradient			
Deg	Degree of overbank flooding potential / floodplain connectivity					
		oodplain 🛚	Topographic breaks present in the riverbank			
	☐ Channel is deeply incised ☐ Moder	ately incised	☐ Somewhat incised ☐ Not incised			
Deg	ree of Water level fluctuation (estimated verti	cal difference from	m mean low water to):			
	Bankfull indicators: 2.5-3 ft Top of bar	nk slope: 4 ft L	Floodplain surface: 4 ft			
Fiel	d-Derived Evidence of Hydrologic Conditions					
			Changes in character of soil			
	Bed and banks		Water staining			
	Shelving		Vegetation matted down, bent or absent			
	☐ Wrack lines (litter and debris)		Change in plant community			
	Scour and/or Deposition		Destruction of terrestrial vegetation			
	☐ Line of mud or silt on tree trunks/vegetati	on $\square$	Debris stuck on overhanging tree limbs			
	☐ Other					
Fiel	Field-Derived Evidence of Bankfull Stage/Discharge Water					
	☐ Scour line		Recent changes to river bends/meanders			
	□ Depositional bench (active channel)		Undercuts			
	□ Depositional point bar		Staining of rocks			
	☐ Depositional island		Top of point bars			
	☐ Middle bench for braided rivers		Lower limits in perennial vegetation			
	□ Break in slope of banks (floodplain break)	)				
	Other					
D.	Inventory (Plant Community)					
Rig	nt Bank					
		60 Overhanging Vegetation	tion Riparian Vegetation			
	Percent Cover of Bank and Overhanging Str	eam Vegetation by	by Strata			
	60 20 20 Trees (> 20') Shrubs (< 20') Wood	dy vines <u>0</u>	osses 60 Herbaceous			

Left Bank

	Total % Cover:	90 Bank Vegetation	80 Overhangin	g Vegetation	90 Riparian Vegetation		
	Percent Cover of Bank and Overhanging Stream Vegetat		etation by Stra	ıta			
	0	75 Shrubs (< 20')	40 Woody vines	0 Mosses	20		
				Mosses	Herbaceous		
Per	cent Cover of Rip	parian Vegetation by S	Strata				
	50	75 Shrubs (< 20')	20	0	90		
	, ,	, ,	•		Herbaceous		
Bar					or more of the vegetative cover in each dominant plant species for the strata):		
	•	nt Species	,	Strata	Plant Species		
	Cirata Fiai	породов		Otrata	Tiant openies		
	Rinarian vegeta	tion plant list (species	that comprise 10	1% or more of	the vegetative cover in each strata, or any		
					t species for the strata):		
				_			
Stra	ata: T=Tree, S=S	Shrub, L=Liana (vine),	H=Herb (Include	es grasses, he	erbs, pterophytes [ferns], lichens, woody		
	seedlings, and r						
Not	es: See attache	d tables for plant lists.					
	Important Habi	tat Faaturas					
	Important Habitat Features						
	Wildlife Food						
	Important wetland/aquatic food plants						
	☐ Abundant	⊠ Prese	ent [	Absent	☐ Not Applicable		
	mportant upland food plants (hard mast and fruit/berry producers)						
	☐ Abundant	⊠ Prese	ent [	Absent	☐ Not Applicable		
	Cover/Perches/Basking/Denning/Nesting Habitat						
	Trees (live or de	rees (live or dead) > 30" DBH					
	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	, ⊠ Prese	ant F	Absent	□ Not Applicable		
		△ Prese	511L _	] Ansent	☐ Not Applicable		
	Standing dead t	rees (potential for cav	ities and perches	()			

Abundant	□ Present	☐ Absent	□ Not Applicable		
Tree cavities in trunks or li	mbs				
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable		
Small mammal burrows:					
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable		
Dense herbaceous cover (	voles, small mammals, a	mphibians & reptiles)			
Abundant		☐ Absent	☐ Not Applicable		
Large woody debris on the	ground (small mammals	, mink, amphibians & rep	otiles)		
Abundant	□ Present	☐ Absent	☐ Not Applicable		
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)		
Abundant		Absent	□ Not Applicable		
Overhanging branches at or within 1 m above the water's surface (turtles, snakes, frogs, wading birds, wood duck, mink, raccoon)					
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable		
Rock piles, crevices, or ho	llow logs suitable for vari	ous mammals (otter, min	k, porcupine, racoon):		
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable		
Live or dead tall standing vegetation overhanging or near water offering good visibility of open water (e.g., osprey, kingfisher, flycatchers, cedar waxwings)					
	☐ Present	Absent	☐ Not Applicable		
Other Important Habitat Characteristics:					
Underwater banks of fine s	silt and/or clay (beaver, m	uskrat, otter)			
Abundant		☐ Absent	☐ Not Applicable		
Undercut or overhanging b	oanks (small mammals, m	nink, weasels, turtles)			
Abundant		☐ Absent	☐ Not Applicable		
Vertical sandy banks (bank swallow, kingfisher)					
Abundant	☐ Present		Not Applicable		
Mud flats					
Abundant		Absent	☐ Not Applicable		
Exposed areas of well-drained, sandy soil suitable for turtle nesting					
☐ Abundant	□ Present	Absent	□ Not Applicable		

#### Wildlife Dens/Nests (if observed)

	Turtle nesting sites					
	Abundant	☐ Present		☐ Not Applicable		
	Bank swallow colony(ies)					
	Abundant	Present		□ Not Applicable		
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron		
	Den(s) present of	☐ Otter	☐ Mink	☐ Beaver		
	Other nests or dens (identif	y species):				
IV.	/. Connectivity with Adjoining Natural Habitats					
	☐ No direct connections to adjacent areas of wildlife habitat (little connectivity function)					
	☐ Limited number of connectors to adjacent areas of habitat (somewhat important for connectivity function)					
	☐ Riverbank is embedded in a large area of natural habitat with unimpeded connection to other habitats (high connectivity function)					
٧.	Rare Species and MNHES	SP Core Area Habitat D	esignation			
	☐ Core Area 1 ☐ Core	Area 2 🔀 Core Are	a 3 🔲 Core	Area 4		
	Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat					
	State-listed species habitat (including species with known overlapping Priority Habitat):					
	Hairy Wild Rye, Matted Spike-sedge, Mustard White, Spine-crowned Clubtail, Wapato, Wood Turtle					
	Rare species direct observations during current field surveys:					
VI.	Incidental Direct Wildlife	Observations				
	Kingfisher					
	Wood pewee					
	Phoebe					
	Painted turtle					

General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form		
VII. Habitat Degradation (identify specific location on b	ank segment if applicable)	
☐ Evidence of significant levels of dumping		
Evidence of significant erosion or sedimentation pr	oblems	
Occurrence of invasive plants: Bittersweet, forget-me-not		
Evidence of other human disturbance; describe:		
VIII.Restoration Opportunities		
☑ Presence of potential restoration resources (e.g., be bank stabilization or hibernacula, plant propagation sour Medium woody debris/Coarse woody debris, cobbletic.)		
○ Other restoration opportunities:		
R: Grade bank/Coir matting; Reshape point bar; Bank	c spurs	
L: Grade bank/Coir matting; Bank spurs		
Invasive species control		
Revegetation		

Bank 20 Plan	nt Species List
<u>Left bank</u>	Right bank
nodding beggar-ticks   Bidens cernua   herb	sugar maple   Acer saccharum   tree
red-osier dogwood   Cornus sericea   shrub	Asian bittersweet   Celastrus orbiculatus   vine/liana   *
wild cucumber   Echinocystis lobata   vine	red-osier dogwood   Cornus sericea   shrub
black walnut   Juglans nigra   tree	wild cucumber   Echinocystis lobata   vine
common water-purslane   Ludwigia palustris   herb	European spindle-tree   Euonymus europaeus   shrub/tree
water forget-me-not   Myosotis scorpioides   herb   *	American beech   Fagus grandifolia   tree
water-pepper smartweed   Persicaria hydropiper   herb	American witch hazel   Hamamelis virginiana   shrub
pale smartweed   Persicaria lapathifolia   herb	border privet   Ligustrum obtusifolium   shrub
American bur-reed   Sparganium americanum   herb	ostrich fern   Matteuccia struthiopteris   herb
blue vervain   Verbena hastata   herb	Allegheny monkeyflower   Mimulus ringens   herb
	pale smartweed   Persicaria lapathifolia   herb
	American bur-reed   Sparganium americanum   herb
	eastern hemlock   Tsuga canadensis   tree

<sup>\*</sup>Invasive species

#### Bank 20 Floodplain Plant Species Cornus amomum

silky dogwood	Cornus amomum	S
Joe-Pye weed	Eutrochium maculatum	Н
moneywort	Lysimachia nummularia	Н
senstive fern	Onoclea sensibilis	Н
jewelweed	Impatiens capensis	Н
tearthumb	Persicaria sagittata	Н
Japanese knotweed	Fallopia japonica	Н
Asian bittersweet	Celastrus orbiculatus	V
river grape	Vitis riparia	V
red maple	Acer rubrum	T
American linden	Tilia americana	T
sugar maple	Acer saccharum	T
black cherry	Prunus serotina	T
hickory	Carya sp.	Т
American witch hazel	Hamamelis virginiana	Н
poison ivy	Toxicodendron radicans	Н
Pennsylvania sedge	Carex pensylvanica	Н
jumpseed	Persicaria virginiana	Н
burning bush	Euonymus alatus	S



Bank 20 Stations 154-1156; straight channel before right bend below Joseph Road residential area

Photos of Bank 20 Area, August 16, 2022 downstream left bank (left side) to right bank from Station right bank at Station 155+50 155 Right bank at Station 156 Left bank at Station 156

I.	General Informa	ation						
	Housatonic ROR R5A Bank 21							
	Site Name and Eva			مداء م	wi.u.			
	Location/Physical I	157-161. 400-ft stretch Description	around snarp right be	na to	run			
	8/16/22	·						
	Date(s) of Site Visit(s) and Data Collection							
	Weather Condition	s During Site Visit						
	AECOM Field Stoff Borform	ing Evolution			Date this form was completed			
	Field Staff Perform	ing Evaluation			Date this form was completed			
II.	Site Description	1						
A.	Bank Characteriza	ation						
Phy	sical Dimensions	(ft):						
Ler	ngth: 400'	Width: 80'	Bank Height: R 6-7'	L 4'	Slope: R 90% L 30%			
Sec	diment / Substrate	composition:						
% 5	Sand 30	% Silt 30	% Clay		% Gravel/cobble 20			
% E	Boulder/Bedrock 2	20 % O	rganic matter					
		rved erosional conditio						
Lef	t bank has high N	BS, but is stable with r	ock. Right bank has u	unde	rcuts but is well vegetated.			
В.	Bordering Habitat	Types						
We	tland		Up	land				
		floodplain forest		$\boxtimes$	Northern Hardwoods-Hemlock-White Pine			
		•			Forest			
		floodplain forest		Ш	Rich mesic forest			
	☐ Red maple s	wamp			Red Oak-Sugar Maple Transition Forest			
	✓ Vernal pool			$\boxtimes$	Agricultural fields			
	Black ash-red swamp	d maple-tamarack calc	careous seepage	$\boxtimes$	Cultural grassland			
	☐ Deep emerge	ent marsh			Successional northern hardwoods			
	☐ Shallow eme	rgent marsh			Spruce-fir-northern hardwood forest			
	☐ Shrub swam	р		$\boxtimes$	Developed/disturbed cover types			
	☐ Wet meadow	I			Other			
	Other							
Not	es:							

C.	Hydrology							
Stre	Stream gradient:							
De	Degree of overbank flooding potential / floodplain connectivity							
	☐ High-flow cha	annels present ir	n adjacent floo	odplain 🛚	Торо	graphic breaks presen	t in the riverbank	
	☐ Channel is de	eeply incised	☐ Moderat	tely incised	$\boxtimes$	Somewhat incised	☐ Not incised	
De	gree of Water leve	I fluctuation (est	imated vertica	al difference fro	n mea	n low water to):		
	Bankfull indicator	s: 2.5-3 ft	Top of bank	slope: 4-7' ft	Flo	odplain surface: 4-7'ft		
Fie	ld-Derived Eviden	ce of Hydrologic	Conditions					
		line impressed	on bank	$\boxtimes$	Chan	ges in character of soil	I	
		ks			Wate	r staining		
	Shelving				Vege	tation matted down, be	ent or absent	
	☐ Wrack lines (	litter and debris)	)	$\boxtimes$	Chan	Change in plant community		
	Scour and/or     Scour and/or	Deposition			Destruction of terrestrial vegetation			
	☐ Line of mud o	or silt on tree tru	nks/vegetatio	n 🗆	Debri	is stuck on overhanging	g tree limbs	
	Other							
Fie	ld-Derived Eviden	ce of Bankfull St	age/Discharg	e Water				
	☐ Scour line				Rece	nt changes to river ber	nds/meanders	
	□ Depositional	bench (active ch	nannel)	$\boxtimes$	Undercuts			
	☐ Depositional	point bar			Staining of rocks			
	☐ Depositional	island			Top of point bars			
	☐ Middle bench	for braided rive	ers	$\boxtimes$	Lower limits in perennial vegetation			
	□ Break in slop	e of banks (floo	dplain break)					
	Other							
D.	Inventory (Plant C	Community)						
Rig	ıht Bank							
	Total % Cover:	70 Bank Vegetation	50 on Ov	) verhanging Vegeta	ion	90 Riparian Vegetation	<u> </u>	
	Percent Cover of			ım Vegetation t	y Stra	ta		
	80 Trees (> 20')	50 Shrubs (< 20')	50 Woody	vines 0	nsses	10 Herbaceous		

Left Bank

Total % C	over: 60		50		80	
	Ва	Bank Vegetation Overhanging V			Riparian Vegetation	
		and Overhang		getation by Strat		
50 Trees (> 20'	30 Shrub	s (< 20')	20 Woody vines	<u>0</u> 	80 Herbaceous	
,	,	/egetation by S	•	Widooco	Horsaccous	
	·	regulation by C				
70 Trees (> 20'	60 Shrub	s (< 20')	20 Woody vines	<u>0</u> 	40 Herbaceous	
Bank and ove strata, or Strata	erhanging veg any amount o Plant Spec	f an invasive p	t (species that of lant species; "*"	comprise 10% c " designates a d Strata	or more of the vegetative colominant plant species for the Plant Species	ver in each ne strata):
	· 					
					the vegetative cover in each species for the strata):	n strata, or any
seedlings Notes: See a	, and mosses)	ofor plant spec		— ———des grasses, hei	rbs, pterophytes [ferns], lich	ens, woody
III. Importan		tures				
Wildlife F	<u>food</u>					
Important	wetland/aqua	tic food plants				
Abun	dant	□ Prese	ent	☐ Absent	☐ Not Applicable	
Important	upland food p	olants (hard ma	st and fruit/ber	ry producers)		
Abun	dant	□ Prese	nt	☐ Absent	☐ Not Applicable	
Cover/Pe	rches/Baskir	ng/Denning/Ne	esting Habitat			
Trees (live	e or dead) > 3	0" DBH				
Abun	dant	⊠ Prese	ent	☐ Absent	☐ Not Applicable	
Standing	dead trees (no	otential for cavi	ties and perche	es)		

Abundant	□ Present	☐ Absent	☐ Not Applicable
Tree cavities in trunks or lin	nbs		
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable
Small mammal burrows:			
☐ Abundant	□ Present	Absent	☐ Not Applicable
Dense herbaceous cover (v	voles, small mammals, ar	mphibians & reptiles)	
☐ Abundant	□ Present	Absent	☐ Not Applicable
Large woody debris on the	ground (small mammals	, mink, amphibians & rep	tiles)
	Present	Absent	☐ Not Applicable
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)
	Present	Absent	□ Not Applicable
Overhanging branches at o duck, mink, raccoon)	r within 1 m above the w	ater's surface (turtles, sr	akes, frogs, wading birds, wood
☐ Abundant	□ Present	Absent	☐ Not Applicable
Rock piles, crevices, or hol	low logs suitable for vario	ous mammals (otter, min	k, porcupine, racoon):
	Present	Absent	☐ Not Applicable
Live or dead tall standing v osprey, kingfisher, flycatche		near water offering goo	d visibility of open water (e.g.,
	Present	Absent	☐ Not Applicable
Other Important Habitat C	Characteristics:		
Underwater banks of fine s	ilt and/or clay (beaver, m	uskrat, otter)	
☐ Abundant	□ Present	Absent	☐ Not Applicable
Undercut or overhanging ba	anks (small mammals, m	ink, weasels, turtles)	
☐ Abundant	□ Present	Absent	☐ Not Applicable
Vertical sandy banks (bank	swallow, kingfisher)		
☐ Abundant	Present		Not Applicable
Mud flats			
☐ Abundant	□ Present	Absent	□ Not Applicable
Exposed areas of well-drain	ned, sandy soil suitable f	or turtle nesting	
☐ Abundant		Absent	□ Not Applicable

### Wildlife Dens/Nests (if observed)

	Turtle nesting sites						
	☐ Abundant	☐ Present		□ Not Applicable			
	Bank swallow colony(ies)						
	Abundant	☐ Present		☐ Not Applicable			
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron			
	Den(s) present of	☐ Otter	Mink	☐ Beaver			
	Other nests or dens (identify	y species):					
IV.	Connectivity with Adjoini	ng Natural Habitats					
	☐ No direct connections t	o adjacent areas of wildli	fe habitat (little c	connectivity function)			
		nectors to adjacent areas	of habitat (some	ewhat important for connectivity function)			
	Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with un	nimpeded connection to other habitats (high			
٧.	Rare Species and MNHES	SP Core Area Habitat De	esignation				
	☐ Core Area 1 ☐ Core	Area 2 🔀 Core Area	a 3 🔲 Core A	Area 4			
	$\boxtimes$ Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat						
	•	bitat (including species v		··· · · · · · · · · · · · · · · · · ·			
	Hairy Wild Rye, Matted Sp	ike-sedge, Mustard Whit	e, Spine-crowne	ed Clubtail, Wapato, Wood Turtle			
	Rare species direct observa	ations during current field	surveys:				
VI.	Incidental Direct Wildlife	Observations					

	B-1: Riverbank Habitat Inventory Form	
VII. Hal	pitat Degradation (identify specific location on b	ank segment if applicable)
	Evidence of significant levels of dumping	
	Evidence of significant erosion or sedimentation pr	oblems
	Occurrence of invasive plants	
•	Common buckthorn, bittersweet, forget-me-not	
	Evidence of other human disturbance; describe: or	utlet culvert
VIII.Res	storation Opportunities	
ban	Presence of potential restoration resources (e.g., but stabilization or hibernacula, plant propagation so coarse woody debris, large trees, root wads, cobble	
$\boxtimes$	Other restoration opportunities:	
R	Reshape point bar	
L	: Coir matting; Vegetated rip rap	
Ir	nvasive species control	
R	Revegetation	

Bank 21 Plant Species List					
<u>Left bank</u>	Right bank				
silver maple   Acer saccharinum   tree	sugar maple   Acer saccharum   tree				
nodding beggar-ticks   Bidens cernua   herb	yellow birch   Betula alleghaniensis   tree				
ironwood   Carpinus caroliniana   tree	Asian bittersweet   Celastrus orbiculatus   vine/liana   *				
Asian bittersweet   Celastrus orbiculatus   vine/liana   *	red-osier dogwood   Cornus sericea   shrub				
red-osier dogwood   Cornus sericea   shrub	red-root flatsedge   Cyperus erythrorhizos   herb				
water forget-me-not   Myosotis scorpioides   herb   *	common buckthorn   Rhamnus cathartica   herb   *				
water-pepper smartweed   Persicaria hydropiper   herb	eastern hemlock   Tsuga canadensis   tree				
American sycamore   Platanus occidentalis   tree					
eastern hemlock   Tsuga canadensis   tree					
river grape   Vitis riparia   vine/liana					

<sup>\*</sup>Invasive species

### **Bank 21 Floodplain Plant Species**

red maple	Acer rubrum	T
American linden	Tilia americana	T
sugar maple	Acer saccharum	T
black cherry	Prunus serotina	T
hickory	Carya sp.	T
American witch hazel	Hamamelis virginiana	Н
poison ivy	Toxicodendron radicans	Н
sensitive fern	Onoclea sensibilis	Н
Pennsylvania sedge	Carex pensylvanica	Н
jumpseed	Persicaria virginiana	Н
burning bush	Euonymus alatus	S



Bank 21: Stations 157-161. 400-ft stretch along sharp right bend to run from Station 157-161

Photos of Bank 21 Area. August 16 2022 Right bank (left side) to left bank at bend, looking Right bank near Station 158 upstream Left bank near Station 159 Right bank near Station 159





I.	General Informa	tion				
	Housatonic ROR R					
	Site Name and Eva					
	Bank 22: Stations 1 Location/Physical D	169-172. 300-ft run.				
	8/16/22	Description				
		t(s) and Data Collection				
	Weather Conditions	s During Site Visit				
	AECOM					
	Field Staff Perform	ing Evaluation				Date this form was completed
II.	Site Description					
A.	Bank Characteriza	ation				
Phy	sical Dimensions	(ft):				
Ler	ngth: 300'	Width: 80'	Bank Height: R	4' L 4'		Slope: R 40% L 40%
Sec	diment / Substrate	composition:				
% 5	Sand 45	% Silt 45	% Clay			% Gravel/cobble 10
% E	Boulder/Bedrock	% Or	ganic matter			
Bar	nk stability / Obser	ved erosional condition	ns:			
				ut banks	S.	Both banks moderate BEHI and low NBS.
В.	Bordering Habitat	Types				
We	tland			Uplan	nd	
		loodplain forest			_	Northern Hardwoods-Hemlock-White Pine Forest
	☐ High terrace	floodplain forest				Rich mesic forest
	☐ Red maple sv	wamp				Red Oak-Sugar Maple Transition Forest
	∀ Vernal pool					Agricultural fields
	Black ash-red swamp	d maple-tamarack calc	areous seepage		$\leq$	Cultural grassland
	Deep emerge	ent marsh				Successional northern hardwoods
	☐ Shallow eme	rgent marsh				Spruce-fir-northern hardwood forest
	Shrub swamp     Shrub	)			$\leq$	Developed/disturbed cover types
	☐ Wet meadow					Other
	Other					
Not	es:					

C. Hyd	drology								
Stream	gradient:	⊠ Low Grad	lient	☐ Mid-Grad	ient		] High-Gradient		
Degree	e of overbank fl	ooding potential	/ floodplai	n connectivity					
$\boxtimes$	High-flow cha	nnels present in	adjacent f	floodplain	$\boxtimes$	Topograp	ohic breaks prese	nt in the ri	verbank
	Channel is de	eply incised	☐ Mode	erately incised		☐ So	mewhat incised	$\boxtimes$	Not incised
Degree	Degree of Water level fluctuation (estimated vertical difference from mean low water to):								
Ва	nkfull indicators	s: 2-3 ft	Top of ba	nk slope: 4 ft		Floodp	lain surface: 4 ft		
Field-D	erived Evidend	ce of Hydrologic	Conditions	3					
$\boxtimes$	Clear natural	line impressed o	n bank		$\boxtimes$	Changes	in character of so	oil	
$\boxtimes$	Bed and bank	(S				Water sta	aining		
	Shelving					Vegetatio	on matted down, b	ent or ab	sent
	Wrack lines (I	itter and debris)			$\boxtimes$	Change in plant community			
	Scour and/or	Deposition				Destruction	on of terrestrial ve	egetation	
	Line of mud o	r silt on tree trur	ks/vegeta	tion		Debris st	uck on overhangi	ng tree lim	nbs
	Other								
Field-D	erived Evidenc	ce of Bankfull Sta	age/Discha	arge Water					
	Scour line					Recent c	hanges to river be	ends/mear	nders
$\boxtimes$	Depositional b	pench (active ch	annel)			Undercuts			
	Depositional p	point bar				☐ Staining of rocks			
	Depositional i	sland				Top of point bars			
	Middle bench	for braided river	S		$\boxtimes$	Lower limits in perennial vegetation			
$\boxtimes$	Break in slope	e of banks (flood	plain brea	k)					
	Other								
D. Inv	entory (Plant C	Community)							
Right E	Bank								
To	tal % Cover:	80 Bank Vegetatio	<u> </u>	30 Overhanging Ve	getati		00 parian Vegetation		
Pe	rcent Cover of	Bank and Overh					· · · · ·		
10 Tre	es (> 20')	10 Shrubs (< 20')	10	ody vines	0 Mos	sses	80 Herbaceous		

Left Bank

	Total % Cover:	80 Bank Vegetation	10 Overhangir	ng Vegetation	70 Riparian Vegetation	
	Percent Cover of	Percent Cover of Bank and Overhanging Stream Vegeta		etation by Strat	a	
	0	80 Shrubs (< 20')	10	0	80	
	Trees (> 20')	Shrubs (< 20')	Woody vines	Mosses	Herbaceous	
Pei	rcent Cover of Rip	parian Vegetation by S	Strata			
	10	80 Shrubs (< 20')	10	0	80 Herbaceous	
_			•			
Bai	nk and overhangi strata, or any an	ng vegetation plant lis nount of an invasive p	t (species that c lant species; "*"	comprise 10% c designates a d	or more of the vegetative cover ominant plant species for the s	in each strata):
	Strata Plan	nt Species	•	Strata	Plant Species	,
		·			•	
					-	
					the vegetative cover in each st	rata, or any
	amount of an inv	asive plant species; "	ar designates a	dominant plant	species for the strata):	
Stra	ata: T=Tree, S=S	Shrub, L=Liana (vine),	H=Herb (Includ	es grasses, hei	bs, pterophytes [ferns], lichens	s, woody
	seedlings, and n					
Not	tes: See attached	d tables for plant spec	ies lists.			
III.	Important Habit	tat Features				
	Wildlife Food					
	Important wetlar	nd/aquatic food plants				
	☐ Abundant	⊠ Prese	ent	☐ Absent	☐ Not Applicable	
	Important upland	d food plants (hard ma	st and fruit/berr	y producers)		
	_	' ∖ ⊠ Prese		_	□ Not Applicable	
	☐ Abundant	∠ Prese	erit.	Absent	☐ Not Applicable	
	Cover/Perches/	Basking/Denning/Ne	esting Habitat			
	Trees (live or de	ad) > 30" DBH				
	☐ Abundant	☐ Prese	ent [	⊠ Absent	☐ Not Applicable	
	Standing dead to	rees (potential for cavi	ties and perche	s)		

Abundant	☐ Present		☐ Not Applicable
Tree cavities in trunks	or limbs		
Abundant	☐ Present		☐ Not Applicable
Small mammal burrow	/s:		
Abundant		☐ Absent	□ Not Applicable
Dense herbaceous co	ver (voles, small mamma	als, amphibians & reptile	es)
	☐ Present	☐ Absent	☐ Not Applicable
Large woody debris or	n the ground (small mam	mals, mink, amphibians	s & reptiles)
Abundant		☐ Absent	☐ Not Applicable
Rocks, crevices, logs,	tree roots or hummocks	at water's edge or unde	er water's surface (turtles, snakes, frogs)
Abundant		☐ Absent	□ Not Applicable
Overhanging branched duck, mink, raccoon)	s at or within 1 m above	the water's surface (turt	les, snakes, frogs, wading birds, wood
Abundant	☐ Present		☐ Not Applicable
Rock piles, crevices, c	or hollow logs suitable for	r various mammals (otte	er, mink, porcupine, racoon):
☐ Abundant	☐ Present		☐ Not Applicable
	ing vegetation overhang atchers, cedar waxwings		g good visibility of open water (e.g.,
Abundant		☐ Absent	☐ Not Applicable
Other Important Hab	itat Characteristics:		
Underwater banks of f	ine silt and/or clay (beav	er, muskrat, otter)	
Abundant		☐ Absent	☐ Not Applicable
Undercut or overhang	ing banks (small mamma	als, mink, weasels, turtle	es)
Abundant	☐ Present		□ Not Applicable
Vertical sandy banks (	bank swallow, kingfisher	·)	
Abundant	☐ Present		☐ Not Applicable
Mud flats			
Abundant		☐ Absent	☐ Not Applicable
Exposed areas of well	-drained, sandy soil suita	able for turtle nesting	
☐ Abundant	☐ Present		☐ Not Applicable

### Wildlife Dens/Nests (if observed)

	Turtle nesting sites			
	☐ Abundant	☐ Present		☐ Not Applicable
	Bank swallow colony(ies)			
	Abundant	☐ Present		□ Not Applicable
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron
	Den(s) present of	☐ Otter	Mink	☐ Beaver
	Other nests or dens (identif	y species):		
IV.	Connectivity with Adjoini	ng Natural Habitats		
	☐ No direct connections t	o adjacent areas of wildl	ife habitat (little	connectivity function)
	Limited number of con	nectors to adjacent areas	s of habitat (som	ewhat important for connectivity function)
	☐ Riverbank is embedded connectivity function)	d in a large area of natur	al habitat with ui	nimpeded connection to other habitats (high
٧.	Rare Species and MNHES	SP Core Area Habitat De	esignation	
	☐ Core Area 1 ☒ Core	Area 2 🔀 Core Are	a 3 🛛 Core	Area 4
	☐ Federally listed threate habitat): Northern long-ear		cies habitat (incl	uding species with known overlapping
	·	abitat (including species v		
	Hairy Wild Rye, Matted Sp	oike Sedge, Mustard Whi	te, Spine-crown	ed Clubtail, Wapato, Wood Turtle
	Rare species direct observa	ations during current field	d surveys:	
VI.	Incidental Direct Wildlife	Observations		
	Spotted sandpiper			
	Red-tailed hawk			
	Green frog			
	Raccoon tracks			
	Deer			

General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form				
VII. Habitat Degradation (identify specific location on b	ank segment if applicable)			
☐ Evidence of significant levels of dumping				
Evidence of significant erosion or sedimentation pr	oblems			
<ul> <li>☑ Occurrence of invasive plants:</li> <li>Reed canary grass, Eurasian water-milfoil, forget-me-not</li> </ul>				
	isturbed by foot traffic for canoe launching			
VIII.Restoration Opportunities				
□ Presence of potential restoration resources (e.g., bank stabilization or hibernacula, plant propagation so Coarse woody debris	poulders, large trees or woody debris, root wad material for urce material). Identify specific items:			
○ Other restoration opportunities:				
R: Grade bank/Coir matting				
L: Grade bank/Coir matting; Log or rock vanes				
Invasive species control				
Revegetation				

Bank 22 Plant Species List			
Left bank	Right bank		
nodding beggar-ticks   Bidens cernua   herb	nodding beggar-ticks   Bidens cernua   herb		
red-osier dogwood   Cornus sericea   shrub	umbrella sedge   Cyperus strigosus   herb		
spotted Joe-Pye weed   Eupatorium maculatum   herb	eastern willow-herb   Epilobium coloratum   herb		
sensitive fern   Onoclea sensibilis   herb	jewelweed   Impatiens capensis   herb		
pale smartweed   Persicaria lapathifolia   herb	common water-purslane   Ludwigia palustris   herb		
American bur-reed   Sparganium americanum   herb	Eurasian water-milfoil   Myriophyllum spicatum   herb   *		
river grape   Vitis riparia   vine/liana	water forget-me-not   Myosotis scorpioides   herb   *		
rough cocklebur   Xanthium strumarium   herb	water-pepper smartweed   Persicaria hydropiper   herb		
	pale smartweed   Persicaria lapathifolia   herb		
	arrow-leaved tearthumb   Persicaria sagittata   herb		
	reed canary grass   Phalaris arundinacea   herb   *		
	American bur-reed   Sparganium americanum   herb		
	blue vervain   Verbena hastata   herb		
	American speedwell   Veronica americana   herb		

<sup>\*</sup>Invasive species

#### **Bank 22 Floodplain Plant Species**

red maple	Acer rubrum	T
silky dogwood	Cornus amomum	S
pussy willow	Salix discolor	S
white meadowsweet	Spiraea alba	S
currant	Ribes sp.	S
sensitive fern	Onoclea sensibilis	Н
moneywort	Lysimachia nummularia	Н
river grape	Vitis riparia	V



Bank 22: Stations 169-172. 300-ft straight stretch from Station 169-172

Photos of Bank 22 Area. August 16, 2022



Left bank (right side) to right bank from Station 172 looking upstream





	Housatonic ROR R5A Bank 23 Site Name and Evaluation Segment					
	Bank 23: Stations 172-175. 300-ft stretch around sharp right bend.  Location/Physical Description					
	8/16/22 Date(s) of Site Visit(s) and Data Collection					
	Weather Conditions					
	Field Staff Perform	ing Evaluation			Date this form was completed	
II.	Site Description					
A.	Bank Characteriza	ation				
Phy	ysical Dimensions	(ft):				
Ler	ngth: 300'	Width: 80'	Bank Height: R 6-7	" L5	' Slope: R 80% L 90%	
Sec	diment / Substrate	composition:				
% \$	Sand 40	% Silt 40	% Clay		% Gravel/cobble 20	
% E	Boulder Bedrock	9	% Organic matter			
	Right bank is cut Thalweg runs alo	ng the left.		ndercu	utting, but rocky. Left bank has extreme NBS.	
B.	Bordering Habitat	Types				
We	tland		U	lpland		
		loodplain forest		$\boxtimes$	Northern Hardwoods-Hemlock-White Pine Forest	
		floodplain forest			Rich mesic forest	
	☐ Red maple sv	wamp			Red Oak-Sugar Maple Transition Forest	
	✓ Vernal pool				Agricultural fields	
	Black ash-red swamp	d maple-tamarack	calcareous seepage		Cultural grassland	
	☐ Deep emerge	ent marsh			Successional northern hardwoods	
	☐ Shallow eme	rgent marsh			Spruce-fir-northern hardwood forest	
	☐ Shrub swamp	)			Developed/disturbed cover types	
	☐ Wet meadow				Other	
	Other					

Not	es:						
C.	Hydrology						
Stre	eam gradient:	☐ Low Grad	dient 🛛 Mid-	Gradient		☐ High-Gradient	
Deg	Degree of overbank flooding potential / floodplain connectivity						
		annels present in	adjacent floodplain	$\boxtimes$	Topog	graphic breaks present i	n the riverbank
	☐ Channel is de	eeply incised	☐ Moderately inc	ised	$\boxtimes$	Somewhat incised	☐ Not incised
Deg	gree of Water leve	el fluctuation (esti	mated vertical differ	ence fron	n mear	n low water to):	
	Bankfull indicator	rs: 3 ft	Top of bank slope:	5-7 ft	Floo	odplain surface: 5-7 ft	
Fiel	d-Derived Eviden	ce of Hydrologic	Conditions				
		line impressed of	on bank	$\boxtimes$	Chanç	ges in character of soil	
		ks			Water	staining	
	Shelving				Veget	ation matted down, ben	t or absent
	☐ Wrack lines (	(litter and debris)		$\boxtimes$	Chanç	ge in plant community	
	Scour and/or     Scour and/or	Deposition			Destru	uction of terrestrial vege	etation
	Line of mud	or silt on tree trur	nks/vegetation		Debris	s stuck on overhanging	tree limbs
	Other						
Fiel	d-Derived Eviden	ce of Bankfull St	age/Discharge Wate	er			
	☐ Scour line				Recer	nt changes to river bend	ls/meanders
	□ Depositional	bench (active ch	annel)	$\boxtimes$	Under	cuts	
	□ Depositional	point bar			Stainir	ng of rocks	
	□ Depositional	island		$\boxtimes$	Top of	f point bars	
	_	n for braided rive	rs 9	$\boxtimes$		· · limits in perennial vege	etation
	_	e of banks (flood				, ,	
	_		•				
D.	Inventory (Plant (						
Ria	ht Bank	,,					
<del></del> - <del>-</del>	Total % Cover:	80 Bank Vegetation	on 60 Overhangin	ng Vegetati	on .	90 Riparian Vegetation	-
	Percent Cover of	f Bank and Overl	nanging Stream Veg	etation b	y Strata	a	
	70 Trees (> 20')	70 Shrubs (< 20')	30 Woody vines	<u>0</u>	sses	50 Herbaceous	

Left Bank

	Total % Cover:	60	70		100	
	Total % Cover.	Bank Vegetation	Overhangin	g Vegetation	Riparian Vegetation	
	Percent Cover o	f Bank and Overhang	ing Stream Vege	etation by Strat	ta	
	70 Trace (+ 20')	20 Shrubs (< 20')	0 Woody vines	0 	10 Herbaceous	
_	Trees (> 20')	,	•	Mosses	Herbaceous	
Pei	cent Cover of Rip	arian Vegetation by S	Strata			
	80	60	20	0	60	
	Trees (> 20')	Shrubs (< 20')	Woody vines	Mosses	Herbaceous	
Ba					or more of the vegetative cor lominant plant species for th	
	•	·	iant species,	•	·	ie strata).
	Strata Plan	t Species		Strata	Plant Species	
					the vegetative cover in each species for the strata):	n strata, or any
	amount of an inv	asive plant species,	designates a t	Johnnant Plant	species for the strata).	
Str	ata: T=Tree, S=S seedlings, and m		H=Herb (Include	es grasses, hei	rbs, pterophytes [ferns], lich	ens, woody
N. I	<u> </u>	,	P			
INO	tes: See attached	I tables for plant spec	ies lists.			
III.	Important Habit	at Features				
	-					
	Wildlife Food					
	Important wetlan	d/aquatic food plants				
	☐ Abundant	☐ Prese	ent		☐ Not Applicable	
	_	_		_		
	Important upland	I food plants (hard ma	ast and fruit/berry	producers)		
	Abundant	⊠ Prese	ent	☐ Absent	☐ Not Applicable	
	Cayar/Darahaa/	Booking/Donning/Na	ating Ushitat			
	Cover/Percnes/	Basking/Denning/Ne	sung nabitat			
	Trees (live or dea	ad) > 30" DBH				
	☐ Abundant	⊠ Prese	ent 「	Absent	☐ Not Applicable	
	_	_		_		
	Standing dead tr	ees (potential for cavi	ties and perches	3)		

Abundant	□ Present	☐ Absent	☐ Not Applicable
Tree cavities in trunks	or limbs		
Abundant		☐ Absent	□ Not Applicable
Small mammal burrow	vs:		
Abundant		☐ Absent	□ Not Applicable
Dense herbaceous co	ver (voles, small mamma	als, amphibians & reptile	es)
Abundant	☐ Present		☐ Not Applicable
Large woody debris or	n the ground (small mam	mals, mink, amphibians	s & reptiles)
Abundant		☐ Absent	□ Not Applicable
Rocks, crevices, logs,	tree roots or hummocks	at water's edge or under	er water's surface (turtles, snakes, frogs)
Abundant		☐ Absent	□ Not Applicable
Overhanging brancheduck, mink, raccoon)	s at or within 1 m above	the water's surface (turt	eles, snakes, frogs, wading birds, wood
Abundant	□ Present	Absent	☐ Not Applicable
Rock piles, crevices, c	or hollow logs suitable for	r various mammals (otte	er, mink, porcupine, racoon):
Abundant		☐ Absent	☐ Not Applicable
	ling vegetation overhang catchers, cedar waxwing		ng good visibility of open water (e.g.,
	☐ Present	☐ Absent	□ Not Applicable
Other Important Hab	itat Characteristics:		
Underwater banks of f	fine silt and/or clay (beav	er, muskrat, otter)	
Abundant		☐ Absent	□ Not Applicable
Undercut or overhang	ing banks (small mamma	als, mink, weasels, turtle	es)
Abundant		☐ Absent	□ Not Applicable
Vertical sandy banks (	(bank swallow, kingfisher	·)	
Abundant	☐ Present		☐ Not Applicable
Mud flats			
Abundant		☐ Absent	□ Not Applicable
Exposed areas of well	l-drained, sandy soil suita	able for turtle nesting	
Abundant	□ Present	☐ Absent	☐ Not Applicable

### Wildlife Dens/Nests (if observed)

	Turtle nesting sites						
	Abundant	Present		☐ Not Applicable			
	Bank swallow colony(ies)						
	☐ Abundant	☐ Present		☐ Not Applicable			
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron			
	Den(s) present of	☐ Otter	Mink	☐ Beaver			
	Other nests or dens (identify	y species):					
IV.	Connectivity with Adjoini	ng Natural Habitats					
	☐ No direct connections t	o adjacent areas of wildli	fe habitat (little c	connectivity function)			
	☐ Limited number of conr	nectors to adjacent areas	of habitat (some	ewhat important for connectivity function)			
	Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with un	impeded connection to other habitats (high			
٧.	Rare Species and MNHES	SP Core Area Habitat De	esignation				
	☐ Core Area 1 ☐ Core	Area 2 🔀 Core Area	a 3 🔲 Core A	Area 4			
	Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat						
	<u> </u>	bitat (including species v		· · · · · · · · · · · · · · · · · · ·			
	Hairy Wild Rye, Matted Spil	ke-sedge, Mustard White	, Spine-crowned	l Clubtail, Wapato, Wood Turtle			
	Rare species direct observa	ations during current field	surveys:				
VI.	Incidental Direct Wildlife	Observations					
	Kingfisher						
	Veery						

General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form	
VII. Habitat Degradation (identify specific location on b	ank segment if applicable)
☐ Evidence of significant levels of dumping	
Evidence of significant erosion or sedimentation pro	oblems
○ Occurrence of invasive plants:     Bittersweet, common buckthorn	
Evidence of other human disturbance; describe:	
VIII.Restoration Opportunities	
☑ Presence of potential restoration resources (e.g., b bank stabilization or hibernacula, plant propagation sou Coarse woody debris, large trees, root wads, cobble	
○ Other restoration opportunities:	
R: Grade bank/Coir matting	
L: Log or rock vanes; Root wads; Vegetated riprap	
Invasive species control	
Revegetation	

Bank 23 Plant Species List				
<u>Left bank</u>	Right bank			
sugar maple   Acer saccharum   tree	silver maple   Acer saccharinum   tree			
Asian bittersweet   Celastrus orbiculatus   vine/liana   *	Asian bittersweet   Celastrus orbiculatus   vine/liana   *			
eastern hemlock   Tsuga canadensis   tree	white ash   Fraxinus americana   tree			
American elm   Ulmus americana   tree	ostrich fern   Matteuccia struthiopteris   herb			
	common buckthorn   Rhamnus cathartica   herb   *			
	green-headed coneflower   Rudbeckia laciniata   herb			
	American linden   Tilia americana   tree			

<sup>\*</sup>Invasive species


#### **Bank 23 Floodplain Plant Species**

Solomon's seal	Polygonatum sp.	Н
Japanese barberry	Berberis thunbergii	S
greater bladder sedge	Carex intumescens	Н
ostrich fern	Matteuccia struthiopteris	Н
meadow horsetail	Equisetum pratense	Н
white ash	Fraxinus americana	T
American linden	Tilia americana	T
silver maple	Acer saccharinum	T
American hornbeam	Carpinus caroliniana	T
American hornbeam	Carpinus caroliniana	S
poison-ivy	Toxicodendron radicans	V
Virginia creeper	Parthenocissus quinquefolia	V



Bank 23: Stations 172-175. Right bend from Station 172 to 175. Left bank at bend in river

Right bank downstream of Station 174



Right bank around Station 174-175

I.	General Informa	ation					
	Housatonic ROR R5A Bank 24						
	Site Name and Evaluation Segment						
	Bank 24: Stations 182-185. 300-ft stretch around sharp right bend  Location/Physical Description						
	8/16/22						
	Date(s) of Site Visit(s) and Data Collection						
	Weather Condition	s During Site Visit					
	AECOM	ing Evaluation			Date this forms was completed		
	Field Staff Perform	ling Evaluation			Date this form was completed		
II.	Site Description	1					
A.	Bank Characteriza	ation					
Physical Dimensions (ft):							
Ler	ngth: 300'	Width: 80'	Bank Height: R: 6' L	6'	Slope: R 60% L 90%		
Sed	diment / Substrate	composition:					
% \$	Sand 30	% Silt 30	% Clay		% Gravel/cobble 30		
% E	Boulder/Bedrock 1	0 % O	rganic matter				
Bar	nk stability / Obser	rved erosional conditio	ns:				
	t bank is erosiona	l cut bank. Left bank B	EHI is high, and NBS i	s ve	ery high from Stations 182-183. Right bank is		
	stable. Thalweg	runs from left side to o	enter.				
В.	Bordering Habitat	Types					
We	tland		Upl	Upland			
		floodplain forest		$\boxtimes$	Northern Hardwoods-Hemlock-White Pine Forest		
	☐ High terrace	floodplain forest			Rich mesic forest		
	☐ Red maple s	wamp			Red Oak-Sugar Maple Transition Forest		
					Agricultural fields		
	Black ash-red swamp	d maple-tamarack calc	areous seepage		Cultural grassland		
	☐ Deep emerge	ent marsh			Successional northern hardwoods		
	☐ Shallow eme	rgent marsh			Spruce-fir-northern hardwood forest		
	☐ Shrub swam	р			Developed/disturbed cover types		
	☐ Wet meadow	I			Other		
	Other						

Notes:								
C.	Hydrology							
Stre	Stream gradient:							
Deg	Degree of overbank flooding potential / floodplain connectivity							
		annels present ir	adjacent floodplain		Topog	graphic breaks present i	n the riverbank	
	☐ Channel is d	eeply incised		sed		Somewhat incised	□ Not incised	
Deg	Degree of Water level fluctuation (estimated vertical difference from mean low water to):							
	Bankfull indicator	rs: 2 ft	Top of bank slope:	6 ft	Floc	odplain surface: 8 ft		
Fiel	d-Derived Eviden	ce of Hydrologic	Conditions					
		l line impressed o	on bank	$\boxtimes$	Changes in character of soil			
		ks			Water staining			
	☐ Shelving				Veget	ation matted down, ben	t or absent	
		(litter and debris)		$\boxtimes$	Chanç	ge in plant community		
	☐ Scour and/or	Deposition			Destruction of terrestrial vegetation			
	☐ Line of mud or silt on tree trunks/vegetation			Debris stuck on overhanging tree limbs				
	Other							
Fiel	d-Derived Eviden	ce of Bankfull St	age/Discharge Wate	r				
	☐ Scour line				Recer	nt changes to river bend	ls/meanders	
	<ul> <li>         □ Depositional bench (active channel)     </li> </ul>				Undercuts			
	□ Depositional point bar				Staining of rocks			
	<ul><li>☑ Depositional island</li><li>☑ Middle bench for braided rivers</li></ul>		$\boxtimes$	Top of point bars				
			$\boxtimes$	Lower limits in perennial vegetation				
☐ Break in slope of banks (floodplain break)								
	☐ Other							
D.	Inventory (Plant (	Community)						
Rig	ht Bank	•						
J	Total % Cover:	70 Bank Vegetation	on 60 Overhangin	ng Vegetati	on	100 Riparian Vegetation	-	
	Percent Cover of	f Bank and Overl	nanging Stream Veg	etation b	y Strata	a		
	40 Trees (> 20')	50 Shrubs (< 20')	30 Woody vines	<u>0</u>	sses	70 Herbaceous		

Left Bank

	Total % Cover:	70	80		90			
		Bank Vegetation Overhanging V		-	Riparian Vegetation			
	Percent Cover of Bank and Overhanging Stre			etation by Stra	ta			
	80 Trees (> 20')	40 Shrubs (< 20')	50 Woody vines	$\underline{}$ Mosses	10 Herbaceous			
Dor	,	parian Vegetation by	•	Wiodoco	Horbaccoas			
rei	cent Cover of Kip	danan vegetation by	Siraia					
	70	60 Shrubs (< 20')	Woody vines	0 	60 Herbaceous			
_	Trees (> 20')	, ,	•		1.0.200000			
Bai	nk and overhangi strata. or anv an	ng vegetation plant lis nount of an invasive p	st (species that c plant species: "*"	omprise 10% o designates a o	or more of the vegetative cover dominant plant species for the	er in each estrata):		
	•	Plant Species		Strata	Plant Species			
	Strata Fian	порестез		Strata	riant opecies			
				_				
				_				
					the vegetative cover in each stapecies for the strata):	strata, or any		
	amount of an inv	rasive plant species,	designates a	uominant piam	i species for the strata).			
	<del></del>							
Stra	ata: T=Tree, S=S seedlings, and m		H=Herb (Include	es grasses, he	rbs, pterophytes [ferns], licher	ns, woody		
_	<u> </u>	,						
Not	tes: See attached	d tables for plant spec	cies lists.					
— III.	Important Habit	tat Features						
	Wildlife Food							
	Important wetland/aquatic food plants							
	☐ Abundant	⊠ Prese	ant	☐ Absent				
	Abundant	⊠ Fiese	311L	☐ Apsent	☐ Not Applicable			
	Important upland	mportant upland food plants (hard mast and fruit/berry producers)						
	☐ Abundant	⊠ Prese	ent	☐ Absent	☐ Not Applicable			
	Cover/Perches/Basking/Denning/Nesting Habitat							
	Trees (live or de	es (live or dead) > 30" DBH						
	☐ Abundant	⊠ Prese	ant [	Absent	□ Not Applicable			
	Abundant	△ Fiese	5111 <u></u>	☐ VN2GIII	☐ Not Applicable			
Standing dead trees (potential for cavities and perches)								

☐ Abundant	□ Present	☐ Absent	□ Not Applicable						
Tree cavities in trunks or limbs									
Abundant	□ Present	☐ Absent	☐ Not Applicable						
Small mammal burrows:									
Abundant	□ Present	☐ Absent	☐ Not Applicable						
Dense herbaceous cover (v	Dense herbaceous cover (voles, small mammals, amphibians & reptiles)								
Abundant	□ Present	Absent	☐ Not Applicable						
Large woody debris on the	ground (small mammals	, mink, amphibians & rep	otiles)						
Abundant	□ Present	Absent	□ Not Applicable						
Rocks, crevices, logs, tree roots or hummocks at water's edge or under water's surface (turtles, snakes, frogs)									
	☐ Present	Absent	☐ Not Applicable						
Overhanging branches at or within 1 m above the water's surface (turtles, snakes, frogs, wading birds, wood duck, mink, raccoon)									
Abundant	□ Present	Absent	□ Not Applicable						
Rock piles, crevices, or hollow logs suitable for various mammals (otter, mink, porcupine, racoon):									
Abundant	□ Present	Absent	□ Not Applicable						
Live or dead tall standing vegetation overhanging or near water offering good visibility of open water (e.g., osprey, kingfisher, flycatchers, cedar waxwings)									
	☐ Present	Absent	□ Not Applicable						
Other Important Habitat C	Characteristics:								
Underwater banks of fine silt and/or clay (beaver, muskrat, otter)									
Abundant	□ Present	Absent	□ Not Applicable						
Undercut or overhanging banks (small mammals, mink, weasels, turtles)									
Abundant	□ Present	☐ Absent	□ Not Applicable						
Vertical sandy banks (bank swallow, kingfisher)									
Abundant	☐ Present		Not Applicable						
Mud flats									
Abundant	□ Present	☐ Absent	☐ Not Applicable						
Exposed areas of well-drain	Exposed areas of well-drained, sandy soil suitable for turtle nesting								
Abundant	Present		□ Not Applicable						

### Wildlife Dens/Nests (if observed)

	Turtle nesting sites							
	☐ Abundant	Present		☐ Not Applicable				
	Bank swallow colony(ies)							
	☐ Abundant	☐ Present		☐ Not Applicable				
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron				
	Den(s) present of	☐ Otter	Mink	□ Beaver				
	Other nests or dens (identify	y species):						
IV.	Connectivity with Adjoining Natural Habitats							
	☐ No direct connections to adjacent areas of wildlife habitat (little connectivity function)							
	☐ Limited number of connectors to adjacent areas of habitat (somewhat important for connectivity function)							
	⊠ Riverbank is embedded in a large area of natural habitat with unimpeded connection to other habitats (high connectivity function)							
٧.	Rare Species and MNHESP Core Area Habitat Designation							
	☐ Core Area 1 ☐ Core Area 2 ☐ Core Area 3 ☐ Core Area 4							
	□ Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat							
	State-listed species habitat (including species with known overlapping Priority Habitat):							
	Hairy Wild Rye, Matted Spike-sedge, Mustard White, Spine-crowned Clubtail, Wapato, Wood Turtle							
	Rare species direct observations during current field surveys:							
VI.	. Incidental Direct Wildlife Observations							


General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form	
VII. Habitat Degradation (identify specific location on b	ank segment if applicable)
☐ Evidence of significant levels of dumping	
Evidence of significant erosion or sedimentation process.	oblems
Occurrence of invasive plants: Bittersweet, bishop's goutweed	
Evidence of other human disturbance; describe:	
VIII.Restoration Opportunities	
☑ Presence of potential restoration resources (e.g., b bank stabilization or hibernacula, plant propagation sou Coarse woody debris, large trees, root wads, cobblete.	
○ Other restoration opportunities:	
R: Grade bank/Coir matting	
L: Vegetated riprap; Log or rock vanes; Grade bank/	Coir matting
Invasive species control	
Revegetation	

Bank 24 Plant Species List					
<u>Left bank</u>	Right bank				
bishop's goutweed   Aegopodium podagraria   herb   *	boxelder   Acer negundo   tree				
ironwood   Carpinus caroliniana   tree	silver maple   Acer saccharinum   tree				
Asian bittersweet   Celastrus orbiculatus   vine/liana   *	nodding beggar-ticks   Bidens cernua   herb				
American linden   Tilia americana   tree	black walnut   Juglans nigra   tree				
eastern hemlock   Tsuga canadensis   tree	lady's-thumb smartweed   Persicaria maculosa   herb				
river grape   Vitis riparia   vine/liana	American sycamore   Platanus occidentalis   tree				
	American elm   Ulmus americana   tree				
	blue vervain   Verbena hastata   herb				
	river grape   Vitis riparia   vine/liana				
	rough cocklebur   Xanthium strumarium   herb				

<sup>\*</sup>Invasive species

#### **Bank 24 Floodplain Plant Species**

wrinkled-leaved goldenrod	Solidago rugosa	Н
ostrich fern	Matteuccia struthiopteris	Н
blue cohosh	Caulophyllum thalictroides	Н
Morrow's honeysuckle	Lonicera morrowii	S
common buckthorn	Rhamnus cathartica	S
sugar maple	Acer saccharum	T
white ash	Fraxinus americana	Т
black cherry	Prunus serotina	Т
American linden	Tilia americana	T
Asian bittersweet	Celastrus orbiculatus	V
Japanese barberry	Berberis thunbergii	V



Bank 24: Stations 182-185. 300-ft along Right bend.

Photos of Bank 24. August 16, 2022



Looking upstream at point/mid-channel bar around Station 176-177. Right bank is left.



Looking upstream toward point/mid-channel bar at left bend in river at Station 177

Right bank near Station 182





I.	General Informa	tion						
	Housatonic ROR R5A Bank 25 Site Name and Evaluation Segment							
	Bank 25: Stations 188-192. 400-ft stretch around moderate right bend Location/Physical Description							
	8/16/22 Date(s) of Site Visit	t(s) and Data Collection	on					
	Weather Conditions	s During Site Visit						
	Field Staff Perform	ing Evaluation			Da	te this form was completed		
II.	Site Description							
A.	Bank Characteriza	ation						
Phy	sical Dimensions	(ft):						
Len	gth: 400'	Width: 80'	Bank Height: R 8	' L7'	Slope: R 90%	L 60%		
Sec	liment / Substrate	composition:						
% S	Sand 40	% Silt 40	% Clay		% Gravel/cobble			
% E	Boulder Bedrock 1	0 %	Organic matter ~5					
	Stable on both sid		om moderate – high o		sides. Right bank NBS g runs from right to lef	S is extreme from Stations t side.		
B.	Bordering Habitat	Types						
We	tland			Upland				
		loodplain forest			Northern Hardwoods- Forest	Hemlock-White Pine		
	☐ High terrace	floodplain forest			Rich mesic forest			
	Red maple s	wamp			Red Oak-Sugar Mapl	e Transition Forest		
	∀ Vernal pool				Agricultural fields			
	☐ Black ash-red swamp	d maple-tamarack c	alcareous seepage		Cultural grassland			
	☐ Deep emerge	ent marsh			Successional norther	n hardwoods		
	☐ Shallow eme	rgent marsh			Spruce-fir-northern ha	ardwood forest		
	Shrub swamp     Shrub	o			Developed/disturbed	cover types		
	☐ Wet meadow	,			Other			
	Other							
Not	es: Ria	ht bank borders Pit	tsfield POTW					

C.	Hydrology								
Stre	eam gradient:	☐ Low Grad	dient	⊠ Mid-Grad	dient		☐ High-Gradient		
De	Degree of overbank flooding potential / floodplain connectivity								
	☐ High-flow cha	annels present in	adjacent f	loodplain		Topo	graphic breaks present	in the riverbank	
	☐ Channel is de	eeply incised	☐ Mode	erately incised		$\boxtimes$	Somewhat incised	☐ Not incised	
De	Degree of Water level fluctuation (estimated vertical difference from mean low water to):								
	Bankfull indicator	rs: 3 ft	Top of ba	nk slope: 7-8	ft	Flo	odplain surface: 8 ft		
Fie	ld-Derived Eviden	ce of Hydrologic	Conditions	3					
		line impressed of	on bank		$\boxtimes$	Chan	ges in character of soil		
	⊠ Bed and ban	ks			$\boxtimes$	Wate	r staining		
	Shelving					Vege	tation matted down, be	nt or absent	
		(litter and debris)			$\boxtimes$	Chan	ge in plant community		
	Scour and/or     Scour and/or	Deposition			$\boxtimes$	Destr	uction of terrestrial veg	etation	
		or silt on tree trur	nks/vegeta	tion		Debri	s stuck on overhanging	g tree limbs	
	Other								
Fie	ld-Derived Eviden	ce of Bankfull St	age/Discha	arge Water					
	☐ Scour line					Rece	nt changes to river ber	nds/meanders	
	□ Depositional	bench (active ch	annel)			Unde	rcuts		
	□ Depositional	point bar				Staini	ing of rocks		
	□ Depositional	island			$\boxtimes$	Top of point bars			
	☐ Middle bench	n for braided rive	rs		$\boxtimes$	Lower limits in perennial vegetation			
		e of banks (flood	lplain brea	k)					
	Other								
D.	Inventory (Plant 0	Community)							
Rig	ht Bank								
	Total % Cover:	80 Bank Vegetation	n .	60 Overhanging Ve	egetati	on	100 Riparian Vegetation	_	
	Percent Cover of	f Bank and Overl	nanging St	ream Vegetat	ion b	y Strat	ta		
	50 Trees (> 20')	60 Shrubs (< 20')	40 Woo	ody vines	0 Mo	sses	60 Herbaceous		

Left Bank

	Total % Cover:	75	50		90
		Bank Vegetation			Riparian Vegetation
	Percent Cover of	of Bank and Overhand	ging Stream Ve	getation by Stra	ıta
	50 Trees (> 20')	70 Shrubs (< 20')	40 Woody vines	0 	70 Herbaceous
_	, ,	,	·	MOSSES	nerbaceous
Pe	cent Cover of Ri	parian Vegetation by	Strata		
	80	60	30	0	50
	Trees (> 20')	Shrubs (< 20')	Woody vines	Mosses	Herbaceous
Ва					or more of the vegetative cover in each
	•	•	plant species; "^	•	dominant plant species for the strata):
	Strata Plai	nt Species		Strata	Plant Species
	H Per	sicaria		S	Cornus sericea
	H Spa	ırganium		T	Boxelder
	V/L Rive	er grape		T	Linden
	Riparian vegeta	tion plant list (species	that comprise '	10% or more of	the vegetative cover in each strata, or any t species for the strata):
	amount of an in	vasive plant species,	designates a	dominant plan	t species for the strata).
				<u> </u>	
Str	ata: T=Tree, S=	Shrub, L=Liana (vine),	, H=Herb (Includ	des grasses, he	erbs, pterophytes [ferns], lichens, woody
	seedlings, and r		`		
No	tes: See attache	d tables for plant spec	cies lists.		
_		<u> </u>			
III.	Important Habi	tat Features			
	Wildlife Food				
	Wildlife Food				
	Important wetlar	nd/aquatic food plants	<b>;</b>		
	☐ Abundant	⊠ Prese	ent	☐ Absent	☐ Not Applicable
	Important uplan	d food plants (hard ma	ast and fruit/ber	ry producers)	
	portain apian	a 100a piamo (mara m			
	☐ Abundant	⊠ Prese	ent	Absent	□ Not Applicable
	Cover/Perches	/Basking/Denning/N	esting Habitat		
	Trees (live or de	ead) > 30" DBH			
	☐ Abundant	⊠ Pres	ent	Absent	□ Not Applicable
	_			_	☐ Not Applicable
	Standing dead t	rees (potential for cav	ities and perche	es)	

Abundant	□ Present	☐ Absent	☐ Not Applicable
Tree cavities in trunks	or limbs		
Abundant		☐ Absent	☐ Not Applicable
Small mammal burrow	vs:		
Abundant		☐ Absent	☐ Not Applicable
Dense herbaceous co	ver (voles, small mamma	als, amphibians & reptile	es)
Abundant		☐ Absent	☐ Not Applicable
Large woody debris or	n the ground (small mam	mals, mink, amphibians	s & reptiles)
Abundant		☐ Absent	☐ Not Applicable
Rocks, crevices, logs,	tree roots or hummocks	at water's edge or unde	er water's surface (turtles, snakes, frogs)
Abundant		☐ Absent	☐ Not Applicable
Overhanging brancheduck, mink, raccoon)	s at or within 1 m above	the water's surface (tur	tles, snakes, frogs, wading birds, wood
Abundant	□ Present	☐ Absent	☐ Not Applicable
Rock piles, crevices, c	or hollow logs suitable for	r various mammals (otte	er, mink, porcupine, racoon):
Abundant		☐ Absent	☐ Not Applicable
	ling vegetation overhang catchers, cedar waxwing		ng good visibility of open water (e.g.,
	☐ Present	☐ Absent	☐ Not Applicable
Other Important Hab	itat Characteristics:		
Underwater banks of f	fine silt and/or clay (beav	er, muskrat, otter)	
Abundant		☐ Absent	☐ Not Applicable
Undercut or overhang	ing banks (small mamma	als, mink, weasels, turtle	es)
Abundant		☐ Absent	☐ Not Applicable
Vertical sandy banks (	(bank swallow, kingfisher	·)	
Abundant	☐ Present		☐ Not Applicable
Mud flats			
Abundant		☐ Absent	☐ Not Applicable
Exposed areas of well	l-drained, sandy soil suita	able for turtle nesting	
Abundant	☐ Present		☐ Not Applicable

#### Wildlife Dens/Nests (if observed)

	Turtle nesting sites						
	Abundant	☐ Present		☐ Not Applicable			
	Bank swallow colony(ies)						
	Abundant	Present		□ Not Applicable			
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron			
	Den(s) present of	☐ Otter	Mink	☐ Beaver			
	Other nests or dens (identif	y species):					
IV.	Connectivity with Adjoini	ng Natural Habitats					
	☐ No direct connections t	o adjacent areas of wildli	fe habitat (little	connectivity function)			
	Limited number of conf	nectors to adjacent areas	of habitat (som	ewhat important for connectivity function)			
	Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with ur	nimpeded connection to other habitats (high			
٧.	Rare Species and MNHES	SP Core Area Habitat De	esignation				
	☐ Core Area 1 ☐ Core	Area 2 🔀 Core Area	a 3 🔲 Core	Area 4			
	☐ Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat						
	State-listed species ha	abitat (including species v	vith known overl	apping Priority Habitat):			
	Hairy Wild Rye, Matted Sp	rike-sedge, Mustard White	e, Spine-crowne	ed Clubtail, Wapato, Wood Turtle			
	Rare species direct observa	ations during current field	surveys:				
VI.	Incidental Direct Wildlife	Observations					
	Dragonflies						
	Phoebe						
	Great crested flycato	her					
	Titmouse						


General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory For	m					
VII. Habitat Degradation (identify specific loc	cation on bank segment if applicable)					
☐ Evidence of significant levels of dumpin	g					
Evidence of significant erosion or sedim	nentation problems					
○ Occurrence of invasive plants:   Minor amounts of purple loosestrife and Japanese knotweed; Asian bittersweet prevalent throughout (>25%), reed canary grass, yellow iris						
Evidence of other human disturbance; of	describe: POTW abutment and related material					
VIII.Restoration Opportunities						
	rces (e.g., boulders, large trees or woody debris, root wad material for pagation source material). Identify specific items: wads, boulders					
Remove POTW structures						
R: Log or rock vanes; Grade bank/Coir ma	atting; Vegetated riprap					
L: Reshape point bar; Grade bank/Coir matting; Vegetated riprap						
Invasive species control						
Revegetation						
V						

Bank 25 Plant Species List				
Left bank	Right bank			
boxelder   Acer negundo   tree	boxelder   Acer negundo   tree			
sugar maple   Acer saccharum   tree	nodding beggar-ticks   Bidens cernua   herb			
Asian bittersweet   Celastrus orbiculatus   vine/liana   *	black mustard   Brassica nigra   herb			
red-osier dogwood   Cornus sericea   shrub	ironwood   Carpinus caroliniana   tree			
yellow iris   Iris pseudacorus   herb   *	Asian bittersweet   Celastrus orbiculatus   vine/liana   *			
purple loosestrife   Lythrum salicaria   herb   *	wild cucumber   Echinocystis lobata   vine			
ostrich fern   Matteuccia struthiopteris   herb	pale smartweed   Persicaria lapathifolia   herb			
sensitive fern   Onoclea sensibilis   herb	reed canary grass   Phalaris arundinacea   herb   *			
pale smartweed   Persicaria lapathifolia   herb	Canada clearweed   Pilea pumila   herb			
green-headed coneflower   Rudbeckia laciniata   herb	green-headed coneflower   Rudbeckia laciniata   herb			
American bur-reed   Sparganium americanum   herb	American linden   Tilia americana   tree			
blue vervain   Verbena hastata   herb	river grape   Vitis riparia   vine/liana			
river grape   Vitis riparia   vine/liana				

<sup>\*</sup>Invasive species

#### **Bank 26 Floodplain Plant Species**

Morrow's honeysuckle	Lonicera morrowii	S
common buckthorn	Rhamnus cathartica	S
wrinkled-leaved goldenrod	Solidago rugosa	Н
ostrich fern	Matteuccia struthiopteris	Н
dame's-rocket	Hesperis matronalis	Н
Asian bittersweet	Celastrus orbiculatus	V
Virginia creeper	Parthenocissus quinquefolia	V
river grape	Vitis riparia	V



Bank 25: Stations 188-192. 400-ft stretch around moderate right bend

Photos of Bank 25 Area. August 16, 2022






Right bank at upper limit of Bank 25, by WWTP fence near Station 189

Right bank, looking downstream. WWTP foundation near Station 189








Looking downstream through Bank 25 area below Station 190.





I.	General Informa	ntion							
	Housatonic ROR R5A Bank 26								
	Site Name and Evaluation Segment								
	Bank 26: Stations 202-205. 300-ft stretch entering halfway around sharp right bend Location/Physical Description								
	8/10/22								
	Date(s) of Site Visit(s) and Data Collection								
	Weather Conditions	s During Site Visit							
	AECOM	ing Evaluation			Data this forms was completed				
	Field Staff Perform	ing Evaluation			Date this form was completed				
II.	Site Description	ı							
A.	Bank Characteriza	ation							
Phy	sical Dimensions	(ft):							
Ler	ngth: 300'	Width: 80'	Bank Height: R 8'	L 6'	Slope: R 90% L 90%				
Sed	diment / Substrate	composition:							
% \$	Sand 45	% Silt 45	% Clay		% Gravel/cobble 10				
% E	Boulder/Bedrock	% C	rganic matter						
Bar	nk stabilitv / Obser	ved erosional condition	ons:						
	Both banks are st	teep but stable. Left b	ank borders steep u		hillside. BEHI mostly moderate on both sides.				
	NBS is low on bo	oth sides. Thalweg mo	oves from right to cer	nter.					
В.	Bordering Habitat	Types							
We	tland		L	Jpland					
	<b>N T 1 1 1 1 1 1 1 1 1 1</b>	To a latela format		$\square$	Northern Hardwoods-Hemlock-White Pine				
		loodplain forest		_	Forest				
	☐ High terrace	floodplain forest			Rich mesic forest				
	☐ Red maple s	wamp			Red Oak-Sugar Maple Transition Forest				
	☐ Vernal pool			$\boxtimes$	Agricultural fields				
	Black ash-red swamp	d maple-tamarack cal	careous seepage		Cultural grassland				
	☐ Deep emerge	ent marsh			Successional northern hardwoods				
	☐ Shallow eme	rgent marsh			Spruce-fir-northern hardwood forest				
	☐ Shrub swamp	p			Developed/disturbed cover types				
	☐ Wet meadow	1			Other				
	Other								

Notes	•						
C. Hy	drology						
Strea	m gradient:	☐ Low Gra	dient 🛛 Mid	d-Gradient		☐ High-Gradient	
Degre	e of overbank f	looding potentia	/ floodplain conne	ctivity			
$\triangleright$	] High-flow cha	annels present ir	adjacent floodplai	in 🖂	Topogra	aphic breaks present	t in the riverbank
	Channel is de	eeply incised		ncised	□s	Somewhat incised	□ Not incised
Degre	e of Water leve	I fluctuation (est	mated vertical diffe	erence fron	n mean	low water to):	
В	ankfull indicator	s: 3 ft	Top of bank slope	e: 6-8 ft	Flood	dplain surface: 6-8 ft	
Field-	Derived Eviden	ce of Hydrologic	Conditions				
$\triangleright$	Clear natural	line impressed	on bank	$\boxtimes$	Change	es in character of soil	l
$\triangleright$	Bed and banl	ks			Water s	staining	
$\triangleright$	Shelving				Vegeta	tion matted down, be	ent or absent
	] Wrack lines (	litter and debris)			Change in plant community		
$\triangleright$	Scour and/or	Deposition			Destruction of terrestrial vegetation		
	Line of mud o	or silt on tree trui	nks/vegetation	$\boxtimes$	Debris stuck on overhanging tree limbs		
	Other						
Field-	Derived Eviden	ce of Bankfull St	age/Discharge Wa	ter			
	] Scour line				Recent	changes to river ber	nds/meanders
$\triangleright$	Depositional	bench (active ch	annel)		Underc	uts	
$\triangleright$	Depositional	point bar			Staining of rocks		
	Depositional	island		$\boxtimes$	Top of point bars		
	] Middle bench	for braided rive	rs	$\boxtimes$	Lower I	imits in perennial veg	getation
$\triangleright$	Break in slop	e of banks (flood	lplain break)				
	Other						
D. In	ventory (Plant 0	Community)					
Right	Bank						
To	otal % Cover:	80 Bank Vegetation	on 50 Overhan	ging Vegetation		90 Riparian Vegetation	
Р	ercent Cover of	Ba40nk and Ov	erhanging Stream	Vegetation	by Stra	ıta	
<u>50</u> Tr	ees (> 20')	40 Shrubs (< 20')	0 Woody vines	0	sses	60 Herbaceous	

Left Bank

Tot	al % Cover:	50	80		100	
		Bank Vegetation	Overhanging Vegetation		Riparian Vegetation	
	rcent Cover o	f Bank and Overhang		etation by Stra		
80 Tree	es (> 20')	10 Shrubs (< 20')	10 Woody vines	<del>0</del> Mosses	<u>10</u> Herbaceous	
Percent	t Cover of Rip	arian Vegetation by S	•			
70	·	40	40	0	50	
_	es (> 20')	Shrubs (< 20')	10 Woody vines	Mosses	Herbaceous	
Bank ai stra Stra	ata, or any am	ng vegetation plant lis nount of an invasive p t Species	t (species that co	omprise 10% o designates a o Strata	or more of the vegetative cover in dominant plant species for the str Plant Species	า each ·ata):
					the vegetative cover in each strats t species for the strata):	ata, or any
see Notes:	edlings, and m	nosses) I tables for plant spec	· .	es grasses, he	rbs, pterophytes [ferns], lichens,	woody
<u>Wil</u>	dlife Food					
lmp	oortant wetlan	d/aquatic food plants				
	Abundant	⊠ Prese	ent [	Absent	☐ Not Applicable	
Imp	ortant upland	food plants (hard ma	st and fruit/berry	producers)		
	Abundant	□ Prese	ent [	Absent	□ Not Applicable	
Co	ver/Perches/	Basking/Denning/Ne	esting Habitat			
Tre	es (live or dea	ad) > 30" DBH				
	Abundant		ent [	Absent	☐ Not Applicable	
Sta	nding dead tr	ees (potential for cavi	ties and perches	:)		

☐ Abundant	□ Present	☐ Absent	□ Not Applicable			
Tree cavities in trunks or lin	nbs					
Abundant	□ Present	☐ Absent	☐ Not Applicable			
Small mammal burrows:						
Abundant	□ Present	Absent	☐ Not Applicable			
Dense herbaceous cover (v	voles, small mammals, ar	mphibians & reptiles)				
Abundant	□ Present	Absent	☐ Not Applicable			
Large woody debris on the	ground (small mammals	, mink, amphibians & rep	tiles)			
	☐ Present	Absent	□ Not Applicable			
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)			
Abundant	□ Present	Absent	□ Not Applicable			
Overhanging branches at o duck, mink, raccoon)	r within 1 m above the w	ater's surface (turtles, sr	nakes, frogs, wading birds, wood			
☐ Abundant	□ Present	Absent	□ Not Applicable			
Rock piles, crevices, or holl	low logs suitable for vario	ous mammals (otter, min	k, porcupine, racoon):			
Abundant	□ Present	Absent	□ Not Applicable			
Live or dead tall standing veosprey, kingfisher, flycatche		near water offering goo	d visibility of open water (e.g.,			
	☐ Present	Absent	□ Not Applicable			
Other Important Habitat C	Characteristics:					
Underwater banks of fine si	ilt and/or clay (beaver, m	uskrat, otter)				
Abundant	□ Present	Absent	□ Not Applicable			
Undercut or overhanging banks (small mammals, mink, weasels, turtles)						
Abundant	□ Present	Absent	□ Not Applicable			
Vertical sandy banks (bank swallow, kingfisher)						
Abundant	Present		Not Applicable			
Mud flats						
Abundant	□ Present	Absent	□ Not Applicable			
Exposed areas of well-drain	ned, sandy soil suitable f	or turtle nesting				
☐ Abundant	☐ Present		□ Not Applicable			

#### Wildlife Dens/Nests (if observed)

	Turtle nesting sites						
	Abundant	□ Present	☐ Absent	□ Not Applicable			
	Bank swallow colony(ies)						
	Abundant	☐ Present		☐ Not Applicable			
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron			
	Den(s) present of	☐ Otter	☐ Mink	☐ Beaver			
	Other nests or dens (identify	y species):					
IV.	Connectivity with Adjoini	ng Natural Habitats					
	☐ No direct connections to	o adjacent areas of wildli	fe habitat (little d	connectivity function)			
	☐ Limited number of conr	nectors to adjacent areas	of habitat (some	ewhat important for connectivity function)			
	Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with un	nimpeded connection to other habitats (high			
٧.	Rare Species and MNHES	SP Core Area Habitat De	esignation				
	☐ Core Area 1 ☐ Core Area 2 ☐ Core Area 3 ☐ Core Area 4						
	☑ Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat						
	State-listed species ha	bitat (including species v	vith known overl	apping Priority Habitat):			
	Hairy Wild Rye, Matted Spi	ike-sedge, Mustard White	e, Spine-crowned	d Clubtail, Wapato, Wood Turtle			
	Rare species direct observa	ations during current field	surveys:				
VI.	Incidental Direct Wildlife	Observations					
	Great blue heron						
	Red tail hawk						
	Redstart						
	Phoebe						
	Painted turtle						

General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form			
VII. Habitat Degradation (identify specific location on b	ank segment if applicable)		
Evidence of significant levels of dumping			
Evidence of significant erosion or sedimentation pr	oblems		
○ Occurrence of invasive plants:     Japanese knotweed, bittersweet, common buckthorn, privet			
⊠ Evidence of other human disturbance; describe: Bı	ricks and metal debris near toe of left bank		
VIII.Restoration Opportunities			
□ Presence of potential restoration resources (e.g., beank stabilization or hibernacula, plant propagation sour Coarse woody debris, large trees, root wads, cobbe.			
○ Other restoration opportunities:			
R: Reshape point bar			
L: Log and rock vanes			
Invasive species control			
Revegetation			

Bank 26 Plant Species List					
<u>Left bank</u>	Right bank				
boxelder   Acer negundo   tree	boxelder   Acer negundo   tree				
striped maple   Acer pensylvanicum   tree	silver maple   Acer saccharinum   tree				
paper birch   Betula papyrifera   tree	nodding beggar-ticks   Bidens cernua   herb				
ironwood   Carpinus caroliniana   tree	Japanese knotweed   Fallopia japonica   herb   *				
Asian bittersweet   Celastrus orbiculatus   vine/liana   *	border privet   Ligustrum obtusifolium   shrub   *				
wood-reed grass   Cinna arundinacea   herb	pale smartweed   Persicaria lapathifolia   herb				
burning bush   Euonymus alatus   shrub	common buckthorn   Rhamnus cathartica   herb   *				
ostrich fern   Matteuccia struthiopteris   herb					
Canada clearweed   Pilea pumila   herb					
eastern hemlock   Tsuga canadensis   tree					
American elm   Ulmus americana   tree					

<sup>\*</sup>Invasive species

(A-82)	Bank 26 Floodplain Plant Species
--------	----------------------------------

(		
American beech	Fraxinus grandifolia	T
Basswood	Tilia cordata	T
Silver maple	Acer saccharinum	T
Boxelder maple	Acer negundo	S
American elm	Ulmus americana	S
Senstive fern	Onoclea sensibilis	Н
American aster	Symphyotrichum lateriflorum	Н
Horsetail	Equisetum hyemale	Н
Moneywort	Lysimachia nummularia	Н
Sweet wood-reed	Cinna arundinacea	Н
Lady fern	Athyrium angustum	Н
(B- <b>78</b> )		



Bank 26: Stations 202-205. 300-ft stretch entering halfway around sharp right bend.

Photos of Bank 26 Area. August 10, 2022 Left bank (right side) to right bank (left side) Station 203 Left bank, looking upstream from Station 204 area Left bank (left) to right bank (right) looking downstream Left bank Station 203 area Left bank hemlock roots near Station 204 Right bank view from left bank; Station 204 area

I.	Gene	eral Informat	tion					
	Housatonic ROR R5A Bank 27							
	Site Name and Evaluation Segment							
		27: Stations ion/Physical D		t stretch coming out of s	harp rig	ht bend.		
	8/10/2		escription					
			(s) and Data Colle	ction				<del></del> -
			During Site Visit					
	AECC Field	DM Staff Performir	ng Evaluation				Date th	is form was completed
II.	Site	Description						
A.	Bank	Characteriza	tion					
Phy	/sical	Dimensions (	(ft):					
Len	ngth: 2	200'	Width: 70'	Bank Height: R 6	' L7'	Slope%: F	R 60%	L 100%
Sec	diment	t / Substrate o	composition:					
% 5	Sand 4	45	% Silt 50	% Clay		% Gravel/cobble 5		
% E	Boulde	er/Bedrock		% Organic matter				
Bar	nk stal	bility / Observ	ved erosional co	nditions:				
	Left I	bank undercu	ut, eroding and s	lumping; Right bank stal	ble. Ex	treme NBS on left b	ank at	Stations 207-208.
	Thalv	weg along left	t side.					
B.	Borde	ering Habitat	Types					
We	tland				Upland			
	□ T	ransitional flo	oodplain forest		$\boxtimes$	Northern Hardwoo Forest	ds-Hen	nlock-White Pine
	□ F	ligh terrace fl	loodplain forest			Rich mesic forest		
	□ F	Red maple sw	vamp			Red Oak-Sugar M	aple Tra	ansition Forest
	□ \	/ernal pool			$\boxtimes$	Agricultural fields		
		Black ash-red wamp	maple-tamaracl	calcareous seepage		Cultural grassland		
		Deep emerge	nt marsh			Successional north	nern ha	rdwoods
	☐ Shallow emergent marsh			Spruce-fir-northern	n hardw	rood forest		
	☐ Shrub swamp				Developed/disturb	ed cove	er types	
	□ v	Vet meadow				Other		
		Other						
Not	ως.							

C.	Hydrology						
Stre	eam gradient:		dient	Mid-Gradient	:	☐ High-Gradient	
Deg	gree of overbank f	looding potential	/ floodplain c	onnectivity			
	☐ High-flow cha	annels present in	adjacent floo	dplain 🛚	Top	oographic breaks prese	nt in the riverbank
	☐ Channel is de	eeply incised	☐ Moderat	ely incised		Somewhat incised	☐ Not incised
Deg	gree of Water leve	I fluctuation (est	mated vertica	l difference fro	m m	ean low water to):	
	Bankfull indicator	s: 3 ft To	p of bank slop	e: R 6 L 7 ft	F	Floodplain surface: 6-7 f	t
Fiel	d-Derived Eviden	ce of Hydrologic	Conditions				
		line impressed of	on bank	$\boxtimes$	Ch	anges in character of so	pil
		ks			Wa	ater staining	
	Shelving				Ve	getation matted down, b	ent or absent
		litter and debris)		$\boxtimes$	Ch	ange in plant communit	y
	Scour and/or     Scour and/or	Deposition			De	struction of terrestrial ve	egetation
	Line of mud of	or silt on tree trur	nks/vegetation		De	bris stuck on overhangi	ng tree limbs
	Other						
Fiel	d-Derived Eviden	ce of Bankfull St	age/Discharge	e Water			
	☐ Scour line				Re	cent changes to river be	ends/meanders
	□ Depositional	bench (active ch	annel)	$\boxtimes$	Un	dercuts	
	☐ Depositional	point bar			Sta	nining of rocks	
	☐ Depositional	island			Top	o of point bars	
	☐ Middle bench	for braided rive	rs	$\boxtimes$	Lov	wer limits in perennial ve	egetation
		e of banks (flood	Iplain break)				
	Other						
D.	Inventory (Plant 0	Community)					
Rig	ht Bank						
	Total % Cover:	75 Bank Vegetation	on 60	erhanging Vegeta	ion	90 Riparian Vegetation	<u> </u>
	Percent Cover of	Bank and Overl	nanging Strea	m Vegetation b	y St	rata	
	10 Trees (> 20')	20 Shrubs (< 20')	10 Woody	vines 0	osses	90 Herbaceous	

Left Bank

	Total % Cover:	90 Bank Vegetation	75 Overhandi	ng Vegetation	80 Riparian Vegetation	
	Percent Cover o	f Bank and Overhang	_	-	-	
	90	50	70	0	0	
	Trees (> 20')	Shrubs (< 20')	Woody vines	Mosses	Herbaceous	_
Per	cent Cover of Rip	parian Vegetation by S	Strata			
	70	60	20	0	60	_
	Trees (> 20')	Shrubs (< 20')	Woody vines	Mosses	Herbaceous	
Ban	nk and overhanging strata. Or any am	ng vegetation plant lis	t (species that of the state of the species of the species of the species of the state of the st	comprise 10% o	or more of the vegetative or dominant plant species for	cover in each the strata):
		t Species	iain oposios,	Strata	Plant Species	ino oli alay.
	Strata Flair	Opecies		Strata	riant opecies	
- 5						
	Riparian vegetat	ion plant list (species vasive plant species: "	that comprise 1	0% or more of	the vegetative cover in eat species for the strata):	ich strata, or any
	amount of all inv	doive plant openies,	acoignates a	dominant plan	t opeoles for the strata).	
	ita: T=Tree, S=S seedlings, and m		H=Herb (Includ	les grasses, he	erbs, pterophytes [ferns], lie	chens, woody
		,	ioc lists			
NOI	es. See allached	I tables for plant spec	ies lists.			
III.	Important Habit	at Features				
	Wildlife Food					
	Important wetlan	d/aquatic food plants				
	☐ Abundant	⊠ Prese	ent	Absent	☐ Not Applicab	le
	Important upland	I food plants (hard ma	ast and fruit/ber	y producers)		
	_				□ NI. A P P	la.
	☐ Abundant	⊠ Prese	ent	Absent	☐ Not Applicab	le
	Cover/Perches/	Basking/Denning/Ne	esting Habitat			
	Trees (live or de	ad) > 30" DBH				
	☐ Abundant	□ Prese	ent	Absent	☐ Not Applicab	le
	Standing dead tr	ees (potential for cavi	ities and perche	es)		

Abundant	□ Present	☐ Absent	□ Not Applicable					
Tree cavities in trunks or li	mbs							
Abundant	□ Present	☐ Absent	□ Not Applicable					
Small mammal burrows:	Small mammal burrows:							
Abundant	□ Present	☐ Absent	☐ Not Applicable					
Dense herbaceous cover	(voles, small mammals, a	mphibians & reptiles)						
Abundant	□ Present	☐ Absent	☐ Not Applicable					
Large woody debris on the	e ground (small mammals	s, mink, amphibians & rep	otiles)					
Abundant	□ Present	☐ Absent	☐ Not Applicable					
Rocks, crevices, logs, tree	roots or hummocks at w	ater's edge or under wat	er's surface (turtles, snakes, frogs)					
Abundant	□ Present	Absent	☐ Not Applicable					
Overhanging branches at duck, mink, raccoon)	or within 1 m above the w	vater's surface (turtles, si	nakes, frogs, wading birds, wood					
Abundant		Absent	☐ Not Applicable					
Rock piles, crevices, or ho	llow logs suitable for vari	ous mammals (otter, mir	nk, porcupine, racoon):					
Abundant	□ Present	☐ Absent	☐ Not Applicable					
Live or dead tall standing osprey, kingfisher, flycatch		r near water offering goo	d visibility of open water (e.g.,					
	☐ Present	☐ Absent	☐ Not Applicable					
Other Important Habitat	Characteristics:							
Underwater banks of fine	silt and/or clay (beaver, m	nuskrat, otter)						
	☐ Present	Absent	☐ Not Applicable					
Undercut or overhanging b	oanks (small mammals, m	nink, weasels, turtles)						
Abundant	□ Present	☐ Absent	☐ Not Applicable					
Vertical sandy banks (ban	Vertical sandy banks (bank swallow, kingfisher)							
Abundant	☐ Present		Not Applicable					
Mud flats								
	☐ Present	☐ Absent	☐ Not Applicable					
Exposed areas of well-dra	ined, sandy soil suitable f	for turtle nesting						
Abundant	Present		□ Not Applicable					

#### Wildlife Dens/Nests (if observed)

	Turtle nesting sites						
	Abundant	Present		□ Not Applicable			
	Bank swallow colony(ies)						
	Abundant	☐ Present		☐ Not Applicable			
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron			
	Den(s) present of	☐ Otter	Mink	☐ Beaver			
	Other nests or dens (identify	y species):					
IV.	. Connectivity with Adjoining Natural Habitats						
	☐ No direct connections to adjacent areas of wildlife habitat (little connectivity function)						
	☐ Limited number of connectors to adjacent areas of habitat (somewhat important for connectivity function)						
	Riverbank is embedded in a large area of natural habitat with unimpeded connection to other habitats (high connectivity function)						
٧.							
	☐ Core Area 1 ☐ Core Area 2 ☐ Core Area 3 ☐ Core Area 4						
	□ Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat						
	State-listed species habitat (including species with known overlapping Priority Habitat):						
	Matted Spike-sedge, Mustard White, Spine-crowned Clubtail, Wapato, Wood Turtle						
	Rare species direct observations during current field surveys:						
VI.	Incidental Direct Wildlife Observations						
	Creek chub						

General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form						
VII. Habitat Degradation (identify specific location on b	ank segment if applicable)					
☐ Evidence of significant levels of dumping	Evidence of significant levels of dumping					
Evidence of significant erosion or sedimentation problems						
Occurrence of invasive plants: Bittersweet						
Evidence of other human disturbance; describe:						
VIII.Restoration Opportunities						
Presence of potential restoration resources (e.g., boulders, large trees or woody debris, root wad material for bank stabilization or hibernacula, plant propagation source material). Identify specific items:  Coarse woody debris, large trees, root wads, cobbles						
○ Other restoration opportunities:						
R: Reshape point bar						
L: Log or rock vanes; Root wads; Vegetated riprap						
Invasive species control						
Revegetation						

Bank 27 Plant Species List				
<u>Left bank</u>	Right bank			
boxelder   Acer negundo   tree	boxelder   Acer negundo   tree			
ironwood   Carpinus caroliniana   tree	nodding beggar-ticks   Bidens cernua   herb			
Asian bittersweet   Celastrus orbiculatus   vine/liana   *	Asian bittersweet   Celastrus orbiculatus   vine/liana   *			
red-osier dogwood   Cornus sericea   shrub	common water-purslane   Ludwigia palustris   herb			
Virgini-creeper   Parthenocissus quinquefolia   vine/liana	pale smartweed   Persicaria lapathifolia   herb			
American elm   Ulmus americana   tree	eastern cottonwood   Populus deltoides   tree			
river grape   Vitis riparia   vine/liana	American bur-reed   Sparganium americanum   herb			
	American elm   Ulmus americana   tree			
	blue vervain   Verbena hastata   herb			
	river grape   Vitis riparia   vine/liana			

<sup>\*</sup>Invasive species

(A-66) Bank	27 Floodplain Plant Species	
boxelder maple	Acer negundo	Т
devil's beggar-tick	Bidens frondosa	Н
clearweed	Pilea pumila	Н
moneywort	Lysimachia nummularia	Н
burr-cucumber	Sicyos sp.	Н
marsh bedstraw	Galium palustre	Н
smartweed	Persicaria hydropiper	Н
jewelweed	Impatiens capensis	Н
(B-78)		



Bank 27: Stations 207-209. 200-ft stretch coming out of sharp right bend.

Left bank







I.	General Informa	tion						
	Housatonic ROR R5A Bank 28							
	Site Name and Evaluation Segment  Bank 28: Stations 214-217. 300-ft run entering left bend							
	Location/Physical Description							
	8/10/22 Date(s) of Site Visit(s) and Data Collection							
	Weather Conditions	s During Site Visit						
	AECOM	-						
	Field Staff Perform	ing Evaluation			Date this form was completed			
II.	Site Description							
A.	Bank Characteriza	ation						
Phy	sical Dimensions	(ft):						
Ler	ngth: 300'	Width: 70'	Bank Height: R 7	" L 6'	Slope%: R 90% L 40%			
Sec	diment / Substrate	composition:						
% 5	Sand 45	% Silt 45	% Clay		% Gravel/cobble 10			
% E	Boulder/Bedrock	Q	% Organic matter					
		ved erosional con						
	Right bank is stee	p with some slump	oing. Left bank is gentl	le and st	table. Thalweg runs along right side.			
B.	Bordering Habitat	Types						
We	tland			Upland				
		loodplain forest			Northern Hardwoods-Hemlock-White Pine Forest			
	☐ High terrace	floodplain forest			Rich mesic forest			
	☐ Red maple sv	wamp			Red Oak-Sugar Maple Transition Forest			
	☐ Vernal pool			$\boxtimes$	Agricultural fields			
	Black ash-red swamp	d maple-tamarack	calcareous seepage		Cultural grassland			
	☐ Deep emerge	ent marsh			Successional northern hardwoods			
	Shallow eme     Shall	rgent marsh			Spruce-fir-northern hardwood forest			
	☐ Shrub swamp	ס			Developed/disturbed cover types			
	☐ Wet meadow				Other			
	Other							
Not	es:							

C.	Hydrology							
Stre	eam gradient:	☐ Low Grad	dient	⊠ Mid-Grad	ient		☐ High-Gradient	
De	Degree of overbank flooding potential / floodplain connectivity							
	☐ High-flow cha	annels present ir	adjacent flo	odplain	$\boxtimes$	Topogra	aphic breaks presen	t in the riverbank
	☐ Channel is de	eeply incised	☐ Modera	ately incised		□ S	Somewhat incised	Not incised
De	gree of Water leve	I fluctuation (est	imated vertic	al difference	fron	n mean	low water to):	
	Bankfull indicator	s: 3 ft	Top of bank	k slope: 6-7f	t	Flood	lplain surface: 6-7 ft	
Fie	ld-Derived Eviden	ce of Hydrologic	Conditions					
		line impressed	on bank		$\boxtimes$	Change	es in character of soi	I
	⊠ Bed and ban	ks				Waters	staining	
	Shelving					Vegeta	tion matted down, be	ent or absent
	☐ Wrack lines (	litter and debris)			$\boxtimes$	Change	e in plant community	
	☐ Scour and/or	Deposition				Destruc	ction of terrestrial veg	getation
	☐ Line of mud of	or silt on tree trui	nks/vegetatio	n		Debris	stuck on overhangin	g tree limbs
	Other							
Fie	ld-Derived Eviden	ce of Bankfull St	age/Dischar	ge Water				
	☐ Scour line					Recent	changes to river ber	nds/meanders
	□ Depositional	bench (active ch	annel)		$\boxtimes$	Underc	uts	
	□ Depositional	point bar				Staining	g of rocks	
	Depositional	island			$\boxtimes$	Top of	point bars	
	☐ Middle bench	for braided rive	rs		$\boxtimes$	Lower I	imits in perennial ve	getation
		e of banks (flood	dplain break)					
	Other							
D.	Inventory (Plant 0	Community)						
Rig	ht Bank							
	Total % Cover:	80 Bank Vegetation		0 Dverhanging Veç	getatio		100 Riparian Vegetation	_
	Percent Cover of	Bank and Over	hanging Stre	am Vegetation	on b	y Strata		
	60 Trees (> 20')	40 Shrubs (< 20')	20 Woods	v vines	0 Mos	sses	30 Herbaceous	

Left Bank

Total % Cover:     30	_					
20         60         30         0         70           Trees (> 20')         Shrubs (< 20')         Woody vines         Mosses         Herbaceous           Percent Cover of Riparian Vegetation by Strata           50         50         25         0         60           Trees (> 20')         Shrubs (< 20')         Woody vines         Mosses         Herbaceous	_					
Trees (> 20') Shrubs (< 20') Woody vines Mosses Herbaceous  Percent Cover of Riparian Vegetation by Strata  50 50 25 0 0 60  Trees (> 20') Shrubs (< 20') Woody vines Mosses Herbaceous	_					
Percent Cover of Riparian Vegetation by Strata    50   50   25   0     60     Trees (> 20')   Shrubs (< 20')   Woody vines   Mosses   Herbaceous						
50         50         25         0         60           Trees (> 20')         Shrubs (< 20')         Woody vines         Mosses         Herbaceous						
Trees (> 20') Shrubs (< 20') Woody vines Mosses Herbaceous						
,,	_					
strata, or any amount of an invasive plant species; "*" designates a dominant plant species for Strata Plant Species	cover in each r the strata):					
Riparian vegetation plant list (species that comprise 10% or more of the vegetative cover in earnount of an invasive plant species; "*" designates a dominant plant species for the strata):	ach strata, or any					
Strata: T=Tree, S=Shrub, L=Liana (vine), H=Herb (Includes grasses, herbs, pterophytes [ferns], li seedlings, and mosses)  Notes: See attached tables for plant species lists.  III. Important Habitat Features	chens, woody					
Wildlife Food						
Important wetland/aquatic food plants						
☐ Abundant ☐ Present ☐ Absent ☐ Not Applicab	ole					
Important upland food plants (hard mast and fruit/berry producers)						
☐ Abundant ☐ Present ☐ Absent ☐ Not Applicab	ole					
Cover/Perches/Basking/Denning/Nesting Habitat						
Trees (live or dead) > 30" DBH						
☐ Abundant ☐ Present ☐ Absent ☐ Not Applicab	ole					
Standing dead trees (potential for cavities and perches)	-					

☐ Abundant	□ Present	☐ Absent	☐ Not Applicable			
Tree cavities in trunks or limbs						
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable			
Small mammal burrows:						
Abundant	□ Present	Absent	☐ Not Applicable			
Dense herbaceous cover (v	voles, small mammals, ar	mphibians & reptiles)				
Abundant	□ Present	Absent	☐ Not Applicable			
Large woody debris on the	ground (small mammals	, mink, amphibians & rep	tiles)			
Abundant	□ Present	Absent	□ Not Applicable			
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)			
Abundant	□ Present	Absent	□ Not Applicable			
Overhanging branches at o duck, mink, raccoon)	r within 1 m above the w	ater's surface (turtles, sr	akes, frogs, wading birds, wood			
Abundant	□ Present	Absent	□ Not Applicable			
Rock piles, crevices, or hol	low logs suitable for vario	ous mammals (otter, min	k, porcupine, racoon):			
Abundant	□ Present	Absent	□ Not Applicable			
Live or dead tall standing v osprey, kingfisher, flycatche		near water offering goo	d visibility of open water (e.g.,			
	Present	Absent	□ Not Applicable			
Other Important Habitat C	Characteristics:					
Underwater banks of fine s	ilt and/or clay (beaver, m	uskrat, otter)				
Abundant	□ Present	Absent	□ Not Applicable			
Undercut or overhanging ba	anks (small mammals, m	ink, weasels, turtles)				
Abundant	□ Present	Absent	□ Not Applicable			
Vertical sandy banks (bank	swallow, kingfisher)					
Abundant	☐ Present		Not Applicable			
Mud flats						
Abundant	□ Present	Absent	□ Not Applicable			
Exposed areas of well-drained, sandy soil suitable for turtle nesting						
Abundant	Present		□ Not Applicable			

### Wildlife Dens/Nests (if observed)

	Turtle nesting sites						
	☐ Abundant	☐ Present		□ Not Applicable			
	Bank swallow colony(ies)						
	☐ Abundant	☐ Present		□ Not Applicable			
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron			
	Den(s) present of	☐ Otter	☐ Mink	☐ Beaver			
	Other nests or dens (identif	y species):					
IV.	Connectivity with Adjoini	ng Natural Habitats					
	☐ No direct connections t	o adjacent areas of wildl	ife habitat (little d	connectivity function)			
	Limited number of conf	nectors to adjacent areas	of habitat (som	ewhat important for connectivity function)			
	Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with ur	nimpeded connection to other habitats (high			
٧.	Rare Species and MNHES	SP Core Area Habitat Do	esignation				
	☐ Core Area 1 ☐ Core	Area 2	a 3 🔲 Core	Area 4			
$\boxtimes$ Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat							
	State-listed species habitat (including species with known overlapping Priority Habitat):						
	Matted Spike-sedge, Musta	ard White, Spine-crowne	d Clubtail, Wapa	ato, Wood Turtle			
	Rare species direct observa	ations during current field	l surveys:				
VI.	Incidental Direct Wildlife	Observations					
	-						

General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form	
VII. Habitat Degradation (identify specific location on I	pank segment if applicable)
Evidence of significant levels of dumping	
Evidence of significant erosion or sedimentation p	roblems
○ Occurrence of invasive plants:     Bittersweet	
Evidence of other human disturbance; describe: _	
VIII.Restoration Opportunities	
□ Presence of potential restoration resources (e.g., bank stabilization or hibernacula, plant propagation so Coarse woody debris, large trees, root wads, cobbined.	
○ Other restoration opportunities:	
R: Bank spurs; Log or rock vanes; Grade bank/Coir	matting
L: Grade bank/Coir matting; Reshape point bar; Ba	nk spurs
Invasive species control	
Revegetation	

Bank 28 Plant Species List					
<u>Left bank</u>	Right bank				
boxelder   Acer negundo   tree	boxelder   Acer negundo   tree				
nodding beggar-ticks   Bidens cernua   herb	Asian bittersweet   Celastrus orbiculatus   vine/liana   *				
ironwood   Carpinus caroliniana   tree	common water-purslane   Ludwigia palustris   herb				
Asian bittersweet   Celastrus orbiculatus   vine/liana   *	pale smartweed   Persicaria lapathifolia   herb				
red-osier dogwood   Cornus sericea   shrub	eastern cottonwood   Populus deltoides   tree				
Virginia-creeper   Parthenocissus quinquefolia   vine/liana	American bur-reed   Sparganium americanum   herb				
pale smartweed   Persicaria lapathifolia   herb	blue vervain   Verbena hastata   herb				
common arrowhead   Sagittaria latifolia   herb	river grape   Vitis riparia   vine/liana				
American elm   Ulmus americana   tree					
river grape   Vitis riparia   vine/liana					

<sup>\*</sup>Invasive species

### **Bank 28 Floodplain Plant Species**

boxelder	Acer negundo	T
devil's beggar-tick	Bidens frondosa	Н
Canada clearweed	Pilea pumila	Н
moneywort	Lysimachia nummularia	Н
burr-cucumber	Sicyos sp.	Н
marsh bedstraw	Galium palustre	Н
water pepper smartweed	Persicaria hydropiper	Н
jewelweed	Impatiens capensis	Н

(B-79)



Bank 28: Stations 214-217. 300-ft run entering left bend.

Photos of Bank 28 Area. August 10, 2022.





Left bank. Multi-stem silver maple at station 214

Left bank. Multi-stem silver maple at station 214







Left bank near Station 215 looking downstream


Left bank near Station 215 looking upstream





Left bank, looking upstream near Station214







Sagittaria latifolia...Left bank





### **General Information** Housatonic ROR R5A Bank 29 Site Name and Evaluation Segment Bank 29: Stations 218-220. 200-ft stretch from halfway around left bend Location/Physical Description 8/10/22 Date(s) of Site Visit(s) and Data Collection Weather Conditions During Site Visit Field Staff Performing Evaluation Date this form was completed Site Description A. Bank Characterization Physical Dimensions (ft): Length: 200' Width: 70' Bank Height: R 6'-7' L5' Slope: R 70% L 40% Sediment / Substrate composition: % Gravel/cobble 10 % Sand 45 % Silt 45 % Clay % Boulder/Bedrock % Organic matter Bank stability / Observed erosional conditions: Right bank is stable but steep, high BEHI at 218-219 and moderate NBS at 218-219. Left bank is stable with point bar development. Thalweg along right side B. Bordering Habitat Types Wetland Upland Northern Hardwoods-Hemlock-White Pine **Forest** ☐ High terrace floodplain forest Rich mesic forest Red maple swamp Red Oak-Sugar Maple Transition Forest Vernal pool Agricultural fields ☐ Black ash-red maple-tamarack calcareous seepage Cultural grassland swamp Deep emergent marsh ☐ Successional northern hardwoods ☐ Shallow emergent marsh Spruce-fir-northern hardwood forest Shrub swamp ☐ Developed/disturbed cover types Other \_\_\_\_\_ ☐ Wet meadow Other \_\_\_\_\_

Notes: C. Hydrology Low Gradient Mid-Gradient ☐ High-Gradient Stream gradient: Degree of overbank flooding potential / floodplain connectivity High-flow channels present in adjacent floodplain ☐ Topographic breaks present in the riverbank Channel is deeply incised Moderately incised Not incised Degree of Water level fluctuation (estimated vertical difference from mean low water to): Bankfull indicators: R 3ft L 2ft Top of bank slope: 5-7ft Floodplain surface: 5-7ft Field-Derived Evidence of Hydrologic Conditions Clear natural line impressed on bank Changes in character of soil Bed and banks ☐ Water staining Vegetation matted down, bent or absent Shelving □ Change in plant community Wrack lines (litter and debris) Scour and/or Deposition Destruction of terrestrial vegetation Line of mud or silt on tree trunks/vegetation Debris stuck on overhanging tree limbs Other Field-Derived Evidence of Bankfull Stage/Discharge Water ☐ Scour line ☐ Recent changes to river bends/meanders Depositional bench (active channel) Undercuts Depositional point bar Staining of rocks Depositional island Break in slope of banks (floodplain break) Other D. Inventory (Plant Community) Right Bank Total % Cover: Overhanging Vegetation **Bank Vegetation** Riparian Vegetation Percent Cover of Bank and Overhanging Stream Vegetation by Strata Trees (> 20') Shrubs (< 20') Herbaceous Woody vines Mosses

Left Bank

	Total % Cover:	75 Bank Vegetation	50 Overhangin	g Vegetation	80 Riparian Vegetation		
	Percent Cover of	of Bank and Overhang	ging Stream Vege	etation by Stra	nta		
	10	0 Shrubs (< 20')	0	0	90		
	Trees (> 20')	Shrubs (< 20')	Woody vines	Mosses	Herbaceous		
Per	cent Cover of Rip	parian Vegetation by	Strata				
	70	75 Shrubs (< 20')	25	0	70		
			-				
Bar	nk and overhangi strata. or anv an	ing vegetation plant lis	st (species that co plant species: "*" o	omprise 10% designates a d	or more of the vegetative cover in each dominant plant species for the strata):		
	•	nt Species	,	Strata	Plant Species		
	Otrata Fiai	пороско		Ottata	Tiant oposios		
	Piparian yagata	tion plant list (species	that comprise 10	00/ or more of	the vegetative cover in each strata, or any		
					t species for the strata):		
					-		
Stra	ata: T=Tree, S=S	Shrub, L=Liana (vine),	H=Herb (Include	es grasses, he	erbs, pterophytes [ferns], lichens, woody		
	seedlings, and n		•				
Not	es: See attache	d tables for plant spec	cies lists.				
	lmmentent Hebi	tot Footives					
ш.	Important Habi	tat reatures					
	Wildlife Food						
	Important wetland/aquatic food plants						
	☐ Abundant	⊠ Prese	ent [	Absent	□ Not Applicable		
	_	<del>_</del>		_			
	Important upland food plants (hard mast and fruit/berry producers)						
	☐ Abundant	⊠ Prese	ent [	Absent	□ Not Applicable		
	Cover/Perches	/Basking/Denning/N	esting Habitat				
	Trees (live or de	ead) > 30" DBH					
	☐ Abundant	∑ Prese	ent 「	Absent	□ Not Applicable		
	_	<del>_</del>		_	☐ Not Applicable		
	Standing dead to	rees (potential for cav	rities and perches	;)			

☐ Abundant	□ Present	☐ Absent	□ Not Applicable			
Tree cavities in trunks or limbs						
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable			
Small mammal burrows:						
Abundant	□ Present	Absent	☐ Not Applicable			
Dense herbaceous cover (v	voles, small mammals, ar	mphibians & reptiles)				
Abundant	□ Present	Absent	☐ Not Applicable			
Large woody debris on the	ground (small mammals	, mink, amphibians & rep	tiles)			
Abundant	□ Present	Absent	□ Not Applicable			
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)			
Abundant	□ Present	Absent	□ Not Applicable			
Overhanging branches at o duck, mink, raccoon)	r within 1 m above the w	ater's surface (turtles, sr	akes, frogs, wading birds, wood			
Abundant	□ Present	Absent	□ Not Applicable			
Rock piles, crevices, or hol	low logs suitable for vario	ous mammals (otter, min	k, porcupine, racoon):			
Abundant	□ Present	Absent	□ Not Applicable			
Live or dead tall standing v osprey, kingfisher, flycatche		near water offering goo	d visibility of open water (e.g.,			
	Present	Absent	□ Not Applicable			
Other Important Habitat C	Characteristics:					
Underwater banks of fine s	ilt and/or clay (beaver, m	uskrat, otter)				
Abundant	□ Present	Absent	□ Not Applicable			
Undercut or overhanging ba	anks (small mammals, m	ink, weasels, turtles)				
Abundant	□ Present	Absent	□ Not Applicable			
Vertical sandy banks (bank	swallow, kingfisher)					
Abundant	☐ Present		Not Applicable			
Mud flats						
Abundant	□ Present	Absent	□ Not Applicable			
Exposed areas of well-drained, sandy soil suitable for turtle nesting						
Abundant	Present		□ Not Applicable			

### Wildlife Dens/Nests (if observed)

	Turtle nesting sites						
	☐ Abundant	☐ Present		□ Not Applicable			
	Bank swallow colony(ies)						
	Abundant	☐ Present		☐ Not Applicable			
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	Great Blue Heron			
	Den(s) present of	Otter	Mink	Beaver			
	Other nests or dens (identify	y species):					
IV.	Connectivity with Adjoini	ng Natural Habitats					
	☐ No direct connections t	to adjacent areas of wildli	ife habitat (little d	connectivity function)			
	Limited number of conr	nectors to adjacent areas	of habitat (some	ewhat important for connectivity function)			
	☐ Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with ur	nimpeded connection to other habitats (high			
V.	Rare Species and MNHES	SP Core Area Habitat De	esignation				
	☐ Core Area 1 ☐ Core	Area 2 Core Area	a 3 🔲 Core A	Area 4			
	Example 2 Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat						
	State-listed species habitat (including species with known overlapping Priority Habitat):						
	Matted Spike-sedge, Must	tard White, Spine-crowne	ed Clubtail, Wapa	ato, Wood Turtle			
	Rare species direct observa	ations during current field	l surveys:				
VI.	Incidental Direct Wildlife	Observations					

	General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form	
	·	
VII	VII. Habitat Degradation (identify specific location on bank seg	ment if applicable)
	Evidence of significant levels of dumping	
	Evidence of significant erosion or sedimentation problems	
:	<ul><li>Occurrence of invasive plants:</li><li>Bittersweet, Japanese knotweed, purple loosestrife, common</li></ul>	buckthorn
	Evidence of other human disturbance; describe:	
VII	VIII.Restoration Opportunities	
	Presence of potential restoration resources (e.g., boulders, bank stabilization or hibernacula, plant propagation source mat Coarse woody debris, large trees, cobbles	
	○ Other restoration opportunities:	
	R: Log or rock vanes; Root wads; Vegetated riprap	
	L: Reshape point bar	
	Invasive species control	
	Revegetation	
_		

Bank 29 Plant Species List				
<u>Left bank</u>	Right bank			
boxelder   Acer negundo   tree	boxelder   Acer negundo   tree			
nodding beggar-ticks   Bidens cernua   herb	silver maple   Acer saccharinum   tree			
black mustard   Brassica nigra   herb	nodding beggar-ticks   Bidens cernua   herb			
wild cucumber   Echinocystis lobata   vine	Asian bittersweet   Celastrus orbiculatus   vine/liana   *			
Japanese knotweed   Fallopia japonica   herb   *	pale smartweed   Persicaria lapathifolia   herb			
purple loosestrife   Lythrum salicaria   herb   *	common buckthorn   Rhamnus cathartica   herb   *			
pale smartweed   Persicaria lapathifolia   herb	river grape   Vitis riparia   vine/liana			
jumpseed   Persicaria virginiana   herb				
American speedwell   Veronica americana   herb				
river grape   Vitis riparia   vine/liana				
rough cocklebur   Xanthium strumarium   herb				

<sup>\*</sup>Invasive species

### **Bank 29 Floodplain Plant Species**

Boxelder	Acer negundo	T
devil's beggar-tick	Bidens frondosa	Н
Canada clearweed	Pilea pumila	Н
moneywort	Lysimachia nummularia	Н
burr-cucumber	Sicyos sp.	Н
marsh bedstraw	Galium palustre	Н
water-pepper smartweed	Persicaria hydropiper	Н
jewelweed	Impatiens capensis	Н



Bank 29: Stations 218-220. 200-ft stretch from halfway around left bend.

Photos of Bank 29 Area. August 10, 2022. Right bank Right bank Right bank







,							
	Housatonic ROR R5A Bank 30 Site Name and Evaluation Segment						
	Bank 30: Stations 2 Location/Physical I	221-223. 200-ft stretch t	hat enters left bei	nd			
	8/10/22						
	Date(s) of Site Visit(s) and Data Collection						
	Weather Conditions	s During Site Visit					
	AECOM Field Staff Perform	ing Evaluation					Date this form was completed
II.	Site Description	ı					
A.	Bank Characteriza	ation					
Ph	ysical Dimensions	(ft):					
Ler	ngth: 200'	Width: 80'	Bank Height:	R 4'-6'	L6	Slope%: R 4	0 L 70
Se	diment / Substrate	composition:					
% :	Sand 40	% Silt 40	% Clay			% Gravel/cobble 20	0
% I	Boulder/Bedrock	% O	rganic matter				
		rved erosional conditionely stable. Low - mode		low NB	S oı	n both banks. Thalv	veg towards right side.
B.	Bordering Habitat	Types					
We	etland			Upla	and		
		loodplain forest			$\boxtimes$	Northern Hardwood Forest	ds-Hemlock-White Pine
	☐ High terrace	floodplain forest				Rich mesic forest	
	☐ Red maple s	wamp				Red Oak-Sugar Ma	aple Transition Forest
	☐ Vernal pool				$\boxtimes$	Agricultural fields	
	☐ Black ash-red swamp	d maple-tamarack cald	careous seepag	е		Cultural grassland	
	☐ Deep emerge	ent marsh				Successional north	ern hardwoods
	Shallow eme	rgent marsh				Spruce-fir-northern	hardwood forest
	☐ Shrub swamp	p				Developed/disturbe	ed cover types
	☐ Wet meadow	1				Other	
	Other						
No	tes:						

	Hydrology						
Stre	am gradient:	dient	☐ High-Gradient				
Deg	Degree of overbank flooding potential / floodplain connectivity						
	☐ High-flow channels present in adjacent floodplain		Topographic breaks present in the riverbank				
☐ Channel is deeply incised ☐ Moderately incised ☐ Somewhat incised ☐							
Deg	ree of Water level fluctuation (estimated vertical differenc	e fron	n mean low water to):				
	Bankfull indicators: R 3 ft L3 ft Top of bank slope: 4-6	ft	Floodplain surface: 4-6 ft				
Fiel	d-Derived Evidence of Hydrologic Conditions						
			Changes in character of soil				
	⊠ Bed and banks		Water staining				
	Shelving		Vegetation matted down, bent or absent				
			Change in plant community				
	Scour and/or Deposition		Destruction of terrestrial vegetation				
	Line of mud or silt on tree trunks/vegetation		Debris stuck on overhanging tree limbs				
	☐ Other						
<b>-</b>	Field-Derived Evidence of Bankfull Stage/Discharge Water						
Field	d-Derived Evidence of Bankfull Stage/Discharge Water						
Field	d-Derived Evidence of Bankfull Stage/Discharge Water  Scour line		Recent changes to river bends/meanders				
Fiel	_		Recent changes to river bends/meanders Undercuts				
Fiel	Scour line     ■						
Field	<ul><li>Scour line</li><li>Depositional bench (active channel)</li></ul>		Undercuts				
Fiel	<ul> <li>Scour line</li> <li>Depositional bench (active channel)</li> <li>Depositional point bar</li> </ul>		Undercuts Staining of rocks				
Fiel	<ul> <li>Scour line</li> <li>Depositional bench (active channel)</li> <li>Depositional point bar</li> <li>□ Depositional island</li> </ul>		Undercuts Staining of rocks Top of point bars				
Fiel	<ul> <li>Scour line</li> <li>Depositional bench (active channel)</li> <li>Depositional point bar</li> <li>Depositional island</li> <li>Middle bench for braided rivers</li> </ul>		Undercuts Staining of rocks Top of point bars				
	<ul> <li>Scour line</li> <li>Depositional bench (active channel)</li> <li>Depositional point bar</li> <li>Depositional island</li> <li>Middle bench for braided rivers</li> <li>Break in slope of banks (floodplain break)</li> </ul>		Undercuts Staining of rocks Top of point bars				
D.	<ul> <li>Scour line</li> <li>Depositional bench (active channel)</li> <li>Depositional point bar</li> <li>Depositional island</li> <li>Middle bench for braided rivers</li> <li>Break in slope of banks (floodplain break)</li> <li>Other</li> </ul>		Undercuts Staining of rocks Top of point bars				
D.	<ul> <li>Scour line</li> <li>Depositional bench (active channel)</li> <li>Depositional point bar</li> <li>Depositional island</li> <li>Middle bench for braided rivers</li> <li>Break in slope of banks (floodplain break)</li> <li>Other</li></ul>		Undercuts Staining of rocks Top of point bars Lower limits in perennial vegetation				
D.	<ul> <li>Scour line</li> <li>Depositional bench (active channel)</li> <li>Depositional point bar</li> <li>Depositional island</li> <li>Middle bench for braided rivers</li> <li>Break in slope of banks (floodplain break)</li> <li>Other</li></ul>	□ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □	Undercuts  Staining of rocks  Top of point bars  Lower limits in perennial vegetation   90  Riparian Vegetation				

Left Bank

	Total % Cover:	80 Bank Vegetation	60 Overhanging	g Vegetation	80 Riparian Vegetation
	Percent Cover of	of Bank and Overhang	ging Stream Vege	tation by Stra	ıta
	30	30 Shrubs (< 20')	10	0 Mosses	60
	Trees (> 20')		Woody vines	Mosses	Herbaceous
Per	cent Cover of Rip	parian Vegetation by S	Strata		
	40	70 Shrubs (< 20')	30	0 Mosses	60
			· ·		Herbaceous
Bar	nk and overhangi strata. or anv ar	ng vegetation plant lis	st (species that co plant species: "*" o	omprise 10% ( designates a d	or more of the vegetative cover in each dominant plant species for the strata):
	•	nt Species		Strata	Plant Species
	Circia Fiai	поробов		Otrata	Tiant openies
	Piparian vogeta	tion plant list (species	that comprise 10	10/2 or more of	the vegetative cover in each strata, or any
					t species for the strata):
				<del></del>	
				<del></del>	-
				=	
Stra	ata: T=Tree.S=S	Shrub. L=Liana (vine).	H=Herb (Include	s grasses, he	erbs, pterophytes [ferns], lichens, woody
	seedlings, and n				
Not	es: See attache	d tables for plant spec	cies lists.		
		4-4-54			
III.	Important Habi	tat reatures			
	Wildlife Food				
	Important wetlar	nd/aquatic food plants			
	☐ Abundant	⊠ Prese	ont [	Absent	☐ Not Applicable
	_	_		-	☐ Not Applicable
	Important upland	d food plants (hard ma	ast and fruit/berry	producers)	
	☐ Abundant	□ Prese	ent [	Absent	☐ Not Applicable
	Cover/Perches/	/Basking/Denning/Ne	esting Habitat		
	Trees (live or de				
		<u></u>	· -	7	
	☐ Abundant	⊠ Prese	ent _	Absent	☐ Not Applicable
	Standing dead to	rees (potential for cav	ities and perches	)	

Abundant	□ Present	☐ Absent	☐ Not Applicable
Tree cavities in trunks	or limbs		
Abundant		☐ Absent	□ Not Applicable
Small mammal burrow	/s:		
Abundant		☐ Absent	□ Not Applicable
Dense herbaceous co	ver (voles, small mamma	als, amphibians & reptile	es)
Abundant		☐ Absent	☐ Not Applicable
Large woody debris or	n the ground (small mam	mals, mink, amphibians	s & reptiles)
Abundant		☐ Absent	□ Not Applicable
Rocks, crevices, logs,	tree roots or hummocks	at water's edge or unde	er water's surface (turtles, snakes, frogs)
Abundant		☐ Absent	□ Not Applicable
Overhanging branched duck, mink, raccoon)	s at or within 1 m above	the water's surface (turt	les, snakes, frogs, wading birds, wood
Abundant		Absent	☐ Not Applicable
Rock piles, crevices, c	or hollow logs suitable for	various mammals (otte	er, mink, porcupine, racoon):
☐ Abundant		☐ Absent	☐ Not Applicable
	ling vegetation overhang catchers, cedar waxwing		ng good visibility of open water (e.g.,
	☐ Present	☐ Absent	□ Not Applicable
Other Important Hab	itat Characteristics:		
Underwater banks of f	ine silt and/or clay (beav	er, muskrat, otter)	
Abundant		☐ Absent	☐ Not Applicable
Undercut or overhang	ing banks (small mamma	als, mink, weasels, turtle	es)
Abundant		☐ Absent	□ Not Applicable
Vertical sandy banks (	(bank swallow, kingfisher	·)	
Abundant	☐ Present		☐ Not Applicable
Mud flats			
Abundant		☐ Absent	□ Not Applicable
Exposed areas of well	-drained, sandy soil suita	able for turtle nesting	
☐ Abundant	□ Present	☐ Absent	□ Not Applicable

### Wildlife Dens/Nests (if observed)

	Turtle nesting sites			
	☐ Abundant	☐ Present		☐ Not Applicable
	Bank swallow colony(ies)			
	Abundant	☐ Present		□ Not Applicable
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron
	Den(s) present of	☐ Otter	☐ Mink	Beaver
	Other nests or dens (identify	y species):		
IV.	Connectivity with Adjoini	ng Natural Habitats		
	☐ No direct connections t	to adjacent areas of wildli	ife habitat (little d	connectivity function)
	Limited number of conr	nectors to adjacent areas	of habitat (som	ewhat important for connectivity function)
	☐ Riverbank is embedded connectivity function)	d in a large area of natura	al habitat with ur	nimpeded connection to other habitats (high
٧.	Rare Species and MNHES	SP Core Area Habitat De	esignation	
	☐ Core Area 1 ☐ Core	Area 2 Core Area	a 3 🔲 Core	Area 4
	☐ Federally listed threate habitat): Northern long-ear		cies habitat (inclu	uding species with known overlapping
	<u> </u>	abitat (including species v		· · · · · · · · · · · · · · · · · · ·
	Matted Spike-sedge, Musta	ard White, Spine-crowned	d Clubtail, Wapa	ato, Wood Turtle
_				
	Rare species direct observa	ations during current field	l surveys:	
_				
VI.	Incidental Direct Wildlife	Observations		
	Spotted sandpiper			

General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form					
VII. Habitat Degradation (identify specific location on b	pank segment if applicable)				
Evidence of significant levels of dumping					
Evidence of significant erosion or sedimentation p	roblems				
Occurrence of invasive plants: Bittersweet, yellow iris, Japanese knotweed					
Evidence of other human disturbance; describe:					
VIII.Restoration Opportunities					
Presence of potential restoration resources (e.g., I bank stabilization or hibernacula, plant propagation so Coarse woody debris, large trees, root wads, cobb					
○ Other restoration opportunities:					
R: Grade bank/Coir matting; Log or rock vanes					
L: Grade bank/Coir matting					
Invasive species control					
Revegetation					

Bank 30 Pla	nt Species List		
<u>Left bank</u>	Right bank		
boxelder   Acer negundo   tree	boxelder   Acer negundo   tree		
silver maple   Acer saccharinum   tree	silver maple   Acer saccharinum   tree		
nodding beggar-ticks   Bidens cernua   herb	nodding beggar-ticks   Bidens cernua   herb		
Japanese knotweed   Fallopia japonica   herb   *	Asian bittersweet   Celastrus orbiculatus   vine/liana   *		
common water-purslane   Ludwigia palustris   herb	umbrella sedge   Cyperus strigosus   herb		
pale smartweed   Persicaria lapathifolia   herb	eastern willow-herb   Epilobium coloratum   herb		
Canada clearweed   Pilea pumila   herb	yellow iris   Iris pseudacorus   herb   *		
	Virginia water-horehound   Lycopus virginicus   herb		
	ostrich fern   Matteuccia struthiopteris   herb		
	American wild mint   Mentha canadensis   herb		
	Allegheny monkeyflower   Mimulus ringens   herb		
	water-pepper smartweed   Persicaria hydropiper   herb		
	pale smartweed   Persicaria lapathifolia   herb		
	jumpseed   Persicaria virginiana   herb		
	creeping yellow-cress   Rorippa sylvestris   herb		
	American speedwell   Veronica americana   herb		

<sup>\*</sup>Invasive species


### **Bank 30 Floodplain Plant Species**

boxelder	Acer negundo	T
devil's beggar-tick	Bidens frondosa	Н
Canada clearweed	Pilea pumila	Н
moneywort	Lysimachia nummularia	Н
burr-cucumber	Sicyos sp.	Н
marsh bedstraw	Galium palustre	Н
water-pepper smartweed	Persicaria hydropiper	Н
jewelweed	Impatiens capensis	Н



Bank 30: Stations 221-223. 200-ft stretch that enters left bend.

Right bank, downstream end of reach. Station 223.





	I.	General Informa	tion					
		Housatonic ROR R5A Bank 31						
		Site Name and Evaluation Segment						
		Bank 31: Stations 223-224. 100' sharp bend to left.						
	Location/Physical Description							
	8/10/22 Date(s) of Site Visit(s) and Data Collection							
		Weather Condition	o During Cita Vioit					
		Weather Conditions AECOM	s During Site visit					
		Field Staff Perform	ing Evaluation			Date this form was completed		
II.	Site	e Description						
Α	Ban	k Characterization	1					
			•					
FII	ysica	al Dimensions (ft):						
Lei	ngth:	: 100'	Width: 70'	Bank Height: R 8'	L 5'	Slope%: R 100 L 50		
Se	dime	ent / Substrate con	nposition:					
%	Sand	d 45	% Silt 45	% Clay		% Gravel/cobble 10		
%	Boul	der/Bedrock	% O	rganic matter				
Ва	Rig	ht bank is steep bu	erosional conditions: ut stable. Right bank B are low – moderate.	EHI is high and NBS	S is ex	treme. Left bank more gentle and stable. Left		
В.	Boro	dering Habitat Typ	es					
We	etlan	d		U	lpland			
	$\boxtimes$	Transitional flood	plain forest			Northern Hardwoods-Hemlock-White Pine Forest		
		High terrace flood	dplain forest			Rich mesic forest		
		Red maple swam	пр			Red Oak-Sugar Maple Transition Forest		
		Vernal pool			$\boxtimes$	Agricultural fields		
		Black ash-red ma swamp	aple-tamarack calcared	ous seepage		Cultural grassland		
		Deep emergent n	narsh			Successional northern hardwoods		
	$\boxtimes$	Shallow emergen	nt marsh			Spruce-fir-northern hardwood forest		
		Shrub swamp				Developed/disturbed cover types		
		Wet meadow				Other		
		Other						

Notes:								
C. Hyd	drology							
Stream	Stream gradient:				t High-Gradient			
Degree	e of overbank flood	ing potential / floodpla	ain connectivity					
	High-flow channe	els present in adjacent	floodplain	$\boxtimes$	Topographic breaks present in the riverbank			
	Channel is deeply	y incised	Moderately incise	ed		ł		
Degree	egree of Water level fluctuation (estimated vertical difference from mean low water to):							
Bank	full indicators: R 3	ft L 3 ft Top	of bank slope: 5-	8 ft	Floodplain surface: 5-8 ft			
Field-D	erived Evidence o	f Hydrologic Condition	าร					
	Clear natural line	impressed on bank		$\boxtimes$	Changes in character of soil			
	⊠ Bed and banks				Water staining			
	Shelving				Vegetation matted down, bent or absent			
	☐ Wrack lines (litter and debris)			$\boxtimes$	Change in plant community			
$\boxtimes$					Destruction of terrestrial vegetation			
	Line of mud or sil	t on tree trunks/veget	ation		Debris stuck on overhanging tree limbs			
	Other					_		
Field-D	erived Evidence o	f Bankfull Stage/Disch	narge Water					
	Scour line				Recent changes to river bends/meanders			
	Depositional bene	ch (active channel)		$\boxtimes$ (	Undercuts			
$\boxtimes$	Depositional poin	t bar			Staining of rocks			
	Depositional islar	nd		$\boxtimes$				
	Middle bench for	braided rivers		⊠ I				
$\boxtimes$	Break in slope of	banks (floodplain bre	ak)					
	Other					_		
D. Inv	entory (Plant Com	munity)						
Right E	Bank							
_	tal % Cover:	80 Bank Vegetation	80 Overhanging	Vegetatio	tion   90   Riparian Vegetation			
	ercent Cover of Bar	nk and Overhanging S	•	•				
20 Tre	es (> 20')	70 Shrubs (< 20')	20 Woody vines	0 Moss	osses 40 Herbaceous			

#### Left Bank

Total % Cover:	80	30 Overhanging Vegetation		80	
10tai 70 00vci.	Bank Vegetation			Riparian Vegetation	
Percent Cover of	f Bank and Overhanging	Stream Vegetation	n by Strata		
20	40	20	0	70	
Trees (> 20')	Shrubs (< 20')	Woody vines	Mosses	Herbaceous	
Percent Cover of Rip	arian Vegetation by Strat	a			
40	60	30	0	70	
Trees (> 20')	Shrubs (< 20')	Woody vines	Mosses	Herbaceous	
Bank and overhangir any amount of ar	ng vegetation plant list (sp n invasive plant species;	pecies that compr "" designates a d	ise 10% or n ominant plar	nore of the vegetative cover in nt species for the strata):	n each strata, or
Strata I	Plant Species		Strata	Plant Species	
amount of an inv	asive plant species; "*" dent	esignates a domir	nant plant sp	vegetative cover in each stratecies for the strata):	
III. Important Habit	at Features				
Wildlife Food					
Important wetlan	d/aquatic food plants				
☐ Abundant	□ Present	☐ Ab	sent	☐ Not Applicable	
Important upland	food plants (hard mast a	and fruit/berry prod	ducers)		
☐ Abundant	□ Present	☐ Ab	osent	□ Not Applicable	
Cover/Perches/	Basking/Denning/Nestir	ng Habitat			
Trees (live or dea	ad) > 30" DBH				
☐ Abundant	☐ Present	⊠ At	osent	□ Not Applicable	
Standing dead tr	ees (potential for cavities	and perches)			

#### Form RB-1: Riverbank Habitat Inventory Form ☐ Present ☐ Not Applicable Abundant Tree cavities in trunks or limbs Abundant Present Absent ☐ Not Applicable Small mammal burrows: Abundant □ Present ☐ Absent Not Applicable Dense herbaceous cover (voles, small mammals, amphibians & reptiles) Abundant □ Present Not Applicable Absent Large woody debris on the ground (small mammals, mink, amphibians & reptiles) Abundant □ Present ☐ Absent Not Applicable Rocks, crevices, logs, tree roots or hummocks at water's edge or under water's surface (turtles, snakes, frogs) □ Present Abundant Absent ☐ Not Applicable Overhanging branches at or within 1 m above the water's surface (turtles, snakes, frogs, wading birds, wood duck, mink, raccoon) □ Present Abundant Absent Not Applicable Rock piles, crevices, or hollow logs suitable for various mammals (otter, mink, porcupine, racoon): Abundant Present Not Applicable Live or dead tall standing vegetation overhanging or near water offering good visibility of open water (e.g., osprey, kingfisher, flycatchers, cedar waxwings) Not Applicable Abundant Present Absent **Other Important Habitat Characteristics:** Underwater banks of fine silt and/or clay (beaver, muskrat, otter) □ Present Abundant Absent Not Applicable Undercut or overhanging banks (small mammals, mink, weasels, turtles) Abundant Present Absent Not Applicable Vertical sandy banks (bank swallow, kingfisher) Abundant Present Not Applicable Mud flats Abundant Present Absent Not Applicable Exposed areas of well-drained, sandy soil suitable for turtle nesting □ Present Abundant Not Applicable Absent

**General Electric Housatonic Rest of River** 

#### Wildlife Dens/Nests (if observed)

	Turtle nesting sites						
	Abundant	Present		□ Not Applicable			
	Bank swallow colony(ies)						
	Abundant	Present		□ Not Applicable			
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron			
	Den(s) present of	☐ Otter	☐ Mink	☐ Beaver			
	Other nests or dens (identif	y species):					
IV.	Connectivity with Adjoini	ng Natural Habitats					
	☐ No direct connections t	to adjacent areas of wildl	ife habitat (little	connectivity function)			
	Limited number of con	nectors to adjacent areas	s of habitat (som	ewhat important for connectivity function)			
	☐ Riverbank is embedded connectivity function)	d in a large area of natur	al habitat with u	nimpeded connection to other habitats (high			
٧.	Rare Species and MNHES	SP Core Area Habitat D	esignation				
	☐ Core Area 1 ☐ Core	Area 2	ea 3 🔲 Core	Area 4			
	☐ Federally listed threatened or endangered species habitat (including species with known overlapping habitat):     Northern long-eared bat						
	State-listed species ha	abitat (including species v	with known over	lapping Priority Habitat):			
	Matted Spike-sedge, Musta	ard White, Spine-crowne	d Clubtail, Wapa	ato, Wood Turtle			
	Rare species direct observa	ations during current field	d surveys:				
VI.	Incidental Direct Wildlife	Observations					
	Spotted sandpiper						
	Canada geese						

	General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form	
VII.	I. Habitat Degradation (identify specific location on bank	segment if applicable)
	Evidence of significant levels of dumping	
	Evidence of significant erosion or sedimentation probler	ms
	Occurrence of invasive plants:  Morrow's honeysuckle, Japanese knotweed, common be	ouckthorn
	Evidence of other human disturbance; describe:	
VIII	II.Restoration Opportunities	
	Presence of potential restoration resources (e.g., boulded bank stabilization or hibernacula, plant propagation source a Coarse woody debris, large trees, cobbles	
	○ Other restoration opportunities:	
	R: Log or rock vanes; Root wads; Vegetated riprap	
	L: Reshape point bar	
	Invasive species control	
	Revegetation	

Bank 31 Plant Species List					
<u>Left bank</u>	Right bank				
northern water-plantain   Alisma triviale   herb	boxelder   Acer negundo   tree				
nodding beggar-ticks   Bidens cernua   herb	Morrow's honeysuckle   Lonicera morrowii   shrub   *				
black mustard   Brassica nigra   herb	common buckthorn   Rhamnus cathartica   herb   *				
wild cucumber   Echinocystis lobata   vine	American elm   Ulmus americana   tree				
Japanese knotweed   Fallopia japonica   herb   *					
yellow-seeded false pimpernel   Lindernia dubia   herb					
common water-purslane   Ludwigia palustris   herb					
water-pepper smartweed   Persicaria hydropiper   herb					
Pale smartweed   Persicaria lapathifolia   herb					
eastern cottonwood   Populus deltoides   tree					
blue vervain   Verbena hastata   herb					

<sup>\*</sup>Invasive species

#### **Bank 31 Floodplain Plant Species**

red maple	Acer rubrum	T
silver maple	Acer saccharinum	T
American linden	Tilia americana	T
boxelder	Acer negundo	Т
devil's beggar-tick	Bidens frondosa	Н
Pennsylvania smartweed	Persicaria pensylvanica	Н
moneywort	Lysimachia nummularia	Н
Canada clearweed	Pilea pumila	Н
water-starwort	Callitriche palustris	Н



Bank 31: Stations 223-224. 100-ft sharp bend to left.

Photos of Bank 31 Area. August 10, 2022



I.	General Informa	ation			
	Housatonic ROR F				
	Site Name and Even	aluation Segment 225-227. 200-ft mild	l right hend		
	Location/Physical		ingrit boria		
	8/10/22 Date(s) of Site Visi	t(s) and Data Collec	tion		
		. ,	NOT		
	Weather Condition AECOM	s During Site Visit			
	Field Staff Perform	ing Evaluation			Date this form was completed
II.	Site Description	1			
A.	Bank Characteriz	ation			
Phy	ysical Dimensions	(ft):			
Ler	ngth: 200'	Width: 90'	Bank Height: R 6'-	7' L 4' Slope	%: R 30 L 90
Sec	diment / Substrate	composition:			
% \$	Sand 45	% Silt 45	% Clay	% Gravel/co	obble 10
% E	Boulder/Bedrock		% Organic matter		
Bar	nk stability / Obse	rved erosional con	ditions:		
	Right bank is stee	ep but only minor o	erosion. Right bank NBS		ne - low. Left bank more gradual and
	stable with low –	moderate NBS ar	nd BEHI. Thalweg move	s from right side to	center.
B.	Bordering Habitat	Types			
We	etland		l	Jpland	
		floodplain forest		Northern Ha	ardwoods-Hemlock-White Pine
	Z Hansilionari	ilooupiaiii iorest		Forest	
	☐ High terrace	floodplain forest		☐ Rich mesic	forest
	☐ Red maple s	wamp		☐ Red Oak-Su	gar Maple Transition Forest
	✓ Vernal pool			Agricultural	fields
	Black ash-re swamp	d maple-tamarack	calcareous seepage	☐ Cultural gra	ssland
	☐ Deep emerg	ent marsh		Succession	al northern hardwoods
	Shallow eme     Shall	rgent marsh		☐ Spruce-fir-n	orthern hardwood forest
	☐ Shrub swam	р		☐ Developed/d	disturbed cover types
	☐ Wet meadow	I		Other	
	Other				
Not	too				

1

C.	Hydrology							
Stre	eam gradient:		dient	☐ Mid-Gradi	ient		High-Gradient	
Deg	Degree of overbank flooding potential / floodplain connectivity							
	☐ High-flow cha	annels present ir	adjacent flo	odplain	$\boxtimes$	Topograph	ic breaks present i	n the riverbank
	☐ Channel is de	eeply incised	⊠ Modera	tely incised		☐ Som	ewhat incised	☐ Not incised
Deg	gree of Water leve	I fluctuation (est	imated vertica	al difference	fron	n mean low	water to):	
Bar	nkfull indicators: R	3 ft L 2 ft To	p of bank slo	pe:R 6-7ft L	4ft	Floodpla	in surface: 4-7ft	
Fiel	d-Derived Eviden	ce of Hydrologic	Conditions					
		line impressed	on bank		$\boxtimes$	Changes in	n character of soil	
	Bed and banl	ks				Water stair	ning	
	Shelving					Vegetation	matted down, ben	t or absent
	☐ Wrack lines (	litter and debris)			$\boxtimes$	Change in	plant community	
	Scour and/or     Scour and/or	Deposition				Destruction	n of terrestrial vege	tation
	Line of mud of	or silt on tree tru	nks/vegetatio	n		Debris stud	ck on overhanging	tree limbs
	Other							
Fiel	d-Derived Eviden	ce of Bankfull St	age/Discharg	je Water				
	☐ Scour line					Recent cha	anges to river bend	s/meanders
	□ Depositional	bench (active ch	nannel)		$\boxtimes$	Undercuts		
	Depositional	point bar				Staining of	rocks	
	Depositional	island				Top of poir	nt bars	
	☐ Middle bench	for braided rive	rs		$\boxtimes$	Lower limit	s in perennial vege	etation
		e of banks (flood	dplain break)					
	Other							
D.	Inventory (Plant 0	Community)						
Rig	ht Bank							
	Total % Cover:	50 Bank Vegetation	on 3	0 verhanging Veg	jetatio	80 Ripa	rian Vegetation	
	Percent Cover of	Bank and Over	hanging Strea	am Vegetatic	on b	y Strata		
	30 Trees (> 20')	70 Shrubs (< 20')	70 Woody	vines	0 Mos	sses	10 Herbaceous	

Left Bank

	Total % Cover:	60 Bank Vegetation	80 Overhangin	g Vegetation	60 Riparian Vegetation			
	Percent Cover of	of Bank and Overhang	ging Stream Vege	etation by Stra	ıta			
	40	60	30	0	60			
	Trees (> 20')	Shrubs (< 20')	Woody vines	Mosses	Herbaceous			
Per	cent Cover of Rip	parian Vegetation by S	Strata					
	40	60 Shrubs (< 20')	20 Woody vines	0 Mosses	60			
	Trees (> 20')		-		Herbaceous			
Bar	nk and overhangi strata. or anv an	ng vegetation plant lis	st (species that co plant species: "*" o	omprise 10% d designates a d	or more of the vegetative cover in each dominant plant species for the strata):			
	•	nt Species	,	Strata	Plant Species			
	Circia Fiai	п оресто		Otrata	Tank openies			
	Diparian vocata	tion plant list (species	that comprise 10	00/ or more of	the vegetative cover in each strata, or any			
					t species for the strata):			
Stra	ata: T=Tree.S=S	Shrub. L=Liana (vine).	H=Herb (Include	es grasses, he	erbs, pterophytes [ferns], lichens, woody			
	seedlings, and n							
Not	es: See attached	d tables for plant spec	cies lists.					
		4-4-54						
III.	important Habi	Important Habitat Features						
	Wildlife Food							
	Important wetland/aquatic food plants							
	☐ Abundant	⊠ Prese	ent [	Absent	☐ Not Applicable			
	Important upland food plants (hard mast and fruit/berry producers)							
	☐ Abundant	⊠ Prese	ent [	Absent	☐ Not Applicable			
	Cover/Perches/	/Basking/Denning/Ne	esting Habitat					
	Trees (live or de	ead) > 30" DBH						
	` Abundant	r ☐ Prese	ent D	Absent	☐ Not Applicable			
		□ Fiese	511L <u>/</u>	7 Vnociii	☐ Not Applicable			
	Standing dead to	rees (potential for cav	ities and perches	(;				

☐ Abundant		☐ Absent	□ Not Applicable				
Tree cavities in trunks or limbs							
Abundant	□ Present	☐ Absent	☐ Not Applicable				
Small mammal burrows:							
Abundant	□ Present	Absent	☐ Not Applicable				
Dense herbaceous cover (v	voles, small mammals, ar	mphibians & reptiles)					
Abundant	□ Present	Absent	☐ Not Applicable				
Large woody debris on the	ground (small mammals	, mink, amphibians & rep	tiles)				
Abundant	□ Present	Absent	□ Not Applicable				
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)				
Abundant	□ Present	Absent	□ Not Applicable				
Overhanging branches at o duck, mink, raccoon)	r within 1 m above the w	ater's surface (turtles, sr	nakes, frogs, wading birds, wood				
Abundant	□ Present	Absent	□ Not Applicable				
Rock piles, crevices, or holl	low logs suitable for vario	ous mammals (otter, min	k, porcupine, racoon):				
Abundant	□ Present	Absent	□ Not Applicable				
Live or dead tall standing voosprey, kingfisher, flycatche		near water offering goo	d visibility of open water (e.g.,				
Abundant	□ Present	Absent	□ Not Applicable				
Other Important Habitat C	Characteristics:						
Underwater banks of fine si	ilt and/or clay (beaver, m	uskrat, otter)					
Abundant	□ Present	Absent	□ Not Applicable				
Undercut or overhanging ba	anks (small mammals, m	ink, weasels, turtles)					
Abundant	□ Present	Absent	□ Not Applicable				
Vertical sandy banks (bank swallow, kingfisher)							
Abundant	Present		Not Applicable				
Mud flats							
Abundant	□ Present	Absent	□ Not Applicable				
Exposed areas of well-drain	Exposed areas of well-drained, sandy soil suitable for turtle nesting						
☐ Abundant	□ Present	Absent	□ Not Applicable				

#### Wildlife Dens/Nests (if observed)

	Turtle nesting sites						
	☐ Abundant	Present		□ Not Applicable			
	Bank swallow colony(ies)						
	Abundant	Present		□ Not Applicable			
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron			
	Den(s) present of	☐ Otter	Mink	Beaver			
	Other nests or dens (identif	y species):					
IV.	Connectivity with Adjoini	ng Natural Habitats					
	☐ No direct connections t	o adjacent areas of wildl	ife habitat (little d	connectivity function)			
	Limited number of con	nectors to adjacent areas	of habitat (som	ewhat important for connectivity function)			
	Riverbank is embedded connectivity function)	d in a large area of natur	al habitat with ur	nimpeded connection to other habitats (high			
٧.	Rare Species and MNHES	SP Core Area Habitat Do	esignation				
	☐ Core Area 1 ☐ Core	Area 2	a 3 🔲 Core	Area 4			
	$oxed{\boxtimes}$ Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat						
	State-listed species habitat (including species with known overlapping Priority Habitat):						
	Matted Spike-sedge, Must	tard White, Spine-crowne	ed Clubtail, Wap	ato, Wood Turtle			
	Rare species direct observa	ations during current field	l surveys:				
VI.	Incidental Direct Wildlife	Observations					
	Deer tracks						
	Raccoon tracks						
	Goldfinch						

General Electric Housatonic Rest of River Form RB-1: Riverbank Habitat Inventory Form	
VII. Habitat Degradation (identify specific location on b	ank segment if applicable)
☐ Evidence of significant levels of dumping	
Evidence of significant erosion or sedimentation pr	oblems
○ Occurrence of invasive plants:     Common buckthorn, Morrow's honeysuckle, bitters	sweet, Japanese knotweed, purple loosestrife
Evidence of other human disturbance; describe:	
VIII.Restoration Opportunities	
☑ Presence of potential restoration resources (e.g., be bank stabilization or hibernacula, plant propagation sour Coarse woody debris, large trees, root wads, cobbe.	
○ Other restoration opportunities:	
R: Grade bank/Coir matting	
L: Grade bank/Coir matting	
Invasive species control	
Revegetation	

Bank 32 Plant Species List				
<u>Left bank</u>	Right bank			
boxelder   Acer negundo   tree	boxelder   Acer negundo   tree			
black mustard   Brassica nigra   herb	nodding beggar-ticks   Bidens cernua   herb			
wild cucumber   Echinocystis lobata   vine	Asian bittersweet   Celastrus orbiculatus   vine/liana   *			
Japanese knotweed   Fallopia japonica   herb   *	Morrow's honeysuckle   Lonicera morrowii   shrub   *			
common water-purslane   Ludwigia palustris   herb	pale smartweed   Persicaria lapathifolia   herb			
purple loosestrife   Lythrum salicaria   herb   *	common buckthorn   Rhamnus cathartica   herb   *			
Allegheny monkeyflower   Mimulus ringens   herb	river grape   Vitis riparia   vine/liana			
pale smartweed   Persicaria lapathifolia   herb				
eastern cottonwood   Populus deltoides   tree				
blue vervain   Verbena hastata   herb				

<sup>\*</sup>Invasive species

#### **Bank 32 Floodplain Plant Species**

red maple	Acer rubrum	T
silver maple	Acer saccharinum	T
American linden	Tilia americana	T
boxelder	Acer negundo	T
devil's beggar-tick	Bidens frondosa	Н
Pennsylvania smartweed	Persicaria pensylvanica	Н
moneywort	Lysimachia nummularia	Н
Canada clearweed	Pilea pumila	Н
water-starwort	Callitriche palustris	Н



Bank 32 Stations 225-227. 200-ft mild right bend.

Photos of Bank 32 Area. August 10, 2022 Right bank above Station 226 Right bank near Station 226 Right bank (left) to left bank (right) looking upstream Left bank from Station 225 area Left bank from Station 225 area

I.	Gene	eral Informat	tion					
		atonic ROR R						
	Site Name and Evaluation Segment  Bank 33: Stations 232-236. 400-ft stretch with last 200' entering and following halfway around sharp left bend.							
Location/Physical Description								
	8/10/2 Date(s		(s) and Data Colle	ction			_	
	Weath	ner Conditions	During Site Visit					
	AECC	DM	-					
	Field	Staff Performir	ng Evaluation				Date this form was completed	
II.	Site I	Description						
A.	Bank	Characteriza	tion					
Phy	/sical l	Dimensions (	(ft):					
Ler	ngth: 4	.00'	Width: 80'	Bank Height: R:6	6 ft L7	ft	Slope: R 30% L 90%	
Sec	diment	t / Substrate	composition:					
% 5	Sand 4	10	% Silt 40	% Clay		% Gra	avel/cobble 20	
% E	Boulde	er/Bedrock		% Organic matter				
Bar	Bank stability / Observed erosional conditions: Right bank is stable, with low BEHI except high between 235-236. Right bank NBS is low except extreme between 235-236. Left bank is an eroding sandy bank with slumping silt at base. Left bank BEHI is very high and NBS is low.							
В.	Borde	ring Habitat <sup>-</sup>	Types					
We	tland				Upland			
		ransitional flo	oodplain forest		$\boxtimes$	Northe Fores	ern Hardwoods-Hemlock-White Pine t	
	□ F	ligh terrace f	loodplain forest			Rich r	nesic forest	
	☐ R	Red maple sw	vamp			Red C	Oak-Sugar Maple Transition Forest	
	⊠ V	ernal pool			$\boxtimes$	Agricu	ıltural fields	
		Black ash-red wamp	maple-tamaracl	k calcareous seepage	$\boxtimes$	Cultur	ral grassland	
		Deep emerge	nt marsh			Succe	essional northern hardwoods	
	□ s	Shallow emer	gent marsh			Spruc	e-fir-northern hardwood forest	
		Shrub swamp	1			Devel	oped/disturbed cover types	
	⊠ V	Vet meadow				Other		
		Other						
Not	es.							

С. пу	drology							
Stream	n gradient:	⊠ Low Grad	lient [	☐ Mid-Gradi	ent	☐ Hig	h-Gradient	
Degree	e of overbank fl	ooding potential	/ floodplain	connectivity				
	High-flow cha	nnels present in	adjacent flo	odplain	$\boxtimes$	Topographic b	reaks present	in the riverbank
	Channel is de	eply incised		ately incised		☐ Somewh	at incised	☐ Not incised
Degree	e of Water leve	I fluctuation (esti	mated vertic	al difference	fron	n mean low wat	er to):	
Bankfu	ıll indicators: R	4ft L3ft	Top of bank	k slope: 6-7 ft	t	Floodplain s	urface: 6-7 ft	
Field-D	Derived Evidend	ce of Hydrologic	Conditions					
$\boxtimes$	Clear natural	line impressed o	n bank		$\boxtimes$	Changes in ch	aracter of soil	
	Bed and bank	(S				Water staining		
	Shelving					Vegetation ma	tted down, ber	nt or absent
	Wrack lines (I	litter and debris)			$\boxtimes$	Change in plant community		
	Scour and/or	Deposition				Destruction of	terrestrial veg	etation
	Line of mud o	or silt on tree trun	ks/venetatio	ın		Debris stuck o	n overhanging	tree limbs
			ino, vogetatie	11	ш	Dodino otaon o	3 3	
	Other							
□ Field-□						202110 014011 0		
Field-E						Recent change		
Field-D	Derived Evidend		age/Discharç					
	Derived Evidend Scour line Depositional I	ce of Bankfull Sta	age/Discharç			Recent change	es to river bend	
	Derived Evidend Scour line Depositional I	ce of Bankfull Sta bench (active ch	age/Discharç			Recent change Undercuts	es to river bend	
	Derived Evidence Scour line Depositional l Depositional l Depositional i	ce of Bankfull Sta bench (active ch	age/Discharo			Recent change Undercuts Staining of roc	es to river bend ks	ds/meanders
	Derived Evidence Scour line Depositional I Depositional I Depositional i Middle bench	ce of Bankfull Sta bench (active ch point bar	age/Discharg annel)			Recent change Undercuts Staining of roc Top of point ba	es to river bend ks	ds/meanders
	Derived Evidence Scour line Depositional I Depositional i Depositional i Middle bench Break in slope	ce of Bankfull State bench (active chapoint bar island for braided river	age/Discharg annel) rs plain break)	ge Water		Recent change Undercuts Staining of roc Top of point ba	es to river bend ks	ds/meanders
	Derived Evidence Scour line Depositional I Depositional i Depositional i Middle bench Break in slope	ce of Bankfull Sta bench (active cha point bar island for braided river e of banks (flood	age/Discharg annel) rs plain break)	ge Water		Recent change Undercuts Staining of roc Top of point ba	es to river bend ks	ds/meanders
	Derived Evidence Scour line Depositional I Depositional i Depositional i Middle bench Break in slope Other ventory (Plant C	ce of Bankfull Sta bench (active cha point bar island for braided river e of banks (flood	age/Discharg annel) rs plain break)	ge Water		Recent change Undercuts Staining of roc Top of point ba	es to river bend ks	ds/meanders
D. Inv	Derived Evidence Scour line Depositional I Depositional i Depositional i Middle bench Break in slope Other ventory (Plant C	ce of Bankfull Sta bench (active cha point bar island for braided river e of banks (flood	age/Dischard annel) rs plain break)	ge Water		Recent change Undercuts Staining of roc Top of point ba Lower limits in	es to river bend ks	ds/meanders
D. Inv	Derived Evidence Scour line Depositional I Depositional I Depositional I Middle bench Break in slope Other Ventory (Plant Co	ce of Bankfull State bench (active chapoint bar disland for braided river e of banks (flood	age/Dischargannel)  s plain break)	ge Water  5  Overhanging Veg		Recent change Undercuts Staining of roc Top of point be Lower limits in	es to river bend ks ars perennial veg	ds/meanders

Left Bank

	Total % Cover:	60	20		90				
		Bank Vegetation Overhanging V		•	Riparian Vegetation				
	Percent Cover of	ging Stream Vege	etation by Stra	ta					
	10 Trees (> 20')	30 Shrubs (< 20')	20 Woody vines	0 Mosses	60 Herbaceous				
Da	,	,	•	MOSSES	Herbaceous				
Per	cent Cover of Rip	parian Vegetation by	Siraia						
	50	50	30	0 Mosses	80				
	Trees (> 20')	Shrubs (< 20')	Woody vines		Herbaceous	_			
Baı	nk and overhangi strata. or anv an	ng vegetation plant lis	st (species that collant species: "*"	omprise 10% ( designates a d	or more of the vegetative cover i dominant plant species for the st	n each rata):			
	•	·	nam species,	Strata	Plant Species	rata):			
	Strata Flan	t Species		Silaia	Flant Species				
					the vegetative cover in each stra	ata, or any			
	amount of an inv	asive plant species;	"^" designates a d	dominant plan	t species for the strata):				
					_				
Stra	ata: T=Tree, S=S	Shrub, L=Liana (vine),	H=Herb (Include	es grasses, he	rbs, pterophytes [ferns], lichens,	, woody			
	seedlings, and m	nosses)							
Not	es: See attached	d tables for plant spec	cies lists.						
III.	Important Habit	at Features							
	Wildlife Food								
	Important wotlan	ud/aquatic food plants							
	important wettan	id/aquatic food plants							
	☐ Abundant	⊠ Prese	ent [	Absent	☐ Not Applicable				
	Important upland	d food plants (hard ma	ast and fruit/berry	producers)					
	☐ Abundant	⊠ Prese	ont [	Absent	□ Not Applicable				
	Abundani	△ Fiese	ent [	_ Absent	☐ Not Applicable				
	Cover/Perches/Basking/Denning/Nesting Habitat								
	Trees (live or de	ad) > 30" DBH							
	□ Abundant	<b>⊠</b> D••••	ont <sup>[</sup>	7 Absent	□ Not Applicable				
	☐ Abundant	⊠ Prese	zııı _	Absent	☐ Not Applicable				
	Standing dead tr	ees (potential for cav	ities and perches	s)					

Abundant		☐ Absent	☐ Not Applicable
Tree cavities in trunks or lin	nbs		
☐ Abundant	□ Present	Absent	☐ Not Applicable
Small mammal burrows:			
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable
Dense herbaceous cover (v	voles, small mammals, ar	mphibians & reptiles)	
	☐ Present	☐ Absent	☐ Not Applicable
Large woody debris on the	ground (small mammals,	mink, amphibians & rep	tiles)
Abundant	□ Present	☐ Absent	☐ Not Applicable
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)
Abundant	□ Present	☐ Absent	□ Not Applicable
Overhanging branches at o duck, mink, raccoon)	r within 1 m above the w	ater's surface (turtles, sn	akes, frogs, wading birds, wood
☐ Abundant	□ Present	Absent	□ Not Applicable
Rock piles, crevices, or holl	ow logs suitable for vario	ous mammals (otter, min	k, porcupine, racoon):
Abundant	□ Present	Absent	☐ Not Applicable
Live or dead tall standing veosprey, kingfisher, flycatche		near water offering good	d visibility of open water (e.g.,
☐ Abundant	□ Present	Absent	☐ Not Applicable
Other Important Habitat C	characteristics:		
Underwater banks of fine si	ilt and/or clay (beaver, m	uskrat, otter)	
	Present	Absent	☐ Not Applicable
Undercut or overhanging ba	anks (small mammals, m	ink, weasels, turtles)	
Abundant	□ Present	Absent	☐ Not Applicable
Vertical sandy banks (bank	swallow, kingfisher)		
	Present	☐ Absent ☐	Not Applicable
Mud flats			
Abundant	□ Present	Absent	☐ Not Applicable
Exposed areas of well-drain	ned, sandy soil suitable fo	or turtle nesting	
☐ Abundant	□ Present	Absent	□ Not Applicable

#### Wildlife Dens/Nests (if observed)

	Turtle nesting sites			
	☐ Abundant	☐ Present		☐ Not Applicable
	Bank swallow colony(ies)	Bank swallow colony(ies)		
	Abundant	□ Present	☐ Absent	☐ Not Applicable
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron
	Den(s) present of	☐ Otter	☐ Mink	☐ Beaver
	Other nests or dens (identif	y species):		
IV.	Connectivity with Adjoini	ng Natural Habitats		
	☐ No direct connections t	to adjacent areas of wildl	life habitat (little	connectivity function)
	Limited number of con	nectors to adjacent areas	s of habitat (som	newhat important for connectivity function)
	☐ Riverbank is embedded connectivity function)	d in a large area of natur	al habitat with u	nimpeded connection to other habitats (high
٧.	Rare Species and MNHES	SP Core Area Habitat D	esignation	
	☐ Core Area 1 ☐ Core	Area 2	ea 3 🔲 Core	Area 4
	□ Federally listed threate habitat): Northern long-ear		cies habitat (incl	uding species with known overlapping
	State-listed species have a	abitat (including species	with known over	lapping Priority Habitat):
	Matted Spike-sedge, Mus	tard White, Spine-crowne	ed Clubtail, Wap	ato, Wood Turtle
	Rare species direct observa	ations during current field	d surveys:	
VI.	Incidental Direct Wildlife	Observations		
	Painted turtle			
	Bull frog			
	Green frog			
	Song sparrow			
	Rohin			

Catbird						
Veery						
Bank swallow nesting cavities						
VII. Habitat Degradation (identify specific location on b	ank segment if applicable)					
☐ Evidence of significant levels of dumping						
Evidence of significant erosion or sedimentation pr	oblems					
○ Occurrence of invasive plants:     Bittersweet, Morrow's honeysuckle, yellow iris, gard	Occurrence of invasive plants: Bittersweet, Morrow's honeysuckle, yellow iris, garlic mustard, Japanese knotweed, forget-me-not					
Evidence of other human disturbance; describe:						
VIII.Restoration Opportunities						
□ Presence of potential restoration resources (e.g., beank stabilization or hibernacula, plant propagation sour Coarse woody debris, large trees, root wads, cobbined.)						
R: Log or rock vanes; Grade bank/Coir matting						
L: Log or rock vanes; Compartmentalized fill						
Invasive species control						
Revegetation						

Bank 33 Plan	t Species List
<u>Left</u>	<u>Right</u>
garlic-mustard   Alliaria petiolata   herb   *	silver maple   Acer saccharinum   tree
swamp milkweed   Asclepias incarnata   herb	nodding beggar-ticks   Bidens cernua   herb
nodding beggar-ticks   Bidens cernua   herb	lurid sedge   Carex lurida   herb
black mustard   Brassica nigra   herb	Asian bittersweet   Celastrus orbiculatus   vine/liana   *
wild cucumber   Echinocystis lobata   vine	Japanese knotweed   Fallopia japonica   herb   *
eastern willow-herb   Epilobium coloratum   herb	yellow iris   Iris pseudacorus   herb   *
field horsetail   Equisetum arvense   herb	Morrow's honeysuckle   Lonicera morrowii   shrub   *
climbing bindweed   Fallopia scandens   vine	ostrich fern   Matteuccia struthiopteris   herb
yellow-seeded false pimpernel   Lindernia dubia   herb	pale smartweed   Persicaria lapathifolia   herb
ostrich fern   Matteuccia struthiopteris   herb	green-headed coneflower   Rudbeckia laciniata   herb
water forget-me-not   Myosotis scorpioides   herb   *	blue vervain   Verbena hastata   herb
common evening primrose   Oenothera biennis   herb	Boxelder   Acer negundo   tree
ditch-stonecrop   Penthorum sedoides   herb	
red raspberry   Rubus idaeus   shrub	
common soapwort   Saponaria officinalis   herb	
common mullein   Verbascum thapsus   herb	
blue vervain   Verbena hastata   herb	
rough cocklebur   Xanthium strumarium   herb	


<sup>\*</sup>Invasive species

#### **Bank 33 Floodplain Plant Species**

	• •	
reed canary grass	Phalaris arundinacea	Н
green-headed coneflower	Rudbeckia laciniata	Н
stinging nettle	Urtica dioica	Н
hemp dogbane (Indina hemp)	Apocynum cannabinum	Н
bedstraw	Galium aparine	Н
purple-stemmed aster	Symphyotrichum puniceum	Н
common dandelion	Taraxacum officinale	Н
boxelder	Acer negundo	T
silky dogwood	Cornus amomum	S
Canada goldenrod	Solidago canadensis	Н
river grape	Vitis riparia	V




Bank 33 Stations 232-236. 400-ft stretch with last 200' entering and following halfway around sharp left bend.



Left bank (left) to right bank looking downstream from Station 233

Left bank (left) to right bank looking downstream from Station 233











	Housatonic ROR R						
	Bank 34: Stations 243-247. 400-ft stretch around right to left bend. POTW discharge along right bank.  Location/Physical Description						
	8/10/22 Date(s) of Site Visit	t(s) and Data Collection	on				
	Weather Condition AECOM	s During Site Visit					
	Field Staff Perform	ing Evaluation			Date this form was completed		
II.	Site Description	ı					
A.	Bank Characteriza	ation					
Phy	sical Dimensions	(ft):					
Len	gth 400'	Width 80'	Bank Height R 6-7'	L 7-8	3' Slope: R 60% L 90-100%		
Sec	liment / Substrate	composition:					
% S	Sand 50	% Silt 50	% Clay		% Gravel/cobble		
% E	Boulder/Bedrock	%	Organic matter				
		ved erosional cond	itions: HI and low NBS on both	hank	ze. Thalwag in contar		
L	our banks relative	ary stable. Trigit be	THE AND TOWN INDO ON DOLL	i Daiin	os. Thalweg in center.		
В.	Bordering Habitat	Types					
We	tland		U	pland			
		loodplain forest			Northern Hardwoods-Hemlock-White Pine Forest		
	☐ High terrace	floodplain forest			Rich mesic forest		
	☐ Red maple s	wamp			Red Oak-Sugar Maple Transition Forest		
	☐ Vernal pool			$\boxtimes$	Agricultural fields		
	Black ash-red swamp	d maple-tamarack o	calcareous seepage		Cultural grassland		
	□ Deep emerge	ent marsh			Successional northern hardwoods		
	Shallow eme	rgent marsh			Spruce-fir-northern hardwood forest		
	☐ Shrub swam	0			Developed/disturbed cover types		
	☐ Wet meadow	,			Other		
	Other						
Not	es:						

C.	Hydrology								
Stre	eam gradien	t: 🛛 Low Gra	dient	☐ Mid-Grad	lient		☐ High-Gradient		
De	Degree of overbank flooding potential / floodplain connectivity								
	☐ High-flo	ow channels present i	n adjacent f	loodplain	$\boxtimes$	Topo	graphic breaks preser	nt in the riverbank	
	☐ Channe	el is deeply incised	☐ Mode	rately incised		$\boxtimes$	Somewhat incised	☐ Not incised	
De	Degree of Water level fluctuation (estimated vertical difference from mean low water to):								
	Bankfull ind	dicators: R 3ft L ft	Top of ba	nk slope: 4ft		Flo	odplain surface: 4ft		
Fie	d-Derived E	vidence of Hydrologic	Conditions						
		atural line impressed	on bank		$\boxtimes$	Chan	ges in character of so	il	
	⊠ Bed and	d banks				Wate	r staining		
	Shelvin	ng				Vege	tation matted down, b	ent or absent	
	☐ Wrack	lines (litter and debris	)		$\boxtimes$	Change in plant community			
	Scour a	and/or Deposition				Destr	ruction of terrestrial ve	getation	
	☐ Line of	mud or silt on tree tru	nks/vegetat	ion		Debri	s stuck on overhangir	ng tree limbs	
	Other_								
Fie	d-Derived E	vidence of Bankfull S	tage/Discha	rge Water					
		ine				Rece	nt changes to river be	nds/meanders	
	□ Deposit     □ Depos	tional bench (active c	hannel)		$\boxtimes$	Unde	rcuts		
	□ Deposit     □ Depos	tional point bar				☐ Staining of rocks			
	☐ Deposit	tional island			$\boxtimes$	Top of point bars			
	☐ Middle	bench for braided rive	ers		$\boxtimes$	Lower limits in perennial vegetation			
	□ Break in	n slope of banks (floo	dplain break	κ)					
	Other_								
D.	Inventory (F	Plant Community)							
Rig	ht Bank								
	Total % Co	ver: $\frac{70}{8}$	on	60 Overhanging Ve	getati	on .	90 Riparian Vegetation	<u> </u>	
	Percent Co	over of Bank and Ove		0 0	•				
	40 Trees (> 20')	70 Shrubs (< 20')	30 Woo	dy vines	0 Mo	sses	70 Herbaceous		

Left Bank

	Total % Cover:	80 Bank Vegetation	30 Overhangin	g Vegetation	90 Riparian Vegetation	
	Percent Cover of Bank and Overhan		-	-		
	20	50	30	0	70	
	Trees (> 20')	Shrubs (< 20')	Woody vines	Mosses	Herbaceous	
Per	cent Cover of Rip	parian Vegetation by	Strata			
	30	50 Shrubs (< 20')	30	0 Mosses	60	
	Trees (> 20')	Shrubs (< 20')	Woody vines	Mosses	Herbaceous	
Baı					or more of the vegetative cover in each dominant plant species for the strata):	
	•	t Species	nam opodioo,	Strata	Plant Species	
	Strata Flati	ii opecies		Silaia	Fiant Species	
	Piparian vegetat	ion plant list (species	that comprise 10	0% or more of	the vegetative cover in each strata, or an	
	amount of an inv	asive plant species; '	"*" designates a	dominant plan	t species for the strata):	
				=		
Stra	ata: T=Tree.S=S	hrub. L=Liana (vine).	H=Herb (Include	es grasses, he	erbs, pterophytes [ferns], lichens, woody	
	seedlings, and m		(			
Not	es: See attached	tables for plant spec	ies lists.			
	lmmantant Habit	et Factures				
ш.	Important Habit	at reatures				
	Wildlife Food					
	Important wetlan	d/aquatic food plants				
	☐ Abundant	⊠ Prese	ent [	Absent	☐ Not Applicable	
		I food plants (hard ma	- ast and fruit/berry	r producers)		
		. ,	_			
	☐ Abundant	⊠ Prese	ent L	Absent	☐ Not Applicable	
	Cover/Perches/	Basking/Denning/No	esting Habitat			
	Trees (live or de	ad) > 30" DBH				
	☐ Abundant	☐ Prese	ent 🛭	Absent	☐ Not Applicable	
	_	ence (notantial for a	ا مادان	.,	• •	
	Standing dead tr	ees (potential for cav	ities and perches	3)		

Abundant		☐ Absent	☐ Not Applicable
Tree cavities in trunks or lin	nbs		
☐ Abundant	□ Present	Absent	☐ Not Applicable
Small mammal burrows:			
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable
Dense herbaceous cover (v	voles, small mammals, ar	mphibians & reptiles)	
☐ Abundant	□ Present	Absent	☐ Not Applicable
Large woody debris on the	ground (small mammals,	mink, amphibians & rep	tiles)
Abundant	□ Present	☐ Absent	☐ Not Applicable
Rocks, crevices, logs, tree	roots or hummocks at wa	ater's edge or under wate	er's surface (turtles, snakes, frogs)
Abundant	□ Present	☐ Absent	□ Not Applicable
Overhanging branches at o duck, mink, raccoon)	r within 1 m above the w	ater's surface (turtles, sn	akes, frogs, wading birds, wood
☐ Abundant	□ Present	Absent	□ Not Applicable
Rock piles, crevices, or holl	low logs suitable for vario	ous mammals (otter, min	k, porcupine, racoon):
Abundant	□ Present	Absent	□ Not Applicable
Live or dead tall standing veosprey, kingfisher, flycatche		near water offering good	d visibility of open water (e.g.,
Abundant	□ Present	Absent	☐ Not Applicable
Other Important Habitat C	Characteristics:		
Underwater banks of fine si	ilt and/or clay (beaver, m	uskrat, otter)	
Abundant	□ Present	☐ Absent	☐ Not Applicable
Undercut or overhanging ba	anks (small mammals, m	ink, weasels, turtles)	
Abundant	□ Present	☐ Absent	☐ Not Applicable
Vertical sandy banks (bank	swallow, kingfisher)		
☐ Abundant	Present		Not Applicable
Mud flats			
☐ Abundant	□ Present	☐ Absent	□ Not Applicable
Exposed areas of well-drain	ned, sandy soil suitable fo	or turtle nesting	
Abundant	Present		□ Not Applicable

#### Wildlife Dens/Nests (if observed)

	Turtle nesting sites						
	Abundant	☐ Present		□ Not Applicable			
	Bank swallow colony(ies)						
	Abundant	☐ Present		☐ Not Applicable			
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron			
	Den(s) present of	☐ Otter	Mink	☐ Beaver			
	Other nests or dens (identif	y species):					
IV.	Connectivity with Adjoining Natural Habitats						
	☐ No direct connections to adjacent areas of wildlife habitat (little connectivity function)						
	☐ Limited number of connectors to adjacent areas of habitat (somewhat important for connectivity function)						
	Riverbank is embedded in a large area of natural habitat with unimpeded connection to other habitats (high connectivity function)						
٧.							
	☐ Core Area 1 ☐ Core Area 2 ☐ Core Area 3 ☐ Core Area 4						
	Federally listed threatened or endangered species habitat (including species with known overlapping habitat): Northern long-eared bat						
	State-listed species habitat (including species with known overlapping Priority Habitat):						
	Matted Spike-sedge, Mustard White, Rapids Clubtail, Spine-crowned Clubtail, Wapato, Wood Turtle						
	Rare species direct observa	ations during current field	surveys:				
VI.	Incidental Direct Wildlife Observations						
	Spotted sandpiper						

	Electric Housatonic Rest of River 3-1: Riverbank Habitat Inventory Form					
VII. Hab	itat Degradation (identify specific location on b	ank segment if applicable)				
	☐ Evidence of significant levels of dumping					
	Evidence of significant erosion or sedimentation problems					
	○ Occurrence of invasive plants:     Japanese knotweed, bishop's goutweed					
VIII.Res	toration Opportunities					
bank	Presence of potential restoration resources (e.g., boulders, large trees or woody debris, root wad material fo bank stabilization or hibernacula, plant propagation source material). Identify specific items:  Coarse woody debris, large trees, root wads					
$\boxtimes$	Other restoration opportunities:					
R:	Grade bank/Coir matting; Log or rock vanes; Veg	etated riprap				
L:	Grade bank/Coir matting; Root wads					
Inv	rasive species control					
Re	vegetation					

Bank 34 Plant Species List					
<u>Left bank</u>	Right bank				
silver maple   Acer saccharinum   tree	American linden   Tilia americana   tree				
bishop's goutweed   Aegopodium podagraria   herb   *	American elm   Ulmus americana   tree				
Japanese knotweed   Fallopia japonica   herb   *	Japanese knotweed   Fallopia japonica   herb   *				
nodding beggar-ticks   Bidens cernua   herb	Boxelder   Acer negundo   tree				
pale smartweed   Persicaria lapathifolia   herb					
blue vervain   Verbena hastata   herb					

<sup>\*</sup>Invasive species

#### **Bank 34 Floodplain Plant Species**

boxelder	Acer negundo	T
silky dogwood	Cornus amomum	S
Canada goldenrod	Solidago canadensis	Н
bedstraw	Galium aparine	Н
river grape	Vitis riparia	V


(B-76)



Bank 34: Station 243-247. 400-ft stretch around right to left bend. POTW discharge along right bank.


Photos of Bank 34 Area. August 16, 2022. Left bank upstream of Station 243 Right bank just above Station 245 Right bank Right bank near Station 245 Right bank near Station 244; POTW discharge to rear Right bank near Station 244







# Appendix C Backwater Habitat Inventory Forms



Site	BW-1 Name and Backwater Number			
180	Name and Backwater Number			
	0 linear feet south of Holmes Road, between Housatonic Riv (\$84)	er and C	anoe Meadows Sanctua	ary, (-73.2367 42.4249
Loc	ation/Physical Description			
	7/2022			
	e(s) of Site Visit(s) and Data Collection			
	stly cloudy, 70°F ather Conditions During Site Visit			
	ullivan/Stearns		7/	17/2023
Fiel	d Staff Performing Evaluation		D	ate this form was completed
II. Sit	e Description			
A. Bac	kwater Characterization			
Physica	al Dimensions (ft): Length 760' Width	190'	Depth	Area <u>1.4-2 acres</u>
Sedime	ent / Substrate composition: % Sand% Silt _	<u>10</u>	%Organic <u>90</u>	Other
Bank s	ability / Observed erosional conditions: Bank appear	ed stabl	e during site visits.	
			<del>9</del>	
D. Dor	Haring Habitat Turas			
<b>В.</b> ВОГ	dering Habitat Types			
Wetlan	d	Upland		
$\boxtimes$	Transitional floodplain forest		Northern Hardwoods Forest	-Hemlock-White Pine
	High terrace floodplain forest		Rich mesic forest	
	Red maple swamp		Red Oak-Sugar Map	le Transition Forest
	Vernal pool		Agricultural fields	
	Black ash-red maple-tamarack calcareous seepage swamp		Cultural grassland	
	Deep emergent marsh		Successional northe	rn hardwoods
$\boxtimes$	Shallow emergent marsh		Spruce-fir-northern h	ardwood forest
	Shrub swamp		Developed/disturbed	cover types
$\boxtimes$	Wet meadow		Other	
	Other			
Notes:	Backwater area characteristics change with water leve	els. Floo	ded portion at elevation	on 957'.

C.	Hydrology								
Stre	eam gradier Backwater:	nt adjacent to	☐ Low Gradient		Mid-Grad	lient	☐ High-Gradient		
Bac	kwater Hyd	Irologic Connect	ivity to River						
	☐ Perma	nently connected	d (Baseflow hydrology is	s conne	ected to a	and controlled by	the river)		
		ttently exposed	connection (Surface cor	nnectio	n is dry fo	or a short time ar	nnually)		
Des	scribe any o	ther inlets, outle	ts, and other surface wa	ater inp	outs to ba	ckwater: At the	time of the initial survey the		
	majority of area with no surface water. Northern end has standing water. Connected to river by a swale that extends northeast off the main channel of the river. This swale is 3' wide at the bottom elevation. Secondary outlet to Sackett Brook to the southeast.								
Wa	ter level fluc	ctuation:							
Fiel	d-Derived E	Evidence of Hydr	ologic Conditions						
	☐ Clear r	natural line impre	essed on bank		☐ Cha	anges in characte	er of soil		
	☐ Bed an	nd banks			⊠ Wa	ater staining			
	Shelvir	ng							
		lines (litter and o	debris)		⊠ Cha	anges in plant co	ommunity		
	⊠ Scour a	and/or Depositio	n		☐ Destruction of terrestrial vegetation				
		mud or silt on tr	ee trunks/vegetation		□ Debris stuck on overhanging tree limbs				
	Other_								
D.	Inventory of	of Aquatic Plant (	Community						
	% Cover:	Overall Ag	1-5 uatic Vegetation Floating -Le	5 eaved C	over Fm		-50_ ees		
		(species that co	•	the ve	getative c	over in each stra	ita, or any amount of an		
	Strata	Plant Species			Strata	Plant Specie	S		
	RV	Yellow pond-lily	y (Nuphar variegata)		S	Silky dogwoo	od (Cornus amomum)		
	RV	Pickerelweed (	Pontederia cordata)		Н	Sensitive fer	n (Onoclea sensibilis)		
	RV	Water-chestnu	t (Trapa natans)		T	Silver maple	(Acer saccharinum)		
	Н	Rice cut grass	(Leersia oryzoides)		Н		r-reed (Sparganium		
	<u>H</u>	Nodding bur m	arigold ( <i>Bidens cernua</i> )		<u>H</u>		earthumb ( <i>Persicaria</i>		
	<u>H</u>	Woolgrass (Sc	irpus cyperinus)		<u>H</u>	sagittata) Water horeh	ound ( <i>Lycopus uniflorus</i> )		

	<u>H</u>	Canadian wood nettle (Laportea canadensis)	<u>H</u>	False nettle (Boehmeria cylindrica)
	<u>H</u>	Dotted smartweed (Persicaria punctata)	H	Moneywort (Lysimachia nummularia)
	<u>H</u>	Marsh bedstraw (Galium palustre)		
Str	ata: AL=Ald	al, AM=Aquatic Moss, RV=Rooted Vascula	ar. FV=Floatin	g Vascular, PE=Persistent Emergent.
		ersistent Emergent		
III.	Important	Habitat Features		
	Wildlife Fo	<u>ood</u>		
	Important a	equatic food plants (smartweeds, pondweed	ds, wild rice, b	pulrush, wild celery)
	☐ Abunda	ant 🛛 Present [	Absent	□ Not Applicable
	Cover/Per	ches/Basking/Denning/Nesting Habitat		
	Trees (live)	> 30" DBH adjacent to backwater		
	☐ Abunda	ant 🛛 Present [	Absent	☐ Not Applicable
	Standing de	ead trees in or adjacent to backwater (pote	ential for caviti	es and perches)
	☐ Abunda	ant 🛛 Present [	Absent	□ Not Applicable
	Tree cavitie	es in trunks or limbs in or adjacent to backv	vater	
	☐ Abunda	ant 🛛 Present [	Absent	□ Not Applicable
	Small mam	mal burrows on banks of backwater		
	☐ Abunda	ant 🛛 Present [	Absent	□ Not Applicable
	Dense herb	paceous cover on banks of backwater (vole	es, small mam	mals, amphibians & reptiles)
	⊠ Abunda	ant Present [	Absent	□ Not Applicable
	Large wood	dy debris in contact with the water (fish & to	urtles)	
	☐ Abunda	ant 🛛 Present [	Absent	□ Not Applicable
	Rocks, cre	vices, logs, tree roots or hummocks under	water's surfac	e (turtles, snakes, frogs)
	☐ Abunda	ant 🛛 Present [	Absent	□ Not Applicable
		vices, fallen logs, overhanging branches or akes, frogs, wading birds, wood duck, mink		t, or within 1 m above the water's surface

IV.

	Abundant	$\boxtimes$	Present		Absent			Not Applicable
	or dead tall standing verey, kingfisher, flycatche			ater (	or offerin	g good	visibility	of open water (e.g., bald eagle,
	Abundant	$\boxtimes$	Present		Absent			Not Applicable
<u>Oth</u>	er Important Habitat C	hara	acteristics					
Flat	rocks and logs on bank	s or	within exposed porti	ons	of the ba	ckwater	(cover	and basking for herpetofauna)
	Abundant	$\boxtimes$	Present		Absent			Not Applicable
Und	erwater banks of fine si	t an	d/or clay (beaver, mu	uskra	at, otter)			
	Abundant	$\boxtimes$	Present		Absent			Not Applicable
Und	ercut or overhanging ba	nks	(small mammals, mi	nk, v	weasels,	turtles)		
	Abundant	$\boxtimes$	Present		Absent			Not Applicable
Muc	l flats							
	Abundant	$\boxtimes$	Present		Absent			Not Applicable
Wild	llife Dens/Nests (if ob	serv	ed)					
Ban	k swallow colony(ies) (a	djac	ent to backwater)					
	Abundant		Present	$\boxtimes$	Absent		Not App	olicable
Turt	le nesting sites							
	Abundant		Present	$\boxtimes$	Absent			Not Applicable
Nes	t(s) present of		Bald Eagle		Osprey		Great B	lue Heron
Den	(s) present of		Otter		Mink		Beaver	
Othe	er nests or dens (identify	spe	ecies): <u>Muskrat</u>					
<u>Em</u>	ergent Wetlands withir	Ва	ckwater (if Applical	ble)				
	ergent wetland vegetations, green heron, black-cr							son (American bittern, wood n, coot, etc.)
Floc	oded > 5 cm				$\boxtimes$	Present		Absent
Floc	oded > 25 cm (pied-billed	d gre	ebe)		$\boxtimes$	Present		Absent
Con	nectivity with Adjoining	ng N	atural Habitats					
	No direct connections to	adi	acent areas of wildlif	e ha	hitat (no	connec	tivity fur	action)

	☐ Backwater has a limited number of connectors to adjacent areas of habitat (somewhat important for connectivity function)							
	Backwater is embedded in a large area of natural habitat with unimpeded connection between backwater and other habitats (high connectivity function)							
٧.	Rare Species and MNHESP Core Area Habitat Designation							
	□ Core Area 1    □ Core Area 2    □ Core Area 4    □ Core Area 4							
	Federally listed threatened or endangered species habitat (including species with known overlapping habitat):							
	State-listed species habitat (including species with known overlapping Priority Habitat):							
	Rare species direct observations during current field surveys (list):							
VI.	Incidental Direct Wildlife Observations							
	Blue jay							
_	Yellow warbler							
	Yellow warbler							
	Yellow warbler  American goldfinch  Pickerel frog							
	Yellow warbler  American goldfinch							
	Yellow warbler  American goldfinch  Pickerel frog							
	Yellow warbler  American goldfinch  Pickerel frog							
	Yellow warbler  American goldfinch  Pickerel frog							
	Yellow warbler  American goldfinch  Pickerel frog							
	Yellow warbler  American goldfinch  Pickerel frog  Green frog							

□ Presence of invasive plants (e.g., purple loosestrife, <i>Phragmites</i> , Eurasian water-milfoil) or aquatic animals (e.g., zebra mussels, Asian clams); identify and estimate approximate percent coverage of invasive plants; identify invasive aquatic animals: <a href="Water chestnut patch 30'x30">Water chestnut patch 30'x30</a>
Evidence of other human disturbance; describe:
VIII.Restoration Opportunities
☑ Presence of potential restoration resources (e.g., boulders, large downed trees or woody debris, plant propagation source material). Identify specific items:
☐ Other restoration opportunities:
Notes:
IX. General Water Chemistry  Date: 5/9/2023  Record data at multiple locations at least three times during the growing season.
Location 1 (describe): -73.236427 42.425612 WGS84, northeast portion
pH <u>7.63</u> Temperature <u>20.7°C</u> SpC Conductivity <u>458.3</u> Dissolved Oxygen_105%, <u>9.44 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) <u>3 mg/L</u>
Location 2 (describe): -73.236846 42.425428 WGS84, northwest portion
pH <u>7.5</u> Temperature _20.3°C SpC Conductivity _477.0 Dissolved Oxygen 89.4%, 7.93 mg/L Chlorophyll-a (or other measure of photosynthetic organisms) 1 mg/L
Location 3 (describe): -73.236332 42.424562 WGS84, southern portion
pH <u>7.51</u> Temperature <u>19.1°C</u> Sp Conductivity <u>487.8</u>

Dissolved Oxygen\_87.0%, 7.88 mg/L Chlorophyll-a (or other measure of photosynthetic organisms) 1 mg/L Date:6/6/2023 Record data at multiple locations at least three times during the growing season. Location 1 (describe): -73.236427 42.425612 WGS84, northeast portion pH 7.53 Temperature 17.9°C Sp Conductivity 514. Dissolved Oxygen 129.7%, 12.27 mg/L Chlorophyll-a (or other measure of photosynthetic organisms) 1 mg/L Location 2 (describe): \_-73.236846 42.425428 WGS84, northwest portion\_ pH 7.71 Temperature 18.0°C Sp Conductivity 504. Dissolved Oxygen 137%, 12.94mg/L Chlorophyll-a (or other measure of photosynthetic organisms) 0.7 mg/L Location 3 (describe): -73.236332 42.424562 WGS84, southern portion pH 7.81 Temperature 18.8°C Sp Conductivity 513. Dissolved Oxygen 145.9%, 13.55mg/L Chlorophyll-a (or other measure of photosynthetic organisms) 1 mg/L\_ Date:6/14/2023 Record data at multiple locations at least three times during the growing season. Location 1 (describe): -73.236427 42.425612 WGS84, northeast portion pH 7.64 Temperature 15.4°C Sp Conductivity 618\_ Dissolved Oxygen 99.4%, 9.85 mg/L Chlorophyll-a (or other measure of photosynthetic organisms) 0.6 mg/L Location 2 (describe): \_-73.236846 42.425428 WGS84, northwest portion pH 7.72 Temperature 15.7°C Sp Conductivity 518\_ Dissolved Oxygen 106.4%, 10.55 mg/L Chlorophyll-a (or other measure of photosynthetic organisms) 1.2 mg/L

Location 3 (describe): -73.236332 42.424562 WGS84, southern portion\_

pH <u>7.91</u>\_\_\_

Temperature 15.5°C

Sp Conductivity <u>522</u>

Dissolved Oxygen 120.6%, 11.98 mg/L

Chlorophyll-a (or other measure of photosynthetic organisms) 2.0 mg/L

#### **5A BW-1 Representative Photographs**

Flooded conditions with aquatic floating leaved plants

#### Northern end (left) and southern end (right) of BW-1 during period of low water in 2022



Central portion of BW-1 during period of low water dominated by reed-canary grass in 2022





Southern end of BW-1 flooded in 2023



I.	Ge	neral Information		
		BW-2		
		Name and Backwater Number		
		linear feet east Shetland Dr. and Palomino Dr. intersection (-73 ation/Physical Description	.240	4 42.4192 WGS84)
		8/2022		
		e(s) of Site Visit(s) and Data Collection		
		nny, 70°F ather Conditions During Site Visit		
		ullivan/Stearns		7/18/2023
	Fiel	d Staff Performing Evaluation		Date this form was completed
II.	Site	e Description		
A.	Bac	kwater Characterization		
Phy	/sica	al Dimensions (ft): Length <u>460'</u> Width <u>26-4</u>	<u>4'</u>	DepthArea <u>0.38 acres</u>
Sec	dime	ent / Substrate composition: % Sand% Silt	10	%Organic <u>90</u> Other
Bar	nk st	ability / Observed erosional conditions: Bank appeared	stab	le, large areas are colonized by
Ja	oane	ese knotweed ( <i>Fallopia japonica</i> )		
B.	Bord	dering Habitat Types		
We	tland	d Up	land	
		Transitional floodplain forest		Northern Hardwoods-Hemlock-White Pine Forest
		High terrace floodplain forest		Rich mesic forest
		Red maple swamp		Red Oak-Sugar Maple Transition Forest
		Vernal pool		Agricultural fields
	Ш	Black ash-red maple-tamarack calcareous seepage swamp		Cultural grassland
		Deep emergent marsh		Successional northern hardwoods
	$\boxtimes$	Shallow emergent marsh		Spruce-fir-northern hardwood forest
		Shrub swamp		Developed/disturbed cover types
	$\boxtimes$	Wet meadow		Other
		Other		
Not	es:	during the 8/18/2022 survey	-	resent (approx. 60' x 20'), depth to 6" observed

C. Hydrology	/							
, ,,	ent adjacent to	☐ Low Gradient	⊠ Mid	Alid-Gradient High-Gradient				
Backwater Hy	ydrologic Connec	tivity to River						
☐ Permanently connected (Baseflow hydrology is connected to and controlled by the river)								
Describe any	other inlets, outle	ets, and other surface v	vater inputs	to back	kwater: One outlet to river with small channel			
In middle app	orox. 1' wide with	variable bank height u	o to 12-14".					
Water level fl	uctuation:							
Field-Derived	Evidence of Hyd	Irologic Conditions						
☐ Clear	natural line impr	essed on bank		] Chan	nges in character of soil			
☐ Bed a	and banks			] Wate	er staining			
☐ Shelv	ving			☐ Vegetation matted down, bent or absent				
⊠ Wrac	k lines (litter and	debris)		□ Changes in plant community				
⊠ Scou	r and/or Deposition	on		☐ Destruction of terrestrial vegetation				
Line	of mud or silt on t	ree trunks/vegetation		☐ Debris stuck on overhanging tree limbs				
☐ Other	r							
D. Inventory	of Aquatic Plant	Community						
% Cover:	0-5	0 quatic Vegetation Floating	Looyed Cover		-75 0			
Plant List invasive	ts (species that co		of the vegeta	tive cov	ver in each strata, or any amount of an			
Strata	Plant Species			rata	Plant Species			
<u>H</u>	Onoclea sens	ibilis	<u>H</u>		Bidens cernua			
<u>H</u>	Lysimachia nu	ummularia	<u>H</u>		Ludwiga palustris			
<u>H</u>	Galium palust	re	<u>H</u>		Iris pseudacorus			
<u>H</u>	Boehmeria cy	lindrica	<u>H</u>		Rudbeckia laciniata			
<u>H</u>	Asclepias inca	arnata	<u>H</u>		Bidens frondosa			
<u>H</u>	Persicaria sag	gittata	<u>H</u>		Veronica catenata			
<u>H</u>	Sagittaria latif	olia	<u>H</u>		Leersia oryzoides			

	<u>H</u>	Penthorum sec	loides		<u>H</u>	Myoso	tis scorpioides
	<u>H</u>	Persicaria sp.			Н	Cuscut	ta gronovii
	<u>H</u>	Physostegia vii	rginiana		Н	Eleoch	aris sp.
	<u>H</u>	Verbena hasta	nta		<u>H</u>	Eutroci	hium maculatum
	<u>H</u>	Carex lupulina			Н	Mimulu	us ringens
	<u>H</u>	Lythrum salical	ria		SA	Myriop	hyllum spicatum
	SA	<i>Hydrilla</i> sp.					
Str		al, AM=Aquatic ersistent Emerge	ent		FV=Floating		r, PE=Persistent Emergent,
	Important	Habitat Faatura					
11.	Wildlife Fo	Habitat Feature	:5				
			ts (smartweeds, pondwe	ode	wild rice, but	lruch wi	ld celery)
	_		_	eus,		iiusii, wi	_
	Abunda		⊠ Present	Ш	Absent		☐ Not Applicable
		_	enning/Nesting Habitat	<u>.</u>			
	Trees (live)	> 30" DBH adja	cent to backwater				
	Abunda	ant	☐ Present		Absent		□ Not Applicable
	Standing de	ead trees in or a	djacent to backwater (po	tenti	al for cavities	and pe	rches)
	Abunda	ant	☐ Present		Absent		□ Not Applicable
	Tree cavitie	es in trunks or lin	nbs in or adjacent to back	kwat	er		
	Abunda	ant	□ Present		Absent		□ Not Applicable
	Small mam	mal burrows on	banks of backwater				
	Abunda	ant	□ Present		Absent		□ Not Applicable
	Dense herb	aceous cover o	n banks of backwater (vo	les,	small mamm	als, amp	phibians & reptiles)
		ant	Present		Absent		□ Not Applicable
	Large wood	dy debris in cont	act with the water (fish &	turtl	es)		

Abund	ant	☑ Present		Absent			Not Applicable
Rocks, cre	vices, logs, tree roo	ots or hummocks under	wat	er's surface	(turtles	s, sna	kes, frogs)
Abund	ant	☑ Present		Absent			Not Applicable
		overhanging branches og birds, wood duck, min			or with	in 1 n	n above the water's surface
Abund	ant [2	☑ Present		Absent			Not Applicable
	d tall standing veg gfisher, flycatchers		iter c	or offering go	ood visi	ibility	of open water (e.g., bald eagle
Abund	ant	Present		Absent			Not Applicable
Other Imp	ortant Habitat Cha	aracteristics					
Flat rocks	and logs on banks	or within exposed portion	ons c	of the backw	ater (c	over a	and basking for herpetofauna)
Abund	ant [	✓ Present		Absent			Not Applicable
Underwate	Underwater banks of fine silt and/or clay (beaver, muskrat, otter)						
Abund	ant [	Present		Absent			Not Applicable
Undercut of	r overhanging banl	ks (small mammals, mi	nk, w	veasels, turt	les)		
Abund	ant	☑ Present		Absent			Not Applicable
Mud flats							
Abund	ant	☑ Present		Absent			Not Applicable
Wildlife De	ens/Nests (if obse	erved)					
Bank swall	ow colony(ies) (adj	acent to backwater)					
Abunda	ant [	Present		Absent	☐ No	t App	olicable
Turtle nest	ing sites						
Abunda	ant [	Present		Absent			Not Applicable
Nest(s) pre	esent of	Bald Eagle		Osprey	☐ Gr	eat B	lue Heron
Den(s) pre	sent of	Otter		Mink	□ Ве	aver	
Other nests	s or dens (identify s	species): _Muskrat					

#### **Emergent Wetlands within Backwater (if Applicable)**

Emergent wetland vegetation at least seasonally flooded during the growing season (American bittern, wood duck, green heron, black-crowned night heron, rails [sora, king, Virginia], moorhen, coot, etc.)

	Flooded > 5 cm	□ Present	Absent					
	Flooded > 25 cm (pied-billed grebe)	□ Present	☐ Absent					
IV.	Connectivity with Adjoining Natural Habitats							
	☐ No direct connections to adjacent areas of wildlife h	nabitat (no connectivity	function)					
	☐ Backwater has a limited number of connectors to a connectivity function)	djacent areas of habitat	(somewhat important for					
	□ Backwater is embedded in a large area of natural habitat with unimpeded connection between backwater and other habitats (high connectivity function)							
٧.	Rare Species and MNHESP Core Area Habitat Designation							
	☐ Core Area 1 ☐ Core Area 2 ☐ Core Area 3	Core Area 4						
	Federally listed threatened or endangered species habitat):	habitat (including spec	ies with known overlapping					
	☐ State-listed species habitat (including species with	known overlapping Prid	ority Habitat):					
	Rare species direct observations during current field sur	rveys (list):						
VI.	Incidental Direct Wildlife Observations							
	Gray catbird							
	Snapping turtle							
	American crow							
	Racoon							
	Cedar waxwing							
	Great blue heron							

VII. Habitat Degradation (identify specific location within backwater if applicable)
☐ Evidence of significant levels of dumping
Evidence of significant erosion or sedimentation problems
□ Presence of invasive plants (e.g., purple loosestrife, <i>Phragmites</i> , Eurasian water-milfoil) or aquatic animals (e.g., zebra mussels, Asian clams); identify and estimate approximate percent coverage of invasive plants; identify invasive aquatic animals: <a href="mailto:Japanese knotweed present">Japanese knotweed present</a>
Evidence of other human disturbance; describe:
VIII.Restoration Opportunities
Presence of potential restoration resources (e.g., boulders, large downed trees or woody debris, plant propagation source material). Identify specific items:
Other restoration opportunities:
Notes:
IX. General Water Chemistry
Date: 5/9/2023 Record data at multiple locations at least three times during the growing season.
Location 1 (describe): -73.240243 42.419407 WGS84, northern portion
pH <u>7.72</u> Temperature <u>11.6°C</u> Sp Conductivity <u>432.8</u> Dissolved Oxygen <u>134%, 14.62 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) <u>1 mg/L</u>
Location 2 (describe): -73.240455 42.419242 WGS84, middle (western) portion
pH <u>7.3</u> Temperature <u>11.1°C</u> Sp Conductivity <u>404.0</u> Dissolved Oxygen <u>74.3%</u> , <u>8.15 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) <u>1.8 mg/L</u>

Location 3 (describe): -73.240421 42.419043 WGS84, southern portion
pH <u>8.28</u> Temperature <u>16.0°C</u> Sp Conductivity <u>413.3</u> Dissolved Oxygen <u>158.6%, 15.46 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) <u>1 mg/L</u>
Date:6/6/2023 Record data at multiple locations at least three times during the growing season.
Location 1 (describe): -73.240243 42.419407 WGS84, northern portion
pH <u>7.32</u> Temperature <u>14.8°C</u> Sp Conductivity 561 Dissolved Oxygen <u>67.2%, 6.78 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) <u>1.6 mg/L</u>
Location 2 (describe): -73.240455 42.419242 WGS84, middle (western) portion
pH <u>7.40</u> Temperature <u>12.1°C</u> Sp Conductivity <u>476.5</u> Dissolved Oxygen <u>96.9%, 10.40 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) <u>4.7 mg/L</u>
Location 3 (describe): <u>-73.240421 42.419043 WGS84</u> , southern portion
pH <u>7.55</u> Temperature <u>16.8°C</u> Sp Conductivity <u>431.3</u> . Dissolved Oxygen <u>71.8%, 6.95 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) <u>2.5 mg/L</u>
Date:6/14/2023 Record data at multiple locations at least three times during the growing season.
Location 1 (describe): -73.240243 42.419407 WGS84, northern portion
pH <u>7.47</u> Temperature <u>14.8°C</u> Sp Conductivity <u>499</u> Dissolved Oxygen <u>81.2%, 8.25 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) <u>1.5 mg/L</u>
Location 2 (describe): -73.240455 42.419242 WGS84, middle (western) portion
pH <u>7.24</u>

Temperature 12.8°C

Sp Conductivity 509

Dissolved Oxygen\_79.4%, 8.32 mg/L

Chlorophyll-a (or other measure of photosynthetic organisms) 1.9 mg/L\_

Location 3 (describe): -73.240421 42.419043 WGS84, southern portion

pH 7.50\_

Temperature 19.0°C

Sp Conductivity 449

Dissolved Oxygen 60.0%, 5.53 mg/L


Chlorophyll-a (or other measure of photosynthetic organisms) 2.0 mg/L\_

#### **5A BW-2 Representative Photographs**

Shallowly flooded central portions of BW-2 with aquatic submergent plants still visible in 2022



Dry south-central portion of BW-2 with aquatic emergent, submergent and floating-leaved aquatic still visible in 2022 vegetation



Dry northern portion of BW-2 with aquatic emergent vegetation still visible in 2022



Flooded central portions of BW-2 in 2023



I.	General Information										
	5A-BW-3										
	Site Name and Backwater Number										
	0 feet southeast of Pinto Dr. and Palomino Dr. intersection (-73.2415 42.4175 WGS84) cation/Physical Description										
	8/18/2022										
	Date(s) of Site Visit(s) and Data Collection										
	Sunny, breezy, 73°F Weather Conditions During Site Visit										
	O'Sullivan/Stearns	7/18/2023									
	Field Staff Performing Evaluation	Date this form was completed									
II.	Site Description										
A.	Backwater Characterization										
Ph	ysical Dimensions (ft): Length 235' Width _	<u>24-38'</u> DepthArea <u>0.16 acres</u>									
Se	diment / Substrate composition: % Sand% Silt	t <u>10</u> %Organic <u>90</u> Other									
Baı	nk stability / Observed erosional conditions: Banks a	appear stable									
В	Bordering Habitat Types										
		Unland									
vve	etland	Upland									
	☐ Transitional floodplain forest	Northern Hardwoods-Hemlock-White Pine Forest									
	☐ High terrace floodplain forest	☐ Rich mesic forest									
	☐ Red maple swamp	☐ Red Oak-Sugar Maple Transition Forest									
	☐ Vernal pool	☐ Agricultural fields									
	☐ Black ash-red maple-tamarack calcareous seepage swamp	☐ Cultural grassland									
	☐ Deep emergent marsh	☐ Successional northern hardwoods									
	Shallow emergent marsh	☐ Spruce-fir-northern hardwood forest									
	☐ Shrub swamp	☐ Developed/disturbed cover types									
		Other									
	☐ Other										
No	tes:										

C.	Hydrology							
Stream gradient adjacent to Low Gradient   Backwater:					Mid-Grad	dient	☐ High-Gradient	
Bac	Backwater Hydrologic Connectivity to River							
	☐ Permar	nently connected	d (Baseflow hydrology	/ is conne	cted to a	and controlled by	the river)	
	☐ Intermittently exposed connection (Surface connection is dry for a short time annually)							
Des	Describe any other inlets, outlets, and other surface water inputs to backwater:  One outlet to the river.							
Mea	Measurements at contour 954 outlet channel is 65' long x 2' wide at low flow, 3-4' wide at contour 954							
Wat	er level fluc	tuation:						
Fiel	d-Derived E	vidence of Hydr	ologic Conditions					
	☐ Clear natural line impressed on bank			⊠ Ch	anges in charact	er of soil		
	☐ Bed and banks			⊠ Wa	ater staining			
	<ul><li>☐ Shelving</li><li>☐ Wrack lines (litter and debris)</li><li>☐ Scour and/or Deposition</li></ul>			☐ Vegetation matted down, bent or absent				
					□ Changes in plant community			
					☐ Destruction of terrestrial vegetation			
				☐ De	bris stuck on ove	erhanging tree limbs		
☐ Other								
D. Inventory of Aquatic Plant Community								
	% Cover: 1-5 0			0	96-100	6-15		
Overall Aquatic Vegetation Floating -Leaved Cover E  Plant Lists (species that comprise 10% or more of the vegetative co invasive plant species; "*" designates a dominant plant species for t				Trees ata, or any amount of an				
	Strata	Plant Species	J		Strata	Plant Specie	es	
	SA	Callitriche palu	stris		Н	Mentha cana	adensis	
	H	Persicaria hydi	ropiperoides		Н	Sium suave		
	Н	Phalaris arund	inacea		<u>H</u>	Leersia oryz	oides	
		Cornus amomu	um		<u>H</u>	Myosotis sco	orpioides	
	Н	Penthorum sec	doides		<u>H</u>	Laportea ca	nadensis	
	<u>H</u>	Boehmeria cyli	indrica		Н	Lythrum sali	caria	
	<u>H</u>	Cuscuta grono	vii		<u>H</u>	Galium palu	stre	

	<u>H</u>	Iris pseudacoru	JS		V	Vitis ripari	ia .	
	<u>H</u>	Impatiens cape	ensis		<u>H</u>	Persicaria	punctata	
	<u>H</u>	Epilobium color	ratum		<u>H</u>	Bidens ce	rnua	
	<u>H</u>	Persicaria sp.			Н	Rudbeckia	a laciniata	
	<u>T</u>	Platanus occide	entalis		T	Acer sacc	harinum	
					T	Acer negu	ındo	
Str	Strata: AL=Algal, AM=Aquatic Moss, RV=Rooted Vascular, FV=Floating Vascular, PE=Persistent Emergent, NE=Non-persistent Emergent							
	и⊏=иоп-ре	rsisterit Emerge	er it					
III.	Important I	Habitat Feature	<u></u> 9S					
	Wildlife Food							
	Important aquatic food plants (smartweeds, pondweeds, wild rice, bulrush, wild celery)							
		ant	☐ Present		Absent		Not Applicable	
	Cover/Perches/Basking/Denning/Nesting Habitat							
	Trees (live) > 30" DBH adjacent to backwater							
	☐ Abunda	ant	□ Present		Absent		Not Applicable	
	Standing dead trees in or adjacent to backwater (potential for cavities and perches)							
	☐ Abunda	ant	□ Present		Absent		Not Applicable	
	Tree cavities in trunks or limbs in or adjacent to backwater							
	☐ Abunda	ant	□ Present		Absent		Not Applicable	
	Small mam	mal burrows on	banks of backwater					
	Abunda	ant	☐ Present	$\boxtimes$	Absent		Not Applicable	
	Dense herb	aceous cover o	n banks of backwater (v	oles,	small mamm	nals, amphib	oians & reptiles)	
		ant	☐ Present		Absent		Not Applicable	
	Large wood	ly debris in conta	act with the water (fish	& turtle	es)			
	☐ Abunda	ant	□ Present		Absent		Not Applicable	

Rocks, crevices, logs, tree roots or hummocks under water's surface (turtles, snakes, frogs)							
☐ Abundant	□ Present	☐ Absent	☐ No	ot Applicable			
Rocks, crevices, fallen logs, overhanging branches or hummocks at, or within 1 m above the water's surface (turtles, snakes, frogs, wading birds, wood duck, mink, raccoon)							
Abundant	□ Present	☐ Absent	☐ No	t Applicable			
Live or dead tall standing vegetation overhanging water or offering good visibility of open water (e.g., bald eagle, osprey, kingfisher, flycatchers, cedar waxwings)							
Abundant	□ Present	Absent	☐ No	t Applicable			
Other Important Habitat C	<u>Characteristics</u>						
Flat rocks and logs on banks or within exposed portions of the backwater (cover and basking for herpetofauna)							
☐ Abundant	□ Present	☐ Absent	☐ No	t Applicable			
Underwater banks of fine si	ilt and/or clay (beaver, m	uskrat, otter)					
☐ Abundant	☐ Present		☐ No	t Applicable			
Undercut or overhanging ba	anks (small mammals, m	ink, weasels, tur	tles)				
☐ Abundant	□ Present	☐ Absent	☐ No	t Applicable			
Mud flats							
Abundant	□ Present	☐ Absent	☐ No	t Applicable			
Wildlife Dens/Nests (if observed)							
Bank swallow colony(ies) (a	adjacent to backwater)						
Abundant	☐ Present		☐ Not Applica	able			
Turtle nesting sites							
Abundant	Present		☐ No	t Applicable			
Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue	Heron			
Den(s) present of	☐ Otter	Mink	☐ Beaver				
Other nests or dens (identify	y species):						
Emergent Wetlands within Backwater (if Applicable)							
Emergent wetland vegetation at least seasonally flooded during the growing season (American bittern, wood duck, green heron, black-crowned night heron, rails [sora, king, Virginia], moorhen, coot, etc.)							
Flooded > 5 cm		⊠ Pre	esent	☐ Absent			

	Flooded > 25 cm (pied-billed grebe)	□ Present	☐ Absent					
IV.	. Connectivity with Adjoining Natural Habitats							
	☐ No direct connections to adjacent areas of wildlife habitat (no connectivity function)							
	☐ Backwater has a limited number of connectors to adjacent areas of habitat (somewhat important for connectivity function)							
	$\boxtimes$ Backwater is embedded in a large area of natural habitat with unimpeded connection between backwater and other habitats (high connectivity function)							
٧.	Rare Species and MNHESP Core Area Habitat Designation							
	☐ Core Area 1 ☐ Core Area 2 ☐ Core Area 3	☐ Core Area 4						
	Federally listed threatened or endangered species habitat (including species with known overlapping habitat):							
	State-listed species habitat (including species with known overlapping Priority Habitat):							
	Rare species direct observations during current field surveys (list):							
VI.	/I. Incidental Direct Wildlife Observations							
	Green frog	33331						
	King Fisher							
		•						

5

VII. Habitat Degradation (identify specific location within backwater if applicable)

Evidence of significant levels of dumping
Evidence of significant erosion or sedimentation problems
Presence of invasive plants (e.g., purple loosestrife, <i>Phragmites</i> , Eurasian water-milfoil) or aquatic animals (e.g., zebra mussels, Asian clams); identify and estimate approximate percent coverage of invasive plants; identify invasive aquatic animals:
Evidence of other human disturbance; describe:
VIII.Restoration Opportunities
Presence of potential restoration resources (e.g., boulders, large downed trees or woody debris, plant propagation source material). Identify specific items:
☐ Other restoration opportunities:
Notes:
IX. General Water Chemistry
Date: 5/9/2023 Record data at multiple locations at least three times during the growing season.
Location 1 (describe): <u>-73.241516 42.417558 WGS84</u>
pH <u>7.23</u> Temperature <u>22.4°C</u> Sp Conductivity <u>393.5</u> Dissolved Oxygen <u>74.5%, 6.47 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) <u>1 mg/L</u>
Location 2 (describe): <u>-73.241519 42.417449</u> WGS84
pH <u>7.32</u> Temperature <u>19.6°C</u> Sp Conductivity <u>381.2</u> Dissolved Oxygen_ <u>77.6%, 7.04 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) <u>1 mg/L</u>
Location 3 (describe): -73.241485 42.417326 WGS84

pH _ <u>7.38</u> Temperature <u>17.5°C</u> Sp Conductivity <u>412.9</u> Dissolved Oxygen <u>86.9%, 8.13 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) <u>1 mg/L</u>
Date:6/6/2023 Record data at multiple locations at least three times during the growing season.
Location 1 (describe): -73.241516 42.417558 WGS84
pH <u>7.19</u> Temperature <u>22.0°C</u> Sp Conductivity <u>439.1</u> Dissolved Oxygen <u>80.1%, 6.99 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) <u>1.9 mg/L</u>
Location 2 (describe): -73.241519 42.417449 WGS84
pH _ <u>7.47</u> Temperature _ <u>19.9°C</u> Sp Conductivity <u>469.2</u> Dissolved Oxygen_ <u>112.1%, 10.2 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) _ <u>1.5 mg/L</u>
Location 3 (describe): <u>-73.241485 42.417326 WGS84</u>
pH
Date:6/14/2023 Record data at multiple locations at least three times during the growing season.
Location 1 (describe): <u>-73.241516 42.417558 WGS84</u>
pH
Location 2 (describe): -73.241519 42.417449 WGS84
pH <u>7.6</u> Temperature <u>19.5°C</u> Sp Conductivity <u>482.7</u> Dissolved Oxygen <u>101.8%, 9.30 mg/L</u>

#### Form BW-1: Backwater Habitat Inventory

Chlorophyll-a (or other measure of photosynthetic organisms) \_1 mg/L\_\_\_\_\_

Location 3 (describe): -73.241485 42.417326 WGS84

pH \_7.81\_

Temperature 19.6°C

Sp Conductivity 465

Dissolved Oxygen\_116.6%, 10.6mg/L

Chlorophyll-a (or other measure of photosynthetic organisms) 1.1 mg/L

#### **5A BW-3 Representative Photographs**

Shallowly flooded central portions of BW-3 with aquatic submergent plants still visible in 2022



Dry outlet channel during low water in 2022




Central portion of BW-3 flooded in 2023



Flooded outlet channel during high water 2023



Central portion of BW-3 during low water in 2022



II. Site Description  A. Backwater Characterization  Physical Dimensions (ft): Length 60' Width 30' Depth  Sediment / Substrate composition: % Sand % Silt 10 % Organic 90  Bank stability / Observed erosional conditions: Banks well vegetated and appear stable  B. Bordering Habitat Types  Wetland  Upland	8/18/2022 Date this form was completed
380 feet southeast of Pinto Dr. and Palomino Dr. intersection (-73.2412 42.4176 WGS84) Location/Physical Description 8/18/2022 Date(s) of Site Visit(s) and Data Collection Sunny, breezy, 72°F Weather Conditions During Site Visit O'Sullivan/Stearns Field Staff Performing Evaluation  II. Site Description A. Backwater Characterization Physical Dimensions (ft): Length 60' Width 30' Depth Sediment / Substrate composition: % Sand % Silt 10 %Organic 90  Bank stability / Observed erosional conditions: Banks well vegetated and appear stable  B. Bordering Habitat Types  Wetland Upland  Transitional floodplain forest  Northern Hardwoo Forest	
Location/Physical Description 8/18/2022 Date(s) of Site Visit(s) and Data Collection Sunny, breezy, 72°F Weather Conditions During Site Visit O'Sullivan/Stearns Field Staff Performing Evaluation  II. Site Description  A. Backwater Characterization  Physical Dimensions (ft): Length 60' Width 30' Depth  Sediment / Substrate composition: % Sand % Silt 10 %Organic 90  Bank stability / Observed erosional conditions: Banks well vegetated and appear stable  B. Bordering Habitat Types  Wetland Upland  Transitional floodplain forest Northern Hardwoo Forest	
B/18/2022  Date(s) of Site Visit(s) and Data Collection Sunny, breezy, 72°F Weather Conditions During Site Visit O'Sullivan/Steams Field Staff Performing Evaluation  II. Site Description  A. Backwater Characterization  Physical Dimensions (ft): Length 60' Width 30' Depth Sediment / Substrate composition: % Sand % Silt 10 %Organic 90  Bank stability / Observed erosional conditions: Banks well vegetated and appear stable  B. Bordering Habitat Types  Wetland Upland  Transitional floodplain forest  Northern Hardwoo Forest	
Sunny, breezy, 72°F Weather Conditions During Site Visit O'Sullivan/Stearns Field Staff Performing Evaluation  II. Site Description  A. Backwater Characterization  Physical Dimensions (ft): Length 60' Width 30' Depth Sediment / Substrate composition: % Sand % Silt 10 %Organic 90  Bank stability / Observed erosional conditions: Banks well vegetated and appear stable  B. Bordering Habitat Types  Wetland Upland  Transitional floodplain forest  Northern Hardwoo Forest	
Weather Conditions During Site Visit O'Sullivan/Stearns Field Staff Performing Evaluation  II. Site Description  A. Backwater Characterization  Physical Dimensions (ft): Length 60' Width 30' Depth Sediment / Substrate composition: % Sand % Silt 10 %Organic 90  Bank stability / Observed erosional conditions: Banks well vegetated and appear stable  B. Bordering Habitat Types  Wetland Upland  Transitional floodplain forest  Northern Hardwoo Forest	
O'Sullivan/Stearns Field Staff Performing Evaluation  II. Site Description  A. Backwater Characterization  Physical Dimensions (ft): Length 60' Width 30' Depth  Sediment / Substrate composition: % Sand % Silt 10 % Organic90  Bank stability / Observed erosional conditions: Banks well vegetated and appear stable  B. Bordering Habitat Types  Wetland Upland  Transitional floodplain forest Northern Hardwoon Forest	
II. Site Description  A. Backwater Characterization  Physical Dimensions (ft): Length 60' Width 30' Depth  Sediment / Substrate composition: % Sand % Silt10 %Organic90  Bank stability / Observed erosional conditions: Banks well vegetated and appear stable   B. Bordering Habitat Types  Wetland  Upland  Transitional floodplain forest  Northern Hardwoo Forest	Date this form was completed
A. Backwater Characterization  Physical Dimensions (ft): Length 60' Width 30' Depth  Sediment / Substrate composition: % Sand % Silt 10 %Organic90  Bank stability / Observed erosional conditions: Banks well vegetated and appear stable   B. Bordering Habitat Types  Wetland Upland  Northern Hardwoo Forest	
Physical Dimensions (ft): Length 60' Width 30' Depth  Sediment / Substrate composition: % Sand % Silt 10	
Sediment / Substrate composition: % Sand % Silt 10 %Organic 90  Bank stability / Observed erosional conditions: Banks well vegetated and appear stable  B. Bordering Habitat Types  Wetland	
Bank stability / Observed erosional conditions:  Banks well vegetated and appear stable  B. Bordering Habitat Types  Wetland  Transitional floodplain forest  Northern Hardwoo Forest	Area <u>0.04 acres</u>
B. Bordering Habitat Types  Wetland  Transitional floodplain forest  Torest	Other
Wetland Upland  Transitional floodplain forest  Transitional floodplain forest  Transitional floodplain forest	<u>!</u>
Wetland Upland  Transitional floodplain forest  Transitional floodplain forest  Transitional floodplain forest	
Wetland Upland  Transitional floodplain forest  Transitional floodplain forest  Transitional floodplain forest	
☐ Transitional floodplain forest ☐ Northern Hardwoo Forest ☐	
I ransitional floodplain forest Forest	
☐ High terrace floodplain forest ☐ Rich mesic forest	ds-Hemlock-White Pine
☐ Red maple swamp ☐ Red Oak-Sugar Ma	aple Transition Forest
☐ Vernal pool ☐ Agricultural fields	
☐ Black ash-red maple-tamarack calcareous seepage ☐ Cultural grassland	
☐ Deep emergent marsh ☐ Successional north	nern hardwoods
	hardwood forest
☐ Shrub swamp ☐ Developed/disturbe	ed cover types
☐ Other	
Notes:	

C. Hydrology								
Stream gradient adjacent to Low Gradient   Backwater:				lient	☐ High-Gradient			
Backwater Hydrolo								
Permanent	ly connected (Baseflow	hydrology is	connected to a	and controlled by	the river)			
Describe any other	inlets, outlets, and other	r surface wate	er inputs to ba	ckwater: O	ne outlet to river			
Outlet is appro	x. 100' long and 1-2' wid	le at low flow,	6' wide at cor	tour 954				
Water level fluctuat	ion:							
Field-Derived Evide	ence of Hydrologic Cond	litions						
☐ Clear natural line impressed on bank			⊠ Cha	anges in charact	ter of soil			
☐ Bed and banks			⊠ Wa	ter staining				
<ul> <li>☐ Shelving</li> <li>☑ Wrack lines (litter and debris)</li> <li>☐ Scour and/or Deposition</li> <li>☑ Line of mud or silt on tree trunks/vegetation</li> </ul>			☐ Ve	☐ Vegetation matted down, bent or absent				
			☐ Cha	☐ Changes in plant community				
			☐ De:	☐ Destruction of terrestrial vegetation				
			☐ Del	☐ Debris stuck on overhanging tree limbs				
☐ Other								
D. Inventory of Ac	uatic Plant Community							
% Cover:	1-5 0			96-100	26-50			
Overall Aquatic Vegetation Floating -Leaving Plant Lists (species that comprise 10% or more of the vinvasive plant species; "*" designates a dominant plant		ne vegetative d	Emergent Cover cover in each strate the strate):	Trees ata, or any amount of an				
Strata Pla	ant Species		Strata	Plant Specie	es			
SA Ca	llitriche palustris		<u>H</u>	Cuscuta gro	novii			
<u>H</u>	rbena hastata		<u>H</u>	Rudbeckia la	aciniata			
<u>H</u>	rsicaria hydropiperoides	1	<u>H</u>	Iris pseudac	eorus			
<u>Н М</u> у	rosotis scorpioides		<u>H</u>	Epilobium s	0.			
H Bio	dens frondosa		<u>H</u>	Leersia oryz	roides			
<u>H</u>	patiens capensis		<u>H</u>	Cicuta macı	ulata			
<u>H</u>	sma triviale		<u>H</u>	Persicaria s	agittata			

	<u>H</u>	Bidens cernua			<u>H</u>	Lycopus	uniflorus		
	<u>H</u>	Mentha canade	ensis		<u>H</u>	Mimulus I	ringens		
	<u>H</u>	Veronica caten	ata		<u>T</u>	Acer saco	charinum		
	<u>T</u>	Acer negundo			<u>T</u>				
Str	Strata: AL=Algal, AM=Aquatic Moss, RV=Rooted Vascular, FV=Floating Vascular, PE=Persistent Emergent,								
	NE=Non-persistent Emergent								
<u> </u>	Important I	Habitat Feature	<u> </u>						
••••	Wildlife Fo								
			ts (smartweeds, pondwe	eds.	wild rice, bul	rush. wild (	celery)		
	☐ Abunda			ошо, П	Absent	. uo,a	Not Applicable		
Cover/Perches/Basking/Denning/Nesting Habitat							rtot / ipplicable		
	Trees (live) > 30" DBH adjacent to backwater								
	☐ Abunda	•	□ Present     □		Absent		Not Applicable		
	Standing dead trees in or adjacent to backwater (potential for cavities and perches)								
	☐ Abunda		□ Present		Absent		Not Applicable		
	_		nbs in or adjacent to back				ног дрисавіе		
			Present				Not Applicable		
	☐ Abunda				Absent		ног Арріісавіе		
			banks of backwater		Absort		Not Applicable		
	Abunda		☐ Present		Absent		Not Applicable		
			n banks of backwater (vo	ies,		aıs, ampnıı	• ,		
			Present	Ш.	Absent		Not Applicable		
	_		act with the water (fish &	turtl	·				
	Abunda	ınt	□ Present	Ш	Absent		Not Applicable		
	Rocks, crev	vices, logs, tree	roots or hummocks unde	r wa	ter's surface	(turtles, sn	akes, frogs)		
	Abunda	ınt	□ Present		Absent		Not Applicable		

Rocks, crevices, fallen logs, overhanging branches or hummocks at, or within 1 m above the water's surface (turtles, snakes, frogs, wading birds, wood duck, mink, raccoon)						
Abundant	□ Present	☐ Absent	☐ Not Applicable			
Live or dead tall standing voosprey, kingfisher, flycatche		ater or offering	good visibility of open water (e.g., bald eagle,			
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable			
Other Important Habitat C	Characteristics					
Flat rocks and logs on banks or within exposed portions of the backwater (cover and basking for herpetofauna)						
☐ Abundant	□ Present	☐ Absent	☐ Not Applicable			
Underwater banks of fine si	ilt and/or clay (beaver, m	uskrat, otter)				
Abundant	Present		☐ Not Applicable			
Undercut or overhanging ba	anks (small mammals, m	nink, weasels, tu	rtles)			
Abundant	□ Present	☐ Absent	☐ Not Applicable			
Mud flats						
Abundant	□ Present	☐ Absent	☐ Not Applicable			
Wildlife Dens/Nests (if ob	served)					
Bank swallow colony(ies) (a	adjacent to backwater)					
Abundant	Present		□ Not Applicable			
Turtle nesting sites						
Abundant	☐ Present		☐ Not Applicable			
Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron			
Den(s) present of	Otter	☐ Mink	Beaver			
Other nests or dens (identify species):						
Emergent Wetlands within Backwater (if Applicable)						
Emergent wetland vegetation at least seasonally flooded during the growing season (American bittern, wood duck, green heron, black-crowned night heron, rails [sora, king, Virginia], moorhen, coot, etc.)						
Flooded > 5 cm		⊠ Pr	esent			
Flooded > 25 cm (pied-bille	d grebe)	⊠ Pr	esent			

#### IV. Connectivity with Adjoining Natural Habitats

	☐ No direct connections to adjacent areas of wildlife habitat (no connectivity function)						
	☐ Backwater has a limited number of connectors to adjacent areas of habitat (somewhat important for connectivity function)						
	Backwater is embedded in a large area of natural habitat with unimpeded connection between backwater and other habitats (high connectivity function)						
٧.	Rare Species and MNHESP Core Area Habitat Designation						
	☐ Core Area 1 ☐ Core Area 2 ☐ Core Area 4						
	Federally listed threatened or endangered species habitat (including species with known overlapping habitat):						
	State-listed species habitat (including species with known overlapping Priority Habitat):						
	Rare species direct observations during current field surveys (list):						
VI.	Incidental Direct Wildlife Observations						
VI.	Incidental Direct Wildlife Observations  Green frog						
VI.							
VI.	Green frog						
VI.	Green frog  King Fisher						
VI.	Green frog  King Fisher  Gray catbird						
VI.	Green frog  King Fisher  Gray catbird						
VI.	Green frog  King Fisher  Gray catbird						
VI.	Green frog  King Fisher  Gray catbird						
VI.	Green frog  King Fisher  Gray catbird						
	Green frog  King Fisher  Gray catbird						
	Green frog  King Fisher  Gray catbird  Blue jay						

Presence of invasive plants (e.g., purple loosestrife, <i>Phragmites</i> , Eurasian water-milfoil) or aquatic animal (e.g., zebra mussels, Asian clams); identify and estimate approximate percent coverage of invasive plants;				
identify invasive aquatic animals:				
Evidence of other human disturbance; describe:				
VIII.Restoration Opportunities				
Presence of potential restoration resources (e.g., boulders, large downed trees or woody debris, plant propagation source material). Identify specific items:				
Other restoration opportunities:				
Notes:				
IX. General Water Chemistry  Date: 5/9/2023  Record data at multiple locations at least three times during the growing season.				
Location 1 (describe):73.24116 42.41762 WGS84				
pH _7.48 Temperature _17.4°C Sp Conductivity 470.7 Dissolved Oxygen_73.3%, 6.84 mg/L Chlorophyll-a (or other measure of photosynthetic organisms) _0.5 mg/L				
Location 2 (describe):73.24114 42.41765 WGS84				
pH _ <u>7.38</u> Temperature _ <u>18°C</u> Sp Conductivity _ <u>482.4</u> Dissolved Oxygen <u>58.6%, 5.48 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) <u>0.5 mg/L</u>				
Location 3 (describe): -73.24117 42.41769 WGS84				
pH <u>7.48</u> Temperature <u>17°C</u> Sp Conductivity <u>492.4</u>				

Dissolved Oxygen_73.6%, 7.04 mg/L Chlorophyll-a (or other measure of photosynthetic organisms) _0.5 mg/L
Date:6/6/2023 Record data at multiple locations at least three times during the growing season.
Location 1 (describe):73.24116 42.41762 WGS84_
pH _ <u>7.85</u> Temperature _ <u>17.9°C</u> Sp Conductivity _ <u>444.1</u> Dissolved Oxygen _ <u>139.3%, 13.37 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms)0.7 mg/L
Location 2 (describe):73.24114 42.41765 WGS84_
pH _7.76 Temperature _17.3°C Sp Conductivity 449.4 Dissolved Oxygen 119.8%, 11.50 mg/L Chlorophyll-a (or other measure of photosynthetic organisms)1 mg/L
Location 3 (describe): <u>-73.24117 42.41769 WGS84</u>
pH _7.53 Temperature _17.8°C Sp Conductivity <u>471.7</u> Dissolved Oxygen_97.3%, 9.24 mg/L Chlorophyll-a (or other measure of photosynthetic organisms)1 mg/L
Date:6/14/2023 Record data at multiple locations at least three times during the growing season.
Location 1 (describe):73.24116 42.41762 WGS84
pH
Location 2 (describe):73.24114 42.41765 WGS84_
pH <u>8.29</u> Temperature <u>17.5°C</u> Sp Conductivity <u>423.7</u> Dissolved Oxygen_148.7%, 14.17 mg/L Chlorophyll-a (or other measure of photosynthetic organisms) <u>2.2 mg/L</u>
Location 3 (describe): -73.24117 42.41769 WGS84

pH <u>7.80</u> Temperature <u>17.4°C</u> Sp Conductivity <u>462.0</u>

Dissolved Oxygen 88.0%, 8.41 mg/L

Chlorophyll-a (or other measure of photosynthetic organisms) \_\_\_\_1.7 mg/L

#### **5A BW-4 Representative Photographs**

Shallowly flooded central portions of BW-4 with aquatic submergent plants still visible in 2022



Flooded central portion of BW-4 in 2023



Dry outlet channel during low water in 2022



Flooded outlet channel during high water in 2023



I. Ge	neral Information						
	A-BW-5 ite Name and Backwater Number 300 feet northeast of Utility Dr. and Holms Road intersection (-73.2388 42.4132 WGS84) ocation/Physical Description (10/2022 ate(s) of Site Visit(s) and Data Collection loudy						
Loc							
Clo							
	ather Conditions During Site Visit				7/40/2022		
	Sullivan/Stearns Id Staff Performing Evaluation				8/2023 te this form was completed		
II. Site	e Description						
A. Bac	kwater Characterization						
Physical Dimensions (ft): Length 1,020' Width 25			DepthArea <u>1.6 acres</u>				
Sedime	ent / Substrate composition: % Sand%	% Silt15	%Orga	nic <u>85</u>	Other		
Donk a	tability / Observed erecional and disease		_				
Bank Si	tability / Observed erosional conditions:						
B. Boro	dering Habitat Types						
Wetlan	d	Upland	i				
	Transitional floodplain forest		Northern Ha	ardwoods-	Hemlock-White Pine		
	High terrace floodplain forest		Rich mesic	forest			
	Red maple swamp		Red Oak-S	ugar Maple	e Transition Forest		
	Vernal pool		Agricultural	fields			
	Black ash-red maple-tamarack calcareous seep swamp	page	Cultural gra	ssland			
	Deep emergent marsh		Succession	al northerr	n hardwoods		
	Shallow emergent marsh		Spruce-fir-r	orthern ha	ardwood forest		
	Shrub swamp		Developed/	disturbed o	cover types		
	Wet meadow		Other				
	Other	_					
Notes:	Wet meadow observed during 8/10/20	022 survey th	ough the area	a floods to	more of shallow marsh		
	Conditions at high water.						

C. Hydrology								
Stream gradient adjacent to Low Gradien Backwater:	nt 🛛 Mid-Gradi	ent High-Gradient						
Backwater Hydrologic Connectivity to River								
☐ Permanently connected (Baseflow hydrology is connected to and controlled by the river)								
☐ Intermittently exposed connection (Surfa	☐ Intermittently exposed connection (Surface connection is dry for a short time annually)							
Describe any other inlets, outlets, and other surfa	ace water inputs to bac	ckwater:						
Connects at river during high water approx. 100' Wet meadow/SEM habitats are connected. Cha								
Water level fluctuation: No surface water during								
Field-Derived Evidence of Hydrologic Conditions								
☐ Clear natural line impressed on bank	_	Changes in character of soil						
☐ Bed and banks	_	_						
_	_							
	_							
☐ Wrack lines (litter and debris)	⊠ Cha	☐ Changes in plant community						
☐ Scour and/or Deposition	☐ Des	☐ Destruction of terrestrial vegetation						
☐ Line of mud or silt on tree trunks/vegetat	tion 🗵 Deb	□ Debris stuck on overhanging tree limbs						
Other								
D. Inventory of Aquatic Plant Community								
% Cover: 0 Overall Aquatic Vegetation F	0 Floating -Leaved Cover	76-95 10.5 Emergent Cover Trees						
Plant Lists (species that comprise 10% or minvasive plant species; "*" designates a dom	ore of the vegetative co	over in each strata, or any amount of an						
Strata Plant Species	Strata	Plant Species						
NE Leersia oryzoides	NE	Onoclea sensibilis						
NE Bidens frondosa	RV	Sagittaria latifolia						
PE Acorus calamus	NE	Phalaris arundinacea						
NE Impatiens capensis	NE	Sium suave						
NE Impatiens pallida	NE	Persicaria punctata						
NE <u>Bidens cernua</u>	<u>T</u>	Acer rubrum						
T Acer saccharinum	<u>NE</u>							

Strata: AL=Algal, AM=Aquatic Moss, RV=Rooted Vascular, FV=Floating Vascular, PE=Persistent Emergent, NE=Non-persistent Emergent

III.	. Important Habitat Features					
	Wildlife Food					
	Important aquatic food plan	nts (smartweeds, pondwe	eds, wild rice, bulrush, v	vild celery)		
	☐ Abundant	□ Present	☐ Absent	☐ Not Applicable		
	Cover/Perches/Basking/D	Denning/Nesting Habita	<u>t</u>			
	Trees (live) > 30" DBH adja	acent to backwater				
	☐ Abundant	□ Present	☐ Absent	☐ Not Applicable		
	Standing dead trees in or a	djacent to backwater (po	etential for cavities and po	erches)		
	☐ Abundant	□ Present	☐ Absent	☐ Not Applicable		
	Tree cavities in trunks or lin	mbs in or adjacent to bac	kwater			
	Abundant	□ Present	☐ Absent	☐ Not Applicable		
	Small mammal burrows on	banks of backwater				
	Abundant	□ Present	☐ Absent	☐ Not Applicable		
	Dense herbaceous cover o	n banks of backwater (vo	oles, small mammals, am	nphibians & reptiles)		
		☐ Present	☐ Absent	☐ Not Applicable		
	Large woody debris in cont	act with the water (fish &	turtles)			
		Present	☐ Absent	☐ Not Applicable		
	Rocks, crevices, logs, tree	roots or hummocks unde	er water's surface (turtles	s, snakes, frogs)		
	Abundant	□ Present	☐ Absent	☐ Not Applicable		
	Rocks, crevices, fallen logs (turtles, snakes, frogs, wad			in 1 m above the water's surface		
	Abundant	□ Present	☐ Absent	☐ Not Applicable		
	Live or dead tall standing voosprey, kingfisher, flycatche		ater or offering good visi	bility of open water (e.g., bald eagle,		
	Abundant	□ Present	Absent	□ Not Applicable		

	Other Important Habitat Characteristics						
	Flat rocks and logs on banks or within exposed portions of the backwater (cover and basking for herpetofauna)						
	☐ Abundant	□ Present	☐ Absent	☐ No	t Applicable		
	Underwater banks of fine silt and/or clay (beaver, muskrat, otter)						
	t Applicable						
	Undercut or overhanging ba	anks (small mammals, m	nink, weasels, tu	rtles)			
	☐ Abundant	□ Present	☐ Absent	☐ No	t Applicable		
	Mud flats						
	☐ Abundant	□ Present	☐ Absent	☐ No	t Applicable		
	Wildlife Dens/Nests (if ob	served)					
	Bank swallow colony(ies) (a	adjacent to backwater)					
	☐ Abundant	☐ Present		☐ Not Applica	able		
	Turtle nesting sites						
	☐ Abundant	☐ Present		☐ No	t Applicable		
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue	Heron		
	Den(s) present of	Otter	Mink	Beaver			
	Other nests or dens (identify	y species):					
	Emergent Wetlands within	n Backwater (if Applica	ible)				
	Emergent wetland vegetation duck, green heron, black-cr						
	Flooded > 5 cm		☐ Pr	resent	☐ Absent		
	Flooded > 25 cm (pied-bille	d grebe)	⊠ Pr	resent	☐ Absent		
IV.	Connectivity with Adjoini	ng Natural Habitats					
	☐ No direct connections t	o adjacent areas of wildl	ife habitat (no co	onnectivity function	on)		
	☐ Backwater has a limited connectivity function)	d number of connectors t	to adjacent area	s of habitat (som	ewhat important for		
	☐ Backwater is embedded and other habitats (high con		al habitat with u	nimpeded conne	ction between backwater		

V. Rare Species and MNHESP Core Area Habitat Designation

**General Electric Housatonic Rest of River** Form BW-1: Backwater Habitat Inventory ☐ Core Area 1 ☐ Core Area 2 Federally listed threatened or endangered species habitat (including species with known overlapping habitat): State-listed species habitat (including species with known overlapping Priority Habitat): Rare species direct observations during current field surveys (list): VI. Incidental Direct Wildlife Observations Garter snake Deer tracks Blue jay Black bear – sow with cubs - tracks Tufted titmouse American gold finch Coyote tracks Green frog American toad VII. Habitat Degradation (identify specific location within backwater if applicable) Evidence of significant levels of dumping ☐ Evidence of significant erosion or sedimentation problems Presence of invasive plants (e.g., purple loosestrife, *Phragmites*, Eurasian water-milfoil) or aquatic animals

#### **VIII.Restoration Opportunities**

identify invasive aquatic animals: \_\_\_

Evidence of other human disturbance; describe:

(e.g., zebra mussels, Asian clams); identify and estimate approximate percent coverage of invasive plants;

☐ Presence of potential restoration resources (e.g., boulders, large downed trees or woody debris, plant propagation source material). Identify specific items:
☐ Other restoration opportunities:
Notes:
IX. General Water Chemistry
Date: 5/9/2023 Record data at multiple locations at least three times during the growing season.
Location 1 (describe):73.238468 42.413907 WGS84
pH7.61 Temperature17.8°C Sp Conductivity <u>585</u> Dissolved Oxygen98.4%, 9.24 mg/L Chlorophyll-a (or other measure of photosynthetic organisms) _4 mg/L
Location 2 (describe): -73.239080 42.413035 WGS84
pH _ <u>7.47</u> Temperature _ <u>17.0°C</u> Sp Conductivity <u>572</u> Dissolved Oxygen_ <u>84.8%, 8.09 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) <u>2 mg/L</u>
Location 3 (describe): -73.239820 42.412451 WGS84
pH <u>7.36</u> Temperature _ <u>19.1°C</u> Conductivity <u>603</u> Dissolved Oxygen_ <u>79.7%, 7.34 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) _ <u>2 mg/L</u>
Date:6/6/2023 Record data at multiple locations at least three times during the growing season.
Location 1 (describe):73.238468 42.413907 WGS84
pH _ <u>7.74</u>

Temperature _20.5°C Sp Conductivity <u>676</u> Dissolved Oxygen_107.5%, 9.66 mg/L Chlorophyll-a (or other measure of photosynthetic organisms)2.5 mg/L	
Location 2 (describe): -73.239080 42.413035 WGS84	
pH _ <u>7.45</u>	
Location 3 (describe): -73.239820 42.412451 WGS84	_
pH _ <u>7.49</u> Temperature <u>18.7°C</u> Conductivity <u></u>	
Date:6/14/2023 Record data at multiple locations at least three times during the growing season.	
Location 1 (describe):73.238468 42.413907 WGS84	
pH _ <u>7.88</u>	
Location 2 (describe): <u>-73.239080 42.413035 WGS84</u>	
pH	
Location 3 (describe): <u>-73.239820 42.412451 WGS84</u>	
pH7.48 Temperature18.5°C Sp Conductivity 694 Dissolved Oxygen_60.9%, 5.67 mg/L Chlorophyll-a (or other measure of photosynthetic organisms)1.2 mg/l	

#### **5A BW-5 Representative Photographs**

Dry central portions of BW-5 with aquatic emergent and submergent plants still present in 2022



Flooded outlet channel of BW-5 in 2023



Flooded southern portion of BW-5 in 2023



Dry outlet channel during low water, some aquatic emergent vegetation visible with other wetland sedges and forbs in 2022



Shallowly flooded southern portion of BW-5 With aquatic emergent vegetation



I. General Information								
5A-BW-6	5A-BW-6							
Site Name and Backwater Number								
1200 feet northwest of EPRI Facility ( -73.2396 42.404 WGS84)								
Location/Physical Description								
8/24/2022 Date(s) of Site Visit(s) and Data Collection	8/24/2022							
Sunny 75°F								
Weather Conditions During Site Visit								
O'Sullivan/Stearns		7/18/2023						
Field Staff Performing Evaluation		Date this form was completed						
II. Site Description								
A. Backwater Characterization								
Physical Dimensions (ft): Length 115' Width 1	140'	DepthArea <u>0.36 acres</u>						
Sediment / Substrate composition: % Sand % Silt _	<u>15</u>	%Organic80Other						
Bank stability / Observed erosional conditions: Banks app	near w	ell vegetated						
Dark stability / Observed erosional conditions.	pear w	eli vegetateu						
		-						
B. Bordering Habitat Types								
Wetland L	Upland							
		Northern Hardwoods-Hemlock-White Pine Forest						
☐ High terrace floodplain forest		Rich mesic forest						
☐ Red maple swamp		Red Oak-Sugar Maple Transition Forest						
☐ Vernal pool		Agricultural fields						
☐ Black ash-red maple-tamarack calcareous seepage swamp		Cultural grassland						
☐ Deep emergent marsh		Successional northern hardwoods						
☐ Shallow emergent marsh		Spruce-fir-northern hardwood forest						
☐ Shrub swamp		Developed/disturbed cover types						
Wet meadow     ■     ■ Wet meadow     ■ Meadow		Other						
Other								
Notes:								
Floodway channel feeds BW-5A-6 at high wa	ater							

C. Hydrology							
Stream gradie Backwate	ent adjacent to er:	☐ Low Gradient	⊠ N	/lid-Grad	ient	☐ High-Gradient	
Backwater Hy	drologic Connec	tivity to River					
☐ Perm	anently connecte	ed (Baseflow hydrology	is conne	cted to a	and controlled b	by the river)	
	nittently exposed	connection (Surface co	onnectior	n is dry fo	or a short time	annually)	
Describe any	other inlets, outle	ets, and other surface v	vater inpi	uts to ba	ckwater:		
Surface w	vater connection	along river is about 130	•			annel (B-73) feeds BW, area also	
-	ermittent stream.						
Water level flu	uctuation:						
Field-Derived	Evidence of Hyd	Irologic Conditions					
☐ Clear	natural line impr	essed on bank		⊠ Cha	anges in chara	cter of soil	
☐ Bed a	and banks						
☐ Shelv	ring			☐ Vegetation matted down, bent or absent			
☐ Wrac	k lines (litter and	debris)		□ Changes in plant community			
☐ Scour	<ul><li>☐ Scour and/or Deposition</li><li>☐ Line of mud or silt on tree trunks/vegetation</li></ul>			<ul><li>Destruction of terrestrial vegetation</li><li>Debris stuck on overhanging tree limbs</li></ul>			
☐ Line o							
☐ Other							
D. Inventory	of Aquatic Plant	Community					
% Cover:	0	0 quatic Vegetation Floatin		0	96-100 Emergent Cover	6-15	
	s (species that c		of the veg	etative c	over in each s	Trees trata, or any amount of an	
Strata	Plant Species			Strata	Plant Spec	cies	
<u>H</u>	Bidens cernua	9		<u>H</u>	Lythrum sa	alicaria	
<u>H</u>	Leersia oryzo	ides		<u>H</u>	Lindernia d	dubia	
<u>H</u>	Veronica cate	nata		<u>H</u>	Sagittaria	latifolia	
<u>H</u>	Persicaria lap	athifolia		<u>H</u>	Calla palus	stris	
<u>H</u>	Persicaria pur	nctata		<u>H</u>	Eleocharis	s sp.	
<u>H</u>	Urtica dioica			<u>T</u>	Acer sacci	harinum	
	0.000 0.000				7.00. 00.00.		

Strata: AL=Algal, AM=Aquatic Moss, RV=Rooted Vascular, FV=Floating Vascular, PE=Persistent Emergent, NE=Non-persistent Emergent

Important Habitat Features						
Wildlife Food						
Important aquatic food plants (smartweeds, pondweeds, wild rice, bulrush, wild celery)						
	☐ Present	☐ Absent	☐ Not Applicable			
Cover/Perches/Basking/D	enning/Nesting Habita	<u> </u>				
Trees (live) > 30" DBH adja	cent to backwater					
☐ Abundant	□ Present	Absent	☐ Not Applicable			
Standing dead trees in or a	djacent to backwater (po	tential for cavities and pe	erches)			
☐ Abundant	□ Present	Absent	☐ Not Applicable			
Tree cavities in trunks or lin	nbs in or adjacent to bac	kwater				
☐ Abundant	□ Present	Absent	☐ Not Applicable			
Small mammal burrows on	banks of backwater					
☐ Abundant	Present		☐ Not Applicable			
Dense herbaceous cover o	n banks of backwater (vo	oles, small mammals, am	phibians & reptiles)			
	Present	Absent	☐ Not Applicable			
Large woody debris in cont	act with the water (fish &	turtles)				
☐ Abundant	□ Present	Absent	☐ Not Applicable			
Rocks, crevices, logs, tree	roots or hummocks unde	r water's surface (turtles	, snakes, frogs)			
☐ Abundant	□ Present	Absent	☐ Not Applicable			
			n 1 m above the water's surface			
☐ Abundant	□ Present	Absent	☐ Not Applicable			
		ater or offering good visik	oility of open water (e.g., bald eagle,			
Abundant	□ Present	Absent	☐ Not Applicable			
	Wildlife Food  Important aquatic food plant	Wildlife Food   Important aquatic food plants (smartweeds, pondweeds)   △ Abundant Present   Cover/Perches/Basking/Denning/Nesting Habitat   Trees (live) > 30" DBH adjacent to backwater   △ Abundant Present   Standing dead trees in or adjacent to backwater (pool   △ Abundant Present   Tree cavities in trunks or limbs in or adjacent to backwater   △ Abundant Present   Small mammal burrows on banks of backwater   △ Abundant Present   Dense herbaceous cover on banks of backwater (vol   △ Abundant Present   Large woody debris in contact with the water (fish & Abundant Present   Rocks, crevices, logs, tree roots or hummocks under Abundant   △ Abundant Present   Rocks, crevices, fallen logs, overhanging branches of (turtles, snakes, frogs, wading birds, wood duck, mirror, abundant Present   Live or dead tall standing vegetation overhanging was osprey, kingfisher, flycatchers, cedar waxwings)	Wildlife Food   Important aquatic food plants (smartweeds, pondweeds, wild rice, bulrush, well had bundant			

**Other Important Habitat Characteristics** 

	Flat rocks and logs on banks or within exposed portions of the backwater (cover and basking for herpetofauna)						
	☐ Abundant	□ Present	☐ Absent	☐ Not Applicable			
	Underwater banks of fine silt and/or clay (beaver, muskrat, otter)						
☐ Abundant ☐ Present ☐ Absent ☐ Not Applicable							
	Undercut or overhanging banks (small mammals, mink, weasels, turtles)						
	☐ Abundant	□ Present	☐ Absent	☐ Not Applicable			
	Mud flats						
	☐ Abundant	□ Present	☐ Absent	☐ Not Applicable			
	Wildlife Dens/Nests (if ob	served)					
	Bank swallow colony(ies) (a	adjacent to backwater)					
	☐ Abundant	☐ Present		☐ Not Applicable			
	Turtle nesting sites						
	☐ Abundant	☐ Present		☐ Not Applicable			
	Nest(s) present of	☐ Bald Eagle	☐ Osprey	☐ Great Blue Heron			
	Den(s) present of	☐ Otter	☐ Mink	☐ Beaver			
	Other nests or dens (identif	y species):					
	Emergent Wetlands within Backwater (if Applicable)						
	Emergent wetland vegetation duck, green heron, black-co	•		growing season (American bittern, wood inia], moorhen, coot, etc.)			
	Flooded > 5 cm		⊠ Pre	esent			
	Flooded > 25 cm (pied-bille	ed grebe)	☐ Pre	esent			
IV.	Connectivity with Adjoini	ng Natural Habitats					
	☐ No direct connections t	o adjacent areas of wildl	ife habitat (no co	onnectivity function)			
	☐ Backwater has a limited connectivity function)	d number of connectors t	to adjacent areas	s of habitat (somewhat important for			
	☑ Backwater is embedded in a large area of natural habitat with unimpeded connection between backwater and other habitats (high connectivity function)						
٧.	Rare Species and MNHES	SP Core Area Habitat De	esignation				
	☐ Core Area 1 ☐ Core	Area 2 🖂 Core Are	a 3 🔲 Core	Area 4			

Federally listed threatened or endangered habitat):	species habitat (including species with known overlapping				
State-listed species habitat (including species with known overlapping Priority Habitat):					
Rare species direct observations during current	field surveys (list):				
VI. Incidental Direct Wildlife Observations					
Ruby-throated hummingbird					
American gold finch					
Osprey					
VII. Habitat Degradation (identify specific location	on within hackwater if annlicable)				
Evidence of significant levels of dumping	m within backwater in applicable)				
_					
Evidence of significant erosion or sedimenta	·				
	osestrife, <i>Phragmites</i> , Eurasian water-milfoil) or aquatic animals lestimate approximate percent coverage of invasive plants;				
⊠ Evidence of other human disturbance; descept this area	cribe: _Sewage treatment plant outfall is immediately adjacent to				

### **VIII.Restoration Opportunities**

Presence of potential restoration resources (e.g., boulders, large downed trees or woody debris, plant propagation source material). Identify specific items:
Other restoration opportunities:
Notes:
IX. General Water Chemistry
Date: 5/9/2023 Record data at multiple locations at least three times during the growing season.
Location 1 (describe):73.239622 42.404170 WGS84This location receives back flow from sewage treatment plant outfall
pH <u>8.01</u> Temperature <u>18.4°C</u> Sp Conductivity <u>478.2</u> Dissolved Oxygen <u>193.4%, 15.07 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) <u>40 mg/L</u>
Location 2 (describe):73.239462 42.404128 WGS84
pH _ <u>7.53</u> Temperature <u>25.1°C</u> Sp Conductivity <u>477.8</u> Dissolved Oxygen <u>94.6%, 7.56 mg/L</u> Chlorophyll-a (or other measure of photosynthetic organisms) <u>4 mg/L</u>
Location 3 (describe):73.239387 42.404235 WGS84
pH7.46 Temperature25.1°C Sp Conductivity472.7 Dissolved Oxygen83.2%, 6.86 mg/L Chlorophyll-a (or other measure of photosynthetic organisms) 3 mg/L

Date:6/6/2023 – no surface water present in BW-6 Record data at multiple locations at least three times during the growing season.

### **5A BW-6 Representative Photographs**

Dry central portions of BW-6 in 2022



Flooded conditions in BW-6 during 2023 inspections



Looking west across the outlet to the river 2022






## Appendix D Floodplain Habitat Inventory

- 1. Representative photographs of floodplain habitats
- 2. Form FP-1 (Blank)
- 3. Incidental Wildlife Observations During Floodplain Surveys



D-1 Representative Photographs of Floodplain Habitats



### **PHOTOGRAPHIC LOG**

Client Name:General ElectricSite Location:Housatonic River Reach 5A BRAProject No.Company, Pittsfield, MA60670015

Photo No. 1 Date: 08/02/22 Photo No. 2 Date: 08/02/22

**Description:** View NW, wet meadow / shallow emergent | **Description:** View W, shallow emergent marsh and shrub

marsh habitats. swamp habitats







Photo No. 3 Date: 08/02/22 Photo No. 4 Date: 08/02/22

Description: View S, wet meadow dominated by reed Description: View N, high-flow channel through

canary grass transitional floodplain forest





### **PHOTOGRAPHIC LOG**

Client Name: General Electric Company, Pittsfield, MA

Site Location: Housatonic River Reach 5A BRA 60670015

Photo No. 5 Date: 08/03/22 Photo No. 6 Date: 08/03/22

**Description:** View N, large standing snag with tree **Description:** 

cavities

**Description:** View N, powerline easement across floodplain with developing common reed stand





 Photo No. 7
 Date: 08/05/22
 Photo No. 8
 Date: 08/03/22

**Description:** View NE, Japanese knotweed stand growing along bank and floodplain under powerline easement

**Description:** View N, shrub swamp habitats dominated by box elder and silky dogwood (5A-VP-9)





### **PHOTOGRAPHIC LOG**

**Project No.** 60670015 Client Name: General Electric Site Location: Housatonic River Reach 5A BRA Company, Pittsfield, MA

Photo No. 9 Date: 08/05/22 **Date:** 08/16/22 Photo No. 10

**Description:** View E, transitional floodplain forest with dense cover of ostrich fern Description: View N, Canoe Meadows, West Pond open

water and emergent marsh habitats



Photo No. 11 **Date:** 08/16/22 Photo No. 12 **Date:** 08/16/22

Description: View N, wet meadow and shallow emergent Description: View N, cultural grasslands / former marsh habitats in Canoe Meadows agricultural areas in Canoe Meadows





### **PHOTOGRAPHIC LOG**

Client Name: General Electric **Project No.** 60670015 Site Location: Housatonic River Reach 5A BRA Company, Pittsfield, MA

Photo No. 13 **Date:** 08/17/22 Date: 08/16/22 Photo No. 14

Description: View NW, shallow emergent marsh and shrub swamp habitats in Canoe Meadows with common

Description: View WSW, Canoe Meadows, deep and shallow emergent marsh habitats, beaver lodge and reed stand in background common reed stand on opposite shoreline





Photo No. 15 **Date:** 08/17/22 **Date:** 08/16/22 Photo No. 16

Description: View W, Canoe Meadows open water and shallow emergent marsh habitats with former concrete constructed dam/wier

Description: View NE, Canoe Meadows approximately 5foot tall beaver dam in Sackett Brook





### **PHOTOGRAPHIC LOG**

Client Name:General ElectricSite Location:Housatonic River Reach 5A BRAProject No.Company, Pittsfield, MA60670015

 Photo No. 17
 Date: 08/16/22
 Photo No. 18
 Date: 08/17/22

Description: View NE, Canoe Meadows shallow Description: View NW, large woody debris on the ground

emergent and deep emergent marsh habitats with cavity habitat





Photo No. 19 Date: 08/17/22 Photo No. 20 Date: 08/16/22

**Description:** View NNE, transitional floodplain forest by smartweed. Deep mucky/organic soils

by Smartweed. Deep mucky/organic sons





### **PHOTOGRAPHIC LOG**

Client Name: General Electric Company, Pittsfield, MA

Site Location: Housatonic River Reach 5A BRA 60670015

Photo No. 21 Date: 08/16/22 Photo No. 22 Date: 08/08/22

**Description:** View NW, shallow emergent marsh and shrub swamp habitats in Canoe Meadows with common

reed stand in background

**Description:** View N, transitional floodplain forest, 42" dbh silver maple with knotweed stand adjacent to river





Photo No. 23 Date: 08/04/22 Photo No. 24 Date: 08/18/22

**Description:** View S, buttonbush shrub swamp and shallow emergent marsh habitats in 5A-VP-21

**Description:** View S, shallow emergent marsh and shrub swamp dominated by bur-reed, smartweed, silky dogwood and buttonbush





### **PHOTOGRAPHIC LOG**

Client Name:General ElectricSite Location:Housatonic River Reach 5A BRAProject No.Company, Pittsfield, MA60670015

Photo No. 25 Date: 08/30/22 Photo No. 26 Date: 08/18/22

**Description:** View NW, transitional floodplain forest dominated by silver maple, boxelder and goldenrods

**Description:** View S, shallow and deep emergent marshes with bur-reed, smartweed, soft-stemmed bulrush, rice cut-grass, common arrowhead





Photo No. 27 Date: 08/11/22 Photo No. 28 Date: 08/10/22

**Description:** View ESE, high terrace floodplain forest dominated by sugar maple, ash, American linden, witch-hazel and sensitive fern

**Description:** View SW, former agricultural fields / cultural grasslands





### **PHOTOGRAPHIC LOG**

**Project No.** 60670015 Client Name: General Electric Site Location: Housatonic River Reach 5A BRA Company, Pittsfield, MA

Photo No. 29 **Date:** 04/30/19 Date: 08/24/22 Photo No. 30

Description: View NNW, cattail marsh / deep emergent

marsh habitats

**Description:** View S, high-flow channel through transitional floodplain forest. Drains 5A-VP-71, 72 & 73 View S, into the Housatonic River





Photo No. 31 **Date:** 09/15/22 Photo No. 32 **Date:** 08/31/22

**Description:** View N, shrub swamp in 5A-VP-77. Dominated by buttonbush, black willow, winterberry,

smartweeds, royal fern.

Description: View SE, agricultural fields





### **PHOTOGRAPHIC LOG**

Client Name:General ElectricSite Location:Housatonic River Reach 5A BRAProject No.Company, Pittsfield, MA60670015

Photo No. 33 Date: 08/25/22 Photo No. 34 Date: 08/24/23

**Description:** View S, 7.8-foot dbh (24.4-foot cir) eastern **Description:** View E, trans

cottonwood

**Description:** View E, transitional floodplain forest with silver maple, boxelder and American sycamore tree canopy





Photo No. 35 Date: 08/25/22 Photo No. 36 Date: 09/15/22

**Description:** View N, 6.7-foot dbh silver maple

Description: View W, former gravel pit, developing transitional floodplain forest with eastern cottonwood, American sycamore, American elm, Morrow's

honeysuckle and moneywort





### **PHOTOGRAPHIC LOG**

Client Name: General Electric Company, Pittsfield, MA

Site Location: Housatonic River Reach 5A BRA 60670015

Photo No. 37 Date: 08/2/22 Photo No. 38 Date: 08/24/23

**Description:** View SW, northern hardwoods-hemlock-white pine forest with sugar maple, black birch, white pine, American hazelnut and woodfern

**Description:** View S, successional northern hardwoods with white pine, eastern cottonwood, red maple, Morrow's honeysuckle, European buckthorn, Asian bittersweet





 Photo No. 39
 Date: 08/17/22
 Photo No. 40
 Date: 08/16/22

**Description:** View N, red maple swamp with silky dogwood, arrowwood, sensitive fern and skunk cabbage

**Description:** View S, stream habitats (Sackett Brook)







### D-2 Form FP-1 (Blank)

#### I. General Information

	Site Name and Evaluation Area (including whether wetland or u	pland)
	Location/Physical Description	
	Date(s) of Site Visit(s) and Data Collection	
	Weather Conditions During Site Visit	
	Field Staff Performing Evaluation	Date this form was completed
II.	Site Description	
Α.	Hydrology/Water Regime	
	☐ Permanently flooded	☐ Saturated
	☐ Intermittently exposed	☐ Temporarily flooded
	☐ Semi-permanently flooded	☐ Intermittently flooded
	☐ Seasonally flooded	☐ Artificially flooded
	☐ Upland	
	timated Flooding Regime:Flooded Annually2-Year tes:	Flood10-Year100-Year Flood
В.	Community Cover Type(s)	
We	etland	pland
	☐ Transitional floodplain forest	☐ Northern Hardwoods-Hemlock-White Pine Forest
	☐ High terrace floodplain forest	☐ Rich mesic forest
	☐ Red maple swamp	☐ Red Oak-Sugar Maple Transition Forest
	☐ Vernal pool	☐ Agricultural fields
	☐ Black ash-red maple-tamarack calcareous seepage swamp	☐ Cultural grassland
	☐ Deep emergent marsh	☐ Successional northern hardwoods
	☐ Shallow emergent marsh	☐ Spruce-fir-northern hardwood forest
	☐ Shrub swamp	☐ Developed/disturbed cover types
	☐ Wet meadow	☐ Other
	Other	

No	tes:									
Во	rdering Rive	erine/Aq	uatic Habitat							
	☐ High-g	gradient	stream		☐ L	☐ Low-gradient stream				
	☐ Mediu	m-gradi	ent stream		□ M	loderately alkaline	e lake/pond			
	☐ Backw	/ater								
C.		Inventory (Plant community: tree and vine data obtained in a 30' radius plot; shrubs in a 15' radius plot; and herbaceous plant data in a 5' radius plot.)								
	% Cover:		Trees (> 20') SI	hrubs (< 20')	Woody	vines Moss	es Herbaceous			
		(specie		6 or more of the ve	egetative	cover in each stra	ata or any amount of an			
	Strata	Plant	Species		Strata	a Plant Specie	es			
		-								
						_				
								_		
Str	ata: T=Treessedlings,	e, S=Sh	rub, L=Liana (vine),	H=Herb (Includes	grasses	, herbs, pterophyt	es [ferns], lichens, woody			
No	tes:	and mo	15565)							
D.	Inventory (	(Soils)						_		
	Soil Survey U	Init			Drainad	ge Class				
	Texture (upp				Depth	90 01400				
	Represent		oil Pit Log		Бериі					
So	il Horizon Depth (inches)		Color		Soil Texture	Mottling				
	II I IONZON		Дерит (полоз)	COIOI		Our resture	wottiing			
			<u> </u>							
								ľ		

No	tes:										
III.	Important Habitat Feature	es									
	Wildlife Food	dlife Food									
	Important wetland food plan	nts (smartweeds, pondwe	eeds, wild rice, bulrush, v	wild celery)							
	☐ Abundant	☐ Present	☐ Absent	☐ Not Applicable							
	Important upland food plan	ts (hard mast and fruit/be	erry producers)								
	☐ Abundant	☐ Present	☐ Absent	□ Not Applicable							
	Shrub thickets with suitable	e earthworm habitat (Ame	erican woodcock)								
	☐ Abundant	☐ Present	☐ Absent	☐ Not Applicable							
	Cover/Perches/Basking/D	Denning/Nesting Habita	<u>t</u>								
	Shrub and/or herbaceous v	regetation (suitable for bi	rds such as veery nestin	g)							
	☐ Abundant	☐ Present	☐ Absent	☐ Not Applicable							
	Trees (live or dead) > 30" [	DBH									
	☐ Abundant	Present	☐ Absent	☐ Not Applicable							
	Standing dead trees (poten	ntial for cavities and percl	nes)								
	☐ Abundant	Present	☐ Absent	☐ Not Applicable							
	Tree cavities in trunks or lin	mbs									
	☐ Abundant	Present	☐ Absent	□ Not Applicable							
	Small mammal burrows:										
	Abundant	Present	☐ Absent	□ Not Applicable							
	Dense herbaceous cover (v	voles, small mammals, a	mphibians & reptiles)								
	Abundant	Present	☐ Absent	□ Not Applicable							
	Large woody debris on the	ground (small mammals	, mink, amphibians & rep	otiles)							
	☐ Abundant	Present	☐ Absent	☐ Not Applicable							
	Rocks, crevices, logs, hollo	ow logs, tree roots or hun	nmocks (for multiple wild	life habitat purposes)							
	Abundant	☐ Present	Absent	☐ Not Applicable							

☐ Abundant	Present	☐ Absent			Not Applicable
Depressions that may serv	re as seasonal (vernal/au	tumnal) pool	s		
☐ Abundant	☐ Present	☐ Absent			Not Applicable
Standing water present at	least part of the growing	season, suita	able for u	se by	
☐ Breeding amphibians	1	Non-breeding	ı amphibi	ians (for	aging, re-hydration)
☐ Turtles	F	oraging wat	erfowl		
Sphagnum hummocks or r standing water in spring (fo		or saturated	logs, ove	erhangir	ng or directly adjacent to pools
☐ Abundant	☐ Present	☐ Absent			Not Applicable
Exposed areas of well-drain	ned, sandy soil suitable f	or turtle nest	ing		
Abundant	☐ Present	☐ Absent			Not Applicable
Wildlife Dens/Nests (if ob	oserved)				
Turtle nesting sites					
☐ Abundant	☐ Present	☐ Absent			Not Applicable
Nest(s) present of	☐ Bald Eagle	☐ Osprey	,	Great E	Blue Heron
Den(s) present of	☐ Otter	☐ Mink		Beaver	
Other nests or dens (identi	fy species):				
Emergent Wetlands (if A	oplicable)				
Persistent emergent wetlan wood duck, green heron, b					owing season (American bitte
Flooded > 5 cm	3		Present		☐ Absent
Flooded > 25 cm (pied-bille	ed grebe)		Present	t	☐ Absent
Fine-leafed emergent vege (common snipe, spotted sa		ges) at least	seasonal	ly floode	ed during the growing season
Flooded > 5 cm			Present	t	☐ Absent
Flooded > 25 cm (least bitt	ern, common moorhen)		Present	t	☐ Absent
Notes:					

# Form FP-1: Floodplain Habitat Inventory Form Limited number of connectors to adjacent areas of habitat (somewhat important for connectivity function) Area is embedded in a large area of natural habitat with unimpeded connection to other habitats (high connectivity function) V. Rare Species and MNHESP Core Area Habitat Designation ☐ Core Area 1 ☐ Core Area 2 Core Area 3 ☐ Core Area 4 Federally listed threatened or endangered species habitat (including species with known overlapping habitat): State-listed species habitat (including species with known overlapping Priority Habitat): Rare species direct observations during current field surveys (list): VI. Incidental Direct Wildlife Observations VII. Habitat Degradation (identify specific location within area if applicable) Evidence of significant levels of dumping Evidence of significant erosion or sedimentation problems Presence of invasive plants (e.g., purple loosestrife, *Phragmites*, glossy buckthorn); identify plants and estimate approximate percent coverage: \_ ☐ Disturbance from roads or highways ☐ Evidence of fire Evidence of other human disturbance; describe: \_\_\_\_\_

**General Electric Housatonic Rest of River** 

VII	I.Restoration Opportunities								
	☐ Potential suitability of area for access road or staging area								
	☐ Presence of potential restoration resources (e.g., boulders, large trees or woody debris, plant propagation source material). Identify specific items:								
	Other restoration opportunities:								



D-3 Incidental Wildlife Observations During Floodplain Surveys

#### **WILDLIFE FIELD OBSERVATIONS**

Date:08/02/2022 Time: Various

Weather: Sunny, Scattered Showers

Team member(s): SE, AH

Team activity: Floodplain Surveys

Details of Observations:								
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u> <u>Collected:<sup>2</sup></u>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	<u>Faunal</u> Type⁵	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>	
1323	Bird	No	American crow Corvus brachyrhynchos	42.432166, -73.250955	Bird	Animal	Adult	
1323	Amphibian	No	Green frog Lithobates clamitans	42.432536, -73.250398	Amphibian	Call		
1421	Reptile	No	Unidentified turtle	42.431955 -73.251274	Reptile	Tracks	Potentially snapping turtle ( <i>Chelydra serpentina</i> ) or wood turtle ( <i>Glyptemys insculpta</i> )	
15:55	Small mammal	No	Racoon Procyon lotor	42.432323, -73.252041	Small mammal	Tracks		
0922	Amphibian	No	Green frog Lithobates clamitans	42.432536, -73.250398	Animal	Invertebrate	Multiple individuals calling from edge of vernal pool	
1100	Bird	No	Hummingbird <i>Trochilidae</i>	42.432536, -73.250398	Animal	Bird	One individual flying	
1427	Invertebrate	No	Monarch butterfly Danaus plexippus	42.432536, -73.250398	Animal	Bird	Feeding in joe pyweed (Eutrochium purpureum) flowers	
1505	Invertebrate	No	Tiger swallowtail butterfly Papilio glaucus	42.432536, -73.250398	Animal	Invertebrate		
1520	Amphibian	No	Green frog Lithobates clamitans	42.432536 -73.250398	Animal	Amphibian	Multiple individuals	

Appendix A-1 (continued). Incidental Direct Wildlife Observations during floodplain habitat surveys.

#### **WILDLIFE FIELD OBSERVATIONS**

Date:08/03/2022
Time: Various
Weather: Sunny

Team member(s): SE, AH

Team activity: Floodplain/ Vernal Pool Surveys

#### **Details of Observations:**

Dotail	Details of Observations.							
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u>	Species Observed <sup>3</sup>	Location⁴	<u>Faunal</u>	<b>Observation</b>	Behavior/Condition Description/Habitat Type <sup>6</sup>	
		Collected:2			Type <sup>5</sup>	Type <sup>6</sup>		
1652	Bird	No	Hairy woodpecker	42.432119,	Bird	Animal	Individual	
			Leuconotopicus villosus	-73.248168				
			·					
1711	Amphibian	No	Gray tree frog	42.432141,	Amphibian	Animal	Individual	
			Hyla versicolor	-73.249529				
1050	Amphibian	No	Mood from	42 422247	Amphibian	Animal	Individual matamarah	
1252	Amphibian	No	Wood frog	42.432367,	Amphibian	Allillal	Individual metamorph	
			Lithobates sylvaticus	-73.247571				

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. Species: Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. Location: Station #/GPS coords/Description
- 5. Faunal Type: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. **Observation Type:** Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

Date:08/04/23
Time: Various
Weather: Sunny

Team member(s): SE, AH

Team activity: Floodplain/ Vernal Pool Surveys

Detail	Details of Observations:										
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	<u>Faunal</u>	Observation	Behavior/Condition Description/Habitat Type <sup>6</sup>				
		Collected:2			<u>Type⁵</u>	<u>Type<sup>6</sup></u>					
1358	Bird	No	Baltimore Oriole Icterus galbula	42.427609, -73.238515	Bird	Animal	Individual				
1358	Invertebrate	No	Monarch Butterfly Danaus plexippus	42.427609, -73.238515	Invertebrate	Animal	Individual				
1649	Invertebrate	No	Darner dragonfly Odonata: Aeshnidae	42.426833, -73.239684	Invertebrate	Animal	Multiple individuals				

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. **Species:** Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. Location: Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

# WILDLIFE FIELD OBSERVATIONS

Date:08/05/23
Time: Various

Weather: Partly Cloudy

Team member(s):

Team activity: Floodplain/ Vernal Pool Surveys

Detail	etalis of Observations.										
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u>	Species Observed <sup>3</sup>	Location <sup>4</sup>	<u>Faunal</u>	<u>Observation</u>	Behavior/Condition Description/Habitat Type <sup>6</sup>				
		Collected:2			<u>Type⁵</u>	<u>Type<sup>6</sup></u>					
1500	Bird	No	American crow Corvus brachyrhynchos	42.425869, -73.239612	Bird	Animal	Individual				
1550	Bird	No	Red eyed vireo Vireo olivaceus	42.425110, -73.239445	Bird	Animal	Individual				
1904	Amphibian	No	Leopard frog Lithobates pipiens	42.430467, -73.237122	Amphibian	Animal	Individual				
1936	Reptile	Photo	Painted turtle Chrysemys picta	42.429496, -73.236451	Reptile	Animal	Multiple individuals				

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. Species: Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. **Location:** Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

Date:08/08/2022 Time: Various Weather: Partly Cloudy

Team member(s): SE, AH

Team activity: Floodplain Surveys

<u>Time</u>	Observation <sup>1</sup>	<u>Data</u> Collected: <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location</u> <sup>4</sup>	<u>Faunal</u> Type⁵	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
1321	Bird	No	Woodcock Scolopax minor	42.422814, -73.238697	Bird	Animal	Individual
1327	Bird	No	Gray catbird  Dumetella carolinensis	42.422588, -73.238195	Bird	Animal	Individual
1332	Amphibian	No	Leopard frog Lithobates pipiens	42.422305, -73.237634	Amphibian	Animal	Individual
1949	Bird	No	Belted kingfisher Megaceryle alcyon	42.420429, -73.236149	Bird	Animal	2 individuals

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. **Species:** Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. **Location:** Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

Date:08/10/22 Time: Various

Weather: Partly Cloudy
Team member(s): SE, AH

Team activity: Floodplain/ Vernal Pool Surveys

Detai	Details of Observations:										
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u> <u>Collected:<sup>2</sup></u>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	Faunal Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>				
1443	Bird	No	Mourning dove Zenaida macroura	42.412632, -73.237827	Bird	Animal	Individual				
1745	Bird	No	Cedar waxwing Bombycilla cedrorum	42.412505, -73.235579	Bird	Animal	5 individuals				
1237	Reptile	No	Snapping turtle Chelydra serpentina	42.4117291, -73.239105	Reptile	Nest	Over 6 predated snapping turtle nests				
1519	Reptile	No	Painted turtle Chrysemys picta	42.412921, -73.237214	Reptile	Animal	Deceased individual				
1536	Reptile	No	Painted turtle Chrysemys picta	42.412999, -73.237259	Reptile	Animal	Individual female				
1554	Large mammal	Photo	Coyote Canis latrans	42.413224, -73.238760	Large mammal	Track					
1637	Large mammal	Photo	Black Bear Ursus americanus	42.413977, -73.238308	Large mammal	Track					
1945	Bird	No	Woodcock Scolopax minor	42.414099, -73.235574	Bird	Animal	3 + individuals, likely family group				
2018	Reptile	No	Garter snake Thamnophis sirtalis	42.412720, -73.236392	Reptile	Animal	individual				

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. **Species:** Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. **Location:** Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

Date:08/11/2022 Time: Various Weather: Sunny Team member(s):

Team activity: Floodplain/ Vernal Pool Surveys

Details of Observations:

Detai	etails of Observations:										
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u> <u>Collected:</u> <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	<u>Faunal</u> <u>Type<sup>5</sup></u>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>				
1710	Bird	No	Robin Turdus migratorius	42.412554, -73.233110	Bird	Animal	Individual. Nest also observed w/ juveniles.				
1710	Bird	No	Red-tailed hawk Buteo jamaicensis	42.412554, -73.233110	Bird	Animal	Individual				
1710	Bird	No	Belted kingfisher Megaceryle alcyon	42.412554, -73.233110	Bird	Animal	Individual				
1710	Bird	No	Hairy woodpecker Leuconotopicus villosus	42.412554, -73.233110	Bird	Animal	Individual				
1710	Amphibian	No	Wood frog Lithobates sylvaticus	42.412554, -73.233110	Amphibian	Animal	Multiple Individuals				
1925	Bird	No	Cedar waxwing Bombycilla cedrorum	42.410992, -73.235404	Bird	Animal	Individual				
1925	Invertebrate	No	Moths Lepidoptera	42.410992, -73.235404	Invertebrate	Animal	Individual				
1925	Invertebrate	No	Bees Anthophila	42.410992, -73.235404	Invertebrate	Animal	Individual				
1608	Small mammal	No	Chipmunk Tamias striatus	42.413327, -73.233884	Small mammal	Animal	Multiple individuals				
1715	Small mammal	No	Beaver Castor canadensis	42.412243, -73.234577	Small mammal	Lodge	Individual				
	1				l	1					

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. **Species:** Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. **Location:** Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

Date:08/16/2022 Time: Various Weather: Sunny

Team member(s): SE, AH

Team activity: Floodplain/ Vernal Pool Surveys

Details of Observations:

Detail	s of Observati	ons:					
<u>Time</u>	Observation <sup>1</sup>	Data Collected: <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	<u>Faunal</u> Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
0800	Bird	No	Mallard Anas platyrhynchos	Canoe meadows	Bird	Animal	Multiple individuals feeding/swimming in pond
0800	Reptile	No	Painted turtle Chrysemys picta	Canoe meadows	Reptile	Animal	Multiple individuals feeding/swimming in pond
0820	Large mammal	No	White-tailed deer Odocoileus virginianus	A-38	Large mammal	Animal	Walking & feeding in marsh
0840	Bird	No	Belted kingfisher Megaceryle alcyon	Sackett Brook	Bird	Animal	Calling whilst flying/hunting near beaver dam
1245	Invertebrate	No	Swallowtail butterfly Papilionidae	42.424115, -73.234982	Invertebrate	Animal	Individual
1245	Bird	No	Belted kingfisher Megaceryle alcyon	42.424115, -73.234982	Bird	Animal	Individual
1245	Fish	No	Unidentified fish	42.424115, -73.234982	Fish	Animal	Swimming individual
1520	Bird	No	Gray catbird  Dumetella carolinensis	42.427818, -73.235989	Bird	Call	
1452	Bird	No	Mallard Anas platyrhynchos	42.427842, -73.234817	Bird	Animal	Multiple individuals flying overhead
2027	Small mammal	No	Beaver Castor canadensis	42.422430, -73.235849	Small mammal	Lodge	
1840	Amphibian	Photo	Spring peeper Pseudacris crucifer	42.422430, -73.235849	Amphibian	Animal	Individual
1834	Small mammal	Photo	Beaver Castor canadensis	42.423556, -73.235493	Small mammal	Dam	
1806	Bird	Photo	Canada goose Branta canadensis	42.424872, -73.235217	Bird	Animal	Multiple individuals
18:23	Amphibian	Photo	Green frog	42.424013, -73.235389	Amphibian	Animal	Individual

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. **Species:** Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. **Location:** Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

Date:08/17/2022 Time: Various

Weather: Partly Cloudy Team member(s): SE, AH

Team activity: Floodplain Surveys

Details of Observations:

Detai	ls of Observati	ons:					
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u> <u>Collected:</u> <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location⁴</u>	Faunal Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
0835	Fish	No	Bass Micropterus	Sackett Brook	Fish	Animal	Individual breaking surface of water feeding in deep portion along cut bank
0838	Bird	No	Hummingbird Trochilidae	Sackett Brook	Bird	Animal	Individual female feeding on jewelweed (Impatiens capensis) flowers
0856	Bird	No	Gray catbird  Dumetella carolinensis	A-44 42.422505, -73.232411	Bird	Call	Individual in shrub thicket
0856	Bird	No	Belted kingfisher Megaceryle alcyon	A-44 42.422505, -73.232411	Bird	Animal	Individual flying by
1100	Small mammal	Photo	Beaver Castor canadensis	Sykes Brook	Small mammal	Den/Lodge	
1120	Reptile	Photo	Snapping turtle Chelydra serpentina	Sykes Brook	Reptile	Track	In mud of dried channel next to sykes brook
1300	Large mammal	Photo	Black bear Ursus americanus	Sykes Brook	Large mammal	Track	In mud along edge of the channel below small beaver dam
1343	Amphibian	Photo	Pickerel frog	42.425183, -73.236783	Amphibian	Animal	Individual
1615	Mammal	Photo	Black bear Ursus americanus	VP-24 42.426537, -73.232023	Large mammal	Scat	In trail near VP-24

Date:08/18/22 Time: Various

Weather: Partly Cloudy
Team member(s): SE, AH

Team activity: Floodplain/ Vernal Pool Surveys

Detail	etails of Observations:										
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u> <u>Collected:<sup>2</sup></u>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	<u>Faunal</u> <u>Type<sup>5</sup></u>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>				
1317	Bird	No	American crow Corvus brachyrhynchos	42.422379, -73.240718	Bird	Animal	Individual				
1317	Bird	No	Cedar waxwing Bombycilla cedrorum	42.422379, -73.240718	Bird	Animal	Individual				
1342	Bird	No	Cardinal Cardinalis cardinalis	42.422351, -73.239535	Bird	Animal	Individual				
1342	Bird	No	Green heron Butorides virescens	42.422351, -73.239535	Bird	Animal	Individual				
1342	Bird	No	Gray catbird  Dumetella carolinensis	42.422351, -73.239535	Bird	Animal	Individual				
1430	Small mammal	Photo	Beaver Castor canadensis	42.421437, -73.240720	Small mammal	Lodge					
1430	Bird	No	Downy woodpecker Picoides pubescens	42.421437, -73.240720	Bird	Animal	Individual				
1700	Invertebrate	No	Ruby Meadowhawk Sympetrum rubicundulum	42.410649, -73.240432	Invertebrate	Animal	Individual				
1508	Reptile	Photo	Snapping turtle Chelydra serpentina	42.421269, -73.239880	Reptile	Sign	Shells				

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. **Species:** Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. **Location:** Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

Date:08/24/22 Time: Various

Weather: Partly Cloudy
Team member(s): SE, AH

Team activity: Floodplain/ Vernal Pool Surveys

Detail	etalis of Observations.										
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u> Collected: <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	Faunal Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>				
1248	Bird	No	Mallard Anas platyrhynchos	42.410574, -73.243776	Bird	Animal	Multiple individuals				
1248	Bird	No	Hummingbird Trochilidae	42.410574, -73.243776	Bird	Animal	Multiple individuals				
1314	Bird	No	Goldfinch Spinus tristis	42.412019, -73.243813	Bird	Animal	Individual				
1536	Large mammel	No	Black Bear Ursus americanus	42.403923, -73.241235	Large mammel	Sign					

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. **Species:** Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. Location: Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

# **WILDLIFE FIELD OBSERVATIONS**

Date:08/25/22
Time: Various
Weather: Sunny

Team member(s): SE, AH

Team activity: Floodplain/ Vernal Pool Surveys

Detai	ctalls of Observations.										
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u> <u>Collected:</u> <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	Faunal Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>				
1227	Amphibian	Photo	Wood frog Lithobates sylvaticus	42.405286, -73.239049	Amphibian	Animal	Individual				
1315	Bird	No	Mallard Anas platyrhynchos	42.405232, -73.238013	Bird	Animal	5 individuals flying				
1520	Amphibian	No	Gray tree frog Dryophytes versicolor	42.408008, -73.237887	Amphibian	Animal	Individual				
1228	Amphibian	Photo	Wood frog Lithobates sylvaticus	42.405422, -73.238892	Amphibian	Animal	Multiple morphs hopping through moneywort				
1448	Amphibian	Photo	Wood frog Lithobates sylvaticus	42.406229, -73.235447	Amphibian	Animal	Individual adult				

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. Species: Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. Location: Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. **Observation Type:** Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - **b.** Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

Date:08/30/22 Time: Various

Weather: Partly Cloudy Team member(s): SE, AH

Team activity: Floodplain/ Vernal Pool Surveys
Details of Observations:

Detai	ls of Observati	ons:					
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u> <u>Collected:</u> <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	Faunal Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
1254	Bird	No	Woodcock Scolopax minor	42.418757, -73.239414	Bird	Animal	Individual
1349	Bird	No	American crow Corvus brachyrhynchos	42.416951, -73.240569	Bird	Animal	Individual
1349	Reptile	Photo	Unidentified turtle	42.416951, -73.240569	Reptile	Tracks	
1505	Bird	No	Blue jay Cyanocitta cristata	42.416103, -73.240340	Bird	Animal	Individual
1505	Bird	No	Gray catbird  Dumetella carolinensis	42.416103, -73.240340	Bird	Animal	Individual
1753	Bird	No	Canada goose Branta canadensis	42.414250, -73.239303	Bird	Animal	Multiple individuals flying
1753	Bird	No	Hairy woodpecker Leuconotopicus villosus	42.414250, -73.239303	Bird	Call	
1504	Small mammal	No	Beaver Castor canadensis	42.415949, -73.240299	Small mammal	Sign	Bank slide

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. **Species:** Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. **Location:** Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

# **WILDLIFE FIELD OBSERVATIONS**

Time: Various
Weather: Partly Cloudy

Date:08/31/22

Team member(s): SE, AH

Team activity: Floodplain/ Vernal Pool Surveys

Detail	Details of Observations.										
<u>Time</u>	Observation <sup>1</sup>	Data Collected: <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	<u>Faunal</u> Type⁵	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>				
1354	Bird	No	American crow Corvus brachyrhynchos	42.416081, -73.236924	Bird	Animal	Individual				
1516	Bird	No	Field Sparrow Spizella pusilla	42.415675, -73.238590	Bird	Animal	Individual				
1712	Bird	No	Bald eagle Haliaeetus Ieucocephalus	42.407028, -73.237864	Bird	Animal	Individual flying above				

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. **Species:** Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. Location: Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - **b.** Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

# **WILDLIFE FIELD OBSERVATIONS**

Date:09/15/22
Time: Various
Weather: Sunny

Team member(s): SE, AH

Team activity: Floodplain/ Vernal Pool Surveys

<u>Time</u>	Observation <sup>1</sup>	Data Collected: <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	Faunal Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
1134	Reptile	Photo	Garter snake Thamnophis sirtalis	42.407295, -73.233019	Reptile	Animal	2 individuals
1134	Bird	No	Tufted titmouse Baeolophus bicolor	42.407295, -73.233019	Bird	Animal	Individual
1401	Bird	No	Mourning dove Zenaida macroura	42.408070, -73.234361	Bird	Animal	Multiple individuals
1417	Bird	No	Gray catbird  Dumetella carolinensis	42.408936, -73.234437	Bird	Animal	Individual feeding

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. **Species:** Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. Location: Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

Date:09/28/22 Time: Various Weather: Cloudy

Team member(s): SE, AH

Team activity: Floodplain/ Vernal Pool Surveys

Detai	ls of Observat	ions:					
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u> <u>Collected:</u> <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	<u>Faunal</u> Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
1148	Bird	No	Wild turkey Meleagris gallopavo	42.413540, -73.232722	Bird	Animal	Individual
1148	Bird	No	Mallard Anas platyrhynchos	42.413540, -73.232722	Bird	Animal	Multiple individuals
1148	Bird	No	American crow Corvus brachyrhynchos	42.413540, -73.232722	Bird	Animal	Individual
1148	Bird	No	Tufted titmouse Baeolophus bicolor	42.413540, -73.232722	Bird	Animal	Individual
1148	Bird	No	Cardinal Cardinalis cardinalis	42.413540, -73.232722	Bird	Animal	Individual
1220	Bird	No	Pileated woodpecker Dryocopus pileatus	42.414290, -73.233513	Bird	Animal	Individual
1347	Large mammal	No	Black Bear Ursus americanus	42.426258, -73.230961	Large mammal	Scat	
1602	Small mammal	No	Beaver Castor canadensis	42.427407, -73.233030	Small mammal	Lodge	
1627	Invertebrate	No	Northern Harrier Circus hudsonius	42.426873, -73.234469	Invertebrate	Animal	Individual
1635	Bird	No	Wood duck Aix sponsa	42.425410, -73.234369	Bird	Animal	Multiple individuals
	Bird	No	Great blue heron Ardea herodias		Bird	Animal	Individual

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. **Species:** Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. **Location:** Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

# **WILDLIFE FIELD OBSERVATIONS**

Date:8-2-2022

Time:

Weather: Sunny/Partly Cloudy/Cloudy/Mist/Showers/Rain/Snow: Sunny 70°F

Team member(s): TO, JS

Team activity: Floodplain Surveys

Details (	oi Obsei valions	).					
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u> Collected: <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	Faunal Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
0900	Bird	<u> </u>	King fisher, Black- capped chickadee, Song sparrow, Northern cardinal, Tufted titmouse	Housatonic River	Bird	Call, animal	Flying, adult
0940	Bird		American robin, Song sparrow, Yellow warbler	Housatonic River	Bird	Call, animal	Flying, adult
1030	Bird		Yellow shafted flicker, American robin, Cardinal	Housatonic River	Bird	Call, animal	Flying, adult
1200	Bird		Gray catbird, American crow, Great blue heron, Cedar waxwing,	Housatonic River	Bird	Call, animal	Flying, adult
1300	Bird		American robin, Black- capped chickadee, Cat bird, Pee wee	Housatonic River	Reptile	Call, animal	Flying, adult
1200	Small mammal		Raccoon	Housatonic River	Small mammal	track	

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. Species: Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. Location: Station #/GPS coords/Description
- 5. Faunal Type: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. **Observation Type:** Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - **b.** Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

# **WILDLIFE FIELD OBSERVATIONS**

Date:8-3-2022

Time:

Weather: Sunny/Partly Cloudy/Cloudy/Mist/Showers/Rain/Snow: Sunny 82°F

Team member(s): TO, JS

Team activity: Floodplain Surveys

<u>Time</u>	Observation <sup>1</sup>	<u>Data</u>	Species Observed <sup>3</sup>	Location <sup>4</sup>	Faunal	Observation	Behavior/Condition Description/Habitat Type <sup>6</sup>
TITIC	<u>Observation</u>	Collected: <sup>2</sup>	<u>species observed</u>	Location	Type <sup>5</sup>	Type <sup>6</sup>	Behaviory domaition Description/Habitat Type
0930	Bird		American robin, Black- capped chickadee, Gray catbird, Pee wee	Housatonic River	Bird	Call, animal	Flying, feeding, adults
1200	Bird		American robin, Yellow warbler	Housatonic River	Bird	Call, animal	Flying, adults
1300	Bird		Hairy woodpecker, American robin	Housatonic River	Bird	Call, animal	Flying, feeding, adults
1400	Bird		Cray catbird, American robin, Northern cardinal	Housatonic River	Bird	Call, animal	Flying, resting, adults

- Observation: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. **Species:** Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. Location: Station #/GPS coords/Description
- 5. Faunal Type: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

# **WILDLIFE FIELD OBSERVATIONS**

Date:8-4-2022

Time:

Weather: Sunny/Partly Cloudy/Cloudy/Mist/Showers/Rain/Snow: Sunny 70°F

Team member(s): TO, JS

Team activity: Floodplain Surveys

	of Observations		0 1 01 12			101	
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u>	Species Observed <sup>3</sup>	Location <sup>4</sup>	<u>Faunal</u>	<u>Observation</u>	Behavior/Condition Description/Habitat Type <sup>6</sup>
		Collected:2			Type <sup>5</sup>	Type <sup>6</sup>	
0930	Bird		Gold finch	Housatonic River	Bird	Animal	Flying, adult
1100	Bird		American robin, Great- crested flycatcher	Housatonic River	Bird	Animal	Flying, adult
1200	Bird		Great-crested flycatcher	Housatonic River	Bird	Animal	Feeding, adult
1300	Bird		Great-crested flycatcher, American robin	Housatonic River	Bird	Animal	Feeding, adult
-							

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. Species: Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. Location: Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. **Observation Type:** Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - **b.** Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

# **WILDLIFE FIELD OBSERVATIONS**

Date:8-5-2022

Time:

Weather: Sunny/Partly Cloudy/Cloudy/Mist/Showers/Rain/Snow: Sunny 80°F

Team member(s): JS,CM,DH
Team activity: Floodplain Surveys

Details 0	etails of Observations:											
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u> Collected: <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	<u>Faunal</u> Type⁵	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>					
0830	Amphibian	<u>conected.</u>	Wood frog	Housatonic River	Amphibian	Animal	Resting, subadult					
0930	Bird		American crow, Fish crow, Belted kingfisher	Housatonic River	Bird	Animal, call	Flying, resting, adults					
1200	Bird		Blue jay, Red-tail hawk	Housatonic River	Bird	Animal	Resting, adults					
1400	Bird		4 Mallards	Housatonic River	Bird	Animal	Swimming, adults					

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. Species: Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. Location: Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

#### **WILDLIFE FIELD OBSERVATIONS**

Data:8-8-2022		

Time:

Weather: Sunny/Partly Cloudy/Cloudy/Mist/Showers/Rain/Snow: Sunny 85°F

Team member(s): JS,AM

Team activity: Floodplain Surveys

Dotalio 0	C C C C C C C C C C C C C C C C C C C	•					
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u> <u>Collected:<sup>2</sup></u>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	Faunal Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
1000	Bird		American crow, Pee wee	Housatonic River	Bird	Animal, call	Resting/roosting, adults

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. Species: Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. **Location:** Station #/GPS coords/Description
- 5. Faunal Type: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

# **WILDLIFE FIELD OBSERVATIONS**

Date:8-9-2022

Time:

Weather: Sunny/Partly Cloudy/Cloudy/Mist/Showers/Rain/Snow: Sunny 70°F

Team member(s): TO,JS

Team activity: Floodplain Surveys

Dotails	or observations	<u>'</u> .					·
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u> <u>Collected:<sup>2</sup></u>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	Faunal Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
0900	Bird		American crow	Housatonic River	Bird	Animal, call	Resting/roosting, adult
0945	Bird		American crow, Gray catbird, Pee wee, Downy woodpecker, Blue jay	Housatonic River	Bird	Animal, call	Resting/roosting, flying, adults
1030	Bird		American crow, Goldfinch	Housatonic River	Bird	Animal, call	Flying, adults
1200	Bird		American crow, Pee wee, Goldfinch	Housatonic River	Bird	Animal, call	Resting/roosting, flying, adults
1330	Bird		American crow, House wren	Housatonic River	Bird	Animal, call	Flying, adults
1400	Bird		Cedar waxwing, song sparrow, Goldfinch, Canada goose, Hummingbird	Housatonic River	Bird	Animal, call	Resting/roosting, flying, adults
1445	Bird		Downy woodpecker, Tufted titmouse, American robin, Black- capped chickadee	Housatonic River	Bird	Animal, call	Resting/roosting, flying, adults

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. Species: Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. Location: Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe

# **WILDLIFE FIELD OBSERVATIONS**

Date:8-10-2022

Time:

Weather: Sunny/Partly Cloudy/Cloudy/Mist/Showers/Rain/Snow: Sunny 70°F

Team member(s): TO,JS

Team activity: Floodplain Surveys

Details of Observations:

Details	of Observations	S:					
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	<u>Faunal</u>	<u>Observation</u>	Behavior/Condition Description/Habitat Type <sup>6</sup>
		Collected:2			<u>Type⁵</u>	<u>Type<sup>6</sup></u>	
0900	Bird		American crow, Cedar	Housatonic	Bird	Animal, call	Resting/roosting, flying, feeding, adults
			waxwing, American	River			
			robin, Gray catbird,				
			Tufted titmouse, Black-				
			capped chickadee				
0945	Bird		Ruby-throated	Housatonic	Bird	Animal, call	Resting/roosting, flying, feeding, adults
			hummingbird, American	River			
			crow, Gray catbird,				
			Tufted titmouse,				
1020	Bird		Common yellowthroat Ruby-throated	Housetonie	Dind	Animad adl	Fooding flying adults
1030	BILO		hummingbird, American	Housatonic River	Bird	Animal, call	Feeding, flying, adults
			crow, Gray catbird,	Kivei			
			Canada goose.				
1230	Insect		Monarch butterfly	Housatonic	Insect	Animal	Feeding, adult
				River			- County, county
1330	Bird		Mourning dove,	Housatonic	Bird	Animal, call	Roosting, flying, adults
			Goldfinch	River			
1430	Bird		Ruby-throated	Housatonic	Bird	Animal, call	Feeding, flying, adults
			hummingbird, Goldfinch	River			
1500	D'and		Caldfinale Canada nasas	11	D'and	A !	Flater and the
1500	Bird		Goldfinch, Canada goose,	Housatonic	Bird	Animal, call	Flying, adults
			Song sparrow, Tufted titmouse	River			
			uunouse				
1530	Bird		Ruby-throated	Housatonic	Bird	Animal, call	Feeding, resting, adults
			hummingbird, American	River			
			robin				
1400	Reptile		Garter snake	BW-5	Reptile	Animal	Resting, subadult
1415	Large		Coyote	BW-5	Large	Tracks	a.
	mammal				mammal		
					1	1	

1420	Large mammal	Black bear	BW-5	Large mammal	Tracks	Sow with cubs
1420	Large mammal	Deer	BW-5	Large mammal	Tracks	Adult
1430	Amphibian	Green frog	BW-5	Amphibian	Animal	Resting, subadult
1430	Amphibian	American toad	BW-5	Amphibian	Animal	Resting, subadult
1430	Bird	Blue jay, Tufted titmouse, Goldfinch				Flying, resting, adults

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. **Species:** Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. Location: Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. **Observation Type:** Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

# **WILDLIFE FIELD OBSERVATIONS**

**Date:**8-11-2022

Time:

Weather: Sunny/Partly Cloudy/Cloudy/Mist/Showers/Rain/Snow: Sunny 80°F

Team member(s): TO,JS

Team activity: Floodplain Surveys

Details	or observation.	J.					
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u> <u>Collected:<sup>2</sup></u>	Species Observed <sup>3</sup>	<u>Location</u> <sup>4</sup>	Faunal Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
0900	Bird		American crow	Housatonic River	Bird	Animal, call	Resting, adult
1000	Amphibian		Wood frog	Housatonic River	Amphibian	Animal, call	Resting, subadult
1030	Bird		Red-tailed hawk, Goldfinch, American woodcock	Housatonic River	Bird	Animal, call	Flying, resting, adults
1100	Reptile		Garter snake	Housatonic River	Reptile	Animal	Resting, subadult
1145	Bird		Cedar waxwing	Housatonic River	Bird	Animal, call	Flying, adult
1230	Bird		Gray catbird, Goldfinch, A. robin, Common grackle, Red-tail hawk	Housatonic River	Bird	Animal, call	Foraging, flying, adults
1330	Bird		Blue jay, Red-tail hawk, A. robin, Goldfinch	Housatonic River	Bird	Animal, call	Foraging, Flying, adults
1500	Reptile		Painted turtle shell	Housatonic River	Reptile	Animal	
1530	Small mammal		Muskrat	Housatonic River	Small mammal	Scat	Muskrat in lodge

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. **Species:** Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. **Location:** Station #/GPS coords/Description
- 5. Faunal Type: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown

# **WILDLIFE FIELD OBSERVATIONS**

Date:8-16-2022

Time:

Weather: Sunny/Partly Cloudy/Cloudy/Mist/Showers/Rain/Snow: Sunny 80°F

Team member(s): TO,JS

Team activity: Floodplain Surveys
Details of Observations:

Details	Of Observations	<b>.</b>					
<u>Time</u>	Observation <sup>1</sup>	Data Collected: <sup>2</sup>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	<u>Faunal</u> <u>Type<sup>5</sup></u>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
0900	Bird		American crow, King fisher, Great blue heron	Housatonic River	Bird	Animal, call	Flying, adults
0930	Amphibian		Green frog	Housatonic River	Amphibian	Animal	Resting, adult
1030	Bird		American crow, Yellow warbler, King fisher	Housatonic River	Bird	Animal, call	Flying, adults
1100	Bird		Mourning dove, Goldfinch, Great blue heron, Marsh wren	Housatonic River	Bird	Animal	Resting, flying, adults
1115	Amphibian		Green frog	Housatonic River	Amphibian	Animal	Resting, adult
1200	Bird		Gray catbird, Goldfinch	Housatonic River	Bird	Animal, call	Foraging, flying, adults
1230	Bird		Gray catbird, Goldfinch, American crow	Housatonic River	Bird	Animal, call	Foraging, flying, adults
1300	Bird		Mallard	Housatonic River	Bird	Animal, call	Swimming, adult
1315	Reptile		Painted turtle	Housatonic River	Reptile	Animal	Swimming, subadult
1330	Amphibian		Green frog	Housatonic River	Amphibian	Animal	Resting, subadult
1400	Bird		Gray catbird	Housatonic River	Bird	Animal, call	Resting, adult
1500	Bird		Red-bellied woodpecker	Housatonic River	Bird	Animal, call	Feeding, adult
1545	Bird		Gray catbird, Goldfinch	Housatonic River	Bird	Animal, call	Flying, adults

- **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- **Data Collected:** 
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- Species: Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
   Location: Station #/GPS coords/Description

- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
    c. Life stage Adult/Subadult/Juvenile/Unknown

  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

# **WILDLIFE FIELD OBSERVATIONS**

Date:8-17-2022

Time:

Weather: Sunny/Partly Cloudy/Cloudy/Mist/Showers/Rain/Snow: Cloudy 80°F

Team member(s): TO,JS

Team activity: Floodplain Surveys

<u>Time</u>	Observation <sup>1</sup>	<u>Data</u>	Species Observed <sup>3</sup>	<u>Location<sup>4</sup></u>	Faunal	Observation Turn of	Behavior/Condition Description/Habitat Type <sup>6</sup>
0900	Bird	Collected: <sup>2</sup>	American robin, Blue jay, Pee wee	Housatonic River	Type <sup>5</sup> Bird	Type <sup>6</sup> Animal, call	Flying, resting, adults
0915	Amphibian		Spring peeper	Housatonic River	Amphibian	Animal	Resting, adult
1000	Small mammal		Chipmunk	Housatonic River	Small mammal	Animal	Running, adult
1100	Bird		Ruby-throated hummingbird, A. crow, Gray catbird, Great blue heron	Housatonic River	Bird	Animal	Feeding, flying, adults
1200	Bird		Gray catbird, A. crow, Ruby-throated hummingbird	Housatonic River	Bird	Animal	Feeding, flying, adults
1230	Bird		American crow, Goldfinch	Housatonic River	Bird	Animal, call	Resting, adults
1330	Bird		Ruby-throated hummingbird, A. crow	Housatonic River	Bird	Animal, call	Feeding, flying adults
1400	Amphibian		Green frog	Housatonic River/BW- 1	Amphibian	Animal	Swimming, adult
1415	Amphibian		Pickerel frog	BW-1	Amphibian	Animal	Swimming, subadult
1430	Bird		Blue jay, Yellow warbler, Goldfinch	BW-1	Bird	Animal, call	Flying, resting, adults
1500	Bird		Black-capped chickadee, A. crow	Housatonic River	Bird	Animal, call	Flying, resting, adults

- Observation: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. **Species:** Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. **Location:** Station #/GPS coords/Description
- Faunal Type: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
   Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other

# 7. If animal then record:

- a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  c. Life stage Adult/Subadult/Juvenile/Unknown
  d. Sex Female/Male/Unknown

- e. Other Diseased/Injured/Dead Describe
- f. Number observed Individual/Pair/Family/Multiple (# or range)

# **WILDLIFE FIELD OBSERVATIONS**

Date:8-18-2022

Time:

Weather: Sunny/Partly Cloudy/Cloudy/Mist/Showers/Rain/Snow: Cloudy 80°F

Team member(s): TO,JS

Team activity: Floodplain Surveys
Details of Observations:

Time	Observation <sup>1</sup>	<u>Data</u>	Species Observed <sup>3</sup>	<u>Location</u> <sup>4</sup>	<u>Faunal</u>	Observation	Behavior/Condition Description/Habitat Type <sup>6</sup>
·		Collected:2			Type <sup>5</sup>	Type <sup>6</sup>	
1030	Bird		Green heron, Great blue heron, A. crow, Goldfinch, Catbird	Housatonic River	Bird	Animal, call	Flying, feeding, adults
1200	Bird		Red-tail hawk	Housatonic River	Bird	Animal, call	Flying, adult
1500	Bird		Canada goose, Red-tail hawk	Housatonic River	Bird	Animal, call	Flying, walking, adults
1530	Bird		Gray catbird, Great blue heron, A. crow, Cedar waxwing	Housatonic River/BW- 2	Bird	Animal, call	Flying, resting, adults
1544	Reptile		Snapping turtle	Housatonic River/BW- 2	Reptile	Animal	Swimming, adult
1550	Small mammal		Racoon	Housatonic River/BW- 2	Small mammal	Tracks	Adult
1600	Bird		King fisher	Housatonic River/BW- 3	Bird	Animal	Flying/feeding, adult
1615	Amphibian		Green frog	Housatonic River/BW- 3	Amphibian	Animal	Resting, subadult
1630	Bird		King fisher, Catbird, Blue jay	Housatonic River/BW- 4	Bird	Animal	Flying/feeding, adults
1630	Amphibian		Green frog	Housatonic River/BW- 4	Amphibian	Animal	Resting, adult

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- Species: Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
   Location: Station #/GPS coords/Description

- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. **Observation Type:** Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
    c. Life stage Adult/Subadult/Juvenile/Unknown

  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

# **WILDLIFE FIELD OBSERVATIONS**

Date:8-24-2022

Time:

Weather: Sunny/Partly Cloudy/Cloudy/Mist/Showers/Rain/Snow: Partly sunny 80°F

Team member(s): TO,JS

Team activity: Floodplain Surveys

<u>Time</u>	Observation <sup>1</sup>	Data Collected: <sup>2</sup>	Species Observed <sup>3</sup>	Location <sup>4</sup>	Faunal Type <sup>5</sup>	Observation Type <sup>6</sup>	Behavior/Condition Description/Habitat Type <sup>6</sup>
0900	Bird		Catbird, Mallard, Common grackle	Housatonic River	Bird	Animal, call	Swimming, resting, adults
1000	Bird		Mallard, King fisher, Gray catbird, Goldfinch	Housatonic River	Bird	Animal	Swimming, flying/feeding, adults
1100	Bird		Ruby-throated hummingbird, Gray catbird, Goldfinch, Downy woodpecker	Housatonic River	Bird	Animal	Feeding, adults
1200	Bird		Goldfinch	Housatonic River	Bird	Animal	Flying, adult
1230	Bird		Gray catbird	Housatonic River	Bird	Animal	Foraging, adult
1400	Bird		Black-capped chickadee	Housatonic River	Bird	Animal, call	Resting, adult
1430	Bird		Ruby-throated hummingbird, Osprey, Goldfinch,	BW-6	Bird	Animal, call	Feeding, flying, adults

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. Species: Common name/Family/Genus/Species; Certain/Uncertain/Unknown Basis for determination
- 4. Location: Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - **b.** Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)

Appendix A-1 (continued). Incidental Direct Wildlife Observations during floodplain habitat surveys.

#### **WILDLIFE FIELD OBSERVATIONS**

Date:8-25-2022

Time:

Weather: Sunny/Partly Cloudy/Cloudy/Mist/Showers/Rain/Snow: Sunny 80°F

Team member(s): TO,JS

Team activity: Floodplain Surveys

**Details of Observations:** 

Details C	or Observations	<b>).</b>					
<u>Time</u>	Observation <sup>1</sup>	<u>Data</u>	Species Observed <sup>3</sup>	Location <sup>4</sup>	<u>Faunal</u>	<u>Observation</u>	Behavior/Condition Description/Habitat Type <sup>6</sup>
		Collected:2			<u>Type⁵</u>	Type <sup>6</sup>	
1000	Bird		Goldfinch, Great blue	Housatonic	Bird	Animal, call	Flying, adults
			heron	River			
1130	Bird		Northern cardinal, Gray	Housatonic	Bird	Animal	Flying, resting, adults
			catbird, A. crow	River			
1330	Bird		Gray catbird	Housatonic	Bird	Animal	Foraging, adult
				River			
1330	Amphibian		Wood frog	Housatonic	Amphibian	Animal	Resting, subadult
				River			
1500	Bird		American robin,	Housatonic	Bird	Animal	Flying, adults
			Goldfinch	River			
					1		

- 1. **Observation**: Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 2. Data Collected:
  - a. Photos/video: Yes (number)/No
  - b. Sketch: Yes (attach)/No
- 3. Species: Common name/Family/Genus/Species: Certain/Uncertain/Unknown Basis for determination
- 4. **Location:** Station #/GPS coords/Description
- 5. **Faunal Type:** Bird/Large mammal/Small mammal/Reptile/Amphibian/Fish
- 6. Observation Type: Animal/Scat/Track/Rub/Call or other sound/Eggs/Nest, den, or bed/Molt/Other
- 7. If animal then record:
  - a. Behavior Rest or Roost/Feeding/Watering/Courtship/Reproduction/Territorial/Trapped/
  - b. Nesting/Predation/Flying/Swimming/Running/Walking/Standing/Grooming/Other
  - c. Life stage Adult/Subadult/Juvenile/Unknown
  - d. Sex Female/Male/Unknown
  - e. Other Diseased/Injured/Dead Describe
  - f. Number observed Individual/Pair/Family/Multiple (# or range)



# Appendix E Wetland Function and Value Assessment

#### Appendix E Wetland Function and Value Assessment

As discussed in Section 6.3.4 of the main Baseline Restoration Assessment (BRA) Report for Reach 5A, a floodplain wetland functional assessment was conducted of three wetland functional units in the floodplain of Reach 5A of the Housatonic Rest of River (depicted on Figure 6-4). Those units are:

- Wetlands in Reach 5A from the Confluence to Holmes Road;
- Wetlands of Canoe Meadows (including the association with Sackett Brook/Sykes Brook and other surface waters); and
- Wetlands in the remainder of Reach 5A.

For each of these functional units, the functional assessment process was documented on a Wetland Function Form (Form FP-2). As discussed in Section 6.3.4 of the main BRA Report, this form lists each function and records the criteria considered in documenting the wetland characteristics that contributed to the functional assessment of the particular wetland functional unit. The functions evaluated are groundwater recharge/discharge; floodflow alteration; fish and shellfish habitat; sediment, toxicant, and pathogen retention; nutrient removal, retention, and transformation; production export; sediment and shoreline stabilization; wildlife habitat; recreation; education and scientific value; uniqueness and heritage; visual quality and aesthetics; and threatened or endangered species habitat. The assessment is a qualitative description of the physical characteristics of the wetlands. It is not based on quantitative metrics, but rather provides criteria for assessing whether a wetland's characteristics could contribute to providing the functions listed above.

The results of this wetlands functional assessment are provided in the completed Wetland Function Forms FP-2 for the three wetland functional units. These results are summarized in tabular form in the following Table E-1:

Table E-1: Wetland Functional/Value Assessment Summary Table

		Wetland Functions and Values													
Wetland ID	GW Recharge Discharge	Floodflow Alteration	Fish and Shellfish Habitat	Sediment / Toxicant / Patho Retention	Nutrient Removal / Retention / Trans	Production Export	Sediment / Shoreline Stabilization	Wildlife Habitat	Recreation	Education/ Scientific Value	Uniqueness Heritage	Visual Quality / Aesthetics	T / E Species Habitat		
5A-1	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х		
5A-2	Х	Х	Х	Х	Х	X	Х	Х	Х	Х	Х	Х	Х		
5A-3	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х		

Abbreviations used in table: X = "Principal" function or value. Functions and values can be principal if they are an important physical component of a wetland ecosystem (function only), and/or are considered of special value to society, from a local, regional, and/or national perspective.

The completed Forms FP-2 are provided below. The results are discussed, by function, in Section 6.3.4 of the main BRA Report. Overall, they show that all three of the floodplain wetland units provide a full range of functions and values.

#### Form FP-2: Wetland Function-Value Evaluation Form

**Project Name: GE/Housatonic River** 

Total area of Evaluation Unit: ~160 acres Is area part of a wildlife corridor? Yes

Adjacent land use: Residential

Distance to nearest roadway or development: 100 feet

Dominant wetland/aquatic systems present: Transitional Floodplain Forest, Shallow Emergent Marsh, Shrub Swamp.

Contiguous undeveloped buffer zone present? Yes, located west of Medium-gradient stream.

Upland communities present: Northern Hardwoods-Hemlock-White Pine Forest, Red Oak-Sugar Maple Transitional Forests.

Rare species habitat? Yes, NHESP Estimated Habitats and Priority Habitats of Rare species

Other unique or notable ecological conditions:

Site I.D.: Area 5A-1

**Latitude:** 42.431652 **Longitude:** -73.249945

Prepared by: Julia Stearns Date: 6/21/2023

**Wetland Impact** 

Type: Floodplain Forest, Shallow Emergent Marsh,

Shrub Swamp. **Area:** 160 acres

Evaluation based on:

Office: Yes Field: Yes Delineation completed? No

Function/Value		Suita	bility	D-4:	Principle	Comments		
		Υ	N	Rationale (Reference #*)	F/V	Comments		
Ī	Groundwater Recharge/Discharge		Х	1, 5, 6, 7, 9	F	Associated wetlands meet some of the qualifiers though water quality may not be considered high.		
-	Floodflow Alteration	х		1, 2, 3, 6, 7, 8, 10, 13, 14, 15, 18	F	Wetlands relatively flat, receives and detains excessive flood water from adjacent river.		
-	Fish and Shellfish Habitat	Х		1, 2, 4, 6, 7, 8, 9, 10, 11, 12, 14, 15, 16, 17	F	Stream width greater than 50', wetlands are part of a larger, contiguous watercourse.		
*	Sediment/Toxicant Retention	х		1, 2, 3, 4, 5, 6, 8, 10, 12, 14, 16	F	Known sources of toxicants in watershed above the wetland.		
-	Nutrient Removal	Х		4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14.	F	Sources of excess nutrients present in watershed.		
-	Production Export	Х		1, 2, 4, 7, 8, 10, 12	F	High degree of plant community structure, flowering plants used by nectar-gathering insects.		
	Sediment/Shoreline Stabilization	Х		1, 2, 3, 4, 5, 6, 7, 8. 9, 10, 11, 12, 14, 15, 16	F	Dense vegetation, fine grained mineral and organic soils present.		
-	Wildlife Habitat	Х		3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 22,	F	Animal signs observed, high degree of plant species diversity and diversity of plant community structure, wildlife food sources.		
<b>A</b>	Recreation	х		1, 2, 4, 5, 8, 9, 10, 12	V	Wetlands and river are adjacent to and part of Fred Garner River Park with public parking and canoe access.		
4	Educational/Scientific Value	Х		1, 5, 7, 8, 9,10, 11	٧	Potential for educational value though minimal easy access available at Fred Garner River Park.		
*	Uniqueness/Heritage	х		3, 4, 5, 6, 7, 8, 9, 11, 12, 22, 24,	V	Value is high for wildlife though no opportunity for visual observations available, parking is available at Fred Garner River Park.		
<b>(II</b> )	Visual Quality/Aesthetics		Х	8	V	Area contains threatened/endangered species and contains critical habitat for state listed species though no opportunity for viewing.		
ES	Endangered Species Habitat	Х		1, 2	٧	Wetlands contain threatened/endangered species and contains critical habitat for state listed species.		
	Other							

\*See USACE NED 1995. Highway Methodology Workbook, Wetland Functions and Values, A Descriptive Approach

#### Form FP-2: Wetland Function-Value Evaluation Form

**Project Name: GE/Housatonic River** 

Total area of Evaluation Unit: ~140 acres Is area part of a wildlife corridor? Yes

Adjacent land use: Residential and Recreational

Distance to nearest roadway or development: within 100 feet

Dominant wetland/aquatic systems present: Shrub Swamp, Red Maple Swamp, Wet Meadow, Deep Emergent Marsh, Transitional

Floodplain Forest, Low-gradient Stream, Moderately Alkaline Lakes/Ponds.

Contiguous undeveloped buffer zone present? Yes

Upland communities present: Cultural Grasslands, Northern Hardwoods-Hemlock-White Pine Forest.

Rare species habitat? Yes, NHESP Estimated Habitats and Priority Habitats of Rare species

Site I.D.: Area 5A-2

Latitude: 42.426964 Longitude: -73.234915

Prepared by: Julia Stearns Date: 6/21/2023

Wetland Impact

**Type:** Shrub Swamp, Wet Meadow, Deep Emergent Marsh, Floodplain Forest

Area: 140 acres

Evaluation based on:

Office: Yes Field: Yes Delineation completed? No

Function/Value		Suitability		Deticable (Defended #*)	Principle	Comments		
		Υ	N	Rationale (Reference #*)	F/V	Comments		
Ā	Groundwater Recharge/Discharge		х	1, 5, 6, 7, 9	F	Wetlands meet some of the qualifiers though water quality may no be considered high.		
-	Floodflow Alteration	х		1, 2, 3, 6, 7, 8, 10, 13, 14, 15, 18	F	Wetlands relatively flat, receive and detain excessive flood water from adjacent river.		
-	Fish and Shellfish Habitat	Х		1, 2, 4, 6, 7, 8, 9, 10, 11, 12, 14, 15, 16, 17	F	Stream width greater than 50', wetlands are part of a larger, contiguous watercourse.		
*	Sediment/Toxicant Retention	х		1, 2, 3, 4, 5, 6, 8, 10, 12, 14, 16	F	Known sources of toxicants in watershed above the wetland.		
*	Nutrient Removal	Х		4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14.	F	Sources of excess nutrients present in watershed		
•	Production Export	х		1, 2, 4, 7, 8, 10, 12	F	High degree of plant community structure, flowering plants used be nectar-gathering insects.		
2	Sediment/Shoreline Stabilization	Х		1, 2, 3, 4, 5, 6, 7, 8. 9, 10, 11, 12, 14, 15, 16	F	Dense vegetation, fine grained mineral and organic soils present.		
-	Wildlife Habitat	х		3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 22,	F	Animal signs observed, high degree of plant species diversity and diversity of plant community structure, wildlife food sources.		
A	Recreation	х		1, 4, 5, 7, 8, 9, 10, 11, 12	v	Wetlands are a part of Canoe Meadow Wildlife Sanctuary.		
4	Educational/Scientific Value	х		1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 12, 14, 16	v	Wetlands are associated with and within wildlife sanctuary.		
×	Uniqueness/Heritage	х		1, 4, 5, 6, 7, 11, 12, 22, 24,	v	Value is high for wildlife and opportunities are present for visual observations available.		
CIES	Visual Quality/Aesthetics	Х		1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12	V	Wetlands associated with wildlife sanctuary with access paths.		
ES	Endangered Species Habitat	х		1, 2	V	Wetlands contain threatened/endangered species and contains critical habitat for state listed species.		
	Other							

\*See USACE NED 1995. Highway Methodology Workbook, Wetland Functions and Values, A Descriptive Approach

## Form FP-2: Wetland Function-Value Evaluation Form Project Name: GE/Housatonic River

Total area of Evaluation Unit: ~330 acres

Is area part of a wildlife corridor? Yes

Adjacent land use: Residential, Agricultural, Utilities

Distance to nearest roadway or development: Within approx.. 0.25 miles

Dominant wetland/aquatic systems present: Transitional Floodplain Forest, Red Maple Swamp, Wet Meadow, Deep Emergent

Marsh, Low-gradient stream.

Contiguous undeveloped buffer zone present? Yes

Upland communities present: Agricultural Fields, Successional Northern Hardwoods, Northern Hardwoods-Hemlock-White Pine

Fores

Rare species habitat? Yes, NHESP Estimated Habitats and Priority Habitats of Rare species

Site I.D.: Area 5A-3

**Latitude:** 42.416193 **Longitude:** -73.239080

Prepared by: Julia Stearns Date: 6/21/2023

Wetland Impact

**Type:** Transitional Floodplain Forest, Red Maple Swamp, Shrub Swamp, Wet Meadow, Deep

Emergent Marsh.

Area: 330 acres

Evaluation based on:

Office: Yes Field: Yes Delineation completed? No

	From atting A / along	Suita	bility	Detica de (Defense de 4*)	Principle	Comments		
Function/Value		Υ	N	Rationale (Reference #*)	F/V	Comments		
Ţ	Groundwater Recharge/Discharge		х	1, 5, 6, 7, 9	F	Associated wetlands meet some of the qualifiers though water quality may not be considered high.		
-	Floodflow Alteration	х		2, 3, 6,7,8,9,10,11, 13, 14, 18	F	Wetlands relatively flat, receives and detains excessive flood water from adjacent river.		
•	Fish and Shellfish Habitat	х		1, 2, 4, 6, 7, 8, 9, 10, 11, 12, 14, 15, 16, 17	F	Stream width greater than 50', wetlands are part of a larger, contiguous watercourse.		
*	Sediment/Toxicant Retention	Х		1, 2, 3, 4, 5, 6, 8, 10, 12, 14, 16	F	Known sources of toxicants in watershed above the wetland		
-	Nutrient Removal	Х		4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14.	F	Sources of excess nutrients present in watershed		
•	Production Export	х		1, 2, 4, 7, 8, 10, 12	F	Wildlife food sources, high degree of plant community structure, flowering plants used by nectar-gathering insects		
	Sediment/Shoreline Stabilization	х		1, 2, 3, 4, 5, 6, 8, 10, 12, 14, 16	F	Dense vegetation, fine grained mineral and organic soils present.		
-	Wildlife Habitat	х		3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 22,	F	Animal signs observed, high degree of plant species diversity and diversity of plant community structure, wildlife food sources.		
A	Recreation	Х		4, 5, 7, 9	v	Walking path present, public use present.		
4	Educational/Scientific Value		х	1, 3, 5	v	No potential education sites available though walking path is present.		
×	Uniqueness/Heritage	х		1, 4, 5, 6, 7, 11, 12, 22, 24,	V	Value is high for wildlife though no opportunity for visual observations available.		
(#)	Visual Quality/Aesthetics		х	4, 6, 8	V	No public parking available and no real viewing locations available		
ES	Endangered Species Habitat	Х		1, 2	V	Wetlands contain threatened/endangered species and contains critical habitat for state listed species.		
	Other							

See USACE NED 1995. Highway Methodology Workbook, Wetland Functions and Values, A Descriptive Approach



## Appendix F Vernal Pool Information

- 1. Vernal Pool Photo Log (2018-2019)
- 2. Form VP-1 Vernal Pool Characterization Form (Blank)



F-1 Vernal Pool Photo Log (2018-2019)

#### **PHOTOGRAPHIC LOG**

Client Name: General Electric Company, Pittsfield, MA

Site Location: Housatonic River Reach 5A BRA 60670015

Photo No. 1 Date: Photo No. 2 Date: 4/26/19

**Description:** View of Vernal Pool 5A-VP-1 looking West 
Description: View of Vernal Pool 5A-VP-1A looking North





Photo No. 3 Date: 4/23/19 Photo No. 4 Date: 4/17/18

**Description:** View of Vernal Pool 5A-VP-1B looking North **Description:** View of Vernal Pool 5A-VP-2 looking North





#### **PHOTOGRAPHIC LOG**

Client Name:General ElectricSite Location:Housatonic River Reach 5A BRAProject No.Company, Pittsfield, MA60670015

Photo No. 5 Date: 5/23/18 Photo No. 6 Date: 4/26/18

**Description:** View of Vernal Pool 5A-VP-3 looking North **Description:** View of Vernal Pool 5A-VP-4 looking West





 Photo No. 7
 Date: 4/26/18
 Photo No. 8
 Date: 4/26/18





#### **PHOTOGRAPHIC LOG**

Client Name:General ElectricSite Location:Housatonic River Reach 5A BRAProject No.Company, Pittsfield, MA60670015

Photo No. 9 Date: 5/23/18 Photo No. 10 Date: 4/13/19

**Description:** View of Vernal Pool 5A-VP-7 looking West 
Description: View of Vernal Pool 5A-VP-8 looking West





 Photo No. 11
 Date: 4/10/19
 Photo No. 12
 Date: 4/26/18

**Description:** View of Vernal Pool 5A-VP-9 looking West 
Description: View of Vernal Pool 5A-VP-10 looking North





#### **PHOTOGRAPHIC LOG**

Client Name:General ElectricSite Location:Housatonic River Reach 5A BRAProject No.Company, Pittsfield, MA60670015

Photo No. 13 Date: 6/9/09 Photo No. 14 Date: 7/10/19

**Description:** View of Vernal Pool 5A-VP-12 looking West 
Description: View of Vernal Pool 5A-VP-13 looking West





**Photo No. 15 Date:** 5/2/19 **Photo No. 16 Date:** 4/13/19

Description: View of Vernal Pool 5A-VP-14 looking North Description: View of Vernal Pool 5A-VP-15 looking

Northwest





#### **PHOTOGRAPHIC LOG**

**Project No.** 60670015 Client Name: General Electric Site Location: Housatonic River Reach 5A BRA Company, Pittsfield, MA

Photo No. 17 **Date:** 4/13/19 Photo No. 18 Date: 4/13/19

Description: View of Vernal Pool 5A-VP-15A looking

West

Description: View of Vernal Pool 5A-VP-16 looking North





Photo No. 19 **Date:** 4/26/18 Photo No. 20 **Date:** 4/13/19

Description: View of Vernal Pool 5A-VP-18 looking West **Description:** View of Vernal Pool 5A-VP-18A looking East





#### **PHOTOGRAPHIC LOG**

Client Name:General ElectricSite Location:Housatonic River Reach 5A BRAProject No.Company, Pittsfield, MA60670015

Photo No. 21 Date: 4/25/19 Photo No. 22 Date: 4/26/18

**Description:** View of Vernal Pool 5A-VP-19 looking North **Description:** View of Vernal Pool 5A-VP-20 looking North





Photo No. 23 Date: 4/23/19 Photo No. 24 Date: 4/26/18

**Description:** View of Vernal Pool 5A-VP-21 looking South **Description:** View of Vernal Pool 5A-VP-22 looking North





#### **PHOTOGRAPHIC LOG**

Client Name:General ElectricSite Location:Housatonic River Reach 5A BRAProject No.Company, Pittsfield, MA60670015

Photo No. 25 Date: 5/14/18 Photo No. 26 Date: 4/23/19

**Description:** View of Vernal Pool 5A-VP-24 looking West **Description:** View of Vernal Pool 5A-VP-26 looking West





**Photo No. 27 Date:** 5/1/18 **Photo No. 28 Date:** 4/23/19

**Description:** View of Vernal Pool 5A-VP-27 looking West **Description:** View of Vernal Pool 5A-VP-28A looking

North





#### **PHOTOGRAPHIC LOG**

Client Name:General ElectricSite Location:Housatonic River Reach 5A BRAProject No.Company, Pittsfield, MA60670015

 Photo No. 29
 Date: 5/14/18
 Photo No. 30
 Date: 5/14/18

Description: View of Vernal Pool 5A-VP-32 looking

Northwest

Description: View of Vernal Pool 5A-VP-33 looking

Northeast





Photo No. 31 Date: 4/23/19 Photo No. 32 Date: 5/1/18

**Description:** View of Vernal Pool 5A-VP-36 looking West





#### **PHOTOGRAPHIC LOG**

Client Name: General Electric **Project No.** 60670015 Site Location: Housatonic River Reach 5A BRA Company, Pittsfield, MA

Photo No. 33 **Date:** 5/1/18 Photo No. 34 **Date:** 5/1/18

**Description:** View of Vernal Pool 5A-VP-40 looking West

Description: View of Vernal Pool 5A-VP-42 looking East





Photo No. 35 **Date:** 4/25/19 Photo No. 36 **Date:** 5/3/18

Description: View of Vernal Pool 5A-VP-49A looking East **Description:** View of Vernal Pool 5A-VP-50 looking West





#### **PHOTOGRAPHIC LOG**

Client Name:General ElectricSite Location:Housatonic River Reach 5A BRAProject No.Company, Pittsfield, MA60670015

Photo No. 37 Date: 5/14/18 Photo No. 38 Date: 5/14/18

**Description:** View of Vernal Pool 5A-VP-52 looking North **Description:** View of Vernal Pool 5A-VP-54 looking West





 Photo No. 39
 Date: 9/17/18
 Photo No. 40
 Date: 5/14/18

Description: View of Vernal Pool 5A-VP-55 looking West Description: View of Vernal Pool 5A-VP-57 looking

Southwest





#### **PHOTOGRAPHIC LOG**

Client Name:General ElectricSite Location:Housatonic River Reach 5A BRAProject No.Company, Pittsfield, MA60670015

Photo No. 41 Date: 7/10/19 Photo No. 42 Date: 4/27/18

Description: View of Vernal Pool 5A-VP-59A looking

North

**Description:** View of Vernal Pool 5A-VP-60 looking

Southeast





Photo No. 43 Date: 4/27/18 Photo No. 44 Date: 4/27/18

Description: View of Vernal Pool 5A-VP-61 looking

Southeast

**Description:** View of Vernal Pool 5A-VP-62 looking North





#### **PHOTOGRAPHIC LOG**

Client Name:General ElectricSite Location:Housatonic River Reach 5A BRAProject No.Company, Pittsfield, MA60670015

Photo No. 45 Date: 5/14/18 Photo No. 46 Date: 5/1/18

**Description**: View of Vernal Pool 5A-VP-63 looking West **Description**: View of Vernal Pool 5A-VP-64 looking West





Photo No. 47Date: 5/1/18Photo No. 48Date: 4/27/18Description: View of Vernal Pool 5A-VP-65 looking NorthDescription: View of Vernal Pool 5A-VP-69 looking

Southwest





#### **PHOTOGRAPHIC LOG**

Client Name:General ElectricSite Location:Housatonic River Reach 5A BRAProject No.Company, Pittsfield, MA60670015

Photo No. 49 Date: 4/27/18 Photo No. 50 Date


Northwest





Photo No. 51 Date: 5/14/18 Photo No. 52 Date: 5/14/18

**Description:** View of Vernal Pool 5A-VP-72 looking West **Description:** View of Vernal Pool 5A-VP-73 looking West





#### **PHOTOGRAPHIC LOG**

Client Name:General ElectricSite Location:Housatonic River Reach 5A BRAProject No.Company, Pittsfield, MA60670015

Photo No. 53 Date: 5/14/18 Photo No. 54 Date: 4/27/18

Description: View of Vernal Pool 5A-VP-73A looking

North

**Description:** View of Vernal Pool 5A-VP-74 looking

Southeast





Photo No. 55 Date: 5/3/18 Photo No. 56 Date: 5/2/18

Description: View of Vernal Pool 5A-VP-77 looking North

Description: View of Vernal Pool 5A-VP-79 looking

Southeast





#### **PHOTOGRAPHIC LOG**

**Project No.** 60670015 Client Name: General Electric Site Location: Housatonic River Reach 5A BRA Company, Pittsfield, MA

Photo No. 57 **Date:** 5/2/18 Photo No. 58 **Date:** 5/2/18

Description: View of Vernal Pool 5A-VP-80 looking

Northwest

Description: View of Vernal Pool 5A-VP-81 looking South





Photo No. 59 **Date:** 5/2/18 Photo No. Date: Description: View of Vernal Pool 5A-VP-83 looking Description: Southwest





F-2. Form VP-1 Vernal Pool Characterization Form (Blank)

## Form VP-1: Vernal Pool Characterization Form<sup>1</sup> Pool ID \_\_\_\_\_ Observers: \_\_\_\_\_ Location of vernal pool: Survey date(s): Coordinates (decimal degrees) Latitude(X): \_\_\_\_\_ Longitude (Y): \_\_\_\_\_ A. General Vernal Pool Characteristics 1. Landscape setting (check all that apply) [ ] Discrete depression in floodplain [ ] Pool part of a larger wetland [ ] Pool part of a pool network ( \_\_\_\_ pools within 1000 feet) 2. Vernal pool condition (describe any recent modification to the pool, including natural changes such as beaver impoundments): \_\_\_\_\_ 3. Describe the aquatic resource type(s) in pool (e.g., forested, scrub-shrub, etc.) -4. Pool canopy cover (%): \_\_\_\_\_ 5. Predominant substrate (e.g., mineral soil, organic matter): 6. Pool measurements: a. Approximate pool dimensions at maximum inundation condition (include units): Length \_\_\_\_\_ Width: \_\_\_\_ Area: \_\_\_\_ b. Maximum water depth at deepest point (include units): \_\_\_\_\_ 7. Hydrology a. Estimated month pool dries, or if never: \_\_\_\_\_\_ b. Inlet/outlet (none, temporary, permanent): \_\_\_\_\_ 8. Water quality (clear, high turbidity, high algal content, tannic): \_\_\_\_\_\_

 $<sup>^{\</sup>rm 1}$  Adapted from USACE New England Division Vernal Pool Characterization Form

	% Cover:	Trees (> 20')	Shrubs (< 20')	Woody vine	es Mo	sses	Herbaceous					
	Plant Lists (species that comprise 10% or more of the vegetative cover in each stratum or any amount of an invasive plant species; "*" designates a dominant plant species for the stratum):											
	Strata	Plant Species		Strata	Plant Spe	ecies						
<b>)</b> .	Soil/Subst	rate Composition										
<b>)</b> .	Soil/Subst	•		Drainage Cla	ss							
Э.		nit		Drainage Cla	ss							
Э.	Soil Survey Un	nit			ss							
	Soil Survey Un	r part)	Color	Depth	ss	Mottli	ng					
	Soil Survey Un Texture (uppe	r part) ative Soil Pit Log	Color	Depth		Mottlii	ng					
	Soil Survey Un Texture (uppe	r part) ative Soil Pit Log	Color	Depth		Mottli	ng					
	Soil Survey Un Texture (uppe	r part) ative Soil Pit Log	Color	Depth		Mottli	ng					

## D. In-Pool Physical Habitat Structure Describe physical structure in the vernal pool which may contribute to vernal pool habitat functions: [] Coarse woody debris % cover: Describe [] Fine woody debris \_\_\_\_\_\_% cover: Describe \_\_\_\_\_ [] Shrub and herbaceous stems \_\_\_\_\_%: Describe \_\_\_\_\_ [] Wind-thrown trees and/or root wads \_\_\_\_\_%: Describe \_\_\_\_\_ [] Hummocks \_\_\_\_\_%: Describe \_\_\_\_\_ [] Other \_\_\_\_\_%: Describe \_\_\_\_\_ E. Surrounding Land Use 1. Vernal Pool Envelope (0-100 feet from pool edge)<sup>2</sup> [] Forested \_\_\_\_\_% [] Shrub \_\_\_\_\_% [] Open (e.g., meadow, agriculture, golf course) \_\_\_\_\_% Developed (includes area beyond barriers) \_\_\_\_\_% 2. Critical Terrestrial Habitat (100-750 ft from pool edge)<sup>3</sup> [] Forested \_\_\_\_\_% [] Shrub \_\_\_\_\_% [] Open (e.g., meadow, agriculture, golf course \_\_\_\_\_ % [] Developed (includes area beyond barriers) \_\_\_\_% \_ F. General Water and Soil Chemistry (for selected pools only) 1. Water Quality 2. Soil []pH\_\_\_\_ []pH\_\_\_\_ [] Organic Carbon Content \_\_\_\_\_ [] Temperature \_\_\_\_\_ [] Conductivity \_\_\_\_\_ [] Dissolved Oxygen\_\_\_\_\_

 $<sup>^{\</sup>rm 2}$  As defined by Calhoun and Klemens (2002).

<sup>&</sup>lt;sup>3</sup> As defined by Calhoun and Klemens (2002).



## Appendix G Rare Species Information

#### Appendix G: Rare Species Information

To identify federally listed threatened or endangered species in Reach 5A, the U.S. Fish and Wildlife Service (USFWS) on-line Information, Planning, and Consultation System (IpaC) was consulted in August 2023. That review identified only one federally listed rare species as potentially occurring within the limits of Reach 5A – the northern long-eared bat (*Myotis septentrionalis*). It also identified one candidate species (under consideration for federal listing) – the monarch butterfly (*Danaus plexippus*) – as potentially occurring within the Reach 5A area.

State-listed species and their habitats in Reach 5A were determined based upon information provided by MNHESP. In October 2022 MNHESP provided GE with digital information presenting its delineation of state-listed species habitats in Reaches 5 through 8 of the ROR. These individual species maps are referred to as Species Habitat Maps. They are prepared by MNHESP using the "best scientific evidence available," examining individual occurrence records in the context of species listing status and applying certain criteria, as described in Section 8.1.2 of the main Baseline Restoration Assessment Report for Reach 5A.

Table G-1 presents a summary of the state-listed species information generated from the digital data provided by MNHESP. In addition to the Species Habitat mapping provided by MNHESP for 20 state-listed species in Reach 5A, one additional state-listed species (the northern long-eared bat) is also included in the table that was not included in the MNHESP data. MNHESP has advised GE that it will not allow presentation of the Species Habitat Maps by individual species, although GE may report the overall area (i.e., acreage) in Reach 5A mapped for each state-listed species and present a general description of that area. Therefore, Table G-1 also provides the acreage of the Species Habitat map for each of the 20 species for which digital map information was provided. For the northern long-eared bat, the full area of the Reach 5A limits was included in the acreage tabulation based upon the mapping of this species from the USFWS IPaC consultation.

Following Table G-1, a summary is provided for each of the federally or state-listed species, describing the life-cycle and general habitat requirements of each species, along with a discussion of the extent (i.e., acreage) of the mapped Species Habitat for each state-listed species in Reach 5A and a general description of that area and of the observed suitability of Reach 5A to meet the species' habitat requirements based upon the field surveys conducted to date. Most of the life-cycle and habitat information for each state-listed species has been generated from the species fact sheets provided by MNHESP as available on its website. These fact sheets are referenced in the species summaries and also included in the references listed after those summaries along with some additional references for certain species as appropriate. The extent of mapped Species Habitat for each species is taken from the Species Habitat maps provided by MNHESP.

Table G-1: State-Listed Species with Species Habitat Mapping Overlapping Reach 5A as shown on MNHESP Data Provided in October 2022

		State	Area in 5A	Taxonomic
Scientific Name	Common Name	Status	(Acres)	Group
Botaurus lentiginosus	American Bittern	Е	164.0	Bird
Ranunculus pensylvanicus	Bristly Buttercup	SC	29.4	Plant
Ophiogomphus aspersus	Brook Snaketail	SC	240.6	Invertebrate
Gallinula galeata	Common Gallinule	SC	16.2	Bird
Veronicastrum virginicum	Culver's-Root	T	0.1	Plant
Eragrostis frankii	Frank's Lovegrass	SC	25.9	Plant
Carex grayi	Gray's Sedge	Т	27.5	Plant
Rhododendron maximum	Great Laurel	Т	1.7	Plant
Elymus villosus	Hairy Wild Rye	Е	18.9	Plant
Eleocharis intermedia	Matted Spike-Sedge	Т	116.8	Plant
Pieris oleracea	Mustard White	Т	327.4	Invertebrate
Myotis septentrionalis	Northern Long-Eared Bat	E	409.8*	Mammal
Boyeria grafiana	Ocellated Darner	SC	276.8	Invertebrate
Papaipema sp. 2 near pterisi	Ostrich Fern Borer	SC	171.3	Invertebrate
Phanogomphus quadricolor	Rapids Clubtail	Е	55.0	Invertebrate
Ophiogomphus carolus	Riffle Snaketail	Т	191.7	Invertebrate
Hylogomphus abbreviatus	Spine-Crowned Clubtail	S	256.2	Invertebrate
Carex tuckermanii	Tuckerman's Sedge	E	0.9	Plant
Sagittaria cuneata	Wapato	Т	171.2	Plant
Malaxis monophyllos ssp. brachypoda	White Adder's-Mouth	Е	1.6	Plant
Glyptemys insculpta	Wood Turtle	SC	396.3	Reptile

<sup>\*</sup>The acreage of the Northern Long-Eared Bat is derived from the IPaC data, since no Species Habitat map for this species was provided by MNHESP.

#### **GENERAL INFORMATION ON LISTED RARE SPECIES**

#### American Bittern (Botaurus lentiginosus)

Summary of Species Life Cycle and Habitat Requirements

The American Bittern (*Botaurus lentiginosus*) is a wading bird that inhabits freshwater wetlands, spending most of its time secretly dwelling in marshland emergent vegetation. The American Bittern is an Endangered Species under the Massachusetts Endangered Species Act (MESA) (NHESP 2020). It is a brown, streaked, medium sized (23-34 inches long) heron that hides among emergent vegetation including sedges, rushes, and grasses. It has pale yellow or yellowish-green bill, legs, and feet, and a buff-colored stripe over its yellow eyes. Its wingspan is 32 to 50 inches with black wingtips easily identified in flight. In Massachusetts, the American Bittern inhabits freshwater meadows, marshes, fens, and bogs dominated by cattails, bulrushes, sedges, and grasses, and may also be found in brackish wetlands. It prefers expansive areas of contiguous wetlands but will occasionally utilize upland grasslands for foraging and nesting. Its slow and stealthy walk and characteristic motionless stance with bill pointed upwards when startled, enhance its resemblance to marsh vegetation or debris, a camouflage which the American Bittern relies on to escape notice by predators, or with slowly aimed bill, strike and seize unsuspecting prey. Preferred foods include frogs, small snakes and eels, salamanders, crayfish, fish, and occasionally mice and grasshoppers caught on visits to wet meadows and grasslands.

The American Bittern migrates from its winter habitat in the southern United States and arrives in Massachusetts marshes in April. Courtship behavior includes aerial and ground chases with males stalking females, displaying their white plumes and calling in loud, guttural "pumps." Courtship calls stop by the end of May, and the female builds a nest of dead reeds, cattails, grasses and sedges about 1 foot in (30 cm) in diameter on the ground in dense vegetation. American Bitterns prefer marshes for nesting sites and are known to also construct nesting platforms of vegetation a foot above water. They will occasionally nest in uplands adjacent to wetlands. American Bitterns have shown relatively high site fidelity (Azure 1998). Males appear territorial during the breeding season and stay close to the nest site. They may be polygonous. Females care for the young. A clutch will typically have 4 to 5 eggs that will hatch within 24 to 29 days. The chicks become fledglings after 14 days and by the end of the summer, juvenile American Bitterns begin to wander away from the nest. There is only one clutch per year with the female continuing to tend to her young for an undetermined length of time after they leave the nest. American Bitterns may winter as far north as the east coast of Massachusetts. Migration to habitats in the southern U.S. occurs during October and November, and by December, most American Bitterns have left Massachusetts. The American Bittern has been reported from many towns of Berkshire County, including Pittsfield and Lenox, as well as across Massachusetts (MNHESP 2015).

#### American Bittern Habitat in Reach 5A

According to 2022 MNHESP database information, Species Habitat for the American Bittern occurs in Reach 5A totaling 164 acres in three general areas. One area is located downstream of the Confluence on the west side of the River. A larger habitat area is located to the east of the River associated with the marshes of Canoe Meadows and south to Sykes Brook. The largest of the three

habitat areas within Reach 5A is located to the west of the River, extending from across Sackett Brook along the river corridor to the south to marshes on the north side of the Pittsfield WWTP. The collective assemblage of the habitat types included in the mapped Species Habitat areas for the American Bittern provides conditions suitable for various life-cycle functions of this species, including courtship, nesting, resting, cover, and foraging. The diversity and complex juxtaposition of the varied habitats in Reach 5A are expected to promote a broad distribution of the American Bittern throughout the mapped Species Habitat for these various functions; there are no specific habitat cover types in these mapped areas that would be incompatible with the needs of and use by this species.

### Bristly Buttercup (Ranunculus pensylvanicus)

#### Summary of Species Life Cycle and Habitat Requirements

Bristly Buttercup (Ranunculus pensylvanicus) is an annual or short-lived perennial member of the Buttercup family (Ranunculus). Bristly Buttercup is a Species of Special Concern under the Massachusetts Endangered Species Act (MESA) (NHESP 2020). Bristly Buttercup is differentiated from other buttercups by its leaves, hairy (pubescent) stem, flowers and fruits. Leaves are alternate, toothed, and trifoliate with three deeply cut lobes. Stiff, bristly, spreading hairs cover the tall branched or unbranched stems (1 to 2.25 ft), creating a distinctive pubescence. The small, pale yellow flowers (0.6 to 0.8 cm wide) form on short stalks and are composed of 5 egg-shaped petals which turn whitish over time. The achenes (small dry fruits) have short, stout, but not hooked, appendages projecting from their tips that form a short cylindrical cluster (0.8 cm to 1.3 cm long). In Massachusetts, Bristly Buttercup flowers from the beginning of July through September. Bristly Buttercup is not typically capable of spreading vegetatively, although is able to colonize a variety of habitats through seed dispersal by water and wildlife. The successful germination of its seeds and seedling establishment are critical to its persistence. Suitable habitats for colonization have open to filtered light and wet to periodically flooded conditions including marshes, bogs, moist clearings, wet woods, stream banks, and ditches. Bristly Buttercup may often inhabit disturbed riverbanks and managed wetland communities in utility corridors, as well as other disturbed areas. Massachusetts populations have been documented in marsh edges, vernal pools, seasonally flooded riverbanks, wet swales, drawn down glacial kettle holes, shrub swamps, and edges of or openings in floodplain forests. Bristly Buttercup populations are currently known to occur in Berkshire County in the towns of Pittsfield, Lenox, Sheffield, and New Marlborough; and 14 towns from Hampden and Worcester Counties (MNHESP 2015).

#### Bristly Buttercup Habitat in Reach 5A

According to 2022 MNHESP database information, the Species Habitat of the Bristly Buttercup occurs in one area of Reach 5A, approximately 29.36 acres in size in the central portion of Reach 5A to the west of the Housatonic River. This area contains riverbank and a diversity of floodplain habitats conducive to the growth of the Bristly Buttercup, including floodplain forests, wet meadows, shallow emergent marshes, and shrub swamps. Due to the ability of Bristly Buttercup to grow successfully in many different wetland and floodplain habitats, it could potentially be found within any of the habitat types which have been mapped by MNHESP (other than any strictly aquatic habitat in Reach

5A), and most of the mapped Species Habitat appears suitable for this species. In addition, due to the annual nature of this species, plants may not always occur in the same areas from year to year.

#### **Brook Snaketail (Ophiogomphus aspersus)**

#### Summary of Species Life Cycle and Habitat Requirements

The Brook Snaketail (*Ophiogomphus asperus*) is a dragonfly member of the Gomphidae family known as the clubtails. It is a Species of Special Concern under the Massachusetts Endangered Species Act (MESA) (MNHESP 2020). Clubtails have small, widely separated compound eyes that distinguish it from most other dragonflies. The name clubtail derives from the lateral swelling near the end of the abdomen that appears "club-like". The extent of the swelling or club varies greatly depending on the species. Males generally have a larger club than females. Although unknown, the club may have use in courtship displays or enhance the aerodynamics of flight. The Brook Snaketail belongs to the genus Ophiogomphous which are snaketails that characteristically exhibit a brilliant green thorax, eyes, and face. The club of the Brook Snaketail is over half the width of its thorax. Pale green to yellow markings that run down the sides of the black to dark brown abdomen are largest at the club, while wide, yellow, dagger shaped markings run down the center of the top of the abdomen. The clear wings display a dense network of veins and are held horizontally in the characteristic horizontal perching stance of the Brook Snaketail on rocks, logs, vegetation, and the ground. Adult Brook Snaketails are 1.7-1.8 inches in length. The female is larger and has a smaller club near the tip of the abdomen than the male.

Two distinct stages complete the life cycle of the dragonfly after hatching from an egg including an aquatic larval or nymph stage and a flying adult stage. The nymphs of the Brook Snaketail prefer sandy substrates in clear running water, and have a relatively high oxygen requirement among this family (Hart and Fuller 1974, Merritt and Cummins 1978, NHESP 2008). A near-neutral to slightly basic pH is preferred. Nymphs are found near the surface of the sediment (within the upper inch), where they develop over at least a year-long period, possibly two to three years. Brook Snaketail nymphs spend most of their time burrowing in the sand which protects them from predators. It also camouflages them as they are ambush predators, attacking a variety of aquatic life from passing insects to small fish and tadpoles. When ready to emerge as adults, typically in the last half of May, nymphs climb onto open sandy to gravelly banks and rocks or woody debris, the exoskeleton splits, and adults emerge. The newly emerged adult, or teneral dragonfly, is very soft and vulnerable, and can be damaged by rain showers, falling debris, or predators. As soon as the wings are dry and strong enough, the adult Brook Snaketail flies into adjacent woodland or shrubland that surround the breeding habitat to find safe shelter among the leaves and branches of trees where it can continue to develop. The maturation process of the new adult dragonflies occurs during the following week as they wander from woodland to forest clearings and fields, feeding on small aerial insects such as flies and mosquitos. With completion of the maturation process, the adults return to the stream to breed. The male Brook Snaketail patrols the water and stream banks to search for potential mates and to drive out competing males. This family is typically a "short flight" species requiring substantial perching places as they move along the stream, usually woody debris, live woody plants, and rocks. Females return to the stream only briefly when they are ready to mate and release eggs singly or in small clusters through ovipositors by repeatedly touching their abdomens to the water surface in riffle zones while flying back and forth.

In Massachusetts, the Brook Snaketail is thought to breed from early June through late August. The eggs incubate over one to two weeks and hatch into larvae which re-initiate the life cycle. Adults may live out the rest of the summer far from the stream, often in dense woodland or shrubland. In Massachusetts, the flight period of the adult is mid-May through August. The Brook Snaketail has not been found in large numbers in Massachusetts (MNHESP 2015). Despite the current Brook Snaketail Species Habitat mapping from MNHESP extending throughout Reach 5A of the ROR, the MNHESP (2015) Brook Snaketail fact sheet shows this species to be distributed only in central Massachusetts west to the Connecticut River valley, with no towns in Berkshire County indicated in the MNHESP distribution map of this species.

#### Mapped Species Habitat in Reach 5A

According to 2022 MNHESP database information, mapped Species Habitat of the Brook Snaketail occurs in 240.65 acres within Reach 5A, extending from the confluence of the East and West Branches downstream for approximately two miles. The areal extent of the nymph habitat includes the main stem of the river plus the banks for eclosion (emergence as adults). The areal extent of adult habitat is broader and includes the main stem of the river, backwaters, floodplain, and some adjacent upland forests or scrubland. The MNHESP Species Habitat extends into these habitats.

#### Common Gallinule (Gallinula galeata)

#### Summary of Species Life Cycle and Habitat Requirements

The Common Gallinule (*Gallinula galeata*), formerly known as the Common Moorhen, is a duck-like swimming bird that inhabits large freshwater or brackish marshes and water bodies with cattails and other emergent vegetation. The Common Gallinule is a Species of Special Concern under the Massachusetts Endangered Species Act (MESA) (NHESP 2020). It is described as having a length of 13 inches with a wingspan of 21 inches, large yellow unwebbed feet, a black head and neck, and a yellow-tipped red bill that runs up its forehead to form a red shield. Its back is brown, underside is slate-grey, and its short, upturned tail has white outer and black inner undertail feathers. Preferred habitat is shallow bodies of water with dense stands of emergent vegetation interspersed with areas of open water. In Massachusetts, preferred habitats of the Common Gallinule are water bodies that are at least one foot deep with dense cattail beds, and occasionally shrub marsh adjacent to open water with aquatic bed vegetation. Though Common Gallinules prefer emergent wetlands as foraging, breeding, nesting, and protective cover habitat, they also utilize margins of lakes, ponds, and slow-flowing rivers and streams as feeding areas. Using the cover of the dense vegetation at the edges of open water, the wading or dabbling Common Gallinule feeds on grass, sedge seeds, berries, foliage, underwater plants, and duckweed, along with insects, snails, worms, and other invertebrates.

The Common Gallinule migrates from wintering ranges in the southern U.S. to Massachusetts in late April or May. Nesting begins in May to early June. The nest is well-made of dead cattails, rushes, and stems of other aquatic plants. It is built in supportive dense vegetation typically less than 1 foot over water but up to 2 feet where it is well hidden within the surrounding plants, often with a ramp leading from the water. Unfinished nest-like platforms may be found in the vicinity of the nest for

roosting and brooding, and may be used by the young that have left the original nest to spend the night as they wander the marsh. Incubation of the 6-17 eggs (typically 10-12) beginning in late May involves both parents for 3 weeks. As the chicks hatch, they are cared for by the male while the female incubates the remaining eggs, completing hatching by mid-July. The young are precocial and ready to leave the nest within a day of hatching, feed independently after 3 weeks, and fly in 6-7 weeks, however, they remain with their parents for some time thereafter. The Common Gallinule may have one or two broods per year. Although a rare breeder in Massachusetts, this species has been found breeding across the state. There have been twenty-three verified sites in Massachusetts over the past 25 years with most supporting only single breeding pairs. MNHESP's field surveys find the presence of invasive plants, particularly Phragmites, to be the largest limiting factor to current Common Gallinule occupied sites. The flight pattern of the Common Gallinule tends to consist of short, local flights, except during migration when they are found to exhibit a strong site fidelity, returning to familiar grounds (Bannor and Kiviat 2002). Home range sizes for this species are relatively small averaging approximately 3 acres (range of 0.5-8 acres) for nesting adults, and home ranges of 15 acres for non-nesting adults (Bannor and Kiviat 2002). Migration to their wintering range occurs in October. Reported occurrences of the Common Gallinule in Berkshire County are from the towns of Pittsfield, Lenox, Lee, Richmond, Washington, Stockbridge, Egremont, and Sheffield; other reports are from eastern Massachusetts (MNHESP 2019).

#### Common Gallinule Habitat in Reach 5A

According to 2022 MNHESP database information, the Species Habitat of the Common Gallinule occurs in two small areas in Reach 5A, both in marshes north of the Pittsfield WWTP on the west side of the Housatonic River. The mapped Species Habitat for this species in Reach 5A comprises 16.23 acres. The areal extent of habitat includes the backwater deep marshland off the main stem of the river, and nearby shallow marshes.

#### Culver's-root (Veronicastrum virginicum)

#### Summary of Species Life Cycle and Habitat Requirements

Culver's-root (*Veronicastrum virginicum*) is an herbaceous perennial wildflower of tall stature (2.6-6.5 ft) with showy arrays of dense pink or white flowers on several candelabra-like terminal spikes. Culver's-root is a Threatened Species under the Massachusetts Endangered Species Act (MESA) (NHESP 2020). It has several erect unbranched stems with whorls of three to six finely serrate, narrow leaves to tapering terminal spikes (5-15 cm or 2-6 in long) that are densely covered with tubular flowers. In Massachusetts, Culver's-root flowers from the beginning of July through August. In Massachusetts, Culver's-root is found in open habitats created by periodic disturbances such as flooding, mowing, or grazing. Typically, it inhabits moist, open meadows with alkaline soils that often have been previously cultivated. Reported populations have also occurred along a roadside and in a moist utility right-of-way. Sites in which the plant may have been introduced are not regulated. Culver's-root is found in Berkshire County in the towns of Pittsfield, Lenox, Great Barrington, Alford, Egremont, and Sheffield; and one town each in Hampden, Hampshire and Worcester Counties (MNHESP 2015).

#### Culver's-Root Habitat in Reach 5A

According to 2022 MNHESP database information, Species Habitat of the Culver's-root occurs within one small (0.12 acres) of Reach 5A. The habitat is a tiny area located near the Confluence of Reach 5A to the east of the Housatonic River. Culver's-root could potentially be found within the/any of the habitat types which have been mapped by MNHESP (other than any strictly aquatic habitat in Reach 5A), and most of the mapped Species Habitat is suitable for this species.

### Frank's Lovegrass (Eragrostis frankii)

#### Summary of Species Life Cycle and Habitat Requirements

Frank's lovegrass (*Eragrostis frankii*), also known as sandbar lovegrass, is an annual grass species identified by its repeatedly branching clusters on straight stems from about 4 inches up to a foot high. Frank's lovegrass is listed as a Species of Special Concern under the Massachusetts Endangered Species Act (MESA) (NHESP 2020). It has narrow blades measuring 5-13 cm long and 1-3mm wide, and tiny ovate spikelets with typically 3-5 flowers that flower from August- September. In Massachusetts, Frank's lovegrass occurs on sandbars and sandy riverbanks found only along the Housatonic and Connecticut Rivers. Despite the current Frank's Lovegrass Species Habitat mapping from MNHESP extending throughout the southern portion of Reach 5A, the MNHESP (2015) Frank's Lovegrass fact sheet does not show this species occurring in Pittsfield on the MNHESP distribution map, however does show it occurring in Berkshire County in the towns of Lee, Cheshire, Windsor, Richmond, Great Barrington, Alford, Sheffield, and New Marlborough; as well as in eight towns throughout Franklin, Hampshire, and Hampden Counties. Eighteen current occurrences have been verified (MNHESP 2015).

#### Mapped Species Habitat in Reach 5A

According to the 2010 NHESP database information, the Species Habitat mapping for Frank's Lovegrass did not occur in Reach 5A. According to the 2022 MNHESP database information, the Species Habitat mapping for Frank's Lovegrass now covers the lower half of Reach 5A, as well as further downstream as in 2010. The mapped Species Habitat for Frank's lovegrass is composed of river channel, including sandbars within the river, riverbank, and some floodplain habitat, and totals approximately 25.90 acres in size along a roughly 2.5-mile stretch of the River in the downstream end of Reach 5A. This species prefers sandy substrate within or at edges of the river channel. Based upon the recent surveys of habitat conditions along the Housatonic River in Reach 5A, suitable conditions to support the growth of Frank's Lovegrass appear to occur throughout this portion of Reach 5A.

### Gray's Sedge (Carex grayi)

#### Summary of Species Life Cycle and Habitat Requirements

Gray's Sedge (Carex grayi) is a perennial member of the sedge family (Cyperaceae) that is a clump forming plant with an identifying striking 'spiked-ball looking' flower created by a spherical flowering spike comprised of inflated perigynia radiating outward in all directions. Gray's sedge is a Threatened Species under the Massachusetts Endangered Species Act (MESA) (NHESP 2020). Gray's Sedge grows as clusters of solitary or multiple stems with short rhizomes up to about 3.6 feet high.

The culms (reproductive stems) are triangular and each has a staminate spike above one or two pistillate spikes. Achenes (dry, indehiscent, one-seeded fruit) develop within the perigynia following flowering. Mature perigynia are present throughout most of the summer, from mid-June through September. It has broad (4 to 11 mm wide), pale green to gray-green leaves with loose, persistent purplish-red sheaths at the base.

Gray's Sedge is found in rich, mesic soils of forests, calcareous seepage swamps. marshes, banks, and wet meadows, usually within riparian systems. In Massachusetts, Gray's Sedge inhabits the moist alluvial soils of floodplain forests and adjacent meadow edges of large rivers. More specifically, many current populations of Gray's Sedge in the state are found along oxbows within floodplain forests or in low depression or swales where they prefer lower slopes and bottoms. Despite the current Gray's Sedge Species Habitat mapping from MNHESP shown in the southern portion of Reach 5A of the ROR, the MNHESP (2015) Gray's Sedge fact sheet does not show this species occurring in Pittsfield on the MNHESP distribution map, however does show it occurring in Berkshire County in the towns of Lenox and Sheffield; and in six towns throughout Franklin, Hampshire and Hampden Counties (MNHESP 2015).

#### Gray's Sedge Habitat Reach 5A

According to 2022 MNHESP database information, the Species Habitat for Gray's Sedge within Reach 5A occurs in 27.5 acres of floodplain wetland along a roughly one-mile section of the River north of the Pittsfield WWTP. The mapped Species Habitat in Reach 5A consists primarily of shrub swamp and floodplain forest communities, but also includes some portions of the river channel, riverbanks, and backwaters. As described above, the Gray's Sedge is able to grow successfully in many different wetland and floodplain habitats, therefore most of the mapped Species Habitat, with the exception of the permanently inundated riverine and backwater habitat, appears suitable for this species.

### **Great Laurel (***Rhododendron maximum***)**

#### **Summary of Species Life Cycle and Habitat Requirements**

Great Laurel (*Rhododendron maximum*) is an evergreen shrub or small tree that grows up to 33 ft high belonging to the Ericaceae or Heath family. Great Laurel is a Threatened Species under the Massachusetts Endangered Species Act (MESA) (NHESP 2020). Its leathery evergreen leaves are 3-8 inches long, smooth-margined, alternate, wider above the middle, and vary in color with dark green on top and paler green underneath. The underside of the leaves and young branchlets are pubescent. The flower of Great Laurel is a pink to white, five-lobed calyx having yellow or orange spots on its inner surface. It measures about 1.5 inches long and is clustered on sticky pedicels of terminal inflorescences forming a dome shape. In Massachusetts, Great Laurel flowers from late June to mid-July.

Great Laurel grows best in filtered light in moist woods, swamps, and pond edges. In Massachusetts, its habitats have been observed to include a boggy swamp edge, an Atlantic White Cedar swamp near an open pond, a forested seepage fen where peat is forming and very cold, nutrient-poor water seeps to the surface, and the edge of a red maple swamp. Despite the current Great Laurel Species Habitat mapping from MNHESP shown in the central portion of Reach 5A of the ROR, the MNHESP

(2015) Great Laurel fact sheet does not show this species occurring in Pittsfield on the MNHESP distribution map, however does show it occurring in Berkshire County in the towns of Savoy, Peru, Richmond, Egremont, and Otis; and in 8 towns throughout Hampshire, Franklin, Worcester, Norfolk, Counties (MNHESP 2015).

#### **Great Laurel Habitat in Reach 5A**

According to 2022 MNHESP database information, the Species Habitat for Great Laurel occurs within a single small (1.72 acres) area of Canoe Meadows east of the River in Reach 5A. The mapped Species Habitat in Reach 5A consists primarily of shrub swamp and floodplain forest communities, but also includes some portions of the river channel, riverbanks, and backwaters.

### Hairy Wild Rye (Elymus villosus)

#### Summary of Species Life Cycle and Habitat Requirements

Hairy Wild Rye (*Elymus villosus*) is a native perennial, tufted grass in the family Poaceae distinguished by its bristly, white pubescent "bottle-brush" inflorescence. Hairy wild rye is an Endangered Species under the Massachusetts Endangered Species Act (MESA) (MNHESP 2020). It grows to just over a meter high with stems topped by an elongate, often arching terminal spike (inflorescence) which is densely covered with whitish villous pubescence, creating the very bristly appearance distinctive of Hairy Wild Rye. Spikelets form tightly within the typically arching spike. Each spikelet has 1 or 2 florets containing a mature single seeded fruit or grain for much of the summer (mid-June through September). Its dark green, evenly distributed leaf blades are 4-12 millimeters wide with a dense villous upper surface.

Hairy Wild Rye is found in floodplain forests, rich moist thickets, and rocky woodlands. In Massachusetts, Hairy Wild Rye inhabits high terrace floodplain forests with moist alluvial soils, and moist to dry, rich, rocky open woods and thickets. Hairy Wild Rye is currently known from Berkshire County in the towns of Pittsfield, Great Barrington, and Sheffield, and Worcester County (MNHESP 2015).

#### Hairy Wild Rye Habitat in Reach 5A

According to 2022 MNHESP database information, Species Habitat of hairy wild rye occurs in the central portion of Reach 5A northeast of the City of Pittsfield Wastewater Treatment Facility on the west side of the Housatonic River. Hairy Wild Rye Species Habitat comprises approximately 18.90 acres. The areal extent of the mapped Species Habitat includes the riverbanks as well as forested, shrub swamp, and emergent marsh areas in the floodplain. The Species Habitat contains high quality habitat suitable for Hairy Wild Rye. Specific occurrences of Hairy Wild Rye have been reported within the forested floodplain habitat in Reach 5A (Woodlot 2002).

### Matted Spike-sedge (Eleocharis intermedia)

#### Summary of Species Life Cycle and Habitat Requirements

The Matted Spike-sedge (*Eleocharis intermedia*), formerly known as the Intermediate Spike-sedge, is an annual herb belonging to the Sedge Family. The Matted Spike-sedge is a Threatened Species under the Massachusetts Endangered Species Act (MESA) (MNHESP 2020). The Matted Spike-sedge

is a small, tufted plant, about 2-10 inches tall with thin, wiry, leafless-looking stems of different lengths that typically clump together to form the appearance of a mat as shorter stems stand erect and taller stems bend and lay horizontally. The very slender, round stem has a single vertical groove up it and only leaf sheaths surround it, no leaf blades, which gives its leafless appearance. The apex of each stem has a tight cluster of inconspicuous flowers forming the spike appearance of the spike-sedge. A hard, nut-like, tiny achene ((dry, one-seeded fruit about 1 mm wide) or fruit of the Matted Spike-sedge protects its single seed, and the characteristic narrow, small dunce cap appearance of the achene's tubercle (protuberance) distinguishes it from other spike-sedges. As an annual plant, the occurrence and distribution of the Matted Spike-sedge may vary from year to year depending on the presence of suitable habitat and seed production. The achenes of these species are distributed by moving water, and germinate when conditions are suitable at their dispersed location. The light brown to pale olive or yellow achene matures in mid to late summer, and flowers from August-October.

The Matted Spike-sedge is typically found in marshes, freshwater mudflats, or in other wet areas with muddy substrates. Based on the occurrence of Matted Spike-sedge in freshwater marsh mudflats or muddy soils, observations of populations in Massachusetts established that habitat of Matted Spike-sedge involves an essential proximity to a freshwater source, particularly with beneficial fluctuating water levels that create exposed mud conditions during low-water years, such as rivers, ponds, and streams. Regular flooding and/or gentle wave action create the low-level disturbance needed to maintain the more open, muddy habitat conditions where Matted Spike-sedge thrive. In Massachusetts, the Matted Spike-sedge is found on muddy, alkaline riverbanks and pond shores, usually during periods of low water when mud is exposed. It is reported only in the western part of the state from twelve towns of Berkshire County including Pittsfield, Lenox and Lee; and four towns from Franklin and Hampshire counties (MNHESP 2019).

#### Matted Spike Sedge Habitat in Reach 5A

According to 2022 MNHESP database information, the Species Habitat of the Matted Spike-sedge extends from the Confluence south through all of Reach 5A. Occurrences of the Matted Spike-sedge have historically been reported along the Housatonic River within Reach 5A west of the Joseph Road area (Woodlot 2002). This species prefers muddy shoreline habitat, and such habitat is broadly distributed along the river margins and shallow backwaters throughout the mapped Species Habitat. The total Species Habitat of the Matted Spike-sedge in Reach 5A covers 116.79 acres. The areal extent of the mapped Species Habitat in Reach 5A is primarily confined to the main channel of the Housatonic River, its riverbanks, and the contiguous backwater areas; however, mapped Species Habitat also includes areas of forested floodplain, shrub swamp, and emergent marsh along the margins of the river. It is assumed that plants or achenes are also broadly distributed throughout the river and backwater areas, as well as emergent marsh habitats, within the mapped Species Habitat; however, as this species is an annual plant, the locations of growing plants within the Species Habitat from year to year are likely to vary.

### Monarch Butterfly (*Danaus plexippus*)

#### Summary of Species Life Cycle and Habitat Requirements

The monarch butterfly migrates each year from as far as Canada and across the United States to a few forested overwintering sites in the mountains of central Mexico and coastal California (USFWS 2022b). Adult monarchs are pollinators, feeding on a variety of native wildflowers. Milkweed (*Asclepias syriaca*) is the only host plant used during the larval stage (caterpillars) for this species. The adults lay their eggs on the underside of the leaf and the larva feeds on the leaves as it grows before entering the pupa stage and eventually emerging as an adult butterfly. Over the last two decades, numbers have declined, and therefore this species is a candidate for listing by the USFWS. Primary threats to this species appear to be conversion of grasslands to agriculture, urban development, widespread use of herbicides, logging/thinning at overwintering sites in Mexico, unsuitable management of overwintering groves in California, drought, continued exposure to insecticides, and effects of climate change (USFWS 2022b). The monarch butterfly is not currently a state-listed species in Massachusetts.

#### Monarch Butterfly Habitat in Reach 5A

Open meadows (both wetland and upland) in Reach 5A provide potentially suitable habitat for monarch butterflies. These habitats support several milkweed species which serve as the larval host plants for monarch butterflies. These habitats are most common in the Canoe Meadows area and just north of the Pittsfield WWTF.

### Mustard White (Pieris oleracea)

#### Summary of Species Life Cycle and Habitat Requirements

The Mustard White (*Pieris oleraceae*) is a medium-sized, white (pierid) butterfly member of the Pieridae family that is thought to belong to the Pieris napi complex (an Old World species). It is a Threatened Species under the Massachusetts Endangered Species Act (MESA) (MNHESP 2020). The wings of the spring brood of the Mustard White are white with a small yellow spot on the underside of the hind wing at the humeral angle, and distinct gray to black scales outlining the wing veins that are only faintly seen in later broods. The only markings above are some gray to black shading along the costa and at the apex of the forewing. Its wingspan is 32-50 mm. Typically, there are three broods and three flight periods of the Mustard White. In Massachusetts, the spring brood flies from mid to late April through May, the second brood from July to early August, and a third brood flies in late August to early September. In some years, a fourth late season brood is possible (Nelson 2010). The flight of the Mustard White butterfly is considered weak or docile when compared to other butterfly species (Leahy et al. 2006).

The Mustard White is typically found in moist, rich, (mesic) openings in woodlands and riparian floodplains, edges of fens, marshes and streams, and open wet meadows, fields, and pastures. The home range and travel patterns of the Mustard White appear to depend primarily on the availability and distribution of the host plants at the time of each brood. Two herbaceous woodland plants are essential larval hosts, the native two-leaved toothwort (*Cardamine diphylla*) found in deciduous forests and floodplains and introduced cuckoo-flower from Eurasia (*Cardamine pratensis*) growing in

forests and floodplains, meadows, lawns, and roadsides. Other larval hosts include rape (*Brassica rapa*), which is found in hayfields and on roadsides; watercress (*Nasturtium*), which is found only in wet areas with running water, and other mustard family plants (Brassicaceae), however these are typically only available for second and third broods making nearby forests with the early flowering toothwort a critical habitat requirement, as well as the early flowering cuckoo-flower (Stichter 2015). Females are also attracted to common winter cress (*Barbarea vulgaris*) and field pennycress (*Thlaspi arvense*) as potential host plants, however, these plants do not support larval growth (Leahy et al. 2006).

In Massachusetts, the largest known populations of Mustard White are found in open, damp meadows where larvae feed mainly on the introduced cuckoo-flower (Cardamine pratensis) as it is an early growth larval host plant available for the spring brood as well as later broods, and beneficially promotes a fast growth rate and high survivorship (Stichter 2015). With the spread of invasive garlic mustard, growth of host plants were inhibited, and female Mustard White butterflies began to lay their eggs on garlic mustard despite its effect of slow larval growth and poor survivorship (Courant et al. 1994). Observations in Lee, MA (1990), however, provided initial evidence that the Mustard White may be successfully adapting to effectively use the garlic mustard as a larval host with increasing survivorship, and other similar evidence has accumulated since then (Keeler & Chew 2008), inciting speculation that since garlic mustard (Allaria) is a prominent suitable host for the related P. napi species in Europe, it is feasible that the North American P. napi oleracea may be in the process of adapting to it (Stichter 2015). Adult butterflies feed on the nectar of the larval host plants and other flowers (Nelson 2010). Adult males will patrol open areas in search of receptive females during warm daylight hours. Females deposit single eggs on the underside of the leaves of host plants. The Mustard White overwinters in a chrysalis attached to a plant stem close to the ground.

Massachusetts is the southern range of the Mustard White, and it is currently only known in seven towns in central Berkshire County including Pittsfield, Lenox, and the southernmost town of Lee (MNHESP 2015). The Mustard White has been in decline in Massachusetts since about 1850. The focus of limitations for this species is primarily the loss of forest and meadow habitats and the host plants they support, with greatest emphasis on the host plants, toothwort and cuckoo-flower, that are critical to the success of the spring brood (Stichter 2015). Parasitism by the introduced braconid wasp, Cotesia glomerata, a parasite of the introduced Cabbage White butterfly, inhibited the Mustard White population as its caterpillars were found preferable over those of the Cabbage White, however, in recent years there has been a dramatic decline in the braconid wasp population in Massachusetts (Van Driesche et al 2003). Invasive garlic mustard spread inhibiting host plant growth and used instead by female Mustard White butterflies as host plants to lay eggs on. However, slow larval growth and poor survivorship on garlic mustard contributed to its decline. More recently in Massachusetts, however, there is evidence that larval growth rates and survivorship have improved, indicating adaptability of the Mustard White to effectively use garlic mustard as a host. The adaptability of the Mustard White has also been shown by populations in Massachusetts by using the introduced cuckoo-flower as a host which has proven to promote fast larval growth and high survivorship for all broods. Another limitation for the population of the Mustard White is hydrologic alteration in riparian floodplain habitat where periodic flooding maintains host plants.

#### Mustard White Habitat in Reach 5A

According to 2022 MNHESP database information, the Species Habitat of the Mustard White butterfly extends south contiguously through the southern two-thirds of Reach 5A below the Holmes Road bridge, covering 327.4 acres. The areal extent of the habitat includes the main stem of the Housatonic River and its backwaters, various habitats within the floodplain of the River (including floodplain forest, shrub and emergent marsh habitats, vernal pools, upland forest, and disturbed upland habitats). Although the Mustard White's primary habitat is moist deciduous woodlands, this species utilizes a diversity of habitats and could be found within or at the edges of all these communities. Literature reviews for this species indicate that the species uses a fairly diverse group of habitats, and most of the mapped Species Habitat would be acceptable habitat for the Mustard White during some stage of its life cycle (except for the purely aquatic habitats).

### Northern Long-eared Bat (Myotis septentrionalis)

#### Summary of Species Life Cycle and Habitat Requirements

The Northern Long-eared Bat (Myotis septentrionalis) or Northern Myotis is a small, brown bat with unique large, long ears that distinguish it from other species in Massachusetts. The Northern Longeared Bat is an Endangered Species under the Massachusetts Endangered Species Act (MESA) (MNHESP 2020). Its long ears distinctively extend at least 4mm past its nose when pushed forward. Its light brown fur, wing membranes, and dark base to light tip hairs on its back give it an overall brown color. It averages 50-95 mm in total length with a tail of 34-42 mm, and 5-8 g in weight. The Northern Long-eared Bat is found in forested habitats in the warm months of the year where it roosts in trees and forages. Although found in other tree roosts, it prefers roosts in large, tall cavities of large, live or dead trees in clustered hardwood stands. They may also be found in human made structures. Northern Long-eared Bats forage under canopies through complex strata of forest habitats, often feeding on insects above small ponds, vernal pools, and streams, or along gravel paths, roads and forest edges. After their daytime roosts, Northern Long-eared Bats emerge at dusk to begin feeding flights where they fly slowly, snatching up insects on the fly or resting insects on foliage while navigating through their complex forest environment with the aid of their specially adapted long tails and large wing membranes. They use passive listening and emit high frequency echolocation calls to locate resting insects. The Northern Long-eared Bat's body weight increases up to 45% between August and October, preparing a winter fat reserve for hibernation. Typical winter hibernacula are in natural caves and abandoned mines meeting their preference for sites with high humidity where water droplets may accumulate on their fur. They swarm the entrances of caves in late summer, possibly testing the air for suitable winter hibernacula, and mate at this time with sperm stored within females until spring. Northern Long-eared Bats enter their winter hibernacula sites by early November after migrating up to 56 km from their foraging habitat. They share caves with other species and typically hibernate singly or in small groups in deep cracks or crevices of the caves. Once the Northern Long-eared Bat is settled in its winter hibernacula, its metabolism slows and it enters torpor, although able to stir occasionally to drink water throughout the winter. They return year after year to the same winter hibernacula, but do not necessarily hibernate in the same location. Females bear their single young and rear them from mid-May through July. The longevity record of the Northern Long-eared Bat is 18 years.

Northern Long-eared Bat populations, once common in the northern United States, have been devastated by the spread of the White-nose Syndrome fungus. Infected hibernacula in caves in the Northeast have caused catastrophic population losses of 90-100%. During hibernation, the fungus grows and spreads over the bats causing them to rouse frequently from dormancy and use valuable stored fat needed to survive the winter, resulting in death. The movements of breeding male bats are believed to be primarily responsible for passing the fungus from cave to cave, but transport by humans is also thought to infect some hibernacula. Northern Long-eared Bats are widespread in Massachusetts and have been found in 11 of 14 Counties. Winter hibernacula have been reported in Berkshire, Franklin, Hampden, Middlesex, and Worcester Counties. (MNHESP 2019).

#### Northern Long-Eared Bat Habitat in Reach 5A

MNHESP did not provide Species Habitat mapping of the Northern Long-eared Bat. However, the USFWS IPaC consultation indicates that potential habitat for NLEB occurs throughout all of Reach 5A. The full 410 acres of Reach 5A appears to contain suitable habitat including forested and forest edge areas for roosts as well as foraging, small pond areas, areas of vernal pools, along streams, gravel paths or roads that are frequently used by this species for foraging.

### Ocellated Darner (Boyeria grafiana)

#### <u>Summary of Species Life Cycle and Habitat Requirements</u>

The Ocellated Darner (*Boyeria grafiana*) is an insect member of the dragonflies (Order Odonata, Suborder Anisoptera) in the Aeshnidae family known as the darners. The Ocellated Darner is a Species of Special Concern under the Massachusetts Endangered Species Act (MESA) (MNHESP 2020). Its long, slender abdomen, the dense venation of its wings, and its large head with huge eyes and powerful mouth parts are characteristic of all dragonflies. The darners are further characterized by being one of the largest dragonflies, 2.4 to 2.6 inches long with an average wingspan approximately 3.4 inches, and by its unusually large eyes positioned to wrap around the head to meet along a seam on top of the head. The Ocellated Darner has an overall dull brown coloration with distinguishing markings of yellow or greenish spots on the sides of the thorax, green or greenish-yellow stripes on the top of the thorax, and small dull green to yellow lateral markings on the abdomen. Brighter markings that are more distinct are typical of the male, otherwise appearance is similar to the female. The Ocellated Darner is one of two spotted darner species in North America, both distinguished by the two pale spots on the sides of the thorax from the other groups of darners.

Limited information exists on the life history of the Ocellated Darner, however, published information of the closely related Fawn Darner species is presumed representative of a similar life history and relied on to supplement the knowledge of the Ocellated Darner. Two distinct stages complete the life cycle of the dragonfly after the egg hatches known as the larval or nymph aquatic and adult flying stages. The Ocellated Darner nymph is long and slender, 1.5 inches in length when fully developed and has a dark coloration with a pale spot on the top of the seventh abdominal segment. It is known to inhabit clear, shallow, swift-flowing streams and large, rocky, poorly vegetated lakes. In Massachusetts, it has been observed only in shaded, clear, cold, rocky streams and rivers. Most of

the Ocellated Darner nymph cycle is spent hanging upside-down, clinging under rocks and sunken sticks. The nymphs are voracious and typically dominant predators of their aquatic habitats. Although the time required is unknown for the Ocellated Darner nymph to fully develop to the final step of emergence or eclosion from the nymphal exoskeleton (excuviae) to become a free-flying adult, other species in the family comparatively are known to take one to four years developing. In preparation for the eclosion, the nymph of the Ocellated Darner crawls out of the water onto exposed rocks, emergent vegetation or onto bank vegetation to find a secure perch where the new adult emerges from the exuviae in a very soft form (teneral dragonfly), vulnerable to damage by rain showers, falling debris, or predators. As soon as its wings are dry and strong enough, the Ocellated Darner adult flies to nearby upland areas to find shelter where it can continue to mature. It often inhabits upland woodland with mixed coniferous and deciduous trees. During maturation, Ocellated Darner adults feed on aerial insects captured in flight with the grasping aid of spines on their legs. When resting in the adjacent woodland, the adults hang vertically from the woodland vegetation. Being crepuscular, Ocellated Darner activity peaks late in the day, often flying well after sunset, unlike most Odonates. Unlike many darners, they rarely leave their water habitat, and also do not partake in feeding swarms characteristic of most species in the family. Ocellated Darners prefer shady areas and are often observed active on overcast days. With completion of the maturation process, the males return to the stream to breed. The flight of the male Ocellated Darner is swift and very erratic as it patrols the irregular shoreline, circling emerged rocks and vegetation to search for potential mates. In Massachusetts, males have been observed patrolling early in the morning. Females return to the stream only briefly when they are ready to mate and lay eggs. After mating, females in Massachusetts have been observed flying along rivers dipping their abdomens into the water and into the mud along riverbanks, presumably releasing eggs from the long, thin ovipositor characteristic of darners. Ocellated Darner females further use the ovipositor to slice into emergent vegetation and rotting, submerged logs where they also lay eggs. Once the eggs develop over an unknown length of time, the eggs hatch, and the nymphs re-initiate the life cycle. The Ocellated Darner has a late flight season from mid-July to mid-October with most records occurring from August to mid-September.

The Ocellated Darner in Massachusetts is recorded in 28 towns of Berkshire, Hampden, Hampshire and Franklin Counties. Most reports to date come from the Green, Deerfield, and Westfield river systems, all tributaries of the Connecticut River (MNHESP 2020). Despite the current Ocellated Darner Species Habitat mapping from MNHESP extending throughout Reach 5A of the ROR, the MNHESP (2015) Ocellated Darner fact sheet shows this species to be distributed only in towns to the east of the Housatonic River Valley on the MNHESP distribution map. However, MNHESP states in its fact sheet that there are streams and lakes in western Massachusetts with suitable habitat for the Ocellated Darner and additional population sites will likely be revealed, particularly in Berkshire County.

#### Ocellated Darner Habitat in Reach 5A

According to the 2022 MNHESP database information, the Species Habitat of the Ocellated Darner in Reach 5A occurs from the confluence of the East and West Branches through to the southern extent of the Pittsfield Wastewater Treatment Plant (WWTP). The mapped Species Habitat for this species totals 276.78 acres. Within the Species Habitat, the areal extent of the larval habitat includes the main stem of the river, plus the banks for eclosion (emergence as adults). The areal extent of adult

habitat is broader and includes the main stem of the river, riverbanks, backwaters, the floodplain and some adjacent upland forests or scrubland. Since this species needs large trees in the adult stage, areas where the stream corridor is densely forested offer the best habitat for this species.

### Ostrich Fern Borer (Papaipema sp. 2 near pterisi)

#### Summary of Species Life Cycle and Habitat Requirements

The Ostrich Fern Borer (*Papaipema sp.2 near pterisii*) is a noctuid moth from the Noctuidae (owelet moth) family associated with mature floodplain forests and wooded swamps with stands of Ostrich Fern (*Matteucia struthiopteris*). The Ostrich Fern Borer is a Species of Special Concern under the Massachusetts Endangered Species Act (MESA) (NHESP 2020). It flies at night, typically appearing a couple of hours after sunset. The color of the Ostrich Fern Borer may vary but it typically has bright, orange-yellow forewings overlaid with darker, brownish-orange, and may have pink shading towards the outer wing margins. These moths may also be a lighter, more faded yellowish-orange, or a darker, more brownish-orange. Markings include the large, white with orange center reniform spot, and the white orbicular spot with two identical, merged spots directly below. The hind wings are a solid pinkish-tan, and overall wingspan is 32-36 mm. The larva is orange to orangish-brown on its head and prothorax and its body is cream-color with small black spots and spiracles. It grows to about 1.4 inches.

The Ostrich Fern Borer moth inhabits mature floodplain forests and wooded swamps where Ostrich Fern grows in moderate to dense stands, preferably in a shaded or partially shaded microhabitat. Though the adults may be found along streamsides or any forested or edge habitat (e.g., adjacent to wet meadows, shallow marshes, open fields), they do not utilize aquatic habitats, and are more likely to be found in shaded to partially shaded forested floodplain habitats or red maple swamps containing Ostrich Fern. The Ostrich Fern Borer is monophagus, using the Ostrich Fern (Matteuccia struthiopteris) as its only host food plant. Eggs overwinter on the Ostrich Fern and larvae hatch in the spring. Larvae are typically found at the base of the frond where they bore into the Ostrich Fern and feed on its lower stalks and roots; pupae are found in the soil near the roots (Wagner et al. 2011). Larvae become fully grown and pupate into adults by August. In Massachusetts, Ostrich Fern Borer moths fly from late August through late September. They fly readily to a black light with its abundance of UV light that helps the moths navigate at night as the light reflects off objects and helps the moth to see where it is going. Ostrich Fern Borer moth occurrences have been recorded in Massachusetts in Berkshire County in the towns of Pittsfield, Lee, Great Barrington, and Sheffield; western Hampshire County in the town of Huntington; and western Hampden County in the town of Chester. These Massachusetts populations form the eastern edge of the relatively small Ostrich Fern Borer moth range that extends north to Vermont, south to Pennsylvania, and west to Wisconsin (MNHESP 2012).

#### Ostrich Fern Borer Habitat in Reach 5A

According to 2022 MNHESP database information, Species Habitat of the Ostrich Fern Borer moth occurs in the northcentral portion of Reach 5A, just downstream of the Holmes Road Bridge. The Species Habitat area of the Ostrich Fern Borer moth in Reach 5A comprises 171.26 acres. This Species Habitat area includes approximately 1.3 miles of the main stem of the Housatonic River, several large

backwaters, and an extensive wetland system associated with Sackett Brook, a perennial tributary stream. The dominant habitats are transitional floodplain forest and red maple swamp (both of which are forested floodplain habitats in this area), with interspersed patches of wet meadow, shrub swamp, emergent marsh, and vernal pools. The mapped floodplain habitat adjacent to the River is dominated by deciduous wooded swamp and shrub swamp, and ostrich fern is often a dominant understory species in all the floodplain wetland forested habitat in this area of Reach 5A.

### Rapids Clubtail (Phanogomphus quadricolor)

#### Summary of Species Life Cycle and Habitat Requirements

The long, slender Rapids Clubtail (*Phanogomphus quadricolor*) is an insect member of the dragonflies (Order Odonata, Suborder Anisoptera) in the Gomphidae family, specifically clubtails, which are typically burrowers and predators. It is an Endangered Species under the Massachusetts Endangered Species Act (MESA) (NHESP 2020). Clubtails have small, widely separated compound eyes that distinguish it from most other dragonflies. Their name, clubtail, derives from the lateral swelling near the end of the abdomen that appears "club-like". The small "club" and the dull coloring of grays, greens, browns, and blacks of the Rapids Clubtail are characteristics of the clubtails belonging to the genus Phanogomphus. Rapids Clubtails have blue-green eyes, black legs, yellow to gray-green dorsal and lateral stripes on the sides of the thorax, and a black abdomen. Adult Rapids Clubtails range from about 1.6-1.8 inches in length.

Limited information exists on the life cycle of the Rapids Clubtail, however, the published information of similar species is relied on to supplement the knowledge of the Rapids Clubtail in Massachusetts. The Rapids Clubtail inhabits clear, cold streams and rivers with intermittent sections of rocks and rapids. Two distinct life stages complete the life cycle of the dragonfly after hatching from the egg including an aquatic larval or nymph stage and a flying adult stage. The first major stage begins with the nymph or larva hatching from an egg to an entirely aquatic stage. The nymph of the Rapids Clubtail can typically be found in shallow pools located downstream of rapids, and these pools often contain emergent plants (Walker 1958). In the quiet pools of streams or rivers, Rapids Clubtail nymphs spend most of their time burrowing in the bottom sediment which protects them from predators. It also camouflages them as they are voracious, ambush predators, attacking a variety of aquatic life including passing insects to small fish and tadpoles as dragonfly nymphs have a unique moveable, hinged lower lip that can extend to enhance capture of prey. Although unknown as to the time required for the Rapids Clubtail nymph to fully develop to the final step of emergence or eclosion from the nymphal exoskeleton (excuviae) before becoming a free-flying adult, comparatively it takes about a year for similarly sized dragonflies. In preparation for the eclosion, the nymph of the Rapids Clubtail crawls up onto the bank or exposed rocks or logs to find a secure perch less than a few feet above the water where the new adult emerges from the exuviae in a very soft form (teneral adult), vulnerable to damage by rain showers, falling debris, or predators. As soon as the wings are dry and strong enough, the Rapids Clubtail adult flies into adjacent woodland that surround the breeding habitat to find safe shelter and hide among the leaves and branches of trees where it can continue to mature. During maturation, Rapids Clubtail adults wander from woodland to forest clearings and fields, feeding on small aerial insects such as flies and mosquitos captured with the aid of spines on their legs. With completion of the maturation process, the adults return to the

stream to breed. Adults prefer the swifter sections of rivers, while the nymphs are found in the quiet pools below areas of rapids. The male Rapids Clubtail patrols the water and stream banks to search for potential mates and to drive out competing males, often returning to the same or nearby perch. Females return to the stream only briefly when they are ready to mate and lay eggs. After mating, females fly back and forth touching their abdomens to the water surface in the faster sections of the stream where there are rapids, releasing eggs every few feet. The eggs are then carried downstream from the rapids to shallow pools, where the eggs incubate for a period of at least 5 days and possibly up to a month (COSEWIC 2008) to hatch into larvae which re-initiate the life cycle.

In Massachusetts, the Rapids Clubtail adult breeds through the month of June and flies during the months of June and early July. Although population densities of Rapids Clubtail appear to be low, there may be an impact caused by the elusiveness of the adults, and therefore, focus on the easier to find Rapids Clubtail nymphs may provide a more accurate species population status in Massachusetts. Despite the current Rapids Clubtail Species Habitat mapping from MNHESP extending through the southern portion of Reach 5A of the ROR, the MNHESP (2019) Rapids Clubtail fact sheet shows this species to be distributed only to the east of the Housatonic River Valley with no towns in Berkshire County indicated in the MNHESP distribution map (MNHESP 2019).

#### Rapids Clubtail Habitat in Reach 5A

According to the 2022 MNHESP database information, Species Habitat of the Rapids Clubtail comprises the southern portion of Reach 5A. The overall mapped Species Habitat of the Rapids Clubtail dragonfly in Reach 5A is 55 acres. The areal extent of the nymph habitat includes the main stem of the river, plus the banks for eclosion (emergence as adults). The areal extent of adult habitat is broader and includes the main stem of the river, backwaters, floodplain and some adjacent upland forests or scrubland. The MNHESP Species Habitat designation extends into these areas, and suitable habitat appears to occur in these areas of Reach 5A, although the extent of riffle habitat is somewhat limited. This species needs trees in the adult stage, so areas where the stream corridor is densely forested offer the best habitat for this species, however, they can also be found in fields and open areas.

### Riffle Snaketail (Ophiogomphus carolus)

#### Summary of Species Life Cycle and Habitat Requirements

The Riffle Snaketail (*Ophiogomphous carolus*), is a large and stocky insect member of the dragonflies (Order Odonata, Suborder Anisoptera) in the Gomphidae family or clubtails, which are typically burrowers and predators. It is a Threatened Species under the Massachusetts Endangered Species Act (MESA) (NHESP 2020). Clubtails have small, widely separated compound eyes that distinguish it from most other dragonflies. The name clubtail derives from the lateral swelling near the end of the abdomen that appears "club-like". The extent of the swelling or club varies greatly depending on the species. Males generally have a larger club than females. Although unknown, the club may have use in courtship displays or enhance the aerodynamics of flight. The Riffle Snaketail belongs to the genus Ophiogomphous which are snaketails that characteristically exhibit a brilliant green thorax, eyes, and face. The club of the Riffle Snaketail is over half the width of its thorax. Pale green to yellow markings that run down the sides of the black to dark brown abdomen are largest at the club, while

wide, yellow, dagger shaped markings run down the center of the top of the abdomen. The clear wings display a dense network of veins and are held horizontally in the characteristic horizontal perching stance of the Riffle Snaketail on rocks, logs, vegetation, and the ground. Adult Riffle Snaketails are 1.6-1.7 inches in length. The female is larger and has a smaller club near the tip of the abdomen than the male.

Limited information exists on the life cycle of the Riffle Snaketail, however, published information of similar species is relied on to supplement the knowledge of the Riffle Snaketail. The Riffle Snaketail inhabits clear, cold, rocky streams that are fast flowing with few pools and fine gravel or sand sediment. Two distinct life stages complete the life cycle of the dragonfly after hatching from the egg including an aguatic larval or nymph stage and a flying adult stage. The first major stage begins with the nymph or larva hatching from an egg to an entirely aquatic stage. Riffle Snaketail nymphs burrow in the bottom sediment which protects them from predators. Burrowing also camouflages them as they are ambush predators that attack a variety of aquatic life such as passing aquatic invertebrates, small fish and tadpoles using a moveable, hinged lower lip unique to dragonfly (and damselfly) nymphs that extend to capture prey. Although unknown as to the time required for the Riffle Snaketail nymph to fully develop to the final step of emergence or eclosion from the nymph exoskeleton (exuviae) before becoming a free-flying adult, comparatively it takes about a year for similarly sized dragonflies. In preparation for eclosion, the nymph of the Riffle Snaketail crawls up onto exposed rocks in the stream bed, or onto the stream bank or protruding logs to find a secure perch less than a foot above the water where the new adult emerges from the exoskeleton or exuviae in a very soft form (teneral dragonfly) vulnerable to damage by rain showers, falling debris, or predators. As soon as the wings are dry and strong enough, the Riffle Snaketail adult dragonfly flies into adjacent woodland that surround the breeding habitat to find safe shelter among the leaves and branches of trees where it can continue to mature. During maturation, Riffle Snaketail adults wander from woodland to forest clearings and fields, feeding on small aerial insects such as flies and mosquitos. With completion of the maturation process, the adults return to the stream to breed. From exposed rock perches in the middle of the stream, the male Riffle Snaketail patrols over water to search for potential mates and to drive out competing males, often returning to the same or nearby perch. This family is typically a "short flight" species requiring substantial perching places as they move along the stream, usually woody debris, live woody plants, and rocks. Females return to the stream only briefly when they are ready to mate and lay eggs. Once mating occurs, females fly back and forth touching their abdomens to the water surface in sections of the stream where there are riffles, releasing eggs every few feet. The eggs may then be carried downstream and deposited in pools where they hatch, and the nymphs re-initiate the life cycle.

In Massachusetts, the Riffle Snaketail is thought to breed from early June through late July. Although population densities of clubtails appear low, there may be an impact caused by the elusiveness of the adults, and therefore focus on the easier to find Riffle Snaketail nymphs may provide a more accurate species population status in Massachusetts. In Massachusetts, the Riffle Snaketail has been reported in Berkshire County in the towns of Pittsfield and Windsor; and seven towns from Hampden, Hampshire, and Franklin Counties (MNHESP 2015).

#### Riffle Snaketail Habitat in Reach 5A

According to 2022 MNHESP database information, the Species Habitat of the Riffle Snaketail occurs only in the upstream portion of Reach 5A, from the confluence of the East and West Branches to a point just upstream of the Joseph Road housing development off East New Lenox Road. The Woodlot Alternatives (2002) ecological characterization also documented the presence of this species in this area. The area of Species Habitat associated with Reach 5A is 191.68 acres. The areal extent of the nymph habitat includes the main stem of the river, plus the banks for eclosion (emergence as adults). The areal extent of adult habitat is broader and includes the main stem of the river, backwaters, floodplain and some adjacent upland forests or scrubland.

### Spine-crowned Clubtail (Hylogomphus abbreviatus)

#### Summary of Species Life Cycle and Habitat Requirements

The Spine-crowned Clubtail (Hylogomphus abbreviates) is a large insect (Order Odonata) and member of the dragonflies (Order Odonata, Suborder Anisoptera) in the Gomphidae family, the clubtails, which are typically burrowers and predators. It is listed as a species of Special Concern under the Massachusetts Endangered Species Act (MESA) (NHESP 2020). Clubtails have small, widely separated compound eyes that distinguish it from other dragonflies (with exception of Petaluridae and Damselflies), as well as its characteristic wing venation. The name clubtail derives from the lateral swelling near the end of the abdomen that appears "club-like". The extent of the swelling or club varies greatly depending on the species. Males generally have a larger club than females. The club may have use in courtship displays or enhance the aerodynamics of flight. The Spine-crowned Clubtail belongs to the subgenus Hylogomphus characterized by the medium-sized club on the tip of the abdomen. The dark brown/black Spine-crowned Clubtail dragonfly body has pale yellow stripes on top of the thorax and lateral stripes on the sides of the thorax. Abdomen segments one through seven have yellow markings on top, and two large bright yellow patches mark each side of the club. The face is a varying yellowish in color, and it has black legs. Adult Spine-crowned Clubtails range in length from 1.3 to 1.4 inches in length (34 mm - 35 mm) and have a wingspan averaging 2.6 inches (66 mm). Fully developed nymphs average just under one inch in length (23 mm – 24 mm). Spine-crowned Clubtails inhabit large streams and rivers.

In Massachusetts, Spine-crowned Clubtails have been found on the Connecticut River and other medium to large rivers that have silty and sandy bottoms. Two distinct stages complete the life cycle of the dragonfly including an aquatic larval or nymph stage and a flying adult stage. The first major stage begins with the nymph or larva hatching from an egg to an entirely aquatic stage. The aquatic nymphs burrow under the river bottom sediment, while the flying adults inhabit riparian areas, forested uplands, and fields. The Spine-crowned Clubtail nymphs burrow in the bottom sediment which protects them from predators. Burrowing also camouflages them as they are ambush predators that attack a variety of aquatic life including passing aquatic invertebrates, small fish and tadpoles using a moveable, hinged lower lip unique to the dragonfly (and damselfly). It takes at least a year for the nymphs to fully develop, which involves several molts, to reach the final step of emergence or eclosion from the nymph exoskeleton (exuviae) before becoming a free-flying adult. In preparation for eclosion, the nymph of the Spine-crowned Clubtail crawls up onto exposed rocks in the river, emergent vegetation, partially submerged logs, or steep river banks to find a secure perch

where the new adult emerges from the exoskeleton or exuviae in a very soft form (teneral dragonfly) vulnerable to damage by rain showers, falling debris, or predators. Typically, emergence occurs very early in the morning, and presumed to be in response to predation exposure during this vulnerable period. The nymphal exuviae, or cast exoskeletons, may be used to reliably identify a species and determine its presence. As soon as the wings are strong enough, the Spine-crowned Clubtail adult flies into adjacent woodland that surround the breeding habitat to find safe shelter among the leaves and branches of trees where it can continue to mature. During maturation, Spine-crowned Clubtail adults fly from woodland to forest clearings and fields, feeding on small aerial insects such as flies and mosquitos. They are rarely observed during this time and thought to spend much of this stage in tree tops. After completion of the maturation process, which takes several days or more, the adult males return to the river to breed, perching on sandy shorelines or overhanging vegetation. From there, the male Spine-crowned Clubtail patrols about a foot over the surface of the water, hovering at times, to search for potential mates and to drive out competing males. Females return to the stream only briefly when they are ready to mate and lay eggs. After mating, females fly back and forth touching their abdomens to the water surface to release the eggs. The eggs develop over an unknown length of time, and nymphs hatch to re-initiate the life cycle. In Massachusetts, the flight season of the Spine-crowned Clubtail starts with emergence beginning in late May and early June and the adults flying through July.

In Massachusetts, the Spine-crowned Clubtail has been recorded from several rivers, and reports include Berkshire County in the towns of Pittsfield, Great Barrington, Sheffield, and Sandisfield; 16 towns from Hampden, Hampshire and Franklin Counties; and 11 towns from Worcester, Middlesex and Plymouth Counties (MNHESP 2019).

#### Spine-Crowned Clubtail Habitat in Reach 5A

According to the 2022 MNHESP database information, the Species Habitat of the Spine-crowned Clubtail in Reach 5A occurs from the confluence of the East and West Branches to the southern extent of the Pittsfield Wastewater Treatment Plant (WWTP). The mapped Species Habitat for this species totals 256.2 acres. Within the Species Habitat, the areal extent of the nymphal habitat includes the main stem of the river, plus the banks for eclosion (emergence as adults). The areal extent of adult habitat is broader and includes the main stem of the river, riverbanks, backwaters, the floodplain and some adjacent upland forests or scrubland. Since this species needs large trees in the adult stage, areas where the stream corridor is densely forested offer the best habitat for this species.

### Tuckerman's Sedge (Carex tuckermanii)

#### Summary of Species Life Cycle and Habitat Requirements

Tuckerman's sedge (*Carex tuckermanii*) is a perennial herbaceous wetland sedge (family Cyperaceae) that grows in loose clumps up to a meter tall in habitats including river and lake shores, swamps, and vernal pools. It is an Endangered Species under the Massachusetts Endangered Species Act (MESA) (NHESP 2020). Tuckerman's sedge has short rhizomes, and erect to arching stems with flat, slender linear leaves and reddish-purple basal sheaths. Its triangular reproductive stems or culms have both staminate spikes that are terminal and pistillate spikes having cylindrical rows of ascending perigyna that typically droop pendulously from the stalk. Its most recognizable feature is the distinctive

female flowering spike comprised of clusters of pendulous, inflated teardrop-shaped perigynia that encase the achenes, its one seeded fruit. Perigynia are mature throughout most of the summer, from June through August.

In Massachusetts, Tuckerman's Sedge inhabits the rich soils of lowland river floodplain habitats such as oxbows (C-shaped wetlands adjacent to river channels), low depressions, forests, meadows, swales, and vernal pools in the western and central part of the state. Populations that have persisted over time in Massachusetts are found in low depressions or swales within forested floodplains, and apparently thrive with periodic inundation, also benefiting from flooding as a dispersal mechanism. Reported occurrences of Tuckerman's Sedge are from Berkshire County in the towns of Pittsfield, Stockbridge, Tyringham, Sheffield and New Marlboro; and from four towns in Franklin, Hampshire and Worcester Counties (MNHESP 2019).

#### Tuckerman's Sedge Habitat in Reach 5A

According to 2022 MNHESP database information, Species Habitat of Tuckerman's Sedge occurs in the central portion of Reach 5A northeast of the City of Pittsfield Wastewater Treatment Facility on the west side of the Housatonic River. Tuckerman Sedge Species Habitat comprises approximately .86 acres. This area contains a seasonal pool which has a closed canopy and is bordered by shrub swamp habitat to the north and high terrace floodplain forest on the other three sides. All of the area within the mapped Species Habitat in Reach 5A would be suitable for this species.

### Wapato (Sagittaria cuneata)

#### <u>Summary of Species Life Cycle and Habitat Requirements</u>

The aquatic Wapato (Sagittaria cuneata) is an herbaceous perennial of the water-plantain or arrowhead family (Alismataceae) found in nearly neutral to slightly basic, open-water habitats. The Wapato is a Threatened Species under the Massachusetts Endangered Species Act (MESA) (NHESP 2020). In Massachusetts, Wapato is found in very slow moving or stagnant waters of riverine floodplain habitats in alkaline backwaters, oxbow ponds, small shallow depressions with muddy substrate, and a few occurrences on pond shores. Wapato displays high variability in its growth form as an emergent and emersed plant, a floating plant, or entirely submerged plant depending on its growth conditions. Wapato typically has basal rosettes of leaves with expanded blades with sagittate or arrow-head shaped leaves growing from stoloniferous corms, however, Wapato leaves display great variance (or phenotypic plasticity) having three different leaf morphologies depending on the hydrology and prevailing water level of its habitat. Emersed plants have leaf blades that are linear to sagittate with a central lobe that is broad-lanceolate to triangular-ovate, on top of recurved petioles. Floating plants in moderate to deep water have heart-shaped or sagittate leaf blades with long triangular petioles. Entirely submerged plants in deep water have long narrow, ribbon-like, bladeless, expanded leaf-like petioles (phyllodia). The long-stalked flowering raceme has 2 to 10 whorls of three-lobed white flowers that produce achenes, or one-seeded fruit, that are flattened and encased in dense spheres. Wapato flowers beginning July to mid-September, and fruits mid-July through September. Distinct to the identification of Wapato is a tiny erect beak on its achene, as well as the phenotypic plasticity of its leaf morphology. The average height of Wapato is about 1.5 feet but may reach over 3.5 feet. In Massachusetts, Wapato is reported in Berkshire County in the

towns of Pittsfield, Lenox, Lanesboro, Great Barrington and Sheffield; and Hampden County in the town of Holyoke (MNHESP 2015).

#### Wapato Habitat in Reach 5A

According to the 2022 MNHESP database information, the Species Habitat of Wapato extends from the Confluence of the East and West Branches of the Housatonic River south along the river corridor through Reach 5A. The total mapped Species Habitat for this species in Reaches 5A comprises 171 acres. Principal natural communities identified within the mapped Species Habitat include muddy substrates along the shallow edges of the main stem of the river, backwater habitats, and a variety of floodplain habitats, including emergent marsh, floodplain forest, and shrub swamps bordering the river channel. This species requires total to partial submersion in water during most of its life cycle. Thus, seasonally exposed muddy substrates along the river channel, toe of the riverbank slopes, backwater areas, emergent marshes, and seasonal pools in the floodplain forest constitute the primary habitat for this species.

### White Adder's-mouth (Malaxis monophyllos var. brachypoda)

#### Summary of Species Life Cycle and Habitat Requirements

White Adder's-mouth (*Malaxis monophyllos var. brachypoda*) is a single-leaved orchid member of the family Orchidaceae found in small, shaded, calcareous wetland habitats. It is classified as an Endangered Species under the Massachusetts Endangered Species Act (MESA) (MNHESP 2020). White Adder's-mouth is identified by its slender stem, a 1.2 to12 inch tall raceme, displaying one loosely sheathed elliptical leaf (rarely two) up to 3.7 inches long and a stalked inflorescence of up to fifty tiny greenish-white flowers held by tiny 2 to 4.5 mm pedicels (giving its name brachypoda meaning "short-footed)) on the upper part of the stem. Each flower has a species identifying heart-shaped lip tapering to the bottom of the flower. In Massachusetts, White Adder's-mouth flowers at the beginning of June through mid-August. White-Adder's mouth prefers habitats with accumulations of incompletely decomposed organic material, or peat, dominated by coniferous trees and influenced by highly calcareous water (Schultz 2003). In Massachusetts, White Adder's-mouth is found in calcareous wetlands that may include hillside seeps, but it prefers rich shady bogs and fens in mossy depressions in hummocky, sphagnum moss-dominated habitats shaded by Eastern Hemlock. White-Adder's mouth is currently reported in western Massachusetts in Berkshire County in the towns of Pittsfield and Williamstown; and in Franklin County (MNHESP 2019).

#### White Adder's-mouth Habitat in Reach 5A

According to 2022 MNHESP database information, the Species Habitat for White Adder's-mouth occurs in the northern section of Reach 5A comprising approximately 1.62 acres. Mapped Species habitat consists of floodplain forests and a backwater area associated with an unnamed stream system which flows into Sackett Brook and from there to the Housatonic River.

#### References:

Azure, D. A. 1998. Aspects of American Bittern ecology in northwest Minnesota. M.S. thesis. University of North Dakota, Grand Forks, North Dakota. 139 pages.

Brininger, W. L., Jr. 1996. The ecology of the American Bittern in northwest Minnesota. M.S. thesis. St. Cloud State University, St. Cloud, Minnesota. 70 pages.

Courant, A.V., A.E. Holbrook, E.D. Van der Reijden, and F.S. Chew. 1994. Native pierine butterfly (Pieridae) adapting to naturalized crucifer? Journal of the Lepidopterists' Society. 48(2): 168-170.

Keeler, M.S. and F.S. Chew. 2008. Escaping an evolutionary trap preference and performance of a native insect on an exotic invasive host. Oecologia. 156: 559-568.

Leahy, C.W., B. Cassie, and R. K. Walton (eds). 2006. *Massachusetts Butterfly Atlas 1986-1990*, Massachusetts Audubon Society (www.massaudubon.org/butterflyatlas)

Dechant, J., M. Sondreal, D. Johnson, L. Igl, C. Goldale, A. Zimmerman, and B. Euliss. 2003. Effects of management practices on grassland birds: American Bittern. Northern Prairie Wildlife Research Center. Jamestown, ND. http://www.npwrc.usgs.gov/resource/literatr/grasbird/ambi/ambi.htm

DeGraaf and Yamasaki. 2001. New England Wildlife. University Press of New England, Hanover, NH.

Lowther, Peter, Alan F. Poole, J. P. Gibbs, S. Melvin and F. A. Reid. 2009. American Bittern (Botaurus lentiginosus), The Birds of North America Online (A. Poole, Ed.). Ithaca: Cornell Lab of Ornithology; Retrieved from the Birds of North America Online: http://bna.birds.cornell.edu/bna/species/018

MNHESP 2012. MA Natural Heritage and Endangered Species Program Fact Sheet: Ostrich Fern Borer (*Papaipema* sp. 2 near *pterisii*) Fact Sheet. Westborough, MA.

MNHESP. 2015. MA Natural Heritage and Endangered Species Program Fact Sheet: American Bittern (*Botaurus lentiginosus*). Westborough, MA.

MNHESP. 2015. MA Natural Heritage Endangered Species Program Fact Sheet: Bristly Buttercup (*Ranunculus pensylvanicus*). Westborough, MA.

MNHESP. 2015. MA Natural Heritage and Endangered Species Program Fact Sheet: Culver's-root (Veronicastrum virginicum). Westborough, MA.

MNHESP. 2015. MA Natural Heritage Endangered Species Program Fact Sheet: Frank's Lovegrass (*Eragrostis frankii*). Westborough, MA.

MNHESP 2015. MA Natural Heritage and Endangered Species Program Fact Sheet: Gray's Sedge (*Carex grayi*) Fact Sheet. Westborough, MA.

MNHESP 2015. MA Natural Heritage and Endangered Species Program Fact Sheet: Great Laurel (*Rhododendron maximum*). Westborough, MA.

MNHESP. 2015. MA Natural Heritage Endangered Species Program Fact Sheet: Hairy Wild Rye. (*Elymus villosus*). Westborough, MA.

MNHESP 2015. MA Natural Heritage and Endangered Species Program Fact Sheet: Mustard White (*Pieris oleraceae*) Fact Sheet. Westborough, MA.

MNHESP 2015. MA Natural Heritage and Endangered Species Program Fact Sheet: Ocellated Darner (*Boyeria grafiana*). Westborough, MA.

MNHESP 2015. MA Natural Heritage and Endangered Species Program Fact Sheet: Riffle Snaketail (*Ophiogomphus carolus*) Fact Sheet. Westborough, MA.

MNHESP 2015. MA Natural Heritage and Endangered Species Program Fact Sheet: Wapato (*Sagittaria cuneata*) Fact Sheet. Westborough, MA.

MNHESP. 2015. MA Natural Heritage Endangered Species Program Fact Sheet: Brook Snaketail Ophiomphus aspersus). Westborough, MA.

MNHESP. 2019. MA Natural Heritage Endangered Species Program Fact Sheet: Common Gallinule (*Gallinula chloropus*). Westborough, MA

MNHESP 2019. MA Natural Heritage and Endangered Species Program Fact Sheet: Matted Spike-Sedge (*Eleocharis intermedia*) Fact Sheet. Westborough, MA.

MNHESP. 2019. MA Natural Heritage and Endangered Species Program Fact Sheet: Northern Longeared Bat (*Myotis septentrionalis*). Westborough, MA.

MNHESP 2019. MA Natural Heritage and Endangered Species Program Fact Sheet: Rapids Clubtail (Gompus quadricolor) Fact Sheet. Westborough, MA.

MNHESP 2019. MA Natural Heritage and Endangered Species Program Fact Sheet: Spine-crowned Clubtail (Hylogomphus abbrviatus) Fact Sheet. Westborough, MA.

MNHESP 2019. MA Natural Heritage and Endangered Species Program Fact Sheet: Tuckerman's Sedge (*Carex tuckermanii*) Fact Sheet. Westborough, MA.

MNHESP 2019. MA Natural Heritage and Endangered Species Program Fact Sheet: White Adder's-mouth (Malaxis monophyllos var. Brachypoda) Fact Sheet. Westborough, MA.

MNHESP. 2020. Massachusetts List of Endangered, Threatened and Special Concern Species as published in the Code of Massachusetts Regulations (321 CMR 10.00). Natural Heritage & Endangered Species Program. Westborough, MA.

Stokes. 1996. Stokes Field Guide to Birds, Eastern Region. Little, Brown and Company.

Woodlot Alternatives, Inc. 2002. Ecological Characterization of the Housatonic River. Environmental Remediation Contract. GE/Housatonic River Project, Pittsfield, MA.

United States Department of Agriculture. Natural Resources Conservation Service Website <a href="http://plants.usda.gov/">http://plants.usda.gov/</a>

Completed 08212023

## IPaC resource list

This report is an automatically generated list of species and other resources such as critical habitat (collectively referred to as *trust resources*) under the U.S. Fish and Wildlife Service's (USFWS) jurisdiction that are known or expected to be on or near the project area referenced below. The list may also include trust resources that occur outside of the project area, but that could potentially be directly or indirectly affected by activities in the project area. However, determining the likelihood and extent of effects a project may have on trust resources typically requires gathering additional site-specific (e.g., vegetation/species surveys) and project-specific (e.g., magnitude and timing of proposed activities) information.

Below is a summary of the project information you provided and contact information for the USFWS office(s) with jurisdiction in the defined project area. Please read the introduction to each section that follows (Endangered Species, Migratory Birds, USFWS Facilities, and NWI Wetlands) for additional information applicable to the trust resources addressed in that section.

## Project information

NAME

Housatonic River Floodplain Restoration

LOCATION

Berkshire County, Massachusetts



**DESCRIPTION** 

Some(Floodplain preservation and restoration.)

## Local office

New England Ecological Services Field Office

**(**603) 223-2541

**(603)** 223-0104

70 Commercial Street, Suite 300 Concord, NH 03301-5094

# Endangered species

### This resource list is for informational purposes only and does not constitute an analysis of project level impacts.

The primary information used to generate this list is the known or expected range of each species. Additional areas of influence (AOI) for species are also considered. An AOI includes areas outside of the species range if the species could be indirectly affected by activities in that area (e.g., placing a dam upstream of a fish population even if that fish does not occur at the dam site, may indirectly impact the species by reducing or eliminating water flow downstream). Because species can move, and site conditions can change, the species on this list are not guaranteed to be found on or near the project area. To fully determine any potential effects to species, additional site-specific and project-specific information is often required.

Section 7 of the Endangered Species Act **requires** Federal agencies to "request of the Secretary information whether any species which is listed or proposed to be listed may be present in the area of such proposed action" for any project that is conducted, permitted, funded, or licensed by any Federal agency. A letter from the local office and a species list which fulfills this requirement can **only** be obtained by requesting an official species list from either the Regulatory Review section in IPaC (see directions below) or from the local field office directly.

For project evaluations that require USFWS concurrence/review, please return to the IPaC website and request an official species list by doing the following:

- 1. Log in to IPaC.
- 2. Go to your My Projects list.
- 3. Click PROJECT HOME for this project.
- 4. Click REQUEST SPECIES LIST.

Listed species<sup>1</sup> and their critical habitats are managed by the <u>Ecological Services Program</u> of the U.S. Fish and Wildlife Service (USFWS) and the fisheries division of the National Oceanic and Atmospheric Administration (NOAA Fisheries<sup>2</sup>).

Species and critical habitats under the sole responsibility of NOAA Fisheries are **not** shown on this list. Please contact <u>NOAA</u> <u>Fisheries</u> for <u>species under their jurisdiction</u>.

- 1. Species listed under the <u>Endangered Species Act</u> are threatened or endangered; IPaC also shows species that are candidates, or proposed, for listing. See the <u>listing status page</u> for more information. IPaC only shows species that are regulated by USFWS (see FAQ).
- 2. <u>NOAA Fisheries</u>, also known as the National Marine Fisheries Service (NMFS), is an office of the National Oceanic and Atmospheric Administration within the Department of Commerce.

The following species are potentially affected by activities in this location:

### **Mammals**

NAME STATUS

Northern Long-eared Bat Myotis septentrionalis Endangered

Wherever found

No critical habitat has been designated for this species.

https://ecos.fws.gov/ecp/species/9045

### Insects

NAME STATUS

Candidate

Monarch Butterfly Danaus plexippus

Wherever found

No critical habitat has been designated for this species.

https://ecos.fws.gov/ecp/species/9743

### Critical habitats

Potential effects to critical habitat(s) in this location must be analyzed along with the endangered species themselves.

There are no critical habitats at this location.

You are still required to determine if your project(s) may have effects on all above listed species.



# Appendix H Invasive Species Information

### Appendix H-1: Identification of Invasive Plant Species in Reach 5A

For the assessment of invasive species in Reach 5A, the definition of invasive plant species was based on the plant species listed by recognized organizations – notably, the Massachusetts Invasive Plant Advisory Group (MIPAG) (considering both "invasive" or "likely invasive" species), the USACE New England District, and the Invasive Plant Atlas of New England (IPANE).

MIPAG defines invasive plants as "non-native species that have spread into native or minimally managed plant systems in Massachusetts. These plants cause economic or environmental harm by developing self-sustaining populations and becoming dominant and/or disruptive to those systems" (MIPAG 2005). Its list includes species determined to be "invasive," "likely invasive," and "potentially invasive." For a species to be included on the MIPAG list, it must be substantiated by scientific investigation (including herbarium specimens, peer-reviewed papers, published records and other data available for public review) to meet specific criteria. The process of reviewing individual plant species for their invasiveness in Massachusetts is ongoing and may result in a change in status pending new data and further review. As noted above, for the purposes of assessing invasive species in Reach 5A, the species rated by MIPAG as "invasive" or "likely invasive" were included.

IPANE similarly defines invasive species as "any species that is non-native to the ecosystem under consideration and whose introduction causes or is likely to cause economic or environmental harm or harm to human health. These invasive species aggressively compete with and displace the associated flora and fauna communities" (IPANE 2007). Originally based at the University of Connecticut and specific to New England invasive plant species, IPANE now collaborates with the broader Invasive Plant Atlas of the United States at: Invasive Plant Atlas of the United States - Database of Plants Invading Natural Areas: Invasive Plant Atlas of the United States. Connecticut now provides state-specific invasive species information via the Connecticut Invasive Plant Working Group at Connecticut Invasive Plant List | Connecticut Invasive Plant Working Group (uconn.edu). For the purposes of assessing invasive species in Reach 5A, the list of invasive species published by IPANE at <a href="https://www.ipane.org">www.ipane.org</a> has been used.

The USACE New England District address invasive plant species in its wetland mitigation standard operating procedures document, available at: <a href="NEW ENGLAND DISTRICT REGULATORY DIVISION">NEW ENGLAND DISTRICT REGULATORY DIVISION</a>
<a href="COMPENSATORY">COMPENSATORY (army.mil)</a>. This document provides a focused list of 13 invasive species which the Corps considers invasive at wetland mitigation sites and "must be controlled" at mitigation sites. This list of species has been used in this current assessment as "ACOE Invasive" (see Table H1). This list of invasive species does not include any species that are not listed as invasive or likely invasive by MIPAG or IPANE. Note that the Corps also provides a more extensive list of "unacceptable" species in Appendix K of its mitigation document; these are species which the Corps finds unacceptable to include in wetland planting plans as part of the Section 404 CWA permit program. Table H1 notes the species observed in Reach 5A that are on this expanded list of "unacceptable" species, but these

species are not included as invasive plants for this current assessment, which relies on the MIPAG and IPANE definitions and criteria of invasive plant species.

The methods used in the identification of invasive species in Reach 5A are described in Section 9.1 of the main Baseline Restoration Assessment (BRA) Report for Reach 5A, and the results are discussed in Section 9.2 of that report.

In addition, Table H1 provides a listing of all invasive plant species identified in Reach 5A during the 2022-2023 field investigations. This table identifies where these species were observed among the riverine, riverbank, backwater, floodplain, and vernal pool habitats. It also clarifies the status of each species relative to whether it is listed as MIPAG invasive (or likely invasive), IPANE invasive, ACOE invasive (as described above), or ACOE "unacceptable" (i.e., not invasive as used here, but unacceptable for use in wetland planting plans).

Table H1: Reach 5A Invasive and Other Unacceptable Plant Species Summary Data

Layer	Common Name	Scientific Name	Status <sup>1</sup>	Occurrence*
Tree	Norway maple	Acer platanoides	ABE	FP
	Catalpa	Catalpa speciosa	Е	В
Shrub	Japanese barberry	Berberis thunbergii	ABC	FP; VP
	Autumn olive	Elaeagnus umbellata	ABC	FP
	Burning bush	Euonymus alatus	ABC	FP; B; VP
	Glossy buckthorn	Frangula alnus	ABC	FP; VP
	Border privet	Ligustrum obtusifolium	DE	FP; B; VP
	Morrow's honeysuckle	Lonicera morrowii	ABE	FP; B; VP
	European buckthorn	Rhamnus cathartica	ABC	FP; B; VP
	Multiflora rose	Rosa multiflora	ABC	FP; VP
Woody Vine	Asian bittersweet	Celastrus orbiculatus	ABC	FP; B: VP
	Bishop's goutweed	Aegopodium podagraria	ABE	FP; B
	Garlic mustard	Alliara petiolata	ABE	FP; B
	Japanese knotweed	Fallopia japonica	ABC	FP; B
	Gill-over-the-ground	Glechoma hederacea	BE	В
	Dame's-rocket	Hesperis matronalis	ABE	FP
	Yellow iris	Iris pseudacorus	ABE	FP; B: BW; VP
l lowb	Moneywort	Lysimachia nummularia	AE	FP; BW; VP
Herb	Purple loosestrife	Lythrum salicaria	ABC	FP; BW
	Water forget-me-not	Myosotis scorpioides	DE	FP; B; BW; VP
	Giant chickweed	Myosoton aquaticum	Е	В
	Eurasian water-milfoil	Myriophyllum spicatum	ABE	FP; B; BW; R
	Japanese mountain-spurge	Pachysandra terminalis	Е	FP
	Reed canary grass	Phalaris arundinacea	ABC	FP; B; BW; VP
	Common reed	Phragmites australis	ABC	FP; VP

Layer	Common Name	Scientific Name	Status <sup>1</sup>	Occurrence*
	Curly pondweed	Potamogeton crispus	ABE	B; R
	Water chestnut	Trapa natans	ABC	BW
	Narrow-leaved cattail	Typha angustifolia	E	FP
	Broad-leaved cattail	Typha latifolia	E	FP
	Rough cocklebur	Xanthium strumarium	E	FP; B; VP

<sup>&</sup>lt;sup>1</sup>Invasive Ratings: A= MIPAG Invasive; B=IPANE Invasive; C=ACOE Invasive; D=MIPAG Likely Invasive; E=ACOE Not Invasive, but Unacceptable (for use in wetland mitigation plans)

<sup>\*</sup>Occurrence Codes: FP=Floodplain; B=Bank; BW=Backwater; R=River; VP=Vernal Pool

# Appendix H-2: General Information on Primary Invasive Species Identified Common (or European) Buckthorn (*Rhamnus cathartica*)

While buckthorn was apparently introduced to the United States in Massachusetts in late 1800s. Its occurrence as an invasive species affecting habitat quality has been noted more prominently in the upper Midwest, leading to extensive research and control efforts in those states versus the Northeast. However, the information and experience gained from the upper Midwest are directly applicable to the Northeast given the ecological similarities between these regions. In New England, buckthorn is found most often on disturbed, open, moist sites and successfully invades abundant habitats including "abandoned fields and pastures, open woods, early successional forests, edges, planted forests, floodplain and riparian forests, wet meadows, ravines, open disturbed areas, roadsides, fencerows, vacant lots, and yards or gardens" (IPANE 2007). Buckthorn outcompetes native understory species for light, nutrients, and moisture, potentially forming monotypic stands that suppress plant and animal diversity. Old field areas of this region most often show buckthorn abundance and preference on sites that had a history of plowing compared to former pastures or continuously forested woodlots (McDonald et al. 2008). As buckthorn continues to persist and establish, further invading a forested area to become increasingly dominant, it creates shadier areas throughout the growing season than forested areas not invaded by buckthorn, thus progressively shading out the native seedlings and saplings of herbaceous, shrub and tree layers and outcompeting most plants that try to grow beneath it.

#### Morrow's Honeysuckle (Lonicera morrowii)

Morrow's honeysuckle is a deciduous shrub that was imported from Japan and South Korea in the 1800s for use as an ornamental, wildlife food and cover, and soils erosion control. After wide planting through the 20<sup>th</sup> century, its progressive destructive impact on native species in natural areas, and parks and gardens prompted its recognition as a highly invasive species. It is shade tolerant but prefers full sun where it produces more flowers and fruit, and invades forest edges and interiors, floodplains, pastures, old fields, roadsides and other disturbed areas through the help of rapid seed dispersal by birds and mammals. It also spreads vegetatively promoting its ability to form dense thickets by outcompeting native trees, shrubs and herbaceous plants, thereby displacing them. The branching structure of Morrow's honeysuckle promotes nest predation of birds. Its fruit provides some nutrition for birds and mice in winter, however, is overall insufficient for the nutrition needed to sustain birds, particularly migrating birds, naturally provided by the nutrition rich fruit of native species. Its prevention and control are the same as for buckthorn by pulling (seedlings), cutting larger stems, and applying herbicides containing glyphosate or triclopyr to foliage or cut stems.

#### Multiflora Rose (Rosa multiflora)

Multiflora rose is an invasive shrub introduced to the United States in 1866 from east Asia as rootstock for its aesthetic ornamental roses, and use as a fence, as well as for erosion control and wildlife food and cover. It is found in abandoned fields, hedgerows, forest edges and roadsides with its preference

for full sun to moderate shade environments, but can also endure the shade of mature forests. It flourishes on sites having general poor growth conditions involving light, moisture, salinity, or pH, but does not tolerate extreme cold below -28 degrees F. Multiflora rose spreads by seed, root sprouting and layering, a process where a stem, or cane, comes in contact with the soil as it grows, and produces roots to become a functionally independent plant. The fruit, or hips, persist on branches through winter providing a continuous food source as they are commonly found among the next year's flowers. Birds facilitate seed dispersal and seeds can remain viable in the soil for up to 20 years. After an initial slow growth period the first 1-2 years, the plant reproduces aggressively by seeds and sprouts, and expands through layering to form dense thickets, establishing monocultures that deteriorate natural environments and inhibit plant and wildlife diversity. Native invertebrates rarely consume its leaves creating a change in the chemical composition of the decomposing leaf litter that enhances the shrub's growth and dominance of the site, particularly in riparian areas. Treatment for control of multiflora rose includes the cut with herbicide application method as with buckthorn.

#### Garlic Mustard (Alliaria petiolata)

Garlic mustard is an invasive biennial herb likely introduced to North America from Europe and western Asia for medicinal and herbal uses, and erosion control. It was first recorded in 1868 in Long Island, NY. It is shade tolerant and thrives in forest understories, but also grows in open sun. It grows best on moist, well drained soils, and found in upland and floodplain forests, savannas, along trails, roadsides, and disturbed areas. It reproduces only from seed, seed production is very high, and seeds remain viable in the seedbank for many years. Garlic mustard outcompetes native species for sunlight, moisture, nutrients and space to form dense populations by emerging and growing earlier than native species in the spring, and by releasing chemicals from its roots (allelopathy) which impact mycorrhizal communities critical to native species subsistence, including economically valuable trees. Control and prevention of garlic mustard are the same as for buckthorn by pulling (seedlings) and applying herbicides containing glyphosate or triclopyr to foliage. The primary goals are to prevent second-year plants from producing seed, prevent new seeds from arriving from nearby populations and deplete the seed bank.

#### Asiatic Bittersweet (*Celastrus orbiculatus*)

Asiatic (or Asian) bittersweet is an invasive deciduous, woody, twining vine native to China, Japan, and Korea which was introduced into the United States around 1860 as an ornamental plant. Although hybridization with native American bittersweet has been observed in the laboratory, it is unclear how commonly it may occur naturally. It is most productive in full sun, however it easily germinates in shade and its seedlings are extremely shade tolerant. It is found in grasslands, open woods, woodland edges, closed-canopy forest, roadsides and fence rows, although also a problem on beaches and dunes in some states. Its growth by climbing any available support significantly threatens plant communities. It grows rapidly and shades out the vegetation supporting it, while encircling and girdling trees and shrubs, cutting off water and nutrients. Having a deep, extensive root system, it grows to 30 m (98.5 ft) in length and 18 cm (7 in) in diameter. It reproduces by seed and vegetatively by spreading underground roots

that form new stems, as well as sprouting from the root crown and small root fragments, thereby forming abundant clones from one or few seedlings. Flowers are produced by male (for pollen) and female plants by two years of age, and prolific fruit is produced by mature female plants with highest fruit production in full sun. Fruits are eaten and dispersed by birds and mammals, where the seed has been observed to remain in the gut of birds for extended time (14-42 days) promoting long distance dispersal of the species. Humans also contribute significantly to its dispersal through planting, and the use of its fruiting clustered scarlet berries with yellow-orange outer covering in fall decoration, facilitating its spread. Asian bittersweet vines and leaves may become a massive weight burdening and weakening trees, causing them to become vulnerable to wind and ice storms. Trees attached by these vines may also be pulled down when one tree falls or is cut down. The destructive impacts of invasive Asian bittersweet on trees and shrubs requires its prevention and control with the help of mechanical and chemical methods in meeting these goals, as with the prevention and control of buckthorn.

#### Bishop's Goutweed (Aegopodium podagraria)

Bishop's goutweed was introduced to North America by European settlers as an ornamental groundcover and was established in the United States by 1863. Its use has been as a low maintenance ground cover. It is an invasive, aggressive, creeping herbaceous perennial that forms dense, impenetrable patches that inhibit germination and/or establishment of native tree, shrub and herbaceous seedlings thereby displacing native species and greatly reducing species diversity. It prefers full sun, however it is highly shade tolerant and easily invades forests and dominates understories. It does very well in light to moderate shade and will flower least in dense shade. Seedlings grow best on disturbed, sunny sites, but leaves will die under intense heat or drought conditions. It is found in abandoned fields, pastures, gardens, forests, forest edges, riverbanks, streambanks, meadows, and disturbed areas. Bishop's goutweed tolerates a wide range of soil quality and pH. It changes soil chemistry by altering decomposition and nutrient cycling as well as other ecological processes in forests and woodlands, such as raising humidity and increasing shade near the forest floor which also reduces seedling recruitment of shade tolerant tree species. It reproduces primarily vegetatively by fast growing rhizomes, and spreads quickly as even a small rhizome fragment can resprout. It produces seeds that require cold stratification to germinate, therefore seeds germinate the following year after initial dispersal. Its seedbank is short-lived. It can grow to be 15-40 inches tall. Bishop's goutweed is quickly dispersed as populations grow, increase and spread rapidly through the rhizome system. Humans also are significant in its long-range dispersal through its use as a popular garden plant and sold as an ornamental groundcover. It also spreads through waterways. The destructive impact of bishop's goutweed on native plant species emphasizes the need for its control. The most effective control for an herbaceous, prolific rhizome forming and sprouting plant like bishop's goutweed are systemic herbicides, such as glyphosate, because they are translocated to the roots. Manual treatments are not recommended for bishop's goutweed.

#### Japanese Knotweed (Fallopia japonica)

Japanese knotweed is native to China, Japan, and Korea. It was originally introduced from Japan to the United Kingdom and by around 1855, had become increasingly popular and distributed there through garden catalogs. It was brought to the United States from the United Kingdom by the late 1800s for use in ornamental gardens. By 1894, it was reported as naturalized near Philadelphia, Pennsylvania, Schenectady, NY and Atlantic Highlands. NJ. By 1910, Japanese knotweed was promoted in garden catalogs in the United States, despite the recognition of its aggressive growth and decline in popularity by this time in the United Kingdom. By 1938, published information on how to get rid of Japanese Knotweed in gardens in the United States was available. Japanese knotweed is an upright, shrubby, woody appearing herbaceous perennial plant. It spreads primarily through long rhizomes, although it may produce some viable winged seeds that can spread distances through wind dispersal. New Japanese knotweed plants can sprout from stem nodes or rhizome fragments. Rhizome fragments can be easily dispersed naturally and are particularly problematic along larger rivers where flooding transports rhizomes downstream. They can also be dispersed through human actions. Japanese knotweed is extremely tolerant of dry to seasonally saturated soils as it flourishes in a variety of habitats including open uplands, riverbanks, lake shores, forest edges, and disturbed areas. It prefers full sunlight and thrives in riparian areas and wetlands, but can tolerate moderate shade, dry soil, high temperatures, and high soil salinity. It is found along roadsides, in vacant lots and yards or gardens. It is not tolerant of frost and dies back immediately for the season. It's quite successful in reproducing vegetatively to quickly form dense, persistent thickets that can grow up to 15 feet tall and inhibit growth of native vegetation to their exclusion, to form monoculture stands of Japanese knotweed. Due to its ability to easily grow and disperse new plants from its cut stem and rhizome if in contact with moist soil, its removal is difficult and it is extremely persistent.

#### Purple Loosestrife (Lythrum salicara)

Purple loosestrife, a native plant of Eurasia, was first reported in North America in 1814. Its introduction is unclear and involves multiple likely theories possibly involving multiple introductions. These include being introduced accidentally through ship ballasts or seeds that were transported in imported raw wool or on sheep, or deliberately brought over as an ornamental plant, a source of nectar for beekeeping or for medicinal reasons. The recognized presence of purple loosestrife populations established in estuaries between Massachusetts and New Jersey before 1900 is thought to indicate the area of its original introduction. More inland populations were reported by the 1900s with continual spread through garden plantings and waterways. Purple loosestrife is a striking herbaceous perennial wetland plant, standing 3 to 10 feet tall but 5 feet tall on average, with beautiful purple flowers adorning the 4-16 inch spikes at the tips. Its beauty is deceptive, however, as its rapid, spreading growth forms a monotypic stand that no bird, mammal, or fish depends on. A purple loosestrife plant produces 2.5 to 2.7 million seeds annually that are viable for years remain dormant until germination conditions are suitable, and are easily dispersed and transported by water, wind, birds, mammals, and humans. Purple loosestrife also spreads by resprouting from broken stems, underground roots, and plant fragments. It

has no natural predators, disease or insect, on this continent which only strengthens its prevailing ability to out-compete native vegetation and form monotypic stands. It prefers moist organic soils, fluctuating water levels and full sunlight, conditions under which many native plants are stressed. Purple loosestrife tolerates a wide range of environmental conditions such as temperature, sunlight, pH and nutrient levels, and has the ability to grow and establish on a wide range of substrates including gravel, sand, clay, and organic soil. Its favored habitats are freshwater marshes, open stream margins, and alluvial floodplains, however it successfully invades wet meadows, pasture wetlands, cattail marshes, stream and river banks, lake shores, irrigation ditches, drainage ditches and stormwater retention basins, and disturbed areas such as construction sites. Purple loosestrife displaces and replaces native flora and fauna causing habitat devastation resulting in elimination of food, nesting, and shelter for wildlife, and diminished habitat availability. It threatens wetlands and waterways, and fish spawning and waterfowl habitat. It fills in wetlands and reduces the water flow and flood retention. Although no control method will completely eliminate purple loosestrife, the use of physical, biological, and chemical controls help to stabilize populations within ecologically acceptable limits. Loosestrife-feeding beetles (Galerucella spp.) from Europe have been introduced to North America in the 1990s as a potential biological control. There has been considerable success in using these beetles to control purple loosestrife levels in marshes throughout the Northeast, including in Massachusetts.

#### Reed Canary-Grass (Phalaris arundinaceae)

Reed canary-grass is native to Europe, Asia, and North America; however, the European cultivar was introduced to the United States in the early 1800s for forage grasses and revegetation of eroded stream banks. The growth of the European reed canary-grass is more aggressive and is believed to have been cross-bred for this trait, resulting in the invasive reed canary-grass cultivars. Reed canary-grass is a perennial sod-forming grass that grows 2-9 feet tall. It inhabits areas typical of wet soils, preferably wetlands and floodplains adjacent to rivers and streams that are found in cool-season regions. It is also found thriving along lakesides, and in marshes and ditches. Although it favors wet soils, it can also grow in dry soils in wooded areas that are shaded, and along roadways. Reed canary-grass invades and spreads rapidly through rhizomes and runners and its dense growth eliminates other native vegetation, including tree growth in floodplain forests. It forms dense monotypic colonies that may grow to cover acres, severely diminishing available wildlife or waterfowl habitat. It is difficult to eradicate established colonies and various mechanical and chemical methods are required for control.

#### Common Reed (Phragmites australis)

Common reed, commonly referred to as Phragmites, is native to some parts of the United States. It is known to have been present in New England for at least 4000 years. Phragmites remains in 3000 year-old peat moss samples have been found in Connecticut. At least three strains of Phragmites are found in the United States with one known strain native to the United States. With the recognition of genetically different Phragmites populations, a newer non-native invasive strain was found and determined accidentally introduced to North America from Europe in the late 1700s or early 1800s in ship ballast. This non-native invasive Phragmites first established along the Atlantic coast and spread

across the continent during the 20th century. It currently occurs throughout the eastern half of the United States and is the most common Phragmites strain found in New York and the Northeast. There is no evidence of hybridization between native and introduced strains in the field. Phragmites is a tall, very hardy, sun-loving, perennial grass that grows up to 16 feet high. Its growth forms a large, thick impenetrable wall (as in its name Phragma, Greek meaning fence). It reproduces primarily vegetatively through profuse growth of rhizomes and runners which provide broken fragments that may be transported and grow new plants. Phragmites also reproduces through seeds that are successfully dispersed, however, often experience inhibited germination by environmental conditions resulting in low seed viability. Phragmites is most often found in wet or marshy areas but can thrive in a variety of conditions including fresh or brackish water, an acid to alkaline pH range, and high salinity. Phragmites habitats include freshwater and brackish marshes; tidal and non-tidal wetlands; river, lake, or pond edges; roadside ditches and swales: and disturbed areas. It is an aggressive wetland invader that spreads for acres forming huge monocultures that exclude native vegetation and wildlife, fill in wetlands reducing water flow and flood retention of the wetland, and trap sediments that cause the waterbody to become increasingly shallow. Methods to eliminate and control Phragmites include mechanical removal, chemical herbicide application, hydrologic fluctuation (water level), and prescribed burns.

#### References

IPANE (Invasive Plant Atlas of New England), 2007. European Buckthorn. Department of Ecology and Evolutionary Biology. University of Connecticut. Storrs, CT, USA. Available: <a href="https://www.invasive.org/weedcd/html/ipane.html">https://www.invasive.org/weedcd/html/ipane.html</a>.

MIPAG, 2005. The Evaluation of Non-Native Plant Species for Invasiveness in Massachusetts (with annotated list). Massachusetts Invasive Plant Advisory Group. April 1, 2005. Updates on-line at: <a href="MIPAG">MIPAG</a> - Massachusetts Invasive Plant Advisory Group (massnrc.org).

USACE, 2020. New England District Compensatory Mitigation Standard Operating Procedures.

December 29, 2020. NEW ENGLAND DISTRICT REGULATORY DIVISION COMPENSATORY (army.mil).

The following websites have also provided information in assembling the invasive species summaries:

https://www.invasive.org/weedcd/pdfs/ipane/Phalarisarundinacea.pdf

https://www.mass.gov/doc/phragmites/download

https://nyis.info/invasive\_species/common-reed/

https://www.invasive.org/alien/pubs/midatlantic/phau.htm

https://www.invasive.org/alien/pubs/midatlantic/lomo.htm

https://www.invasive.org/weedcd/pdfs/ipane/Lythrumsalicaria.pdf

www.des.nh.gov

#### Appendix H: Invasive Species Summaries

www.mass.gov/doc/purple-loosestrife-0/download

https://www.invasive.org/weedcd/pdfs/ipane/Phalarisarundinacea.pdf

https://naturalresources.extension.iastate.edu/encyclopedia/reed-canary-grass-invasive-species-profile

https://dnr.wisconsin.gov/sites/default/files/topic/invasives/ReedCanaryGrass.pdf

IPANE - Catalog of Species Search Results (invasive.org)

http://nyis.info>invasive\_species>japanese-knotweed

http://maine.gov>invasive\_plants>fallopia-japonica

(https://extension.psu.edu/multiflora-rose).

https://www.vtinvasives.org/invasive/goutweed-or-bishops-weed

https://www.vtinvasives.org/sites/default/files/2016-10/Goutweed\_finalTREATMENT.pdf

https://www.maine.gov/dacf/mnap/features/invasive\_plants/aegopodium.html

https://www.michigan.gov/invasives/id-report/plants/herbs/garlic-mustard

https://www.michigan.gov/invasives/id-report/plants/vines/oriental-bittersweet