Lower Passaic River Restoration Project

AECOM

Physical Water Column Monitoring Sampling Program
Characterization Summary
Lower Passaic River Study Area RI/FS

May 2019



623743

Prepared for:
Cooperating Parties Group
Newark, New Jersey

Document No.: 60145884.D501

CV014001

Submitted to:
Lower Passaic River
Cooperating Parties Group

Submitted by:
AECOM
Chelmsford, MA
May 2019

Physical Water Column Monitoring Sampling Program Characterization Summary

Lower Passaic River Study Area RI/FS

Submitted to:
Lower Passaic River
Cooperating Parties Group

Submitted by:
AECOM
Chelmsford, MA
May 2019

Physical Water Column Monitoring Sampling Program Characterization Summary

Lower Passaic River Study Area RI/FS

Prepared By
Kristen Durocher, Task Manager, AECOM

Reviewed By
Don Kretchmer, DK Water Resource Consulting LLC

Reviewed By
Debra Simmons, Project Quality Assurance Manager, AECOM

Executive Summary

The Physical Water Column Monitoring (PWCM) program was conducted as a part of the Remedial Investigation/Feasibility Study (RI/FS) for the Lower Passaic River Study Area (LPRSA) and is documented in this report. The LPRSA includes the 17-mile tidal reach of the Lower Passaic River (LPR) from below the Dundee Dam (River Mile [RM] 17.4) to the confluence with Newark Bay (NB) (RM 0). The LPRSA also includes the tributaries to this reach (i.e., Saddle River, Second River, Third River, and the unnamed creek to the head of tide). The PWCM program also included sampling in the Newark Bay Study Area (NBSA) which includes NB and NB at its confluence with the Arthur Kill, the Kill van Kull, and the Hackensack River. The PWCM sampling was conducted to address the Data Quality Objectives (DQOs) described in the RI Water Column Monitoring/Physical Data Collection for the Lower Passaic River, Newark Bay and Wet Weather Monitoring Quality Assurance Project Plan/Field Sampling Plan Addendum (QAPP; AECOM 2010) and occurred between October 2009 and November 2010. Additional field work to measure dissolved oxygen concentrations in the LPR was covered by an addendum to the QAPP (Windward, 2012), and was conducted between August and December 2012. Field work was followed by sample analysis, data validation, and report preparation. The USEPA entered into an Administrative Settlement Agreement and Order on Consent (2007 Settlement Agreement; USEPA 2007) with the Cooperating Parties Group (CPG) to complete the RI/FS for the LPRSA.[1] AECOM was hired by the CPG and developed the PWCM program in accordance with the Guidance for Conducting Remedial Investigations and Feasibility Studies under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) (United States Environmental Protection Agency [USEPA] 1988) and the May 2007 Settlement Agreement (USEPA 2007). It had four primary goals (AECOM 2010):

1. Understand the estuarine dynamics such as the relationship between tidal forcing, freshwater flow and salinity patterns, and the range and nature of the tidal and net circulation. This investigation was designed to evaluate a range of hydrologic conditions (e.g., high and low watershed runoff) in order to understand the influence of those conditions on estuarine dynamics.

2. Characterize the influence of estuarine dynamics on suspended and bed sediments. This involved monitoring optical and acoustic backscatter (ABS) at a number of locations, as well as episodic sample collection and laboratory measurement of suspended solids for comparison with moored instruments and boat-based measurements.

3. Characterize the variation of particulate organic carbon (POC) and dissolved organic carbon (DOC) within the water column with hydrologic events, in space, and with variation in suspended solids.

[1] The CPG includes more than 60 cooperating members identified as potentially responsible parties (PRPs) for environmental response action in the LPRSA. Many other parties who have been identified as potentially responsible are not members of the CPG. Most notably, Tierra Solutions/Maxus/Occidental Chemical, considered the most significant responsible party due to significant contribution of 2,3,7,8-tetrachlorobibenzo-*p*-dioxin (2,3,7,8-TCDD), is no longer part of the CPG and no longer funding the RI/FS effort. In 2012, USEPA issued a Unilateral Administrative Order (UAO) against Occidental for its failure to contribute toward the CPG's removal of 2,3,7,8-TCDD contaminated sediment at RM 10.9.

4. Evaluate the contribution of the Passaic River above the Dundee Dam, the Saddle River, the Second River and the Third River to the suspended solids and POC/DOC balance of the LPR under flow conditions enhanced by storm events.

PWCM sample locations were chosen to fulfill the main goals of the program, providing spatial coverage in the LPRSA and NBSA, and to provide samples at key locations, such as the limit of the salt water incursion in the LPR (AECOM 2010).

The PWCM program was divided into three distinct tasks: (1) long-term deployment of conductivity, temperature and depth (CTD), optical backscatter (OBS) nephelometer, and Acoustic Doppler Current Profiler (ADCP) in the LPR and NBSA as well as deployment of a wave gage in NB during the Spring deployment, (2) boat-based transect surveys and water sampling, and (3) wet weather sampling grab sampling events in the freshwater tributaries (Second River, Saddle River and Third River) and immediately below Dundee Dam (Ackerman Street Bridge at RM 16.9). Two additional tasks, the March 2010 High Flow/Flood grab sampling in LPR, NB and the tributaries, and the Dissolved Oxygen Monitoring Program in the LPR and Upper Passaic River (UPR) were added to the PWCM program.

The program design included the following elements:

- **Long Term Deployment Surveys** – Two long term deployment surveys were conducted. The first survey was conducted in the LPRSA over two months in Fall 2009 (mid October through mid December). The second survey was conducted in the LPRSA and NBSA over four months in Spring 2010 (late March through late July). Instruments (CTD, OBS nephelometer, and ADCP) were deployed on five moorings located at RM 1.4, RM 4.2, RM 6.7, RM 10.2, and RM 13.5 and an additional mooring with only an OBS meter was deployed above Dundee Dam (the United Stated Geological Survey (USGS) water level gage provided flow information at this location). Three water level gages were installed at RM 1.0, RM 6.8, and at RM 13.9, at the fixed locations previously identified and occupied during the CPG Low Resolution Coring Program in 2008. The data from water level gages were collected contingency data should they be needed. Five NBSA locations with CTD, OBS and ADCP instruments were added to the list of moorings above during the second deployment in the spring of 2010 at NB North, NB South, Arthur Kill, Kill Van Kull and Hackensack. In addition, a wave gage was deployed at NB West during the Spring 2010 deployment. The long term deployment survey portion of the PWCM program is summarized in **Table ES-1.**
- **Boat-Based Transect Surveys** – Boat-based transect surveys (ADCP profiles across the transect and CTD and OBS casts at three locations on the transect) were performed during the long term deployment surveys at the locations of the five moorings in the LPR, one mooring above Dundee Dam, and at the five NBSA moorings (Spring 2010 only). The transect surveys were timed to capture both neap and spring tides. Water samples were collected at instrument deployment and retrieval and during each servicing survey prior to, and following, instrument servicing. Water samples were also collected along each transect during the ADCP surveys (separate from the sampling associated with deployment/servicing/retrieval). Nine hundred and fifteen (915) water samples (including quality control (QC) samples) for suspended sediment concentration (SSC) analysis and four hundred and thirty eight (438) water samples (including QC samples) for POC/DOC analysis were planned during the two deployment events combined. More samples than planned were collected due to an extension of the Spring 2010 deployment. One thousand eighty-seven (1,087) water samples (including quality control (QC) samples) for suspended sediment concentration (SSC) analysis, and, including QC samples, five hundred seventeen (517) samples were collected for DOC and five hundred twenty (520) were collected for POC during the two deployment events combined. The boat-based transect survey sampling and maintenance portion of the program is summarized in **Table ES-2**.

- **Wet Weather Sampling** - Wet weather sampling events were conducted in May 2010 and November 2010 for a total of two events. The tributaries included in this program include the Saddle River, the Second River, and the Third River. A location on the upper portion of the LPR just downstream of Dundee Dam (at the Ackerman Avenue Bridge at RM 16.9) was also sampled to provide additional data on potential above-dam suspended solids input. The data collected during the wet weather sampling portion of the PWCM program included SSC, POC and DOC. Samples were collected at two depths (surface and near bottom) for the station at RM 16.9 of the LPR and at mid-depth for locations in the LPRSA tributaries. These sample results were compared with instrument measured OBS in the LPR. Two sampling events were planned, and a total of up to 65 water samples (including QC samples) were planned for SSC and POC/DOC; sixty-four (64) were collected. The Wet Weather sampling event design is summarized in **Table ES-3**.
- **High Flow/Flood Grab Sampling** - In March 2010, an incoming storm was predicted to result in a rise in water levels in the Passaic River to above flood stage. The CPG requested AECOM sample from land-based stations and accompany Bob Chant of Rutgers University who had a vessel and equipment ready to conduct transect surveys in NB and the LPR during the storm event. The primary objective of this event was to collect additional POC, DOC and SSC data during a high flow event. Samples were collected from locations co-located with those sampled by Bob Chant. Overall, thirty-eight (including QC) samples for POC, DOC and SSC were collected during the High Flow/Flood sampling event. The High Flow/Flood sampling program is summarized in **Table ES-4**.
- **Dissolved Oxygen Monitoring -** To supplement the Baseline Ecological Risk Assessment (BERA) for the LPRSA, an addendum (Windward 2012) was written to the PWCM QAPP (AECOM 2010). The subject of this addendum was the addition of a 120-day dissolved oxygen monitoring program to the PWCM program. The program was conducted in late summer/fall (August to December) 2012 to characterize dissolved oxygen in near-bottom (i.e., 8 inches above river bottom) water in various salinity regimes of the LPRSA during times of low freshwater input (Windward 2013). **Table ES-5** summarizes the Dissolved Oxygen Monitoring Program.

Specific performance goals established for the PWCM to ensure that the DQOs were achieved are as follows:

- Field completeness, defined as the percentage of samples actually collected versus those intended to be collected, had a stated goal of greater than 95 percent (AECOM 2010). The PWCM program achieved >100 percent field completeness.
- Analytical completeness was defined as the number of data points that were accepted as usable based on the validation process divided by the total number of data points. The objective for this project was greater than 90 percent laboratory completeness (AECOM 2010). Laboratory completeness was >99 percent (2422 valid and acceptable results out of 2430 total reportable results) for the program.

The PWCM met its DQOs.

This report summarizes the field and laboratory procedures followed for the PWCM program. It also presents SSC, POC and DOC data collected during the PWCM in tables. Ocean Surveys, Inc. (OSI) collected data from the CTD, OBS nephelometer, wave gage and ADCP. Detailed data from these instruments are provided in the reports from OSI, provided in Appendices A, B and C.

Table ES-1
PWCM Program Design: Long Term Deployment Surveys
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Meter Deployments		
Locations[(1)]	**Events**	**Activity**
RM 1.4	Fall 2009, Spring 2010	CTD/OBS Surface and Bottom, ADCP Bottom
RM 4.2	Fall 2009, Spring 2010	CTD/OBS Surface and Bottom, ADCP Bottom
RM 6.7	Fall 2009, Spring 2010	CTD/OBS Surface and Bottom, ADCP Bottom
RM 10.2	Fall 2009, Spring 2010	CTD/OBS Surface and Bottom, ADCP Bottom
RM 13.5	Fall 2009, Spring 2010	CTD/OBS Surface and Bottom, ADCP Bottom
Dundee Dam	Fall 2009, Spring 2010	OBS at Surface
NB North	Spring 2010	CTD/OBS Surface and Bottom, ADCP Bottom
NB South	Spring 2010	CTD/OBS Surface and Bottom, ADCP Bottom
Arthur Kill	Spring 2010	CTD/OBS Surface and Bottom, ADCP Bottom
Kill van Kull	Spring 2010	CTD/OBS Surface and Bottom, ADCP Bottom
Hackensack River	Spring 2010	CTD/OBS Surface and Bottom, ADCP Bottom
Wave Gage Installation Locations		
NB Northwest	Spring 2010	
Water Level Gage Installation Locations		
RM 1.0		
RM 6.8		
RM 13.9		

(1) See Figure 2-1 for sampling locations
NB - Newark Bay
RM - River Mile
CTD - Conductivity, Temperature and Depth
OBS - Optical Backscatter
ADCP - Acoustic Doppler Current Profiler
PWCM - Physical Water Column Monitoring

Table ES-2
PWCM Program Design: Boat-Based Transect Surveys
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Boat Based Transects					
Locations[1]	**Events**	**Activity**	**Frequency**		**Number of Transect Surveys/Casts/Samples**
RM 1.4	Fall 2009	ADCP Transect	Monthly during deployment	Flood Tide and Ebb Tide	One transect
RM 4.2		CTD/OBS Profiles	Monthly during deployment	Flood Tide and Ebb Tide	Three locations along the transect
RM 6.7			Before and after deployment and servicing	Once	One location at mooring
RM 10.2		SSC sampling	Monthly during deployment	Flood Tide and Ebb Tide	Two depths at three locations along the transect
RM 13.5			Before and after deployment and servicing	Once	Two depths at mooring location
		DOC/POC Sampling	Monthly during deployment	Flood Tide and Ebb Tide	Two depths at mooring location
	Spring 2010	ADCP Transect	Monthly during deployment	Flood Tide and Ebb Tide	One transect
		CTD/OBS Profiles	Monthly during deployment	Flood Tide and Ebb Tide	Three locations along the transect
			Before and after deployment and servicing	Once	One location at mooring
		SSC sampling	Monthly during deployment	Flood Tide and Ebb Tide	Two depths at three locations along the transect
			Before and after deployment and servicing	Once	Two depths at mooring location
		DOC/POC Sampling	Monthly during deployment	Flood Tide and Ebb Tide	Two depths at two locations along the transect
Dundee Dam	Fall 2009	ADCP Transect	Monthly during deployment	Once	One transect
		CTD/OBS Profiles	Monthly during deployment	Once	Three locations along the transect
			Before and after deployment and servicing	Once	One location at mooring
		SSC sampling	Monthly during deployment	Once	Shallow depth at three locations along the transect and two depths at mooring
			Before and after deployment and servicing	Once	Two depths at mooring location
		DOC/POC Sampling	Monthly during deployment	Once	Two depths at mooring location
	Spring 2010	ADCP Transect	Monthly during deployment	Once	One transect
		CTD/OBS Profiles	Monthly during deployment	Once	Three locations along the transect
			Before and after deployment and servicing	Once	One location at mooring
		SSC sampling	Monthly during deployment	Once	Shallow depth at three locations along the transect and two depths at mooring
			Before and after deployment and servicing	Once	Two depths at mooring location
		DOC/POC Sampling	Monthly during deployment	Once	Shallow depth at three locations along the transect and two depths at mooring
NB North	Spring 2010	ADCP Transect	Monthly during deployment	Flood Tide and Ebb Tide	One transect
NB South		CTD/OBS Profiles	Monthly during deployment	Flood Tide and Ebb Tide	Three locations along the transect
Arthur Kill			Before and after deployment and servicing	Once	One location at mooring
Kill van Kull		SSC sampling	Monthly during deployment	Flood Tide and Ebb Tide	Two depths at three locations along the transect
Hackensack River			Before and after deployment and servicing	Once	Two depths at mooring location
		DOC/POC Sampling	Monthly during deployment	Flood Tide and Ebb Tide	Two depths at two locations along the transect

(1) See Figure 2-1 for sampling locations
ADCP - Acoustic Doppler Current Profiler
CTD - Conductivity, Temperature and Depth
DOC - Dissolved Organic Carbon
OBS - Optical Backscatter
POC - Particulate Organic Carbon
PWCM - Physical Water Column Monitoring
RM - River Mile
SSC - Suspended Sediment Concentration

Table ES-3
PWCM Program Design: Long Term Deployment Surveys
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Wet Weather Tributary Sampling				
Locations[1]	**Events**	**Activity**	**Frequency**	**Depth**
Saddle River	May 2010	SSC sampling	Once per hour up to 6 times	One at mid-depth[2]
Second River		DOC/POC Sampling	Once per hour up to 6 times	One at mid-depth[2]
Third River		OBS in situ	Once per hour up to 6 times	One at mid-depth[2]
RM 16.9		Water Depth	Once per hour up to 6 times	
	November 2010	SSC sampling	Once per hour up to 6 times	One at mid-depth[2]
		DOC/POC Sampling	Once per hour up to 6 times	One at mid-depth[2]
		OBS in situ	Once per hour up to 6 times	One at mid-depth[2]
		Water Depth	Once per hour up to 6 times	

(1) See Figure 2-2 for sampling locations
(2) Two depths (3 feet from bottom and 3 feet below surface) collected at RM 16.9
DOC - Dissolved Organic Carbon
OBS - Optical Backscatter
POC - Particulate Organic Carbon
PWCM - Physical Water Column Monitoring
RM - River Mile
SSC - Suspended Sediment Concentration

Table ES-4
PWCM Program Design: Long Term Deployment Surveys
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

High Flow/Flood Sampling		
Locations	**Frequency**	**Activity**
Bridge St Bridge	Four times	SSC sampling
Park Avenue Bridge	Four times	DOC/POC Sampling
Union Avenue Bridge	Four times	YSI profile(2,3)
RM 16.9	Four times	CTD profile(4)
Second River at Washington Avenue	Once	
Second River at Head of Tide	Once	
Third River at River Road	Once	
Third River at Head of Tide	Once	
Saddle River at Washington Avenue	Once	
Saddle River at Head of Tide	Once	
Eight Passaic River Locations(1)		
PR1	Once	
PR2	Once	
PR3	Once	
PR4	Once	
PR5	Once	
PR6	Once	
NB3	Once	
NB4	Once	
Four Newark Bay Locations(1)		
NB1	Once	
NB2	Once	
NB5	Once	
NB6	Once	

(1) See Figure 2-3 for sampling locations
(2) YSI profile included dissolved oxygen, turbidity, conductivity, and temperature
(3) YSI profiles were conducted during at least 2 sampling rounds from bridge locations in the LPR. Profiles were also collected at stations in the Second and Third Rivers
(4) CTD profiles were conducted at the eight Passaic River Locations and four Newark Bay locations.
DOC - Dissolved Organic Carbon
NB - Newark Bay
POC - Particulate Organic Carbon
PR - Passaic River
RM - River Mile
SSC - Suspended Sediment Concentration

Table ES-5
PWCM Program Design: Long Term Deployment Surveys
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Dissolved Oxygen Monitoring Program		
Locations[(1)]	**Activity**	**Frequency**
Estuarine Zone	Deployment 8 inches from bottom	Once for 120 days
RM 0.7	Servicing	Once per 20 days
RM 2.1	Vertical profile	Once per 20 days
RM 2.3		
Transitional Zone		
RM 4.2		
RM 5.5		
Lower Freshwater Zone		
RM 8.8		
RM 9.0		
RM 9.6		
Upper Freshwater Zone		
RM 12.8		
RM 14.1		
RM 14.7		
Upper Passaic River/Background		
RM 17.7		
RM 18.3		

(1) See Appendix E for sampling locations
PWCM - Physical Water Column Monitoring
RM - River Mile

List of Acronyms

°C	degrees centigrade
ABS	Acoustical Backscatter
ADCP	Acoustic Doppler Current Profiler
BERA	Baseline Ecological Risk Assessment
CDM Smith	CDM Smith, Inc.
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
cfs	Cubic Feet Per Second
COC	Chain-of-Custody
CPG	Cooperating Parties Group
CSO	Combined Sewer Overflow
CTD	Conductivity, Temperature and Depth
DDT	Dichlorodiphenyltrichloroethane
DGPS	Differential Global Positioning System
dmi	de maximis, inc.
DOC	Dissolved Organic Carbon
DQI	Data Quality Indicator
DQL	Data Quality Level
DQO	Data Quality Objective
DVR	Data Validation Report
EDD	Electronic Data Deliverable
FSP1	The Lower Passaic River Restoration Project Field Sampling Plan Volume 1 (MPI 2006)
FSP2	The Lower Passaic River Restoration Project Draft Field Sampling Plan Volume 2 (MPI et al. 2006)
FSP3	The Lower Passaic River Restoration Project Revised Preliminary Draft Field Sampling Plan Volume 3 (MPI 2005a)
GIS	Geographic Information Systems
GPS	Global Positioning System
HASP	Health and Safety Plan
HQI	HydroQual, Inc.
LBG	Louis Berger Group
LCS	Laboratory Control Sample
LCSD	Laboratory Control Sample Duplicate

LPR	Lower Passaic River
LPRRP	Lower Passaic River Restoration Project
LPRSA	Lower Passaic River Study Area
M&N	Moffatt and Nichol
MDL	Method Detection Limit
MEDD	Multi-Media Electronic Data Deliverable
MLW	Mean Low Water
MPI	Malcolm Pirnie, Inc.
MS	Matrix Spike
MSD	Matrix Spike Duplicate
NB	Newark Bay
NBSA	Newark Bay Study Area
NELAP	National Environmental Laboratory Accreditation Program
NJDEP	New Jersey Department of Environmental Protection
NJDOT	New Jersey Department of Transportation
NOAA	National Oceanic and Atmospheric Administration
NPL	National Priorities List
OBS	Optical Backscatter
OU	Operable Unit
OSI	Ocean Surveys, Inc.
PE	Performance Evaluation
POC	Particulate Organic Carbon
ppth	parts per thousand
PREmis	Passaic River Estuary Management Information System
PRP	Potentially Responsible Party
PWCM	Physical Water Column Monitoring
QA/QC	Quality Assurance/Quality Control
QAPP	Quality Assurance Project Plan
QC	Quality Control
QL	Quantitation Limit
R/V	Research Vessel
RCRA	Resource Conservation and Recovery Act
RI/FS	Remedial Investigation/Feasibility Study
RM	River Mile

RPD	Relative Percent Difference
Settlement Agreement	Administrative Settlement Agreement and Order on Consent
SDG	Sample Delivery Group
SEI	Sea Engineering, Inc.
SOP	Standard Operating Procedure
SSC	Suspended Sediment Concentration
SWO	Stormwater Outfall
TCDD	Tetrachlorodibenzodioxin
TOC	Total Organic Carbon
UAO	Unilateral Administrative Order
UPR	Upper Passaic River
UPS	United Parcel Service
USACE	United States Army Corps of Engineers
USEPA	United States Environmental Protection Agency
USFWS	United States Fish and Wildlife Service
USGS	United States Geological Survey
WRDA	Water Resources Development Act

Contents

1.0 Introduction 1-1

1.1 Environmental History and Setting 1-2
1.1.1 History of the LPR 1-2
1.1.2 Physical Setting of the LPRSA 1-4

1.2 Data Quality Objectives for the PWCM Program 1-6

1.3 PWCM Design 1-6

2.0 PWCM Sampling and Analysis 2-1

2.1 Field Contractors and Subcontractors 2-1
2.1.1 Ocean Surveys, Inc. 2-1
2.1.2 Laboratories 2-2

2.2 Sampling Program 2-2
2.2.1 Long Term Deployment Surveys 2-2
2.2.2 Boat-Based Transect Surveys 2-3
2.2.3 Wet Weather Tributary Sampling 2-4
2.2.4 High Flow/Flood Sampling 2-4
2.2.5 Dissolved Oxygen Study 2-5
2.2.6 Sample Analyses 2-6

2.3 General Field Activities 2-6
2.3.1 Vessel Positioning/Horizontal Control 2-6
2.3.2 Sample Nomenclature 2-6
2.3.3 Equipment Decontamination 2-6
2.3.4 Sample Custody, Storage, and Shipment 2-7

2.4 Quality Assurance/Quality Control 2-7
2.4.1 Quality Control Samples 2-7
2.4.2 Data Validation 2-7

2.5 Data Management 2-8

2.6 Field Modifications and Nonconformances 2-8
2.6.1 Field Modifications 2-8
2.6.2 Nonconformances 2-9

3.0 PWCM Sampling Results 3-1

4.0 Data Usability 4-1

4.1 Data Usability 4-1

4.2 Data Validation Findings 4-1

4.3 Data Quality Indicators 4-2
4.3.1 Precision 4-2
4.3.2 Accuracy 4-2
4.3.3 Representativeness 4-3
4.3.4 Comparability 4-3
4.3.5 Completeness 4-3
4.3.6 Sensitivity 4-4
4.4 Rejected Data 4-5

5.0 References 5-1

List of Appendices

Appendix A Final Report - Fall Deployment Oceanographic Data Acquisition Program, Lower Passaic River Restoration Project. OSI Report #09ES053

Appendix B Final Report - Spring Deployment Oceanographic Data Acquisition Program, Lower Passaic River Restoration Project. OSI Report #09ES053.2

Appendix C Final Report - Spring Deployment Oceanographic Data Acquisition Program – Newark Bay, Lower Passaic River Restoration Project. OSI Report #10ES006

Appendix D PWCM Sample Times During Tide Phases and Stages

Appendix E Dissolved Oxygen Monitoring Program Data Report for the Lower Passaic River Study Area: Summer and Fall 2012 - Draft

Appendix F Data Validation Reports

Appendix G ACDP Current and Wave Data Resubmittal from Fall 2009 and Spring/Summer 2010 Deployments

Appendix H Equipment Blanks

List of Tables

Table ES-1 PWCM Program Design: Long Term Deployment Surveys 4
Table ES-2 PWCM Program Design: Boat-Based Transect Surveys 5
Table ES-3 PWCM Program Design: Wet Weather Tributary Sampling 6
Table ES-4 PWCM Program Design: March 2010 High Flow/Flood Sampling Event 7
Table ES-5 PWCM Program Design: Dissolved Oxygen Monitoring Program 8
Table 2-1 Analytical Methods and Laboratories for PWCM 2-11
Table 2-2 Sample Nomenclature for PWCM Program 2-12
Table 2-3 Sample Location and Identification for PWCM High Flow/Flood Sampling Program 2-13
Table 2-4 Data Qualification Codes and Definitions for PWCM 2-14
Table 2-5 Split Samples Collected During PWCM Boat-Based Deployment Events 2-15
Table 2-6 Split Samples Collected During PWCM Wet Weather Tributary Sampling Events 2-18
Table 2-7 Location of Field and Laboratory Data for PWCM 2-19
Table 2-8 SSC Data Excluded from Regression Analyses by Moffatt and Nichol 2-20
Table 3-1 Results of POC, DOC and SSC Analysis 3-2
Table 4-1 PWCM Data Qualification Summary 4-6

List of Figures

Figure 1-1 Lower Passaic River Study Area 1-8
Figure 2-1 Wave Gauge and Mooring Locations 2-21
Figure 2-2 Wet Weather Event Sample Locations 2-22
Figure 2-3 High Flow/Flood Event Sample Locations 2-23

1.0 Introduction

The LPRSA encompasses the 17.4-mile tidal reach of the Passaic River below the Dundee Dam, its tributaries, and the surrounding watershed that drains to the river below the Dundee Dam (**Figure 1-1**). The LPRSA is an operable unit (OU) of the Diamond Alkali Superfund Site. The Diamond Alkali Superfund Site consists of three OUs, of which the LPRSA is OU2. The other two OUs are the former Diamond Alkali pesticide manufacturing plant and surrounding properties at 80 and 120 Lister Avenue in Newark, New Jersey (OU1), and the NBSA (OU3). An RI/FS, originally begun by the USEPA, is currently underway for the LPRSA in accordance with:

- The Lower Passaic River Restoration Project Work Plan (Malcolm Pirnie, Inc. [MPI], et al. 2005b);
- The Lower Passaic River Restoration Project Field Sampling Plan Volume 1 (FSP1) (MPI 2006);
- The Lower Passaic River Restoration Project Draft Field Sampling Plan Volume 2 (FSP2) (MPI, et al. 2006);
- The Lower Passaic River Restoration Project Revised Preliminary Draft Field Sampling Plan Volume 3 (FSP3) (MPI, et al. 2005a); and
- The Lower Passaic River Restoration Project QAPP (MPI, et al. 2005c).

The Lower Passaic River Restoration Project (LPRRP), congressionally authorized in 1999 under CERCLA and the Water Resources Development Act (WRDA), is a remediation and ecosystem restoration initiative for the LPR watershed. In May 2007, the USEPA entered into an Administrative Settlement Agreement and Order on Consent (2007 Settlement Agreement; USEPA 2007) with the CPG to complete the RI/FS for the LPRSA.[2] In addition to USEPA, several other federal and state agencies—collectively designated under the Settlement Agreement as "Partner Agencies"—have been designated as LPRRP participants. These include the U.S. Army Corps of Engineers (USACE), the New Jersey Department of Transportation (NJDOT), the National Oceanic and Atmospheric Administration (NOAA), the U.S. Fish and Wildlife Service (USFWS), and the New Jersey Department of Environmental Protection (NJDEP). The RI/FS is being conducted under the Settlement Agreement and includes the scopes of work identified in FSP1 (MPI 2006), FSP2 (MPI, et al. 2006), and FSP3 (MPI, et al. 2005a).

The PWCM program was developed in accordance with the Guidance for Conducting Remedial Investigations and Feasibility Studies under CERCLA (USEPA 1988) and the Settlement Agreement to determine the nature and extent of contamination, including chemical characterization of the 17.4-mile LPRSA. The PWCM field program was conducted from October 2009 through December 2012.

The PWCM was developed to meet the specific DQOs, as detailed in Section 1.2 of this report.

---

[2] The CPG includes more than 60 cooperating members identified as potentially responsible parties (PRPs) for environmental response action in the LPRSA. Many other parties who have been identified as potentially responsible are not members of the CPG. Most notably, Tierra Solutions/Maxus/Occidental Chemical, considered the most significant responsible party due to significant contribution of 2,3,7,8-tetrachlorobibenzo-*p*-dioxin (2,3,7,8-TCDD), is no longer part of the CPG and no longer funding the RI/FS effort. In 2012, USEPA issued a Unilateral Administrative Order (UAO) against Occidental for its failure to contribute toward the CPG's removal of 2,3,7,8-TCDD contaminated sediment at RM 10.9.

Field and analytical details for the performance of the PWCM are described in the QAPP prepared for this program (AECOM 2010). The original version of the PWCM QAPP was submitted to USEPA in June 2009. In response to USEPA comments four revisions of the QAPP were issued (Revision 1 was submitted in September 2009, Revision 2 was submitted in December of 2009, Revision 3 was submitted in February of 2010, Revision 4 was submitted in March 2010, and Revision 5 was submitted in April 2010). USEPA approval of the QAPP was received in April 2010. Field work was followed by sample analysis, data validation, and report preparation. As described in the Statement of Work in the Settlement Agreement (Section B.5.d. on page 6) a Characterization Summary report is required after each field investigation. In accordance with the Guidance for Conducting Remedial Investigations and Feasibility Studies under CERCLA (USEPA 1988), this report presents the methods of data collection and field and analytical findings of the PWCM.

This PWCM Sampling Program Characterization Summary report consists of the following sections, which are consistent with the outline for a site characterization summary provided in the Settlement Agreement:

- Executive Summary.
- Section 1.0 covers the history and background of the LPRRP, including the scope of the PWCM component and the DQOs established for this component.
- Section 2.0 includes details of the field implementation of the PWCM, including sample collection and processing, sample analysis, data collection and validation, and quality assurance/quality control (QA/QC) measures.
- Section 3.0 presents a summary of the analytical sample results.
- Section 4.0 provides an assessment of data usability.
- Section 5.0 provides document references.

Tables and figures can be found at the end of each section and all appendices follow the body of the main text.

The PWCM water quality data are summarized in selected tables in this report to provide a general representation of the entire PWCM dataset collected by the CPG. Field and validated laboratory data are provided in Appendices to this report.

1.1 Environmental History and Setting

The LPRSA and NBSA have been highly modified to accommodate urbanization, including the development of residential areas and industrial activities. Changes in the LPR, NB, and the associated watershed that accompanied European settlement and industrialization of the area to the present day are well chronicled (Iannuzzi et al. 2002). Most of the tidal marsh, mudflats, shallow nearshore areas, and tidal wetlands historically present in the LPRSA and NBSA have been either filled or dredged. Today, the majority of the shoreline in the LPR consists of riprap and sheet pile walls resulting in a highly channelized river. Upper portions of the LPR feature generally steeper and less modified shorelines with limited areas of riparian vegetation. The east bank is less modified, consisting of more natural shoreline, residential areas, and parks.

1.1.1 History of the LPR

The LPRSA is located within one of the major centers of the American Industrial Revolution. Early manufacturing was established near Paterson, NJ, during the post-colonial era. Beginning with cotton

mills, the LPR watershed, concentrated along the river, grew to include manufactured gas plants, petroleum refineries, tanneries, shipbuilding, smelting, pharmaceutical, electronic product, dye, paint, pigment, paper and chemical manufacturing plants, and other industrial activity (Shear et al. 1996; AECOM, et al. 2013). Major population centers such as Paterson and Newark transformed the watershed into a mix of residential, commercial, and industrial uses.

In 1858, the Dundee Dam and associated locks were constructed on the LPR. After the completion of the dam, mills were built along the upper LPR near the City of Passaic (Iannuzzi et al. 2002). Above Dundee Dam, the City of Paterson was a significant center of industrialization and manufacturing beginning in the late 18th Century. In the early 20th Century, Newark, NJ, became one of the largest industrial cities in the United States. Industries included petroleum refineries, shipping facilities, tanneries, and various manufacturers (Battelle 2005).

Approximately 88 percent of the wetlands near the LPR and NB were lost after 1816 (Iannuzzi et al. 2002). These wetland areas were ditched, diked, drained, and covered with fill material for various purposes including: salt hay production, gardens and dairies, railroad beds, oil storage/refining, shipyards and shipping ports, mosquito control, municipal and industrial waste disposal, and airport development (Iannuzzi et al. 2002).

Dredging in the LPR began in 1874 to allow for commercial shipping and for deeper-draft ships to dock in the lower section of the LPR. The channel was subject to numerous deepening and maintenance dredging activities over its first 50 years of existence. No new channel construction was authorized after 1932, but the existing channel was maintained for nearly 50 years (Figure 2-1). The river was busy with traffic during the 1940s, as the height of industrialization and manufacturing on the river coincided with World War II. Post-1950, most of the maintenance dredging focused primarily on the lower 2 miles of the channel. The last maintenance dredging conducted by USACE in 1983 removed more than 500,000 cubic yards of sediments to a depth of 30 feet mean low water (MLW) in the lower 1.9 miles of the channel (USACE 2010). A federal navigation channel of varying depth extending from the mouth of the river (RM 0) to the Eighth Street Bridge in Wallington, NJ (RM 15.4) was created in the late 19th century (USACE 2010). The navigation channel had four distinct segments with four different authorized depths (USACE 2010):

- 30-foot segment (RM 0 to RM 2.6). The channel has an authorized depth of 30 feet mean low water (MLW) and is 300 feet wide. The mean tidal range in this segment of the river is 5.5 feet.
- 20-foot segment (RM 2.6 to RM 7.2). The channel has an authorized constructed depth of 20 feet MLW and is 300 feet wide. From RM 4.1 to RM 7.2, the channel had the same authorized width and depth; however, the project was constructed to only 16 feet MLW.
- 16-foot segment (RM 7.2 to RM 8.1). The channel has an authorized constructed depth of 16 feet MLW and is 200 feet wide.
- 10-foot segment (RM 8.1 to RM 15.4). The channel has an authorized constructed depth of 10 feet MLW and is 150 feet wide.

In NB, dredging began in 1860, and between 1891 and 1934, a series of federal navigation channels and the large marine terminal at Port Newark were constructed. The dredge materials were used as fill at Port Newark and along the eastern shoreline to facilitate shoreline development. Maintenance dredging began in 1934 and continues to present day within NB and its tributaries. The latest dredging project, the New York/New Jersey Harbor Deepening Project, includes dredging in Ambrose Channel, Anchorage Channel, Kill van Kull Channel, NB Channels, the Port Jersey Channel, Arthur Kill (to Howland Hook), and Bay Ridge Channel to 50 feet deep in order to allow safe passage of new large container ships. Of

these, NB Channel, Arthur Kill Channel, and Kill van Kull Channel are within the study area for the PWCM program.

The Diamond Alkali Site, also referred to as the Lister Avenue Site, was placed on the National Priorities List (NPL) in September 1984 due to 2,3,7,8-TCDD contamination detected in site soils. Various companies at the 80 and 120 Lister Avenue facilities manufactured chemicals such as pesticides and phenoxy herbicides, including the primary components used to make the military defoliant Agent Orange. Chemical manufacturing and compounding occurred at this location from the 1940s through the 1960s (Bopp et al. 1991, 1998; Chaky 2003; Lillienfeld and Gallo 1989). Several investigators have since concluded that the Lister Avenue Site was the dominant 2,3,7,8-TCDD source to the LPRSA (Bopp et al. 1991, 1998; Chaky 2003; Hansen 2002), and a significant historical dichlorodiphenyltrichloroethane (DDT) source (Bopp et al. 1991, 2006). The Lister Avenue Site underwent several remedial actions under NJDEP and USEPA oversight between 1984 and 2004 (USEPA 2008; Tierra 2008).

Like many other urban systems, the LPR has been subjected to a broad range of contaminant loadings from multiple sources (e.g., untreated industrial and municipal wastewater, combined sewer overflows (CSOs)/stormwater outfalls (SWOs), direct runoff, atmospheric deposition) for a long time. A distinguishing characteristic of the LPR is its elevated levels of 2,3,7,8 TCDD in sediments, which is atypical of most other urban rivers.

1.1.2 Physical Setting of the LPRSA

The LPR is an integral part of the Greater NB complex, along with NB, Hackensack River, Arthur Kill, and Kill Van Kull (Figure 1-1). These water bodies are hydraulically connected through freshwater flows from the rivers to the ocean and by tidal flows that move water both inland and toward the ocean. The tidal flows also connect the NB Complex to New York Harbor and Raritan Bay (also referred to as the New York/New Jersey Harbor estuary or the Hudson-Raritan estuary).

The LPR extends from the Dundee Dam (RM 17.4) to NB (RM 0; Figure 1-1). It receives freshwater from the UPR at the Dundee Dam, three tributaries (Saddle River, Third River, and Second River), and to a lesser extent smaller tributaries; direct discharges from CSOs, SWOs, permitted municipal and industrial discharges; and direct runoff. Groundwater contribution to the LPR is considered small relative to the freshwater flow that enters the LPR from upstream during average flow conditions (AECOM et al. 2013).

The LPR is a partially mixed estuary with circulation and salinity patterns that are controlled mainly by a dynamic hydraulic balance between the upstream freshwater flow and the downstream brackish tidal inflow from NB. These flows and their interactions have resulted in the USEPA classifying the LPR into the following three major sections (AECOM et al. 2013; Sea Engineering Inc. [SEI] and HydroQual Inc. [HQI] 2011):

- RM 17.4 to RM 10 - Freshwater River Section (River Dominant) is the region usually upstream of the salt front (the salt front is upstream of RM 10 typically about 10% of the time, and has extended further upstream to at least RM 13 and during drought conditions to RM 14) (SEI and HQI 2011).
- RM 10 to RM 6 - Transitional River Section (Mixed) is characterized by the most frequent location of the salt front with water conditions varying from slightly brackish (or oligohaline, with salinity values ranging from 0.5 parts per thousand [ppth] to 5 ppth) to moderately brackish (or mesohaline, with salinity values ranging from 5 ppth to 18 ppth).

- RM 6 to RM 0 - Brackish River Section (Estuary Dominant) is located downstream of the typical location of the salt front and is mesohaline, i.e., with salinity values ranging from 5 ppth to 18 ppth.

These designations are qualitative—in reality, the location of the interface between fresh and saline waters (also referred to as the “salt front”) is strongly influenced by the balance between freshwater and tidal flows, as well as the system geometry. The salt front typically moves several miles during each tidal cycle (AECOM et al. 2013; Cañizares et al. 2009), and can reach as far upstream as about RM 14 under extreme low flow conditions (SEI and HQI 2011). The location of the salt front typically coincides with the location of the estuarine turbidity maximum, that is, the region of an estuary with maximum turbidity (Dyer 1995; Chant et al. 2010; Moffatt and Nichol [M&N] and Deltares 2013).

The location of the salt front varies with the freshwater discharge, inter-tidal timing (spring/neap), and intra-tidal timing (flood/ebb) (M&N and Deltares 2013). The salt front location[3] at various river discharges was computed using a hydrodynamic model developed by USEPA Region 2 (HQI 2006). The results indicate that on average, the salt front is situated upriver of RM 5 when discharge at Dundee Dam is below the annual average of 1,200 cubic feet per second (cfs) (HQI 2006; 1,140 cfs at Little Falls based on drainage-area proration). At mean river flow, it can reach RM 7. It is pushed downriver with increasing flow—at 2,000 cfs, it is found on average near RM 3; during a 1-year return flow of 6,000 cfs, it is pushed below RM 2; and during a 5-year return flow of 10,000 cfs, it is pushed below RM 1 (where the river widens). The location of the salt front at a given flow varies with the spring/neap tidal cycle, and can move between 0.5 to 3 miles over the tidal cycle (i.e., the tidal excursion) during neap tides and between 2 and 5 miles during spring tides.

Data collected at the NOAA station at Bergen Point West Reach indicate that LPR tides are semi-diurnal with a period of approximately 12.5 hours. Water levels exhibit a spring-neap period of 13.5 days. The tidal range varies between 0.9 meter at neap tide and 2.2 meters at spring tide (3.0 to 7.2 feet).

The LPR is relatively shallow, with maximum thalweg (i.e., deepest point, laterally, across the river) depths ranging from a few feet (upper portions below Dundee Dam) to 30 feet near the mouth of the river. A federally authorized navigation channel exists between the mouth of the river and approximately RM 15.4 (USACE 2007).

NB is approximately one mile wide and six miles long. According to USACE (1997), NB is naturally a shallow water body, with navigation channels, turning basins and docking facilities encompassing the deepest areas of the bay. Due to the Harbor Deepening Project, areas of NB near the Port of Newark and Elizabeth Marine Terminal reach depths of 50 feet. The eastern side of the bay is very shallow, with depths ranging from 0.5 to 10 feet below MLW. Areas south of Kearny Point and the Elizabeth Channel and along the western side of the bay above and below Port Newark Channel include other smaller pockets of shallow water.

The Passaic and Hackensack Rivers flow into NB from the north. NOAA (1984) estimates an annual average of 1,448 cfs of freshwater discharges to NB from the LPR making it the largest contributor of freshwater to NB; an additional 194 cfs of freshwater enters from the Hackensack River. On the south side of NB, Arthur Kill and Kill van Kull exchange saltwater with NB during tidal cycles.

---

[3] For discussion purposes, the location of the salt front is defined as the location of the 2 ppth isohaline at the bottom of the water column, unless otherwise noted.

1.2 Data Quality Objectives for the PWCM Program

The DQO process establishes performance and acceptance criteria, which serve as the basis for designing a plan for collecting data of sufficient quality and quantity to support the goals of the study. The document, Guidance on Systematic Planning Using the Data Quality Objectives Process (USEPA 2006), was used to develop the DQOs for the PWCM investigation. These DQOs are presented in the PWCM QAPP (AECOM 2010). The DQOs define the decision to which the data would contribute and specify the overall degree of data quality or uncertainty the decision maker is willing to accept during the decision making process.

The PWCM was developed to address the following data needs, as outlined in the PWCM QAPP (AECOM 2010):

- Understand the estuarine dynamics such as the relationship between tidal forcing, freshwater flow and salinity patterns, and the range and nature of the tidal and net circulation. This investigation was designed to evaluate a range of hydrologic conditions (e.g., high and low watershed runoff) in order to understand the influence of those conditions on estuarine dynamics.
- Characterize the influence of estuarine dynamics on suspended and bed sediments. This involved monitoring optical and acoustic backscatter at a number of locations, as well as episodic sample collection and laboratory measurement of suspended solids for comparison with moored instruments and boat-based measurements.
- Characterize the variation of POC and DOC within the water column with hydrologic events, in space, and with variation in suspended solids.
- Evaluate the contribution of the Passaic River above the Dundee Dam, the Saddle River, the Second River and the Third River to the suspended solids and POC/DOC balance of the LPR under flow conditions enhanced by storm events.

It has two primary DQOs (AECOM 2010):

1. Develop a better understanding of the estuarine dynamics and sediment transport of the LPR and NB system.
2. Develop a better understanding of the spatial and temporal variations of organic carbon within the water column.

1.3 PWCM Design

Nine hundred twenty (920) surface water samples (plus QC samples) were proposed for SSC and Four hundred sixty-six samples (466) (plus QC samples) were proposed for POC and DOC.

The program design included the following elements:

- **Long Term Deployment Surveys** – Two long term deployment surveys were conducted. The first survey was conducted in the LPRSA over two months in Fall 2009 (mid October through mid December). The second survey was conducted in the LPRSA and NBSA over four months in Spring 2010 (late March through late July). Instruments were deployed on five moorings located at RM 1.4, RM 4.2, RM 6.7, RM 10.2, and RM 13.5 and an additional mooring with only an OBS meter was deployed above Dundee Dam (the USGS water level gage provided flow information at this location). Three water level gages were installed at RM 1.0, RM 6.8, and at RM 13.9, at the fixed locations previously identified and occupied during the CPG Low

Resolution Coring Program in 2008. The data downloaded from these water level gages were collected for contingency, and were not processed. Five NBSA locations with CTD, OBS and currents using ADCP were added to the list of moorings above during the second deployment in the Spring of 2010 at NB North, NB South, Arthur Kill, Kill Van Kull, and Hackensack River. In addition, a wave gage was deployed at NB West during the Spring 2010 deployment.

- **Boat-Based Transect Surveys** – boat-based transect surveys (ADCP profiles across the transect and CTD and OBS casts at three locations on the transect) were performed at the locations of the six moorings in the LPRSA and at the five NBSA moorings (Spring 2010 only). The transect surveys were timed to capture both neap and spring tides. Water samples were collected at instrument deployment and retrieval and during each servicing survey prior to, and following, instrument servicing. Water samples were also collected along each transect during the ADCP surveys (separate from the sampling associated with deployment/servicing/retrieval). Nine hundred and fifteen (915) water samples (including QC samples) for SSC analysis and four hundred and thirty eight (438) water samples (including QC samples) for POC/DOC analysis were planned during the two deployment events combined.
- **Wet Weather Sampling** - Wet weather sampling events were conducted in May 2010 and November 2010 for a total of two events. The data collected during the wet weather sampling portion of the PWCM program included SSC, POC and DOC. Samples were collected at two depths (surface and near bottom) for the station at RM 16.9 of the LPR and at mid-depth for locations in the LPRSA tributaries. These sample results were compared with instrument measured OBS in the LPR. The tributaries included in this program include the Saddle River, the Second River, and the Third River. A location on the upper portion of the LPR just downstream of Dundee Dam (at the Ackerman Avenue Bridge at RM16.9) was also sampled to provide additional data on potential above-dam suspended solids input. Two sampling events were planned, and a total of up to 65 water samples (including QC samples) were collected for SSC and POC/DOC.
- **High Flow/Flood Grab Sampling** - In March 2010, an incoming storm was predicted to result in a rise in water levels in the Passaic River to above flood stage. The CPG requested AECOM sample from land-based stations and accompany Bob Chant of Rutgers University who had a vessel and equipment ready to conduct transect surveys in NB and the LPR during the storm event. The primary objective of this event was to collect additional data during a high flow event.
- **Dissolved Oxygen Monitoring -** To supplement the BERA for the LPRSA, an addendum (Windward 2012) was written to the PWCM QAPP (AECOM 2010). The subject of this addendum was the addition of a 120-day dissolved oxygen monitoring program to the PWCM program. The program was conducted in late summer/fall (August to December) 2012 to characterize dissolved oxygen in near-bottom (i.e., 8 inches above river bottom) water in the LPRSA during times of low freshwater input (Windward 2013).

Surface water samples were collected at each station using a pump, an Alpha sampling bottle, or direct immersion, depending on the location and accessibility. Details of the collection procedures are provided in Appendices A and B of the PWCM QAPP (AECOM 2010).

Field data collection and laboratory analyses were completed as described in the approved PWCM QAPP (AECOM 2010). Details of the field program implementation, including any modifications to the proposed program, are presented in Section 2.0.



Figure 1-1 Lower Passaic River Study Area

0 1 2 3 4 Miles

Lower Passaic River

LPRSA

6.5 (River Mile)

AECOM

May 2019

Ortho: Copyright:© 2009 ESRI, i-cubed, GeoEye

Map Projection: NJ State Plane, NAD 83 Feet

\\uswtfl1p001\jobs\Water\ProjectFiles\P120\12182_Passaic\Data\GIS\Tasks\RemedialInvestigation\2014RI_Figures\MXD_2014RI

2.0 PWCM Sampling and Analysis

This section provides a description of the field and laboratory activities performed during the PWCM. Each element of the PWCM is described briefly in this section. The PWCM was conducted in accordance with the procedures presented in the PWCM QAPP (AECOM 2010) and the associated field and laboratory standard operating procedures (SOPs) (Appendices B and C of the PWCM QAPP). The following sections describe variances, if any, from the approved procedures.

Anticipated modifications to field procedures that were necessary due to field conditions or equipment limitations were documented as field modifications and submitted to USEPA for approval. Deviations from approved field procedures, generally due to unforeseen circumstances, were documented in the field records at the time of occurrence. Significant deviations were additionally recorded as nonconformances and are summarized in this report (Section 2.6).

The PWCM field investigations were conducted from October 2009 through November 2010, with the dissolved oxygen study conducted August through December 2012. Field work was followed by sample analysis, data validation, and report preparation.

2.1 Field Contractors and Subcontractors

With the exception of the Dissolved Oxygen Monitoring Program, which was led by Windward Environmental under the direction of de maximis, inc. (dmi), AECOM served as the primary contractor for the PWCM field program, also working under the direction of dmi. Sample collection and processing, sample management, and data management for the PWCM program (excluding the Dissolved Oxygen Monitoring Program) were performed by AECOM personnel. Subcontractors were used by AECOM for sampling support and laboratory analyses, as described below.

2.1.1 Ocean Surveys, Inc.

Water quality sampling support was provided by OSI of Old Saybrook, CT. OSI provided vessels, vessel operators, and equipment for sampling, using a variety of their vessels selected to match the expected navigation and sampling challenges at each station and tide stage over a variety of flow, weather, and tide conditions. In general, smaller vessels were used at upstream locations which were constrained by access or bridge clearance while larger vessels were used at downstream locations which were generally more exposed to wind and weather. Each vessel was equipped with navigation equipment (global positioning system [GPS] and charts), a fathometer, *in situ* water quality instrumentation, and pumps to withdraw water samples.

OSI was responsible for the deployment, servicing and retrieval of all deployed instrumentation and conducted preliminary data analysis of data from the long term deployments. These data were provided to USEPA for inclusion in the Passaic River Estuary Management Information System (PREmis) database on a monthly basis as they were collected, and are provided in OSI's reports for the long term deployments (**Appendix A, Appendix B**, and **Appendix C**). OSI was responsible for calibration and operation of all equipment provided.

2.1.2 Laboratories

The analytical subcontractors to AECOM for the PWCM included one laboratory at two locations (AECOM 2010):

- Columbia Analytical Services, Inc. in Tucson, AZ, and
- Columbia Analytical Services, Inc. in Kelso, WA.

The laboratories and the analyses performed by each laboratory are shown in **Table 2-1**.

2.2 Sampling Program

The PWCM program was divided into five distinct tasks:

- Two long-term deployment surveys of CTD, OBS and ADCP in the LPR (Fall 2009 and Spring 2010) and NBSA (Spring 2010) as well as deployment of a wave gage in NB during the Spring deployment,
- Boast-based transect ADCP surveys and water quality sampling (POC, DOC and SSC) during the long term deployment surveys,
- Two wet weather sampling grab sampling events in the freshwater tributaries (Second River, Saddle River and Third River) and immediately below Dundee Dam (Ackerman Street Bridge at RM 16.9),
- The March 2010 High Flow/Flood grab sampling in LPR, NB and the tributaries, and
- The Dissolved Oxygen Monitoring Program in the LPR and UPR conducted in late Summer/early Fall of 2012.

The PWCM design, including selection of target flows, tidal conditions, station locations, target depths, and analytical parameters, is included in the PWCM QAPP (AECOM 2010) and is summarized in **Tables E-1 through E-5**. A summary of the design, including any changes from the proposed program, for each of the elements of the PWCM is presented below.

2.2.1 Long Term Deployment Surveys

2.2.1.1 Design

The data collected during the PWCM long term deployment surveys included salinity, temperature, water depth, turbidity, water velocity, wave height and period, acoustic backscatter, and water levels. Meters were deployed near the deepest part of the river cross section (thalweg), as allowed by boat traffic at two depths (surface and near bottom) for the five stations in RM 0 – 17.4 of the LPR, above Dundee Dam on the LPR, and for the five stations in the NBSA. The depths (3 feet off the bottom and 3 feet from the surface) were selected with the goal of sampling the relevant layer while avoiding artifacts associated with sampling in close proximity to the sediment bed, the pycnocline, and the water surface. The thalweg was the targeted location for the fixed moorings as it was assumed that the denser layer (i.e., colder and more saline water) with net tidal inflow is located in the deepest part of the cross section. The following instruments were deployed:

- *OBS Nephelometer*. This meter provided point measurements of turbidity. The OBS was deployed at two depths in the LPRSA and in NBSA (Spring 2010 only).

- *CTD* (integrated within the nephelometer). This meter provided point measurements of salinity (calculated from conductivity), temperature, and relative water depth over the meter (calculated from pressure). The CTD meter was used both in recording mode for the mooring deployments and in profile mode for use during the support surveys. The CTD was deployed at two depths in the LPR below Dundee Dam and in NBSA (Spring 2010 only). CTD meters were not deployed above Dundee Dam.
- *ADCP*. This meter provided multiple binned measurements of water velocity and acoustic backscatter over the water column. The ADCP was deployed near bottom in the LPR below Dundee Dam and in NBSA (Spring 2010 only). Boat-based ADCP surveys were conducted monthly during the long term deployments to collect measurements of the velocity profiles across the transects (see Section 2.2.2). ADCP was not deployed above Dundee Dam.
- *Water level gage*. This meter measured water pressure to provide measurements of tidally varying water levels. Water level gages were deployed at three locations in the LPR and the data were collected for contingency purposes. These data were not processed.
- *Wave gage*. This meter, an ADCP wave gage was used to measure wave amplitude and period in NBSA during the Spring 2010 deployment.

Two deployments (two-month and four-month) for CTD; OBS (a measure of turbidity); and currents using an ADCP were conducted. Instruments were deployed on five fixed moorings located at RM 1.4, RM 4.2, RM 6.7, RM 10.2, and RM 13.5 during both the Fall 2009 and Spring 2010 deployments. An additional mooring with only an OBS meter was deployed above Dundee Dam (the USGS water level gage provided flow information at this location) during both the Fall 2009 and Spring 2010 deployments. Three additional water level gages were installed at RM 1.0, RM 6.8, and RM 13.9, at fixed locations previously identified and occupied during the CPG Low Resolution Coring Program in 2008. During the second, four-month deployment (Spring 2010), the survey was expanded to include five locations in the NBSA: NB North, NB South, Arthur Kill, Kill van Kull, and Hackensack. **Figure 2-1** provides the locations of the LPRSA and NBSA mooring deployment locations.

Periodic surveys were conducted to allow moored instrument servicing/data downloading. Data were downloaded and reviewed in the field for completeness. These surveys were performed approximately monthly during the deployment.

A wave gage was installed in NB (**Figure 2-1**) during the Spring 2010 deployment.

2.2.1.2 Target Conditions

The long term mooring deployment surveys were conducted during spring and fall, to bracket the historic flows (high and low, respectively).

2.2.2 Boat-Based Transect Surveys

2.2.2.1 Design

The boat-based transect surveys were conducted and grab samples for SSC, DOC and POC were collected during mooring deployment. Boat-based transect ADCP surveys were conducted prior to mooring deployment, during meter maintenance (approximately monthly) and at mooring retrieval. Two deployments (two-month and four-month) were conducted in Fall 2009 and Spring 2010. **Figure 2-1** provides the locations of the LPRSA and NBSA mooring deployment locations; transects were conducted at these mooring locations. Transect surveys were conducted on flood tide and ebb tides. Three transect surveys were conducted in Fall 2009 and five in Spring 2010. SSC, POC and DOC were

collected using a submersible pump at the target sample depth. Samples for SSC, POC and DOC were collected as follows:

- Samples were collected during the boat transect surveys on the flood and ebb tides. CTD and OBS casts were conducted prior to and after collection of samples.
- SSC samples were collected from two depths at the mooring location, and from two locations along each transect.
- POC and DOC were collected from two depths at the mooring location and one additional location along each transect the furthest from the mooring.
- Samples were collected at instrument deployment and retrieval and during each servicing survey prior to and following instrument servicing. Water samples were collected along each transect during the ADCP surveys (separate from the sampling associated with deployments/servicing/retrieval).

2.2.2.2 Target Conditions

The boat-based transect surveys and water sampling events were conducted during the long term deployments in spring and fall, to bracket the historic flows (high and low, respectively). Transect surveys were conducted on flood tide and ebb tides, and were conducted during neap and spring tide conditions. **Appendix D** presents figures demonstrating the time of samples collected during the transect surveys with tide height and stage.

2.2.3 Wet Weather Tributary Sampling

2.2.3.1 Design

The data collected during the wet weather sampling portion of the PWCM program included SSC, POC and DOC. Samples were collected at two depths (surface and near bottom) for the station at RM 16.9 of the LPR and at mid-depth for locations in the LPRSA tributaries. **Figure 2-2** shows the locations of the wet weather tributary sampling stations.

Water samples were collected for laboratory analysis of SSC and POC/DOC to measure the suspended solids contribution of the LPR above Dundee Dam and major tributaries to the LPR under storm-enhanced flow conditions. These sample concentrations were compared to OBS measured by *in-situ* instruments. The tributaries included in this program include the Saddle River, the Second River and the Third River. The upper portion of the LPR just downstream of Dundee Dam (at the Ackerman Avenue Bridge at RM 16.9) was sampled to provide additional data on potential above-dam suspended solids input. Two sampling events occurred (May 2010 and November 2010).

2.2.3.2 Target Conditions

Criteria for mobilization of the field crews for collection of wet weather tributary samples was a forecast of at least 0.5 inches of rainfall over a 12 hour period. The primary forecast tool was the quantitative rainfall forecasts for the Passaic River at Little Falls (http://www.erh.noaa.gov/marfc/Maps/qpf/PITQPSRHA.txt). Additional mid and long range NOAA forecasts from NOAA (http://www.hpc.ncep.noaa.gov/qpf/qpf2.shtml and http://www.cpc.ncep.noaa.gov/products/forecasts/) were consulted as needed.

2.2.4 High Flow/Flood Sampling

The High Flow/Flood sampling event was conducted in response to a large storm that was predicted to generate heavy rain and flood conditions on the LPR. The event was conducted as a supplement to the

PWCM QAPP (AECOM 2010) in consultation with USEPA. Sampling occurred on March 16, 2010. General field procedures for this event followed the PWCM QAPP (AECOM 2010).

2.2.4.1 Design

Four rounds of samples were collected from RM16.9 at the Ackerman Bridge, Park Avenue Bridge, Union Avenue Bridge and Bridge Street Bridge. Each round consisted of one sample analyzed for SSC, POC and DOC. In addition, dissolved oxygen, conductivity, temperature and turbidity readings were made with a YSI© meter. These measurements were made during at least 2 rounds at each bridge.

One round of SSC, POC and DOC samples was collected from 2 locations in each of major tributaries (Second River, Third River and Saddle River). One location in each tributary was the tributary monitoring location identified in the PWCM QAPP and the other was at the USGS identified head of tide. Field measurements of dissolved oxygen, conductivity, temperature and turbidity were made at the Second and Third Rivers. High Flow/Flood sampling locations are presented in **Figure 2-3**.

AECOM accompanied Bob Chant (Rutgers University) in a boat as he performed CTD profiles through NB and the Passaic River below Bridge Street. Twelve surface samples (not including QC) were collected for SSC, POC and DOC analysis in conjunction with profiles. Eight samples were collected in the LPR and 4 samples were collected in NB. Samples/profiles were collected on the flood tide and during the maximum ebb tide.

Where possible, sampling was conducted from a fixed structure such as a bridge. If no fixed structure was available on the tributaries, samplers waded into the stream. Sampling was also conducted from the vessel contracted by Bob Chant as he conducted transect surveys in the LPR and NB. Samples were collected using an Alpha bottle or equivalent from bridges or direct immersion of the sampling bottles from the boat and at some tributary locations.

2.2.4.2 Target Conditions

The High Flow/Flood sampling was conducted based on predictions for high (> 7,000 cfs) flows on the LPR at Little Falls. The river peaked above 16,000 cfs.

2.2.5 Dissolved Oxygen Study

Continuous dissolved oxygen data were obtained from the 17.4-mile stretch of the LPRSA during the summer, when dissolved oxygen concentrations in near-bottom water were expected to be depressed due to relatively low freshwater input, relatively high water temperatures, and elevated sediment oxygen demand (USGS 2012). Since both physical and biological processes may influence dissolved oxygen (e.g., temperature, salinity, and sediment oxygen demand), temperature, pH, conductivity, and turbidity were measured along with dissolved oxygen in near-bottom water using multi-parameter water quality sondes.

2.2.5.1 Design

The sondes were deployed at 11 monitoring locations in the LPRSA that were selected to be representative of the salinity regimes (i.e., estuarine, transitional, and freshwater zones) and sediment total organic carbon (TOC) concentrations of the LPRSA and 2 monitoring locations above Dundee Dam. These monitoring locations, shown on Figure 2-1, were distributed as follows:

- Three monitoring locations in the estuarine zone (RM 0 to RM 4)
- Two monitoring locations in the transitional zone (RM 4 to RM 6)

- Six freshwater monitoring locations (three in the lower [RM 6 to RM 12] and three in the upper [RM 12 to RM 17.4] freshwater segments)
- One monitoring location above Dundee Dam (RM 17.4)

At each monitoring location, a YSI© multi-parameter water quality sonde was attached to a trawl-resistant bottom mount and deployed for 120 days. Dissolved oxygen, temperature, pH, conductivity, and turbidity data were collected at 15-minute intervals over the duration of the program. The sondes were serviced every 20 days to download data, replace batteries, and conduct recalibration. During each servicing, a separate meter was used at each station to obtain a vertical profile of dissolved oxygen, temperature, pH, conductivity, and turbidity. The multi-parameter water quality sondes were removed in the late fall after 120 days of deployment.

Additional details on survey methods and results may be found in the Dissolved Oxygen Monitoring Data Report (Windward 2013) included in **Appendix E**.

2.2.5.2 Target Conditions

The dissolved oxygen survey was conducted in late summer/early fall to target lower flows, when freshwater inputs to the LPR are expected to be minimal.

2.2.6 Sample Analyses

Every sample, excluding some QC samples, collected during the PWCM program was sent to the laboratories for analysis of SSC. A subset of samples was also analyzed for POC and DOC. Ultimately, one thousand, one hundred twenty (1,120) samples were collected for SSC, five-hundred eighty-three (583) for DOC and five hundred eighty six (586) for POC, not including QC samples. Sixty nine (69) field duplicates were collected for SSC, and thirty six (36) field duplicates were collected for POC and DOC.

2.3 General Field Activities

The following section describes general field activities undertaken for the PWCM program.

2.3.1 Vessel Positioning/Horizontal Control

Vessel positioning was performed in accordance with SOP LPR-G-02, Navigation/Positioning, with clarifications on position accuracy provided in the PWCM QAPP (AECOM 2010). For each station the on-board Differential Global Positioning System (DGPS) was used to position the vessel as close to the target location as possible and the vessel position was secured via setting anchors.

The accuracy of the DGPS system was maintained by OSI. The DGPS systems were checked against benchmarks established at OSI's Old Saybrook, CT office before departure and regularly in the field at temporary benchmarks established in the field and/or published benchmarks depending on the area.

2.3.2 Sample Nomenclature

Samples were identified using the sample nomenclature protocols provided in **Table 2-2** (Boat based surveys and wet weather tributary sampling) and **Table 2-3** (High Flow/Flood sampling).

2.3.3 Equipment Decontamination

Decontamination procedures followed those provided in the PWCM QAPP (AECOM 2010) SOPs.

2.3.4 Sample Custody, Storage, and Shipment

Following collection aboard the sampling vessel, samples were placed on ice in coolers. Samples were either transferred from the sampling vessel to a truck or from the sampling vessel to the transport vessel, from the transport vessel to a truck, and all samples were transported by truck to the CPG field facility.

Samples were maintained under chain-of-custody (COC) from collection, through delivery to the CPG field facility, and then through delivery to the laboratories.

At the end of each day, sample coolers were packed for shipment and COC forms were prepared for each cooler. All coolers were shipped via United Parcel Service (UPS) priority overnight delivery.

2.4 Quality Assurance/Quality Control

2.4.1 Quality Control Samples

Field and laboratory QC samples were collected and/or prepared to allow the quality of the data, in terms of accuracy/bias and precision, to be evaluated. Data quality and usability is discussed in Section 4.0.

2.4.1.1 Field Quality Control Samples

Field QC samples included field duplicate samples and equipment rinse blanks that were collected for analysis by the laboratory. Field QC samples were collected at the frequency described in the PWCM QAPP (AECOM 2010). A discussion of the results for these samples and other QC measures is provided in Section 4.0.

2.4.1.2 Laboratory Quality Control Samples

Laboratory QC samples were analyzed to provide a means of assessing the accuracy and precision of the analytical data. The laboratory QC program for the PWCM was based on analytical method requirements and the data quality needs of the program. A summary of the expected laboratory QC samples, frequency, and acceptance criteria was included in the PWCM QAPP (AECOM 2010). These samples included, as appropriate for the method, method/preparation blanks, laboratory control samples (LCSs), surrogates, laboratory duplicates, and matrix spike and matrix spike duplicate (MS/MSD) samples. Laboratory QC samples were analyzed at the frequency described in the PWCM QAPP (AECOM 2010). A discussion of the results for these samples and other QC measures is provided in Section 4.0.

2.4.1.3 Performance Evaluation Program

Performance Evaluation (PE) sample evaluation was used as part of the overall assessment of the laboratories selected for participation in the PWCM. The PE results for the laboratories' National Environmental Laboratory Accreditation Program (NELAP) certification were reviewed and found to be acceptable. No program-specific PE samples were analyzed.

2.4.2 Data Validation

The laboratory results for the PWCM program were subjected to formal data validation and data qualification per the PWCM QAPP (AECOM 2010). All validation was performed by AECOM. USEPA Region 2 validation SOPs were used as the basis for validation. If a Region 2 SOP was not available for a specific method, an SOP for a similar method was adopted for guidance. Data validation reports (DVRs) are contained in **Appendix F**.

At a minimum, 100% full validation was performed on the first two Sample Delivery Groups (SDGs). The remaining SDGs were subject to full validation for every 10 SDGs, and limited validation for the remaining SDGs.

In addition, data packages receiving limited validation received a completeness check so that full validation could be performed at a later date, if necessary.

2.4.2.1 Field Oversight

USEPA's oversight contractors, CDM Smith, Inc. (CDM Smith) in the LPRSA and Louis Berger Group (LBG) in the NBSA, were present at the CPG field facility and with at least one of the sampling teams to perform oversight of sample collection and processing and to collect split samples during each of the sampling events.

2.4.2.2 Split Sample Collection

CDM Smith and LBG personnel provided the required sample containers for split samples. AECOM personnel filled both the PWCM and CDM Smith/LBG sample containers by filling each bottle in a rotating basis by quarters to ensure comparability. The CDM Smith and LBG split samples collected during boat-bases surveys and wet weather tributary sampling operations are listed in **Tables 2-5 and 2-6**, respectively. The information in this table was provided by CDM Smith and LBG.

2.5 Data Management

The data generated during the PWCM program included sample locations, sample collection, *in-situ* field data, sample custody records, analytical results, and miscellaneous other records associated with field activities. Field data were either recorded manually onto standardized forms or in bound logbooks, or were entered into electronic templates on field laptop computers. All field data were electronically transmitted off site at the end of each field day where they were reviewed for completeness and filed electronically. Analytical results were received as data reports in Adobe Acrobat file format and as EQuIS® four-file electronic data deliverables (EDDs).

Table 2-7 lists the types of field and laboratory data that were collected and prepared. For each data type, it is noted whether the data are provided in this report or whether they are included only by reference and are maintained in the project files.

Data was submitted to the USEPA each month, per the Settlement Agreement, in Region 2 multi-media electronic data deliverable (MEDD) format along with the monthly progress report.

2.6 Field Modifications and Nonconformances

The following subsections describe the Field Modifications and Nonconformances that had an impact on the data quality of the PWCM program.

2.6.1 Field Modifications

During the course of the PWCM program, changes to the planned program and established procedures were recorded as Field Modifications and submitted to USEPA for approval. The field modifications listed below were written as modifications to earlier versions of the PWCM QAPP.

1) FM-PWCM 01 proposed that stations would be identified from the left bank looking upstream along each transect (P identifier). This modification was needed because sample location names and target coordinates were assigned for pre-printed labels from the left bank looking

upstream. This was a modification of the PWCM QAPP, Revision 0, Worksheet #27, which specified that stations along a transect would be identified looking downstream. This field modification was effective October 10, 2009.

2) FM-PWCM 02 proposed changing the RM designation, as described in PWCM QAPP Appendix A (FSP Addendum, Revision 1). The sample location names were assigned based on Geographic Information Systems (GIS) evaluation of the closest RM to target coordinates. This field modification changed the designated RM 4.3 to RM 4.2, which did not change the target location, only the sample location name. This field modification was effective October 10, 2009.

3) FM-PWCM 03 proposed changes to SOP LPR-FI-02 CTD/Turbidity Data Collection and Water Sampling. The proposed modification recommended using a vessel's fathometer and real time CTD read out to determine depth and vertical position to avoid potential disturbance of bottom sediments. This field modification was effective October 10, 2009.

4) FM-PWCM 04 proposed changes to the PWCM QAPP (September 2009). According to the aforementioned QAPP, the location and sample approach above the Dundee Dam would be modified following reconnaissance of the area during initial installation of sample locations and site visit. The QAPP was prepared without a detailed reconnaissance survey of the area. This field modification describes the methodology of selecting the mooring location, sample locations, and sample sequencing above the Dundee Dam. The modification was effective October 12, 2009.

2.6.2 Nonconformances

During the course of the PWCM sampling program, deviations to procedures were noted. The majority of the nonconformances did not impact data quality or objectives. The nonconformances that did have an impact on the data quality and/or resulted in variances from the planned program are summarized below.

1) The Seabird CTD failed and no downcast vertical profile was obtained at station T102-P3 during the afternoon flood tide monitoring event in October 2009. Samples for SSC were collected using a ruled staff, but no turbidity data were obtained for the correlation development. The data gap of one station paired turbidity/SSC data does not have a major impact on the overall data quality for the program.

2) During the High Flow/Flood event in NB and lower end of Passaic River, no water pump was available to collect samples at depth due to short notice of sampling event (<12 hours). The QAPP states that, in addition to surface samples, samples will be collected 3 feet above the bottom. Surface samples were collected by direct immersion of the sample bottles. Bottom samples were not collected. This did not cause an impact to the overall data quality of the PWCM program.

3) Due to the immediate mobilization of staff for the March 2010 High Flow/Flood event, an Alpha bottle sampler was not available for use. Samples were collected from bridges on the tributaries and at RM 16.9 using a container, a sash weight, and a lead line. This method of collection was expected to have no impact on data quality. The approved methods in the SOPs were used for subsequent sampling events.

4) Samples for SSC collected on May 24, 2010 were stored overnight in the CPG facility refrigerator. Upon arrival to the facility at 8:00 am on May 25, 2010, it was noted that the refrigerator had been accidentally turned off and the thermostat had reached 18 degrees centigrade (°C). QAPP specifies that samples will be stored at 0-6°C.

The refrigerator was turned back on and the SSC samples were packed immediately with extra ice and stored in the refrigerator until shipping later that day. The data was flagged as estimated ("J") during data validation, consistent with the Region 2 data validation guidelines. There was no significant impact to data quality.

5) Permanent staff gages installed at sample locations on the tributaries and at RM 16.9 were knocked over by high flows so water depths could not be obtained from the staff gages during the Spring 2010 sampling. Alternate methods were used to determine depths. Depth to water was gauged off a known location on the bridges (Ackerman Ave and Saddle River) and from top of wall to water level at Second River, and top of bridge to water level at Third River. This alternate method was used in subsequent sampling events and does not have an impact on data quality.

6) Moffatt and Nichol, the modeling team, used the data collected from the PWCM program to support the fate and transport model. During data analysis, SSC concentrations from eighteen of the 1,120 samples were noted to be inconsistent with OBS and ABS vertical gradients; the surficial SSC concentrations were higher than the near bottom SSC concentrations. These samples were excluded from the OBS-SSC and ABS-SSC regression analyses. The list of samples is provided in **Table 2-8**.

7) Water depths at RM 6.7 from October 12 through November 9, 2009 were noted to be inconsistent with data generated from the NOAA tide gage Bergen Point, and with water depths from RM 10.2 and RM 4.2. These data were corrected using an offset to the average of the water depths at RM 4.2 and 10.2 (offset of -2.15 feet calculated using data at RM 4.2, 10.2 and 6.7 from November 9, 2009 through the end of the Fall 2009 deployment).

8) During the Fall of 2009 and the Spring/Summer of 2010, OSI deployed a series of oceanographic instrumentation within the LPR and NBSA under contract with AECOM. This instrumentation included both ADCPs on bottom moorings and YSI© water quality sondes on bottom moorings and surface buoys. During data review by USEPA, questions arose regarding the current directional data from the ADCPs. OSI reviewed all the ADCP data from both the Fall 2009 and Spring/Summer 2010 datasets and concluded that compass offsets were not originally applied correctly during data processing. The ADCP data were reworked and the data resubmitted. Details of the field procedures and logistical considerations at the time of the deployment along with a description of the data processing steps taken to adjust current directional data are provided in **Appendix G**.

Table 2-1
Analytical Methods and Laboratories for PWCM
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Analysis	Method Reference	Laboratory SOP	Laboratory
TOC, POC, DOC	ASTM D6316-04, ASTM D4239-05, SW-846 9060, EPA 440.0	Total Carbon and Sulfur by Combustion/Infared Detection	CAS, Tucson, AZ
	EPA 440.0	Sample Preparation for Particulate Carbon and Nitrogen and Particulate Organic Carbon in Water	CAS, Tucson, AZ
	SM5310	Total and Dissolved Organic Carbon in Aqueous Matrix	CAS, Phoenix, AZ
SSC	ASTM D3977-97	Sediment Concentration in Aqueous Matrix	CAS, Phoenix, AZ

Notes:
ASTM - American Society for Testing and Materials
CAS - Columbia Analytical Services
DOC - Dissolved Organic Carbon
EPA - United States Environmental Protection Agency
GC/MS - Gas Chromatography/Mass Spectrometry
POC - Particulate Organic Carbon
PWCM - Physical Water Column Monitoring
SOP - Standard Operating Procedure
SSC - Suspended Sediment Concentration

Table 2-2
Sample Nomenclature for PWCM Program
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Program ID		Event ID		Transect		Station		Depth		Type	
09A	Fall 2009 LPRSA Boat Survey	Exx	Sequential number of unique sampling event	T175	Dundee Dam	Px	Sequential number of position along transect	X	No depth interval	S	Normal sample
10A	Spring 2010 LPRSA Boat Survey			T169	RM 16.9			A	Surface sample	T	Field duplicate
10B	High Flow/Flood Event			T135	RM 13.5			B	Second depth	R	Rinsate blank
10C	Wet Weather Tributary Sampling			T102	RM 10.2			C	Third depth		
N01	Spring 2010 NBSA Boat Survey			T067	RM 6.7						
				T042	RM 4.2						
				T014	RM 1.4						
				TKVK	Kill van Kull						
				TARK	Arthur Kill						
				TKHKN	Hackensack River						
				TNBS	Newark Bay South						
				TNBN	Newark Bay North						
				T2Rx	Second River, sequential visit						
				TSRx	Saddle River, sequential visit						
				T3Rx	Third River, sequential visit						

ID - Identification
LPRSA - Lower Passaic River Study Area
NBSA - Newark Bay Study Area
PWCM - Physical Water Column Monitoring
RM - River Mile

Table 2-3
Sample Location and Identification for PWCM High Flow/Flood Sampling Program
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location Coding						Sample Coding	
Program ID		Transect		Station		Sample ID	Location
10B	High Flow/Flood Event	TNBB	Newark Bay	Px	Sequential number of position along transect	Grab Samples	
		TPRB	Passaic River			ACKERMAN 1	Ackerman Bridge Sample #1
		TSR1	Saddle River			ACKERMAN 2	Ackerman Bridge Sample #2
		TSR3	Saddle River Head of Tide			ACKERMAN 3	Ackerman Bridge Sample #3
		T2R1	Second River at Washington Ave			ACKERMAN 4	Ackerman Bridge Sample #4
		T2R2	Second River at Head of Tide			UNION 1	Union Ave Sample #1
		T3R1	Third River			UNION 2	Union Ave Sample #2
		T3R2	Third River Head of Tide			UNION 3	Union Ave Sample #3
		T054	RM 5.4 at Bridge St.			UNION 4	Union Ave Sample #4
		T104	RM 10.4 at Park Ave.			PARK 1	Park Ave Sample #1
		T130	RM 13.0 at Union Ave.			PARK AVE 2	Park Ave Sample #2
		T169	RM 16.9 at Ackerman Bridge			PARK 3	Park Ave Sample #3
						PARK 4	Park Ave Sample #4
						PARK 5	Park Ave Sample #5
						BRIDGE ST. 1	Bridge St. Sample #1
						BRIDGE ST. 2	Bridge St. Sample #2
						BRIDGE 3	Bridge St. Sample #3
						BRIDGE 4	Bridge St. Sample #4
						SADDLE RIVER AVE 1	Saddle River
						SADDLE RIVER HOT 1	Saddle River Head of Tide
						2ND RIVER WASHINGTON AVENUE	Second River
						SECOND HOT	Second River Head of Tide
						THIRD RIVER ROAD 1	Third River
						THIRD RIVER HOT 1	Third River Head of Tide
						Boat-Based Transect Samples	
						PR1	LPR Transect Sample #1
						PR2	LPR Transect Sample #2
						PR3	LPR Transect Sample #3
						PR4	LPR Transect Sample #4
						PR5	LPR Transect Sample #5
						PR6	LPR Transect Sample #6
						NB1	NB Transect Sample #1
						NB2	NB Transect Sample #2
						NB3	NB Transect Sample #3
						NB4	NB Transect Sample #4
						NB5	NB Transect Sample #5
						NB6	NB Transect Sample #6

ID - Identification
LPR - Lower Passaic River
NB - Newark Bay
PWCM - Physical Water Column Monitoring
RM - River Mile

Table 2-4
Data Qualification Codes and Definitions for PWCM
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Qualifier	Definition[1]
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.

Notes:
[1] Qualifier definitions are consistent with USEPA Region 2 data validation guidance documents.
PWCM - Physical Water Column Monitoring
USEPA - United Stated Environmental Protection Agency

Table 2-5
Split Samples Collected During PWCM Boat-Based Deployment Events
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	CPG Sample ID	USEPA Sample ID	QA/QC	Date Collected	SSC	DOC/POC
Samples split with CDM-Smith						
10A-E02-T175-P2	10A-E02-T175-P2-AS	10A-E02-T175-P2-AS-CDM	MS/D for DOC only	3/24/2010	X	X
		10A-E02-T175-P2-AS-X	Duplicate	3/24/2010	X	X
10A-E02-T175-P2	10A-E02-T175-P2-BS	10A-E02-T175-P2-BS-CDM		3/24/2010	X	X
10A-E03-T014-P3	10A-E03-T014-P3-AS	10A-E03-T014-P3-AS-CDM		3/25/2010	X	X
10A-E03-T014-P3	10A-E03-T014-P3-BS	10A-E03-T014-P3-BS-CDM		3/25/2010	X	X
10A-E04-T014-P3	10A-E04-T014-P3-AS	10A-E04-T014-P3-AS-CDM		3/25/2010	X	X
10A-E04-T014-P3	10A-E04-T014-P3-BS	10A-E04-T014-P3-BS-CDM		3/25/2010	X	X
10A-E03-T042-P1	10A-E03-T042-P1-AS	10A-E03-T042-P1-AS-CDM		3/25/2010	X	X
10A-E03-T042-P1	10A-E03-T042-P1-BS	10A-E03-T042-P1-BS-CDM		3/25/2010	X	X
10A-E04-T042-P1	10A-E04-T042-P1-AS	10A-E04-T042-P1-AS-CDM		3/25/2010	X	X
10A-E04-T042-P1	10A-E04-T042-P1-BS	10A-E04-T042-P1-BS-CDM		3/25/2010	X	X
10A-E03-T067-P3	10A-E03-T067-P3-AS	10A-E03-T067-P3-AS-CDM		3/25/2010	X	X
10A-E03-T067-P3	10A-E03-T067-P3-BS	10A-E03-T067-P3-BS-CDM		3/25/2010	X	X
10A-E04-T067-P3	10A-E04-T067-P3-AS	10A-E04-T067-P3-AS-CDM		3/25/2010	X	X
10A-E04-T067-P3	10A-E04-T067-P3-BS	10A-E04-T067-P3-BS-CDM		3/25/2010	X	X
10A-E03-T102-P1	10A-E03-T102-P1-AS	10A-E03-T102-P1-AS-CDM		3/25/2010	X	X
10A-E03-T102-P1	10A-E03-T102-P1-BS	10A-E03-T102-P1-BS-CDM		3/25/2010	X	X
10A-E04-T102-P1	10A-E04-T102-P1-AS	10A-E04-T102-P1-AS-CDM		3/25/2010	X	X
10A-E04-T102-P1	10A-E04-T102-P1-BS	10A-E04-T102-P1-BS-CDM		3/25/2010	X	X
10A-E03-T135-P3	10A-E03-T135-P3-AS	10A-E03-T135-P3-AS-CDM		3/25/2010	X	X
10A-E03-T135-P3	10A-E03-T135-P3-BS	10A-E03-T135-P3-BS-CDM		3/25/2010	X	X
10A-E04-T135-P3	10A-E04-T135-P3-AS	10A-E04-T135-P3-AS-CDM		3/25/2010	X	X
10A-E04-T135-P3	10A-E04-T135-P3-BS	10A-E04-T135-P3-BS-CDM		3/25/2010	X	X
10A-E07-T014-P3	10A-E07-T014-P3-AS	10A-E07-T014-P3-AS-C		5/3/2010	X	X
10A-E07-T014-P3	10A-E07-T014-P3-BS	10A-E07-T014-P3-BS-C		5/3/2010	X	X
10A-E07-T042-P1	10A-E07-T042-P1-AS	10A-E07-T042-P1-AS-C		5/3/2010	X	X
10A-E07-T042-P1	10A-E07-T042-P1-BS	10A-E07-T042-P1-BS-C		5/3/2010	X	X
10A-E07-T067-P3	10A-E07-T067-P3-AS	10A-E07-T067-P3-AS-C		5/3/2010	X	X
10A-E07-T067-P3	10A-E07-T067-P3-BS	10A-E07-T067-P3-BS-C		5/3/2010	X	X
10A-E07-T102-P1	10A-E07-T102-P1-AS	10A-E07-T102-P1-AS-C		5/3/2010	X	X
10A-E07-T102-P1	10A-E07-T102-P1-BS	10A-E07-T102-P1-BS-C		5/3/2010	X	X
10A-E07-T135-P3	10A-E07-T135-P3-AS	10A-E07-T135-P3-AS-C		5/3/2010	X	X
10A-E07-T135-P3	10A-E07-T135-P3-BS	10A-E07-T135-P3-BS-C		5/3/2010	X	X
10A-E06-T175-P2	10A-E06-T175-P2-AS	10A-E06-T175-P2-AS-C	MS/D for DOC only	5/4/2010	X	X
		10A-E06-T175-P2-AS-X	Duplicate	5/4/2010	X	X
10A-E06-T175-P2	10A-E06-T175-P2-BS	10A-E06-T175-P2-BS-C		5/4/2010	X	X
10A-E12-T014-P3	10A-E12-T014-P3-AS	10A-E12-T014-P3-AS-C		5/24/2010	X	X
10A-E12-T014-P3	10A-E12-T014-P3-BS	10A-E12-T014-P3-BS-C		5/24/2010	X	X
10A-E12-T042-P1	10A-E12-T042-P1-AS	10A-E12-T042-P1-AS-C		5/24/2010	X	X
10A-E12-T042-P1	10A-E12-T042-P1-BS	10A-E12-T042-P1-BS-C		5/24/2010	X	X
10A-E12-T067-P3	10A-E12-T067-P3-AS	10A-E12-T067-P3-AS-C		5/24/2010	X	X
10A-E12-T067-P3	10A-E12-T067-P3-BS	10A-E12-T067-P3-BS-C		5/24/2010	X	X
10A-E12-T102-P1	10A-E12-T102-P1-AS	10A-E12-T102-P1-AS-C		5/24/2010	X	X
10A-E12-T102-P1	10A-E12-T102-P1-BS	10A-E12-T102-P1-BS-C		5/24/2010	X	X
10A-E12-T135-P3	10A-E12-T135-P3-AS	10A-E12-T135-P3-AS-C		5/24/2010	X	X
10A-E12-T135-P3	10A-E12-T135-P3-BS	10A-E12-T135-P3-BS-C		5/24/2010	X	X
10A-E11-T175-P2	10A-E11-T175-P2-AS	10A-E11-T175-P2-AS-C	MS/D for DOC only	5/25/2010	X	X
		10A-E11-T175-P2-AS-X	Duplicate	5/25/2010	X	X
10A-E11-T175-P2	10A-E11-T175-P2-BS	10A-E11-T175-P2-BS-C		5/25/2010	X	X
10A-E17-T014-P3	10A-E17-T014-P3-AS	10A-E17-T014-P3-AS-C		6/22/2010	X	X
10A-E17-T014-P3	10A-E17-T014-P3-BS	10A-E17-T014-P3-BS-C		6/22/2010	X	X
10A-E17-T042-P1	10A-E17-T042-P1-AS	10A-E17-T042-P1-AS-C		6/22/2010	X	X

Table 2-5
Split Samples Collected During PWCM Boat-Based Deployment Events
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	CPG Sample ID	USEPA Sample ID	QA/QC	Date Collected	SSC	DOC/POC
10A-E17-T042-P1	10A-E17-T042-P1-BS	10A-E17-T042-P1-BS-C		6/22/2010	X	X
10A-E17-T067-P3	10A-E17-T067-P3-AS	10A-E17-T067-P3-AS-C		6/22/2010	X	X
10A-E17-T067-P3	10A-E17-T067-P3-BS	10A-E17-T067-P3-BS-C		6/22/2010	X	X
10A-E17-T102-P1	10A-E17-T102-P1-AS	10A-E17-T102-P1-AS-C		6/22/2010	X	X
10A-E17-T102-P1	10A-E17-T102-P1-BS	10A-E17-T102-P1-BS-C		6/22/2010	X	X
10A-E17-T135-P3	10A-E17-T135-P3-AS	10A-E17-T135-P3-AS-C		6/22/2010	X	X
10A-E17-T135-P3	10A-E17-T135-P3-BS	10A-E17-T135-P3-BS-C		6/22/2010	X	X
10A-E16-T175-P2	10A-E16-T175-P2-AS	10A-E16-T175-P2-AS-C	MS/D for DOC only	6/21/2010	X	X
		10A-E16-T175-P2-AS-X	Duplicate	6/21/2010	X	X
10A-E16-T175-P2	10A-E16-T175-P2-BS	10A-E16-T175-P2-BS-C		6/21/2010	X	X
10A-E21-T014-P3	10A-E21-T014-P3-AS	10A-E21-T014-P3-AS-C		7/21/2010	X	X
10A-E21-T014-P3	10A-E21-T014-P3-BS	10A-E21-T014-P3-BS-C		7/21/2010	X	X
10A-E21-T042-P1	10A-E21-T042-P1-AS	10A-E21-T042-P1-AS-C		7/21/2010	X	X
10A-E21-T042-P1	10A-E21-T042-P1-BS	10A-E21-T042-P1-BS-C		7/21/2010	X	X
10A-E21-T067-P3	10A-E21-T067-P3-AS	10A-E21-T067-P3-AS-C		7/21/2010	X	X
10A-E21-T067-P3	10A-E21-T067-P3-BS	10A-E21-T067-P3-BS-C		7/21/2010	X	X
10A-E21-T102-P1	10A-E21-T102-P1-AS	10A-E21-T102-P1-AS-C		7/21/2010	X	X
10A-E21-T102-P1	10A-E21-T102-P1-BS	10A-E21-T102-P1-BS-C		7/21/2010	X	X
10A-E21-T135-P3	10A-E21-T135-P3-AS	10A-E21-T135-P3-AS-C		7/21/2010	X	X
10A-E21-T135-P3	10A-E21-T135-P3-BS	10A-E21-T135-P3-BS-C		7/21/2010	X	X
10A-E20-T175-P2	10A-E20-T175-P2-AS	10A-E20-T175-P2-AS-C	MS/D for DOC only	7/22/2010	X	X
		10A-E20-T175-P2-AS-X	Duplicate	7/22/2010	X	X
10A-E20-T175-P2	10A-E20-T175-P2-BS	10A-E20-T175-P2-BS-C		7/22/2010	X	X
Samples split with LBG						
N01-E03-TARK-P1	N01-E03-TARK-P1AS	N01-E03-TARK-P1AS-LB		3/25/2010	X	X
N01-E03-TARK-P1	N01-E03-TARK-P1BS	N01-E03-TARK-P1BS-LB		3/25/2010	X	X
N01-E04-TARK-P1	N01-E04-TARK-P1AS	N01-E04-TARK-P1AS-LB		3/25/2010	X	X
N01-E04-TARK-P1	N01-E04-TARK-P1BS	N01-E04-TARK-P1BS-LB		3/25/2010	X	X
N01-E07-TARK-P1	N01-E07-TARK-P1AS	N01-E07-TARK-P1AS-LB		5/3/2010	X	X
N01-E08-TARK-P1	N01-E08-TARK-P1AS	N01-E08-TARK-P1AS-LB		5/3/2010	X	X
N01-E12-TARK-P1	N01-E12-TARK-P1BS	N01-E12-TARK-P1BS-LB		5/24/2010	X	X
N01-E13-TARK-P1	N01-E13-TARK-P1BS	N01-E13-TARK-P1BS-LB		5/24/2010	X	X
N01-E17-TARK-P1	N01-E17-TARK-P1AS	N01-E17-TARK-P1AS-LB		6/22/2010	X	X
N01-E17-TARK-P1	N01-E17-TARK-P1BS	N01-E17-TARK-P1BS-LB		6/22/2010	X	X
N01-E21-TARK-P1	N01-E21-TARK-P1AS	N01-E21-TARK-P1AS-LB		7/21/2010	X	X
N01-E21-TARK-P1	N01-E21-TARK-P1BS	N01-E21-TARK-P1BS-LB		7/21/2010	X	X
N01-E03-THKN-P1	N01-E03-THKN-P1AS	N01-E03-THKN-P1AS-LB	Laboratory replicate for SSC only	3/25/2010	X	X
N01-E03-THKN-P1	N01-E03-THKN-P1BS	N01-E03-THKN-P1BS-LB		3/25/2010	X	X
N01-E04-THKN-P1	N01-E04-THKN-P1AS	N01-E04-THKN-P1AS-LB	Laboratory Replicate	3/25/2010	X	X
N01-E04-THKN-P1	N01-E04-THKN-P1AX	N01-E04-THKN-P1AX-LB	Field Duplicate	3/25/2010	X	X
N01-E04-THKN-P1	N01-E04-THKN-P1BS	N01-E04-THKN-P1BS-LB		3/25/2010	X	X
N01-E07-THKN-P1	N01-E07-THKN-P1AS	N01-E07-THKN-P1AS-LB	Laboratory Replicate	5/3/2010	X	X
N01-E08-THKN-P1	N01-E08-THKN-P1AS	N01-E08-THKN-P1AS-LB		5/3/2010	X	X
N01-E08-THKN-P1	N01-E08-THKN-P1AX	N01-E08-THKN-P1AX-LB	Field Duplicate	5/3/2010	X	X
N01-E12-THKN-P1	N01-E12-THKN-P1BS	N01-E12-THKN-P1BS-LB	Laboratory Replicate	5/24/2010	X	X
N01-E13-THKN-P1	N01-E13-THKN-P1BS	N01-E13-THKN-P1BS-LB		5/24/2010	X	X
N01-E13-THKN-P1	N01-E13-THKN-P1BX	N01-E13-THKN-P1BX-LB	Field Duplicate	5/24/2010	X	X
N01-E17-THKN-P1	N01-E17-THKN-P1AS	N01-E17-THKN-P1AS-LB	Laboratory Replicate	6/22/2010	X	X
N01-E17-THKN-P1	N01-E17-THKN-P1BS	N01-E17-THKN-P1BS-LB		6/22/2010	X	X
N01-E17-THKN-P1	N01-E17-THKN-P1BX	N01-E17-THKN-P1BX-LB	Field Duplicate	6/22/2010	X	X
N01-E21-THKN-P1	N01-E21-THKN-P1AS	N01-E21-THKN-P1AS-LB	Laboratory Replicate	7/21/2010	X	X
N01-E21-THKN-P1	N01-E21-THKN-P1BS	N01-E21-THKN-P1BS-LB		7/21/2010	X	X
N01-E21-THKN-P1	N01-E21-THKN-P1BX	N01-E21-THKN-P1BX-LB	Field Duplicate	7/21/2010	X	X
N01-E03-TKVK-P1	N01-E03-TKVK-P1AS	N01-E03-TKVK-P1AS-LB		3/25/2010	X	X
N01-E03-TKVK-P1	N01-E03-TKVK-P1BS	N01-E03-TKVK-P1BS-LB		3/25/2010	X	X

Table 2-5
Split Samples Collected During PWCM Boat-Based Deployment Events
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	CPG Sample ID	USEPA Sample ID	QA/QC	Date Collected	SSC	DOC/POC
N01-E04-TKVK-P1	N01-E04-TKVK-P1AS	N01-E04-TKVK-P1AS-LB		3/25/2010	X	X
N01-E04-TKVK-P1	N01-E04-TKVK-P1BS	N01-E04-TKVK-P1BS-LB		3/25/2010	X	X
N01-E07-TKVK-P1	N01-E07-TKVK-P1AS	N01-E07-TKVK-P1AS-LB		5/3/2010	X	X
N01-E08-TKVK-P1	N01-E08-TKVK-P1AS	N01-E08-TKVK-P1AS-LB		5/3/2010	X	X
N01-E12-TKVK-P1	N01-E12-TKVK-P1BS	N01-E12-TKVK-P1BS-LB		5/24/2010	X	X
N01-E13-TKVK-P1	N01-E13-TKVK-P1BS	N01-E13-TKVK-P1BS-LB		5/24/2010	X	X
N01-E17-TKVK-P1	N01-E17-TKVK-P1AS	N01-E17-TKVK-P1AS-LB		6/22/2010	X	X
N01-E17-TKVK-P1	N01-E17-TKVK-P1BS	N01-E17-TKVK-P1BS-LB		6/22/2010	X	X
N01-E22-TKVK-P1	N01-E22-TKVK-P1AS	N01-E22-TKVK-P1AS-LB		7/21/2010	X	X
N01-E22-TKVK-P1	N01-E22-TKVK-P1BS	N01-E22-TKVK-P1BS-LB		7/21/2010	X	X
N01-E03-TNBN-P1	N01-E03-TNBN-P1AS	N01-E03-TNBN-P1AS-LB		3/25/2010	X	X
N01-E03-TNBN-P1	N01-E03-TNBN-P1BS	N01-E03-TNBN-P1BS-LB		3/25/2010	X	X
N01-E04-TNBN-P1	N01-E04-TNBN-P1AS	N01-E04-TNBN-P1AS-LB		3/25/2010	X	X
N01-E04-TNBN-P1	N01-E04-TNBN-P1BS	N01-E04-TNBN-P1BS-LB		3/25/2010	X	X
N01-E07-TNBN-P1	N01-E07-TNBN-P1AS	N01-E07-TNBN-P1AS-LB		5/3/2010	X	X
N01-E08-TNBN-P1	N01-E08-TNBN-P1AS	N01-E08-TNBN-P1AS-LB		5/3/2010	X	X
N01-E12-TNBN-P1	N01-E12-TNBN-P1BS	N01-E12-TNBN-P1BS-LB		5/24/2010	X	X
N01-E13-TNBN-P1	N01-E13-TNBN-P1BS	N01-E13-TNBN-P1BS-LB		5/24/2010	X	X
N01-E17-TNBN-P1	N01-E17-TNBN-P1AS	N01-E17-TNBN-P1AS-LB		6/22/2010	X	X
N01-E17-TNBN-P1	N01-E17-TNBN-P1BS	N01-E17-TNBN-P1BS-LB		6/22/2010	X	X
N01-E21-TNBN-P1	N01-E21-TNBN-P1AS	N01-E21-TNBN-P1AS-LB		7/21/2010	X	X
N01-E21-TNBN-P1	N01-E21-TNBN-P1BS	N01-E21-TNBN-P1BS-LB		7/21/2010	X	X
N01-E03-TNBS-P1	N01-E03-TNBS-P1AS	N01-E03-TNBS-P1AS-LB		3/25/2010	X	X
N01-E03-TNBS-P1	N01-E03-TNBS-P1BS	N01-E03-TNBS-P1BS-LB		3/25/2010	X	X
N01-E04-TNBS-P1	N01-E04-TNBS-P1AS	N01-E04-TNBS-P1AS-LB		3/25/2010	X	X
N01-E04-TNBS-P1	N01-E04-TNBS-P1BS	N01-E04-TNBS-P1BS-LB		3/25/2010	X	X
N01-E07-TNBS-P1	N01-E07-TNBS-P1AS	N01-E07-TNBS-P1AS-LB		5/3/2010	X	X
N01-E08-TNBS-P1	N01-E08-TNBS-P1AS	N01-E08-TNBS-P1AS-LB		5/3/2010	X	X
N01-E12-TNBS-P1	N01-E12-TNBS-P1BS	N01-E12-TNBS-P1BS-LB		5/24/2010	X	X
N01-E13-TNBS-P1	N01-E13-TNBS-P1BS	N01-E13-TNBS-P1BS-LB		5/24/2010	X	X
N01-E17-TNBS-P1	N01-E17-TNBS-P1AS	N01-E17-TNBS-P1AS-LB		6/22/2010	X	X
N01-E17-TNBS-P1	N01-E17-TNBS-P1BS	N01-E17-TNBS-P1BS-LB		6/22/2010	X	X
N01-E22-TNBS-P1	N01-E22-TNBS-P1AS	N01-E22-TNBS-P1AS-LB		7/21/2010	X	X
N01-E22-TNBS-P1	N01-E22-TNBS-P1BS	N01-E22-TNBS-P1BS-LB		7/21/2010	X	X

Notes:
Information in this table provided by CDM Smith and LBG.
CPG - Cooperating Parties Group
DOC - Dissolved Organic Carbon
ID - Identification
LBG - Louis Berger Group
MS/D - Matrix spike and duplicate
POC - Particulate Organic Carbon
PWCM - Physical Water Column Monitoring
QA/QC - Quality Assurance/Quality Control
SSC - Suspended Sediment Concentration
USEPA - United States Environmental Protection Agency

Table 2-6
Split Samples Collected During PWCM Wet Weather Tributary Sampling Events
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	CPG Sample ID	USEPA Sample ID	QA/QC	Date Collected	SSC	DOC/POC
Samples split with CDM Smith						
10C-E01-T169-P2	10C-E01-T169-P2-AS	10C-E01-T169-P2-AS-C		5/12/2010	X	X
10C-E02-T169-P1	10C-E02-T169-P1-AS	10C-E02-T169-P1-AS-C		5/12/2010	X	X
10C-E01-TSR2-P1	10C-E01-TSR2-P1-AS	10C-E01-TSR2-P1-AS-C		5/12/2010	X	X
10C-E03-T2R1-P1	10C-E03-T2R1-P1-AS	10C-E03-T2R1-P1-AS-C	MS/D for DOC only	5/12/2010	X	X
		10C-E03-T2R1-P1-AS-X	Duplicate	5/12/2010	X	X
10C-E03-T3R1-P1	10C-E03-T3R1-P1-AS	10C-E03-T3R1-P1-AS-C		5/12/2010	X	X
E10-T169-P2	E10-T169-P2-AS	E10-T169-P2-AS-C		11/4/2010	X	X
E09-T169-P1	E09-T169-P1-AS	E09-T169-P1-AS-C	MS/D for DOC only	11/4/2010	X	X
E10-TSR2-P1	E10-TSR2-P1-AS	E10-TSR2-P1-AS-C		11/4/2010	X	X
E08-T2R1-P1	E08-T2R1-P1-AS	E08-T2R1-P1-AS-C		11/4/2010	X	X
E07-T3R1-P1	E07-T3R1-P1-AS	E07-T3R1-P1-AS-C		11/4/2010	X	X
		E07-T3R1-P1-AS-X	Duplicate	11/4/2010	X	X

Notes:
Information in this table provided by CDM Smith
CPG - Cooperating Parties Group
DOC - Dissolved Organic Carbon
ID - Identification
LR - Laboratory Replicate
MS/D - Matrix spike and duplicate
POC - Particulate Organic Carbon
PWCM - Physical Water Column Monitoring
QA/QC - Quality Assurance/Quality Control
SSC - Suspended Sediment Concentration
USEPA - United States Environmental Protection Agency

Table 2-7
Location of Field and Laboratory Data for PWCM Program
Physical Water Column Monitoring Sampling Program
Lower Passaic River Restoration Project

Data Type	Location
COC Forms	Project files at AECOM
Tide Gage Locations and Water Elevations	Project files at AECOM
Sample Field Custody and Transfer Forms	Project files at AECOM
Data Validation Reports	Project files at AECOM; included in **Appendix D**
Equipment Blank Results	Project files at AECOM
Field Log Books	Project files at AECOM
Field Modification Forms	Project files at AECOM
HASP Addendum Acceptance Forms	Project files at AECOM
Health & Safety Daily Briefings	Project files at AECOM
Health & Safety Personnel Records	Project files at AECOM
Laboratory EDD	Submitted electronically in MEDD Region 2 format with monthly progress report
Laboratory Data Reports	Project files at AECOM; submitted monthly to USEPA
Nonconformance Forms	Project files at AECOM
QAPP Sign-off	Project files at AECOM
Safety Audit	Project files at AECOM
Sample Summary Table	**Appendix A**
Surface Water Sample Results	**Table 3-1**

COC - Chain of Custody
HASP - Health and Safety Plan
EDD - Electronic data deliverable
QAPP - Quality Assurance Project Plan
PWCM - Physical Water Column Monitoring
MEDD - Multi-Media Electronic Data Deliverable
USEPA - United States Environmental Protection Agency

Table 2-8
SSC Data Excluded from Regression Analyses by Moffatt and Nichol
Physical Water Column Monitoring Sampling Program
Lower Passaic River Restoration Project

Station	Event	Station/ Transect	Depth	Sample Time	SSC (mg/l)	Reason why data were excluded	Excluded from
T014	E09	P3	AS	11/9/09 3:42 PM	19	Qualitatively unexpected vertical gradient with surface SSC > bottom SSC; also inconsistent with OBS and ABS vertical gradients	OBS-SSC regressions and ABS-SSC regressions
T014	E09	P3	BS	11/9/09 3:44 PM	11		
T014	E09	P3	BS	05/02/2010 14:45	96		
T014	E09	P3	AS	05/02/2010 14:46	126		
T014	E14	P3	BS	5/20/10 2:42 PM	8		
T014	E14	P3	AS	5/20/10 2:44 PM	11		
T042	E14	P1	BS	5/20/10 4:40 PM	33		
T042	E14	P1	AS	5/20/10 4:41 PM	40		
T135	E05	P3	BS	5/1/10 1:57 PM	1		
T135	E05	P3	AS	5/1/10 1:58 PM	7		
TNBN	E10	P1	BS	5/22/10 3:57 PM	8		
TNBN	E10	P1	AS	5/22/10 3:58 PM	19		
TNBN	E18	P1	BS	6/22/10 5:39 PM	13		
TNBN	E18	P1	AS	6/22/10 5:40 PM	22		
THKN	E05	P1	BS	4/29/10 4:43 PM	23		
THKN	E05	P1	AS	4/29/10 4:45 PM	36		
THKN	E10	P1	BS	5/23/10 2:51 PM	6		
THKN	E10	P1	AS	5/23/10 2:53 PM	23		

ABS - Acoustical Backscatter
AS - Shallow samples
BS - Deep sample
mg/L - milligrams per liter
OBS - Optical Backscatter
SSC - Suspended Sediment Concentration
T014 - Station at River Mile 1.4
T135 - Station at River Mile 13.5
THKN - Station on the Hackensack River
TNBN - Station at Newark Bay North



Figure 2-1 Wave Gauge and Mooring Locations

0 1 2 3 4 Miles

Legend

Water
Community Boundaries
Shallow Mooring
Deep Mooring
Wave Gauge

NOTE:
NBSA locations and Wave Gauge sampled Spring 2010 only

AECOM

May 2019

Ortho: Copyright:© 2009 ESRI, i-cubed, GeoEye

Map Projection: NJ State Plane, NAD 83 Feet



Figure 2-2 Wet Weather Event Sampling Locations

0 0.5 1 1.5 2 Miles

Legend

- Water
- Community Boundaries
- Wet Weather Sample Locations

AECOM

May 2019

Ortho: Copyright:© 2009 ESRI, i-cubed, GeoEye

Map Projection: NJ State Plane, NAD 83 Feet

\\uswtf1p001\jobs\Water\ProjectFiles\P120\12182_Passaic\Data\GIS\Tasks\RemedialInvestigation\2014RI_Figures\MXD_2014RI



Figure 2-3 High Flow/Flood Event Sample Locations

0 1 2 3 4 Miles

Legend

- Water
- Community Boundaries
- High Flow/Flood Sampling Station

AECOM

May 2019

Ortho: Copyright:© 2009 ESRI, i-cubed, GeoEye

Map Projection: NJ State Plane, NAD 83 Feet

\\uswtf1p001\jobs\Water\ProjectFiles\P120\12182_Passaic\Data\GIS\Tasks\RemedialInvestigation\2014RI_Figures\MXD_2014RI

3.0 PWCM Sampling Results

The PWCM long term deployment data were reported by OSI in three separate reports: LPR Fall 2009, LPR Spring 2010 and NBSA Spring 2010. These reports are presented as **Appendices A**, **B**, and **C**, respectively. The data contained in these reports have been previously provided to USEPA for inclusion in the PREmis database.

Data, including field duplicates, collected for POC, DOC and SSC from the boat based surveys during the long term instrument deployment, the two wet weather tributary sampling events, and the High Flow/Flood sampling event are provided in **Table 3-1**. Data for equipment blanks are presented in **Appendix H**. These data have been previously provided to USEPA for inclusion in the PREmis database.

Results of the dissolved oxygen survey were reported by Windward (2013) (**Appendix E**).

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
Fall 2009 LPRSA Boat Survey						
09A-E01-T014-P3	09A-E01-T014-P3-AS	10/12/09 9:52	3			6 J
09A-E01-T014-P3	09A-E01-T014-P3-BS	10/12/09 9:54	12.7			7 J
09A-E01-T042-P1	09A-E01-T042-P1-AS	10/12/09 10:13	3			8 J
09A-E01-T042-P1	09A-E01-T042-P1-BS	10/12/09 10:14	12.6			7 J
09A-E01-T067-P3	09A-E01-T067-P3-AD	10/12/09 11:25	3			12 J
09A-E01-T067-P3	09A-E01-T067-P3-AS	10/12/09 11:25	3			12 J
09A-E01-T067-P3	09A-E01-T067-P3-BD	10/12/09 11:28	10.1			29 J
09A-E01-T067-P3	09A-E01-T067-P3-BS	10/12/09 11:28	10.1			30 J
09A-E01-T102-P1	09A-E01-T102-P1-AS	10/12/09 11:56	3			20 J
09A-E01-T102-P1	09A-E01-T102-P1-BS	10/12/09 11:59	11.94			29 J
09A-E01-T135-P3	09A-E01-T135-P3-AS	10/12/09 12:21	3			5 J
09A-E01-T135-P3	09A-E01-T135-P3-BS	10/12/09 12:22	11.6			9 J
09A-E02-T175-P1	09A-E02-T175-P1-AS	10/12/09 16:56	4			3
09A-E02-T175-P2	09A-E02-T175-P2-AS	10/12/09 17:13	3	1.1	1.0 J	3
09A-E02-T175-P2	09A-E02-T175-P2-BS	10/12/09 16:56	9	3.4	0.8 UJ	2
09A-E02-T175-P3	09A-E02-T175-P3-AS	10/12/09 17:18	5			2
09A-E02-T175-P3	09A-E02-T175-P3-AT	10/12/09 17:18	5			2
09A-E02-T175-P4	09A-E02-T175-P4-AS	10/12/09 17:20	4			3
09A-E03-T014-P1	09A-E03-T014-P1-AS	10/13/09 8:10	3			9
09A-E03-T014-P1	09A-E03-T014-P1-BS	10/13/09 8:12	12.9			10
09A-E03-T014-P2	09A-E03-T014-P2-AS	10/13/09 8:20	3			7
09A-E03-T014-P2	09A-E03-T014-P2-BS	10/13/09 8:23	14.1			8
09A-E03-T014-P3	09A-E03-T014-P3-AS	10/13/09 8:33	3	2.6	1.3 J	7
09A-E03-T014-P3	09A-E03-T014-P3-BS	10/13/09 8:36	13	1.5	1.0 J	7
09A-E03-T042-P1	09A-E03-T042-P1-AS	10/13/09 9:04	3	3.3	1.2 J	9
09A-E03-T042-P1	09A-E03-T042-P1-BS	10/13/09 9:07	13.5	3.0	1.0 J	9
09A-E03-T042-P2	09A-E03-T042-P2-AS	10/13/09 9:16	3			8
09A-E03-T042-P2	09A-E03-T042-P2-BS	10/13/09 9:18	14			9
09A-E03-T042-P3	09A-E03-T042-P3-AS	10/13/09 9:26	3			9
09A-E03-T042-P3	09A-E03-T042-P3-BS	10/13/09 9:27	12.2			10
09A-E03-T067-P1	09A-E03-T067-P1-AS	10/13/09 9:56	3			20
09A-E03-T067-P1	09A-E03-T067-P1-AT	10/13/09 14:20	3			19 J
09A-E03-T067-P1	09A-E03-T067-P1-BS	10/13/09 9:57	9.2			33
09A-E03-T067-P2	09A-E03-T067-P2-AS	10/13/09 10:03	3			18
09A-E03-T067-P2	09A-E03-T067-P2-BS	10/13/09 10:04	9.8			26
09A-E03-T067-P3	09A-E03-T067-P3-AS	10/13/09 10:10	3	3.2	1.7 J	19
09A-E03-T067-P3	09A-E03-T067-P3-BS	10/13/09 10:12	9.1	3.5	2.2 J	22
09A-E03-T102-P1	09A-E03-T102-P1-AS	10/13/09 8:35	3	2.5 J	2.0 J	17
09A-E03-T102-P1	09A-E03-T102-P1-BS	10/13/09 8:37	7	3.4 J	1.9 J	21
09A-E03-T102-P2	09A-E03-T102-P2-AS	10/13/09 8:46	3			19
09A-E03-T102-P2	09A-E03-T102-P2-BS	10/13/09 8:48	7			22
09A-E03-T102-P3	09A-E03-T102-P3-AS	10/13/09 8:53	3			21
09A-E03-T102-P3	09A-E03-T102-P3-BS	10/13/09 8:54	10			23
09A-E03-T135-P1	09A-E03-T135-P1-AS	10/13/09 9:33	3			5
09A-E03-T135-P1	09A-E03-T135-P1-BS	10/13/09 9:34	5			6
09A-E03-T135-P2	09A-E03-T135-P2-AS	10/13/09 9:41	3			5
09A-E03-T135-P2	09A-E03-T135-P2-BS	10/13/09 9:43	7			6
09A-E03-T135-P3	09A-E03-T135-P3-AS	10/13/09 9:53	3	3.4 J	1.4 J	6
09A-E03-T135-P3	09A-E03-T135-P3-BS	10/13/09 9:55	11	3.3 J	1.2 J	6
09A-E04-T014-P1	09A-E04-T014-P1-AS	10/13/09 12:58	3			6 J
09A-E04-T014-P1	09A-E04-T014-P1-BS	10/13/09 13:00	12.1			35 J
09A-E04-T014-P2	09A-E04-T014-P2-AS	10/13/09 13:06	3			6 J
09A-E04-T014-P2	09A-E04-T014-P2-BS	10/13/09 13:08	14.3			21 J
09A-E04-T014-P3	09A-E04-T014-P3-AS	10/13/09 13:15	3	2.0 J	1.2 J	6 J
09A-E04-T014-P3	09A-E04-T014-P3-BS	10/13/09 13:17	12.6	3.1 J	2.3 J	35 J
09A-E04-T042-P1	09A-E04-T042-P1-AS	10/13/09 13:41	3	3.2 J	1.0 J	8 J
09A-E04-T042-P1	09A-E04-T042-P1-AT	10/13/09 13:41	3	3.3 J	1.0 J	9 J
09A-E04-T042-P1	09A-E04-T042-P1-BS	10/13/09 13:44	14.5	2.9 J	4.5 J	81 J
09A-E04-T042-P2	09A-E04-T042-P2-AS	10/13/09 13:50	3			8 J
09A-E04-T042-P2	09A-E04-T042-P2-BS	10/13/09 13:51	16.2			72 J
09A-E04-T042-P3	09A-E04-T042-P3-AS	10/13/09 13:57	3			11 J
09A-E04-T042-P3	09A-E04-T042-P3-BS	10/13/09 13:59	14.1			18 J
09A-E04-T067-P1	09A-E04-T067-P1-AS	10/13/09 14:20	3			36 J
09A-E04-T067-P1	09A-E04-T067-P1-BS	10/13/09 14:21	12.2			61 J
09A-E04-T067-P2	09A-E04-T067-P2-AS	10/13/09 14:25	3			24 J
09A-E04-T067-P2	09A-E04-T067-P2-BS	10/13/09 14:26	12.6			34 J
09A-E04-T067-P3	09A-E04-T067-P3-AS	10/13/09 14:32	3	3.3 J	2.2 J	30 J
09A-E04-T067-P3	09A-E04-T067-P3-BS	10/13/09 14:33	11.9	3.2 J	5.5 J	61 J

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
09A-E04-T102-P1	09A-E04-T102-P1-AS	10/13/09 13:36	3	3.2 J	3.1 J	37
09A-E04-T102-P1	09A-E04-T102-P1-BS	10/13/09 13:38	10	3.3 J	4.0 J	82
09A-E04-T102-P2	09A-E04-T102-P2-AS	10/13/09 13:42	3			36
09A-E04-T102-P2	09A-E04-T102-P2-BS	10/13/09 13:44	11			160
09A-E04-T102-P3	09A-E04-T102-P3-AS	10/13/09 13:55	3			45
09A-E04-T102-P3	09A-E04-T102-P3-BS	10/13/09 13:57	10			56
09A-E04-T135-P1	09A-E04-T135-P1-AS	10/13/09 15:35	3			7
09A-E04-T135-P1	09A-E04-T135-P1-BS	10/13/09 15:37	7			9
09A-E04-T135-P2	09A-E04-T135-P2-AS	10/13/09 15:40	3			7
09A-E04-T135-P2	09A-E04-T135-P2-BS	10/13/09 15:42	11			11
09A-E04-T135-P3	09A-E04-T135-P3-AS	10/13/09 15:45	3	3.6 J	1.3 J	7
09A-E04-T135-P3	09A-E04-T135-P3-AT	10/13/09 15:45	3			7
09A-E04-T135-P3	09A-E04-T135-P3-BS	10/13/09 15:47	13	3.2 J	1.4 J	8
09A-E05-T014-P3	09A-E05-T014-P3-AS	11/9/09 8:01	3			14
09A-E05-T014-P3	09A-E05-T014-P3-BS	11/9/09 8:03	17			22
09A-E05-T042-P1	09A-E05-T042-P1-AS	11/10/09 8:19	3			20
09A-E05-T042-P1	09A-E05-T042-P1-BS	11/10/09 8:24	12			15
09A-E05-T067-P3	09A-E05-T067-P3-AS	11/9/09 11:31	3			51
09A-E05-T067-P3	09A-E05-T067-P3-BS	11/9/09 11:35	10			62
09A-E05-T102-P1	09A-E05-T102-P1-AS	11/9/09 14:01	3			11
09A-E05-T102-P1	09A-E05-T102-P1-BS	11/9/09 14:02	14.7			10
09A-E05-T135-P3	09A-E05-T135-P3-AS	11/10/09 11:30	3			6
09A-E05-T135-P3	09A-E05-T135-P3-BS	11/10/09 11:31	12.3			8
09A-E06-T175-P1	09A-E06-T175-P1-AS	11/10/09 11:07	3			14
09A-E06-T175-P2	09A-E06-T175-P2-AS	11/10/09 11:19	3	5.2	0.8 UJ	5
09A-E06-T175-P2	09A-E06-T175-P2-BS	11/10/09 11:22	7	5.8	1.0 UJ	6
09A-E06-T175-P3	09A-E06-T175-P3-AS	11/10/09 11:32	3			6
09A-E06-T175-P4	09A-E06-T175-P4-AS	11/10/09 11:43	3			7
09A-E07-T014-P1	09A-E07-T014-P1-AS	11/11/09 7:39	3	5.3	2.2 U	17 J
09A-E07-T014-P1	09A-E07-T014-P1-BS	11/11/09 7:02	12.4			29 J
09A-E07-T014-P2	09A-E07-T014-P2-AS	11/11/09 7:08	3			16 J
09A-E07-T014-P2	09A-E07-T014-P2-BS	11/11/09 7:09	14.2			25 J
09A-E07-T014-P3	09A-E07-T014-P3-AS	11/11/09 7:15	3	4.6	1.4 U	17 J
09A-E07-T014-P3	09A-E07-T014-P3-BS	11/11/09 7:17	14	2.9	1.4 U	18
09A-E07-T042-P1	09A-E07-T042-P1-AS	11/11/09 7:39	3			25
09A-E07-T042-P1	09A-E07-T042-P1-BS	11/11/09 7:42	13	4.5	1.8 U	26
09A-E07-T042-P2	09A-E07-T042-P2-AS	11/11/09 7:48	3			25
09A-E07-T042-P2	09A-E07-T042-P2-BS	11/11/09 7:49	14.5			29
09A-E07-T042-P3	09A-E07-T042-P3-AS	11/11/09 7:55	3			26
09A-E07-T042-P3	09A-E07-T042-P3-BS	11/11/09 7:57	13.2			29
09A-E07-T067-P1	09A-E07-T067-P1-AS	11/11/09 8:24	3			40
09A-E07-T067-P1	09A-E07-T067-P1-BS	11/11/09 8:26	10.1			68
09A-E07-T067-P2	09A-E07-T067-P2-AS	11/11/09 8:30	3			36
09A-E07-T067-P2	09A-E07-T067-P2-BS	11/11/09 8:32	10.8			67
09A-E07-T067-P3	09A-E07-T067-P3-AS	11/11/09 8:39	3	5.1	3.4	31
09A-E07-T067-P3	09A-E07-T067-P3-BS	11/11/09 8:42	10.2	5.8	4.6	48
09A-E07-T067-P3	09A-E07-T067-P3-BT	11/11/09 8:42	10.2			44
09A-E07-T102-P1	09A-E07-T102-P1-AS	11/11/09 8:14	3	5.0	0.8 U	20
09A-E07-T102-P1	09A-E07-T102-P1-BS	11/11/09 8:16	13	5.1	0.8 U	22
09A-E07-T102-P1	09A-E07-T102-P1-BT	11/11/09 8:16	13	5.4	0.8 U	21
09A-E07-T102-P2	09A-E07-T102-P2-AS	11/11/09 8:28	3			21
09A-E07-T102-P2	09A-E07-T102-P2-BS	11/11/09 8:31	13			25
09A-E07-T102-P3	09A-E07-T102-P3-AS	11/11/09 8:38	3			25
09A-E07-T102-P3	09A-E07-T102-P3-BS	11/11/09 8:40	13			27
09A-E07-T135-P1	09A-E07-T135-P1-AS	11/11/09 7:00	3			8
09A-E07-T135-P1	09A-E07-T135-P1-BS	11/11/09 7:02	7			10
09A-E07-T135-P2	09A-E07-T135-P2-AS	11/11/09 7:11	3			6
09A-E07-T135-P2	09A-E07-T135-P2-BS	11/11/09 7:13	11			7
09A-E07-T135-P3	09A-E07-T135-P3-AS	11/11/09 7:25	3	4.8	1.2 U	7 J
09A-E07-T135-P3	09A-E07-T135-P3-BS	11/11/09 7:27	13	5.0	1.5 U	10 J
09A-E08-T014-P1	09A-E08-T014-P1-AS	11/11/09 11:55	3			12
09A-E08-T014-P1	09A-E08-T014-P1-BS	11/11/09 11:57	13.8			100
09A-E08-T014-P2	09A-E08-T014-P2-AS	11/11/09 12:05	3			12
09A-E08-T014-P2	09A-E08-T014-P2-BS	11/11/09 12:07	13.8			56
09A-E08-T014-P3	09A-E08-T014-P3-AS	11/11/09 12:12	3	3.9	1.0 U	12
09A-E08-T014-P3	09A-E08-T014-P3-BS	11/11/09 12:15	15.4	2.7	3.2	57
09A-E08-T042-P1	09A-E08-T042-P1-AS	11/11/09 12:38	3	5.1	1.7 U	16
09A-E08-T042-P1	09A-E08-T042-P1-BS	11/11/09 12:41	15.3	4.1	12	240
09A-E08-T042-P2	09A-E08-T042-P2-AS	11/11/09 12:45	3			23

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
09A-E08-T042-P2	09A-E08-T042-P2-BS	11/11/09 12:47	17.3			160
09A-E08-T042-P3	09A-E08-T042-P3-AS	11/11/09 12:51	3			32
09A-E08-T042-P3	09A-E08-T042-P3-BS	11/11/09 12:52	16			110
09A-E08-T067-P1	09A-E08-T067-P1-AS	11/11/09 14:36	3			20 J
09A-E08-T067-P1	09A-E08-T067-P1-BS	11/11/09 14:37	15			27 J
09A-E08-T067-P2	09A-E08-T067-P2-AS	11/11/09 14:44	3			19 J
09A-E08-T067-P2	09A-E08-T067-P2-BS	11/11/09 14:46	17			27 J
09A-E08-T067-P3	09A-E08-T067-P3-AS	11/11/09 14:53	3	5.5	1.7 U	18 J
09A-E08-T067-P3	09A-E08-T067-P3-BS	11/11/09 14:55	16	5.1	2.2 U	27 J
09A-E08-T102-P1	09A-E08-T102-P1-AS	11/11/09 13:26	3	5.4	2.2 U	26 J
09A-E08-T102-P1	09A-E08-T102-P1-BS	11/11/09 13:27	17	5.6	4.2	41 J
09A-E08-T102-P2	09A-E08-T102-P2-AS	11/11/09 13:34	3			21 J
09A-E08-T102-P2	09A-E08-T102-P2-BS	11/11/09 13:36	17			48 J
09A-E08-T102-P3	09A-E08-T102-P3-AS	11/11/09 13:42	3			20 J
09A-E08-T102-P3	09A-E08-T102-P3-BS	11/11/09 13:44	18			35 J
09A-E08-T135-P1	09A-E08-T135-P1-AS	11/11/09 12:21	3			6 J
09A-E08-T135-P1	09A-E08-T135-P1-BS	11/11/09 12:22	9			7 J
09A-E08-T135-P2	09A-E08-T135-P2-AS	11/11/09 12:28	3			5 J
09A-E08-T135-P2	09A-E08-T135-P2-BS	11/11/09 12:30	11			6 J
09A-E08-T135-P3	09A-E08-T135-P3-AS	11/11/09 12:40	3	5.0	0.8 U	5 J
09A-E08-T135-P3	09A-E08-T135-P3-BS	11/11/09 12:41	15	5.1	0.9 U	7 J
09A-E09-T014-P3	09A-E09-T014-P3-AS	11/9/09 10:42	3			19
09A-E09-T014-P3	09A-E09-T014-P3-BS	11/9/09 10:46	17			11
09A-E09-T042-P1	09A-E09-T042-P1-AS	11/10/09 10:41	3			13
09A-E09-T042-P1	09A-E09-T042-P1-BS	11/10/09 10:42	12.8			15
09A-E09-T067-P3	09A-E09-T067-P3-AS	11/9/09 13:28	3			22
09A-E09-T067-P3	09A-E09-T067-P3-BS	11/9/09 13:29	13.5			19
09A-E09-T102-P1	09A-E09-T102-P1-AS	11/9/09 15:52	3			7
09A-E09-T102-P1	09A-E09-T102-P1-BS	11/9/09 15:53	14.3			10
09A-E09-T135-P3	09A-E09-T135-P3-AS	11/10/09 13:19	3			6
09A-E09-T135-P3	09A-E09-T135-P3-AT	11/10/09 13:20	3			4
09A-E09-T135-P3	09A-E09-T135-P3-BS	11/10/09 13:21	14.8			6
09A-E09-T175-P2	09A-E09-T175-P2-AS	11/10/09 12:53	3			4
09A-E10-T014-P3	09A-E10-T014-P3-AS	12/16/09 14:31	3			12
09A-E10-T014-P3	09A-E10-T014-P3-BS	12/16/09 14:33	14.3			14
09A-E10-T042-P1	09A-E10-T042-P1-AS	12/16/09 15:48	3			33
09A-E10-T042-P1	09A-E10-T042-P1-BS	12/16/09 15:50	15.8			26
09A-E10-T067-P3	09A-E10-T067-P3-AS	12/15/09 18:36	3			30
09A-E10-T067-P3	09A-E10-T067-P3-BS	12/15/09 18:38	9.8			32
09A-E10-T102-P1	09A-E10-T102-P1-AS	12/15/09 16:54	3			14
09A-E10-T102-P1	09A-E10-T102-P1-BS	12/15/09 16:55	13.1			15
09A-E10-T135-P3	09A-E10-T135-P3-AS	12/15/09 15:17	3			10
09A-E10-T135-P3	09A-E10-T135-P3-AT	12/15/09 15:17	3			11
09A-E10-T135-P3	09A-E10-T135-P3-BS	12/15/09 15:19	14.3			11
09A-E11-T175-P1	09A-E11-T175-P1-AS	12/15/09 15:20	3			8
09A-E11-T175-P2	09A-E11-T175-P2-AS	12/15/09 15:32	3	4.6	1.2	11
09A-E11-T175-P2	09A-E11-T175-P2-BS	12/15/09 15:34	8	5.4	1.5	13
09A-E11-T175-P2	09A-E11-T175-P2-BT	12/15/09 15:34	8	5.0	1.3	12
09A-E11-T175-P3	09A-E11-T175-P3-AS	12/15/09 15:46	3			15
09A-E11-T175-P4	09A-E11-T175-P4-AS	12/15/09 15:52	3			15
09A-E12-T014-P1	09A-E12-T014-P1-AS	12/14/09 14:44	3			31
09A-E12-T014-P1	09A-E12-T014-P1-BS	12/14/09 14:45	14			29
09A-E12-T014-P2	09A-E12-T014-P2-AS	12/14/09 14:51	3			18
09A-E12-T014-P2	09A-E12-T014-P2-BS	12/14/09 14:53	12.9			16
09A-E12-T014-P3	09A-E12-T014-P3-AS	12/14/09 15:00	3	4.4	1.7	18
09A-E12-T014-P3	09A-E12-T014-P3-BS	12/14/09 15:02	15.2	3.5	1.0	16
09A-E12-T042-P1	09A-E12-T042-P1-AS	12/14/09 15:27	3	4.5	4.0	53
09A-E12-T042-P1	09A-E12-T042-P1-BS	12/14/09 15:28	14.1	4.4	4.3	44
09A-E12-T042-P2	09A-E12-T042-P2-AS	12/14/09 15:35	3			65
09A-E12-T042-P2	09A-E12-T042-P2-BS	12/14/09 15:37	15.2			72
09A-E12-T042-P3	09A-E12-T042-P3-AS	12/14/09 15:42	3			64
09A-E12-T042-P3	09A-E12-T042-P3-BS	12/14/09 15:44	11.3			130
09A-E12-T067-P1	09A-E12-T067-P1-AS	12/14/09 16:10	3			53
09A-E12-T067-P1	09A-E12-T067-P1-AT	12/14/09 16:10	3			53
09A-E12-T067-P1	09A-E12-T067-P1-BS	12/14/09 16:13	11.1			69
09A-E12-T067-P2	09A-E12-T067-P2-AS	12/14/09 16:20	3			46
09A-E12-T067-P2	09A-E12-T067-P2-BS	12/14/09 16:22	11.6			69
09A-E12-T067-P3	09A-E12-T067-P3-AS	12/14/09 16:28	3	4.6	4.2	45
09A-E12-T067-P3	09A-E12-T067-P3-BS	12/14/09 16:30	10.7	4.7	4.5	55

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
09A-E12-T102-P1	09A-E12-T102-P1-AS	12/14/09 15:52	3	4.9	2.7 J	25
09A-E12-T102-P1	09A-E12-T102-P1-BS	12/14/09 15:55	15	4.7	3.1 J	27
09A-E12-T102-P2	09A-E12-T102-P2-AS	12/14/09 16:04	3			27
09A-E12-T102-P2	09A-E12-T102-P2-BS	12/14/09 16:05	15			32
09A-E12-T102-P3	09A-E12-T102-P3-AS	12/14/09 16:13	3			35
09A-E12-T102-P3	09A-E12-T102-P3-BS	12/14/09 16:17	16			42
09A-E12-T135-P1	09A-E12-T135-P1-AS	12/14/09 14:48	3			15
09A-E12-T135-P1	09A-E12-T135-P1-BS	12/14/09 14:49	11			15
09A-E12-T135-P2	09A-E12-T135-P2-AS	12/14/09 14:59	3			15
09A-E12-T135-P2	09A-E12-T135-P2-BS	12/14/09 15:00	13			18
09A-E12-T135-P3	09A-E12-T135-P3-AS	12/14/09 15:08	3	4.3	2.2 J	16
09A-E12-T135-P3	09A-E12-T135-P3-BS	12/14/09 15:10	16	5.0	2.3 J	18
09A-E13-T014-P1	09A-E13-T014-P1-AS	12/14/09 20:10	3			36
09A-E13-T014-P1	09A-E13-T014-P1-BS	12/14/09 20:11	12.5			54
09A-E13-T014-P2	09A-E13-T014-P2-AS	12/14/09 20:16	3			31
09A-E13-T014-P2	09A-E13-T014-P2-BS	12/14/09 20:18	14.7			81
09A-E13-T014-P3	09A-E13-T014-P3-AS	12/14/09 20:23	3	4.5	2.7	36
09A-E13-T014-P3	09A-E13-T014-P3-BS	12/14/09 20:25	14.1	2.9	6.3	84
09A-E13-T042-P1	09A-E13-T042-P1-AS	12/14/09 20:47	3	5.0	2.2	23
09A-E13-T042-P1	09A-E13-T042-P1-BS	12/14/09 20:49	14.5	4.7	2.9	30
09A-E13-T042-P2	09A-E13-T042-P2-AS	12/14/09 20:55	3			27
09A-E13-T042-P2	09A-E13-T042-P2-BS	12/14/09 20:56	16.1			38
09A-E13-T042-P3	09A-E13-T042-P3-AS	12/14/09 21:03	3			31
09A-E13-T042-P3	09A-E13-T042-P3-BS	12/14/09 21:05	13.9			43
09A-E13-T067-P1	09A-E13-T067-P1-AS	12/14/09 21:25	3			18
09A-E13-T067-P1	09A-E13-T067-P1-BS	12/14/09 21:26	12			20
09A-E13-T067-P2	09A-E13-T067-P2-AS	12/14/09 21:30	3			20
09A-E13-T067-P2	09A-E13-T067-P2-BS	12/14/09 21:31	13.3			22
09A-E13-T067-P3	09A-E13-T067-P3-AS	12/14/09 21:36	3	4.5	1.9	24
09A-E13-T067-P3	09A-E13-T067-P3-BS	12/14/09 21:38	12.5	4.4	2.3	19
09A-E13-T067-P3	09A-E13-T067-P3-BT	12/14/09 21:38	12.5	4.2	1.8	19
09A-E13-T102-P1	09A-E13-T102-P1-AS	12/14/09 21:34	3	4.7	1.5 J	12
09A-E13-T102-P1	09A-E13-T102-P1-BS	12/14/09 21:36	15	4.8	1.5 J	13
09A-E13-T102-P2	09A-E13-T102-P2-AS	12/14/09 21:43	3			11
09A-E13-T102-P2	09A-E13-T102-P2-BS	12/14/09 21:45	16			14
09A-E13-T102-P3	09A-E13-T102-P3-AS	12/14/09 21:54	3			11
09A-E13-T102-P3	09A-E13-T102-P3-BS	12/14/09 21:55	16			14
09A-E13-T102-P3	09A-E13-T102-P3-BT	12/14/09 21:55	16			14
09A-E13-T135-P1	09A-E13-T135-P1-AS	12/14/09 20:38	3			14
09A-E13-T135-P1	09A-E13-T135-P1-BS	12/14/09 20:39	7			14
09A-E13-T135-P2	09A-E13-T135-P2-AS	12/14/09 20:49	3			14
09A-E13-T135-P2	09A-E13-T135-P2-BS	12/14/09 20:51	11			15
09A-E13-T135-P3	09A-E13-T135-P3-AS	12/14/09 20:57	3	4.7	1.5 J	13
09A-E13-T135-P3	09A-E13-T135-P3-BS	12/14/09 20:59	14	4.8	1.6 J	15
Spring 2010 LPRSA Boat Survey						
10A-E01-T014-P3	10A-E01-T014-P3-AS	3/22/10 11:32	3			7 J
10A-E01-T014-P3	10A-E01-T014-P3-BS	3/22/10 11:30	16.5			22 J
10A-E01-T042-P1	10A-E01-T042-P1-AS	3/22/10 11:05	3			7 J
10A-E01-T042-P1	10A-E01-T042-P1-BS	3/22/10 11:02	15.5			9 J
10A-E01-T067-P3	10A-E01-T067-P3-AS	3/23/10 10:04	3			37 J
10A-E01-T067-P3	10A-E01-T067-P3-BS	3/23/10 10:02	10.5			67 J
10A-E01-T102-P1	10A-E01-T102-P1-AS	3/23/10 9:32	3			45 J
10A-E01-T102-P1	10A-E01-T102-P1-BS	3/23/10 9:31	12.5			52 J
10A-E01-T135-P3	10A-E01-T135-P3-AS	3/24/10 10:06	3			19 J
10A-E01-T135-P3	10A-E01-T135-P3-BS	3/24/10 10:04	13.5			21 J
10A-E01-T135-P3	10A-E01-T135-P3-BT	3/24/10 10:04	13.5			27 J
10A-E02-T175-P1	10A-E02-T175-P1-AS	3/24/10 14:23	3	3.7	1.5 J	11 J
10A-E02-T175-P2	10A-E02-T175-P2-AS	3/24/10 14:33	3	3.8	1.5 J	11 J
10A-E02-T175-P2	10A-E02-T175-P2-BS	3/24/10 14:37	5.2	3.5	1.6 J	12 J
10A-E02-T175-P3	10A-E02-T175-P3-AS	3/24/10 14:47	3.2	3.9	1.5 J	12 J
10A-E02-T175-P4	10A-E02-T175-P4-AS	3/24/10 14:53	3.4	4.3	1.6 J	12 J
10A-E03-T014-P1	10A-E03-T014-P1-AS	3/25/10 7:56	3	4.3	3.1 J	38 J
10A-E03-T014-P1	10A-E03-T014-P1-BS	3/25/10 7:54	13	4.1	13 J	110
10A-E03-T014-P2	10A-E03-T014-P2-AS	3/25/10 8:08	3			24 J
10A-E03-T014-P2	10A-E03-T014-P2-BS	3/25/10 8:07	14			51 J
10A-E03-T014-P3	10A-E03-T014-P3-AS	3/25/10 8:22	3	4.0	2.2 J	28 J
10A-E03-T014-P3	10A-E03-T014-P3-BS	3/25/10 8:19	13	3.9	2.5 J	52 J
10A-E03-T042-P1	10A-E03-T042-P1-AS	3/25/10 8:56	3	3.6	2.5 J	21 J

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
10A-E03-T042-P1	10A-E03-T042-P1-AT	3/25/10 8:57	3	3.6	2.3 J	
10A-E03-T042-P1	10A-E03-T042-P1-BS	3/25/10 8:54	14	3.8	2.4 J	22 J
10A-E03-T042-P2	10A-E03-T042-P2-AS	3/25/10 9:08	3			22 J
10A-E03-T042-P2	10A-E03-T042-P2-BS	3/25/10 9:06	16			28 J
10A-E03-T042-P3	10A-E03-T042-P3-AS	3/25/10 9:21	3	3.9	3.1 J	27 J
10A-E03-T042-P3	10A-E03-T042-P3-BS	3/25/10 9:17	13	3.7	2.6 J	25 J
10A-E03-T067-P1	10A-E03-T067-P1-AS	3/25/10 9:22	3	4.0 J	1.9 J	18 J
10A-E03-T067-P1	10A-E03-T067-P1-BS	3/25/10 9:20	9.8	4.0 J	2.2 J	21 J
10A-E03-T067-P2	10A-E03-T067-P2-AS	3/25/10 9:31	3			21 J
10A-E03-T067-P2	10A-E03-T067-P2-BS	3/25/10 9:28	12.2			21 J
10A-E03-T067-P3	10A-E03-T067-P3-AS	3/25/10 9:36	3	4.0 J	1.9 J	28 J
10A-E03-T067-P3	10A-E03-T067-P3-BS	3/25/10 9:34	11.2	4.0 J	2.3 J	25 J
10A-E03-T102-P1	10A-E03-T102-P1-AS	3/25/10 8:09	3	3.9	1.5 J	11 J
10A-E03-T102-P1	10A-E03-T102-P1-AT	3/25/10 8:09	3			11 J
10A-E03-T102-P1	10A-E03-T102-P1-BS	3/25/10 8:06	8.1	4.0	1.5 J	12 J
10A-E03-T102-P2	10A-E03-T102-P2-AS	3/25/10 8:19	3			13 J
10A-E03-T102-P2	10A-E03-T102-P2-BS	3/25/10 8:18	14.1			17 J
10A-E03-T102-P3	10A-E03-T102-P3-AS	3/25/10 8:29	3	3.8	1.5 J	13 J
10A-E03-T102-P3	10A-E03-T102-P3-BS	3/25/10 8:27	7.1	3.9	2.0 J	13 J
10A-E03-T135-P1	10A-E03-T135-P1-AS	3/25/10 7:31	3	3.8	1.2 J	10 J
10A-E03-T135-P1	10A-E03-T135-P1-BS	3/25/10 7:29	10	4.1	1.4 J	10 J
10A-E03-T135-P2	10A-E03-T135-P2-AS	3/25/10 7:19	3			10 J
10A-E03-T135-P2	10A-E03-T135-P2-BS	3/25/10 7:17	11.3			10 J
10A-E03-T135-P3	10A-E03-T135-P3-AS	3/25/10 7:09	3	3.9	1.4 J	10 J
10A-E03-T135-P3	10A-E03-T135-P3-BS	3/25/10 7:06	9.3	4.1	1.6 J	10 J
10A-E04-T014-P1	10A-E04-T014-P1-AS	3/25/10 14:15	3	3.8	1.5 J	10 J
10A-E04-T014-P1	10A-E04-T014-P1-BS	3/25/10 14:13	12	3.9	1.4 J	11 J
10A-E04-T014-P2	10A-E04-T014-P2-AS	3/25/10 14:23	3			8 J
10A-E04-T014-P2	10A-E04-T014-P2-BS	3/25/10 14:22	15			10 J
10A-E04-T014-P3	10A-E04-T014-P3-AS	3/25/10 14:33	3	3.9	1.4 J	9 J
10A-E04-T014-P3	10A-E04-T014-P3-BS	3/25/10 14:30	15	3.2	2.0 J	21 J
10A-E04-T042-P1	10A-E04-T042-P1-AS	3/25/10 15:01	3	4.2	1.3 J	8 J
10A-E04-T042-P1	10A-E04-T042-P1-AT	3/25/10 15:03	3	4.2	1.5 J	
10A-E04-T042-P1	10A-E04-T042-P1-BS	3/25/10 14:59	16	4.3	1.3 J	9 J
10A-E04-T042-P2	10A-E04-T042-P2-AS	3/25/10 15:12	3			8 J
10A-E04-T042-P2	10A-E04-T042-P2-BS	3/25/10 15:11	20			9 J
10A-E04-T042-P3	10A-E04-T042-P3-AS	3/25/10 15:20	3	4.3	1.3 J	8 J
10A-E04-T042-P3	10A-E04-T042-P3-BS	3/25/10 15:17	13	4.5	1.2 J	8 J
10A-E04-T067-P1	10A-E04-T067-P1-AS	3/25/10 15:22	3	4.0	1.2 J	8 J
10A-E04-T067-P1	10A-E04-T067-P1-BS	3/25/10 15:21	7	3.8	1.1 J	8 J
10A-E04-T067-P2	10A-E04-T067-P2-AS	3/25/10 15:29	3			8 J
10A-E04-T067-P2	10A-E04-T067-P2-BS	3/25/10 15:28	14			8 J
10A-E04-T067-P3	10A-E04-T067-P3-AS	3/25/10 15:38	3	3.8	1.1 J	7 J
10A-E04-T067-P3	10A-E04-T067-P3-BS	3/25/10 15:36	13.4	3.8	1.3 J	9 J
10A-E04-T102-P1	10A-E04-T102-P1-AS	3/25/10 14:18	3	3.6	1.4 J	13 J
10A-E04-T102-P1	10A-E04-T102-P1-AT	3/25/10 14:19	3			13 J
10A-E04-T102-P1	10A-E04-T102-P1-BS	3/25/10 14:16	12.1	4.6	1.0 J	18 J
10A-E04-T102-P2	10A-E04-T102-P2-AS	3/25/10 14:28	3			14 J
10A-E04-T102-P2	10A-E04-T102-P2-BS	3/25/10 14:27	13			11 J
10A-E04-T102-P2	10A-E04-T102-P2-BT	3/25/10 14:27	13			11 J
10A-E04-T102-P3	10A-E04-T102-P3-AS	3/25/10 14:28	3	4.0	1.5 J	12 J
10A-E04-T102-P3	10A-E04-T102-P3-BS	3/25/10 14:27	13.2	3.9	1.5 J	13 J
10A-E04-T135-P1	10A-E04-T135-P1-AS	3/25/10 13:06	3	4.1	1.3	11 J
10A-E04-T135-P1	10A-E04-T135-P1-BS	3/25/10 13:04	4.7	4.2	1.5	19 J
10A-E04-T135-P1	10A-E04-T135-P1-BT	3/25/10 13:04	4.7	3.8	1.4 J	
10A-E04-T135-P2	10A-E04-T135-P2-AS	3/25/10 13:15	3			12 J
10A-E04-T135-P2	10A-E04-T135-P2-BS	3/25/10 13:13	9.1			10 J
10A-E04-T135-P3	10A-E04-T135-P3-AS	3/25/10 13:25	3	3.8	1.4	11 J
10A-E04-T135-P3	10A-E04-T135-P3-BS	3/25/10 13:22	12.9	3.8	1.8	10 J
10A-E05-T014-P3	10A-E05-T014-P3-AS	5/2/10 8:36	3			25
10A-E05-T014-P3	10A-E05-T014-P3-BS	5/2/10 8:36	13.5			43
10A-E05-T042-P1	10A-E05-T042-P1-AS	5/2/10 11:15	3			22 J
10A-E05-T042-P1	10A-E05-T042-P1-AT	5/2/10 11:15	3			8 J
10A-E05-T042-P1	10A-E05-T042-P1-BS	5/2/10 11:13	16			10
10A-E05-T067-P3	10A-E05-T067-P3-AS	5/1/10 15:25	3			14
10A-E05-T067-P3	10A-E05-T067-P3-BS	5/1/10 14:44	12			7
10A-E05-T102-P1	10A-E05-T102-P1-AS	5/1/10 0:16	3			5
10A-E05-T102-P1	10A-E05-T102-P1-BS	5/1/10 0:14	15			7
10A-E05-T135-P3	10A-E05-T135-P3-AS	5/1/10 9:58	3			7

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
10A-E05-T135-P3	10A-E05-T135-P3-BS	5/1/10 9:57	14			1 U
10A-E05-T175-P2	10A-E05-T175-P2-AS	5/4/10 0:02	3			9 J
10A-E05-T175-P2	10A-E05-T175-P2-BS	5/4/10 0:01	6			12 J
10A-E06-T175-P1	10A-E06-T175-P1-AS	5/4/10 13:12	3	6.4 J	2.3 J	7 J
10A-E06-T175-P2	10A-E06-T175-P2-AS	5/4/10 13:21	3	6.0 J	2.1 J	8 J
10A-E06-T175-P2	10A-E06-T175-P2-BS	5/4/10 13:20	6	6.0 J	2.9 J	18 J
10A-E06-T175-P3	10A-E06-T175-P3-AS	5/4/10 13:29	3	5.6 J	2.6 J	11 J
10A-E06-T175-P4	10A-E06-T175-P4-AS	5/4/10 13:35	3	5.9 J	2.4 J	13 J
10A-E07-T014-P1	10A-E07-T014-P1-AS	5/3/10 9:34	3	4.7 J	2.1 J	23 J
10A-E07-T014-P1	10A-E07-T014-P1-BS	5/3/10 9:32	10	0.58 J	2.5 J	13 J
10A-E07-T014-P2	10A-E07-T014-P2-AS	5/3/10 9:40	3			15 J
10A-E07-T014-P2	10A-E07-T014-P2-BS	5/3/10 9:39	12			30 J
10A-E07-T014-P3	10A-E07-T014-P3-AS	5/3/10 9:47	3	4.7 J	2.1 J	15 J
10A-E07-T014-P3	10A-E07-T014-P3-BS	5/3/10 9:45	11	3.5 J	1.7 J	17 J
10A-E07-T042-P1	10A-E07-T042-P1-AS	5/3/10 10:13	3	5.1 J	2.2 J	R
10A-E07-T042-P1	10A-E07-T042-P1-BS	5/3/10 10:11	12	5.4 J	1.8 J	R
10A-E07-T042-P2	10A-E07-T042-P2-AS	5/3/10 10:18	3			R
10A-E07-T042-P2	10A-E07-T042-P2-BS	5/3/10 10:17	16			R
10A-E07-T042-P3	10A-E07-T042-P3-AS	5/3/10 10:25	3	5.1 J	2.1 J	R
10A-E07-T042-P3	10A-E07-T042-P3-BS	5/3/10 10:24	12	11 J	2.2 J	R
10A-E07-T067-P1	10A-E07-T067-P1-AS	5/3/10 10:52	3	4.1 J	3.4 J	26 J
10A-E07-T067-P1	10A-E07-T067-P1-AT	5/3/10 10:52	3			27 J
10A-E07-T067-P1	10A-E07-T067-P1-BS	5/3/10 10:50	11.9	4.2 J	3.9 J	27 J
10A-E07-T067-P2	10A-E07-T067-P2-AS	5/3/10 11:01	3			27 J
10A-E07-T067-P2	10A-E07-T067-P2-BS	5/3/10 10:59	12.5			26 J
10A-E07-T067-P3	10A-E07-T067-P3-AS	5/3/10 11:08	3	4.2 J	2.8 J	24 J
10A-E07-T067-P3	10A-E07-T067-P3-BS	5/3/10 11:06	12.2	4.3 J	3.6 J	26 J
10A-E07-T067-P3	10A-E07-T067-P3-BT	5/3/10 11:07	12.2	4.1 J	3.0 J	
10A-E07-T102-P1	10A-E07-T102-P1-AS	5/3/10 9:48	3	4.6 J	3.9 J	40 J
10A-E07-T102-P1	10A-E07-T102-P1-BS	5/3/10 9:45	13	4.8 J	7.9 J	60 J
10A-E07-T102-P2	10A-E07-T102-P2-AS	5/3/10 9:56	3			27 J
10A-E07-T102-P2	10A-E07-T102-P2-BS	5/3/10 9:55	14			30 J
10A-E07-T102-P3	10A-E07-T102-P3-AS	5/3/10 10:05	3	4.6 J	3.1 J	31 J
10A-E07-T102-P3	10A-E07-T102-P3-BS	5/3/10 10:02	13.5	4.7 J	5.6 J	39 J
10A-E07-T135-P1	10A-E07-T135-P1-AS	5/3/10 8:43	3	4.9 J	4.8 J	27 J
10A-E07-T135-P1	10A-E07-T135-P1-BS	5/3/10 8:42	7	4.9 J	7.5 J	61 J
10A-E07-T135-P2	10A-E07-T135-P2-AS	5/3/10 8:56	3			29 J
10A-E07-T135-P2	10A-E07-T135-P2-BS	5/3/10 8:55	10			80 J
10A-E07-T135-P3	10A-E07-T135-P3-AS	5/3/10 9:08	3	4.9 J	5.0 J	30 J
10A-E07-T135-P3	10A-E07-T135-P3-AT	5/3/10 9:08	3			24 J
10A-E07-T135-P3	10A-E07-T135-P3-BS	5/3/10 9:06	13	5.1 J	7.1 J	51 J
10A-E08-T014-P1	10A-E08-T014-P1-AS	5/3/10 16:00	3	4.9 J	2.2 J	14 J
10A-E08-T014-P1	10A-E08-T014-P1-BS	5/3/10 15:58	12	8.1 J	2.3 J	19 J
10A-E08-T014-P2	10A-E08-T014-P2-AS	5/3/10 16:06	3			13 J
10A-E08-T014-P2	10A-E08-T014-P2-BS	5/3/10 16:05	12			R
10A-E08-T014-P3	10A-E08-T014-P3-AS	5/3/10 16:12	3	4.8 J	2.2 J	12 J
10A-E08-T014-P3	10A-E08-T014-P3-BS	5/3/10 16:10	11	8.2 J	1.8 J	R
10A-E08-T042-P1	10A-E08-T042-P1-AS	5/3/10 16:34	3	4.7 J	4.0 J	31 J
10A-E08-T042-P1	10A-E08-T042-P1-BS	5/3/10 16:33	12	4.7 J	4.2 J	29 J
10A-E08-T042-P2	10A-E08-T042-P2-AS	5/3/10 16:39	3			40 J
10A-E08-T042-P2	10A-E08-T042-P2-BS	5/3/10 16:39	15			34 J
10A-E08-T042-P3	10A-E08-T042-P3-AS	5/3/10 16:45	3	4.6 J	4.9 J	39 J
10A-E08-T042-P3	10A-E08-T042-P3-BS	5/3/10 16:44	11	4.8 J	5.4 J	46 J
10A-E08-T067-P1	10A-E08-T067-P1-AS	5/3/10 16:07	3	5.0 J	5.5 J	28 J
10A-E08-T067-P1	10A-E08-T067-P1-BS	5/3/10 16:05	9.3	5.3 J	12 J	73 J
10A-E08-T067-P2	10A-E08-T067-P2-BS	5/3/10 16:16	12			190
10A-E08-T067-P3	10A-E08-T067-P3-AS	5/3/10 16:24	3	5.0 J	3.7 J	31 J
10A-E08-T067-P3	10A-E08-T067-P3-BS	5/3/10 16:22	10	5.1 J	7.7 J	33 J
10A-E08-T102-P1	10A-E08-T102-P1-AS	5/3/10 15:07	3	5.0 J	2.7 J	15 J
10A-E08-T102-P1	10A-E08-T102-P1-BS	5/3/10 15:03	9	5.1 J	3.2 J	18 J
10A-E08-T102-P2	10A-E08-T102-P2-AS	5/3/10 15:14	3			16 J
10A-E08-T102-P2	10A-E08-T102-P2-AT	5/3/10 15:15	3			16 J
10A-E08-T102-P2	10A-E08-T102-P2-BS	5/3/10 15:13	13.8			15 J
10A-E08-T102-P3	10A-E08-T102-P3-AS	5/3/10 15:29	3	4.7 J	4.4 J	26 J
10A-E08-T102-P3	10A-E08-T102-P3-AT	5/3/10 15:29	3	5.4 J	4.8 J	
10A-E08-T102-P3	10A-E08-T102-P3-BS	5/3/10 15:26	11.3	5.1 J	6.5 J	15 J
10A-E08-T135-P1	10A-E08-T135-P1-AS	5/3/10 14:17	3	5.1 J	2.6 J	15 J
10A-E08-T135-P1	10A-E08-T135-P1-BS	5/3/10 14:14	10	5.0 J	4.6 J	29 J
10A-E08-T135-P2	10A-E08-T135-P2-AS	5/3/10 14:26	3			57 J

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
10A-E08-T135-P2	10A-E08-T135-P2-BS	5/3/10 14:25	12.3			20 J
10A-E08-T135-P3	10A-E08-T135-P3-AS	5/3/10 14:34	3	5.0 J	2.4 J	14 J
10A-E08-T135-P3	10A-E08-T135-P3-AT	5/3/10 14:35	3	5.0 J	3.0 J	
10A-E08-T135-P3	10A-E08-T135-P3-BS	5/3/10 14:32	14	4.9 J	3.8 J	16 J
10A-E09-T014-P3	10A-E09-T014-P3-AS	5/2/10 10:46	3			126
10A-E09-T014-P3	10A-E09-T014-P3-BS	5/2/10 10:45	16			96
10A-E09-T042-P1	10A-E09-T042-P1-AS	5/2/10 13:01	3			13
10A-E09-T042-P1	10A-E09-T042-P1-BS	5/2/10 13:00	16.5			7
10A-E09-T067-P3	10A-E09-T067-P3-AS	5/1/10 17:00	3			15
10A-E09-T067-P3	10A-E09-T067-P3-BS	5/1/10 16:59	9			14
10A-E09-T102-P1	10A-E09-T102-P1-AS	5/1/10 14:01	3			10
10A-E09-T102-P1	10A-E09-T102-P1-BS	5/1/10 13:59	14			6
10A-E09-T102-P1	10A-E09-T102-P1-BT	5/1/10 13:59	14			8
10A-E09-T135-P3	10A-E09-T135-P3-AS	5/1/10 11:53	3			7
10A-E09-T135-P3	10A-E09-T135-P3-BS	5/1/10 11:51	14			5
10A-E10-T014-P3	10A-E10-T014-P3-AS	5/20/10 8:57	3			23 J
10A-E10-T014-P3	10A-E10-T014-P3-AT	5/20/10 8:57	3			25 J
10A-E10-T014-P3	10A-E10-T014-P3-BS	5/20/10 8:55	10.5			16 J
10A-E10-T042-P1	10A-E10-T042-P1-AS	5/20/10 11:13	3			27 J
10A-E10-T042-P1	10A-E10-T042-P1-BS	5/20/10 11:12	13.5			108 J
10A-E10-T067-P3	10A-E10-T067-P3-AS	5/19/10 15:24	3			13 J
10A-E10-T067-P3	10A-E10-T067-P3-BS	5/19/10 15:23	12			7 J
10A-E10-T102-P1	10A-E10-T102-P1-AS	5/19/10 0:53	3			9 J
10A-E10-T102-P1	10A-E10-T102-P1-BS	5/19/10 0:52	15			10 J
10A-E10-T135-P3	10A-E10-T135-P3-AS	5/19/10 10:12	3			9 J
10A-E10-T135-P3	10A-E10-T135-P3-BS	5/19/10 10:11	11			8 J
10A-E10-T175-P2	10A-E10-T175-P2-AS	5/25/10 10:35	3			4 J
10A-E10-T175-P2	10A-E10-T175-P2-BS	5/25/10 10:34	6			4 J
10A-E11-T175-P1	10A-E11-T175-P1-AS	5/25/10 11:40	3	4.0 J	1.5	5 J
10A-E11-T175-P2	10A-E11-T175-P2-AS	5/25/10 11:45	3	4.1 J	1.3	4 J
10A-E11-T175-P2	10A-E11-T175-P2-BS	5/25/10 11:43	6	4.0 J	1.1	4 J
10A-E11-T175-P3	10A-E11-T175-P3-AS	5/25/10 11:49	3	4.0 J	1.1	4 J
10A-E11-T175-P4	10A-E11-T175-P4-AS	5/25/10 11:52	3	4.0 J	1.0	13 J
10A-E12-T014-P1	10A-E12-T014-P1-AS	5/24/10 8:41	3	3.4 J	2.2 J	17 J
10A-E12-T014-P1	10A-E12-T014-P1-BS	5/24/10 8:40	11	2.4 J	2.6 J	103 J
10A-E12-T014-P2	10A-E12-T014-P2-AS	5/24/10 8:51	3			15 J
10A-E12-T014-P2	10A-E12-T014-P2-BS	5/24/10 8:50	15			19 J
10A-E12-T014-P3	10A-E12-T014-P3-AS	5/24/10 9:03	3	3.1 J	2.2 J	16 J
10A-E12-T014-P3	10A-E12-T014-P3-AT	5/24/10 9:05	3	3.2 J	2.0 J	
10A-E12-T014-P3	10A-E12-T014-P3-BS	5/24/10 9:01	13	2.8 J	2.0 J	23 J
10A-E12-T042-P1	10A-E12-T042-P1-AS	5/24/10 9:35	3	3.4 J	3.1 J	29 J
10A-E12-T042-P1	10A-E12-T042-P1-BS	5/24/10 9:33	14	3.3 J	3.8 J	38 J
10A-E12-T042-P2	10A-E12-T042-P2-AS	5/24/10 9:44	3			27 J
10A-E12-T042-P2	10A-E12-T042-P2-BS	5/24/10 9:43	17			39 J
10A-E12-T042-P3	10A-E12-T042-P3-AS	5/24/10 9:53	3	3.6 J	3.0 J	29 J
10A-E12-T042-P3	10A-E12-T042-P3-BS	5/24/10 9:52	12	3.6 J	4.8 J	48 J
10A-E12-T067-P1	10A-E12-T067-P1-AS	5/24/10 9:21	3	4.9 J	5.7 J	46 J
10A-E12-T067-P1	10A-E12-T067-P1-BS	5/24/10 9:19	10.4	4.2 J	11 J	132 J
10A-E12-T067-P1	10A-E13-T067-P1-AS	5/24/10 15:33	3	3.6 J	6.4	90 J
10A-E12-T067-P1	10A-E13-T067-P1-BS	5/24/10 15:31	9.6	2.7 J	8.8	118 J
10A-E12-T067-P2	10A-E12-T067-P2-AS	5/24/10 9:28	3			67 J
10A-E12-T067-P2	10A-E12-T067-P2-BS	5/24/10 9:27	13			113 J
10A-E12-T067-P2	10A-E12-T067-P2-BT	5/24/10 9:27	13			65 J
10A-E12-T067-P2	10A-E13-T067-P2-AS	5/24/10 15:37	3			104 J
10A-E12-T067-P2	10A-E13-T067-P2-BS	5/24/10 15:37	9.4			107 J
10A-E12-T067-P3	10A-E12-T067-P3-AS	5/24/10 9:32	3	4.0 J	4.5 J	70 J
10A-E12-T067-P3	10A-E12-T067-P3-BS	5/24/10 9:31	10.7	3.8 J	5.8 J	52 J
10A-E12-T067-P3	10A-E13-T067-P3-AS	5/24/10 15:43	3	3.6 J	5.1	44 J
10A-E12-T067-P3	10A-E13-T067-P3-BS	5/24/10 15:41	9.8	3.6 J	13	180 J
10A-E12-T102-P1	10A-E12-T102-P1-AS	5/24/10 8:28	3	5.1 J	2.2 J	8 J
10A-E12-T102-P1	10A-E12-T102-P1-BS	5/24/10 8:26	13	4.9 J	2.4 J	11 J
10A-E12-T102-P1	10A-E13-T102-P1-AS	5/24/10 14:46	3	3.8 J	1.3	8 J
10A-E12-T102-P1	10A-E13-T102-P1-AT	5/24/10 14:47	3			14 J
10A-E12-T102-P1	10A-E13-T102-P1-BS	5/24/10 14:44	9.9	3.7 J	1.4	7 J
10A-E12-T102-P2	10A-E12-T102-P2-AS	5/24/10 8:36	3			10 J
10A-E12-T102-P2	10A-E12-T102-P2-BS	5/24/10 8:34	14.5			10 J
10A-E12-T102-P2	10A-E13-T102-P2-AS	5/24/10 14:51	3			8 J
10A-E12-T102-P2	10A-E13-T102-P2-BS	5/24/10 14:50	9.4			8 J
10A-E12-T102-P3	10A-E12-T102-P3-AS	5/24/10 8:43	3	4.1 J	2.6 J	12 J

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
10A-E12-T102-P3	10A-E12-T102-P3-BS	5/24/10 8:41	14.6	4.9 J	2.7 J	16 J
10A-E12-T102-P3	10A-E13-T102-P3-AS	5/24/10 14:56	3	3.8 J	1.4	10 J
10A-E12-T102-P3	10A-E13-T102-P3-BS	5/24/10 14:54	10.4	3.2 J	2.6	10 J
10A-E12-T135-P1	10A-E12-T135-P1-AS	5/24/10 7:27	3	4.2 J	1.9	5 J
10A-E12-T135-P1	10A-E12-T135-P1-BS	5/24/10 7:26	7	4.4 J	1.8	8 J
10A-E12-T135-P1	10A-E13-T135-P1-AS	5/24/10 14:00	3	4.0 J	1.5	5 J
10A-E12-T135-P1	10A-E13-T135-P1-AT	5/24/10 14:01	3	4.0 J	1.2	
10A-E12-T135-P1	10A-E13-T135-P1-BS	5/24/10 13:58	6	5.0 J	1.7	7 J
10A-E12-T135-P2	10A-E12-T135-P2-AS	5/24/10 7:34	3			5 J
10A-E12-T135-P2	10A-E12-T135-P2-BS	5/24/10 7:33	12.9			6 J
10A-E12-T135-P2	10A-E13-T135-P2-AS	5/24/10 14:07	3			7 J
10A-E12-T135-P2	10A-E13-T135-P2-BS	5/24/10 14:06	8.6			7 J
10A-E12-T135-P3	10A-E12-T135-P3-AS	5/24/10 7:43	3	4.8 J	2.0	7 J
10A-E12-T135-P3	10A-E12-T135-P3-BS	5/24/10 7:40	14	4.2 J	2.0	9 J
10A-E12-T135-P3	10A-E13-T135-P3-AS	5/24/10 14:12	3	3.9 J	1.2	6 J
10A-E12-T135-P3	10A-E13-T135-P3-BS	5/24/10 14:11	9.6	4.0 J	1.3	8 J
10A-E13-T014-P1	10A-E13-T014-P1-AS	5/24/10 15:01	3	3.2 J	1.7	15 J
10A-E13-T014-P1	10A-E13-T014-P1-BS	5/24/10 15:00	10	2.7 J	9.0	31 J
10A-E13-T014-P2	10A-E13-T014-P2-AS	5/24/10 15:09	3			14 J
10A-E13-T014-P2	10A-E13-T014-P2-BS	5/24/10 15:08	15			69 J
10A-E13-T014-P3	10A-E13-T014-P3-AS	5/24/10 15:17	3	4.4 J	1.0 U	15 J
10A-E13-T014-P3	10A-E13-T014-P3-BS	5/24/10 15:14	15	3.7 J	5.1	106 J
10A-E13-T014-P3	10A-E13-T014-P3-BT	5/24/10 15:15	15			113 J
10A-E13-T042-P1	10A-E13-T042-P1-AS	5/24/10 15:45	3	4.3 J	2.2	22 J
10A-E13-T042-P1	10A-E13-T042-P1-BS	5/24/10 15:44	15	4.0 J	22.8	289 J
10A-E13-T042-P1	10A-E13-T042-P1-BT	5/24/10 15:44	15	4.1 J	19.2	
10A-E13-T042-P2	10A-E13-T042-P2-AS	5/24/10 15:53	3			23 J
10A-E13-T042-P2	10A-E13-T042-P2-BS	5/24/10 15:52	18			223 J
10A-E13-T042-P3	10A-E13-T042-P3-AS	5/24/10 16:00	3	4.2 J	3.0	34 J
10A-E13-T042-P3	10A-E13-T042-P3-BS	5/24/10 15:59	16	4.0 J	18.2	131 J
10A-E14-T014-P3	10A-E14-T014-P3-AS	5/20/10 10:44	3			11 J
10A-E14-T014-P3	10A-E14-T014-P3-BS	5/20/10 10:42	13			8 J
10A-E14-T042-P1	10A-E14-T042-P1-AS	5/20/10 0:41	3			40 J
10A-E14-T042-P1	10A-E14-T042-P1-BS	5/20/10 0:40	15.5			33 J
10A-E14-T067-P3	10A-E14-T067-P3-AS	5/19/10 16:53	3			33 J
10A-E14-T067-P3	10A-E14-T067-P3-BS	5/19/10 16:51	11			51 J
10A-E14-T102-P1	10A-E14-T102-P1-AS	5/19/10 14:40	3			7 J
10A-E14-T102-P1	10A-E14-T102-P1-BS	5/19/10 14:38	16			30 J
10A-E14-T135-P3	10A-E14-T135-P3-AS	5/19/10 0:17	3			7 J
10A-E14-T135-P3	10A-E14-T135-P3-AT	5/19/10 0:17	3			6 J
10A-E14-T135-P3	10A-E14-T135-P3-BS	5/19/10 0:16	14			15 J
10A-E15-T014-P3	10A-E15-T014-P3-AS	6/18/10 8:56	3			18 J
10A-E15-T014-P3	10A-E15-T014-P3-BS	6/18/10 8:55	11.9			18 J
10A-E15-T042-P1	10A-E15-T042-P1-AS	6/18/10 11:57	3			31 J
10A-E15-T042-P1	10A-E15-T042-P1-BS	6/18/10 11:56	13.2			338
10A-E15-T067-P3	10A-E15-T067-P3-AS	6/17/10 14:50	3			45 J
10A-E15-T067-P3	10A-E15-T067-P3-BS	6/17/10 14:49	13.3			45 J
10A-E15-T102-P1	10A-E15-T102-P1-AS	6/17/10 0:16	3			45 J
10A-E15-T102-P1	10A-E15-T102-P1-BS	6/17/10 0:15	13.8			27 J
10A-E15-T135-P3	10A-E15-T135-P3-AS	6/17/10 9:28	3			15 J
10A-E15-T135-P3	10A-E15-T135-P3-BS	6/17/10 9:27	8.3			17 J
10A-E15-T175-P2	10A-E15-T175-P2-AS	6/21/10 15:15	3			12 J
10A-E15-T175-P2	10A-E15-T175-P2-BS	6/21/10 15:14	7			20 J
10A-E15-T175-P2	10A-E15-T175-P2-BT	6/21/10 15:14	7			15 J
10A-E16-T175-P1	10A-E16-T175-P1-AS	6/21/10 16:17	3	5.2	5.9	46 J
10A-E16-T175-P2	10A-E16-T175-P2-AS	6/21/10 16:23	3	5.0	3.8	15 J
10A-E16-T175-P2	10A-E16-T175-P2-BS	6/21/10 16:21	7	4.6	3.8	13 J
10A-E16-T175-P3	10A-E16-T175-P3-AS	6/21/10 16:28	3	4.5	2.7	10 J
10A-E16-T175-P4	10A-E16-T175-P4-AS	6/21/10 16:31	3	4.3	4.4	10 J
10A-E17-T014-P1	10A-E17-T014-P1-AS	6/22/10 8:23	3	3.1	1.0 U	16 J
10A-E17-T014-P1	10A-E17-T014-P1-BS	6/22/10 8:22	12	2.7	1.0	10 J
10A-E17-T014-P2	10A-E17-T014-P2-AS	6/22/10 8:30	3			24 J
10A-E17-T014-P2	10A-E17-T014-P2-BS	6/22/10 8:30	15			11 J
10A-E17-T014-P3	10A-E17-T014-P3-AS	6/22/10 8:39	3	0.46	1.0	10 J
10A-E17-T014-P3	10A-E17-T014-P3-BS	6/22/10 8:38	13	2.7	1.0 U	9 J
10A-E17-T042-P1	10A-E17-T042-P1-AS	6/22/10 9:09	3	2.7	1.9	14 J
10A-E17-T042-P1	10A-E17-T042-P1-BS	6/22/10 9:07	13	3.6	1.6	13 J
10A-E17-T042-P2	10A-E17-T042-P2-AS	6/22/10 9:14	3			15 J
10A-E17-T042-P2	10A-E17-T042-P2-AT	6/22/10 9:14	3			14 J

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
10A-E17-T042-P2	10A-E17-T042-P2-BS	6/22/10 9:13	17			14 J
10A-E17-T042-P3	10A-E17-T042-P3-AS	6/22/10 9:19	3	3.6	2.2	25 J
10A-E17-T042-P3	10A-E17-T042-P3-BS	6/22/10 9:18	12	3.3	2.0	18 J
10A-E17-T067-P1	10A-E17-T067-P1-AS	6/22/10 8:37	3	3.7	2.7	20 J
10A-E17-T067-P1	10A-E17-T067-P1-BS	6/22/10 8:35	11.2	3.7	4.7	37 J
10A-E17-T067-P2	10A-E17-T067-P2-AS	6/22/10 8:41	3			20 J
10A-E17-T067-P2	10A-E17-T067-P2-BS	6/22/10 8:40	13.2			27 J
10A-E17-T067-P3	10A-E17-T067-P3-AS	6/22/10 8:50	3	3.6	2.7	22 J
10A-E17-T067-P3	10A-E17-T067-P3-BS	6/22/10 8:47	11.6	2.8	4.5	32 J
10A-E17-T067-P3	10A-E17-T067-P3-BT	6/22/10 8:48	11.6	3.7	3.4	
10A-E17-T102-P1	10A-E17-T102-P1-AS	6/22/10 7:56	3	3.7	4.4	34 J
10A-E17-T102-P1	10A-E17-T102-P1-BS	6/22/10 7:54	13.19	3.7	6.2	46 J
10A-E17-T102-P2	10A-E17-T102-P2-AS	6/22/10 8:00	3			34 J
10A-E17-T102-P2	10A-E17-T102-P2-BS	6/22/10 7:59	13.3			33 J
10A-E17-T102-P3	10A-E17-T102-P3-AS	6/22/10 8:08	3	3.7	4.9	36 J
10A-E17-T102-P3	10A-E17-T102-P3-BS	6/22/10 8:06	13.1	4.0	5.2 J	39 J
10A-E17-T102-P3	10A-E17-T102-P3-BT	6/22/10 8:06	13.1			38 J
10A-E17-T135-P1	10A-E17-T135-P1-AS	6/22/10 7:18	3		3.8	17 J
10A-E17-T135-P1	10A-E17-T135-P1-BS	6/22/10 7:15	7.96		4.5	27 J
10A-E17-T135-P2	10A-E17-T135-P2-AS	6/22/10 7:22	3			16 J
10A-E17-T135-P2	10A-E17-T135-P2-BS	6/22/10 7:21	11.4			27 J
10A-E17-T135-P3	10A-E17-T135-P3-AS	6/22/10 7:29	3	4.0	3.4	18 J
10A-E17-T135-P3	10A-E17-T135-P3-BS	6/22/10 7:26	13.08		4.1	25 J
10A-E18-T014-P1	10A-E18-T014-P1-AS	6/22/10 16:29	3	2.9	0.9 J	8 J
10A-E18-T014-P1	10A-E18-T014-P1-BS	6/22/10 16:28	16	2.5	1.4 J	21 J
10A-E18-T014-P2	10A-E18-T014-P2-AS	6/22/10 16:33	3			6 J
10A-E18-T014-P2	10A-E18-T014-P2-BS	6/22/10 16:32	18			19 J
10A-E18-T014-P3	10A-E18-T014-P3-AS	6/22/10 16:38	3	3.0	1.2 J	7 J
10A-E18-T014-P3	10A-E18-T014-P3-AT	6/22/10 16:38	3	3.2	1.0 UJ	
10A-E18-T014-P3	10A-E18-T014-P3-BS	6/22/10 16:35	16	2.6	1.2 J	13 J
10A-E18-T042-P1	10A-E18-T042-P1-AS	6/22/10 15:57	3	2.6	1.9 J	13 J
10A-E18-T042-P1	10A-E18-T042-P1-BS	6/22/10 15:55	16	3.1	5.3 J	73
10A-E18-T042-P2	10A-E18-T042-P2-AS	6/22/10 16:00	3			15 J
10A-E18-T042-P2	10A-E18-T042-P2-BS	6/22/10 16:00	21			79 J
10A-E18-T042-P3	10A-E18-T042-P3-AS	6/22/10 16:05	3	3.6	1.4 J	19 J
10A-E18-T042-P3	10A-E18-T042-P3-BS	6/22/10 16:03	16	3.5	1.5 J	27 J
10A-E18-T067-P1	10A-E18-T067-P1-AS	6/22/10 15:13	3	3.0	7.9 J	53 J
10A-E18-T067-P1	10A-E18-T067-P1-BS	6/22/10 15:12	10.2	2.7	8.5	106 J
10A-E18-T067-P2	10A-E18-T067-P2-AS	6/22/10 15:16	3			45 J
10A-E18-T067-P2	10A-E18-T067-P2-BS	6/22/10 15:15	13.2			87 J
10A-E18-T067-P3	10A-E18-T067-P3-AS	6/22/10 15:23	3	2.8	5.5	52 J
10A-E18-T067-P3	10A-E18-T067-P3-BS	6/22/10 15:21	13.6	2.8	4.3 J	99 J
10A-E18-T102-P1	10A-E18-T102-P1-AS	6/22/10 14:28	3	4.1	6.7	57 J
10A-E18-T102-P1	10A-E18-T102-P1-BS	6/22/10 14:23	11.26	3.7	11.6	105 J
10A-E18-T102-P2	10A-E18-T102-P2-AS	6/22/10 14:32	3			43 J
10A-E18-T102-P2	10A-E18-T102-P2-BS	6/22/10 14:32	12.2			82 J
10A-E18-T102-P3	10A-E18-T102-P3-AS	6/22/10 14:37	3	4.0	4.4	35 J
10A-E18-T102-P3	10A-E18-T102-P3-BS	6/22/10 14:36	13.3	4.0	7.5	82 J
10A-E18-T135-P1	10A-E18-T135-P1-AS	6/22/10 13:46	3	3.9	3.0	18 J
10A-E18-T135-P1	10A-E18-T135-P1-BS	6/22/10 13:44	5.1	4.0	4.2	20 J
10A-E18-T135-P2	10A-E18-T135-P2-AS	6/22/10 13:50	3			13 J
10A-E18-T135-P2	10A-E18-T135-P2-BS	6/22/10 13:49	6.5			14 J
10A-E18-T135-P3	10A-E18-T135-P3-AS	6/22/10 13:56	3	4.2	4.2	13 J
10A-E18-T135-P3	10A-E18-T135-P3-AT	6/22/10 13:57	3	4.5	4.0	
10A-E18-T135-P3	10A-E18-T135-P3-BS	6/22/10 13:54	10.5	3.9	4.2	20 J
10A-E19-T014-P3	10A-E19-T014-P3-AS	6/18/10 11:04	3			15 J
10A-E19-T014-P3	10A-E19-T014-P3-BS	6/18/10 11:03	15.1			66 J
10A-E19-T042-P1	10A-E19-T042-P1-AS	6/18/10 14:08	3			37 J
10A-E19-T042-P1	10A-E19-T042-P1-AT	6/18/10 14:09	3			21 J
10A-E19-T042-P1	10A-E19-T042-P1-BS	6/18/10 14:08	16.4			33 J
10A-E19-T067-P3	10A-E19-T067-P3-AS	6/17/10 16:43	3			91 J
10A-E19-T067-P3	10A-E19-T067-P3-BS	6/17/10 16:42	12.4			137
10A-E19-T102-P1	10A-E19-T102-P1-AS	6/17/10 13:54	3			22 J
10A-E19-T102-P1	10A-E19-T102-P1-BS	6/17/10 13:53	14.7			22 J
10A-E19-T135-P3	10A-E19-T135-P3-AS	6/17/10 11:39	3			20 J
10A-E19-T135-P3	10A-E19-T135-P3-BS	6/17/10 11:37	10			14 J
10A-E19-T135-P3	10A-E19-T135-P3-BT	6/17/10 11:38	10			18 J
10A-E20-T175-P1	10A-E20-T175-P1-AS	7/22/10 9:52	3	5.13	19.1 J	280 J
10A-E20-T175-P2	10A-E20-T175-P2-AS	7/22/10 9:59	3	4.96	2.8 J	10 J

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
10A-E20-T175-P2	10A-E20-T175-P2-BS	7/22/10 9:56	6	5.19	2.7 J	11 J
10A-E20-T175-P3	10A-E20-T175-P3-AS	7/22/10 10:03	3	4.99	2.7 J	9 J
10A-E20-T175-P4	10A-E20-T175-P4-AS	7/22/10 10:07	3	4.97	2.6 J	10 J
10A-E21-T014-P1	10A-E21-T014-P1-AS	7/21/10 8:06	3	3.1	1.2 J	13
10A-E21-T014-P1	10A-E21-T014-P1-BS	7/21/10 8:05	13	2.22 J	1.1 J	13
10A-E21-T014-P2	10A-E21-T014-P2-AS	7/21/10 8:12	3			10
10A-E21-T014-P2	10A-E21-T014-P2-BS	7/21/10 8:12	14			11
10A-E21-T014-P3	10A-E21-T014-P3-AS	7/21/10 8:18	3	2.74 J	1.2 J	10
10A-E21-T014-P3	10A-E21-T014-P3-BS	7/21/10 8:16	13	1.9	1.1 J	14
10A-E21-T042-P1	10A-E21-T042-P1-AS	7/21/10 8:42	3	3.6	1.8 J	17
10A-E21-T042-P1	10A-E21-T042-P1-BS	7/21/10 8:41	13	3.0	2 J	21
10A-E21-T042-P2	10A-E21-T042-P2-AS	7/21/10 8:47	3			21
10A-E21-T042-P2	10A-E21-T042-P2-BS	7/21/10 8:46	17			19
10A-E21-T042-P3	10A-E21-T042-P3-AS	7/21/10 8:52	3	3.2	2.1 J	18
10A-E21-T042-P3	10A-E21-T042-P3-BS	7/21/10 8:51	12	2.6	2.1 J	28
10A-E21-T067-P1	10A-E21-T067-P1-AS	7/21/10 8:51	3	4.45	2.8 J	19
10A-E21-T067-P1	10A-E21-T067-P1-BS	7/21/10 8:50	9.9	4.31	8.1 J	73
10A-E21-T067-P1	10A-E21-T067-P2-BT	7/21/10 8:58	11.8			50 J
10A-E21-T067-P2	10A-E21-T067-P2-AS	7/21/10 9:00	3			25
10A-E21-T067-P2	10A-E21-T067-P2-BS	7/21/10 8:58	11.8			117 J
10A-E21-T067-P3	10A-E21-T067-P3-AS	7/21/10 9:10	3	4.58	4 J	24
10A-E21-T067-P3	10A-E21-T067-P3-AT	7/21/10 9:11	3	4.46	4 J	26
10A-E21-T067-P3	10A-E21-T067-P3-BS	7/21/10 9:09	11.4	4.07	7 J	42
10A-E21-T102-P1	10A-E21-T102-P1-AS	7/21/10 7:59	3	4.6 J	3.4	18 J
10A-E21-T102-P1	10A-E21-T102-P1-BS	7/21/10 7:57	10.7	4.6 J	3.4	19 J
10A-E21-T102-P2	10A-E21-T102-P2-AS	7/21/10 8:04	3			18 J
10A-E21-T102-P2	10A-E21-T102-P2-BS	7/21/10 8:03	14.1			22 J
10A-E21-T102-P2	10A-E21-T102-P2-BT	7/21/10 8:03	14.1			25
10A-E21-T102-P3	10A-E21-T102-P3-AS	7/21/10 8:10	3	4.5 J	3.5	18 J
10A-E21-T102-P3	10A-E21-T102-P3-BS	7/21/10 8:08	14.4	5.45	4.1	29 J
10A-E21-T135-P1	10A-E21-T135-P1-AS	7/21/10 7:11	3	4.7 J	2.8	9 J
10A-E21-T135-P1	10A-E21-T135-P1-BS	7/21/10 7:10	6	5.7	2.5 J	9
10A-E21-T135-P2	10A-E21-T135-P2-AS	7/21/10 7:17	3			9 J
10A-E21-T135-P2	10A-E21-T135-P2-BS	7/21/10 7:17	10.6			12 J
10A-E21-T135-P3	10A-E21-T135-P3-AS	7/21/10 7:23	3	5.6	2.9 J	9
10A-E21-T135-P3	10A-E21-T135-P3-BS	7/21/10 7:21	11.6	4.8 J	2.6	11 J
10A-E22-T014-P1	10A-E22-T014-P1-AS	7/21/10 14:16	3	2.19 J	1.1	12 J
10A-E22-T014-P1	10A-E22-T014-P1-BS	7/21/10 14:14	12	5.0 UJ	3.6	64 J
10A-E22-T014-P2	10A-E22-T014-P2-AS	7/21/10 14:22	3			9 J
10A-E22-T014-P2	10A-E22-T014-P2-BS	7/21/10 14:21	14			85 J
10A-E22-T014-P3	10A-E22-T014-P3-AS	7/21/10 14:27	3	2.22 J	1.3	12 J
10A-E22-T014-P3	10A-E22-T014-P3-BS	7/21/10 14:26	15	1.77 J	4.3	62 J
10A-E22-T042-P1	10A-E22-T042-P1-AS	7/21/10 14:53	3	3.14 J	1.2	14 J
10A-E22-T042-P1	10A-E22-T042-P1-BS	7/21/10 14:52	15	2.13 J	5.6	91 J
10A-E22-T042-P2	10A-E22-T042-P2-AS	7/21/10 14:58	3			13 J
10A-E22-T042-P2	10A-E22-T042-P2-BS	7/21/10 14:57	18			96 J
10A-E22-T042-P3	10A-E22-T042-P3-AS	7/21/10 15:04	3	3.07 J	1.9	20 J
10A-E22-T042-P3	10A-E22-T042-P3-BS	7/21/10 15:03	14	2.63 J	2	96 J
10A-E22-T067-P1	10A-E22-T067-P1-AS	7/21/10 15:10	3	3.79	4.1	35 J
10A-E22-T067-P1	10A-E22-T067-P1-BS	7/21/10 15:08	11.2	3.84	5.4	65 J
10A-E22-T067-P2	10A-E22-T067-P2-AS	7/21/10 15:14	3			83 J
10A-E22-T067-P2	10A-E22-T067-P2-BS	7/21/10 15:14	14.4			95 J
10A-E22-T067-P3	10A-E22-T067-P3-AS	7/21/10 15:19	3	3.97 J	3.7	38 J
10A-E22-T067-P3	10A-E22-T067-P3-BS	7/21/10 15:18	13.5	3.8	9.8	72 J
10A-E22-T067-P3	10A-E22-T067-P3-BT	7/21/10 15:18	13.5			86 J
10A-E22-T102-P1	10A-E22-T102-P1-AS	7/21/10 14:26	3	5.54	3.6	37 J
10A-E22-T102-P1	10A-E22-T102-P1-BS	7/21/10 14:24	12.4	5.13	9.2 J	104 J
10A-E22-T102-P1	10A-E22-T102-P1-BT	7/21/10 14:25	12.4	5.26	7.4 J	97 J
10A-E22-T102-P2	10A-E22-T102-P2-AS	7/21/10 14:30	3			28 J
10A-E22-T102-P2	10A-E22-T102-P2-BS	7/21/10 14:29	12.2			51 J
10A-E22-T102-P3	10A-E22-T102-P3-AS	7/21/10 14:34	3	5.35	3.5	44 J
10A-E22-T102-P3	10A-E22-T102-P3-BS	7/21/10 14:33	14.1	5.35	5	48 J
10A-E22-T135-P1	10A-E22-T135-P1-AS	7/21/10 13:45	3	4.9	3.7	7 J
10A-E22-T135-P1	10A-E22-T135-P1-AT	7/21/10 13:46	3	4.7	3.4	6 J
10A-E22-T135-P1	10A-E22-T135-P1-BS	7/21/10 13:44	6.3	5.57	2.5	9 J
10A-E22-T135-P2	10A-E22-T135-P2-AS	7/21/10 13:51	3			7 J
10A-E22-T135-P2	10A-E22-T135-P2-BS	7/21/10 13:50	7.8			6 J
10A-E22-T135-P3	10A-E22-T135-P3-AS	7/21/10 13:57	3	4.8	3.7	9 J
10A-E22-T135-P3	10A-E22-T135-P3-BS	7/21/10 13:55	9.08	4.7	2.1	7 J

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
10A-E22-T135-P3	10A-E22-T135-P3-BT	7/21/10 13:55	9.08			7 J
10A-E23-T014-P3	10A-E23-T014-P3-BS	7/22/10 8:37	14			4
10A-E23-T042-P1	10A-E23-T042-P1-AS	7/22/10 8:52	3			20 J
10A-E23-T042-P1	10A-E23-T042-P1-BS	7/22/10 8:51	15			5 J
10A-E23-T067-P3	10A-E23-T067-P3-AS	7/23/10 9:18	3			21 J
10A-E23-T067-P3	10A-E23-T067-P3-BS	7/23/10 9:16	14			9 J
10A-E23-T102-P1	10A-E23-T102-P1-AS	7/23/10 9:41	3			26 J
10A-E23-T102-P1	10A-E23-T102-P1-BS	7/23/10 9:39	13.5			33 J
10A-E23-T135-P3	10A-E23-T135-P3-AS	7/23/10 10:03	3			9 J
10A-E23-T135-P3	10A-E23-T135-P3-BS	7/23/10 10:02	12			19 J
High Flow / Flood Event						
10B-T054-P1	BRIDGE 1 [b]	3/16/10 9:25	1	3.3 J	6.9 J	110
10B-T054-P1	BRIDGE 2 [c]	3/16/10 11:29	1	3.3 J	5.5 J	120
10B-T054-P1	BRIDGE 3	3/16/10 14:49	1	3.2 J	16 J	180
10B-T054-P1	BRIDGE 4	3/16/10 16:04	1	3.4 J	11 J	170
10B-T104-P1	PARK 1	3/16/10 9:02	1	3.6 J	6.6 J	70
10B-T104-P1	PARK 2 [d]	3/16/10 10:54	1	3.4 J	4.8 J	67
10B-T104-P1	PARK 3	3/16/10 14:21	1	3.4 J	4.1 J	88
10B-T104-P1	PARK 3D	3/16/10 14:21	1	3.1 J	5.1 J	68
10B-T104-P1	PARK 4	3/16/10 15:40	1	3.4 J	4.2 J	80
10B-T104-P1	PARK 5	3/16/10 16:27	1	3.5 J	4.6 J	66
10B-T130-P1	UNION 1	3/16/10 8:25	1	3.1	4.9 J	60
10B-T130-P1	UNION 2	3/16/10 11:40	1	3.5 J	4.7 J	59
10B-T130-P1	UNION 3	3/16/10 14:15	1	3.3	4.4 J	69
10B-T130-P1	UNION 4	3/16/10 15:30	1	3.8	6.2 J	71
10B-T169-P1	ACKERMAN 1	3/16/10 9:15	1	3.5	4.1 J	210
10B-T169-P1	ACKERMAN 2	3/16/10 12:10	1	3.5 J	4.7 J	68
10B-T169-P1	ACKERMAN 2D	3/16/10 12:10	1	3.4 J	5.3 J	59
10B-T169-P1	ACKERMAN 3	3/16/10 15:05	1	3.9	4.4 J	63
10B-T169-P1	ACKERMAN 4	3/16/10 15:55	1	4.0	3.7 J	54
10B-T2R1-P1	2ND RIVER WASHINGTON AVENUE	3/16/10 12:44	1	2.5 J	1.0 UJ	1 U
10B-T2R2-P1	SECOND HOT	3/16/10 12:19	1	2.6 J	1.1 J	1 U
10B-T3R1-P1	THIRD RIVER ROAD 1	3/16/10 13:50	1	2.6	1.0 UJ	2
10B-T3R2-P1	THIRD RIVER HOT 1	3/16/10 13:17	1	2.6	1.0 UJ	4
10B-TNBB-P1	NB1	3/16/10 10:47	1	3.4	1.7 J	23
10B-TNBB-P2	NB2	3/16/10 11:02	1	3.1	2.3 J	32
10B-TNBB-P3	NB3	3/16/10 11:13	1	3.2 J	2.9 J	42
10B-TNBB-P3	NB3-DUP	3/16/10 11:14	1	4.1 J	2.7 J	41
10B-TNBB-P4	NB4	3/16/10 11:23	1	3.4	3.2 J	47
10B-TNBB-P5	NB5	3/16/10 14:08	1	3.1	2.4 J	25
10B-TNBB-P6	NB6	3/16/10 14:45	1	3.3	2.1 J	19
10B-TPRB-P1	PR1	3/16/10 11:33	1	3.2	3.8 J	59
10B-TPRB-P2	PR2	3/16/10 0:00	1	3.3	4.5 J	84
10B-TPRB-P3	PR3	3/16/10 12:52	1	3.2	3.1 J	56
10B-TPRB-P4	PR4	3/16/10 12:59	1	3.4	6.3 J	84
10B-TPRB-P5	PR5	3/16/10 13:15	1	3.3	5.0 J	63
10B-TPRB-P6	PR6	3/16/10 13:25	1	3.4	6.5 J	91
10B-TSR1-P1	SADDLE RIVER AVE 1	3/16/10 10:15	1	4.1	2.0 J	11
10B-TSR3-P1	SADDLE RIVER HOT 1	3/16/10 9:40	1	3.5	1.6 J	11
Wet Weather Tributary Sampling						
10C-T169-P1	10C-E01-T169-P1-AS	5/12/10 6:50	(a)	5.3	1.9	8
10C-T169-P1	10C-E02-T169-P1-AS	5/12/10 8:15	(a)	5.5	2.1	8
10C-T169-P1	10C-E03-T169-P1-AS	5/12/10 9:25	(a)	5.1	2.1	8
10C-T169-P1	10C-E04-T169-P1-AS	5/12/10 10:19	(a)	6.1	2.1	8
10C-T169-P1	10C-E05-T169-P1-AS	5/12/10 11:02	(a)	5.2	1.7	8
10C-T169-P1	10C-E06-T169-P1-AS	5/12/10 11:50	(a)	6.7	1.9	8
10C-T169-P1	10C-E07-T169-P1-AS	11/4/10 8:35	(a)	7.36 J	1.2 J	6
10C-T169-P1	10C-E08-T169-P1-AS	11/4/10 9:41	(a)	7.69 J	1.3 J	8
10C-T169-P1	10C-E09-T169-P1-AS	11/4/10 10:46	(a)	7.43 J	1.6 J	9
10C-T169-P1	10C-E10-T169-P1-AS	11/4/10 11:46	(a)	7.73 J	1.9	13
10C-T169-P1	10C-E11-T169-P1-AS	11/4/10 12:51	(a)	7.53 J	2.3	20
10C-T169-P1	10C-E12-T169-P1-AS	11/4/10 13:49	(a)	5.89 J	2.2	18
10C-T169-P2	10C-E01-T169-P2-AS	5/12/10 6:35	(a)	6.2	1.9	10
10C-T169-P2	10C-E02-T169-P2-AS	5/12/10 8:05	(a)	5.9	2.2	9
10C-T169-P2	10C-E03-T169-P2-AS	5/12/10 9:17	(a)	5.7	2.2	10
10C-T169-P2	10C-E04-T169-P2-AS	5/12/10 10:15	(a)	5.5	1.9	8
10C-T169-P2	10C-E05-T169-P2-AS	5/12/10 10:57	(a)	5.6	2.0	9
10C-T169-P2	10C-E06-T169-P2-AS	5/12/10 11:43	(a)	5.4	1.9	8

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
10C-T169-P2	10C-E07-T169-P2-AS	11/4/10 8:48	(a)	6.03	1.6	8 J
10C-T169-P2	10C-E08-T169-P2-AS	11/4/10 9:52	(a)	6.28	1.3	5 J
10C-T169-P2	10C-E09-T169-P2-AS	11/4/10 10:59	(a)	6.36	2.9	16 J
10C-T169-P2	10C-E10-T169-P2-AS	11/4/10 11:55	(a)	6.25	1.4	8 J
10C-T169-P2	10C-E11-T169-P2-AS	11/4/10 13:01	(a)	6.33	2.8	15 J
10C-T169-P2	10C-E12-T169-P2-AS	11/4/10 13:59	(a)	5.99	3.3	26 J
10C-T2R1-P1	10C-E01-T2R1-P1-AS	5/12/10 6:35	(a)	4.9	4.7	18
10C-T2R1-P1	10C-E02-T2R1-P1-AS	5/12/10 7:53	(a)	4.9	2.5	8
10C-T2R1-P1	10C-E03-T2R1-P1-AS	5/12/10 9:04	(a)	4.5	1.7	4
10C-T2R1-P1	10C-E04-T2R1-P1-AS	5/12/10 10:31	(a)	4.4	2.0	5
10C-T2R1-P1	10C-E04-T2R1-P1-AT	5/12/10 10:25	(a)	5.4	1.9	6
10C-T2R1-P1	10C-E05-T2R1-P1-AS	5/12/10 11:39	(a)	5.4	2.6	8
10C-T2R1-P1	10C-E06-T2R1-P1-AS	5/12/10 12:48	(a)	4.7	1.6	4
10C-T2R1-P1	10C-E07-T2R1-P1-AS	11/4/10 20:03	(a)	15	28.5 J	113 J
10C-T2R1-P1	10C-E08-T2R1-P1-AS	11/4/10 21:15	(a)	11.4	20.2 J	174 J
10C-T2R1-P1	10C-E09-T2R1-P1-AS	11/4/10 10:10	(a)	14.8	12 J	62 J
10C-T2R1-P1	10C-E10-T2R1-P1-AS	11/4/10 11:10	(a)	15.7	10.1 J	43 J
10C-T2R1-P1	10C-E11-T2R1-P1-AS	11/4/10 12:00	(a)	8.79	11.7 J	166 J
10C-T2R1-P1	10C-E12-T2R1-P1-AS	11/4/10 12:55	(a)	10.5	9.6 J	63 J
10C-T3R1-P1	10C-E01-T3R1-P1-AS	5/12/10 7:05	(a)	3.8	2.9	13
10C-T3R1-P1	10C-E02-T3R1-P1-AS	5/12/10 8:30	(a)	4.1	2.7	11
10C-T3R1-P1	10C-E03-T3R1-P1-AS	5/12/10 9:48	(a)	4.2	2.49	9
10C-T3R1-P1	10C-E04-T3R1-P1-AS	5/12/10 11:07	(a)	4.4	2.1	8
10C-T3R1-P1	10C-E05-T3R1-P1-AS	5/12/10 12:11	(a)	4.6	2.1	7
10C-T3R1-P1	10C-E06-T3R1-P1-AS	5/12/10 13:19	(a)	4.9	1.7	6
10C-T3R1-P1	10C-E07-T3R1-P1-AS	11/4/10 8:36	(a)	5.96	3.5	22
10C-T3R1-P1	10C-E08-T3R1-P1-AS	11/4/10 9:45	(a)	6.46	4.2	26
10C-T3R1-P1	10C-E09-T3R1-P1-AS	11/4/10 10:45	(a)	9.47	3.5	19
10C-T3R1-P1	10C-E09-T3R1-P1-AT	11/4/10 10:45	(a)	9.05	3.8	20
10C-T3R1-P1	10C-E10-T3R1-P1-AS	11/4/10 11:35	(a)	8.89	6	41
10C-T3R1-P1	10C-E11-T3R1-P1-AS	11/4/10 12:30	(a)	6.8	9.3	80
10C-T3R1-P1	10C-E12-T3R1-P1-AS	11/4/10 13:22	(a)	8.57	11.9	85
10C-TSR2-P1	10C-E01-TSR2-P1-AS	5/12/10 7:30	(a)	4.3	3.4	22
10C-TSR2-P1	10C-E02-TSR2-P1-AS	5/12/10 8:50	(a)	4.3	3.9	25
10C-TSR2-P1	10C-E03-TSR2-P1-AS	5/12/10 9:50	(a)	4.3	4.0	23
10C-TSR2-P1	10C-E03-TSR2-P1-AT	5/12/10 9:50	(a)	4.5	3.5	20
10C-TSR2-P1	10C-E04-TSR2-P1-AS	5/12/10 10:38	(a)	5.3	3.5	22
10C-TSR2-P1	10C-E05-TSR2-P1-AS	5/12/10 11:22	(a)	5.3	3.6	21
10C-TSR2-P1	10C-E06-TSR2-P1-AS	5/12/10 12:10	(a)	4.4	3.5	21
10C-TSR2-P1	10C-E07-TSR2-P1-AS	11/4/10 8:06	(a)	6.4	2.3	12
10C-TSR2-P1	10C-E08-TSR2-P1-AS	11/4/10 9:19	(a)	6.79	4.2	25
10C-TSR2-P1	10C-E09-TSR2-P1-AS	11/4/10 10:22	(a)	6.22	3.7	34 J
10C-TSR2-P1	10C-E09-TSR2-P1-AT	11/4/10 10:22	(a)	6.45	3.2 J	25 J
10C-TSR2-P1	10C-E10-TSR2-P1-AS	11/4/10 11:25	(a)	6.6	3.9 J	28
10C-TSR2-P1	10C-E11-TSR2-P1-AS	11/4/10 12:23	(a)	6.34	4.2 J	36
10C-TSR2-P1	10C-E12-TSR2-P1-AS	11/4/10 13:26	(a)	6.13	5.7 J	42 J
Spring 2010 NBSA Boat Survey						
N01-E01-TARK-P1	N01-E01-TARK-P1-AS	3/19/10 13:20	3			7
N01-E01-TARK-P1	N01-E01-TARK-P1-BS	3/19/10 13:14	39			11
N01-E01-THKN-P1	N01-E01-THKN-P1-AS	3/21/10 10:17	3			10
N01-E01-THKN-P1	N01-E01-THKN-P1-BS	3/21/10 10:14	34			24
N01-E01-TKVK-P1	N01-E01-TKVK-P1-AS	3/19/10 12:49	3			8
N01-E01-TKVK-P1	N01-E01-TKVK-P1-BS	3/19/10 12:47	49			11
N01-E01-TNBN-P1	N01-E01-TNBN-P1-AS	3/20/10 12:34	3			7
N01-E01-TNBN-P1	N01-E01-TNBN-P1-BS	3/20/10 12:30	29			8
N01-E01-TNBS-P1	N01-E01-TNBS-P1-AS	3/20/10 12:00	3			7
N01-E01-TNBS-P1	N01-E01-TNBS-P1-BS	3/20/10 11:55	49			12
N01-E01-TNBS-P1	N01-E01-TNBS-P1-BT	3/20/10 11:56	49			12
N01-E03-TARK-P1	N01-E03-TARK-P1-AS	3/25/10 10:07	3	3.5	1.0 UJ	11 J
N01-E03-TARK-P1	N01-E03-TARK-P1-BS	3/25/10 10:03	31	2.5	1.3 J	11 J
N01-E03-TARK-P2	N01-E03-TARK-P2-AS	3/25/10 10:20	3			14 J
N01-E03-TARK-P2	N01-E03-TARK-P2-BS	3/25/10 10:18	42			12 J
N01-E03-TARK-P3	N01-E03-TARK-P3-AS	3/25/10 10:34	3	3.1	1.0 J	7 J
N01-E03-TARK-P3	N01-E03-TARK-P3-BS	3/25/10 10:32	40	3.2	1.0 UJ	7 J
N01-E03-THKN-P1	N01-E03-THKN-P1-AS	3/25/10 6:51	3	3.3	1.4 J	13 J
N01-E03-THKN-P1	N01-E03-THKN-P1-BS	3/25/10 6:48	34	3.0	1.6 J	20 J
N01-E03-THKN-P2	N01-E03-THKN-P2-AS	3/25/10 7:06	3			16 J
N01-E03-THKN-P2	N01-E03-THKN-P2-BS	3/25/10 7:03	30			20 J

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
N01-E03-THKN-P3	N01-E03-THKN-P3-AS	3/25/10 7:15	3	3.2	1.5 J	15 J
N01-E03-THKN-P3	N01-E03-THKN-P3-BS	3/25/10 7:13	26	3.2	1.8 J	18 J
N01-E03-TKVK-P1	N01-E03-TKVK-P1-AS	3/25/10 9:13	3	2.9	1.0 UJ	9 J
N01-E03-TKVK-P1	N01-E03-TKVK-P1-BS	3/25/10 9:09	37	2.2	1.0 UJ	11 J
N01-E03-TKVK-P1	N01-E03-TKVK-P1-BT	3/25/10 9:10	37	2.3	1.0 UJ	
N01-E03-TKVK-P2	N01-E03-TKVK-P2-AS	3/25/10 9:22	3			11 J
N01-E03-TKVK-P2	N01-E03-TKVK-P2-BS	3/25/10 9:21	46			9 J
N01-E03-TKVK-P3	N01-E03-TKVK-P3-AS	3/25/10 9:33	3	1.9	1.0 UJ	14 J
N01-E03-TKVK-P3	N01-E03-TKVK-P3-BS	3/25/10 9:31	52	2.3	1.0 J	9 J
N01-E03-TNBN-P1	N01-E03-TNBN-P1-AS	3/25/10 7:04	3	3.8	1.8 J	20 J
N01-E03-TNBN-P1	N01-E03-TNBN-P1-BS	3/25/10 7:01	19	3.2	1.6 J	15 J
N01-E03-TNBN-P2	N01-E03-TNBN-P2-AS	3/25/10 7:16	3			13 J
N01-E03-TNBN-P2	N01-E03-TNBN-P2-BS	3/25/10 7:14	8			17 J
N01-E03-TNBN-P3	N01-E03-TNBN-P3-AS	3/25/10 7:27	3	4.0	1.5 J	11 J
N01-E03-TNBN-P3	N01-E03-TNBN-P3-BS	3/25/10 7:24	6	3.8	1.3 J	14 J
N01-E03-TNBS-P1	N01-E03-TNBS-P1-AS	3/25/10 8:11	3	3.4	1.1 J	7 J
N01-E03-TNBS-P1	N01-E03-TNBS-P1-BS	3/25/10 8:07	47	1.7	1.0 UJ	8 J
N01-E03-TNBS-P2	N01-E03-TNBS-P2-AS	3/25/10 8:25	3			13 J
N01-E03-TNBS-P2	N01-E03-TNBS-P2-BS	3/25/10 8:23	47			13 J
N01-E03-TNBS-P3	N01-E03-TNBS-P3-AS	3/25/10 8:39	3	4.1	1.0 UJ	7 J
N01-E03-TNBS-P3	N01-E03-TNBS-P3-BS	3/25/10 8:37	9	2.6	1.0 UJ	7 J
N01-E03-TNBS-P3	N01-E03-TNBS-P3-BT	3/25/10 8:37	9			8 J
N01-E04-TARK-P1	N01-E04-TARK-P1-AS	3/25/10 15:52	3	3.0	1.0 J	6 J
N01-E04-TARK-P1	N01-E04-TARK-P1-BS	3/25/10 15:50	34	2.1	1.3 J	9 J
N01-E04-TARK-P2	N01-E04-TARK-P2-AS	3/25/10 16:01	3			7 J
N01-E04-TARK-P2	N01-E04-TARK-P2-BS	3/25/10 15:59	47			7 J
N01-E04-TARK-P3	N01-E04-TARK-P3-AS	3/25/10 16:10	3	2.1	1.1 J	11 J
N01-E04-TARK-P3	N01-E04-TARK-P3-BS	3/25/10 16:08	42	1.9	1.3 J	8 J
N01-E04-THKN-P1	N01-E04-THKN-P1-AS	3/25/10 12:56	3	4.3	1.4 J	9 J
N01-E04-THKN-P1	N01-E04-THKN-P1-BS	3/25/10 12:53	31	3.9	2.0 J	18 J
N01-E04-THKN-P2	N01-E04-THKN-P2-AS	3/25/10 13:10	3			10 J
N01-E04-THKN-P2	N01-E04-THKN-P2-BS	3/25/10 13:08	28			33 J
N01-E04-THKN-P3	N01-E04-THKN-P3-AS	3/25/10 13:20	3	4.4	1.4 J	9 J
N01-E04-THKN-P3	N01-E04-THKN-P3-BS	3/25/10 13:18	22	4.5	1.4 J	14 J
N01-E04-TKVK-P1	N01-E04-TKVK-P1-AS	3/25/10 14:54	3	2.4	1.1 J	9 J
N01-E04-TKVK-P1	N01-E04-TKVK-P1-BS	3/25/10 14:51	42	1.9	2.2 J	43 J
N01-E04-TKVK-P1	N01-E04-TKVK-P1-BT	3/25/10 14:52	42	1.9	1.6 J	
N01-E04-TKVK-P2	N01-E04-TKVK-P2-AS	3/25/10 15:18	52	2.4	1.2 J	34 J
N01-E04-TKVK-P2	N01-E04-TKVK-P2-BS	3/25/10 15:16	52			12 J
N01-E04-TKVK-P3	N01-E04-TKVK-P3-AS	3/25/10 15:28	3			10 J
N01-E04-TKVK-P3	N01-E04-TKVK-P3-BS	3/25/10 15:26	46	1.7	1.4 J	10 J
N01-E04-TNBN-P1	N01-E04-TNBN-P1-AS	3/25/10 13:02	3	3.2	1.1 J	9 J
N01-E04-TNBN-P1	N01-E04-TNBN-P1-BS	3/25/10 12:59	27	2.5	1.0 UJ	8 J
N01-E04-TNBN-P2	N01-E04-TNBN-P2-AS	3/25/10 13:12	3			7 J
N01-E04-TNBN-P2	N01-E04-TNBN-P2-BS	3/25/10 13:11	6			8 J
N01-E04-TNBN-P3	N01-E04-TNBN-P3-AS	3/25/10 13:23	3	3.3	1.1 J	7 J
N01-E04-TNBN-P3	N01-E04-TNBN-P3-BS	3/25/10 13:21	5	3.9	1.0 J	8 J
N01-E04-TNBS-P1	N01-E04-TNBS-P1-AS	3/25/10 14:07	3	3.6	1.0 J	6 J
N01-E04-TNBS-P1	N01-E04-TNBS-P1-BS	3/25/10 14:04	43	3.1	1.0 J	25 J
N01-E04-TNBS-P2	N01-E04-TNBS-P2-AS	3/25/10 14:19	3			7 J
N01-E04-TNBS-P2	N01-E04-TNBS-P2-BS	3/25/10 14:17	46			18 J
N01-E04-TNBS-P2	N01-E04-TNBS-P2-BT	3/25/10 14:18	46			12 J
N01-E04-TNBS-P3	N01-E04-TNBS-P3-AS	3/25/10 14:29	3	3.4	1.0 J	7 J
N01-E04-TNBS-P3	N01-E04-TNBS-P3-BS	3/25/10 14:27	10	3.1	1.1 J	7 J
N01-E04-TNBS-P3	N01-E04-TNBS-P3-BT	3/25/10 14:28	10			7 J
N01-E05-TARK-P1	N01-E05-TARK-P1-AS	4/29/10 9:05	3			9
N01-E05-TARK-P1	N01-E05-TARK-P1-BS	4/29/10 9:03	38			14
N01-E05-THKN-P1	N01-E05-THKN-P1-AS	4/29/10 0:45	3			36
N01-E05-THKN-P1	N01-E05-THKN-P1-BS	4/29/10 0:43	33			23
N01-E05-TKVK-P1	N01-E05-TKVK-P1-AS	4/30/10 8:57	3			51
N01-E05-TKVK-P1	N01-E05-TKVK-P1-BS	4/30/10 8:55	45			81
N01-E05-TNBN-P1	N01-E05-TNBN-P1-AS	4/28/10 0:42	3			14
N01-E05-TNBN-P1	N01-E05-TNBN-P1-AT	4/28/10 0:42	3			16
N01-E05-TNBN-P1	N01-E05-TNBN-P1-BS	4/28/10 0:37	26			91
N01-E05-TNBS-P1	N01-E05-TNBS-P1-AS	4/30/10 11:34	3			11
N01-E05-TNBS-P1	N01-E05-TNBS-P1-BS	4/30/10 11:32	48			19
N01-E07-TARK-P1	N01-E07-TARK-P1-AS	5/3/10 11:32	3	3.3	2.0 J	8
N01-E07-TARK-P1	N01-E07-TARK-P1-BS	5/3/10 11:29	37	3.0	1.2 J	16
N01-E07-TARK-P2	N01-E07-TARK-P2-AS	5/3/10 11:48	3			24

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
N01-E07-TARK-P2	N01-E07-TARK-P2-BS	5/3/10 11:44	45.3			7
N01-E07-TARK-P3	N01-E07-TARK-P3-AS	5/3/10 0:03	3	2.7	1.3 J	13
N01-E07-TARK-P3	N01-E07-TARK-P3-BS	5/3/10 0:01	43.2	2.2	1.4 J	17
N01-E07-THKN-P1	N01-E07-THKN-P1-AS	5/3/10 8:43	3	4.5	1.8 J	16
N01-E07-THKN-P1	N01-E07-THKN-P1-BS	5/3/10 8:40	26	4.3	2.1 J	26
N01-E07-THKN-P2	N01-E07-THKN-P2-AS	5/3/10 8:51	3			24
N01-E07-THKN-P2	N01-E07-THKN-P2-BS	5/3/10 8:50	25			17
N01-E07-THKN-P3	N01-E07-THKN-P3-AS	5/3/10 8:59	3	3.5	2.0 J	39
N01-E07-THKN-P3	N01-E07-THKN-P3-BS	5/3/10 8:58	20	8.9	3.4 J	19
N01-E07-TKVK-P1	N01-E07-TKVK-P1-AS	5/3/10 10:42	3	3.0	2.0 J	18
N01-E07-TKVK-P1	N01-E07-TKVK-P1-BS	5/3/10 10:40	42	2.0	1.8 J	16
N01-E07-TKVK-P2	N01-E07-TKVK-P2-AS	5/3/10 10:51	3			22
N01-E07-TKVK-P2	N01-E07-TKVK-P2-BS	5/3/10 10:50	54			10
N01-E07-TKVK-P3	N01-E07-TKVK-P3-AS	5/3/10 11:08	3	5.2	1.4 J	23
N01-E07-TKVK-P3	N01-E07-TKVK-P3-BS	5/3/10 11:07	54.3	1.9	1.9 J	17
N01-E07-TNBN-P1	N01-E07-TNBN-P1-AS	5/3/10 8:43	3	3.5	1.5 J	12
N01-E07-TNBN-P1	N01-E07-TNBN-P1-BS	5/3/10 8:40	28.2	2.3	2.6 J	31
N01-E07-TNBN-P1	N01-E07-TNBN-P1-BT	5/3/10 8:42	28.2			34
N01-E07-TNBN-P2	N01-E07-TNBN-P2-AS	5/3/10 8:57	3			10
N01-E07-TNBN-P2	N01-E07-TNBN-P2-BS	5/3/10 8:55	6.3			12
N01-E07-TNBN-P3	N01-E07-TNBN-P3-AS	5/3/10 9:08	3	3.3	1.4 J	8
N01-E07-TNBN-P3	N01-E07-TNBN-P3-AT	5/3/10 9:11	3	3.2	1.3 J	
N01-E07-TNBN-P3	N01-E07-TNBN-P3-BS	5/3/10 9:06	5.6	3.2	1.3 J	10
N01-E07-TNBS-P1	N01-E07-TNBS-P1-AS	5/3/10 9:55	3	2.8	1.5 J	48
N01-E07-TNBS-P1	N01-E07-TNBS-P1-BS	5/3/10 9:51	47.2	2.0	3.1 J	59
N01-E07-TNBS-P2	N01-E07-TNBS-P2-AS	5/3/10 10:21	3			30
N01-E07-TNBS-P2	N01-E07-TNBS-P2-BS	5/3/10 10:19	49.4			30
N01-E07-TNBS-P3	N01-E07-TNBS-P3-AS	5/3/10 10:09	3	2.9	1.2 J	8
N01-E07-TNBS-P3	N01-E07-TNBS-P3-BS	5/3/10 10:07	10.5	2.6	1.3 J	8
N01-E08-TARK-P1	N01-E08-TARK-P1-AS	5/3/10 17:06	3	2.5	1.5 J	9
N01-E08-TARK-P1	N01-E08-TARK-P1-BS	5/3/10 17:04	33	2.1	1.6 J	9
N01-E08-TARK-P2	N01-E08-TARK-P2-AS	5/3/10 17:18	3			11
N01-E08-TARK-P2	N01-E08-TARK-P2-BS	5/3/10 17:17	43			19
N01-E08-TARK-P3	N01-E08-TARK-P3-AS	5/3/10 17:29	3	3.8	1.6 J	8
N01-E08-TARK-P3	N01-E08-TARK-P3-AT	5/3/10 17:30	3			9
N01-E08-TARK-P3	N01-E08-TARK-P3-BS	5/3/10 17:26	40.4	1.8	2.1 J	27
N01-E08-THKN-P1	N01-E08-THKN-P1-AS	5/3/10 14:41	3	3.8	1.8 J	8
N01-E08-THKN-P1	N01-E08-THKN-P1-BS	5/3/10 14:36	32	2.6	1.6 J	16
N01-E08-THKN-P2	N01-E08-THKN-P2-AS	5/3/10 14:50	3			12
N01-E08-THKN-P2	N01-E08-THKN-P2-BS	5/3/10 14:49	22			11
N01-E08-THKN-P3	N01-E08-THKN-P3-AS	5/3/10 15:20	3	4.3	2.3 J	14
N01-E08-THKN-P3	N01-E08-THKN-P3-BS	5/3/10 15:17	21	3.0	1.6 J	16
N01-E08-TKVK-P1	N01-E08-TKVK-P1-AS	5/3/10 16:17	3	3.8	1.7 J	9
N01-E08-TKVK-P1	N01-E08-TKVK-P1-BS	5/3/10 16:13	43.5	2.1 J	1.5 J	12
N01-E08-TKVK-P1	N01-E08-TKVK-P1-BT	5/3/10 16:14	43.5	1.6 J	1.4 J	
N01-E08-TKVK-P2	N01-E08-TKVK-P2-AS	5/3/10 16:28	3			11
N01-E08-TKVK-P2	N01-E08-TKVK-P2-BS	5/3/10 16:26	53.2			14
N01-E08-TKVK-P3	N01-E08-TKVK-P3-AS	5/3/10 16:43	3	5.1	1.3 J	8
N01-E08-TKVK-P3	N01-E08-TKVK-P3-BS	5/3/10 16:41	52.6	2.5	1.6 J	12
N01-E08-TNBN-P1	N01-E08-TNBN-P1-AS	5/3/10 14:24	3	3.0	1.5 J	9
N01-E08-TNBN-P1	N01-E08-TNBN-P1-BS	5/3/10 14:22	30.3	2.4	1.5 J	11
N01-E08-TNBN-P2	N01-E08-TNBN-P2-AS	5/3/10 14:34	3			7
N01-E08-TNBN-P2	N01-E08-TNBN-P2-BS	5/3/10 14:32	8			9
N01-E08-TNBN-P3	N01-E08-TNBN-P3-AS	5/3/10 14:45	3	0.57	1.4 J	7
N01-E08-TNBN-P3	N01-E08-TNBN-P3-BS	5/3/10 14:43	6.8	3.0	1.4 J	28
N01-E08-TNBS-P1	N01-E08-TNBS-P1-AS	5/3/10 15:25	3	2.4	1.4 J	10
N01-E08-TNBS-P1	N01-E08-TNBS-P1-BS	5/3/10 15:23	45	1.8	1.5 J	11
N01-E08-TNBS-P2	N01-E08-TNBS-P2-AS	5/3/10 15:38	3			12
N01-E08-TNBS-P2	N01-E08-TNBS-P2-BS	5/3/10 15:37	48.6			13
N01-E08-TNBS-P3	N01-E08-TNBS-P3-AS	5/3/10 15:49	3	2.4	1.4 J	11
N01-E08-TNBS-P3	N01-E08-TNBS-P3-BS	5/3/10 15:47	11	4.7	1.5 J	9
N01-E09-TARK-P1	N01-E09-TARK-P1-AS	4/29/10 11:48	3			30 J
N01-E09-TARK-P1	N01-E09-TARK-P1-AT	4/29/10 11:48	3			8 J
N01-E09-TARK-P1	N01-E09-TARK-P1-BS	4/29/10 11:46	41			49
N01-E09-THKN-P1	N01-E09-THKN-P1-AS	4/29/10 15:46	3			53
N01-E09-THKN-P1	N01-E09-THKN-P1-BS	4/29/10 15:44	29			47
N01-E09-TKVK-P1	N01-E09-TKVK-P1-AS	4/30/10 11:18	3			17
N01-E09-TKVK-P1	N01-E09-TKVK-P1-BS	4/30/10 11:16	46			27
N01-E09-TNBN-P1	N01-E09-TNBN-P1-AS	4/28/10 14:54	3			25

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
N01-E09-TNBN-P1	N01-E09-TNBN-P1-BS	4/28/10 14:51	27			36
N01-E09-TNBS-P1	N01-E09-TNBS-P1-AS	4/30/10 14:39	3			11
N01-E09-TNBS-P1	N01-E09-TNBS-P1-BS	4/30/10 14:38	45			14
N01-E10-TARK-P1	N01-E10-TARK-P1-AS	5/21/10 8:57	3			11 J
N01-E10-TARK-P1	N01-E10-TARK-P1-BS	5/21/10 8:55	39.5			10 J
N01-E10-THKN-P1	N01-E10-THKN-P1-AS	5/23/10 10:53	3			23 J
N01-E10-THKN-P1	N01-E10-THKN-P1-BS	5/23/10 10:51	30			6 J
N01-E10-TKVK-P1	N01-E10-TKVK-P1-AS	5/22/10 8:56	3			10 J
N01-E10-TKVK-P1	N01-E10-TKVK-P1-BS	5/22/10 8:54	41.5			6 J
N01-E10-TNBN-P1	N01-E10-TNBN-P1-AS	5/22/10 11:58	3			19 J
N01-E10-TNBN-P1	N01-E10-TNBN-P1-BS	5/22/10 11:57	29			8 J
N01-E10-TNBS-P1	N01-E10-TNBS-P1-AS	5/21/10 11:43	3			9 J
N01-E10-TNBS-P1	N01-E10-TNBS-P1-AT	5/21/10 11:43	3			9 J
N01-E10-TNBS-P1	N01-E10-TNBS-P1-BS	5/21/10 11:41	47			53 J
N01-E12-TARK-P1	N01-E12-TARK-P1-AS	5/24/10 9:32	3	2.4 J	1.5 J	9 J
N01-E12-TARK-P1	N01-E12-TARK-P1-BS	5/24/10 9:31	33	2.9 J	1.4 J	11 J
N01-E12-TARK-P2	N01-E12-TARK-P2-AS	5/24/10 9:38	3			8 J
N01-E12-TARK-P2	N01-E12-TARK-P2-BS	5/24/10 9:37	43			14 J
N01-E12-TARK-P3	N01-E12-TARK-P3-AS	5/24/10 9:45	3	3.1 J	1.3	10 J
N01-E12-TARK-P3	N01-E12-TARK-P3-BS	5/24/10 9:43	39.5	2.2 J	1.7 J	24 J
N01-E12-THKN-P1	N01-E12-THKN-P1-AS	5/24/10 7:28	3	3.3 J	1.9	10 J
N01-E12-THKN-P1	N01-E12-THKN-P1-BS	5/24/10 7:22	32	2.4 J	1.8	18 J
N01-E12-THKN-P2	N01-E12-THKN-P2-AS	5/24/10 7:41	3			11 J
N01-E12-THKN-P2	N01-E12-THKN-P2-BS	5/24/10 7:39	33			19 J
N01-E12-THKN-P3	N01-E12-THKN-P3-AS	5/24/10 7:51	3	3.6 J	1.6	14 J
N01-E12-THKN-P3	N01-E12-THKN-P3-BS	5/24/10 7:49	23	3.3 J	1.8	17 J
N01-E12-TKVK-P1	N01-E12-TKVK-P1-AS	5/24/10 8:51	3	3.2 J	1.4 J	10 J
N01-E12-TKVK-P1	N01-E12-TKVK-P1-BS	5/24/10 8:48	44	3.2 J	1.9 J	25 J
N01-E12-TKVK-P2	N01-E12-TKVK-P2-AS	5/24/10 9:04	3			10 J
N01-E12-TKVK-P2	N01-E12-TKVK-P2-BS	5/24/10 9:02	53			22 J
N01-E12-TKVK-P3	N01-E12-TKVK-P3-AS	5/24/10 9:10	3	2.2 J	1.4 J	18 J
N01-E12-TKVK-P3	N01-E12-TKVK-P3-AT	5/24/10 9:11	3	3.2 J	1.4 J	
N01-E12-TKVK-P3	N01-E12-TKVK-P3-BS	5/24/10 9:09	52	2.1 J	1.5 J	16 J
N01-E12-TNBN-P1	N01-E12-TNBN-P1-AS	5/24/10 7:18	3	3.0 J	1.4 J	9 J
N01-E12-TNBN-P1	N01-E12-TNBN-P1-AT	5/24/10 7:18	3			9 J
N01-E12-TNBN-P1	N01-E12-TNBN-P1-BS	5/24/10 7:16	23	2.7 J	1.5 J	13 J
N01-E12-TNBN-P2	N01-E12-TNBN-P2-AS	5/24/10 7:26	3			8 J
N01-E12-TNBN-P2	N01-E12-TNBN-P2-BS	5/24/10 7:24	7			9 J
N01-E12-TNBN-P3	N01-E12-TNBN-P3-AS	5/24/10 7:34	3	2.1 J	1.3 J	10 J
N01-E12-TNBN-P3	N01-E12-TNBN-P3-BS	5/24/10 7:33	6.5	2.3 J	1.3 J	10 J
N01-E12-TNBS-P1	N01-E12-TNBS-P1-AS	5/24/10 8:13	3	2.1 J	1.2 J	8 J
N01-E12-TNBS-P1	N01-E12-TNBS-P1-BS	5/24/10 8:10	47	2.2 J	1.4 J	12 J
N01-E12-TNBS-P2	N01-E12-TNBS-P2-AS	5/24/10 8:21	3			8 J
N01-E12-TNBS-P2	N01-E12-TNBS-P2-BS	5/24/10 8:19	49			15 J
N01-E12-TNBS-P3	N01-E12-TNBS-P3-AS	5/24/10 8:30	3	3.2 J	1.3 J	9 J
N01-E12-TNBS-P3	N01-E12-TNBS-P3-BS	5/24/10 8:29	11	2.2 J	1.7 J	14 J
N01-E13-TARK-P1	N01-E13-TARK-P1-AS	5/24/10 15:45	3	2.4 J	1.0 U	11 J
N01-E13-TARK-P1	N01-E13-TARK-P1-BS	5/24/10 15:43	37	2.9 J	1.0 U	14 J
N01-E13-TARK-P2	N01-E13-TARK-P2-AS	5/24/10 15:54	3			10 J
N01-E13-TARK-P2	N01-E13-TARK-P2-BS	5/24/10 15:52	45.5			16 J
N01-E13-TARK-P3	N01-E13-TARK-P3-AS	5/24/10 16:00	3	2.8 J	2.1	11 J
N01-E13-TARK-P3	N01-E13-TARK-P3-BS	5/24/10 15:58	44.5	3.2 J	2.2	11 J
N01-E13-THKN-P1	N01-E13-THKN-P1-AS	5/24/10 14:10	3	4.3 J	1.5	14 J
N01-E13-THKN-P1	N01-E13-THKN-P1-BS	5/24/10 14:09	27	4.3 J	1.6	19 J
N01-E13-THKN-P2	N01-E13-THKN-P2-AS	5/24/10 14:18	3			14 J
N01-E13-THKN-P2	N01-E13-THKN-P2-BS	5/24/10 14:17	25			37 J
N01-E13-THKN-P3	N01-E13-THKN-P3-AS	5/24/10 14:23	3	4.3 J	1.2	16 J
N01-E13-THKN-P3	N01-E13-THKN-P3-BS	5/24/10 14:22	21	3.9 J	2.5	26 J
N01-E13-TKVK-P1	N01-E13-TKVK-P1-AS	5/24/10 15:06	3	3.2 J	1.0	17 J
N01-E13-TKVK-P1	N01-E13-TKVK-P1-BS	5/24/10 15:04	38	1.9 J	1.0 U	20 J
N01-E13-TKVK-P2	N01-E13-TKVK-P2-AS	5/24/10 15:19	3			22 J
N01-E13-TKVK-P2	N01-E13-TKVK-P2-BS	5/24/10 15:17	53.5			38 J
N01-E13-TKVK-P3	N01-E13-TKVK-P3-AS	5/24/10 15:25	3	3.0 J	1.0	16 J
N01-E13-TKVK-P3	N01-E13-TKVK-P3-AT	5/24/10 15:25	3			16 J
N01-E13-TKVK-P3	N01-E13-TKVK-P3-BS	5/24/10 15:23	53	2.0 J	1.1	18 J
N01-E13-TNBN-P1	N01-E13-TNBN-P1-AS	5/24/10 13:40	3	4.3 J	1.3	18 J
N01-E13-TNBN-P1	N01-E13-TNBN-P1-BS	5/24/10 13:39	25	2.1 J	2.4	31 J
N01-E13-TNBN-P2	N01-E13-TNBN-P2-AS	5/24/10 13:48	3			12 J
N01-E13-TNBN-P2	N01-E13-TNBN-P2-BS	5/24/10 13:47	4.5			12 J

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
N01-E13-TNBN-P2	N01-E13-TNBN-P2-BT	5/24/10 13:47	4.5			12 J
N01-E13-TNBN-P3	N01-E13-TNBN-P3-AS	5/24/10 13:56	3	4.1 J	1.4	12 J
N01-E13-TNBN-P3	N01-E13-TNBN-P3-BS	5/24/10 13:55	3.5	3.8 J	1.5	12 J
N01-E13-TNBS-P1	N01-E13-TNBS-P1-AS	5/24/10 14:29	3	2.4 J	1.2	12 J
N01-E13-TNBS-P1	N01-E13-TNBS-P1-AT	5/24/10 14:29	3	2.5 J	1.3	
N01-E13-TNBS-P1	N01-E13-TNBS-P1-BS	5/24/10 14:27	45.5	2.4 J	1.8	18 J
N01-E13-TNBS-P2	N01-E13-TNBS-P2-AS	5/24/10 14:36	3			11 J
N01-E13-TNBS-P2	N01-E13-TNBS-P2-BS	5/24/10 14:35	48			12 J
N01-E13-TNBS-P3	N01-E13-TNBS-P3-AS	5/24/10 14:43	3	3.6 J	1.1	11 J
N01-E13-TNBS-P3	N01-E13-TNBS-P3-BS	5/24/10 14:41	11	2.3 J	1.0 U	10 J
N01-E14-TARK-P1	N01-E14-TARK-P1-AS	5/21/10 11:27	3			10 J
N01-E14-TARK-P1	N01-E14-TARK-P1-BS	5/21/10 11:25	37			15 J
N01-E14-THKN-P1	N01-E14-THKN-P1-AS	5/23/10 0:48	3			17 J
N01-E14-THKN-P1	N01-E14-THKN-P1-BS	5/23/10 0:47	30.5			27 J
N01-E14-TKVK-P1	N01-E14-TKVK-P1-AS	5/22/10 11:24	3			8 J
N01-E14-TKVK-P1	N01-E14-TKVK-P1-BS	5/22/10 11:22	40			8 J
N01-E14-TNBN-P1	N01-E14-TNBN-P1-AS	5/22/10 14:04	3			13 J
N01-E14-TNBN-P1	N01-E14-TNBN-P1-BS	5/22/10 14:03	34			13 J
N01-E14-TNBS-P1	N01-E14-TNBS-P1-AS	5/21/10 14:06	3			12 J
N01-E14-TNBS-P1	N01-E14-TNBS-P1-BS	5/21/10 14:04	46			7 J
N01-E15-TARK-P1	N01-E15-TARK-P1-AS	6/19/10 8:47	3			6 J
N01-E15-TARK-P1	N01-E15-TARK-P1-BS	6/19/10 8:46	28.7			9 J
N01-E15-THKN-P1	N01-E15-THKN-P1-AS	6/21/10 10:17	3			11 J
N01-E15-THKN-P1	N01-E15-THKN-P1-BS	6/21/10 10:15	30.1			15 J
N01-E15-TKVK-P1	N01-E15-TKVK-P1-AS	6/20/10 8:37	3			3 J
N01-E15-TKVK-P1	N01-E15-TKVK-P1-BS	6/20/10 8:36	40.1			4 J
N01-E15-TNBN-P1	N01-E15-TNBN-P1-AS	6/20/10 0:04	3			13 J
N01-E15-TNBN-P1	N01-E15-TNBN-P1-BS	6/20/10 0:02	24.8			91
N01-E15-TNBS-P1	N01-E15-TNBS-P1-AS	6/19/10 11:44	3			7 J
N01-E15-TNBS-P1	N01-E15-TNBS-P1-AT	6/19/10 11:44	3			7 J
N01-E15-TNBS-P1	N01-E15-TNBS-P1-BS	6/19/10 11:42	41			6 J
N01-E17-TARK-P1	N01-E17-TARK-P1-AS	6/22/10 9:28	3	2.4 J	1.0 U	7 J
N01-E17-TARK-P1	N01-E17-TARK-P1-BS	6/22/10 9:27	34	2.5 J	1.0	6 J
N01-E17-TARK-P2	N01-E17-TARK-P2-AS	6/22/10 9:34	3			5 J
N01-E17-TARK-P2	N01-E17-TARK-P2-BS	6/22/10 9:33	44			4 J
N01-E17-TARK-P3	N01-E17-TARK-P3-AS	6/22/10 9:40	3	2.5 J	1.0 U	4 J
N01-E17-TARK-P3	N01-E17-TARK-P3-BS	6/22/10 9:38	41	2.6 J	1.2	5 J
N01-E17-THKN-P1	N01-E17-THKN-P1-AS	6/22/10 7:23	3	3.3 J	1.0 U	14 J
N01-E17-THKN-P1	N01-E17-THKN-P1-BS	6/22/10 7:20	28	2.8 J	1.0 U	9 J
N01-E17-THKN-P2	N01-E17-THKN-P2-AS	6/22/10 7:35	3			10 J
N01-E17-THKN-P2	N01-E17-THKN-P2-BS	6/22/10 7:33	32			8 J
N01-E17-THKN-P3	N01-E17-THKN-P3-AS	6/22/10 7:43	3	2.1 J	1.0 U	9 J
N01-E17-THKN-P3	N01-E17-THKN-P3-AT	6/22/10 7:44	3	2.2 J	1.1	
N01-E17-THKN-P3	N01-E17-THKN-P3-BS	6/22/10 7:42	21	2.3 J	1.0 U	8 J
N01-E17-TKVK-P1	N01-E17-TKVK-P1-AS	6/22/10 8:55	3	2.4 J	1.0 U	6 J
N01-E17-TKVK-P1	N01-E17-TKVK-P1-BS	6/22/10 8:52	46	2.0 J	1.0 U	10 J
N01-E17-TKVK-P2	N01-E17-TKVK-P2-AS	6/22/10 9:01	3			5 J
N01-E17-TKVK-P2	N01-E17-TKVK-P2-BS	6/22/10 8:59	53			6 J
N01-E17-TKVK-P3	N01-E17-TKVK-P3-AS	6/22/10 9:08	3	2.2 J	1.0 U	5 J
N01-E17-TKVK-P3	N01-E17-TKVK-P3-BS	6/22/10 9:06	51	2.3 J	1.0	7 J
N01-E17-TNBN-P1	N01-E17-TNBN-P1-AS	6/22/10 7:04	3	2.4 J	1.0 U	4 J
N01-E17-TNBN-P1	N01-E17-TNBN-P1-BS	6/22/10 7:02	35	2.4 J	1.0 U	6 J
N01-E17-TNBN-P2	N01-E17-TNBN-P2-AS	6/22/10 7:19	3			5 J
N01-E17-TNBN-P2	N01-E17-TNBN-P2-BS	6/22/10 7:19	8			4 J
N01-E17-TNBN-P3	N01-E17-TNBN-P3-AS	6/22/10 7:29	3	2.6 J	1.0 U	6 J
N01-E17-TNBN-P3	N01-E17-TNBN-P3-BS	6/22/10 7:28	7	2.6 J	1.0 U	4 J
N01-E17-TNBS-P1	N01-E17-TNBS-P1-AS	6/22/10 8:13	3	0.76 J	1.0 U	3 J
N01-E17-TNBS-P1	N01-E17-TNBS-P1-BS	6/22/10 8:10	45	0.62 J	1.0 U	8 J
N01-E17-TNBS-P2	N01-E17-TNBS-P2-AS	6/22/10 8:19	3			4 J
N01-E17-TNBS-P2	N01-E17-TNBS-P2-BS	6/22/10 8:18	49			4 J
N01-E17-TNBS-P3	N01-E17-TNBS-P3-AS	6/22/10 8:26	3	0.91 J	1.0 U	7 J
N01-E17-TNBS-P3	N01-E17-TNBS-P3-BS	6/22/10 8:25	10	0.98 J	1.0 U	3 J
N01-E17-TNBS-P3	N01-E17-TNBS-P3-BT	6/22/10 8:25	10			8 J
N01-E18-TARK-P1	N01-E18-TARK-P1-AS	6/22/10 15:36	3	2.4 J	1.0 U	4 J
N01-E18-TARK-P1	N01-E18-TARK-P1-BS	6/22/10 15:34	35	2.9 J	1.0 U	4 J
N01-E18-TARK-P1	N01-E18-TARK-P1-BT	6/22/10 15:34	35			4 J
N01-E18-TARK-P2	N01-E18-TARK-P2-AS	6/22/10 15:42	3			3 J
N01-E18-TARK-P2	N01-E18-TARK-P2-BS	6/22/10 15:40	47			6 J
N01-E18-TARK-P3	N01-E18-TARK-P3-AS	6/22/10 15:48	3	2.1 J	1.0 U	5 J

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
N01-E18-TARK-P3	N01-E18-TARK-P3-BS	6/22/10 15:47	45	2.4 J	1.0 U	4 J
N01-E18-THKN-P1	N01-E18-THKN-P1-AS	6/22/10 13:45	3	4.5 J	1.0	8 J
N01-E18-THKN-P1	N01-E18-THKN-P1-BS	6/22/10 13:44	26	4.0 J	1.2	22 J
N01-E18-THKN-P2	N01-E18-THKN-P2-AS	6/22/10 13:54	3			9 J
N01-E18-THKN-P2	N01-E18-THKN-P2-BS	6/22/10 13:52	25			25 J
N01-E18-THKN-P3	N01-E18-THKN-P3-AS	6/22/10 14:00	3	3.1 J	1.0	7 J
N01-E18-THKN-P3	N01-E18-THKN-P3-BS	6/22/10 13:58	22	3.2 J	2.1	24 J
N01-E18-TKVK-P1	N01-E18-TKVK-P1-AS	6/22/10 15:04	3	0.90 J	1.3	15 J
N01-E18-TKVK-P1	N01-E18-TKVK-P1-BS	6/22/10 15:02	43	0.77 J	2.1	36 J
N01-E18-TKVK-P2	N01-E18-TKVK-P2-AS	6/22/10 15:10	3			14 J
N01-E18-TKVK-P2	N01-E18-TKVK-P2-BS	6/22/10 15:09	55			12 J
N01-E18-TKVK-P3	N01-E18-TKVK-P3-AS	6/22/10 15:17	3	0.87 J	1.1	8 J
N01-E18-TKVK-P3	N01-E18-TKVK-P3-BS	6/22/10 15:15	54	0.88 J	1.0 U	10 J
N01-E18-TNBN-P1	N01-E18-TNBN-P1-AS	6/22/10 13:40	3	0.87 J	1.1	22 J
N01-E18-TNBN-P1	N01-E18-TNBN-P1-BS	6/22/10 13:39	25	2.8 J	1.9	13 J
N01-E18-TNBN-P2	N01-E18-TNBN-P2-AS	6/22/10 13:47	3			9 J
N01-E18-TNBN-P2	N01-E18-TNBN-P2-BS	6/22/10 13:46	6			4 J
N01-E18-TNBN-P3	N01-E18-TNBN-P3-AS	6/22/10 13:55	3	1.8 J	1.0 U	6 J
N01-E18-TNBN-P3	N01-E18-TNBN-P3-AT	6/22/10 13:55	3	2.5 J	1.0 U	
N01-E18-TNBN-P3	N01-E18-TNBN-P3-BS	6/22/10 13:53	6	2.8 J	1.0 U	6 J
N01-E18-TNBN-P3	N01-E18-TNBN-P3-BT	6/22/10 13:54	6			6 J
N01-E18-TNBS-P1	N01-E18-TNBS-P1-AS	6/22/10 14:29	3	2.3 J	1.0 U	8 J
N01-E18-TNBS-P1	N01-E18-TNBS-P1-BS	6/22/10 14:28	42	2.6 J	1.0	6 J
N01-E18-TNBS-P2	N01-E18-TNBS-P2-AS	6/22/10 14:35	3			8 J
N01-E18-TNBS-P2	N01-E18-TNBS-P2-BS	6/22/10 14:34	49			6 J
N01-E18-TNBS-P3	N01-E18-TNBS-P3-AS	6/22/10 14:41	3	2.0 J	1.0 U	10 J
N01-E18-TNBS-P3	N01-E18-TNBS-P3-BS	6/22/10 14:40	12	2.3 J	1.2	5 J
N01-E19-TARK-P1	N01-E19-TARK-P1-AS	6/19/10 11:29	3			6 J
N01-E19-TARK-P1	N01-E19-TARK-P1-BS	6/19/10 11:28	33			10 J
N01-E19-THKN-P1	N01-E19-THKN-P1-AS	6/21/10 0:04	3			8 J
N01-E19-THKN-P1	N01-E19-THKN-P1-BS	6/21/10 0:02	31.1			12 J
N01-E19-TKVK-P1	N01-E19-TKVK-P1-AS	6/20/10 11:26	3			7 J
N01-E19-TKVK-P1	N01-E19-TKVK-P1-BS	6/20/10 11:24	41.2			22 J
N01-E19-TNBN-P1	N01-E19-TNBN-P1-AS	6/20/10 14:04	3			10 J
N01-E19-TNBN-P1	N01-E19-TNBN-P1-BS	6/20/10 14:02	37.3			20 J
N01-E19-TNBS-P1	N01-E19-TNBS-P1-AS	6/19/10 14:20	3			6 J
N01-E19-TNBS-P1	N01-E19-TNBS-P1-BS	6/19/10 14:18	46.8			10 J
N01-E21-TARK-P1	N01-E21-TARK-P1-AS	7/21/10 8:57	3	1.57 J	1 U	7
N01-E21-TARK-P1	N01-E21-TARK-P1-BS	7/21/10 8:54	36	1.68 J	1.2	15
N01-E21-TARK-P2	N01-E21-TARK-P2-AS	7/21/10 9:04	3			5
N01-E21-TARK-P2	N01-E21-TARK-P2-BS	7/21/10 9:02	42			7
N01-E21-TARK-P2	N01-E21-TARK-P2-BT	7/21/10 9:02	42			7
N01-E21-TARK-P3	N01-E21-TARK-P3-AS	7/21/10 9:10	3	1.61 J	1	5
N01-E21-TARK-P3	N01-E21-TARK-P3-BS	7/21/10 9:08	40	1.44 J	1 U	23
N01-E21-THKN-P1	N01-E21-THKN-P1-AS	7/21/10 7:16	3	2.10 J	1.1 J	9
N01-E21-THKN-P1	N01-E21-THKN-P1-BS	7/21/10 7:13	28	1.78 J	1 J	13
N01-E21-THKN-P2	N01-E21-THKN-P2-AS	7/21/10 7:26	3			10 J
N01-E21-THKN-P2	N01-E21-THKN-P2-BS	7/21/10 7:25	27			12 J
N01-E21-THKN-P3	N01-E21-THKN-P3-AS	7/21/10 7:32	3	2.5	1 J	11
N01-E21-THKN-P3	N01-E21-THKN-P3-AT	7/21/10 7:33	3	2.01 J	1 U	11
N01-E21-THKN-P3	N01-E21-THKN-P3-BS	7/21/10 7:31	24	1.9	1 J	12
N01-E21-TKVK-P1	N01-E21-TKVK-P1-AS	7/21/10 8:20	3	1.36 J	1	5
N01-E21-TKVK-P1	N01-E21-TKVK-P1-BS	7/21/10 8:17	44	1.29 J	1	9
N01-E21-TKVK-P2	N01-E21-TKVK-P2-AS	7/21/10 8:27	3			7
N01-E21-TKVK-P2	N01-E21-TKVK-P2-BS	7/21/10 8:25	53			11
N01-E21-TKVK-P3	N01-E21-TKVK-P3-AS	7/21/10 8:35	3	1.25 J	1	8
N01-E21-TKVK-P3	N01-E21-TKVK-P3-BS	7/21/10 8:33	52	1.26 J	1	8
N01-E21-TNBN-P1	N01-E21-TNBN-P1-AS	7/21/10 6:50	3	2.2	1 U	9
N01-E21-TNBN-P1	N01-E21-TNBN-P1-BS	7/21/10 6:48	29.5	1.49 J	1 U	14
N01-E21-TNBN-P2	N01-E21-TNBN-P2-AS	7/21/10 7:00	3			6
N01-E21-TNBN-P2	N01-E21-TNBN-P2-BS	7/21/10 6:58	8			7
N01-E21-TNBN-P3	N01-E21-TNBN-P3-AS	7/21/10 7:07	3	1.78 J	1 U	7
N01-E21-TNBN-P3	N01-E21-TNBN-P3-BS	7/21/10 7:06	7	1.63 J	1 U	9
N01-E21-TNBS-P1	N01-E21-TNBS-P1-AS	7/21/10 7:46	3	1.60 J	1 U	6
N01-E21-TNBS-P1	N01-E21-TNBS-P1-BS	7/21/10 7:44	47	1.95 J	1	12
N01-E21-TNBS-P2	N01-E21-TNBS-P2-AS	7/21/10 7:54	3			5
N01-E21-TNBS-P2	N01-E21-TNBS-P2-BS	7/21/10 7:52	49			6
N01-E21-TNBS-P3	N01-E21-TNBS-P1-BT	7/21/10 7:44	47			13
N01-E21-TNBS-P3	N01-E21-TNBS-P3-AS	7/21/10 8:01	3	2.04 J	1.2	15

Table 3-1
Results of DOC, POC and SSC Laboratory Analysis
Physical Water Column Monitoring Sampling Program Characterization Summary
Lower Passaic River Restoration Project

Location ID	Sample ID	Sample Time	Depth (ft)	DOC (mg/L)	POC (mg/L)	SSC (mg/L)
N01-E21-TNBS-P3	N01-E21-TNBS-P3-BS	7/21/10 7:59	11	1.81 J	1	11
N01-E22-TARK-P1	N01-E22-TARK-P1-AS	7/21/10 15:24	3	2.26 J	1.3	6
N01-E22-TARK-P1	N01-E22-TARK-P1-BS	7/21/10 15:22	32	2.00 J	1 U	9
N01-E22-TARK-P2	N01-E22-TARK-P2-AS	7/21/10 15:30	3			11
N01-E22-TARK-P2	N01-E22-TARK-P2-BS	7/21/10 15:28	46			23
N01-E22-TARK-P3	N01-E22-TARK-P3-AS	7/21/10 15:39	3	1.53	1	11
N01-E22-TARK-P3	N01-E22-TARK-P3-BS	7/21/10 15:36	45	1.7	1	10
N01-E22-THKN-P1	N01-E22-THKN-P1-AS	7/21/10 13:27	3	3.8	1.1	10
N01-E22-THKN-P1	N01-E22-THKN-P1-BS	7/21/10 13:26	31	2.9	1.4	23
N01-E22-THKN-P2	N01-E22-THKN-P2-AS	7/21/10 13:32	3			10
N01-E22-THKN-P2	N01-E22-THKN-P2-BS	7/21/10 13:32	25			26
N01-E22-THKN-P3	N01-E22-THKN-P3-AS	7/21/10 13:39	3	4.2	1.1	10
N01-E22-THKN-P3	N01-E22-THKN-P3-BS	7/21/10 13:38	22	3.2	2.3	12
N01-E22-TKVK-P1	N01-E22-TKVK-P1-AS	7/21/10 14:47	3	1.48 J	1	8 J
N01-E22-TKVK-P1	N01-E22-TKVK-P1-BS	7/21/10 14:43	42	1.27 J	1.7	21 J
N01-E22-TKVK-P1	N01-E22-TKVK-P1-BT	7/21/10 14:43	42	1.53 J	1.2	20 J
N01-E22-TKVK-P2	N01-E22-TKVK-P2-AS	7/21/10 14:53	3			13 J
N01-E22-TKVK-P2	N01-E22-TKVK-P2-BS	7/21/10 14:51	55			8 J
N01-E22-TKVK-P3	N01-E22-TKVK-P3-AS	7/21/10 15:03	3	1.51 J	1 U	8 J
N01-E22-TKVK-P3	N01-E22-TKVK-P3-BS	7/21/10 15:02	54	1.93 J	1	11 J
N01-E22-TNBN-P1	N01-E22-TNBN-P1-AS	7/21/10 13:15	3	2.03 J	1 J	7 J
N01-E22-TNBN-P1	N01-E22-TNBN-P1-BS	7/21/10 13:13	32	1.84 J	1.2 J	34 J
N01-E22-TNBN-P2	N01-E22-TNBN-P2-AS	7/21/10 13:23	3			14 J
N01-E22-TNBN-P2	N01-E22-TNBN-P2-BS	7/21/10 13:21	6.5			9 J
N01-E22-TNBN-P3	N01-E22-TNBN-P3-AS	7/21/10 13:30	3	2.34 J	1 J	9 J
N01-E22-TNBN-P3	N01-E22-TNBN-P3-BS	7/21/10 13:28	5	2.11 J	1 U	9 J
N01-E22-TNBS-P1	N01-E22-TNBS-P1-AS	7/21/10 14:07	3	1.81 J	1 U	8 J
N01-E22-TNBS-P1	N01-E22-TNBS-P1-BS	7/21/10 14:04	46.5	1.61 J	1.4	38 J
N01-E22-TNBS-P2	N01-E22-TNBS-P2-AS	7/21/10 14:15	3			6 J
N01-E22-TNBS-P2	N01-E22-TNBS-P2-BS	7/21/10 14:13	49			16 J
N01-E22-TNBS-P3	N01-E22-TNBS-P3-AS	7/21/10 14:21	3	1.87 J	1 U	5 J
N01-E22-TNBS-P3	N01-E22-TNBS-P3-AT	7/21/10 14:22	3			6 J
N01-E22-TNBS-P3	N01-E22-TNBS-P3-BS	7/21/10 14:20	12	1.87 J	1.3 J	7 J
N01-E23-TARK-P1	N01-E23-TARK-P1-AS	7/24/10 9:10	3			8 J
N01-E23-TARK-P1	N01-E23-TARK-P1-BS	7/24/10 9:09	31			9 J
N01-E23-THKN-P1	N01-E23-THKN-P1-AS	7/26/10 10:12	3			12 J
N01-E23-THKN-P1	N01-E23-THKN-P1-BS	7/26/10 10:11	35			5 J
N01-E23-TKVK-P1	N01-E23-TKVK-P1-AS	7/25/10 8:43	3			6 J
N01-E23-TKVK-P1	N01-E23-TKVK-P1-BS	7/25/10 8:41	46			7 J
N01-E23-TNBN-P1	N01-E23-TNBN-P1-AS	7/24/10 8:52	33.5			13 J
N01-E23-TNBN-P1	N01-E23-TNBN-P1-BS	7/24/10 8:50	3			12 J
N01-E23-TNBS-P1	N01-E23-TNBS-P1-AS	7/25/10 8:32	3			7 J
N01-E23-TNBS-P1	N01-E23-TNBS-P1-AT	7/25/10 8:32	3			8 J
N01-E23-TNBS-P1	N01-E23-TNBS-P1-BS	7/25/10 8:31	50			7 J

Notes:
DOC - Dissolved organic carbon
ft - feet
J - Estimated Value
mg/L - milligrams per liter
POC - Particulate organic carbon
SSC - Suspended Sediment Concentration (particle size is >1.2 um)
U - Non-detect at laboratory detection limit
um - microns
(a) Depth estimated during High Flow/Flood Event to be <1 foot. Samples collected by direct immersion.
(b) Listed in database as "BRIDGE ST. 1"
(c) Listed in database as "BRIDGE ST. 2"
(d) Listed in database as "PARK AVE 2"

4.0 Data Usability

The DQOs developed for the PWCM program are presented in PWCM QAPP (AECOM 2010) and are summarized in Section 1.2 of this report. These DQOs establish the level of data quality that was considered necessary to support the objectives of the study. This section describes the data usability assessment that was performed to verify the quality of the data generated during the PWCM program and to evaluate its acceptability for use in site decisions.

This section of the report is separated into four subsections: Section 4.2 discusses the overall data validation findings. Section 4.3 presents the data quality indicators (DQIs) of precision, accuracy, representativeness, comparability, completeness, and sensitivity. Section 4.4 discusses data that were rejected following the data validation/review process.

Note that the data usability evaluation focuses on the water column sample and field duplicate results and does not include the aqueous QC samples (equipment rinsate blanks). Qualifications of the aqueous QC samples are discussed in the DVRs. Data for the water column samples, including any qualifiers that were applied, are presented in **Table 3-1**. Data for equipment blanks are presented in **Appendix H**.

4.1 Data Usability

The data usability assessment was based primarily on the results of the data validation process described in Section 2.4.2. The validation process consisted of two steps: verification of adherence to program specifications (QAPP, analytical methods, and contractual documents) and an evaluation of the quality of the data in terms of precision, accuracy, representativeness, comparability, and completeness. These elements (precision, accuracy, representativeness, comparability, and completeness), referred to as data quality indicators (DQIs), were assessed by comparing the sample results generated during the PWCM program to pre-established standards or criteria documented in the PWCM QAPP (AECOM 2010).

Major deviations from project criteria, as identified during data validation, required data rejection. Decisions as to the acceptance or rejection of data were based on USEPA Region 2 validation guidance where available; in the absence of Region 2 guidance, other validation guidance or professional judgment was used. In other cases, data associated with minor deviations from established criteria were considered acceptable and appropriate for use, and were flagged with a qualifier (for example, with a “J” as estimated); Region 2 data validation guidance does not provide a mechanism for assigning bias.

In addition to the data validation procedures, data were reviewed by the modeling team, Moffat and Nichol. Eighteen of 1,120 results for SSC were found to be inconsistent with OBS and ABS vertical gradients (**Table 2-8**). These data were excluded from the analysis.

4.2 Data Validation Findings

All data generated from investigative (field) samples including field duplicates were validated and form the basis of this data usability assessment. Data measured in the field (i.e., salinity and turbidity) were measured *in-situ* and were not part of the formal validation program. Additional data validation detail (batch by batch QC sample findings, QC sample results, data qualification rationale) are provided in formal DVRs presented in **Appendix F**.

Of the 2,430 water column data points generated during the PWCM program, 2,422 were valid and acceptable for assessment purposes; 8 SSC data points (0.3 percent) were rejected during the validation

process due to equipment blank contamination. Twenty-nine percent of the valid data were accepted as reported by the laboratory, with no further qualification required. **Table 4-1** details the cases in which some validation action (qualification) was identified. The most common reason for qualifying data (33 percent) related to equipment blank contamination. The next most common data qualification related to exceedances of holding times (23 percent of the total validated data).

4.3 Data Quality Indicators

The following sections discuss each of the DQIs and related issues identified during the validation process. Specific validation findings regarding selected analytes or locations are provided in the individual DVRs provided in **Appendix F**.

4.3.1 Precision

Precision is the measure of agreement among repeated measurements of the same property under identical or substantially similar conditions and includes both field and analytical (laboratory) components. Program precision requirements are detailed in Worksheet #28 of the PWCM QAPP (AECOM 2010). Overall, greater than 99.9 percent of the data, from a precision assessment perspective, were usable without precision-related qualification. Data that did not meet the QAPP-specified precision criteria were qualified.

Field precision was assessed through the collection and measurement of field duplicates and expressed as the relative percent difference (RPD) of the sample and field duplicate results. Field duplicates were placed into a duplicate set of storage containers at a frequency outlined in the PWCM QAPP (AECOM 2010). Field duplicates were collected concurrently from the tubing or Alpha bottles used for sampling. During the High Flow/Flood event, field duplicates were collected by immersing the field duplicate bottles immediately after the bottles for the parent samples. Less than 0.9 percent of all reportable data were qualified as estimated on the basis of field duplicate results.

Laboratory precision was assessed using matrix duplicates, LCS/laboratory control sample duplicates (LCSD) pairs, and MS/MSD pairs. Matrix duplicates and MS/MSD pairs do not reflect laboratory precision as effectively as LCS/LCSD pairs since sample heterogeneity may impact both matrix duplicate and MS/MSD precision. However, it should be noted that for the PWCM data, no differentiation is made between RPD exceedances for matrix duplicates, LCS/LCSD, or MS/MSD precision. The percent of all reportable water results that was qualified as estimated on the basis of laboratory duplicate RPDs was 0.08 percent.

Overall, the program precision objectives (AECOM 2010) were achieved. Less than 1.0 percent of the reportable data points were qualified for reasons related to either field or laboratory precision. No data were rejected based on laboratory precision. A detailed discussion of field and laboratory duplicate results is contained in the individual DVRs provided in **Appendix F**.

4.3.2 Accuracy

Accuracy is the degree of agreement between an observed value and an accepted reference or true value. During the validation process, there are several elements of the analytical chemistry report associated with accuracy that are reviewed. These include instrumental ion abundance or suppression information, interference checks, internal standard areas, LCS and MS recovery information, and blank contamination. This assessment focuses on accuracy assessments related to positive control samples (i.e., field and laboratory blank samples, LCS and MS samples).

Overall, greater than 99 percent of the results were considered acceptable and usable without qualification following comparison to program accuracy criteria (AECOM 2010). Data that did not meet the pre-established criteria were qualified. In 8 cases, data were rejected because of equipment blank contamination; in all other cases the data were considered valid and acceptable for use.

Laboratory accuracy was assessed using the recoveries of positive control samples (i.e., MS, LCS, and blank samples). As detailed in **Table 4-1**, 1.6 percent of the validated dataset were qualified as estimated for LCS nonconformance, and 1.6 percent of data points were qualified based on MS recovery nonconformance.

Accuracy was also indirectly addressed via the negative control samples for field activities (i.e., equipment rinsate blanks), as well as laboratory negative control samples, such as method blanks. Equipment blanks were collected weekly during project performance and method blanks were prepared with each sample batch. The percentages of results that were qualified due to associated equipment or laboratory blank contamination were 33 and less than 1 percent, respectively. Overall, the program accuracy objectives (AECOM 2010) were achieved.

4.3.3 Representativeness

Representativeness is a qualitative and quantitative measure of the degree to which data suitably represents a characteristic of a population, parameter variations at a sampling point, a process condition, or an environmental condition. Aspects of representativeness addressed during validation included COC documentation, conformity of laboratory analyses to the PWCM QAPP (AECOM 2010), adherence of the documented laboratory procedures to method requirements, and completeness of the laboratory data packages.

Field and laboratory precision, also an aspect of representativeness, are addressed above in Section 4.3.1. Holding/storage time is another aspect of representativeness, and 23 percent of the data were qualified as a result of holding time exceedances (**Table 4-1**). Approximately 570 data points were qualified because holding times were exceeded beyond the acceptable threshold. Most of these data (301 data points) correspond to SSCs related to samples collected during Events 10A and N01. There were also 238 POC data points qualified due to holding time exceedances over the course of all PWCM events.

Detailed validation findings associated with data representativeness are discussed in the individual DVRs contained in **Appendix F**.

4.3.4 Comparability

Comparability is a qualitative expression of the measure of confidence that two or more data sets may contribute to a common analysis and interpretation. Comparability of data within the investigation was maximized by using standard methods for sampling and analysis, reporting of data, and data validation. In general, standard Resource Conservation and Recovery Act (RCRA) program methods from SW-846 or alternate USEPA or other accepted methods were used. To eliminate inter-laboratory variability, specific analytical methods were assigned to each laboratory for the duration of the project.

4.3.5 Completeness

Completeness is a measure of the amount of valid data obtained from a measurement system, expressed as a percentage of the number of valid measurements that were or should have been collected. Valid data are defined as all data points judged to be usable (i.e., not rejected as a result of the validation process).

Field completeness is defined as the percentage of samples actually collected versus those intended to be collected. The total number of samples planned in Revision 5 of the QAPP (AECOM 2010) (minus QC samples) to be submitted to the laboratories was 920 surface water samples for SSC and 466 for POC and DOC. Due to an extension in the Spring 2010 deployment from three to four months and the addition of the High Flow/Flood sampling event, 220 SSC and 79 POC and DOC samples were planned to be added to the program, making the total planned samples 1,140 for SSC and 586 for POC and DOC. The actual number of samples collected and sent to laboratories was 1,120 for SSC, 583 for DOC, and 586 for POC. The field completeness for SSC, DOC and POC was 98, 99 and just over 100 percent, respectively. The goal established for the PWCM program (AECOM 2010) was greater than 95 percent field completeness.

During long-term deployments of *in situ* meters, biofouling occurred; data were not reliable during the periods the instruments were fouled and these data were removed from the PWCM dataset used for the solids rating curves. Since the ABS-SSC relationships tend to be somewhat poorer than the OBS-SSC relationships, the ABS-derived SSC time-series was compared against the OBS-derived SSC as an additional check. Prior to performing this comparison, time-series of turbidity measured by the OBS were screened and filtered to exclude data considered to be affected by fouling (typically seen as a high-frequency oscillation in the measured signal with no coherence or structure with respect to the tide, velocity, or Dundee Dam discharge, and also inconsistent with the ABS time-series). The periods of fouled data at Dundee Dam included:

- 10/12/2009 to 10/24/2009
- 10/28/2009 to 11/10/2009
- 11/20/2009 to 12/7/2009
- 4/15/2010 to 4/24/2010
- 6/27/2010 to 7/14/2010

Laboratory completeness is defined as the percentage of valid data points versus the total expected from the laboratory analyses. Valid data points are those that have not been rejected during the validation process. The objective for this project was greater than 95 percent laboratory completeness (AECOM 2010). Overall laboratory completeness was greater than 99 percent (2,422 valid and acceptable results out of 2,430 total reportable water results).

4.3.6 Sensitivity

Sensitivity is the ability of a method or instrument to measure a constituent at low levels. For the USEPA methods employed in this project, sensitivity was measured by the Method Detection Limit (MDL) and Quantitation Limit (QL). Both nominal MDLs and QLs were provided by the analytical laboratories in their analytical report and were verified during validation. All reporting limits, both the QL and MDL, were corrected by the laboratory for sample-specific factors, such as exact aliquot size and dilutions. The laboratories were instructed to report estimated (J) results if concentrations were above the MDL but below the QL.

In general, the methods selected were sufficiently sensitive to meet the project data quality levels (DQLs) (AECOM 2010). Those methods that could not meet the project DQLs were identified in the PWCM QAPP. During validation, the actual laboratory QLs were also compared to the achievable laboratory limits identified in the PWCM QAPP (AECOM 2010). Results for selected analytes in some samples did not meet the QL goals due to sample specific matrix issues. These instances occurred most commonly in the analysis of DOC. A detailed discussion of quantitation issues is provided in the individual DVRs contained in **Appendix F**.

4.4 Rejected Data

Of the 2,430 analytical data points (SSC, POC, and DOC) generated during the PWCM site characterization, all were validated (100 percent). Of the 2,430 validated records, 8 were rejected (<1 percent) and considered not useable. All other data are considered useable for decision-making purposes. The 8 sample points were rejected due to SSC equipment blank contamination.

Table 4-1

PWCM Data Qualification Summary

Physical Water Column Monitoring Sampling Program Characterization Summary

Lower Passaic River Restoration Project

Program Qualifier Applications	Number of Cases	Percentage of Total
Total validated	2430	-
Total qualified (as estimate, rejected, etc.)	1729	71%
Laboratory blank contamination	18	0.74%
Equipment blank contamination	793	33%
Calibration issue	119	4.9%
Holding times	569	23%
LCS recoveries	38	1.6%
MS recovery	40	1.6%
Field duplicate RPDs	20	0.82%
Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)	2	0.08%
Sample preparation issue	13	0.53%
Temperature Preservation Issue	117	4.8%
Quantity with one or more accuracy related qualifiers	889	37%
Quantity with one or more precision related qualifiers	22	0.91%
Quantity rejected	8	0.33%
Rejected data containing accuracy related qualifiers	8	0.33%
Rejected data containing precision related qualifiers	0	0.0%

Notes:

LCS - Laboratory Control Sample

LCSD - Laboratory Control Sample Duplicate

MS - Matrix spike

MSD - Matrix Spike Duplicate

RPD - Relative Percent Difference

PWCM - Physical Water Column Monitoring

5.0 References

AECOM, 2010. Quality Assurance Project Plan. Lower Passaic River Study Area. Quality Assurance Project Plan/Field Sampling Plan Addendum. RI Water Column Monitoring/Physical Data Collection for the Lower Passaic River, Newark Bay and Wet Weather Monitoring. Revision 5. April 2010.

AECOM, Anchor QEA, de maximis, inc., Integral Consulting, mab environmental, Moffatt & Nichol, and Windward Environmental, 2013. Lower Passaic River Study Area Remedial Investigation/ Feasibility Study, Interim Conceptual Site Model. December 2013.

Battelle, 2005. Lower Passaic River Restoration Project. Pathways Analysis Report. Prepared for U.S. Environmental Protection Agency Region 2 and U.S. Army Corps of Engineers. Battelle, Duxbury, Massachusetts.

Bopp, R.F., M.L. Gross, H. Tong, H.J. Simpson, S.J. Monson, B.L. Deck, and F.C. Moser, 1991. A major incident of dioxin contamination: sediments of New Jersey estuaries. Environmental Science and Technology 25(5):951-956.

Bopp, R.F., S.N. Chillrud, E.L. Shuster, and H.J. Simpson, 2006. Contaminant Chronologies from Hudson River Sedimentary Records. In: The Hudson River Estuary. J. Levinton and J. Waldman eds., Cambridge University Press, January 2006, Chapter 26: 383-397.

Bopp, R.F., S.N. Chillrud, E.L. Shuster, H.J. Simpson, and F.D. Estabrooks, 1998. Trends in Chlorinated Hydrocarbon Levels in Hudson River Basin Sediments. Environmental Health Perspectives 106(4):1075-81.

Cañizares, R., H. Winterwerp, L. Schmied, and R. Hampson, 2009. Variability of Lower Passaic River Estuarine Dynamics Associated with Bathymetric Uncertainty and Dredging. Presentation to the Society for Environmental Toxicology and Chemistry North America 30th Annual Meeting. November 19-23. New Orleans, LA.

Chaky, D.A., 2003. Polychlorinated biphenyls, polychlorinated dibenzo-p-dioxins and furans in the New York metropolitan area: interpreting atmospheric deposition and sediment chronologies. Ph.D. Thesis, Rensselaer Polytechnic Institute.

Chant, R.J., D. Fugate, and E. Garvey, 2010. The Shaping of an Estuarine Superfund Site: Roles of Evolving Dynamics and Geomorphology. Estuaries and Coasts 34(1):90-105.

Dyer, K.R., 1995. Sediment Transport Processes in Estuaries. Developments in Sedimentology 53:423-449.

Hansen, W.J., 2002. A Statistical and Spatial Analysis of Dioxin-Furan Contamination in the Hudson Estuary. Northeastern Geology and Environmental Sciences 24(3):159-170.

HQI, 2006. Lower Passaic River Restoration Project: Draft Hydrodynamic Modeling Report. Prepared for U.S. Environmental Protection Agency Region 2 and US Army Corps of Engineers. HydroQual, Inc., Mahwah, NJ.

Iannuzzi T. J., D. F. Ludwig J. C. Kinnell, J. M. Wallin, W. H. Desvousges, and R. W. Dunford, 2002. A common tragedy: history of an urban river. Amherst Scientific Publishers, Amherst, Massachusetts.

Lillienfeld, D.E., and M.A. Gallo, 1989. 2,4-D, 2,4,5-T, and 2,3,7,8-TCDD: An Overview. Epidemiologic Reviews 11:28-58.

M&N and Deltares, 2013. Status of the CPG's Sediment Transport Model. Prepared for the Cooperating Parties Group, Moffatt & Nichol and Deltares, New York; January.

MPI, 2006. Lower Passaic River Restoration Project. Field Sampling Plan. Volume 1. Prepared for USEPA and USACE, Malcolm Pirnie, Inc., White Plains, New York; January.

MPI, Earth Tech and Battelle. 2006. Lower Passaic River Restoration Project. Draft Field Sampling Plan. Volume 2. Prepared for USEPA, USACE, and New Jersey Department of Transportation/Office of Maritime Resources. Malcolm Pirnie, Inc., White Plains, New York; Earth Tech, Inc., Bloomfield, New Jersey; Battelle, Stony Brook, New York. June.

MPI, Earth Tech and Battelle, 2005a. Lower Passaic River Restoration Project. Revised Preliminary Draft Field Sampling Plan. Volume 3. Prepared for USEPA, USACE, and New Jersey Department of Transportation/Office of Maritime Resources. Malcolm Pirnie, Inc., White Plains, New York; Earth Tech, Inc., Bloomfield, New Jersey; Battelle, Stony Brook, New York. July.

MPI, Earth Tech and Battelle, 2005b. Lower Passaic River Restoration Project. Work Plan. Prepared for USEPA, and USACE, Malcolm Pirnie, Inc., White Plains, New York; Earth Tech, Inc., Bloomfield, New Jersey; Battelle, Stony Brook, New York. August.

MPI, Earth Tech and Battelle, 2005c. Lower Passaic River Restoration Project. Quality Assurance Project Plan. Prepared for USEPA and USACE. Malcolm Pirnie, Inc., White Plains, New York; Earth Tech, Inc., Bloomfield, New Jersey; Battelle, Stony Brook, New York. August.

NOAA, 1984. A geochemical assessment of sedimentation and contaminant distributions in the Hudson-Raritan Estuary. National Oceanic and Atmospheric Administration, National Ocean Service, Rockville, MD.

SEI and HQI, 2011. Lower Passaic River: System Understanding of Sediment Transport. May 2011 version.

Shear, N.M., C.W. Schmidt, S.L. Huntley, D.W. Crawford, and B.L. Finley, 1996. Evaluation of the Factors Relating Combined Sewer Overflows with Sediment Contamination of the Lower Passaic River. Marine Pollution Bulletin 32(3):288-304.

Tierra Solutions Inc., 2008. Phase I Engineering Evaluation/Cost Analysis. CERCLA Non-Time-Critical Removal Action – Lower Passaic River Study Area. November 2008.

USACE, 2010. Lower Passaic River Commercial Navigation Analysis. Rev. July 2010.

USACE, 2007. Lower Passaic River Restoration Project source control early action (Draft). Appendix F, Navigation Studies, CENAN - Lower Passaic River navigation analysis. US Army Corps of Engineers New York District.

USACE, 1997. Final environmental impact statement on the Newark Bay Confined Disposal Facility. US Army Corps of Engineers, New York District, New York, NY. April 1997.

USEPA, 2008. Diamond Alkali Co. Superfund Site Fact Sheet. http://www.epa.gov/region02/superfund/npl/0200613c.pdf.

USEPA, 2007. Administrative settlement agreement and order on consent for remedial investigation/feasibility study, Lower Passaic River Study Area portion of the Diamond Alkali Superfund site. USEPA Region 2 CERCLA docket no. 02-2007-2009. U.S. Environmental Protection Agency, Region 2, New York, New York.

USEPA, 2006. Guidance on Systematic Planning Using the Data Quality Objectives Process, EPA-QAG4. EPA Docket No. EPA/240/B-06/001. Washington D.C.: United States Environmental Protection Agency, Office of Environmental Information. Available at: http://www.epa.gov/QUALITY/qs-docs/g4-final.pdf. February 2006.

USEPA, 1988. Guidance for Conducting Remedial Investigations and Feasibility Studies under CERCLA, Interim Final EPA 540/G-89/004, OSWER 9355.3-01 October.

USGS. 2012. USGS 01390000 Passaic River at Garfield NJ: streamflow and temperature. National Water Information System Web Interface [online]. US Geological Survey, West Trenton, NJ. http://waterdata.usgs.gov/nwis/inventory?agency_code=USGS&site_no=01390000.

Windward, 2012. Summer and Fall 2012 dissolved oxygen monitoring program. Addendum to the Quality Assurance Project Plan. Remedial investigation water column monitoring/physical data collection for the Lower Passaic River, Newark Bay and wet weather monitoring. Addendum No. 1. Final. Prepared for Cooperating Parties Group, Newark, NJ. August 6, 2012. Lower Passaic River Restoration Project. Lower Passaic River Study Area RI/FS. Windward Environmental LLC, Seattle, WA.

Windward, 2013. Dissolved Oxygen Monitoring Program Data Report for the Lower Passaic River Study Area: Summer and Fall 2012. Draft. Windward Environmental LLC, Seattle, WA. September 2013.

Appendix A

Final Report - Fall Deployment Oceanographic Data Acquisition Program, Lower Passaic River Restoration Project. OSI Report #09ES053

Final Report

Fall Deployment
Oceanographic Data Acquistion Program
Lower Passaic River Restoration Project

Passaic River, Newark to Passaic, NJ

OSI Report #09ES053
26 August 2010



Prepared For:
AECOM
171 Daniel Webster Highway, Suite 11
Belmont, New Hampshire 03220

Prepared By:
Ocean Surveys, Inc.
91 Sheffield Street
Old Saybrook, CT 06475

FINAL REPORT

FALL DEPLOYMENT

OCEANOGRAPHIC DATA ACQUISITION PROGRAM

LOWER PASSAIC RIVER RESTORATION PROJECT

PASSAIC RIVER, NEWARK TO PASSAIC, NJ

OSI Report No. 09ES053

Prepared For: AECOM
171 Daniel Webster Highway, Suite 11
Belmont, New Hampshire 03220

Prepared By: Ocean Surveys, Inc.
91 Sheffield Street
Old Saybrook, CT 06475

26 August 2010

TABLE OF CONTENTS

Page

TABLE OF CONTENTS i

LIST OF FIGURES & TABLES ii

1.0 INTRODUCTION 1

1.1 Project Summary 1
1.2 Project Tasks 3

2.0 FIELD OPERATIONS SUMMARY 5

2.1 Field Crew, Survey Vessel, & Navigation 5
2.2 Field Schedule 6
2.3 *In Situ* Instrumentation and Moorings 7

2.3.1 YSI Environmental 6920 Multiparameter Sonde 8
2.3.2 Acoustic Doppler Current Profiler 9

2.4 Real-Time Data Collection 10

3.0 DATA DISCUSSION AND PRESENTATION 10

3.1 Water Sample Data 10
3.2 *In Situ* Instrumentation 10

3.2.1 CT-OBS Water Quality Data 11
3.2.2 ADCP Current and Acoustic SSC Data 12
3.2.3 Mooring CTD-OBS Vertical Profiles 12

3.3 Real-Time Survey Events 13

3.3.1 Vessel Mounted Currents 13
3.3.2 CTD Vertical Profiles 13

3.4 Project Summary 14

LIST OF FIGURES & TABLES

Figure 1. Site map of *in situ* instrumentation and real-time survey transects.. 2
Figure 2. ADCP/CT-OBS mooring and CT-OBS surface buoy 8
Figure 3. *In situ* CT-OBS and ADCP bottom mooring. 9
Figure 4. Station 042 CT-OBS near bottom turbidity data relative to ADCP current direction. 11

Table 1. Field crews 5
Table 2. Field schedule 6

APPENDICES

1 Water Sampling Log
2 Survey Equipment, Procedures and Data Processing
3 Instrument Calibration
4 YSI Water Quality Time Series Plots
5 *In Situ* ADCP Time Series Plots
6 Mooring CTD-OBS Vertical Profiles – Events E01, E05, E09, & E10
7 Trip 1 Real Time Surveys Events E02-E04
8 Trip 2 Real Time Surveys Events E06-E08
9 Trip 3 Real Time Surveys Events E11-E13
10 Data CD

FINAL REPORT

FALL DEPLOYMENT

OCEANOGRAPHIC DATA ACQUISITION PROGRAM

LOWER PASSAIC RIVER RESTORATION PROJECT

PASSAIC RIVER, NEWARK TO PASSAIC, NJ

1.0 INTRODUCTION

During the period 10 October 2009 through 16 December 2009, Ocean Surveys, Inc. (OSI) conducted an oceanographic data acquisition program on the Lower Passaic River during a traditional low flow period. The overall program was created to provide *in situ* and real-time data over two three-month periods coinciding within low and high river flows to provide data on flows, salinity, and solids under a range of flow conditions

1.1 Project Summary

This program includes the deployment of six CT-OBS mooring buoys and five Acoustic Doppler Current Profilers (ADCP) bottom moorings (Figure 1) along with real-time boat-based transect surveys coinciding with CTD-OBS vertical profiles and water sampling at each of the mooring locations. The moorings were deployed in October 2009, scheduled to be deployed for 3 months. The deployment was reduced to a two-month deployment in December because of weather concerns on the Passaic River. OSI conducted a real-time boat-based surveys after the moorings were deployed, serviced, and before instrument recovery. Details of the operational aspects of the field program along with a brief discussion of the data are presented in the following report.



Figure 1. Site map of *in situ* instrumentation and real-time survey transects.

1.2 Project Tasks

AECOM has developed a series of designations for all field tasks performed on site. The overall field program has been broken down to two program designations for the fall and spring flow conditions. The fall 2009 field program was given the program designation of 09A. During this program, each individual field task was broken down to individual events. CTD-OBS vertical profiles and water samples were completed after deployment (Event E01), prior to servicing (Event E05), after redeployment (Event E09), and prior to recovery (Event E10) for the five stations below Dundee Dam. Real-time survey operations conducted during each trip to the site were completed under Events E02 & E03 (October 2009), Events E07 & E08 (November 2009) and Events E12 & E13 (December 2009). The *in situ* mooring CTD-OBS vertical profiles and water samples along with the real-time survey operations completed above Dundee Dam at Station 175 were completed under Event E02 (October 2009), Event E06 (November 2009), and Event E11 (December 2009).

The investigation included the following project tasks:

1) ***In Situ* CT-OBS Data:** *In situ* water quality was documented using both surface and bottom instrument moorings. Eleven (11) YSI water quality sondes were deployed one on each of the five bottom mounted instrument moorings and one on each of the six surface buoys. Instruments were mounted 3 feet above the bottom and 3 feet below the surface, respectively. Each sonde was configured to record temperature, salinity, and turbidity at 12-minute intervals. The six instrument mooring stations were located along a 17.5-mile stretch of the lower Passaic River (Figure 1).

2) ***In Situ* Current Velocity Profiling:** *In situ* current velocities were monitored using five bottom-mounted TRDI Workhorse Sentinel Acoustic Doppler Current Profilers (ADCPs). The ADCPs were deployed at each of the five locations along the Passaic River below Dundee Dam (Figure 1). The ADCPs were programmed to record data throughout the water column at 0.5-meter vertical bins every 12 minutes.

3) **Vessel Mounted ADCP (VMADCP) Transects:** Current velocity and backscatter data were collected along six cross-river transects. Each transect corresponded with the *in situ* instrument locations (Figure 1). The five lower transects were completed twice coinciding with flood and ebb tidal conditions, while Transect 175 above Dundee Dam, was completed only once. The VMADCP surveys were completed after instrument deployments, during servicing, and prior to instrument recovery. Current velocity and backscatter data were collected throughout the water column at 0.5-meter vertical bins.

4) **CTD-Turbidity Profiling:** Sea-bird Electronics, Inc. Model SBE-19 SeaCat profiler was used to document the temperature, salinity, and turbidity of the water column versus depth. Profiles were collected at each mooring location after deployment, before and after servicing, and prior to recovery. In addition, three profiles were collected across each transect during the VMADCP surveys. Above Dundee Dam at Transect 175, four profiles were collected along a single transect.

5) **Documenting Total Suspended Solids:** Water samples were collected at each mooring location after deployment, before and after servicing, and prior to recovery. In addition, samples were collected at each of the CTD profiling station throughout the VMADCP surveys. Samples were collected primarily to record suspended sediment concentrations (SSC) with periodic additional samples collected during the VMADCP surveys for POC/DOC analysis. Water samples were collected at 3 feet below the surface and 3 feet above the bottom. AECOM was responsible for water sample handling and subsequent lab analysis.

2.0 FIELD OPERATIONS SUMMARY

2.1 Field Crew, Survey Vessel, & Navigation

OSI conducted all fieldwork aboard the ***R/V Ready II*** and ***R/V Skimmer***, each equipped with a DMS 212 DGPS receiver and staffed by a two-person OSI field team consisting of a Project Manager/Scientist and a Field Engineer. Each vessel was powered by twin outboard motors and equipped with winch and davit capabilities to support installation, servicing, and recovery of the *in situ* instrument moorings. Each vessel was also equipped with an RD Instruments vessel-mounted 1200 kHz ADCP and Sea-Bird Electronics CTD-OBS (Conductivity, Temperature, Depth and Turbidity) vertical profiler.

The following personnel comprised the two-person field crews (Table 1):

Table 1. Field crews

Survey	R/V Ready II	R/V Skimmer
October 2009	Steve Bodak	Dustin Kach
	Ryan Bollenbach	Jeff Motti
November 2009	Steve Bodak	Ken Cadmus
	Dustin Kach	Jason DeLorenzo
December 2009	Steve Bodak	Ken Cadmus
	Dustin Kach	Ryan Bollenbach

In addition, representatives from AECOM and EPA (CDM) were present throughout the field effort.

The survey navigation system consisted of Coast Guard Differential GPS (DGPS) that was fed directly into the HYPACK survey navigation and data collection software on each vessel. A full description of the navigational system and survey instrumentation is available in Appendix 1 along with a brief description of operational and data processing procedures. The designated coordinate system for the project was the New Jersey State Plane in the North American Datum of 1983 (NAD83). Horizontal grid units were in U.S. Survey feet.

2.2 Field Schedule

Project tasks were conducted from 10 October 2009 through 16 December 2009. A detailed schedule of field operations is listed below (Table 2):

Table 2. Field schedule

Date	*R/V Ready II* Task	*R/V Skimmer* Task
10/9/2009	Travel to site, launch and ready boat	
10/10/2009	Deploy equipment at Stations 014 and 042	
10/11/2009	Deploy Stations 102 and 135	
10/12/2009	Deploy Station 067, collect CTD-OBS vertical profiles and water samples at the lower 5 stations, & calibrated VMADCP.	Travel to site, launch and ready boat, deploy instrument at Station 175, collect CTD-OBS vertical profiles, water samples and VMADCP.
10/13/2009	Collect CTD-OBS vertical profiles, water samples and VMADCP at Stations and Transects 014, 042, & 067.	Launch boat, collect CTD-OBS vertical profiles, water samples and VMADCP at Stations and Transects 102 & 135.
10/14/2009	Travel to OSI at Old Saybrook, CT	Travel to OSI at Old Saybrook, CT
11/8/2009	Travel to site, launch and ready boat.	
11/9/2009	Recover, service, and redeploy equipment at Stations 014, 067 and 102. Collect CTD-OBS vertical profiles and water samples	
11/10/2009	Recover, service, and redeploy equipment at Stations 042 and 135. Collect CTD-OBS vertical profiles and water samples. Calibrate the VMADCP.	Travel to site, launch and ready boat. Recover, service, and redeploy equipment, conduct VMADCP survey, and water samples at Station 175..
11/11/2009	Collect CTD-OBS vertical profiles, water samples and VMADCP at Stations and Transects 014, 042, & 067.	Collect CTD-OBS vertical profiles, water samples and VMADCP at Stations and Transects 102, 067, & 135.
11/12/2009	Travel to OSI at Old Saybrook, CT.	Travel to OSI at Old Saybrook, CT.
12/13/2009	Travel to site, launch and ready boat	Travel to site, launch and ready boat
12/14/2009	Collect CTD-OBS vertical profiles, water samples and VMADCP at Stations and Transects 014, 042, & 067.	Launch boat, collect CTD-OBS vertical profiles, water samples and VMADCP at Stations and Transects 102 & 135.
12/15/2009	Collect CTD-OBS vertical profiles and water samples then recovered equipment and buoys at Stations 135, 102 and 067	Travel to 175, launch and ready boat, Collect CTD-OBS vertical profiles, water samples and VMADCP then recovered instrumentation. Travel back to OSI at Old Saybrook, CT
12/16/2009	Collect CTD-OBS vertical profiles and water samples then recovered equipment and buoys at Stations 042 and 014	
12/17/2009	Travel to OSI at Old Saybrook, CT	

2.3 *In Situ* Instrumentation and Moorings

OSI maintained six CT-OBS mooring buoys and five ADCP bottom moorings throughout the Lower Passaic River and just above the Dundee Dam (Table 1). At each station, two moorings were deployed as seen in Figure 2 except at Station 175 above the Dundee Dam, which consisted of just one CT-OBS mooring buoy. The specific details of the instrumentation deployed are described below. After deployment, before and after servicings, and prior to recovery, OSI conducted CTD-OBS vertical profiles and collected water samples adjacent to the instrument moorings for data quality checks. A water-sampling log including sample locations, date & time, sample depths, and total water depth is available in Appendix 1. Detailed information on instrument operations and data processing procedures is available in Appendix 2. A brief discussion on general instrument calibration procedures is available in Appendix 3.

Table 1. *In Situ* Instrument Mooring Locations

Station	Bottom Moorings		Buoy Moorings	
	Easting	Northing	Easting	Northing
014	597991	691237	597986	691190
042	588246	692301	588277	692311
067	586136	702829	586122	702806
102	592110	719748	592107	719715
135	597205	734298	597193	734263
175	NaN	NaN	594485	747484

Station 175 was located above Dundee Dam and did not included bottom-mounted instrumentation.



Figure 2. ADCP/CT-OBS mooring and CT-OBS surface buoy .

2.3.1 YSI Environmental 6920 Multiparameter Sonde

In situ water quality was documented using YSI Series 6000 (or equivalent) Multiparameter Sondes. A total of eleven sondes were deployed, two at each of the five moorings that were deployed throughout the lower Passaic River and one above Dundee Dam. At each station, one unit was placed 3 feet off the bottom or 3 feet below the surface and programmed to record, temperature, salinity, and turbidity at 12-minute intervals (Figure 3). The one unit placed above the Dundee Dam at Station 175 was located 3 feet below the water surface.

Figure 3. *In situ* CT-OBS and ADCP bottom mooring.

2.3.2 Acoustic Doppler Current Profiler

OSI deployed five ADCPs between 10 - 12 October 2009 and 15-16 December 2009 consisting of three 1200 kHz ADCPs and two 600 kHz ADCPs. The 1200kHz ADCPs were deployed in approximately 15 to 20 feet of water at Stations 067, 102 and 135. The 600kHz ADCPs were deployed in approximately 20 to 30 feet of water at Stations 014 and 042. Each ADCP was secured to a bottom mount in an upward looking position. OSI's custom ADCP mounts are approximately 2.5-feet long by 2.5-feet wide and project less than two feet off the bottom. A gimbal attachment within the collar to the instrument kept the ADCPs plumb. These specialized mounts have no buoys or other surface expression. Each ADCP was programmed to record current velocity and backscatter data at 12-minute intervals using 0.5-meter vertical bins.

2.4 Real-Time Data Collection

Current velocity and water quality data were collected in real-time along six cross-river transects corresponding to the six *in situ* instrument mooring. Current velocity and backscatter data was collected in real-time using a downward looking vessel–mounted 1200kHz ADCP. The ADCP data was collected in 0.5-meter vertical bins. Upon completion of each transect, a Seabird SBE 19 SeaCat water quality vertical profiler equipped to record temperature, salinity, and turbidity was deployed at three locations evenly spaced across each transect (four locations above Dundee Dam). At each of the vertical profile stations, water samples were collected through a pump system attached to the CTD vertical profiler. Water samples were collected 3 feet below the surface and 3 feet above the bottom. All water samples were collected and handled by both the onboard AECOM and EPA representatives. In addition, periodic water samples for POC/DOC analysis were collected.

3.0 DATA DISCUSSION AND PRESENTATION

3.1 Water Sample Data

The water samples collected throughout the field program were analyzed for Suspended Sediment Concentrations (SSC) by Columbia Analytical Services, an EPA approved lab. The lab results of the water samples were amassed by AECOM and will be delivered under separate cover.

3.2 *In Situ* Instrumentation

In situ measurements of current velocity and water quality parameters were recorded continuously from mid October through mid December 2009 with only one minor break in the data during servicing operations in mid November. The data have been processed and presented as time series plots in Appendices 4 (CT-OBS) and 5 (ADCP vertically averaged currents) and are available in Microsoft Excel spreadsheets on the enclosed CD-ROM in Appendix 10.

3.2.1 CT-OBS Water Quality Data

The *in situ* CT-OBS water quality data provided insight into the characteristics of the Passaic River estuary. As typical with a river to tidal dominated estuary, salinity values were in flux with the tide in the lower three stations (Stations 014, 042, & 067), yet under the river flow conditions at the time, the upper two stations of the lower Passaic River (Stations 102 & 135) revealed very low salinity values. The highest recorded salinity was seen at Station 014 on the bottom at 22.36 (PSU) at 13:36 (UTC) on 18 October. Salinity values in the lower three stations saw three significant drops in salinity on 25 October, 29 October, and 10 December directly associated with local weather events. In the lower three stations where salinity tidal fluxes were detected there was also small tidal fluxes in water temperature on the order of 1 to 2 ºC. Temperatures across all six stations slowly came down of the course of the fall deployment ranging from 15 to 17 ºC in October to just under 2 ºC in December. Temperatures tended to be slightly warmer to the south and decrease slowly up the river from south to north. The highest turbidity was 299.6 (NTU) seen at Station 042 at 14:48 (UTC) on 7 December. Turbidity tidal fluxes were common at the lower three stations and small tidal fluxes in turbidity were seen at Station 102. While high values were recorded on the both ebb and flood tides at various times throughout the deployment, the most significant turbidity values were seen during periods of strong flood tidal currents. Figure 4 shows the relationship commonly seen between current direction and fluxes in turbidity values.



Figure 4. Station 042 CT-OBS near bottom turbidity data relative to ADCP current direction.

3.2.2 ADCP Current and Acoustic SSC Data

The *in situ* ADCP current velocity from the five bottom moorings deployed at the lower Passaic River are presented as time series plots of vertically averaged current magnitude and direction (Appendix 5). Current direction was fairly uniform throughout the deployment showing simple bi-directional flow as the tide pulsed in and out of the river. The duration of the incoming (flooding) current changed from station to station. The furthest north ADCP at Station 135 had periods of days when no flood tidal currents were present due to high freshwater discharge from upriver. The most significant event occurred from 24 October through 31 October when Station 135 only experience two slight changes in current direction over 14 tidal cycles.

The strongest recorded currents at each station occurred during the falling tide when freshwater river discharge and tidal drainage combined. The highest recorded flow over the course of this deployment program was recorded at Station 014 at 01:24 (UTC) on 14 December reaching values as high as 99.8 cm/s (~ 1.9 kts). Currents were fairly uniform through the lower four stations with only a small reduction in current magnitudes up the river. However, overall Station 135 magnitudes were significantly reduced as compared to Station 014 by nearly 50%.

3.2.3 Mooring CTD-OBS Vertical Profiles

The CTD-OBS vertical profiles recorded after deployment (Event E01), prior to servicing (Event E05), after redeployment (Event E09), and prior to recovery (Event E10) are presented in Appendix 6. Vertical profiles collected above Dundee Dam were incorporated with the real-time survey events and are listed in the corresponding Appendices listed below.

3.3 Real-Time Survey Events

3.3.1 Vessel Mounted Currents

Current data from the VMADCP are presented as vector plots in Appendix 7 (Trip 1, Events E02-E04), Appendix 8 (Trip 2, Events E06-E08) and Appendix 9 (Trip 3, Events E11-E13). The highest current velocity during the first two real-time surveys was seen during under flood tidal conditions yet due to high river flows the ebb tide had the strongest currents during the Trip 3 real-time surveys. Currents reached as high as 52 cm/sec at Transect 014 for Trip 1, 64 cm/sec at Transect 102 for Trip 2, and 67 cm/sec at Transect 067 for Trip 3. The current magnitude during these mappings varied across the cross-section with lower velocities seen closer to the riverbanks while the highest velocities occurring in the center of each transect. The current magnitude decreased up river with the lowest currents recorded at Station 135 for each mapping. The rain event that occurred before the Trip 3 real-time surveys influenced flow characteristics of the river. The flood tide was weak and was only evident at Stations 014 and 042. Station 067 was slack water during the predicted max flood and Stations 102 and 135 continued to flow down river throughout the rising of the tide.

3.3.2 CTD Vertical Profiles

Data from the CTD-OBS vertical profiles are presented in Appendix 7-9 corresponding to each trip as seen above. CTD-OBS data shows a wide range of turbidity with surface water concentrations ranging from 2 to 22 NTU and bottom concentrations ranging between 9 and 125 NTU. A pycnocline was also observed of which the gradient decreased upriver. Transects 014 & 042 had the highest salinities and the pycnocline was seen at Stations 014, 042 and 067; yet upriver (Stations 102, 135 and 175) there was no pycnocline present resulting in a well-mixed water column. During the Trip 3 mappings the pycnocline was only observed at Transect 014 due to the increase of freshwater from weather events prior to these mappings. Data files of the vertical profiles are available on the enclosed CD-ROM in Appendix 10.

3.4 Project Summary

The low flow oceanographic data acquisition equipment was deployed for a two-month period and three real time boat based surveys were conducted during this time. The *in situ* instrumentation was deployed over six stations; five were located in the lower Passaic River and one above Dundee Dam. The instrumentation was deployed to collect data during a typical low flow period, however, during late October the first of three major rainfalls occurred causing flow rates to increase. These events can be seen in the data where freshwater input affected the salinity at all stations, and had an impact on the current magnitude and direction. At Stations 067, 102 and 135 the flood tide was greatly reduced and at Station 135 a flood tide was not observed during the December 2009 real-time surveys and at various times throughout the *in situ* deployment period. The data revealed that the highest turbidity values at Stations 014 and 042 were seen near the bottom during strong flood tides whereas up the river in areas of reducing or limited salinity the higher turbidity values were present during the higher flow events caused by rainfall. The program successfully documented a range of flow conditions, characterizing the hydrodynamic environment of the lower Passaic River during the fall of 2009.

APPENDIX 1: Water Sampling Log

Water Sampling Log: Events E01-E04
Passaic River, Newark, NJ
Client: AECOM
OSI Job # 09ES053

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
10/12/2009	13:53	597978	691244	09A	E01	T014	P3	AS	15.7	3.0
10/12/2009	13:56	597990	691251	09A	E01	T014	P3	BS	15.7	12.7
10/12/2009	14:12	588238	692294	09A	E01	T042	P1	AS	15.6	3.0
10/12/2009	14:14	588257	692297	09A	E01	T042	P1	BS	15.6	12.6
10/12/2009	15:25	586129	702827	09A	E01	T067	P3	AS	13.1	3.0
10/12/2009	15:28	586147	702831	09A	E01	T067	P3	BS	13.1	10.1
10/12/2009	15:56	592117	719758	09A	E01	T102	P1	AS	14.9	3.0
10/12/2009	15:58	592106	719758	09A	E01	T102	P1	BS	14.9	11.9
10/12/2009	16:21	597198	734305	09A	E01	T135	P3	AS	14.6	3.0
10/12/2009	16:22	597200	734296	09A	E01	T135	P3	BS	14.6	11.6
10/12/2009	16:56	594434	747325	09A	E02	T175	P1	AS	4.0	3.0
10/12/2009	17:13	594484	747519	09A	E02	T175	P2	AS	9.0	3.0
10/12/2009	17:14	594474	747517	09A	E02	T175	P2	BS	9.0	6.0
10/12/2009	17:18	594631	747666	09A	E02	T175	P3	AS	5.0	3.0
10/12/2009	17:22	594681	747740	09A	E02	T175	P4	AS	4.0	3.0
10/13/2009	12:11	597781	691283	09A	E03	T014	P1	AS	15.9	3.0
10/13/2009	12:12	597799	691291	09A	E03	T014	P1	BS	15.9	12.9
10/13/2009	12:20	597905	691238	09A	E03	T014	P2	AS	17.1	3.0
10/13/2009	12:23	597911	691249	09A	E03	T014	P2	BS	17.1	14.1
10/13/2009	12:33	597989	691227	09A	E03	T014	P3	AS	16.0	3.0
10/13/2009	12:36	597993	691230	09A	E03	T014	P3	BS	16.0	13.0
10/13/2009	13:04	588243	692306	09A	E03	T042	P1	AS	16.5	3.0
10/13/2009	13:07	588241	692308	09A	E03	T042	P1	BS	16.5	13.5
10/13/2009	13:16	588234	692396	09A	E03	T042	P2	AS	17.0	3.0
10/13/2009	13:18	588238	692393	09A	E03	T042	P2	BS	17.0	14.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
10/13/2009	13:26	588230	692465	09A	E03	T042	P3	AS	15.2	3.0
10/13/2009	13:56	586006	702927	09A	E03	T067	P1	AS	12.2	3.0
10/13/2009	13:57	586008	702939	09A	E03	T067	P1	BS	12.2	9.2
10/13/2009	14:03	586078	702887	09A	E03	T067	P2	AS	12.8	3.0
10/13/2009	14:04	586077	702882	09A	E03	T067	P2	BS	12.8	9.8
10/13/2009	14:10	586131	702832	09A	E03	T067	P3	AS	12.1	3.0
10/13/2009	14:13	586126	702840	09A	E03	T067	P3	BS	12.1	9.1
10/13/2009	12:35	592106	719745	09A	E03	T102	P1	AS	10.0	3.0
10/13/2009	12:37	592103	719745	09A	E03	T102	P1	BS	10.0	7.0
10/13/2009	12:46	592154	719745	09A	E03	T102	P2	AS	10.0	3.0
10/13/2009	12:47	592153	719745	09A	E03	T102	P2	BS	10.0	7.0
10/13/2009	12:52	592214	719744	09A	E03	T102	P3	AS	10.0	3.0
10/13/2009	12:54	592213	719745	09A	E03	T102	P3	BS	10.0	7.0
10/13/2009	13:34	597073	734357	09A	E03	T135	P1	AS	8.0	3.0
10/13/2009	13:35	597079	734357	09A	E03	T135	P1	BS	8.0	5.0
10/13/2009	13:42	597151	734312	09A	E03	T135	P2	AS	10.0	3.0
10/13/2009	13:44	597152	734316	09A	E03	T135	P2	BS	10.0	7.0
10/13/2009	13:53	597207	734287	09A	E03	T135	P3	AS	14.0	3.0
10/13/2009	13:54	597206	734291	09A	E03	T135	P3	BS	14.0	11.0
10/13/2009	16:58	597791	691291	09A	E04	T014	P1	AS	15.1	3.0
10/13/2009	17:00	597800	691302	09A	E04	T014	P1	BS	15.1	12.1
10/13/2009	17:06	597905	691249	09A	E04	T014	P2	AS	17.3	3.0
10/13/2009	17:08	597910	691262	09A	E04	T014	P2	BS	17.3	14.3
10/13/2009	17:15	597993	691233	09A	E04	T014	P3	AS	15.6	3.0
10/13/2009	17:17	598007	691231	09A	E04	T014	P3	BS	15.6	12.6
10/13/2009	17:41	588231	692289	09A	E04	T042	P1	AS	17.5	3.0
10/13/2009	17:44	588238	692299	09A	E04	T042	P1	BS	17.5	14.5
10/13/2009	17:50	588234	692403	09A	E04	T042	P2	AS	19.2	3.0
10/13/2009	17:52	588231	692395	09A	E04	T042	P2	BS	19.2	16.2
10/13/2009	17:58	588230	692466	09A	E04	T042	P3	AS	17.1	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
10/13/2009	17:59	588230	692467	09A	E04	T042	P3	BS	17.1	14.1
10/13/2009	18:20	586019	702934	09A	E04	T067	P1	AS	15.2	3.0
10/13/2009	18:26	586085	702887	09A	E04	T067	P2	BS	15.6	12.6
10/13/2009	18:32	586130	702846	09A	E04	T067	P3	AS	14.9	3.0
10/13/2009	18:33	586138	702848	09A	E04	T067	P3	BS	14.9	11.9
10/13/2009	17:34	592105	719746	09A	E04	T102	P1	AS	13.0	3.0
10/13/2009	17:36	592105	719744	09A	E04	T102	P1	BS	13.0	10.0
10/13/2009	17:44	592153	719745	09A	E04	T102	P2	AS	14.0	3.0
10/13/2009	17:46	592153	719745	09A	E04	T102	P2	BS	14.0	11.0
10/13/2009	17:50	592215	719745	09A	E04	T102	P3	AS	13.0	3.0
10/13/2009	17:52	592213	719744	09A	E04	T102	P3	BS	13.0	10.0
10/13/2009	19:31	597072	734352	09A	E04	T135	P1	AS	10.0	3.0
10/13/2009	19:32	597074	734356	09A	E04	T135	P1	BS	10.0	7.0
10/13/2009	19:40	597154	734313	09A	E04	T135	P2	AS	14.0	3.0
10/13/2009	19:42	597150	734313	09A	E04	T135	P2	BS	14.0	11.0
10/13/2009	19:50	597202	734286	09A	E04	T135	P3	AS	16.0	3.0
10/13/2009	19:51	597205	734289	09A	E04	T135	P3	BS	16.0	13.0

Water Sampling Log: Events E05-E09
Passaic River, Newark, NJ
Client: AECOM
OSI Job # 09ES053

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
11/09/2009	13:01	597992	691229	09A	E05	T014	P3	AS	20.0	3.0
11/09/2009	13:04	598003	691229	09A	E05	T014	P3	BS	20.0	17.0
11/10/2009	13:19	588257	692301	09A	E05	T042	P1	AS	15.0	3.0
11/10/2009	13:24	588253	692306	09A	E05	T042	P1	BS	15.0	12.0
11/09/2009	16:31	586141	702835	09A	E05	T067	P3	AS	13.0	3.0
11/09/2009	16:34	586148	702833	09A	E05	T067	P3	BS	13.0	10.0
11/09/2009	19:00	592110	719753	09A	E05	T102	P1	AS	17.7	3.0
11/09/2009	19:01	592108	719753	09A	E05	T102	P1	BS	17.7	14.7
11/10/2009	16:30	597215	734289	09A	E05	T135	P3	AS	15.2	3.0
11/10/2009	16:31	597211	734284	09A	E05	T135	P3	BS	15.2	12.3
11/10/2009	16:07	594439	747322	09A	E06	T175	P1	AS	5.0	3.0
11/10/2009	16:19	594474	747518	09A	E06	T175	P2	AS	10.0	3.0
11/10/2009	16:22	594478	747519	09A	E06	T175	P2	BS	10.0	7.0
11/10/2009	16:32	594629	747629	09A	E06	T175	P3	AS	5.0	3.0
11/10/2009	16:43	594685	747740	09A	E06	T175	P4	AS	4.0	3.0
11/11/2009	12:00	597786	691279	09A	E07	T014	P1	AS	15.4	3.0
11/11/2009	12:02	597800	691283	09A	E07	T014	P1	BS	15.4	12.4
11/11/2009	12:08	597908	691236	09A	E07	T014	P2	AS	17.2	3.0
11/11/2009	12:09	597908	691241	09A	E07	T014	P2	BS	17.2	14.2
11/11/2009	12:14	597988	691217	09A	E07	T014	P3	AS	17.0	3.0
11/11/2009	12:16	597979	691216	09A	E07	T014	P3	BS	17.0	14,0
11/11/2009	12:38	588239	692286	09A	E07	T042	P1	AS	16.0	3.0
11/11/2009	12:40	588247	692292	09A	E07	T042	P1	BS	16.0	13.0
11/11/2009	12:47	588234	692401	09A	E07	T042	P2	AS	17.5	3.0
11/11/2009	12:49	588236	692382	09A	E07	T042	P2	BS	17.5	14.5

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
11/11/2009	12:55	588236	692469	09A	E07	T042	P3	AS	16.2	3.0
11/11/2009	12:57	588232	692453	09A	E07	T042	P3	BS	16.2	13.2
11/11/2009	13:26	586033	702928	09A	E07	T067	P1	BS	13.1	10.1
11/11/2009	13:30	586083	702888	09A	E07	T067	P2	AS	13.8	3.0
11/11/2009	13:31	586090	702880	09A	E07	T067	P2	BS	13.8	10.8
11/11/2009	13:37	586140	702844	09A	E07	T067	P3	AS	13.2	3.0
11/11/2009	13:40	586142	702839	09A	E07	T067	P3	BS	13.2	10.2
11/11/2009	13:14	592104	719742	09A	E07	T102	P1	AS	16.0	3.0
11/11/2009	13:16	592102	719742	09A	E07	T102	P1	BS	16.0	13.0
11/11/2009	13:28	592155	719745	09A	E07	T102	P2	AS	16.0	3.0
11/11/2009	13:31	592154	719744	09A	E07	T102	P2	BS	16.0	13.0
11/11/2009	13:38	592213	719743	09A	E07	T102	P3	AS	16.0	3.0
11/11/2009	13:40	592214	719744	09A	E07	T102	P3	BS	16.0	13.0
11/11/2009	12:00	597078	734350	09A	E07	T135	P1	AS	10.0	3.0
11/11/2009	12:02	597077	734351	09A	E07	T135	P1	BS	10.0	7.0
11/11/2009	12:11	597154	734313	09A	E07	T135	P2	AS	14.0	3.0
11/11/2009	12:13	597155	734310	09A	E07	T135	P2	BS	14.0	11.0
11/11/2009	12:25	597203	734287	09A	E07	T135	P3	AS	16.0	2.0
11/11/2009	12:27	597204	734287	09A	E07	T135	P3	BS	16.0	13.0
11/11/2009	16:55	597776	691292	09A	E08	T014	P1	AS	16.8	3.0
11/11/2009	16:56	597773	691289	09A	E08	T014	P1	BS	16.8	13.8
11/11/2009	17:05	597898	691257	09A	E08	T014	P2	AS	16.8	3.0
11/11/2009	17:06	597895	691270	09A	E08	T014	P2	BS	16.8	13.8
11/11/2009	17:11	597976	691234	09A	E08	T014	P3	AS	18.4	3.0
11/11/2009	17:13	597973	691233	09A	E08	T014	P3	BS	18.4	15.4
11/11/2009	17:37	588226	692300	09A	E08	T042	P1	AS	18.3	3.0
11/11/2009	17:39	588228	692294	09A	E08	T042	P1	BS	18.3	15.3
11/11/2009	17:45	588225	692380	09A	E08	T042	P2	AS	20.3	3.0
11/11/2009	17:46	588221	692395	09A	E08	T042	P2	BS	20.3	17.3
11/11/2009	17:51	588234	692454	09A	E08	T042	P3	AS	19.0	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
11/11/2009	17:52	588225	692451	09A	E08	T042	P3	BS	19.0	16.0
11/11/2009	19:36	586021	702932	09A	E08	T067	P1	AS	18.0	3.0
11/11/2009	19:37	586023	702931	09A	E08	T067	P1	BS	18.0	15.0
11/11/2009	19:44	586083	702882	09A	E08	T067	P2	AS	20.0	3.0
11/11/2009	19:55	586135	702830	09A	E08	T067	P3	BS	19.0	16.0
11/11/2009	18:26	592103	719744	09A	E08	T102	P1	AS	20.0	3.0
11/11/2009	18:27	592103	719745	09A	E08	T102	P1	BS	20.0	17.0
11/11/2009	18:34	592151	719745	09A	E08	T102	P2	AS	20.0	3.0
11/11/2009	18:36	592152	719744	09A	E08	T102	P2	BS	20.0	17.0
11/11/2009	18:42	592212	719745	09A	E08	T102	P3	AS	21.0	3.0
11/11/2009	18:44	592214	719745	09A	E08	T102	P3	BS	21.0	18.0
11/11/2009	17:21	597078	734354	09A	E08	T135	P1	AS	12.0	3.0
11/11/2009	17:22	597077	734353	09A	E08	T135	P1	BS	12.0	9.0
11/11/2009	17:30	597152	734314	09A	E08	T135	P2	AS	14.0	3.0
11/11/2009	17:31	597153	734314	09A	E08	T135	P2	BS	14.0	11.0
11/11/2009	17:40	597203	734289	09A	E08	T135	P3	AS	18.0	3.0
11/11/2009	17:41	597203	734288	09A	E08	T135	P3	BS	18.0	15.0
11/09/2009	15:42	597984	691261	09A	E09	T014	P3	AS	20.0	3.0
11/09/2009	15:44	597992	691249	09A	E09	T014	P3	BS	20.0	17.0
11/10/2009	15:41	588246	692292	09A	E09	T042	P1	AS	15.8	3.0
11/10/2009	15:42	588243	692283	09A	E09	T042	P1	BS	15.8	12.8
11/09/2009	18:27	586135	702820	09A	E09	T067	P3	AS	16.5	3.0
11/09/2009	18:28	586140	702825	09A	E09	T067	P3	BS	16.5	13.5
11/09/2009	20:51	592111	719736	09A	E09	T102	P1	AS	17.3	3.0
11/09/2009	20:53	592111	719733	09A	E09	T102	P1	BS	17.3	14.3
11/10/2009	18:18	597212	734296	09A	E09	T135	P3	AS	17.8	3.0
11/10/2009	18:21	597214	734289	09A	E09	T135	P3	BS	17.8	14.8
11/10/2009	17:53	594478	747518	09A	E09	T175	P2	AS	10.0	3.0

Water Sampling Log: Events E10-E13
Passaic River, Newark, NJ
Client: AECOM
OSI Job # 09ES053

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
12/16/2009	14:31	598008	691240	09A	E10	T014	P3	AS	17.0	3.0
12/16/2009	14:33	598004	691240	09A	E10	T014	P3	BS	17.0	14.0
12/16/2009	15:48	588268	692292	09A	E10	T042	P1	AS	18.8	3.0
12/16/2009	15:50	588260	692295	09A	E10	T042	P1	BS	18.8	15.8
12/15/2009	18:36	586131	702843	09A	E10	T067	P3	AS	12.8	3.0
12/15/2009	18:38	586135	702843	09A	E10	T067	P3	BS	12.8	9.8
12/15/2009	16:54	592099	719737	09A	E10	T102	P1	AS	16.1	3.0
12/15/2009	16:55	592096	719739	09A	E10	T102	P1	BS	16.1	13.1
12/15/2009	15:17	597200	734280	09A	E10	T135	P3	AS	17.3	3.0
12/15/2009	15:19	597204	734285	09A	E10	T135	P3	BS	17.3	14.3
12/15/2009	15:20	594441	747322	09A	E11	T175	P1	AS	6.0	3.0
12/15/2009	15:32	594478	747515	09A	E11	T175	P2	AS	11.0	3.0
12/15/2009	15:34	594479	747517	09A	E11	T175	P2	BS	11.0	8.0
12/15/2009	15:46	594631	747628	09A	E11	T175	P3	AS	7.0	3.0
12/15/2009	15:52	594686	747739	09A	E11	T175	P4	AS	6.0	3.0
12/14/2009	14:44	597773	691285	09A	E12	T014	P1	AS	17.0	3.0
12/14/2009	14:45	597788	691276	09A	E12	T014	P1	BS	17.0	14.0
12/14/2009	14:51	597902	691237	09A	E12	T014	P2	AS	15.9	3.0
12/14/2009	14:53	597892	691240	09A	E12	T014	P2	BS	15.9	12.9
12/14/2009	15:00	597975	691211	09A	E12	T014	P3	AS	18.2	3.0
12/14/2009	15:02	597976	691234	09A	E12	T014	P3	BS	18.2	15.2
12/14/2009	15:27	588250	692293	09A	E12	T042	P1	AS	17.1	3.0
12/14/2009	15:29	588262	692292	09A	E12	T042	P1	BS	17.1	14.1
12/14/2009	15:35	588242	692376	09A	E12	T042	P2	AS	18.2	3.0
12/14/2009	15:37	588249	692381	09A	E12	T042	P2	BS	18.2	15.2

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
12/14/2009	15:42	588242	692463	09A	E12	T042	P3	AS	14.3	3.0
12/14/2009	15:44	588242	692473	09A	E12	T042	P3	BS	14.3	11.3
12/14/2009	16:10	586007	702935	09A	E12	T067	P1	AS	14.1	3.0
12/14/2009	16:13	586012	702927	09A	E12	T067	P1	BS	14.1	11.1
12/14/2009	16:20	586065	702884	09A	E12	T067	P2	AS	14.6	3.0
12/14/2009	16:23	586069	702877	09A	E12	T067	P2	BS	14.6	11.6
12/14/2009	16:28	586124	702827	09A	E12	T067	P3	AS	13.7	3.0
12/14/2009	16:30	586129	702826	09A	E12	T067	P3	BS	13.7	10.7
12/14/2009	15:52	592102	719743	09A	E12	T102	P1	AS	18.0	3.0
12/14/2009	15:55	592105	719742	09A	E12	T102	P1	BS	18.0	15.0
12/14/2009	16:04	592151	719744	09A	E12	T102	P2	AS	18.0	3.0
12/14/2009	16:05	592154	719745	09A	E12	T102	P2	BS	18.0	15.0
12/14/2009	16:13	592213	719744	09A	E12	T102	P3	AS	19.0	3.0
12/14/2009	16:17	592214	719746	09A	E12	T102	P3	BS	19.0	16.0
12/14/2009	14:48	597079	734353	09A	E12	T135	P1	AS	14.0	3.0
12/14/2009	14:49	597079	734351	09A	E12	T135	P1	BS	14.0	11.0
12/14/2009	14:59	597152	734314	09A	E12	T135	P2	AS	16.0	3.0
12/14/2009	15:00	597153	734311	09A	E12	T135	P2	BS	16.0	13.0
12/14/2009	15:08	597202	734287	09A	E12	T135	P3	AS	19.0	3.0
12/14/2009	15:10	597204	734285	09A	E12	T135	P3	BS	19.0	16.0
12/14/2009	20:10	597796	691295	09A	E13	T014	P1	AS	15.5	3.0
12/14/2009	20:11	597793	691300	09A	E13	T014	P1	BS	15.5	12.5
12/14/2009	20:16	597901	691260	09A	E13	T014	P2	AS	17.7	3.0
12/14/2009	20:18	597898	691261	09A	E13	T014	P2	BS	17.7	14.7
12/14/2009	20:24	597987	691237	09A	E13	T014	P3	AS	17.1	3.0
12/14/2009	20:26	597994	691232	09A	E13	T014	P3	BS	17.1	14.1
12/14/2009	20:56	588230	692405	09A	E13	T042	P2	BS	19.1	16.1
12/14/2009	21:03	588234	692473	09A	E13	T042	P3	AS	16.9	3.0
12/14/2009	21:05	588231	692469	09A	E13	T042	P3	BS	16.9	13.9
12/14/2009	20:47	588226	692302	09A	E13	T043	P1	AS	17.5	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
12/14/2009	20:49	588235	692289	09A	E13	T043	P1	BS	17.5	14.5
12/14/2009	20:55	588233	692405	09A	E13	T043	P2	AS	19.1	3.0
12/14/2009	21:25	586030	702929	09A	E13	T067	P1	AS	15.0	3.0
12/14/2009	21:26	586036	702937	09A	E13	T067	P1	BS	15.0	12.0
12/14/2009	21:30	586073	702896	09A	E13	T067	P2	AS	16.3	3.0
12/14/2009	21:31	586090	702890	09A	E13	T067	P2	BS	16.3	13.3
12/14/2009	21:36	586139	702845	09A	E13	T067	P3	AS	15.5	3.0
12/14/2009	21:38	586138	702839	09A	E13	T067	P3	BS	15.5	12.5
12/14/2009	21:34	592103	719745	09A	E13	T102	P1	AS	18.0	3.0
12/14/2009	21:36	592103	719746	09A	E13	T102	P1	BS	18.0	15.0
12/14/2009	21:43	592151	719743	09A	E13	T102	P2	AS	19.0	3.0
12/14/2009	21:45	592152	719746	09A	E13	T102	P2	BS	19.0	16.0
12/14/2009	21:54	592213	719742	09A	E13	T102	P3	AS	19.0	3.0
12/14/2009	21:55	592214	719743	09A	E13	T102	P3	BS	19.0	16.0
12/14/2009	20:38	597080	734354	09A	E13	T135	P1	AS	10.0	3.0
12/14/2009	20:49	597153	734313	09A	E13	T135	P2	AS	14.0	3.0
12/14/2009	20:51	597154	734311	09A	E13	T135	P2	BS	14.0	11.0
12/14/2009	20:57	597205	734289	09A	E13	T135	P3	AS	17.0	3.0
12/14/2009	20:59	597203	734289	09A	E13	T135	P3	BS	17.0	14.0

APPENDIX 2: Survey Equipment, Procedures & Data Processing

- Survey Vessel Navigation
- YSI Environmental 6920 Sondes
- Acoustic Doppler Current Profilers
- CTD-Turbidity Vertical Profiling

Survey Vessel Navigation

A Differential Global Positioning System (DGPS) interfaced with the PC-based hydrographic software package HYPACK was used for survey-vessel navigation and positioning. The global positioning system consists of 24 earth-orbiting satellites, which broadcast radio signals to the surface. These signals are used by the GPS receiver to calculate its position based on the signal time delay. Four or more satellite signals are required to accurately calculate the receiver's position. Differential correctors, used to increase vessel position accuracy to ± 1 meter, were received from a USCG beacon transmitter via a radio link. The geodetic positions derived from the DGPS system were converted to the NJ State Plane Coordinate system, East zone (NAD83, feet) for survey operations and preparation of final products.

The OSI navigation system consists of a portable personal computer with HYPACK software installed. Geodetic coordinate information from the DGPS was updated at one-second intervals and input to the navigation computer, which processed the geodetic position data into State Plane Coordinates used to guide the survey vessel. The incoming data are logged on disk and processed in real time allowing the vessel position to be displayed on a video monitor and compared to pre-plotted trackline and positions as the survey progresses. Digitized shoreline and the locations of existing structures, buoys, and control points can also be displayed on the monitor in relation to the vessel position. This system provides a highly accurate visual representation of survey vessel location in real time, combined with data logging capabilities and post-survey data processing and plotting.

YSI Environmental 6920 Sonde

The YSI 6920 Sondes (dataloggers) are self-contained microprocessors that record conductivity and temperature, from which salinity was calculated. The temperature probe utilizes sintered metallic oxides, which change resistance with temperature variations. These thermistors are accurate to +/- 0.15 ºC. Specific conductance is calculated through a direct

relationship between water temperature and conductivity. The conductivity of a solution is measured through a cell with four pure nickel electrodes. Two electrodes are current driven, and two are used to measure the voltage drop. The measured voltage drop is then converted into a conductance value. The accuracy of the conductance readings is 0.5%. Turbidity data were recorded using the 6136 fouling-resistant turbidity sensor. It provides accurate *in situ* measurements of turbidity in fresh, brackish, and saltwater, and features a mechanical self-wiping capability for long-term monitoring. The turbidity probe is accurate to +/-2% of the reading or 0.3 NTU, whichever is greater. Long-term deployments with these sensors, as part of YSI's submersible, multi-parameter water quality monitoring systems, have demonstrated constant measurement accuracy and stability.

The raw data from the dataloggers were downloaded in a binary form and converted to engineering units in YSI's EcoWatch software. The data were then transferred and processed in Microsoft Excel where salinity were calculated from the recorded temperature and conductivity data.

Acoustic Doppler Current Profilers (ADCPs)

Three self-contained, internally logging Acoustic Doppler Current Profilers (ADCPs) were deployed in an upward looking configuration on an OSI-designed bottom mount equipped with a gimble to accommodate slope at the deployment site. The ADCPs were programmed to measure and record water velocity profiles at 12-minute intervals with a vertical resolution of 0.5 meters. The ADCP contains four transducers that simultaneously transmit and receive sonic pulses at sound frequencies of 600 kHz or 1200 kHz, depending on the selected instrument. The transducer faces are angled 20° away from vertical and are evenly spaced around the head of the instrument in a "Janus" configuration.

To measure water velocity, the instrument sends out a coded series of sonic pulses (a ping) at a predetermined rate and measures the Doppler shift of these pings as they reflect off particles suspended in the water column. (On average, suspended particles move with the same velocity as the water in which they are suspended). Data from a minimum of three transducers are required to calculate a three-dimensional current vector from the measurements of Doppler shift. The fourth transducer provides redundant data which aids in reducing errors in the vertical component of velocity and helps to ensure that there are at least three beams available to compute the horizontal components of velocity at all times.

Single ping velocity errors are too large to meet most measurement requirements. Therefore, many pings are averaged into ping ensembles. After a preset number of pings (an ensemble) is transmitted and received, these measurements are averaged over the length of the ensemble.

By range-gating the echo signal, the ADCP divides the velocity profile into uniform segments called depth cells (or bins). Unlike conventional eularian current meters, ADCPs do not make point measurements of small, localized volumes of water at individual depths. Instead, they perform a weighted average of the velocity field over a depth range slightly larger than the nominal thickness of an entire depth cell. Data collected from the center of

each cell are more heavily weighted than data collected at the overlapping fringes of each cell. Averaging the velocity field in this way reduces measurement uncertainty and spatial aliasing. Furthermore, the overlapping nature of the depth cells combined with the weighted averaging within the cells ensures complete water column coverage and presents a smoother, more representative current profile.

CTD-Turbidity Vertical Profiling

Conductivity, temperature, turbidity, and pH data were collected using a Sea-Bird Electronics, Inc. Model SBE 19 SEACAT Profiler. The SEACAT Profiler is a self-powered, self-contained micro processing unit capable of collecting turbidity, temperature, salinity, and depth data at a rate of two scans per second. Data are internally processed, corrected, and recorded in solid-state memory and can later be transferred via an RS-232 port to a computer where the operator can view the data and archive it for future processing.

To collect a cast, the SEACAT was first lowered over the side of the vessel into the water where it was allowed to equilibrate with the surrounding water. The instrument was initialized and then lowered through the water column to the bottom. Once at the bottom, the SEACAT was held steady for one minute, then returned to the surface.

Water quality data collected by the SEACAT Profiler were downloaded to a computer and post-processed using Sea-Bird Electronics CTD Data Acquisition Software, Seasoft Version 4.238. The raw data were calibration corrected and reduced to listings of depth versus turbidity (NTU), temperature (°C), salinity (PSU), pH and calculated SSC.

APPENDIX 3: Instrument Calibration

- General Instrument Calibration
    - ADCPs
    - CTD-OBS and CT-OBS Instrumentation

General Instrumentation Calibration

ADCPs

TRDI ADCP's transducers are factory calibrated during their production and do not require follow up calibration unless the instrument has undergone a tremendous stress or experiences some form of internal electronic failure. Internal tests prior to deployment, verify that each ADCP is operating correctly. The internal compass for the deployed ADCPs were calibrated at OSI following the manufactures calibration procedures. The internal compass of the vessel-mounted ADCPs were calibrated in the field, on the water, prior to real-time surveys.

CTD-OBS and CT-OBS Instrumentation

The Seabird CTD-OBS vertical profilers are factory calibrated on a yearly basis for conductivity, temperature, and depth. YSI sondes (CT-OBS) are factory calibrated for temperature. The YSI sondes' and CTDs' OBS sensors were calibrated by OSI with fixed standardized turbidity calibration solutions prior to their use on this project. Likewise, the conductivity probe of the YSI sondes were also calibrated by OSI prior to the project using fixed standardized calibration solutions.

APPENDIX 4: YSI Water Quality Time Series Plots

Temperature, Salinity and Turbidity

- Station 014
- Station 042
- Station 067
- Station 102
- Station 135
- Station 175

In Situ Water Quality Data
Station 014: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 014: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 014: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 014: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 014: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 014: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 014: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 014: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 014: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 014: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 067: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 067: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 067: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 067: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 067: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 067: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 067: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 067: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 067: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 067: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 102: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 102: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 102: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 102: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 135: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 135: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 135: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 135: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 135: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 135: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 135: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 135: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 135: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 135: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 175: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 175: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 175: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 175: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 175: 3ft Below Surface
Passaic River, NJ



APPENDIX 5: *In Situ* ADCP Time Series Plots

Vertically Averaged

Current Magnitude and Direction

- Station 014
- Station 042
- Station 067
- Station 102
- Station 135

In Situ ADCP Current Data
Station 014
Passaic River, NJ



In Situ ADCP Current Data
Station 014
Passaic River, NJ





In Situ ADCP Current Data
Station 014
Passaic River, NJ



In Situ ADCP Current Data
Station 014
Passaic River, NJ



In Situ ADCP Current Data
Station 014
Passaic River, NJ





In Situ ADCP Current Data
Station 042
Passaic River, NJ



In Situ ADCP Current Data
Station 042
Passaic River, NJ





In Situ ADCP Current Data
Station 042
Passaic River, NJ



In Situ ADCP Current Data
Station 042
Passaic River, NJ



In Situ ADCP Current Data
Station 042
Passaic River, NJ





In Situ ADCP Current Data
Station 067
Passaic River, NJ





In Situ ADCP Current Data
Station 067
Passaic River, NJ





In Situ ADCP Current Data
Station 067
Passaic River, NJ





In Situ ADCP Current Data
Station 067
Passaic River, NJ





In Situ ADCP Current Data
Station 067
Passaic River, NJ





In Situ ADCP Current Data
Station 102
Passaic River, NJ





In Situ ADCP Current Data
Station 102
Passaic River, NJ





In Situ ADCP Current Data
Station 102
Passaic River, NJ





In Situ ADCP Current Data
Station 102
Passaic River, NJ





In Situ ADCP Current Data
Station 102
Passaic River, NJ





In Situ ADCP Current Data
Station 135
Passaic River, NJ



In Situ ADCP Current Data
Station 135
Passaic River, NJ





In Situ ADCP Current Data
Station 135
Passaic River, NJ





In Situ ADCP Current Data
Station 135
Passaic River, NJ



In Situ ADCP Current Data
Station 135
Passaic River, NJ





APPENDIX 6: Mooring CTD-OBS Vertical Profiles

Events E01, E05, E09, & E10

Presented Per Trip

- Station 014
- Station 042
- Station 067
- Station 102
- Station 135
- Station 175

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E01-T014-P3

10/12/09 13:50 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.15
Max Temp:	17.10
Avg Temp:	16.58
Min Cond:	15.25
Max Cond:	26.62
Avg Cond:	20.66
Min Salinity:	11.22
Max Salinity:	19.56
Avg Salinity:	15.07
Min Sigma-Theta:	7.51
Max Sigma-Theta:	13.68
Avg Sigma-Theta:	10.37
Min Turbidity:	8.34
Max Turbidity:	9.89
Avg Turbidity:	9.21

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E01-T042-P1

10/12/09 14:09 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.77
Max Temp:	16.38
Avg Temp:	15.66
Min Cond:	7.30
Max Cond:	13.14
Avg Cond:	9.08
Min Salinity:	5.05
Max Salinity:	9.23
Avg Salinity:	6.34
Min Sigma-Theta:	2.92
Max Sigma-Theta:	5.95
Avg Sigma-Theta:	3.89
Min Turbidity:	9.48
Max Turbidity:	10.65
Avg Turbidity:	10.17

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E01-T067-P3

10/12/09 15:24 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.29
Max Temp:	15.85
Avg Temp:	15.51
Min Cond:	1.25
Max Cond:	4.61
Avg Cond:	2.34
Min Salinity:	0.82
Max Salinity:	3.05
Avg Salinity:	1.51
Min Sigma-Theta:	-0.32
Max Sigma-Theta:	1.34
Avg Sigma-Theta:	0.19
Min Turbidity:	18.00
Max Turbidity:	33.97
Avg Turbidity:	24.31

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E01-T102-P1

10/12/09 15:52 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.50
Max Temp:	15.57
Avg Temp:	15.53
Min Cond:	0.57
Max Cond:	0.57
Avg Cond:	0.57
Min Salinity:	0.34
Max Salinity:	0.34
Avg Salinity:	0.34
Min Sigma-Theta:	-0.72
Max Sigma-Theta:	-0.71
Avg Sigma-Theta:	-0.72
Min Turbidity:	18.46
Max Turbidity:	32.55
Avg Turbidity:	22.52

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E01-T135-P3

10/12/09 16:18 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.62
Max Temp:	15.66
Avg Temp:	15.63
Min Cond:	0.53
Max Cond:	0.54
Avg Cond:	0.54
Min Salinity:	0.32
Max Salinity:	0.32
Avg Salinity:	0.32
Min Sigma-Theta:	-0.75
Max Sigma-Theta:	-0.74
Avg Sigma-Theta:	-0.75
Min Turbidity:	6.13
Max Turbidity:	8.54
Avg Turbidity:	7.49

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E05-T014-P3

11/09/09 12:57 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	8.99
Max Temp:	12.60
Avg Temp:	11.01
Min Cond:	3.63
Max Cond:	19.11
Avg Cond:	10.26
Min Salinity:	2.82
Max Salinity:	15.28
Avg Salinity:	8.11
Min Sigma-Theta:	2.01
Max Sigma-Theta:	11.23
Avg Sigma-Theta:	5.89
Min Turbidity:	13.03
Max Turbidity:	20.54
Avg Turbidity:	17.62

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E05-T042-P1

11/10/09 13:15 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.00
Max Temp:	10.95
Avg Temp:	10.24
Min Cond:	0.84
Max Cond:	6.92
Avg Cond:	2.75
Min Salinity:	0.59
Max Salinity:	5.71
Avg Salinity:	2.10
Min Sigma-Theta:	0.16
Max Sigma-Theta:	3.49
Avg Sigma-Theta:	1.26
Min Turbidity:	20.02
Max Turbidity:	28.87
Avg Turbidity:	23.38

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E05-T067-P3

11/09/09 16:28 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.77
Max Temp:	9.93
Avg Temp:	9.81
Min Cond:	0.69
Max Cond:	0.88
Avg Cond:	0.83
Min Salinity:	0.41
Max Salinity:	0.62
Avg Salinity:	0.56
Min Sigma-Theta:	0.06
Max Sigma-Theta:	0.21
Avg Sigma-Theta:	0.16
Min Turbidity:	33.53
Max Turbidity:	74.95
Avg Turbidity:	51.63

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E05-T102-P1

11/09/09 18:58 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.69
Max Temp:	10.02
Avg Temp:	9.81
Min Cond:	0.36
Max Cond:	0.37
Avg Cond:	0.36
Min Salinity:	0.25
Max Salinity:	0.25
Avg Salinity:	0.25
Min Sigma-Theta:	-0.10
Max Sigma-Theta:	-0.08
Avg Sigma-Theta:	-0.09
Min Turbidity:	9.43
Max Turbidity:	10.97
Avg Turbidity:	10.11

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E05-T135-P3

11/10/09 16:27 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.37
Max Temp:	10.73
Avg Temp:	10.50
Min Cond:	0.38
Max Cond:	0.39
Avg Cond:	0.39
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-0.15
Max Sigma-Theta:	-0.13
Avg Sigma-Theta:	-0.14
Min Turbidity:	5.74
Max Turbidity:	8.64
Avg Turbidity:	7.23

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E09-T014-P3

11/09/09 15:37 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.67
Max Temp:	12.62
Avg Temp:	12.38
Min Cond:	9.33
Max Cond:	19.41
Avg Cond:	16.84
Min Salinity:	7.22
Max Salinity:	15.53
Avg Salinity:	13.39
Min Sigma-Theta:	5.14
Max Sigma-Theta:	11.42
Avg Sigma-Theta:	9.81
Min Turbidity:	12.44
Max Turbidity:	38.92
Avg Turbidity:	23.80

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E09-T042-P1

11/10/09 15:37 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.17
Max Temp:	11.59
Avg Temp:	10.47
Min Cond:	0.85
Max Cond:	12.05
Avg Cond:	3.81
Min Salinity:	0.58
Max Salinity:	9.51
Avg Salinity:	2.93
Min Sigma-Theta:	0.08
Max Sigma-Theta:	6.93
Avg Sigma-Theta:	1.94
Min Turbidity:	13.41
Max Turbidity:	88.27
Avg Turbidity:	27.79

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E09-T067-P3

11/09/09 18:25 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.03
Max Temp:	10.33
Avg Temp:	10.12
Min Cond:	0.86
Max Cond:	2.13
Avg Cond:	1.65
Min Salinity:	0.59
Max Salinity:	1.56
Avg Salinity:	1.19
Min Sigma-Theta:	0.11
Max Sigma-Theta:	0.92
Avg Sigma-Theta:	0.62
Min Turbidity:	14.04
Max Turbidity:	22.01
Avg Turbidity:	19.68

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E09-T102-P1

11/09/09 20:49 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.80
Max Temp:	10.74
Avg Temp:	10.00
Min Cond:	0.36
Max Cond:	0.37
Avg Cond:	0.37
Min Salinity:	0.24
Max Salinity:	0.25
Avg Salinity:	0.25
Min Sigma-Theta:	-0.11
Max Sigma-Theta:	-0.09
Avg Sigma-Theta:	-0.10
Min Turbidity:	6.05
Max Turbidity:	15.19
Avg Turbidity:	9.35

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E09-T135-P3

11/10/09 18:16 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.15
Max Temp:	10.87
Avg Temp:	10.50
Min Cond:	0.35
Max Cond:	0.41
Avg Cond:	0.38
Min Salinity:	0.21
Max Salinity:	0.27
Avg Salinity:	0.26
Min Sigma-Theta:	-0.61
Max Sigma-Theta:	-0.13
Avg Sigma-Theta:	-0.17
Min Turbidity:	6.14
Max Turbidity:	6.88
Avg Turbidity:	6.55

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E10-T014-P3

12/16/09 14:28 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	3.42
Max Temp:	7.63
Avg Temp:	4.80
Min Cond:	3.18
Max Cond:	20.03
Avg Cond:	8.58
Min Salinity:	2.91
Max Salinity:	18.43
Avg Salinity:	7.96
Min Sigma-Theta:	2.31
Max Sigma-Theta:	14.33
Avg Sigma-Theta:	6.27
Min Turbidity:	12.43
Max Turbidity:	15.93
Avg Turbidity:	14.01

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E10-T042-P1

12/16/09 15:43 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	3.40
Max Temp:	5.60
Avg Temp:	3.79
Min Cond:	0.67
Max Cond:	11.62
Avg Cond:	2.91
Min Salinity:	0.57
Max Salinity:	10.83
Avg Salinity:	2.65
Min Sigma-Theta:	0.43
Max Sigma-Theta:	8.53
Avg Sigma-Theta:	2.09
Min Turbidity:	20.23
Max Turbidity:	29.11
Avg Turbidity:	24.78

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E10-T067-P3

12/15/09 18:33 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	3.23
Max Temp:	4.30
Avg Temp:	3.56
Min Cond:	0.26
Max Cond:	0.27
Avg Cond:	0.27
Min Salinity:	0.20
Max Salinity:	0.22
Avg Salinity:	0.22
Min Sigma-Theta:	0.14
Max Sigma-Theta:	0.15
Avg Sigma-Theta:	0.15
Min Turbidity:	18.81
Max Turbidity:	25.50
Avg Turbidity:	22.31

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E10-T102-P1

12/15/09 16:52 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	3.15
Max Temp:	4.46
Avg Temp:	3.40
Min Cond:	0.26
Max Cond:	0.27
Avg Cond:	0.26
Min Salinity:	0.20
Max Salinity:	0.22
Avg Salinity:	0.21
Min Sigma-Theta:	0.14
Max Sigma-Theta:	0.15
Avg Sigma-Theta:	0.14
Min Turbidity:	11.66
Max Turbidity:	16.01
Avg Turbidity:	14.68

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E10-T135-P3

12/15/09 15:14 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	3.12
Max Temp:	3.34
Avg Temp:	3.19
Min Cond:	0.26
Max Cond:	0.27
Avg Cond:	0.26
Min Salinity:	0.21
Max Salinity:	0.22
Avg Salinity:	0.21
Min Sigma-Theta:	0.14
Max Sigma-Theta:	0.15
Avg Sigma-Theta:	0.14
Min Turbidity:	11.39
Max Turbidity:	13.48
Avg Turbidity:	12.72

APPENDIX 7: Trip 1 Real Time Survey Events E02-E04

- Vertically Averaged Current Vector Plots
- CTD-OBS Vertical Profiles



LEGEND FOR CURRENT VELOCITY MAPPINGS:

CURRENT VECTOR SCALE
1" = 150 CM/S

SCALE : 1"=750'
750 0 750

NOTES:

1. GRID SYSTEM IS IN FEET AND IS THE NEW JERSEY STATE PLANE COORDINATE SYSTEM, NAD83.
2. ORTHOPHOTO IMAGERY ARE TRUE COLOR ONE FOOT GROUND SAMPLE DISTANCE IMAGES PRODUCED FROM AERIAL PHOTOS FLOWN IN 2007 AND OBTAINED FROM THE NEW JERSEY GEOGRAPHIC INFORMATION NETWORK (NJGIN).
3. THE INFORMATION PRESENTED ON THESE DRAWINGS REPRESENTS THE RESULTS OF A SURVEY PEFORMED BY OCEAN SURVEYS, INC. ON 12–13 OCTOBER 2009 AND CAN ONLY BE CONSIDERED AS INDICATING THE CONDITIONS EXISTING AT THAT TIME. REUSE OF THIS INFORMATION BY CLIENT OF OTHERS BEYOND THE SCOPE OF WORK FOR WHICH IT WAS ACQUIRED SHALL BE AT THE SOLE RISK OF THE USER AND WITHOUT LIABILITY TO OSI.

OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388–4631
www.oceansurveys.com

Vertically Averaged Current Data
Program 09A, Location Map & Event 02
12-13 October 2009
Passaic River, New Jersey



OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388-4631
www.oceansurveys.com

Vertically Averaged Current Data - Ebb Tide
Program 09A, Event 03
13 October 2009, 11:46 - 13:19 (UTC) Hours
Passaic River, New Jersey



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Flood Tide
Program 09A, Event 04
13 October 2009, 16:43 - 19:15 (UTC) Hours
Passaic River, New Jersey

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E02-T175-P1

10/12/09 16:55 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.74
Max Temp:	14.78
Avg Temp:	14.76
Min Cond:	0.54
Max Cond:	0.54
Avg Cond:	0.54
Min Salinity:	0.33
Max Salinity:	0.34
Avg Salinity:	0.33
Min Sigma-Theta:	-0.61
Max Sigma-Theta:	-0.60
Avg Sigma-Theta:	-0.61
Min Turbidity:	4.43
Max Turbidity:	5.39
Avg Turbidity:	5.10

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E02-T175-P2

10/12/09 17:07 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.66
Max Temp:	14.72
Avg Temp:	14.69
Min Cond:	0.53
Max Cond:	0.54
Avg Cond:	0.54
Min Salinity:	0.33
Max Salinity:	0.35
Avg Salinity:	0.33
Min Sigma-Theta:	-0.60
Max Sigma-Theta:	-0.59
Avg Sigma-Theta:	-0.60
Min Turbidity:	2.16
Max Turbidity:	3.75
Avg Turbidity:	3.08

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E02-T175-P3

10/12/09 17:16 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.69
Max Temp:	14.70
Avg Temp:	14.69
Min Cond:	0.54
Max Cond:	0.54
Avg Cond:	0.54
Min Salinity:	0.32
Max Salinity:	0.33
Avg Salinity:	0.33
Min Sigma-Theta:	-0.60
Max Sigma-Theta:	-0.60
Avg Sigma-Theta:	-0.60
Min Turbidity:	3.04
Max Turbidity:	3.38
Avg Turbidity:	3.16

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E02-T175-P4

10/12/09 17:22 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.67
Max Temp:	14.67
Avg Temp:	14.67
Min Cond:	0.54
Max Cond:	0.54
Avg Cond:	0.54
Min Salinity:	0.32
Max Salinity:	0.33
Avg Salinity:	0.32
Min Sigma-Theta:	-0.59
Max Sigma-Theta:	-0.59
Avg Sigma-Theta:	-0.59
Min Turbidity:	2.86
Max Turbidity:	3.91
Avg Turbidity:	3.21

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E03-T014-P1

10/13/09 12:04 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.13
Max Temp:	16.54
Avg Temp:	16.33
Min Cond:	21.23
Max Cond:	25.57
Avg Cond:	23.30
Min Salinity:	15.79
Max Salinity:	18.98
Avg Salinity:	17.26
Min Sigma-Theta:	11.01
Max Sigma-Theta:	13.35
Avg Sigma-Theta:	12.09
Min Turbidity:	10.78
Max Turbidity:	13.42
Avg Turbidity:	12.31

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E03-T014-P2

10/13/09 12:18 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.13
Max Temp:	16.60
Avg Temp:	16.34
Min Cond:	20.89
Max Cond:	26.16
Avg Cond:	22.85
Min Salinity:	15.52
Max Salinity:	19.45
Avg Salinity:	16.92
Min Sigma-Theta:	10.79
Max Sigma-Theta:	13.71
Avg Sigma-Theta:	11.84
Min Turbidity:	9.00
Max Turbidity:	11.98
Avg Turbidity:	10.39

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E03-T014-P3

10/13/09 12:29 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.08
Max Temp:	16.56
Avg Temp:	16.26
Min Cond:	20.37
Max Cond:	26.03
Avg Cond:	22.45
Min Salinity:	15.04
Max Salinity:	19.35
Avg Salinity:	16.65
Min Sigma-Theta:	10.44
Max Sigma-Theta:	13.63
Avg Sigma-Theta:	11.64
Min Turbidity:	9.21
Max Turbidity:	12.28
Avg Turbidity:	10.45

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E03-T042-P1

10/13/09 13:00 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.68
Max Temp:	16.31
Avg Temp:	15.87
Min Cond:	10.16
Max Cond:	19.94
Avg Cond:	13.97
Min Salinity:	7.12
Max Salinity:	14.55
Avg Salinity:	10.01
Min Sigma-Theta:	4.46
Max Sigma-Theta:	10.02
Avg Sigma-Theta:	6.64
Min Turbidity:	10.01
Max Turbidity:	13.17
Avg Turbidity:	11.74

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E03-T042-P2

10/13/09 13:14 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.68
Max Temp:	16.31
Avg Temp:	15.87
Min Cond:	10.19
Max Cond:	20.84
Avg Cond:	13.79
Min Salinity:	7.14
Max Salinity:	15.26
Avg Salinity:	9.87
Min Sigma-Theta:	4.47
Max Sigma-Theta:	10.57
Avg Sigma-Theta:	6.53
Min Turbidity:	9.87
Max Turbidity:	11.82
Avg Turbidity:	10.84

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E03-T042-P3

10/13/09 13:23 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.67
Max Temp:	16.20
Avg Temp:	15.82
Min Cond:	10.05
Max Cond:	17.84
Avg Cond:	12.67
Min Salinity:	7.03
Max Salinity:	12.92
Avg Salinity:	9.01
Min Sigma-Theta:	4.40
Max Sigma-Theta:	8.80
Avg Sigma-Theta:	5.88
Min Turbidity:	10.41
Max Turbidity:	13.47
Avg Turbidity:	12.35

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E03-T067-P1

10/13/09 13:53 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.22
Max Temp:	15.63
Avg Temp:	15.31
Min Cond:	2.58
Max Cond:	7.13
Avg Cond:	3.91
Min Salinity:	1.67
Max Salinity:	4.87
Avg Salinity:	2.60
Min Sigma-Theta:	0.35
Max Sigma-Theta:	2.75
Avg Sigma-Theta:	1.06
Min Turbidity:	17.95
Max Turbidity:	25.15
Avg Turbidity:	21.84

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E03-T067-P2

10/13/09 14:01 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.86
Max Temp:	15.60
Avg Temp:	15.19
Min Cond:	2.53
Max Cond:	7.41
Avg Cond:	3.76
Min Salinity:	1.64
Max Salinity:	5.08
Avg Salinity:	2.50
Min Sigma-Theta:	0.36
Max Sigma-Theta:	2.92
Avg Sigma-Theta:	1.00
Min Turbidity:	19.47
Max Turbidity:	23.92
Avg Turbidity:	21.16

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E03-T067-P3

10/13/09 14:08 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.15
Max Temp:	15.47
Avg Temp:	15.23
Min Cond:	2.35
Max Cond:	6.46
Avg Cond:	3.24
Min Salinity:	1.52
Max Salinity:	4.40
Avg Salinity:	2.14
Min Sigma-Theta:	0.25
Max Sigma-Theta:	2.41
Avg Sigma-Theta:	0.71
Min Turbidity:	19.51
Max Turbidity:	24.62
Avg Turbidity:	21.93

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E03-T102-P1

10/13/09 12:32 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.87
Max Temp:	14.93
Avg Temp:	14.91
Min Cond:	0.55
Max Cond:	0.55
Avg Cond:	0.55
Min Salinity:	0.34
Max Salinity:	0.34
Avg Salinity:	0.34
Min Sigma-Theta:	-0.63
Max Sigma-Theta:	-0.62
Avg Sigma-Theta:	-0.62
Min Turbidity:	12.35
Max Turbidity:	16.73
Avg Turbidity:	13.84

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E03-T102-P2

10/13/09 12:43 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.91
Max Temp:	14.93
Avg Temp:	14.92
Min Cond:	0.54
Max Cond:	0.55
Avg Cond:	0.55
Min Salinity:	0.34
Max Salinity:	0.34
Avg Salinity:	0.34
Min Sigma-Theta:	-0.63
Max Sigma-Theta:	-0.62
Avg Sigma-Theta:	-0.63
Min Turbidity:	15.01
Max Turbidity:	17.43
Avg Turbidity:	16.18

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E03-T102-P3

10/13/09 12:50 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.94
Max Temp:	14.95
Avg Temp:	14.94
Min Cond:	0.55
Max Cond:	0.56
Avg Cond:	0.56
Min Salinity:	0.34
Max Salinity:	0.34
Avg Salinity:	0.34
Min Sigma-Theta:	-0.64
Max Sigma-Theta:	-0.63
Avg Sigma-Theta:	-0.63
Min Turbidity:	17.20
Max Turbidity:	19.64
Avg Turbidity:	18.39

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E03-T135-P1

10/13/09 12:31 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.24
Max Temp:	14.26
Avg Temp:	14.25
Min Cond:	0.56
Max Cond:	0.56
Avg Cond:	0.56
Min Salinity:	0.34
Max Salinity:	0.34
Avg Salinity:	0.34
Min Sigma-Theta:	-0.52
Max Sigma-Theta:	-0.52
Avg Sigma-Theta:	-0.52
Min Turbidity:	5.08
Max Turbidity:	5.90
Avg Turbidity:	5.43

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E03-T135-P2

10/13/09 12:39 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.27
Max Temp:	14.30
Avg Temp:	14.28
Min Cond:	0.55
Max Cond:	0.56
Avg Cond:	0.56
Min Salinity:	0.34
Max Salinity:	0.34
Avg Salinity:	0.34
Min Sigma-Theta:	-0.53
Max Sigma-Theta:	-0.53
Avg Sigma-Theta:	-0.53
Min Turbidity:	4.61
Max Turbidity:	6.00
Avg Turbidity:	5.56

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E03-T135-P3

10/13/09 12:49 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.28
Max Temp:	14.30
Avg Temp:	14.29
Min Cond:	0.55
Max Cond:	0.55
Avg Cond:	0.55
Min Salinity:	0.34
Max Salinity:	0.34
Avg Salinity:	0.34
Min Sigma-Theta:	-0.53
Max Sigma-Theta:	-0.53
Avg Sigma-Theta:	-0.53
Min Turbidity:	5.02
Max Turbidity:	5.80
Avg Turbidity:	5.39

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E04-T014-P1

10/13/09 16:56 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.29
Max Temp:	16.59
Avg Temp:	16.45
Min Cond:	18.49
Max Cond:	26.98
Avg Cond:	24.49
Min Salinity:	11.69
Max Salinity:	20.11
Avg Salinity:	17.85
Min Sigma-Theta:	7.48
Max Sigma-Theta:	14.21
Avg Sigma-Theta:	12.49
Min Turbidity:	8.26
Max Turbidity:	45.64
Avg Turbidity:	19.33

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E04-T014-P2

10/13/09 17:03 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.35
Max Temp:	16.52
Avg Temp:	16.42
Min Cond:	17.99
Max Cond:	26.56
Avg Cond:	23.89
Min Salinity:	10.29
Max Salinity:	19.80
Avg Salinity:	17.44
Min Sigma-Theta:	7.26
Max Sigma-Theta:	13.99
Avg Sigma-Theta:	12.28
Min Turbidity:	7.19
Max Turbidity:	19.67
Avg Turbidity:	10.30

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E04-T014-P3

10/13/09 17:11 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.32
Max Temp:	16.52
Avg Temp:	16.41
Min Cond:	20.20
Max Cond:	26.28
Avg Cond:	23.64
Min Salinity:	11.59
Max Salinity:	19.57
Avg Salinity:	16.93
Min Sigma-Theta:	6.18
Max Sigma-Theta:	13.81
Avg Sigma-Theta:	11.52
Min Turbidity:	7.32
Max Turbidity:	28.46
Avg Turbidity:	14.46

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E04-T042-P1

10/13/09 17:37 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.07
Max Temp:	16.39
Avg Temp:	16.19
Min Cond:	10.96
Max Cond:	18.17
Avg Cond:	13.97
Min Salinity:	7.62
Max Salinity:	13.19
Avg Salinity:	9.95
Min Sigma-Theta:	4.71
Max Sigma-Theta:	9.01
Avg Sigma-Theta:	6.53
Min Turbidity:	10.36
Max Turbidity:	56.77
Avg Turbidity:	23.44

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E04-T042-P2

10/13/09 17:47 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.14
Max Temp:	16.25
Avg Temp:	16.21
Min Cond:	11.57
Max Cond:	19.27
Avg Cond:	15.48
Min Salinity:	8.09
Max Salinity:	14.04
Avg Salinity:	11.10
Min Sigma-Theta:	5.11
Max Sigma-Theta:	9.65
Avg Sigma-Theta:	7.41
Min Turbidity:	11.27
Max Turbidity:	57.40
Avg Turbidity:	30.11

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E04-T042-P3

10/13/09 17:57 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.18
Max Temp:	16.29
Avg Temp:	16.23
Min Cond:	12.47
Max Cond:	19.41
Avg Cond:	16.41
Min Salinity:	8.73
Max Salinity:	14.14
Avg Salinity:	11.81
Min Sigma-Theta:	5.60
Max Sigma-Theta:	9.72
Avg Sigma-Theta:	7.95
Min Turbidity:	14.41
Max Turbidity:	46.24
Avg Turbidity:	25.45

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E04-T067-P1

10/13/09 18:18 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.74
Max Temp:	15.75
Avg Temp:	15.74
Min Cond:	7.22
Max Cond:	7.54
Avg Cond:	7.44
Min Salinity:	4.94
Max Salinity:	5.15
Avg Salinity:	5.09
Min Sigma-Theta:	2.78
Max Sigma-Theta:	2.94
Avg Sigma-Theta:	2.90
Min Turbidity:	30.01
Max Turbidity:	57.05
Avg Turbidity:	41.80

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E04-T067-P2

10/13/09 18:24 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.77
Max Temp:	15.78
Avg Temp:	15.78
Min Cond:	7.12
Max Cond:	7.81
Avg Cond:	7.62
Min Salinity:	4.93
Max Salinity:	5.35
Avg Salinity:	5.21
Min Sigma-Theta:	2.76
Max Sigma-Theta:	3.09
Avg Sigma-Theta:	2.99
Min Turbidity:	21.09
Max Turbidity:	56.46
Avg Turbidity:	29.55

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E04-T067-P3

10/13/09 18:30 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.77
Max Temp:	15.78
Avg Temp:	15.78
Min Cond:	7.07
Max Cond:	7.89
Avg Cond:	7.68
Min Salinity:	4.81
Max Salinity:	5.39
Avg Salinity:	5.24
Min Sigma-Theta:	2.68
Max Sigma-Theta:	3.12
Avg Sigma-Theta:	3.02
Min Turbidity:	27.18
Max Turbidity:	55.07
Avg Turbidity:	34.21

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E04-T102-P1

10/13/09 17:31 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.02
Max Temp:	15.12
Avg Temp:	15.06
Min Cond:	0.56
Max Cond:	0.56
Avg Cond:	0.56
Min Salinity:	0.34
Max Salinity:	0.34
Avg Salinity:	0.34
Min Sigma-Theta:	-0.66
Max Sigma-Theta:	-0.64
Avg Sigma-Theta:	-0.65
Min Turbidity:	16.01
Max Turbidity:	36.08
Avg Turbidity:	26.89

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E04-T102-P2

10/13/09 17:38 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.07
Max Temp:	15.13
Avg Temp:	15.08
Min Cond:	0.56
Max Cond:	0.56
Avg Cond:	0.56
Min Salinity:	0.34
Max Salinity:	0.37
Avg Salinity:	0.34
Min Sigma-Theta:	-0.66
Max Sigma-Theta:	-0.65
Avg Sigma-Theta:	-0.65
Min Turbidity:	24.57
Max Turbidity:	86.65
Avg Turbidity:	44.96

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E04-T135-P1

10/13/09 19:33 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.50
Max Temp:	15.15
Avg Temp:	14.64
Min Cond:	0.55
Max Cond:	0.66
Avg Cond:	0.58
Min Salinity:	0.34
Max Salinity:	0.40
Avg Salinity:	0.35
Min Sigma-Theta:	-0.61
Max Sigma-Theta:	-0.56
Avg Sigma-Theta:	-0.57
Min Turbidity:	7.01
Max Turbidity:	10.06
Avg Turbidity:	8.46

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E04-T135-P2

10/13/09 19:40 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.40
Max Temp:	14.58
Avg Temp:	14.52
Min Cond:	0.52
Max Cond:	0.56
Avg Cond:	0.55
Min Salinity:	0.32
Max Salinity:	0.34
Avg Salinity:	0.34
Min Sigma-Theta:	-0.57
Max Sigma-Theta:	-0.56
Avg Sigma-Theta:	-0.56
Min Turbidity:	7.37
Max Turbidity:	9.61
Avg Turbidity:	8.58

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E04-T135-P3

10/13/09 19:48 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.21
Max Temp:	14.65
Avg Temp:	14.53
Min Cond:	0.51
Max Cond:	0.56
Avg Cond:	0.55
Min Salinity:	0.32
Max Salinity:	0.34
Avg Salinity:	0.34
Min Sigma-Theta:	-0.58
Max Sigma-Theta:	-0.54
Avg Sigma-Theta:	-0.57
Min Turbidity:	7.08
Max Turbidity:	9.49
Avg Turbidity:	8.58

APPENDIX 8: Trip 2 Real Time Survey Events E06-E08

- Vertically Averaged Current Vector Plots
- CTD-OBS Vertical Profiles



LEGEND FOR CURRENT VELOCITY MAPPINGS:

CURRENT VECTOR SCALE
1" = 150 CM/S

SCALE : 1"=750'
750 0 750

NOTES:

1. GRID SYSTEM IS IN FEET AND IS THE NEW JERSEY STATE PLANE COORDINATE SYSTEM, NAD83.
2. ORTHOPHOTO IMAGERY ARE TRUE COLOR ONE FOOT GROUND SAMPLE DISTANCE IMAGES PRODUCED FROM AERIAL PHOTOS FLOWN IN 2007 AND OBTAINED FROM THE NEW JERSEY GEOGRAPHIC INFORMATION NETWORK (NJGIN).
3. THE INFORMATION PRESENTED ON THESE DRAWINGS REPRESENTS THE RESULTS OF A SURVEY PEFORMED BY OCEAN SURVEYS, INC. ON 10–11 NOVEMBER 2009 AND CAN ONLY BE CONSIDERED AS INDICATING THE CONDITIONS EXISTING AT THAT TIME. REUSE OF THIS INFORMATION BY CLIENT OF OTHERS BEYOND THE SCOPE OF WORK FOR WHICH IT WAS ACQUIRED SHALL BE AT THE SOLE RISK OF THE USER AND WITHOUT LIABILITY TO OSI.

OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388–4631
www.oceansurveys.com

Vertically Averaged Current Data
Program 09A, Location Map & Event 06
10 November 2009
Passaic River, New Jersey



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Ebb Tide
Program 09A, Event 07
11 November 2009, 11:36 - 13:13 (UTC) Hours
Passaic River, New Jersey



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Flood Tide
Program 09A, Event 08
11 November 2009, 17:01 - 19:15 (UTC) Hours
Passaic River, New Jersey

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E06-T175-P1

11/10/09 16:02 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.48
Max Temp:	10.52
Avg Temp:	10.49
Min Cond:	0.35
Max Cond:	0.35
Avg Cond:	0.35
Min Salinity:	0.24
Max Salinity:	0.24
Avg Salinity:	0.24
Min Sigma-Theta:	-0.16
Max Sigma-Theta:	-0.16
Avg Sigma-Theta:	-0.16
Min Turbidity:	8.87
Max Turbidity:	9.77
Avg Turbidity:	9.08

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E06-T175-P2

11/10/09 16:16 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.88
Max Temp:	9.91
Avg Temp:	9.89
Min Cond:	0.36
Max Cond:	0.36
Avg Cond:	0.36
Min Salinity:	0.24
Max Salinity:	0.24
Avg Salinity:	0.24
Min Sigma-Theta:	-0.10
Max Sigma-Theta:	-0.10
Avg Sigma-Theta:	-0.10
Min Turbidity:	5.43
Max Turbidity:	6.07
Avg Turbidity:	5.77

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E06-T175-P3

11/10/09 16:30 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.90
Max Temp:	9.92
Avg Temp:	9.90
Min Cond:	0.36
Max Cond:	0.36
Avg Cond:	0.36
Min Salinity:	0.24
Max Salinity:	0.24
Avg Salinity:	0.24
Min Sigma-Theta:	-0.10
Max Sigma-Theta:	-0.10
Avg Sigma-Theta:	-0.10
Min Turbidity:	6.33
Max Turbidity:	6.55
Avg Turbidity:	6.48

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E06-T175-P4

11/10/09 16:40 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.39
Max Temp:	9.94
Avg Temp:	9.80
Min Cond:	0.36
Max Cond:	0.36
Avg Cond:	0.36
Min Salinity:	0.24
Max Salinity:	0.24
Avg Salinity:	0.24
Min Sigma-Theta:	-0.10
Max Sigma-Theta:	-0.10
Avg Sigma-Theta:	-0.10
Min Turbidity:	6.80
Max Turbidity:	7.00
Avg Turbidity:	6.94

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E07-T014-P1

11/11/09 11:57 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.19
Max Temp:	12.60
Avg Temp:	11.97
Min Cond:	11.46
Max Cond:	19.19
Avg Cond:	15.53
Min Salinity:	9.18
Max Salinity:	15.34
Avg Salinity:	12.41
Min Sigma-Theta:	6.37
Max Sigma-Theta:	11.28
Avg Sigma-Theta:	9.06
Min Turbidity:	18.92
Max Turbidity:	27.93
Avg Turbidity:	24.12

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E07-T014-P2

11/11/09 12:05 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	11.45
Max Temp:	12.58
Avg Temp:	11.96
Min Cond:	11.28
Max Cond:	18.96
Avg Cond:	15.15
Min Salinity:	8.89
Max Salinity:	15.15
Avg Salinity:	12.06
Min Sigma-Theta:	6.46
Max Sigma-Theta:	11.13
Avg Sigma-Theta:	8.84
Min Turbidity:	10.33
Max Turbidity:	21.74
Avg Turbidity:	18.50

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E07-T014-P3

11/11/09 12:11 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.47
Max Temp:	12.59
Avg Temp:	12.00
Min Cond:	11.43
Max Cond:	19.08
Avg Cond:	15.43
Min Salinity:	9.23
Max Salinity:	15.25
Avg Salinity:	12.35
Min Sigma-Theta:	6.72
Max Sigma-Theta:	11.22
Avg Sigma-Theta:	9.06
Min Turbidity:	15.25
Max Turbidity:	22.17
Avg Turbidity:	18.41

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E07-T042-P1

11/11/09 12:36 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.44
Max Temp:	11.69
Avg Temp:	10.76
Min Cond:	3.81
Max Cond:	12.69
Avg Cond:	5.93
Min Salinity:	2.85
Max Salinity:	10.04
Avg Salinity:	4.56
Min Sigma-Theta:	1.88
Max Sigma-Theta:	7.32
Avg Sigma-Theta:	3.18
Min Turbidity:	22.20
Max Turbidity:	27.72
Avg Turbidity:	25.42

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E07-T042-P2

11/11/09 12:44 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.40
Max Temp:	12.23
Avg Temp:	10.94
Min Cond:	4.00
Max Cond:	16.38
Avg Cond:	7.21
Min Salinity:	3.01
Max Salinity:	13.04
Avg Salinity:	5.60
Min Sigma-Theta:	2.02
Max Sigma-Theta:	9.56
Avg Sigma-Theta:	3.97
Min Turbidity:	21.25
Max Turbidity:	27.74
Avg Turbidity:	25.00

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E07-T042-P3

11/11/09 12:52 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.41
Max Temp:	11.87
Avg Temp:	10.85
Min Cond:	3.37
Max Cond:	13.32
Avg Cond:	6.23
Min Salinity:	2.51
Max Salinity:	10.52
Avg Salinity:	4.80
Min Sigma-Theta:	1.63
Max Sigma-Theta:	7.67
Avg Sigma-Theta:	3.36
Min Turbidity:	15.95
Max Turbidity:	30.89
Avg Turbidity:	25.46

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E07-T067-P1

11/11/09 13:20 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.28
Max Temp:	10.34
Avg Temp:	10.32
Min Cond:	0.39
Max Cond:	0.40
Avg Cond:	0.39
Min Salinity:	0.26
Max Salinity:	0.27
Avg Salinity:	0.27
Min Sigma-Theta:	-0.12
Max Sigma-Theta:	-0.11
Avg Sigma-Theta:	-0.12
Min Turbidity:	40.27
Max Turbidity:	58.76
Avg Turbidity:	50.46

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E07-T067-P2

11/11/09 13:27 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.30
Max Temp:	10.35
Avg Temp:	10.33
Min Cond:	0.39
Max Cond:	0.39
Avg Cond:	0.39
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-0.12
Max Sigma-Theta:	-0.12
Avg Sigma-Theta:	-0.12
Min Turbidity:	26.46
Max Turbidity:	63.78
Avg Turbidity:	46.91

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E07-T067-P3

11/11/09 13:35 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.22
Max Temp:	10.34
Avg Temp:	10.31
Min Cond:	0.39
Max Cond:	0.39
Avg Cond:	0.39
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-0.12
Max Sigma-Theta:	-0.11
Avg Sigma-Theta:	-0.12
Min Turbidity:	28.12
Max Turbidity:	49.64
Avg Turbidity:	39.45

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E07-T102-P1

11/11/09 13:11 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.55
Max Temp:	10.55
Avg Temp:	10.55
Min Cond:	0.39
Max Cond:	0.39
Avg Cond:	0.39
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-0.14
Max Sigma-Theta:	-0.14
Avg Sigma-Theta:	-0.14
Min Turbidity:	13.76
Max Turbidity:	17.88
Avg Turbidity:	15.50

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E07-T102-P2

11/11/09 13:25 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.54
Max Temp:	10.55
Avg Temp:	10.54
Min Cond:	0.39
Max Cond:	0.39
Avg Cond:	0.39
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-0.14
Max Sigma-Theta:	-0.14
Avg Sigma-Theta:	-0.14
Min Turbidity:	14.42
Max Turbidity:	19.05
Avg Turbidity:	16.44

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E07-T102-P3

11/11/09 13:36 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.52
Max Temp:	10.53
Avg Temp:	10.53
Min Cond:	0.39
Max Cond:	0.39
Avg Cond:	0.39
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-0.14
Max Sigma-Theta:	-0.14
Avg Sigma-Theta:	-0.14
Min Turbidity:	16.74
Max Turbidity:	19.56
Avg Turbidity:	18.17

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E07-T135-P1

11/11/09 11:56 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.85
Max Temp:	10.86
Avg Temp:	10.85
Min Cond:	0.41
Max Cond:	0.42
Avg Cond:	0.41
Min Salinity:	0.28
Max Salinity:	0.28
Avg Salinity:	0.28
Min Sigma-Theta:	-0.16
Max Sigma-Theta:	-0.16
Avg Sigma-Theta:	-0.16
Min Turbidity:	5.33
Max Turbidity:	7.71
Avg Turbidity:	6.42

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E07-T135-P2

11/11/09 12:10 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.85
Max Temp:	10.86
Avg Temp:	10.86
Min Cond:	0.42
Max Cond:	0.42
Avg Cond:	0.42
Min Salinity:	0.28
Max Salinity:	0.28
Avg Salinity:	0.28
Min Sigma-Theta:	-0.16
Max Sigma-Theta:	-0.16
Avg Sigma-Theta:	-0.16
Min Turbidity:	5.25
Max Turbidity:	5.81
Avg Turbidity:	5.58

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E07-T135-P3

11/11/09 12:21 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.84
Max Temp:	10.85
Avg Temp:	10.85
Min Cond:	0.42
Max Cond:	0.42
Avg Cond:	0.42
Min Salinity:	0.28
Max Salinity:	0.28
Avg Salinity:	0.28
Min Sigma-Theta:	-0.16
Max Sigma-Theta:	-0.16
Avg Sigma-Theta:	-0.16
Min Turbidity:	5.96
Max Turbidity:	8.06
Avg Turbidity:	7.11

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E08-T014-P1

11/11/09 16:52 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.47
Max Temp:	12.65
Avg Temp:	11.99
Min Cond:	11.32
Max Cond:	20.84
Avg Cond:	15.68
Min Salinity:	8.98
Max Salinity:	16.77
Avg Salinity:	12.53
Min Sigma-Theta:	6.53
Max Sigma-Theta:	12.37
Avg Sigma-Theta:	9.20
Min Turbidity:	17.56
Max Turbidity:	98.46
Avg Turbidity:	44.40

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E08-T014-P2

11/11/09 16:59 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.43
Max Temp:	12.65
Avg Temp:	12.02
Min Cond:	11.30
Max Cond:	20.76
Avg Cond:	15.66
Min Salinity:	8.92
Max Salinity:	16.69
Avg Salinity:	12.50
Min Sigma-Theta:	6.49
Max Sigma-Theta:	12.32
Avg Sigma-Theta:	9.17
Min Turbidity:	14.09
Max Turbidity:	39.20
Avg Turbidity:	22.88

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E08-T014-P3

11/11/09 17:09 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.66
Max Temp:	12.64
Avg Temp:	12.17
Min Cond:	13.13
Max Cond:	20.71
Avg Cond:	17.40
Min Salinity:	10.54
Max Salinity:	16.66
Avg Salinity:	13.95
Min Sigma-Theta:	7.71
Max Sigma-Theta:	12.29
Avg Sigma-Theta:	10.27
Min Turbidity:	12.40
Max Turbidity:	50.22
Avg Turbidity:	29.74

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E08-T042-P1

11/11/09 17:34 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.87
Max Temp:	12.04
Avg Temp:	11.35
Min Cond:	6.13
Max Cond:	14.87
Avg Cond:	9.59
Min Salinity:	4.69
Max Salinity:	11.80
Avg Salinity:	7.50
Min Sigma-Theta:	3.28
Max Sigma-Theta:	8.63
Avg Sigma-Theta:	5.39
Min Turbidity:	22.99
Max Turbidity:	196.34
Avg Turbidity:	86.41

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E08-T042-P2

11/11/09 17:43 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.93
Max Temp:	12.07
Avg Temp:	11.49
Min Cond:	5.97
Max Cond:	15.10
Avg Cond:	10.70
Min Salinity:	4.55
Max Salinity:	11.99
Avg Salinity:	8.40
Min Sigma-Theta:	3.16
Max Sigma-Theta:	8.77
Avg Sigma-Theta:	6.08
Min Turbidity:	22.46
Max Turbidity:	172.30
Avg Turbidity:	80.22

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E08-T042-P3

11/11/09 17:48 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.91
Max Temp:	11.94
Avg Temp:	11.43
Min Cond:	5.56
Max Cond:	14.20
Avg Cond:	10.15
Min Salinity:	4.22
Max Salinity:	11.26
Avg Salinity:	7.95
Min Sigma-Theta:	2.91
Max Sigma-Theta:	8.23
Avg Sigma-Theta:	5.74
Min Turbidity:	26.12
Max Turbidity:	79.56
Avg Turbidity:	41.64

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E08-T067-P1

11/11/09 19:33 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.74
Max Temp:	10.79
Avg Temp:	10.77
Min Cond:	3.78
Max Cond:	4.61
Avg Cond:	4.33
Min Salinity:	2.81
Max Salinity:	3.46
Avg Salinity:	3.24
Min Sigma-Theta:	1.83
Max Sigma-Theta:	2.33
Avg Sigma-Theta:	2.16
Min Turbidity:	19.34
Max Turbidity:	27.85
Avg Turbidity:	23.04

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E08-T067-P2

11/11/09 19:41 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.74
Max Temp:	10.82
Avg Temp:	10.78
Min Cond:	3.86
Max Cond:	4.88
Avg Cond:	4.53
Min Salinity:	2.87
Max Salinity:	3.68
Avg Salinity:	3.40
Min Sigma-Theta:	1.88
Max Sigma-Theta:	2.49
Avg Sigma-Theta:	2.28
Min Turbidity:	19.04
Max Turbidity:	31.32
Avg Turbidity:	21.99

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E08-T067-P3

11/11/09 19:50 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.73
Max Temp:	10.83
Avg Temp:	10.79
Min Cond:	3.91
Max Cond:	5.01
Avg Cond:	4.60
Min Salinity:	2.91
Max Salinity:	3.78
Avg Salinity:	3.46
Min Sigma-Theta:	1.91
Max Sigma-Theta:	2.58
Avg Sigma-Theta:	2.33
Min Turbidity:	19.00
Max Turbidity:	24.59
Avg Turbidity:	21.65

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E08-T102-P1

11/11/09 18:22 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.63
Max Temp:	10.65
Avg Temp:	10.64
Min Cond:	0.39
Max Cond:	0.39
Avg Cond:	0.39
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-0.15
Max Sigma-Theta:	-0.15
Avg Sigma-Theta:	-0.15
Min Turbidity:	17.68
Max Turbidity:	36.20
Avg Turbidity:	26.96

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E08-T102-P2

11/11/09 18:32 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.63
Max Temp:	10.65
Avg Temp:	10.64
Min Cond:	0.39
Max Cond:	0.39
Avg Cond:	0.39
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-0.15
Max Sigma-Theta:	-0.15
Avg Sigma-Theta:	-0.15
Min Turbidity:	17.05
Max Turbidity:	31.34
Avg Turbidity:	23.30

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E08-T102-P3

11/11/09 18:40 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.63
Max Temp:	10.65
Avg Temp:	10.64
Min Cond:	0.39
Max Cond:	0.39
Avg Cond:	0.39
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-0.15
Max Sigma-Theta:	-0.15
Avg Sigma-Theta:	-0.15
Min Turbidity:	14.56
Max Turbidity:	23.01
Avg Turbidity:	18.73

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E08-T135-P1

11/11/09 17:18 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.82
Max Temp:	10.86
Avg Temp:	10.84
Min Cond:	0.41
Max Cond:	0.41
Avg Cond:	0.41
Min Salinity:	0.28
Max Salinity:	0.28
Avg Salinity:	0.28
Min Sigma-Theta:	-0.16
Max Sigma-Theta:	-0.16
Avg Sigma-Theta:	-0.16
Min Turbidity:	5.91
Max Turbidity:	7.04
Avg Turbidity:	6.48

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E08-T135-P2

11/11/09 17:28 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.79
Max Temp:	10.85
Avg Temp:	10.82
Min Cond:	0.41
Max Cond:	0.41
Avg Cond:	0.41
Min Salinity:	0.27
Max Salinity:	0.28
Avg Salinity:	0.27
Min Sigma-Theta:	-0.16
Max Sigma-Theta:	-0.16
Avg Sigma-Theta:	-0.16
Min Turbidity:	5.32
Max Turbidity:	6.20
Avg Turbidity:	5.71

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E08-T135-P3

11/11/09 17:36 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.83
Max Temp:	10.93
Avg Temp:	10.87
Min Cond:	0.42
Max Cond:	0.42
Avg Cond:	0.42
Min Salinity:	0.28
Max Salinity:	0.28
Avg Salinity:	0.28
Min Sigma-Theta:	-0.17
Max Sigma-Theta:	-0.16
Avg Sigma-Theta:	-0.16
Min Turbidity:	5.50
Max Turbidity:	6.55
Avg Turbidity:	6.01

APPENDIX 9: Trip 3 Real Time Survey Events E11-E13

- Vertically Averaged Current Vector Plots
- CTD-OBS Vertical Profiles

LOCATION MAP

NOT TO SCALE



LEGEND FOR CURRENT VELOCITY MAPPINGS:

CURRENT VECTOR SCALE
1" = 150 CM/S

SCALE : 1"=750'

750 0 750

NOTES:

1. GRID SYSTEM IS IN FEET AND IS THE NEW JERSEY STATE PLANE COORDINATE SYSTEM, NAD83.
2. ORTHOPHOTO IMAGERY ARE TRUE COLOR ONE FOOT GROUND SAMPLE DISTANCE IMAGES PRODUCED FROM AERIAL PHOTOS FLOWN IN 2007 AND OBTAINED FROM THE NEW JERSEY GEOGRAPHIC INFORMATION NETWORK (NJGIN).
3. THE INFORMATION PRESENTED ON THESE DRAWINGS REPRESENTS THE RESULTS OF A SURVEY PEFORMED BY OCEAN SURVEYS, INC. ON 14–15 DECEMBER 2009 AND CAN ONLY BE CONSIDERED AS INDICATING THE CONDITIONS EXISTING AT THAT TIME. REUSE OF THIS INFORMATION BY CLIENT OF OTHERS BEYOND THE SCOPE OF WORK FOR WHICH IT WAS ACQUIRED SHALL BE AT THE SOLE RISK OF THE USER AND WITHOUT LIABILITY TO OSI.

OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388-4631
www.oceansurveys.com

Vertically Averaged Current Data
Program 09A, Location Map & Event 11
15 December 2009
Passaic River, New Jersey



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Ebb Tide
Program 09A, Event 12
14 December 2009, 14:27 - 16:00 (UTC) Hours
Passaic River, New Jersey



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Flood Tide
Program 09A, Event 13
14 December 2009, 20:00 - 21:21 (UTC) Hours
Passaic River, New Jersey

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E11-T175-P1

12/15/09 15:18 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	3.00
Max Temp:	3.01
Avg Temp:	3.01
Min Cond:	0.25
Max Cond:	0.25
Avg Cond:	0.25
Min Salinity:	0.20
Max Salinity:	0.20
Avg Salinity:	0.20
Min Sigma-Theta:	0.13
Max Sigma-Theta:	0.13
Avg Sigma-Theta:	0.13
Min Turbidity:	12.86
Max Turbidity:	14.21
Avg Turbidity:	13.54

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E11-T175-P2

12/15/09 15:31 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.95
Max Temp:	2.95
Avg Temp:	2.95
Min Cond:	0.25
Max Cond:	0.25
Avg Cond:	0.25
Min Salinity:	0.20
Max Salinity:	0.20
Avg Salinity:	0.20
Min Sigma-Theta:	0.13
Max Sigma-Theta:	0.13
Avg Sigma-Theta:	0.13
Min Turbidity:	14.47
Max Turbidity:	17.00
Avg Turbidity:	15.43

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E11-T175-P3

12/15/09 15:44 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.97
Max Temp:	2.97
Avg Temp:	2.97
Min Cond:	0.25
Max Cond:	0.25
Avg Cond:	0.25
Min Salinity:	0.20
Max Salinity:	0.20
Avg Salinity:	0.20
Min Sigma-Theta:	0.13
Max Sigma-Theta:	0.13
Avg Sigma-Theta:	0.13
Min Turbidity:	16.46
Max Turbidity:	17.20
Avg Turbidity:	16.82

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E11-T175-P4

12/15/09 15:51 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.99
Max Temp:	2.99
Avg Temp:	2.99
Min Cond:	0.25
Max Cond:	0.25
Avg Cond:	0.25
Min Salinity:	0.20
Max Salinity:	0.20
Avg Salinity:	0.20
Min Sigma-Theta:	0.13
Max Sigma-Theta:	0.13
Avg Sigma-Theta:	0.13
Min Turbidity:	16.88
Max Turbidity:	17.39
Avg Turbidity:	17.23

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E12-T014-P1

12/14/09 14:40 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	2.59
Max Temp:	6.51
Avg Temp:	4.16
Min Cond:	1.62
Max Cond:	16.84
Avg Cond:	7.76
Min Salinity:	1.44
Max Salinity:	13.28
Avg Salinity:	6.92
Min Sigma-Theta:	1.13
Max Sigma-Theta:	10.23
Avg Sigma-Theta:	5.42
Min Turbidity:	20.05
Max Turbidity:	53.81
Avg Turbidity:	30.00

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E12-T014-P2

12/14/09 14:49 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.53
Max Temp:	6.48
Avg Temp:	4.12
Min Cond:	1.54
Max Cond:	14.31
Avg Cond:	6.93
Min Salinity:	1.39
Max Salinity:	12.76
Avg Salinity:	6.46
Min Sigma-Theta:	1.08
Max Sigma-Theta:	9.98
Avg Sigma-Theta:	5.05
Min Turbidity:	15.39
Max Turbidity:	27.75
Avg Turbidity:	20.60

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E12-T014-P3

12/14/09 14:56 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.57
Max Temp:	6.53
Avg Temp:	4.12
Min Cond:	1.60
Max Cond:	14.96
Avg Cond:	6.53
Min Salinity:	1.43
Max Salinity:	12.60
Avg Salinity:	5.94
Min Sigma-Theta:	1.12
Max Sigma-Theta:	9.90
Avg Sigma-Theta:	4.67
Min Turbidity:	13.29
Max Turbidity:	25.39
Avg Turbidity:	19.34

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E12-T042-P1

12/14/09 15:25 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.00
Max Temp:	2.41
Avg Temp:	2.27
Min Cond:	0.27
Max Cond:	0.28
Avg Cond:	0.28
Min Salinity:	0.19
Max Salinity:	0.24
Avg Salinity:	0.23
Min Sigma-Theta:	0.13
Max Sigma-Theta:	0.15
Avg Sigma-Theta:	0.14
Min Turbidity:	39.74
Max Turbidity:	54.80
Avg Turbidity:	43.90

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E12-T042-P2

12/14/09 15:32 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.15
Max Temp:	2.20
Avg Temp:	2.16
Min Cond:	0.26
Max Cond:	0.26
Avg Cond:	0.26
Min Salinity:	0.22
Max Salinity:	0.22
Avg Salinity:	0.22
Min Sigma-Theta:	0.13
Max Sigma-Theta:	0.13
Avg Sigma-Theta:	0.13
Min Turbidity:	40.96
Max Turbidity:	54.95
Avg Turbidity:	45.53

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E12-T042-P3

12/14/09 15:40 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.16
Max Temp:	2.20
Avg Temp:	2.17
Min Cond:	0.26
Max Cond:	0.26
Avg Cond:	0.26
Min Salinity:	0.22
Max Salinity:	0.22
Avg Salinity:	0.22
Min Sigma-Theta:	0.13
Max Sigma-Theta:	0.13
Avg Sigma-Theta:	0.13
Min Turbidity:	41.60
Max Turbidity:	67.85
Avg Turbidity:	54.20

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E12-T067-P1

12/14/09 16:08 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.49
Max Temp:	2.96
Avg Temp:	2.67
Min Cond:	0.31
Max Cond:	0.33
Avg Cond:	0.32
Min Salinity:	0.22
Max Salinity:	0.27
Avg Salinity:	0.27
Min Sigma-Theta:	0.15
Max Sigma-Theta:	0.19
Avg Sigma-Theta:	0.18
Min Turbidity:	30.05
Max Turbidity:	37.82
Avg Turbidity:	34.02

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E12-T067-P2

12/14/09 16:17 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.30
Max Temp:	2.45
Avg Temp:	2.33
Min Cond:	0.32
Max Cond:	0.33
Avg Cond:	0.32
Min Salinity:	0.27
Max Salinity:	0.27
Avg Salinity:	0.27
Min Sigma-Theta:	0.17
Max Sigma-Theta:	0.18
Avg Sigma-Theta:	0.17
Min Turbidity:	31.11
Max Turbidity:	40.55
Avg Turbidity:	35.07

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E12-T067-P3

12/14/09 16:26 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.31
Max Temp:	2.52
Avg Temp:	2.35
Min Cond:	0.32
Max Cond:	0.33
Avg Cond:	0.33
Min Salinity:	0.28
Max Salinity:	0.28
Avg Salinity:	0.28
Min Sigma-Theta:	0.18
Max Sigma-Theta:	0.18
Avg Sigma-Theta:	0.18
Min Turbidity:	30.60
Max Turbidity:	40.20
Avg Turbidity:	34.85

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E12-T102-P1

12/14/09 15:50 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.18
Max Temp:	2.19
Avg Temp:	2.18
Min Cond:	0.32
Max Cond:	0.32
Avg Cond:	0.32
Min Salinity:	0.27
Max Salinity:	0.27
Avg Salinity:	0.27
Min Sigma-Theta:	0.17
Max Sigma-Theta:	0.17
Avg Sigma-Theta:	0.17
Min Turbidity:	24.73
Max Turbidity:	27.46
Avg Turbidity:	26.65

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E12-T102-P2

12/14/09 16:01 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.17
Max Temp:	2.19
Avg Temp:	2.18
Min Cond:	0.31
Max Cond:	0.31
Avg Cond:	0.31
Min Salinity:	0.26
Max Salinity:	0.27
Avg Salinity:	0.27
Min Sigma-Theta:	0.16
Max Sigma-Theta:	0.16
Avg Sigma-Theta:	0.16
Min Turbidity:	29.13
Max Turbidity:	35.13
Avg Turbidity:	32.67

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E12-T102-P3

12/14/09 16:11 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.17
Max Temp:	2.19
Avg Temp:	2.18
Min Cond:	0.31
Max Cond:	0.31
Avg Cond:	0.31
Min Salinity:	0.26
Max Salinity:	0.27
Avg Salinity:	0.27
Min Sigma-Theta:	0.16
Max Sigma-Theta:	0.16
Avg Sigma-Theta:	0.16
Min Turbidity:	29.13
Max Turbidity:	35.13
Avg Turbidity:	32.67

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E12-T135-P1

12/14/09 14:46 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.04
Max Temp:	2.05
Avg Temp:	2.04
Min Cond:	0.31
Max Cond:	0.31
Avg Cond:	0.31
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	0.16
Max Sigma-Theta:	0.16
Avg Sigma-Theta:	0.16
Min Turbidity:	17.74
Max Turbidity:	24.39
Avg Turbidity:	21.68

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E12-T135-P2

12/14/09 14:57 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.03
Max Temp:	2.05
Avg Temp:	2.04
Min Cond:	0.31
Max Cond:	0.31
Avg Cond:	0.31
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	0.16
Max Sigma-Theta:	0.16
Avg Sigma-Theta:	0.16
Min Turbidity:	20.43
Max Turbidity:	25.65
Avg Turbidity:	23.18

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E12-T135-P3

12/14/09 15:05 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.04
Max Temp:	2.05
Avg Temp:	2.04
Min Cond:	0.31
Max Cond:	0.31
Avg Cond:	0.31
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	0.16
Max Sigma-Theta:	0.16
Avg Sigma-Theta:	0.16
Min Turbidity:	21.58
Max Turbidity:	24.99
Avg Turbidity:	23.35

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E13-T014-P1

12/14/09 20:07 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.68
Max Temp:	5.68
Avg Temp:	3.71
Min Cond:	0.32
Max Cond:	8.33
Avg Cond:	2.66
Min Salinity:	0.26
Max Salinity:	7.55
Avg Salinity:	2.39
Min Sigma-Theta:	0.18
Max Sigma-Theta:	5.94
Avg Sigma-Theta:	1.87
Min Turbidity:	22.55
Max Turbidity:	98.92
Avg Turbidity:	45.43

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E13-T014-P2

12/14/09 20:14 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.51
Max Temp:	6.09
Avg Temp:	3.67
Min Cond:	0.31
Max Cond:	11.70
Avg Cond:	3.54
Min Salinity:	0.25
Max Salinity:	10.01
Avg Salinity:	3.18
Min Sigma-Theta:	0.18
Max Sigma-Theta:	7.90
Avg Sigma-Theta:	2.49
Min Turbidity:	34.61
Max Turbidity:	119.89
Avg Turbidity:	54.32

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E13-T014-P3

12/14/09 20:21 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.56
Max Temp:	5.85
Avg Temp:	3.86
Min Cond:	0.44
Max Cond:	11.98
Avg Cond:	4.72
Min Salinity:	0.37
Max Salinity:	9.80
Avg Salinity:	3.68
Min Sigma-Theta:	0.26
Max Sigma-Theta:	7.87
Avg Sigma-Theta:	2.90
Min Turbidity:	18.83
Max Turbidity:	116.79
Avg Turbidity:	55.63

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E13-T042-P1

12/14/09 20:44 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.53
Max Temp:	2.84
Avg Temp:	2.59
Min Cond:	0.35
Max Cond:	0.39
Avg Cond:	0.36
Min Salinity:	0.29
Max Salinity:	0.32
Avg Salinity:	0.30
Min Sigma-Theta:	0.19
Max Sigma-Theta:	0.23
Avg Sigma-Theta:	0.20
Min Turbidity:	24.12
Max Turbidity:	28.61
Avg Turbidity:	27.49

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E13-T042-P2

12/14/09 20:52 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.49
Max Temp:	2.59
Avg Temp:	2.51
Min Cond:	0.30
Max Cond:	0.33
Avg Cond:	0.33
Min Salinity:	0.25
Max Salinity:	0.28
Avg Salinity:	0.27
Min Sigma-Theta:	0.16
Max Sigma-Theta:	0.18
Avg Sigma-Theta:	0.18
Min Turbidity:	22.63
Max Turbidity:	32.10
Avg Turbidity:	30.21

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E13-T042-P3

12/14/09 21:00 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.50
Max Temp:	2.54
Avg Temp:	2.52
Min Cond:	0.32
Max Cond:	0.32
Avg Cond:	0.32
Min Salinity:	0.26
Max Salinity:	0.27
Avg Salinity:	0.27
Min Sigma-Theta:	0.17
Max Sigma-Theta:	0.18
Avg Sigma-Theta:	0.18
Min Turbidity:	28.16
Max Turbidity:	33.95
Avg Turbidity:	31.80

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E13-T067-P1

12/14/09 21:22 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.48
Max Temp:	2.75
Avg Temp:	2.52
Min Cond:	0.33
Max Cond:	0.33
Avg Cond:	0.33
Min Salinity:	0.26
Max Salinity:	0.28
Avg Salinity:	0.27
Min Sigma-Theta:	0.17
Max Sigma-Theta:	0.18
Avg Sigma-Theta:	0.18
Min Turbidity:	21.11
Max Turbidity:	23.52
Avg Turbidity:	22.51

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E13-T067-P2

12/14/09 21:27 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.45
Max Temp:	2.46
Avg Temp:	2.45
Min Cond:	0.33
Max Cond:	0.33
Avg Cond:	0.33
Min Salinity:	0.27
Max Salinity:	0.27
Avg Salinity:	0.27
Min Sigma-Theta:	0.18
Max Sigma-Theta:	0.18
Avg Sigma-Theta:	0.18
Min Turbidity:	20.09
Max Turbidity:	22.46
Avg Turbidity:	21.26

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E13-T067-P3

12/14/09 21:34 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.43
Max Temp:	2.47
Avg Temp:	2.44
Min Cond:	0.33
Max Cond:	0.33
Avg Cond:	0.33
Min Salinity:	0.27
Max Salinity:	0.27
Avg Salinity:	0.27
Min Sigma-Theta:	0.18
Max Sigma-Theta:	0.18
Avg Sigma-Theta:	0.18
Min Turbidity:	18.10
Max Turbidity:	21.00
Avg Turbidity:	19.93

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E13-T102-P1

12/14/09 21:32 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.45
Max Temp:	2.46
Avg Temp:	2.45
Min Cond:	0.30
Max Cond:	0.30
Avg Cond:	0.30
Min Salinity:	0.25
Max Salinity:	0.25
Avg Salinity:	0.25
Min Sigma-Theta:	0.16
Max Sigma-Theta:	0.16
Avg Sigma-Theta:	0.16
Min Turbidity:	10.43
Max Turbidity:	17.93
Avg Turbidity:	17.10

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E13-T102-P2

12/14/09 21:41 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.42
Max Temp:	2.44
Avg Temp:	2.43
Min Cond:	0.29
Max Cond:	0.30
Avg Cond:	0.29
Min Salinity:	0.25
Max Salinity:	0.25
Avg Salinity:	0.25
Min Sigma-Theta:	0.16
Max Sigma-Theta:	0.16
Avg Sigma-Theta:	0.16
Min Turbidity:	16.36
Max Turbidity:	20.90
Avg Turbidity:	18.61

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E13-T102-P3

12/14/09 21:51 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.40
Max Temp:	2.42
Avg Temp:	2.41
Min Cond:	0.29
Max Cond:	0.30
Avg Cond:	0.30
Min Salinity:	0.25
Max Salinity:	0.25
Avg Salinity:	0.25
Min Sigma-Theta:	0.16
Max Sigma-Theta:	0.16
Avg Sigma-Theta:	0.16
Min Turbidity:	17.56
Max Turbidity:	20.59
Avg Turbidity:	18.75

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E13-T135-P1

12/14/09 20:36 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.53
Max Temp:	2.54
Avg Temp:	2.53
Min Cond:	0.28
Max Cond:	0.29
Avg Cond:	0.28
Min Salinity:	0.23
Max Salinity:	0.24
Avg Salinity:	0.24
Min Sigma-Theta:	0.15
Max Sigma-Theta:	0.15
Avg Sigma-Theta:	0.15
Min Turbidity:	18.02
Max Turbidity:	21.06
Avg Turbidity:	19.58

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E13-T135-P2

12/14/09 20:48 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.52
Max Temp:	2.52
Avg Temp:	2.52
Min Cond:	0.28
Max Cond:	0.28
Avg Cond:	0.28
Min Salinity:	0.23
Max Salinity:	0.23
Avg Salinity:	0.23
Min Sigma-Theta:	0.14
Max Sigma-Theta:	0.14
Avg Sigma-Theta:	0.14
Min Turbidity:	18.30
Max Turbidity:	21.56
Avg Turbidity:	20.54

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

09A-E13-T135-P3

12/14/09 20:55 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	2.51
Max Temp:	2.51
Avg Temp:	2.51
Min Cond:	0.28
Max Cond:	0.28
Avg Cond:	0.28
Min Salinity:	0.23
Max Salinity:	0.23
Avg Salinity:	0.23
Min Sigma-Theta:	0.14
Max Sigma-Theta:	0.14
Avg Sigma-Theta:	0.14
Min Turbidity:	19.18
Max Turbidity:	20.99
Avg Turbidity:	20.25

APPENDIX 10: Data CD

Appendix B

Final Report - Spring Deployment Oceanographic Data Acquisition Program, Lower Passaic River Restoration Project. OSI Report #09ES053.2

Final Report

Spring Deployment
Oceanographic Data Acquistion Program
Lower Passaic River Restoration Project

Passaic River, Newark to Passaic, NJ

OSI Report #09ES053.2
12 October 2010

Prepared For:
AECOM
171 Daniel Webster Highway, Suite 11
Belmont, New Hampshire 03220

Prepared By:
Ocean Surveys, Inc.
91 Sheffield Street
Old Saybrook, CT 06475

FINAL REPORT

SPRING DEPLOYMENT

OCEANOGRAPHIC DATA ACQUISITION PROGRAM

LOWER PASSAIC RIVER RESTORATION PROJECT

PASSAIC RIVER, NEWARK TO PASSAIC, NJ

OSI Report No. 09ES053.2

Prepared For: AECOM
171 Daniel Webster Highway, Suite 11
Belmont, New Hampshire 03220

Prepared By: Ocean Surveys, Inc.
91 Sheffield Street
Old Saybrook, CT 06475

12 October 2010

TABLE OF CONTENTS

Page

TABLE OF CONTENTS i

LIST OF FIGURES & TABLES ii

1.0 INTRODUCTION 1

1.1 Project Summary 1
1.2 Project Tasks 3

2.0 FIELD OPERATIONS SUMMARY 6

2.1 Field Crew, Survey Vessel, & Navigation 6
2.2 Field Schedule 7
2.3 *In Situ* Instrumentation and Moorings 10

2.3.1 YSI Environmental 6920 Multiparameter Sonde 11
2.3.2 Acoustic Doppler Current Profiler 12

2.4 Real-Time Data Collection 13

3.0 DATA PRESENTATION 13

3.1 Water Sample Data 13
3.2 *In Situ* Instrumentation 13
3.3 Real-Time Survey Events 15

4.0 PROJECT SUMMARY 15

LIST OF FIGURES & TABLES

Figure 1. Site map of *in situ* instrumentation and real-time survey transects.. 2
Figure 2. ADCP/CT-OBS mooring and CT-OBS surface buoy. 11
Figure 3. *In situ* CT-OBS and ADCP bottom mooring. 12

Table 1. Project tasks listed by event number..... 5
Table 2. Field crews..... 6
Table 3. Field schedule 7
Table 4. *In Situ* Instrument Mooring Locations..... 10
Table 5. *In Situ* Instrument Fouling Periods 14
Table 6. CTD-OBS Temperature Inconsistencies 15

APPENDICES

1 Water Sampling Log
2 Survey Equipment, Procedures and Data Processing
3 Instrument Calibration
4 YSI Water Quality Time Series Plots
5 *In Situ* ADCP Time Series Plots
6 Mooring CTD-OBS Vertical Profiles – Events E01, E05, E09, & E10
7 Trip 4 Real Time Surveys Events E02-E04
8 Trip 5 Real Time Surveys Events E06-E08
9 Trip 6 Real Time Surveys Events E11-E13
10 Trip 7 Real Time Surveys Events E16-E18
11 Trip 8 Real Time Surveys Events E20-E22
12 Data CD

FINAL REPORT

SPRING DEPLOYMENT

OCEANOGRAPHIC DATA ACQUISITION PROGRAM

LOWER PASSAIC RIVER RESTORATION PROJECT

PASSAIC RIVER, NEWARK TO PASSAIC, NJ

1.0 INTRODUCTION

The oceanographic data acquisition program for the Lower Passaic River Restoration Project was created to provide *in situ* and real time data over two three-month periods coinciding with low and high river flows to provide data on flows, salinity, and solids under a range of flow conditions. During the period 22 March 2010 through 23 July 2010, Ocean Surveys, Inc. (OSI) conducted the oceanographic data acquisition program on the Lower Passaic River (LPR) during an expected high flow period. The spring program was extended for an additional month to capture expected low flow conditions. This work was conducted parallel to an oceanographic data acquisition program focused on Newark Bay, which included the Hackensack River, Newark Bay, Kill Van Kull, and Arthur Kill to provide a more regional data set. The Newark Bay report is provided under separate cover.

1.1 Project Summary

This program included the deployment of six Conductivity, Temperature-Optical Backscatter (CT-OBS) mooring buoys and five Acoustic Doppler Current Profilers (ADCP) bottom moorings (Figure 1) along with real-time, boat-based vessel-mounted ADCP (VMADCP) transect surveys that included the collection of Conductivity, Temperature, Depth-Optical Backscatter (CTD-OBS) vertical profiles and water samples at each of the mooring locations. The moorings were deployed in March 2010 and were scheduled to be deployed for three months. The deployment was extended an additional month into July 2010 to capture low flow conditions. Consistent with the *Remedial Investigation Water Column*

Monitoring/Physical Data Collection for the Lower Passaic River Restoration Project Quality Assurance Project Plan[1], OSI conducted real-time boat-based surveys immediately following deployment and servicing of the moorings and just prior to recovery. Details of the operational aspects of the field program and a presentation of the data are included in this report.



Figure 1. Site map of *in situ* instrumentation and real-time survey transects.

[1] AECOM 2010, Quality Assurance Project Plan/Field Sampling Addendum – Remedial Investigation Water Column Monitoring/Physical Data Collection – Lower Passaic River Restoration Project, Revision 5, April 2010, 319p.

1.2 Project Tasks

The oceanographic data acquisition program included five project tasks: *in situ* CT-OBS data, *in situ* current velocity profiling, vessel mounted ADCP transects, CTD-Turbidity profiling, and water sampling for total suspended solids.

1) ***In Situ* CT-OBS Data:** *In situ* water quality was measured using two moorings at each location, one for surface measurements and the other for bottom measurements. YSI Inc. Model 6920 and 6600 water quality sondes were deployed at the bottom in conjunction with each of the five bottom mounted ADCP moorings and on each of the six CT-OBS surface buoys, five of which were deployed in close proximity to the ADCP bottom moorings. Instruments were mounted 3 feet above the bottom and 3 feet below the water surface. Each sonde was configured to record temperature, conductivity/salinity, and turbidity at 12-minute intervals. The six instrument mooring stations were located along a 17.5-mile stretch of the lower Passaic River (Figure 1).

2) ***In Situ* Current Velocity Profiling:** *In situ* current velocities were monitored using bottom-mounted Teledyne RD Instruments (TRDI) Workhorse Sentinel ADCPs. The ADCPs were deployed at five locations along the Passaic River below Dundee Dam (Figure 1). The ADCPs were programmed to record current velocity and acoustic backscatter throughout the water column at 0.5-meter vertical bins every 12 minutes.

3) **Vessel Mounted ADCP (VMADCP) Transects:** Current velocity and backscatter data were collected along six transects. Each transect corresponded with an *in situ* CT-OBS instrument location (Figure 1). The five lower transects were conducted twice, coinciding with flood and ebb tidal conditions, while Transect 175 above Dundee Dam, was conducted only once. The VMADCP surveys were conducted after instrument deployments, during servicing, and prior to instrument recovery. Current velocity and backscatter data were collected throughout the water column in 0.5-meter vertical bins.

4) **CTD-Turbidity Profiling:** Sea-bird Electronics, Inc. Model SBE-19 SeaCat profiler was used to measure vertical profiles of temperature, salinity, and turbidity in the water column. Profiles were collected at each mooring location after deployment, before and after servicing, and prior to recovery. In addition, three profiles were collected across each transect during the VMADCP surveys. Above Dundee Dam at Transect 175, four profiles were collected along a single transect.

5) **Total Suspended Solids:** Water samples were collected at each mooring location after deployment, before and after servicing, and prior to recovery. In addition, samples were collected at each of the CTD profiling stations occupied during the VMADCP surveys. Samples were collected primarily to measure suspended sediment concentrations (SSC) with periodic additional samples collected during the VMADCP surveys for particulate organic carbon/dissolved organic carbon (POC/DOC) analyses. Water samples were collected at 3 feet below the surface and 3 feet above the bottom. AECOM was responsible for water sample handling and subsequent lab analysis.

AECOM has developed a series of alphanumerical designations for all field tasks performed on site. The overall field program has been divided into two program designations for the fall and spring surveys. The spring 2010 program was given a program designation of 10A while the fall 2009 program was designated 09A. During this program, each individual field task was broken down into individual events (Table 1). For the five stations below Dundee Dam, CTD-OBS vertical profiles and water sample collection were conducted after mooring deployment (Event E01), prior to servicing and after redeployment (Events E05 & E09-May 2010, Events E10 & E14-May 2010, Events E15 & E19-June 2010), and prior to recovery (Event E23-July 2010). Real-time ADCP transect survey operations during each trip to the site were conducted under Events E03 & E04 (March 2010), Events E07 & E08 (May 2010), Events E12 & E13 (May 2010), Events E17 & E18 (June 2010), and Events E21 & E22 (July 2010). The *in situ* mooring CTD-OBS vertical profiles and water sample collection along with the real-time ADCP survey operations conducted above Dundee Dam at Station 175

were designated as Event E02 (March 2010), Event E06 (May 2010), Event E11 (May 2010), E16 (June 2010), and Event E20 (July 2010).

Table 1. Project tasks listed by event number

Survey	Month	Event	Name
4	March	E01	Post-deployment moorings
4	March	E02	Above Dundee Dam transect
4	March	E03	Ebb tide transects
4	March	E04	Flood tide transects
5	May	E05	Pre-service moorings
5	May	E06	Above Dundee Dam transect
5	May	E07	Flood tide transects
5	May	E08	Ebb tide transects
5	May	E09	Post-service moorings
6	May	E10	Pre-recovery moorings
6	May	E11	Above Dundee Dam transect
6	May	E12	Ebb tide transects
6	May	E13	Flood tide transects
6	May	E14	Post-service moorings
7	June	E15	Pre-recovery moorings
7	June	E16	Above Dundee Dam transect
7	June	E17	Ebb tide transects
7	June	E18	Flood tide transects
7	June	E19	Post-service moorings
8	July	E20	Above Dundee Dam transect
8	July	E21	Ebb tide transects
8	July	E22	Flood tide transects
8	July	E23	Pre-recovery moorings

2.0 FIELD OPERATIONS SUMMARY

2.1 Field Crew, Survey Vessel, & Navigation

OSI conducted all fieldwork aboard a variety of vessels, each equipped with a DSM 212 Differential Global Positioning System (DGPS) receiver and staffed by a two-person OSI field team consisting of a Project Manager/Scientist and a Field Engineer. Each vessel was powered by outboard motors and equipped with winch and davit capabilities to support installation, servicing, and recovery of the *in situ* instrument moorings. Each vessel was also equipped with a Teledyne RD Instruments vessel-mounted 1200 kHz ADCP and Sea-Bird Electronics CTD-OBS vertical profiler.

The following personnel comprised the two-person field crews (Table 2):

Table 2. Field crews

Survey	*R/V Ready II*	*R/V Able or R/V Echo Echo*	*R/V Skiff or R/V Skimmer*
4	Steve Bodak	Ryan Bollenbach	Dustin Kach*
	Dustin Kach*	Jeff Motti	Jason DeLorenzo
5	Steve Bodak*	Steve Bodak*	Dustin Kach*
	Dustin Kach*	Kevin Murphy	Ryan Bollenbach
6	Steve Bodak	Ryan Bollenbach	Dustin Kach*
	Dustin Kach*	Steve Gadomski	Jason DeLorenzo
7	Dustin Kach*	Ryan Bollenbach*	Dustin Kach*
	Ryan Bollenbach*	Kevin Ridarelli	Jason DeLorenzo
8	Steve Bodak	Ryan Bollenbach	Dustin Kach*
	Dustin Kach*	Kevin Ridarelli	Jason DeLorenzo

* Personnel transferred between vessels.

In addition, representatives from AECOM and EPA (CDM) were present throughout the field effort.

The survey navigation system consisted of Coast Guard DGPS that was fed directly into the HYPACK survey navigation and data collection software on each vessel. A full description of the navigational system and survey instrumentation is available in Appendix 2, along with a brief description of operational and data processing procedures. The designated coordinate system for the project was the New Jersey State Plane in the North American Datum of 1983 (NAD83). Horizontal grid units were in U.S. Survey feet.

2.2 Field Schedule

Project tasks were conducted from 22 March 2010 through 23 July 2010. A detailed schedule of field operations is listed below (Table 3):

Table 3. Field schedule

Date	*R/V Ready II* Task	*R/V Able* Task	*R/V Skiff* Task
03/18/2010	Travel to site and ready boat.		
03/19 – 3/21/2010	Newark Bay operations.		
03/22/2010	Deploy equipment at Stations 014 and 042, collect CTD-OBS vertical profiles and water samples.		
03/23/2010	Deploy equipment at Stations 67 and 102, collect CTD-OBS vertical profiles and water samples.		
03/24/2010	Deploy Station 135, collect CTD-OBS vertical profiles and water samples. Calibrate the VMADCP in Newark Bay.	Travel to site, ready boat, and calibrate VMADCP.	Travel to site, ready boat, deploy instrument at Station 175, calibrate VMADCP, collect CTD-OBS vertical profiles, water samples and conduct VMADCP survey.
03/25/2010	Newark Bay operations.	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects 014 & 042 along with one additional transect on the Hackensack River.	Ready boat, collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects 067, 102 & 135.
03/26/2010	Travel to OSI at Old Saybrook, CT.	Add floatation and weight to Station 135. Replaced damaged buoys and increase anchor weight at Stations 67 & 102. Travel to OSI at Old Saybrook, CT.	Add floatation and anchor weight to Station 175. Travel to OSI at Old Saybrook, CT
	R/V Ready II	***R/V Echo Echo***	***R/V Skiff***
04/27/2010	Travel to site and ready boat.		
04/28-04/30/2010	Newark Bay operations.		
05/01/2010	Recover, service, and redeploy equipment at Stations 067, 102, and 135. Collect CTD-OBS vertical profiles and water samples.		

Table 3 continued

	R/V Ready II	***R/V Echo Echo***	***R/V Skiff***
05/02/2010	Recover, service, and redeploy equipment at Stations 014 and 042. Collect CTD-OBS vertical profiles and water samples. Calibrate the VMADCP in Newark Bay.	Travel to site, ready boat, and calibrate VMADCP.	Travel to site, ready boat, and calibrate VMADCP.
05/03/2010	Newark Bay operations.	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects 014 & 042 along with one additional transect on the Hackensack River.	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects 067, 102 & 135.
05/04/2010	Travel to OSI at Old Saybrook, CT.	Travel to OSI at Old Saybrook, CT.	Recover, service, and redeploy equipment at Transect 175. Collect CTD-OBS vertical profiles, water samples and conduct VMADCP survey. Travel to OSI at Old Saybrook, CT.
	R/V Ready II	***R/V Echo Echo***	***R/V Skimmer***
05/18/2010	Travel to site and ready boat		
05/19/2010	Recover, service, and redeploy equipment at Stations 067, 102, and 135. Collect CTD-OBS vertical profiles and water samples.		
05/20/2010	Recover, service, and redeploy equipment at Stations 014 and 042. Collect CTD-OBS vertical profiles and water samples.		
05/21-05/22/2010	Newark Bay operations.		
05/23/2010	Newark Bay operations.	Travel to site, ready boat, and calibrate VMADCP.	Travel to site, ready boat, and calibrate VMADCP.
05/24/2010	Newark Bay operations.	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects 014 & 042 along with one additional transect on the Hackensack River.	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects 067, 102 & 135.
05/25/2010	Travel to OSI at Old Saybrook, CT.	Travel to OSI at Old Saybrook, CT	Recover, service, and redeploy equipment at Transect 175. Collect CTD-OBS vertical profiles, water samples and conduct VMADCP survey. Travel to OSI at Old Saybrook, CT.

Table 3 continued

	R/V Ready II	*R/V Echo Echo*	*R/V Skimmer*
06/16/2010	Travel to site and ready boat.		
06/17/2010	Recover, service, and redeploy equipment at Stations 067, 102, and 135. Collect CTD-OBS vertical profiles and water samples.		
06/18/2010	Recover, service, and redeploy equipment at Stations 014 and 042. Collect CTD-OBS vertical profiles and water samples.		
06/19-06/20/2010	Newark Bay operations.		
06/21/2010	Newark Bay operations.	Travel to site, ready boat, and calibrate VMADCP.	Travel to site, ready boat and calibrate VMADCP. Recover, service, and redeploy equipment at Transect 175. Collect CTD-OBS vertical profiles, water samples and conduct VMADCP survey.
06/22/2010	Newark Bay operations.	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects 014 & 042 along with one additional transect on the Hackensack River.	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects 067, 102 & 135.
06/23/2010	Travel to OSI at Old Saybrook, CT.	Travel to OSI at Old Saybrook, CT	Travel to OSI at Old Saybrook, CT.
	R/V Ready II	*R/V Echo Echo*	*R/V Skimmer*
07/20/2010	Travel to site and ready boat, calibrate VMADCP.	Travel to site, ready boat, and calibrate VMADCP.	Travel to site, ready boat, and calibrate VMADCP.
07/21/2010	Newark Bay operations	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects 014 & 042 along with one additional transect on the Hackensack River.	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects 067, 102 & 135.
07/22/2010	Collect CTD-OBS vertical profiles and water samples then recovered equipment and moorings at Stations 014 and 042.	Travel to OSI at Old Saybrook, CT	Conduct VMADCP survey and collect CTD-OBS vertical profiles and water samples then recovered equipment and moorings at Transect 175. Travel to OSI at Old Saybrook, CT

Table 3 continued

	R/V Ready II	*R/V Echo Echo*	*R/V Skimmer*
07/23/2010	Collect CTD-OBS vertical profiles and water samples then recovered equipment and moorings at Stations 067, 102, 135.		
07/24 – 7/25/2010	Newark Bay operations		
07/26/2010	Newark Bay operations and travel to OSI at Old Saybrook, CT		

2.3 *In Situ* Instrumentation and Moorings

OSI maintained six CT-OBS mooring buoys and five ADCP bottom moorings throughout the Lower Passaic River and just above the Dundee Dam (Table 4). As shown in Figure 2, two moorings (one "bottom mooring" and one "surface mooring") were deployed at each station except at Station 175 above the Dundee Dam, which consisted of one CT-OBS surface mooring. After deployment, before and after servicings, and prior to recovery, OSI conducted CTD-OBS vertical profiles and collected water samples adjacent to the instrument moorings for data quality checks and calibration. A water-sampling log including sample locations, date & time, sample depths, and total water depth is available in Appendix 1. Detailed information on instrument operations and data processing procedures is available in Appendix 2. A brief discussion on general instrument calibration procedures is available in Appendix 3.

Table 4. *In Situ* Instrument Mooring Locations

Station	Bottom Moorings		Surface Moorings	
	Easting	Northing	Easting	Northing
014	597,991	691,229	597,985	691,195
042	588,243	692,307	588,278	692,309
067	586,142	702,835	586,129	702,811
102	592,106	719,746	592,097	719,711
135	597,214	734,295	597,194	734,261
175*	N/A	N/A	594,477	747,516

* Station 175 was located above Dundee Dam and did not included bottom-mounted instrumentation.



Figure 2. ADCP/CT-OBS mooring and CT-OBS surface buoy.

2.3.1 YSI Environmental 6920 Multiparameter Sonde

In situ water quality was measured and recorded using YSI Series 6920 & 6600 Multiparameter Sondes. A total of eleven sondes were deployed, two at each of the five moorings that were deployed throughout the lower Passaic River and one above Dundee Dam. At each station, one unit was placed 3 feet off the bottom and one unit 3 feet below the surface and programmed to record temperature, conductivity/salinity, and turbidity at 12-minute intervals (Figure 3). The one unit placed above the Dundee Dam at Station 175 was located 3 feet below the water surface.

Figure 3. *In situ* CT-OBS and ADCP bottom mooring.

2.3.2 Acoustic Doppler Current Profiler

Between March 22 - 24 2010 OSI deployed five 1200 kHz ADCPs. The ADCPs were deployed in approximately 15 to 20 feet of water at Stations 067, 102 and 135 and approximately 20 to 30 feet of water at Stations 014 and 042. Each ADCP was secured to a bottom mount in an upward looking position. OSI's custom ADCP mounts are approximately 2.5-feet long by 2.5-feet wide and project less than two feet off the bottom. A gimbal attachment within the instrument housing kept the ADCPs plumb. These specialized mounts have no buoys or other surface expression. Each ADCP was programmed to record current velocity and backscatter data at 12-minute intervals using 0.5-meter vertical bins. The ADCPs were recovered on July 22 and 23, 2010.

2.4 Real-Time Data Collection

Current velocity and water quality data were collected in real-time along six transects corresponding to the six *in situ* CT-OBS instrument moorings. Current velocity and backscatter data were collected in real-time using downward looking, vessel–mounted 1200 kHz ADCPs. The ADCP data were collected in 0.5-meter vertical bins. Upon completion of each transect, a Seabird SBE 19 SeaCat water quality vertical profiler was used at three locations, evenly spaced along each transect (four above Dundee Dam) to measure temperature, conductivity/salinity, and turbidity. This unit had a direct hard-wired connection to an on-board computer that records the data in real-time. At each of the vertical profile stations, water samples were collected through a pump system attached to the CTD vertical profiler. Water samples were collected 3 feet below the surface and 3 feet above the bottom. All water samples were collected and handled by both the onboard AECOM and EPA representatives. In addition, periodic water samples for POC/DOC analyses were collected.

3.0 DATA PRESENTATION

3.1 Water Sample Data

The water samples collected throughout the field program were analyzed for Suspended Sediment Concentrations (SSC) by Columbia Analytical Services, an EPA approved lab. The lab results of the water samples were amassed by AECOM and will be delivered under separate cover.

3.2 *In Situ* Instrumentation

In situ measurements of current velocity and water quality parameters were recorded continuously from late March through late July 2010 with only three minor instrument stoppages (typically less than 2 hrs) during servicing operations at each station. OSI took multiple steps to limit biological fouling on the moorings through the use of bottom paint,

copper, zinc anodes, and instrument wipers. However biological fouling occurred at most of the moorings during the months of June and July, which primarily influenced the *in situ* turbidity, probes. Table 5 lists the periods of each CT-OBS instrument when turbidity data was beyond the range of expected values.

Table 5. *In Situ* Instrument Fouling Periods

	Fouling Period	
Station	**Begin**	**End**
014 Surface	06/11/2010 13:00	06/18/2010 14:00
014 Surface	07/01/2010 15:48	07/22/2010 14:48
014 Bottom	05/31/2010 16:48	06/18/2010 13:12
014 Bottom	06/26/2010 19:48	07/10/2010 19:00
042 Surface	05/27/2010 04:00	06/18/2010 17:12
042 Surface	06/26/2010 12:00	07/22/2010 17:24
042 Bottom	06/07/2010 01:24	06/18/2010 16:12
042 Bottom	06/29/2010 17:36	07/22/2010 12:36
067 Surface	07/04/2010 02:00	07/23/2010 16:36
067 Bottom	06/11/2010 20:12	06/17/2010 18:48
067 Bottom	07/02/2010 00:24	07/23/2010 16:12
102 Bottom	06/13/2010 10:12	06/17/2010 16:24
135 Surface	07/07/2010 18:48	07/15/2010 03:36
135 Bottom	07/14/2010 15:24	07/15/2010 21:12

The CT-OBS and ADCP times series plots have been plotted in two colors (red=ebb, blue=flood) to emphasis tidal flow conditions as determine by the ADCP vertically averaged current direction data at each station. The CT-OBS data have been presented as time series plots of temperature (º C), salinity (PSU), and turbidity (NTU) in Appendix 4. The ADCP current velocity data are presented as time series plots of vertically averaged current speed (mm/s) and direction (º True) in Appendix 5. The data are also available in Microsoft Excel spreadsheets on the enclosed CD-ROM in Appendix 12

The CTD-OBS vertical profiles recorded after deployment (Event E01), before and after servicing (Events E05, E09, E10, E14, E15, & E19), and prior to recovery (Event E23) are presented in Appendix 6. Vertical profiles collected above Dundee Dam were incorporated with the real-time survey events and are listed in the corresponding Appendices 7-11.

3.3 Real-Time Survey Events

Current data from the VMADCP are presented as vector plots in Appendix 7 (Trip 4, Events E02-E04), Appendix 8 (Trip 5, Events E06-E08), Appendix 9 (Trip 6, Events E11-E13) Appendix 10 (Trip 7, Events E16-E18) and Appendix 11 (Trip 8, Events E20-E22).

Six CTD-OBS profiles conducted during the March 2010 real-time survey events recorded temperature values inconsistent with *in situ* instrumentation and adjacent profiles (Table 6). The CTD-OBS profiler continued to operate properly before and after these profiles and all other parameters recorded correctly.

Table 6. CTD-OBS Temperature Inconsistencies

CTD-OBS Vertical Profiles
10A-E03-T102-P1
10A-E03-T135-P1
10A-E03-T135-P3
10A-E04-T067-P1
10A-E04-T102-P1
10A-E04-T135-P1

Data from the CTD-OBS vertical profiles are presented in Appendix 7-11 corresponding to each trip. Data files of the vertical profiles are available on the enclosed CD-ROM in Appendix 12.

4.0 PROJECT SUMMARY

The oceanographic data acquisition equipment was deployed for a four-month period during which five real time boat based surveys were conducted. The *in situ* instrumentation was deployed at six stations; five were located in the lower Passaic River and one above Dundee Dam. The instrumentation was deployed to collect data during an expected high flow period and the deployment extended to capture low flow conditions. The program successfully measured the range of flow conditions extant (140 ft^3/s – 10,200 ft^3/s) in the lower Passaic River during the spring and summer of 2010 with daily tidal ranges between 4 and 7 feet.

APPENDIX 1: Water Sampling Log

Water Sample Data: Events E01-E23
Passaic River, Newark, NJ
Client: AECOM
OSI Job # 09ES053

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
03/22/2010	15:32	597991	691234	10A	E01	T014	P3	AS	19.5	3.0
03/22/2010	15:30	597989	691236	10A	E01	T014	P3	BS	19.5	16.5
03/22/2010	15:05	588242	692308	10A	E01	T042	P1	AS	18.5	3.0
03/22/2010	15:02	588245	692305	10A	E01	T042	P1	BS	18.5	15.5
03/23/2010	14:04	586141	702832	10A	E01	T067	P3	AS	13.5	3.0
03/23/2010	14:02	586135	702833	10A	E01	T067	P3	BS	13.5	10.5
03/23/2010	13:32	592110	719741	10A	E01	T102	P1	AS	15.5	3.0
03/23/2010	13:31	592111	719748	10A	E01	T102	P1	BS	15.5	12.5
03/24/2010	14:06	597208	734290	10A	E01	T135	P3	AS	16.5	3.0
03/24/2010	14:04	597211	597211	10A	E01	T135	P3	BS	16.5	13.5
03/24/2010	14:04	597212	734294	10A	E01	T135	P3	BT	16.5	13.5
03/24/2010	18:23	594437	747325	10A	E02	T175	P1	AS	7.5	3.0
03/24/2010	18:33	594488	747508	10A	E02	T175	P2	AS	8.2	3.0
03/24/2010	18:37	594485	747512	10A	E02	T175	P2	BS	8.2	5.2
03/24/2010	18:47	594632	747680	10A	E02	T175	P3	AS	6.3	3.2
03/24/2010	18:53	594674	747746	10A	E02	T175	P4	AS	6.8	3.4
03/25/2010	11:56	597790	691293	10A	E03	T014	P1	AS	16.0	3.0
03/25/2010	11:54	597783	691292	10A	E03	T014	P1	BS	16.0	13.0
03/25/2010	12:08	597913	691253	10A	E03	T014	P2	AS	17.0	3.0
03/25/2010	12:07	597909	691244	10A	E03	T014	P2	BS	17.0	14.0
03/25/2010	12:22	598000	691224	10A	E03	T014	P3	AS	16.0	3.0
03/25/2010	12:19	597998	691221	10A	E03	T014	P3	BS	16.0	13.0
03/25/2010	12:56	588237	692307	10A	E03	T042	P1	AS	17.0	3.0
03/25/2010	12:57	588240	692301	10A	E03	T042	P1	AT	17.0	3.0
03/25/2010	12:54	588240	692302	10A	E03	T042	P1	BS	17.0	14.0
03/25/2010	13:08	588239	692388	10A	E03	T042	P2	AS	19.0	3.0
03/25/2010	13:06	588230	692383	10A	E03	T042	P2	BS	19.0	16.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
03/25/2010	13:21	588231	692459	10A	E03	T042	P3	AS	16.0	3.0
03/25/2010	13:17	588234	692457	10A	E03	T042	P3	BS	16.0	13.0
03/25/2010	13:22	586020	702933	10A	E03	T067	P1	AS	12.8	3.0
03/25/2010	13:20	586023	702929	10A	E03	T067	P1	BS	12.8	9.8
03/25/2010	13:31	586080	702882	10A	E03	T067	P2	AS	15.2	3.0
03/25/2010	13:28	586079	702882	10A	E03	T067	P2	BS	15.2	12.2
03/25/2010	13:36	586128	702830	10A	E03	T067	P3	AS	14.2	3.0
03/25/2010	13:34	586130	702829	10A	E03	T067	P3	BS	14.2	11.2
03/25/2010	12:09	592095	719745	10A	E03	T102	P1	AS	11.1	3.0
03/25/2010	12:09	592098	719746	10A	E03	T102	P1	AT	11.1	8.1
03/25/2010	12:06	592098	719742	10A	E03	T102	P1	BS	11.1	8.1
03/25/2010	12:19	592150	719746	10A	E03	T102	P2	AS	17.1	3.0
03/25/2010	12:18	592153	719747	10A	E03	T102	P2	BS	17.1	14.1
03/25/2010	12:29	592210	719742	10A	E03	T102	P3	AS	10.1	3.0
03/25/2010	12:27	592213	719741	10A	E03	T102	P3	BS	10.1	7.1
03/25/2010	11:31	597077	734351	10A	E03	T135	P1	AS	13.2	3.0
03/25/2010	11:29	597076	734353	10A	E03	T135	P1	BS	13.2	10.0
03/25/2010	11:19	597151	734313	10A	E03	T135	P2	AS	14.3	3.0
03/25/2010	11:17	597151	734312	10A	E03	T135	P2	BS	14.3	11.3
03/25/2010	11:09	597200	734288	10A	E03	T135	P3	AS	12.3	3.0
03/25/2010	11:06	597203	734285	10A	E03	T135	P3	BS	12.3	9.3
03/25/2010	18:15	597786	691295	10A	E04	T014	P1	AS	15.0	3.0
03/25/2010	18:13	597790	691295	10A	E04	T014	P1	BS	15.0	12.0
03/25/2010	18:23	597898	691248	10A	E04	T014	P2	AS	18.0	3.0
03/25/2010	18:22	597901	691253	10A	E04	T014	P2	BS	18.0	15.0
03/25/2010	18:33	597994	691224	10A	E04	T014	P3	AS	18.0	3.0
03/25/2010	18:30	597996	691226	10A	E04	T014	P3	BS	18.0	15.0
03/25/2010	19:01	588247	692306	10A	E04	T042	P1	AS	19.0	3.0
03/25/2010	19:03	588255	692305	10A	E04	T042	P1	AT	19.0	3.0
03/25/2010	18:59	588251	692306	10A	E04	T042	P1	BS	19.0	16.0
03/25/2010	19:12	588230	692389	10A	E04	T042	P2	AS	23.0	3.0
03/25/2010	19:11	588231	692392	10A	E04	T042	P2	BS	23.0	20.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
03/25/2010	19:20	588226	692461	10A	E04	T042	P3	AS	18.0	3.0
03/25/2010	19:17	588223	692463	10A	E04	T042	P3	BS	18.0	13.0
03/25/2010	19:22	586022	702931	10A	E04	T067	P1	AS	10.0	3.0
03/25/2010	19:21	586020	702934	10A	E04	T067	P1	BS	10.0	7.0
03/25/2010	19:29	586078	702885	10A	E04	T067	P2	AS	17.0	3.0
03/25/2010	19:28	586080	702882	10A	E04	T067	P2	BS	17.0	14.0
03/25/2010	19:38	586133	702833	10A	E04	T067	P3	AS	16.4	3.0
03/25/2010	19:36	586133	702836	10A	E04	T067	P3	BS	16.4	13.4
03/25/2010	18:18	592101	719743	10A	E04	T102	P1	AS	15.1	3.0
03/25/2010	18:19	592102	719744	10A	E04	T102	P1	AT	15.1	3.0
03/25/2010	18:16	592101	719744	10A	E04	T102	P1	BS	15.1	12.1
03/25/2010	18:28	592155	719744	10A	E04	T102	P2	AS	16.0	3.0
03/25/2010	18:27	592155	719745	10A	E04	T102	P2	BS	16.0	13.0
03/25/2010	18:27	592148	719745	10A	E04	T102	P2	BT	16.0	13.0
03/25/2010	18:28	592155	719744	10A	E04	T102	P3	AS	16.2	3.0
03/25/2010	18:27	592148	719745	10A	E04	T102	P3	BS	16.2	13.2
03/25/2010	17:06	597076	734351	10A	E04	T135	P1	AS	7.7	3.0
03/25/2010	17:04	597077	734351	10A	E04	T135	P1	BS	7.7	4.7
03/25/2010	17:04	597076	734353	10A	E04	T135	P1	BT	7.7	4.7
03/25/2010	17:15	597152	734316	10A	E04	T135	P2	AS	12.1	3.0
03/25/2010	17:13	597151	734313	10A	E04	T135	P2	BS	12.1	9.1
03/25/2010	17:25	597200	734288	10A	E04	T135	P3	AS	15.9	3.0
03/25/2010	17:22	597202	734286	10A	E04	T135	P3	BS	15.9	12.9

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
05/02/2010	12:36	597997	691232	10A	E05	T014	P3	BS	16.5	13.5
05/02/2010	12:36	597990	691224	10A	E05	T014	P3	AS	16.5	3.0
05/02/2010	15:13	588240	692308	10A	E05	T042	P1	BS	19.0	16.0
05/02/2010	15:15	588245	692311	10A	E05	T042	P1	AS	19.0	3.0
05/02/2010	15:15	588245	692311	10A	E05	T042	P1	AT	19.0	3.0
05/01/2010	18:44	586137	702839	10A	E05	T067	P3	BS	15.0	12.0
05/01/2010	19:25	586138	702831	10A	E05	T067	P3	AS	15.0	3.0
05/01/2010	16:14	592104	719744	10A	E05	T102	P1	BS	18.0	15.0
05/01/2010	16:16	592109	719742	10A	E05	T102	P1	AS	18.0	3.0
05/01/2010	13:57	597212	734286	10A	E05	T135	P3	BS	17.0	14.0
05/01/2010	13:58	597211	734291	10A	E05	T135	P3	AS	17.0	3.0
05/04/2010	16:01	594478	747521	10A	E05	T175	P2	BS	9.0	6.0
05/04/2010	16:02	594476	747518	10A	E05	T175	P2	AS	9.0	3.0
05/04/2010	17:12	594439	747325	10A	E06	T175	P1	AS	4.0	3.0
05/04/2010	17:20	594467	747520	10A	E06	T175	P2	BS	9.0	6.0
05/04/2010	17:21	594477	747519	10A	E06	T175	P2	AS	9.0	3.0
05/04/2010	17:29	594626	747669	10A	E06	T175	P3	AS	6.0	3.0
05/04/2010	17:35	594679	747740	10A	E06	T175	P4	AS	5.0	3.0
05/03/2010	13:32	597791	691299	10A	E07	T014	P1	BS	13.0	10.0
05/03/2010	13:34	597783	691295	10A	E07	T014	P1	AS	13.0	3.0
05/03/2010	13:39	597917	691245	10A	E07	T014	P2	BS	15.0	12.0
05/03/2010	13:40	597909	691241	10A	E07	T014	P2	AS	15.0	3.0
05/03/2010	13:45	597984	691225	10A	E07	T014	P3	BS	14.0	11.0
05/03/2010	13:47	597985	691229	10A	E07	T014	P3	AS	14.0	3.0
05/03/2010	14:11	588235	692304	10A	E07	T042	P1	BS	15.0	12.0
05/03/2010	14:13	588241	692304	10A	E07	T042	P1	AS	15.0	3.0
05/03/2010	14:17	588244	692382	10A	E07	T042	P2	BS	19.0	16.0
05/03/2010	14:18	588240	692387	10A	E07	T042	P2	AS	19.0	3.0
05/03/2010	14:24	588213	692454	10A	E07	T042	P3	BS	15.0	12.0
05/03/2010	14:25	588219	692467	10A	E07	T042	P3	AS	15.0	3.0
05/03/2010	14:50	586018	702935	10A	E07	T067	P1	BS	14.9	11.9
05/03/2010	14:52	586023	702938	10A	E07	T067	P1	AS	14.9	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
05/03/2010	14:52	586018	702938	10A	E07	T067	P1	AT	14.9	3.0
05/03/2010	14:59	586077	702888	10A	E07	T067	P2	BS	15.5	12.5
05/03/2010	15:01	586072	702885	10A	E07	T067	P2	AS	15.5	3.0
05/03/2010	15:06	586128	702837	10A	E07	T067	P3	BS	15.2	12.2
05/03/2010	15:07	586129	702835	10A	E07	T067	P3	BT	15.2	12.2
05/03/2010	15:08	586128	702833	10A	E07	T067	P3	AS	15.2	3.0
05/03/2010	13:45	592105	719746	10A	E07	T102	P1	BS	16.0	13.0
05/03/2010	13:48	592099	719746	10A	E07	T102	P1	AS	16.0	3.0
05/03/2010	13:55	592153	719743	10A	E07	T102	P2	BS	17.0	14.0
05/03/2010	13:56	592156	719742	10A	E07	T102	P2	AS	17.0	3.0
05/03/2010	14:02	592209	719749	10A	E07	T102	P3	BS	16.5	13.5
05/03/2010	14:05	592210	719744	10A	E07	T102	P3	AS	16.5	3.0
05/03/2010	12:42	597078	734355	10A	E07	T135	P1	BS	10.0	7.0
05/03/2010	12:43	597081	734356	10A	E07	T135	P1	AS	10.0	3.0
05/03/2010	12:55	597153	734311	10A	E07	T135	P2	BS	13.0	10.0
05/03/2010	12:56	597149	734313	10A	E07	T135	P2	AS	13.0	3.0
05/03/2010	13:06	597204	734286	10A	E07	T135	P3	BS	16.0	13.0
05/03/2010	13:08	597201	734287	10A	E07	T135	P3	AS	16.0	3.0
05/03/2010	13:08	597201	734287	10A	E07	T135	P3	AT	16.0	3.0
05/03/2010	19:58	597791	691287	10A	E08	T014	P1	BS	15.0	12.0
05/03/2010	20:00	597787	691277	10A	E08	T014	P1	AS	15.0	3.0
05/03/2010	20:05	597906	691226	10A	E08	T014	P2	BS	15.0	12.0
05/03/2010	20:06	597908	691247	10A	E08	T014	P2	AS	15.0	3.0
05/03/2010	20:10	597973	691212	10A	E08	T014	P3	BS	13.5	10.5
05/03/2010	20:12	597989	691208	10A	E08	T014	P3	AS	13.5	3.0
05/03/2010	20:33	588240	692292	10A	E08	T042	P1	BS	15.0	12.0
05/03/2010	20:34	588233	692294	10A	E08	T042	P1	AS	15.0	3.0
05/03/2010	20:39	588232	692386	10A	E08	T042	P2	BS	18.0	15.0
05/03/2010	20:39	588233	692375	10A	E08	T042	P2	AS	18.0	3.0
05/03/2010	20:44	588226	692452	10A	E08	T042	P3	BS	13.0	11.0
05/03/2010	20:45	588227	692465	10A	E08	T042	P3	AS	13.0	3.0
05/03/2010	20:05	586022	702937	10A	E08	T067	P1	BS	12.3	9.3

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
05/03/2010	20:07	586017	702937	10A	E08	T067	P1	AS	12.3	3.0
05/03/2010	20:16	586076	702885	10A	E08	T067	P2	BS	15.0	12.0
05/03/2010	20:17	586079	702884	10A	E08	T067	P2	AS	15.0	3.0
05/03/2010	20:22	586130	702829	10A	E08	T067	P3	BS	13.0	10.0
05/03/2010	20:24	586127	702833	10A	E08	T067	P3	AS	13.0	3.0
05/03/2010	19:03	592099	719742	10A	E08	T102	P1	BS	11.0	9.0
05/03/2010	19:07	592097	719738	10A	E08	T102	P1	AS	11.0	3.0
05/03/2010	19:13	592147	719746	10A	E08	T102	P2	BS	16.8	13.8
05/03/2010	19:14	592149	719744	10A	E08	T102	P2	AS	16.8	3.0
05/03/2010	19:15	592148	719750	10A	E08	T102	P2	AT	16.8	3.0
05/03/2010	19:26	592213	719750	10A	E08	T102	P3	BS	14.3	11.3
05/03/2010	19:29	592209	719747	10A	E08	T102	P3	AS	14.3	3.0
05/03/2010	19:29	592215	719749	10A	E08	T102	P3	AT	14.3	3.0
05/03/2010	18:14	597073	734349	10A	E08	T135	P1	BS	13.0	10.0
05/03/2010	18:17	597073	734353	10A	E08	T135	P1	AS	13.0	3.0
05/03/2010	18:25	597150	734311	10A	E08	T135	P2	BS	15.3	12.3
05/03/2010	18:26	597148	734315	10A	E08	T135	P2	AS	15.3	3.0
05/03/2010	18:32	597199	734287	10A	E08	T135	P3	BS	16.0	14.0
05/03/2010	18:34	597199	734284	10A	E08	T135	P3	AS	16.0	3.0
05/03/2010	18:35	597201	734290	10A	E08	T135	P3	AT	16.0	3.0
05/02/2010	14:45	598000	691235	10A	E09	T014	P3	BS	19.0	16.0
05/02/2010	14:46	597993	691234	10A	E09	T014	P3	AS	19.0	3.0
05/02/2010	17:00	588243	692308	10A	E09	T042	P1	BS	19.5	16.5
05/02/2010	17:01	588241	692312	10A	E09	T042	P1	AS	19.5	3.0
05/01/2010	20:59	586143	702835	10A	E09	T067	P3	BS	12.0	9.0
05/01/2010	21:00	586138	702842	10A	E09	T067	P3	AS	12.0	3.0
05/01/2010	17:59	592107	719758	10A	E09	T102	P1	BS	17.0	14.0
05/01/2010	17:59	592107	719758	10A	E09	T102	P1	BT	17.0	14.0
05/01/2010	18:01	592111	719752	10A	E09	T102	P1	AS	17.0	3.0
05/01/2010	15:51	597208	597208	10A	E09	T135	P3	BS	17.0	14.0
05/01/2010	15:53	597209	734290	10A	E09	T135	P3	AS	17.0	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
05/20/2010	12:55	598001	691231	10A	E10	T014	P3	BS	13.5	10.5
05/20/2010	12:57	597996	691233	10A	E10	T014	P3	AS	13.5	3.0
05/20/2010	12:57	597996	691233	10A	E10	T014	P3	AT	13.5	3.0
05/20/2010	15:12	588246	692309	10A	E10	T042	P1	BS	16.5	13.5
05/20/2010	15:13	588247	692304	10A	E10	T042	P1	AS	16.5	3.0
05/19/2010	19:23	586136	702834	10A	E10	T067	P3	BS	15.0	12.0
05/19/2010	19:24	586134	702826	10A	E10	T067	P3	AS	15.0	3.0
05/19/2010	16:52	592108	719749	10A	E10	T102	P1	BS	18.0	15.0
05/19/2010	16:53	592102	719749	10A	E10	T102	P1	AS	18.0	3.0
05/19/2010	14:11	597210	734294	10A	E10	T135	P3	BS	14.0	11.0
05/19/2010	14:12	597209	734291	10A	E10	T135	P3	AS	14.0	3.0
05/25/2010	14:34	594478	747516	10A	E10	T175	P2	BS	9.0	6.0
05/25/2010	14:35	594476	747516	10A	E10	T175	P2	AS	9.0	3.0
05/25/2010	15:40	594438	747321	10A	E11	T175	P1	AS	4.0	3.0
05/25/2010	15:43	594477	747516	10A	E11	T175	P2	BS	9.0	6.0
05/25/2010	15:45	594476	747517	10A	E11	T175	P2	AS	9.0	3.0
05/25/2010	15:49	594628	747664	10A	E11	T175	P3	AS	5.0	3.0
05/25/2010	15:52	594684	747740	10A	E11	T175	P4	AS	4.6	3.0
05/24/2010	12:40	597788	691284	10A	E12	T014	P1	BS	14.0	11.0
05/24/2010	12:41	597782	691292	10A	E12	T014	P1	AS	14.0	3.0
05/24/2010	12:50	597910	691251	10A	E12	T014	P2	BS	18.0	15.0
05/24/2010	12:51	597902	691251	10A	E12	T014	P2	AS	18.0	3.0
05/24/2010	13:01	597990	691225	10A	E12	T014	P3	BS	16.0	13.0
05/24/2010	13:03	597994	691224	10A	E12	T014	P3	AS	16.0	3.0
05/24/2010	13:05	597990	691224	10A	E12	T014	P3	AT	16.0	3.0
05/24/2010	13:33	588242	692305	10A	E12	T042	P1	BS	17.0	14.0
05/24/2010	13:35	588242	692302	10A	E12	T042	P1	AS	17.0	3.0
05/24/2010	13:43	588227	692391	10A	E12	T042	P2	BS	20.0	17.0
05/24/2010	13:44	692391	692387	10A	E12	T042	P2	AS	20.0	3.0
05/24/2010	13:52	588221	692460	10A	E12	T042	P3	BS	15.0	12.0
05/24/2010	13:53	588225	692462	10A	E12	T042	P3	AS	15.0	3.0
05/24/2010	13:19	586020	702932	10A	E12	T067	P1	BS	13.4	10.4

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
05/24/2010	13:21	586023	702931	10A	E12	T067	P1	AS	13.4	3.0
05/24/2010	13:27	586082	702886	10A	E12	T067	P2	BS	16.0	13.0
05/24/2010	13:27	586080	702887	10A	E12	T067	P2	BT	16.0	13.0
05/24/2010	13:28	586078	702885	10A	E12	T067	P2	AS	16.0	3.0
05/24/2010	13:31	586132	702830	10A	E12	T067	P3	BS	14.7	10.7
05/24/2010	13:32	586131	702833	10A	E12	T067	P3	AS	14.7	3.0
05/24/2010	12:26	592101	719743	10A	E12	T102	P1	BS	16.0	13.0
05/24/2010	12:28	592102	719745	10A	E12	T102	P1	AS	16.0	3.0
05/24/2010	12:34	592153	719742	10A	E12	T102	P2	BS	17.5	14.5
05/24/2010	12:36	592151	719743	10A	E12	T102	P2	AS	17.5	3.0
05/24/2010	12:41	592213	719742	10A	E12	T102	P3	BS	17.6	14.6
05/24/2010	12:43	592211	719742	10A	E12	T102	P3	AS	17.6	3.0
05/24/2010	11:26	597075	734354	10A	E12	T135	P1	BS	10.0	7.0
05/24/2010	11:27	597078	734354	10A	E12	T135	P1	AS	10.0	3.0
05/24/2010	11:33	597152	734315	10A	E12	T135	P2	BS	15.9	12.9
05/24/2010	11:34	597152	734313	10A	E12	T135	P2	AS	15.9	3.0
05/24/2010	11:40	597201	734289	10A	E12	T135	P3	BS	17.0	14.0
05/24/2010	11:43	597202	734288	10A	E12	T135	P3	AS	17.0	3.0
05/24/2010	19:00	597790	691290	10A	E13	T014	P1	BS	13.0	10.0
05/24/2010	19:01	597795	691293	10A	E13	T014	P1	AS	13.0	3.0
05/24/2010	19:08	597901	691252	10A	E13	T014	P2	BS	18.0	15.0
05/24/2010	19:09	597907	691249	10A	E13	T014	P2	AS	18.0	3.0
05/24/2010	19:14	597990	691221	10A	E13	T014	P3	BS	18.0	15.0
05/24/2010	19:15	597990	691220	10A	E13	T014	P3	BT	18.0	15.0
05/24/2010	19:17	597987	691220	10A	E13	T014	P3	AS	18.0	3.0
05/24/2010	19:44	588240	692297	10A	E13	T042	P1	BS	18.0	15.0
05/24/2010	19:44	588237	692294	10A	E13	T042	P1	BT	18.0	15.0
05/24/2010	19:45	588243	692294	10A	E13	T042	P1	AS	18.0	3.0
05/24/2010	19:52	588229	692389	10A	E13	T042	P2	BS	21.0	18.0
05/24/2010	19:53	588229	692387	10A	E13	T042	P2	AS	21.0	3.0
05/24/2010	19:59	588226	692458	10A	E13	T042	P3	BS	19.0	16.0
05/24/2010	20:00	588230	692460	10A	E13	T042	P3	AS	19.0	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
05/24/2010	19:31	586021	702931	10A	E13	T067	P1	BS	12.6	9.6
05/24/2010	19:33	586020	702933	10A	E13	T067	P1	AS	12.6	3.0
05/24/2010	19:37	586081	702883	10A	E13	T067	P2	BS	12.4	9.4
05/24/2010	19:37	586081	702885	10A	E13	T067	P2	AS	12.4	3.0
05/24/2010	19:41	586130	702831	10A	E13	T067	P3	BS	13.8	9.8
05/24/2010	19:43	586132	702833	10A	E13	T067	P3	AS	13.8	3.0
05/24/2010	18:44	592103	719746	10A	E13	T102	P1	BS	12.9	9.9
05/24/2010	18:46	592104	719745	10A	E13	T102	P1	AS	12.9	3.0
05/24/2010	18:47	592102	719746	10A	E13	T102	P1	AT	12.9	3.0
05/24/2010	18:50	592151	719744	10A	E13	T102	P2	BS	12.4	9.4
05/24/2010	18:51	592151	719743	10A	E13	T102	P2	AS	12.4	3.0
05/24/2010	18:54	592212	719744	10A	E13	T102	P3	BS	13.4	10.4
05/24/2010	18:56	592212	719744	10A	E13	T102	P3	AS	13.4	3.0
05/24/2010	17:58	597079	734354	10A	E13	T135	P1	BS	9.0	6.0
05/24/2010	18:00	597079	734352	10A	E13	T135	P1	AS	9.0	3.0
05/24/2010	18:01	597077	734354	10A	E13	T135	P1	AT	9.0	3.0
05/24/2010	18:06	597152	734315	10A	E13	T135	P2	BS	11.6	8.6
05/24/2010	18:07	597154	734315	10A	E13	T135	P2	AS	11.6	3.0
05/24/2010	18:11	597203	734286	10A	E13	T135	P3	BS	12.6	9.6
05/24/2010	18:12	597201	734287	10A	E13	T135	P3	AS	12.6	3.0
05/20/2010	14:42	597998	691237	10A	E14	T014	P3	BS	16.0	13.0
05/20/2010	14:44	598004	691237	10A	E14	T014	P3	AS	16.0	3.0
05/20/2010	16:40	588244	692306	10A	E14	T042	P1	BS	18.5	15.5
05/20/2010	16:41	588236	692316	10A	E14	T042	P1	AS	18.5	3.0
05/19/2010	20:51	586138	702836	10A	E14	T067	P3	BS	14.0	11.0
05/19/2010	20:53	586135	702837	10A	E14	T067	P3	AS	14.0	3.0
05/19/2010	18:38	592109	719748	10A	E14	T102	P1	BS	19.0	16.0
05/19/2010	18:40	592108	719746	10A	E14	T102	P1	AS	19.0	3.0
05/19/2010	16:16	597208	734293	10A	E14	T135	P3	BS	17.0	14.0
05/19/2010	16:17	597207	734291	10A	E14	T135	P3	AS	17.0	3.0
05/19/2010	16:17	597207	734291	10A	E14	T135	P3	AT	17.0	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
06/18/2010	12:55	597996	691239	10A	E15	T014	P3	BS	14.9	11.9
06/18/2010	12:56	597994	691238	10A	E15	T014	P3	AS	14.9	3.0
06/18/2010	15:56	588239	692304	10A	E15	T042	P1	BS	16.2	13.2
06/18/2010	15:57	588242	692306	10A	E15	T042	P1	AS	16.2	3.0
06/17/2010	18:49	586136	702832	10A	E15	T067	P3	BS	16.6	13.3
06/17/2010	18:50	586140	702829	10A	E15	T067	P3	AS	16.6	3.0
06/17/2010	16:15	592105	719751	10A	E15	T102	P1	BS	16.8	13.8
06/17/2010	16:16	592106	719752	10A	E15	T102	P1	AS	16.8	3.0
06/17/2010	13:27	597205	734300	10A	E15	T135	P3	BS	11.3	8.3
06/17/2010	13:28	597206	734297	10A	E15	T135	P3	AS	11.3	3.0
06/21/2010	19:14	594478	747515	10A	E15	T175	P2	BS	10.0	7.0
06/21/2010	19:14	594475	747517	10A	E15	T175	P2	BT	10.0	7.0
06/21/2010	19:15	594478	747518	10A	E15	T175	P2	AS	10.0	3.0
06/21/2010	20:17	594438	747322	10A	E16	T175	P1	AS	6.0	3.0
06/21/2010	20:21	594477	747517	10A	E16	T175	P2	BS	10.0	7.0
06/21/2010	20:23	594476	747517	10A	E16	T175	P2	AS	10.0	3.0
06/21/2010	20:28	594625	747664	10A	E16	T175	P3	AS	5.0	3.0
06/21/2010	20:31	594684	747738	10A	E16	T175	P4	AS	6.0	3.0
06/22/2010	12:22	597791	691290	10A	E17	T014	P1	BS	15.0	12.0
06/22/2010	12:23	597789	691292	10A	E17	T014	P1	AS	15.0	3.0
06/22/2010	12:30	597903	691248	10A	E17	T014	P2	BS	18.0	15.0
06/22/2010	12:30	597905	691250	10A	E17	T014	P2	AS	18.0	3.0
06/22/2010	12:38	597981	691223	10A	E17	T014	P3	BS	16.0	13.0
06/22/2010	12:39	597981	691227	10A	E17	T014	P3	AS	16.0	3.0
06/22/2010	13:07	588242	692300	10A	E17	T042	P1	BS	16.0	13.0
06/22/2010	13:09	588246	692302	10A	E17	T042	P1	AS	16.0	3.0
06/22/2010	13:13	588226	692387	10A	E17	T042	P2	BS	20.0	17.0
06/22/2010	13:14	588234	692387	10A	E17	T042	P2	AS	20.0	3.0
06/22/2010	13:14	588225	692386	10A	E17	T042	P2	AT	20.0	3.0
06/22/2010	13:18	588223	692465	10A	E17	T042	P3	BS	15.0	12.0
06/22/2010	13:19	588224	692468	10A	E17	T042	P3	AS	15.0	3.0
06/22/2010	12:35	586021	702929	10A	E17	T067	P1	BS	14.2	11.2

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
06/22/2010	12:37	586021	702933	10A	E17	T067	P1	AS	14.2	3.0
06/22/2010	12:40	586080	702883	10A	E17	T067	P2	BS	16.2	13.2
06/22/2010	12:41	586081	702885	10A	E17	T067	P2	AS	16.2	3.0
06/22/2010	12:47	586131	702832	10A	E17	T067	P3	BS	14.6	11.6
06/22/2010	12:48	586133	702831	10A	E17	T067	P3	BT	14.6	11.6
06/22/2010	12:50	586130	702830	10A	E17	T067	P3	AS	14.6	3.0
06/22/2010	11:54	592101	719744	10A	E17	T102	P1	BS	16.2	13.2
06/22/2010	11:56	592102	719744	10A	E17	T102	P1	AS	16.2	3.0
06/22/2010	11:59	592151	719743	10A	E17	T102	P2	BS	17.3	13.3
06/22/2010	12:00	592150	719744	10A	E17	T102	P2	AS	17.3	3.0
06/22/2010	12:06	592211	719742	10A	E17	T102	P3	BS	16.1	13.1
06/22/2010	12:06	592212	719744	10A	E17	T102	P3	BT	16.1	13.1
06/22/2010	12:08	592212	719742	10A	E17	T102	P3	AS	16.1	3.0
06/22/2010	11:15	597077	734351	10A	E17	T135	P1	BS	11.0	8.0
06/22/2010	11:18	597075	734353	10A	E17	T135	P1	AS	11.0	3.0
06/22/2010	11:21	597155	734315	10A	E17	T135	P2	BS	14.4	11.4
06/22/2010	11:22	597151	734314	10A	E17	T135	P2	AS	14.4	3.0
06/22/2010	11:26	597204	734288	10A	E17	T135	P3	BS	16.1	13.1
06/22/2010	11:29	597203	734287	10A	E17	T135	P3	AS	16.1	3.0
06/22/2010	20:28	597788	691289	10A	E18	T014	P1	BS	19.1	16.1
06/22/2010	20:29	597788	691292	10A	E18	T014	P1	AS	19.1	3.0
06/22/2010	20:32	597905	691249	10A	E18	T014	P2	BS	20.9	17.9
06/22/2010	20:33	597906	691247	10A	E18	T014	P2	AS	20.9	3.0
06/22/2010	20:35	597981	691223	10A	E18	T014	P3	BS	18.7	15.7
06/22/2010	20:38	597983	691222	10A	E18	T014	P3	AS	18.7	3.0
06/22/2010	20:38	597982	691222	10A	E18	T014	P3	AT	18.7	3.0
06/22/2010	19:55	588240	692299	10A	E18	T042	P1	BS	19.1	16.0
06/22/2010	19:57	588241	692299	10A	E18	T042	P1	AS	19.1	3.0
06/22/2010	20:00	588234	692389	10A	E18	T042	P2	BS	23.5	21.0
06/22/2010	20:00	588231	692387	10A	E18	T042	P2	AS	23.5	3.0
06/22/2010	20:03	588226	692464	10A	E18	T042	P3	BS	18.9	15.9
06/22/2010	20:05	588226	692461	10A	E18	T042	P3	AS	18.9	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
06/22/2010	19:12	586020	702931	10A	E18	T067	P1	BS	13.2	10.2
06/22/2010	19:13	586020	702930	10A	E18	T067	P1	AS	13.2	3.0
06/22/2010	19:15	586079	702883	10A	E18	T067	P2	BS	15.2	13.2
06/22/2010	19:16	586079	702885	10A	E18	T067	P2	AS	15.2	3.0
06/22/2010	19:21	586131	702829	10A	E18	T067	P3	BS	16.6	13.6
06/22/2010	19:23	586131	702831	10A	E18	T067	P3	AS	16.6	3.0
06/22/2010	18:23	592101	719746	10A	E18	T102	P1	BS	14.3	11.3
06/22/2010	18:28	592103	719746	10A	E18	T102	P1	AS	14.3	3.0
06/22/2010	18:32	592153	719745	10A	E18	T102	P2	BS	15.2	12.2
06/22/2010	18:32	592150	719746	10A	E18	T102	P2	AS	15.2	3.0
06/22/2010	18:36	592213	719744	10A	E18	T102	P3	BS	16.3	13.3
06/22/2010	18:37	592210	719743	10A	E18	T102	P3	AS	16.3	3.0
06/22/2010	17:44	597076	734353	10A	E18	T135	P1	BS	8.1	5.1
06/22/2010	17:46	597077	734353	10A	E18	T135	P1	AS	8.1	3.0
06/22/2010	17:49	597153	734314	10A	E18	T135	P2	BS	9.5	6.5
06/22/2010	17:50	597152	734313	10A	E18	T135	P2	AS	9.5	3.0
06/22/2010	17:54	597204	734288	10A	E18	T135	P3	BS	13.5	10.5
06/22/2010	17:56	597203	734287	10A	E18	T135	P3	AS	13.5	3.0
06/22/2010	17:57	597203	734287	10A	E18	T135	P3	AT	13.5	3.0
06/18/2010	15:03	597993	691241	10A	E19	T014	P3	BS	15.1	18.1
06/18/2010	15:04	597994	691242	10A	E19	T014	P3	AS	3.0	18.1
06/18/2010	18:08	588240	692306	10A	E19	T042	P1	BS	16.4	19.4
06/18/2010	18:08	588239	692306	10A	E19	T042	P1	AS	3.0	19.4
06/18/2010	18:09	588239	692305	10A	E19	T042	P1	AT	3.0	19.4
06/17/2010	20:42	586135	702830	10A	E19	T067	P3	BS	12.4	15.4
06/17/2010	20:43	586137	702830	10A	E19	T067	P3	AS	3.0	15.4
06/17/2010	17:53	592109	719753	10A	E19	T102	P1	BS	14.7	17.7
06/17/2010	17:54	592105	719752	10A	E19	T102	P1	AS	3.0	17.7
06/17/2010	15:37	597206	734299	10A	E19	T135	P3	BS	10.0	13.0
06/17/2010	15:38	597204	734299	10A	E19	T135	P3	BT	10.0	13.0
06/17/2010	15:39	597208	734301	10A	E19	T135	P3	AS	3.0	13.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
07/22/2010	13:52	594440	747323	10A	E20	T175	P1	AS	4.0	3.0
07/22/2010	13:56	594480	747517	10A	E20	T175	P2	BS	4.0	6.0
07/22/2010	13:59	594475	747517	10A	E20	T175	P2	AS	9.0	3.0
07/22/2010	14:03	594625	747665	10A	E20	T175	P3	AS	4.3	3.0
07/22/2010	14:07	594686	747739	10A	E20	T175	P4	AS	3.9	3.0
07/21/2010	12:05	597789	691293	10A	E21	T014	P1	BS	16.0	13.0
07/21/2010	12:06	597790	691297	10A	E21	T014	P1	AS	16.0	3.0
07/21/2010	12:12	597905	691252	10A	E21	T014	P2	BS	17.0	14.0
07/21/2010	12:12	597907	691250	10A	E21	T014	P2	AS	17.0	3.0
07/21/2010	12:16	597988	691223	10A	E21	T014	P3	BS	16.0	13.0
07/21/2010	12:18	597986	691222	10A	E21	T014	P3	AS	16.0	3.0
07/21/2010	12:41	588239	692301	10A	E21	T042	P1	BS	16.0	13.0
07/21/2010	12:42	588237	692300	10A	E21	T042	P1	AS	16.0	3.0
07/21/2010	12:46	588231	692388	10A	E21	T042	P2	BS	20.0	17.0
07/21/2010	12:47	588231	692390	10A	E21	T042	P2	AS	20.0	3.0
07/21/2010	12:51	588222	692461	10A	E21	T042	P3	BS	15.0	12.0
07/21/2010	12:52	588222	692467	10A	E21	T042	P3	AS	15.0	3.0
07/21/2010	12:50	586024	702933	10A	E21	T067	P1	BS	12.9	9.9
07/21/2010	12:51	586024	702932	10A	E21	T067	P1	AS	12.9	3.0
07/21/2010	12:58	586080	702882	10A	E21	T067	P2	BS	14.8	11.8
07/21/2010	12:58	586079	702885	10A	E21	T067	P1	BT	14.8	11.8
07/21/2010	13:00	586080	702883	10A	E21	T067	P2	AS	14.8	3.0
07/21/2010	13:09	586133	702831	10A	E21	T067	P3	BS	14.4	11..4
07/21/2010	13:10	586133	702833	10A	E21	T067	P3	AS	14.4	3.0
07/21/2010	13:11	586130	702833	10A	E21	T067	P3	AT	14.4	3.0
07/21/2010	11:57	592103	719744	10A	E21	T102	P1	BS	13.7	10.7
07/21/2010	11:59	592099	719745	10A	E21	T102	P1	AS	13.7	3.0
07/21/2010	12:03	592155	719744	10A	E21	T102	P2	BS	17.1	14.1
07/21/2010	12:03	592154	719746	10A	E21	T102	P2	BT	17.1	14.1
07/21/2010	12:04	592152	719745	10A	E21	T102	P2	AS	17.1	3.0
07/21/2010	12:08	592213	719743	10A	E21	T102	P3	BS	17.4	14.4
07/21/2010	12:10	592211	719745	10A	E21	T102	P3	AS	17.4	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
07/21/2010	11:10	597078	734352	10A	E21	T135	P1	BS	9.0	6.0
07/21/2010	11:11	597079	734351	10A	E21	T135	P1	AS	9.0	3.0
07/21/2010	11:17	597152	734314	10A	E21	T135	P2	BS	13.6	10.6
07/21/2010	11:17	597154	734313	10A	E21	T135	P2	AS	13.6	3.0
07/21/2010	11:21	597204	734287	10A	E21	T135	P3	BS	14.6	11.6
07/21/2010	11:23	597202	734290	10A	E21	T135	P3	AS	14.6	3.0
07/21/2010	18:14	597790	691292	10A	E22	T014	P1	BS	15.0	12.0
07/21/2010	18:16	597794	691288	10A	E22	T014	P1	AS	15.0	3.0
07/21/2010	18:21	597903	691249	10A	E22	T014	P2	BS	17.0	14.0
07/21/2010	18:22	597901	691257	10A	E22	T014	P2	AS	17.0	3.0
07/21/2010	18:26	597986	691223	10A	E22	T014	P3	BS	18.0	15.0
07/21/2010	18:27	597983	691226	10A	E22	T014	P3	AS	18.0	3.0
07/21/2010	18:52	588241	692301	10A	E22	T042	P1	BS	18.0	15.0
07/21/2010	18:53	588238	692296	10A	E22	T042	P1	AS	18.0	3.0
07/21/2010	18:57	588239	692386	10A	E22	T042	P2	BS	21.0	18.0
07/21/2010	18:58	588237	692394	10A	E22	T042	P2	AS	21.0	3.0
07/21/2010	19:03	588227	692468	10A	E22	T042	P3	BS	17.0	14.0
07/21/2010	19:04	588223	692468	10A	E22	T042	P3	AS	17.0	3.0
07/21/2010	19:08	586022	702932	10A	E22	T067	P1	BS	14.2	11.2
07/21/2010	19:10	586022	702930	10A	E22	T067	P1	AS	14.2	3.0
07/21/2010	19:14	586080	702884	10A	E22	T067	P2	BS	17.4	14.4
07/21/2010	19:14	586077	702883	10A	E22	T067	P2	AS	17.4	3.0
07/21/2010	19:18	586134	702831	10A	E22	T067	P3	BS	16.5	13.5
07/21/2010	19:18	586135	702834	10A	E22	T067	P3	BT	16.5	13.5
07/21/2010	19:19	586133	702833	10A	E22	T067	P3	AS	16.5	3.0
07/21/2010	18:24	592102	719743	10A	E22	T102	P1	BS	15.4	12.4
07/21/2010	18:25	592104	719744	10A	E22	T102	P1	BT	15.4	12.4
07/21/2010	18:26	592102	719745	10A	E22	T102	P1	AS	15.4	3.0
07/21/2010	18:29	592153	719744	10A	E22	T102	P2	BS	15.2	12.2
07/21/2010	18:30	592151	719744	10A	E22	T102	P2	AS	15.2	3.0
07/21/2010	18:33	592211	719745	10A	E22	T102	P3	BS	17.1	14.1
07/21/2010	18:34	592212	719745	10A	E22	T102	P3	AS	17.1	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
07/21/2010	17:44	597077	734351	10A	E22	T135	P1	BS	9.3	6.3
07/21/2010	17:45	597076	734350	10A	E22	T135	P1	AS	9.3	3.0
07/21/2010	17:46	597074	734352	10A	E22	T135	P1	AT	9.3	3.0
07/21/2010	17:50	597152	734314	10A	E22	T135	P2	BS	10.8	7.8
07/21/2010	17:51	597152	734314	10A	E22	T135	P2	AS	10.8	3.0
07/21/2010	17:55	597203	734288	10A	E22	T135	P3	BS	12.1	9.1
07/21/2010	17:55	597201	734289	10A	E22	T135	P3	BT	12.1	9.1
07/21/2010	17:57	597203	734291	10A	E22	T135	P3	AS	12.1	3.0
07/22/2010	12:37	597998	691236	10A	E23	T014	P3	BS	17.0	14.0
07/22/2010	12:37	597995	691239	10A	E23	T014	P3	AS	17.0	3.0
07/22/2010	12:51	588252	692304	10A	E23	T042	P1	BS	18.0	15.0
07/22/2010	12:52	588245	692303	10A	E23	T042	P1	AS	18.0	3.0
07/23/2010	13:16	586140	702831	10A	E23	T067	P3	BS	17.0	14.0
07/23/2010	13:18	586143	702831	10A	E23	T067	P3	AS	17.0	3.0
07/23/2010	13:39	592107	719742	10A	E23	T102	P1	BS	16.5	13.5
07/23/2010	13:41	592110	719748	10A	E23	T102	P1	AS	16.5	3.0
07/23/2010	14:02	597209	734294	10A	E23	T135	P3	BS	15.0	12.0
07/23/2010	14:03	597202	734295	10A	E23	T135	P3	AS	15.0	3.0

APPENDIX 2: Survey Equipment, Procedures & Data Processing

- Survey Vessel Navigation
- YSI Environmental 6920 Sondes
- Acoustic Doppler Current Profilers
- CTD-Turbidity Vertical Profiling
- Manufacturer's Equipment Specification Sheets

Survey Vessel Navigation

A Trimble Model DMS 212 Differential Global Positioning System (DGPS) interfaced with the PC-based hydrographic software package HYPACK was used for survey-vessel navigation and positioning. The global positioning system consists of 24 earth-orbiting satellites, which broadcast radio signals to the surface. These signals are used by the GPS receiver to calculate its position based on the signal time delay. Four or more satellite signals are required to accurately calculate the receiver's position. Differential correctors, used to increase vessel position accuracy to ± 1 meter, were received from a USCG beacon transmitter via a radio link. The geodetic positions derived from the DGPS system were converted to the NJ State Plane Coordinate system, East zone (NAD83, feet) for survey operations and preparation of final products.

The OSI navigation system consists of a portable personal computer with HYPACK software installed. Geodetic coordinate information from the DGPS was updated at one-second intervals and input to the navigation computer, which processed the geodetic position data into State Plane Coordinates used to guide the survey vessel. The incoming data were saved on the computer hard drive and processed in real time allowing the vessel position to be displayed on a video monitor and compared to pre-plotted trackline and positions as the survey progressed. Digitized shoreline and the locations of existing structures, buoys, and control points can also be displayed on the monitor in relation to the vessel position. This system provides a highly accurate visual representation of survey vessel location in real time, combined with data logging capabilities and post-survey data processing and plotting.

CT-OBS

The YSI Environmental Model 6920 and 6600 Sondes (dataloggers) were used to measure and record conductivity/salinity, temperature, and optical backscatter. The temperature and conductivity recorded in these self-contained microprocessors were used internally by each sonde to calculate salinity. The temperature probe utilizes sintered metallic oxides, which change resistance with temperature variations. These thermistors are accurate to +/- 0.15 ºC.

Specific conductance is calculated through a direct relationship between water temperature and conductivity. The conductivity of a solution is measured through a cell with four pure nickel electrodes. Two electrodes are current driven, and two are used to measure the voltage drop. The measured voltage drop is then converted into a conductance value. The accuracy of the conductance readings is 0.5%. Turbidity data were recorded using the 6136 fouling-resistant turbidity sensor. It provides accurate *in situ* measurements of turbidity in fresh, brackish, and saltwater, and features a mechanical self-wiping capability for long-term monitoring. The turbidity probe is accurate to +/-2% of the reading or 0.3 NTU, whichever is greater. Long-term deployments with these sensors, as part of YSI's submersible, multi-parameter water quality monitoring systems, have demonstrated constant measurement accuracy and stability.

The raw data from the dataloggers were downloaded in a binary form and converted to engineering units in YSI's EcoWatch software. The engineering units included temperature (deg. C), salinity (PSU), and turbidity (NTU).

Acoustic Doppler Current Profiler (ADCP)

Three self-contained, internally logging Acoustic Doppler Current Profilers (ADCPs) were deployed in an upward looking configuration on an OSI-designed bottom mount equipped with a gimbal to accommodate slope at the deployment site.

The Teledyne Workhorse Sentinel ADCP contains four transducers that simultaneously transmit and receive sonic pulses at sound frequencies of 600 kHz or 1200 kHz, depending on the selected instrument. The transducer faces are angled 20° away from vertical and are evenly spaced around the head of the instrument in a "Janus" configuration. The ADCPs were programmed to measure and record water velocity profiles at 12-minute intervals with a vertical resolution of 0.5 meters.

To measure water current velocity, the instrument sends out a coded series of sonic pulses (a ping) at a predetermined rate and measures the Doppler shift of these pings as they reflect off particles suspended in the water column. (On average, suspended particles move with the same velocity as the water in which they are suspended). Data from a minimum of three transducers are required to calculate a three-dimensional current vector from the measurements of Doppler shift. The fourth transducer provides redundant data which aids in reducing errors in the vertical component of velocity and helps to ensure that there are at least three beams available to compute the horizontal components of velocity at all times.

Single ping velocity errors are too large to meet most measurement requirements. Therefore, many pings are averaged into ping ensembles. After a preset number of pings (an ensemble) is transmitted and received, these measurements are averaged over the length of the ensemble.

By range-gating the echo signal, the ADCP divides the velocity profile into uniform segments called depth cells (or bins). Unlike conventional Eulerian current meters, ADCPs do not make point measurements of small, localized volumes of water at individual depths. Instead, they perform a weighted average of the velocity field over a depth range slightly larger than the nominal thickness of an entire depth cell. Data collected from the center of each cell are more heavily weighted than data collected at the overlapping fringes of each cell. Averaging the velocity field in this way reduces measurement uncertainty and spatial aliasing. Furthermore, the overlapping nature of the depth cells, combined with the weighted averaging within the cells, ensures complete water column coverage and presents a smoother, more representative current profile.

Each time the ADCP transmits a pulse, the ADCP turns off the transducers and waits for a short period call the blank period. This allows the “ringing” of the transducers to stop before the ADCP begins listening for the return pulse. This blanking distance results in a small area just above the head of the ADCP which cannot be measured. The ADCP begins measuring currents at one vertical bin size above the blanking distance. Blanking distances for this

program varied by ADCP frequency and mounting considerations (vessel-mounted verses bottom mounts) resulting in blanking distanced no greater than 0.5 meters and near field current measurements no greater than 1.0 meters from the head of the ADCP.

As the ADCP signal propagates through the water column, the signal comes into contact with the opposing boundary, such as the riverbed for a vessel-mounted unit or the water surface on a bottom mounted unit. Since an ADCP which is setup to range gate bins to 0.5 meters actually acquires data from 1.0 meters (0.5 meters above and below center) due to the overlapping nature of the bins, an area between one and two bin sizes (0.5-1.0 meters) cannot be measured in these areas due to the interference of the boundary.

CTD-Turbidity Vertical Profiling

Conductivity/salinity, temperature, and turbidity data were collected using a Sea-Bird Electronics, Inc. Model SBE 19 SEACAT Profiler. The SEACAT Profiler is a self-powered, self-contained micro processing unit capable of collecting turbidity, temperature, conductivity/salinity, and depth data at a rate of two scans per second. Data are internally processed, corrected, and recorded in solid-state memory and were transferred via an RS-232 port to a computer in real time and downloaded again after deployment where the operator can view the data and archive it for future processing.

To collect a cast, the SEACAT was first lowered over the side of the vessel into the water where it was allowed to equilibrate to the temperature of the surrounding water. The instrument was initialized and then lowered through the water column to the bottom. Once at the bottom, the SEACAT was held steady for one minute, and then returned to the surface.

Water quality data collected by the SEACAT Profiler were downloaded to a computer and post-processed using Sea-Bird Electronics CTD Data Acquisition Software, Seasoft Version 4.238. The raw data were calibration corrected and reduced to listings of depth versus turbidity (NTU), temperature (°C), and salinity (PSU).

DSM12/212 Product Family

Integrated, cost-effective and reliable sub-meter positioning for your marine application

Key features and benefits

- Compact
- Easy Installation
- High Position Output Rate With Low Latency
- Easy To Use & Setup
- Low Power Consumption
- Increased Jamming Resistance
- Optional Everest Multipath Rejection
- Isolated Power Supply

The DSM12/212 Product Family targets marine professionals in need of sub-meter positioning during applications such as precise positioning, dredging, hydrographic surveying, high speed vessel positioning, and many more.

Complete System Solution

The product family includes three mobile receivers and one reference station receiver:

- DSM12™ – DGPS receiver
- DSM212L™ – Integrated GPS/MSK receiver, 1Hz output
- DSM212H™ – Integrated GPS/MSK receiver, 10Hz output
- DSM12RS™ – DGPS Reference Station receiver

Cost Effective

The family of 12 channel GPS receivers use Trimble's latest technology to achieve sub-meter positioning accuracy. These receivers maintain their high performance in environments where GPS availability and accuracy are sometimes an issue. Everest™ technology improves results in high multipath environments and locations where other radio frequencies could jam the GPS signals such as harbors, oil platforms, and construction sites. The DSM12, DSM212L & DSM212H can all accept RTCM SC-104 differential corrections from an external source through a serial interface. The DSM212L & DSM212H also include an integrated dual-channel low-noise MSK beacon receiver.



Integrated GPS and dual-channel MSK beacon receiver, DSM212H

The MSK beacon receiver provides superior weak-signal reception performance, allowing differential corrections to be received at long distances from the reference station and during challenging weather conditions. The dual-channel capability allows for intelligent and seamless switching between beacons.

Superior Integration

The DSM12, DSM212L and DSM212H are easy to connect with other onboard equipment such as integrated bridge systems, radars, autopilots and plotters. Through one of the two serial ports, these receivers output standard NMEA-0183 messages, including position, velocity and status information. The DSM12 & DSM212L receivers output position reports once a second.

The DSM212H outputs position reports at an increased output rate of 10 Hz, with a maximum latency of 0.1 second. The second serial port is for setup, control and data output using Trimble Standard Interface Protocol (TSIP). For easy setup, a Windows-based Trimble Navigation software, TSIP Talker™ is included. The receivers also feature a 1 PPS output available on either serial port and offer a differential speed accuracy of better than 0.1 Knot.

Reference Station

The DSM12RS is a cost-effective solution for providing high quality DGPS corrections. The corrections are generated in the standard RTCM SC-104 format for broadcast.

Trimble

DSM12/212 Product Family

Integrated, cost-effective and reliable sub-meter positioning for your marine application

STANDARD FEATURES

Standard Configuration

- 12-channel GPS receiver
- Integrated GPS and dual channel MSK beacon receiver (DSM212L & DSM212H)
- External RTCM SC-104 input
- Isolated power supply
- Positioning based on carrier-phase filtered L1 pseudo-ranges
- Two programmable RS-232 serial ports:
  - NMEA-0183 output or RTCM SC-104 output
  - RTCM SC-104 input
  - TSIP Input & Output
- 1PPS output
- Windows Configuration software
- DSM12/212 Operation manual
- Compact L1 GPS antenna (DSM12)
- Compact L1 Geodetic GPS antenna with removable groundplane (DSM12RS)
- Combined L1 GPS and MSK H-field loop antenna (DSM212L & DSM212H)
- 15 meter RG58 antenna cable (DSM12, DSM212L, & DSM212H)
- 30 meter RG213 antenna cable (DSM12RS)
- Power/data cable
- 12Pin to Split I/O Cable (DSM12)
- 12Pin to Split RTCM Cable (DSM12RS)
- 12Pin to Data Cable (DSM212L & DSM212H)

PHYSICAL CHARACTERISTICS

Receiver

Size:	14.5cmW x 5.1cmH x 19.5cmD (5.7”W x 2.0”H x 7.7”D)
Weight:	0.76kg (1.68 lb.)
Power:	5W (max.), 10 to 32 VDC
Operating temp:	-30°C to +65°C
Storage temp:	-40°C to +85°C
Humidity:	100% condensing, unit fully sealed

Combined Antenna (DSM212L & DSM212H)

Size:	15cmD x 15.5cmH (5.8”D X 6.0”H)
Weight:	4.9kg (2.2 lb.)
Operating temp:	-40°C to +65°C
Humidity:	100%-fully sealed

Compact Dome Antenna (DSM12)

Size:	15.4cmD x 8.9cmH (6”D X 3.5”H)
Weight:	0.29kg (0.645 lb.)
Operating temp:	-40°C to +70°C
Humidity:	100%-fully sealed

Compact L1 Geodetic Antenna (DSM12RS)

Size:	48cmD x 9cmH (19”D X 3.5”H)
Weight:	2.6kg (5.7 lb.)
Operating temp:	-40°C to +65°C
Humidity:	100% - fully sealed

PERFORMANCE CHARACTERISTICS

GPS Receiver

General:	12-channel, parallel tracking, L1 C/A code with carrier phase filtered measurements and multi-bit digitizer
Output rate:	1 Hz standard (DSM12, DSM12RS, & DSM212L) 10 Hz standard (DSM212H)
Differential speed accuracy:	0.1 kn (0.1 MPH, 0.16 km/h, 5.6cm/s)*
Differential position accuracy:	Less than 1 meter horizontal RMS* (At least 5 satellites, PDOP <4 and RTCM SC-104 standard format broadcast from a Trimble DSM12RS or equivalent reference station.)
Time to first fix:	<30 seconds, typical
NMEA messages:	ALM, GGA**, GLL, GSA, GSV, VTG**, ZDA, RMC, MSS **Default messages

MSK beacon Dual-channel Receiver

Frequency range:	283.5 KHz to 325.0 KHz
Channel spacing:	500 Hz
MSK modulation:	50, 100 & 200 bits/second
Signal strength:	10 µV/meter minimum @ 100BPS
Dynamic range:	100 dB
Channel selectivity:	70 dB >500 Hz offset
Frequency offset:	17 ppm maximum
3rd order intercept:	+15 dBm @ RF input (min. AGC setting)
Beacon acquisition time:	<5 sec, typical

OPTIONS

- High Output Rate
- Everest Multipath Rejection
- Reference Station
- Carrier Phase Output
- Extended hardware warranty
- Firmware update service

*To achieve differential speed and position, the unit must be operating within the broadcast area of a reference station conforming to the International Association of Lighthouse Authorities Standards. All non-differential GPS receivers are subject to degradation of position and velocity accuracy under U.S. Department of Defense-imposed Selective Availability (S/A). Positions may be degraded up to 100 meters 2D RMS.

Trimble follows a policy of continuous product improvement. Specifications are thus subject to change without notice.

© March 1998, Trimble Navigation Limited. All rights reserved. Trimble with the Trimble logo is a registered trademark and DSM12, DSM212L, DSM212H, DSM12RS, Everest and TSIP Talker are trademarks of Trimble Navigation Limited, Sunnyvale, California, U.S.A. All other brand names, product names and trademarks belong to their respective owners. TID11202 (3/98)

Trimble
THE GPS SOLUTION

Trimble Navigation Limited
Corporate Headquarters
645 North Mary Avenue
Sunnyvale, CA 94086
+1-408-481-8000
+1-408-481-2000 Fax
www.trimble.com

Trimble Navigation Europe Limited
Trimble House,
Meridian Office Park
Osborne Way
Hook, Hampshire RG27 9HX U.K.
+44 1256-760-150
+44 1256-760-148 Fax

YSI Environmental

NEW

YSI 6820 and 6920 V2 Sondes

With 1 or 2 optical ports and new sensor options

The YSI 6820 V2-2 and 6920 V2-2 Sondes

Measure multiple parameters simultaneously including:

- Temperature
- Conductivity
- Specific Conductance
- Salinity
- Resistivity
- TDS
- pH
- ORP
- Depth or Level
- Nitrate, Ammonium or Chloride
- Rapid Pulse™ DO (V2-1 only)

And 1 or 2 of the following optical sensors:

- ROX™ Optical DO *NEW*
- Turbidity
- Chlorophyll
- Blue-Green Algae *NEW*
  (Phycocyanin or Phycoerythrin)
- Rhodamine

- **Two bulkhead versions available:**
  - **The 6820/6920 V2-1 has one optical port, conductivity/temperature port, Rapid Pulse™ DO port, pH/ORP port. and three ISE ports**
  - **The 6820/6920 V2-2 has two optical ports, conductivity/temperature port, pH/ORP port. and one ISE port**
- **Self-cleaning optical sensors with improved wiping**
- **Field-replaceable sensors**
- **6920 V2 has a built-in battery compartment for long-term *in situ* monitoring**

Take Advantage of YSI's New Optical Sensors

In addition to turbidity, chlorophyll, and rhodamine, YSI now offers these optical sensors:

ROX Reliable Optical Dissolved Oxygen

The ROX sensor uses lifetime luminescence detection technology to offer the most reliable oxygen sensor with the lowest possible maintenance effort. Experience significantly less membrane maintenance while obtaining excellent accuracy, sensitivity, and range.

ROX

Blue-Green Algae (BGA)

YSI's fluorescence-based blue-green algae sensors will allow you to monitor blue-green algae populations where their presence is a concern. Whether providing an early warning to an algal bloom, tracking taste and odor-causing species in drinking water supplies, or conducting ecosystem research; YSI BGA sensors will provide sensitive and reliable *in situ* data.

Pure Data for a Healthy Planet.®

Compact sondes for field sampling and data collection platforms

6820 and 6920 Upgrades Available

YSI is committed to offering our customers reliable and cost-effective water monitoring solutions. To this end, we are offering V2-2 Upgrades for existing 6820/6920s. Upgrades will be available from YSI Authorized Service Centers and will include the new 6820/6920 V2-2 bulkhead, an Optical Dissolved Oxygen Sensor, and firmware/software upgrades. In addition, the sonde will be fully tested and calibrated by an experienced YSI service technician.

To order, or for more info, contact YSI Environmental.

+1 937 767 7241
800 897 4151 (US)
www.ysi.com

YSI Environmental
+1 937 767 7241
Fax +1 937 767 9353
environmental@ysi.com

YSI Integrated Systems & Services
+1 508 748 0366
Fax +1 508 748 2543
systems@ysi.com

SonTek/YSI
+1 858 546 8327
Fax +1 858 546 8150
inquiry@sontek.com

YSI Gulf Coast
+1 225 753 2650
Fax +1 225 753 8669
environmental@ysi.com

YSI Hydrodata (UK)
+44 1462 673 581
Fax +44 1462 673 582
europe@ysi.com

YSI Middle East (Bahrain)
+973 1753 6222
Fax +973 1753 6333
halsalem@ysi.com

YSI (Hong Kong) Limited
+852 2891 8154
Fax +852 2834 0034
hongkong@ysi.com

YSI (China) Limited
+86 10 5203 9675
Fax +86 10 5203 9679
beijing@ysi-china.com

YSI Nanotech (Japan)
+81 44 222 0009
Fax +81 44 221 1102
nanotech@ysi.com

ISO 9001
ISO 14001
Yellow Springs, Ohio Facility

ROX and Rapid Pulse are trademarks and EcoWatch, Pure Data for a Healthy Planet and Who's Minding the Planet? are registered trademarks of YSI Incorporated.

©2006 YSI Incorporated
Printed in USA 0807 E36-03

CE

*Sensors with listed with the ETV logo were submitted to the ETV program on the YSI 6600EDS. Information on the performance characteristics of YSI water quality sensors can be found at www.epa.gov/etv, or call YSI at 800.897.4151 for the ETV verification report. Use of the ETV name or logo does not imply approval or certification of this product nor does it make any explicit or implied warranties or guarantees as to product performance.

YSI *incorporated*
Who's Minding the Planet?®

YSI 6820 V2 & 6920 V2 Sensor Specifications

	Range	Resolution	Accuracy
ROX™ Optical Dissolved Oxygen• % Saturation	0 to 500%	0.1%	0 to 200%: ±1% of reading or 1% air saturation, whichever is greater; 200 to 500%: ±15% of reading, relative to calibration gases
ROX™ Optical Dissolved Oxygen• mg/L	0 to 50 mg/L	0.01 mg/L	0 to 20 mg/L: ± 0.1 mg/L or 1% of reading, whichever is greater; 20 to 50 mg/L: ±15% of reading, relative to calibration gases
Dissolved Oxygen•• % Saturation ETV 6562 Rapid Pulse™ Sensor*	0 to 500%	0.1%	0 to 200%: ±2% of reading or 2% air saturation, whichever is greater; 200 to 500%: ±6% of reading
Dissolved Oxygen•• mg/L ETV 6562 Rapid Pulse™ Sensor*	0 to 50 mg/L	0.01 mg/L	0 to 20 mg/L: ± 0.2 mg/L or 2% of reading, whichever is greater; 20 to 50 mg/L: ±6% of reading
Conductivity••• ETV 6560 Sensor*	0 to 100 mS/cm	0.001 to 0.1 mS/cm (range dependent)	±0.5% of reading + 0.001 mS/cm
Salinity	0 to 70 ppt	0.01 ppt	±1% of reading or 0.1 ppt, whichever is greater
Temperature ETV 6560 Sensor*	-5 to +50°C	0.01°C	±0.15°C
pH ETV 6561 Sensor*	0 to 14 units	0.01 unit	±0.2 unit
ORP	-999 to +999 mV	0.1 mV	±20 mV
Depth Medium Shallow Vented Level	0 to 200 ft, 61 m 0 to 30 ft, 9.1 m 0 to 30 ft, 9.1 m	0.001 ft, 0.001 m 0.001 ft, 0.001 m 0.001 ft, 0.001 m	±0.4 ft, ±0.12 m ±0.06 ft, ±0.02 m ±0.01 ft, 0.003 m
Turbidity• ETV 6136 Sensor*	0 to 1,000 NTU	0.1 NTU	±2% of reading or 0.3 NTU, whichever is greater**
Nitrate/nitrogen••••	0 to 200 mg/L-N	0.001 to 1 mg/L-N (range dependent)	±10% of reading or 2 mg/L, whichever is greater
Ammonium/ammonia/ nitrogen••••	0 to 200 mg/L-N	0.001 to 1 mg/L-N (range dependent)	±10% of reading or 2 mg/L, whichever is greater
Chloride••••	0 to 1000 mg/L	0.001 to 1 mg/L (range dependent)	±15% of reading or 5 mg/L, whichever is greater
Rhodamine•	0-200 µg/L	0.1 µg/L	±5% reading or 1 µg/L, whichever is greater

• Maximum depth rating for all standard optical sensors is 200 feet, 61 m.
•• Rapid Pulse is only available on the 6820/6920 V2-1 (one optical port version)
••• Report outputs of specific conductance (conductivity corrected to 25° C), resistivity, and total dissolved solids are also provided. These values are automatically calculated from conductivity according to algorithms found in *Standard Methods for the Examination of Water and Wastewater* (ed 1989).
•••• Freshwater only, Maximum depth rating of 50 feet, 15.2 m. 6820/6920 V2-1 have 3 ISE ports, 6820/6920 V2-2 have 1 ISE port.

**In YSI AMCO-AEPA Polymer Standards.

	Range	Detection Limit	Resolution	Linearity
BGA - Phycocyanin•	~0 to 280,000 cells/mL† 0 to 100 RFU	~220 cells/mL§	1 cell/mL 0.1 RFU	$R^2 > 0.9999$**
BGA - Phycoerythrin•	~0 to 200,000 cells/mL† 0 to 100 RFU	~450 cells/mL§§	1 cell/mL 0.1 RFU	$R^2 > 0.9999$***
Chlorophyll• ETV 6025 Sensor*	~0 to 400 µg/L 0 to 100 RFU	~0.1 µg/L§§§	0.1 µg/L Chl 0.1% RFU	$R^2 > 0.9999$****

• Maximum depth rating for all standard optical probes is 200 feet, 61 m.
BGA = Blue-Green Algae
RFU = Relative Fluorescence Units
~ = Approximately

† Explanation of Ranges can be found in the 'Principles of Operation' section of the 6-Series Manual, Rev D.

§ Estimated from cultures of *Microcystis aeruginosa*.
§§ Estimated from cultures *Synechococcus sp.*
§§§ Determined from cultures of *Isochrysis sp.* and chlorophyll *a* concentration determined via extractions.

**Relative to serial dilution of Rhodamine WT (0-400 ug/L).
***Relative to serial dilution of Rhodamine WT (0-8 µg/L).
****Relative to serial dilution of Rhodamine WT (0-500 ug/L).

YSI 6820 V2 & 6920 V2 Sonde Specifications

Medium	Fresh, sea or polluted water	Software	EcoWatch®
Temperature Operating Storage	-5 to +50°C -10 to +60°C	Dimensions 6820 V2 I 6920 V2 Diameter Length Weight	2.86 in, 7.3 cm | 2.85 in, 7.24 cm 13.5 in, 34.3 cm | 18 in, 45.7 cm 3.4 lbs, 1.5 kg | 4 lbs, 1.8 kg
Communications	RS-232, SDI-12	Power External Internal	12 V DC 8 AA-size alkaline batteries

NEW

YSI 6600 V2 Sonde

With 2 or 4 optical ports and new sensor options

Make the most of your environmental monitoring efforts: The 6600 V2 sonde offers the most comprehensive water quality monitoring package available with simultaneous measurement of conductivity (salinity), temperature, depth or level, pH/ORP. The 6600 V2-4 also measures these parameters: dissolved oxygen, turbidity, chlorophyll, and blue-green algae; the V2-2 measures two of the four parameters simultaneously. Additional calculated parameters include total dissolved solids, resistivity, and specific conductance.

Take advantage of YSI's new optical sensor design and anti-fouling wiper control for improved reliability during extended deployments.

- **Self-cleaning optical sensors with integrated wipers remove biofouling and maintain high data accuracy**
- **Field-replaceable sensors make trips to the field quick**
- **Optimal power management and built-in battery compartment extends *in situ* monitoring periods**

Take Advantage of YSI's New Optical Sensors

In addition to turbidity, chlorophyll, and rhodamine, YSI now offers these optical sensors:

ROX Reliable Optical Dissolved Oxygen

The ROX sensor uses lifetime luminescence detection technology to offer the most reliable oxygen sensor with the lowest possible maintenance effort. The sensor is insensitive to hydrogen sulfide interference and does not require regular membrane changes.

Blue-Green Algae (BGA)

YSI's fluorescence-based blue-green algae sensors will allow you to monitor blue-green algae populations where their presence is a concern. Whether providing an early warning to an algal bloom, tracking taste and odor-causing species in drinking water supplies, or conducting ecosystem research, YSI BGA sensors will provide sensitive and reliable *in situ* data.

Complete Data Record

The YSI 6600 V2-4 Sonde, with 4 optical sensor ports, is the only instrument available to simultaneously measure dissolved oxygen, turbidity, chlorophyll, and blue-green algae!

Pure Data for a Healthy Planet.®

Upgraded sondes for rugged long-term deployment

*Sensor performance verified**

The 6600 V2 sonde uses sensor technology that was verified through the US EPA's Environmental Technology Verification Program (ETV). For information on which sensors were performance-verified, turn this sheet over and look for the ETV logo.

6600 Upgrades Available

YSI is committed to offering our customers reliable and cost-effective water monitoring solutions. To this end, we are offering V2 Upgrades for existing 6600s. Upgrades will be available from YSI Authorized Service Centers and will include the new 6600 V2 bulkhead, a ROX Optical Dissolved Oxygen Sensor, and firmware/software upgrades. In addition, the sonde will be fully tested and calibrated by an experienced YSI service technician.

YSI 6600 V2 Sensor Specifications

	Range	Resolution	Accuracy
ROX™ Optical Dissolved Oxygen• % Saturation	0 to 500%	0.1%	0 to 200%: ±1% of reading or 1% air saturation, whichever is greater; 200 to 500%: ±15% of reading
ROX™ Optical Dissolved Oxygen• mg/L	0 to 50 mg/L	0.01 mg/L	0 to 20 mg/L: ± 0.1 mg/L or 1% of reading, whichever is greater; 20 to 50 mg/L: ±15% of reading
Dissolved Oxygen•• % Saturation ETV 6562 Rapid Pulse™ Sensor*	0 to 500%	0.1%	0 to 200%: ±2% of reading or 2% air saturation, whichever is greater; 200 to 500%: ±6% of reading
Dissolved Oxygen•• mg/L ETV 6562 Rapid Pulse™ Sensor*	0 to 50 mg/L	0.01 mg/L	0 to 20 mg/L: ± 0.2 mg/L or 2% of reading, whichever is greater; 20 to 50 mg/L: ±6% of reading
Conductivity••• ETV 6560 Sensor*	0 to 100 mS/cm	0.001 to 0.1 mS/cm (range dependent)	±0.5% of reading + 0.001 mS/cm
Salinity	0 to 70 ppt	0.01 ppt	±1% of reading or 0.1 ppt, whichever is greater
Temperature ETV 6560 Sensor*	-5 to +50°C	0.01°C	±0.15°C
pH ETV 6561 Sensor*	0 to 14 units	0.01 unit	±0.2 unit
ORP	-999 to +999 mV	0.1 mV	±20 mV
Depth — Deep	0 to 656 ft, 200 m	0.001 ft, 0.001 m	±1 ft, ±0.3 m
Depth — Medium	0 to 200 ft, 61 m	0.001 ft, 0.001 m	±0.4 ft, ±0.12 m
Depth — Shallow	0 to 30 ft, 9.1 m	0.001 ft, 0.001 m	±0.06 ft, ±0.02 m
Depth — Vented Level	0 to 30 ft, 9.1 m	0.001 ft, 0.001 m	±0.01 ft, 0.003 m
Turbidity• ETV 6136 Sensor*	0 to 1,000 NTU	0.1 NTU	±2% of reading or 0.3 NTU, whichever is greater**
Nitrate/nitrogen••••	0 to 200 mg/L-N	0.001 to 1 mg/L-N (range dependent)	±10% of reading or 2 mg/L, whichever is greater
Ammonium/ammonia/ nitrogen••••	0 to 200 mg/L-N	0.001 to 1 mg/L-N (range dependent)	±10% of reading or 2 mg/L, whichever is greater
Chloride••••	0 to 1000 mg/L	0.001 to 1 mg/L (range dependent)	±15% of reading or 5 mg/L, whichever is greater
Rhodamine•	0-200 µg/L	0.1 µg/L	±5% reading or 1 µg/L, whichever is greater

• Maximum depth rating for all optical probes is 200 feet, 61 m. Turbidity and Rhodamine are also available in a Deep Depth option (0 to 200 m).
•• Rapid Pulse is only available on 6600 V2-2 (two optical ports version).
••• Report outputs of specific conductance (conductivity corrected to 25° C), resistivity, and total dissolved solids are also provided. These values are automatically calculated from conductivity according to algorithms found in *Standard Methods for the Examination of Water and Wastewater* (ed 1989).
•••• Freshwater only. Maximum depth rating of 50 feet, 15.2 m. 6600 V2-2 has 3 ISE ports; not available on the 6600V2-4.

**In YSI AMCO-AEPA Polymer Standards.

	Range	Detection Limit	Resolution	Linearity
Blue-Green Algae Phycocyanin•	~0 to 280,000 cells/mL† 0 to 100 RFU	~220 cells/mL§	1 cell/mL 0.1 RFU	$R^2 > 0.9999$**
Blue-Green Algae Phycoerythrin•	~0 to 200,000 cells/mL† 0 to 100 RFU	~450 cells/mL§§	1 cell/mL 0.1 RFU	$R^2 > 0.9999$***
Chlorophyll• ETV 6025 Sensor*	~0 to 400 µg/L 0 to 100 RFU	~0.1 µg/L§§§	0.1 µg/L Chl 0.1% RFU	$R^2 > 0.9999$****

• Maximum depth rating for all optical probes is 200 feet, 61 m. Also available in a Deep Depth option (0 to 200 m).
RFU = Relative Fluorescence Units

† Explanation of Ranges can be found in the 'Principles of Operation' section of the 6-Series Manual, Rev D.

§ Estimated from cultures of *Microcystis aeruginosa*.
§§ Estimated from cultures *Synechococcus sp*.
§§§ Determined from cultures of *Isochrysis sp.* and chlorophyll *a* concentration determined via extractions.

**For serial dilution of Rhodamine WT (0-400 ug/L).
***For serial dilution of Rhodamine WT (0-8 µg/L).
****For serial dilution of Rhodamine WT (0-500 ug/L).

YSI 6600 V2 Sonde Specifications

Medium	Fresh, sea or polluted water	Software	EcoWatch®
Temperature — Operating	-5 to +50°C	Dimensions — Diameter	3.5 in, 8.9 cm
Temperature — Storage	-10 to +60°C	Dimensions — Length, no depth	19.6 in, 49.8 cm
		Dimensions — Length, with depth	21.6 in, 54.9 cm
		Dimensions — Weight	7 lbs, 3.18 kg (batteries installed, with depth)
Communications	RS-232, SDI-12	Power — External	12 V DC
		Power — Internal	8 C-size alkaline batteries

To order, or for more info, contact YSI Environmental.

+1 937 767 7241
800 897 4151 (US)
www.ysi.com

YSI Environmental
+1 937 767 7241
Fax +1 937 767 9353
environmental@ysi.com

Endeco/YSI
+1 508 748 0366
Fax +1 508 748 2543
systems@ysi.com

SonTek/YSI
+1 858 546 8327
Fax +1 858 546 8150
inquiry@sontek.com

YSI Gulf Coast
+1 225 753 2650
Fax +1 225 753 8669
environmental@ysi.com

YSI Hydrodata (UK)
+44 1462 673 581
Fax +44 1462 673 582
europe@ysi.com

YSI Middle East (Bahrain)
+973 1753 6222
Fax +973 1753 6333
halsalem@ysi.com

YSI (Hong Kong) Limited
+852 2891 8154
Fax +852 2834 0034
hongkong@ysi.com

YSI (China) Limited
+86 10 5203 9675
Fax +86 10 5203 9679
beijing@ysi-china.com

YSI Nanotech (Japan)
+81 44 222 0009
Fax +81 44 221 1102
nanotech@ysi.com

ISO 9001
ISO 14001
Yellow Springs, Ohio Facility

ROX and Rapid Pulse are trademarks and EcoWatch, Pure Data for a Healthy Planet and Who's Minding the Planet? are registered trademarks of YSI Incorporated.

©2006 YSI Incorporated

Printed in USA 1206 E52-01

*Sensors with listed with ETV logo were submitted to the ETV program on the YSI 6600EDS. Information on performance characteristics of YSI water quality sensors can be found at www.epa.gov/etv, or call YSI at 800.897.4151 for the ETV verification report. Use of ETV name or logo does not imply approval or certification of this product nor does it make any explicit or implied warranties or guarantees as to product performance.

YSI incorporated
Who's Minding the Planet?®

Workhorse Sentinel ADCP

Self-Contained 1200, 600 or 300 kHz

Our most popular instrument. Over 1000 Workhorse Sentinel ADCPs are profiling currents in 50 countries. Our customers choose it for its unbeatable precision in shallow waters, for its 175-meter profiling range and for an unmatched low power consumption that makes it ideal for year-long deployments.

Customers tell us they like it because it's light and easy to deploy on buoys, boats or on the bottom. Links to shore are by cable or modem and Sentinel is easily upgraded to measure pressure, to undertake bottom-tracking tasks or to be used as a directional wave gauge.

			Long Range Mode	
Frequency	Range	Cell Size	Range	Cell Size
1200 kHz	14m	1m	19m	2m
600 kHz	47m	2m	67m	4m
300 kHz	126m	8m	165m	8m

RD Instruments
Tel: (858) 693-1178
sales@rdinstruments.com

RD Instruments

www.rdinstruments.com

Included in a complete system:

Transducer and electronics: molded composite plastic transducer head with four beams at 20° from vertical in a convex configuration, temperature sensor, electronics assemblies, fluxgate compass, pitch and roll sensors.

Batteries: one 28-D cell alkaline battery pack (factory degaussed).

Memory: 10 MB PC card internal memory (upgradeable to 440Mb).

Pressure case: composite plastic, 200m rated. End cap with wet-mateable connector and dummy plug.

Power supply for laboratory testing: 110-220V AC/24V DC power converter.

Input/output cable: 5 meter cable for communications and power.

Manuals and software: users guide; operation manual and easy-to-use Windows software package.

Spares parts and tool kit for maintenance.

Ship case: ruggedized compact case.

Workhorse Sentinel ADCP 1200, 600 or 300 kHz

Water Profiling

Depth Cell Size[a]	Typical range 12m[b] 1200kHz		Typical range 50m[b] 600kHz		Typical range 110m[b] 300kHz	
Vertical Resolution	Range (m)	Std. Dev.[c] (mm/s)	Range (m)	Std. Dev.[c] (mm/s)	Range (m)	Std. Dev.[c] (mm/s)
0.25m	11	182				
0.50m	12	66	36	182	see (a)	
1.0m	14	30	41	66	86	182
2.0m	15[b]	18	47	30	99	66
4.0m	see (a)		52[b]	18	112	30
8.0m					126[b]	18

Notes: a) user's choice of depth cell size is not limited to the typical values specified, b) longer ranges available, c) BroadBand mode single-ping standard deviation (Std.Dev.)

Long Range Mode

	Range (m)	Depth Cell Size (m)	Std. Dev. (mm/s)
1200kHz	19	2	35
600kHz	67	4	38
300kHz	165	8	38

Profile Parameters

Velocity accuracy:
- 1200, 600: ± 0.25% of the water velocity relative to the ADCP ± 2.5mm/s
- 300: ± 0.5% of the water velocity relative to the ADCP ± 5 mm/s

Velocity resolution: 1mm/s
Velocity range: ± 5m/s (default):
± 20m/s (maximum)
Number of depth cells: 1-128
Ping rate: 2 Hz (typical)

Echo Intensity Profile

Vertical resolution: depth cell size
Dynamic range: 80 dB
Precision: ± 1.5dB (relative measure)

Transducer and Hardware

Beam angle: 20°
Configuration: 4 beam, convex
Internal memory: Unit comes with 10Mb card, standard. Two PCMCIA card slots available (10-220Mb each).
Communications: Serial port selectable by switch for RS-232 or RS-422. ASCII or binary output at 1200-115,400 baud.

Standard Sensors

Temperature (mounted on transducer)
- Range: -5° to 45°C
- Precision: ± 0.4°C
- Resolution: 0.01°

Tilt
- Range: ± 15°
- Accuracy : ± 0.5°
- Precision: ± 0.5°
- Resolution: 0.01°

Compass (fluxgate type, includes built-in field calibration feature)
- Accuracy: ± 2° [e]
- Precision: ± 0.5° [e]
- Resolution: 0.01°
- Maximum tilt: ± 15°

Note: e) @ 60° magnetic dip angle, 0.5G total field

Power

DC input: 20-60V DC. Internal battery pack, external battery pack or external power supply.
Voltage: 42V DC (new)
28V DC (depleted)
Capacity: @ 0°C: 400 watt hours

Transmit
- 16W @ 35V (1200kHz)
- 37W @ 35V (600kHz)
- 115W @ 35V (300kHz)

Environmental

Standard depth rating: 200m. Optional to 6000m.
Operating temperature: -5° to 45°C
Storage temperature: -30° to 75°C
Weight in air: 13.0kg
Weight in water: 4.5kg

Dimensions



Software

Use RDI's Windows™-based software for the best results:
- WinSC — Data Acquisition
- WinADCP — Data Display and Export

Upgrades Available

- Memory - 10-220Mb PCMCIA cards
- Pressure sensor
- External battery case
- High resolution water profiling modes
- Bottom tracking
- AC/DC power converter, 48V DC output
- Pressure cases for depths up to 6000m

For More Information

Call, e-mail or visit our web page. Ask for our Primer about ADCPs.

Internet: www.rdinstruments.com

RD Instruments
9855 Businesspark Avenue
San Diego, CA 92131 USA
Tel: (858) 693-1178 Fax: (858) 695-1459
E-mail: sales@rdinstruments.com

SEACAT PROFILER

SBE19

Fast, accurate profiles of salinity, temperature, density, sound velocity, dissolved oxygen, pH, ORP, light transmission, PAR.

Proven sensors, computer-less field operation, semi-conductor memory, RS-232 data download, powerful software.



SBE 19 Seacat Profiler data plotted using Sea-Bird's SEASOFT CTD Data Acquisition software. Salinity, density, and sound velocity were computed from the raw conductivity, temperature, pressure data according to the algorithms in Unesco Technical Paper no. 44 which incorporate the 1978 International Practical Salinity Scale (IPSS 78) and the 1980 equations of state (EOS 80).

Very narrow ranges of each variable have been chosen (for example, 1 ppt in salinity) so that the Profiler's high resolving capability may be easily perceived. SEASOFT offers menu control of variable choices and ranges.

The plot was made using an IBM PC compatible computer and Hewlett-Packard HP 7475A plotter.

CONVENIENCE - PORTABILITY - PERFORMANCE - VALUE

SBE Sea-Bird Electronics, Inc 1808-136th Place NE Bellevue, Washington 98005 USA
Telephone: (206) 643-9866 · Telex: 292915 SBEI UR · Telefax: (206) 643-9954

Operation

The Seacat Profiler samples at a programmable rate up to 2 "scans" per second, and is able to characterize the water column with high accuracy and half-second resolution. Conductivity and temperature frequencies are multiplexed through a precision Wein bridge. Automatic circuitry periodically corrects any time or temperature-induced errors in the electronics. Pressure is acquired with high resolution through an A/D converter. Collecting high quality data is easy and and reliable, following these few simple steps:

- Connect the profiler to a computer, check instrument status and select sampling parameters using menu-driven SEASOFT software.
- Switch the profiler ON just before lowering into the water (cast number, time and date are automatically recorded).
- When the cast is complete, switch the profiler OFF. Up to 100 casts can be recorded (within limit of available memory) before uploading to computer.
- After recovery, connect profiler to the computer and transfer the stored CTD data (plus any auxiliary sensor data) to floppy or hard disk files.
- Run SEASOFT's graphing/plotting program to convert to engineering units, display the data and create presentation quality graphics.



Profiler Configuration and Options

The Seacat's sensors consist of an internal-field glass conductivity cell with platinum electrodes, an aged, pressure-protected thermistor temperature sensor, and a mechanical strain gauge pressure sensor with a stainless steel or titanium element (depending on sensor range). Four single-ended 12-bit A/D input channels, and output power for optional auxiliary sensors (+10 volt, 50 ma) are provided through a separate connector. Depending on the auxiliary sensor requirements, the 4 A/D input channels can be optionally configured as 2 differential input channels and 1 channel can also be configured for a current (log) input sensor (PAR). See Application Note 29 for more information about configuration options.

The standard plastic housing is rated for 600 meters, and holds 6 "D" size alkaline cells. Optional aluminum or titanium housings are available for 3400, 6800 or 10500 meters. 9-cell housings required to power a fluorometer are available in plastic or aluminum. Battery life is about 40 hrs. without optional equipment. Battery life with optional pump and most auxiliary sensors is about 15-20 hrs.

Memory and Communication

128K bytes of CMOS static RAM is standard; 512K or 1024K is optional. Each sample (scan) of conductivity, temperature, and pressure uses 6 bytes. Auxiliary input voltages are stored in pairs, adding 3 bytes per pair. The 128K memory will last 3 hours when recording C, T, and P at 2 scans per second. When the main batteries are removed, the memory is supported for up to 3 years by board-mounted lithium cells. The Seacat Profiler communicates via a standard RS-232 interface. Stored data is uploaded at up to 38K baud, permitting 128K bytes of memory transfer in less than 2 minutes. In addition to recording internally, real-time data can be simultaneously transmitted short distances at 600 baud. Optional isolated line drivers permit real-time telemetry over cables up to 7,000 meters long.



SEACAT PROFILER WITH D.O., pH & PUMP

Profiler Specifications

	Range	Accuracy	Resolution
Conductivity (S/m)	0 - 7	± 0.001	± 0.0001
Temperature (°C)	-5 to +35	± 0.01	± 0.001
Depth (meters)[1]	60-1000	± 0.25%	± 0.015%
	2000-10000	± 0.15%	± 0.015%

Weight (air)Plastic housing 5.1 Kg; aluminum 7.2 Kg; titanium 10.9 Kg
Weight (water)Plastic housing 1.2 Kg; aluminum 3.3 Kg; titanium 7.0 Kg
[1]Select range for intended operating depth: 60/100/200/340/600/1000/2000/3400/6800 or 10,500 meters. See Application Note 27, *Minimizing Strain Gauge Sensor Errors*

Optional Equipment

SBE 5T Submersible Pump	Stainless Steel Guard Cage	Altimeter
NMEA 0183 GPS interface	SBE 18 pH sensor	SBE 27 pH/ORP sensor
SBE 23 Dissolved Oxygen sensor	Transmissometer	Fluorometer
Optical Backscatter Sensor	Chlorophyll Absorption Meter	PAR sensor

SEA-BIRD ELECTRONICS, INC.
1808 136th Place NE, Bellevue, WA 98005
Telephone (206) 643-9866
e-mail: <seabird@seabird.com>
Telefax (206) 643-9954

APPENDIX 3: Instrument Calibration

- General Instrument Calibration
    - ADCPs
    - CTD-OBS and CT-OBS Instrumentation

General Instrumentation Calibration

ADCPs

TRDI ADCP's transducers are factory calibrated during their production and do not require follow-up calibration unless the instrument has undergone a tremendous stress or experiences some form of internal electronic failure. Internal tests, prior to deployment, verify that the ADCP is operating correctly. The internal compasses were calibrated by OSI following the manufacture's calibration procedures. The internal compasses of the vessel-mounted ADCPs were calibrated in the field, following the manufacturer's calibration procedures, prior to real-time surveys.

CTD-OBS and CT-OBS Instrumentation

The Seabird CTD-OBS vertical profilers are factory calibrated on a yearly basis for conductivity, temperature, and depth. YSI sondes (CT-OBS) are factory calibrated for temperature. The conductivity probes of the YSI sondes were calibrated by OSI prior to the project using fixed standardized calibration solutions. The YSI sondes' and CTDs' OBS sensors were calibrated by OSI with fixed standardized turbidity calibration solutions prior to their use on this project.

APPENDIX 4: CT-OBS Water Quality Time Series Plots

Temperature, Salinity and Turbidity

- Station 014
- Station 042
- Station 067
- Station 102
- Station 135
- Station 175

(Tidal phase indicated by color based on vertically averaged current direction data from each station's ADCP)

In Situ Water Quality Data
Station 014: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 014: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 014: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 014: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 014: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 014: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 014: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 014: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 014: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 014: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 014: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 014: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 014: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 014: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 014: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 014: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 014: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 014: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 042: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 042: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 042: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 042: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 042: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 042: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 042: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 042: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 042: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 042: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 067: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 067: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 067: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 067: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 067: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 067: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 067: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 067: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 067: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 067: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 067: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 067: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 067: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 067: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 067: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 067: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 067: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 067: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 102: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 102: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 102: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 102: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 102: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 102: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 135: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 135: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 135: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 135: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 135: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 135: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 135: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 135: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 135: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 135: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 135: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 135: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 135: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 135: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 135: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 135: 3ft Above Bottom
Passaic River, NJ







In Situ Water Quality Data
Station 135: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 135: 3ft Above Bottom
Passaic River, NJ



In Situ Water Quality Data
Station 175: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 175: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 175: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 175: 3ft Below Surface
Passaic River, NJ







In Situ Water Quality Data
Station 175: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 175: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 175: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 175: 3ft Below Surface
Passaic River, NJ



In Situ Water Quality Data
Station 175: 3ft Below Surface
Passaic River, NJ



APPENDIX 5: *In Situ* ADCP Time Series Plots

Vertically Averaged

Current Magnitude and Direction

- Station 014
- Station 042
- Station 067
- Station 102
- Station 135

In Situ ADCP Current Data
Station 014
Passaic River, NJ





In Situ ADCP Current Data
Station 014
Passaic River, NJ



In Situ ADCP Current Data
Station 014
Passaic River, NJ





In Situ ADCP Current Data
Station 014
Passaic River, NJ



In Situ ADCP Current Data
Station 014
Passaic River, NJ





In Situ ADCP Current Data
Station 014
Passaic River, NJ





In Situ ADCP Current Data
Station 014
Passaic River, NJ





In Situ ADCP Current Data
Station 014
Passaic River, NJ





In Situ ADCP Current Data
Station 014
Passaic River, NJ



In Situ ADCP Current Data
Station 042
Passaic River, NJ



In Situ ADCP Current Data
Station 042
Passaic River, NJ





In Situ ADCP Current Data
Station 042
Passaic River, NJ





In Situ ADCP Current Data
Station 042
Passaic River, NJ



In Situ ADCP Current Data
Station 042
Passaic River, NJ



In Situ ADCP Current Data
Station 042
Passaic River, NJ





In Situ ADCP Current Data
Station 042
Passaic River, NJ





In Situ ADCP Current Data
Station 042
Passaic River, NJ



In Situ ADCP Current Data
Station 042
Passaic River, NJ





In Situ ADCP Current Data
Station 067
Passaic River, NJ





In Situ ADCP Current Data
Station 067
Passaic River, NJ





In Situ ADCP Current Data
Station 067
Passaic River, NJ





In Situ ADCP Current Data
Station 067
Passaic River, NJ





In Situ ADCP Current Data
Station 067
Passaic River, NJ





In Situ ADCP Current Data
Station 067
Passaic River, NJ





In Situ ADCP Current Data
Station 067
Passaic River, NJ





In Situ ADCP Current Data
Station 067
Passaic River, NJ



In Situ ADCP Current Data
Station 067
Passaic River, NJ



In Situ ADCP Current Data
Station 102
Passaic River, NJ



In Situ ADCP Current Data
Station 102
Passaic River, NJ





In Situ ADCP Current Data
Station 102
Passaic River, NJ



In Situ ADCP Current Data
Station 102
Passaic River, NJ





In Situ ADCP Current Data
Station 102
Passaic River, NJ





In Situ ADCP Current Data
Station 102
Passaic River, NJ





In Situ ADCP Current Data
Station 102
Passaic River, NJ





In Situ ADCP Current Data
Station 102
Passaic River, NJ





In Situ ADCP Current Data
Station 102
Passaic River, NJ



In Situ ADCP Current Data
Station 135
Passaic River, NJ





In Situ ADCP Current Data
Station 135
Passaic River, NJ





In Situ ADCP Current Data
Station 135
Passaic River, NJ





In Situ ADCP Current Data
Station 135
Passaic River, NJ





In Situ ADCP Current Data
Station 135
Passaic River, NJ





In Situ ADCP Current Data
Station 135
Passaic River, NJ



In Situ ADCP Current Data
Station 135
Passaic River, NJ





In Situ ADCP Current Data
Station 135
Passaic River, NJ





In Situ ADCP Current Data
Station 135
Passaic River, NJ





APPENDIX 6: Mooring CTD-OBS Vertical Profiles

Events E01, E05, E09, E10, E14, E19, & E23

Presented Per Trip

- Station 014
- Station 042
- Station 067
- Station 102
- Station 135
- Station 175

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E01-T014-P3

3/22/10 15:26 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	8.65
Max Temp:	11.32
Avg Temp:	10.02
Min Cond:	0.25
Max Cond:	9.77
Avg Cond:	5.31
Min Salinity:	0.17
Max Salinity:	8.22
Avg Salinity:	4.33
Min Sigma-Theta:	-0.29
Max Sigma-Theta:	6.25
Avg Sigma-Theta:	3.09
Min Turbidity:	9.47
Max Turbidity:	20.56
Avg Turbidity:	12.17

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E01-T042-P1

3/22/10 14:55 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.10
Max Temp:	11.15
Avg Temp:	11.11
Min Cond:	0.25
Max Cond:	0.27
Avg Cond:	0.25
Min Salinity:	0.16
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	-0.28
Max Sigma-Theta:	-0.27
Avg Sigma-Theta:	-0.27
Min Turbidity:	9.15
Max Turbidity:	10.14
Avg Turbidity:	9.80

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E01-T067-P3

3/23/10 13:58 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.61
Max Temp:	11.61
Avg Temp:	11.61
Min Cond:	0.23
Max Cond:	0.23
Avg Cond:	0.23
Min Salinity:	0.15
Max Salinity:	0.15
Avg Salinity:	0.15
Min Sigma-Theta:	-0.34
Max Sigma-Theta:	-0.34
Avg Sigma-Theta:	-0.34
Min Turbidity:	32.12
Max Turbidity:	68.56
Avg Turbidity:	46.25

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E01-T102-P1

3/23/10 13:25 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.50
Max Temp:	11.51
Avg Temp:	11.50
Min Cond:	0.24
Max Cond:	0.24
Avg Cond:	0.24
Min Salinity:	0.15
Max Salinity:	0.15
Avg Salinity:	0.15
Min Sigma-Theta:	-0.33
Max Sigma-Theta:	-0.33
Avg Sigma-Theta:	-0.33
Min Turbidity:	40.01
Max Turbidity:	44.71
Avg Turbidity:	41.92

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E01-T135-P3

3/24/10 13:56 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.22
Max Temp:	9.23
Avg Temp:	9.23
Min Cond:	0.21
Max Cond:	0.21
Avg Cond:	0.21
Min Salinity:	0.14
Max Salinity:	0.14
Avg Salinity:	0.14
Min Sigma-Theta:	-0.12
Max Sigma-Theta:	-0.12
Avg Sigma-Theta:	-0.12
Min Turbidity:	16.51
Max Turbidity:	19.66
Avg Turbidity:	17.98

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E05-T014-P3

5/02/10 12:23 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	13.52
Max Temp:	15.98
Avg Temp:	14.96
Min Cond:	1.57
Max Cond:	16.66
Avg Cond:	8.55
Min Salinity:	0.96
Max Salinity:	12.84
Avg Salinity:	6.31
Min Sigma-Theta:	-0.43
Max Sigma-Theta:	9.21
Avg Sigma-Theta:	3.96
Min Turbidity:	7.41
Max Turbidity:	116.70
Avg Turbidity:	36.63

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E05-T042-P1

5/02/10 15:11 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.18
Max Temp:	16.79
Avg Temp:	15.29
Min Cond:	1.36
Max Cond:	11.55
Avg Cond:	6.58
Min Salinity:	0.82
Max Salinity:	8.49
Avg Salinity:	4.67
Min Sigma-Theta:	-0.62
Max Sigma-Theta:	5.76
Avg Sigma-Theta:	2.64
Min Turbidity:	2.37
Max Turbidity:	22.01
Avg Turbidity:	13.79

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E05-T067-P3

5/01/10 18:42 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.57
Max Temp:	15.99
Avg Temp:	15.72
Min Cond:	0.32
Max Cond:	0.34
Avg Cond:	0.33
Min Salinity:	0.19
Max Salinity:	0.20
Avg Salinity:	0.20
Min Sigma-Theta:	-1.04
Max Sigma-Theta:	-0.83
Avg Sigma-Theta:	-0.87
Min Turbidity:	10.43
Max Turbidity:	23.73
Avg Turbidity:	15.32

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E05-T102-P1

5/01/10 16:12 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.92
Max Temp:	16.19
Avg Temp:	15.40
Min Cond:	0.33
Max Cond:	0.34
Avg Cond:	0.33
Min Salinity:	0.19
Max Salinity:	0.20
Avg Salinity:	0.20
Min Sigma-Theta:	-0.94
Max Sigma-Theta:	-0.73
Avg Sigma-Theta:	-0.81
Min Turbidity:	4.11
Max Turbidity:	5.28
Avg Turbidity:	4.81

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E05-T135-P3

5/01/10 13:53 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.24
Max Temp:	15.00
Avg Temp:	14.50
Min Cond:	0.32
Max Cond:	0.72
Avg Cond:	0.39
Min Salinity:	0.20
Max Salinity:	0.21
Avg Salinity:	0.20
Min Sigma-Theta:	-0.64
Max Sigma-Theta:	-0.63
Avg Sigma-Theta:	-0.63
Min Turbidity:	5.12
Max Turbidity:	6.57
Avg Turbidity:	6.05

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E05-T175-P2

5/04/10 15:58 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.01
Max Temp:	20.04
Avg Temp:	20.02
Min Cond:	0.33
Max Cond:	0.33
Avg Cond:	0.33
Min Salinity:	0.18
Max Salinity:	0.18
Avg Salinity:	0.18
Min Sigma-Theta:	-1.66
Max Sigma-Theta:	-1.66
Avg Sigma-Theta:	-1.66
Min Turbidity:	9.81
Max Turbidity:	9.93
Avg Turbidity:	9.86

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E09-T014-P3

5/02/10 14:41 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	13.50
Max Temp:	16.60
Avg Temp:	14.69
Min Cond:	5.96
Max Cond:	17.87
Avg Cond:	13.96
Min Salinity:	3.83
Max Salinity:	13.85
Avg Salinity:	10.45
Min Sigma-Theta:	1.60
Max Sigma-Theta:	9.99
Avg Sigma-Theta:	7.17
Min Turbidity:	7.70
Max Turbidity:	28.90
Avg Turbidity:	19.19

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E09-T042-P1

5/02/10 16:58 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	13.87
Max Temp:	17.03
Avg Temp:	15.23
Min Cond:	1.49
Max Cond:	14.57
Avg Cond:	8.14
Min Salinity:	0.89
Max Salinity:	11.00
Avg Salinity:	5.91
Min Sigma-Theta:	-0.54
Max Sigma-Theta:	7.74
Avg Sigma-Theta:	3.61
Min Turbidity:	6.40
Max Turbidity:	17.15
Avg Turbidity:	10.78

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E09-T067-P3

5/01/10 20:50 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.73
Max Temp:	16.77
Avg Temp:	15.97
Min Cond:	0.33
Max Cond:	0.35
Avg Cond:	0.34
Min Salinity:	0.19
Max Salinity:	0.21
Avg Salinity:	0.20
Min Sigma-Theta:	-1.04
Max Sigma-Theta:	-0.85
Avg Sigma-Theta:	-0.90
Min Turbidity:	7.83
Max Turbidity:	11.88
Avg Turbidity:	9.50

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E09-T102-P1

5/01/10 17:56 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.23
Max Temp:	16.79
Avg Temp:	15.56
Min Cond:	0.33
Max Cond:	0.35
Avg Cond:	0.34
Min Salinity:	0.20
Max Salinity:	0.20
Avg Salinity:	0.20
Min Sigma-Theta:	-1.03
Max Sigma-Theta:	-0.78
Avg Sigma-Theta:	-0.83
Min Turbidity:	3.40
Max Turbidity:	7.47
Avg Turbidity:	6.49

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E09-T135-P3

5/01/10 15:49 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.52
Max Temp:	15.67
Avg Temp:	14.71
Min Cond:	0.32
Max Cond:	0.33
Avg Cond:	0.32
Min Salinity:	0.19
Max Salinity:	0.20
Avg Salinity:	0.19
Min Sigma-Theta:	-0.86
Max Sigma-Theta:	-0.68
Avg Sigma-Theta:	-0.70
Min Turbidity:	3.44
Max Turbidity:	6.60
Avg Turbidity:	6.00

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E10-T014-P3

5/20/10 12:53 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.66
Max Temp:	16.14
Avg Temp:	15.56
Min Cond:	5.82
Max Cond:	16.67
Avg Cond:	10.59
Min Salinity:	3.87
Max Salinity:	12.47
Avg Salinity:	7.54
Min Sigma-Theta:	1.89
Max Sigma-Theta:	8.74
Avg Sigma-Theta:	4.81
Min Turbidity:	16.60
Max Turbidity:	56.15
Avg Turbidity:	25.25

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E10-T042-P1

5/20/10 15:10 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.75
Max Temp:	16.88
Avg Temp:	16.26
Min Cond:	1.45
Max Cond:	7.32
Avg Cond:	3.55
Min Salinity:	0.87
Max Salinity:	4.99
Avg Salinity:	2.33
Min Sigma-Theta:	-0.53
Max Sigma-Theta:	2.82
Avg Sigma-Theta:	0.69
Min Turbidity:	13.83
Max Turbidity:	90.04
Avg Turbidity:	34.69

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E10-T067-P3

5/19/10 19:21 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	17.03
Max Temp:	17.26
Avg Temp:	17.13
Min Cond:	0.46
Max Cond:	0.46
Avg Cond:	0.46
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-1.07
Max Sigma-Theta:	-1.03
Avg Sigma-Theta:	-1.04
Min Turbidity:	11.35
Max Turbidity:	26.49
Avg Turbidity:	16.67

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E10-T102-P1

5/19/10 16:50 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.28
Max Temp:	16.61
Avg Temp:	16.36
Min Cond:	0.38
Max Cond:	0.38
Avg Cond:	0.38
Min Salinity:	0.24
Max Salinity:	0.24
Avg Salinity:	0.24
Min Sigma-Theta:	-0.38
Max Sigma-Theta:	-0.34
Avg Sigma-Theta:	-0.35
Min Turbidity:	10.18
Max Turbidity:	11.64
Avg Turbidity:	11.14

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
10A-E10-T135-P3

5/19/10 14:08 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.51
Max Temp:	16.55
Avg Temp:	16.52
Min Cond:	0.38
Max Cond:	0.38
Avg Cond:	0.38
Min Salinity:	0.25
Max Salinity:	0.25
Avg Salinity:	0.25
Min Sigma-Theta:	-0.26
Max Sigma-Theta:	-0.25
Avg Sigma-Theta:	-0.25
Min Turbidity:	10.00
Max Turbidity:	11.10
Avg Turbidity:	10.60

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E10-T175-P2

5/25/10 14:33 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.23
Max Temp:	20.62
Avg Temp:	20.49
Min Cond:	0.48
Max Cond:	0.49
Avg Cond:	0.49
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-1.73
Max Sigma-Theta:	-1.69
Avg Sigma-Theta:	-1.71
Min Turbidity:	4.35
Max Turbidity:	5.73
Avg Turbidity:	4.86

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E14-T014-P3

5/20/10 14:40 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.07
Max Temp:	17.14
Avg Temp:	14.88
Min Cond:	6.41
Max Cond:	20.46
Avg Cond:	16.33
Min Salinity:	4.19
Max Salinity:	15.83
Avg Salinity:	12.32
Min Sigma-Theta:	1.96
Max Sigma-Theta:	11.42
Avg Sigma-Theta:	8.59
Min Turbidity:	15.59
Max Turbidity:	122.70
Avg Turbidity:	56.83

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E14-T042-P1

5/20/10 16:32 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.02
Max Temp:	17.76
Avg Temp:	16.11
Min Cond:	4.44
Max Cond:	14.45
Avg Cond:	9.55
Min Salinity:	2.79
Max Salinity:	10.58
Avg Salinity:	6.74
Min Sigma-Theta:	0.78
Max Sigma-Theta:	7.23
Avg Sigma-Theta:	4.09
Min Turbidity:	15.65
Max Turbidity:	117.13
Avg Turbidity:	36.99

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E14-T067-P3

5/19/10 20:50 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.66
Max Temp:	16.70
Avg Temp:	16.68
Min Cond:	0.42
Max Cond:	0.42
Avg Cond:	0.42
Min Salinity:	0.24
Max Salinity:	0.25
Avg Salinity:	0.24
Min Sigma-Theta:	-0.98
Max Sigma-Theta:	-0.98
Avg Sigma-Theta:	-0.98
Min Turbidity:	21.58
Max Turbidity:	49.48
Avg Turbidity:	31.73

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E14-T102-P1

5/19/10 18:37 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.33
Max Temp:	16.59
Avg Temp:	16.39
Min Cond:	0.37
Max Cond:	0.38
Avg Cond:	0.38
Min Salinity:	0.24
Max Salinity:	0.24
Avg Salinity:	0.24
Min Sigma-Theta:	-0.38
Max Sigma-Theta:	-0.35
Avg Sigma-Theta:	-0.36
Min Turbidity:	9.11
Max Turbidity:	11.12
Avg Turbidity:	10.40

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E14-T135-P3

5/19/10 16:14 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.54
Max Temp:	16.69
Avg Temp:	16.60
Min Cond:	0.38
Max Cond:	0.38
Avg Cond:	0.38
Min Salinity:	0.25
Max Salinity:	0.25
Avg Salinity:	0.25
Min Sigma-Theta:	-0.27
Max Sigma-Theta:	-0.25
Avg Sigma-Theta:	-0.26
Min Turbidity:	9.04
Max Turbidity:	9.98
Avg Turbidity:	9.43

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E15-T014-P3

6/18/10 12:53 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.54
Max Temp:	22.25
Avg Temp:	22.03
Min Cond:	8.52
Max Cond:	25.62
Avg Cond:	15.80
Min Salinity:	4.41
Max Salinity:	16.87
Avg Salinity:	9.90
Min Sigma-Theta:	1.08
Max Sigma-Theta:	10.62
Avg Sigma-Theta:	5.24
Min Turbidity:	15.65
Max Turbidity:	23.31
Avg Turbidity:	19.79

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E15-T042-P1

6/18/10 15:55 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	22.13
Max Temp:	24.37
Avg Temp:	23.27
Min Cond:	11.06
Max Cond:	18.53
Avg Cond:	13.69
Min Salinity:	6.10
Max Salinity:	9.69
Avg Salinity:	8.04
Min Sigma-Theta:	1.25
Max Sigma-Theta:	4.87
Avg Sigma-Theta:	3.46
Min Turbidity:	16.22
Max Turbidity:	113.06
Avg Turbidity:	61.07

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E15-T067-P3

6/17/10 18:49 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	23.22
Max Temp:	23.57
Avg Temp:	23.34
Min Cond:	1.21
Max Cond:	1.34
Avg Cond:	1.26
Min Salinity:	0.63
Max Salinity:	0.69
Avg Salinity:	0.65
Min Sigma-Theta:	-2.08
Max Sigma-Theta:	-1.99
Avg Sigma-Theta:	-2.04
Min Turbidity:	39.12
Max Turbidity:	51.71
Avg Turbidity:	45.27

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E15-T102-P1

6/17/10 16:14 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.45
Max Temp:	23.01
Avg Temp:	22.67
Min Cond:	0.44
Max Cond:	0.61
Avg Cond:	0.59
Min Salinity:	0.23
Max Salinity:	0.31
Avg Salinity:	0.30
Min Sigma-Theta:	-2.23
Max Sigma-Theta:	-1.93
Avg Sigma-Theta:	-2.15
Min Turbidity:	12.47
Max Turbidity:	38.69
Avg Turbidity:	29.45

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E15-T135-P3

6/17/10 13:26 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	22.18
Max Temp:	22.82
Avg Temp:	22.34
Min Cond:	0.47
Max Cond:	0.60
Avg Cond:	0.59
Min Salinity:	0.24
Max Salinity:	0.31
Avg Salinity:	0.30
Min Sigma-Theta:	-2.24
Max Sigma-Theta:	-2.04
Avg Sigma-Theta:	-2.08
Min Turbidity:	15.11
Max Turbidity:	19.40
Avg Turbidity:	16.55

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E15-T175-P2

6/21/10 19:13 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	22.18
Max Temp:	22.82
Avg Temp:	22.34
Min Cond:	0.47
Max Cond:	0.60
Avg Cond:	0.59
Min Salinity:	0.24
Max Salinity:	0.31
Avg Salinity:	0.30
Min Sigma-Theta:	-2.24
Max Sigma-Theta:	-2.04
Avg Sigma-Theta:	-2.08
Min Turbidity:	15.11
Max Turbidity:	19.40
Avg Turbidity:	16.55

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E19-T014-P3

6/18/10 15:02 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	22.12
Max Temp:	24.67
Avg Temp:	23.00
Min Cond:	20.02
Max Cond:	24.97
Avg Cond:	22.21
Min Salinity:	13.74
Max Salinity:	16.34
Avg Salinity:	14.43
Min Sigma-Theta:	7.54
Max Sigma-Theta:	9.91
Avg Sigma-Theta:	8.41
Min Turbidity:	16.20
Max Turbidity:	81.37
Avg Turbidity:	36.82

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E19-T042-P1

6/18/10 18:07 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.82
Max Temp:	24.48
Avg Temp:	22.61
Min Cond:	11.36
Max Cond:	25.05
Avg Cond:	22.50
Min Salinity:	5.64
Max Salinity:	16.28
Avg Salinity:	14.23
Min Sigma-Theta:	-0.61
Max Sigma-Theta:	10.10
Avg Sigma-Theta:	8.16
Min Turbidity:	16.49
Max Turbidity:	34.70
Avg Turbidity:	23.91

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E19-T067-P3

6/17/10 20:41 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	23.12
Max Temp:	23.19
Avg Temp:	23.16
Min Cond:	0.49
Max Cond:	0.73
Avg Cond:	0.70
Min Salinity:	0.25
Max Salinity:	0.37
Avg Salinity:	0.35
Min Sigma-Theta:	-2.30
Max Sigma-Theta:	-2.21
Avg Sigma-Theta:	-2.23
Min Turbidity:	54.34
Max Turbidity:	119.58
Avg Turbidity:	86.16

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E19-T102-P1

6/17/10 17:52 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	22.87
Max Temp:	24.20
Avg Temp:	23.16
Min Cond:	0.48
Max Cond:	0.63
Avg Cond:	0.61
Min Salinity:	0.24
Max Salinity:	0.32
Avg Salinity:	0.31
Min Sigma-Theta:	-2.57
Max Sigma-Theta:	-2.19
Avg Sigma-Theta:	-2.26
Min Turbidity:	19.03
Max Turbidity:	26.47
Avg Turbidity:	21.97

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E19-T135-P3

6/17/10 15:36 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	22.29
Max Temp:	22.67
Avg Temp:	22.43
Min Cond:	0.44
Max Cond:	0.61
Avg Cond:	0.59
Min Salinity:	0.23
Max Salinity:	0.31
Avg Salinity:	0.30
Min Sigma-Theta:	-2.17
Max Sigma-Theta:	-2.06
Avg Sigma-Theta:	-2.10
Min Turbidity:	14.02
Max Turbidity:	17.99
Avg Turbidity:	16.24

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E23-T014-P3

7/22/10 12:35 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.96
Max Temp:	27.43
Avg Temp:	27.08
Min Cond:	22.21
Max Cond:	34.78
Avg Cond:	30.82
Min Salinity:	13.08
Max Salinity:	20.94
Avg Salinity:	18.30
Min Sigma-Theta:	6.59
Max Sigma-Theta:	12.20
Avg Sigma-Theta:	10.17
Min Turbidity:	9.58
Max Turbidity:	17.79
Avg Turbidity:	13.44

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E23-T042-P1

7/22/10 12:50 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.97
Max Temp:	27.41
Avg Temp:	27.14
Min Cond:	14.70
Max Cond:	29.03
Avg Cond:	21.90
Min Salinity:	8.54
Max Salinity:	17.04
Avg Salinity:	12.58
Min Sigma-Theta:	3.47
Max Sigma-Theta:	9.16
Avg Sigma-Theta:	5.88
Min Turbidity:	9.37
Max Turbidity:	18.36
Avg Turbidity:	16.85

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E23-T067-P3

7/23/10 13:13 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.52
Max Temp:	27.62
Avg Temp:	27.57
Min Cond:	8.50
Max Cond:	14.69
Avg Cond:	12.03
Min Salinity:	4.47
Max Salinity:	8.07
Avg Salinity:	6.52
Min Sigma-Theta:	-0.29
Max Sigma-Theta:	2.41
Avg Sigma-Theta:	1.23
Min Turbidity:	14.09
Max Turbidity:	17.06
Avg Turbidity:	14.88

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E23-T102-P1

7/23/10 13:37 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.06
Max Temp:	27.44
Avg Temp:	27.39
Min Cond:	0.51
Max Cond:	0.58
Avg Cond:	0.56
Min Salinity:	0.23
Max Salinity:	0.27
Avg Salinity:	0.26
Min Sigma-Theta:	-3.67
Max Sigma-Theta:	-3.01
Avg Sigma-Theta:	-3.40
Min Turbidity:	16.32
Max Turbidity:	26.21
Avg Turbidity:	21.87

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E23-T135-P3

7/23/10 14:00 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.31
Max Temp:	26.93
Avg Temp:	26.84
Min Cond:	0.54
Max Cond:	0.61
Avg Cond:	0.58
Min Salinity:	0.26
Max Salinity:	0.28
Avg Salinity:	0.27
Min Sigma-Theta:	-3.40
Max Sigma-Theta:	-3.00
Avg Sigma-Theta:	-3.25
Min Turbidity:	6.77
Max Turbidity:	10.62
Avg Turbidity:	9.15

APPENDIX 7: Trip 4 Real Time Survey Events E02-E04

- Vertically Averaged Current Vector Plots
- CTD-OBS Vertical Profiles



LEGEND FOR CURRENT VELOCITY MAPPINGS:

CURRENT VECTOR SCALE
1" = 150 CM/S

SCALE : 1"=750'
750 0 750

NOTES:

1. GRID SYSTEM IS IN FEET AND IS THE NEW JERSEY STATE PLANE COORDINATE SYSTEM, NAD83.
2. ORTHOPHOTO IMAGERY ARE TRUE COLOR ONE FOOT GROUND SAMPLE DISTANCE IMAGES PRODUCED FROM AERIAL PHOTOS FLOWN IN 2007 AND OBTAINED FROM THE NEW JERSEY GEOGRAPHIC INFORMATION NETWORK (NJGIN).
3. THE INFORMATION PRESENTED ON THESE DRAWINGS REPRESENTS THE RESULTS OF A SURVEY PEFORMED BY OCEAN SURVEYS, INC. ON 24–25 MARCH 2010 AND CAN ONLY BE CONSIDERED AS INDICATING THE CONDITIONS EXISTING AT THAT TIME. REUSE OF THIS INFORMATION BY CLIENT OF OTHERS BEYOND THE SCOPE OF WORK FOR WHICH IT WAS ACQUIRED SHALL BE AT THE SOLE RISK OF THE USER AND WITHOUT LIABILITY TO OSI.

OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388–4631
OSI
www.oceansurveys.com

Vertically Averaged Current Data
Program 10A, Location Map & Event 02
24 March 2010
Passaic River, New Jersey



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Ebb Tide
Program 10A, Event 03
25 March 2010, 10:49 - 13:06 (UTC) Hours
Passaic River, New Jersey



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Flood Tide
Program 10A, Event 04
25 March 2010, 16:52 - 19:08 (UTC) Hours
Passaic River, New Jersey

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E02-T175-P1

3/24/10 18:17 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.91
Max Temp:	15.30
Avg Temp:	15.11
Min Cond:	0.00
Max Cond:	0.03
Avg Cond:	0.02
Min Salinity:	0.00
Max Salinity:	0.03
Avg Salinity:	0.02
Min Sigma-Theta:	-0.95
Max Sigma-Theta:	-0.89
Avg Sigma-Theta:	-0.91
Min Turbidity:	11.88
Max Turbidity:	18.81
Avg Turbidity:	14.04

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E02-T175-P2

3/24/10 18:28 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.39
Max Temp:	10.94
Avg Temp:	10.58
Min Cond:	0.00
Max Cond:	0.00
Avg Cond:	0.00
Min Salinity:	0.01
Max Salinity:	0.01
Avg Salinity:	0.01
Min Sigma-Theta:	-0.39
Max Sigma-Theta:	-0.33
Avg Sigma-Theta:	-0.35
Min Turbidity:	10.82
Max Turbidity:	13.12
Avg Turbidity:	11.90

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E02-T175-P3

3/24/10 18:43 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.51
Max Temp:	10.69
Avg Temp:	10.62
Min Cond:	0.24
Max Cond:	0.25
Avg Cond:	0.25
Min Salinity:	0.16
Max Salinity:	0.17
Avg Salinity:	0.16
Min Sigma-Theta:	-0.24
Max Sigma-Theta:	-0.22
Avg Sigma-Theta:	-0.23
Min Turbidity:	11.69
Max Turbidity:	13.56
Avg Turbidity:	12.59

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E02-T175-P4

3/24/10 18:50 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.78
Max Temp:	11.04
Avg Temp:	10.97
Min Cond:	0.26
Max Cond:	0.26
Avg Cond:	0.26
Min Salinity:	0.17
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	-0.27
Max Sigma-Theta:	-0.25
Avg Sigma-Theta:	-0.26
Min Turbidity:	12.22
Max Turbidity:	13.16
Avg Turbidity:	12.50

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E03-T014-P1

3/25/10 11:51 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.47
Max Temp:	9.81
Avg Temp:	9.76
Min Cond:	0.23
Max Cond:	0.32
Avg Cond:	0.24
Min Salinity:	0.16
Max Salinity:	0.18
Avg Salinity:	0.16
Min Sigma-Theta:	-0.16
Max Sigma-Theta:	-0.12
Avg Sigma-Theta:	-0.15
Min Turbidity:	22.53
Max Turbidity:	77.81
Avg Turbidity:	42.43

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E03-T014-P2

3/25/10 12:03 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.77
Max Temp:	9.78
Avg Temp:	9.77
Min Cond:	0.22
Max Cond:	0.23
Avg Cond:	0.23
Min Salinity:	0.15
Max Salinity:	0.16
Avg Salinity:	0.15
Min Sigma-Theta:	-0.16
Max Sigma-Theta:	-0.15
Avg Sigma-Theta:	-0.16
Min Turbidity:	20.27
Max Turbidity:	32.91
Avg Turbidity:	25.30

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E03-T014-P3

3/25/10 12:16 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.68
Max Temp:	9.77
Avg Temp:	9.75
Min Cond:	0.22
Max Cond:	0.23
Avg Cond:	0.22
Min Salinity:	0.15
Max Salinity:	0.15
Avg Salinity:	0.15
Min Sigma-Theta:	-0.16
Max Sigma-Theta:	-0.15
Avg Sigma-Theta:	-0.16
Min Turbidity:	16.01
Max Turbidity:	20.52
Avg Turbidity:	17.10

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E03-T042-P1

3/25/10 12:51 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.17
Max Temp:	9.75
Avg Temp:	9.71
Min Cond:	0.20
Max Cond:	0.22
Avg Cond:	0.21
Min Salinity:	0.14
Max Salinity:	0.15
Avg Salinity:	0.15
Min Sigma-Theta:	-0.16
Max Sigma-Theta:	-0.12
Avg Sigma-Theta:	-0.16
Min Turbidity:	14.83
Max Turbidity:	17.73
Avg Turbidity:	16.23

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E03-T042-P2

3/25/10 13:02 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.75
Max Temp:	9.76
Avg Temp:	9.75
Min Cond:	0.21
Max Cond:	0.21
Avg Cond:	0.21
Min Salinity:	0.14
Max Salinity:	0.14
Avg Salinity:	0.14
Min Sigma-Theta:	-0.16
Max Sigma-Theta:	-0.16
Avg Sigma-Theta:	-0.16
Min Turbidity:	15.45
Max Turbidity:	17.72
Avg Turbidity:	16.32

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E03-T042-P3

3/25/10 13:13 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.75
Max Temp:	9.76
Avg Temp:	9.76
Min Cond:	0.21
Max Cond:	0.21
Avg Cond:	0.21
Min Salinity:	0.14
Max Salinity:	0.14
Avg Salinity:	0.14
Min Sigma-Theta:	-0.16
Max Sigma-Theta:	-0.16
Avg Sigma-Theta:	-0.16
Min Turbidity:	8.00
Max Turbidity:	21.40
Avg Turbidity:	18.13

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E03-T067-P1

3/25/10 13:15 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.23
Max Temp:	10.90
Avg Temp:	10.46
Min Cond:	0.23
Max Cond:	0.24
Avg Cond:	0.24
Min Salinity:	0.16
Max Salinity:	0.16
Avg Salinity:	0.16
Min Sigma-Theta:	-0.26
Max Sigma-Theta:	-0.11
Avg Sigma-Theta:	-0.22
Min Turbidity:	12.49
Max Turbidity:	16.24
Avg Turbidity:	15.27

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E03-T067-P2

3/25/10 13:27 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.89
Max Temp:	10.24
Avg Temp:	10.08
Min Cond:	0.23
Max Cond:	0.23
Avg Cond:	0.23
Min Salinity:	0.15
Max Salinity:	0.16
Avg Salinity:	0.16
Min Sigma-Theta:	-0.20
Max Sigma-Theta:	-0.17
Avg Sigma-Theta:	-0.18
Min Turbidity:	14.45
Max Turbidity:	18.24
Avg Turbidity:	16.18

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E03-T067-P3

3/25/10 13:31 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.91
Max Temp:	10.33
Avg Temp:	10.15
Min Cond:	0.23
Max Cond:	0.23
Avg Cond:	0.23
Min Salinity:	0.15
Max Salinity:	0.16
Avg Salinity:	0.15
Min Sigma-Theta:	-0.21
Max Sigma-Theta:	-0.17
Avg Sigma-Theta:	-0.19
Min Turbidity:	14.45
Max Turbidity:	15.51
Avg Turbidity:	15.19

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E03-T102-P1

3/25/10 12:02 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	5.48
Max Temp:	6.39
Avg Temp:	5.95
Min Cond:	0.21
Max Cond:	0.21
Avg Cond:	0.21
Min Salinity:	0.16
Max Salinity:	0.16
Avg Salinity:	0.16
Min Sigma-Theta:	0.06
Max Sigma-Theta:	0.08
Avg Sigma-Theta:	0.07
Min Turbidity:	11.70
Max Turbidity:	13.18
Avg Turbidity:	12.79

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E03-T102-P2

3/25/10 12:14 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	8.98
Max Temp:	9.37
Avg Temp:	9.19
Min Cond:	0.23
Max Cond:	0.23
Avg Cond:	0.23
Min Salinity:	0.16
Max Salinity:	0.16
Avg Salinity:	0.16
Min Sigma-Theta:	-0.12
Max Sigma-Theta:	-0.09
Avg Sigma-Theta:	-0.11
Min Turbidity:	13.21
Max Turbidity:	14.41
Avg Turbidity:	13.81

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E03-T102-P3

3/25/10 12:23 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.11
Max Temp:	9.29
Avg Temp:	9.24
Min Cond:	0.23
Max Cond:	0.23
Avg Cond:	0.23
Min Salinity:	0.16
Max Salinity:	0.16
Avg Salinity:	0.16
Min Sigma-Theta:	-0.12
Max Sigma-Theta:	-0.10
Avg Sigma-Theta:	-0.11
Min Turbidity:	13.77
Max Turbidity:	15.80
Avg Turbidity:	14.28

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E03-T135-P1

3/25/10 11:26 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	7.81
Max Temp:	8.20
Avg Temp:	8.07
Min Cond:	0.23
Max Cond:	0.23
Avg Cond:	0.23
Min Salinity:	0.16
Max Salinity:	0.16
Avg Salinity:	0.16
Min Sigma-Theta:	-0.03
Max Sigma-Theta:	-0.01
Avg Sigma-Theta:	-0.03
Min Turbidity:	10.52
Max Turbidity:	13.22
Avg Turbidity:	11.77

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E03-T135-P2

3/25/10 11:14 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	8.64
Max Temp:	8.87
Avg Temp:	8.78
Min Cond:	0.23
Max Cond:	0.24
Avg Cond:	0.23
Min Salinity:	0.16
Max Salinity:	0.16
Avg Salinity:	0.16
Min Sigma-Theta:	-0.08
Max Sigma-Theta:	-0.06
Avg Sigma-Theta:	-0.07
Min Turbidity:	10.65
Max Turbidity:	12.86
Avg Turbidity:	11.95

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E03-T135-P3

3/25/10 11:02 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	3.94
Max Temp:	4.73
Avg Temp:	4.28
Min Cond:	0.21
Max Cond:	0.22
Avg Cond:	0.22
Min Salinity:	0.17
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	0.11
Max Sigma-Theta:	0.11
Avg Sigma-Theta:	0.11
Min Turbidity:	12.00
Max Turbidity:	13.79
Avg Turbidity:	12.90

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E04-T014-P1

3/25/10 18:11 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.15
Max Temp:	10.87
Avg Temp:	10.23
Min Cond:	0.22
Max Cond:	0.35
Avg Cond:	0.24
Min Salinity:	0.15
Max Salinity:	0.23
Avg Salinity:	0.16
Min Sigma-Theta:	-0.20
Max Sigma-Theta:	-0.19
Avg Sigma-Theta:	-0.19
Min Turbidity:	10.38
Max Turbidity:	11.58
Avg Turbidity:	11.02

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E04-T014-P2

3/25/10 18:20 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.07
Max Temp:	10.25
Avg Temp:	10.18
Min Cond:	0.23
Max Cond:	0.23
Avg Cond:	0.23
Min Salinity:	0.15
Max Salinity:	0.15
Avg Salinity:	0.15
Min Sigma-Theta:	-0.20
Max Sigma-Theta:	-0.19
Avg Sigma-Theta:	-0.19
Min Turbidity:	10.05
Max Turbidity:	10.92
Avg Turbidity:	10.46

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E04-T014-P3

3/25/10 18:27 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.30
Max Temp:	10.19
Avg Temp:	9.90
Min Cond:	0.23
Max Cond:	8.28
Avg Cond:	2.80
Min Salinity:	0.15
Max Salinity:	6.75
Avg Salinity:	2.21
Min Sigma-Theta:	-0.19
Max Sigma-Theta:	5.05
Avg Sigma-Theta:	1.45
Min Turbidity:	9.34
Max Turbidity:	30.88
Avg Turbidity:	14.80

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E04-T042-P1

3/25/10 18:56 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.10
Max Temp:	11.04
Avg Temp:	10.24
Min Cond:	0.21
Max Cond:	0.23
Avg Cond:	0.22
Min Salinity:	0.14
Max Salinity:	0.15
Avg Salinity:	0.15
Min Sigma-Theta:	-0.29
Max Sigma-Theta:	-0.19
Avg Sigma-Theta:	-0.20
Min Turbidity:	8.09
Max Turbidity:	9.98
Avg Turbidity:	9.33

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E04-T042-P2

3/25/10 19:06 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.09
Max Temp:	10.29
Avg Temp:	10.14
Min Cond:	0.21
Max Cond:	0.22
Avg Cond:	0.22
Min Salinity:	0.15
Max Salinity:	0.15
Avg Salinity:	0.15
Min Sigma-Theta:	-0.21
Max Sigma-Theta:	-0.19
Avg Sigma-Theta:	-0.19
Min Turbidity:	8.11
Max Turbidity:	10.74
Avg Turbidity:	9.72

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E04-T042-P3

3/25/10 19:15 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.11
Max Temp:	10.24
Avg Temp:	10.16
Min Cond:	0.21
Max Cond:	0.22
Avg Cond:	0.22
Min Salinity:	0.14
Max Salinity:	0.15
Avg Salinity:	0.15
Min Sigma-Theta:	-0.21
Max Sigma-Theta:	-0.19
Avg Sigma-Theta:	-0.20
Min Turbidity:	7.99
Max Turbidity:	10.59
Avg Turbidity:	9.65

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E04-T067-P1

3/25/10 19:18 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.26
Max Temp:	16.31
Avg Temp:	15.69
Min Cond:	0.26
Max Cond:	0.27
Avg Cond:	0.26
Min Salinity:	0.15
Max Salinity:	0.16
Avg Salinity:	0.15
Min Sigma-Theta:	-0.99
Max Sigma-Theta:	-0.67
Avg Sigma-Theta:	-0.89
Min Turbidity:	8.99
Max Turbidity:	9.46
Avg Turbidity:	9.26

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E04-T067-P2

3/25/10 19:24 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.29
Max Temp:	12.00
Avg Temp:	11.73
Min Cond:	0.23
Max Cond:	0.24
Avg Cond:	0.24
Min Salinity:	0.15
Max Salinity:	0.15
Avg Salinity:	0.15
Min Sigma-Theta:	-0.38
Max Sigma-Theta:	-0.30
Avg Sigma-Theta:	-0.35
Min Turbidity:	8.73
Max Turbidity:	10.14
Avg Turbidity:	9.22

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E04-T067-P3

3/25/10 19:32 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.22
Max Temp:	11.51
Avg Temp:	11.33
Min Cond:	0.23
Max Cond:	0.24
Avg Cond:	0.23
Min Salinity:	0.15
Max Salinity:	0.15
Avg Salinity:	0.15
Min Sigma-Theta:	-0.33
Max Sigma-Theta:	-0.30
Avg Sigma-Theta:	-0.31
Min Turbidity:	9.02
Max Turbidity:	11.29
Avg Turbidity:	9.57

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E04-T102-P1

3/25/10 18:14 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.38
Max Temp:	16.64
Avg Temp:	16.13
Min Cond:	0.27
Max Cond:	0.27
Avg Cond:	0.27
Min Salinity:	0.15
Max Salinity:	0.16
Avg Salinity:	0.16
Min Sigma-Theta:	-1.04
Max Sigma-Theta:	-0.84
Avg Sigma-Theta:	-0.96
Min Turbidity:	9.78
Max Turbidity:	11.45
Avg Turbidity:	10.24

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E04-T102-P2

3/25/10 18:22 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.65
Max Temp:	11.16
Avg Temp:	11.02
Min Cond:	0.23
Max Cond:	0.23
Avg Cond:	0.23
Min Salinity:	0.15
Max Salinity:	0.15
Avg Salinity:	0.15
Min Sigma-Theta:	-0.29
Max Sigma-Theta:	-0.24
Avg Sigma-Theta:	-0.27
Min Turbidity:	9.15
Max Turbidity:	11.20
Avg Turbidity:	10.11

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E04-T102-P3

3/25/10 18:31 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.50
Max Temp:	11.00
Avg Temp:	10.77
Min Cond:	0.23
Max Cond:	0.23
Avg Cond:	0.23
Min Salinity:	0.15
Max Salinity:	0.15
Avg Salinity:	0.15
Min Sigma-Theta:	-0.27
Max Sigma-Theta:	-0.22
Avg Sigma-Theta:	-0.25
Min Turbidity:	10.37
Max Turbidity:	12.15
Avg Turbidity:	11.61

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E04-T135-P1

3/25/10 17:01 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.73
Max Temp:	16.96
Avg Temp:	16.87
Min Cond:	0.27
Max Cond:	0.27
Avg Cond:	0.27
Min Salinity:	0.16
Max Salinity:	0.16
Avg Salinity:	0.16
Min Sigma-Theta:	-1.10
Max Sigma-Theta:	-1.06
Avg Sigma-Theta:	-1.08
Min Turbidity:	10.30
Max Turbidity:	11.72
Avg Turbidity:	11.03

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E04-T135-P2

3/25/10 17:10 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.89
Max Temp:	11.31
Avg Temp:	11.23
Min Cond:	0.23
Max Cond:	0.24
Avg Cond:	0.24
Min Salinity:	0.15
Max Salinity:	0.15
Avg Salinity:	0.15
Min Sigma-Theta:	-0.30
Max Sigma-Theta:	-0.26
Avg Sigma-Theta:	-0.30
Min Turbidity:	11.03
Max Turbidity:	11.64
Avg Turbidity:	11.34

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E04-T135-P3

3/25/10 17:18 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.43
Max Temp:	10.83
Avg Temp:	10.76
Min Cond:	0.23
Max Cond:	0.23
Avg Cond:	0.23
Min Salinity:	0.15
Max Salinity:	0.15
Avg Salinity:	0.15
Min Sigma-Theta:	-0.25
Max Sigma-Theta:	-0.22
Avg Sigma-Theta:	-0.25
Min Turbidity:	10.89
Max Turbidity:	11.87
Avg Turbidity:	11.47

APPENDIX 8: Trip 5 Real Time Survey Events E06-E08

- Vertically Averaged Current Vector Plots
- CTD-OBS Vertical Profiles

LEGEND FOR CURRENT VELOCITY MAPPINGS:

CURRENT VECTOR SCALE
1" = 150 CM/S

SCALE : 1"=750'
750 0 750

NOTES:

1. GRID SYSTEM IS IN FEET AND IS THE NEW JERSEY STATE PLANE COORDINATE SYSTEM, NAD83.
2. ORTHOPHOTO IMAGERY ARE TRUE COLOR ONE FOOT GROUND SAMPLE DISTANCE IMAGES PRODUCED FROM AERIAL PHOTOS FLOWN IN 2007 AND OBTAINED FROM THE NEW JERSEY GEOGRAPHIC INFORMATION NETWORK (NJGIN).
3. THE INFORMATION PRESENTED ON THESE DRAWINGS REPRESENTS THE RESULTS OF A SURVEY PEFORMED BY OCEAN SURVEYS, INC. ON 3–4 MAY 2010 AND CAN ONLY BE CONSIDERED AS INDICATING THE CONDITIONS EXISTING AT THAT TIME. REUSE OF THIS INFORMATION BY CLIENT OF OTHERS BEYOND THE SCOPE OF WORK FOR WHICH IT WAS ACQUIRED SHALL BE AT THE SOLE RISK OF THE USER AND WITHOUT LIABILITY TO OSI.

OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388-4631
www.oceansurveys.com

Vertically Averaged Current Data
Program 10A, Location Map & Event 06
4 May 2010
Passaic River, New Jersey



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Flood Tide
Program 10A, Event 07
3 May 2010, 12:36 - 15:08 (UTC) Hours
Passaic River, New Jersey



OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388-4631
www.oceansurveys.com

Vertically Averaged Current Data -Ebb Tide
Program 10A, Event 08
3 May 2010, 18:12 - 20:24 (UTC) Hours
Passaic River, New Jersey

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E06-T175-P1

5/04/10 17:10 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.21
Max Temp:	20.26
Avg Temp:	20.24
Min Cond:	0.32
Max Cond:	0.32
Avg Cond:	0.32
Min Salinity:	0.17
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	-1.71
Max Sigma-Theta:	-1.71
Avg Sigma-Theta:	-1.71
Min Turbidity:	11.42
Max Turbidity:	11.84
Avg Turbidity:	11.66

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E06-T175-P2

5/04/10 17:17 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.16
Max Temp:	20.24
Avg Temp:	20.19
Min Cond:	0.32
Max Cond:	0.32
Avg Cond:	0.32
Min Salinity:	0.17
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	-1.71
Max Sigma-Theta:	-1.70
Avg Sigma-Theta:	-1.71
Min Turbidity:	10.36
Max Turbidity:	10.92
Avg Turbidity:	10.66

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E06-T175-P3

5/04/10 17:27 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.24
Max Temp:	20.24
Avg Temp:	20.24
Min Cond:	0.32
Max Cond:	0.32
Avg Cond:	0.32
Min Salinity:	0.17
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	-1.71
Max Sigma-Theta:	-1.71
Avg Sigma-Theta:	-1.71
Min Turbidity:	13.16
Max Turbidity:	13.87
Avg Turbidity:	13.53

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E06-T175-P4

5/04/10 17:33 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.26
Max Temp:	20.26
Avg Temp:	20.26
Min Cond:	0.32
Max Cond:	0.32
Avg Cond:	0.32
Min Salinity:	0.17
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	-1.72
Max Sigma-Theta:	-1.72
Avg Sigma-Theta:	-1.72
Min Turbidity:	9.85
Max Turbidity:	10.44
Avg Turbidity:	10.20

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E07-T014-P1

5/03/10 13:30 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.51
Max Temp:	17.89
Avg Temp:	16.10
Min Cond:	2.68
Max Cond:	16.71
Avg Cond:	11.40
Min Salinity:	1.63
Max Salinity:	12.42
Avg Salinity:	8.15
Min Sigma-Theta:	-0.14
Max Sigma-Theta:	8.67
Avg Sigma-Theta:	5.17
Min Turbidity:	12.31
Max Turbidity:	29.51
Avg Turbidity:	18.09

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E07-T014-P2

5/03/10 13:37 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.28
Max Temp:	17.77
Avg Temp:	15.67
Min Cond:	2.35
Max Cond:	17.18
Avg Cond:	12.82
Min Salinity:	1.42
Max Salinity:	13.03
Avg Salinity:	9.37
Min Sigma-Theta:	-0.27
Max Sigma-Theta:	9.31
Avg Sigma-Theta:	6.18
Min Turbidity:	12.82
Max Turbidity:	46.24
Avg Turbidity:	21.66

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E07-T014-P3

5/03/10 13:42 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.23
Max Temp:	17.86
Avg Temp:	15.77
Min Cond:	2.33
Max Cond:	16.90
Avg Cond:	12.22
Min Salinity:	1.40
Max Salinity:	12.68
Avg Salinity:	8.88
Min Sigma-Theta:	-0.30
Max Sigma-Theta:	8.99
Avg Sigma-Theta:	5.79
Min Turbidity:	11.69
Max Turbidity:	25.34
Avg Turbidity:	17.22

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E07-T042-P1

5/03/10 14:08 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	18.25
Max Temp:	18.49
Avg Temp:	18.37
Min Cond:	0.36
Max Cond:	0.38
Avg Cond:	0.37
Min Salinity:	0.20
Max Salinity:	0.21
Avg Salinity:	0.20
Min Sigma-Theta:	-1.34
Max Sigma-Theta:	-1.29
Avg Sigma-Theta:	-1.31
Min Turbidity:	8.37
Max Turbidity:	10.47
Avg Turbidity:	8.99

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E07-T042-P2

5/03/10 14:15 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	18.31
Max Temp:	18.54
Avg Temp:	18.38
Min Cond:	0.36
Max Cond:	0.37
Avg Cond:	0.37
Min Salinity:	0.20
Max Salinity:	0.21
Avg Salinity:	0.20
Min Sigma-Theta:	-1.35
Max Sigma-Theta:	-1.30
Avg Sigma-Theta:	-1.32
Min Turbidity:	9.06
Max Turbidity:	9.98
Avg Turbidity:	9.44

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E07-T042-P3

5/03/10 14:21 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	18.40
Max Temp:	18.52
Avg Temp:	18.44
Min Cond:	0.36
Max Cond:	0.37
Avg Cond:	0.37
Min Salinity:	0.20
Max Salinity:	0.21
Avg Salinity:	0.20
Min Sigma-Theta:	-1.35
Max Sigma-Theta:	-1.32
Avg Sigma-Theta:	-1.33
Min Turbidity:	8.20
Max Turbidity:	9.33
Avg Turbidity:	8.66

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E07-T067-P1

5/03/10 14:47 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.85
Max Temp:	19.95
Avg Temp:	19.87
Min Cond:	0.25
Max Cond:	0.25
Avg Cond:	0.25
Min Salinity:	0.13
Max Salinity:	0.14
Avg Salinity:	0.14
Min Sigma-Theta:	-1.68
Max Sigma-Theta:	-1.66
Avg Sigma-Theta:	-1.66
Min Turbidity:	35.02
Max Turbidity:	36.87
Avg Turbidity:	35.86

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E07-T067-P2

5/03/10 14:58 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.81
Max Temp:	19.89
Avg Temp:	19.84
Min Cond:	0.25
Max Cond:	0.26
Avg Cond:	0.25
Min Salinity:	0.13
Max Salinity:	0.14
Avg Salinity:	0.14
Min Sigma-Theta:	-1.66
Max Sigma-Theta:	-1.65
Avg Sigma-Theta:	-1.65
Min Turbidity:	36.92
Max Turbidity:	40.04
Avg Turbidity:	38.69

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E07-T067-P3

5/03/10 15:03 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.81
Max Temp:	19.90
Avg Temp:	19.84
Min Cond:	0.26
Max Cond:	0.27
Avg Cond:	0.26
Min Salinity:	0.14
Max Salinity:	0.14
Avg Salinity:	0.14
Min Sigma-Theta:	-1.65
Max Sigma-Theta:	-1.64
Avg Sigma-Theta:	-1.65
Min Turbidity:	30.67
Max Turbidity:	35.49
Avg Turbidity:	32.74

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E07-T102-P1

5/03/10 13:41 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.64
Max Temp:	19.66
Avg Temp:	19.64
Min Cond:	0.30
Max Cond:	0.30
Avg Cond:	0.30
Min Salinity:	0.16
Max Salinity:	0.16
Avg Salinity:	0.16
Min Sigma-Theta:	-1.60
Max Sigma-Theta:	-1.60
Avg Sigma-Theta:	-1.60
Min Turbidity:	28.57
Max Turbidity:	38.14
Avg Turbidity:	34.77

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E07-T102-P2

5/03/10 13:52 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.57
Max Temp:	19.58
Avg Temp:	19.57
Min Cond:	0.31
Max Cond:	0.31
Avg Cond:	0.31
Min Salinity:	0.17
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	-1.58
Max Sigma-Theta:	-1.58
Avg Sigma-Theta:	-1.58
Min Turbidity:	23.05
Max Turbidity:	32.10
Avg Turbidity:	27.72

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E07-T102-P3

5/03/10 13:59 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.55
Max Temp:	19.57
Avg Temp:	19.56
Min Cond:	0.31
Max Cond:	0.32
Avg Cond:	0.32
Min Salinity:	0.17
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	-1.58
Max Sigma-Theta:	-1.57
Avg Sigma-Theta:	-1.57
Min Turbidity:	22.46
Max Turbidity:	29.36
Avg Turbidity:	25.56

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E07-T135-P1

5/03/10 12:36 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.48
Max Temp:	19.50
Avg Temp:	19.49
Min Cond:	0.32
Max Cond:	0.32
Avg Cond:	0.32
Min Salinity:	0.17
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	-1.56
Max Sigma-Theta:	-1.56
Avg Sigma-Theta:	-1.56
Min Turbidity:	26.77
Max Turbidity:	30.87
Avg Turbidity:	30.14

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E07-T135-P2

5/03/10 12:52 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.36
Max Temp:	19.37
Avg Temp:	19.37
Min Cond:	0.33
Max Cond:	0.33
Avg Cond:	0.33
Min Salinity:	0.18
Max Salinity:	0.18
Avg Salinity:	0.18
Min Sigma-Theta:	-1.53
Max Sigma-Theta:	-1.53
Avg Sigma-Theta:	-1.53
Min Turbidity:	25.93
Max Turbidity:	35.78
Avg Turbidity:	32.32

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E07-T135-P3

5/03/10 13:03 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.29
Max Temp:	19.30
Avg Temp:	19.29
Min Cond:	0.35
Max Cond:	0.35
Avg Cond:	0.35
Min Salinity:	0.19
Max Salinity:	0.19
Avg Salinity:	0.19
Min Sigma-Theta:	-1.51
Max Sigma-Theta:	-1.51
Avg Sigma-Theta:	-1.51
Min Turbidity:	22.33
Max Turbidity:	30.80
Avg Turbidity:	27.71

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E08-T014-P1

5/03/10 19:56 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	13.71
Max Temp:	18.56
Avg Temp:	15.59
Min Cond:	2.81
Max Cond:	20.10
Avg Cond:	15.18
Min Salinity:	1.68
Max Salinity:	15.79
Avg Salinity:	11.34
Min Sigma-Theta:	-0.22
Max Sigma-Theta:	11.29
Avg Sigma-Theta:	7.70
Min Turbidity:	14.84
Max Turbidity:	18.43
Avg Turbidity:	16.14

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E08-T014-P2

5/03/10 20:03 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	13.44
Max Temp:	18.63
Avg Temp:	15.70
Min Cond:	2.75
Max Cond:	20.73
Avg Cond:	14.41
Min Salinity:	1.64
Max Salinity:	16.26
Avg Salinity:	10.72
Min Sigma-Theta:	-0.27
Max Sigma-Theta:	11.87
Avg Sigma-Theta:	7.21
Min Turbidity:	12.55
Max Turbidity:	14.24
Avg Turbidity:	13.45

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E08-T014-P3

5/03/10 20:08 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	13.66
Max Temp:	18.63
Avg Temp:	16.06
Min Cond:	3.04
Max Cond:	20.25
Avg Cond:	13.48
Min Salinity:	1.83
Max Salinity:	15.70
Avg Salinity:	9.90
Min Sigma-Theta:	-0.12
Max Sigma-Theta:	11.42
Avg Sigma-Theta:	6.52
Min Turbidity:	12.47
Max Turbidity:	14.50
Avg Turbidity:	13.39

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E08-T042-P1

5/03/10 20:31 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.96
Max Temp:	19.97
Avg Temp:	19.96
Min Cond:	0.32
Max Cond:	0.32
Avg Cond:	0.32
Min Salinity:	0.17
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	-1.66
Max Sigma-Theta:	-1.66
Avg Sigma-Theta:	-1.66
Min Turbidity:	27.02
Max Turbidity:	27.82
Avg Turbidity:	27.45

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E08-T042-P2

5/03/10 20:36 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.96
Max Temp:	19.96
Avg Temp:	19.96
Min Cond:	0.32
Max Cond:	0.32
Avg Cond:	0.32
Min Salinity:	0.17
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	-1.66
Max Sigma-Theta:	-1.65
Avg Sigma-Theta:	-1.65
Min Turbidity:	24.31
Max Turbidity:	28.32
Avg Turbidity:	26.01

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E08-T042-P3

5/03/10 20:41 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.96
Max Temp:	19.96
Avg Temp:	19.96
Min Cond:	0.33
Max Cond:	0.33
Avg Cond:	0.33
Min Salinity:	0.17
Max Salinity:	0.18
Avg Salinity:	0.17
Min Sigma-Theta:	-1.65
Max Sigma-Theta:	-1.65
Avg Sigma-Theta:	-1.65
Min Turbidity:	30.68
Max Turbidity:	43.06
Avg Turbidity:	36.34

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E08-T067-P1

5/03/10 20:03 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.93
Max Temp:	19.95
Avg Temp:	19.94
Min Cond:	0.31
Max Cond:	0.31
Avg Cond:	0.31
Min Salinity:	0.17
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	-1.66
Max Sigma-Theta:	-1.65
Avg Sigma-Theta:	-1.65
Min Turbidity:	24.56
Max Turbidity:	41.84
Avg Turbidity:	34.88

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E08-T067-P2

5/03/10 20:13 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.90
Max Temp:	19.92
Avg Temp:	19.90
Min Cond:	0.31
Max Cond:	0.31
Avg Cond:	0.31
Min Salinity:	0.17
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	-1.65
Max Sigma-Theta:	-1.65
Avg Sigma-Theta:	-1.65
Min Turbidity:	31.53
Max Turbidity:	58.32
Avg Turbidity:	48.32

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E08-T067-P3

5/03/10 20:21 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.97
Max Temp:	19.99
Avg Temp:	19.98
Min Cond:	0.31
Max Cond:	0.31
Avg Cond:	0.31
Min Salinity:	0.17
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	-1.66
Max Sigma-Theta:	-1.66
Avg Sigma-Theta:	-1.66
Min Turbidity:	24.00
Max Turbidity:	24.05
Avg Turbidity:	24.02

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E08-T102-P1

5/03/10 19:00 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.85
Max Temp:	19.86
Avg Temp:	19.85
Min Cond:	0.31
Max Cond:	0.31
Avg Cond:	0.31
Min Salinity:	0.17
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	-1.64
Max Sigma-Theta:	-1.64
Avg Sigma-Theta:	-1.64
Min Turbidity:	15.01
Max Turbidity:	15.75
Avg Turbidity:	15.64

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E08-T102-P2

5/03/10 19:10 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.80
Max Temp:	19.82
Avg Temp:	19.81
Min Cond:	0.31
Max Cond:	0.31
Avg Cond:	0.31
Min Salinity:	0.17
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	-1.63
Max Sigma-Theta:	-1.63
Avg Sigma-Theta:	-1.63
Min Turbidity:	16.04
Max Turbidity:	23.32
Avg Turbidity:	19.43

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E08-T102-P3

5/03/10 19:18 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.85
Max Temp:	19.89
Avg Temp:	19.86
Min Cond:	0.31
Max Cond:	0.31
Avg Cond:	0.31
Min Salinity:	0.17
Max Salinity:	0.17
Avg Salinity:	0.17
Min Sigma-Theta:	-1.64
Max Sigma-Theta:	-1.64
Avg Sigma-Theta:	-1.64
Min Turbidity:	22.43
Max Turbidity:	40.09
Avg Turbidity:	32.51

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E08-T135-P1

5/03/10 18:12 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.00
Max Temp:	20.01
Avg Temp:	20.00
Min Cond:	0.29
Max Cond:	0.29
Avg Cond:	0.29
Min Salinity:	0.16
Max Salinity:	0.16
Avg Salinity:	0.16
Min Sigma-Theta:	-1.68
Max Sigma-Theta:	-1.68
Avg Sigma-Theta:	-1.68
Min Turbidity:	21.19
Max Turbidity:	29.80
Avg Turbidity:	28.00

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E08-T135-P2

5/03/10 18:22 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.01
Max Temp:	20.03
Avg Temp:	20.02
Min Cond:	0.29
Max Cond:	0.29
Avg Cond:	0.29
Min Salinity:	0.16
Max Salinity:	0.16
Avg Salinity:	0.16
Min Sigma-Theta:	-1.68
Max Sigma-Theta:	-1.68
Avg Sigma-Theta:	-1.68
Min Turbidity:	20.68
Max Turbidity:	46.93
Avg Turbidity:	38.88

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E08-T135-P3

5/03/10 18:29 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.04
Max Temp:	20.07
Avg Temp:	20.05
Min Cond:	0.29
Max Cond:	0.29
Avg Cond:	0.29
Min Salinity:	0.16
Max Salinity:	0.16
Avg Salinity:	0.16
Min Sigma-Theta:	-1.69
Max Sigma-Theta:	-1.68
Avg Sigma-Theta:	-1.68
Min Turbidity:	16.33
Max Turbidity:	18.78
Avg Turbidity:	18.31

APPENDIX 9: Trip 6 Real Time Survey Events E11-E13

- Vertically Averaged Current Vector Plots
- CTD-OBS Vertical Profiles

LEGEND FOR CURRENT VELOCITY MAPPINGS:

CURRENT VECTOR SCALE
1" = 150 CM/S

SCALE : 1"=750'
750 0 750

NOTES:

1. GRID SYSTEM IS IN FEET AND IS THE NEW JERSEY STATE PLANE COORDINATE SYSTEM, NAD83.
2. ORTHOPHOTO IMAGERY ARE TRUE COLOR ONE FOOT GROUND SAMPLE DISTANCE IMAGES PRODUCED FROM AERIAL PHOTOS FLOWN IN 2007 AND OBTAINED FROM THE NEW JERSEY GEOGRAPHIC INFORMATION NETWORK (NJGIN).
3. THE INFORMATION PRESENTED ON THESE DRAWINGS REPRESENTS THE RESULTS OF A SURVEY PEFORMED BY OCEAN SURVEYS, INC. ON 14–15 DECEMBER 2009 AND CAN ONLY BE CONSIDERED AS INDICATING THE CONDITIONS EXISTING AT THAT TIME. REUSE OF THIS INFORMATION BY CLIENT OF OTHERS BEYOND THE SCOPE OF WORK FOR WHICH IT WAS ACQUIRED SHALL BE AT THE SOLE RISK OF THE USER AND WITHOUT LIABILITY TO OSI.

OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388-4631
www.oceansurveys.com

Vertically Averaged Current Data
Program 09A, Location Map & Event 11
15 December 2009
Passaic River, New Jersey



OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388-4631
www.oceansurveys.com

Vertically Averaged Current Data - Ebb Tide
Program 10A, Event 12
24 May 2010, 11:14 - 13:18 (UTC) Hours
Passaic River, New Jersey



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Flood Tide
Program 10A, Event 13
24 May 2010, 16:40 - 19:23 (UTC) Hours
Passaic River, New Jersey

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E11-T175-P1

5/25/10 15:40 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.51
Max Temp:	21.86
Avg Temp:	21.69
Min Cond:	0.50
Max Cond:	0.52
Avg Cond:	0.51
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-2.23
Max Sigma-Theta:	-1.92
Avg Sigma-Theta:	-2.07
Min Turbidity:	8.30
Max Turbidity:	8.66
Avg Turbidity:	8.52

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E11-T175-P2

5/25/10 15:42 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.34
Max Temp:	22.20
Avg Temp:	20.93
Min Cond:	0.49
Max Cond:	0.49
Avg Cond:	0.49
Min Salinity:	0.25
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-2.32
Max Sigma-Theta:	-1.67
Avg Sigma-Theta:	-1.82
Min Turbidity:	1.36
Max Turbidity:	4.52
Avg Turbidity:	3.91

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E11-T175-P3

5/25/10 15:48 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.10
Max Temp:	20.46
Avg Temp:	20.29
Min Cond:	0.48
Max Cond:	0.49
Avg Cond:	0.48
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-1.69
Max Sigma-Theta:	-1.62
Avg Sigma-Theta:	-1.65
Min Turbidity:	4.39
Max Turbidity:	4.80
Avg Turbidity:	4.64

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E11-T175-P4

5/25/10 15:51 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.24
Max Temp:	20.51
Avg Temp:	20.41
Min Cond:	0.44
Max Cond:	0.49
Avg Cond:	0.47
Min Salinity:	0.24
Max Salinity:	0.26
Avg Salinity:	0.25
Min Sigma-Theta:	-1.72
Max Sigma-Theta:	-1.65
Avg Sigma-Theta:	-1.69
Min Turbidity:	4.69
Max Turbidity:	10.42
Avg Turbidity:	7.48

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E12-T014-P1

5/24/10 12:39 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.50
Max Temp:	17.74
Avg Temp:	16.46
Min Cond:	11.99
Max Cond:	23.71
Avg Cond:	20.16
Min Salinity:	8.08
Max Salinity:	17.93
Avg Salinity:	14.77
Min Sigma-Theta:	4.81
Max Sigma-Theta:	12.76
Avg Sigma-Theta:	10.16
Min Turbidity:	14.83
Max Turbidity:	25.89
Avg Turbidity:	21.80

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E12-T014-P2

5/24/10 12:49 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.32
Max Temp:	17.81
Avg Temp:	16.54
Min Cond:	11.43
Max Cond:	24.49
Avg Cond:	19.62
Min Salinity:	7.67
Max Salinity:	18.66
Avg Salinity:	14.34
Min Sigma-Theta:	4.48
Max Sigma-Theta:	13.35
Avg Sigma-Theta:	9.82
Min Turbidity:	15.06
Max Turbidity:	20.68
Avg Turbidity:	18.10

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E12-T014-P3

5/24/10 12:59 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.58
Max Temp:	17.93
Avg Temp:	16.91
Min Cond:	10.75
Max Cond:	23.67
Avg Cond:	17.63
Min Salinity:	7.15
Max Salinity:	17.46
Avg Salinity:	12.64
Min Sigma-Theta:	4.07
Max Sigma-Theta:	12.62
Avg Sigma-Theta:	8.46
Min Turbidity:	16.57
Max Turbidity:	25.90
Avg Turbidity:	20.68

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E12-T042-P1

5/24/10 13:32 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	17.27
Max Temp:	19.22
Avg Temp:	18.66
Min Cond:	3.90
Max Cond:	15.56
Avg Cond:	8.02
Min Salinity:	2.34
Max Salinity:	10.85
Avg Salinity:	5.23
Min Sigma-Theta:	0.15
Max Sigma-Theta:	7.01
Avg Sigma-Theta:	2.46
Min Turbidity:	26.27
Max Turbidity:	35.75
Avg Turbidity:	31.61

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E12-T042-P2

5/24/10 13:42 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.72
Max Temp:	19.27
Avg Temp:	18.36
Min Cond:	3.52
Max Cond:	18.97
Avg Cond:	9.81
Min Salinity:	2.10
Max Salinity:	13.84
Avg Salinity:	6.65
Min Sigma-Theta:	-0.06
Max Sigma-Theta:	9.63
Avg Sigma-Theta:	3.60
Min Turbidity:	20.66
Max Turbidity:	37.17
Avg Turbidity:	29.41

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E12-T042-P3

5/24/10 13:51 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	18.57
Max Temp:	19.19
Avg Temp:	19.03
Min Cond:	4.11
Max Cond:	8.28
Avg Cond:	5.23
Min Salinity:	2.48
Max Salinity:	5.32
Avg Salinity:	3.23
Min Sigma-Theta:	0.26
Max Sigma-Theta:	2.55
Avg Sigma-Theta:	0.87
Min Turbidity:	28.24
Max Turbidity:	107.89
Avg Turbidity:	40.70

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E12-T067-P1

5/24/10 13:19 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.59
Max Temp:	19.90
Avg Temp:	19.77
Min Cond:	0.39
Max Cond:	0.48
Avg Cond:	0.47
Min Salinity:	0.22
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-1.58
Max Sigma-Theta:	-1.37
Avg Sigma-Theta:	-1.54
Min Turbidity:	14.80
Max Turbidity:	113.34
Avg Turbidity:	60.07

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E12-T067-P2

5/24/10 13:24 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.74
Max Temp:	19.93
Avg Temp:	19.90
Min Cond:	0.48
Max Cond:	0.48
Avg Cond:	0.48
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-1.58
Max Sigma-Theta:	-1.54
Avg Sigma-Theta:	-1.58
Min Turbidity:	26.21
Max Turbidity:	85.18
Avg Turbidity:	46.51

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E12-T067-P3

5/24/10 13:30 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.89
Max Temp:	19.95
Avg Temp:	19.94
Min Cond:	0.48
Max Cond:	0.48
Avg Cond:	0.48
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-1.59
Max Sigma-Theta:	-1.57
Avg Sigma-Theta:	-1.58
Min Turbidity:	25.22
Max Turbidity:	95.90
Avg Turbidity:	49.60

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E12-T102-P1

5/24/10 12:25 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.46
Max Temp:	19.69
Avg Temp:	19.56
Min Cond:	0.47
Max Cond:	0.48
Avg Cond:	0.48
Min Salinity:	0.24
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-1.53
Max Sigma-Theta:	-1.28
Avg Sigma-Theta:	-1.49
Min Turbidity:	5.21
Max Turbidity:	10.52
Avg Turbidity:	7.69

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E12-T102-P2

5/24/10 12:33 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.16
Max Temp:	19.74
Avg Temp:	19.66
Min Cond:	0.39
Max Cond:	0.48
Avg Cond:	0.47
Min Salinity:	0.21
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-1.54
Max Sigma-Theta:	-1.46
Avg Sigma-Theta:	-1.53
Min Turbidity:	6.56
Max Turbidity:	11.88
Avg Turbidity:	8.56

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E12-T102-P3

5/24/10 12:40 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.16
Max Temp:	19.74
Avg Temp:	19.66
Min Cond:	0.38
Max Cond:	0.48
Avg Cond:	0.47
Min Salinity:	0.21
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-1.54
Max Sigma-Theta:	-1.46
Avg Sigma-Theta:	-1.53
Min Turbidity:	6.56
Max Turbidity:	11.88
Avg Turbidity:	8.56

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E12-T135-P1

5/24/10 11:24 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.04
Max Temp:	20.67
Avg Temp:	20.17
Min Cond:	0.40
Max Cond:	0.49
Avg Cond:	0.47
Min Salinity:	0.22
Max Salinity:	0.26
Avg Salinity:	0.25
Min Sigma-Theta:	-1.62
Max Sigma-Theta:	-1.32
Avg Sigma-Theta:	-1.56
Min Turbidity:	5.50
Max Turbidity:	7.73
Avg Turbidity:	6.10

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E12-T135-P2

5/24/10 11:32 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	19.86
Max Temp:	20.17
Avg Temp:	20.11
Min Cond:	0.38
Max Cond:	0.49
Avg Cond:	0.48
Min Salinity:	0.20
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-1.63
Max Sigma-Theta:	-1.60
Avg Sigma-Theta:	-1.62
Min Turbidity:	5.53
Max Turbidity:	8.81
Avg Turbidity:	6.62

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E12-T135-P3

5/24/10 11:39 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.08
Max Temp:	20.17
Avg Temp:	20.15
Min Cond:	0.48
Max Cond:	0.49
Avg Cond:	0.49
Min Salinity:	0.22
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-1.64
Max Sigma-Theta:	-1.62
Avg Sigma-Theta:	-1.63
Min Turbidity:	6.24
Max Turbidity:	7.62
Avg Turbidity:	6.81

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E13-T014-P1

5/24/10 18:58 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.12
Max Temp:	19.73
Avg Temp:	17.52
Min Cond:	7.56
Max Cond:	22.26
Avg Cond:	13.24
Min Salinity:	4.69
Max Salinity:	16.46
Avg Salinity:	9.31
Min Sigma-Theta:	1.83
Max Sigma-Theta:	11.52
Avg Sigma-Theta:	5.79
Min Turbidity:	14.31
Max Turbidity:	124.60
Avg Turbidity:	70.01

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E13-T014-P2

5/24/10 19:07 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.21
Max Temp:	18.70
Avg Temp:	17.07
Min Cond:	9.65
Max Cond:	22.29
Avg Cond:	19.43
Min Salinity:	5.49
Max Salinity:	16.46
Avg Salinity:	13.95
Min Sigma-Theta:	2.54
Max Sigma-Theta:	11.50
Avg Sigma-Theta:	9.41
Min Turbidity:	15.19
Max Turbidity:	69.51
Avg Turbidity:	38.78

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E13-T014-P3

5/24/10 19:14 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	16.31
Max Temp:	18.79
Avg Temp:	16.97
Min Cond:	11.02
Max Cond:	21.97
Avg Cond:	19.34
Min Salinity:	7.37
Max Salinity:	16.17
Avg Salinity:	14.29
Min Sigma-Theta:	4.01
Max Sigma-Theta:	11.26
Avg Sigma-Theta:	9.69
Min Turbidity:	15.36
Max Turbidity:	81.00
Avg Turbidity:	43.34

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E13-T042-P1

5/24/10 19:43 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	17.46
Max Temp:	19.58
Avg Temp:	18.56
Min Cond:	5.96
Max Cond:	14.67
Avg Cond:	10.46
Min Salinity:	3.66
Max Salinity:	10.13
Avg Salinity:	6.94
Min Sigma-Theta:	1.08
Max Sigma-Theta:	6.43
Avg Sigma-Theta:	3.78
Min Turbidity:	21.91
Max Turbidity:	104.60
Avg Turbidity:	60.14

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E13-T042-P2

5/24/10 19:51 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	17.56
Max Temp:	19.56
Avg Temp:	18.45
Min Cond:	6.39
Max Cond:	14.28
Avg Cond:	10.96
Min Salinity:	3.94
Max Salinity:	9.81
Avg Salinity:	7.28
Min Sigma-Theta:	1.29
Max Sigma-Theta:	6.17
Avg Sigma-Theta:	4.06
Min Turbidity:	21.70
Max Turbidity:	104.62
Avg Turbidity:	65.27

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E13-T042-P3

5/24/10 19:58 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	17.61
Max Temp:	19.45
Avg Temp:	18.32
Min Cond:	6.40
Max Cond:	14.07
Avg Cond:	11.44
Min Salinity:	3.95
Max Salinity:	9.64
Avg Salinity:	7.65
Min Sigma-Theta:	1.33
Max Sigma-Theta:	6.02
Avg Sigma-Theta:	4.37
Min Turbidity:	28.80
Max Turbidity:	114.58
Avg Turbidity:	65.61

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E13-T067-P1

5/24/10 19:30 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.17
Max Temp:	20.40
Avg Temp:	20.28
Min Cond:	0.50
Max Cond:	0.51
Avg Cond:	0.50
Min Salinity:	0.27
Max Salinity:	0.27
Avg Salinity:	0.27
Min Sigma-Theta:	-1.67
Max Sigma-Theta:	-1.62
Avg Sigma-Theta:	-1.65
Min Turbidity:	61.08
Max Turbidity:	87.75
Avg Turbidity:	72.90

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E13-T067-P2

5/24/10 19:36 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.15
Max Temp:	20.22
Avg Temp:	20.20
Min Cond:	0.51
Max Cond:	0.52
Avg Cond:	0.52
Min Salinity:	0.27
Max Salinity:	0.28
Avg Salinity:	0.28
Min Sigma-Theta:	-1.63
Max Sigma-Theta:	-1.62
Avg Sigma-Theta:	-1.63
Min Turbidity:	65.56
Max Turbidity:	79.14
Avg Turbidity:	70.61

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E13-T067-P3

5/24/10 19:40 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.22
Max Temp:	20.26
Avg Temp:	20.24
Min Cond:	0.53
Max Cond:	0.53
Avg Cond:	0.53
Min Salinity:	0.29
Max Salinity:	0.29
Avg Salinity:	0.29
Min Sigma-Theta:	-1.63
Max Sigma-Theta:	-1.62
Avg Sigma-Theta:	-1.63
Min Turbidity:	28.56
Max Turbidity:	115.88
Avg Turbidity:	73.34

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E13-T102-P1

5/24/10 18:41 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.95
Max Temp:	21.03
Avg Temp:	21.01
Min Cond:	0.50
Max Cond:	0.51
Avg Cond:	0.50
Min Salinity:	0.27
Max Salinity:	0.27
Avg Salinity:	0.27
Min Sigma-Theta:	-1.81
Max Sigma-Theta:	-1.79
Avg Sigma-Theta:	-1.80
Min Turbidity:	6.39
Max Turbidity:	7.54
Avg Turbidity:	6.82

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E13-T102-P2

5/24/10 18:50 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.67
Max Temp:	20.82
Avg Temp:	20.75
Min Cond:	0.50
Max Cond:	0.50
Avg Cond:	0.50
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-1.77
Max Sigma-Theta:	-1.73
Avg Sigma-Theta:	-1.75
Min Turbidity:	6.56
Max Turbidity:	11.34
Avg Turbidity:	8.08

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E13-T102-P3

5/24/10 18:53 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.59
Max Temp:	20.64
Avg Temp:	20.62
Min Cond:	0.50
Max Cond:	0.50
Avg Cond:	0.50
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-1.73
Max Sigma-Theta:	-1.72
Avg Sigma-Theta:	-1.72
Min Turbidity:	7.54
Max Turbidity:	11.39
Avg Turbidity:	8.91

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E13-T135-P1

5/24/10 17:57 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.23
Max Temp:	20.86
Avg Temp:	20.48
Min Cond:	0.36
Max Cond:	0.51
Avg Cond:	0.49
Min Salinity:	0.18
Max Salinity:	0.27
Avg Salinity:	0.26
Min Sigma-Theta:	-2.26
Max Sigma-Theta:	-1.63
Avg Sigma-Theta:	-1.75
Min Turbidity:	3.27
Max Turbidity:	5.91
Avg Turbidity:	5.22

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E13-T135-P2

5/24/10 18:05 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.03
Max Temp:	20.14
Avg Temp:	20.09
Min Cond:	0.36
Max Cond:	0.50
Avg Cond:	0.48
Min Salinity:	0.19
Max Salinity:	0.27
Avg Salinity:	0.26
Min Sigma-Theta:	-1.68
Max Sigma-Theta:	-1.60
Avg Sigma-Theta:	-1.62
Min Turbidity:	4.70
Max Turbidity:	6.61
Avg Turbidity:	5.60

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E13-T135-P3

5/24/10 18:09 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.07
Max Temp:	20.22
Avg Temp:	20.15
Min Cond:	0.34
Max Cond:	0.50
Avg Cond:	0.48
Min Salinity:	0.18
Max Salinity:	0.27
Avg Salinity:	0.26
Min Sigma-Theta:	-1.68
Max Sigma-Theta:	-1.60
Avg Sigma-Theta:	-1.63
Min Turbidity:	2.64
Max Turbidity:	6.36
Avg Turbidity:	5.52

APPENDIX 10: Trip 7 Real Time Survey Events E16-E18

- Vertically Averaged Current Vector Plots
- CTD-OBS Vertical Profiles

LEGEND FOR CURRENT VELOCITY MAPPINGS:

CURRENT VECTOR SCALE
1" = 150 CM/S

SCALE : 1"=750'
750 0 750

NOTES:

1. GRID SYSTEM IS IN FEET AND IS THE NEW JERSEY STATE PLANE COORDINATE SYSTEM, NAD83.
2. ORTHOPHOTO IMAGERY ARE TRUE COLOR ONE FOOT GROUND SAMPLE DISTANCE IMAGES PRODUCED FROM AERIAL PHOTOS FLOWN IN 2007 AND OBTAINED FROM THE NEW JERSEY GEOGRAPHIC INFORMATION NETWORK (NJGIN).
3. THE INFORMATION PRESENTED ON THESE DRAWINGS REPRESENTS THE RESULTS OF A SURVEY PEFORMED BY OCEAN SURVEYS, INC. ON 21–22 JUNE 2010 AND CAN ONLY BE CONSIDERED AS INDICATING THE CONDITIONS EXISTING AT THAT TIME. REUSE OF THIS INFORMATION BY CLIENT OF OTHERS BEYOND THE SCOPE OF WORK FOR WHICH IT WAS ACQUIRED SHALL BE AT THE SOLE RISK OF THE USER AND WITHOUT LIABILITY TO OSI.

OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388-4631
www.oceansurveys.com

Vertically Averaged Current Data
Program 10A, Location Map & Event 16
21 June 2010
Passaic River, New Jersey



OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388-4631
www.oceansurveys.com

Vertically Averaged Current Data - Ebb Tide
Program 10A, Event 17
22 June 2010, 11:07 - 12:59 (UTC) Hours
Passaic River, New Jersey



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Flood Tide
Program 10A, Event 18
22 June 2010, 17:37 - 20:20 (UTC) Hours
Passaic River, New Jersey

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E16-T175-P1

6/21/10 20:16 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.21
Max Temp:	27.29
Avg Temp:	26.83
Min Cond:	0.67
Max Cond:	0.67
Avg Cond:	0.67
Min Salinity:	0.31
Max Salinity:	0.31
Avg Salinity:	0.31
Min Sigma-Theta:	-3.62
Max Sigma-Theta:	-3.62
Avg Sigma-Theta:	-3.62
Min Turbidity:	10.08
Max Turbidity:	10.57
Avg Turbidity:	10.32

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E16-T175-P2

6/21/10 20:20 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.57
Max Temp:	27.20
Avg Temp:	26.69
Min Cond:	0.63
Max Cond:	0.64
Avg Cond:	0.64
Min Salinity:	0.30
Max Salinity:	0.30
Avg Salinity:	0.30
Min Sigma-Theta:	-3.32
Max Sigma-Theta:	-2.08
Avg Sigma-Theta:	-3.06
Min Turbidity:	10.05
Max Turbidity:	13.62
Avg Turbidity:	11.74

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E16-T175-P3

6/21/10 20:26 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.88
Max Temp:	26.93
Avg Temp:	26.90
Min Cond:	0.64
Max Cond:	0.64
Avg Cond:	0.64
Min Salinity:	0.30
Max Salinity:	0.30
Avg Salinity:	0.30
Min Sigma-Theta:	-3.26
Max Sigma-Theta:	-3.23
Avg Sigma-Theta:	-3.25
Min Turbidity:	9.14
Max Turbidity:	10.79
Avg Turbidity:	9.78

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E16-T175-P4

6/21/10 20:30 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.84
Max Temp:	27.08
Avg Temp:	26.99
Min Cond:	0.57
Max Cond:	0.65
Avg Cond:	0.62
Min Salinity:	0.29
Max Salinity:	0.30
Avg Salinity:	0.29
Min Sigma-Theta:	-3.28
Max Sigma-Theta:	-3.26
Avg Sigma-Theta:	-3.27
Min Turbidity:	10.06
Max Turbidity:	10.92
Avg Turbidity:	10.49

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E17-T014-P1

6/22/10 12:21 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	22.48
Max Temp:	23.54
Avg Temp:	23.05
Min Cond:	22.46
Max Cond:	30.93
Avg Cond:	27.64
Min Salinity:	14.38
Max Salinity:	20.36
Avg Salinity:	17.79
Min Sigma-Theta:	8.11
Max Sigma-Theta:	12.94
Avg Sigma-Theta:	10.90
Min Turbidity:	8.92
Max Turbidity:	11.29
Avg Turbidity:	9.97

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E17-T014-P2

6/22/10 12:29 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	22.27
Max Temp:	23.56
Avg Temp:	23.04
Min Cond:	22.58
Max Cond:	31.46
Avg Cond:	27.88
Min Salinity:	14.74
Max Salinity:	20.79
Avg Salinity:	18.00
Min Sigma-Theta:	8.75
Max Sigma-Theta:	13.39
Avg Sigma-Theta:	11.13
Min Turbidity:	7.80
Max Turbidity:	9.40
Avg Turbidity:	8.48

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E17-T014-P3

6/22/10 12:36 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	22.42
Max Temp:	23.45
Avg Temp:	23.04
Min Cond:	21.01
Max Cond:	31.13
Avg Cond:	27.51
Min Salinity:	13.70
Max Salinity:	20.52
Avg Salinity:	17.75
Min Sigma-Theta:	7.70
Max Sigma-Theta:	13.12
Avg Sigma-Theta:	10.89
Min Turbidity:	7.73
Max Turbidity:	9.85
Avg Turbidity:	8.69

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E17-T042-P1

6/22/10 13:06 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	23.31
Max Temp:	24.19
Avg Temp:	23.87
Min Cond:	12.21
Max Cond:	24.55
Avg Cond:	17.62
Min Salinity:	7.73
Max Salinity:	15.25
Avg Salinity:	10.77
Min Sigma-Theta:	3.11
Max Sigma-Theta:	8.92
Avg Sigma-Theta:	5.44
Min Turbidity:	11.55
Max Turbidity:	15.19
Avg Turbidity:	14.07

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E17-T042-P2

6/22/10 13:12 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	23.15
Max Temp:	24.17
Avg Temp:	23.76
Min Cond:	12.24
Max Cond:	25.94
Avg Cond:	18.82
Min Salinity:	7.18
Max Salinity:	16.48
Avg Salinity:	11.54
Min Sigma-Theta:	2.67
Max Sigma-Theta:	9.91
Avg Sigma-Theta:	6.04
Min Turbidity:	11.44
Max Turbidity:	15.48
Avg Turbidity:	14.12

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E17-T042-P3

6/22/10 13:17 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	23.39
Max Temp:	24.26
Avg Temp:	23.96
Min Cond:	11.57
Max Cond:	22.75
Avg Cond:	16.02
Min Salinity:	6.85
Max Salinity:	14.21
Avg Salinity:	9.64
Min Sigma-Theta:	2.39
Max Sigma-Theta:	8.14
Avg Sigma-Theta:	4.56
Min Turbidity:	13.23
Max Turbidity:	17.58
Avg Turbidity:	15.35

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E17-T067-P1

6/22/10 12:34 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.36
Max Temp:	24.58
Avg Temp:	24.50
Min Cond:	5.51
Max Cond:	8.88
Avg Cond:	6.84
Min Salinity:	3.06
Max Salinity:	4.94
Avg Salinity:	3.79
Min Sigma-Theta:	-0.54
Max Sigma-Theta:	0.93
Avg Sigma-Theta:	0.03
Min Turbidity:	19.23
Max Turbidity:	35.83
Avg Turbidity:	27.28

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E17-T067-P2

6/22/10 12:39 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.29
Max Temp:	24.54
Avg Temp:	24.44
Min Cond:	5.38
Max Cond:	9.65
Avg Cond:	6.93
Min Salinity:	2.94
Max Salinity:	5.39
Avg Salinity:	3.85
Min Sigma-Theta:	-0.61
Max Sigma-Theta:	1.27
Avg Sigma-Theta:	0.09
Min Turbidity:	20.63
Max Turbidity:	35.30
Avg Turbidity:	27.52

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E17-T067-P3

6/22/10 12:44 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.32
Max Temp:	24.60
Avg Temp:	24.44
Min Cond:	5.21
Max Cond:	9.38
Avg Cond:	6.43
Min Salinity:	2.85
Max Salinity:	3.85
Avg Salinity:	3.25
Min Sigma-Theta:	-0.70
Max Sigma-Theta:	0.57
Avg Sigma-Theta:	-0.25
Min Turbidity:	18.72
Max Turbidity:	35.43
Avg Turbidity:	29.50

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E17-T102-P1

6/22/10 11:52 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.42
Max Temp:	25.25
Avg Temp:	25.17
Min Cond:	0.66
Max Cond:	0.66
Avg Cond:	0.66
Min Salinity:	0.32
Max Salinity:	0.32
Avg Salinity:	0.32
Min Sigma-Theta:	-2.78
Max Sigma-Theta:	-2.56
Avg Sigma-Theta:	-2.76
Min Turbidity:	16.79
Max Turbidity:	36.68
Avg Turbidity:	29.34

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E17-T102-P2

6/22/10 11:58 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.94
Max Temp:	25.27
Avg Temp:	25.22
Min Cond:	0.57
Max Cond:	0.66
Avg Cond:	0.65
Min Salinity:	0.31
Max Salinity:	0.32
Avg Salinity:	0.32
Min Sigma-Theta:	-2.78
Max Sigma-Theta:	-2.74
Avg Sigma-Theta:	-2.77
Min Turbidity:	17.59
Max Turbidity:	32.28
Avg Turbidity:	28.96

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E17-T102-P3

6/22/10 12:04 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.98
Max Temp:	25.25
Avg Temp:	25.22
Min Cond:	0.57
Max Cond:	0.66
Avg Cond:	0.65
Min Salinity:	0.31
Max Salinity:	0.32
Avg Salinity:	0.32
Min Sigma-Theta:	-2.78
Max Sigma-Theta:	-2.77
Avg Sigma-Theta:	-2.77
Min Turbidity:	17.90
Max Turbidity:	34.42
Avg Turbidity:	32.36

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E17-T135-P1

6/22/10 11:14 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.11
Max Temp:	25.40
Avg Temp:	25.34
Min Cond:	0.67
Max Cond:	0.68
Avg Cond:	0.68
Min Salinity:	0.33
Max Salinity:	0.33
Avg Salinity:	0.33
Min Sigma-Theta:	-2.81
Max Sigma-Theta:	-2.71
Avg Sigma-Theta:	-2.80
Min Turbidity:	13.06
Max Turbidity:	25.45
Avg Turbidity:	18.15

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E17-T135-P2

6/22/10 11:20 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.27
Max Temp:	25.43
Avg Temp:	25.32
Min Cond:	0.60
Max Cond:	0.68
Avg Cond:	0.67
Min Salinity:	0.29
Max Salinity:	0.33
Avg Salinity:	0.33
Min Sigma-Theta:	-2.82
Max Sigma-Theta:	-2.62
Avg Sigma-Theta:	-2.80
Min Turbidity:	13.25
Max Turbidity:	24.01
Avg Turbidity:	17.73

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E17-T135-P3

6/22/10 11:25 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.41
Max Temp:	25.47
Avg Temp:	25.43
Min Cond:	0.67
Max Cond:	0.68
Avg Cond:	0.68
Min Salinity:	0.33
Max Salinity:	0.33
Avg Salinity:	0.33
Min Sigma-Theta:	-2.83
Max Sigma-Theta:	-2.81
Avg Sigma-Theta:	-2.82
Min Turbidity:	14.09
Max Turbidity:	21.54
Avg Turbidity:	17.36

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E18-T014-P1

6/22/10 20:26 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	22.48
Max Temp:	23.71
Avg Temp:	23.24
Min Cond:	29.03
Max Cond:	31.20
Avg Cond:	29.97
Min Salinity:	18.28
Max Salinity:	20.51
Avg Salinity:	19.28
Min Sigma-Theta:	11.03
Max Sigma-Theta:	13.12
Avg Sigma-Theta:	11.99
Min Turbidity:	7.37
Max Turbidity:	20.01
Avg Turbidity:	12.03

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E18-T014-P2

6/22/10 20:31 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	22.53
Max Temp:	23.76
Avg Temp:	23.21
Min Cond:	27.88
Max Cond:	31.18
Avg Cond:	29.98
Min Salinity:	18.30
Max Salinity:	20.47
Avg Salinity:	19.34
Min Sigma-Theta:	11.03
Max Sigma-Theta:	13.08
Avg Sigma-Theta:	12.04
Min Turbidity:	6.39
Max Turbidity:	16.97
Avg Turbidity:	9.74

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E18-T014-P3

6/22/10 20:34 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	23.19
Max Temp:	23.72
Avg Temp:	23.50
Min Cond:	29.28
Max Cond:	29.59
Avg Cond:	29.39
Min Salinity:	18.63
Max Salinity:	19.04
Avg Salinity:	18.76
Min Sigma-Theta:	11.42
Max Sigma-Theta:	11.83
Avg Sigma-Theta:	11.54
Min Turbidity:	6.45
Max Turbidity:	12.52
Avg Turbidity:	9.16

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E18-T042-P1

6/22/10 19:53 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	23.74
Max Temp:	24.70
Avg Temp:	24.26
Min Cond:	18.25
Max Cond:	22.64
Avg Cond:	20.53
Min Salinity:	10.94
Max Salinity:	14.03
Avg Salinity:	12.50
Min Sigma-Theta:	5.34
Max Sigma-Theta:	7.93
Avg Sigma-Theta:	6.63
Min Turbidity:	16.00
Max Turbidity:	73.05
Avg Turbidity:	38.43

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E18-T042-P2

6/22/10 19:58 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	23.74
Max Temp:	24.76
Avg Temp:	24.39
Min Cond:	16.69
Max Cond:	22.77
Avg Cond:	18.73
Min Salinity:	9.61
Max Salinity:	13.98
Avg Salinity:	11.24
Min Sigma-Theta:	4.54
Max Sigma-Theta:	7.87
Avg Sigma-Theta:	5.65
Min Turbidity:	16.53
Max Turbidity:	53.65
Avg Turbidity:	32.42

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E18-T042-P3

6/22/10 20:02 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.23
Max Temp:	24.66
Avg Temp:	24.53
Min Cond:	16.11
Max Cond:	18.15
Avg Cond:	17.48
Min Salinity:	9.51
Max Salinity:	10.91
Avg Salinity:	10.41
Min Sigma-Theta:	4.30
Max Sigma-Theta:	5.47
Avg Sigma-Theta:	4.99
Min Turbidity:	14.37
Max Turbidity:	52.05
Avg Turbidity:	24.40

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E18-T067-P1

6/22/10 19:10 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.02
Max Temp:	25.18
Avg Temp:	25.07
Min Cond:	6.84
Max Cond:	6.91
Avg Cond:	6.86
Min Salinity:	3.74
Max Salinity:	3.78
Avg Salinity:	3.75
Min Sigma-Theta:	-0.15
Max Sigma-Theta:	-0.12
Avg Sigma-Theta:	-0.13
Min Turbidity:	68.14
Max Turbidity:	104.60
Avg Turbidity:	82.47

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E18-T067-P2

6/22/10 19:15 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.57
Max Temp:	25.18
Avg Temp:	24.98
Min Cond:	6.85
Max Cond:	7.30
Avg Cond:	7.09
Min Salinity:	3.74
Max Salinity:	4.02
Avg Salinity:	3.89
Min Sigma-Theta:	-0.18
Max Sigma-Theta:	0.07
Avg Sigma-Theta:	-0.02
Min Turbidity:	46.09
Max Turbidity:	75.64
Avg Turbidity:	58.37

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E18-T067-P3

6/22/10 19:20 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.35
Max Temp:	25.00
Avg Temp:	24.91
Min Cond:	6.05
Max Cond:	7.66
Avg Cond:	7.20
Min Salinity:	3.33
Max Salinity:	4.24
Avg Salinity:	3.97
Min Sigma-Theta:	-0.28
Max Sigma-Theta:	0.26
Avg Sigma-Theta:	0.06
Min Turbidity:	51.91
Max Turbidity:	93.27
Avg Turbidity:	63.86

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E18-T102-P1

6/22/10 18:23 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.81
Max Temp:	26.38
Avg Temp:	26.14
Min Cond:	0.67
Max Cond:	0.68
Avg Cond:	0.67
Min Salinity:	0.32
Max Salinity:	0.32
Avg Salinity:	0.32
Min Sigma-Theta:	-3.08
Max Sigma-Theta:	-2.95
Avg Sigma-Theta:	-3.01
Min Turbidity:	40.25
Max Turbidity:	101.95
Avg Turbidity:	64.27

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E18-T102-P2

6/22/10 18:30 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.72
Max Temp:	25.99
Avg Temp:	25.90
Min Cond:	0.61
Max Cond:	0.67
Avg Cond:	0.66
Min Salinity:	0.32
Max Salinity:	0.32
Avg Salinity:	0.32
Min Sigma-Theta:	-2.97
Max Sigma-Theta:	-2.90
Avg Sigma-Theta:	-2.95
Min Turbidity:	15.84
Max Turbidity:	95.03
Avg Turbidity:	53.39

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E18-T102-P3

6/22/10 18:34 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.74
Max Temp:	26.06
Avg Temp:	25.91
Min Cond:	0.57
Max Cond:	0.68
Avg Cond:	0.66
Min Salinity:	0.27
Max Salinity:	0.32
Avg Salinity:	0.32
Min Sigma-Theta:	-2.99
Max Sigma-Theta:	-2.90
Avg Sigma-Theta:	-2.95
Min Turbidity:	17.44
Max Turbidity:	74.57
Avg Turbidity:	47.46

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E18-T135-P1

6/22/10 17:42 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.09
Max Temp:	27.16
Avg Temp:	26.62
Min Cond:	0.70
Max Cond:	0.72
Avg Cond:	0.71
Min Salinity:	0.33
Max Salinity:	0.34
Avg Salinity:	0.34
Min Sigma-Theta:	-3.25
Max Sigma-Theta:	-2.98
Avg Sigma-Theta:	-3.12
Min Turbidity:	11.54
Max Turbidity:	17.43
Avg Turbidity:	14.21

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E18-T135-P2

6/22/10 17:48 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.16
Max Temp:	26.62
Avg Temp:	26.34
Min Cond:	0.57
Max Cond:	0.69
Avg Cond:	0.67
Min Salinity:	0.31
Max Salinity:	0.33
Avg Salinity:	0.32
Min Sigma-Theta:	-3.14
Max Sigma-Theta:	-3.01
Avg Sigma-Theta:	-3.06
Min Turbidity:	11.95
Max Turbidity:	15.99
Avg Turbidity:	13.31

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E18-T135-P3

6/22/10 17:52 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.63
Max Temp:	26.89
Avg Temp:	26.18
Min Cond:	0.68
Max Cond:	0.69
Avg Cond:	0.69
Min Salinity:	0.32
Max Salinity:	0.33
Avg Salinity:	0.33
Min Sigma-Theta:	-3.21
Max Sigma-Theta:	-2.86
Avg Sigma-Theta:	-3.02
Min Turbidity:	11.75
Max Turbidity:	17.61
Avg Turbidity:	14.74

APPENDIX 11: Trip 8 Real Time Survey Events E20-E22

- Vertically Averaged Current Vector Plots
- CTD-OBS Vertical Profiles

LEGEND FOR CURRENT VELOCITY MAPPINGS:

CURRENT VECTOR SCALE
1" = 150 CM/S

SCALE : 1"=750'
750 0 750

NOTES:

1. GRID SYSTEM IS IN FEET AND IS THE NEW JERSEY STATE PLANE COORDINATE SYSTEM, NAD83.
2. ORTHOPHOTO IMAGERY ARE TRUE COLOR ONE FOOT GROUND SAMPLE DISTANCE IMAGES PRODUCED FROM AERIAL PHOTOS FLOWN IN 2007 AND OBTAINED FROM THE NEW JERSEY GEOGRAPHIC INFORMATION NETWORK (NJGIN).
3. THE INFORMATION PRESENTED ON THESE DRAWINGS REPRESENTS THE RESULTS OF A SURVEY PEFORMED BY OCEAN SURVEYS, INC. ON 21–22 JULY 2010 AND CAN ONLY BE CONSIDERED AS INDICATING THE CONDITIONS EXISTING AT THAT TIME. REUSE OF THIS INFORMATION BY CLIENT OF OTHERS BEYOND THE SCOPE OF WORK FOR WHICH IT WAS ACQUIRED SHALL BE AT THE SOLE RISK OF THE USER AND WITHOUT LIABILITY TO OSI.

OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388-4631
www.oceansurveys.com

Vertically Averaged Current Data
Program 10A, Location Map & Event 20
22 July 2010
Passaic River, New Jersey



OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388-4631
www.oceansurveys.com

Vertically Averaged Current Data - Ebb Tide
Program 10A, Event 21
21 July 2010, 10:57 - 12:40 (UTC) Hours
Passaic River, New Jersey



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Flood Tide
Program 10A, Event 22
21 July 2010, 17:32 - 18:59 (UTC) Hours
Passaic River, New Jersey

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E20-T175-P1

7/22/10 13:52 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.30
Max Temp:	27.82
Avg Temp:	27.57
Min Cond:	0.51
Max Cond:	0.52
Avg Cond:	0.52
Min Salinity:	0.23
Max Salinity:	0.23
Avg Salinity:	0.23
Min Sigma-Theta:	-3.32
Max Sigma-Theta:	-3.32
Avg Sigma-Theta:	-3.32
Min Turbidity:	6.33
Max Turbidity:	7.44
Avg Turbidity:	6.86

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E20-T175-P2

7/22/10 13:54 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.39
Max Temp:	27.37
Avg Temp:	27.06
Min Cond:	0.51
Max Cond:	0.53
Avg Cond:	0.51
Min Salinity:	0.23
Max Salinity:	0.25
Avg Salinity:	0.24
Min Sigma-Theta:	-3.42
Max Sigma-Theta:	-3.13
Avg Sigma-Theta:	-3.33
Min Turbidity:	9.03
Max Turbidity:	15.08
Avg Turbidity:	11.80

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E20-T175-P3

7/22/10 14:02 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.24
Max Temp:	27.42
Avg Temp:	27.37
Min Cond:	0.50
Max Cond:	0.51
Avg Cond:	0.51
Min Salinity:	0.23
Max Salinity:	0.23
Avg Salinity:	0.23
Min Sigma-Theta:	-3.43
Max Sigma-Theta:	-3.41
Avg Sigma-Theta:	-3.42
Min Turbidity:	8.12
Max Turbidity:	8.47
Avg Turbidity:	8.28

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E20-T175-P4

7/22/10 14:06 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.43
Max Temp:	27.46
Avg Temp:	27.45
Min Cond:	0.51
Max Cond:	0.51
Avg Cond:	0.51
Min Salinity:	0.23
Max Salinity:	0.23
Avg Salinity:	0.23
Min Sigma-Theta:	-3.43
Max Sigma-Theta:	-3.42
Avg Sigma-Theta:	-3.43
Min Turbidity:	8.57
Max Turbidity:	10.70
Avg Turbidity:	9.20

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E21-T014-P1

7/21/10 12:04 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.43
Max Temp:	27.24
Avg Temp:	27.02
Min Cond:	18.40
Max Cond:	34.32
Avg Cond:	30.13
Min Salinity:	10.55
Max Salinity:	20.73
Avg Salinity:	17.90
Min Sigma-Theta:	4.57
Max Sigma-Theta:	12.08
Avg Sigma-Theta:	9.89
Min Turbidity:	12.45
Max Turbidity:	29.26
Avg Turbidity:	14.82

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E21-T014-P2

7/21/10 12:11 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.80
Max Temp:	27.32
Avg Temp:	27.11
Min Cond:	16.49
Max Cond:	34.29
Avg Cond:	29.49
Min Salinity:	9.29
Max Salinity:	20.63
Avg Salinity:	17.45
Min Sigma-Theta:	3.52
Max Sigma-Theta:	11.98
Avg Sigma-Theta:	9.52
Min Turbidity:	11.37
Max Turbidity:	16.32
Avg Turbidity:	12.37

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E21-T014-P3

7/21/10 12:16 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.84
Max Temp:	27.19
Avg Temp:	27.06
Min Cond:	18.80
Max Cond:	34.09
Avg Cond:	29.69
Min Salinity:	10.69
Max Salinity:	20.48
Avg Salinity:	17.59
Min Sigma-Theta:	4.53
Max Sigma-Theta:	11.86
Avg Sigma-Theta:	9.65
Min Turbidity:	10.88
Max Turbidity:	13.91
Avg Turbidity:	12.62

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E21-T042-P1

7/21/10 12:41 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.99
Max Temp:	27.55
Avg Temp:	27.22
Min Cond:	11.15
Max Cond:	27.97
Avg Cond:	19.95
Min Salinity:	6.06
Max Salinity:	16.47
Avg Salinity:	11.39
Min Sigma-Theta:	1.05
Max Sigma-Theta:	8.83
Avg Sigma-Theta:	4.97
Min Turbidity:	16.94
Max Turbidity:	21.59
Avg Turbidity:	19.21

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E21-T042-P2

7/21/10 12:45 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.91
Max Temp:	27.39
Avg Temp:	27.19
Min Cond:	10.17
Max Cond:	29.58
Avg Cond:	21.63
Min Salinity:	5.45
Max Salinity:	17.55
Avg Salinity:	12.47
Min Sigma-Theta:	0.50
Max Sigma-Theta:	9.61
Avg Sigma-Theta:	5.78
Min Turbidity:	18.52
Max Turbidity:	27.16
Avg Turbidity:	22.01

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E21-T042-P3

7/21/10 12:50 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.98
Max Temp:	27.37
Avg Temp:	27.22
Min Cond:	10.75
Max Cond:	27.03
Avg Cond:	18.80
Min Salinity:	5.83
Max Salinity:	15.89
Avg Salinity:	10.68
Min Sigma-Theta:	0.89
Max Sigma-Theta:	8.33
Avg Sigma-Theta:	4.44
Min Turbidity:	14.76
Max Turbidity:	27.50
Avg Turbidity:	22.59

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E21-T067-P1

7/21/10 12:48 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.65
Max Temp:	27.79
Avg Temp:	27.70
Min Cond:	0.52
Max Cond:	0.53
Avg Cond:	0.53
Min Salinity:	0.26
Max Salinity:	0.26
Avg Salinity:	0.26
Min Sigma-Theta:	-3.41
Max Sigma-Theta:	-3.39
Avg Sigma-Theta:	-3.40
Min Turbidity:	18.24
Max Turbidity:	57.11
Avg Turbidity:	34.33

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E21-T067-P2

7/21/10 12:57 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.67
Max Temp:	27.78
Avg Temp:	27.74
Min Cond:	0.50
Max Cond:	0.50
Avg Cond:	0.50
Min Salinity:	0.23
Max Salinity:	0.23
Avg Salinity:	0.23
Min Sigma-Theta:	-3.44
Max Sigma-Theta:	-3.42
Avg Sigma-Theta:	-3.43
Min Turbidity:	20.11
Max Turbidity:	45.79
Avg Turbidity:	33.12

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E21-T067-P3

7/21/10 13:07 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.71
Max Temp:	27.77
Avg Temp:	27.74
Min Cond:	0.51
Max Cond:	0.52
Avg Cond:	0.52
Min Salinity:	0.24
Max Salinity:	0.24
Avg Salinity:	0.24
Min Sigma-Theta:	-3.42
Max Sigma-Theta:	-3.40
Avg Sigma-Theta:	-3.42
Min Turbidity:	19.24
Max Turbidity:	47.32
Avg Turbidity:	32.66

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E21-T102-P1

7/21/10 11:56 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.40
Max Temp:	27.45
Avg Temp:	27.43
Min Cond:	0.50
Max Cond:	0.50
Avg Cond:	0.50
Min Salinity:	0.23
Max Salinity:	0.23
Avg Salinity:	0.23
Min Sigma-Theta:	-3.43
Max Sigma-Theta:	-3.41
Avg Sigma-Theta:	-3.43
Min Turbidity:	12.49
Max Turbidity:	19.80
Avg Turbidity:	15.66

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E21-T102-P2

7/21/10 12:01 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.43
Max Temp:	27.44
Avg Temp:	27.44
Min Cond:	0.50
Max Cond:	0.50
Avg Cond:	0.50
Min Salinity:	0.23
Max Salinity:	0.23
Avg Salinity:	0.23
Min Sigma-Theta:	-3.43
Max Sigma-Theta:	-3.43
Avg Sigma-Theta:	-3.43
Min Turbidity:	15.07
Max Turbidity:	18.11
Avg Turbidity:	16.66

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E21-T102-P3

7/21/10 12:06 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.42
Max Temp:	27.45
Avg Temp:	27.42
Min Cond:	0.50
Max Cond:	0.50
Avg Cond:	0.50
Min Salinity:	0.23
Max Salinity:	0.23
Avg Salinity:	0.23
Min Sigma-Theta:	-3.43
Max Sigma-Theta:	-3.43
Avg Sigma-Theta:	-3.43
Min Turbidity:	17.11
Max Turbidity:	23.79
Avg Turbidity:	18.99

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E21-T135-P1

7/21/10 11:09 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.93
Max Temp:	26.98
Avg Temp:	26.96
Min Cond:	0.51
Max Cond:	0.59
Avg Cond:	0.54
Min Salinity:	0.20
Max Salinity:	0.28
Avg Salinity:	0.25
Min Sigma-Theta:	-3.29
Max Sigma-Theta:	-3.05
Avg Sigma-Theta:	-3.23
Min Turbidity:	7.64
Max Turbidity:	8.76
Avg Turbidity:	8.14

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E21-T135-P2

7/21/10 11:15 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.56
Max Temp:	27.01
Avg Temp:	26.94
Min Cond:	0.46
Max Cond:	0.46
Avg Cond:	0.46
Min Salinity:	0.21
Max Salinity:	0.21
Avg Salinity:	0.21
Min Sigma-Theta:	-3.33
Max Sigma-Theta:	-3.29
Avg Sigma-Theta:	-3.31
Min Turbidity:	7.24
Max Turbidity:	11.11
Avg Turbidity:	9.14

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E21-T135-P3

7/21/10 11:19 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.46
Max Temp:	27.00
Avg Temp:	26.93
Min Cond:	0.46
Max Cond:	0.46
Avg Cond:	0.46
Min Salinity:	0.21
Max Salinity:	0.21
Avg Salinity:	0.21
Min Sigma-Theta:	-3.33
Max Sigma-Theta:	-3.30
Avg Sigma-Theta:	-3.31
Min Turbidity:	7.63
Max Turbidity:	10.01
Avg Turbidity:	8.67

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E22-T014-P1

7/21/10 18:14 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.01
Max Temp:	27.84
Avg Temp:	27.26
Min Cond:	22.91
Max Cond:	33.50
Avg Cond:	31.43
Min Salinity:	12.60
Max Salinity:	20.07
Avg Salinity:	18.56
Min Sigma-Theta:	5.23
Max Sigma-Theta:	11.52
Avg Sigma-Theta:	10.22
Min Turbidity:	12.52
Max Turbidity:	60.84
Avg Turbidity:	32.94

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E22-T014-P2

7/21/10 18:20 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.14
Max Temp:	28.47
Avg Temp:	27.58
Min Cond:	18.20
Max Cond:	33.49
Avg Cond:	30.79
Min Salinity:	10.11
Max Salinity:	20.02
Avg Salinity:	18.13
Min Sigma-Theta:	3.81
Max Sigma-Theta:	11.44
Avg Sigma-Theta:	9.89
Min Turbidity:	10.95
Max Turbidity:	68.49
Avg Turbidity:	36.70

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E22-T014-P3

7/21/10 18:25 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.14
Max Temp:	28.43
Avg Temp:	27.83
Min Cond:	25.17
Max Cond:	33.18
Avg Cond:	29.70
Min Salinity:	14.13
Max Salinity:	19.81
Avg Salinity:	17.32
Min Sigma-Theta:	6.54
Max Sigma-Theta:	11.28
Avg Sigma-Theta:	9.19
Min Turbidity:	10.85
Max Turbidity:	80.35
Avg Turbidity:	38.07

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E22-T042-P1

7/21/10 18:51 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.25
Max Temp:	28.64
Avg Temp:	27.95
Min Cond:	12.94
Max Cond:	27.64
Avg Cond:	21.75
Min Salinity:	6.91
Max Salinity:	16.17
Avg Salinity:	12.36
Min Sigma-Theta:	1.30
Max Sigma-Theta:	8.52
Avg Sigma-Theta:	5.47
Min Turbidity:	14.74
Max Turbidity:	105.13
Avg Turbidity:	47.81

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E22-T042-P2

7/21/10 18:56 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.26
Max Temp:	28.70
Avg Temp:	27.82
Min Cond:	13.04
Max Cond:	27.53
Avg Cond:	22.76
Min Salinity:	6.95
Max Salinity:	16.09
Avg Salinity:	13.01
Min Sigma-Theta:	1.27
Max Sigma-Theta:	8.47
Avg Sigma-Theta:	6.00
Min Turbidity:	16.24
Max Turbidity:	110.52
Avg Turbidity:	49.25

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E22-T042-P3

7/21/10 19:03 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.27
Max Temp:	28.31
Avg Temp:	27.81
Min Cond:	13.66
Max Cond:	26.94
Avg Cond:	22.04
Min Salinity:	7.37
Max Salinity:	15.71
Avg Salinity:	12.52
Min Sigma-Theta:	1.70
Max Sigma-Theta:	8.18
Avg Sigma-Theta:	5.63
Min Turbidity:	12.87
Max Turbidity:	119.11
Avg Turbidity:	46.80

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E22-T067-P1

7/21/10 19:04 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.96
Max Temp:	28.45
Avg Temp:	28.02
Min Cond:	8.95
Max Cond:	9.54
Avg Cond:	9.21
Min Salinity:	4.70
Max Salinity:	5.02
Avg Salinity:	4.85
Min Sigma-Theta:	-0.26
Max Sigma-Theta:	0.00
Avg Sigma-Theta:	-0.14
Min Turbidity:	29.45
Max Turbidity:	99.83
Avg Turbidity:	54.05

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E22-T067-P2

7/21/10 19:12 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	28.03
Max Temp:	28.23
Avg Temp:	28.08
Min Cond:	9.53
Max Cond:	9.94
Avg Cond:	9.87
Min Salinity:	4.99
Max Salinity:	5.24
Avg Salinity:	5.19
Min Sigma-Theta:	0.00
Max Sigma-Theta:	0.15
Avg Sigma-Theta:	0.11
Min Turbidity:	30.15
Max Turbidity:	87.97
Avg Turbidity:	62.47

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E22-T067-P3

7/21/10 19:17 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	28.04
Max Temp:	28.45
Avg Temp:	28.10
Min Cond:	9.44
Max Cond:	10.38
Avg Cond:	10.05
Min Salinity:	4.96
Max Salinity:	5.49
Avg Salinity:	5.30
Min Sigma-Theta:	0.06
Max Sigma-Theta:	0.32
Avg Sigma-Theta:	0.22
Min Turbidity:	36.23
Max Turbidity:	111.61
Avg Turbidity:	63.28

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E22-T102-P1

7/21/10 18:22 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.13
Max Temp:	28.43
Avg Temp:	27.81
Min Cond:	0.50
Max Cond:	0.54
Avg Cond:	0.51
Min Salinity:	0.23
Max Salinity:	0.25
Avg Salinity:	0.23
Min Sigma-Theta:	-3.71
Max Sigma-Theta:	-3.33
Avg Sigma-Theta:	-3.54
Min Turbidity:	21.46
Max Turbidity:	101.97
Avg Turbidity:	47.76

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E22-T102-P2

7/21/10 18:28 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.38
Max Temp:	28.55
Avg Temp:	27.86
Min Cond:	0.50
Max Cond:	0.51
Avg Cond:	0.50
Min Salinity:	0.23
Max Salinity:	0.23
Avg Salinity:	0.23
Min Sigma-Theta:	-3.75
Max Sigma-Theta:	-3.42
Avg Sigma-Theta:	-3.55
Min Turbidity:	16.23
Max Turbidity:	62.65
Avg Turbidity:	32.36

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E22-T102-P3

7/21/10 18:32 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.53
Max Temp:	28.61
Avg Temp:	27.90
Min Cond:	0.50
Max Cond:	0.51
Avg Cond:	0.50
Min Salinity:	0.23
Max Salinity:	0.23
Avg Salinity:	0.23
Min Sigma-Theta:	-3.77
Max Sigma-Theta:	-3.46
Avg Sigma-Theta:	-3.57
Min Turbidity:	16.24
Max Turbidity:	53.50
Avg Turbidity:	24.80

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E22-T135-P1

7/21/10 17:42 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.04
Max Temp:	28.46
Avg Temp:	27.54
Min Cond:	0.55
Max Cond:	0.56
Avg Cond:	0.55
Min Salinity:	0.25
Max Salinity:	0.26
Avg Salinity:	0.25
Min Sigma-Theta:	-4.00
Max Sigma-Theta:	-3.30
Avg Sigma-Theta:	-3.50
Min Turbidity:	6.23
Max Turbidity:	9.58
Avg Turbidity:	7.66

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E22-T135-P2

7/21/10 17:49 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.99
Max Temp:	27.83
Avg Temp:	27.33
Min Cond:	0.55
Max Cond:	0.55
Avg Cond:	0.55
Min Salinity:	0.25
Max Salinity:	0.25
Avg Salinity:	0.25
Min Sigma-Theta:	-3.53
Max Sigma-Theta:	-3.29
Avg Sigma-Theta:	-3.40
Min Turbidity:	5.97
Max Turbidity:	8.58
Avg Turbidity:	6.79

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

10A-E22-T135-P3

7/21/10 17:53 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.02
Max Temp:	29.57
Avg Temp:	27.88
Min Cond:	0.54
Max Cond:	0.55
Avg Cond:	0.55
Min Salinity:	0.24
Max Salinity:	0.25
Avg Salinity:	0.25
Min Sigma-Theta:	-3.97
Max Sigma-Theta:	-3.30
Avg Sigma-Theta:	-3.54
Min Turbidity:	6.54
Max Turbidity:	7.43
Avg Turbidity:	6.96

APPENDIX 12: Data CD

Appendix C

Final Report - Spring Deployment Oceanographic Data Acquisition Program – Newark Bay, Lower Passaic River Restoration Project. OSI Report #10ES006

Final Report

Spring Deployment
Oceanographic Data Acquistion Program - Newark Bay
Lower Passaic River Restoration Project

Passaic River, Newark to Passaic, NJ

OSI Report #10ES006
26 October 2010

Prepared For:
AECOM
171 Daniel Webster Highway, Suite 11
Belmont, New Hampshire 03220

Prepared By:
Ocean Surveys, Inc.
91 Sheffield Street
Old Saybrook, CT 06475

FINAL REPORT

SPRING DEPLOYMENT

OCEANOGRAPHIC DATA ACQUISITION PROGRAM - NEWARK BAY

LOWER PASSAIC RIVER RESTORATION PROJECT

NEWARK BAY, NJ

OSI Report No. 10ES006

Prepared For: AECOM
171 Daniel Webster Highway, Suite 11
Belmont, New Hampshire 03220

Prepared By: Ocean Surveys, Inc.
91 Sheffield Street
Old Saybrook, CT 06475

26 October 2010

TABLE OF CONTENTS

Page

TABLE OF CONTENTS i

LIST OF FIGURES & TABLES ii

1.0 INTRODUCTION 1

1.1 Project Summary 1
1.2 Project Tasks 3

2.0 FIELD OPERATIONS SUMMARY 6

2.1 Field Crew, Survey Vessel, & Navigation 6
2.2 Field Schedule 7
2.3 *In Situ* Instrumentation and Moorings 9

2.3.1 YSI Environmental 6920 Multiparameter Sonde 11
2.3.2 Acoustic Doppler Current Profiler 12

2.4 Real-Time Data Collection 12

3.0 DATA PRESENTATION 13

3.1 Water Sample Data 13
3.2 *In Situ* Instrumentation 13
3.3 Real-Time Survey Events 15

4.0 Project Summary 15

LIST OF FIGURES & TABLES

Figure 1. Site map of *in situ* instrumentation and real-time survey transects.. 2
Figure 2. ADCP/CT-OBS mooring and CT-OBS surface buoy. 10
Figure 3. *In situ* CT-OBS and ADCP bottom mooring. 11

Table 1. Project tasks listed by event number..... 5
Table 2. Field crews..... 6
Table 3. Field schedule 7
Table 4. In situ instrument mooring locations 10
Table 5. *In situ* instrument salinity fouling periods 14
Table 6. *In situ* instrument turbidity fouling periods 14

APPENDICES

1 Water Sampling Log
2 Survey Equipment, Procedures and Data Processing
3 Instrument Calibration
4 YSI Water Quality Time Series Plots
5 *In Situ* ADCP Time Series Plots
6 Mooring CTD-OBS Vertical Profiles – Events E01, E05, E09, & E10
7 Trip 4 Real Time Surveys Events E03-E04
8 Trip 5 Real Time Surveys Events E07-E08
9 Trip 6 Real Time Surveys Events E12-E13
10 Trip 7 Real Time Surveys Events E17-E18
11 Trip 8 Real Time Surveys Events E21-E22
12 Data CD

FINAL REPORT

SPRING DEPLOYMENT

OCEANOGRAPHIC DATA ACQUISITION PROGRAM - NEWARK BAY

LOWER PASSAIC RIVER RESTORATION PROJECT

NEWARK BAY, NJ

1.0 INTRODUCTION

The oceanographic data acquisition program for the Lower Passaic River Restoration Project – Newark Bay was developed to provide *in situ* and real time data over a three-month period on flows, salinity, and solids under a range of flow conditions. During the period 18 March 2010 through 26 July 2010, Ocean Surveys, Inc. (OSI) conducted the oceanographic data acquisition program in and around Newark Bay during an expected high flow period. The program was extended for an additional month to capture expected low flow conditions. This work was conducted parallel to an oceanographic data acquisition program in the Lower Passaic River (LPR). The Lower Passaic River (LPR) report is provided under separate cover.

1.1 Project Summary

This program included the deployment of five Conductivity, Temperature-Optical Backscatter (CT-OBS) mooring buoys and six Acoustic Doppler Current Profilers (ADCP) bottom moorings (Figure 1) along with real-time, boat-based vessel-mounted ADCP (VMADCP) transect surveys that included the collection of Conductivity, Temperature, Depth-Optical Backscatter (CTD-OBS) vertical profiles and water samples at each of the mooring locations. The moorings were deployed in March 2010 and were scheduled to be deployed for three months. The deployment was extended an additional month into July 2010 to capture low flow conditions. Consistent with the *Remedial Investigation Water*

Column Monitoring/Physical Data Collection for the Lower Passaic River Restoration Project Quality Assurance Project Plan[1], OSI conducted real-time boat-based surveys immediately following deployment and servicing of the moorings and just prior to recovery. Details of the operational aspects of the field program and a presentation of the data are included in this report.



Figure 1. Site map of *in situ* instrumentation and real-time survey transects.

[1] AECOM 2010, Quality Assurance Project Plan/Field Sampling Addendum – Remedial Investigation Water Column Monitoring/Physical Data Collection – Lower Passaic River Restoration Project, Revision 5, April 2010, 319p.

1.2 Project Tasks

The oceanographic data acquisition program included six project tasks: *in situ* CT-OBS data, *in situ* current velocity profiling, *in situ* wave measurements, vessel mounted ADCP transects, CTD-Turbidity profiling, and water sampling for total suspended solids.

1) ***In Situ* CT-OBS Data:** *In situ* water quality was measured using instruments set on two moorings at each of the 5 monitoring locations (Figure 1), one for surface measurements and the other for bottom measurements. YSI Inc. Model 6920 and 6600 water quality sondes were deployed at the bottom in conjunction with each of the five primary bottom mounted ADCP moorings and on each of the five CT-OBS surface buoys, which were deployed in close proximity to the ADCP bottom moorings. Instruments were mounted 3 feet above the bottom and 3 feet below the water surface. Each sonde was configured to record temperature, conductivity/salinity, and turbidity at 12-minute intervals. The five instrument mooring stations were located: Hackensack River, Newark Bay (north and south), Kill Van Kull, and Arthur Kill (Figure 1).

2) ***In Situ* Current Velocity Profiling:** *In situ* current velocities were monitored using bottom-mounted Teledyne RD Instruments (TRDI) Workhorse Sentinel ADCPs. The ADCPs were deployed at five locations: Hackensack River, Newark Bay (north and south), Kill Van Kull, and Arthur Kill (Figure 1). The ADCPs were programmed to record current velocity and acoustic backscatter throughout the water column at 0.5-meter vertical bins every 12 minutes.

3) ***In Situ* Wave Measurements:** Wave data were collected using a bottom-mounted TRDI Workhorse Sentinel ADCP. The ADCP was deployed within Newark Bay (Figure 1). The ADCP was programmed to record wave data in 20 minute bursts every hour.

4) **Vessel Mounted ADCP (VMADCP) Transects:** Current velocity and backscatter data were collected along five transects. Each transect corresponded with an *in situ* CT-OBS instrument location (Figure 1). The transects were conducted twice, coinciding with flood and ebb tidal conditions. The VMADCP surveys were conducted after instrument deployments, during servicing, and prior to instrument recovery. Current velocity and backscatter data were collected throughout the water column in 0.5-meter vertical bins.

5) **CTD-Turbidity Profiling:** Sea-bird Electronics, Inc. Model SBE-19 SeaCat profiler was used to measure vertical profiles of temperature, conductivity/salinity, and turbidity in the water column. Profiles were collected at each mooring location after deployment, before and after servicing, and prior to recovery. In addition, three profiles were collected across each transect during the VMADCP surveys.

6) **Total Suspended Solids:** Water samples were collected at each mooring location after deployment, before and after servicing, and prior to recovery. In addition, samples were collected at each of the CTD profiling stations occupied during the VMADCP surveys. Samples were collected primarily to measure suspended sediment concentrations (SSC) with periodic additional samples collected during the VMADCP surveys for particulate organic carbon/dissolved organic carbon (POC/DOC) analyses. Water samples were collected at 3 feet below the surface and 3 feet above the bottom. AECOM was responsible for water sample handling and subsequent lab analysis.

AECOM has developed a series of alphanumerical designations for all field tasks performed on site. The spring 2010 Newark Bay program was given a program designation of N01. During this program, each individual field task was broken down into individual events (Table 1). CTD-OBS vertical profiles and water sample collection were conducted after mooring deployment (Event E01), prior to servicing and after redeployment (Events E05 & E09-April 2010, Events E10 & E14-May 2010, Events E15 & E19-June 2010), and prior to recovery (Event E23-July 2010). Real-time ADCP transect survey operations during each

trip to the site were conducted under Events E03 & E04 (March 2010), Events E07 & E08 (May 3, 2010), Events E12 & E13 (May 24, 2010), Events E17 & E18 (June 2010), and Events E21 & E22 (July 2010).

Table 1. Project tasks listed by event number

Survey	Month	Event	Name
4	March	E01	Post-deployment moorings
4	March	E03	Ebb tide transects
4	March	E04	Flood tide transects
5	April	E05	Pre-service moorings
5	May	E07	Flood tide transects
5	May	E08	Ebb tide transects
5	April	E09	Post-service moorings
6	May	E10	Pre-recovery moorings
6	May	E12	Ebb tide transects
6	May	E13	Flood tide transects
6	May	E14	Post-service moorings
7	June	E15	Pre-recovery moorings
7	June	E17	Ebb tide transects
7	June	E18	Flood tide transects
7	June	E19	Post-service moorings
8	July	E21	Ebb tide transects
8	July	E22	Flood tide transects
8	July	E23	Pre-recovery moorings

* Events E02, E06, E11, E16, & E20 were conducted as part of the LPR field program only. Surveys 1-3 were conducted in the LPR during the fall of 2009.

2.0 FIELD OPERATIONS SUMMARY

2.1 Field Crew, Survey Vessel, & Navigation

OSI conducted all fieldwork aboard a variety of vessels, each equipped with a DMS 212 Differential Global Positioning System (DGPS) receiver and staffed by a two-person OSI field team consisting of a Project Manager/Scientist and a Field Engineer. Each vessel was powered by twin outboard motors and equipped with winch and davit capabilities to support installation, servicing, and recovery of the *in situ* instrument moorings. Each vessel was also equipped with a Teledyne RD Instruments vessel-mounted 1200 kHz ADCP and Sea-Bird Electronics CTD-OBS vertical profiler.

The following personnel comprised the two-person field crews (Table 2):

Table 2. Field crews

Survey	*R/V Ready II* Servicing	*R/V Able or R/V Ready II* Mapping	*R/V Echo Echo*
Trip 4	Steve Bodak	Steve Bodak	Ryan Bollenbach
	Dustin Kach	Mike Lincoln	Jeff Motti
Trip 5	Steve Bodak	Ken Cadmus	Steve Bodak
	Dustin Kach	Kyle Toothaker	Kevin Murphy
Trip 6	Steve Bodak	Steve Bodak	Ryan Bollenbach
	Dustin Kach	Mike Lincoln	Steve Gadomski
Trip 7	Dustin Kach	Steve Bodak	Ryan Bollenbach
	Ryan Bollenbach	Mike Lincoln	Kevin Ridarelli
Trip 8	Steve Bodak	Steve Bodak	Ryan Bollenbach
	Dustin Kach	Mike Lincoln	Kevin Ridarelli

In addition, representatives from AECOM and EPA (Louis Berger) were present throughout the field effort.

The survey navigation system consisted of Coast Guard DGPS that was fed directly into the HYPACK survey navigation and data collection system on each vessel. A full description of the navigational system and survey instrumentation is available in Appendix 2, along with a brief description of operational and data processing procedures. The designated coordinate system for the project was the New Jersey State Plane in the North American Datum of 1983 (NAD83). Horizontal grid units were in U.S. Survey feet.

2.2 Field Schedule

Project tasks were conducted from 18 March 2010 through 26 July 2010. A detailed schedule of field operations is listed below (Table 3):

Table 3. Field schedule

Date	*R/V Ready II* Task	*R/V Able* Task
03/18/2010	Travel to site and ready boat.	
03/19/2010	Deploy equipment at Stations KVK and ARK, collect CTD-OBS vertical profiles and water samples.	
03/20/2010	Deploy equipment at Stations NBN and NBS, collect CTD-OBS vertical profiles and water samples.	
03/21/2010	Deploy equipment at Stations HKN and NBW, collect CTD-OBS vertical profiles and water samples.	
03/22 – 03/23/2010	LPR operations.	
03/24/2010	LPR operations. Calibrate the VMADCP in Newark Bay.	Travel to site, ready boat, and calibrate VMADCP.
03/25/2010	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects NBN, NBS, KVK, & ARK.	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects HKN along with two additional transect on the Passaic River.
03/26/2010	Travel to OSI at Old Saybrook, CT.	Travel to OSI at Old Saybrook, CT.
	R/V Ready II	***R/V Echo Echo***
04/27/2010	Travel to site and ready boat.	
04/28/2010	Recover, service, and redeploy equipment at Stations NBW and NBN. Collect CTD-OBS vertical profiles and water samples.	
04/29/2010	Recover, service, and redeploy equipment at Stations ARK and HKN. Collect CTD-OBS vertical profiles and water samples.	
04/30/2010	Recover, service, and redeploy equipment at Stations KVK and NBS. Collect CTD-OBS vertical profiles and water samples.	
05/01/2010	LPR operations	
05/02/2010	LPR operations. Calibrate the VMADCP in Newark Bay.	Travel to site, ready boat, and calibrate VMADCP.

Table 3 continued.

	R/V Ready II	***R/V Echo Echo***
05/03/2010	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects NBN, NBS, KVK, & ARK.	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects HKN along with two additional transect on the Passaic River.
05/04/2010	Travel to OSI at Old Saybrook, CT.	Travel to OSI at Old Saybrook, CT.
05/18/2010	Travel to site and ready boat.	
05/19 – 05/20/2010	LPR operations.	
05/21/2010	Recover, service, and redeploy equipment at Stations ARK and NBS. Collect CTD-OBS vertical profiles and water samples.	
05/22/2010	Recover, service, and redeploy equipment at Stations KVK and NBN. Collect CTD-OBS vertical profiles and water samples.	
05/23/2010	Recover, service, and redeploy equipment at Stations NBW and HKN. Collect CTD-OBS vertical profiles and water samples. Calibrate VMADCP.	Travel to site, ready boat, and calibrate VMADCP.
05/24/2010	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects NBN, NBS, KVK, & ARK	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects HKN along with two additional transect on the Passaic River.
05/25/2010	Travel to OSI at Old Saybrook, CT.	Travel to OSI at Old Saybrook, CT.
06/16/2010	Travel to site and ready boat.	
06/17 – 06/18/2010	LPR operations.	
06/19/2010	Recover, service, and redeploy equipment at Stations ARK and NBS. Collect CTD-OBS vertical profiles and water samples.	
06/20/2010	Recover, service, and redeploy equipment at Stations KVK and NBN. Collect CTD-OBS vertical profiles and water samples.	
06/21/2010	Recover, service, and redeploy equipment at Stations NBW and HKN. Collect CTD-OBS vertical profiles and water samples. Calibrate VMADCP.	Travel to site, ready boat, and calibrate VMADCP.
06/22/2010	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects NBN, NBS, KVK, & ARK	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects HKN along with two additional transect on the Passaic River.
06/23/2010	Travel to OSI at Old Saybrook, CT.	Travel to OSI at Old Saybrook, CT.

Table 3 continued.

	R/V Ready II	*R/V Echo Echo*
07/20/2010	Travel to site, ready boat, and calibrate VMADCP.	Travel to site, ready boat, and calibrate VMADCP.
07/21/2010	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects NBN, NBS, KVK, & ARK	Collect CTD-OBS vertical profiles and water samples and conduct VMADCP survey at Transects HKN along with two additional transect on the Passaic River.
07/22 – 07/23/2010	LPR operations	Travel to OSI at Old Saybrook, CT.
07/24/2010	Collect CTD-OBS vertical profiles and water samples then recovered equipment and moorings at Stations ARK and NBN.	
07/25/2010	Collect CTD-OBS vertical profiles and water samples then recovered equipment and moorings at Stations NBS KVK and NBW.	
07/26/2010	Collect CTD-OBS vertical profiles and water samples then recovered equipment and moorings at Station HKN. Travel to OSI at Old Saybrook, CT.	

2.3 ***In Situ* Instrumentation and Moorings**

OSI maintained five CT-OBS mooring buoys and six ADCP bottom moorings throughout the Hackensack River, Newark Bay, Kill Van Kull, and Arthur Kill (Table 4). As shown in Figure 2, two moorings (one "bottom mooring" and one "surface mooring") were deployed at each station except at Station NBW, which consisted of one ADCP bottom mooring for wave measurements. After deployment, before and after servicings, and prior to recovery, OSI conducted CTD-OBS vertical profiles and collected water samples adjacent to the instrument moorings for data quality checks and calibration. A water-sampling log including sample locations, date & time, sample depths, and total water depth is available in Appendix 1. Detailed information on instrument operations and data processing procedures is available in Appendix 2. A brief discussion on general instrument calibration procedures is available in Appendix 3.

Table 4. In situ instrument mooring locations

Station	Bottom Mooring		Surface Moorings	
	Easting	Northing	Easting	Northing
HKN	605477	694143	605453	694155
NBN	596225	677617	596197	677593
NBS	589886	663884	589848	663865
ARK	579791	660674	579783	660711
KVK	595167	659803	595164	659821
NBW	596211	673974	N/A*	N/A*

* Station NBW was a bottom moored wave gauge. There was no surface mooring at this location.



Figure 2. ADCP/CT-OBS mooring and CT-OBS surface buoy.

2.3.1 YSI Environmental 6920 Multiparameter Sonde

In situ water quality was measured and recorded using YSI Series 6920 & 6600 Multiparameter Sondes. A total of ten sondes were deployed, two at each of the five moorings that were deployed throughout the Hackensack River, Newark Bay, Kill Van Kull, and Arthur Kill. At each station, one unit was placed 3 feet off the bottom and one unit 3 feet below the surface and programmed to record temperature, conductivity/salinity, and turbidity at 12-minute intervals (Figure 3).

Figure 3. *In situ* CT-OBS and ADCP bottom mooring.

2.3.2 Acoustic Doppler Current Profiler

Between March 19 & 21 2010, OSI deployed five 600 kHz ADCPs. The ADCPs were deployed in approximately 30 to 55 feet of water at Stations HKN, NBN, NBS, KVK and ARK. Each ADCP was secured to a bottom mount in an upward looking position. OSI's custom ADCP mounts are approximately 2.5-feet long by 2.5-feet wide and project less than two feet off the bottom. A gimbal attachment within the instrument housing kept the ADCPs plumb. These specialized mounts have no buoys or other surface expression. Each ADCP was programmed to record current velocity and backscatter data at 12-minute intervals using 0.5-meter vertical bins. In addition to the five primary mooring locations, a 1200 kHz ADCP wave gauge was installed on a bottom mount in approximately 12 feet of water within Newark Bay. The ADCP was set to record wave data in 20 minute bursts every 60 minutes. Each burst consists of 2,400 samples collected at a rate of 2 Hz. This setup allowed waves to be detected down to a period of 2 seconds (0.5 Hz). The ADCPs were recovered between July 24 - 26, 2010.

2.4 Real-Time Data Collection

Current velocity and water quality data were collected in real-time along five transects corresponding to the five *in situ* CT-OBS instrument moorings. Current velocity and backscatter data were collected in real-time using downward looking, vessel–mounted 1200 kHz ADCPs. The ADCP data were collected in 0.5-meter vertical bins. Upon completion of each transect, a Seabird SBE 19 SeaCat water quality vertical profiler was used at three locations, evenly spaced along each transect to measure temperature, conductivity/salinity, and turbidity. This unit had a direct hard-wired connection to an on-board computer that recorded the data in real-time. At each of the vertical profile stations, water samples were collected through a pump system attached to the CTD vertical profiler. Water samples were collected 3 feet below the surface and 3 feet above the bottom. All water samples were collected and handled by both the onboard AECOM and EPA representatives. In addition, periodic water samples for POC/DOC analyses were collected.

3.0 DATA PRESENTATION

3.1 Water Sample Data

The water samples collected throughout the field program were analyzed for Suspended Sediment Concentrations (SSC) by Columbia Analytical Services, an EPA approved lab. The lab results of the water samples were amassed by AECOM and will be delivered under separate cover.

3.2 *In Situ* Instrumentation

In situ measurements of current velocity and water quality parameters were recorded continuously from late March through late July 2010. During the deployment period there were three minor instrument stoppages (typically less than 2 hrs) during servicing operations at each station, two longer stoppages and two instrument fouling periods. The CT-OBS unit near the bottom at Station HKN malfunctioned 5 April 2010 at 16:36 (UTC) through 29 April 2010 at 19:24 (UTC) resulting in a loss of data during this period. In addition, the ADCP at Station ARK encountered a corrupt data file which caused a loss of current data between 19 April 2010 at 04:48 (UTC) and 29 April 2010 at 15:54 (UTC). OSI took multiple steps to limit biological fouling on the moorings through the use of bottom paint, copper, zinc anodes, and instrument wipers. However biological fouling occurred at most of the moorings during the months of June and July, which primarily influenced the *in situ* turbidity, and salinity probes. Tables 5 & 6 list the periods for each CT-OBS instrument when turbidity and salinity data were beyond the range of expected values.

Table 5. *In situ* instrument salinity fouling periods

	Fouling Period Salinity	
Station	Begin	End
HKN Bottom	06/15/2010 11:00	06/21/2010 14:36
HKN Bottom	07/09/2010 00:00	07/26/2010 14:36
NBN Top	05/22/2010 17:48	05/26/2010 15:36
NBN Top	07/02/2010 13:12	07/24/2010 16:36
KVK Bottom	07/09/2010 00:36	07/25/2010 19:36
ARK Top	06/12/2010 06:24	06/18/2010 15:12
ARK Top	07/11/2010 17:24	07/24/2010 14:12
ARK Bottom	07/05/2010 18:36	07/11/2010 20:48

Table 6. *In situ* instrument turbidity fouling periods

	Fouling Period Turbidity	
Station	Begin	End
HKN Bottom	07/01/2010 21:12	07/26/2010 14:36
NBN Top	06/01/2010 22:00	06/20/2010 17:00
NBN Top	07/01/2010 10:24	07/02/2010 07:36
NBN Top	07/06/2010 12:48	07/24/2010 16:36
NBN Bottom	07/12/2010 19:48	07/24/2010 15:00
NBS Top	06/04/2010 11:24	06/19/2010 17:00
NBS Top	06/27/2010 06:36	07/25/2010 16:24
NBS Bottom	06/09/2010 12:24	06/19/2010 16:00
KVK Top	06/03/2010 02:24	06/20/2010 14:12
KVK Top	07/01/2010 06:12	07/25/2010 13:24
KVK Bottom	05/30/2010 07:24	06/20/2010 13:00
KVK Bottom	07/15/2010 11:48	07/25/2010 19:36
ARK Top	06/02/2010 21:00	06/19/2010 14:12
ARK Top	06/29/2010 16:48	07/21/2010 00:12
ARK Bottom	06/09/2010 11:24	06/19/2010 12:48

The CT-OBS and ADCP times series plots have been plotted in two colors (red=ebb, blue=flood) to emphasis tidal flow conditions as determine by the ADCP vertically averaged current direction data at each station. The CT-OBS data have been presented as time series plots of temperature (º C), salinity (PSU), and turbidity (NTU) in Appendix 4. The ADCP current velocity data are presented as time series plots of vertically averaged current speed (mm/s) and direction (º True) Appendix 5. The ADCP wave gauge data are presented as time series plots of significant wave height (m), peak period (s), and peak direction (º True). The data are also available in Microsoft Excel spreadsheets on the enclosed CD-ROM in Appendix 12.

The CTD-OBS vertical profiles recorded after deployment (Event E01), before and after servicing (Events E05, E09, E10, E14, E15, & E19), and prior to recovery (Event E23) are presented in Appendix 6.

3.3 Real-Time Survey Events

Current data from the VMADCP are presented as vector plots in Appendix 7 (Trip 4, Events E03-E04), Appendix 8 (Trip 5, Events E07-E08), Appendix 9 (Trip 6, Events E12-E13) Appendix 10 (Trip 7, Events E17-E18) and Appendix 11 (Trip 8, Events E21-E22). Data from the CTD-OBS vertical profiles are presented in Appendix 7-11 corresponding to each trip. Data files of the vertical profiles are available on the enclosed CD-ROM in Appendix 12.

4.0 Project Summary

The oceanographic data acquisition equipment was deployed for a four-month period during which five real time boat based surveys were conducted. The *in situ* instrumentation was deployed at six stations. Three stations were located within Newark Bay with additional stations in the Hackensack River, Kill Van Kull, and Arthur Kill. The program was implemented in parallel to the data acquisition program in the LPR. The instrumentation was deployed to collect data during an expected high flow period and the deployment extended to capture low flow conditions occurring in the Lower Passaic and Hackensack Rivers.

APPENDIX 1: Water Sampling Log

Water Sample Data: Events E01-E23
Newark Bay, Newark, NJ
Client: AECOM
OSI Job # 10ES006

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
03/19/2010	17:20	579788	660678	N01	E01	TARK	P1	AS	41.5	3.0
03/19/2010	17:14	579786	660677	N01	E01	TARK	P1	BS	41.5	38.5
03/21/2010	14:17	605471	694141	N01	E01	THKN	P1	AS	36.5	3.0
03/21/2010	14:14	605473	694141	N01	E01	THKN	P1	BS	36.5	33.5
03/19/2010	16:49	595182	659791	N01	E01	TKVK	P1	AS	51.5	3.0
03/19/2010	16:47	595181	659793	N01	E01	TKVK	P1	BS	51.5	48.5
03/20/2010	16:34	596227	677618	N01	E01	TNBN	P1	AS	31.5	3.0
03/20/2010	16:30	596235	677617	N01	E01	TNBN	P1	BS	31.5	28.5
03/20/2010	16:00	589880	663876	N01	E01	TNBS	P1	AS	51.5	3.0
03/20/2010	15:55	589892	663878	N01	E01	TNBS	P1	BS	51.5	48.5
03/20/2010	15:56	589889	663876	N01	E01	TNBS	P1	BT	51.5	48.5
03/25/2010	14:07	579788	660674	N01	E03	TARK	P1	AS	33.5	3.0
03/25/2010	14:03	579794	660674	N01	E03	TARK	P1	BS	33.5	30.5
03/25/2010	14:20	579866	660351	N01	E03	TARK	P2	AS	45.0	3.0
03/25/2010	14:18	579878	660354	N01	E03	TARK	P2	BS	45.0	42.0
03/25/2010	14:34	579952	660070	N01	E03	TARK	P3	AS	43.0	3.0
03/25/2010	14:32	579961	660066	N01	E03	TARK	P3	BS	43.0	40.0
03/25/2010	10:51	605474	694140	N01	E03	THKN	P1	AS	37.0	3.0
03/25/2010	10:48	605475	694120	N01	E03	THKN	P1	BS	37.0	34.0
03/25/2010	11:06	605557	693982	N01	E03	THKN	P2	AS	33.0	3.0
03/25/2010	11:03	605564	693989	N01	E03	THKN	P2	BS	33.0	30.0
03/25/2010	11:15	605673	693803	N01	E03	THKN	P3	AS	29.0	3.0
03/25/2010	11:13	605664	693810	N01	E03	THKN	P3	BS	29.0	26.0
03/25/2010	13:13	595167	659801	N01	E03	TKVK	P1	AS	40.0	3.0
03/25/2010	13:09	595165	659800	N01	E03	TKVK	P1	BS	40.0	37.0
03/25/2010	13:10	595163	659799	N01	E03	TKVK	P1	BT	40.0	37.0
03/25/2010	13:22	595169	659377	N01	E03	TKVK	P2	AS	49.0	3.0
03/25/2010	13:21	595168	659378	N01	E03	TKVK	P2	BS	49.0	46.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
03/25/2010	13:33	595168	659009	N01	E03	TKVK	P3	AS	54.5	3.0
03/25/2010	13:31	595164	659000	N01	E03	TKVK	P3	BS	54.5	51.5
03/25/2010	11:04	596220	677626	N01	E03	TNBN	P1	AS	21.5	3.0
03/25/2010	11:01	596218	677617	N01	E03	TNBN	P1	BS	21.5	18.5
03/25/2010	11:16	597236	677118	N01	E03	TNBN	P2	AS	10.5	3.0
03/25/2010	11:14	597239	677112	N01	E03	TNBN	P2	BS	10.5	7.5
03/25/2010	11:27	598275	676635	N01	E03	TNBN	P3	AS	9.0	3.0
03/25/2010	11:24	598283	676641	N01	E03	TNBN	P3	BS	9.0	6.0
03/25/2010	12:11	589885	663880	N01	E03	TNBS	P1	AS	50.0	3.0
03/25/2010	12:07	589885	663882	N01	E03	TNBS	P1	BS	50.0	47.0
03/25/2010	12:25	590444	663597	N01	E03	TNBS	P2	AS	50.0	3.0
03/25/2010	12:23	590443	663597	N01	E03	TNBS	P2	BS	50.0	47.0
03/25/2010	12:39	591014	663337	N01	E03	TNBS	P3	AS	11.5	3.0
03/25/2010	12:37	591008	663335	N01	E03	TNBS	P3	BS	11.5	8.5
03/25/2010	12:37	591009	663338	N01	E03	TNBS	P3	BT	11.5	8.5
03/25/2010	19:52	579799	660678	N01	E04	TARK	P1	AS	36.5	3.0
03/25/2010	19:50	579799	660676	N01	E04	TARK	P1	BS	36.5	33.5
03/25/2010	20:01	579876	660344	N01	E04	TARK	P2	AS	49.5	3.0
03/25/2010	19:59	579879	660350	N01	E04	TARK	P2	BS	49.5	46.5
03/25/2010	20:10	579964	660069	N01	E04	TARK	P3	AS	45.0	3.0
03/25/2010	20:08	579959	660065	N01	E04	TARK	P3	BS	45.0	42.0
03/25/2010	16:56	605470	694140	N01	E04	THKN	P1	AS	34.0	3.0
03/25/2010	16:53	605470	694143	N01	E04	THKN	P1	BS	34.0	31.0
03/25/2010	17:10	605573	693972	N01	E04	THKN	P2	AS	30.0	3.0
03/25/2010	17:08	605570	693980	N01	E04	THKN	P2	BS	30.0	28.0
03/25/2010	17:20	605671	693805	N01	E04	THKN	P3	AS	25.0	3.0
03/25/2010	17:18	605679	693813	N01	E04	THKN	P3	BS	25.0	22.0
03/25/2010	18:54	595160	659806	N01	E04	TKVK	P1	AS	44.5	3.0
03/25/2010	18:51	595168	659809	N01	E04	TKVK	P1	BS	44.5	41.5
03/25/2010	18:52	595166	659801	N01	E04	TKVK	P1	BT	44.5	41.5
03/25/2010	19:18	595163	659384	N01	E04	TKVK	P2	AS	55.0	52.0
03/25/2010	19:16	595164	659372	N01	E04	TKVK	P2	BS	55.0	52.0
03/25/2010	19:28	595170	659005	N01	E04	TKVK	P3	AS	48.5	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
03/25/2010	19:26	595169	659013	N01	E04	TKVK	P3	BS	48.5	45.5
03/25/2010	17:02	596225	677622	N01	E04	TNBN	P1	AS	29.5	3.0
03/25/2010	16:59	596221	677618	N01	E04	TNBN	P1	BS	29.5	26.5
03/25/2010	17:12	597246	677115	N01	E04	TNBN	P2	AS	8.5	3.0
03/25/2010	17:11	597244	677109	N01	E04	TNBN	P2	BS	8.5	5.5
03/25/2010	17:23	598279	676635	N01	E04	TNBN	P3	AS	8.0	3.0
03/25/2010	17:21	598278	676627	N01	E04	TNBN	P3	BS	8.0	5.0
03/25/2010	18:07	589883	663889	N01	E04	TNBS	P1	AS	46.0	3.0
03/25/2010	18:04	589889	663885	N01	E04	TNBS	P1	BS	46.0	43.0
03/25/2010	18:19	590433	663603	N01	E04	TNBS	P2	AS	48.5	3.0
03/25/2010	18:17	590440	663601	N01	E04	TNBS	P2	BS	48.5	45.5
03/25/2010	18:18	590437	663606	N01	E04	TNBS	P2	BT	48.5	45.5
03/25/2010	18:29	591018	663346	N01	E04	TNBS	P3	AS	13.0	3.0
03/25/2010	18:27	591013	663343	N01	E04	TNBS	P3	BS	13.0	10.0
03/25/2010	18:28	591013	663341	N01	E04	TNBS	P3	BT	13.0	10.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
04/29/2010	16:43	605486	694144	N01	E05	THKN	P1	BS	35.0	33.0
04/29/2010	16:45	605488	694145	N01	E05	THKN	P1	AS	35.0	3.0
04/28/2010	16:37	596225	677628	N01	E05	TNBN	P1	BS	29.0	26.0
04/28/2010	16:42	596231	677619	N01	E05	TNBN	P1	AS	29.0	3.0
04/28/2010	16:42	596231	677619	N01	E05	TNBN	P1	AT	29.0	3.0
04/30/2010	15:32	589890	663884	N01	E05	TNBS	P1	BS	51.0	48.0
04/30/2010	15:34	589889	663882	N01	E05	TNBS	P1	AS	51.0	3.0
04/30/2010	12:55	595164	659798	N01	E05	TKVK	P1	BS	48.0	45.0
04/30/2010	12:57	595165	659797	N01	E05	TKVK	P1	AS	48.0	3.0
04/29/2010	13:03	579791	660669	N01	E05	TARK	P1	BS	41.0	38.0
04/29/2010	13:05	579795	660663	N01	E05	TARK	P1	AS	41.0	3.0
05/03/2010	12:40	605482	694151	N01	E07	THKN	P1	BS	29.0	26.0
05/03/2010	12:43	605482	694138	N01	E07	THKN	P1	AS	29.0	3.0
05/03/2010	12:50	605569	693975	N01	E07	THKN	P2	BS	28.0	25.0
05/03/2010	12:51	605573	693973	N01	E07	THKN	P2	AS	28.0	3.0
05/03/2010	12:58	605669	693808	N01	E07	THKN	P3	BS	23.0	20.0
05/03/2010	12:59	605662	693794	N01	E07	THKN	P3	AS	23.0	3.0
05/03/2010	12:40	596223	677617	N01	E07	TNBN	P1	BS	31.2	28.2
05/03/2010	12:42	596224	677618	N01	E07	TNBN	P1	BT	31.2	28.2
05/03/2010	12:43	596224	677615	N01	E07	TNBN	P1	AS	31.2	3.0
05/03/2010	12:55	597246	677107	N01	E07	TNBN	P2	BS	9.3	6.3
05/03/2010	12:57	597249	677106	N01	E07	TNBN	P2	AS	9.3	3.0
05/03/2010	13:06	598282	676634	N01	E07	TNBN	P3	BS	8.6	5.6
05/03/2010	13:08	598281	676634	N01	E07	TNBN	P3	AS	8.6	3.0
05/03/2010	13:11	598282	676635	N01	E07	TNBN	P3	AT	8.6	3.0
05/03/2010	13:51	589885	663883	N01	E07	TNBS	P1	BS	50.2	47.2
05/03/2010	13:55	589886	663882	N01	E07	TNBS	P1	AS	50.2	3.0
05/03/2010	14:19	590445	663602	N01	E07	TNBS	P2	BS	52.4	49.4
05/03/2010	14:21	590444	663599	N01	E07	TNBS	P2	AS	52.4	3.0
05/03/2010	14:07	591017	663342	N01	E07	TNBS	P3	BS	13.5	10.5
05/03/2010	14:09	591018	663334	N01	E07	TNBS	P3	AS	13.5	3.0
05/03/2010	14:40	595168	659801	N01	E07	TKVK	P1	BS	45.0	42.0
05/03/2010	14:42	595162	659803	N01	E07	TKVK	P1	AS	45.0	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
05/03/2010	14:50	595170	659374	N01	E07	TKVK	P2	BS	57.0	54.0
05/03/2010	14:51	595167	659374	N01	E07	TKVK	P2	AS	57.0	3.0
05/03/2010	15:07	595171	659015	N01	E07	TKVK	P3	BS	57.3	54.3
05/03/2010	15:08	595172	659008	N01	E07	TKVK	P3	AS	57.3	3.0
05/03/2010	15:29	579790	660673	N01	E07	TARK	P1	BS	40.0	37.0
05/03/2010	15:32	579793	660675	N01	E07	TARK	P1	AS	40.0	3.0
05/03/2010	15:44	579872	660356	N01	E07	TARK	P2	BS	48.3	45.3
05/03/2010	15:48	579876	660355	N01	E07	TARK	P2	AS	48.3	3.0
05/03/2010	16:01	579959	660068	N01	E07	TARK	P3	BS	46.2	43.2
05/03/2010	16:03	579959	660071	N01	E07	TARK	P3	AS	46.2	3.0
05/03/2010	18:36	605471	694150	N01	E08	THKN	P1	BS	35.0	32.0
05/03/2010	18:41	605479	694150	N01	E08	THKN	P1	AS	35.0	3.0
05/03/2010	18:49	605567	693971	N01	E08	THKN	P2	BS	25.0	22.0
05/03/2010	18:50	605574	693968	N01	E08	THKN	P2	AS	25.0	3.0
05/03/2010	19:17	605665	693803	N01	E08	THKN	P3	BS	24.0	21.0
05/03/2010	19:20	605658	693809	N01	E08	THKN	P3	AS	24.0	3.0
05/03/2010	18:22	596225	677617	N01	E08	TNBN	P1	BS	33.3	30.3
05/03/2010	18:24	596229	677615	N01	E08	TNBN	P1	AS	33.3	3.0
05/03/2010	18:32	597243	677108	N01	E08	TNBN	P2	BS	11.0	8.0
05/03/2010	18:34	597243	677106	N01	E08	TNBN	P2	AS	11.0	3.0
05/03/2010	18:43	598280	676634	N01	E08	TNBN	P3	BS	9.8	6.8
05/03/2010	18:45	598282	676631	N01	E08	TNBN	P3	AS	9.8	3.0
05/03/2010	19:23	589887	663882	N01	E08	TNBS	P1	BS	48.0	45.0
05/03/2010	19:25	589886	663880	N01	E08	TNBS	P1	AS	48.0	3.0
05/03/2010	19:37	590442	663597	N01	E08	TNBS	P2	BS	51.6	48.6
05/03/2010	19:38	590441	663601	N01	E08	TNBS	P2	AS	51.6	3.0
05/03/2010	19:47	591018	663336	N01	E08	TNBS	P3	BS	14.0	11.0
05/03/2010	19:49	591018	663337	N01	E08	TNBS	P3	AS	14.0	3.0
05/03/2010	20:13	595168	659800	N01	E08	TKVK	P1	BS	46.5	43.5
05/03/2010	20:14	595168	659801	N01	E08	TKVK	P1	BT	46.5	43.5
05/03/2010	20:17	595168	659803	N01	E08	TKVK	P1	AS	46.5	3.0
05/03/2010	20:26	595171	659373	N01	E08	TKVK	P2	BS	56.2	53.2
05/03/2010	20:28	595165	659377	N01	E08	TKVK	P2	AS	56.2	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
05/03/2010	20:41	595171	659008	N01	E08	TKVK	P3	BS	55.6	52.6
05/03/2010	20:43	595168	659010	N01	E08	TKVK	P3	AS	55.6	3.0
05/03/2010	21:04	579791	660670	N01	E08	TARK	P1	BS	36.0	33.0
05/03/2010	21:06	579793	660674	N01	E08	TARK	P1	AS	36.0	3.0
05/03/2010	21:17	579870	660351	N01	E08	TARK	P2	BS	46.0	43.0
05/03/2010	21:18	579875	660355	N01	E08	TARK	P2	AS	46.0	3.0
05/03/2010	21:26	579961	660068	N01	E08	TARK	P3	BS	43.4	40.4
05/03/2010	21:29	579958	660065	N01	E08	TARK	P3	AS	43.4	3.0
05/03/2010	21:30	579962	660072	N01	E08	TARK	P3	AT	43.4	3.0
04/29/2010	19:44	605481	694136	N01	E09	THKN	P1	BS	32.0	29.0
04/29/2010	19:46	605484	694134	N01	E09	THKN	P1	AS	32.0	3.0
04/28/2010	18:51	596226	677617	N01	E09	TNBN	P1	BS	30.0	27.0
04/28/2010	18:54	596230	677612	N01	E09	TNBN	P1	AS	30.0	3.0
04/30/2010	18:38	589884	663873	N01	E09	TNBS	P1	BS	48.0	45.0
04/30/2010	18:39	589888	663873	N01	E09	TNBS	P1	AS	48.0	3.0
04/30/2010	15:16	595171	659800	N01	E09	TKVK	P1	BS	49.0	46.0
04/30/2010	15:18	595171	659794	N01	E09	TKVK	P1	AS	49.0	3.0
04/29/2010	15:46	579795	660669	N01	E09	TARK	P1	BS	44.0	41.0
04/29/2010	15:48	579798	660669	N01	E09	TARK	P1	AS	44.0	3.0
04/29/2010	15:48	579798	660669	N01	E09	TARK	P1	AT	44.0	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
05/23/2010	14:51	605479	694137	N01	E10	THKN	P1	BS	33.0	30.0
05/23/2010	14:53	605479	694134	N01	E10	THKN	P1	AS	33.0	3.0
05/22/2010	15:57	596228	677620	N01	E10	TNBN	P1	BS	32.0	29.0
05/22/2010	15:58	596228	677614	N01	E10	TNBN	P1	AS	32.0	3.0
05/21/2010	15:41	589889	663883	N01	E10	TNBS	P1	BS	50.0	47.0
05/21/2010	15:43	589893	663877	N01	E10	TNBS	P1	AS	50.0	3.0
05/21/2010	15:43	589893	663877	N01	E10	TNBS	P1	AT	50.0	3.0
05/22/2010	12:54	595169	659796	N01	E10	TKVK	P1	BS	44.5	41.5
05/22/2010	12:56	595173	659798	N01	E10	TKVK	P1	AS	44.5	3.0
05/21/2010	12:55	579794	660669	N01	E10	TARK	P1	BS	42.5	39.5
05/21/2010	12:57	579794	660672	N01	E10	TARK	P1	AS	42.5	3.0
05/24/2010	11:22	605451	694158	N01	E12	THKN	P1	BS	35	32
05/24/2010	11:28	605460	694156	N01	E12	THKN	P1	AS	35	3
05/24/2010	11:39	605561	693977	N01	E12	THKN	P2	BS	36	33
05/24/2010	11:41	605566	693972	N01	E12	THKN	P2	AS	36	3
05/24/2010	11:49	605668	693812	N01	E12	THKN	P3	BS	26	23
05/24/2010	11:51	605671	693808	N01	E12	THKN	P3	AS	26	3
05/24/2010	11:16	596222	677618	N01	E12	TNBN	P1	BS	26.0	23.0
05/24/2010	11:18	596223	677618	N01	E12	TNBN	P1	AS	26.0	3.0
05/24/2010	11:18	596223	677618	N01	E12	TNBN	P1	AT	26.0	3.0
05/24/2010	11:24	597243	677112	N01	E12	TNBN	P2	BS	10.0	7.0
05/24/2010	11:26	597247	677112	N01	E12	TNBN	P2	AS	10.0	3.0
05/24/2010	11:33	598278	676636	N01	E12	TNBN	P3	BS	9.5	6.5
05/24/2010	11:34	598279	676644	N01	E12	TNBN	P3	AS	9.5	3.0
05/24/2010	12:10	589887	663883	N01	E12	TNBS	P1	BS	50.0	47.0
05/24/2010	12:13	589890	663883	N01	E12	TNBS	P1	AS	50.0	3.0
05/24/2010	12:19	590443	663591	N01	E12	TNBS	P2	BS	52.0	49.0
05/24/2010	12:21	590440	663596	N01	E12	TNBS	P2	AS	52.0	3.0
05/24/2010	12:29	591014	663332	N01	E12	TNBS	P3	BS	14.0	11.0
05/24/2010	12:30	591013	663338	N01	E12	TNBS	P3	AS	14.0	3.0
05/24/2010	12:48	595170	659789	N01	E12	TKVK	P1	BS	47.0	44.0
05/24/2010	12:51	595167	659799	N01	E12	TKVK	P1	AS	47.0	3.0
05/24/2010	13:02	595169	659376	N01	E12	TKVK	P2	BS	56.0	53.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
05/24/2010	13:04	595167	659370	N01	E12	TKVK	P2	AS	56.0	3.0
05/24/2010	13:09	595165	659005	N01	E12	TKVK	P3	BS	55.0	52.0
05/24/2010	13:10	595163	659004	N01	E12	TKVK	P3	AS	55.0	3.0
05/24/2010	13:11	595163	659005	N01	E12	TKVK	P3	AT	55.0	3.0
05/24/2010	13:31	579791	660676	N01	E12	TARK	P1	BS	36.0	33.0
05/24/2010	13:32	579785	660673	N01	E12	TARK	P1	AS	36.0	3.0
05/24/2010	13:37	579877	660345	N01	E12	TARK	P2	BS	46.0	43.0
05/24/2010	13:38	579879	660351	N01	E12	TARK	P2	AS	46.0	3.0
05/24/2010	13:43	579962	660069	N01	E12	TARK	P3	BS	42.5	39.5
05/24/2010	13:45	579964	660074	N01	E12	TARK	P3	AS	42.5	3.0
05/24/2010	18:09	605458	694149	N01	E13	THKN	P1	BS	30	27
05/24/2010	18:10	605455	694154	N01	E13	THKN	P1	AS	30	3
05/24/2010	18:17	605562	693976	N01	E13	THKN	P2	BS	28	25
05/24/2010	18:18	605562	693976	N01	E13	THKN	P2	AS	28	3
05/24/2010	18:22	605673	693811	N01	E13	THKN	P3	BS	24	21
05/24/2010	18:23	605663	693815	N01	E13	THKN	P3	AS	24	3
05/24/2010	17:39	596224	677618	N01	E13	TNBN	P1	BS	28.0	25.0
05/24/2010	17:40	596228	677623	N01	E13	TNBN	P1	AS	28.0	3.0
05/24/2010	17:47	597242	677113	N01	E13	TNBN	P2	BS	7.5	4.5
05/24/2010	17:47	597236	677111	N01	E13	TNBN	P2	BT	7.5	4.5
05/24/2010	17:48	597241	677115	N01	E13	TNBN	P2	AS	7.5	3.0
05/24/2010	17:55	598283	676634	N01	E13	TNBN	P3	BS	6.5	3.5
05/24/2010	17:56	598283	676636	N01	E13	TNBN	P3	AS	6.5	3.0
05/24/2010	18:27	589883	663885	N01	E13	TNBS	P1	BS	48.5	45.5
05/24/2010	18:29	589887	663882	N01	E13	TNBS	P1	AS	48.5	3.0
05/24/2010	18:29	589885	663885	N01	E13	TNBS	P1	AT	48.5	3.0
05/24/2010	18:35	590448	663601	N01	E13	TNBS	P2	BS	51.0	48.0
05/24/2010	18:36	590447	663605	N01	E13	TNBS	P2	AS	51.0	3.0
05/24/2010	18:41	591024	663338	N01	E13	TNBS	P3	BS	14.0	11.0
05/24/2010	18:43	591012	663343	N01	E13	TNBS	P3	AS	14.0	3.0
05/24/2010	19:04	595167	659803	N01	E13	TKVK	P1	BS	41.0	38.0
05/24/2010	19:06	595163	659794	N01	E13	TKVK	P1	AS	41.0	3.0
05/24/2010	19:17	595169	659365	N01	E13	TKVK	P2	BS	56.5	53.5

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
05/24/2010	19:19	595163	659370	N01	E13	TKVK	P2	AS	56.5	3.0
05/24/2010	19:23	595170	659001	N01	E13	TKVK	P3	BS	56.0	53.0
05/24/2010	19:25	595170	659006	N01	E13	TKVK	P3	AS	56.0	3.0
05/24/2010	19:25	595165	659003	N01	E13	TKVK	P3	AT	56.0	3.0
05/24/2010	19:43	579789	660675	N01	E13	TARK	P1	BS	40.0	37.0
05/24/2010	19:45	579788	660673	N01	E13	TARK	P1	AS	40.0	3.0
05/24/2010	19:52	579872	660354	N01	E13	TARK	P2	BS	48.5	45.5
05/24/2010	19:54	579875	660347	N01	E13	TARK	P2	AS	48.5	3.0
05/24/2010	19:58	579967	660068	N01	E13	TARK	P3	BS	47.5	44.5
05/24/2010	20:00	579970	660071	N01	E13	TARK	P3	AS	47.5	3.0
05/23/2010	16:47	605480	694136	N01	E14	THKN	P1	BS	33.5	30.5
05/23/2010	16:48	605482	694134	N01	E14	THKN	P1	AS	33.5	3.0
05/22/2010	18:03	596231	677616	N01	E14	TNBN	P1	BS	37.0	34.0
05/22/2010	18:04	596232	677615	N01	E14	TNBN	P1	AS	37.0	3.0
05/21/2010	18:04	589889	663884	N01	E14	TNBS	P1	BS	49.0	46.0
05/21/2010	18:06	589887	663876	N01	E14	TNBS	P1	AS	49.0	3.0
05/22/2010	15:22	595163	659797	N01	E14	TKVK	P1	BS	43.0	40.0
05/22/2010	15:24	595167	659809	N01	E14	TKVK	P1	AS	43.0	3.0
05/21/2010	15:25	579793	660669	N01	E14	TARK	P1	BS	40.0	37.0
05/21/2010	15:27	579791	660672	N01	E14	TARK	P1	AS	40.0	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
06/21/2010	14:15	605477	694134	N01	E15	THKN	P1	BS	33.1	30.1
06/21/2010	14:17	605477	694133	N01	E15	THKN	P1	AS	33.1	3.0
06/20/2010	16:02	596227	677619	N01	E15	TNBN	P1	BS	27.8	24.8
06/20/2010	16:04	596227	677620	N01	E15	TNBN	P1	AS	27.8	3.0
06/19/2010	15:42	589887	663874	N01	E15	TNBS	P1	BS	44.0	41.0
06/19/2010	15:44	589886	663878	N01	E15	TNBS	P1	AS	44.0	3.0
06/19/2010	15:44	589886	663878	N01	E15	TNBS	P1	AT	44.0	3.0
06/20/2010	12:36	595169	659802	N01	E15	TKVK	P1	BS	43.1	40.1
06/20/2010	12:37	595164	659801	N01	E15	TKVK	P1	AS	43.1	3.0
06/19/2010	12:46	579773	660688	N01	E15	TARK	P1	BS	31.7	28.7
06/19/2010	12:47	579772	660691	N01	E15	TARK	P1	AS	31.7	3.0
06/22/2010	11:20	605451	694146	N01	E17	THKN	P1	BS	31.0	28.0
06/22/2010	11:23	605453	694152	N01	E17	THKN	P1	AS	31.0	3.0
06/22/2010	11:33	605565	693983	N01	E17	THKN	P2	BS	35.0	32.0
06/22/2010	11:35	605569	693985	N01	E17	THKN	P2	AS	35.0	3.0
06/22/2010	11:42	605673	693815	N01	E17	THKN	P3	BS	24.0	21.0
06/22/2010	11:43	605671	693811	N01	E17	THKN	P3	AS	24.0	3.0
06/22/2010	11:44	605673	693813	N01	E17	THKN	P3	AT	24.0	3.0
06/22/2010	11:02	596226	677618	N01	E17	TNBN	P1	BS	38.0	35.0
06/22/2010	11:04	596228	677617	N01	E17	TNBN	P1	AS	38.0	3.0
06/22/2010	11:19	597251	677113	N01	E17	TNBN	P2	BS	11.0	8.0
06/22/2010	11:19	597243	677109	N01	E17	TNBN	P2	AS	11.0	3.0
06/22/2010	11:28	598285	676629	N01	E17	TNBN	P3	BS	10.0	7.0
06/22/2010	11:29	598282	676635	N01	E17	TNBN	P3	AS	10.0	3.0
06/22/2010	12:10	589880	663881	N01	E17	TNBS	P1	BS	48.0	45.0
06/22/2010	12:13	589879	663889	N01	E17	TNBS	P1	AS	48.0	3.0
06/22/2010	12:18	590437	663607	N01	E17	TNBS	P2	BS	52.0	49.0
06/22/2010	12:19	590439	663598	N01	E17	TNBS	P2	AS	52.0	3.0
06/22/2010	12:25	591016	663342	N01	E17	TNBS	P3	BS	13.0	10.0
06/22/2010	12:25	591019	663337	N01	E17	TNBS	P3	BT	13.0	10.0
06/22/2010	12:26	591017	663343	N01	E17	TNBS	P3	AS	13.0	3.0
06/22/2010	12:52	595171	659799	N01	E17	TKVK	P1	BS	49.0	46.0
06/22/2010	12:55	595163	659800	N01	E17	TKVK	P1	AS	49.0	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
06/22/2010	12:59	595172	659376	N01	E17	TKVK	P2	BS	56.0	53.0
06/22/2010	13:01	595168	659370	N01	E17	TKVK	P2	AS	56.0	3.0
06/22/2010	13:06	595173	659009	N01	E17	TKVK	P3	BS	55.0	51.0
06/22/2010	13:08	595163	659008	N01	E17	TKVK	P3	AS	55.0	3.0
06/22/2010	13:27	579788	660678	N01	E17	TARK	P1	BS	37.0	34.0
06/22/2010	13:28	579787	660676	N01	E17	TARK	P1	AS	37.0	3.0
06/22/2010	13:33	579879	660357	N01	E17	TARK	P2	BS	47.0	44.0
06/22/2010	13:34	579872	660350	N01	E17	TARK	P2	AS	47.0	3.0
06/22/2010	13:38	579959	660068	N01	E17	TARK	P3	BS	44.0	41.0
06/22/2010	13:40	579964	660076	N01	E17	TARK	P3	AS	44.0	3.0
06/22/2010	17:44	605455	694146	N01	E18	THKN	P1	BS	29.0	26.0
06/22/2010	17:45	605455	694149	N01	E18	THKN	P1	AS	29.0	3.0
06/22/2010	17:52	605569	693982	N01	E18	THKN	P2	BS	28.0	25.0
06/22/2010	17:54	605569	693983	N01	E18	THKN	P2	AS	28.0	3.0
06/22/2010	17:58	605670	693815	N01	E18	THKN	P3	BS	25.0	22.0
06/22/2010	18:00	605670	693814	N01	E18	THKN	P3	AS	25.0	3.0
06/22/2010	17:39	596227	677621	N01	E18	TNBN	P1	BS	28.0	25.0
06/22/2010	17:40	596227	677617	N01	E18	TNBN	P1	AS	28.0	3.0
06/22/2010	17:46	597241	677109	N01	E18	TNBN	P2	BS	9.0	6.0
06/22/2010	17:47	597250	677115	N01	E18	TNBN	P2	AS	9.0	3.0
06/22/2010	17:53	598282	676630	N01	E18	TNBN	P3	BS	9.0	6.0
06/22/2010	17:54	598286	676639	N01	E18	TNBN	P3	BT	9.0	6.0
06/22/2010	17:55	598277	676635	N01	E18	TNBN	P3	AS	9.0	3.0
06/22/2010	17:55	598278	676633	N01	E18	TNBN	P3	AT	9.0	3.0
06/22/2010	18:28	589885	663892	N01	E18	TNBS	P1	BS	45.0	42.0
06/22/2010	18:29	589887	663891	N01	E18	TNBS	P1	AS	45.0	3.0
06/22/2010	18:34	590442	663601	N01	E18	TNBS	P2	BS	52.0	49.0
06/22/2010	18:35	590436	663606	N01	E18	TNBS	P2	AS	52.0	3.0
06/22/2010	18:40	591019	663333	N01	E18	TNBS	P3	BS	15.0	12.0
06/22/2010	18:41	591016	663344	N01	E18	TNBS	P3	AS	15.0	3.0
06/22/2010	19:02	595166	659799	N01	E18	TKVK	P1	BS	46.0	43.0
06/22/2010	19:04	595170	659803	N01	E18	TKVK	P1	AS	46.0	3.0
06/22/2010	19:09	595161	659376	N01	E18	TKVK	P2	BS	58.0	55.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
06/22/2010	19:10	595166	659384	N01	E18	TKVK	P2	AS	58.0	3.0
06/22/2010	19:15	595164	659011	N01	E18	TKVK	P3	BS	57.0	54.0
06/22/2010	19:17	595167	659011	N01	E18	TKVK	P3	AS	57.0	3.0
06/22/2010	19:34	579796	660671	N01	E18	TARK	P1	BS	38.0	35.0
06/22/2010	19:34	579794	660671	N01	E18	TARK	P1	BT	38.0	35.0
06/22/2010	19:36	579799	660674	N01	E18	TARK	P1	AS	38.0	3.0
06/22/2010	19:40	579873	660356	N01	E18	TARK	P2	BS	50.0	47.0
06/22/2010	19:42	579878	660359	N01	E18	TARK	P2	AS	50.0	3.0
06/22/2010	19:47	579969	660074	N01	E18	TARK	P3	BS	48.0	45.0
06/22/2010	19:48	579960	660069	N01	E18	TARK	P3	AS	48.0	3.0
06/21/2010	16:02	605477	694138	N01	E19	THKN	P1	BS	34.1	31.1
06/21/2010	16:04	605479	694135	N01	E19	THKN	P1	AS	34.1	3.0
06/20/2010	18:02	596226	677623	N01	E19	TNBN	P1	BS	40.3	37.3
06/20/2010	18:04	596225	677621	N01	E19	TNBN	P1	AS	40.3	3.0
06/19/2010	18:18	589886	663878	N01	E19	TNBS	P1	BS	49.8	46.8
06/19/2010	18:20	589885	663881	N01	E19	TNBS	P1	AS	49.8	3.0
06/20/2010	15:24	595161	659802	N01	E19	TKVK	P1	BS	44.2	41.2
06/20/2010	15:26	595159	659800	N01	E19	TKVK	P1	AS	44.2	3.0
06/19/2010	15:28	579774	660689	N01	E19	TARK	P1	BS	34.0	33.0
06/19/2010	15:29	579771	660692	N01	E19	TARK	P1	AS	34.0	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
07/21/2010	11:13	605455	694146	N01	E21	THKN	P1	BS	31.0	28.0
07/21/2010	11:16	605458	694150	N01	E21	THKN	P1	AS	31.0	3.0
07/21/2010	11:25	605562	693980	N01	E21	THKN	P2	BS	30.0	27.0
07/21/2010	11:26	605558	693983	N01	E21	THKN	P2	AS	30.0	3.0
07/21/2010	11:31	605672	693815	N01	E21	THKN	P3	BS	27.0	24.0
07/21/2010	11:32	605668	693811	N01	E21	THKN	P3	AS	27.0	3.0
07/21/2010	11:33	605672	693811	N01	E21	THKN	P3	AT	27.0	3.0
07/21/2010	10:48	596227	677612	N01	E21	TNBN	P1	BS	32.5	29.5
07/21/2010	10:50	596225	677617	N01	E21	TNBN	P1	AS	32.5	3.0
07/21/2010	10:58	597246	677114	N01	E21	TNBN	P2	BS	11.0	8.0
07/21/2010	11:00	597243	677106	N01	E21	TNBN	P2	AS	11.0	3.0
07/21/2010	11:06	598283	676632	N01	E21	TNBN	P3	BS	10.0	7.0
07/21/2010	11:07	598276	676631	N01	E21	TNBN	P3	AS	10.0	3.0
07/21/2010	11:44	589888	663882	N01	E21	TNBS	P1	BS	50.0	47.0
07/21/2010	11:44	589886	663886	N01	E21	TNBS	P3	BT	50.0	47.0
07/21/2010	11:46	589879	663882	N01	E21	TNBS	P1	AS	50.0	3.0
07/21/2010	11:52	590435	663600	N01	E21	TNBS	P2	BS	52.0	49.0
07/21/2010	11:54	590439	663611	N01	E21	TNBS	P2	AS	52.0	3.0
07/21/2010	11:59	591013	663337	N01	E21	TNBS	P3	BS	14.0	11.0
07/21/2010	12:01	591017	663333	N01	E21	TNBS	P3	AS	14.0	3.0
07/21/2010	12:17	595169	659797	N01	E21	TKVK	P1	BS	47.0	44.0
07/21/2010	12:20	595171	659792	N01	E21	TKVK	P1	AS	47.0	3.0
07/21/2010	12:25	595165	659369	N01	E21	TKVK	P2	BS	56.0	53.0
07/21/2010	12:27	595164	659371	N01	E21	TKVK	P2	AS	56.0	3.0
07/21/2010	12:33	595169	659007	N01	E21	TKVK	P3	BS	55.0	52.0
07/21/2010	12:35	595172	659003	N01	E21	TKVK	P3	AS	55.0	3.0
07/21/2010	12:54	579791	660680	N01	E21	TARK	P1	BS	39.0	36.0
07/21/2010	12:57	579798	660674	N01	E21	TARK	P1	AS	39.0	3.0
07/21/2010	13:02	579873	660358	N01	E21	TARK	P2	BS	45.0	42.0
07/21/2010	13:02	579872	660359	N01	E21	TARK	P2	BT	45.0	42.0
07/21/2010	13:04	579869	660349	N01	E21	TARK	P2	AS	45.0	3.0
07/21/2010	13:08	579961	660067	N01	E21	TARK	P3	BS	43.0	40.0
07/21/2010	13:10	579963	660075	N01	E21	TARK	P3	AS	43.0	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
07/21/2010	17:26	605483	694142	N01	E22	THKN	P1	BS	34.0	31.0
07/21/2010	17:27	605479	694143	N01	E22	THKN	P1	AS	34.0	3.0
07/21/2010	17:32	605565	693974	N01	E22	THKN	P2	BS	28.0	25.0
07/21/2010	17:32	605562	693977	N01	E22	THKN	P2	AS	28.0	3.0
07/21/2010	17:38	605669	693811	N01	E22	THKN	P3	BS	25.0	22.0
07/21/2010	17:39	605672	693813	N01	E22	THKN	P3	AS	25.0	3.0
07/21/2010	17:13	596229	677617	N01	E22	TNBN	P1	BS	35.0	32.0
07/21/2010	17:15	596224	677615	N01	E22	TNBN	P1	AS	35.0	3.0
07/21/2010	17:21	597249	677116	N01	E22	TNBN	P2	BS	9.5	6.5
07/21/2010	17:23	597251	677108	N01	E22	TNBN	P2	AS	9.5	3.0
07/21/2010	17:28	598288	676635	N01	E22	TNBN	P3	BS	8.0	5.0
07/21/2010	17:30	598278	676635	N01	E22	TNBN	P3	AS	8.0	3.0
07/21/2010	18:04	589894	663884	N01	E22	TNBS	P1	BS	49.5	46.5
07/21/2010	18:07	589890	663886	N01	E22	TNBS	P1	AS	49.5	3.0
07/21/2010	18:13	590448	663604	N01	E22	TNBS	P2	BS	52.0	49.0
07/21/2010	18:15	590450	663602	N01	E22	TNBS	P2	AS	52.0	3.0
07/21/2010	18:20	591019	663342	N01	E22	TNBS	P3	BS	15.0	12.0
07/21/2010	18:21	591018	663334	N01	E22	TNBS	P3	AS	15.0	3.0
07/21/2010	18:22	591014	663333	N01	E22	TNBS	P3	AT	15.0	3.0
07/21/2010	18:43	595163	659801	N01	E22	TKVK	P1	BS	45.0	42.0
07/21/2010	18:47	595166	659799	N01	E22	TKVK	P1	AS	45.0	3.0
07/21/2010	18:51	595160	659368	N01	E22	TKVK	P2	BS	58.0	55.0
07/21/2010	18:53	595165	659374	N01	E22	TKVK	P2	AS	58.0	3.0
07/21/2010	19:02	595167	659008	N01	E22	TKVK	P3	BS	57.0	54.0
07/21/2010	19:03	595166	659015	N01	E22	TKVK	P3	AS	57.0	3.0
07/21/2010	19:22	579796	660681	N01	E22	TARK	P1	BS	35.0	32.0
07/21/2010	19:24	579791	660676	N01	E22	TARK	P1	AS	35.0	3.0
07/21/2010	19:28	579874	660353	N01	E22	TARK	P2	BS	49.0	46.0
07/21/2010	19:30	579871	660349	N01	E22	TARK	P2	AS	49.0	3.0
07/21/2010	19:36	579957	660072	N01	E22	TARK	P3	BS	48.0	45.0
07/21/2010	19:39	579961	660070	N01	E22	TARK	P3	AS	48.0	3.0
07/26/2010	14:11	605482	694139	N01	E23	THKN	P1	BS	38.0	35.0
07/26/2010	14:12	605480	694137	N01	E23	THKN	P1	AS	38.0	3.0

Date	Time (UTC)	Easting (ft)	Northing (ft)	Program	Event	Transect	Station	Depth-Type	Water Depth (ft)	Sample Depth (ft)
07/24/2010	12:50	596229	677614	N01	E23	TNBN	P1	BS	36.5	3.0
07/24/2010	12:52	596230	677615	N01	E23	TNBN	P1	AS	36.5	33.5
07/25/2010	12:31	589887	663874	N01	E23	TNBS	P1	BS	53.0	50.0
07/25/2010	12:32	589880	663884	N01	E23	TNBS	P1	AS	53.0	3.0
07/25/2010	12:32	589878	663883	N01	E23	TNBS	P1	AT	53.0	3.0
07/25/2010	12:41	595166	659800	N01	E23	TKVK	P1	BS	49.0	46.0
07/25/2010	12:43	595163	659796	N01	E23	TKVK	P1	AS	49.0	3.0
07/24/2010	13:09	579779	660692	N01	E23	TARK	P1	BS	34.0	31.0
07/24/2010	13:10	579779	660689	N01	E23	TARK	P1	AS	34.0	3.0

APPENDIX 2: Survey Equipment, Procedures & Data Processing

- Survey Vessel Navigation
- YSI Environmental 6920 Sondes
- Acoustic Doppler Current Profilers
- CTD-Turbidity Vertical Profiling
- Manufacturer's Equipment Specification Sheets

Survey Vessel Navigation

A Differential Global Positioning System (DGPS) interfaced with the PC-based hydrographic software package HYPACK was used for survey-vessel navigation and positioning. The global positioning system consists of 24 earth-orbiting satellites, which broadcast radio signals to the surface. These signals are used by the GPS receiver to calculate its position based on the signal time delay. Four or more satellite signals are required to accurately calculate the receiver's position. Differential correctors, used to increase vessel position accuracy to ± 1 meter, were received from a USCG beacon transmitter via a radio link. The geodetic positions derived from the DGPS system were converted to the NJ State Plane Coordinate system, East zone (NAD83, feet) for survey operations and preparation of final products.

The OSI navigation system consists of a portable personal computer with HYPACK software installed. Geodetic coordinate information from the DGPS was updated at one-second intervals and input to the navigation computer, which processed the geodetic position data into State Plane Coordinates used to guide the survey vessel. The incoming data are logged on disk and processed in real time allowing the vessel position to be displayed on a video monitor and compared to pre-plotted trackline and positions as the survey progresses. Digitized shoreline and the locations of existing structures, buoys, and control points can also be displayed on the monitor in relation to the vessel position. This system provides a highly accurate visual representation of survey vessel location in real time, combined with data logging capabilities and post-survey data processing and plotting.

YSI Environmental 6920 Sonde

The YSI 6920 Sondes (dataloggers) are self-contained microprocessors that record conductivity and temperature, from which salinity was calculated. The temperature probe utilizes sintered metallic oxides, which change resistance with temperature variations. These thermistors are accurate to +/- 0.15 ºC. Specific conductance is calculated through a direct relationship between water temperature and conductivity. The conductivity of a solution is

measured through a cell with four pure nickel electrodes. Two electrodes are current driven, and two are used to measure the voltage drop. The measured voltage drop is then converted into a conductance value. The accuracy of the conductance readings is 0.5%. Turbidity data were recorded using the 6136 fouling-resistant turbidity sensor. It provides accurate *in situ* measurements of turbidity in fresh, brackish, and saltwater, and features a mechanical self-wiping capability for long-term monitoring. The turbidity probe is accurate to +/-2% of the reading or 0.3 NTU, whichever is greater. Long-term deployments with these sensors, as part of YSI's submersible, multi-parameter water quality monitoring systems, have demonstrated constant measurement accuracy and stability.

The raw data from the dataloggers were downloaded in a binary form and converted to engineering units in YSI's EcoWatch software. The data were then transferred and processed in Microsoft Excel where salinity were calculated from the recorded temperature and conductivity data.

Acoustic Doppler Current Profilers (ADCPs)

Three self-contained, internally logging Acoustic Doppler Current Profilers (ADCPs) were deployed in an upward looking configuration on an OSI-designed bottom mount equipped with a gimble to accommodate slope at the deployment site. The ADCPs were programmed to measure and record water velocity profiles at 12-minute intervals with a vertical resolution of 0.5 meters. The ADCP contains four transducers that simultaneously transmit and receive sonic pulses at sound frequencies of 600 kHz or 1200 kHz, depending on the selected instrument. The transducer faces are angled 20° away from vertical and are evenly spaced around the head of the instrument in a "Janus" configuration.

To measure water velocity, the instrument sends out a coded series of sonic pulses (a ping) at a predetermined rate and measures the Doppler shift of these pings as they reflect off particles suspended in the water column. (On average, suspended particles move with the same velocity as the water in which they are suspended). Data from a minimum of three

transducers are required to calculate a three-dimensional current vector from the measurements of Doppler shift. The fourth transducer provides redundant data which aids in reducing errors in the vertical component of velocity and helps to ensure that there are at least three beams available to compute the horizontal components of velocity at all times.

Single ping velocity errors are too large to meet most measurement requirements. Therefore, many pings are averaged into ping ensembles. After a preset number of pings (an ensemble) is transmitted and received, these measurements are averaged over the length of the ensemble.

By range-gating the echo signal, the ADCP divides the velocity profile into uniform segments called depth cells (or bins). Unlike conventional eularian current meters, ADCPs do not make point measurements of small, localized volumes of water at individual depths. Instead, they perform a weighted average of the velocity field over a depth range slightly larger than the nominal thickness of an entire depth cell. Data collected from the center of each cell are more heavily weighted than data collected at the overlapping fringes of each cell. Averaging the velocity field in this way reduces measurement uncertainty and spatial aliasing. Furthermore, the overlapping nature of the depth cells combined with the weighted averaging within the cells ensures complete water column coverage and presents a smoother, more representative current profile.

CTD-Turbidity Vertical Profiling

Conductivity, temperature, turbidity, and pH data were collected using a Sea-Bird Electronics, Inc. Model SBE 19 SEACAT Profiler. The SEACAT Profiler is a self-powered, self-contained micro processing unit capable of collecting turbidity, temperature, salinity, and depth data at a rate of two scans per second. Data are internally processed, corrected, and recorded in solid-state memory and can later be transferred via an RS-232 port to a computer where the operator can view the data and archive it for future processing.

To collect a cast, the SEACAT was first lowered over the side of the vessel into the water where it was allowed to equilibrate with the surrounding water. The instrument was initialized and then lowered through the water column to the bottom. Once at the bottom, the SEACAT was held steady for one minute, then returned to the surface.

Water quality data collected by the SEACAT Profiler were downloaded to a computer and post-processed using Sea-Bird Electronics CTD Data Acquisition Software, Seasoft Version 4.238. The raw data were calibration corrected and reduced to listings of depth versus turbidity (NTU), temperature (°C), salinity (PSU), pH and calculated SSC.

DSM12/212 Product Family

Integrated, cost-effective and reliable sub-meter positioning for your marine application

Key features and benefits

- Compact
- Easy Installation
- High Position Output Rate With Low Latency
- Easy To Use & Setup
- Low Power Consumption
- Increased Jamming Resistance
- Optional Everest Multipath Rejection
- Isolated Power Supply

The DSM12/212 Product Family targets marine professionals in need of sub-meter positioning during applications such as precise positioning, dredging, hydrographic surveying, high speed vessel positioning, and many more.

Complete System Solution

The product family includes three mobile receivers and one reference station receiver:

- DSM12™ – DGPS receiver
- DSM212L™ – Integrated GPS/MSK receiver, 1Hz output
- DSM212H™ – Integrated GPS/MSK receiver, 10Hz output
- DSM12RS™ – DGPS Reference Station receiver

Cost Effective

The family of 12 channel GPS receivers use Trimble's latest technology to achieve sub-meter positioning accuracy. These receivers maintain their high performance in environments where GPS availability and accuracy are sometimes an issue. Everest™ technology improves results in high multipath environments and locations where other radio frequencies could jam the GPS signals such as harbors, oil platforms, and construction sites. The DSM12, DSM212L & DSM212H can all accept RTCM SC-104 differential corrections from an external source through a serial interface. The DSM212L & DSM212H also include an integrated dual-channel low-noise MSK beacon receiver.



Integrated GPS and dual-channel MSK beacon receiver, DSM212H

The MSK beacon receiver provides superior weak-signal reception performance, allowing differential corrections to be received at long distances from the reference station and during challenging weather conditions. The dual-channel capability allows for intelligent and seamless switching between beacons.

Superior Integration

The DSM12, DSM212L and DSM212H are easy to connect with other onboard equipment such as integrated bridge systems, radars, autopilots and plotters. Through one of the two serial ports, these receivers output standard NMEA-0183 messages, including position, velocity and status information. The DSM12 & DSM212L receivers output position reports once a second.

The DSM212H outputs position reports at an increased output rate of 10 Hz, with a maximum latency of 0.1 second. The second serial port is for setup, control and data output using Trimble Standard Interface Protocol (TSIP). For easy setup, a Windows-based Trimble Navigation software, TSIP Talker™ is included. The receivers also feature a 1 PPS output available on either serial port and offer a differential speed accuracy of better than 0.1 Knot.

Reference Station

The DSM12RS is a cost-effective solution for providing high quality DGPS corrections. The corrections are generated in the standard RTCM SC-104 format for broadcast.

Trimble

DSM12/212 Product Family

Integrated, cost-effective and reliable sub-meter positioning for your marine application

STANDARD FEATURES

Standard Configuration

- 12-channel GPS receiver
- Integrated GPS and dual channel MSK beacon receiver (DSM212L & DSM212H)
- External RTCM SC-104 input
- Isolated power supply
- Positioning based on carrier-phase filtered L1 pseudo-ranges
- Two programmable RS-232 serial ports:
  - NMEA-0183 output or RTCM SC-104 output
  - RTCM SC-104 input
  - TSIP Input & Output
- 1PPS output
- Windows Configuration software
- DSM12/212 Operation manual
- Compact L1 GPS antenna (DSM12)
- Compact L1 Geodetic GPS antenna with removable groundplane (DSM12RS)
- Combined L1 GPS and MSK H-field loop antenna (DSM212L & DSM212H)
- 15 meter RG58 antenna cable (DSM12, DSM212L, & DSM212H)
- 30 meter RG213 antenna cable (DSM12RS)
- Power/data cable
- 12Pin to Split I/O Cable (DSM12)
- 12Pin to Split RTCM Cable (DSM12RS)
- 12Pin to Data Cable (DSM212L & DSM212H)

PHYSICAL CHARACTERISTICS

Receiver

Size:	14.5cmW x 5.1cmH x 19.5cmD (5.7”W x 2.0”H x 7.7”D)
Weight:	0.76kg (1.68 lb.)
Power:	5W (max.), 10 to 32 VDC
Operating temp:	-30°C to +65°C
Storage temp:	-40°C to +85°C
Humidity:	100% condensing, unit fully sealed

Combined Antenna (DSM212L & DSM212H)

Size:	15cmD x 15.5cmH (5.8”D X 6.0”H)
Weight:	4.9kg (2.2 lb.)
Operating temp:	-40°C to +65°C
Humidity:	100%-fully sealed

Compact Dome Antenna (DSM12)

Size:	15.4cmD x 8.9cmH (6”D X 3.5”H)
Weight:	0.29kg (0.645 lb.)
Operating temp:	-40°C to +70°C
Humidity:	100%-fully sealed

Compact L1 Geodetic Antenna (DSM12RS)

Size:	48cmD x 9cmH (19”D X 3.5”H)
Weight:	2.6kg (5.7 lb.)
Operating temp:	-40°C to +65°C
Humidity:	100% - fully sealed

PERFORMANCE CHARACTERISTICS

GPS Receiver

General:	12-channel, parallel tracking, L1 C/A code with carrier phase filtered measurements and multi-bit digitizer
Output rate:	1 Hz standard (DSM12, DSM12RS, & DSM212L) 10 Hz standard (DSM212H)
Differential speed accuracy:	0.1 kn (0.1 MPH, 0.16 km/h, 5.6cm/s)*
Differential position accuracy:	Less than 1 meter horizontal RMS* (At least 5 satellites, PDOP <4 and RTCM SC-104 standard format broadcast from a Trimble DSM12RS or equivalent reference station.)
Time to first fix:	<30 seconds, typical
NMEA messages:	ALM, GGA**, GLL, GSA, GSV, VTG**, ZDA, RMC, MSS **Default messages

MSK beacon Dual-channel Receiver

Frequency range:	283.5 KHz to 325.0 KHz
Channel spacing:	500 Hz
MSK modulation:	50, 100 & 200 bits/second
Signal strength:	10 µV/meter minimum @ 100BPS
Dynamic range:	100 dB
Channel selectivity:	70 dB >500 Hz offset
Frequency offset:	17 ppm maximum
3rd order intercept:	+15 dBm @ RF input (min. AGC setting)
Beacon acquisition time:	<5 sec, typical

OPTIONS

- High Output Rate
- Everest Multipath Rejection
- Reference Station
- Carrier Phase Output
- Extended hardware warranty
- Firmware update service

*To achieve differential speed and position, the unit must be operating within the broadcast area of a reference station conforming to the International Association of Lighthouse Authorities Standards. All non-differential GPS receivers are subject to degradation of position and velocity accuracy under U.S. Department of Defense-imposed Selective Availability (S/A). Positions may be degraded up to 100 meters 2D RMS.

Trimble follows a policy of continuous product improvement. Specifications are thus subject to change without notice.

© March 1998, Trimble Navigation Limited. All rights reserved. Trimble with the Trimble logo is a registered trademark and DSM12, DSM212L, DSM212H, DSM12RS, Everest and TSIP Talker are trademarks of Trimble Navigation Limited, Sunnyvale, California, U.S.A. All other brand names, product names and trademarks belong to their respective owners. TID11202 (3/98)

Trimble
THE GPS SOLUTION

Trimble Navigation Limited
Corporate Headquarters
645 North Mary Avenue
Sunnyvale, CA 94086
+1-408-481-8000
+1-408-481-2000 Fax
www.trimble.com

Trimble Navigation Europe Limited
Trimble House,
Meridian Office Park
Osborne Way
Hook, Hampshire RG27 9HX U.K.
+44 1256-760-150
+44 1256-760-148 Fax

YSI Environmental

NEW

YSI 6820 and 6920 V2 Sondes

With 1 or 2 optical ports and new sensor options

The YSI 6820 V2-2 and 6920 V2-2 Sondes

Measure multiple parameters simultaneously including:

- Temperature
- Conductivity
- Specific Conductance
- Salinity
- Resistivity
- TDS
- pH
- ORP
- Depth or Level
- Nitrate, Ammonium or Chloride
- Rapid Pulse™ DO (V2-1 only)

And 1 or 2 of the following optical sensors:

- ROX™ Optical DO *NEW*
- Turbidity
- Chlorophyll
- Blue-Green Algae *NEW*
  (Phycocyanin or Phycoerythrin)
- Rhodamine

- **Two bulkhead versions available:**
  - **The 6820/6920 V2-1 has one optical port, conductivity/temperature port, Rapid Pulse™ DO port, pH/ORP port. and three ISE ports**
  - **The 6820/6920 V2-2 has two optical ports, conductivity/temperature port, pH/ORP port. and one ISE port**
- **Self-cleaning optical sensors with improved wiping**
- **Field-replaceable sensors**
- **6920 V2 has a built-in battery compartment for long-term *in situ* monitoring**

Take Advantage of YSI's New Optical Sensors

In addition to turbidity, chlorophyll, and rhodamine, YSI now offers these optical sensors:

ROX Reliable Optical Dissolved Oxygen

The ROX sensor uses lifetime luminescence detection technology to offer the most reliable oxygen sensor with the lowest possible maintenance effort. Experience significantly less membrane maintenance while obtaining excellent accuracy, sensitivity, and range.

ROX

Blue-Green Algae (BGA)

YSI's fluorescence-based blue-green algae sensors will allow you to monitor blue-green algae populations where their presence is a concern. Whether providing an early warning to an algal bloom, tracking taste and odor-causing species in drinking water supplies, or conducting ecosystem research; YSI BGA sensors will provide sensitive and reliable *in situ* data.

Pure Data for a Healthy Planet.®

Compact sondes for field sampling and data collection platforms

6820 and 6920 Upgrades Available

YSI is committed to offering our customers reliable and cost-effective water monitoring solutions. To this end, we are offering V2-2 Upgrades for existing 6820/6920s. Upgrades will be available from YSI Authorized Service Centers and will include the new 6820/6920 V2-2 bulkhead, an Optical Dissolved Oxygen Sensor, and firmware/software upgrades. In addition, the sonde will be fully tested and calibrated by an experienced YSI service technician.

To order, or for more info, contact YSI Environmental.

+1 937 767 7241
800 897 4151 (US)
www.ysi.com

YSI Environmental
+1 937 767 7241
Fax +1 937 767 9353
environmental@ysi.com

YSI Integrated Systems & Services
+1 508 748 0366
Fax +1 508 748 2543
systems@ysi.com

SonTek/YSI
+1 858 546 8327
Fax +1 858 546 8150
inquiry@sontek.com

YSI Gulf Coast
+1 225 753 2650
Fax +1 225 753 8669
environmental@ysi.com

YSI Hydrodata (UK)
+44 1462 673 581
Fax +44 1462 673 582
europe@ysi.com

YSI Middle East (Bahrain)
+973 1753 6222
Fax +973 1753 6333
halsalem@ysi.com

YSI (Hong Kong) Limited
+852 2891 8154
Fax +852 2834 0034
hongkong@ysi.com

YSI (China) Limited
+86 10 5203 9675
Fax +86 10 5203 9679
beijing@ysi-china.com

YSI Nanotech (Japan)
+81 44 222 0009
Fax +81 44 221 1102
nanotech@ysi.com

ISO 9001
ISO 14001
Yellow Springs, Ohio Facility

ROX and Rapid Pulse are trademarks and EcoWatch, Pure Data for a Healthy Planet and Who's Minding the Planet? are registered trademarks of YSI Incorporated.

©2006 YSI Incorporated
Printed in USA 0807 E36-03

CE

*Sensors with listed with the ETV logo were submitted to the ETV program on the YSI 6600EDS. Information on the performance characteristics of YSI water quality sensors can be found at www.epa.gov/etv, or call YSI at 800.897.4151 for the ETV verification report. Use of the ETV name or logo does not imply approval or certification of this product nor does it make any explicit or implied warranties or guarantees as to product performance.

YSI *incorporated*
Who's Minding the Planet?®

YSI 6820 V2 & 6920 V2 Sensor Specifications

	Range	Resolution	Accuracy
ROX™ Optical Dissolved Oxygen• % Saturation	0 to 500%	0.1%	0 to 200%: ±1% of reading or 1% air saturation, whichever is greater; 200 to 500%: ±15% of reading, relative to calibration gases
ROX™ Optical Dissolved Oxygen• mg/L	0 to 50 mg/L	0.01 mg/L	0 to 20 mg/L: ± 0.1 mg/L or 1% of reading, whichever is greater; 20 to 50 mg/L: ±15% of reading, relative to calibration gases
Dissolved Oxygen•• % Saturation ETV 6562 Rapid Pulse™ Sensor*	0 to 500%	0.1%	0 to 200%: ±2% of reading or 2% air saturation, whichever is greater; 200 to 500%: ±6% of reading
Dissolved Oxygen•• mg/L ETV 6562 Rapid Pulse™ Sensor*	0 to 50 mg/L	0.01 mg/L	0 to 20 mg/L: ± 0.2 mg/L or 2% of reading, whichever is greater; 20 to 50 mg/L: ±6% of reading
Conductivity••• ETV 6560 Sensor*	0 to 100 mS/cm	0.001 to 0.1 mS/cm (range dependent)	±0.5% of reading + 0.001 mS/cm
Salinity	0 to 70 ppt	0.01 ppt	±1% of reading or 0.1 ppt, whichever is greater
Temperature ETV 6560 Sensor*	-5 to +50°C	0.01°C	±0.15°C
pH ETV 6561 Sensor*	0 to 14 units	0.01 unit	±0.2 unit
ORP	-999 to +999 mV	0.1 mV	±20 mV
Depth Medium Shallow Vented Level	0 to 200 ft, 61 m 0 to 30 ft, 9.1 m 0 to 30 ft, 9.1 m	0.001 ft, 0.001 m 0.001 ft, 0.001 m 0.001 ft, 0.001 m	±0.4 ft, ±0.12 m ±0.06 ft, ±0.02 m ±0.01 ft, 0.003 m
Turbidity• ETV 6136 Sensor*	0 to 1,000 NTU	0.1 NTU	±2% of reading or 0.3 NTU, whichever is greater**
Nitrate/nitrogen••••	0 to 200 mg/L-N	0.001 to 1 mg/L-N (range dependent)	±10% of reading or 2 mg/L, whichever is greater
Ammonium/ammonia/ nitrogen••••	0 to 200 mg/L-N	0.001 to 1 mg/L-N (range dependent)	±10% of reading or 2 mg/L, whichever is greater
Chloride••••	0 to 1000 mg/L	0.001 to 1 mg/L (range dependent)	±15% of reading or 5 mg/L, whichever is greater
Rhodamine•	0-200 µg/L	0.1 µg/L	±5% reading or 1 µg/L, whichever is greater

• Maximum depth rating for all standard optical sensors is 200 feet, 61 m.
•• Rapid Pulse is only available on the 6820/6920 V2-1 (one optical port version)
••• Report outputs of specific conductance (conductivity corrected to 25° C), resistivity, and total dissolved solids are also provided. These values are automatically calculated from conductivity according to algorithms found in *Standard Methods for the Examination of Water and Wastewater* (ed 1989).
•••• Freshwater only, Maximum depth rating of 50 feet, 15.2 m. 6820/6920 V2-1 have 3 ISE ports, 6820/6920 V2-2 have 1 ISE port.

**In YSI AMCO-AEPA Polymer Standards.

	Range	Detection Limit	Resolution	Linearity
BGA - Phycocyanin•	~0 to 280,000 cells/mL† 0 to 100 RFU	~220 cells/mL§	1 cell/mL 0.1 RFU	$R^2 > 0.9999$**
BGA - Phycoerythrin•	~0 to 200,000 cells/mL† 0 to 100 RFU	~450 cells/mL§§	1 cell/mL 0.1 RFU	$R^2 > 0.9999$***
Chlorophyll• ETV 6025 Sensor*	~0 to 400 µg/L 0 to 100 RFU	~0.1 µg/L§§§	0.1 µg/L Chl 0.1% RFU	$R^2 > 0.9999$****

• Maximum depth rating for all standard optical probes is 200 feet, 61 m.
BGA = Blue-Green Algae
RFU = Relative Fluorescence Units
~ = Approximately

† Explanation of Ranges can be found in the 'Principles of Operation' section of the 6-Series Manual, Rev D.

§ Estimated from cultures of *Microcystis aeruginosa*.
§§ Estimated from cultures *Synechococcus sp.*
§§§ Determined from cultures of *Isochrysis sp.* and chlorophyll *a* concentration determined via extractions.

**Relative to serial dilution of Rhodamine WT (0-400 ug/L).
***Relative to serial dilution of Rhodamine WT (0-8 µg/L).
****Relative to serial dilution of Rhodamine WT (0-500 ug/L).

YSI 6820 V2 & 6920 V2 Sonde Specifications

Medium	Fresh, sea or polluted water	Software	EcoWatch®
Temperature Operating Storage	-5 to +50°C -10 to +60°C	Dimensions 6820 V2 I 6920 V2 Diameter Length Weight	2.86 in, 7.3 cm | 2.85 in, 7.24 cm 13.5 in, 34.3 cm | 18 in, 45.7 cm 3.4 lbs, 1.5 kg | 4 lbs, 1.8 kg
Communications	RS-232, SDI-12	Power External Internal	12 V DC 8 AA-size alkaline batteries

NEW

YSI 6600 V2 Sonde

With 2 or 4 optical ports and new sensor options

Make the most of your environmental monitoring efforts: The 6600 V2 sonde offers the most comprehensive water quality monitoring package available with simultaneous measurement of conductivity (salinity), temperature, depth or level, pH/ORP. The 6600 V2-4 also measures these parameters: dissolved oxygen, turbidity, chlorophyll, and blue-green algae; the V2-2 measures two of the four parameters simultaneously. Additional calculated parameters include total dissolved solids, resistivity, and specific conductance.

Take advantage of YSI's new optical sensor design and anti-fouling wiper control for improved reliability during extended deployments.

- **Self-cleaning optical sensors with integrated wipers remove biofouling and maintain high data accuracy**
- **Field-replaceable sensors make trips to the field quick**
- **Optimal power management and built-in battery compartment extends *in situ* monitoring periods**

Take Advantage of YSI's New Optical Sensors

In addition to turbidity, chlorophyll, and rhodamine, YSI now offers these optical sensors:

ROX Reliable Optical Dissolved Oxygen

The ROX sensor uses lifetime luminescence detection technology to offer the most reliable oxygen sensor with the lowest possible maintenance effort. The sensor is insensitive to hydrogen sulfide interference and does not require regular membrane changes.

Blue-Green Algae (BGA)

YSI's fluorescence-based blue-green algae sensors will allow you to monitor blue-green algae populations where their presence is a concern. Whether providing an early warning to an algal bloom, tracking taste and odor-causing species in drinking water supplies, or conducting ecosystem research, YSI BGA sensors will provide sensitive and reliable *in situ* data.

Complete Data Record

The YSI 6600 V2-4 Sonde, with 4 optical sensor ports, is the only instrument available to simultaneously measure dissolved oxygen, turbidity, chlorophyll, and blue-green algae!

Pure Data for a Healthy Planet.®

Upgraded sondes for rugged long-term deployment

*Sensor performance verified**

The 6600 V2 sonde uses sensor technology that was verified through the US EPA's Environmental Technology Verification Program (ETV). For information on which sensors were performance-verified, turn this sheet over and look for the ETV logo.

6600 Upgrades Available

YSI is committed to offering our customers reliable and cost-effective water monitoring solutions. To this end, we are offering V2 Upgrades for existing 6600s. Upgrades will be available from YSI Authorized Service Centers and will include the new 6600 V2 bulkhead, a ROX Optical Dissolved Oxygen Sensor, and firmware/software upgrades. In addition, the sonde will be fully tested and calibrated by an experienced YSI service technician.

YSI 6600 V2 Sensor Specifications

	Range	Resolution	Accuracy
ROX™ Optical Dissolved Oxygen• % Saturation	0 to 500%	0.1%	0 to 200%: ±1% of reading or 1% air saturation, whichever is greater; 200 to 500%: ±15% of reading
ROX™ Optical Dissolved Oxygen• mg/L	0 to 50 mg/L	0.01 mg/L	0 to 20 mg/L: ± 0.1 mg/L or 1% of reading, whichever is greater; 20 to 50 mg/L: ±15% of reading
Dissolved Oxygen•• % Saturation ETV 6562 Rapid Pulse™ Sensor*	0 to 500%	0.1%	0 to 200%: ±2% of reading or 2% air saturation, whichever is greater; 200 to 500%: ±6% of reading
Dissolved Oxygen•• mg/L ETV 6562 Rapid Pulse™ Sensor*	0 to 50 mg/L	0.01 mg/L	0 to 20 mg/L: ± 0.2 mg/L or 2% of reading, whichever is greater; 20 to 50 mg/L: ±6% of reading
Conductivity••• ETV 6560 Sensor*	0 to 100 mS/cm	0.001 to 0.1 mS/cm (range dependent)	±0.5% of reading + 0.001 mS/cm
Salinity	0 to 70 ppt	0.01 ppt	±1% of reading or 0.1 ppt, whichever is greater
Temperature ETV 6560 Sensor*	-5 to +50°C	0.01°C	±0.15°C
pH ETV 6561 Sensor*	0 to 14 units	0.01 unit	±0.2 unit
ORP	-999 to +999 mV	0.1 mV	±20 mV
Depth — Deep	0 to 656 ft, 200 m	0.001 ft, 0.001 m	±1 ft, ±0.3 m
Depth — Medium	0 to 200 ft, 61 m	0.001 ft, 0.001 m	±0.4 ft, ±0.12 m
Depth — Shallow	0 to 30 ft, 9.1 m	0.001 ft, 0.001 m	±0.06 ft, ±0.02 m
Depth — Vented Level	0 to 30 ft, 9.1 m	0.001 ft, 0.001 m	±0.01 ft, 0.003 m
Turbidity• ETV 6136 Sensor*	0 to 1,000 NTU	0.1 NTU	±2% of reading or 0.3 NTU, whichever is greater**
Nitrate/nitrogen••••	0 to 200 mg/L-N	0.001 to 1 mg/L-N (range dependent)	±10% of reading or 2 mg/L, whichever is greater
Ammonium/ammonia/ nitrogen••••	0 to 200 mg/L-N	0.001 to 1 mg/L-N (range dependent)	±10% of reading or 2 mg/L, whichever is greater
Chloride••••	0 to 1000 mg/L	0.001 to 1 mg/L (range dependent)	±15% of reading or 5 mg/L, whichever is greater
Rhodamine•	0-200 µg/L	0.1 µg/L	±5% reading or 1 µg/L, whichever is greater

• Maximum depth rating for all optical probes is 200 feet, 61 m. Turbidity and Rhodamine are also available in a Deep Depth option (0 to 200 m).
•• Rapid Pulse is only available on 6600 V2-2 (two optical ports version).
••• Report outputs of specific conductance (conductivity corrected to 25° C), resistivity, and total dissolved solids are also provided. These values are automatically calculated from conductivity according to algorithms found in *Standard Methods for the Examination of Water and Wastewater* (ed 1989).
•••• Freshwater only. Maximum depth rating of 50 feet, 15.2 m. 6600 V2-2 has 3 ISE ports; not available on the 6600V2-4.

**In YSI AMCO-AEPA Polymer Standards.

	Range	Detection Limit	Resolution	Linearity
Blue-Green Algae Phycocyanin•	~0 to 280,000 cells/mL† 0 to 100 RFU	~220 cells/mL§	1 cell/mL 0.1 RFU	$R^2 > 0.9999$**
Blue-Green Algae Phycoerythrin•	~0 to 200,000 cells/mL† 0 to 100 RFU	~450 cells/mL§§	1 cell/mL 0.1 RFU	$R^2 > 0.9999$***
Chlorophyll• ETV 6025 Sensor*	~0 to 400 µg/L 0 to 100 RFU	~0.1 µg/L§§§	0.1 µg/L Chl 0.1% RFU	$R^2 > 0.9999$****

• Maximum depth rating for all optical probes is 200 feet, 61 m. Also available in a Deep Depth option (0 to 200 m).
RFU = Relative Fluorescence Units

† Explanation of Ranges can be found in the 'Principles of Operation' section of the 6-Series Manual, Rev D.

§ Estimated from cultures of *Microcystis aeruginosa*.
§§ Estimated from cultures *Synechococcus sp*.
§§§ Determined from cultures of *Isochrysis sp.* and chlorophyll *a* concentration determined via extractions.

**For serial dilution of Rhodamine WT (0-400 ug/L).
***For serial dilution of Rhodamine WT (0-8 µg/L).
****For serial dilution of Rhodamine WT (0-500 ug/L).

YSI 6600 V2 Sonde Specifications

Medium	Fresh, sea or polluted water	Software	EcoWatch®
Temperature — Operating	-5 to +50°C	Dimensions — Diameter	3.5 in, 8.9 cm
Temperature — Storage	-10 to +60°C	Dimensions — Length, no depth	19.6 in, 49.8 cm
		Dimensions — Length, with depth	21.6 in, 54.9 cm
		Dimensions — Weight	7 lbs, 3.18 kg (batteries installed, with depth)
Communications	RS-232, SDI-12	Power — External	12 V DC
		Power — Internal	8 C-size alkaline batteries

To order, or for more info, contact YSI Environmental.

+1 937 767 7241
800 897 4151 (US)
www.ysi.com

YSI Environmental
+1 937 767 7241
Fax +1 937 767 9353
environmental@ysi.com

Endeco/YSI
+1 508 748 0366
Fax +1 508 748 2543
systems@ysi.com

SonTek/YSI
+1 858 546 8327
Fax +1 858 546 8150
inquiry@sontek.com

YSI Gulf Coast
+1 225 753 2650
Fax +1 225 753 8669
environmental@ysi.com

YSI Hydrodata (UK)
+44 1462 673 581
Fax +44 1462 673 582
europe@ysi.com

YSI Middle East (Bahrain)
+973 1753 6222
Fax +973 1753 6333
halsalem@ysi.com

YSI (Hong Kong) Limited
+852 2891 8154
Fax +852 2834 0034
hongkong@ysi.com

YSI (China) Limited
+86 10 5203 9675
Fax +86 10 5203 9679
beijing@ysi-china.com

YSI Nanotech (Japan)
+81 44 222 0009
Fax +81 44 221 1102
nanotech@ysi.com

ISO 9001
ISO 14001
Yellow Springs, Ohio Facility

ROX and Rapid Pulse are trademarks and EcoWatch, Pure Data for a Healthy Planet and Who's Minding the Planet? are registered trademarks of YSI Incorporated.

©2006 YSI Incorporated

Printed in USA 1206 E52-01

*Sensors with listed with ETV logo were submitted to the ETV program on the YSI 6600EDS. Information on performance characteristics of YSI water quality sensors can be found at www.epa.gov/etv, or call YSI at 800.897.4151 for the ETV verification report. Use of ETV name or logo does not imply approval or certification of this product nor does it make any explicit or implied warranties or guarantees as to product performance.

YSI incorporated
Who's Minding the Planet?®

Workhorse Sentinel ADCP

Self-Contained 1200, 600 or 300 kHz

Our most popular instrument. Over 1000 Workhorse Sentinel ADCPs are profiling currents in 50 countries. Our customers choose it for its unbeatable precision in shallow waters, for its 175-meter profiling range and for an unmatched low power consumption that makes it ideal for year-long deployments.

Customers tell us they like it because it's light and easy to deploy on buoys, boats or on the bottom. Links to shore are by cable or modem and Sentinel is easily upgraded to measure pressure, to undertake bottom-tracking tasks or to be used as a directional wave gauge.

			Long Range Mode	
Frequency	Range	Cell Size	Range	Cell Size
1200 kHz	14m	1m	19m	2m
600 kHz	47m	2m	67m	4m
300 kHz	126m	8m	165m	8m

RD Instruments
Tel: (858) 693-1178
sales@rdinstruments.com

RD Instruments

www.rdinstruments.com

Included in a complete system:

Transducer and electronics: molded composite plastic transducer head with four beams at 20° from vertical in a convex configuration, temperature sensor, electronics assemblies, fluxgate compass, pitch and roll sensors.

Batteries: one 28-D cell alkaline battery pack (factory degaussed).

Memory: 10 MB PC card internal memory (upgradeable to 440Mb).

Pressure case: composite plastic, 200m rated. End cap with wet-mateable connector and dummy plug.

Power supply for laboratory testing: 110-220V AC/24V DC power converter.

Input/output cable: 5 meter cable for communications and power.

Manuals and software: users guide; operation manual and easy-to-use Windows software package.

Spares parts and tool kit for maintenance.

Ship case: ruggedized compact case.

Workhorse Sentinel ADCP 1200, 600 or 300 kHz

Water Profiling

Depth Cell Size[a]	Typical range 12m[b] 1200kHz		Typical range 50m[b] 600kHz		Typical range 110m[b] 300kHz	
Vertical Resolution	Range (m)	Std. Dev.[c] (mm/s)	Range (m)	Std. Dev.[c] (mm/s)	Range (m)	Std. Dev.[c] (mm/s)
0.25m	11	182				
0.50m	12	66	36	182	see (a)	
1.0m	14	30	41	66	86	182
2.0m	15[b]	18	47	30	99	66
4.0m	see (a)		52[b]	18	112	30
8.0m					126[b]	18

Notes: a) user's choice of depth cell size is not limited to the typical values specified, b) longer ranges available, c) BroadBand mode single-ping standard deviation (Std.Dev.)

Long Range Mode

	Range (m)	Depth Cell Size (m)	Std. Dev. (mm/s)
1200kHz	19	2	35
600kHz	67	4	38
300kHz	165	8	38

Profile Parameters

Velocity accuracy:
- 1200, 600: ± 0.25% of the water velocity relative to the ADCP ± 2.5mm/s
- 300: ± 0.5% of the water velocity relative to the ADCP ± 5 mm/s

Velocity resolution: 1mm/s
Velocity range: ± 5m/s (default):
± 20m/s (maximum)
Number of depth cells: 1-128
Ping rate: 2 Hz (typical)

Echo Intensity Profile

Vertical resolution: depth cell size
Dynamic range: 80 dB
Precision: ± 1.5dB (relative measure)

Transducer and Hardware

Beam angle: 20°
Configuration: 4 beam, convex
Internal memory: Unit comes with 10Mb card, standard. Two PCMCIA card slots available (10-220Mb each).
Communications: Serial port selectable by switch for RS-232 or RS-422. ASCII or binary output at 1200-115,400 baud.

Standard Sensors

Temperature (mounted on transducer)
- Range: -5° to 45°C
- Precision: ± 0.4°C
- Resolution: 0.01°

Tilt
- Range: ± 15°
- Accuracy : ± 0.5°
- Precision: ± 0.5°
- Resolution: 0.01°

Compass (fluxgate type, includes built-in field calibration feature)
- Accuracy: ± 2° [e]
- Precision: ± 0.5° [e]
- Resolution: 0.01°
- Maximum tilt: ± 15°

Note: e) @ 60° magnetic dip angle, 0.5G total field

Power

DC input: 20-60V DC. Internal battery pack, external battery pack or external power supply.
Voltage: 42V DC (new)
28V DC (depleted)
Capacity: @ 0°C: 400 watt hours

Transmit
- 16W @ 35V (1200kHz)
- 37W @ 35V (600kHz)
- 115W @ 35V (300kHz)

Environmental

Standard depth rating: 200m. Optional to 6000m.
Operating temperature: -5° to 45°C
Storage temperature: -30° to 75°C
Weight in air: 13.0kg
Weight in water: 4.5kg

Dimensions



Software

Use RDI's Windows™-based software for the best results:
- WinSC — Data Acquisition
- WinADCP — Data Display and Export

Upgrades Available

- Memory - 10-220Mb PCMCIA cards
- Pressure sensor
- External battery case
- High resolution water profiling modes
- Bottom tracking
- AC/DC power converter, 48V DC output
- Pressure cases for depths up to 6000m

For More Information

Call, e-mail or visit our web page. Ask for our Primer about ADCPs.

Internet: www.rdinstruments.com

RD Instruments
9855 Businesspark Avenue
San Diego, CA 92131 USA
Tel: (858) 693-1178 Fax: (858) 695-1459
E-mail: sales@rdinstruments.com

SEACAT PROFILER

SBE19

Fast, accurate profiles of salinity, temperature, density, sound velocity, dissolved oxygen, pH, ORP, light transmission, PAR.

Proven sensors, computer-less field operation, semi-conductor memory, RS-232 data download, powerful software.



SBE 19 Seacat Profiler data plotted using Sea-Bird's SEASOFT CTD Data Acquisition software. Salinity, density, and sound velocity were computed from the raw conductivity, temperature, pressure data according to the algorithms in Unesco Technical Paper no. 44 which incorporate the 1978 International Practical Salinity Scale (IPSS 78) and the 1980 equations of state (EOS 80).

Very narrow ranges of each variable have been chosen (for example, 1 ppt in salinity) so that the Profiler's high resolving capability may be easily perceived. SEASOFT offers menu control of variable choices and ranges.

The plot was made using an IBM PC compatible computer and Hewlett-Packard HP 7475A plotter.

CONVENIENCE - PORTABILITY - PERFORMANCE - VALUE

SBE Sea-Bird Electronics, Inc 1808-136th Place NE Bellevue, Washington 98005 USA
Telephone: (206) 643-9866 · Telex: 292915 SBEI UR · Telefax: (206) 643-9954

Operation

The Seacat Profiler samples at a programmable rate up to 2 "scans" per second, and is able to characterize the water column with high accuracy and half-second resolution. Conductivity and temperature frequencies are multiplexed through a precision Wein bridge. Automatic circuitry periodically corrects any time or temperature-induced errors in the electronics. Pressure is acquired with high resolution through an A/D converter. Collecting high quality data is easy and and reliable, following these few simple steps:

- Connect the profiler to a computer, check instrument status and select sampling parameters using menu-driven SEASOFT software.
- Switch the profiler ON just before lowering into the water (cast number, time and date are automatically recorded).
- When the cast is complete, switch the profiler OFF. Up to 100 casts can be recorded (within limit of available memory) before uploading to computer.
- After recovery, connect profiler to the computer and transfer the stored CTD data (plus any auxiliary sensor data) to floppy or hard disk files.
- Run SEASOFT's graphing/plotting program to convert to engineering units, display the data and create presentation quality graphics.



Profiler Configuration and Options

The Seacat's sensors consist of an internal-field glass conductivity cell with platinum electrodes, an aged, pressure-protected thermistor temperature sensor, and a mechanical strain gauge pressure sensor with a stainless steel or titanium element (depending on sensor range). Four single-ended 12-bit A/D input channels, and output power for optional auxiliary sensors (+10 volt, 50 ma) are provided through a separate connector. Depending on the auxiliary sensor requirements, the 4 A/D input channels can be optionally configured as 2 differential input channels and 1 channel can also be configured for a current (log) input sensor (PAR). See Application Note 29 for more information about configuration options.

The standard plastic housing is rated for 600 meters, and holds 6 "D" size alkaline cells. Optional aluminum or titanium housings are available for 3400, 6800 or 10500 meters. 9-cell housings required to power a fluorometer are available in plastic or aluminum. Battery life is about 40 hrs. without optional equipment. Battery life with optional pump and most auxiliary sensors is about 15-20 hrs.

Memory and Communication

128K bytes of CMOS static RAM is standard; 512K or 1024K is optional. Each sample (scan) of conductivity, temperature, and pressure uses 6 bytes. Auxiliary input voltages are stored in pairs, adding 3 bytes per pair. The 128K memory will last 3 hours when recording C, T, and P at 2 scans per second. When the main batteries are removed, the memory is supported for up to 3 years by board-mounted lithium cells. The Seacat Profiler communicates via a standard RS-232 interface. Stored data is uploaded at up to 38K baud, permitting 128K bytes of memory transfer in less than 2 minutes. In addition to recording internally, real-time data can be simultaneously transmitted short distances at 600 baud. Optional isolated line drivers permit real-time telemetry over cables up to 7,000 meters long.



SEACAT PROFILER WITH D.O., pH & PUMP

Profiler Specifications

	Range	Accuracy	Resolution
Conductivity (S/m)	0 - 7	± 0.001	± 0.0001
Temperature (°C)	-5 to +35	± 0.01	± 0.001
Depth (meters)[1]	60-1000	± 0.25%	± 0.015%
	2000-10000	± 0.15%	± 0.015%

Weight (air)Plastic housing 5.1 Kg; aluminum 7.2 Kg; titanium 10.9 Kg
Weight (water)Plastic housing 1.2 Kg; aluminum 3.3 Kg; titanium 7.0 Kg
[1]Select range for intended operating depth: 60/100/200/340/600/1000/2000/3400/6800 or 10,500 meters. See Application Note 27, *Minimizing Strain Gauge Sensor Errors*

Optional Equipment

SBE 5T Submersible Pump	Stainless Steel Guard Cage	Altimeter
NMEA 0183 GPS interface	SBE 18 pH sensor	SBE 27 pH/ORP sensor
SBE 23 Dissolved Oxygen sensor	Transmissometer	Fluorometer
Optical Backscatter Sensor	Chlorophyll Absorption Meter	PAR sensor

SEA-BIRD ELECTRONICS, INC.
1808 136th Place NE, Bellevue, WA 98005
Telephone (206) 643-9866
e-mail: <seabird@seabird.com>
Telefax (206) 643-9954

APPENDIX 3: Instrument Calibration

- General Instrument Calibration
    - ADCPs
    - CTD-OBS and CT-OBS Instrumentation

General Instrumentation Calibration

ADCPs

TRDI ADCP's transducers are factory calibrated during their production and do not require follow up calibration unless the instrument has undergone a tremendous stress or experiences some form of internal electronic failure. Internal tests prior to deployment, verify that each ADCP is operating correctly. The internal compass for the deployed ADCPs were calibrated at OSI following the manufactures calibration procedures. The internal compass of the vessel-mounted ADCPs were calibrated in the field, on the water, prior to real-time surveys.

CTD-OBS and CT-OBS Instrumentation

The Seabird CTD-OBS vertical profilers are factory calibrated on a yearly basis for conductivity, temperature, and depth. YSI sondes (CT-OBS) are factory calibrated for temperature. The YSI sondes' and CTDs' OBS sensors were calibrated by OSI with fixed standardized turbidity calibration solutions prior to their use on this project. Likewise, the conductivity probe of the YSI sondes were also calibrated by OSI prior to the project using fixed standardized calibration solutions.

APPENDIX 4: CT-OBS Water Quality Time Series Plots

Temperature, Salinity and Turbidity

- Station HKN
- Station NBN
- Station NBS
- Station KVK
- Station ARK

(Tidal phase indicated by color based on vertically averaged current direction data from each station's ADCP)

In Situ Water Quality Data
Station HKN: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station HKN: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station HKN: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station HKN: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station HKN: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station HKN: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station HKN: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station HKN: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station HKN: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station HKN: 3ft Above Bottom
Newark, NJ







In Situ Water Quality Data
Station HKN: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station HKN: 3ft Above Bottom
Newark, NJ







In Situ Water Quality Data
Station HKN: 3ft Above Bottom
Newark, NJ







In Situ Water Quality Data
Station HKN: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station HKN: 3ft Above Bottom
Newark, NJ







In Situ Water Quality Data
Station HKN: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station HKN: 3ft Above Bottom
Newark, NJ







In Situ Water Quality Data
Station HKN: 3ft Above Bottom
Newark, NJ







In Situ Water Quality Data
Station NBN: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station NBN: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station NBN: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station NBN: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station NBN: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station NBN: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station NBN: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station NBN: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station NBN: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station NBN: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station NBN: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station NBN: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station NBN: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station NBN: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station NBN: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station NBN: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station NBN: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station NBN: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station NBS: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station NBS: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station NBS: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station NBS: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station NBS: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station NBS: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station NBS: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station NBS: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station NBS: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station NBS: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station NBS: 3ft Above Bottom
Newark, NJ







In Situ Water Quality Data
Station NBS: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station NBS: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station NBS: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station NBS: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station NBS: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station NBS: 3ft Above Bottom
Newark, NJ







In Situ Water Quality Data
Station NBS: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station KVK: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station KVK: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station KVK: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station KVK: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station KVK: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station KVK: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station KVK: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station KVK: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station KVK: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station KVK: 3ft Above Bottom
Newark, NJ







In Situ Water Quality Data
Station KVK: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station KVK: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station KVK: 3ft Above Bottom
Newark, NJ







In Situ Water Quality Data
Station KVK: 3ft Above Bottom
Newark, NJ







In Situ Water Quality Data
Station KVK: 3ft Above Bottom
Newark, NJ







In Situ Water Quality Data
Station KVK: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station KVK: 3ft Above Bottom
Newark, NJ







In Situ Water Quality Data
Station KVK: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station ARK: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station ARK: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station ARK: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station ARK: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station ARK: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station ARK: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station ARK: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station ARK: 3ft Below Surface
Newark, NJ







In Situ Water Quality Data
Station ARK: 3ft Below Surface
Newark, NJ



In Situ Water Quality Data
Station ARK: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station ARK: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station ARK: 3ft Above Bottom
Newark, NJ







In Situ Water Quality Data
Station ARK: 3ft Above Bottom
Newark, NJ







In Situ Water Quality Data
Station ARK: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station ARK: 3ft Above Bottom
Newark, NJ







In Situ Water Quality Data
Station ARK: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station ARK: 3ft Above Bottom
Newark, NJ



In Situ Water Quality Data
Station ARK: 3ft Above Bottom
Newark, NJ



APPENDIX 5: *In Situ* ADCP Time Series Plots

Vertically Averaged

Current Magnitude and Direction

- Station HKN
- Station NBN
- Station NBS
- Station KVK
- Station ARK

In Situ ADCP Current Data
Station HKN
Newark, NJ





In Situ ADCP Current Data
Station HKN
Newark, NJ





In Situ ADCP Current Data
Station HKN
Newark, NJ





In Situ ADCP Current Data
Station HKN
Newark, NJ





In Situ ADCP Current Data
Station HKN
Newark, NJ





In Situ ADCP Current Data
Station HKN
Newark, NJ





In Situ ADCP Current Data
Station HKN
Newark, NJ





In Situ ADCP Current Data
Station HKN
Newark, NJ





In Situ ADCP Current Data
Station HKN
Newark, NJ





In Situ ADCP Current Data
Station NBN
Newark, NJ





In Situ ADCP Current Data
Station NBN
Newark, NJ





In Situ ADCP Current Data
Station NBN
Newark, NJ





In Situ ADCP Current Data
Station NBN
Newark, NJ





In Situ ADCP Current Data
Station NBN
Newark, NJ





In Situ ADCP Current Data
Station NBN
Newark, NJ





In Situ ADCP Current Data
Station NBN
Newark, NJ





In Situ ADCP Current Data
Station NBN
Newark, NJ





***In Situ* ADCP Current Data**
Station NBN
Newark, NJ





***In Situ* ADCP Current Data**
Station NBS
Newark, NJ





In Situ ADCP Current Data
Station NBS
Newark, NJ





In Situ ADCP Current Data
Station NBS
Newark, NJ





In Situ ADCP Current Data
Station NBS
Newark, NJ





***In Situ* ADCP Current Data**
Station NBS
Newark, NJ





In Situ ADCP Current Data
Station NBS
Newark, NJ



***In Situ* ADCP Current Data**
Station NBS
Newark, NJ





***In Situ* ADCP Current Data**
Station NBS
Newark, NJ





In Situ ADCP Current Data
Station NBS
Newark, NJ



In Situ ADCP Current Data
Station KVK
Newark, NJ



In Situ ADCP Current Data
Station KVK
Newark, NJ





In Situ ADCP Current Data
Station KVK
Newark, NJ





In Situ ADCP Current Data
Station KVK
Newark, NJ





In Situ ADCP Current Data
Station KVK
Newark, NJ





In Situ ADCP Current Data
Station KVK
Newark, NJ





In Situ ADCP Current Data
Station KVK
Newark, NJ





In Situ ADCP Current Data
Station KVK
Newark, NJ



In Situ ADCP Current Data
Station KVK
Newark, NJ





In Situ ADCP Current Data
Station ARK
Newark, NJ





In Situ ADCP Current Data
Station ARK
Newark, NJ





In Situ ADCP Current Data
Station ARK
Newark, NJ





In Situ ADCP Current Data
Station ARK
Newark, NJ





In Situ ADCP Current Data
Station ARK
Newark, NJ





In Situ ADCP Current Data
Station ARK
Newark, NJ





In Situ ADCP Current Data
Station ARK
Newark, NJ





In Situ ADCP Current Data
Station ARK
Newark, NJ





In Situ ADCP Current Data
Station ARK
Newark, NJ





In Situ ADCP Wave Data
Station NBW
Newark, NJ



In Situ ADCP Wave Data
Station NBW
Newark, NJ



In Situ ADCP Wave Data
Station NBW
Newark, NJ



In Situ ADCP Wave Data
Station NBW
Newark, NJ



In Situ ADCP Wave Data
Station NBW
Newark, NJ



In Situ ADCP Wave Data
Station NBW
Newark, NJ



In Situ ADCP Wave Data
Station NBW
Newark, NJ



In Situ ADCP Wave Data
Station NBW
Newark, NJ



In Situ ADCP Wave Data
Station NBW
Newark, NJ



APPENDIX 6: Mooring CTD-OBS Vertical Profiles

Events E01, E05, E09, E10, E14, E19, & E23

Presented Per Trip

- Station HKN
- Station NBN
- Station NBS
- Station KVK
- Station ARK

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E01-THKN-P1

3/21/10 14:03 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	8.26
Max Temp:	9.63
Avg Temp:	8.93
Min Cond:	3.79
Max Cond:	8.90
Avg Cond:	6.57
Min Salinity:	2.97
Max Salinity:	7.52
Avg Salinity:	5.37
Min Sigma-Theta:	2.07
Max Sigma-Theta:	5.74
Avg Sigma-Theta:	4.01
Min Turbidity:	11.92
Max Turbidity:	25.84
Avg Turbidity:	16.31

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E01-TNBN-P1

3/20/10 16:17 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	6.08
Max Temp:	8.90
Avg Temp:	7.30
Min Cond:	5.76
Max Cond:	17.72
Avg Cond:	11.50
Min Salinity:	4.46
Max Salinity:	16.88
Avg Salinity:	10.37
Min Sigma-Theta:	3.16
Max Sigma-Theta:	13.30
Avg Sigma-Theta:	8.04
Min Turbidity:	10.04
Max Turbidity:	11.80
Avg Turbidity:	10.88

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E01-TNBS-P1

3/20/10 15:47 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	5.57
Max Temp:	8.11
Avg Temp:	6.60
Min Cond:	7.08
Max Cond:	22.75
Avg Cond:	15.65
Min Salinity:	5.91
Max Salinity:	22.49
Avg Salinity:	14.74
Min Sigma-Theta:	4.49
Max Sigma-Theta:	17.73
Avg Sigma-Theta:	11.54
Min Turbidity:	9.87
Max Turbidity:	13.58
Avg Turbidity:	10.96

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E01-TKVK-P1

3/19/10 16:38 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	6.55
Max Temp:	7.98
Avg Temp:	7.05
Min Cond:	9.18
Max Cond:	23.26
Avg Cond:	16.92
Min Salinity:	7.97
Max Salinity:	22.27
Avg Salinity:	15.90
Min Sigma-Theta:	6.16
Max Sigma-Theta:	17.39
Avg Sigma-Theta:	12.41
Min Turbidity:	12.84
Max Turbidity:	19.69
Avg Turbidity:	15.92

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E01-TARK-P1

3/19/10 17:04 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	5.98
Max Temp:	7.62
Avg Temp:	6.68
Min Cond:	9.53
Max Cond:	17.19
Avg Cond:	13.12
Min Salinity:	8.30
Max Salinity:	16.35
Avg Salinity:	12.01
Min Sigma-Theta:	6.39
Max Sigma-Theta:	12.85
Avg Sigma-Theta:	9.39
Min Turbidity:	10.15
Max Turbidity:	13.25
Avg Turbidity:	11.75

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E05-THKN-P1

4/29/10 16:38 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.72
Max Temp:	13.12
Avg Temp:	12.66
Min Cond:	14.61
Max Cond:	18.68
Avg Cond:	15.34
Min Salinity:	11.28
Max Salinity:	15.25
Avg Salinity:	12.01
Min Sigma-Theta:	8.07
Max Sigma-Theta:	11.35
Avg Sigma-Theta:	8.71
Min Turbidity:	31.50
Max Turbidity:	39.56
Avg Turbidity:	36.16

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E05-TNBN-P1

4/28/10 16:28 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.41
Max Temp:	11.99
Avg Temp:	11.76
Min Cond:	15.96
Max Cond:	21.89
Avg Cond:	18.80
Min Salinity:	12.76
Max Salinity:	18.28
Avg Salinity:	15.36
Min Sigma-Theta:	9.38
Max Sigma-Theta:	13.73
Avg Sigma-Theta:	11.42
Min Turbidity:	13.01
Max Turbidity:	52.25
Avg Turbidity:	27.05

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E05-TNBS-P1

4/30/10 15:26 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.81
Max Temp:	12.72
Avg Temp:	11.35
Min Cond:	19.08
Max Cond:	23.26
Avg Cond:	21.65
Min Salinity:	15.21
Max Salinity:	19.85
Avg Salinity:	18.12
Min Sigma-Theta:	11.42
Max Sigma-Theta:	15.04
Avg Sigma-Theta:	13.62
Min Turbidity:	11.95
Max Turbidity:	19.38
Avg Turbidity:	14.60

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E05-TKVK-P1

4/30/10 12:48 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.76
Max Temp:	11.10
Avg Temp:	10.84
Min Cond:	23.26
Max Cond:	23.95
Avg Cond:	23.38
Min Salinity:	19.78
Max Salinity:	20.04
Avg Salinity:	19.93
Min Sigma-Theta:	14.83
Max Sigma-Theta:	15.19
Avg Sigma-Theta:	15.09
Min Turbidity:	19.01
Max Turbidity:	38.34
Avg Turbidity:	25.13

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E05-TARK-P1

4/29/10 12:57 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.10
Max Temp:	11.29
Avg Temp:	11.22
Min Cond:	20.05
Max Cond:	21.98
Avg Cond:	20.83
Min Salinity:	16.68
Max Salinity:	18.91
Avg Salinity:	17.43
Min Sigma-Theta:	12.52
Max Sigma-Theta:	13.93
Avg Sigma-Theta:	13.09
Min Turbidity:	10.02
Max Turbidity:	16.77
Avg Turbidity:	12.65

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E09-THKN-P1

4/29/10 19:40 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.04
Max Temp:	14.56
Avg Temp:	14.14
Min Cond:	10.70
Max Cond:	11.05
Avg Cond:	10.87
Min Salinity:	7.82
Max Salinity:	8.12
Avg Salinity:	7.96
Min Sigma-Theta:	5.23
Max Sigma-Theta:	5.50
Avg Sigma-Theta:	5.36
Min Turbidity:	35.78
Max Turbidity:	54.08
Avg Turbidity:	43.17

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E09-TNBN-P1

4/28/10 18:47 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	12.33
Max Temp:	12.84
Avg Temp:	12.66
Min Cond:	14.27
Max Cond:	17.41
Avg Cond:	15.59
Min Salinity:	11.09
Max Salinity:	13.90
Avg Salinity:	12.23
Min Sigma-Theta:	7.99
Max Sigma-Theta:	10.21
Avg Sigma-Theta:	8.87
Min Turbidity:	22.14
Max Turbidity:	40.67
Avg Turbidity:	31.05

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E09-TNBS-P1

4/30/10 18:32 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.16
Max Temp:	14.92
Avg Temp:	11.82
Min Cond:	18.87
Max Cond:	22.24
Avg Cond:	21.16
Min Salinity:	14.33
Max Salinity:	18.72
Avg Salinity:	17.45
Min Sigma-Theta:	10.12
Max Sigma-Theta:	14.11
Avg Sigma-Theta:	13.03
Min Turbidity:	8.03
Max Turbidity:	14.36
Avg Turbidity:	11.18

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E09-TKVK-P1

4/30/10 15:11 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.71
Max Temp:	12.81
Avg Temp:	11.11
Min Cond:	22.92
Max Cond:	23.56
Avg Cond:	23.34
Min Salinity:	18.63
Max Salinity:	20.19
Avg Salinity:	19.78
Min Sigma-Theta:	13.78
Max Sigma-Theta:	15.32
Avg Sigma-Theta:	14.94
Min Turbidity:	11.29
Max Turbidity:	19.05
Avg Turbidity:	15.51

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E09-TARK-P1

4/29/10 15:42 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.50
Max Temp:	11.95
Avg Temp:	11.02
Min Cond:	20.86
Max Cond:	23.27
Avg Cond:	22.01
Min Salinity:	16.96
Max Salinity:	19.94
Avg Salinity:	18.58
Min Sigma-Theta:	12.58
Max Sigma-Theta:	15.05
Avg Sigma-Theta:	14.02
Min Turbidity:	8.87
Max Turbidity:	82.55
Avg Turbidity:	22.07

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E10-THKN-P1

5/23/10 14:49 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	17.90
Max Temp:	18.04
Avg Temp:	17.95
Min Cond:	16.21
Max Cond:	16.53
Avg Cond:	16.40
Min Salinity:	11.13
Max Salinity:	11.41
Avg Salinity:	11.30
Min Sigma-Theta:	7.07
Max Sigma-Theta:	7.31
Avg Sigma-Theta:	7.22
Min Turbidity:	21.02
Max Turbidity:	25.63
Avg Turbidity:	24.26

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E10-TNBN-P1

5/22/10 15:55 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	13.71
Max Temp:	16.68
Avg Temp:	14.77
Min Cond:	19.10
Max Cond:	25.48
Avg Cond:	23.19
Min Salinity:	13.82
Max Salinity:	20.31
Avg Salinity:	17.90
Min Sigma-Theta:	9.40
Max Sigma-Theta:	14.92
Avg Sigma-Theta:	12.88
Min Turbidity:	12.35
Max Turbidity:	70.33
Avg Turbidity:	26.51

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E10-TNBS-P1

5/21/10 15:38 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	12.94
Max Temp:	15.53
Avg Temp:	13.90
Min Cond:	23.03
Max Cond:	26.52
Avg Cond:	24.93
Min Salinity:	17.37
Max Salinity:	21.66
Avg Salinity:	19.77
Min Sigma-Theta:	12.33
Max Sigma-Theta:	16.10
Avg Sigma-Theta:	14.47
Min Turbidity:	10.00
Max Turbidity:	51.03
Avg Turbidity:	20.12

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E10-TKVK-P1

5/22/10 12:52 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	13.67
Max Temp:	14.60
Avg Temp:	14.09
Min Cond:	25.06
Max Cond:	26.64
Avg Cond:	25.88
Min Salinity:	19.58
Max Salinity:	21.35
Avg Salinity:	20.47
Min Sigma-Theta:	14.21
Max Sigma-Theta:	15.73
Avg Sigma-Theta:	14.97
Min Turbidity:	9.10
Max Turbidity:	11.72
Avg Turbidity:	10.03

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E10-TARK-P1

5/21/10 12:53 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	13.10
Max Temp:	14.25
Avg Temp:	13.80
Min Cond:	24.65
Max Cond:	26.48
Avg Cond:	25.32
Min Salinity:	19.28
Max Salinity:	21.90
Avg Salinity:	20.18
Min Sigma-Theta:	14.22
Max Sigma-Theta:	15.98
Avg Sigma-Theta:	14.80
Min Turbidity:	8.31
Max Turbidity:	20.28
Avg Turbidity:	11.48

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E14-THKN-P1

5/23/10 16:44 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	17.61
Max Temp:	18.30
Avg Temp:	17.95
Min Cond:	15.90
Max Cond:	17.21
Avg Cond:	16.51
Min Salinity:	10.86
Max Salinity:	12.00
Avg Salinity:	11.38
Min Sigma-Theta:	6.68
Max Sigma-Theta:	7.82
Avg Sigma-Theta:	7.28
Min Turbidity:	15.12
Max Turbidity:	39.99
Avg Turbidity:	22.10

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E14-TNBN-P1

5/22/10 18:01 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	13.78
Max Temp:	15.56
Avg Temp:	14.37
Min Cond:	22.63
Max Cond:	25.68
Avg Cond:	24.59
Min Salinity:	17.11
Max Salinity:	20.45
Avg Salinity:	19.23
Min Sigma-Theta:	12.16
Max Sigma-Theta:	15.01
Avg Sigma-Theta:	13.97
Min Turbidity:	10.18
Max Turbidity:	26.97
Avg Turbidity:	14.53

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E14-TNBS-P1

5/21/10 18:02 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	13.46
Max Temp:	14.83
Avg Temp:	14.04
Min Cond:	25.36
Max Cond:	26.85
Avg Cond:	26.25
Min Salinity:	20.03
Max Salinity:	21.66
Avg Salinity:	20.82
Min Sigma-Theta:	14.52
Max Sigma-Theta:	16.00
Avg Sigma-Theta:	15.25
Min Turbidity:	10.00
Max Turbidity:	14.87
Avg Turbidity:	11.82

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E14-TKVK-P1

5/22/10 15:20 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	13.70
Max Temp:	14.47
Avg Temp:	14.17
Min Cond:	25.57
Max Cond:	26.62
Avg Cond:	25.93
Min Salinity:	20.08
Max Salinity:	21.30
Avg Salinity:	20.47
Min Sigma-Theta:	14.62
Max Sigma-Theta:	15.68
Avg Sigma-Theta:	14.96
Min Turbidity:	8.57
Max Turbidity:	26.24
Avg Turbidity:	12.12

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E14-TARK-P1

5/21/10 15:21 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	13.61
Max Temp:	15.20
Avg Temp:	14.41
Min Cond:	24.89
Max Cond:	25.70
Avg Cond:	25.19
Min Salinity:	19.18
Max Salinity:	20.54
Avg Salinity:	19.71
Min Sigma-Theta:	13.82
Max Sigma-Theta:	15.11
Avg Sigma-Theta:	14.33
Min Turbidity:	9.92
Max Turbidity:	13.35
Avg Turbidity:	11.21

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E15-THKN-P1

6/21/10 14:14 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.31
Max Temp:	24.65
Avg Temp:	24.39
Min Cond:	23.51
Max Cond:	23.91
Avg Cond:	23.71
Min Salinity:	14.40
Max Salinity:	14.70
Avg Salinity:	14.55
Min Sigma-Theta:	8.00
Max Sigma-Theta:	8.26
Avg Sigma-Theta:	8.14
Min Turbidity:	10.23
Max Turbidity:	11.98
Avg Turbidity:	11.04

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E15-TNBN-P1

6/20/10 16:01 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.07
Max Temp:	23.60
Avg Temp:	21.82
Min Cond:	28.30
Max Cond:	31.99
Avg Cond:	30.58
Min Salinity:	17.54
Max Salinity:	21.75
Avg Salinity:	20.36
Min Sigma-Theta:	10.64
Max Sigma-Theta:	14.42
Avg Sigma-Theta:	13.18
Min Turbidity:	5.25
Max Turbidity:	48.37
Avg Turbidity:	16.26

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E15-TNBS-P1

6/19/10 15:41 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.56
Max Temp:	21.38
Avg Temp:	20.70
Min Cond:	31.95
Max Cond:	32.38
Avg Cond:	32.22
Min Salinity:	21.31
Max Salinity:	22.19
Avg Salinity:	22.12
Min Sigma-Theta:	14.28
Max Sigma-Theta:	14.88
Avg Sigma-Theta:	14.81
Min Turbidity:	4.19
Max Turbidity:	13.55
Avg Turbidity:	8.58

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E15-TKVK-P1

6/20/10 12:35 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.68
Max Temp:	22.43
Avg Temp:	21.07
Min Cond:	32.23
Max Cond:	33.06
Avg Cond:	32.72
Min Salinity:	21.08
Max Salinity:	22.79
Avg Salinity:	22.31
Min Sigma-Theta:	13.69
Max Sigma-Theta:	15.31
Avg Sigma-Theta:	14.86
Min Turbidity:	3.49
Max Turbidity:	5.55
Avg Turbidity:	4.07

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E15-TARK-P1

6/19/10 12:44 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.69
Max Temp:	21.26
Avg Temp:	20.81
Min Cond:	31.85
Max Cond:	32.15
Avg Cond:	32.04
Min Salinity:	21.24
Max Salinity:	22.10
Avg Salinity:	21.92
Min Sigma-Theta:	14.10
Max Sigma-Theta:	14.78
Avg Sigma-Theta:	14.62
Min Turbidity:	4.39
Max Turbidity:	6.36
Avg Turbidity:	5.10

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E19-THKN-P1

6/21/10 16:01 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.39
Max Temp:	25.78
Avg Temp:	24.80
Min Cond:	22.93
Max Cond:	23.76
Avg Cond:	23.26
Min Salinity:	13.35
Max Salinity:	14.57
Avg Salinity:	14.08
Min Sigma-Theta:	6.84
Max Sigma-Theta:	8.14
Avg Sigma-Theta:	7.66
Min Turbidity:	7.43
Max Turbidity:	10.69
Avg Turbidity:	8.63

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E19-TNBN-P1

6/20/10 18:01 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.93
Max Temp:	22.81
Avg Temp:	21.96
Min Cond:	31.02
Max Cond:	32.46
Avg Cond:	32.22
Min Salinity:	20.88
Max Salinity:	22.40
Avg Salinity:	21.57
Min Sigma-Theta:	12.72
Max Sigma-Theta:	14.76
Avg Sigma-Theta:	14.00
Min Turbidity:	5.56
Max Turbidity:	13.49
Avg Turbidity:	8.47

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E19-TNBS-P1

6/19/10 18:17 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.14
Max Temp:	21.33
Avg Temp:	20.57
Min Cond:	33.04
Max Cond:	33.75
Avg Cond:	33.29
Min Salinity:	22.48
Max Salinity:	23.11
Avg Salinity:	23.02
Min Sigma-Theta:	15.14
Max Sigma-Theta:	15.68
Avg Sigma-Theta:	15.51
Min Turbidity:	4.39
Max Turbidity:	6.17
Avg Turbidity:	5.35

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E19-TKVK-P1

6/20/10 15:23 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.82
Max Temp:	22.81
Avg Temp:	21.35
Min Cond:	32.91
Max Cond:	33.64
Avg Cond:	33.25
Min Salinity:	20.93
Max Salinity:	22.76
Avg Salinity:	22.55
Min Sigma-Theta:	13.66
Max Sigma-Theta:	15.20
Avg Sigma-Theta:	14.96
Min Turbidity:	4.97
Max Turbidity:	12.05
Avg Turbidity:	7.83

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E19-TARK-P1

6/19/10 15:26 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	20.61
Max Temp:	22.64
Avg Temp:	21.37
Min Cond:	32.12
Max Cond:	33.04
Avg Cond:	32.63
Min Salinity:	21.33
Max Salinity:	22.28
Avg Salinity:	22.08
Min Sigma-Theta:	14.12
Max Sigma-Theta:	14.82
Avg Sigma-Theta:	14.63
Min Turbidity:	2.18
Max Turbidity:	6.95
Avg Turbidity:	5.01

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E23-THKN-P1

7/26/10 14:06 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.24
Max Temp:	27.23
Avg Temp:	26.59
Min Cond:	32.81
Max Cond:	35.82
Avg Cond:	34.49
Min Salinity:	19.58
Max Salinity:	21.98
Avg Salinity:	20.93
Min Sigma-Theta:	11.11
Max Sigma-Theta:	13.17
Avg Sigma-Theta:	12.28
Min Turbidity:	9.50
Max Turbidity:	14.11
Avg Turbidity:	11.26

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E23-TNBN-P1

7/24/10 12:48 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.53
Max Temp:	26.55
Avg Temp:	25.83
Min Cond:	36.12
Max Cond:	37.21
Avg Cond:	36.77
Min Salinity:	22.30
Max Salinity:	23.28
Avg Salinity:	22.83
Min Sigma-Theta:	13.32
Max Sigma-Theta:	14.36
Avg Sigma-Theta:	13.93
Min Turbidity:	9.49
Max Turbidity:	13.12
Avg Turbidity:	11.48

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E23-TNBS-P1

7/25/10 12:28 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.58
Max Temp:	26.41
Avg Temp:	25.40
Min Cond:	36.56
Max Cond:	38.56
Avg Cond:	37.75
Min Salinity:	22.34
Max Salinity:	24.72
Avg Salinity:	23.73
Min Sigma-Theta:	13.41
Max Sigma-Theta:	15.72
Avg Sigma-Theta:	14.73
Min Turbidity:	5.25
Max Turbidity:	9.11
Avg Turbidity:	6.48

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E23-TKVK-P1

7/25/10 12:40 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.23
Max Temp:	24.79
Avg Temp:	24.42
Min Cond:	38.42
Max Cond:	38.68
Avg Cond:	38.52
Min Salinity:	24.73
Max Salinity:	24.93
Avg Salinity:	24.79
Min Sigma-Theta:	15.66
Max Sigma-Theta:	15.97
Avg Sigma-Theta:	15.81
Min Turbidity:	4.34
Max Turbidity:	6.03
Avg Turbidity:	4.90

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E23-TARK-P1

7/24/10 13:07 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.97
Max Temp:	26.29
Avg Temp:	26.07
Min Cond:	36.12
Max Cond:	37.13
Avg Cond:	36.97
Min Salinity:	22.81
Max Salinity:	22.93
Avg Salinity:	22.85
Min Sigma-Theta:	13.80
Max Sigma-Theta:	13.94
Avg Sigma-Theta:	13.88
Min Turbidity:	5.10
Max Turbidity:	7.78
Avg Turbidity:	5.66

APPENDIX 7: Trip 4 Real Time Survey Events E03-E04

- Vertically Averaged Current Vector Plots
- CTD-OBS Vertical Profiles



LEGEND FOR CURRENT VELOCITY MAPPINGS:

CURRENT VECTOR SCALE
1" = 150 CM/S

SCALE : 1"=1000'
1000 0 1000

NOTES:

1. GRID SYSTEM IS IN FEET AND IS THE NEW JERSEY STATE PLANE COORDINATE SYSTEM, NAD83.
2. ORTHOPHOTO IMAGERY ARE TRUE COLOR ONE FOOT GROUND SAMPLE DISTANCE IMAGES PRODUCED FROM AERIAL PHOTOS FLOWN IN 2007 AND OBTAINED FROM THE NEW JERSEY GEOGRAPHIC INFORMATION NETWORK (NJGIN).
3. THE INFORMATION PRESENTED ON THESE DRAWINGS REPRESENTS THE RESULTS OF A SURVEY PEFORMED BY OCEAN SURVEYS, INC. ON 25 MARCH 2010 AND CAN ONLY BE CONSIDERED AS INDICATING THE CONDITIONS EXISTING AT THAT TIME. REUSE OF THIS INFORMATION BY CLIENT OF OTHERS BEYOND THE SCOPE OF WORK FOR WHICH IT WAS ACQUIRED SHALL BE AT THE SOLE RISK OF THE USER AND WITHOUT LIABILITY TO OSI.

OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388-4631
OSI
www.oceansurveys.com

Vertically Averaged Current Data
Program N01, Location Map
25 March 2010
New Jersey - New York Waters



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Ebb Tide
Program N01, Event 03
25 March 2010, 10:30 - 13:45 (UTC) Hours
New Jersey - New York Waters



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Flood Tide
Program N01, Event 04
25 March 2010, 16:35 - 19:39 (UTC) Hours
New Jersey - New York Waters

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E03-THKN-P1

3/25/10 10:42 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.22
Max Temp:	9.59
Avg Temp:	9.33
Min Cond:	8.42
Max Cond:	9.62
Avg Cond:	9.02
Min Salinity:	6.84
Max Salinity:	7.96
Avg Salinity:	7.40
Min Sigma-Theta:	5.23
Max Sigma-Theta:	6.00
Avg Sigma-Theta:	5.56
Min Turbidity:	10.11
Max Turbidity:	16.33
Avg Turbidity:	13.04

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E03-THKN-P2

3/25/10 11:00 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	8.63
Max Temp:	9.43
Avg Temp:	9.26
Min Cond:	7.86
Max Cond:	12.29
Avg Cond:	9.32
Min Salinity:	6.37
Max Salinity:	10.52
Avg Salinity:	7.71
Min Sigma-Theta:	4.74
Max Sigma-Theta:	8.04
Avg Sigma-Theta:	5.79
Min Turbidity:	12.16
Max Turbidity:	17.41
Avg Turbidity:	15.08

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E03-THKN-P3

3/25/10 11:09 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	8.89
Max Temp:	9.44
Avg Temp:	9.27
Min Cond:	7.00
Max Cond:	11.02
Avg Cond:	8.85
Min Salinity:	5.66
Max Salinity:	9.28
Avg Salinity:	7.28
Min Sigma-Theta:	4.20
Max Sigma-Theta:	7.05
Avg Sigma-Theta:	5.46
Min Turbidity:	12.72
Max Turbidity:	16.74
Avg Turbidity:	15.30

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E03-TNBN-P1

3/25/10 10:54 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	7.86
Max Temp:	9.53
Avg Temp:	9.05
Min Cond:	6.61
Max Cond:	15.92
Avg Cond:	10.20
Min Salinity:	5.29
Max Salinity:	14.27
Avg Salinity:	8.60
Min Sigma-Theta:	3.89
Max Sigma-Theta:	11.05
Avg Sigma-Theta:	6.51
Min Turbidity:	11.58
Max Turbidity:	28.58
Avg Turbidity:	16.26

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E03-TNBN-P2

3/25/10 11:11 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.35
Max Temp:	9.58
Avg Temp:	9.48
Min Cond:	4.57
Max Cond:	8.10
Avg Cond:	6.40
Min Salinity:	3.67
Max Salinity:	6.58
Avg Salinity:	5.12
Min Sigma-Theta:	2.62
Max Sigma-Theta:	4.91
Avg Sigma-Theta:	3.76
Min Turbidity:	11.50
Max Turbidity:	17.32
Avg Turbidity:	14.38

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E03-TNBN-P3

3/25/10 11:21 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.53
Max Temp:	9.55
Avg Temp:	9.54
Min Cond:	5.27
Max Cond:	6.50
Avg Cond:	6.06
Min Salinity:	4.33
Max Salinity:	5.18
Avg Salinity:	4.83
Min Sigma-Theta:	3.13
Max Sigma-Theta:	3.80
Avg Sigma-Theta:	3.52
Min Turbidity:	14.36
Max Turbidity:	22.73
Avg Turbidity:	17.14

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E03-TNBS-P1

3/25/10 12:02 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	6.46
Max Temp:	9.33
Avg Temp:	7.95
Min Cond:	4.69
Max Cond:	22.42
Avg Cond:	15.39
Min Salinity:	3.74
Max Salinity:	21.56
Avg Salinity:	13.95
Min Sigma-Theta:	2.74
Max Sigma-Theta:	16.91
Avg Sigma-Theta:	10.80
Min Turbidity:	7.32
Max Turbidity:	19.28
Avg Turbidity:	11.38

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E03-TNBS-P2

3/25/10 12:17 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	6.52
Max Temp:	9.36
Avg Temp:	7.95
Min Cond:	5.50
Max Cond:	22.33
Avg Cond:	15.35
Min Salinity:	4.46
Max Salinity:	21.43
Avg Salinity:	13.90
Min Sigma-Theta:	3.27
Max Sigma-Theta:	16.80
Avg Sigma-Theta:	10.76
Min Turbidity:	9.19
Max Turbidity:	16.94
Avg Turbidity:	11.22

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E03-TNBS-P3

3/25/10 12:30 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	8.88
Max Temp:	9.29
Avg Temp:	9.12
Min Cond:	6.09
Max Cond:	10.90
Avg Cond:	9.00
Min Salinity:	4.94
Max Salinity:	9.19
Avg Salinity:	7.45
Min Sigma-Theta:	3.64
Max Sigma-Theta:	6.98
Avg Sigma-Theta:	5.61
Min Turbidity:	9.46
Max Turbidity:	12.01
Avg Turbidity:	10.67

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E03-TKVK-P1

3/25/10 13:03 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	6.50
Max Temp:	8.79
Avg Temp:	7.65
Min Cond:	10.29
Max Cond:	23.01
Avg Cond:	16.63
Min Salinity:	8.67
Max Salinity:	22.14
Avg Salinity:	15.22
Min Sigma-Theta:	6.59
Max Sigma-Theta:	17.35
Avg Sigma-Theta:	11.83
Min Turbidity:	8.89
Max Turbidity:	11.80
Avg Turbidity:	10.03

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E03-TKVK-P2

3/25/10 13:17 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	6.08
Max Temp:	8.70
Avg Temp:	7.49
Min Cond:	10.81
Max Cond:	25.56
Avg Cond:	17.53
Min Salinity:	9.16
Max Salinity:	25.17
Avg Salinity:	16.20
Min Sigma-Theta:	6.98
Max Sigma-Theta:	19.79
Avg Sigma-Theta:	12.61
Min Turbidity:	9.16
Max Turbidity:	11.68
Avg Turbidity:	10.51

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E03-TKVK-P3

3/25/10 13:26 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	5.60
Max Temp:	8.55
Avg Temp:	7.32
Min Cond:	11.47
Max Cond:	27.33
Avg Cond:	18.52
Min Salinity:	9.83
Max Salinity:	27.48
Avg Salinity:	17.34
Min Sigma-Theta:	7.51
Max Sigma-Theta:	21.66
Avg Sigma-Theta:	13.52
Min Turbidity:	9.49
Max Turbidity:	18.43
Avg Turbidity:	11.03

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E03-TARK-P1

3/25/10 13:55 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	7.34
Max Temp:	9.34
Avg Temp:	8.66
Min Cond:	9.27
Max Cond:	18.90
Avg Cond:	12.39
Min Salinity:	7.63
Max Salinity:	17.47
Avg Salinity:	10.70
Min Sigma-Theta:	5.72
Max Sigma-Theta:	13.56
Avg Sigma-Theta:	8.19
Min Turbidity:	8.62
Max Turbidity:	16.34
Avg Turbidity:	10.39

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E03-TARK-P2

3/25/10 14:10 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	6.71
Max Temp:	9.56
Avg Temp:	8.24
Min Cond:	8.69
Max Cond:	21.73
Avg Cond:	14.46
Min Salinity:	7.10
Max Salinity:	20.68
Avg Salinity:	12.93
Min Sigma-Theta:	5.29
Max Sigma-Theta:	16.19
Avg Sigma-Theta:	9.97
Min Turbidity:	9.02
Max Turbidity:	18.42
Avg Turbidity:	11.42

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E03-TARK-P3

3/25/10 14:23 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	6.71
Max Temp:	9.42
Avg Temp:	8.15
Min Cond:	8.57
Max Cond:	21.60
Avg Cond:	14.54
Min Salinity:	7.17
Max Salinity:	20.54
Avg Salinity:	13.04
Min Sigma-Theta:	5.36
Max Sigma-Theta:	16.08
Avg Sigma-Theta:	10.07
Min Turbidity:	8.15
Max Turbidity:	22.28
Avg Turbidity:	13.90

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E04-THKN-P1

3/25/10 16:49 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.43
Max Temp:	11.36
Avg Temp:	10.78
Min Cond:	4.73
Max Cond:	6.17
Avg Cond:	5.42
Min Salinity:	3.51
Max Salinity:	4.78
Avg Salinity:	4.09
Min Sigma-Theta:	2.31
Max Sigma-Theta:	3.39
Avg Sigma-Theta:	2.82
Min Turbidity:	10.24
Max Turbidity:	19.98
Avg Turbidity:	12.54

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E04-THKN-P2

3/25/10 17:04 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.24
Max Temp:	11.01
Avg Temp:	10.63
Min Cond:	4.80
Max Cond:	6.72
Avg Cond:	5.76
Min Salinity:	3.60
Max Salinity:	5.27
Avg Salinity:	4.43
Min Sigma-Theta:	2.43
Max Sigma-Theta:	3.79
Avg Sigma-Theta:	3.10
Min Turbidity:	9.52
Max Turbidity:	20.13
Avg Turbidity:	12.78

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E04-THKN-P3

3/25/10 17:13 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.29
Max Temp:	11.03
Avg Temp:	10.83
Min Cond:	5.00
Max Cond:	6.63
Avg Cond:	5.45
Min Salinity:	3.76
Max Salinity:	5.18
Avg Salinity:	4.09
Min Sigma-Theta:	2.54
Max Sigma-Theta:	3.71
Avg Sigma-Theta:	2.82
Min Turbidity:	10.24
Max Turbidity:	20.12
Avg Turbidity:	11.81

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E04-TNBN-P1

3/25/10 16:55 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	7.68
Max Temp:	9.90
Avg Temp:	9.08
Min Cond:	5.46
Max Cond:	15.99
Avg Cond:	10.31
Min Salinity:	4.42
Max Salinity:	14.76
Avg Salinity:	8.70
Min Sigma-Theta:	3.11
Max Sigma-Theta:	11.67
Avg Sigma-Theta:	6.59
Min Turbidity:	9.19
Max Turbidity:	12.12
Avg Turbidity:	9.83

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E04-TNBN-P2

3/25/10 17:08 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.45
Max Temp:	9.76
Avg Temp:	9.62
Min Cond:	5.88
Max Cond:	7.45
Avg Cond:	6.82
Min Salinity:	4.70
Max Salinity:	6.00
Avg Salinity:	5.45
Min Sigma-Theta:	3.40
Max Sigma-Theta:	4.45
Avg Sigma-Theta:	4.00
Min Turbidity:	8.23
Max Turbidity:	9.85
Avg Turbidity:	9.15

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E04-TNBN-P3

3/25/10 17:18 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	9.35
Max Temp:	9.97
Avg Temp:	9.65
Min Cond:	6.21
Max Cond:	7.70
Avg Cond:	7.18
Min Salinity:	4.86
Max Salinity:	6.24
Avg Salinity:	5.74
Min Sigma-Theta:	3.37
Max Sigma-Theta:	4.64
Avg Sigma-Theta:	4.20
Min Turbidity:	7.45
Max Turbidity:	8.99
Avg Turbidity:	8.11

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E04-TNBS-P1

3/25/10 17:58 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	6.19
Max Temp:	9.76
Avg Temp:	8.29
Min Cond:	8.00
Max Cond:	24.65
Avg Cond:	14.69
Min Salinity:	6.42
Max Salinity:	24.12
Avg Salinity:	13.22
Min Sigma-Theta:	4.66
Max Sigma-Theta:	18.95
Avg Sigma-Theta:	10.20
Min Turbidity:	8.23
Max Turbidity:	44.90
Avg Turbidity:	14.48

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E04-TNBS-P2

3/25/10 18:12 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	6.18
Max Temp:	9.67
Avg Temp:	8.10
Min Cond:	9.07
Max Cond:	24.31
Avg Cond:	15.18
Min Salinity:	7.37
Max Salinity:	23.76
Avg Salinity:	13.70
Min Sigma-Theta:	5.49
Max Sigma-Theta:	18.67
Avg Sigma-Theta:	10.60
Min Turbidity:	8.60
Max Turbidity:	22.32
Avg Turbidity:	11.00

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E04-TNBS-P3

3/25/10 18:23 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	8.82
Max Temp:	9.69
Avg Temp:	9.09
Min Cond:	9.32
Max Cond:	11.10
Avg Cond:	10.54
Min Salinity:	7.77
Max Salinity:	9.39
Avg Salinity:	8.84
Min Sigma-Theta:	5.80
Max Sigma-Theta:	7.15
Avg Sigma-Theta:	6.69
Min Turbidity:	9.01
Max Turbidity:	10.11
Avg Turbidity:	9.67

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E04-TKVK-P1

3/25/10 18:45 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	5.70
Max Temp:	7.65
Avg Temp:	7.13
Min Cond:	11.36
Max Cond:	26.08
Avg Cond:	15.73
Min Salinity:	9.98
Max Salinity:	26.03
Avg Salinity:	14.50
Min Sigma-Theta:	7.72
Max Sigma-Theta:	20.50
Avg Sigma-Theta:	11.31
Min Turbidity:	10.22
Max Turbidity:	69.07
Avg Turbidity:	17.45

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E04-TKVK-P2

3/25/10 18:58 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	5.70
Max Temp:	7.44
Avg Temp:	6.85
Min Cond:	11.12
Max Cond:	26.18
Avg Cond:	17.35
Min Salinity:	10.17
Max Salinity:	26.13
Avg Salinity:	16.36
Min Sigma-Theta:	7.89
Max Sigma-Theta:	20.58
Avg Sigma-Theta:	12.80
Min Turbidity:	11.44
Max Turbidity:	37.51
Avg Turbidity:	16.92

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E04-TKVK-P3

3/25/10 19:21 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	5.81
Max Temp:	8.12
Avg Temp:	6.97
Min Cond:	11.70
Max Cond:	25.40
Avg Cond:	18.01
Min Salinity:	10.13
Max Salinity:	25.19
Avg Salinity:	16.95
Min Sigma-Theta:	7.81
Max Sigma-Theta:	19.83
Avg Sigma-Theta:	13.25
Min Turbidity:	10.99
Max Turbidity:	21.76
Avg Turbidity:	13.71

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E04-TARK-P1

3/25/10 19:44 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	6.87
Max Temp:	9.68
Avg Temp:	8.35
Min Cond:	9.32
Max Cond:	19.86
Avg Cond:	14.36
Min Salinity:	7.58
Max Salinity:	18.93
Avg Salinity:	12.70
Min Sigma-Theta:	5.65
Max Sigma-Theta:	14.81
Avg Sigma-Theta:	9.79
Min Turbidity:	8.85
Max Turbidity:	10.24
Avg Turbidity:	9.59

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E04-TARK-P2

3/25/10 19:56 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	6.73
Max Temp:	9.50
Avg Temp:	8.00
Min Cond:	9.65
Max Cond:	21.29
Avg Cond:	15.84
Min Salinity:	8.04
Max Salinity:	20.20
Avg Salinity:	14.27
Min Sigma-Theta:	6.03
Max Sigma-Theta:	15.81
Avg Sigma-Theta:	11.04
Min Turbidity:	8.83
Max Turbidity:	11.31
Avg Turbidity:	9.31

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E04-TARK-P3

3/25/10 20:04 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	6.71
Max Temp:	9.54
Avg Temp:	8.02
Min Cond:	9.91
Max Cond:	21.33
Avg Cond:	15.85
Min Salinity:	8.11
Max Salinity:	20.27
Avg Salinity:	14.23
Min Sigma-Theta:	6.02
Max Sigma-Theta:	15.87
Avg Sigma-Theta:	11.01
Min Turbidity:	8.89
Max Turbidity:	13.75
Avg Turbidity:	9.79

APPENDIX 8: Trip 5 Real Time Survey Events E07-E08

- Vertically Averaged Current Vector Plots
- CTD-OBS Vertical Profiles



LEGEND FOR CURRENT VELOCITY MAPPINGS:

CURRENT VECTOR SCALE
1" = 150 CM/S

SCALE : 1"=1000'
1000 0 1000

NOTES:

1. GRID SYSTEM IS IN FEET AND IS THE NEW JERSEY STATE PLANE COORDINATE SYSTEM, NAD83.
2. ORTHOPHOTO IMAGERY ARE TRUE COLOR ONE FOOT GROUND SAMPLE DISTANCE IMAGES PRODUCED FROM AERIAL PHOTOS FLOWN IN 2007 AND OBTAINED FROM THE NEW JERSEY GEOGRAPHIC INFORMATION NETWORK (NJGIN).
3. THE INFORMATION PRESENTED ON THESE DRAWINGS REPRESENTS THE RESULTS OF A SURVEY PEFORMED BY OCEAN SURVEYS, INC. ON 3 MAY 2010 AND CAN ONLY BE CONSIDERED AS INDICATING THE CONDITIONS EXISTING AT THAT TIME. REUSE OF THIS INFORMATION BY CLIENT OF OTHERS BEYOND THE SCOPE OF WORK FOR WHICH IT WAS ACQUIRED SHALL BE AT THE SOLE RISK OF THE USER AND WITHOUT LIABILITY TO OSI.

OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388-4631
www.oceansurveys.com

Vertically Averaged Current Data
Program N01, Location Map
3 May 2010
New Jersey - New York Waters



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Flood Tide
Program N01, Event 07
3 May 2010, 12:11 - 15:20 (UTC) Hours
New Jersey - New York Waters



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Ebb Tide
Program N01, Event 08
3 May 2010, 18:01 - 20:58 (UTC) Hours
New Jersey - New York Waters

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E07-THKN-P1

5/03/10 12:35 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	17.78
Max Temp:	17.93
Avg Temp:	17.86
Min Cond:	11.84
Max Cond:	12.33
Avg Cond:	12.17
Min Salinity:	7.91
Max Salinity:	8.33
Avg Salinity:	8.19
Min Sigma-Theta:	4.62
Max Sigma-Theta:	5.00
Avg Sigma-Theta:	4.87
Min Turbidity:	23.28
Max Turbidity:	29.09
Avg Turbidity:	25.62

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E07-THKN-P2

5/03/10 12:48 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	17.63
Max Temp:	18.06
Avg Temp:	17.86
Min Cond:	11.90
Max Cond:	12.68
Avg Cond:	12.33
Min Salinity:	7.95
Max Salinity:	8.67
Avg Salinity:	8.31
Min Sigma-Theta:	4.64
Max Sigma-Theta:	5.30
Avg Sigma-Theta:	4.97
Min Turbidity:	22.43
Max Turbidity:	42.17
Avg Turbidity:	29.95

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E07-THKN-P3

5/03/10 12:55 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	17.64
Max Temp:	18.04
Avg Temp:	17.77
Min Cond:	11.98
Max Cond:	12.62
Avg Cond:	12.43
Min Salinity:	8.02
Max Salinity:	8.55
Avg Salinity:	8.40
Min Sigma-Theta:	4.71
Max Sigma-Theta:	5.19
Avg Sigma-Theta:	5.05
Min Turbidity:	21.38
Max Turbidity:	43.90
Avg Turbidity:	33.84

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E07-TNBN-P1

5/03/10 12:27 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	12.29
Max Temp:	17.50
Avg Temp:	14.46
Min Cond:	13.74
Max Cond:	23.14
Avg Cond:	18.40
Min Salinity:	9.42
Max Salinity:	18.97
Avg Salinity:	14.05
Min Sigma-Theta:	5.88
Max Sigma-Theta:	14.13
Avg Sigma-Theta:	9.98
Min Turbidity:	12.60
Max Turbidity:	27.99
Avg Turbidity:	14.92

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E07-TNBN-P2

5/03/10 12:52 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.83
Max Temp:	16.10
Avg Temp:	15.30
Min Cond:	14.05
Max Cond:	16.42
Avg Cond:	15.53
Min Salinity:	9.99
Max Salinity:	12.22
Avg Salinity:	11.38
Min Sigma-Theta:	6.58
Max Sigma-Theta:	8.52
Avg Sigma-Theta:	7.79
Min Turbidity:	8.47
Max Turbidity:	11.93
Avg Turbidity:	10.72

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E07-TNBN-P3

5/03/10 13:04 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.73
Max Temp:	16.21
Avg Temp:	15.25
Min Cond:	13.46
Max Cond:	16.32
Avg Cond:	15.34
Min Salinity:	9.51
Max Salinity:	12.17
Avg Salinity:	11.25
Min Sigma-Theta:	6.19
Max Sigma-Theta:	8.49
Avg Sigma-Theta:	7.70
Min Turbidity:	7.51
Max Turbidity:	9.41
Avg Turbidity:	8.42

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E07-TNBS-P1

5/03/10 13:48 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	12.10
Max Temp:	14.98
Avg Temp:	13.42
Min Cond:	17.52
Max Cond:	24.62
Avg Cond:	21.52
Min Salinity:	12.62
Max Salinity:	20.41
Avg Salinity:	17.07
Min Sigma-Theta:	8.55
Max Sigma-Theta:	15.27
Avg Sigma-Theta:	12.48
Min Turbidity:	8.91
Max Turbidity:	44.91
Avg Turbidity:	17.69

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E07-TNBS-P2

5/03/10 14:15 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	11.87
Max Temp:	15.24
Avg Temp:	13.23
Min Cond:	17.24
Max Cond:	25.22
Avg Cond:	22.41
Min Salinity:	12.62
Max Salinity:	21.08
Avg Salinity:	17.95
Min Sigma-Theta:	8.68
Max Sigma-Theta:	15.82
Avg Sigma-Theta:	13.19
Min Turbidity:	8.11
Max Turbidity:	27.54
Avg Turbidity:	13.76

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E07-TNBS-P3

5/03/10 14:03 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.13
Max Temp:	15.71
Avg Temp:	14.68
Min Cond:	17.78
Max Cond:	20.23
Avg Cond:	19.22
Min Salinity:	13.03
Max Salinity:	15.62
Avg Salinity:	14.57
Min Sigma-Theta:	8.98
Max Sigma-Theta:	11.24
Avg Sigma-Theta:	10.34
Min Turbidity:	7.67
Max Turbidity:	9.74
Avg Turbidity:	8.39

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E07-TKVK-P1

5/03/10 14:36 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.60
Max Temp:	13.83
Avg Temp:	12.52
Min Cond:	21.56
Max Cond:	26.04
Avg Cond:	24.47
Min Salinity:	17.06
Max Salinity:	21.99
Avg Salinity:	20.10
Min Sigma-Theta:	13.04
Max Sigma-Theta:	16.59
Avg Sigma-Theta:	14.99
Min Turbidity:	9.90
Max Turbidity:	16.20
Avg Turbidity:	11.67

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E07-TKVK-P2

5/03/10 14:48 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	10.82
Max Temp:	15.23
Avg Temp:	12.17
Min Cond:	20.43
Max Cond:	27.41
Avg Cond:	25.15
Min Salinity:	15.34
Max Salinity:	23.77
Avg Salinity:	20.91
Min Sigma-Theta:	10.83
Max Sigma-Theta:	18.07
Avg Sigma-Theta:	15.65
Min Turbidity:	8.95
Max Turbidity:	17.10
Avg Turbidity:	11.53

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E07-TKVK-P3

5/03/10 15:01 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.29
Max Temp:	13.14
Avg Temp:	12.53
Min Cond:	22.17
Max Cond:	26.69
Avg Cond:	24.36
Min Salinity:	18.36
Max Salinity:	22.80
Avg Salinity:	19.97
Min Sigma-Theta:	13.45
Max Sigma-Theta:	17.25
Avg Sigma-Theta:	14.86
Min Turbidity:	9.01
Max Turbidity:	12.39
Avg Turbidity:	10.47

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E07-TARK-P1

5/03/10 15:26 (UTC)







CTD-OBS Calculated Statistics

Min Temp:	12.58
Max Temp:	16.64
Avg Temp:	13.71
Min Cond:	18.00
Max Cond:	23.75
Avg Cond:	22.05
Min Salinity:	12.59
Max Salinity:	19.38
Avg Salinity:	17.37
Min Sigma-Theta:	8.26
Max Sigma-Theta:	14.40
Avg Sigma-Theta:	12.66
Min Turbidity:	8.51
Max Turbidity:	11.52
Avg Turbidity:	9.39

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E07-TARK-P2

5/03/10 15:40 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	12.41
Max Temp:	16.87
Avg Temp:	13.61
Min Cond:	18.35
Max Cond:	24.03
Avg Cond:	22.64
Min Salinity:	12.90
Max Salinity:	19.71
Avg Salinity:	17.92
Min Sigma-Theta:	8.86
Max Sigma-Theta:	14.68
Avg Sigma-Theta:	13.10
Min Turbidity:	9.17
Max Turbidity:	14.13
Avg Turbidity:	10.55

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E07-TARK-P3

5/03/10 15:57 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	12.25
Max Temp:	17.43
Avg Temp:	13.37
Min Cond:	18.92
Max Cond:	23.97
Avg Cond:	22.86
Min Salinity:	13.36
Max Salinity:	19.64
Avg Salinity:	18.22
Min Sigma-Theta:	8.89
Max Sigma-Theta:	14.62
Avg Sigma-Theta:	13.37
Min Turbidity:	10.00
Max Turbidity:	14.49
Avg Turbidity:	11.00

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E08-THKN-P1

5/03/10 18:33 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	13.23
Max Temp:	17.39
Avg Temp:	14.70
Min Cond:	11.58
Max Cond:	20.92
Avg Cond:	18.01
Min Salinity:	7.85
Max Salinity:	16.58
Avg Salinity:	13.65
Min Sigma-Theta:	4.70
Max Sigma-Theta:	12.13
Avg Sigma-Theta:	9.63
Min Turbidity:	10.59
Max Turbidity:	17.41
Avg Turbidity:	14.38

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E08-THKN-P2

5/03/10 18:45 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	13.73
Max Temp:	17.32
Avg Temp:	15.34
Min Cond:	11.79
Max Cond:	20.27
Avg Cond:	16.67
Min Salinity:	8.02
Max Salinity:	15.87
Avg Salinity:	12.36
Min Sigma-Theta:	4.85
Max Sigma-Theta:	11.53
Avg Sigma-Theta:	8.53
Min Turbidity:	11.79
Max Turbidity:	15.28
Avg Turbidity:	13.83

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E08-THKN-P3

5/03/10 18:52 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.42
Max Temp:	17.25
Avg Temp:	15.44
Min Cond:	12.52
Max Cond:	18.54
Avg Cond:	16.45
Min Salinity:	8.58
Max Salinity:	14.10
Avg Salinity:	12.12
Min Sigma-Theta:	5.28
Max Sigma-Theta:	9.98
Avg Sigma-Theta:	8.32
Min Turbidity:	9.51
Max Turbidity:	16.42
Avg Turbidity:	14.43

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E08-TNBN-P1

5/03/10 18:19 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	12.48
Max Temp:	15.78
Avg Temp:	13.96
Min Cond:	18.01
Max Cond:	22.93
Avg Cond:	20.50
Min Salinity:	13.32
Max Salinity:	18.70
Avg Salinity:	15.99
Min Sigma-Theta:	9.15
Max Sigma-Theta:	13.89
Avg Sigma-Theta:	11.56
Min Turbidity:	8.27
Max Turbidity:	14.50
Avg Turbidity:	10.98

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E08-TNBN-P2

5/03/10 18:31 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.05
Max Temp:	15.82
Avg Temp:	15.47
Min Cond:	18.50
Max Cond:	19.10
Avg Cond:	18.65
Min Salinity:	13.48
Max Salinity:	14.70
Avg Salinity:	13.79
Min Sigma-Theta:	9.20
Max Sigma-Theta:	10.55
Avg Sigma-Theta:	9.58
Min Turbidity:	8.26
Max Turbidity:	9.84
Avg Turbidity:	9.27

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E08-TNBN-P3

5/03/10 18:41 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.64
Max Temp:	16.74
Avg Temp:	15.58
Min Cond:	17.02
Max Cond:	18.40
Avg Cond:	17.74
Min Salinity:	12.12
Max Salinity:	13.90
Avg Salinity:	13.05
Min Sigma-Theta:	8.08
Max Sigma-Theta:	9.83
Avg Sigma-Theta:	9.02
Min Turbidity:	6.77
Max Turbidity:	9.13
Avg Turbidity:	8.24

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E08-TNBS-P1

5/03/10 19:18 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	12.30
Max Temp:	14.92
Avg Temp:	13.33
Min Cond:	20.10
Max Cond:	24.39
Avg Cond:	22.64
Min Salinity:	15.02
Max Salinity:	20.09
Avg Salinity:	18.05
Min Sigma-Theta:	11.00
Max Sigma-Theta:	14.99
Avg Sigma-Theta:	13.28
Min Turbidity:	7.48
Max Turbidity:	12.68
Avg Turbidity:	9.80

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E08-TNBS-P2

5/03/10 19:32 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.53
Max Temp:	14.91
Avg Temp:	13.00
Min Cond:	19.96
Max Cond:	26.07
Avg Cond:	23.32
Min Salinity:	15.01
Max Salinity:	22.07
Avg Salinity:	18.84
Min Sigma-Theta:	10.44
Max Sigma-Theta:	16.65
Avg Sigma-Theta:	13.90
Min Turbidity:	8.07
Max Turbidity:	12.32
Avg Turbidity:	9.89

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E08-TNBS-P3

5/03/10 19:44 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.02
Max Temp:	15.41
Avg Temp:	14.99
Min Cond:	18.80
Max Cond:	20.90
Avg Cond:	20.04
Min Salinity:	13.61
Max Salinity:	16.23
Avg Salinity:	15.07
Min Sigma-Theta:	9.28
Max Sigma-Theta:	11.73
Avg Sigma-Theta:	10.64
Min Turbidity:	8.00
Max Turbidity:	12.22
Avg Turbidity:	9.74

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E08-TKVK-P1

5/03/10 20:09 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	10.97
Max Temp:	14.71
Avg Temp:	12.62
Min Cond:	21.10
Max Cond:	27.25
Avg Cond:	24.60
Min Salinity:	16.57
Max Salinity:	23.53
Avg Salinity:	20.23
Min Sigma-Theta:	11.91
Max Sigma-Theta:	17.86
Avg Sigma-Theta:	15.05
Min Turbidity:	9.29
Max Turbidity:	11.36
Avg Turbidity:	10.40

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E08-TKVK-P2

5/03/10 20:23 (UTC)







CTD-OBS Calculated Statistics

Min Temp:	10.72
Max Temp:	15.20
Avg Temp:	12.39
Min Cond:	20.90
Max Cond:	27.75
Avg Cond:	24.94
Min Salinity:	15.74
Max Salinity:	24.15
Avg Salinity:	20.66
Min Sigma-Theta:	11.14
Max Sigma-Theta:	18.39
Avg Sigma-Theta:	15.42
Min Turbidity:	8.70
Max Turbidity:	13.37
Avg Turbidity:	10.59

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E08-TKVK-P3

5/03/10 20:35 (UTC)







CTD-OBS Calculated Statistics

Min Temp:	10.73
Max Temp:	15.29
Avg Temp:	12.14
Min Cond:	20.92
Max Cond:	27.72
Avg Cond:	25.29
Min Salinity:	15.72
Max Salinity:	24.13
Avg Salinity:	21.09
Min Sigma-Theta:	11.11
Max Sigma-Theta:	18.37
Avg Sigma-Theta:	15.79
Min Turbidity:	7.45
Max Turbidity:	11.51
Avg Turbidity:	9.92

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E08-TARK-P1

5/03/10 21:01 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	12.43
Max Temp:	15.53
Avg Temp:	13.94
Min Cond:	21.23
Max Cond:	24.42
Avg Cond:	22.66
Min Salinity:	15.49
Max Salinity:	20.06
Avg Salinity:	17.77
Min Sigma-Theta:	10.69
Max Sigma-Theta:	14.94
Avg Sigma-Theta:	12.92
Min Turbidity:	7.91
Max Turbidity:	18.79
Avg Turbidity:	10.48

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E08-TARK-P2

5/03/10 21:13 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	12.14
Max Temp:	15.67
Avg Temp:	13.67
Min Cond:	21.25
Max Cond:	24.90
Avg Cond:	23.05
Min Salinity:	15.84
Max Salinity:	20.64
Avg Salinity:	18.27
Min Sigma-Theta:	11.13
Max Sigma-Theta:	15.44
Avg Sigma-Theta:	13.36
Min Turbidity:	7.10
Max Turbidity:	17.74
Avg Turbidity:	11.15

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E08-TARK-P3

5/03/10 21:24 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	11.96
Max Temp:	16.57
Avg Temp:	13.95
Min Cond:	19.57
Max Cond:	25.07
Avg Cond:	23.00
Min Salinity:	14.16
Max Salinity:	21.07
Avg Salinity:	18.12
Min Sigma-Theta:	9.67
Max Sigma-Theta:	15.80
Avg Sigma-Theta:	13.19
Min Turbidity:	8.04
Max Turbidity:	34.33
Avg Turbidity:	15.20

APPENDIX 9: Trip 6 Real Time Survey Events E12-E13

- Vertically Averaged Current Vector Plots
- CTD-OBS Vertical Profiles



LEGEND FOR CURRENT VELOCITY MAPPINGS:

CURRENT VECTOR SCALE
1" = 150 CM/S

SCALE : 1"=1000'
1000 0 1000

NOTES:

1. GRID SYSTEM IS IN FEET AND IS THE NEW JERSEY STATE PLANE COORDINATE SYSTEM, NAD83.
2. ORTHOPHOTO IMAGERY ARE TRUE COLOR ONE FOOT GROUND SAMPLE DISTANCE IMAGES PRODUCED FROM AERIAL PHOTOS FLOWN IN 2007 AND OBTAINED FROM THE NEW JERSEY GEOGRAPHIC INFORMATION NETWORK (NJGIN).
3. THE INFORMATION PRESENTED ON THESE DRAWINGS REPRESENTS THE RESULTS OF A SURVEY PEFORMED BY OCEAN SURVEYS, INC. ON 24 MAY 2010 AND CAN ONLY BE CONSIDERED AS INDICATING THE CONDITIONS EXISTING AT THAT TIME. REUSE OF THIS INFORMATION BY CLIENT OF OTHERS BEYOND THE SCOPE OF WORK FOR WHICH IT WAS ACQUIRED SHALL BE AT THE SOLE RISK OF THE USER AND WITHOUT LIABILITY TO OSI.

OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388-4631
www.oceansurveys.com

Vertically Averaged Current Data
Program N01, Location Map
24 May 2010
New Jersey - New York Waters



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Ebb Tide
Program N01, Event 12
24 May 2010, 10:56 - 13:23 (UTC) Hours
New Jersey - New York Waters



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Flood Tide
Program N01, Event 13
24 May 2010, 17:24 - 19:36 (UTC) Hours
New Jersey - New York Waters

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E12-THKN-P1

5/24/10 11:21 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	15.16
Max Temp:	16.17
Avg Temp:	15.48
Min Cond:	21.24
Max Cond:	24.60
Avg Cond:	23.63
Min Salinity:	15.64
Max Salinity:	18.85
Avg Salinity:	17.89
Min Sigma-Theta:	10.88
Max Sigma-Theta:	13.52
Avg Sigma-Theta:	12.73
Min Turbidity:	12.08
Max Turbidity:	21.45
Avg Turbidity:	16.87

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E12-THKN-P2

5/24/10 11:39 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.16
Max Temp:	16.15
Avg Temp:	15.57
Min Cond:	21.39
Max Cond:	24.49
Avg Cond:	23.32
Min Salinity:	15.76
Max Salinity:	18.74
Avg Salinity:	17.59
Min Sigma-Theta:	10.98
Max Sigma-Theta:	13.45
Avg Sigma-Theta:	12.49
Min Turbidity:	12.28
Max Turbidity:	19.33
Avg Turbidity:	16.54

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E12-THKN-P3

5/24/10 11:49 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.35
Max Temp:	16.57
Avg Temp:	15.72
Min Cond:	20.49
Max Cond:	24.06
Avg Cond:	23.23
Min Salinity:	14.99
Max Salinity:	18.30
Avg Salinity:	17.45
Min Sigma-Theta:	10.43
Max Sigma-Theta:	13.06
Avg Sigma-Theta:	12.36
Min Turbidity:	13.23
Max Turbidity:	18.08
Avg Turbidity:	16.23

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E12-TNBN-P1

5/24/10 11:14 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.65
Max Temp:	15.52
Avg Temp:	15.00
Min Cond:	24.41
Max Cond:	26.15
Avg Cond:	25.40
Min Salinity:	17.85
Max Salinity:	20.39
Avg Salinity:	19.52
Min Sigma-Theta:	12.70
Max Sigma-Theta:	14.80
Avg Sigma-Theta:	14.08
Min Turbidity:	10.21
Max Turbidity:	16.43
Avg Turbidity:	12.14

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E12-TNBN-P2

5/24/10 11:23 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.09
Max Temp:	15.63
Avg Temp:	15.36
Min Cond:	23.33
Max Cond:	25.26
Avg Cond:	24.47
Min Salinity:	17.56
Max Salinity:	19.42
Avg Salinity:	18.64
Min Sigma-Theta:	12.46
Max Sigma-Theta:	13.98
Avg Sigma-Theta:	13.33
Min Turbidity:	9.24
Max Turbidity:	10.94
Avg Turbidity:	9.80

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E12-TNBN-P3

5/24/10 11:31 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.15
Max Temp:	15.68
Avg Temp:	15.33
Min Cond:	23.34
Max Cond:	25.19
Avg Cond:	24.69
Min Salinity:	17.55
Max Salinity:	19.37
Avg Salinity:	18.84
Min Sigma-Theta:	12.44
Max Sigma-Theta:	13.89
Avg Sigma-Theta:	13.49
Min Turbidity:	10.27
Max Turbidity:	11.57
Avg Turbidity:	11.15

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E12-TNBS-P1

5/24/10 12:08 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.55
Max Temp:	15.39
Avg Temp:	14.90
Min Cond:	24.96
Max Cond:	26.99
Avg Cond:	26.10
Min Salinity:	19.01
Max Salinity:	21.17
Avg Salinity:	20.23
Min Sigma-Theta:	13.68
Max Sigma-Theta:	15.43
Avg Sigma-Theta:	14.64
Min Turbidity:	10.00
Max Turbidity:	15.30
Avg Turbidity:	10.98

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E12-TNBS-P2

5/24/10 12:18 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.15
Max Temp:	15.50
Avg Temp:	14.67
Min Cond:	24.83
Max Cond:	27.81
Avg Cond:	26.66
Min Salinity:	18.53
Max Salinity:	22.11
Avg Salinity:	20.82
Min Sigma-Theta:	13.22
Max Sigma-Theta:	16.22
Avg Sigma-Theta:	15.14
Min Turbidity:	9.86
Max Turbidity:	13.24
Avg Turbidity:	10.90

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E12-TNBS-P3

5/24/10 12:26 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.08
Max Temp:	15.82
Avg Temp:	15.23
Min Cond:	24.81
Max Cond:	25.50
Avg Cond:	25.25
Min Salinity:	18.49
Max Salinity:	19.63
Avg Salinity:	19.30
Min Sigma-Theta:	13.29
Max Sigma-Theta:	14.14
Avg Sigma-Theta:	13.87
Min Turbidity:	11.80
Max Turbidity:	19.07
Avg Turbidity:	14.40

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E12-TKVK-P1

5/24/10 12:46 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.64
Max Temp:	15.18
Avg Temp:	14.97
Min Cond:	25.55
Max Cond:	26.68
Avg Cond:	26.06
Min Salinity:	19.70
Max Salinity:	20.90
Avg Salinity:	20.16
Min Sigma-Theta:	14.20
Max Sigma-Theta:	15.17
Avg Sigma-Theta:	14.57
Min Turbidity:	9.86
Max Turbidity:	20.41
Avg Turbidity:	12.65

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E12-TKVK-P2

5/24/10 13:01 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.39
Max Temp:	15.26
Avg Temp:	14.80
Min Cond:	25.40
Max Cond:	27.34
Avg Cond:	26.57
Min Salinity:	19.56
Max Salinity:	21.55
Avg Salinity:	20.70
Min Sigma-Theta:	14.06
Max Sigma-Theta:	15.75
Avg Sigma-Theta:	15.02
Min Turbidity:	9.65
Max Turbidity:	17.74
Avg Turbidity:	12.60

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E12-TKVK-P3

5/24/10 13:07 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.53
Max Temp:	15.48
Avg Temp:	14.78
Min Cond:	25.81
Max Cond:	27.10
Avg Cond:	26.55
Min Salinity:	20.00
Max Salinity:	21.21
Avg Salinity:	20.69
Min Sigma-Theta:	14.40
Max Sigma-Theta:	15.46
Avg Sigma-Theta:	15.02
Min Turbidity:	12.93
Max Turbidity:	15.53
Avg Turbidity:	13.70

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E12-TARK-P1

5/24/10 13:28 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.25
Max Temp:	15.71
Avg Temp:	15.61
Min Cond:	25.80
Max Cond:	26.28
Avg Cond:	26.01
Min Salinity:	19.61
Max Salinity:	20.16
Avg Salinity:	19.79
Min Sigma-Theta:	13.97
Max Sigma-Theta:	14.49
Avg Sigma-Theta:	14.16
Min Turbidity:	8.62
Max Turbidity:	11.98
Avg Turbidity:	9.20

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E12-TARK-P2

5/24/10 13:35 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.35
Max Temp:	15.78
Avg Temp:	15.22
Min Cond:	25.72
Max Cond:	27.39
Avg Cond:	26.39
Min Salinity:	19.35
Max Salinity:	21.67
Avg Salinity:	20.32
Min Sigma-Theta:	14.01
Max Sigma-Theta:	15.87
Avg Sigma-Theta:	14.65
Min Turbidity:	8.15
Max Turbidity:	22.74
Avg Turbidity:	10.38

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E12-TARK-P3

5/24/10 13:42 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.44
Max Temp:	15.69
Avg Temp:	15.26
Min Cond:	25.28
Max Cond:	27.36
Avg Cond:	26.15
Min Salinity:	18.30
Max Salinity:	21.55
Avg Salinity:	20.05
Min Sigma-Theta:	13.95
Max Sigma-Theta:	15.75
Avg Sigma-Theta:	14.48
Min Turbidity:	9.74
Max Turbidity:	21.67
Avg Turbidity:	12.64

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E13-THKN-P1

5/24/10 18:08 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	18.11
Max Temp:	18.87
Avg Temp:	18.42
Min Cond:	16.41
Max Cond:	17.75
Avg Cond:	17.10
Min Salinity:	11.09
Max Salinity:	12.25
Avg Salinity:	11.69
Min Sigma-Theta:	6.88
Max Sigma-Theta:	7.91
Avg Sigma-Theta:	7.41
Min Turbidity:	15.37
Max Turbidity:	25.40
Avg Turbidity:	20.33

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E13-THKN-P2

5/24/10 18:16 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	17.93
Max Temp:	18.96
Avg Temp:	18.35
Min Cond:	16.26
Max Cond:	18.28
Avg Cond:	17.42
Min Salinity:	10.92
Max Salinity:	12.71
Avg Salinity:	11.95
Min Sigma-Theta:	6.71
Max Sigma-Theta:	8.29
Avg Sigma-Theta:	7.63
Min Turbidity:	14.95
Max Turbidity:	32.37
Avg Turbidity:	23.44

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E13-THKN-P3

5/24/10 18:22 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	17.98
Max Temp:	19.08
Avg Temp:	18.66
Min Cond:	16.40
Max Cond:	18.19
Avg Cond:	17.06
Min Salinity:	10.99
Max Salinity:	12.62
Avg Salinity:	11.59
Min Sigma-Theta:	6.75
Max Sigma-Theta:	8.22
Avg Sigma-Theta:	7.29
Min Turbidity:	14.96
Max Turbidity:	48.59
Avg Turbidity:	23.74

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E13-TNBN-P1

5/24/10 17:37 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.24
Max Temp:	17.81
Avg Temp:	15.98
Min Cond:	20.27
Max Cond:	24.69
Avg Cond:	23.20
Min Salinity:	15.02
Max Salinity:	18.86
Avg Salinity:	17.38
Min Sigma-Theta:	10.04
Max Sigma-Theta:	13.52
Avg Sigma-Theta:	12.24
Min Turbidity:	13.10
Max Turbidity:	34.44
Avg Turbidity:	18.67

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E13-TNBN-P2

5/24/10 17:45 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.84
Max Temp:	17.13
Avg Temp:	16.42
Min Cond:	20.85
Max Cond:	23.07
Avg Cond:	22.12
Min Salinity:	15.01
Max Salinity:	17.25
Avg Salinity:	16.26
Min Sigma-Theta:	10.36
Max Sigma-Theta:	12.17
Avg Sigma-Theta:	11.34
Min Turbidity:	17.60
Max Turbidity:	19.21
Avg Turbidity:	18.04

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E13-TNBN-P3

5/24/10 17:53 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.98
Max Temp:	16.87
Avg Temp:	16.32
Min Cond:	20.67
Max Cond:	23.46
Avg Cond:	22.40
Min Salinity:	14.91
Max Salinity:	17.51
Avg Salinity:	16.50
Min Sigma-Theta:	10.19
Max Sigma-Theta:	12.35
Avg Sigma-Theta:	11.51
Min Turbidity:	12.24
Max Turbidity:	14.53
Avg Turbidity:	13.03

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E13-TNBS-P1

5/24/10 18:25 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.58
Max Temp:	15.89
Avg Temp:	15.23
Min Cond:	24.05
Max Cond:	26.76
Avg Cond:	25.52
Min Salinity:	18.00
Max Salinity:	20.95
Avg Salinity:	19.53
Min Sigma-Theta:	12.72
Max Sigma-Theta:	15.25
Avg Sigma-Theta:	14.04
Min Turbidity:	12.34
Max Turbidity:	18.72
Avg Turbidity:	14.73

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E13-TNBS-P2

5/24/10 18:33 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.58
Max Temp:	15.64
Avg Temp:	15.04
Min Cond:	25.10
Max Cond:	26.82
Avg Cond:	25.94
Min Salinity:	19.10
Max Salinity:	21.01
Avg Salinity:	20.03
Min Sigma-Theta:	13.63
Max Sigma-Theta:	15.30
Avg Sigma-Theta:	14.46
Min Turbidity:	10.43
Max Turbidity:	18.56
Avg Turbidity:	12.33

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E13-TNBS-P3

5/24/10 18:40 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.44
Max Temp:	15.90
Avg Temp:	15.57
Min Cond:	25.09
Max Cond:	25.37
Avg Cond:	25.27
Min Salinity:	18.75
Max Salinity:	19.32
Avg Salinity:	19.16
Min Sigma-Theta:	13.29
Max Sigma-Theta:	13.84
Avg Sigma-Theta:	13.69
Min Turbidity:	12.04
Max Turbidity:	12.73
Avg Turbidity:	12.37

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E13-TKVK-P1

5/24/10 19:03 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.10
Max Temp:	14.81
Avg Temp:	14.44
Min Cond:	27.32
Max Cond:	29.06
Avg Cond:	28.25
Min Salinity:	21.20
Max Salinity:	23.23
Avg Salinity:	22.33
Min Sigma-Theta:	15.30
Max Sigma-Theta:	17.09
Avg Sigma-Theta:	16.33
Min Turbidity:	14.05
Max Turbidity:	17.70
Avg Turbidity:	15.88

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E13-TKVK-P2

5/24/10 19:16 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.09
Max Temp:	14.73
Avg Temp:	14.36
Min Cond:	27.02
Max Cond:	28.76
Avg Cond:	27.95
Min Salinity:	21.19
Max Salinity:	22.97
Avg Salinity:	22.13
Min Sigma-Theta:	15.42
Max Sigma-Theta:	16.89
Avg Sigma-Theta:	16.20
Min Turbidity:	15.23
Max Turbidity:	26.11
Avg Turbidity:	18.23

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E13-TKVK-P3

5/24/10 19:22 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.33
Max Temp:	14.87
Avg Temp:	14.59
Min Cond:	27.03
Max Cond:	28.02
Avg Cond:	27.45
Min Salinity:	21.11
Max Salinity:	22.18
Avg Salinity:	21.56
Min Sigma-Theta:	15.33
Max Sigma-Theta:	16.24
Avg Sigma-Theta:	15.72
Min Turbidity:	12.77
Max Turbidity:	18.46
Avg Turbidity:	15.55

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E13-TARK-P1

5/24/10 19:42 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	15.00
Max Temp:	16.00
Avg Temp:	15.33
Min Cond:	25.58
Max Cond:	26.15
Avg Cond:	25.91
Min Salinity:	19.44
Max Salinity:	20.21
Avg Salinity:	19.86
Min Sigma-Theta:	13.87
Max Sigma-Theta:	14.58
Avg Sigma-Theta:	14.27
Min Turbidity:	9.46
Max Turbidity:	14.92
Avg Turbidity:	10.88

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E13-TARK-P2

5/24/10 19:50 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.88
Max Temp:	15.90
Avg Temp:	15.40
Min Cond:	25.62
Max Cond:	26.65
Avg Cond:	25.96
Min Salinity:	19.41
Max Salinity:	20.71
Avg Salinity:	19.86
Min Sigma-Theta:	13.82
Max Sigma-Theta:	15.01
Avg Sigma-Theta:	14.26
Min Turbidity:	9.83
Max Turbidity:	23.91
Avg Turbidity:	12.13

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E13-TARK-P3

5/24/10 19:57 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	14.95
Max Temp:	15.77
Avg Temp:	15.45
Min Cond:	25.65
Max Cond:	26.47
Avg Cond:	25.90
Min Salinity:	19.48
Max Salinity:	20.51
Avg Salinity:	19.79
Min Sigma-Theta:	13.90
Max Sigma-Theta:	14.84
Avg Sigma-Theta:	14.19
Min Turbidity:	8.47
Max Turbidity:	16.63
Avg Turbidity:	11.63

APPENDIX 10: Trip 7 Real Time Survey Events E17-E18

- Vertically Averaged Current Vector Plots
- CTD-OBS Vertical Profiles



LEGEND FOR CURRENT VELOCITY MAPPINGS:

CURRENT VECTOR SCALE
1" = 150 CM/S

SCALE : 1"=1000'
1000 0 1000

NOTES:

1. GRID SYSTEM IS IN FEET AND IS THE NEW JERSEY STATE PLANE COORDINATE SYSTEM, NAD83.
2. ORTHOPHOTO IMAGERY ARE TRUE COLOR ONE FOOT GROUND SAMPLE DISTANCE IMAGES PRODUCED FROM AERIAL PHOTOS FLOWN IN 2007 AND OBTAINED FROM THE NEW JERSEY GEOGRAPHIC INFORMATION NETWORK (NJGIN).
3. THE INFORMATION PRESENTED ON THESE DRAWINGS REPRESENTS THE RESULTS OF A SURVEY PEFORMED BY OCEAN SURVEYS, INC. ON 22 JUNE 2010 AND CAN ONLY BE CONSIDERED AS INDICATING THE CONDITIONS EXISTING AT THAT TIME. REUSE OF THIS INFORMATION BY CLIENT OF OTHERS BEYOND THE SCOPE OF WORK FOR WHICH IT WAS ACQUIRED SHALL BE AT THE SOLE RISK OF THE USER AND WITHOUT LIABILITY TO OSI.

OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388-4631
www.oceansurveys.com

Vertically Averaged Current Data
Program N01, Location Map
22 June 2010
New Jersey - New York Waters



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Ebb Tide
Program N01, Event 17
22 June 2010, 10:45 - 13:20 (UTC) Hours
New Jersey - New York Waters



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Flood Tide
Program N01, Event 18
22 June 2010, 13:26 - 19:28 (UTC) Hours
New Jersey - New York Waters

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E17-THKN-P1

6/22/10 11:18 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	22.44
Max Temp:	22.94
Avg Temp:	22.70
Min Cond:	28.95
Max Cond:	30.79
Avg Cond:	29.94
Min Salinity:	18.52
Max Salinity:	20.23
Avg Salinity:	19.50
Min Sigma-Theta:	11.40
Max Sigma-Theta:	12.92
Avg Sigma-Theta:	12.30
Min Turbidity:	6.02
Max Turbidity:	8.44
Avg Turbidity:	6.88

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E17-THKN-P2

6/22/10 11:31 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	22.26
Max Temp:	23.60
Avg Temp:	22.79
Min Cond:	27.90
Max Cond:	31.31
Avg Cond:	29.91
Min Salinity:	17.30
Max Salinity:	20.70
Avg Salinity:	19.43
Min Sigma-Theta:	10.41
Max Sigma-Theta:	13.33
Avg Sigma-Theta:	12.23
Min Turbidity:	6.17
Max Turbidity:	7.85
Avg Turbidity:	6.99

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E17-THKN-P3

6/22/10 11:40 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	22.46
Max Temp:	23.46
Avg Temp:	22.88
Min Cond:	28.18
Max Cond:	30.77
Avg Cond:	29.75
Min Salinity:	17.67
Max Salinity:	20.20
Avg Salinity:	19.26
Min Sigma-Theta:	10.68
Max Sigma-Theta:	12.88
Avg Sigma-Theta:	12.08
Min Turbidity:	7.45
Max Turbidity:	8.95
Avg Turbidity:	7.93

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E17-TNBN-P1

6/22/10 10:59 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.71
Max Temp:	22.48
Avg Temp:	21.92
Min Cond:	31.59
Max Cond:	32.93
Avg Cond:	32.50
Min Salinity:	20.55
Max Salinity:	22.15
Avg Salinity:	21.70
Min Sigma-Theta:	13.06
Max Sigma-Theta:	14.56
Avg Sigma-Theta:	14.15
Min Turbidity:	3.22
Max Turbidity:	5.83
Avg Turbidity:	4.32

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E17-TNBN-P2

6/22/10 11:09 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.51
Max Temp:	22.32
Avg Temp:	22.06
Min Cond:	30.79
Max Cond:	32.08
Avg Cond:	31.47
Min Salinity:	19.62
Max Salinity:	21.38
Avg Salinity:	20.70
Min Sigma-Theta:	12.60
Max Sigma-Theta:	13.90
Avg Sigma-Theta:	13.37
Min Turbidity:	3.49
Max Turbidity:	4.11
Avg Turbidity:	3.77

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E17-TNBN-P3

6/22/10 11:27 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.86
Max Temp:	22.48
Avg Temp:	22.13
Min Cond:	30.35
Max Cond:	31.98
Avg Cond:	31.40
Min Salinity:	20.20
Max Salinity:	21.27
Avg Salinity:	20.83
Min Sigma-Theta:	12.92
Max Sigma-Theta:	13.81
Avg Sigma-Theta:	13.45
Min Turbidity:	4.22
Max Turbidity:	8.53
Avg Turbidity:	5.67

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E17-TNBS-P1

6/22/10 12:08 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.67
Max Temp:	22.35
Avg Temp:	21.79
Min Cond:	31.38
Max Cond:	33.19
Avg Cond:	32.95
Min Salinity:	20.71
Max Salinity:	22.37
Avg Salinity:	22.13
Min Sigma-Theta:	13.07
Max Sigma-Theta:	14.73
Avg Sigma-Theta:	14.52
Min Turbidity:	2.80
Max Turbidity:	6.27
Avg Turbidity:	5.20

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E17-TNBS-P2

6/22/10 12:16 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.25
Max Temp:	22.17
Avg Temp:	21.68
Min Cond:	32.08
Max Cond:	33.93
Avg Cond:	33.22
Min Salinity:	21.01
Max Salinity:	23.14
Avg Salinity:	22.37
Min Sigma-Theta:	13.37
Max Sigma-Theta:	15.43
Avg Sigma-Theta:	14.73
Min Turbidity:	2.87
Max Turbidity:	4.80
Avg Turbidity:	3.36

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E17-TNBS-P3

6/22/10 12:23 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	22.00
Max Temp:	22.13
Avg Temp:	22.08
Min Cond:	32.06
Max Cond:	32.55
Avg Cond:	32.45
Min Salinity:	21.41
Max Salinity:	21.90
Avg Salinity:	21.65
Min Sigma-Theta:	13.79
Max Sigma-Theta:	14.12
Avg Sigma-Theta:	14.05
Min Turbidity:	3.21
Max Turbidity:	6.78
Avg Turbidity:	5.24

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E17-TKVK-P1

6/22/10 12:50 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.87
Max Temp:	22.00
Avg Temp:	21.90
Min Cond:	32.89
Max Cond:	32.96
Avg Cond:	32.92
Min Salinity:	22.02
Max Salinity:	22.09
Avg Salinity:	22.05
Min Sigma-Theta:	14.41
Max Sigma-Theta:	14.48
Avg Sigma-Theta:	14.44
Min Turbidity:	2.66
Max Turbidity:	6.14
Avg Turbidity:	4.67

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E17-TKVK-P2

6/22/10 12:58 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.43
Max Temp:	22.03
Avg Temp:	21.64
Min Cond:	32.76
Max Cond:	33.62
Avg Cond:	33.30
Min Salinity:	21.78
Max Salinity:	22.81
Avg Salinity:	22.46
Min Sigma-Theta:	14.12
Max Sigma-Theta:	15.14
Avg Sigma-Theta:	14.81
Min Turbidity:	3.40
Max Turbidity:	5.33
Avg Turbidity:	4.14

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E17-TKVK-P3

6/22/10 13:05 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.32
Max Temp:	22.03
Avg Temp:	21.53
Min Cond:	32.74
Max Cond:	33.75
Avg Cond:	33.44
Min Salinity:	21.86
Max Salinity:	22.96
Avg Salinity:	22.63
Min Sigma-Theta:	14.12
Max Sigma-Theta:	15.27
Avg Sigma-Theta:	14.96
Min Turbidity:	3.14
Max Turbidity:	4.41
Avg Turbidity:	3.71

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E17-TARK-P1

6/22/10 13:25 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.76
Max Temp:	22.55
Avg Temp:	22.23
Min Cond:	32.79
Max Cond:	33.20
Avg Cond:	33.01
Min Salinity:	21.74
Max Salinity:	22.22
Avg Salinity:	21.95
Min Sigma-Theta:	14.05
Max Sigma-Theta:	14.54
Avg Sigma-Theta:	14.28
Min Turbidity:	3.06
Max Turbidity:	5.65
Avg Turbidity:	4.26

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E17-TARK-P2

6/22/10 13:31 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.37
Max Temp:	22.46
Avg Temp:	22.14
Min Cond:	32.31
Max Cond:	33.74
Avg Cond:	33.05
Min Salinity:	20.27
Max Salinity:	22.94
Avg Salinity:	21.98
Min Sigma-Theta:	13.07
Max Sigma-Theta:	15.24
Avg Sigma-Theta:	14.32
Min Turbidity:	2.62
Max Turbidity:	5.34
Avg Turbidity:	3.20

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E17-TARK-P3

6/22/10 13:36 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.21
Max Temp:	22.42
Avg Temp:	22.06
Min Cond:	32.33
Max Cond:	33.75
Avg Cond:	33.11
Min Salinity:	21.10
Max Salinity:	22.93
Avg Salinity:	22.09
Min Sigma-Theta:	13.69
Max Sigma-Theta:	15.23
Avg Sigma-Theta:	14.43
Min Turbidity:	2.35
Max Turbidity:	15.07
Avg Turbidity:	6.29

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E18-THKN-P1

6/22/10 17:43 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.59
Max Temp:	25.34
Avg Temp:	24.98
Min Cond:	24.46
Max Cond:	26.20
Avg Cond:	25.23
Min Salinity:	14.47
Max Salinity:	16.15
Avg Salinity:	15.33
Min Sigma-Theta:	8.07
Max Sigma-Theta:	9.27
Avg Sigma-Theta:	8.58
Min Turbidity:	8.12
Max Turbidity:	16.72
Avg Turbidity:	10.98

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E18-THKN-P2

6/22/10 17:51 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.52
Max Temp:	25.38
Avg Temp:	24.98
Min Cond:	24.58
Max Cond:	26.52
Avg Cond:	25.47
Min Salinity:	14.54
Max Salinity:	16.39
Avg Salinity:	15.48
Min Sigma-Theta:	8.10
Max Sigma-Theta:	9.47
Avg Sigma-Theta:	8.71
Min Turbidity:	8.24
Max Turbidity:	15.79
Avg Turbidity:	9.57

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E18-THKN-P3

6/22/10 17:57 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.49
Max Temp:	25.56
Avg Temp:	24.99
Min Cond:	24.20
Max Cond:	26.49
Avg Cond:	25.54
Min Salinity:	14.54
Max Salinity:	16.38
Avg Salinity:	15.59
Min Sigma-Theta:	7.80
Max Sigma-Theta:	9.47
Avg Sigma-Theta:	8.74
Min Turbidity:	9.64
Max Turbidity:	29.77
Avg Turbidity:	14.18

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E18-TNBN-P1

6/22/10 17:38 (UTC)









CTD-OBS Calculated Statistics

Min Temp:	21.84
Max Temp:	26.29
Avg Temp:	22.90
Min Cond:	29.42
Max Cond:	32.52
Avg Cond:	31.26
Min Salinity:	18.16
Max Salinity:	21.79
Avg Salinity:	20.39
Min Sigma-Theta:	10.62
Max Sigma-Theta:	14.25
Avg Sigma-Theta:	12.94
Min Turbidity:	4.22
Max Turbidity:	18.81
Avg Turbidity:	8.95

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E18-TNBN-P2

6/22/10 17:45 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	22.78
Max Temp:	23.17
Avg Temp:	22.97
Min Cond:	29.84
Max Cond:	30.82
Avg Cond:	30.40
Min Salinity:	17.35
Max Salinity:	20.09
Avg Salinity:	19.21
Min Sigma-Theta:	10.24
Max Sigma-Theta:	12.73
Avg Sigma-Theta:	11.93
Min Turbidity:	2.95
Max Turbidity:	6.28
Avg Turbidity:	5.15

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E18-TNBN-P3

6/22/10 17:52 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	23.00
Max Temp:	23.61
Avg Temp:	23.41
Min Cond:	29.94
Max Cond:	31.00
Avg Cond:	30.50
Min Salinity:	16.41
Max Salinity:	19.92
Avg Salinity:	18.79
Min Sigma-Theta:	11.13
Max Sigma-Theta:	12.42
Avg Sigma-Theta:	11.91
Min Turbidity:	3.46
Max Turbidity:	9.76
Avg Turbidity:	5.67

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E18-TNBS-P1

6/22/10 18:26 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.82
Max Temp:	22.50
Avg Temp:	21.96
Min Cond:	32.91
Max Cond:	33.08
Avg Cond:	33.01
Min Salinity:	21.77
Max Salinity:	22.21
Avg Salinity:	22.09
Min Sigma-Theta:	14.03
Max Sigma-Theta:	14.58
Avg Sigma-Theta:	14.45
Min Turbidity:	3.26
Max Turbidity:	9.71
Avg Turbidity:	5.18

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E18-TNBS-P2

6/22/10 18:33 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.62
Max Temp:	22.28
Avg Temp:	21.93
Min Cond:	32.96
Max Cond:	33.33
Avg Cond:	33.14
Min Salinity:	21.43
Max Salinity:	22.50
Avg Salinity:	22.17
Min Sigma-Theta:	14.11
Max Sigma-Theta:	14.85
Avg Sigma-Theta:	14.53
Min Turbidity:	2.23
Max Turbidity:	7.47
Avg Turbidity:	3.70

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E18-TNBS-P3

6/22/10 18:39 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.89
Max Temp:	22.19
Avg Temp:	22.08
Min Cond:	32.80
Max Cond:	33.06
Avg Cond:	33.01
Min Salinity:	21.10
Max Salinity:	22.07
Avg Salinity:	21.92
Min Sigma-Theta:	13.08
Max Sigma-Theta:	14.41
Avg Sigma-Theta:	14.25
Min Turbidity:	5.11
Max Turbidity:	8.11
Avg Turbidity:	6.63

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E18-TKVK-P1

6/22/10 18:59 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.00
Max Temp:	22.08
Avg Temp:	21.17
Min Cond:	33.84
Max Cond:	34.68
Avg Cond:	34.44
Min Salinity:	22.62
Max Salinity:	23.84
Avg Salinity:	23.57
Min Sigma-Theta:	14.88
Max Sigma-Theta:	16.02
Avg Sigma-Theta:	15.77
Min Turbidity:	10.25
Max Turbidity:	21.67
Avg Turbidity:	15.72

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E18-TKVK-P2

6/22/10 19:08 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.01
Max Temp:	21.53
Avg Temp:	21.21
Min Cond:	33.74
Max Cond:	34.55
Avg Cond:	34.20
Min Salinity:	22.72
Max Salinity:	23.74
Avg Salinity:	23.36
Min Sigma-Theta:	14.96
Max Sigma-Theta:	15.95
Avg Sigma-Theta:	15.60
Min Turbidity:	5.22
Max Turbidity:	17.75
Avg Turbidity:	7.95

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E18-TKVK-P3

6/22/10 19:13 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.22
Max Temp:	21.51
Avg Temp:	21.42
Min Cond:	33.40
Max Cond:	34.28
Avg Cond:	33.85
Min Salinity:	22.64
Max Salinity:	23.42
Avg Salinity:	22.99
Min Sigma-Theta:	14.96
Max Sigma-Theta:	15.65
Avg Sigma-Theta:	15.27
Min Turbidity:	4.10
Max Turbidity:	8.87
Avg Turbidity:	4.77

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E18-TARK-P1

6/22/10 19:33 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.84
Max Temp:	22.99
Avg Temp:	22.52
Min Cond:	33.01
Max Cond:	33.13
Avg Cond:	33.06
Min Salinity:	21.37
Max Salinity:	21.99
Avg Salinity:	21.80
Min Sigma-Theta:	13.16
Max Sigma-Theta:	14.25
Avg Sigma-Theta:	14.03
Min Turbidity:	2.16
Max Turbidity:	4.56
Avg Turbidity:	2.84

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E18-TARK-P2

6/22/10 19:39 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.99
Max Temp:	22.84
Avg Temp:	22.40
Min Cond:	32.91
Max Cond:	33.23
Avg Cond:	33.07
Min Salinity:	21.58
Max Salinity:	22.23
Avg Salinity:	21.91
Min Sigma-Theta:	13.19
Max Sigma-Theta:	14.55
Avg Sigma-Theta:	14.15
Min Turbidity:	2.01
Max Turbidity:	3.54
Avg Turbidity:	2.55

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E18-TARK-P3

6/22/10 19:45 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	21.68
Max Temp:	22.82
Avg Temp:	22.39
Min Cond:	32.70
Max Cond:	33.25
Avg Cond:	33.04
Min Salinity:	21.23
Max Salinity:	22.17
Avg Salinity:	21.87
Min Sigma-Theta:	13.40
Max Sigma-Theta:	14.59
Avg Sigma-Theta:	14.17
Min Turbidity:	2.12
Max Turbidity:	5.80
Avg Turbidity:	3.42

APPENDIX 11: Trip 8 Real Time Survey Events E21-E22

- Vertically Averaged Current Vector Plots
- CTD-OBS Vertical Profiles



LEGEND FOR CURRENT VELOCITY MAPPINGS:

CURRENT VECTOR SCALE
1" = 150 CM/S

SCALE : 1"=1000'
1000 0 1000

NOTES:

1. GRID SYSTEM IS IN FEET AND IS THE NEW JERSEY STATE PLANE COORDINATE SYSTEM, NAD83.
2. ORTHOPHOTO IMAGERY ARE TRUE COLOR ONE FOOT GROUND SAMPLE DISTANCE IMAGES PRODUCED FROM AERIAL PHOTOS FLOWN IN 2007 AND OBTAINED FROM THE NEW JERSEY GEOGRAPHIC INFORMATION NETWORK (NJGIN).
3. THE INFORMATION PRESENTED ON THESE DRAWINGS REPRESENTS THE RESULTS OF A SURVEY PEFORMED BY OCEAN SURVEYS, INC. ON 21 JULY 2010 AND CAN ONLY BE CONSIDERED AS INDICATING THE CONDITIONS EXISTING AT THAT TIME. REUSE OF THIS INFORMATION BY CLIENT OF OTHERS BEYOND THE SCOPE OF WORK FOR WHICH IT WAS ACQUIRED SHALL BE AT THE SOLE RISK OF THE USER AND WITHOUT LIABILITY TO OSI.

OCEAN SURVEYS, INC.
OLD SAYBROOK, CONNECTICUT
(860) 388-4631
www.oceansurveys.com

Vertically Averaged Current Data
Program N01, Location Map
21 July 2010
New Jersey - New York Waters



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Ebb Tide
Program N01, Event 21
21 July 2010, 10:30 - 12:46 (UTC) Hours
New Jersey - New York Waters



OCEAN SURVEYS, INC.

OLD SAYBROOK, CONNECTICUT

(860) 388-4631

www.oceansurveys.com

Vertically Averaged Current Data - Flood Tide
Program N01, Event 22
21 July 2010, 17:00 - 19:04 (UTC) Hours
New Jersey - New York Waters

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E21-THKN-P1

7/21/10 11:11 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.75
Max Temp:	27.93
Avg Temp:	27.24
Min Cond:	30.93
Max Cond:	34.39
Avg Cond:	32.95
Min Salinity:	17.92
Max Salinity:	20.78
Avg Salinity:	19.62
Min Sigma-Theta:	9.58
Max Sigma-Theta:	12.12
Avg Sigma-Theta:	11.10
Min Turbidity:	10.91
Max Turbidity:	14.65
Avg Turbidity:	12.09

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E21-THKN-P2

7/21/10 11:24 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.59
Max Temp:	28.00
Avg Temp:	27.26
Min Cond:	31.03
Max Cond:	34.83
Avg Cond:	33.08
Min Salinity:	17.55
Max Salinity:	21.14
Avg Salinity:	19.66
Min Sigma-Theta:	9.33
Max Sigma-Theta:	12.44
Avg Sigma-Theta:	11.12
Min Turbidity:	11.12
Max Turbidity:	12.88
Avg Turbidity:	11.87

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E21-THKN-P3

7/21/10 11:30 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.72
Max Temp:	27.97
Avg Temp:	27.22
Min Cond:	30.99
Max Cond:	34.55
Avg Cond:	33.29
Min Salinity:	18.08
Max Salinity:	20.90
Avg Salinity:	19.86
Min Sigma-Theta:	9.79
Max Sigma-Theta:	12.22
Avg Sigma-Theta:	11.29
Min Turbidity:	11.25
Max Turbidity:	14.40
Avg Turbidity:	12.56

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E21-TNBN-P1

7/21/10 10:46 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.77
Max Temp:	26.13
Avg Temp:	25.96
Min Cond:	33.30
Max Cond:	37.12
Avg Cond:	36.26
Min Salinity:	20.95
Max Salinity:	23.09
Avg Salinity:	22.45
Min Sigma-Theta:	12.54
Max Sigma-Theta:	14.16
Avg Sigma-Theta:	13.61
Min Turbidity:	6.13
Max Turbidity:	14.32
Avg Turbidity:	10.11

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E21-TNBN-P2

7/21/10 10:57 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.71
Max Temp:	26.20
Avg Temp:	26.09
Min Cond:	32.37
Max Cond:	36.17
Avg Cond:	34.86
Min Salinity:	19.21
Max Salinity:	22.29
Avg Salinity:	21.34
Min Sigma-Theta:	11.25
Max Sigma-Theta:	13.46
Avg Sigma-Theta:	12.73
Min Turbidity:	6.13
Max Turbidity:	11.69
Avg Turbidity:	8.85

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E21-TNBN-P3

7/21/10 11:05 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.86
Max Temp:	26.32
Avg Temp:	26.17
Min Cond:	32.01
Max Cond:	35.95
Avg Cond:	34.87
Min Salinity:	19.23
Max Salinity:	22.13
Avg Salinity:	21.33
Min Sigma-Theta:	10.48
Max Sigma-Theta:	13.32
Avg Sigma-Theta:	12.63
Min Turbidity:	7.62
Max Turbidity:	11.04
Avg Turbidity:	9.57

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E21-TNBS-P1

7/21/10 11:42 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.31
Max Temp:	26.12
Avg Temp:	25.80
Min Cond:	34.82
Max Cond:	38.31
Avg Cond:	36.97
Min Salinity:	21.27
Max Salinity:	24.07
Avg Salinity:	22.97
Min Sigma-Theta:	12.90
Max Sigma-Theta:	14.98
Avg Sigma-Theta:	14.05
Min Turbidity:	5.14
Max Turbidity:	9.46
Avg Turbidity:	7.72

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E21-TNBS-P2

7/21/10 11:51 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.21
Max Temp:	26.17
Avg Temp:	25.72
Min Cond:	35.04
Max Cond:	38.54
Avg Cond:	37.28
Min Salinity:	21.20
Max Salinity:	24.37
Avg Salinity:	23.23
Min Sigma-Theta:	12.90
Max Sigma-Theta:	15.27
Avg Sigma-Theta:	14.27
Min Turbidity:	5.14
Max Turbidity:	8.76
Avg Turbidity:	6.32

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E21-TNBS-P3

7/21/10 11:58 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.03
Max Temp:	26.28
Avg Temp:	26.16
Min Cond:	35.30
Max Cond:	36.23
Avg Cond:	35.81
Min Salinity:	21.40
Max Salinity:	22.32
Avg Salinity:	21.99
Min Sigma-Theta:	12.68
Max Sigma-Theta:	13.47
Avg Sigma-Theta:	13.20
Min Turbidity:	3.68
Max Turbidity:	12.37
Avg Turbidity:	9.21

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E21-TKVK-P1

7/21/10 12:15 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.24
Max Temp:	25.89
Avg Temp:	25.66
Min Cond:	36.26
Max Cond:	38.39
Avg Cond:	37.44
Min Salinity:	22.15
Max Salinity:	24.25
Avg Salinity:	23.37
Min Sigma-Theta:	13.70
Max Sigma-Theta:	15.17
Avg Sigma-Theta:	14.39
Min Turbidity:	5.20
Max Turbidity:	10.92
Avg Turbidity:	7.59

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E21-TKVK-P2

7/21/10 12:23 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.24
Max Temp:	25.89
Avg Temp:	25.61
Min Cond:	36.00
Max Cond:	38.40
Avg Cond:	37.55
Min Salinity:	22.21
Max Salinity:	24.25
Avg Salinity:	23.47
Min Sigma-Theta:	13.34
Max Sigma-Theta:	15.17
Avg Sigma-Theta:	14.47
Min Turbidity:	5.84
Max Turbidity:	8.12
Avg Turbidity:	6.91

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E21-TKVK-P3

7/21/10 12:30 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.13
Max Temp:	25.92
Avg Temp:	25.54
Min Cond:	35.17
Max Cond:	38.48
Avg Cond:	37.58
Min Salinity:	22.01
Max Salinity:	24.35
Avg Salinity:	23.54
Min Sigma-Theta:	13.14
Max Sigma-Theta:	15.27
Avg Sigma-Theta:	14.55
Min Turbidity:	5.56
Max Turbidity:	6.99
Avg Turbidity:	6.00

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E21-TARK-P1

7/21/10 12:52 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.35
Max Temp:	26.22
Avg Temp:	26.00
Min Cond:	36.41
Max Cond:	37.70
Avg Cond:	37.11
Min Salinity:	22.56
Max Salinity:	23.36
Avg Salinity:	22.96
Min Sigma-Theta:	13.68
Max Sigma-Theta:	14.28
Avg Sigma-Theta:	13.97
Min Turbidity:	6.60
Max Turbidity:	16.90
Avg Turbidity:	8.80

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E21-TARK-P2

7/21/10 13:00 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.80
Max Temp:	25.92
Avg Temp:	25.86
Min Cond:	24.12
Max Cond:	24.30
Avg Cond:	24.21
Min Salinity:	14.32
Max Salinity:	14.46
Avg Salinity:	14.40
Min Sigma-Theta:	7.24
Max Sigma-Theta:	7.63
Avg Sigma-Theta:	7.58
Min Turbidity:	4.62
Max Turbidity:	8.56
Avg Turbidity:	5.76

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E21-TARK-P3

7/21/10 13:06 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.71
Max Temp:	25.92
Avg Temp:	25.87
Min Cond:	23.02
Max Cond:	23.05
Avg Cond:	23.04
Min Salinity:	13.47
Max Salinity:	13.66
Avg Salinity:	13.63
Min Sigma-Theta:	7.02
Max Sigma-Theta:	7.40
Avg Sigma-Theta:	7.06
Min Turbidity:	4.33
Max Turbidity:	24.13
Avg Turbidity:	9.44

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E22-THKN-P1

7/21/10 17:25 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	28.74
Max Temp:	30.28
Avg Temp:	29.49
Min Cond:	28.89
Max Cond:	31.27
Avg Cond:	30.10
Min Salinity:	15.30
Max Salinity:	17.95
Avg Salinity:	16.92
Min Sigma-Theta:	6.89
Max Sigma-Theta:	9.40
Avg Sigma-Theta:	8.38
Min Turbidity:	11.46
Max Turbidity:	29.04
Avg Turbidity:	16.94

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E22-THKN-P2

7/21/10 17:31 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	28.63
Max Temp:	30.42
Avg Temp:	29.46
Min Cond:	28.10
Max Cond:	31.49
Avg Cond:	30.14
Min Salinity:	15.41
Max Salinity:	18.12
Avg Salinity:	16.99
Min Sigma-Theta:	7.08
Max Sigma-Theta:	9.56
Avg Sigma-Theta:	8.46
Min Turbidity:	12.18
Max Turbidity:	28.39
Avg Turbidity:	17.79

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E22-THKN-P3

7/21/10 17:37 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	28.86
Max Temp:	30.34
Avg Temp:	29.81
Min Cond:	28.43
Max Cond:	31.11
Avg Cond:	29.67
Min Salinity:	15.48
Max Salinity:	17.80
Avg Salinity:	16.56
Min Sigma-Theta:	7.15
Max Sigma-Theta:	9.25
Avg Sigma-Theta:	8.02
Min Turbidity:	11.26
Max Turbidity:	40.49
Avg Turbidity:	18.70

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E22-TNBN-P1

7/21/10 17:10 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.88
Max Temp:	27.48
Avg Temp:	26.48
Min Cond:	32.81
Max Cond:	36.74
Avg Cond:	35.17
Min Salinity:	19.63
Max Salinity:	22.78
Avg Salinity:	21.45
Min Sigma-Theta:	10.71
Max Sigma-Theta:	13.88
Avg Sigma-Theta:	12.66
Min Turbidity:	5.36
Max Turbidity:	40.07
Avg Turbidity:	17.03

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E22-TNBN-P2

7/21/10 17:20 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.90
Max Temp:	27.55
Avg Temp:	27.13
Min Cond:	32.63
Max Cond:	33.53
Avg Cond:	33.28
Min Salinity:	19.21
Max Salinity:	20.14
Avg Salinity:	19.86
Min Sigma-Theta:	9.68
Max Sigma-Theta:	11.60
Avg Sigma-Theta:	11.21
Min Turbidity:	8.76
Max Turbidity:	13.74
Avg Turbidity:	11.67

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E22-TNBN-P3

7/21/10 17:21 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	27.34
Max Temp:	28.19
Avg Temp:	27.56
Min Cond:	31.48
Max Cond:	33.75
Avg Cond:	32.95
Min Salinity:	18.30
Max Salinity:	20.10
Avg Salinity:	19.45
Min Sigma-Theta:	10.03
Max Sigma-Theta:	11.44
Avg Sigma-Theta:	10.88
Min Turbidity:	5.07
Max Turbidity:	15.91
Avg Turbidity:	11.26

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E22-TNBS-P1

7/21/10 18:01 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.65
Max Temp:	26.99
Avg Temp:	25.87
Min Cond:	36.66
Max Cond:	37.50
Avg Cond:	37.24
Min Salinity:	22.02
Max Salinity:	23.41
Avg Salinity:	23.13
Min Sigma-Theta:	13.16
Max Sigma-Theta:	14.42
Avg Sigma-Theta:	14.15
Min Turbidity:	6.16
Max Turbidity:	22.84
Avg Turbidity:	13.33

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E22-TNBS-P2

7/21/10 18:11 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.45
Max Temp:	26.13
Avg Temp:	25.92
Min Cond:	36.67
Max Cond:	37.88
Avg Cond:	37.22
Min Salinity:	22.59
Max Salinity:	23.78
Avg Salinity:	23.09
Min Sigma-Theta:	13.17
Max Sigma-Theta:	14.75
Avg Sigma-Theta:	14.08
Min Turbidity:	5.74
Max Turbidity:	12.92
Avg Turbidity:	8.33

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E22-TNBS-P3

7/21/10 18:18 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.08
Max Temp:	26.51
Avg Temp:	26.28
Min Cond:	36.60
Max Cond:	37.05
Avg Cond:	36.85
Min Salinity:	22.47
Max Salinity:	22.89
Avg Salinity:	22.65
Min Sigma-Theta:	13.23
Max Sigma-Theta:	13.90
Avg Sigma-Theta:	13.63
Min Turbidity:	6.92
Max Turbidity:	9.54
Avg Turbidity:	7.77

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E22-TKVK-P1

7/21/10 18:41 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.48
Max Temp:	26.07
Avg Temp:	24.95
Min Cond:	37.98
Max Cond:	39.61
Avg Cond:	39.10
Min Salinity:	23.77
Max Salinity:	25.53
Avg Salinity:	24.93
Min Sigma-Theta:	14.37
Max Sigma-Theta:	16.35
Avg Sigma-Theta:	15.76
Min Turbidity:	6.05
Max Turbidity:	12.81
Avg Turbidity:	9.46

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E22-TKVK-P2

7/21/10 18:50 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.66
Max Temp:	25.45
Avg Temp:	24.93
Min Cond:	38.35
Max Cond:	39.32
Avg Cond:	38.98
Min Salinity:	24.07
Max Salinity:	25.22
Avg Salinity:	24.84
Min Sigma-Theta:	15.01
Max Sigma-Theta:	16.07
Avg Sigma-Theta:	15.70
Min Turbidity:	4.00
Max Turbidity:	17.11
Avg Turbidity:	10.17

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E22-TKVK-P3

7/21/10 19:00 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	24.63
Max Temp:	25.58
Avg Temp:	25.15
Min Cond:	38.04
Max Cond:	39.36
Avg Cond:	38.73
Min Salinity:	23.93
Max Salinity:	25.26
Avg Salinity:	24.54
Min Sigma-Theta:	14.81
Max Sigma-Theta:	16.11
Avg Sigma-Theta:	15.42
Min Turbidity:	5.02
Max Turbidity:	12.54
Avg Turbidity:	7.38

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E22-TARK-P1

7/21/10 19:20 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	26.05
Max Temp:	26.64
Avg Temp:	26.31
Min Cond:	36.78
Max Cond:	36.98
Avg Cond:	36.86
Min Salinity:	22.31
Max Salinity:	22.86
Avg Salinity:	22.62
Min Sigma-Theta:	13.30
Max Sigma-Theta:	13.89
Avg Sigma-Theta:	13.63
Min Turbidity:	5.06
Max Turbidity:	9.47
Avg Turbidity:	6.30

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ
N01-E22-TARK-P2

7/21/10 19:27 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.88
Max Temp:	26.39
Avg Temp:	26.13
Min Cond:	36.13
Max Cond:	37.20
Avg Cond:	36.93
Min Salinity:	22.06
Max Salinity:	23.10
Avg Salinity:	22.79
Min Sigma-Theta:	13.16
Max Sigma-Theta:	14.12
Avg Sigma-Theta:	13.81
Min Turbidity:	8.46
Max Turbidity:	20.63
Avg Turbidity:	13.89

CTD-OBS Vertical Profile

Real-Time Monitoring - Passaic River - Newark, NJ

N01-E22-TARK-P3

7/21/10 19:35 (UTC)











CTD-OBS Calculated Statistics

Min Temp:	25.57
Max Temp:	26.70
Avg Temp:	26.16
Min Cond:	35.03
Max Cond:	37.25
Avg Cond:	36.89
Min Salinity:	21.54
Max Salinity:	23.32
Avg Salinity:	22.76
Min Sigma-Theta:	12.74
Max Sigma-Theta:	14.26
Avg Sigma-Theta:	13.77
Min Turbidity:	7.45
Max Turbidity:	12.28
Avg Turbidity:	8.80

APPENDIX 12: Data CD

Appendix D

PWCM Sample Times During Tide Phases and Stages

Figure D-1. Tide Height (NAVD 1988; feet) at USGS Gauge Station #01392650 and Timing of Sample Collections, October 2009.



Figure D-2. Tide Height (NAVD 1988; feet) at USGS Gauge Station #01392650 and Timing of Sample Collections, November 2009.



Figure D-3. Tide Height (NAVD 1988; feet) at USGS Gauge Station #01392650 and Timing of Sample Collections, December 2009.



Figure D-4. Tide Height (NAVD 1988; feet) at USGS Gage Station #01392650 and Timing of Sample Collections, March 2010.



Figure D-5. Tide Height (NAVD 1988; feet) at USGS Gage Station #01392650 and Timing of Sample Collections, April 2010.



Figure D-6. Tide Height (NAVD 1988; feet) at USGS Gage Station #01392650 and Timing of Sample Collections, May 2010 (Plot 1 of 2).



Figure D-7. Tide Height (NAVD 1988; feet) at USGS Gage Station #01392650 and Timing of Sample Collections, May 2010 (Plot 2 of 2).



Figure D-8. Tide Height (NAVD 1988; feet) at USGS Gage Station #01392650 and Timing of Sample Collections, June 2010.



Figure D-9. Tide Height (NAVD 1988; feet) at USGS Gage Station #01392650 and Timing of Sample Collections, July 2010.



Appendix E

Dissolved Oxygen Monitoring Program Data Report for the Lower Passaic River Study Area: Summer and Fall 2012 - Finalized October 2018 (provided under separate cover)

Appendix F

Data Validation Reports

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09100211		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60139066.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 4, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09100211_LP651_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on October 12, 2009.

Client Sample ID	Matrix
09A-E01-T014-P3-AS	Aqueous
09A-E01-T014-P3-BS	Aqueous
09A-E01-T042-P1-AS	Aqueous
09A-E01-T042-P1-BS	Aqueous
09A-E01-T067-P3-AT	Aqueous
09A-E01-T067-P3-AS	Aqueous
09A-E01-T067-P3-BT	Aqueous
09A-E01-T067-P3-BS	Aqueous
09A-E01-T102-P1-AS	Aqueous
09A-E01-T102-P1-BS	Aqueous
09A-E01-T135-P3-AS	Aqueous
09A-E01-T135-P3-BS	Aqueous

The following method was applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above method(s) along with USEPA Region II validation SOP(s) (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results			√
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results			√
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Samples 09A-E01-T067-P3AT and 09A-E01-T067-P3BT were incorrectly reported by the laboratory as 09A-E01-T067-P3AD and 09A-E01-T067-P3BD. Sample IDs were corrected during validation.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

The temperature blank associated with the samples in this data set was above the criteria (11.2°C). All samples in this data set were qualified as estimated (J) on this basis.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and initial and continuing calibration blanks (ICBs and CCBs) were evaluated as to whether there were contaminants detected above the method detection limit (MDL). There were no EBs associated with the samples in this data set.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria. MS/MSD analyses were not performed on the samples in this data set.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL) for SSC.

The field duplicate pairs 09A-E01-T067-P3AS/09A-E01-T067-P3AT and 09A-E01-T067-P3BS/09A-E01-T067-P3BT were analyzed for SSC only. All QC criteria were met.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

No laboratory duplicate analysis was performed on the samples in this data set.

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This "J" qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: LPRRP Validation Qualifier Codes and Explanation

Attachment B: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
09A-E01-T014-P3-AS	w	SSC	6	1	mg/L	J	t
09A-E01-T014-P3-BS	w	SSC	7	1	mg/L	J	t
09A-E01-T042-P1-AS	w	SSC	8	1	mg/L	J	t
09A-E01-T042-P1-BS	w	SSC	7	1	mg/L	J	t
09A-E01-T067-P3-AT	w	SSC	12	1	mg/L	J	t
09A-E01-T067-P3-AS	w	SSC	12	1	mg/L	J	t
09A-E01-T067-P3-BT	w	SSC	29	1	mg/L	J	t
09A-E01-T067-P3-BS	w	SSC	30	1	mg/L	J	t
09A-E01-T102-P1-AS	w	SSC	20	1	mg/L	J	t
09A-E01-T102-P1-BS	w	SSC	29	1	mg/L	J	t
09A-E01-T135-P3-AS	w	SSC	5	1	mg/L	J	t
09A-E01-T135-P3-BS	w	SSC	9	1	mg/L	J	t

Notes:

- Refer to Attachment A for validation qualifier definitions
- Refer to Attachment B for validation reason code definitions
- There will be no value under the Result column if the result is nondetect

Attachment A

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment B

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09100246		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Full		
AECOM Project Number	60139066.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 4, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09100246_LP654_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on October 12, 2009.

Client Sample ID	Matrix
09A-E02-T175-P1AS	Aqueous
09A-E02-T175-P2AS	Aqueous
09A-E02-T175-P2BS	Aqueous
09A-E02-T175-P3AS	Aqueous
09A-E02-T175-P3AT	Aqueous
09A-E02-T175-P4AS	Aqueous
09A-E04-T135-P3XR	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Sample 09A-E02-T175-P1AS was listed on the COC for SSC, POC, and DOC. Sample 09A-E02-T175-P2BS was listed on the COC for SSC only. After review of the COC bottle descriptions, field notes, and the laboratory log in discrepancy notes, the validator in collaboration with the field task manager, determined that the POC and DOC results reported for sample 09A-E02-T175-P1AS for 09A-E02-T175-P2B. Only SSC should have been reported for sample 09A-E02-T175-P1AS. Sample data was not affected by these changes.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

The temperature blank associated with the samples in this data set was above the criteria (7.9°C). No qualifications were necessary for this minor nonconformance.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

The laboratory QA/QC summary report for POC noted a CCV %R of 96%, which exceeded the ± 3% QAPP acceptance criteria; however, the %R documented in the raw data was 96.6%. No qualification actions were necessary on the basis of CCV %R.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "R" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. The MB for DOC was positive for DOC < QL (0.14 mg/L). Data qualification on the basis of MB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
MB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> 5x concentration of blank	No qualification
	> the QL	>the QL but < the MB	Qualify results as unusable (R)
		>the MB but <10x the MB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the MB	No action is taken based on AECOM professional judgment

All DOC results were > 5x the MB contamination therefore, no DOC results were qualified on this basis.

EBs were associated with all samples collected in the same month as the EB. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB	Qualify results as unusable (R)
		>the EB but <10x the EB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB	No action is taken based on AECOM professional judgment

DOC was detected > the MDL, but < the quantitation limit (QL) in EB 09A-E04-T135-P3XR; however, but all associated sample results were >5x the blank concentration; therefore, no qualifications were necessary on this basis.

POC was detected > QL (0.6mg/L) in EB 09A-E04-T135-P3XR. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

Data qualification on the basis of field duplicate RPDs was as follows (see above for acceptance criteria):

Criteria	Action	
	Detected	Nondetected
RPD greater than the acceptance criteria, but < 120% and sample and duplicate results >5x the SQL	J	Not Applicable
RPD ≥ 120%	R	Not Applicable
If sample and/or duplicate is <5x the QL and absolute difference is >2x and ≤ 4x the QL	J	UJ
If the sample and/or duplicate is <5x the QL and absolute difference is >4x the QL.	R	R

The field duplicate pair 09A-E02-T175-P3AS/09A-E02-T175-P3AT was analyzed for SSC only. All QC criteria were met.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL). Data qualification on the basis of laboratory duplicate RPDs contamination was as follows:

Criteria	Actions	
	Detect	Nondetect
RPD > 20% but < 100% and sample results ≥ the QL	J	Not Applicable
Sample and/or duplicate is <5x the QL, absolute difference is > the QL	J	UJ
Absolute difference is > 2x the QL and sample results are <5x	R	R

Criteria	Actions	
the QL		
RPD ≥ 100% and results ≥ the QL	R	Not Applicable
Sample and duplicate are both <5x the QL	No action is taken based on AECOM professional judgment	

The laboratory duplicate RPDs exceeded the criteria for POC (26% and 40%), but since the sample and duplicate results in each case were each < 5x the QL, no qualifications were applied to the samples in this data set on this basis.

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This "J" qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
09A-E02-T175-P2BS	w	POC	0.8	0.8	mg/L	J	h
09A-E02-T175-P2AS	w	POC	1.0	0.8	mg/L	J	h
09A-E04-T135-P3XR	w	POC	0.6	0.4	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractural Holding Time Criteria (Days)
09A-E02-T175-P2BS	POC	30	28
09A-E02-T175-P2AS			
09A-E04-T135-P3XR		29	

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09100244		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60139066.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 4, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09100244_LP652_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on October 13, 2009.

Client Sample ID	Matrix
09A-E03-T102-P1-AS	Aqueous
09A-E03-T102-P1-BS	Aqueous
09A-E03-T135-P3-AS	Aqueous
09A-E03-T135-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).

Analyte	Matrix	Primary Method Reference
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

The temperature blank associated with the samples in this data set was above the criteria (11°C). All samples in this data set were qualified as estimated on this basis.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that the QC acceptance criteria were met.

The laboratory QA/QC summary report for POC noted a CCV 1 %R of 96%, which exceeded the ± 3% QAPP acceptance criteria; however, the %R documented in the raw data was 96.6%. No qualification actions were necessary on the basis of CCV %R.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and initial and continuing calibration blanks (ICBs and CCBs) were evaluated as to whether there were contaminants detected above the method detection limit (MDL). The MB for DOC was positive for DOC < QL (0.14 mg/L). Data qualification on the basis of MB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
MB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> 5x concentration of blank	No qualification
	> the QL	>the QL but < the MB	Qualify results as unusable (R)
		>the MB but <10x the MB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the MB	No action is taken based on AECOM professional judgment

All DOC results were > 5x the MB contamination therefore, no DOC results were qualified on this basis.

EBs were associated with all samples collected in the same month as the EB. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB	Qualify results as unusable (R)
		>the EB but <10x the EB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB	No action is taken based on AECOM professional judgment

DOC was detected > the MDL, but < the quantitation limit (QL) in EB 09A-E04-T135-P3XR; however, all results were > 5x the EB concentration therefore, no DOC results were qualified on this basis.

POC was detected > QL (0.6mg/L) in EB 09A-E04-T135-P3XR. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

There were no field duplicates associated with the samples in this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL). Data qualification on the basis of laboratory duplicate RPDs contamination was as follows:

Criteria	Actions	
	Detect	**Nondetect**
RPD > 20% but < 100% and sample results ≥ the QL	J	Not Applicable
Sample and/or duplicate is <5x the QL, absolute difference is > the QL	J	UJ
Absolute difference is > 2x the QL and sample results are <5x the QL	R	R
RPD ≥ 100% and results ≥ the QL	R	Not Applicable
Sample and duplicate are both <5x the QL	No action is taken based on AECOM professional judgment	

The laboratory duplicate RPDs exceeded the criteria for POC (26% and 40%), but since the sample and duplicate results in each case were each < 5x the QL no qualifications were applied to the samples in this data set on this basis.

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This "J" qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
09A-E03-T102-P1-AS	w	POC	2.0	0.8	mg/L	J	h,t,be
09A-E03-T102-P1-BS	w	POC	1.9	0.8	mg/L	J	h,t,be
09A-E03-T135-P3-AS	w	POC	1.4	0.8	mg/L	J	h,t,be
09A-E03-T135-P3-BS	w	POC	1.2	0.8	mg/L	J	h,t,be
09A-E03-T102-P1-AS	w	DOC	2.5	0.30	mg/L	J	t
09A-E03-T102-P1-BS	w	DOC	3.4	0.30	mg/L	J	t
09A-E03-T135-P3-AS	w	DOC	3.4	0.30	mg/L	J	t
09A-E03-T135-P3-BS	w	DOC	3.3	0.30	mg/L	J	t

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractural Holding Time Criteria (Days)
09A-E03-T102-P1-AS	POC	29	28
09A-E03-T102-P1-BS			
09A-E03-T135-P3-AS			
09A-E03-T135-P3-BS			

Table A-2 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
EB 09A-E04-T135-P3XR	POC	0.6	0.4	2.0	0.8	09A-E03-T102-P1-AS
				1.9	0.8	09A-E03-T102-P1-BS
				1.4	0.8	09A-E03-T135-P3-AS
				1.2	0.8	09A-E03-T135-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09100245		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60139066.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 4, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09100245_LP653_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on October 13, 2009.

Client Sample ID	Matrix
09A-E03-T014-P3-AS	Aqueous
09A-E03-T014-P3-BS	Aqueous
09A-E03-T042-P1-AS	Aqueous
09A-E03-T042-P1-BS	Aqueous
09A-E03-T067-P3-AS	Aqueous
09A-E03-T067-P3-BS	Aqueous
09A-E04-T014-P3-AS	Aqueous
09A-E04-T014-P3-BS	Aqueous
09A-E04-T042-P1-AS	Aqueous
09A-E04-T042-P1-AT	Aqueous

Client Sample ID	Matrix
09A-E04-T042-P1-BS	Aqueous
09A-E04-T067-P3-AS	Aqueous
09A-E04-T067-P3-BS	Aqueous
09A-E03-T014-P1-AS	Aqueous
09A-E03-T014-P1-BS	Aqueous
09A-E03-T014-P2-AS	Aqueous
09A-E03-T014-P2-BS	Aqueous
09A-E03-T042-P2-AS	Aqueous
09A-E03-T042-P2-BS	Aqueous
09A-E03-T042-P3-AS	Aqueous
09A-E03-T042-P3-BS	Aqueous
09A-E03-T067-P1-AS	Aqueous
09A-E03-T067-P1-AT	Aqueous
09A-E03-T067-P1-BS	Aqueous
09A-E03-T067-P2-AS	Aqueous
09A-E03-T067-P2-BS	Aqueous
09A-E04-T014-P1-AS	Aqueous
09A-E04-T014-P1-BS	Aqueous
09A-E04-T014-P2-AS	Aqueous
09A-E04-T014-P2-BS	Aqueous
09A-E04-T042-P2-AS	Aqueous
09A-E04-T042-P2-BS	Aqueous
09A-E04-T042-P3-AS	Aqueous
09A-E04-T042-P3-BS	Aqueous
09A-E04-T067-P1-AS	Aqueous
09A-E04-T067-P1-BS	Aqueous
09A-E04-T067-P2-AS	Aqueous
09A-E04-T067-P2-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic	Aqueous	*Total Organic Carbon, Standard methods for the Examination of*

Analyte	Matrix	Primary Method Reference
Carbon (DOC)		*Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Three of the four temperature blanks associated with the samples in this data set were above the criteria (11°C to 14°C). All samples in the associated coolers were qualified as estimated (J) on this basis.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

The laboratory QA/QC summary report for POC noted a CCV %R of 96%, which exceeded the ± 3% QAPP acceptance criteria; however, the %R documented in the raw data was 96.6%. No qualification actions were necessary on the basis of CCV %R.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), the initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. The MB for DOC was positive for DOC < QL (0.14 mg/L). Data qualification on the basis of MB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
MB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> 5x concentration of blank	No qualification
	> the QL	>the QL but < the MB	Qualify results as unusable (R)

Blank Type	Blank Result	Sample Result	Actions
		>the MB but <10x the MB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the MB	No action is taken based on AECOM professional judgment

All DOC results were > 5x the MB contamination; therefore, no DOC results were qualified on this basis.

EB sample with “E01” as the fourth, fifth, and sixth characters in the sample ID were associated with field samples with “E01” in the sample ID as the fourth, fifth, and sixth characters, likewise, EB sample with “E02” in the sample ID were associated with field samples with a “E02” in the sample ID, and so on. Data validation qualifiers for individual samples are based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB	Qualify results as unusable (R)
		>the EB but <10x the EB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB	No action is taken based on AECOM professional judgment

DOC was detected > the MDL, but < the quantitation limit (QL) in EB 09A-E04-T135-P3XR; however, but all associated sample results were >5x the blank concentration; therefore, no qualifications were necessary on this basis.

POC was detected > QL (0.6mg/L) in EB 09A-E04-T135-P3XR. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten

times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL). Data qualification on the basis of laboratory duplicate RPDs contamination was as follows:

Criteria	Actions	
	Detect	**Nondetect**
RPD > 20% but < 100% and sample results ≥ the QL	J	Not Applicable
Sample and/or duplicate is <5x the QL, absolute difference is > the QL	J	UJ
Absolute difference is > 2x the QL and sample results are <5x the QL	R	R
RPD ≥ 100% and results ≥ the QL	R	Not Applicable
Sample and duplicate are both <5x the QL	No action is taken based on AECOM professional judgment	

The laboratory duplicate RPDs exceeded the criteria for POC (26% and 40%), but since the sample and duplicate results in each case were each < 5x the QL, no qualifications were applied to the samples in this data set on this basis.

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
09A-E04-T014-P3-AS	w	DOC	2.0	1.5	mg/L	J	t
09A-E04-T014-P3-BS	w	DOC	3.1	1.5	mg/L	J	t
09A-E04-T042-P1-AS	w	DOC	3.2	1.2	mg/L	J	t
09A-E04-T042-P1-AT	w	DOC	3.3	1.5	mg/L	J	t
09A-E04-T042-P1-BS	w	DOC	2.9	1.5	mg/L	J	t
09A-E04-T067-P3-AS	w	DOC	3.3	1.2	mg/L	J	t
09A-E04-T067-P3-BS	w	DOC	3.2	1.5	mg/L	J	t
09A-E03-T067-P1-AT	w	SSC	19	1	mg/L	J	t
09A-E04-T014-P1-AS	w	SSC	22	1	mg/L	J	t
09A-E04-T014-P1-BS	w	SSC	6	1	mg/L	J	t
09A-E04-T014-P2-AS	w	SSC	35	1	mg/L	J	t
09A-E04-T014-P2-BS	w	SSC	6	1	mg/L	J	t
09A-E04-T014-P3-AS	w	SSC	21	1	mg/L	J	t
09A-E04-T014-P3-BS	w	SSC	6	1	mg/L	J	t
09A-E04-T042-P1-AS	w	SSC	35	1	mg/L	J	t
09A-E04-T042-P1-AT	w	SSC	8	1	mg/L	J	t
09A-E04-T042-P1-BS	w	SSC	9	1	mg/L	J	t
09A-E04-T042-P2-AS	w	SSC	81	1	mg/L	J	t
09A-E04-T042-P2-BS	w	SSC	8	1	mg/L	J	t
09A-E04-T042-P3-AS	w	SSC	72	1	mg/L	J	t
09A-E04-T042-P3-BS	w	SSC	11	1	mg/L	J	t
09A-E04-T067-P1-AS	w	SSC	18	1	mg/L	J	t
09A-E04-T067-P1-BS	w	SSC	36	1	mg/L	J	t
09A-E04-T067-P2-AS	w	SSC	61	1	mg/L	J	t
09A-E04-T067-P2-BS	w	SSC	24	1	mg/L	J	t
09A-E04-T067-P3-AS	w	SSC	34	1	mg/L	J	t
09A-E04-T067-P3-BS	w	SSC	30	1	mg/L	J	t
09A-E03-T014-P3-AS	w	POC	1.3	0.8	mg/L	J	h,be
09A-E03-T014-P3-BS	w	POC	1.0	0.8	mg/L	J	h,be
09A-E03-T042-P1-AS	w	POC	1.2	0.8	mg/L	J	h,be
09A-E03-T042-P1-BS	w	POC	1.0	0.8	mg/L	J	h,be
09A-E03-T067-P3-AS	w	POC	1.7	0.8	mg/L	J	h,be
09A-E03-T067-P3-BS	w	POC	2.2	0.8	mg/L	J	h,be

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
09A-E04-T014-P3-AS	w	POC	1.2	0.8	mg/L	J	t,h,be
09A-E04-T014-P3-BS	w	POC	2.3	0.8	mg/L	J	t,h,be
09A-E04-T042-P1-AS	w	POC	1.0	0.8	mg/L	J	t,h,be
09A-E04-T042-P1-AT	w	POC	1.0	0.8	mg/L	J	t,h,be
09A-E04-T042-P1-BS	w	POC	4.5	0.8	mg/L	J	t,h,be
09A-E04-T067-P3-AS	w	POC	2.2	0.8	mg/L	J	t,h,be
09A-E04-T067-P3-BS	w	POC	5.5	0.8	mg/L	J	t,h,be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractural Holding Time Criteria (Days)
09A-E03-TO14-P3-AS	POC	29	28
09A-E03-TO14-P3-AS			
09A-E03-TO42-P1-AS			
09A-E03-TO42-P1-BS			
09A-E03-TO67-P3-AS			
09A-E03-TO67-P3-BS			
09A-E04-TO14-P3-AS			
09A-E04-TO14-P3-BS			
09A-E04-TO42-P1-AS			
09A-E04-TO14-P1-BS			
09A-E04-TO67-P3-AS			
09A-E04-TO67-P3-BS			
09A-E04-TO42-P1-AT			

Table A-2 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
EB 09A-E04-T135-P3XR	POC	0.6	0.4	1.3	0.8	09A-E03-TO14-P3-AS
				1.0	0.8	09A-E03-TO14-P3-AS
				1.2	0.8	09A-E03-TO42-P1-AS
				1.0	0.8	09A-E03-TO42-P1-BS
				1.7	0.8	09A-E03-TO67-P3-AS
				2.2	0.8	09A-E03-TO67-P3-BS
				1.2	0.8	09A-E04-TO14-P3-AS
				2.3	0.8	09A-E04-TO14-P3-BS
				1.0	0.8	09A-E04-TO42-P1-AS
				4.5	0.8	09A-E04-TO14-P1-BS
				2.2	0.8	09A-E04-TO67-P3-AS
				5.5	0.8	09A-E04-TO67-P3-BS
				1.0	0.8	09A-E04-TO42-P1-AT

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09100267		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Full		
AECOM Project Number	60139066.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 4, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09100267_LP655_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on October 13, 2009.

Client Sample ID	Matrix
09A-E03-T102-P1-AS	Aqueous
09A-E03-T102-P1-BS	Aqueous
09A-E03-T102-P2-AS	Aqueous
09A-E03-T102-P2-BS	Aqueous
09A-E03-T102-P3-AS	Aqueous
09A-E03-T102-P3-BS	Aqueous
09A-E03-T135-P1-AS	Aqueous
09A-E03-T135-P1-BS	Aqueous
09A-E03-T135-P2-AS	Aqueous
09A-E03-T135-P2-BS	Aqueous
09A-E03-T135-P3-AS	Aqueous
09A-E03-T135-P3-BS	Aqueous

The following method was applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above method(s) along with USEPA Region II validation SOP(s) (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results			√
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results			√
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and initial and continuing calibration blanks (ICBs and CCBs) were evaluated as to whether there were contaminants detected above the method detection limit (MDL).

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria. MS/MSD analyses were not performed on the samples in this data set.

Field Duplicate Results

There were no field duplicates associated with the samples in this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

No laboratory duplicate analysis was performed on the samples in this data set.

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No qualification actions were applied to the samples in this data set.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09100268		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5310C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Full		
AECOM Project Number	60139066.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 4, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09100268_LP656_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on October 13, 2009.

Client Sample ID	Matrix
09A-E04-T135-P1AS	Aqueous
09A-E04-T135-P1BS	Aqueous
09A-E04-T135-P2AS	Aqueous
09A-E04-T135-P2BS	Aqueous
09A-E04-T135-P3AS	Aqueous
09A-E04-T135-P3BS	Aqueous
09A-E04-T135-P3AS	Aqueous
09A-E04-T135-P3BS	Aqueous
09A-E04-T135-P3AT	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

The laboratory QA/QC summary report for POC noted a CCV %R of 96%, which exceeded the ± 3% QAPP acceptance criteria; however, the %R documented in the raw data was 96.6%. No qualification actions were necessary on the basis of CCV %R.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), the initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination.

EBs were associated with all samples collected in the same month as the EB. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB or MB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB/MB	Qualify results as unusable (R)
		>the EB but <10x the EB/MB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB/MB	No action is taken based on AECOM professional judgment

DOC was detected > the MDL, but < the quantitation limit (QL) in EB 09A-E04-T135-P3XR; however, but all associated sample results were >5x the blank concentration; therefore, no qualifications were necessary on this basis.

POC was detected > QL (0.6mg/L) in EB 09A-E04-T135-P3XR. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

Data qualification on the basis of field duplicate RPDs was as follows (see above for acceptance criteria):

Criteria	Action	
	Detected	Nondetected
RPD greater than the acceptance criteria, but < 120% and sample and duplicate results >5x the SQL	J	Not Applicable
RPD ≥ 120%	R	Not Applicable
If sample and/or duplicate is <5x the QL and absolute difference is >2x and ≤ 4x the QL	J	UJ
If the sample and/or duplicate is <5x the QL and absolute difference is >4x the QL.	R	R

The field duplicate pair 09A-E04-T135-P3AS/09A-E04-T135-P3AT was analyzed for SSC only. All QC criteria was met.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL). Data qualification on the basis of laboratory duplicate RPDs contamination was as follows:

Criteria	Actions	
	Detect	Nondetect
RPD > 20% but < 100% and sample results ≥ the QL	J	Not Applicable
Sample and/or duplicate is <5x the QL, absolute difference is > the QL	J	UJ
Absolute difference is > 2x the QL and sample results are <5x the QL	R	R
RPD ≥ 100% and results ≥ the QL	R	Not Applicable
Sample and duplicate are both <5x the QL	No action is taken based on AECOM professional judgment	

The laboratory duplicate RPDs exceeded the criteria for POC (26% and 40%), but since the sample and duplicate results in each case were each < 5x the QL, no qualifications were applied to the samples in this data set on this basis.

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL) but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
09A-E04-T135-P3AS	w	POC	1.3	0.8	mg/L	J	h, be
09A-E04-T135-P3BS	w	POC	1.4	0.8	mg/L	J	h, be
09A-E04-T135-P3AS	w	DOC	3.6	0.6	mg/L	J	h
09A-E04-T135-P3BS	w	DOC	3.2	1.5	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1a - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Holding Time Criteria (Days)
09A-E04-T135-P3AS	POC	29	28
09A-E04-T135-P3BS			

Table A-1b - Hold Time

Sample ID	Analyte	Hours from Sampling to Prep	Holding Time Criteria (Hours)
09A-E04-T135-P3AS	DOC	64	48
09A-E04-T135-P3BS			

Table A-2 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
EB 09A-E04-T135-P3XR	POC	0.6	0.4	1.3	0.8	09A-E04-T135-P3AS
				1.4	0.8	09A-E04-T135-P3BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09100270		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5310C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60139066.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 4, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09100270_LP657_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on October 13, 2009.

Client Sample ID	Matrix
09A-E04-T102-P1-AS	Aqueous
09A-E04-T102-P1-BS	Aqueous
09A-E04-T102-P2-AS	Aqueous
09A-E04-T102-P2-BS	Aqueous
09A-E04-T102-P3-AS	Aqueous
09A-E04-T102-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance), and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below, compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results			√
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1a and A-1b. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

The laboratory QA/QC summary report for POC noted a CCV %R of 96%, which exceeded the ± 3% QAPP acceptance criteria; however, the %R documented in the raw data was 96.6%. No qualification actions were necessary on the basis of CCV %R.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination.

EBs were associated with all samples collected in the same month as the EB. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB	Qualify results as unusable (R)
		>the EB but <10x the EB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB	No action is taken based on AECOM professional judgment

DOC was detected > the MDL, but < the quantitation limit (QL) in EB 09A-E04-T135-P3XR; however, all results were > 5x the EB concentration therefore, no DOC results were qualified on this basis.

POC was detected > QL (0.6mg/L) in EB 09A-E04-T135-P3XR. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

There were no field duplicates associated with the samples in this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

No laboratory duplicate analysis was performed on the samples in this data set.

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
09A-E04-T102-P1-AS	w	DOC	3.2	1.5	mg/L	J	h
09A-E04-T102-P2-BS	w	DOC	3.3	5.0	mg/L	J	h
09A-E04-T102-P1-AS	w	POC	3.1	0.8	mg/L	J	h,be
09A-E04-T102-P2-BS	w	POC	4.0	0.8	mg/L	J	h,be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1a - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractural Holding Time Criteria (Days)
09A-E04-T102-P1-AS	POC	29	28
09A-E04-T102-P2-BS			

Table A-1b – Prep Hold Time

Sample ID	Analyte	Days from Sampling to Prep	Holding Time Criteria (Days)
09A-E04-T102-P1-AS	DOC	3	2
09A-E04-T102-P2-BS			

Table A-2 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
EB 09A-E04-T135-P3XR	POC	0.6	0.4	3.1	0.8	09A-E04-T102-P1-AS
				4.0	0.8	09A-E04-T102-P2-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09110210		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Full		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 20, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09110210_LP658_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on November 10, 2009.

Client Sample ID	Matrix
09A-E06-T175-P1-AS	Aqueous
09A-E06-T175-P2-AS	Aqueous
09A-E06-T175-P2-BS	Aqueous
09A-E06-T175-P3-AS	Aqueous
09A-E06-T175-P4-AS	Aqueous
09A-E09-T175-P2-AS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Nonconformances are summarized in Attachment A, Table A-2. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> QL, but < 5x concentration of blank	Qualify reported result as nondetect (U)
		> QL and ≥ 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB	Qualify results as unusable (R)
		>the EB but <10x the EB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB	No action is taken based on AECOM professional judgment

DOC was detected > the MDL (0.2mg/L), but < the quantitation limit (QL) in EB 09A-E08-T067-P3-XR. All associated sample results for DOC were >5x the blank concentration; therefore, no qualifications were necessary on this basis.

POC was also detected > the MDL (0.5 mg/L), but < the quantitation limit (QL) in EB 09A-E08-T067-P3-XR. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

No field duplicates were associated with this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
09A-E06-T175-P2-AS	WS	POC		0.8	mg/L	UJ	h,be
09A-E06-T175-P2-BS	WS	POC	1	0.8	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- There will be no value under the Result column if the result is nondetect

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Holding Time Criteria (Days)
09A-E06-T175-P2-AS	POC	29	28
09A-E06-T175-P2-BS			

Table A-2 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
09A-E08-T067-P3-XR	POC	0.5 J	0.8	0.7	0.8	09A-E06-T175-P2-AS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09110211		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 14, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09110211_LP659_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on November 10, 2009.

Client Sample ID	Matrix
09A-E05-T042-P1-AS	Aqueous
09A-E05-T042-P1-BS	Aqueous
09A-E05-T135-P3-AS	Aqueous
09A-E05-T135-P3-BS	Aqueous
09A-E09-T042-P1-AS	Aqueous
09A-E09-T042-P1-BS	Aqueous
09A-E09-T135-P3-AS	Aqueous
09A-E09-T135-P3-AT	Aqueous
09A-E09-T135-P3-BS	Aqueous

The following method was applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This "J" qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No sample results were qualified as a result of validation actions.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09110212		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 14, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09110212_LP660_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on November 9, 2009.

Client Sample ID	Matrix
09A-E05-T042-P1-AS	Aqueous
09A-E05-T042-P1-BS	Aqueous
09A-E05-T135-P3-AS	Aqueous
09A-E05-T135-P3-BS	Aqueous
09A-E09-T042-P1-AS	Aqueous
09A-E09-T042-P1-BS	Aqueous
09A-E09-T135-P3-AS	Aqueous
09A-E09-T135-P3-AT	Aqueous
09A-E09-T135-P3-BS	Aqueous

The following method was applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above method(s) along with USEPA Region II validation SOP(s) (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results			√
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results			√
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and initial and continuing calibration blanks (ICBs and CCBs) were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria. MS/MSD analyses were not performed on the samples in this data set.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

No laboratory duplicate analysis was performed on the samples in this data set.

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No sample results were qualified as a result of validation actions.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09110237		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Full		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 20, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09110237_LP661_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on November 11, 2009.

Client Sample ID	Matrix
09A-E08-T067-P1-AS	Aqueous
09A-E08-T067-P1-BS	Aqueous
09A-E08-T067-P2-AS	Aqueous
09A-E08-T067-P2-BS	Aqueous
09A-E08-T067-P3-AS	Aqueous
09A-E08-T067-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Nonconformances are summarized in Attachment A, Table A-1. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> QL, but < 5x concentration of blank	Qualify reported result as nondetect (U)
		> QL and ≥ 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB	Qualify results as unusable (R)
		>the EB but <10x the EB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB	No action is taken based on AECOM professional judgment

DOC was detected > the MDL (0.2 mg/L), but < the quantitation limit (QL) in EB 09A-E08-T067-P3-XR. All associated sample results were > QL and ≥ 5x the blank concentration; therefore, no qualifications were necessary on this basis.

POC was also detected > the MDL (0.5 mg/L), but < the quantitation limit (QL) in EB 09A-E08-T067-P3-XR. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

No field duplicates were associated with this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This "J" qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
09A-E08-T067-P3-AS	WS	POC		0.8	mg/L	U	be
09A-E08-T067-P3-BS	WS	POC		0.8	mg/L	U	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- There will be no value under the Result column if the result is nondetect

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
EB 09A-E04-T135-P3XR	POC	0.6	0.4	1.7	0.8	09A-E08-T067-P3-AS
				2.2	0.8	09A-E08-T067-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09110238		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 14, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09110238_LP662_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on November 11, 2009.

Client Sample ID	Matrix
09A-E07-T042-P2-AS	Aqueous
09A-E07-T042-P2-BS	Aqueous
09A-E07-T042-P3-AS	Aqueous
09A-E07-T067-P1-AS	Aqueous
09A-E08-T042-P2-AS	Aqueous
09A-E08-T042-P2-BS	Aqueous
09A-E08-T042-P3-AS	Aqueous
09A-E08-T042-P3-BS	Aqueous

The following method was applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above method(s) along with USEPA Region II validation SOP(s) (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results			√
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results			√
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and initial and continuing calibration blanks (ICBs and CCBs) were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria. MS/MSD analyses were not performed on the samples in this data set.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL) for SSC.

There were no field duplicates associated with this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

No laboratory duplicate analysis was performed on the samples in this data set.

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No sample results were qualified as a result of validation actions.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09110239		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 20, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09110239_LP663_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on November 11, 2009.

Client Sample ID	Matrix
09A-E08-T014-P1-AS	Aqueous
09A-E08-T014-P1-BS	Aqueous
09A-E08-T014-P2-AS	Aqueous
09A-E08-T014-P2-BS	Aqueous
09A-E08-T014-P3-AS	Aqueous
09A-E08-T014-P3-BS	Aqueous
09A-E08-T042-P1-AS	Aqueous
09A-E08-T042-P1-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Nonconformances are summarized in Attachment A, Table A-1. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> QL, but < 5x concentration of blank	Qualify reported result as nondetect (U)
		> QL and ≥ 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB	Qualify results as unusable (R)
		>the EB but <10x the EB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB	No action is taken based on AECOM professional judgment

DOC was detected > the MDL (0.2 mg/L), but < the quantitation limit (QL)) in EB 09A-E08-T067-P3-XR. All associated sample results were > QL and ≥ 5x the blank concentration; therefore, no qualifications were necessary on this basis.

POC was also detected > the MDL (0.5 mg/L), but < the quantitation limit (QL) in EB 09A-E08-T067-P3-XR. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

No field duplicates were associated with this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
09A-E08-T014-P3-AS	WS	POC		0.8	mg/L	U	be
09A-E08-T042-P1-AS	WS	POC		0.8	mg/L	U	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- There will be no value under the Result column if the result is nondetect

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
EB 09A-E04-T135-P3XR	POC	0.6	0.4	1.0	0.8	09A-E08-T014-P3-AS
				1.7	0.8	09A-E08-T042-P1-AS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09110240		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 19, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09110240_LP664_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on November 11, 2009.

Client Sample ID	Matrix
09A-E07-T042-P3-BS	Aqueous
09A-E07-T067-P1-BS	Aqueous
09A-E07-T067-P2-AS	Aqueous
09A-E07-T067-P2-BS	Aqueous
09A-E07-T067-P3-AS	Aqueous
09A-E07-T067-P3-BS	Aqueous
09A-E07-T067-P3-BT	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> QL, but < 5x concentration of blank	Qualify reported result as nondetect (U)
		> QL and ≥ 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB	Qualify results as unusable (R)
		>the EB but <10x the EB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB	No action is taken based on AECOM professional judgment

DOC and POC were detected > the MDL, but < the quantitation limit (QL) in EB 09A-E08-T067-P3-XR. All associated sample results were > QL and ≥ 5x the blank concentration; therefore, no qualifications were necessary on this basis.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

No field duplicates were associated with this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No sample results were qualified as a result of validation actions.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09110241		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 20, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09110241_LP665_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on November 11, 2009.

Client Sample ID	Matrix
09A-E07-T135-P1-AS	Aqueous
09A-E07-T135-P1-BS	Aqueous
09A-E07-T135-P2-AS	Aqueous
09A-E07-T135-P2-BS	Aqueous
09A-E07-T135-P3-AS	Aqueous
09A-E07-T135-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results		√	
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Nonconformances are summarized in Attachment A, Table A-1. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> QL, but < 5x concentration of blank	Qualify reported result as nondetect (U)
		> QL and ≥ 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB	Qualify results as unusable (R)
		>the EB but <10x the EB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB	No action is taken based on AECOM professional judgment

DOC was detected > the MDL (0.2 mg/L), but < the quantitation limit (QL) in EB 09A-E08-T067-P3-XR. All associated sample results were > QL and ≥ 5x the blank concentration; therefore, no qualifications were necessary on this basis.

POC was also detected > the MDL (0.5 mg/L), but < the quantitation limit (QL) in EB 09A-E08-T067-P3-XR. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

No field duplicates were associated with this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria. Nonconformances are summarized in Attachment A, Table A-2. Data qualification on the basis of LCS nonconformance was as follows:

Criteria	Actions	
	Detected	Nondetected
%R < 50%	R	R
%R = 50 – 79% (SSC, DOC)	J	UJ
%R > 121% to 150% (SSC, DOC)	J	Accept
%R > 106% to 150% (POC)		
%R >150%	R	Accept

Samples were qualified on a batch basis for LCS nonconformance. Qualified sample results are shown in Table 1.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
09A-E07-T135-P3-AS	WS	SSC	7	1	mg/L	J	I
09A-E07-T135-P3-BS	WS	SSC	10	1	mg/L	J	I
09A-E07-T135-P3-AS	WS	POC		0.8	mg/L	U	be
09A-E07-T135-P3-BS	WS	POC		0.8	mg/L	U	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- There will be no value under the Result column if the result is nondetect

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
EB 09A-E04-T135-P3XR	POC	0.6	0.4	1.2	0.8	09A-E07-T135-P3-AS
				1.5	0.8	09A-E07-T135-P3-BS

Table A-2 – Laboratory Control Sample

LCS Batch ID	Analyte	LCS %R	Associated Samples
TSS_SDMT_B_11/25/200	SSC	79	09A-E03-T102-P1-AS
			09A-E03-T102-P1-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09110242		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 20, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09110242_LP666_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on November 11, 2009.

Client Sample ID	Matrix
09A-E08-T135-P1-AS	Aqueous
09A-E08-T135-P1-BS	Aqueous
09A-E08-T135-P2-AS	Aqueous
09A-E08-T135-P2-BS	Aqueous
09A-E08-T135-P3-AS	Aqueous
09A-E08-T135-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results		√	
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Nonconformances are summarized in Attachment A, Table A-1. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> QL, but < 5x concentration of blank	Qualify reported result as nondetect (U)
		> QL and ≥ 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB	Qualify results as unusable (R)
		>the EB but <10x the EB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB	No action is taken based on AECOM professional judgment

DOC was detected > the MDL (0.2 mg/L), but < the quantitation limit (QL) in EB 09A-E08-T067-P3-XR. All associated sample results were > QL and ≥ 5x the blank concentration; therefore, no qualifications were necessary on this basis.

POC was also detected > the MDL (0.5 mg/L), but < the quantitation limit (QL) in EB 09A-E08-T067-P3-XR. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

No field duplicates were associated with this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria. Nonconformances are summarized in Attachment A, Table A-2. Data qualification on the basis of LCS nonconformance was as follows:

Criteria	Actions	
	Detected	Nondetected
%R < 50%	R	R
%R = 50 – 79% (SSC, DOC)	J	UJ
%R > 121% to 150% (SSC, DOC)	J	Accept
%R > 106% to 150% (POC)		
%R >150%	R	Accept

Samples were qualified on a batch basis for LCS nonconformance. Qualified sample results are shown in Table 1.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
09A-E08-T135-P1-AS	WS	SSC	6	1	mg/L	J	I
09A-E08-T135-P1-BS	WS	SSC	7	1	mg/L	J	I
09A-E08-T135-P2-AS	WS	SSC	5	1	mg/L	J	I
09A-E08-T135-P2-BS	WS	SSC	6	1	mg/L	J	I
09A-E08-T135-P3-AS	WS	SSC	5	1	mg/L	J	I
09A-E08-T135-P3-BS	WS	SSC	7	1	mg/L	J	I
09A-E08-T135-P3-AS	WS	POC		0.8	mg/L	U	be
09A-E08-T135-P3-BS	WS	POC		0.8	mg/L	U	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- There will be no value under the Result column if the result is nondetect

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
09A-E08-T067-P3-XR	POC	0.5 J	0.8	0.8	0.8	09A-E08-T135-P3-AS
			0.8	0.9	0.8	09A-E08-T135-P3-BS

Table A-2 – Laboratory Control Sample

LCS Batch ID	Analyte	LCS %R	Associated Samples
TSS_SDMT_B_11/25/200	SSC	79	09A-E08-T135-P1-AS
			09A-E08-T135-P1-BS
			09A-E08-T135-P2-AS
			09A-E08-T135-P2-BS
			09A-E08-T135-P3-AS
			09A-E08-T135-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09110243		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 20, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09110243_LP667_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on November 11, 2009.

Client Sample ID	Matrix
09A-E08-T067-P3-XR	Aqueous
09A-E08-T102-P1-AS	Aqueous
09A-E08-T102-P1-BS	Aqueous
09A-E08-T102-P2-AS	Aqueous
09A-E08-T102-P2-BS	Aqueous
09A-E08-T102-P3-AS	Aqueous
09A-E08-T102-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results		√	
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Sample 09A-E08-T067-P3-XR was incorrectly indicated on the COC as 09A-E08-T067-P3-XT. This error was corrected during validation. No validation actions other than this notation were necessary.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Nonconformances are summarized in Attachment A, Table A-1. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> QL, but < 5x concentration of blank	Qualify reported result as nondetect (U)
		> QL and ≥ 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB	Qualify results as unusable (R)
		>the EB but <10x the EB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB	No action is taken based on AECOM professional judgment

DOC was detected > the MDL (0.2 mg/L), but < the quantitation limit (QL) in EB 09A-E08-T067-P3-XR. All associated sample results were > QL and ≥ 5x the blank concentration; therefore, no qualifications were necessary on this basis.

POC was also detected > the MDL (0.5 mg/L), but < the quantitation limit (QL) in EB 09A-E08-T067-P3-XR. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

No field duplicates were associated with this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria. Nonconformances are summarized in Attachment A, Table A-2. Data qualification on the basis of LCS nonconformance was as follows:

Criteria	Actions	
	Detected	Nondetected
%R < 50%	R	R
%R = 50 – 79% (SSC, DOC)	J	UJ
%R > 121% to 150% (SSC, DOC)	J	Accept
%R > 106% to 150% (POC)		
%R >150%	R	Accept

Samples were qualified on a batch basis for LCS nonconformance. Qualified sample results are shown in Table 1.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
09A-E08-T067-P3-XR	WS	SSC		1	mg/L	UJ	I
09A-E08-T102-P1-AS	WS	SSC	26	1	mg/L	J	I
09A-E08-T102-P1-BS	WS	SSC	41	1	mg/L	J	I
09A-E08-T102-P2-AS	WS	SSC	21	1	mg/L	J	I
09A-E08-T102-P2-BS	WS	SSC	48	1	mg/L	J	I
09A-E08-T102-P3-AS	WS	SSC	20	1	mg/L	J	I
09A-E08-T102-P3-BS	WS	SSC	35	1	mg/L	J	I
09A-E08-T102-P1-AS	WS	POC		0.8	Mg/L	U	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- There will be no value under the Result column if the result is nondetect

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
EB 09A-E04-T135-P3XR	POC	0.6	0.4	2.2	0.8	09A-E07-T014-P1-AS

Table A-2 – Laboratory Control Sample

LCS Batch ID	Analyte	LCS %R	Associated Samples
TSS_SDMT_B_11/25/200	SSC	79	09A-E08-T067-P3-XR
			09A-E08-T102-P1-AS
			09A-E08-T102-P1-BS
			09A-E08-T102-P2-AS
			09A-E08-T102-P2-BS
			09A-E08-T102-P3-AS
			09A-E08-T102-P3-BS
			09A-E08-T067-P3-XR

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09110244		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 20, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09110244_LP668_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on November 11, 2009.

Client Sample ID	Matrix
09A-E07-T014-P1-AS	Aqueous
09A-E07-T014-P1-BS	Aqueous
09A-E07-T014-P2-AS	Aqueous
09A-E07-T014-P2-BS	Aqueous
09A-E07-T014-P3-AS	Aqueous
09A-E07-T014-P3-BS	Aqueous
09A-E07-T042-P1-AS	Aqueous
09A-E07-T042-P1-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results		√	
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Nonconformances are summarized in Attachment A, Table A-1. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> QL, but < 5x concentration of blank	Qualify reported result as nondetect (U)
		> QL and ≥ 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB	Qualify results as unusable (R)
		>the EB but <10x the EB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB	No action is taken based on AECOM professional judgment

DOC was detected > the MDL (0.2 mg/L), but < the quantitation limit (QL) in EB 09A-E08-T067-P3-XR. All associated sample results were > QL and ≥ 5x the blank concentration; therefore, no qualifications were necessary on this basis.

POC was also detected > the MDL (0.5 mg/L), but < the quantitation limit (QL) in EB 09A-E08-T067-P3-XR. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

No field duplicates were associated with this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria. Nonconformances are summarized in Attachment A, Table A-2. Data qualification on the basis of LCS nonconformance was as follows:

Criteria	Actions	
	Detected	Nondetected
%R < 50%	R	R
%R = 50 – 79% (SSC, DOC)	J	UJ
%R > 121% to 150% (SSC, DOC)	J	Accept
%R > 106% to 150% (POC)		
%R >150%	R	Accept

Samples were qualified on a batch basis for LCS nonconformance. Qualified sample results are shown in Table 1.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
09A-E07-T014-P1-AS	WS	SSC	17	1	mg/L	J	I
09A-E07-T014-P1-BS	WS	SSC	29	1	mg/L	J	I
09A-E07-T014-P2-AS	WS	SSC	16	1	mg/L	J	I
09A-E07-T014-P2-BS	WS	SSC	25	1	mg/L	J	I
09A-E07-T014-P3-AS	WS	SSC	17	1	mg/L	J	I
09A-E07-T014-P1-AS	WS	POC		0.8	mg/L	U	be
09A-E07-T014-P3-AS	WS	POC		0.8	mg/L	U	be
09A-E07-T014-P3-BS	WS	POC		0.8	mg/L	U	be
09A-E07-T042-P1-BS	WS	POC		0.8	mg/L	U	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
EB 09A-E04-T135-P3XR	POC	0.6	0.4	2.2	0.8	09A-E07-T014-P1-AS
				1.4	0.8	09A-E07-T014-P3-AS
				1.4	0.8	09A-E07-T014-P3-BS
				1.8	0.8	09A-E07-T042-P1-BS

Table A-2 – Laboratory Control Sample

LCS Batch ID	Analyte	LCS %R	Associated Samples
TSS_SDMT_B_11/25/200	SSC	79	09A-E07-T014-P1-AS
			09A-E07-T014-P1-BS
			09A-E07-T014-P2-AS
			09A-E07-T014-P2-BS
			09A-E07-T014-P3-AS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09110245		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed January 20, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09110245_LP669_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on November 11, 2009.

Client Sample ID	Matrix
09A-E07-T102-P1-AS	Aqueous
09A-E07-T102-P1-BS	Aqueous
09A-E07-T102-P1-BT	Aqueous
09A-E07-T102-P2-AS	Aqueous
09A-E07-T102-P2-BS	Aqueous
09A-E07-T102-P3-AS	Aqueous
09A-E07-T102-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Nonconformances are summarized in Attachment A, Table A-1. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> QL, but < 5x concentration of blank	Qualify reported result as nondetect (U)
		> QL and ≥ 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB	Qualify results as unusable (R)
		>the EB but <10x the EB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB	No action is taken based on AECOM professional judgment

DOC was detected > the MDL (0.2 mg/L), but < the quantitation limit (QL) in EB 09A-E08-T067-P3-XR. All associated sample results were > QL and ≥ 5x the blank concentration; therefore, no qualifications were necessary on this basis.

POC was also detected > the MDL (0.5 mg/L), but < the quantitation limit (QL) in EB 09A-E08-T067-P3-XR. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

No field duplicates were associated with this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This "J" qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
09A-E07-T102-P1-AS	WS	POC		0.8	mg/L	U	be
09A-E07-T102-P1-BS	WS	POC		0.8	mg/L	U	be
09A-E07-T102-P1-BT	WS	POC		0.8	mg/L	U	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- There will be no value under the Result column if the result is nondetect

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
EB 09A-E04-T135-P3XR	POC	0.6	0.4	1.5	0.8	09A-E07-T102-P1-AS
				1.8	0.8	09A-E07-T102-P1-BS
				2.2	0.8	09A-E07-T102-P1-BT

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09120270		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Full		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed February 22, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09120270_LP670_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on December 14, 2009.

Client Sample ID	Matrix
09A-E12-T102-P1-AS	Aqueous
09A-E12-T102-P1-BS	Aqueous
09A-E12-T135-P3-AS	Aqueous
09A-E12-T135-P3-BS	Aqueous
09A-E12-T102-P3-XR	Aqueous
09A-E13-T102-P1-AS	Aqueous
09A-E13-T102-P1-BS	Aqueous
09A-E13-T135-P3-AS	Aqueous
09A-E13-T135-P3-BS	Aqueous
TRIP BLANK	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)		√	
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The equipment blank sample ID was noted on the COC as 09A-E12-XR; however the correct sample ID should be 09A-E12-T102-P3-XR. The sample ID was corrected during validation.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial (ICV) and continuing calibrations (CCV) percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met. Data qualification on the basis of calibration %R was as follows:

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

There were no field duplicates associated with the samples in this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This "J" qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
09A-E12-T102-P1-AS	w	POC	2.7	1.0	mg/L	J	c
09A-E12-T102-P1-BS	w	POC	3.1	1.0	mg/L	J	c
09A-E12-T135-P3-AS	w	POC	2.2	1.0	mg/L	J	c
09A-E12-T135-P3-BS	w	POC	2.3	1.0	mg/L	J	c
09A-E12-T102-P3-XR	w	POC		1.0	mg/L	UJ	c
09A-E13-T135-P3-AS	w	POC	1.5	1.0	mg/L	J	c
09A-E13-T135-P3-BS	w	POC	1.6	1.0	mg/L	J	c
TRIP BLANK	w	POC		1.0	mg/L	UJ	c

- No value will appear in the results column where the sample result was nondetected
- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Calibration Recovery

ICV/CCV	Analyte	Standard (% Carbon)	Result (% Carbon)	Recovery (%)	Affected Samples
AR 4017 5/1/10	DOC	0.470	0.448	95.3	09A-E12-T102-P1-AS
					09A-E12-T102-P1-BS
					09A-E12-T135-P3-AS
					09A-E12-T135-P3-BS
					09A-E12-T102-P3-XR
					09A-E13-T135-P3-AS
					09A-E13-T135-P3-BS
					TRIP BLANK

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09120271		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed February 22, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09120271_LP671_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on December 14, 2009.

Client Sample ID	Matrix
09A-E12-T014-P3-AS	Aqueous
09A-E12-T014-P3-BS	Aqueous
09A-E12-T042-P1-AS	Aqueous
09A-E12-T042-P1-BS	Aqueous
09A-E12-T067-P3-AS	Aqueous
09A-E12-T067-P3-BS	Aqueous
09A-E13-T014-P3-AS	Aqueous
09A-E13-T014-P3-BS	Aqueous
09A-E13-T042-P1-AS	Aqueous
09A-E13-T042-P1-BS	Aqueous
09A-E13-T067-P3-AS	Aqueous
09A-E13-T067-P3-BS	Aqueous
09A-E13-T067-P3-BT	Aqueous
TRIP BLANK 02	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL). Data qualification on the basis of laboratory duplicate RPDs contamination was as follows:

Criteria	Actions	
	Detect	**Nondetect**
RPD > 20% but < 100% and sample results ≥ the QL	J	Not Applicable
Sample and/or duplicate is <5x the QL, absolute difference is > the QL	J	UJ
Absolute difference is > 2x the QL and sample results are <5x the QL	R	R
RPD ≥ 100% and results ≥ the QL	R	Not Applicable
Sample and duplicate are both <5x the QL	No action is taken based on AECOM professional judgment	

One laboratory duplicate RPD exceeded the criteria for POC (40%); however, since the sample and duplicate results were each < 5x the QL, and the absolute difference between the sample and duplicate result was < the QL, no qualification actions were necessary.

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No sample results were qualified as a result of validation actions.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09120293		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed February 22, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09120293_LP673_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on December 14, 2009.

Client Sample ID	Matrix
09A-E12-T014-P1-AS	Aqueous
09A-E12-T014-P1-BS	Aqueous
09A-E12-T014-P2-AS	Aqueous
09A-E12-T014-P2-BS	Aqueous
09A-E12-T014-P3-AS	Aqueous
09A-E12-T014-P3-BS	Aqueous
09A-E12-T042-P1-AS	Aqueous
09A-E12-T042-P1-BS	Aqueous
09A-E12-T042-P2-AS	Aqueous
09A-E12-T042-P2-BS	Aqueous
09A-E12-T042-P3-AS	Aqueous
09A-E12-T042-P3-BS	Aqueous
09A-E12-T067-P1-AS	Aqueous
09A-E12-T067-P1-AT	Aqueous

Client Sample ID	Matrix
09A-E12-T067-P1-BS	Aqueous
09A-E12-T067-P2-AS	Aqueous
09A-E12-T067-P2-BS	Aqueous
09A-E12-T067-P3-AS	Aqueous
09A-E12-T067-P3-BS	Aqueous
09A-E13-T014-P1-AS	Aqueous
09A-E13-T014-P1-BS	Aqueous
09A-E13-T014-P2-AS	Aqueous
09A-E13-T014-P2-BS	Aqueous
09A-E13-T014-P3-AS	Aqueous
09A-E13-T014-P3-BS	Aqueous
09A-E13-T042-P1-AS	Aqueous
09A-E13-T042-P1-BS	Aqueous
09A-E13-T042-P2-AS	Aqueous
09A-E13-T042-P2-BS	Aqueous
09A-E13-T042-P3-AS	Aqueous
09A-E13-T042-P3-BS	Aqueous
09A-E13-T067-P1-AS	Aqueous
09A-E13-T067-P1-BS	Aqueous
09A-E13-T067-P2-AS	Aqueous
09A-E13-T067-P2-BS	Aqueous
09A-E13-T067-P3-AS	Aqueous
09A-E13-T067-P3-BS	Aqueous
09A-E13-T067-P3-BT	Aqueous

The following method was applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results			√
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results			√
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "R" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

MS/MSD Results

MS/MSD analyses are not applicable for SSC analysis.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

Laboratory duplicate analyses are performed as LCS/LCSD samples for SSC analysis.

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This "J" qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No sample results were qualified as a result of validation actions.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09120294		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed February 22, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09120294_LP674_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on December 14, 2009.

Client Sample ID	Matrix
09A-E13-T135-P1-AS	Aqueous
09A-E13-T135-P1-BS	Aqueous
09A-E13-T135-P2-AS	Aqueous
09A-E13-T135-P2-BS	Aqueous
09A-E13-T135-P3-AS	Aqueous
09A-E13-T135-P3-BS	Aqueous
09A-E13-T102-P1-AS	Aqueous
09A-E13-T102-P1-BS	Aqueous
09A-E13-T102-P2-AS	Aqueous
09A-E13-T102-P2-BS	Aqueous
09A-E13-T102-P3-AS	Aqueous
09A-E13-T102-P3-BS	Aqueous

Client Sample ID	Matrix
09A-E13-T102-P3-BT	Aqueous

The following method was applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results			√
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results			√
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The electronic data deliverable (EDD) was submitted with an incorrect sample collection date of 2/14/2009 instead of the correct date of 12/14/2009. The sampling date error was corrected during validation.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

MS/MSD Results

MS/MSD analyses are not applicable for SSC analysis.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

Laboratory duplicate analyses are performed as LCS/LCSD samples for SSC analysis.

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No sample results were qualified as a result of validation actions.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09120299		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Full		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed February 22, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09120299_LP675_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on December 15, 2009.

Client Sample ID	Matrix
09A-E11-T175-P1-AS	Aqueous
09A-E11-T175-P2-AS	Aqueous
09A-E11-T175-P2-BS	Aqueous
09A-E11-T175-P2-BT	Aqueous
09A-E11-T175-P3-AS	Aqueous
09A-E11-T175-P4-AS	Aqueous
TRIP BLANK 03	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL). Data qualification on the basis of laboratory duplicate RPDs contamination was as follows:

Criteria	Actions	
	Detect	**Nondetect**
RPD > 20% but < 100% and sample results ≥ the QL	J	Not Applicable
Sample and/or duplicate is <5x the QL, absolute difference is > the QL	J	UJ
Absolute difference is > 2x the QL and sample results are <5x the QL	R	R
RPD ≥ 100% and results ≥ the QL	R	Not Applicable
Sample and duplicate are both <5x the QL	No action is taken based on AECOM professional judgment	

One laboratory duplicate RPD exceeded the criteria for POC (40%); however, since the sample and duplicate results were each < 5x the QL, and the absolute difference between the sample and duplicate result was < the QL, no qualification actions were necessary.

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No sample results were qualified as a result of validation actions.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09120300		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed February 22, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09120300_LP676_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on December 15, 2009.

Client Sample ID	Matrix
09A-E10-T135-P3-AS	Aqueous
09A-E10-T135-P3-BS	Aqueous
09A-E10-T135-P3-AT	Aqueous
09A-E10-T102-P1-AS	Aqueous
09A-E10-T102-P1-BS	Aqueous
09A-E10-T067-P3-AS	Aqueous
09A-E10-T067-P3-BS	Aqueous

The following method was applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	**No**	**NA**
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results			√
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results			√
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

Samples 09A-E10-T135-P3-AS, 09A-E10-T135-P3-BS, and 09A-E10-T135-P3-AT were listed on the COC as 09A-E10-T135-<u>P1</u>-AS, 09A-E10-T135-<u>P1</u>-BS, and 09A-E10-T135-<u>P1</u>-AT. An amended COC was submitted. No validation actions other than this note were necessary.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

MS/MSD Results

MS/MSD analyses are not applicable for SSC analysis.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

Laboratory duplicate analyses are performed as LCS/LCSD samples for SSC analysis.

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No sample results were qualified as a result of validation actions.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09120328		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed February 22, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09120328_LP677_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on December 16, 2009.

Client Sample ID	Matrix
09A-E10-T014-P3-AS	Aqueous
09A-E10-T014-P3-BS	Aqueous
09A-E10-T042-P1-AS	Aqueous
09A-E10-T042-P1-BS	Aqueous

The following method was applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the

elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	**No**	**NA**
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results			√
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results			√
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

<u>Data Completeness</u>

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

<u>Holding Times/Sample Preservation</u>

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "R" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

MS/MSD Results

MS/MSD analyses are not applicable for SSC analysis.

Field Duplicate Results

No field duplicates were associated with this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

Laboratory duplicate analyses are performed as LCS/LCSD samples for SSC analysis.

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This "J" qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No sample results were qualified as a result of validation actions.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	09120292		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed February 22, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 09120292_LP672_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on December 16, 2009.

Client Sample ID	Matrix
09A-E12-T102-P1-AS	Aqueous
09A-E12-T102-P1-BS	Aqueous
09A-E12-T102-P2-AS	Aqueous
09A-E12-T102-P2-BS	Aqueous
09A-E12-T102-P3-AS	Aqueous
09A-E12-T102-P3-BS	Aqueous
09A-E12-T135-P1-AS	Aqueous
09A-E12-T135-P1-BS	Aqueous
09A-E12-T135-P2-AS	Aqueous
09A-E12-T135-P2-BS	Aqueous
09A-E12-T135-P3-AS	Aqueous
09A-E12-T135-P3-BS	Aqueous
09A-E12-T102-P3-XR	Aqueous

The following method was applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results			√
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results			√
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The equipment blank sample ID was noted on the COC as 09A-E12-XR; however the correct sample ID should be 09A-E12-T102-P3-XR. The sample ID was corrected during validation.

The electronic data deliverable (EDD) was submitted with an incorrect sample collection date of 12/14/2008 instead of the correct date of 12/14/2009. The sampling date error was corrected during validation.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs were associated with all samples collected in the same month as the EB.

MS/MSD Results

MS/MSD analyses are not applicable for SSC analysis.

Field Duplicate Results

No field duplicates were associated with this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

Laboratory duplicate analyses are performed as LCS/LCSD samples for SSC analysis.

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No sample results were qualified as a result of validation actions.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	10030303		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Full		
AECOM Project Number	60139067.A441		

Prepared by	Sharon McKechnie/AECOM	Completed May 5, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030303_LP678_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on March 16, 2010.

Client Sample ID	Matrix
NB1	Aqueous
NB3-DUP (field duplicate of NB3, discussed in SDG 10030308)	Aqueous
NB4	Aqueous
PR1	Aqueous
PR2	Aqueous
PR3	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results		√	
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified either with the words “Field Blank”, an “RB”, or an “FB” at the end of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EB NB6-FB in SDG 10030309 was associated with the samples in this data set.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates (FD) are identified with the letters "DUP" or a "D" as the last character(s) of the sample ID. The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC. FD pair NB3/NB3-DUP is associated with the samples in this data set. The sample results for the parent sample NB3 were reported in SDG 10030308 (LP683). Nonconformances are summarized in Attachment A, Table A-2.

Data qualification on the basis of field duplicate RPDs was as follows (see above for acceptance criteria):

Criteria	Action	
	Detected	Nondetected
RPD greater than the acceptance criteria, but < 120% and sample and duplicate results >5x the SQL	J	Not Applicable
RPD ≥ 120%	R	Not Applicable
If sample and/or duplicate is <5x the QL and absolute difference is >2x and ≤ 4x the QL	J	UJ
If the sample and/or duplicate is <5x the QL and absolute difference is >4x the QL.	R	R

Qualified sample results are shown in Table 1.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This "J" qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

A blank correction of 0.1646 mg/l was factored into the sample results by the laboratory due to the analytical instrument being moved during analysis. No qualification actions are necessary on this basis.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
NB1	SW	POC	1.7	1	mg/L	J	h
NB3-DUP	SW	POC	2.7	1	mg/L	J	h
NB4	SW	POC	3.2	1	mg/L	J	h
PR1	SW	POC	3.8	1	mg/L	J	h
PR2	SW	POC	4.5	1	mg/L	J	h
PR3	SW	POC	3.1	1	mg/L	J	h
NB3-DUP	SW	DOC	4.1	0.3	mg/L	J	fd

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
NB1	POC	29	28
NB3-DUP			
NB4			
PR1			
PR2			
PR3			

Table A-2 - Field Duplicate

Sample ID	Duplicate ID	Analyte	Sample Result	Duplicate Result	QL	Units	RPD
NB3	NB3-DUP	DOC	3.2	4.1	0.3	mg/L	25

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	10030304		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60139067.A441		

Prepared by	Sharon McKechnie/AECOM	Completed May 5, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030304_LP679_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on March 16, 2010.

Client Sample ID	Matrix
BRIDGE 3	Aqueous
BRIDGE 4	Aqueous
PARK 3	Aqueous
PARK 3D (field duplicate of PARK 3)	Aqueous
PARK 4	Aqueous
PARK 5	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified either with the words “Field Blank”, an “RB”, or an “FB” at the end of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EB Lower River Field Blank in SDG 10030305 was associated with the samples in this data set. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB or MB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB/MB	Qualify results as unusable (R)
		>the EB but <10x the EB/MB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB/MB	No action is taken based on AECOM professional judgment

DOC was detected > QL (0.81 mg/L) in EB Lower River Field Blank. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

SSC was detected >QL (3 mg/L) in EB Lower River Field Blank, however; all associated sample results were > 10x the EB, therefore no qualification action was necessary on this basis.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with the letters “DUP” or a “D” as the last character(s) of the sample ID. The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
BRIDGE 3	SW	POC	16	1	mg/L	J	h
BRIDGE 4	SW	POC	11	1	mg/L	J	h
PARK 3	SW	POC	4.1	1	mg/L	J	h
PARK 3D (field duplicate of PARK 3)	SW	POC	5.1	1	mg/L	J	h
PARK 4	SW	POC	4.2	1	mg/L	J	h
PARK 5	SW	POC	4.6	1	mg/L	J	h
BRIDGE 3	SW	DOC	3.2	0.30	mg/L	J	be
BRIDGE 4	SW	DOC	3.4	0.30	mg/L	J	be
PARK 3	SW	DOC	3.4	0.30	mg/L	J	be
PARK 3D (field duplicate of PARK 3)	SW	DOC	3.1	0.30	mg/L	J	be
PARK 4	SW	DOC	3.4	0.30	mg/L	J	be
PARK 5	SW	DOC	3.5	0.30	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
BRIDGE 3	POC	29	28
BRIDGE 4			
PARK 3			
PARK 3D (field duplicate of PARK 3)			
PARK 4			
PARK 5			

Table A-2 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
Lower River Field Blank	DOC	0.81	0.30	3.2	0.3	BRIDGE 3
				3.4		BRIDGE 4
				3.4		PARK 3
				3.1		PARK 3D (field duplicate of PARK 3)
				3.4		PARK 4
				3.5		PARK 5

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	10030305		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60139067.A441		

Prepared by	Sharon McKechnie/AECOM	Completed May 5, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030305_LP680_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on March 16, 2010.

Client Sample ID	Matrix
2ND RIVER WASHINGTON AVENUE	Aqueous
ACKERMAN 2	Aqueous
ACKERMAN 2D (field duplicate of ACKERMAN 2)	Aqueous
LOWER RIVER FIELD BLANK	Aqueous
SECOND HOT	Aqueous
UNION 2	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified either with the words “Field Blank”, an “RB”, or an “FB” at the end of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination.

EBs Lower River Field Blank in this SDG and Ackerman 4-RB in SDG 10030308 were associated with the samples in this data set. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB or MB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB/MB	Qualify results as unusable (R)
		>the EB but <10x the EB/MB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB/MB	No action is taken based on AECOM professional judgment

DOC was detected > QL (0.81 mg/L) and SSC was detected >QL (3 mg/L) in EB Lower River Field Blank. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with the letters “DUP” or a “D” as the last character(s) of the sample ID. The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
2ND RIVER WASHINGTON AVENUE	SW	POC		1	mg/L	UJ	h
ACKERMAN 2	SW	POC	4.7	1	mg/L	J	h
ACKERMAN 2D	SW	POC	5.3	1	mg/L	J	h
LOWER RIVER FIELD BLANK	SW	POC		1	mg/L	UJ	h
SECOND HOT	SW	POC	1.1	1	mg/L	J	h
UNION 2	SW	POC	4.7	1	mg/L	J	h
2ND RIVER WASHINGTON AVENUE	SW	DOC	2.5	0.30	mg/L	J	be
ACKERMAN 2	SW	DOC	3.5	0.30	mg/L	J	be
ACKERMAN 2D	SW	DOC	3.4	0.30	mg/L	J	be
SECOND HOT	SW	DOC	2.6	0.30	mg/L	J	be
UNION 2	SW	DOC	3.5	0.30	mg/L	J	be
SECOND HOT	SW	SSC		1	mg/L	U	be
2ND RIVER WASHINGTON AVENUE	SW	SSC		1	mg/L	U	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- No result value will be shown where result was non detected

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
2ND RIVER WASHINGTON AVENUE	POC	29	28
ACKERMAN 2			
ACKERMAN 2D			
SECOND HOT			
UNION 2			
LOWER RIVER FIELD BLANK			

Table A-2 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
Lower River Field Blank	DOC	0.81	0.30	2.5	0.30	2ND RIVER WASHINGTON AVENUE
				3.5		ACKERMAN 2
				3.4		ACKERMAN 2D
				2.6		SECOND HOT
				3.5		UNION 2
	SSC	3	1	1	1	SECOND HOT
				1		2ND RIVER WASHINGTON AVENUE

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	10030306		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60139067.A441		

Prepared by	Sharon McKechnie/AECOM	Completed May 5, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030306_LP681_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on March 16, 2010.

Client Sample ID	Matrix
ACKERMAN 1	Aqueous
SADDLE RIVER HOT 1	Aqueous
THIRD RIVER HOT	Aqueous
THIRD RIVER ROAD 1	Aqueous
UNION 3	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations(Analytical balance for SSC)		√	
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met. Data qualification on the basis of calibration %R was as follows:

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified either with the words “Field Blank”, an “RB”, or an “FB” at the end of the sample ID. Per Region II guidance, EBs were not qualified on the basis

of MB contamination. EB Ackerman 4 RB in SDG 10030308 was associated with the samples in this data set.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with the letters "DUP" or a "D" as the last character(s) of the sample ID. The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

There were no field duplicates associated with the samples in this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This "J" qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
ACKERMAN 1	SW	POC	4.1	1	mg/L	J	h,c
SADDLE RIVER HOT 1	SW	POC	1.6	1	mg/L	J	h,c
THIRD RIVER HOT	SW	POC		1	mg/L	UJ	h,c
THIRD RIVER ROAD 1	SW	POC		1	mg/L	UJ	h,c
UNION 3	SW	POC	4.4	1	mg/L	J	h,c

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- No result value will be shown where result was non detected

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
ACKERMAN 1	POC	29	28
SADDLE RIVER HOT 1			
THIRD RIVER HOT			
THIRD RIVER ROAD 1			
UNION 3			

Table A-2 – Calibration Recovery

ICV/CCV	Analyte	Standard (% Carbon)	Result (% Carbon)	Recovery (%)	Affected Samples
AR 4018 4/14/10	POC	1.30	1.219	93.8	ACKERMAN 1
					SADDLE RIVER HOT 1
					THIRD RIVER HOT
					THIRD RIVER ROAD 1
					UNION 3

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	10030307		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60139067.A441		

Prepared by	Sharon McKechnie/AECOM	Completed May 5, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030307_LP682_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on March 16, 2010.

Client Sample ID	Matrix
BRIDGE ST. 1	Aqueous
BRIDGE ST. 2	Aqueous
PARK 1	Aqueous
PARK AVE 2	Aqueous
SADDLE RIVER AVE 1	Aqueous
UNION 1	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations(Analytical balance for SSC)		√	
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met. Data qualification on the basis of calibration %R was as follows:

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified either with the words “Field Blank”, an “RB”, or an “FB” at the end of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination.

EBs Lower River Field Blank in SDG 10030305 (associated with Bridge St. 1, Park 1, Park Ave. 2, and Bridge St. 2) and Ackerman 4 RB in SDG 10030308 (associated with Union 1 and Saddle River Ave 1) were associated with the samples in this data set. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB or MB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB/MB	Qualify results as unusable (R)
		>the EB but <10x the EB/MB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB/MB	No action is taken based on AECOM professional judgment

DOC was detected > QL (0.81 mg/L) in EB Lower River Field Blank. Nonconformances are summarized in Attachment A, Table A-3. Qualified sample results are shown in Table 1.

SSC was detected >QL (3 mg/L) in EB Lower River Field Blank, however; all associated sample results were > 10x the EB, therefore no qualification action was necessary on this basis.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with the letters “DUP” or a “D” as the last character(s) of the sample ID. The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

There were no field duplicates associated with the samples in this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This "J" qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
BRIDGE ST. 1	SW	POC	6.9	1	mg/L	J	h,c
BRIDGE ST. 2	SW	POC	5.5	1	mg/L	J	h,c
PARK 1	SW	POC	6.6	1	mg/L	J	h,c
PARK AVE 2	SW	POC	4.8	1	mg/L	J	h,c
SADDLE RIVER AVE 1	SW	POC	2.0	1	mg/L	J	h,c
UNION 1	SW	POC	4.9	0.30	mg/L	J	h,c
BRIDGE ST. 1	SW	DOC	3.3	0.30	mg/L	J	be
BRIDGE ST. 2	SW	DOC	3.3	0.30	mg/L	J	be
PARK 1	SW	DOC	3.6	0.30	mg/L	J	be
PARK AVE 2	SW	DOC	3.4	0.30	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- No result value will be shown where result was non detected

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
BRIDGE ST. 1	POC	29	28
BRIDGE ST. 2			
PARK 1			
PARK AVE 2			
SADDLE RIVER AVE 1			
UNION 1			

Table A-2 – Calibration Recovery

ICV/CCV	Analyte	Standard (% Carbon)	Result (% Carbon)	Recovery (%)	Affected Samples
AR 4018 4/14/10	POC	1.30	1.219	93.8	BRIDGE ST. 1
					BRIDGE ST. 2
					PARK 1
					PARK AVE 2
					SADDLE RIVER AVE 1
					UNION 1

Table A-3 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
Lower River Field Blank	DOC	0.81	0.30	3.3	0.30	BRIDGE ST. 1
				3.3		BRIDGE ST. 2
				3.6		PARK 1
				3.4		PARK AVE 2

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	10030308		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60139067.A441		

Prepared by	Sharon McKechnie/AECOM	Completed May 5, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030308_LP683_WCM.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on March 16, 2010.

Client Sample ID	Matrix
ACKERMAN 3	Aqueous
ACKERMAN 4	Aqueous
ACKERMAN 4-RB (field blank)	Aqueous
NB2	Aqueous
NB3 (NB3-DUP reported in SDG 10030303)	Aqueous
UNION 4	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results		√	
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified either with the words “Field Blank”, an “RB”, or an “FB” at the end of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EBs Ackerman 4 RB in SDG 10030308 and NB6-FB in SDG 10030309 were associated with the samples in this data set.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates (FD) are identified with the letters "DUP" or a "D" as the last character(s) of the sample ID. The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC. FD pair NB3/NB3-DUP is associated with the samples in this data set. The sample results for FD NB3-DUP were reported in SDG 10030303 (LP678). Nonconformances are summarized in Attachment A, Table A-2.

Data qualification on the basis of field duplicate RPDs was as follows (see above for acceptance criteria):

Criteria	Action	
	Detected	Nondetected
RPD greater than the acceptance criteria, but < 120% and sample and duplicate results >5x the SQL	J	Not Applicable
RPD ≥ 120%	R	Not Applicable
If sample and/or duplicate is <5x the QL and absolute difference is >2x and ≤ 4x the QL	J	UJ
If the sample and/or duplicate is <5x the QL and absolute difference is >4x the QL.	R	R

Qualified sample results are shown in Table 1.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This "J" qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

A blank correction of 0.1503 mg/l was factored into the sample results by the laboratory due to the analytical instrument being moved during analysis. No qualification actions are necessary on this basis.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
ACKERMAN 3	SW	POC	4.4	1	mg/L	J	h
ACKERMAN 4	SW	POC	3.7	1	mg/L	J	h
ACKERMAN 4-RB (field blank)	SW	POC		1	mg/L	UJ	h
NB2	SW	POC	2.3	1	mg/L	J	h
NB3	SW	POC	2.9	1	mg/L	J	h
UNION 4	SW	POC	6.2	1	mg/L	J	h
NB3	SW	DOC	3.2	0.3	mg/L	J	fd

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- No result value will be shown where result was non detected

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
ACKERMAN 3	POC	29	28
ACKERMAN 4			
ACKERMAN 4-RB (field blank)			
NB2			
UNION 4			
NB3	POC	37	

Table A-2 - Field Duplicate

Sample ID	Duplicate ID	Analyte	Sample Result	Duplicate Result	QL	Units	RPD
NB3	NB3-DUP	DOC	3.2	4.1	0.3	mg/L	25

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Columbia Analytical Services, Phoenix, AZ		
Work Order	10030309		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0, Total and Dissolved Organic Carbon in Aqueous Matrix/5130C, and Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60139067.A441		

Prepared by	Sharon McKechnie/AECOM	Completed May 5, 2010	
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030309_LP684_WCM.doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on March 16, 2010.

Client Sample ID	Matrix
NB5	Aqueous
NB6	Aqueous
NB6-FB (field blank)	Aqueous
PR4	Aqueous
PR5	Aqueous
PR6	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Raw data applicable to the samples in this SDG was not furnished with the original data report. The laboratory was notified and a revised report sent May 5, 2010. No qualification actions were necessary on this basis.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. In the case of SSC, analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified either with the words “Field Blank”, an “RB”, or an “FB” at the end of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. EB NB6-FB in this SDG was associated with the samples in this data set.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with the letters “DUP” or a “D” as the last character(s) of the sample ID. The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC and ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

There were no field duplicates associated with the samples in this data set.

LCS Results

The LCSs %Rs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

All analytes detected at concentrations less than the method reporting limit (MRL), but greater than the MDL were qualified by the laboratory as estimated (J). This “J” qualifier was retained during data validation.

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
NB5	SW	POC	2.4	1	mg/L	J	h
NB6	SW	POC	2.1	1	mg/L	J	h
NB6-FB (field blank)	SW	POC		1	mg/L	UJ	h
PR4	SW	POC	6.3	1	mg/L	J	h
PR5	SW	POC	5.0	1	mg/L	J	h
PR6	SW	POC	6.5	1	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- No result value will be shown where result was non detected

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
NB6	POC	29	28
NB6-FB (field blank)			
PR4			
PR6			
NB5	POC	37	28
PR5			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Routine March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030462		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Full		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed June 25, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030462_LP697.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 24, 2010.

Client Sample ID	Matrix
10A-E02-T175-P1-AS	Aqueous
10A-E02-T175-P2-AS	Aqueous
10A-E02-T175-P2-BS	Aqueous
10A-E02-T175-P3-AS	Aqueous
10A-E02-T175-P4-AS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E01-T014-P3-XR, collected 3/22/2010 and reported in SDG 10030416, applies to the samples in this data set, and had no detected POC or DOC. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E02-T175-P1-AS	W	POC	1.5	1.0	mg/L	J	h
10A-E02-T175-P2-AS	W	POC	1.5	1.0	mg/L	J	h
10A-E02-T175-P2-BS	W	POC	1.6	1.0	mg/L	J	h
10A-E02-T175-P3-AS	W	POC	1.5	1.0	mg/L	J	h
10A-E02-T175-P4-AS	W	POC	1.6	1.0	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E02-T175-P1-AS	POC	29	28
10A-E02-T175-P2-AS			
10A-E02-T175-P2-BS			
10A-E02-T175-P3-AS			
10A-E02-T175-P4-AS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Routine March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030507		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed June 25, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030507_LP699.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
10A-E03-T014-P1-AS	Aqueous
10A-E03-T014-P1-BS	Aqueous
10A-E03-T014-P3-AS	Aqueous
10A-E03-T014-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations		√	
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial (ICV) and continuing calibrations (CCV) percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. Data qualification on the basis of calibration %R was as follows:

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E01-T014-P3-XR, collected 3/22/2010 and reported in SDG 10030416, applies to the samples in this data set, and had no detected POC or DOC. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E03-T014-P1-AS	W	POC	3.1	1.0	mg/L	J	h,c
10A-E03-T014-P1-BS	W	POC	13	1.0	mg/L	J	h,c
10A-E03-T014-P3-AS	W	POC	2.2	1.0	mg/L	J	h,c
10A-E03-T014-P3-BS	W	POC	2.5	1.0	mg/L	J	h,c

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E03-T014-P1-AS	POC	29	28
10A-E03-T014-P1-BS			
10A-E03-T014-P3-AS			
10A-E03-T014-P3-BS			

Table A-2 – Calibration Recovery

ICV/CCV	Analyte	Standard (% Carbon)	Result (% Carbon)	Recovery (%)	Affected Samples
AR 4018 3/15/10	POC	1.300	1.238	95	10A-E03-T014-P1-AS
					10A-E03-T014-P1-BS
					10A-E03-T014-P3-AS
					10A-E03-T014-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay, March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030514		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Full		
AECOM Project Number	60144462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed June 15, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030514_LP686.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
N01-E03-TARK-P1-AS	Aqueous
N01-E03-TARK-P1-BS	Aqueous
N01-E03-TARK-P3-AS	Aqueous
N01-E03-TARK-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination.

EBs were associated with all samples collected in the same week as the EB. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL). Data qualification on the basis of laboratory duplicate RPD nonconformance was as follows:

Criteria	Actions	
	Detect	Nondetect
RPD > 20% but < 100% and sample results ≥ the QL	J	Not Applicable
Sample and/or duplicate is <5x the QL, absolute difference is > the QL	J	UJ
Absolute difference is > 2x the QL and sample results are <5x the QL	R	R
RPD ≥ 100% and results ≥ the QL	R	Not Applicable
Sample and duplicate are both <5x the QL	No action is taken based on AECOM professional judgment	

The RPD of the POC LD analysis performed on sample N01-E03-TKVK-P3-AS (reported in this SDG) was not calculable (NC) due to a non-detected result in the parent sample. Precision was deemed acceptable since the detected result in the duplicate sample was < 5x the QL.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E03-TARK-P1-AS	W	POC		1.0	mg/L	UJ	h
N01-E03-TARK-P1-BS	W	POC	1.3	1.0	mg/L	J	h
N01-E03-TARK-P3-AS	W	POC	1.0	1.0	mg/L	J	h
N01-E03-TARK-P3-BS	W	POC		1.0	mg/L	UJ	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E03-TARK-P1-AS	POC	29	28
N01-E03-TARK-P1-BS			
N01-E03-TARK-P3-AS			
N01-E03-TARK-P3-BS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay, March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030515		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60144462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed June 4, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030514_LP687.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
N01-E03-TKVK-P3-AS	Aqueous
N01-E03-TKVK-P3-BS	Aqueous
N01-E03-TKVK-P1-AS	Aqueous
N01-E03-TKVK-P1-BS	Aqueous
N01-E03-TKVK-P1-BT (field duplicate of N01-E03-TKVK-P1-BS)	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination.

EBs were associated with all samples collected in the same week as the EB. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL). Data qualification on the basis of LD RPD nonconformance was as follows:

Criteria	Actions	
	Detect	Nondetect
RPD > 20% but < 100% and sample results ≥ the QL	J	Not Applicable
Sample and/or duplicate is <5x the QL, absolute difference is > the QL	J	UJ
Absolute difference is > 2x the QL and sample results are <5x the QL	R	R
RPD ≥ 100% and results ≥ the QL	R	Not Applicable
Sample and duplicate are both <5x the QL	No action is taken based on AECOM professional judgment	

The RPD of the POC LD analysis performed on sample N01-E03-TKVK-P3-AS (reported in this SDG) was not calculable (NC) due to a non-detected result in the parent sample. Precision was deemed acceptable since the detected result in the duplicate sample was < 5x the QL.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E03-TKVK-P3-AS	W	POC		1.0	mg/L	UJ	h
N01-E03-TKVK-P3-BS	W	POC	1.0	1.0	mg/L	J	h
N01-E03-TKVK-P1-AS	W	POC		1.0	mg/L	UJ	h
N01-E03-TKVK-P1-BS	W	POC		1.0	mg/L	UJ	h
N01-E03-TKVK-P1-BT	W	POC		1.0	mg/L	UJ	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E03-TKVK-P3-AS	POC	29	28
N01-E03-TKVK-P3-BS			
N01-E03-TKVK-P1-AS			
N01-E03-TKVK-P1-BS			
N01-E03-TKVK-P1-BT			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Routine March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030516		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed June 25, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030516_LP700.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
10A-E03-T042-P1-AS	Aqueous
10A-E03-T042-P1-AT (Field duplicate of 10A-E03-T042-P1-AS)	Aqueous
10A-E03-T042-P1-BS	Aqueous
10A-E03-T042-P3-AS	Aqueous
10A-E03-T042-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E04-T067-P3-XR, collected 3/25/2010 and reported in SDG 10030517, applies to the samples in this data set, and had no detected POC or DOC. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

One laboratory duplicate RPD for POC was not calculable due to a non-detected result in the sample. Precision was deemed acceptable since the duplicate result was < 5x the QL.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E03-T042-P1-AS	W	POC	2.5	1.0	mg/L	J	h
10A-E03-T042-P1-AT	W	POC	2.3	1.0	mg/L	J	h
10A-E03-T042-P1-BS	W	POC	2.4	1.0	mg/L	J	h
10A-E03-T042-P3-AS	W	POC	3.1	1.0	mg/L	J	h
10A-E03-T042-P3-BS	W	POC	2.6	1.0	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E03-T042-P1-AS	POC	29	28
10A-E03-T042-P1-AT			
10A-E03-T042-P1-BS			
10A-E03-T042-P3-AS			
10A-E03-T042-P3-BS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Routine March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030517		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed June 25, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030517_LP701.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
10A-E04-T067-P1-AS	Aqueous
10A-E04-T067-P1-BS	Aqueous
10A-E04-T067-P3-AS	Aqueous
10A-E04-T067-P3-BS	Aqueous
10A-E04-T067-P3-XR (Equipment blank 3/25/10)	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations		√	
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial (ICV) and continuing calibrations (CCV) percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. Data qualification on the basis of calibration %R was as follows:

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E04-T067-P3-XR, collected 3/25/2010 and reported in this SDG, applies to the samples in this data set, and had no detected POC or DOC. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E04-T067-P1-AS	W	POC	1.2	1.0	mg/L	J	h,c
10A-E04-T067-P1-BS	W	POC	1.1	1.0	mg/L	J	h,c
10A-E04-T067-P3-AS	W	POC	1.1	1.0	mg/L	J	h,c
10A-E04-T067-P3-BS	W	POC	1.3	1.0	mg/L	J	h,c
10A-E04-T067-P3-XR	W	POC		1.0	mg/L	UJ	h,c

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E04-T067-P1-AS	POC	29	28
10A-E04-T067-P1-BS			
10A-E04-T067-P3-AS			
10A-E04-T067-P3-BS			
10A-E04-T067-P3-XR			

Table A-2 – Calibration Recovery

ICV/CCV	Analyte	Standard (% Carbon)	Result (% Carbon)	Recovery (%)	Affected Samples
AR 4018 3/15/10	POC	1.300	1.238	95	10A-E04-T067-P1-AS
					10A-E04-T067-P1-BS
					10A-E04-T067-P3-AS
					10A-E04-T067-P3-BS
					10A-E04-T067-P3-XR

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay, March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030518		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60144462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed June 15, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030518_LP688.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
N01-E03-THKN-P1-AS	Aqueous
N01-E03-THKN-P1-BS	Aqueous
N01-E03-THKN-P3-AS	Aqueous
N01-E03-THKN-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination.

EBs were associated with all samples collected in the same week as the EB. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E03-THKN-P1-AS	W	POC	1.4	1.0	mg/L	J	h
N01-E03-THKN-P1-BS	W	POC	1.6	1.0	mg/L	J	h
N01-E03-THKN-P3-AS	W	POC	1.5	1.0	mg/L	J	h
N01-E03-THKN-P3-BS	W	POC	1.8	1.0	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E03-THKN-P1-AS	POC	29	28
N01-E03-THKN-P1-BS			
N01-E03-THKN-P3-AS			
N01-E03-THKN-P3-BS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Routine March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030519		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed June 25, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030519_LP702.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
10A-E03-T102-P1-AS	Aqueous
10A-E03-T102-P1-BS	Aqueous
10A-E03-T102-P3-AS	Aqueous
10A-E03-T102-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations		√	
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial (ICV) and continuing calibrations (CCV) percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. Data qualification on the basis of calibration %R was as follows:

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E04-T067-P3-XR, collected 3/25/2010 and reported in SDG 10030517, applies to the samples in this data set, and had no detected POC or DOC. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E03-T102-P1-AS	W	POC	1.5	1.0	mg/L	J	h
10A-E03-T102-P1-BS	W	POC	1.5	1.0	mg/L	J	h
10A-E03-T102-P3-AS	W	POC	1.5	1.0	mg/L	J	h,c
10A-E03-T102-P3-BS	W	POC	2.0	1.0	mg/L	J	h,c

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E03-T102-P1-AS	POC	29	28
10A-E03-T102-P1-BS			
10A-E03-T102-P3-AS			
10A-E03-T102-P3-BS			

Table A-2 – Calibration Recovery

ICV/CCV	Analyte	Standard (% Carbon)	Result (% Carbon)	Recovery (%)	Affected Samples
AR 4018 3/15/10	POC	1.300	1.238	95	10A-E03-T102-P3-AS
					10A-E03-T102-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Routine March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030520		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed June 25, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030520_LP703.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
10A-E04-T014-P1-AS	Aqueous
10A-E04-T014-P1-BS	Aqueous
10A-E04-T014-P3-AS	Aqueous
10A-E04-T014-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations		√	
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial (ICV) and continuing calibrations (CCV) percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. Data qualification on the basis of calibration %R was as follows:

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E04-T067-P3-XR, collected 3/25/2010 and reported in SDG 10030517, applies to the samples in this data set, and had no detected POC or DOC. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E04-T014-P1-AS	W	POC	1.5	1.0	mg/L	J	h
10A-E04-T014-P1-BS	W	POC	1.4	1.0	mg/L	J	h,c
10A-E04-T014-P3-AS	W	POC	1.4	1.0	mg/L	J	h
10A-E04-T014-P3-BS	W	POC	2.0	1.0	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E04-T014-P1-AS	POC	29	28
10A-E04-T014-P1-BS			
10A-E04-T014-P3-AS			
10A-E04-T014-P3-BS			

Table A-2 – Calibration Recovery

ICV/CCV	Analyte	Standard (% Carbon)	Result (% Carbon)	Recovery (%)	Affected Samples
AR 4018 3/15/10	POC	1.300	1.238	95	10A-E04-T014-P1-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay, March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030521		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60144462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed June 15, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030521_LP689.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
N01-E04-TARK-P1-AS	Aqueous
N01-E04-TARK-P1-BS	Aqueous
N01-E04-TARK-P3-AS	Aqueous
N01-E04-TARK-P3-BS	Aqueous
N01-E04-TARK-P3-XR (Equipment blank 3/25/10)	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination.

EBs were associated with all samples collected in the same week as the EB. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL). Data qualification on the basis of laboratory duplicate RPD nonconformance was as follows:

Criteria	Actions	
	Detect	Nondetect
RPD > 20% but < 100% and sample results ≥ the QL	J	Not Applicable
Sample and/or duplicate is <5x the QL, absolute difference is > the QL	J	UJ
Absolute difference is > 2x the QL and sample results are <5x the QL	R	R
RPD ≥ 100% and results ≥ the QL	R	Not Applicable
Sample and duplicate are both <5x the QL	No action is taken based on AECOM professional judgment	

The POC LD analysis performed on sample 10A-E03-TO67-P3-BS (reported in SDG 10030541) exceeded the RPD criteria (52%). Precision was deemed acceptable since the sample and duplicate results were both <5x the QL.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E04-TARK-P1-AS	W	POC	1.0	1.0	mg/L	J	h
N01-E04-TARK-P1-BS	W	POC	1.3	1.0	mg/L	J	h
N01-E04-TARK-P3-AS	W	POC	1.1	1.0	mg/L	J	h
N01-E04-TARK-P3-BS	W	POC	1.3	1.0	mg/L	J	h
N01-E04-TARK-P3-XR	W	POC		1.0	mg/L	UJ	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E04-TARK-P1-AS	POC	29	28
N01-E04-TARK-P1-BS			
N01-E04-TARK-P3-AS			
N01-E04-TARK-P3-BS			
N01-E04-TARK-P3-XR			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay, March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030522		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60144462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed June 15, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030522_LP690.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
N01-E04-TNBN-P1-AS	Aqueous
N01-E04-TNBN-P1-BS	Aqueous
N01-E04-TNBN-P3-AS	Aqueous
N01-E04-TNBN-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination.

EBs were associated with all samples collected in the same week as the EB. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E04-TNBN-P1-AS	W	POC	1.1	1.0	mg/L	J	h
N01-E04-TNBN-P1-BS	W	POC		1.0	mg/L	UJ	h
N01-E04-TNBN-P3-AS	W	POC	1.1	1.0	mg/L	J	h
N01-E04-TNBN-P3-BS	W	POC	1.0	1.0	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E04-TNBN-P1-AS	POC	29	28
N01-E04-TNBN-P1-BS			
N01-E04-TNBN-P3-AS			
N01-E04-TNBN-P3-BS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Routine March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030523		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed June 25, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030523_LP704.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 26, 2010.

Client Sample ID	Matrix
10A-E04-T135-P1-AS	Aqueous
10A-E04-T135-P1-BS	Aqueous
10A-E04-T135-P1-BT (Field duplicate of 10A-E04-T135-P1-BS)	Aqueous
10A-E04-T135-P3-AS	Aqueous
10A-E04-T135-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations		√	
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial (ICV) and continuing calibrations (CCV) percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. Data qualification on the basis of calibration %R was as follows:

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E04-T067-P3-XR, collected 3/25/2010 and reported in SDG 10030517, applies to the samples in this data set, and had no detected POC or DOC. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E04-T135-P1-BT	W	POC	1.4	1.0	mg/L	J	c

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Calibration Recovery

ICV/CCV	Analyte	Standard (% Carbon)	Result (% Carbon)	Recovery (%)	Affected Samples
AR 4018 3/15/10	POC	1.300	1.238	95	10A-E04-T135-P1-BT

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay, March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030524		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60144462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed June 15, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030524_LP691.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
N01-E04-TNBS-P1-AS	Aqueous
N01-E04-TNBS-P1-BS	Aqueous
N01-E04-TNBS-P3-AS	Aqueous
N01-E04-TNBS-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination.

EBs were associated with all samples collected in the same week as the EB. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E04-TNBS-P1-AS	W	POC	1.0	1.0	mg/L	J	h
N01-E04-TNBS-P1-BS	W	POC	1.0	1.0	mg/L	J	h
N01-E04-TNBS-P3-AS	W	POC	1.0	1.0	mg/L	J	h
N01-E04-TNBS-P3-BS	W	POC	1.1	1.0	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E04-TNBS-P1-AS	POC	29	28
N01-E04-TNBS-P1-BS			
N01-E04-TNBS-P3-AS			
N01-E04-TNBS-P3-BS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay, March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030525		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60144462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed June 7, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030525_LP692.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
N01-E04-TKVK-P1-AS	Aqueous
N01-E04-TKVK-P1-BS	Aqueous
N01-E04-TKVK-P1-BT (Field duplicate of N01-E04-TKVK-P1-BS)	Aqueous
N01-E04-TKVK-P2-AS	Aqueous
N01-E04-TKVK-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination.

EBs were associated with all samples collected in the same week as the EB. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

Data qualification on the basis of field duplicate RPD nonconformance was as follows (see above for acceptance criteria):

Criteria	Action	
	Detected	Nondetected
RPD greater than the acceptance criteria, but < 120% and sample and duplicate results >5x the SQL	J	Not Applicable
RPD ≥ 120%	R	Not Applicable
If sample and/or duplicate is <5x the QL and absolute difference is >2x and ≤ 4x the QL	J	UJ
If the sample and/or duplicate is <5x the QL and absolute difference is >4x the QL.	R	R

The field duplicate pair N01-E04-TKVK-P1-BS/ N01-E04-TKVK-P1-BT exceeded the RPD criteria for POC (32%). Precision was deemed acceptable since the sample and duplicate results were each < 5x the QL.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E04-TKVK-P1-AS	W	POC	1.1	1.0	mg/L	J	h
N01-E04-TKVK-P1-BS	W	POC	2.2	1.0	mg/L	J	h
N01-E04-TKVK-P1-BT	W	POC	1.6	1.0	mg/L	J	h
N01-E04-TKVK-P2-AS	W	POC	1.2	1.0	mg/L	J	h
N01-E04-TKVK-P3-BS	W	POC	1.4	1.0	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E04-TKVK-P1-AS	POC	29	28
N01-E04-TKVK-P1-BS			
N01-E04-TKVK-P1-BT			
N01-E04-TKVK-P2-AS			
N01-E04-TKVK-P3-BS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Routine March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030531		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed June 25, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030531_LP705.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
10A-E04-T102-P1-AS	Aqueous
10A-E04-T102-P1-BS	Aqueous
10A-E04-T102-P3-AS	Aqueous
10A-E04-T102-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E04-T067-P3-XR, collected 3/25/2010 and reported in SDG 10030517, applies to the samples in this data set, and had no detected POC or DOC. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

One laboratory duplicate RPD for POC was not calculable due to a non-detected result in the sample. Precision was deemed acceptable since the duplicate result was < 5x the QL.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E04-T102-P1-AS	W	POC	1.4	1.0	mg/L	J	h
10A-E04-T102-P1-BS	W	POC	1.0	1.0	mg/L	J	h
10A-E04-T102-P3-AS	W	POC	1.5	1.0	mg/L	J	h
10A-E04-T102-P3-BS	W	POC	1.5	1.0	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E04-T102-P1-AS	POC	29	28
10A-E04-T102-P1-BS			
10A-E04-T102-P3-AS			
10A-E04-T102-P3-BS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay, March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030534		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60144462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed June 15, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030534_LP693.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
N01-E04-THKN-P1-AS	Aqueous
N01-E04-THKN-P1-BS	Aqueous
N01-E04-THKN-P3-AS	Aqueous
N01-E04-THKN-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination.

EBs were associated with all samples collected in the same week as the EB. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL). Data qualification on the basis of laboratory duplicate RPD nonconformance was as follows:

Criteria	Actions	
	Detect	Nondetect
RPD > 20% but < 100% and sample results ≥ the QL	J	Not Applicable
Sample and/or duplicate is <5x the QL, absolute difference is > the QL	J	UJ
Absolute difference is > 2x the QL and sample results are <5x the QL	R	R
RPD ≥ 100% and results ≥ the QL	R	Not Applicable
Sample and duplicate are both <5x the QL	No action is taken based on AECOM professional judgment	

The RPD of the POC LD analysis performed on sample N01-E03-TKVK-P3-AS (reported in SDG 10030514) was not calculable (NC) due to a non-detected result in the parent sample. Precision was deemed acceptable since the detected result in the duplicate sample was < 5x the QL.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E04-THKN-P1-AS	W	POC	1.4	1.0	mg/L	J	h
N01-E04-THKN-P1-BS	W	POC	2.0	1.0	mg/L	J	h
N01-E04-THKN-P3-AS	W	POC	1.4	1.0	mg/L	J	h
N01-E04-THKN-P3-BS	W	POC	1.4	1.0	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E04-THKN-P1-AS	POC	29	28
N01-E04-THKN-P1-BS			
N01-E04-THKN-P3-AS			
N01-E04-THKN-P3-BS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay, March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030535		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60144462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed June 15, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030535_LP694.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
N01-E03-TNBS-P1-AS	Aqueous
N01-E03-TNBS-P1-BS	Aqueous
N01-E03-TNBS-P3-AS	Aqueous
N01-E03-TNBS-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody. The following discrepancy was noted:

- The second page of the COC was not signed as being relinquished; however, all other required signatures were present on the COC and the first page of the COC was complete. No actions other than this note were necessary.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination.

EBs were associated with all samples collected in the same week as the EB. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL). Data qualification on the basis of laboratory duplicate RPD nonconformance was as follows:

Criteria	Actions	
	Detect	Nondetect
RPD > 20% but < 100% and sample results ≥ the QL	J	Not Applicable
Sample and/or duplicate is <5x the QL, absolute difference is > the QL	J	UJ
Absolute difference is > 2x the QL and sample results are <5x the QL	R	R
RPD ≥ 100% and results ≥ the QL	R	Not Applicable
Sample and duplicate are both <5x the QL	No action is taken based on AECOM professional judgment	

The RPD of the POC LD analysis performed on sample N01-E03-TKVK-P3-AS (reported in SDG 10030514) was not calculable (NC) due to a non-detected result in the parent sample. Precision was deemed acceptable since the detected result in the duplicate sample was < 5x the QL.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E03-TNBS-P1-AS	W	POC	1.1	1.0	mg/L	J	h
N01-E03-TNBS-P1-BS	W	POC		1.0	mg/L	UJ	h
N01-E03-TNBS-P3-AS	W	POC		1.0	mg/L	UJ	h
N01-E03-TNBS-P3-BS	W	POC		1.0	mg/L	UJ	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E03-TNBS-P1-AS	POC	29	28
N01-E03-TNBS-P1-BS			
N01-E03-TNBS-P3-AS			
N01-E03-TNBS-P3-BS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Routine March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030536		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed June 25, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030536_LP706.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
10A-E03-T135-P1-AS	Aqueous
10A-E03-T135-P1-BS	Aqueous
10A-E03-T135-P3-AS	Aqueous
10A-E03-T135-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E04-T067-P3-XR, collected 3/25/2010 and reported in SDG 10030517, applies to the samples in this data set, and had no detected POC or DOC. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E03-T135-P1-AS	W	POC	1.2	1.0	mg/L	J	h
10A-E03-T135-P1-BS	W	POC	1.4	1.0	mg/L	J	h
10A-E03-T135-P3-AS	W	POC	1.4	1.0	mg/L	J	h
10A-E03-T135-P3-BS	W	POC	1.6	1.0	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E03-T135-P1-AS	POC	29	28
10A-E03-T135-P1-BS			
10A-E03-T135-P3-AS			
10A-E03-T135-P3-BS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Routine March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030541		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed June 25, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030541_LP707.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
10A-E03-T067-P1-AS	Aqueous
10A-E03-T067-P1-BS	Aqueous
10A-E03-T067-P3-AS	Aqueous
10A-E03-T067-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

DOC samples in this data set were received at the laboratory approximately one hour past the filtration hold time of 48 hours. POC samples in this data set were also analyzed outside of holding time.

Nonconformances are summarized in Attachment A, Table A-1a for POC and Table A-1b for DOC. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E04-T067-P3-XR, collected 3/25/2010 and reported in SDG 10030517, applies to the samples in this data set, and had no detected POC or DOC. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL.

One laboratory duplicate RPD exceeded (52%) the criteria for POC; however, since the sample and duplicate results were each < 5x the QL, no qualification actions were necessary.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E03-T067-P1-AS	W	POC	1.9	1.0	mg/L	J	h
10A-E03-T067-P1-BS	W	POC	2.2	1.0	mg/L	J	h
10A-E03-T067-P3-AS	W	POC	1.9	1.0	mg/L	J	h
10A-E03-T067-P3-BS	W	POC	2.3	1.0	mg/L	J	h
10A-E03-T067-P1-AS	W	DOC	4.0	5.0	mg/L	J	h
10A-E03-T067-P1-BS	W	DOC	4.0	5.0	mg/L	J	h
10A-E03-T067-P3-AS	W	DOC	4.0	5.0	mg/L	J	h
10A-E03-T067-P3-BS	W	DOC	4.0	5.0	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1a - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E03-T067-P1-AS	POC	29	28
10A-E03-T067-P1-BS			
10A-E03-T067-P3-AS			
10A-E03-T067-P3-BS			

Table A-1b - Hold Time

Sample ID	Analyte	Hours from Sampling to Prep (Filtration)	Criteria (Hours)
10A-E03-T067-P1-AS	DOC	52	48
10A-E03-T067-P1-BS			
10A-E03-T067-P3-AS			
10A-E03-T067-P3-BS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Routine March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030542		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Full		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed June 25, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030542_LP708.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
10A-E04-T042-P1-AS	Aqueous
10A-E04-T042-P1-AT (Field duplicate of 10A-E04-T042-P1-AS)	Aqueous
10A-E04-T042-P1-BS	Aqueous
10A-E04-T042-P3-AS	Aqueous
10A-E04-T042-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E04-T067-P3-XR, collected 3/25/2010 and reported in SDG 10030517, applies to the samples in this data set, and had no detected POC or DOC. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E04-T042-P1-AS	W	POC	1.3	1.0	mg/L	J	h
10A-E04-T042-P1-AT	W	POC	1.5	1.0	mg/L	J	h
10A-E04-T042-P1-BS	W	POC	1.3	1.0	mg/L	J	h
10A-E04-T042-P3-AS	W	POC	1.3	1.0	mg/L	J	h
10A-E04-T042-P3-BS	W	POC	1.2	1.0	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E04-T042-P1-AS	POC	29	28
10A-E04-T042-P1-AT			
10A-E04-T042-P1-BS			
10A-E04-T042-P3-AS			
10A-E04-T042-P3-BS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay, March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10030543		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60144462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed June 15, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10030543_LP695.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
N01-E03-TNBN-P1-AS	Aqueous
N01-E03-TNBN-P1-BS	Aqueous
N01-E03-TNBN-P3-AS	Aqueous
N01-E03-TNBN-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation		√	
Calibrations	√		
Laboratory method blanks/equipment blanks	√		
Matrix spike/matrix spike duplicate (MS/MSD) results	√		
Field duplicate results			√
Laboratory control sample (LCS) results	√		
Laboratory duplicate results	√		
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), initial and continuing calibration blanks (ICBs and CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “R” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination.

EBs were associated with all samples collected in the same week as the EB. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL). Data qualification on the basis of laboratory duplicate RPD nonconformance was as follows:

Criteria	Actions	
	Detect	Nondetect
RPD > 20% but < 100% and sample results ≥ the QL	J	Not Applicable
Sample and/or duplicate is <5x the QL, absolute difference is > the QL	J	UJ
Absolute difference is > 2x the QL and sample results are <5x the QL	R	R
RPD ≥ 100% and results ≥ the QL	R	Not Applicable
Sample and duplicate are both <5x the QL	No action is taken based on AECOM professional judgment	

The POC LD analysis performed on sample 10A-E03-TO67-P3-BS (reported in SDG 10030541) exceeded the RPD criteria (52%). Precision was deemed acceptable since the sample and duplicate results were both <5x the QL.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E03-TNBN-P1-AS	W	POC	1.8	1.0	mg/L	J	h
N01-E03-TNBN-P1-BS	W	POC	1.6	1.0	mg/L	J	h
N01-E03-TNBN-P3-AS	W	POC	1.5	1.0	mg/L	J	h
N01-E03-TNBN-P3-BS	W	POC	1.3	1.0	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E03-TNBN-P1-AS	POC	29	28
N01-E03-TNBN-P1-BS			
N01-E03-TNBN-P3-AS			
N01-E03-TNBN-P3-BS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay, March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10030535		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60144462.A410		
Prepared by	Sharon McKechnie/AECOM	Completed June 15, 2010	
Reviewed by	Lisa Krowitz/AECOM	File Name: LPR PWCM Newark Bay March SSC_LP694only.doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 25, 2010.

Client Sample ID	Matrix
N01-E03-TNBS-P1-AS	Aqueous
N01-E03-TNBS-P1-BS	Aqueous
N01-E03-TNBS-P2-AS	Aqueous
N01-E03-TNBS-P2-BS	Aqueous
N01-E03-TNBS-P3-AS	Aqueous
N01-E03-TNBS-P3-BS	Aqueous
N01-E03-TNBS-P3-BT (Field duplicate of N01-E03-TNBS-P3-BS)	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results			√
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results			√
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in the MB associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB N01-E04-TARK-P3-XR, collected on 3/25/2010 is associated with all samples collected 3/22/2010 through 3/28/2010. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB or MB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB/MB	Qualify results as unusable (R)
		>the EB but <10x the EB/MB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB/MB	No action is taken based on AECOM professional judgment

SSC was detected (5 mg/L) > quantitation limit (QL) in EB N01-E04-TARK-P3-XR (collected 3/25/10 and reported in SDG 10030521). Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E03-TNBS-P1-AS	W	SSC	7	1	mg/L	J	be
N01-E03-TNBS-P1-BS	W	SSC	8	1	mg/L	J	be
N01-E03-TNBS-P2-AS	W	SSC	13	1	mg/L	J	be
N01-E03-TNBS-P2-BS	W	SSC	13	1	mg/L	J	be
N01-E03-TNBS-P3-AS	W	SSC	7	1	mg/L	J	be
N01-E03-TNBS-P3-BS	W	SSC	7	1	mg/L	J	be
N01-E03-TNBS-P3-BT	W	SSC	8	1	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
EB N01-E04-TARK-P3-XR (3/25/10)	SSC	5.0	1.0	7	1.0	N01-E03-TNBS-P1-AS
				8		N01-E03-TNBS-P1-BS
				13		N01-E03-TNBS-P2-AS
				13		N01-E03-TNBS-P2-BS
				7		N01-E03-TNBS-P3-AS
				7		N01-E03-TNBS-P3-BS
				8		N01-E03-TNBS-P3-BT

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay, March Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10030415, 10030514, 10030515, 10030518, 10030521, 10030522, 10030524, 10030525, 10030534, 10030535, and 10030543		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited (All SDGs except 10030415) Full (10030415 only)		
AECOM Project Number	60144462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed June 15, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: LPR PWCM Newark Bay March SSC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on March 19, 20, 21, and 25, 2010.

SDG	Client Sample ID	Matrix
10030415	N01-E01-TARK-P1-AS	Aqueous
	N01-E01-TARK-P1-BS	Aqueous
	N01-E01-THKN-P1-AS	Aqueous
	N01-E01-THKN-P1-BS	Aqueous
	N01-E01-TKVK-P1-AS	Aqueous
	N01-E01-TKVK-P1-BS	Aqueous
	N01-E01-TNBN-P1-AS	Aqueous
	N01-E01-TNBN-P1-BS	Aqueous
	N01-E01-TNBN-P1-XR (Equipment blank 3/20/10)	Aqueous
	N01-E01-TNBS-P1-AS	Aqueous
	N01-E01-TNBS-P1-BS	Aqueous
	N01-E01-TNBS-P1-BT (Field duplicate of N01-E01-TNBS-P1-BS)	Aqueous

SDG	Client Sample ID	Matrix
10030514	N01-E03-TARK-P1-AS	Aqueous
	N01-E03-TARK-P1-BS	Aqueous
	N01-E03-TARK-P2-AS	Aqueous
	N01-E03-TARK-P2-BS	Aqueous
	N01-E03-TARK-P3-AS	Aqueous
	N01-E03-TARK-P3-BS	Aqueous
10030515	N01-E03-TKVK-P1-AS	Aqueous
	N01-E03-TKVK-P1-BS	Aqueous
	N01-E03-TKVK-P2-AS	Aqueous
	N01-E03-TKVK-P2-BS	Aqueous
	N01-E03-TKVK-P3-AS	Aqueous
	N01-E03-TKVK-P3-BS	Aqueous
10030518	N01-E03-THKN-P1-AS	Aqueous
	N01-E03-THKN-P1-BS	Aqueous
	N01-E03-THKN-P2-AS	Aqueous
	N01-E03-THKN-P2-BS	Aqueous
	N01-E03-THKN-P3-AS	Aqueous
	N01-E03-THKN-P3-BS	Aqueous
10030521	N01-E04-TARK-P1-AS	Aqueous
	N01-E04-TARK-P1-BS	Aqueous
	N01-E04-TARK-P2-AS	Aqueous
	N01-E04-TARK-P2-BS	Aqueous
	N01-E04-TARK-P3-AS	Aqueous
	N01-E04-TARK-P3-BS	Aqueous
	N01-E04-TARK-P3-XR (Equipment blank 3/25/10)	Aqueous
10030522	N01-E04-TNBN-P1-AS	Aqueous
	N01-E04-TNBN-P1-BS	Aqueous
	N01-E04-TNBN-P2-AS	Aqueous
	N01-E04-TNBN-P2-BS	Aqueous
	N01-E04-TNBN-P3-AS	Aqueous
	N01-E04-TNBN-P3-BS	Aqueous
10030524	N01-E04-TNBS-P1-AS	Aqueous
	N01-E04-TNBS-P1-BS	Aqueous
	N01-E04-TNBS-P2-AS	Aqueous
	N01-E04-TNBS-P2-BS	Aqueous
	N01-E04-TNBS-P2-BT (Field duplicate of N01-E04-TNBS-P2-BS)	Aqueous
	N01-E04-TNBS-P3-AS	Aqueous
	N01-E04-TNBS-P3-BS	Aqueous

SDG	Client Sample ID	Matrix
10030524	N01-E04-TNBS-P3-BT (Field duplicate of N01-E04-TNBS-P3-BS)	Aqueous
10030525	N01-E04-TKVK-P1-AS	Aqueous
	N01-E04-TKVK-P1-BS	Aqueous
	N01-E04-TKVK-P2-AS	Aqueous
	N01-E04-TKVK-P2-BS	Aqueous
	N01-E04-TKVK-P3-AS	Aqueous
	N01-E04-TKVK-P3-BS	Aqueous
10030534	N01-E04-THKN-P1-AS	Aqueous
	N01-E04-THKN-P1-BS	Aqueous
	N01-E04-THKN-P2-AS	Aqueous
	N01-E04-THKN-P2-BS	Aqueous
	N01-E04-THKN-P3-AS	Aqueous
	N01-E04-THKN-P3-BS	Aqueous
10030543	N01-E03-TNBN-P1-AS	Aqueous
	N01-E03-TNBN-P1-BS	Aqueous
	N01-E03-TNBN-P2-AS	Aqueous
	N01-E03-TNBN-P2-BS	Aqueous
	N01-E03-TNBN-P3-AS	Aqueous
	N01-E03-TNBN-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results			√
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results			√
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody. The following discrepancy was noted:

- SDG 10030514: Results were reported twice for sample N01-E03-TARK-P3-BS with collection times of 1432 and 1434. The COC listed the sample collected at 1434 as N01-E03-TARK-P3-AS. The sample ID was corrected during validation.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB N01-E01-TNBN-P1-XR, collected on 3/20/2010 is associated with all samples collected 3/15/2010 through 3/21/2010. EB N01-E04-TARK-P3-XR, collected on 3/25/2010 is associated with all samples collected 3/22/2010 through 3/28/2010. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB or MB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB/MB	Qualify results as unusable (R)
		>the EB but <10x the EB/MB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB/MB	No action is taken based on AECOM professional judgment

SSC was detected (5 mg/L) > quantitation limit (QL) in EB N01-E04-TARK-P3-XR (collected 3/25/10 and reported in SDG 10030521). Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

SSC was not detected in EB N01-E01-TNBN-P1-XR (collected 3/20/2010 and reported in SDG 10030415).

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E03-TARK-P1-AS	W	SSC	11	1	mg/L	J	be
N01-E03-TARK-P1-BS	W	SSC	11	1	mg/L	J	be
N01-E03-TARK-P2-AS	W	SSC	14	1	mg/L	J	be
N01-E03-TARK-P2-BS	W	SSC	12	1	mg/L	J	be
N01-E03-TARK-P3-AS	W	SSC	7	1	mg/L	J	be
N01-E03-TARK-P3-BS	W	SSC	7	1	mg/L	J	be
N01-E03-TKVK-P1-AS	W	SSC	9	1	mg/L	J	be
N01-E03-TKVK-P1-BS	W	SSC	11	1	mg/L	J	be
N01-E03-TKVK-P2-AS	W	SSC	11	1	mg/L	J	be
N01-E03-TKVK-P2-BS	W	SSC	9	1	mg/L	J	be
N01-E03-TKVK-P3-AS	W	SSC	14	1	mg/L	J	be
N01-E03-TKVK-P3-BS	W	SSC	9	1	mg/L	J	be
N01-E03-THKN-P1-AS	W	SSC	13	1	mg/L	J	be
N01-E03-THKN-P1-BS	W	SSC	20	1	mg/L	J	be
N01-E03-THKN-P2-AS	W	SSC	16	1	mg/L	J	be
N01-E03-THKN-P2-BS	W	SSC	20	1	mg/L	J	be
N01-E03-THKN-P3-AS	W	SSC	15	1	mg/L	J	be
N01-E03-THKN-P3-BS	W	SSC	18	1	mg/L	J	be
N01-E04-TARK-P1-AS	W	SSC	6	1	mg/L	J	be
N01-E04-TARK-P1-BS	W	SSC	9	1	mg/L	J	be
N01-E04-TARK-P2-AS	W	SSC	7	1	mg/L	J	be
N01-E04-TARK-P2-BS	W	SSC	7	1	mg/L	J	be
N01-E04-TARK-P3-AS	W	SSC	11	1	mg/L	J	be
N01-E04-TARK-P3-BS	W	SSC	8	1	mg/L	J	be
N01-E04-TNBN-P1-AS	W	SSC	9	1	mg/L	J	be
N01-E04-TNBN-P1-BS	W	SSC	8	1	mg/L	J	be
N01-E04-TNBN-P2-AS	W	SSC	7	1	mg/L	J	be
N01-E04-TNBN-P2-BS	W	SSC	8	1	mg/L	J	be
N01-E04-TNBN-P3-AS	W	SSC	7	1	mg/L	J	be
N01-E04-TNBN-P3-BS	W	SSC	8	1	mg/L	J	be
N01-E04-TNBS-P1-AS	W	SSC	6	1	mg/L	J	be
N01-E04-TNBS-P1-BS	W	SSC	25	1	mg/L	J	be
N01-E04-TNBS-P2-AS	W	SSC	7	1	mg/L	J	be
N01-E04-TNBS-P2-BS	W	SSC	18	1	mg/L	J	be
N01-E04-TNBS-P2-BT	W	SSC	12	1	mg/L	J	be
N01-E04-TNBS-P3-AS	W	SSC	7	1	mg/L	J	be
N01-E04-TNBS-P3-BS	W	SSC	7	1	mg/L	J	be
N01-E04-TNBS-P3-BT	W	SSC	7	1	mg/L	J	be
N01-E04-TKVK-P1-AS	W	SSC	9	1	mg/L	J	be
N01-E04-TKVK-P1-BS	W	SSC	43	1	mg/L	J	be
N01-E04-TKVK-P2-AS	W	SSC	34	1	mg/L	J	be
N01-E04-TKVK-P2-BS	W	SSC	12	1	mg/L	J	be

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E04-TKVK-P3-AS	W	SSC	10	1	mg/L	J	be
N01-E04-TKVK-P3-BS	W	SSC	10	1	mg/L	J	be
N01-E04-THKN-P1-AS	W	SSC	9	1	mg/L	J	be
N01-E04-THKN-P1-BS	W	SSC	18	1	mg/L	J	be
N01-E04-THKN-P2-AS	W	SSC	10	1	mg/L	J	be
N01-E04-THKN-P2-BS	W	SSC	33	1	mg/L	J	be
N01-E04-THKN-P3-AS	W	SSC	9	1	mg/L	J	be
N01-E04-THKN-P3-BS	W	SSC	14	1	mg/L	J	be
N01-E03-TNBN-P1-AS	W	SSC	20	1	mg/L	J	be
N01-E03-TNBN-P1-BS	W	SSC	15	1	mg/L	J	be
N01-E03-TNBN-P2-AS	W	SSC	13	1	mg/L	J	be
N01-E03-TNBN-P2-BS	W	SSC	17	1	mg/L	J	be
N01-E03-TNBN-P3-AS	W	SSC	11	1	mg/L	J	be
N01-E03-TNBN-P3-BS	W	SSC	14	1	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
EB N01-E04-TARK-P3-XR (3/25/10)	SSC	5.0	1.0	11	1.0	N01-E03-TARK-P1-AS
				11		N01-E03-TARK-P1-BS
				14		N01-E03-TARK-P2-AS
				12		N01-E03-TARK-P2-BS
				7		N01-E03-TARK-P3-AS
				7		N01-E03-TARK-P3-BS
				9		N01-E03-TKVK-P1-AS
				11		N01-E03-TKVK-P1-BS
				11		N01-E03-TKVK-P2-AS
				9		N01-E03-TKVK-P2-BS
				14		N01-E03-TKVK-P3-AS
				9		N01-E03-TKVK-P3-BS
				13		N01-E03-THKN-P1-AS
				20		N01-E03-THKN-P1-BS
				16		N01-E03-THKN-P2-AS
				20		N01-E03-THKN-P2-BS
				15		N01-E03-THKN-P3-AS
				18		N01-E03-THKN-P3-BS
				6		N01-E04-TARK-P1-AS
				9		N01-E04-TARK-P1-BS
				7		N01-E04-TARK-P2-AS
				7		N01-E04-TARK-P2-BS
				11		N01-E04-TARK-P3-AS
				8		N01-E04-TARK-P3-BS
				9		N01-E04-TNBN-P1-AS
				8		N01-E04-TNBN-P1-BS
				7		N01-E04-TNBN-P2-AS
				8		N01-E04-TNBN-P2-BS
				7		N01-E04-TNBN-P3-AS
				8		N01-E04-TNBN-P3-BS
				6		N01-E04-TNBS-P1-AS
				25		N01-E04-TNBS-P1-BS
				7		N01-E04-TNBS-P2-AS
				18		N01-E04-TNBS-P2-BS
				12		N01-E04-TNBS-P2-BT
				7		N01-E04-TNBS-P3-AS
				7		N01-E04-TNBS-P3-BS
				7		N01-E04-TNBS-P3-BT
				9		N01-E04-TKVK-P1-AS

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
EB N01-E04-TARK-P3-XR (3/25/10)	SSC	5.0	1.0	43	1.0	N01-E04-TKVK-P1-BS
				34		N01-E04-TKVK-P2-AS
				12		N01-E04-TKVK-P2-BS
				10		N01-E04-TKVK-P3-AS
				10		N01-E04-TKVK-P3-BS
				9		N01-E04-THKN-P1-AS
				18		N01-E04-THKN-P1-BS
				10		N01-E04-THKN-P2-AS
				33		N01-E04-THKN-P2-BS
				9		N01-E04-THKN-P3-AS
				14		N01-E04-THKN-P3-BS
				20		N01-E03-TNBN-P1-AS
				15		N01-E03-TNBN-P1-BS
				13		N01-E03-TNBN-P2-AS
				17		N01-E03-TNBN-P2-BS
				11		N01-E03-TNBN-P3-AS
				14		N01-E03-TNBN-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10030416, 10030462, 10030469, 10030507, 10030516, 10030517, 10030519, 10030520, 10030523, 10030531, 10030536, 10030541, and 10030542		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited (All SDGs except SDGs 10030462 and 10030542) Full (10030462 and 10030542 only)		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed June 15, 2010	
Reviewed by	Lisa Krowitz/AECOM	File Name: LPR PWCM March SSC.doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on March 22, 23, 24, and 25, 2010.

SDG	Client Sample ID	Matrix
10030416	10A-E01-T014-P3-AS	Aqueous
	10A-E01-T014-P3-BS	Aqueous
	10A-E01-T014-P3-XR (Equipment blank 3/22/10)	Aqueous
	10A-E01-T042-P1-AS	Aqueous
	10A-E01-T042-P1-BS	Aqueous
10030462	10A-E02-T175-P1-AS	Aqueous
	10A-E02-T175-P2-AS	Aqueous
	10A-E02-T175-P2-BS	Aqueous
	10A-E02-T175-P3-AS	Aqueous
	10A-E02-T175-P4-AS	Aqueous
10030469	10A-E01-T067-P3-AS	Aqueous
10030469	10A-E01-T067-P3-BS	Aqueous

SDG	Client Sample ID	Matrix
	10A-E01-T102-P1-AS	Aqueous
	10A-E01-T102-P1-BS	Aqueous
	10A-E01-T135-P3-AS	Aqueous
	10A-E01-T135-P3-BS	Aqueous
	10A-E01-T135-P3-BT (Field duplicate of 10A-E01-T135-P3-BS)	Aqueous
10030507	10A-E03-T014-P1-AS	Aqueous
	10A-E03-T014-P1-BS	Aqueous
	10A-E03-T014-P2-AS	Aqueous
	10A-E03-T014-P2-BS	Aqueous
	10A-E03-T014-P3-AS	Aqueous
	10A-E03-T014-P3-BS	Aqueous
10030516	10A-E03-T042-P1-AS	Aqueous
	10A-E03-T042-P1-BS	Aqueous
	10A-E03-T042-P2-AS	Aqueous
	10A-E03-T042-P2-BS	Aqueous
	10A-E03-T042-P3-AS	Aqueous
	10A-E03-T042-P3-BS	Aqueous
10030517	10A-E04-T067-P1-AS	Aqueous
	10A-E04-T067-P1-BS	Aqueous
	10A-E04-T067-P2-AS	Aqueous
	10A-E04-T067-P2-BS	Aqueous
	10A-E04-T067-P3-AS	Aqueous
	10A-E04-T067-P3-BS	Aqueous
	10A-E04-T067-P3-XR (Equipment blank 3/25/10)	Aqueous
10030519	10A-E03-T102-P1-AS	Aqueous
	10A-E03-T102-P1-AT (Field duplicate of 10A-E03-T102-P1-AS)	Aqueous
	10A-E03-T102-P1-BS	Aqueous
	10A-E03-T102-P2-AS	Aqueous
	10A-E03-T102-P2-BS	Aqueous
	10A-E03-T102-P3-AS	Aqueous
	10A-E03-T102-P3-BS	Aqueous
10030520	10A-E04-T014-P1-AS	Aqueous
	10A-E04-T014-P1-BS	Aqueous
	10A-E04-T014-P2-AS	Aqueous
	10A-E04-T014-P2-BS	Aqueous
	10A-E04-T014-P3-AS	Aqueous
10030520	10A-E04-T014-P3-BS	Aqueous

SDG	Client Sample ID	Matrix
10030523	10A-E04-T135-P1-AS	Aqueous
	10A-E04-T135-P1-BS	Aqueous
	10A-E04-T135-P2-AS	Aqueous
	10A-E04-T135-P2-BS	Aqueous
	10A-E04-T135-P3-AS	Aqueous
	10A-E04-T135-P3-BS	Aqueous
10030531	10A-E04-T102-P1-AS	Aqueous
	10A-E04-T102-P1-AT (Field duplicate of 10A-E04-T102-P1-AS)	Aqueous
	10A-E04-T102-P1-BS	Aqueous
	10A-E04-T102-P2-AS	Aqueous
	10A-E04-T102-P2-BS	Aqueous
	10A-E04-T102-P2-BT (Field duplicate of 10A-E04-T102-P2-BS)	Aqueous
	10A-E04-T102-P3-AS	Aqueous
	10A-E04-T102-P3-BS	Aqueous
10030536	10A-E03-T135-P1-AS	Aqueous
	10A-E03-T135-P1-BS	Aqueous
	10A-E03-T135-P2-AS	Aqueous
	10A-E03-T135-P2-BS	Aqueous
	10A-E03-T135-P3-AS	Aqueous
	10A-E03-T135-P3-BS	Aqueous
10030541	10A-E03-T067-P1-AS	Aqueous
	10A-E03-T067-P1-BS	Aqueous
	10A-E03-T067-P2-AS	Aqueous
	10A-E03-T067-P2-BS	Aqueous
	10A-E03-T067-P3-AS	Aqueous
	10A-E03-T067-P3-BS	Aqueous
10030542	10A-E04-T042-P1-AS	Aqueous
	10A-E04-T042-P1-BS	Aqueous
	10A-E04-T042-P2-AS	Aqueous
	10A-E04-T042-P2-BS	Aqueous
	10A-E04-T042-P3-AS	Aqueous
	10A-E04-T042-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	√		
Data completeness	√		
Holding times and sample preservation	√		
Calibrations(Analytical balance for SSC)	√		
Laboratory method blanks/equipment blanks		√	
Matrix spike/matrix spike duplicate (MS/MSD) results			√
Field duplicate results	√		
Laboratory control sample (LCS) results	√		
Laboratory duplicate results			√
Sample results	√		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E01-T014-P3-XR, collected on 3/22/2010 is associated with all samples collected 3/22/2010 through 3/28/2010. EB 10A-E04-T067-P3-XR, collected on 3/25/2010 is associated with all samples collected 3/22/2010 through 3/28/2010. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Blank Result	Sample Result	Actions
EB or MB	≥ the MDL but ≤ the QL	Nondetect	No action
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		> 5x concentration of blank	No qualification
	> the QL	>the QL but < the EB/MB	Qualify results as unusable (R)
		>the EB but <10x the EB/MB	Qualify results as estimated (J)
		≥ the MDL but ≤ the QL	Qualify as nondetect (U) at the QL
		≥ 10x the EB/MB	No action is taken based on AECOM professional judgment

SSC was detected (7 mg/L) > quantitation limit (QL) in EB 10A-E01-T014-P3-XR (collected 3/22/10, reported in SDG 10030416). Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

SSC was not detected in EB 10A-E04-T067-P3-XR (collected 3/25/2010, and reported in SDG 10030517).

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E01-T014-P3-AS	W	SSC	7	1	mg/L	J	be
10A-E01-T014-P3-BS	W	SSC	22	1	mg/L	J	be
10A-E01-T042-P1-AS	W	SSC	7	1	mg/L	J	be
10A-E01-T042-P1-BS	W	SSC	9	1	mg/L	J	be
10A-E02-T175-P1-AS	W	SSC	11	1	mg/L	J	be
10A-E02-T175-P2-AS	W	SSC	11	1	mg/L	J	be
10A-E02-T175-P2-BS	W	SSC	12	1	mg/L	J	be
10A-E02-T175-P3-AS	W	SSC	12	1	mg/L	J	be
10A-E02-T175-P4-AS	W	SSC	12	1	mg/L	J	be
10A-E01-T067-P3-AS	W	SSC	37	1	mg/L	J	be
10A-E01-T067-P3-BS	W	SSC	67	1	mg/L	J	be
10A-E01-T102-P1-AS	W	SSC	45	1	mg/L	J	be
10A-E01-T102-P1-BS	W	SSC	52	1	mg/L	J	be
10A-E01-T135-P3-AS	W	SSC	19	1	mg/L	J	be
10A-E01-T135-P3-BS	W	SSC	21	1	mg/L	J	be
10A-E01-T135-P3-BT	W	SSC	27	1	mg/L	J	be
10A-E03-T014-P1-AS	W	SSC	38	1	mg/L	J	be
10A-E03-T014-P2-AS	W	SSC	24	1	mg/L	J	be
10A-E03-T014-P2-BS	W	SSC	51	1	mg/L	J	be
10A-E03-T014-P3-AS	W	SSC	28	1	mg/L	J	be
10A-E03-T014-P3-BS	W	SSC	52	1	mg/L	J	be
10A-E03-T042-P1-AS	W	SSC	21	1	mg/L	J	be
10A-E03-T042-P1-BS	W	SSC	22	1	mg/L	J	be
10A-E03-T042-P2-AS	W	SSC	22	1	mg/L	J	be
10A-E03-T042-P2-BS	W	SSC	28	1	mg/L	J	be
10A-E01-T014-P3-AS	W	SSC	27	1	mg/L	J	be
10A-E01-T014-P3-BS	W	SSC	25	1	mg/L	J	be
10A-E01-T042-P1-AS	W	SSC	8	1	mg/L	J	be
10A-E01-T042-P1-BS	W	SSC	8	1	mg/L	J	be
10A-E02-T175-P1-AS	W	SSC	8	1	mg/L	J	be
10A-E02-T175-P2-AS	W	SSC	8	1	mg/L	J	be
10A-E02-T175-P2-BS	W	SSC	7	1	mg/L	J	be
10A-E02-T175-P3-AS	W	SSC	9	1	mg/L	J	be
10A-E03-T102-P1-AS	W	SSC	11	1	mg/L	J	be
10A-E03-T102-P1-AT	W	SSC	11	1	mg/L	J	be
10A-E03-T102-P1-BS	W	SSC	12	1	mg/L	J	be
10A-E03-T102-P2-AS	W	SSC	13	1	mg/L	J	be
10A-E03-T102-P2-BS	W	SSC	17	1	mg/L	J	be
10A-E03-T102-P3-AS	W	SSC	13	1	mg/L	J	be
10A-E03-T102-P3-BS	W	SSC	13	1	mg/L	J	be
10A-E04-T014-P1-AS	W	SSC	10	1	mg/L	J	be
10A-E04-T014-P1-BS	W	SSC	11	1	mg/L	J	be
10A-E04-T014-P2-AS	W	SSC	8	1	mg/L	J	be
10A-E04-T014-P2-BS	W	SSC	10	1	mg/L	J	be
10A-E04-T014-P3-AS	W	SSC	9	1	mg/L	J	be

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E04-T014-P3-BS	W	SSC	21	1	mg/L	J	be
10A-E04-T135-P1-AS	W	SSC	11	1	mg/L	J	be
10A-E04-T135-P1-BS	W	SSC	19	1	mg/L	J	be
10A-E04-T135-P2-AS	W	SSC	12	1	mg/L	J	be
10A-E04-T135-P2-BS	W	SSC	10	1	mg/L	J	be
10A-E04-T135-P3-AS	W	SSC	11	1	mg/L	J	be
10A-E04-T135-P3-BS	W	SSC	10	1	mg/L	J	be
10A-E04-T102-P1-AS	W	SSC	13	1	mg/L	J	be
10A-E04-T102-P1-AT	W	SSC	13	1	mg/L	J	be
10A-E04-T102-P1-BS	W	SSC	18	1	mg/L	J	be
10A-E04-T102-P2-AS	W	SSC	14	1	mg/L	J	be
10A-E04-T102-P2-BS	W	SSC	11	1	mg/L	J	be
10A-E04-T102-P2-BT	W	SSC	11	1	mg/L	J	be
10A-E04-T102-P3-AS	W	SSC	12	1	mg/L	J	be
10A-E04-T102-P3-BS	W	SSC	13	1	mg/L	J	be
10A-E03-T135-P1-AS	W	SSC	10	1	mg/L	J	be
10A-E03-T135-P1-BS	W	SSC	10	1	mg/L	J	be
10A-E03-T135-P2-AS	W	SSC	10	1	mg/L	J	be
10A-E03-T135-P2-BS	W	SSC	10	1	mg/L	J	be
10A-E03-T135-P3-AS	W	SSC	10	1	mg/L	J	be
10A-E03-T135-P3-BS	W	SSC	10	1	mg/L	J	be
10A-E03-T067-P1-AS	W	SSC	18	1	mg/L	J	be
10A-E03-T067-P1-BS	W	SSC	21	1	mg/L	J	be
10A-E03-T067-P2-AS	W	SSC	21	1	mg/L	J	be
10A-E03-T067-P2-BS	W	SSC	21	1	mg/L	J	be
10A-E03-T067-P3-AS	W	SSC	28	1	mg/L	J	be
10A-E03-T067-P3-BS	W	SSC	25	1	mg/L	J	be
10A-E04-T042-P1-AS	W	SSC	8	1	mg/L	J	be
10A-E04-T042-P1-BS	W	SSC	9	1	mg/L	J	be
10A-E04-T042-P2-AS	W	SSC	8	1	mg/L	J	be
10A-E04-T042-P2-BS	W	SSC	9	1	mg/L	J	be
10A-E04-T042-P3-AS	W	SSC	8	1	mg/L	J	be
10A-E04-T042-P3-BS	W	SSC	8	1	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E01-T014-P3XR (3/22/10)	SSC	7.0	1.0	7	1.0	10A-E01-T014-P3-AS
				22		10A-E01-T014-P3-BS
				7		10A-E01-T042-P1-AS
				9		10A-E01-T042-P1-BS
				11		10A-E02-T175-P1-AS
				11		10A-E02-T175-P2-AS
				12		10A-E02-T175-P2-BS
				12		10A-E02-T175-P3-AS
				12		10A-E02-T175-P4-AS
				37		10A-E01-T067-P3-AS
				67		10A-E01-T067-P3-BS
				45		10A-E01-T102-P1-AS
				52		10A-E01-T102-P1-BS
				19		10A-E01-T135-P3-AS
				21		10A-E01-T135-P3-BS
				27		10A-E01-T135-P3-BT
				38		10A-E03-T014-P1-AS
				24		10A-E03-T014-P2-AS
				51		10A-E03-T014-P2-BS
				28		10A-E03-T014-P3-AS
				52		10A-E03-T014-P3-BS
				21		10A-E03-T042-P1-AS
				22		10A-E03-T042-P1-BS
				22		10A-E03-T042-P2-AS
				28		10A-E03-T042-P2-BS
				27		10A-E01-T014-P3-AS
				25		10A-E01-T014-P3-BS
				8		10A-E01-T042-P1-AS
				8		10A-E01-T042-P1-BS
				8		10A-E02-T175-P1-AS
				8		10A-E02-T175-P2-AS
				7		10A-E02-T175-P2-BS
				9		10A-E02-T175-P3-AS
				11		10A-E03-T102-P1-AS
				11		10A-E03-T102-P1-AT
				12		10A-E03-T102-P1-BS
				13		10A-E03-T102-P2-AS
				17		10A-E03-T102-P2-BS
				13		10A-E03-T102-P3-AS

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E01-T014-P3XR (3/22/10)	SSC	7.0	1.0	13	1.0	10A-E03-T102-P3-BS
				10		10A-E04-T014-P1-AS
				11		10A-E04-T014-P1-BS
				8		10A-E04-T014-P2-AS
				10		10A-E04-T014-P2-BS
				9		10A-E04-T014-P3-AS
				21		10A-E04-T014-P3-BS
				11		10A-E04-T135-P1-AS
				19		10A-E04-T135-P1-BS
				12		10A-E04-T135-P2-AS
				10		10A-E04-T135-P2-BS
				11		10A-E04-T135-P3-AS
				10		10A-E04-T135-P3-BS
				13		10A-E04-T102-P1-AS
				13		10A-E04-T102-P1-AT
				18		10A-E04-T102-P1-BS
				14		10A-E04-T102-P2-AS
				11		10A-E04-T102-P2-BS
				11		10A-E04-T102-P2-BT
				12		10A-E04-T102-P3-AS
				13		10A-E04-T102-P3-BS
				10		10A-E03-T135-P1-AS
				10		10A-E03-T135-P1-BS
				10		10A-E03-T135-P2-AS
				10		10A-E03-T135-P2-BS
				10		10A-E03-T135-P3-AS
				10		10A-E03-T135-P3-BS
				18		10A-E03-T067-P1-AS
				21		10A-E03-T067-P1-BS
				21		10A-E03-T067-P2-AS
				21		10A-E03-T067-P2-BS
				28		10A-E03-T067-P3-AS
				25		10A-E03-T067-P3-BS
				8		10A-E04-T042-P1-AS
				9		10A-E04-T042-P1-BS
				8		10A-E04-T042-P2-AS
				9		10A-E04-T042-P2-BS
				8		10A-E04-T042-P3-AS
				8		10A-E04-T042-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Rev. 12

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection April Sampling Event, Newark Bay	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10050031, 10050033, 1005035, 10050036, and 10050037		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	6014462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed August 5, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: April NB PWCM DOC POC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on May 3, 2010.

SDG	Client Sample ID	Matrix
10050031	N01-E07-TARK-P1-AS	Aqueous
	N01-E07-TARK-P1-BS	Aqueous
	N01-E07-TARK-P3-AS	Aqueous
	N01-E07-TARK-P3-BS	Aqueous
	N01-E07-TNBN-P1-AS	Aqueous
	N01-E07-TNBN-P1-BS	Aqueous
	N01-E07-TNBN-P3-AS	Aqueous
	N01-E07-TNBN-P3-AT (Field duplicate of N01-E07-TNBN-P3-AS)	Aqueous
	N01-E07-TNBN-P3-BS	Aqueous
	N01-E07-TNBS-P1-AS	Aqueous
	N01-E07-TNBS-P1-BS	Aqueous
10050031	N01-E07-TNBS-P3-AS	Aqueous

SDG	Client Sample ID	Matrix
	N01-E07-TNBS-P3-BS	Aqueous
10050033	N01-E07-THKN-P1-AS	Aqueous
	N01-E07-THKN-P1-BS	Aqueous
	N01-E07-THKN-P3-AS	Aqueous
	N01-E07-THKN-P3-BS	Aqueous
	N01-E07-TKVK-P1-AS	Aqueous
	N01-E07-TKVK-P1-BS	Aqueous
	N01-E07-TKVK-P3-AS	Aqueous
	N01-E07-TKVK-P3-BS	Aqueous
10050035	N01-E08-TARK-P3-XR (Equipment blank collected 5/3/10)	Aqueous
	N01-E08-TKVK-P1-AS	Aqueous
	N01-E08-TKVK-P1-BS	Aqueous
	N01-E08-TKVK-P1-BT (Field duplicate of N01-E08-TKVK-P1-BS)	Aqueous
	N01-E08-TKVK-P3-AS	Aqueous
	N01-E08-TKVK-P3-BS	Aqueous
	N01-E08-TNBS-P1-AS	Aqueous
	N01-E08-TNBS-P1-BS	Aqueous
	N01-E08-TNBS-P3-AS	Aqueous
	N01-E08-TNBS-P3-BS	Aqueous
10050036	N01-E08-TARK-P1-AS	Aqueous
	N01-E08-TARK-P1-BS	Aqueous
	N01-E08-TARK-P3-AS	Aqueous
	N01-E08-TARK-P3-BS	Aqueous
	N01-E08-TNBN-P1-AS	Aqueous
	N01-E08-TNBN-P1-BS	Aqueous
	N01-E08-TNBN-P3-AS	Aqueous
	N01-E08-TNBN-P3-BS	Aqueous
10050037	N01-E08-THKN-P1-AS	Aqueous
	N01-E08-THKN-P1-BS	Aqueous
	N01-E08-THKN-P3-AS	Aqueous
	N01-E08-THKN-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness		Ö	
Holding times and sample preservation		Ö	
Calibrations		Ö	
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results		Ö	
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Data report 10050033 contained the POC results for data set SDG 10050031. The laboratory was contacted and the report resubmitted with the correct results included.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per

Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of CCB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

No contaminants were detected above the MDL in any of the CCBs associated with the samples in this data set, but were detected below the MDL as noted below:

Blank ID	Analyte	QL for Blank (mg/L)	Blank Concentration (mg/L)
GF/F Blank #5	POC	1.0	0.4
CaCO3 Blank #5			0.9

CCB nonconformances are summarized in Attachment A, Table A-3. Qualified sample results are shown in Table 1.

EBs were associated with all samples collected in the same week as the EB. EB N01-E08-TARK-P3-XR, collected on 5/3/2010 and reported in SDG 10050035 is associated with all samples collected 5/3/2010 through 5/9/2010. No POC or DOC contamination was noted in this EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E08-TKVK-P1-BS	W	DOC	2.1	0.30	mg/L	J	fd
N01-E08-TKVK-P1-BT	W	DOC	1.6	0.30	mg/L	J	fd
N01-E07-TARK-P1-AS	W	POC	2.0	1.0	mg/L	J	h
N01-E07-TARK-P1-BS	W	POC	1.2	1.0	mg/L	J	h
N01-E07-TARK-P3-AS	W	POC	1.3	1.0	mg/L	J	h
N01-E07-TARK-P3-BS	W	POC	1.4	1.0	mg/L	J	h
N01-E07-TNBN-P1-AS	W	POC	1.5	1.0	mg/L	J	h
N01-E07-TNBN-P1-BS	W	POC	2.6	1.0	mg/L	J	h
N01-E07-TNBN-P3-AS	W	POC	1.4	1.0	mg/L	J	h
N01-E07-TNBN-P3-AT	W	POC	1.3	1.0	mg/L	J	h
N01-E07-TNBN-P3-BS	W	POC	1.3	1.0	mg/L	J	h
N01-E07-TNBS-P1-AS	W	POC	1.5	1.0	mg/L	J	h
N01-E07-TNBS-P1-BS	W	POC	3.1	1.0	mg/L	J	h
N01-E07-TNBS-P3-AS	W	POC	1.2	1.0	mg/L	J	h
N01-E07-TNBS-P3-BS	W	POC	1.3	1.0	mg/L	J	h
N01-E07-THKN-P1-AS	W	POC	1.8	1.0	mg/L	J	h
N01-E07-THKN-P1-BS	W	POC	2.1	1.0	mg/L	J	h
N01-E07-THKN-P3-AS	W	POC	2.0	1.0	mg/L	J	h
N01-E07-THKN-P3-BS	W	POC	3.4	1.0	mg/L	J	h
N01-E07-TKVK-P1-AS	W	POC	2.0	1.0	mg/L	J	h
N01-E07-TKVK-P1-BS	W	POC	1.8	1.0	mg/L	J	h
N01-E07-TKVK-P3-AS	W	POC	1.4	1.0	mg/L	J	h
N01-E07-TKVK-P3-BS	W	POC	1.9	1.0	mg/L	J	h
N01-E08-TARK-P3-XR	W	POC		1.0	mg/L	UJ	h
N01-E08-TKVK-P1-AS	W	POC	1.7	1.0	mg/L	J	h,c
N01-E08-TKVK-P1-BS	W	POC	1.5	1.0	mg/L	J	h,c
N01-E08-TKVK-P1-BT	W	POC	1.4	1.0	mg/L	J	h,c
N01-E08-TKVK-P3-AS	W	POC	1.3	1.0	mg/L	J	h,c
N01-E08-TKVK-P3-BS	W	POC	1.6	1.0	mg/L	J	h
N01-E08-TNBS-P1-AS	W	POC	1.4	1.0	mg/L	J	h
N01-E08-TNBS-P1-BS	W	POC	1.5	1.0	mg/L	J	h
N01-E08-TNBS-P3-AS	W	POC	1.4	1.0	mg/L	J	h
N01-E08-TNBS-P3-BS	W	POC	1.5	1.0	mg/L	J	h
N01-E08-TARK-P1-AS	W	POC	1.5	1.0	mg/L	J	h,bl
N01-E08-TARK-P1-BS	W	POC	1.6	1.0	mg/L	J	h,bl
N01-E08-TARK-P3-AS	W	POC	1.6	1.0	mg/L	J	h,bl
N01-E08-TARK-P3-BS	W	POC	2.1	1.0	mg/L	J	h,bl
N01-E08-TNBN-P1-AS	W	POC	1.5	1.0	mg/L	J	h
N01-E08-TNBN-P1-BS	W	POC	1.5	1.0	mg/L	J	h
N01-E08-TNBN-P3-AS	W	POC	1.4	1.0	mg/L	J	h
N01-E08-TNBN-P3-BS	W	POC	1.4	1.0	mg/L	J	h
N01-E08-THKN-P1-AS	W	POC	1.8	1.0	mg/L	J	h

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E08-THKN-P1-BS	W	POC	1.6	1.0	mg/L	J	h
N01-E08-THKN-P3-AS	W	POC	2.3	1.0	mg/L	J	h
N01-E08-THKN-P3-BS	W	POC	1.6	1.0	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E07-TARK-P1-AS	POC	30-31	28
N01-E07-TARK-P1-BS			
N01-E07-TARK-P3-AS			
N01-E07-TARK-P3-BS			
N01-E07-TNBN-P1-AS			
N01-E07-TNBN-P1-BS			
N01-E07-TNBN-P3-AS			
N01-E07-TNBN-P3-AT			
N01-E07-TNBN-P3-BS			
N01-E07-TNBS-P1-AS			
N01-E07-TNBS-P1-BS			
N01-E07-TNBS-P3-AS			
N01-E07-TNBS-P3-BS			
N01-E07-THKN-P1-AS			
N01-E07-THKN-P1-BS			
N01-E07-THKN-P3-AS			
N01-E07-THKN-P3-BS			
N01-E07-TKVK-P1-AS			
N01-E07-TKVK-P1-BS			
N01-E07-TKVK-P3-AS			
N01-E07-TKVK-P3-BS			
N01-E08-TARK-P3-XR			
N01-E08-TKVK-P1-AS			
N01-E08-TKVK-P1-BS			
N01-E08-TKVK-P1-BT			
N01-E08-TKVK-P3-AS			
N01-E08-TKVK-P3-BS			
N01-E08-TNBS-P1-AS			
N01-E08-TNBS-P1-BS			
N01-E08-TNBS-P3-AS			
N01-E08-TNBS-P3-BS			
N01-E08-TARK-P1-AS			
N01-E08-TARK-P1-BS			
N01-E08-TARK-P3-AS			
N01-E08-TARK-P3-BS			
N01-E08-TNBN-P1-AS			
N01-E08-TNBN-P1-BS			
N01-E08-TNBN-P3-AS			
N01-E08-TNBN-P3-BS			
N01-E08-THKN-P1-AS			
N01-E08-THKN-P1-BS			
N01-E08-THKN-P3-AS			
N01-E08-THKN-P3-BS			

Table A-2 – Calibration Recovery

ICV/CCV	Analyte	Standard mg/L C	Result (mg/L C)	Recovery (%)	Affected Samples
CCV #9 (6/3/10)	POC	1.30	1.254	96	N01-E08-TKVK-P1-AS
					N01-E08-TKVK-P1-BS
					N01-E08-TKVK-P1-BT
					N01-E08-TKVK-P3-AS

Table A-3 – Calibration Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
GF/F Blank #5	POC	0.9	1.0	1.5	1.0	N01-E08-TARK-P1-AS
				1.6	1.0	N01-E08-TARK-P1-BS
CaCO3 Blank #5				1.6	1.0	N01-E08-TARK-P3-AS
				2.1	1.0	N01-E08-TARK-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay April Sampling Events	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10040597, 10050030, 10050048 (sample N01-E09-TNBS-P1-XR only), 10050075, 10050078, 10050080, 10050081, and 10050082		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited (All SDGs except 10050078) Full (10050078 only)		
AECOM Project Number	60144462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed June 23, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: May NB PWCM SSC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on April 28, 29, 30, and May 2, and 3, 2010.

SDG	Client Sample ID	Matrix
10040597	N01-E05-TARK-P1-AS	Aqueous
	N01-E05-TARK-P1-BS	Aqueous
	N01-E05-THKN-P1-AS	Aqueous
	N01-E05-THKN-P1-BS	Aqueous
	N01-E05-TNBN-P1-AS	Aqueous
	N01-E05-TNBN-P1-AT (Field duplicate of N01-E05-TNBN-P1-AS)	Aqueous
	N01-E05-TNBN-P1-BS	Aqueous
	N01-E09-TARK-P1-AS	Aqueous
	N01-E09-TARK-P1-AT (Field duplicate of N01-E09-TARK-P1-AS)	Aqueous
	N01-E09-TARK-P1-BS	Aqueous
	N01-E09-THKN-P1-AS	Aqueous
	N01-E09-THKN-P1-BS	Aqueous
10040597	N01-E09-TNBN-P1-AS	Aqueous

SDG	Client Sample ID	Matrix
	N01-E09-TNBN-P1-BS	Aqueous
10050030	N01-E05-TKVK-P1-AS	Aqueous
	N01-E05-TKVK-P1-BS	Aqueous
	N01-E05-TNBS-P1-AS	Aqueous
	N01-E05-TNBS-P1-BS	Aqueous
	N01-E09-TKVK-P1-AS	Aqueous
	N01-E09-TKVK-P1-BS	Aqueous
	N01-E09-TNBS-P1-AS	Aqueous
	N01-E09-TNBS-P1-BS	Aqueous
10050048	N01- E09-TNBS-P1-XR (Equipment blank 4/30/2010)	Aqueous
10050075	N01-E08-TKVK-P1-AS	Aqueous
	N01-E08-TKVK-P1-BS	Aqueous
	N01-E08-TKVK-P2-BS	Aqueous
	N01-E08-TKVK-P3-AS	Aqueous
	N01-E08-TKVK-P3-BS	Aqueous
	N01-E08-TNBN-P1-AS	Aqueous
	N01-E08-TNBN-P1-BS	Aqueous
	N01-E08-TNBS-P1-AS	Aqueous
	N01-E08-TNBS-P1-BS	Aqueous
	N01-E08-TNBS-P2-AS	Aqueous
	N01-E08-TNBS-P2-BS	Aqueous
	N01-E08-TNBS-P3-AS	Aqueous
	N01-E08-TNBS-P3-BS	Aqueous
10050078	N01-E07-THKN-P1-AS	Aqueous
	N01-E07-THKN-P1-BS	Aqueous
	N01-E07-THKN-P3-AS	Aqueous
	N01-E07-THKN-P3-BS	Aqueous
	N01-E07-TKVK-P2-AS	Aqueous
	N01-E07-TKVK-P2-BS	Aqueous
	N01-E07-TKVK-P3-AS	Aqueous
	N01-E08-THKN-P1-AS	Aqueous
	N01-E08-THKN-P1-BS	Aqueous
	N01-E08-THKN-P2-AS	Aqueous
	N01-E08-THKN-P2-BS	Aqueous
	N01-E08-THKN-P3-AS	Aqueous
	N01-E08-THKN-P3-BS	Aqueous
10050080	N01-E07-TARK-P1-AS	Aqueous
	N01-E07-TARK-P1-BS	Aqueous
10050080	N01-E07-TARK-P3-AS	Aqueous

SDG	Client Sample ID	Matrix
	N01-E07-TNBS-P1-AS	Aqueous
	N01-E08-TARK-P3-AS	Aqueous
	N01-E08-TARK-P3-XR (Equipment blank 5/3/2010)	Aqueous
	N01-E08-TNBN-P2-AS	Aqueous
	N01-E08-TNBN-P2-BS	Aqueous
10050081	N01-E07-TARK-P2-BS	Aqueous
	N01-E07-THKN-P2-AS	Aqueous
	N01-E07-THKN-P2-BS	Aqueous
	N01-E07-TKVK-P1-AS	Aqueous
	N01-E07-TKVK-P1-BS	Aqueous
	N01-E07-TKVK-P3-BS	Aqueous
	N01-E08-TARK-P1-AS	Aqueous
	N01-E08-TARK-P1-BS	Aqueous
	N01-E08-TARK-P2-AS	Aqueous
	N01-E08-TARK-P3-AT (Field duplicate of N01-E08-TARK-P3-AS)	Aqueous
	N01-E08-TARK-P3-BS	Aqueous
	N01-E08-TNBN-P3-AS	Aqueous
	N01-E08-TNBN-P3-BS	Aqueous
10050082	N01-E07-TARK-P2-AS	Aqueous
	N01-E07-TARK-P2-BS	Aqueous
	N01-E07-TARK-P3-BS	Aqueous
	N01-E07-TNBN-P1-AS	Aqueous
	N01-E07-TNBN-P1-BS	Aqueous
	N01-E07-TNBN-P1-BT (Field duplicate of N01-E07-TNBN-P1-BS)	Aqueous
	N01-E07-TNBN-P2-AS	Aqueous
	N01-E07-TNBN-P2-BS	Aqueous
	N01-E07-TNBN-P3-AS	Aqueous
	N01-E07-TNBN-P3-BS	Aqueous
	N01-E07-TNBS-P1-BS	Aqueous
	N01-E07-TNBS-P2-AS	Aqueous
	N01-E07-TNBS-P2-BS	Aqueous
	N01-E07-TNBS-P3-AS	Aqueous
	N01-E07-TNBS-P3-BS	Aqueous
	N01-E08-TKVK-P2-AS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity		Ö	
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results		Ö	
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody. The following discrepancy was noted:

- SDG 10050048: A discrepancy was noted between the COC and the laboratory report for sample N01-E09-TNBS-P1-XR. The COC listed this sample as **N01**-E09-TNBS-P1-XR while the laboratory reported this sample as **10A**-E09-TNBS-P1-XR. The field sampling team was contacted and it was determined that the correct sample ID should be **N01**-E09-TNBS-P1-XR as noted on the COC. No qualifications were necessary on this basis.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB N01-E09-TNBS-P1-XR, collected on 4/30/2010 and reported in SDG 10050048 is associated with all samples collected 4/28/2010 through 4/30/2010. EB N01-E08-TARK-P3-XR, collected on 5/3/2010 and reported in SDG 10050080 is associated with all samples collected 5/3/2010 through 5/9/2010. No SSC was detected above the MDL in the EBs associated with the samples in this data set. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC.

Data qualification on the basis of field duplicate RPDs was as follows (see above for acceptance criteria):

Criteria	Action	
	Detected	Nondetected
RPD greater than the acceptance criteria, but < 120% and sample and duplicate results >5x the SQL	J	Not Applicable
RPD ≥ 120%	R	Not Applicable
If sample and/or duplicate is <5x the QL and absolute difference is >2x and ≤ 4x the QL	J	UJ
If the sample and/or duplicate is <5x the QL and absolute difference is >4x the QL.	R	R

Field duplicate pair N01-E09-TARK-P1-AS / N01-E09-TARK-P1-AT (reported in SDG 10040597) exceeded (116 %) the RPD criteria. All remaining field duplicate pair RPDs met the RPD criteria.

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E09-TARK-P1-AS	W	SSC	30	1	mg/L	J	fd
N01-E09-TARK-P1-AT	W	SSC	8	1	mg/L	J	fd

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Field Duplicate

Sample ID	Duplicate ID	Compound	Sample Result	Duplicate Result	QL	Units	RPD (%)
N01-E09-TARK-P1-AS	N01-E09-TARK-P1-AT	SSC	30	8	1	mg/L	116

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Routine April Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10050029, 10050032, 10050034, 10050037, 10050039, and 10050063		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited (All except 10050029) Full (Only 10050029)		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed August 5, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: April Routine PWCM DOC POC 6 SDGs.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on May 3, 2010.

SDG	Client Sample ID	Matrix
10050029	10A-E08-T067-P1-AS	Aqueous
	10A-E08-T067-P1-BS	Aqueous
	10A-E08-T067-P3-AS	Aqueous
	10A-E08-T067-P3-BS	Aqueous
	10A-E08-T102-P1-AS	Aqueous
	10A-E08-T102-P1-BS	Aqueous
	10A-E08-T102-P3-AS	Aqueous
	10A-E08-T102-P3-AT (Field duplicate of 10A-E08-T102-P3-AS)	Aqueous
	10A-E08-T102-P3-BS	Aqueous
10050029	10A-E08-T135-P1-AS	Aqueous

SDG	Client Sample ID	Matrix
	10A-E08-T135-P1-BS	Aqueous
	10A-E08-T135-P3-AS	Aqueous
	10A-E08-T135-P3-AT (Field duplicate of 10A-E08-T135-P3-AS)	Aqueous
	10A-E08-T135-P3-BS	Aqueous
10050032	10A-E07-T067-P1-AS	Aqueous
	10A-E07-T067-P1-BS	Aqueous
	10A-E07-T067-P3-AS	Aqueous
	10A-E07-T067-P3-BS	Aqueous
	10A-E07-T067-P3-BT (Field duplicate of 10A-E07-T067-P3-BS)	Aqueous
10050034	10A-E07-T042-P1-AS	Aqueous
	10A-E07-T042-P1-BS	Aqueous
	10A-E07-T042-P3-AS	Aqueous
	10A-E07-T042-P3-BS	Aqueous
	10A-E07-T135-P1-AS	Aqueous
	10A-E07-T135-P1-BS	Aqueous
	10A-E07-T135-P3-AS	Aqueous
	10A-E07-T135-P3-BS	Aqueous
10050037	10A-E08-T014-P1-AS	Aqueous
	10A-E08-T014-P1-BS	Aqueous
	10A-E08-T014-P3-AS	Aqueous
	10A-E08-T014-P3-BS	Aqueous
	10A-E08-T042-P1-AS	Aqueous
	10A-E08-T042-P1-BS	Aqueous
	10A-E08-T042-P3-AS	Aqueous
	10A-E08-T042-P3-BS	Aqueous
	10A-E09-T042-P3-XR (Equipment blank collected 5/3/10)	Aqueous
10050039	10A-E07-T102-P1-AS	Aqueous
	10A-E07-T102-P1-BS	Aqueous
	10A-E07-T102-P3-AS	Aqueous
	10A-E07-T102-P3-BS	Aqueous
10050063	10A-E06-T175-P1-AS	Aqueous
	10A-E06-T175-P2-AS	Aqueous
	10A-E06-T175-P2-BS	Aqueous
	10A-E06-T175-P3-AS	Aqueous
	10A-E06-T175-P4-AS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness		Ö	
Holding times and sample preservation		Ö	
Calibrations		Ö	
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results		Ö	
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests. No discrepancies were noted except for the following:

- One extra sample result for POC that was not part of this data set was included in the POC results for SDG 10050032. The laboratory was contacted and a revised Form 1 submitted. No qualification actions were necessary.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of CCB/EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

No contaminants were detected above the MDL in any of the CCBs associated with the samples in this data set, but were detected below the MDL as noted below:

Blank ID	Analyte	QL for Blank (mg/L)	Blank Concentration (mg/L)
GF/F Blank #5	POC	1.0	0.4
CaCO3 Blank #5			0.9

CCB nonconformances are summarized in Attachment A, Table A-3. Qualified sample results are shown in Table 1.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E09-T042-P3-XR, collected on 5/3/2010 and reported in SDG 10050037 is associated with all samples collected 5/3/2010 through 5/9/2010. POC was detected in the EB < QL (0.9 mg/L). DOC was detected in the EB > QL (5.3 mg/L). Data qualification on the basis of EB contamination was as noted above.

EB nonconformances are summarized in Attachment A, Table A-4. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria. DOC MS 10050029-03B %R exceeded the criteria, but since these samples were already rejected for EB contamination, no qualifiers were applied on this basis.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E08-T102-P3-BS	W	DOC	5.1	0.30	mg/L	J	be
10A-E08-T102-P1-BS	W	DOC	5.1	0.30	mg/L	J	be
10A-E08-T102-P1-AS	W	DOC	5.0	0.30	mg/L	J	be
10A-E08-T102-P3-AT	W	DOC	5.4	0.30	mg/L	J	be
10A-E08-T067-P1-BS	W	DOC	5.3	0.30	mg/L	J	be
10A-E08-T067-P1-AS	W	DOC	5.0	0.30	mg/L	J	be
10A-E08-T067-P3-BS	W	DOC	5.1	0.30	mg/L	J	be
10A-E08-T067-P3-AS	W	DOC	5.0	0.30	mg/L	J	be
10A-E08-T135-P3-BS	W	DOC	4.9	0.30	mg/L	J	be
10A-E08-T135-P3-AS	W	DOC	5.0	0.30	mg/L	J	be
10A-E08-T135-P1-BS	W	DOC	5.0	0.30	mg/L	J	be
10A-E08-T135-P3-AT	W	DOC	5.0	0.30	mg/L	J	be
10A-E08-T135-P1-AS	W	DOC	5.1	0.30	mg/L	J	be
10A-E08-T102-P3-AS	W	DOC	4.7	0.30	mg/L	J	be
10A-E07-T067-P1-AS	W	DOC	4.1	0.30	mg/L	J	be
10A-E07-T067-P1-BS	W	DOC	4.2	0.30	mg/L	J	be
10A-E07-T067-P3-AS	W	DOC	4.2	0.30	mg/L	J	be
10A-E07-T067-P3-BS	W	DOC	4.3	0.30	mg/L	J	be
10A-E07-T067-P3-BT	W	DOC	4.1	0.30	mg/L	J	be
10A-E07-T042-P1-AS	W	DOC	5.1	0.30	mg/L	J	be
10A-E07-T042-P1-BS	W	DOC	5.4	0.30	mg/L	J	be
10A-E07-T042-P3-AS	W	DOC	5.1	0.30	mg/L	J	be
10A-E07-T042-P3-BS	W	DOC	11	0.30	mg/L	J	be
10A-E07-T135-P1-AS	W	DOC	4.9	0.30	mg/L	J	be
10A-E07-T135-P1-BS	W	DOC	4.9	0.30	mg/L	J	be
10A-E07-T135-P3-AS	W	DOC	4.9	0.30	mg/L	J	be
10A-E07-T135-P3-BS	W	DOC	5.1	0.30	mg/L	J	be
10A-E08-T014-P1-AS	W	DOC	4.9	0.30	mg/L	J	be
10A-E08-T014-P1-BS	W	DOC	8.1	0.30	mg/L	J	be
10A-E08-T014-P3-AS	W	DOC	4.8	0.30	mg/L	J	be
10A-E08-T014-P3-BS	W	DOC	8.2	0.30	mg/L	J	be
10A-E08-T042-P1-AS	W	DOC	4.7	0.30	mg/L	J	be
10A-E08-T042-P1-BS	W	DOC	4.7	0.30	mg/L	J	be
10A-E08-T042-P3-AS	W	DOC	4.6	0.30	mg/L	J	be
10A-E08-T042-P3-BS	W	DOC	4.8	0.30	mg/L	J	be
10A-E07-T102-P1-AS	W	DOC	4.6	0.30	mg/l	J	be
10A-E07-T102-P1-BS	W	DOC	4.8	0.30	mg/L	J	be
10A-E07-T102-P3-AS	W	DOC	4.6	0.30	mg/L	J	be
10A-E07-T102-P3-BS	W	DOC	4.7	0.30	mg/L	J	be
10A-E06-T175-P1-AS	W	DOC	6.4	0.30	mg/L	J	be
10A-E06-T175-P2-AS	W	DOC	6.0	0.30	mg/L	J	be
10A-E06-T175-P2-BS	W	DOC	6.0	0.30	mg/L	J	be
10A-E06-T175-P3-AS	W	DOC	5.6	0.30	mg/L	J	be

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E06-T175-P4-AS	W	DOC	5.9	0.30	mg/L	J	be
10A-E08-T102-P3-BS	W	POC	6.5	1.0	mg/L	J	h
10A-E08-T102-P1-BS	W	POC	3.2	1.0	mg/L	J	h
10A-E08-T102-P1-AS	W	POC	2.7	1.0	mg/L	J	h
10A-E08-T102-P3-AT	W	POC	4.8	1.0	mg/L	J	h
10A-E08-T067-P1-BS	W	POC	12	1.0	mg/L	J	h,c
10A-E08-T067-P1-AS	W	POC	5.5	1.0	mg/L	J	h,c
10A-E08-T067-P3-BS	W	POC	7.7	1.0	mg/L	J	h,c
10A-E08-T067-P3-AS	W	POC	3.7	1.0	mg/L	J	h,c
10A-E08-T135-P3-BS	W	POC	3.8	1.0	mg/L	J	h
10A-E08-T135-P3-AS	W	POC	2.4	1.0	mg/L	J	h
10A-E08-T135-P1-BS	W	POC	4.6	1.0	mg/L	J	h
10A-E08-T135-P3-AT	W	POC	3.0	1.0	mg/L	J	h
10A-E08-T135-P1-AS	W	POC	2.6	1.0	mg/L	J	h
10A-E08-T102-P3-AS	W	POC	4.4	1.0	mg/L	J	h,c
10A-E07-T067-P1-AS	W	POC	3.4	1.0	mg/L	J	h
10A-E07-T067-P1-BS	W	POC	3.9	1.0	mg/L	J	h
10A-E07-T067-P3-AS	W	POC	2.8	1.0	mg/L	J	h
10A-E07-T067-P3-BS	W	POC	3.6	1.0	mg/L	J	h
10A-E07-T067-P3-BT	W	POC	3.0	1.0	mg/L	J	h
10A-E07-T042-P1-AS	W	POC	2.2	1.0	mg/L	J	h
10A-E07-T042-P1-BS	W	POC	1.8	1.0	mg/L	J	h
10A-E07-T042-P3-AS	W	POC	2.1	1.0	mg/L	J	h
10A-E07-T042-P3-BS	W	POC	2.2	1.0	mg/L	J	h
10A-E07-T135-P1-AS	W	POC	4.8	1.0	mg/L	J	h
10A-E07-T135-P1-BS	W	POC	7.5	1.0	mg/L	J	h
10A-E07-T135-P3-AS	W	POC	5.0	1.0	mg/L	J	h
10A-E07-T135-P3-BS	W	POC	7.1	1.0	mg/L	J	h
10A-E08-T014-P1-AS	W	POC	2.2	1.0	mg/L	J	h,bl
10A-E08-T014-P1-BS	W	POC	2.3	1.0	mg/L	J	h,c
10A-E08-T014-P3-AS	W	POC	2.2	1.0	mg/L	J	h,bl
10A-E08-T014-P3-BS	W	POC	1.8	1.0	mg/L	J	h,bl
10A-E08-T042-P1-AS	W	POC	4.0	1.0	mg/L	J	h
10A-E08-T042-P1-BS	W	POC	4.2	1.0	mg/L	J	h
10A-E08-T042-P3-AS	W	POC	4.9	1.0	mg/L	J	h
10A-E08-T042-P3-BS	W	POC	5.4	1.0	mg/L	J	h
10A-E09-T042-P3-XR	W	POC		1.0	mg/L	UJ	h
10A-E07-T102-P1-AS	W	POC	3.9	1.0	mg/L	J	h
10A-E07-T102-P1-BS	W	POC	7.9	1.0	mg/L	J	h
10A-E07-T102-P3-AS	W	POC	3.1	1.0	mg/L	J	h
10A-E07-T102-P3-BS	W	POC	5.6	1.0	mg/L	J	h
10A-E06-T175-P1-AS	W	POC	2.3	1.0	mg/L	J	bl,h
10A-E06-T175-P2-AS	W	POC	2.1	1.0	mg/L	J	bl,h
10A-E06-T175-P2-BS	W	POC	2.9	1.0	mg/L	J	bl,h
10A-E06-T175-P3-AS	W	POC	2.6	1.0	mg/L	J	bl,h

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E06-T175-P4-AS	W	POC	2.4	1.0	mg/L	J	bl,h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E08-T102-P3-BS	POC	30-31	28
10A-E08-T102-P1-BS			
10A-E08-T102-P1-AS			
10A-E08-T102-P3-AT			
10A-E08-T067-P1-BS			
10A-E08-T067-P1-AS			
10A-E08-T067-P3-BS			
10A-E08-T067-P3-AS			
10A-E08-T135-P3-BS			
10A-E08-T135-P3-AS			
10A-E08-T135-P1-BS			
10A-E08-T135-P3-AT			
10A-E08-T135-P1-AS			
10A-E08-T102-P3-AS			
10A-E07-T067-P1-AS			
10A-E07-T067-P1-BS			
10A-E07-T067-P3-AS			
10A-E07-T067-P3-BS			
10A-E07-T067-P3-BT			
10A-E07-T042-P1-AS			
10A-E07-T042-P1-BS			
10A-E07-T042-P3-AS			
10A-E07-T042-P3-BS			
10A-E07-T135-P1-AS			
10A-E07-T135-P1-BS			
10A-E07-T135-P3-AS			
10A-E07-T135-P3-BS			
10A-E08-T014-P1-AS			
10A-E08-T014-P1-BS			
10A-E08-T014-P3-AS			
10A-E08-T014-P3-BS			
10A-E08-T042-P1-AS			
10A-E08-T042-P1-BS			
10A-E08-T042-P3-AS			
10A-E08-T042-P3-BS			
10A-E09-T042-P3-XR			
10A-E07-T102-P1-AS			
10A-E07-T102-P1-BS			
10A-E07-T102-P3-AS			
10A-E07-T102-P3-BS			
10A-E06-T175-P1-AS			
10A-E06-T175-P2-AS			

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E06-T175-P2-BS	POC	30-31	28
10A-E06-T175-P3-AS			
10A-E06-T175-P4-AS			

Table A-2 – Calibration Recovery

ICV/CCV	Analyte	Standard mg/L C	Result (mg/L C)	Recovery (%)	Affected Samples
CCV #9 (6/3/10)	POC	1.30	1.254	96	10A-E08-T067-P1-BS
					10A-E08-T067-P1-AS
					10A-E08-T067-P3-BS
					10A-E08-T067-P3-AS
					10A-E08-T102-P3-AS

Table A-3 – Calibration Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
CaCO3 Blank #5	POC	0.9	1.0	2.2	1.0	10A-E08-T014-P1-AS
				2.2	1.0	10A-E08-T014-P3-AS
				1.8	1.0	10A-E08-T014-P3-BS
				2.3	1.0	10A-E06-T175-P1-AS
				2.1	1.0	10A-E06-T175-P2-AS
				2.9	1.0	10A-E06-T175-P2-BS
				2.6	1.0	10A-E06-T175-P3-AS
				2.4	1.0	10A-E06-T175-P4-AS

Table A-4 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E09-T042-P3-XR	DOC	5.3	1.0	5.1	1.0	10A-E08-T102-P3-BS
				5.1	1.0	10A-E08-T102-P1-BS
				5.0	1.0	10A-E08-T102-P1-AS
				5.4	1.0	10A-E08-T102-P3-AT
				5.3	1.0	10A-E08-T067-P1-BS
				5.0	1.0	10A-E08-T067-P1-AS
				5.1	1.0	10A-E08-T067-P3-BS
				5.0	1.0	10A-E08-T067-P3-AS
				4.9	1.0	10A-E08-T135-P3-BS
				5.0	1.0	10A-E08-T135-P3-AS
				5.0	1.0	10A-E08-T135-P1-BS
				5.0	1.0	10A-E08-T135-P3-AT
				5.1	1.0	10A-E08-T135-P1-AS
				4.7	1.0	10A-E08-T102-P3-AS
				4.1	1.0	10A-E07-T067-P1-AS
				4.2	1.0	10A-E07-T067-P1-BS
				4.2	1.0	10A-E07-T067-P3-AS
				4.3	1.0	10A-E07-T067-P3-BS
				4.1	1.0	10A-E07-T067-P3-BT
				5.1	1.0	10A-E07-T042-P1-AS
				5.4	1.0	10A-E07-T042-P1-BS
				5.1	1.0	10A-E07-T042-P3-AS
				11	1.0	10A-E07-T042-P3-BS
				4.9	1.0	10A-E07-T135-P1-AS
				4.9	1.0	10A-E07-T135-P1-BS
				4.9	1.0	10A-E07-T135-P3-AS
				5.1	1.0	10A-E07-T135-P3-BS
				4.9	1.0	10A-E08-T014-P1-AS
				8.1	1.0	10A-E08-T014-P1-BS
				4.8	1.0	10A-E08-T014-P3-AS
				8.2	1.0	10A-E08-T014-P3-BS
				4.7	1.0	10A-E08-T042-P1-AS
				4.7	1.0	10A-E08-T042-P1-BS
				4.6	1.0	10A-E08-T042-P3-AS
				4.8	1.0	10A-E08-T042-P3-BS
				4.6	1.0	10A-E07-T102-P1-AS
				4.8	1.0	10A-E07-T102-P1-BS
				4.6	1.0	10A-E07-T102-P3-AS
				4.7	1.0	10A-E07-T102-P3-BS
				6.4	1.0	10A-E06-T175-P1-AS
				6.0	1.0	10A-E06-T175-P2-AS
				6.0	1.0	10A-E06-T175-P2-BS

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E09-T042-P3-XR	DOC	5.3	1.0	5.6	1.0	10A-E06-T175-P3-AS
				5.9	1.0	10A-E06-T175-P4-AS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection April Routine Sampling Events	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	A10050025, 10050048, A10050080, A10050083, A10050084, A10050085		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed June 29, 2010 Revised August 2, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: April Routine PWCM SSC 6 SDGs.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on May 1, 2, and 3, 2010.

SDG	Client Sample ID	Matrix
10050025	10A-E05-T067-P3-AS	Aqueous
	10A-E05-T067-P3-BS	Aqueous
	10A-E05-T102-P1-AS	Aqueous
	10A-E05-T102-P1-BS	Aqueous
	10A-E05-T135-P3-AS	Aqueous
	10A-E05-T135-P3-BS	Aqueous
	10A-E09-T067-P3-AS	Aqueous
	10A-E09-T067-P3-BS	Aqueous
	10A-E09-T067-P3-XR (Equipment blank 5/1/2010)	Aqueous
	10A-E09-T102-P1-AS	Aqueous
	10A-E09-T102-P1-BS	Aqueous
	10A-E09-T102-P1-BT (Field duplicate of 10A-E09-T102-P1-BS)	Aqueous
	10A-E09-T135-P3-AS	Aqueous
10050025	10A-E09-T135-P3-BS	Aqueous

SDG	Client Sample ID	Matrix
10050048	10A-E05-T014-P3-AS	Aqueous
	10A-E05-T014-P3-BS	Aqueous
	10A-E05-T042-P1-AS	Aqueous
	10A-E05-T042-P1-AT (Field duplicate of 10A-E05-T042-P1-AS)	Aqueous
	10A-E05-T042-P1-BS	Aqueous
	10A-E09-T014-P3-AS	Aqueous
	10A-E09-T014-P3-BS	Aqueous
	10A-E09-T042-P1-AS	Aqueous
	10A-E09-T042-P1-BS	Aqueous
10050080	10A-E07-T042-P1-BS	Aqueous
	10A-E07-T042-P3-BS	Aqueous
	10A-E07-T135-P1-BS	Aqueous
	10A-E07-T135-P3-AS	Aqueous
	10A-E07-T135-P3-AT (Field duplicate of 10A-E07-T135-P3-AS)	Aqueous
10050083	10A-E07-T042-P1-AS	Aqueous
	10A-E07-T042-P2-AS	Aqueous
	10A-E07-T042-P2-BS	Aqueous
	10A-E07-T042-P3-AS	Aqueous
	10A-E07-T135-P2-AS	Aqueous
	10A-E07-T135-P2-BS	Aqueous
	10A-E07-T135-P3-AS	Aqueous
	10A-E07-T135-P3-BS	Aqueous
	10A-E08-T067-P1-BS	Aqueous
	10A-E08-T067-P2-BS	Aqueous
	10A-E08-T102-P2-AS	Aqueous
	10A-E08-T102-P2-AT (Field duplicate of 10A-E08-T102-P2-AS)	Aqueous
	10A-E08-T102-P2-BS	Aqueous
10050084	10A-E08-T014-P1-AS	Aqueous
	10A-E08-T014-P1-BS	Aqueous
	10A-E08-T014-P2-AS	Aqueous
	10A-E08-T014-P2-BS	Aqueous
	10A-E08-T014-P3-AS	Aqueous
	10A-E08-T014-P3-BS	Aqueous
	10A-E08-T135-P1-AS	Aqueous
	10A-E08-T135-P1-BS	Aqueous
	10A-E08-T135-P2-AS	Aqueous
	10A-E08-T135-P2-BS	Aqueous
10050084	10A-E08-T135-P3-AS	Aqueous

SDG	Client Sample ID	Matrix
	10A-E08-T135-P3-BS	Aqueous
	10A-E09-T042-P3-XR (Equipment blank 5/3/2010)	Aqueous
10050085	10A-E08-T042-P1-AS	Aqueous
	10A-E08-T042-P1-BS	Aqueous
	10A-E08-T042-P2-AS	Aqueous
	10A-E08-T042-P2-BS	Aqueous
	10A-E08-T042-P3-AS	Aqueous
	10A-E08-T042-P3-BS	Aqueous
	10A-E08-T067-P1-AS	Aqueous
	10A-E08-T067-P3-AS	Aqueous
	10A-E08-T067-P3-BS	Aqueous
	10A-E08-T102-P1-AS	Aqueous
	10A-E08-T102-P1-BS	Aqueous
	10A-E08-T102-P3-AS	Aqueous
	10A-E08-T102-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity		Ö	
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations(Analytical balance for SSC)	Ö		

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results		Ö	
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody. The following discrepancies were noted:

- SDG 10050085: Samples 10A-E08-T042-P3-BS and 10A-E08-T102-P3-AS were reported as 10A-E08-T042-PS-BS and 10A-E08-T102-PS-AS. The sample IDs were corrected during data validation. No qualification action was necessary on this basis.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E09-T067-P3-XR, collected on 5/1/2010 and reported in SDG 10050025 is associated with all samples collected 4/26/2010 through 5/2/2010. EB 10A-E09-T042-P3-XR, collected on 5/3/2010 and reported in SDG 10050084 is associated with all samples collected 5/3/2010 through 5/9/2010. No SSC was detected above the MDL in EB 10A-E09-T067-P3-XR (associated with the 4/26/2010 through 5/2/2010 sample data set). Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

SSC was detected (12 mg/L) >quantitation limit (QL) in EB 10A-E09-T042-P3-XR. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC.

Data qualification on the basis of field duplicate RPDs was as follows (see above for acceptance criteria):

Criteria	Action	
	Detected	Nondetected
RPD greater than the acceptance criteria, but < 120% and sample and duplicate results >5x the SQL	J	Not Applicable
RPD ≥ 120%	R	Not Applicable
If sample and/or duplicate is <5x the QL and absolute difference is >2x and ≤ 4x the QL	J	UJ
If the sample and/or duplicate is <5x the QL and absolute difference is >4x the QL.	R	R

Field duplicate pair 10A-E05-T042-P1-AS / 10A-E05-T042-P1-AT (reported in SDG 10050048) exceeded (93 %) the RPD criteria. All remaining field duplicate pair RPDs met the RPD criteria.

Nonconformances are summarized in Attachment A, Table A-3. Qualified sample results are shown in Table 1.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E05-T042-P1-AS	W	SSC	22	1	mg/L	J	fd
10A-E05-T042-P1-AT	W	SSC	8	1	mg/L	J	fd
10A-E07-T042-P1-BS	W	SSC	9	1	mg/L	J	be
10A-E07-T042-P3-BS	W	SSC	8	1	mg/L	J	be
10A-E07-T042-P1-AS	W	SSC	9	1	mg/L	J	be
10A-E07-T042-P2-AS	W	SSC	9	1	mg/L	J	be
10A-E07-T042-P2-BS	W	SSC	8	1	mg/L	J	be
10A-E07-T042-P3-AS	W	SSC	8	1	mg/L	J	be
10A-E08-T014-P3-BS	W	SSC	10	1	mg/L	J	be
10A-E08-T014-P2-BS	W	SSC	11	1	mg/L	J	be
10A-E07-T135-P1-BS	W	SSC	61	1	mg/L	J	be
10A-E07-T135-P3-AS	W	SSC	27	1	mg/L	J	be
10A-E07-T135-P3-AT	W	SSC	24	1	mg/L	J	be
10A-E07-T135-P2-AS	W	SSC	29	1	mg/L	J	be
10A-E07-T135-P2-BS	W	SSC	80	1	mg/L	J	be
10A-E07-T135-P3-AS	W	SSC	30	1	mg/L	J	be
10A-E07-T135-P3-BS	W	SSC	51	1	mg/L	J	be
10A-E08-T067-P1-BS	W	SSC	73	1	mg/L	J	be
10A-E08-T102-P2-AS	W	SSC	16	1	mg/L	J	be
10A-E08-T102-P2-AT	W	SSC	16	1	mg/L	J	be
10A-E08-T102-P2-BS	W	SSC	15	1	mg/L	J	be
10A-E08-T135-P3-BS	W	SSC	16	1	mg/L	J	be
10A-E08-T014-P1-AS	W	SSC	14	1	mg/L	J	h,be
10A-E08-T014-P1-BS	W	SSC	19	1	mg/L	J	h,be
10A-E08-T014-P2-AS	W	SSC	13	1	mg/L	J	h,be
10A-E08-T014-P3-AS	W	SSC	12	1	mg/L	J	h,be
10A-E08-T135-P1-AS	W	SSC	15	1	mg/L	J	h,be
10A-E08-T135-P1-BS	W	SSC	29	1	mg/L	J	h,be
10A-E08-T135-P2-AS	W	SSC	57	1	mg/L	J	h,be
10A-E08-T135-P2-BS	W	SSC	20	1	mg/L	J	h,be
10A-E08-T135-P3-AS	W	SSC	14	1	mg/L	J	h,be
10A-E08-T042-P1-AS	W	SSC	31	1	mg/L	J	h,be
10A-E08-T042-P1-BS	W	SSC	29	1	mg/L	J	h,be
10A-E08-T042-P2-AS	W	SSC	40	1	mg/L	J	h,be
10A-E08-T042-P2-BS	W	SSC	34	1	mg/L	J	h,be
10A-E08-T042-P3-AS	W	SSC	39	1	mg/L	J	h,be
10A-E08-T042-P3-BS	W	SSC	46	1	mg/L	J	h,be
10A-E08-T067-P1-AS	W	SSC	28	1	mg/L	J	h,be
10A-E08-T067-P3-AS	W	SSC	31	1	mg/L	J	h,be
10A-E08-T067-P3-BS	W	SSC	33	1	mg/L	J	h,be
10A-E08-T102-P1-AS	W	SSC	15	1	mg/L	J	h,be

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E08-T102-P1-BS	W	SSC	18	1	mg/L	J	h,be
10A-E08-T102-P3-AS	W	SSC	26	1	mg/L	J	h,be
10A-E08-T102-P3-BS	W	SSC	15	1	mg/L	J	h,be
10A-E09-T042-P3-XR	W	SSC	12	1	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E08-T014-P1-AS	SSC	29	28
10A-E08-T014-P1-BS			
10A-E08-T014-P2-AS			
10A-E08-T014-P2-BS			
10A-E08-T014-P3-AS			
10A-E08-T014-P3-BS			
10A-E08-T135-P1-AS			
10A-E08-T135-P1-BS			
10A-E08-T135-P2-AS			
10A-E08-T135-P2-BS			
10A-E08-T135-P3-AS			
10A-E09-T042-P3-XR			
10A-E08-T042-P1-AS			
10A-E08-T042-P1-BS			
10A-E08-T042-P2-AS			
10A-E08-T042-P2-BS			
10A-E08-T042-P3-AS			
10A-E08-T042-P3-BS			
10A-E08-T067-P3-AS			
10A-E08-T067-P3-BS			
10A-E08-T067-P1-AS	SSC	30	
10A-E08-T102-P1-AS			
10A-E08-T102-P1-BS			
10A-E08-T102-P3-AS			
10A-E08-T102-P3-BS			

Table A-2 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E09-T042-P3-XR	SSC	12	1.0	9	1.0	10A-E07-T042-P1-BS
				8	1.0	10A-E07-T042-P3-BS
				9	1.0	10A-E07-T042-P1-AS
				9	1.0	10A-E07-T042-P2-AS
				8	1.0	10A-E07-T042-P2-BS
				8	1.0	10A-E07-T042-P3-AS
				10	1.0	10A-E08-T014-P3-BS
				11	1.0	10A-E08-T014-P2-BS
				61	1.0	10A-E07-T135-P1-BS
				27	1.0	10A-E07-T135-P3-AS
				24	1.0	10A-E07-T135-P3-AT
				29	1.0	10A-E07-T135-P2-AS

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E09-T042-P3-XR	SSC	12	1.0	80	1.0	10A-E07-T135-P2-BS
				30	1.0	10A-E07-T135-P3-AS
				51	1.0	10A-E07-T135-P3-BS
				73	1.0	10A-E08-T067-P1-BS
				16	1.0	10A-E08-T102-P2-AS
				16	1.0	10A-E08-T102-P2-AT
				15	1.0	10A-E08-T102-P2-BS
				16	1.0	10A-E08-T135-P3-BS
				14	1.0	10A-E08-T014-P1-AS
				19	1.0	10A-E08-T014-P1-BS
				13	1.0	10A-E08-T014-P2-AS
				12	1.0	10A-E08-T014-P3-AS
				15	1.0	10A-E08-T135-P1-AS
				29	1.0	10A-E08-T135-P1-BS
				57	1.0	10A-E08-T135-P2-AS
				20	1.0	10A-E08-T135-P2-BS
				14	1.0	10A-E08-T135-P3-AS
				31	1.0	10A-E08-T042-P1-AS
				29	1.0	10A-E08-T042-P1-BS
				40	1.0	10A-E08-T042-P2-AS
				34	1.0	10A-E08-T042-P2-BS
				39	1.0	10A-E08-T042-P3-AS
				46	1.0	10A-E08-T042-P3-BS
				28	1.0	10A-E08-T067-P1-AS
				31	1.0	10A-E08-T067-P3-AS
				33	1.0	10A-E08-T067-P3-BS
				15	1.0	10A-E08-T102-P1-AS
				18	1.0	10A-E08-T102-P1-BS
				26	1.0	10A-E08-T102-P3-AS
				15	1.0	10A-E08-T102-P3-BS

Table A-3 – Field Duplicate

Sample ID	Duplicate ID	Analyte	Sample Result	Duplicate Result	QL	Units	RPD
10A-E05-T042-P1-AS	10A-E05-T042-P1-AT	SSC	22	8	1.0	mg/L	93

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection April Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10050032, 10050039, and 10050063		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed August 2, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: April Routine PWMC SSC 3 SDGs.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on May 3, 2010.

SDG	Client Sample ID	Matrix
10050032	10A-E07-T067-P1-AS	Aqueous
	10A-E07-T067-P1-AT (Field duplicate of 10A-E07-T067-P1-AS)	Aqueous
	10A-E07-T067-P1-BS	Aqueous
	10A-E07-T067-P2-AS	Aqueous
	10A-E07-T067-P2-BS	Aqueous
	10A-E07-T067-P3-AS	Aqueous
	10A-E07-T067-P3-BS	Aqueous
10050039	10A-E07-T102-P1-AS	Aqueous
	10A-E07-T102-P1-BS	Aqueous
	10A-E07-T102-P2-AS	Aqueous
	10A-E07-T102-P2-BS	Aqueous
	10A-E07-T102-P3-AS	Aqueous
	10A-E07-T102-P3-BS	Aqueous

SDG	Client Sample ID	Matrix
10050063	10A-E05-T175-P2-AS	Aqueous
	10A-E05-T175-P2-BS	Aqueous
	10A-E06-T175-P1-AS	Aqueous
	10A-E06-T175-P2-AS	Aqueous
	10A-E06-T175-P2-BS	Aqueous
	10A-E06-T175-P3-AS	Aqueous
	10A-E06-T175-P4-AS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. No EB was collected during the week of 5/5/2010 through 5/9/2010. The next EB collected closest to the sampling period was EB 10A-E09-T042-P3-XR collected 5/3/10 and reported in SDG 10050084. This EB was associated with samples collected during the period 5/5/2010 through 5/9/2010. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

SSC was detected (1 mg/L) > quantitation limit (QL) in EB 10A-E09-T042-P3-XR. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E07-T067-P1-AS	W	SSC	26	1	mg/L	J	be
10A-E07-T067-P1-AT	W	SSC	27	1	mg/L	J	be
10A-E07-T067-P1-BS	W	SSC	27	1	mg/L	J	be
10A-E07-T067-P2-AS	W	SSC	27	1	mg/L	J	be
10A-E07-T067-P2-BS	W	SSC	26	1	mg/L	J	be
10A-E07-T067-P3-AS	W	SSC	24	1	mg/L	J	be
10A-E07-T067-P3-BS	W	SSC	26	1	mg/L	J	be
10A-E07-T102-P1-AS	W	SSC	40	1	mg/L	J	be
10A-E07-T102-P1-BS	W	SSC	60	1	mg/L	J	be
10A-E07-T102-P2-AS	W	SSC	27	1	mg/L	J	be
10A-E07-T102-P2-BS	W	SSC	30	1	mg/L	J	be
10A-E07-T102-P3-AS	W	SSC	31	1	mg/L	J	be
10A-E07-T102-P3-BS	W	SSC	39	1	mg/L	J	be
10A-E05-T175-P2-AS	W	SSC	9	1	mg/L	J	be
10A-E05-T175-P2-BS	W	SSC	12	1	mg/L	J	be
10A-E06-T175-P1-AS	W	SSC	7	1	mg/L	J	be
10A-E06-T175-P2-AS	W	SSC	8	1	mg/L	J	be
10A-E06-T175-P2-BS	W	SSC	18	1	mg/L	J	be
10A-E06-T175-P3-AS	W	SSC	11	1	mg/L	J	be
10A-E06-T175-P4-AS	W	SSC	13	1	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E09-T042-P3-XR	SSC	12	1.0	26	1.0	10A-E07-T067-P1-AS
				27	1.0	10A-E07-T067-P1-AT
				27	1.0	10A-E07-T067-P1-BS
				27	1.0	10A-E07-T067-P2-AS
				26	1.0	10A-E07-T067-P2-BS
				24	1.0	10A-E07-T067-P3-AS
				26	1.0	10A-E07-T067-P3-BS
				40	1.0	10A-E07-T102-P1-AS
				60	1.0	10A-E07-T102-P1-BS
				27	1.0	10A-E07-T102-P2-AS
				30	1.0	10A-E07-T102-P2-BS
				31	1.0	10A-E07-T102-P3-AS
				39	1.0	10A-E07-T102-P3-BS
				9	1.0	10A-E05-T175-P2-AS
				12	1.0	10A-E05-T175-P2-BS
				7	1.0	10A-E06-T175-P1-AS
				8	1.0	10A-E06-T175-P2-AS
				18	1.0	10A-E06-T175-P2-BS
				11	1.0	10A-E06-T175-P3-AS
				13	1.0	10A-E06-T175-P4-AS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Routine April Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10050038		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed August 2, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: April Routine PWCM DOC POC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on May 3, 2010.

SDG	Client Sample ID	Matrix
10050038	10A-E07-T014-P1-AS	Aqueous
	10A-E07-T014-P1-BS	Aqueous
	10A-E07-T014-P3-AS	Aqueous
	10A-E07-T014-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E09-T042-P3-XR, collected on 5/3/2010 and reported in SDG 10050037 is associated with all samples collected 5/3/2010 through 5/9/2010.

Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

DOC was detected > QL (5.3 mg/L) in the EB. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

POC was detected <QL (0.9 mg/L) in the EB. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria. DOC MS 10050029-03B %R exceeded the criteria, but since these samples were already rejected for EB contamination, no qualifiers were applied on this basis.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E07-T014-P1-AS	W	DOC	4.7	0.30	mg/L	J	be
10A-E07-T014-P1-BS	W	DOC	0.58	0.30	mg/L	J	be
10A-E07-T014-P3-AS	W	DOC	4.7	0.30	mg/L	J	be
10A-E07-T014-P3-BS	W	DOC	3.5	1.5	mg/L	J	be
10A-E07-T014-P1-AS	W	POC	2.1	1.0	mg/L	J	h,be
10A-E07-T014-P1-BS	W	POC	2.5	1.0	mg/L	J	h,be
10A-E07-T014-P3-AS	W	POC	2.1	1.0	mg/L	J	h,be
10A-E07-T014-P3-BS	W	POC	1.7	1.0	mg/L	J	h,be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E07-T014-P1-AS	POC	31	28
10A-E07-T014-P1-BS			
10A-E07-T014-P3-AS			
10A-E07-T014-P3-BS			

Table A-2 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E09-T042-P3-XR	DOC	5.3	1.5	4.7	0.30	10A-E07-T014-P1-AS
				0.58	0.30	10A-E07-T014-P1-BS
				4.7	0.30	10A-E07-T014-P3-AS
				3.5	1.5	10A-E07-T014-P3-BS
10A-E09-T042-P3-XR	POC	0.9	1.0	2.1	1.0	10A-E07-T014-P1-AS
				2.5	1.0	10A-E07-T014-P1-BS
				2.1	1.0	10A-E07-T014-P3-AS
				1.7	1.0	10A-E07-T014-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection, April Routine Sampling Events	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10050038		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed August 2, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: April Routine PWCM SSC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay New Jersey on May 3, 2010.

SDG	Client Sample ID	Matrix
10050038	10A-E07-T014-P1-AS	Aqueous
	10A-E07-T014-P1-BS	Aqueous
	10A-E07-T014-P2-AS	Aqueous
	10A-E07-T014-P2-BS	Aqueous
	10A-E07-T014-P3-AS	Aqueous
	10A-E07-T014-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were

used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	**No**	**NA**
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

<u>Data Completeness</u>

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

<u>Holding Times/Sample Preservation</u>

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

<u>Calibrations</u>

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E09-T042-P3-XR, collected on 5/3/2010 and reported in SDG 10050084 is associated with all samples collected 5/3/2010 through 5/9/2010. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

SSC was detected (12 mg/L) >quantitation limit (QL) in EB 10A-E09-T042-P3-XR. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E07-T014-P1-AS	W	SSC	23	1	mg/L	J	be
10A-E07-T014-P1-BS	W	SSC	13	1	mg/L	J	be
10A-E07-T014-P2-AS	W	SSC	15	1	mg/L	J	be
10A-E07-T014-P2-BS	W	SSC	30	1	mg/L	J	be
10A-E07-T014-P3-AS	W	SSC	15	1	mg/L	J	be
10A-E07-T014-P3-BS	W	SSC	17	1	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E09-T042-P3-XR (5/3/10)	SSC	12	1	23	1	10A-E07-T014-P1-AS
				13	1	10A-E07-T014-P1-BS
				15	1	10A-E07-T014-P2-AS
				30	1	10A-E07-T014-P2-BS
				15	1	10A-E07-T014-P3-AS
				17	1	10A-E07-T014-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection May Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10050436		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 7, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10050436 May Routine DOC POC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on May 24, 2010.

SDG	Client Sample ID	Matrix
10050436	10A-E12-T014-P1-AS	Aqueous
	10A-E12-T014-P1-BS	Aqueous
	10A-E12-T014-P3-AS	Aqueous
	10A-E12-T014-P3-AT (Field duplicate of 10A-E12-T014-P3-AS)	Aqueous
	10A-E12-T014-P3-BS	Aqueous
	10A-E12-T042-P1-AS	Aqueous
	10A-E12-T042-P1-BS	Aqueous
	10A-E12-T042-P3-AS	Aqueous
	10A-E12-T042-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations		Ö	
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Several CaCO3 blanks had positive results greater than the RL. The laboratory determined that the CaCO3 was not spread evenly during blank prep therefore, CaCO3 was left behind on the filter and was detected greater than the RL. In addition, this blank was not part of Method 440.0 and its applicability to our samples has not been established. These blanks were not factored into the data quality assessment since they were not considered representative of the sample analyses.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E13-T042-P3-XR, collected on 5/24/2010 and reported in SDG 10050421 is associated with all samples collected 5/24/2010 through 5/30/2010.

Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

DOC was detected > QL (0.65 mg/L) in the EB. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E12-T014-P1-AS	W	DOC	3.4	1.5	mg/L	J	be
10A-E12-T014-P1-BS	W	DOC	2.4	1.5	mg/L	J	be
10A-E12-T014-P3-AS	W	DOC	3.1	1.5	mg/L	J	be
10A-E12-T014-P3-AT	W	DOC	3.2	1.5	mg/L	J	be
10A-E12-T014-P3-BS	W	DOC	2.8	1.5	mg/L	J	be
10A-E12-T042-P1-AS	W	DOC	3.4	1.5	mg/L	J	be
10A-E12-T042-P1-BS	W	DOC	3.3	1.5	mg/L	J	be
10A-E12-T042-P3-AS	W	DOC	3.6	1.5	mg/L	J	be
10A-E12-T042-P3-BS	W	DOC	3.6	1.5	mg/L	J	be
10A-E12-T014-P1-AS	W	POC	2.2	1.0	mg/L	J	c
10A-E12-T014-P1-BS	W	POC	2.6	1.0	mg/L	J	c
10A-E12-T014-P3-AS	W	POC	2.2	1.0	mg/L	J	c
10A-E12-T014-P3-AT	W	POC	2.0	1.0	mg/L	J	c
10A-E12-T014-P3-BS	W	POC	2.0	1.0	mg/L	J	c
10A-E12-T042-P1-AS	W	POC	3.1	1.0	mg/L	J	c
10A-E12-T042-P1-BS	W	POC	3.8	1.0	mg/L	J	c
10A-E12-T042-P3-AS	W	POC	3.0	1.0	mg/L	J	c
10A-E12-T042-P3-BS	W	POC	4.8	1.0	mg/L	J	c

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Calibration Recovery

ICV/CCV	Analyte	Standard mg/L C	Result (mg/L C)	Recovery (%)
CCV 4	POC	1.30	1.371	105
CCV 5			1.366	105
CCV 6			1.196	92
CCV 8			1.225	94
CCV 11			1.235	95
CCV 12			1.212	93
Affected Samples:	All samples in this SDG			

Table A-2 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E13-T042-P3-XR (5/24/10)	DOC	0.65	1.5	3.4	1.5	10A-E12-T014-P1-AS
				2.4	1.5	10A-E12-T014-P1-BS
				3.1	1.5	10A-E12-T014-P3-AS
				3.2	1.5	10A-E12-T014-P3-AT
				2.8	1.5	10A-E12-T014-P3-BS
				3.4	1.5	10A-E12-T042-P1-AS
				3.3	1.5	10A-E12-T042-P1-BS
				3.6	1.5	10A-E12-T042-P3-AS
				3.6	1.5	10A-E12-T042-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection May Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10050463		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 7, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10050463 May Routine DOC POC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on May 25, 2010.

SDG	Client Sample ID	Matrix
10050463	10A-E11-T175-P3-AS	Aqueous
	10A-E11-T175-P3-AS	Aqueous
	10A-E11-T175-P1-AS	Aqueous
	10A-E11-T175-P1-AS	Aqueous
	10A-E11-T175-P4-AS	Aqueous
	10A-E11-T175-P4-AS	Aqueous
	10A-E11-T175-P2-BS	Aqueous
	10A-E11-T175-P2-BS	Aqueous
	10A-E11-T175-P2-AS	Aqueous
	10A-E11-T175-P2-AS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Several CaCO3 blanks had positive results greater than the RL. The laboratory determined that the CaCO3 was not spread evenly during blank prep therefore, CaCO3 was left behind on the filter and was detected greater than the RL. In addition, this blank was not part of Method 440.0 and its applicability to our samples has not been established. These blanks were not factored into the data quality assessment since they were not considered representative of the sample analyses.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E13-T042-P3-XR, collected on 5/24/2010 and reported in SDG 10050421 is associated with all samples collected 5/24/2010 through 5/30/2010.

Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

DOC was detected > QL (0.65 mg/L) in the EB. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E11-T175-P3-AS	W	DOC	4.0	1.5	mg/L	J	be
10A-E11-T175-P1-AS	W	DOC	4.0	1.5	mg/L	J	be
10A-E11-T175-P4-AS	W	DOC	4.0	1.5	mg/L	J	be
10A-E11-T175-P2-BS	W	DOC	4.0	1.5	mg/L	J	be
10A-E11-T175-P2-AS	W	DOC	4.1	1.5	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E13-T042-P3-XR (5/24/10)	DOC	0.65	1.5	4.0	1.5	10A-E11-T175-P3-AS
				4.0	1.5	10A-E11-T175-P1-AS
				4.0	1.5	10A-E11-T175-P4-AS
				4.0	1.5	10A-E11-T175-P2-BS
				4.1	1.5	10A-E11-T175-P2-AS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection May Routine Sampling Events	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10050463		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 7, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10050463 May Routine SSC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on May 25, 2010.

SDG	Client Sample ID	Matrix
10050463	10A-E10-T175-P2-AS	Aqueous
	10A-E10-T175-P2-BS	Aqueous
	10A-E11-T175-P1-AS	Aqueous
	10A-E11-T175-P2-AS	Aqueous
	10A-E11-T175-P2-BS	Aqueous
	10A-E11-T175-P3-AS	Aqueous
	10A-E11-T175-P4-AS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E13-T042-P3-XR, collected on 5/24/2010 and reported in SDG 10050421 is associated with all samples collected 5/24/2010 through 5/30/2010. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

SSC was detected (5 mg/L) >quantitation limit (QL) in EB 10A-E13-T042-P3-XR. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E10-T175-P2-AS	W	SSC	4	1	mg/L	J	be
10A-E10-T175-P2-BS	W	SSC	4	1	mg/L	J	be
10A-E11-T175-P1-AS	W	SSC	5	1	mg/L	J	be
10A-E11-T175-P2-AS	W	SSC	4	1	mg/L	J	be
10A-E11-T175-P2-BS	W	SSC	4	1	mg/L	J	be
10A-E11-T175-P3-AS	W	SSC	4	1	mg/L	J	be
10A-E11-T175-P4-AS	W	SSC	13	1	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E13-T042-P3-XR (5/24/10)	SSC	5	1	4	1	10A-E10-T175-P2-AS
				4	1	10A-E10-T175-P2-BS
				5	1	10A-E11-T175-P1-AS
				4	1	10A-E11-T175-P2-AS
				4	1	10A-E11-T175-P2-BS
				4	1	10A-E11-T175-P3-AS
				13	1	10A-E11-T175-P4-AS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection, May Routine Sampling Events	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10050468 and 10050470		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited (All except 10050470) Full (100500470 only)		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed August 2, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: LPR PWCM LP749-750 May Routine SSC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay New Jersey on May 24.

SDG	Client Sample ID	Matrix
10050468	10A-E13-T067-P1-AS	Aqueous
	10A-E13-T067-P1-BS	Aqueous
	10A-E13-T067-P2-AS	Aqueous
	10A-E13-T067-P2-BS	Aqueous
	10A-E13-T067-P3-AS	Aqueous
	10A-E13-T067-P3-BS	Aqueous
	10A-E13-T102-P1-AS	Aqueous
	10A-E13-T135-P1-AS	Aqueous
	10A-E13-T135-P1-BS	Aqueous
	10A-E13-T135-P2-AS	Aqueous
	10A-E13-T135-P2-BS	Aqueous
	10A-E13-T135-P3-AS	Aqueous
10050468	10A-E13-T135-P3-BS	Aqueous

SDG	Client Sample ID	Matrix
10050470	10A-E12-T067-P1-AS	Aqueous
	10A-E12-T067-P1-BS	Aqueous
	10A-E12-T067-P2-AS	Aqueous
	10A-E12-T067-P2-BS	Aqueous
	10A-E12-T067-P2-BT (Field duplicate of 10A-E12-T067-P2-BS)	Aqueous
	10A-E12-T067-P3-AS	Aqueous
	10A-E12-T067-P3-BS	Aqueous
	10A-E12-T102-P1-AS	Aqueous
	10A-E12-T102-P1-BS	Aqueous
	10A-E12-T102-P2-AS	Aqueous
	10A-E12-T102-P2-BS	Aqueous
	10A-E12-T102-P3-AS	Aqueous
	10A-E12-T102-P3-BS	Aqueous
	10A-E12-T135-P1-AS	Aqueous
	10A-E12-T135-P1-BS	Aqueous
	10A-E12-T135-P2-AS	Aqueous
	10A-E12-T135-P2-BS	Aqueous
	10A-E12-T135-P3-AS	Aqueous
	10A-E12-T135-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results		Ö	
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Selected samples were stored in a refrigerator which malfunctioned prior to sample shipment to the laboratory. Upon discovery of the malfunction, the temperature was 18°C. All affected samples were qualified as estimated (J). Nonconformances are summarized in Attachment A, Table A-2.

Qualified sample results are shown in Table 1.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E09-T042-P3-XR, collected on 5/3/2010 and reported in SDG 10050084 is associated with all samples collected 5/3/2010 through 5/9/2010. No EB was collected during the period 5/24/10 through 5/30/10. EB 10A-E14-T042-P1-XR, collected on 5/20/2010 and reported in SDG 10050386 was applied to the samples collected during the period 5/24/10 through 5/30/10. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

SSC was detected (12 mg/L) >quantitation limit (QL) in EB 10A-E09-T042-P3-XR. Nonconformances are summarized in Attachment A, Table A-3a. Qualified sample results are shown in Table 1.

SSC was detected (13 mg/L) >quantitation limit (QL) in EB 10A-E14-T042-P1-XR. Nonconformances are summarized in Attachment A, Table A-3b. Qualified sample results are shown in Table 1.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC. Data qualification on the basis of field duplicate RPDs was as follows (see above for acceptance criteria):

Criteria	Action	
	Detected	Nondetected
RPD greater than the acceptance criteria, but < 120% and sample and duplicate results >5x the SQL	J	Not Applicable
RPD ≥ 120%	R	Not Applicable
If sample and/or duplicate is <5x the QL and absolute difference is >2x and ≤ 4x the QL	J	UJ
If the sample and/or duplicate is <5x the QL and absolute difference is >4x the QL.	R	R

Qualified sample results are shown in Table 1. Nonconformances are summarized in Attachment A, Table A-4. Qualified sample results are shown in Table 1.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E13-T067-P1-AS	W	SSC	90	1	mg/L	J	h,t,be
10A-E13-T067-P1-BS	W	SSC	118	1	mg/L	J	h,t,be
10A-E13-T067-P2-AS	W	SSC	104	1	mg/L	J	h,t,be
10A-E13-T067-P2-BS	W	SSC	107	1	mg/L	J	h,t,be
10A-E13-T067-P3-AS	W	SSC	44	1	mg/L	J	h,t,be
10A-E13-T067-P3-BS	W	SSC	180	1	mg/L	J	h,t,be
10A-E13-T102-P1-AS	W	SSC	8	1	mg/L	J	h,t,be
10A-E13-T135-P1-AS	W	SSC	5	1	mg/L	J	h,t,be
10A-E13-T135-P1-BS	W	SSC	7	1	mg/L	J	h,t,be
10A-E13-T135-P2-AS	W	SSC	7	1	mg/L	J	h,t,be
10A-E13-T135-P2-BS	W	SSC	7	1	mg/L	J	h,t,be
10A-E13-T135-P3-AS	W	SSC	6	1	mg/L	J	h,t,be
10A-E13-T135-P3-BS	W	SSC	8	1	mg/L	J	h,t,be
10A-E12-T067-P1-AS	W	SSC	46	1	mg/L	J	h,t,be
10A-E12-T067-P1-BS	W	SSC	132	1	mg/L	J	h,t,be
10A-E12-T067-P2-AS	W	SSC	67	1	mg/L	J	h,t,be
10A-E12-T067-P2-BS	W	SSC	113	1	mg/L	J	h,t,fd,be
10A-E12-T067-P2-BT	W	SSC	65	1	mg/L	J	h,t,fd,be
10A-E12-T067-P3-AS	W	SSC	70	1	mg/L	J	h,t,be
10A-E12-T067-P3-BS	W	SSC	52	1	mg/L	J	h,t,be
10A-E12-T102-P1-AS	W	SSC	8	1	mg/L	J	h,t,be
10A-E12-T102-P1-BS	W	SSC	11	1	mg/L	J	h,t,be
10A-E12-T102-P2-AS	W	SSC	10	1	mg/L	J	h,t,be
10A-E12-T102-P2-BS	W	SSC	10	1	mg/L	J	h,t,be
10A-E12-T102-P3-AS	W	SSC	12	1	mg/L	J	h,t,be
10A-E12-T102-P3-BS	W	SSC	16	1	mg/L	J	h,t,be
10A-E12-T135-P1-AS	W	SSC	5	1	mg/L	J	h,t,be
10A-E12-T135-P1-BS	W	SSC	8	1	mg/L	J	h,t,be
10A-E12-T135-P2-AS	W	SSC	5	1	mg/L	J	h,t,be
10A-E12-T135-P2-BS	W	SSC	6	1	mg/L	J	h,t,be
10A-E12-T135-P3-AS	W	SSC	7	1	mg/L	J	h,t,be
10A-E12-T135-P3-BS	W	SSC	9	1	mg/L	J	h,t,be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E13-T067-P1-AS	SSC	37-44	28
10A-E13-T067-P1-BS			
10A-E13-T067-P2-AS			
10A-E13-T067-P2-BS			
10A-E13-T067-P3-AS			
10A-E13-T067-P3-BS			
10A-E13-T102-P1-AS			
10A-E13-T135-P1-AS			
10A-E13-T135-P1-BS			
10A-E13-T135-P2-AS			
10A-E13-T135-P2-BS			
10A-E13-T135-P3-AS			
10A-E13-T135-P3-BS			
10A-E12-T067-P1-AS			
10A-E12-T067-P1-BS			
10A-E12-T067-P2-AS			
10A-E12-T067-P2-BS			
10A-E12-T067-P2-BT			
10A-E12-T067-P3-AS			
10A-E12-T067-P3-BS			
10A-E12-T102-P1-AS			
10A-E12-T102-P1-BS			
10A-E12-T102-P2-AS			
10A-E12-T102-P2-BS			
10A-E12-T102-P3-AS			
10A-E12-T102-P3-BS			
10A-E12-T135-P1-AS			
10A-E12-T135-P1-BS			
10A-E12-T135-P2-AS			
10A-E12-T135-P2-BS			
10A-E12-T135-P3-AS			
10A-E12-T135-P3-BS			

Table A-2 – Temperature Preservation

Sample ID	Analyte	Nonconforming Temperature (°C)	TemperatureCriteria (°C)
10A-E13-T067-P1-AS	SSC	18	0-6
10A-E13-T067-P1-BS			
10A-E13-T067-P2-AS			
10A-E13-T067-P2-BS			
10A-E13-T067-P3-AS			
10A-E13-T067-P3-BS			
10A-E13-T102-P1-AS			
10A-E13-T135-P1-AS			
10A-E13-T135-P1-BS			
10A-E13-T135-P2-AS			
10A-E13-T135-P2-BS			
10A-E13-T135-P3-AS			
10A-E13-T135-P3-BS			
10A-E12-T067-P1-AS			
10A-E12-T067-P1-BS			
10A-E12-T067-P2-AS			
10A-E12-T067-P2-BS			
10A-E12-T067-P2-BT			
10A-E12-T067-P3-AS			
10A-E12-T067-P3-BS			
10A-E12-T102-P1-AS			
10A-E12-T102-P1-BS			
10A-E12-T102-P2-AS			
10A-E12-T102-P2-BS			
10A-E12-T102-P3-AS			
10A-E12-T102-P3-BS			
10A-E12-T135-P1-AS			
10A-E12-T135-P1-BS			
10A-E12-T135-P2-AS			
10A-E12-T135-P2-BS			
10A-E12-T135-P3-AS			
10A-E12-T135-P3-BS			

Table A-3a – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E09-T042-P3-XR (5/3/10)	SSC	12	1	23	1	10A-E07-T014-P1-AS
				13	1	10A-E07-T014-P1-BS
				15	1	10A-E07-T014-P2-AS
				30	1	10A-E07-T014-P2-BS
				15	1	10A-E07-T014-P3-AS
				17	1	10A-E07-T014-P3-BS

Table A-3b – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E14-T042-P1-XR (5/20/10)	SSC	13	1	90	1	10A-E13-T067-P1-AS
				118		10A-E13-T067-P1-BS
				104		10A-E13-T067-P2-AS
				107		10A-E13-T067-P2-BS
				44		10A-E13-T067-P3-AS
				180		10A-E13-T067-P3-BS
				8		10A-E13-T102-P1-AS
				5		10A-E13-T135-P1-AS
				7		10A-E13-T135-P1-BS
				7		10A-E13-T135-P2-AS
				7		10A-E13-T135-P2-BS
				6		10A-E13-T135-P3-AS
				8		10A-E13-T135-P3-BS
				46		10A-E12-T067-P1-AS
				132		10A-E12-T067-P1-BS
				67		10A-E12-T067-P2-AS
				113		10A-E12-T067-P2-BS
				65		10A-E12-T067-P2-BT
				70		10A-E12-T067-P3-AS
				52		10A-E12-T067-P3-BS
				8		10A-E12-T102-P1-AS
				11		10A-E12-T102-P1-BS
				10		10A-E12-T102-P2-AS
				10		10A-E12-T102-P2-BS
				12		10A-E12-T102-P3-AS
				16		10A-E12-T102-P3-BS
				5		10A-E12-T135-P1-AS
				8		10A-E12-T135-P1-BS
				5		10A-E12-T135-P2-AS
				6		10A-E12-T135-P2-BS
				7		10A-E12-T135-P3-AS
				9		10A-E12-T135-P3-BS

Table A-4 – Field Duplicate RPDs

Sample ID	Duplicate ID	Analyte	Sample Result	Duplicate Result	QL	Units	RPD
10A-E12-T067-P2-BS	10A-E12-T067-P2-BS	SSC	113	65	1	mg/L	54
10A-E19-T042-P1-AS	10A-E19-T042-P1-AS	SSC	37	21	1	mg/L	55

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay May Sampling Events	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10050427 and 10050431		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60144462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed August 20, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: May NB 10050427 & 431 SSC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on May 24 and 25, 2010.

SDG	Client Sample ID	Matrix
10050427	N01-E13-TARK-P3-XR (Equipment blank collected 5/24/10)	Aqueous
10050431	N01-E12-THKN-P1-AS	Aqueous
	N01-E12-THKN-P1-BS	Aqueous
	N01-E12-THKN-P2-AS	Aqueous
	N01-E12-THKN-P2-BS	Aqueous
	N01-E12-TKVK-P1-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB N01-E13-TARK-P3-XR collected 5/24/10 and reported in SDG 10050427 applies to samples collected 5/24/10 through 5/30/10. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

SSC was detected (6 mg/L) >quantitation limit (QL) in EB N01-E13-TARK-P3-XR. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E12-THKN-P1-AS	W	SSC	10	1	mg/L	J	be
N01-E12-THKN-P1-BS	W	SSC	18	1	mg/L	J	be
N01-E12-THKN-P2-AS	W	SSC	11	1	mg/L	J	be
N01-E12-THKN-P2-BS	W	SSC	19	1	mg/L	J	be
N01-E12-TKVK-P1-BS	W	SSC	25	1	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
N01-E13-TARK-P3-XR (5/24/10)	SSC	6	1	10	1	N01-E12-THKN-P1-AS
				18	1	N01-E12-THKN-P1-BS
				11	1	N01-E12-THKN-P2-AS
				19	1	N01-E12-THKN-P2-BS
				25	1	N01-E12-TKVK-P1-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Routine May Sampling Event, Newark Bay	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10050420, 10050427, 10050431, and 10050433		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60144462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed September 7, 2010	
Reviewed by	Lisa Krowitz/AECOM	File Name: May NB PWCM DOC POC 4 SDGs.doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay New Jersey on May 24, 2010.

SDG	Client Sample ID	Matrix
10050420	N01-E13-THKN-P1-AS	Aqueous
	N01-E13-THKN-P1-BS	Aqueous
	N01-E13-THKN-P3-AS	Aqueous
	N01-E13-THKN-P3-BS	Aqueous
	N01-E13-TKVK-P1-AS	Aqueous
	N01-E13-TKVK-P1-BS	Aqueous
	N01-E13-TKVK-P3-BS	Aqueous
	N01-E13-TNBN-P1-AS	Aqueous
	N01-E13-TNBN-P1-BS	Aqueous
	N01-E13-TNBS-P1-AS	Aqueous
	N01-E13-TNBS-P1-AT (Field duplicate of N01-E13-TNBS-P1-AS)	Aqueous
	N01-E13-TNBS-P1-BS	Aqueous
10050427	N01-E13-TARK-P1-AS	Aqueous

SDG	Client Sample ID	Matrix
	N01-E13-TARK-P1-BS	Aqueous
	N01-E13-TARK-P3-AS	Aqueous
	N01-E13-TARK-P3-BS	Aqueous
	N01-E13-TARK-P3-XR (Equipment blank collected 5/24/10)	Aqueous
	N01-E13-TKVK-P3-AS	Aqueous
	N01-E13-TNBN-P3-AS	Aqueous
	N01-E13-TNBN-P3-BS	Aqueous
	N01-E13-TNBS-P3-AS	Aqueous
	N01-E13-TNBS-P3-BS	Aqueous
10050431	N01-E12-TARK-P1-AS	Aqueous
	N01-E12-TARK-P1-BS	Aqueous
	N01-E12-TARK-P3-AS	Aqueous
	N01-E12-TARK-P3-BS	Aqueous
	N01-E12-THKN-P1-AS	Aqueous
	N01-E12-THKN-P1-BS	Aqueous
	N01-E12-THKN-P3-AS	Aqueous
	N01-E12-THKN-P3-BS	Aqueous
10050433	N01-E12-TKVK-P1-AS	Aqueous
	N01-E12-TKVK-P1-BS	Aqueous
	N01-E12-TKVK-P3-AS	Aqueous
	N01-E12-TKVK-P3-AT (Field duplicate of N01-E12-TKVK-P3-AS)	Aqueous
	N01-E12-TKVK-P3-BS	Aqueous
	N01-E12-TNBN-P1-AS	Aqueous
	N01-E12-TNBN-P1-BS	Aqueous
	N01-E12-TNBN-P3-AS	Aqueous
	N01-E12-TNBN-P3-BS	Aqueous
	N01-E12-TNBS-P1-AS	Aqueous
	N01-E12-TNBS-P1-BS	Aqueous
	N01-E12-TNBS-P3-AS	Aqueous
	N01-E12-TNBS-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic	Aqueous	*Total Organic Carbon, Standard methods for the Examination of*

Analyte	Matrix	Primary Method Reference
Carbon (DOC)		*Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations		Ö	
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Several CaCO3 blanks had positive results > RL. These blanks will not be factored into data quality assessment since they are not considered representative of the sample analyses in this data set. Explain why not representative (your email had some great information, such as the cmpd was not properly spread, etc.…)

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of CCB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

EBs were associated with all samples collected in the same week as the EB. EB N01-E13-TARK-P3-XR, collected on 5/24/2010 and reported in SDG 10050427 is associated with all samples collected 5/21/2010 through 5/27/2010.

No POC contamination was noted in this EB.

DOC was detected (2.6 mg/L) >quantitation limit (QL) in EB N01-E13-TARK-P3-XR. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

The field duplicate pair N01-E12-TKVK-P3-AS / N01-E12-TKVK-P3-AT (reported in SDG 10050420) exceeded the RPD criteria for POC (37%). Precision was deemed acceptable since the sample and duplicate results were each < 5x the QL.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E12-TNBN-P1-AS	W	POC	1.4	1.0	mg/L	J	c
N01-E12-TNBN-P1-BS	W	POC	1.5	1.0	mg/L	J	c
N01-E12-TNBN-P3-AS	W	POC	1.3	1.0	mg/L	J	c
N01-E12-TNBN-P3-BS	W	POC	1.3	1.0	mg/L	J	c
N01-E12-TNBS-P1-AS	W	POC	1.2	1.0	mg/L	J	c
N01-E12-TNBS-P1-BS	W	POC	1.4	1.0	mg/L	J	c
N01-E12-TNBS-P3-AS	W	POC	1.3	1.0	mg/L	J	c
N01-E12-TNBS-P3-BS	W	POC	1.7	1.0	mg/L	J	c
N01-E12-TARK-P1-AS	W	POC	1.5	1.0	mg/L	J	c
N01-E12-TARK-P1-BS	W	POC	1.4	1.0	mg/L	J	c
N01-E12-TARK-P3-BS	W	POC	1.7	1.0	mg/L	J	c
N01-E13-THKN-P1-AS	W	DOC	4.3	1.5	mg/L	J	be
N01-E13-THKN-P1-BS	W	DOC	4.3	1.5	mg/L	J	be
N01-E13-THKN-P3-AS	W	DOC	4.3	1.5	mg/L	J	be
N01-E13-THKN-P3-BS	W	DOC	3.9	1.5	mg/L	J	be
N01-E13-TKVK-P1-AS	W	DOC	3.2	1.5	mg/L	J	be
N01-E13-TKVK-P1-BS	W	DOC	1.9	1.5	mg/L	J	be
N01-E13-TKVK-P3-BS	W	DOC	2.0	1.5	mg/L	J	be
N01-E13-TNBN-P1-AS	W	DOC	4.3	1.5	mg/L	J	be
N01-E13-TNBN-P1-BS	W	DOC	2.1	1.5	mg/L	J	be
N01-E13-TNBS-P1-AS	W	DOC	2.4	1.5	mg/L	J	be
N01-E13-TNBS-P1-AT	W	DOC	2.5	1.5	mg/L	J	be
N01-E13-TNBS-P1-BS	W	DOC	2.4	1.5	mg/L	J	be
N01-E13-TARK-P1-AS	W	DOC	2.4	1.5	mg/L	J	be
N01-E13-TARK-P1-BS	W	DOC	2.9	1.5	mg/L	J	be
N01-E13-TARK-P3-AS	W	DOC	2.8	1.5	mg/L	J	be
N01-E13-TARK-P3-BS	W	DOC	3.2	1.5	mg/L	J	be
N01-E13-TKVK-P3-AS	W	DOC	3.0	1.5	mg/L	J	be
N01-E13-TNBN-P3-AS	W	DOC	4.1	1.5	mg/L	J	be
N01-E13-TNBN-P3-BS	W	DOC	3.8	1.5	mg/L	J	be
N01-E13-TNBS-P3-AS	W	DOC	3.6	1.5	mg/L	J	be
N01-E13-TNBN-P3-BS	W	DOC	3.8	1.5	mg/L	J	be
N01-E13-TNBS-P3-AS	W	DOC	3.6	1.5	mg/L	J	be
N01-E13-TNBS-P3-BS	W	DOC	2.3	1.5	mg/L	J	be
N01-E12-TARK-P1-AS	W	DOC	2.4	1.5	mg/L	J	be
N01-E12-TARK-P1-BS	W	DOC	2.9	1.5	mg/L	J	be
N01-E12-TARK-P3-AS	W	DOC	3.1	1.5	mg/L	J	be
N01-E12-TARK-P3-BS	W	DOC	2.2	1.5	mg/L	J	be
N01-E12-THKN-P1-AS	W	DOC	3.3	1.5	mg/L	J	be
N01-E12-THKN-P1-BS	W	DOC	2.4	1.5	mg/L	J	be
N01-E12-THKN-P3-AS	W	DOC	3.6	1.5	mg/L	J	be
N01-E12-THKN-P3-BS	W	DOC	3.3	1.5	mg/L	J	be

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E12-TKVK-P1-AS	W	DOC	3.2	1.5	mg/L	J	be
N01-E12-TKVK-P1-BS	W	DOC	3.2	1.5	mg/L	J	be
N01-E12-TKVK-P3-AS	W	DOC	2.2	1.5	mg/L	J	be
N01-E12-TKVK-P3-AT	W	DOC	3.2	1.5	mg/L	J	be
N01-E12-TKVK-P3-BS	W	DOC	2.1	1.5	mg/L	J	be
N01-E12-TNBN-P1-AS	W	DOC	3.0	1.5	mg/L	J	be
N01-E12-TNBN-P1-BS	W	DOC	2.7	1.5	mg/L	J	be
N01-E12-TNBN-P3-AS	W	DOC	2.1	1.5	mg/L	J	be
N01-E12-TNBN-P3-BS	W	DOC	2.3	1.5	mg/L	J	be
N01-E12-TNBS-P1-AS	W	DOC	2.1	1.5	mg/L	J	be
N01-E12-TNBS-P1-BS	W	DOC	2.2	1.5	mg/L	J	be
N01-E12-TNBS-P3-AS	W	DOC	3.2	1.5	mg/L	J	be
N01-E12-TNBS-P3-BS	W	DOC	2.2	1.5	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Calibration Recovery

ICV/CCV	Analyte	Standard mg/L C	Result (mg/L C)	Recovery (%)
CCV 4	POC	1.30	1.371	105
CCV 5			1.366	105
CCV 6			1.196	92
CCV 8			1.225	94
CCV 11			1.235	95
CCV 12			1.212	93
Associated Samples: N01-E12-TNBN-P1-AS, N01-E12-TNBN-P1-BS, N01-E12-TNBN-P3-AS, N01-E12-TNBN-P3-BS, N01-E12-TNBS-P1-AS, N01-E12-TNBS-P1-BS, N01-E12-TNBS-P3-AS, N01-E12-TNBS-P3-BS, N01-E12-TARK-P1-AS, N01-E12-TARK-P1-BS, N01-E12-TARK-P3-BS				

Table A-2 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
N01-E13-TARK-P3-XR	DOC	2.6	1.5	4.3	1.5	N01-E13-THKN-P1-AS
				4.3	1.5	N01-E13-THKN-P1-BS
				4.3	1.5	N01-E13-THKN-P3-AS
				3.9	1.5	N01-E13-THKN-P3-BS
				3.2	1.5	N01-E13-TKVK-P1-AS
				1.9	1.5	N01-E13-TKVK-P1-BS
				2.0	1.5	N01-E13-TKVK-P3-BS
				4.3	1.5	N01-E13-TNBN-P1-AS
				2.1	1.5	N01-E13-TNBN-P1-BS
				2.4	1.5	N01-E13-TNBS-P1-AS
				2.5	1.5	N01-E13-TNBS-P1-AT

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
N01-E13-TARK-P3-XR	DOC	2.6	1.5	2.4	1.5	N01-E13-TNBS-P1-BS
				2.4	1.5	N01-E13-TARK-P1-AS
				2.9	1.5	N01-E13-TARK-P1-BS
				2.8	1.5	N01-E13-TARK-P3-AS
				3.2	1.5	N01-E13-TARK-P3-BS
				3.0	1.5	N01-E13-TKVK-P3-AS
				4.1	1.5	N01-E13-TNBN-P3-AS
				3.8	1.5	N01-E13-TNBN-P3-BS
				3.6	1.5	N01-E13-TNBS-P3-AS
				3.8	1.5	N01-E13-TNBN-P3-BS
				3.6	1.5	N01-E13-TNBS-P3-AS
				2.3	1.5	N01-E13-TNBS-P3-BS
				2.4	1.5	N01-E12-TARK-P1-AS
				2.9	1.5	N01-E12-TARK-P1-BS
				3.1	1.5	N01-E12-TARK-P3-AS
				2.2	1.5	N01-E12-TARK-P3-BS
				3.3	1.5	N01-E12-THKN-P1-AS
				2.4	1.5	N01-E12-THKN-P1-BS
				3.6	1.5	N01-E12-THKN-P3-AS
				3.3	1.5	N01-E12-THKN-P3-BS
				3.2	1.5	N01-E12-TKVK-P1-AS
				3.2	1.5	N01-E12-TKVK-P1-BS
				2.2	1.5	N01-E12-TKVK-P3-AS
				3.2	1.5	N01-E12-TKVK-P3-AT
				2.1	1.5	N01-E12-TKVK-P3-BS
				3.0	1.5	N01-E12-TNBN-P1-AS
				2.7	1.5	N01-E12-TNBN-P1-BS
				2.1	1.5	N01-E12-TNBN-P3-AS
				2.3	1.5	N01-E12-TNBN-P3-BS
				2.1	1.5	N01-E12-TNBS-P1-AS
				2.2	1.5	N01-E12-TNBS-P1-BS
				3.2	1.5	N01-E12-TNBS-P3-AS
				2.2	1.5	N01-E12-TNBS-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection May Newark Bay Sampling Events	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10050437, 10050441, 10050442, and 10050464		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed August 2, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: May NB PWCM SSC 4 SDGs.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on May 21, 22, and 24, 2010.

SDG	Client Sample ID	Matrix
10050437	N01-E12-TKVK-P1-AS	Aqueous
	N01-E12-TKVK-P2-AS	Aqueous
	N01-E12-TKVK-P2-BS	Aqueous
	N01-E12-TKVK-P3-AS	Aqueous
	N01-E12-TKVK-P3-BS	Aqueous
	N01-E12-TNBN-P1-AS	Aqueous
	N01-E12-TNBN-P1-AT (Field duplicate of N01-E12-TNBN-P1-AS)	Aqueous
	N01-E12-TNBN-P1-BS	Aqueous
	N01-E12-TNBN-P2-AS	Aqueous
	N01-E12-TNBN-P2-BS	Aqueous
	N01-E12-TNBN-P3-AS	Aqueous
	N01-E12-TNBN-P3-BS	Aqueous
	N01-E12-TNBS-P1-AS	Aqueous

SDG	Client Sample ID	Matrix
10050437	N01-E12-TNBS-P1-BS	Aqueous
	N01-E12-TNBS-P2-AS	Aqueous
	N01-E12-TNBS-P2-BS	Aqueous
	N01-E12-TNBS-P3-AS	Aqueous
	N01-E12-TNBS-P3-BS	Aqueous
10050441	N01-E10-TKVK-P1-AS	Aqueous
	N01-E10-TKVK-P1-BS	Aqueous
	N01-E10-TNBN-P1-AS	Aqueous
	N01-E10-TNBN-P1-BS	Aqueous
	N01-E14-TKVK-P1-AS	Aqueous
	N01-E14-TKVK-P1-BS	Aqueous
	N01-E14-TNBN-P1-AS	Aqueous
	N01-E14-TNBN-P1-BS	Aqueous
	N01-E14-TNBN-P1-XR (Equipment blank collected 5/22/10)	Aqueous
10050442	N01-E10-TARK-P1-AS	Aqueous
	N01-E10-TARK-P1-BS	Aqueous
	N01-E10-THKN-P1-AS	Aqueous
	N01-E10-THKN-P1-BS	Aqueous
	N01-E10-TNBS-P1-AS	Aqueous
	N01-E10-TNBS-P1-AT (Field duplicate of N01-E10-TNBS-P1-AS)	Aqueous
	N01-E10-TNBS-P1-BS	Aqueous
	N01-E14-TARK-P1-AS	Aqueous
	N01-E14-TARK-P1-BS	Aqueous
	N01-E14-THKN-P1-AS	Aqueous
	N01-E14-THKN-P1-BS	Aqueous
	N01-E14-TNBS-P1-AS	Aqueous
	N01-E14-TNBS-P1-BS	Aqueous
10050464	N01-E13-TARK-P1-AS	Aqueous
	N01-E13-TARK-P2-AS	Aqueous
	N01-E13-TARK-P2-BS	Aqueous
	N01-E13-TARK-P3-AS	Aqueous
	N01-E13-TARK-P3-BS	Aqueous
	N01-E13-THKN-P1-AS	Aqueous
	N01-E13-THKN-P2-AS	Aqueous
	N01-E13-THKN-P2-BS	Aqueous
	N01-E13-THKN-P3-AS	Aqueous
	N01-E13-THKN-P3-BS	Aqueous
	N01-E13-TNBN-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody. The following discrepancies were noted:

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB N01-E14-TNBN-P1-XR, collected on 5/22/2010 and reported in SDG 10050441 is associated with all samples collected 5/17/2010 through 5/23/2010. No EB was collected during the period 5/24/10 through 5/30/10. The next closest EB was N01-E14-TNBN-P1-XR (collected 5/22/10 and reported in SDG 10050441) was applied to the samples collected during the period 5/24/10 through 5/30/10. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

SSC was detected (9 mg/L) >quantitation limit (QL) in EB N01-E14-TNBN-P1-XR. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E12-TKVK-P1-AS	W	SSC	10	1	mg/L	J	be
N01-E12-TKVK-P2-AS	W	SSC	10	1	mg/L	J	be
N01-E12-TKVK-P2-BS	W	SSC	22	1	mg/L	J	be
N01-E12-TKVK-P3-AS	W	SSC	18	1	mg/L	J	be
N01-E12-TKVK-P3-BS	W	SSC	16	1	mg/L	J	be
N01-E12-TNBN-P1-AS	W	SSC	9	1	mg/L	J	be
N01-E12-TNBN-P1-AT	W	SSC	9	1	mg/L	J	be
N01-E12-TNBN-P1-BS	W	SSC	13	1	mg/L	J	be
N01-E12-TNBN-P2-AS	W	SSC	8	1	mg/L	J	be
N01-E12-TNBN-P2-BS	W	SSC	9	1	mg/L	J	be
N01-E12-TNBN-P3-AS	W	SSC	10	1	mg/L	J	be
N01-E12-TNBN-P3-BS	W	SSC	10	1	mg/L	J	be
N01-E12-TNBS-P1-AS	W	SSC	8	1	mg/L	J	be
N01-E12-TNBS-P1-BS	W	SSC	12	1	mg/L	J	be
N01-E12-TNBS-P2-AS	W	SSC	8	1	mg/L	J	be
N01-E12-TNBS-P2-BS	W	SSC	15	1	mg/L	J	be
N01-E12-TNBS-P3-AS	W	SSC	9	1	mg/L	J	be
N01-E12-TNBS-P3-BS	W	SSC	14	1	mg/L	J	be
N01-E10-TKVK-P1-AS	W	SSC	10	1	mg/L	J	be
N01-E10-TKVK-P1-BS	W	SSC	6	1	mg/L	J	be
N01-E10-TNBN-P1-AS	W	SSC	19	1	mg/L	J	be
N01-E10-TNBN-P1-BS	W	SSC	8	1	mg/L	J	be
N01-E14-TKVK-P1-AS	W	SSC	8	1	mg/L	J	be
N01-E14-TKVK-P1-BS	W	SSC	8	1	mg/L	J	be
N01-E14-TNBN-P1-AS	W	SSC	13	1	mg/L	J	be
N01-E14-TNBN-P1-BS	W	SSC	13	1	mg/L	J	be
N01-E10-TARK-P1-AS	W	SSC	11	1	mg/L	J	be
N01-E10-TARK-P1-BS	W	SSC	10	1	mg/L	J	be
N01-E10-THKN-P1-AS	W	SSC	23	1	mg/L	J	be
N01-E10-THKN-P1-BS	W	SSC	6	1	mg/L	J	be
N01-E10-TNBS-P1-AT	W	SSC	9	1	mg/L	J	be
N01-E10-TNBS-P1-BS	W	SSC	53	1	mg/L	J	be
N01-E14-TARK-P1-BS	W	SSC	10	1	mg/L	J	be
N01-E14-THKN-P1-AS	W	SSC	15	1	mg/L	J	be
N01-E14-THKN-P1-BS	W	SSC	17	1	mg/L	J	be
N01-E14-TNBS-P1-AS	W	SSC	27	1	mg/L	J	be
N01-E14-TNBS-P1-BS	W	SSC	12	1	mg/L	J	be
N01-E13-TARK-P1-AS	W	SSC	7	1	mg/L	J	be
N01-E13-TARK-P2-AS	W	SSC	11	1	mg/L	J	be
N01-E13-TARK-P2-BS	W	SSC	10	1	mg/L	J	be
N01-E13-TARK-P3-AS	W	SSC	16	1	mg/L	J	be

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E13-TARK-P3-BS	W	SSC	11	1	mg/L	J	h,be
N01-E13-THKN-P1-AS	W	SSC	11	1	mg/L	J	h,be
N01-E13-THKN-P2-AS	W	SSC	14	1	mg/L	J	h,be
N01-E13-THKN-P2-BS	W	SSC	14	1	mg/L	J	h,be
N01-E13-THKN-P3-AS	W	SSC	37	1	mg/L	J	h,be
N01-E13-THKN-P3-BS	W	SSC	16	1	mg/L	J	be
N01-E13-TNBN-P3-BS	W	SSC	26	1	mg/L	J	h,be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E13-TARK-P3-BS	SSC	32	28
N01-E13-THKN-P1-AS			
N01-E13-THKN-P2-AS			
N01-E13-THKN-P2-BS			
N01-E13-THKN-P3-AS			
N01-E13-TNBN-P3-BS			

Table A-2 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
N01-E14-TNBN-P1-XR	SSC	9.0	1.0	10	1.0	N01-E12-TKVK-P1-AS
				10	1.0	N01-E12-TKVK-P2-AS
				22	1.0	N01-E12-TKVK-P2-BS
				18	1.0	N01-E12-TKVK-P3-AS
				16	1.0	N01-E12-TKVK-P3-BS
				9	1.0	N01-E12-TNBN-P1-AS
				9	1.0	N01-E12-TNBN-P1-AT
				13	1.0	N01-E12-TNBN-P1-BS
				8	1.0	N01-E12-TNBN-P2-AS
				9	1.0	N01-E12-TNBN-P2-BS
				10	1.0	N01-E12-TNBN-P3-AS
				10	1.0	N01-E12-TNBN-P3-BS
				8	1.0	N01-E12-TNBS-P1-AS
				12	1.0	N01-E12-TNBS-P1-BS
				8	1.0	N01-E12-TNBS-P2-AS
				15	1.0	N01-E12-TNBS-P2-BS
				9	1.0	N01-E12-TNBS-P3-AS
				14	1.0	N01-E12-TNBS-P3-BS
				10	1.0	N01-E10-TKVK-P1-AS
				6	1.0	N01-E10-TKVK-P1-BS
				19	1.0	N01-E10-TNBN-P1-AS
				8	1.0	N01-E10-TNBN-P1-BS
				8	1.0	N01-E14-TKVK-P1-AS
				8	1.0	N01-E14-TKVK-P1-BS
				13	1.0	N01-E14-TNBN-P1-AS
				13	1.0	N01-E14-TNBN-P1-BS
				11	1.0	N01-E10-TARK-P1-AS
				10	1.0	N01-E10-TARK-P1-BS
				23	1.0	N01-E10-THKN-P1-AS
				6	1.0	N01-E10-THKN-P1-BS
				9	1.0	N01-E10-TNBS-P1-AS
				9	1.0	N01-E10-TNBS-P1-AT

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
N01-E14-TNBN-P1-XR	SSC	9.0	1.0	53	1.0	N01-E10-TNBS-P1-BS
				10	1.0	N01-E14-TARK-P1-BS
				15	1.0	N01-E14-THKN-P1-AS
				17	1.0	N01-E14-THKN-P1-BS
				27	1.0	N01-E14-TNBS-P1-AS
				12	1.0	N01-E14-TNBS-P1-BS
				7	1.0	N01-E13-TARK-P1-AS
				11	1.0	N01-E13-TARK-P2-AS
				10	1.0	N01-E13-TARK-P2-BS
				16	1.0	N01-E13-TARK-P3-AS
				11	1.0	N01-E13-TARK-P3-BS
				11	1.0	N01-E13-THKN-P1-AS
				14	1.0	N01-E13-THKN-P2-AS
				14	1.0	N01-E13-THKN-P2-BS
				37	1.0	N01-E13-THKN-P3-AS
				16	1.0	N01-E13-THKN-P3-BS
				26	1.0	N01-E13-TNBN-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection May Newark Bay Sampling Events	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10050467 and 10050469		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60144462.A410		
Prepared by	Sharon McKechnie/AECOM	Completed August 5, 2010	
Reviewed by	Lisa Krowitz/AECOM	File Name: May NB PWCM SSC 2 SDGs.doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay New Jersey on May 24, 2010.

SDG	Client Sample ID	Matrix
10050467	N01-E13-TNBN-P1-BS	Aqueous
	N01-E13-TNBN-P2-BS	Aqueous
	N01-E13-TNBN-P2-BT (Field duplicate of N01-E13-TNBN-P2-BS)	Aqueous
	N01-E13-TNBN-P2-AS	Aqueous
	N01-E13-TNBN-P3-AS	Aqueous
	N01-E13-TKVK-P2-BS	Aqueous
	N01-E13-TKVK-P2-AS	Aqueous
	N01-E13-TKVK-P3-BS	Aqueous
	N01-E12-TARK-P1-BS	Aqueous
	N01-E12-TARK-P1-AS	Aqueous
	N01-E12-TARK-P2-BS	Aqueous
	N01-E12-TARK-P2-AS	Aqueous
	N01-E12-TARK-P3-BS	Aqueous
	N01-E12-TARK-P3-AS	Aqueous
	N01-E12-THKN-P3-BS	Aqueous
10050467	N01-E12-THKN-P3-AS	Aqueous

SDG	Client Sample ID	Matrix
	N01-E13-THKN-P1-BS	Aqueous
10050469	N01-E13-TNBS-P1-BS	Aqueous
	N01-E13-TNBS-P1-AS	Aqueous
	N01-E13-TNBS-P2-BS	Aqueous
	N01-E13-TNBS-P2-AS	Aqueous
	N01-E13-TNBS-P3-BS	Aqueous
	N01-E13-TNBS-P3-AS	Aqueous
	N01-E13-TKVK-P1-BS	Aqueous
	N01-E13-TKVK-P3-AS	Aqueous
	N01-E13-TKVK-P3-AT (Field duplicate of N01-E13-TKVK-P3-AS)	Aqueous
	N01-E13-TARK-P1-BS	Aqueous
	N01-E13-TKVK-P1-AS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results	Ö		

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. No EB was collected during the period 5/24/10 through 5/30/10. The next closest EB was N01-E14-TNBN-P1-

XR (collected 5/22/10 and reported in SDG 10050441) was applied to the samples collected during the period 5/24/10 through 5/30/10. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

SSC was detected (4 mg/L) >quantitation limit (QL) in EB N01-E14-TNBN-P1-XR. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E12-TARK-P1-AS	W	SSC	9	1	mg/L	J	h,be
N01-E12-TARK-P1-BS	W	SSC	11	1	mg/L	J	h,be
N01-E12-TARK-P2-AS	W	SSC	8	1	mg/L	J	h,be
N01-E12-TARK-P2-BS	W	SSC	14	1	mg/L	J	h,be
N01-E12-TARK-P3-AS	W	SSC	10	1	mg/L	J	h,be
N01-E12-TARK-P3-BS	W	SSC	24	1	mg/L	J	h,be
N01-E12-THKN-P3-AS	W	SSC	14	1	mg/L	J	h,be
N01-E12-THKN-P3-BS	W	SSC	17	1	mg/L	J	h,be
N01-E13-THKN-P1-BS	W	SSC	19	1	mg/L	J	h,be
N01-E13-TKVK-P2-AS	W	SSC	22	1	mg/L	J	h,be
N01-E13-TKVK-P2-BS	W	SSC	38	1	mg/L	J	h,be
N01-E13-TKVK-P3-BS	W	SSC	18	1	mg/L	J	h,be
N01-E13-TNBN-P1-BS	W	SSC	31	1	mg/L	J	h,be
N01-E13-TNBN-P2-AS	W	SSC	12	1	mg/L	J	h,be
N01-E13-TNBN-P2-BS	W	SSC	12	1	mg/L	J	h,be
N01-E13-TNBN-P2-BT	W	SSC	12	1	mg/L	J	h,be
N01-E13-TNBN-P3-AS	W	SSC	12	1	mg/L	J	h,be
N01-E13-TARK-P1-BS	W	SSC	14	1	mg/L	J	h,be
N01-E13-TKVK-P1-AS	W	SSC	17	1	mg/L	J	h,be
N01-E13-TKVK-P1-BS	W	SSC	20	1	mg/L	J	h,be
N01-E13-TKVK-P3-AS	W	SSC	16	1	mg/L	J	h,be
N01-E13-TKVK-P3-AT	W	SSC	16	1	mg/L	J	h,be
N01-E13-TNBS-P1-AS	W	SSC	12	1	mg/L	J	h,be
N01-E13-TNBS-P1-BS	W	SSC	18	1	mg/L	J	h,be
N01-E13-TNBS-P2-AS	W	SSC	11	1	mg/L	J	h,be
N01-E13-TNBS-P2-BS	W	SSC	12	1	mg/L	J	h,be
N01-E13-TNBS-P3-AS	W	SSC	11	1	mg/L	J	h,be
N01-E13-TNBS-P3-BS	W	SSC	10	1	mg/L	J	h,be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E12-TARK-P1-AS	SSC	35-39	28
N01-E12-TARK-P1-BS			
N01-E12-TARK-P2-AS			
N01-E12-TARK-P2-BS			
N01-E12-TARK-P3-AS			
N01-E12-TARK-P3-BS			
N01-E12-THKN-P3-AS			
N01-E12-THKN-P3-BS			
N01-E13-TARK-P1-BS			
N01-E13-THKN-P1-BS			
N01-E13-TKVK-P1-AS			
N01-E13-TKVK-P1-BS			
N01-E13-TKVK-P2-AS			
N01-E13-TKVK-P2-BS			
N01-E13-TKVK-P3-AS			
N01-E13-TKVK-P3-AT			
N01-E13-TKVK-P3-BS			
N01-E13-TNBN-P1-AS			
N01-E13-TNBN-P1-BS			
N01-E13-TNBN-P2-AS			
N01-E13-TNBN-P2-BS			
N01-E13-TNBN-P2-BT			
N01-E13-TNBN-P3-AS			
N01-E13-TNBS-P1-AS			
N01-E13-TNBS-P1-BS			
N01-E13-TNBS-P2-AS			
N01-E13-TNBS-P2-BS			
N01-E13-TNBS-P3-AS			
N01-E13-TNBS-P3-BS			

Table A-2b – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
N01-E14-TNBN-P1-XR (5/22/10)	SSC	9	1	9	1	N01-E12-TARK-P1-AS
				11	1	N01-E12-TARK-P1-BS
				8	1	N01-E12-TARK-P2-AS
				14	1	N01-E12-TARK-P2-BS
				10	1	N01-E12-TARK-P3-AS
				24	1	N01-E12-TARK-P3-BS
				14	1	N01-E12-THKN-P3-AS
				17	1	N01-E12-THKN-P3-BS

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
				19	1	N01-E13-THKN-P1-BS
				22	1	N01-E13-TKVK-P2-AS
				38	1	N01-E13-TKVK-P2-BS
				18	1	N01-E13-TKVK-P3-BS
				31	1	N01-E13-TNBN-P1-BS
				12	1	N01-E13-TNBN-P2-AS
				12	1	N01-E13-TNBN-P2-BS
				12	1	N01-E13-TNBN-P2-BT
				12	1	N01-E13-TNBN-P3-AS
				14	1	N01-E13-TARK-P1-BS
				17	1	N01-E13-TKVK-P1-AS
				20	1	N01-E13-TKVK-P1-BS
				16	1	N01-E13-TKVK-P3-AS
				16	1	N01-E13-TKVK-P3-AT
				12	1	N01-E13-TNBS-P1-AS
				18	1	N01-E13-TNBS-P1-BS
				11	1	N01-E13-TNBS-P2-AS
				12	1	N01-E13-TNBS-P2-BS
				11	1	N01-E13-TNBS-P3-AS
				10	1	N01-E13-TNBS-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection, May Routine Sampling Events	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10050421		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed August 31, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: May Routine PWCM DOC POC10050421.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on May 24.

SDG	Client Sample ID	Matrix
10050421	10A-E13-T014-P1-AS	Aqueous
	10A-E13-T014-P1-BS	Aqueous
	10A-E13-T014-P3-AS	Aqueous
	10A-E13-T014-P3-BS	Aqueous
	10A-E13-T042-P1-AS	Aqueous
	10A-E13-T042-P1-BS	Aqueous
	10A-E13-T042-P1-BT (Field duplicate of 10A-E13-T042-P1-BS)	Aqueous
	10A-E13-T042-P3-AS	Aqueous
	10A-E13-T042-P3-BS	Aqueous
	10A-E13-T042-P3-XR (Equipment blank collected 5/24/10)	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Several CaCO3 blanks had positive results greater than the RL. The laboratory determined that the CaCO3 was not spread evenly during blank prep therefore, CaCO3 was left behind on the filter and was detected greater than the RL. In addition, this blank was not part of Method 440.0 and its applicability to our samples has not been established. These blanks were not factored into the data quality assessment since they were not considered representative of the sample analyses.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E13-T042-P3-XR, collected on 5/24/2010 is associated with all samples collected 5/24/2010 through 5/30/2010. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

DOC was detected (0.65 mg/L) >quantitation limit (QL) in EB 10A-E13-T042-P3-XR. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria. **LCS Results**

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E13-T014-P1-AS	W	DOC	3.2	1.5	mg/L	J	be
10A-E13-T014-P1-BS	W	DOC	2.7	1.5	mg/L	J	be
10A-E13-T014-P3-AS	W	DOC	4.4	1.5	mg/L	J	be
10A-E13-T014-P3-BS	W	DOC	3.7	1.5	mg/L	J	be
10A-E13-T042-P1-AS	W	DOC	4.3	1.5	mg/L	J	be
10A-E13-T042-P1-BS	W	DOC	4.0	1.5	mg/L	J	be
10A-E13-T042-P1-BT	W	DOC	4.1	1.5	mg/L	J	be
10A-E13-T042-P3-AS	W	DOC	4.2	1.5	mg/L	J	be
10A-E13-T042-P3-BS	W	DOC	4.0	1.5	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E13-T042-P3-XR	DOC	0.65	1.5	3.2	1.5	10A-E13-T014-P1-AS
				2.7	1.5	10A-E13-T014-P1-BS
				4.4	1.5	10A-E13-T014-P3-AS
				3.7	1.5	10A-E13-T014-P3-BS
				4.3	1.5	10A-E13-T042-P1-AS
				4.0	1.5	10A-E13-T042-P1-BS
				4.1	1.5	10A-E13-T042-P1-BT
				4.2	1.5	10A-E13-T042-P3-AS
				4.0	1.5	10A-E13-T042-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Routine May Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10050428		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed August 31, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: May Routine PWCM DOC POC 10050428 .doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on May 24, 2010.

SDG	Client Sample ID	Matrix
10050428	10A-E13-T067-P1-AS	Aqueous
	10A-E13-T067-P1-BS	Aqueous
	10A-E13-T067-P3-AS	Aqueous
	10A-E13-T067-P3-BS	Aqueous
	10A-E13-T102-P1-AS	Aqueous
	10A-E13-T102-P1-BS	Aqueous
	10A-E13-T102-P3-AS	Aqueous
	10A-E13-T102-P3-BS	Aqueous
	10A-E13-T135-P1-AS	Aqueous
	10A-E13-T135-P1-AT (Field duplicate of 10A-E13-T135-P1-AS)	Aqueous
	10A-E13-T135-P1-BS	Aqueous
	10A-E13-T135-P3-AS	Aqueous

SDG	Client Sample ID	Matrix
10050428	10A-E13-T135-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Several CaCO3 blanks had positive results greater than the RL. The laboratory determined that the CaCO3 was not spread evenly during blank prep therefore, CaCO3 was left behind on the filter and was detected greater than the RL. In addition, this blank was not part of Method 440.0 and its applicability to our samples has not been established. These blanks were not factored into the data quality assessment since they were not considered representative of the sample analyses.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E13-T042-P3-XR, collected on 5/24/2010 and reported in SDG 10050421 is associated with all samples collected 5/24/2010 through 5/30/2010.

Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

DOC was detected > QL (0.65 mg/L) in the EB. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

The field duplicate pair 10A-E13-T135-P1-AS/10A-E13-T135-P1-AT exceeded the RPD criteria for POC (22%). Precision was deemed acceptable since the sample and duplicate results were each < 5x the QL.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E13-T067-P1-AS	W	DOC	3.6	1.5	mg/L	J	be
10A-E13-T067-P1-BS	W	DOC	2.7	1.5	mg/L	J	be
10A-E13-T067-P3-AS	W	DOC	3.6	1.5	mg/L	J	be
10A-E13-T067-P3-BS	W	DOC	3.6	1.5	mg/L	J	be
10A-E13-T102-P1-AS	W	DOC	3.8	1.5	mg/L	J	be
10A-E13-T102-P1-BS	W	DOC	3.7	1.5	mg/L	J	be
10A-E13-T102-P3-AS	W	DOC	3.8	1.5	mg/L	J	be
10A-E13-T102-P3-BS	W	DOC	3.2	1.5	mg/L	J	be
10A-E13-T135-P1-AS	W	DOC	4.0	1.5	mg/L	J	be
10A-E13-T135-P1-AT	W	DOC	4.0	1.5	mg/L	J	be
10A-E13-T135-P1-BS	W	DOC	5.0	1.5	mg/L	J	be
10A-E13-T135-P3-AS	W	DOC	3.9	1.5	mg/L	J	be
10A-E13-T135-P3-BS	W	DOC	4.0	1.5	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blank

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E13-T042-P3-XR	DOC	0.65	1.5	3.6	1.5	10A-E13-T067-P1-AS
				2.7	1.5	10A-E13-T067-P1-BS
				3.6	1.5	10A-E13-T067-P3-AS
				3.6	1.5	10A-E13-T067-P3-BS
				3.8	1.5	10A-E13-T102-P1-AS
				3.7	1.5	10A-E13-T102-P1-BS
				3.8	1.5	10A-E13-T102-P3-AS
				3.2	1.5	10A-E13-T102-P3-BS
				4.0	1.5	10A-E13-T135-P1-AS
				4.0	1.5	10A-E13-T135-P1-AT
				5.0	1.5	10A-E13-T135-P1-BS
				3.9	1.5	10A-E13-T135-P3-AS
				4.0	1.5	10A-E13-T135-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Routine May Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10050429		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed August 30, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: May Routine PWCM DOC POC 10050429.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on May 24, 2010.

SDG	Client Sample ID	Matrix
10050429	10A-E12-T067-P1-AS	Aqueous
	10A-E12-T067-P1-BS	Aqueous
	10A-E12-T067-P3-AS	Aqueous
	10A-E12-T067-P3-BS	Aqueous
	10A-E12-T102-P1-AS	Aqueous
	10A-E12-T102-P1-BS	Aqueous
	10A-E12-T102-P3-AS	Aqueous
	10A-E12-T102-P3-BS	Aqueous
	10A-E12-T135-P1-AS	Aqueous
	10A-E12-T135-P1-BS	Aqueous

SDG	Client Sample ID	Matrix
10050429	10A-E12-T135-P3-AS	Aqueous
	10A-E12-T135-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations		Ö	
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Several CaCO3 blanks had positive results greater than the RL. The laboratory determined that the CaCO3 was not spread evenly during blank prep therefore, CaCO3 was left behind on the filter and was detected greater than the RL. In addition, this blank was not part of Method 440.0 and its applicability to our samples has not been established. These blanks were not factored into the data quality assessment since they were not considered representative of the sample analyses.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in

the same week as the EB. EB 10A-E13-T042-P3-XR, collected on 5/24/2010 and reported in SDG 10050421 is associated with all samples collected 5/24/2010 through 5/30/2010.

Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

DOC was detected > QL (0.65 mg/L) in the EB. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E12-T067-P1-AS	W	DOC	4.9	1.5	mg/L	J	be
10A-E12-T067-P1-BS	W	DOC	4.2	1.5	mg/L	J	be
10A-E12-T067-P3-AS	W	DOC	4.0	1.5	mg/L	J	be
10A-E12-T067-P3-BS	W	DOC	3.8	1.5	mg/L	J	be
10A-E12-T102-P1-AS	W	DOC	5.1	1.5	mg/L	J	be
10A-E12-T102-P1-BS	W	DOC	4.9	1.5	mg/L	J	be
10A-E12-T102-P3-AS	W	DOC	4.1	1.5	mg/L	J	be
10A-E12-T102-P3-BS	W	DOC	4.9	1.5	mg/L	J	be
10A-E12-T135-P1-AS	W	DOC	4.2	1.5	mg/L	J	be
10A-E12-T135-P1-BS	W	DOC	4.4	1.5	mg/L	J	be
10A-E12-T135-P3-AS	W	DOC	4.8	1.5	mg/L	J	be
10A-E12-T135-P3-BS	W	DOC	4.2	1.5	mg/L	J	be
10A-E12-T067-P1-AS	W	POC	5.7	1.0	mg/L	J	c
10A-E12-T067-P1-BS	W	POC	11	1.0	mg/L	J	c
10A-E12-T067-P3-AS	W	POC	4.5	1.0	mg/L	J	c
10A-E12-T067-P3-BS	W	POC	5.8	1.0	mg/L	J	c
10A-E12-T102-P1-AS	W	POC	2.2	1.0	mg/L	J	c
10A-E12-T102-P1-BS	W	POC	2.4	1.0	mg/L	J	c
10A-E12-T102-P3-AS	W	POC	2.6	1.0	mg/L	J	c
10A-E12-T102-P3-BS	W	POC	2.7	1.0	mg/L	J	c

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Calibration Recovery

ICV/CCV	Analyte	Standard mg/L C	Result (mg/L C)	Recovery (%)
CCV 4	POC	1.30	1.371	105
CCV 5			1.366	105
CCV 6			1.196	92
CCV 8			1.225	94
CCV 11			1.235	95
CCV 12			1.212	93
Affected Samples:	10A-E12-T067-P1-AS, 10A-E12-T067-P1-BS, 10A-E12-T067-P3-AS, 10A-E12-T067-P3-BS, 10A-E12-T102-P1-AS, 10A-E12-T102-P1-BS, 10A-E12-T102-P3-AS, 10A-E12-T102-P3-BS			

Table A-2 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E13-T042-P3-XR	DOC	0.65	1.5	4.9	1.5	10A-E12-T067-P1-AS
				4.2	1.5	10A-E12-T067-P1-BS
				4.0	1.5	10A-E12-T067-P3-AS
				3.8	1.5	10A-E12-T067-P3-BS
				5.1	1.5	10A-E12-T102-P1-AS
				4.9	1.5	10A-E12-T102-P1-BS
				4.1	1.5	10A-E12-T102-P3-AS
				4.9	1.5	10A-E12-T102-P3-BS
				4.2	1.5	10A-E12-T135-P1-AS
				4.4	1.5	10A-E12-T135-P1-BS
				4.8	1.5	10A-E12-T135-P3-AS
				4.2	1.5	10A-E12-T135-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection May Routine Sampling Events	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10050386, 10050387, 10050465, and 10050466		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Full (10050387), Limited (10050386, 10050465, and 10050466)		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed August 2, 2010 / Revised August 31, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: May Routine PWCM SSC 4 SDGs.doc

This report was revised to add text and reason codes to data in SDGs 10050465 and 10050466 for temperature nonconformances.

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on May 19, 20, and 24, 2010.

SDG	Client Sample ID	Matrix
10050386	10A-E10-T014-P3-AS	Aqueous
	10A-E10-T014-P3-AT (Field duplicate of 10A-E10-T014-P3-AS)	Aqueous
	10A-E10-T014-P3-BS	Aqueous
	10A-E10-T042-P1-AS	Aqueous
	10A-E10-T042-P1-BS	Aqueous
	10A-E14-T014-P3-AS	Aqueous
	10A-E14-T014-P3-BS	Aqueous
	10A-E14-T042-P1-AS	Aqueous
	10A-E14-T042-P1-BS	Aqueous
	10A-E14-T042-P1-XR (Equipment blank collected 5/20/10)	Aqueous
10050387	10A-E10-T067-P3-AS	Aqueous

SDG	Client Sample ID	Matrix
	10A-E10-T067-P3-BS	Aqueous
	10A-E10-T102-P1-AS	Aqueous
	10A-E10-T102-P1-BS	Aqueous
	10A-E10-T135-P3-AS	Aqueous
	10A-E10-T135-P3-BS	Aqueous
	10A-E14-T012-P1-BS	Aqueous
	10A-E14-T067-P3-AS	Aqueous
	10A-E14-T067-P3-BS	Aqueous
	10A-E14-T102-P1-AS	Aqueous
	10A-E14-T135-P3-AS	Aqueous
	10A-E14-T135-P3-AT (Field duplicate of 10A-E14-T135-P3-AS)	Aqueous
	10A-E14-T135-P3-BS	Aqueous
10050465	10A-E13-T014-P1-AS	Aqueous
	10A-E13-T014-P1-BS	Aqueous
	10A-E13-T014-P2-AS	Aqueous
	10A-E13-T014-P2-BS	Aqueous
	10A-E13-T014-P3-AS	Aqueous
	10A-E13-T014-P3-BS	Aqueous
	10A-E13-T014-P3-BT (Field duplicate of 10A-E13-T014-P3-BS)	Aqueous
	10A-E13-T042-P1-AS	Aqueous
	10A-E13-T042-P1-BS	Aqueous
	10A-E13-T042-P2-AS	Aqueous
	10A-E13-T042-P2-BS	Aqueous
	10A-E13-T042-P3-AS	Aqueous
	10A-E13-T042-P3-BS	Aqueous
	10A-E13-T102-P1-AT (No field duplicate collected)	Aqueous
	10A-E13-T102-P2-AS	Aqueous
	10A-E13-T102-P2-BS	Aqueous
	10A-E13-T102-P3-AS	Aqueous
	10A-E13-T102-P3-BS	Aqueous
10050466	10A-E12-T014-P1-AS	Aqueous
	10A-E12-T014-P1-BS	Aqueous
	10A-E12-T014-P2-AS	Aqueous
	10A-E12-T014-P2-BS	Aqueous
	10A-E12-T014-P3-AS	Aqueous
	10A-E12-T014-P3-BS	Aqueous
	10A-E12-T042-P1-AS	Aqueous
10050466	10A-E12-T042-P1-BS	Aqueous

SDG	Client Sample ID	Matrix
	10A-E12-T042-P2-AS	Aqueous
	10A-E12-T042-P2-BS	Aqueous
	10A-E12-T042-P3-AS	Aqueous
	10A-E12-T042-P3-BS	Aqueous
	10A-E13-T102-P1-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Selected samples were stored in a refrigerator which malfunctioned prior to sample shipment to the laboratory. Upon discovery of the malfunction, the temperature was 18°C. All affected samples were qualified as estimated (J). Nonconformances are summarized in Attachment A, Table A-2.

Qualified sample results are shown in Table 1.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E14-T042-P1-XR, collected on 5/20/2010 and reported in SDG 10050385 is associated with all samples collected 5/17/2010 through 5/23/2010. No EB was collected during the period 5/24/10 through 5/30/10. EB 10A-E14-T042-P1-XR, collected on 5/20/2010 was applied to the samples collected during the period 5/24/10 through 5/30/10. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

SSC was detected (13 mg/L) > quantitation limit (QL) in EB 10A-E14-T042-P1-XR. Nonconformances are summarized in Attachment A, Table A-3. Qualified sample results are shown in Table 1.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC.

Sample 10A-E13-T102-P1-AT (reported in SDG 10050465) had no associated parent sample. No qualification actions were necessary on this basis.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E10-T014-P3-AS	W	SSC	23	1	mg/L	J	be
10A-E10-T014-P3-AT	W	SSC	25	1	mg/L	J	be
10A-E10-T014-P3-BS	W	SSC	16	1	mg/L	J	be
10A-E10-T042-P1-AS	W	SSC	27	1	mg/L	J	be
10A-E10-T042-P1-BS	W	SSC	108	1	mg/L	J	be
10A-E14-T014-P3-AS	W	SSC	11	1	mg/L	J	be
10A-E14-T014-P3-BS	W	SSC	8	1	mg/L	J	be
10A-E14-T042-P1-AS	W	SSC	40	1	mg/L	J	be
10A-E14-T042-P1-BS	W	SSC	33	1	mg/L	J	be
10A-E10-T067-P3-AS	W	SSC	13	1	mg/L	J	be
10A-E10-T067-P3-BS	W	SSC	7	1	mg/L	J	be
10A-E10-T102-P1-AS	W	SSC	9	1	mg/L	J	be
10A-E10-T102-P1-BS	W	SSC	10	1	mg/L	J	be
10A-E10-T135-P3-AS	W	SSC	9	1	mg/L	J	be
10A-E10-T135-P3-BS	W	SSC	8	1	mg/L	J	be
10A-E14-T012-P1-BS	W	SSC	30	1	mg/L	J	be
10A-E14-T067-P3-AS	W	SSC	33	1	mg/L	J	be
10A-E14-T067-P3-BS	W	SSC	51	1	mg/L	J	be
10A-E14-T102-P1-AS	W	SSC	7	1	mg/L	J	be
10A-E14-T135-P3-AS	W	SSC	7	1	mg/L	J	be
10A-E14-T135-P3-AT	W	SSC	6	1	mg/L	J	be
10A-E14-T135-P3-BS	W	SSC	15	1	mg/L	J	be
10A-E13-T014-P1-AS	W	SSC	15	1	mg/L	J	h,be,t
10A-E13-T014-P1-BS	W	SSC	31	1	mg/L	J	h,be,t
10A-E13-T014-P2-AS	W	SSC	14	1	mg/L	J	h,be,t
10A-E13-T014-P2-BS	W	SSC	69	1	mg/L	J	h,be,t
10A-E13-T014-P3-AS	W	SSC	15	1	mg/L	J	h,be,t
10A-E13-T014-P3-BS	W	SSC	106	1	mg/L	J	h,be,t
10A-E13-T014-P3-BT	W	SSC	113	1	mg/L	J	h,be,t
10A-E13-T042-P1-AS	W	SSC	22	1	mg/L	J	h,be,t
10A-E13-T042-P1-BS	W	SSC	289	1	mg/L	J	h,t
10A-E13-T042-P2-AS	W	SSC	23	1	mg/L	J	h,be,t
10A-E13-T042-P2-BS	W	SSC	223	1	mg/L	J	h,t
10A-E13-T042-P3-AS	W	SSC	34	1	mg/L	J	h,be,t
10A-E13-T042-P3-BS	W	SSC	131	1	mg/L	J	h,t
10A-E13-T102-P1-AT	W	SSC	14	1	mg/L	J	h,be,t
10A-E13-T102-P2-AS	W	SSC	8	1	mg/L	J	h,be,t
10A-E13-T102-P2-BS	W	SSC	8	1	mg/L	J	h,be,t
10A-E13-T102-P3-AS	W	SSC	10	1	mg/L	J	h,be,t
10A-E13-T102-P3-BS	W	SSC	10	1	mg/L	J	h,be,t
10A-E12-T014-P1-AS	W	SSC	17	1	mg/L	J	h,be,t

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E12-T014-P1-BS	W	SSC	103	1	mg/L	J	h,be,t
10A-E12-T014-P2-AS	W	SSC	15	1	mg/L	J	h,b,t
10A-E12-T014-P2-BS	W	SSC	19	1	mg/L	J	h,be,t
10A-E12-T014-P3-AS	W	SSC	16	1	mg/L	J	h,be,t
10A-E12-T014-P3-BS	W	SSC	23	1	mg/L	J	h,be,t
10A-E12-T042-P1-AS	W	SSC	29	1	mg/L	J	h,be,t
10A-E12-T042-P1-BS	W	SSC	38	1	mg/L	J	h,be,t
10A-E12-T042-P2-AS	W	SSC	27	1	mg/L	J	h,be,t
10A-E12-T042-P2-BS	W	SSC	39	1	mg/L	J	h,be,t
10A-E12-T042-P3-AS	W	SSC	29	1	mg/L	J	h,be,t
10A-E12-T042-P3-BS	W	SSC	48	1	mg/L	J	h,be,t
10A-E13-T102-P1-BS	W	SSC	7	1	mg/L	J	h,be,t

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E13-T014-P1-AS	SSC	32	28
10A-E13-T014-P1-BS			
10A-E13-T014-P2-AS			
10A-E13-T014-P2-BS			
10A-E13-T014-P3-AS			
10A-E13-T014-P3-BS			
10A-E13-T014-P3-BT			
10A-E13-T042-P1-AS			
10A-E13-T042-P1-BS			
10A-E13-T042-P2-AS			
10A-E13-T042-P2-BS			
10A-E13-T042-P3-AS			
10A-E13-T042-P3-BS			
10A-E13-T102-P2-BS			
10A-E12-T014-P1-AS		33	
10A-E12-T014-P1-BS			
10A-E12-T014-P2-AS			
10A-E12-T014-P2-BS			
10A-E12-T014-P3-AS			
10A-E12-T014-P3-BS			
10A-E13-T102-P1-AT			
10A-E13-T102-P2-AS			
10A-E13-T102-P3-AS			
10A-E13-T102-P3-BS			
10A-E12-T042-P1-AS		35	
10A-E12-T042-P1-BS			
10A-E12-T042-P2-AS			
10A-E12-T042-P2-BS			
10A-E12-T042-P3-AS			
10A-E12-T042-P3-BS			
10A-E13-T102-P1-BS			

Table A-2 – Temperature Preservation

Sample ID	Analyte	Nonconforming Temperature (°C)	TemperatureCriteria (°C)
10A-E13-T014-P1-AS	SSC	18	0-6
10A-E13-T014-P1-BS			
10A-E13-T014-P2-AS			
10A-E13-T014-P2-BS			
10A-E13-T014-P3-AS			
10A-E13-T014-P3-BS			
10A-E13-T014-P3-BT			
10A-E13-T042-P1-AS			
10A-E13-T042-P1-BS			
10A-E13-T042-P2-AS			
10A-E13-T042-P2-BS			
10A-E13-T042-P3-AS			
10A-E13-T042-P3-BS			
10A-E13-T102-P1-AT			
10A-E13-T102-P2-AS			
10A-E13-T102-P2-BS			
10A-E13-T102-P3-AS			
10A-E13-T102-P3-BS			
10A-E12-T014-P1-AS			
10A-E12-T014-P1-BS			
10A-E12-T014-P2-AS			
10A-E12-T014-P2-BS			
10A-E12-T014-P3-AS			
10A-E12-T014-P3-BS			
10A-E12-T042-P1-AS			
10A-E12-T042-P1-BS			
10A-E12-T042-P2-AS			
10A-E12-T042-P2-BS			
10A-E12-T042-P3-AS			
10A-E12-T042-P3-BS			
10A-E13-T102-P1-BS			

Table A-3 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E14-T042-P1-XR	SSC	13	1.0	23	1.0	10A-E10-T014-P3-AS
				25	1.0	10A-E10-T014-P3-AT
				16	1.0	10A-E10-T014-P3-BS
				27	1.0	10A-E10-T042-P1-AS
				108	1.0	10A-E10-T042-P1-BS
				11	1.0	10A-E14-T014-P3-AS
				8	1.0	10A-E14-T014-P3-BS
				40	1.0	10A-E14-T042-P1-AS
				33	1.0	10A-E14-T042-P1-BS
				13	1.0	10A-E10-T067-P3-AS
				7	1.0	10A-E10-T067-P3-BS
				9	1.0	10A-E10-T102-P1-AS
				10	1.0	10A-E10-T102-P1-BS
				9	1.0	10A-E10-T135-P3-AS
				8	1.0	10A-E10-T135-P3-BS
				30	1.0	10A-E14-T012-P1-BS
				33	1.0	10A-E14-T067-P3-AS
				51	1.0	10A-E14-T067-P3-BS
				7	1.0	10A-E14-T102-P1-AS
				7	1.0	10A-E14-T135-P3-AS
				6	1.0	10A-E14-T135-P3-AT
				15	1.0	10A-E14-T135-P3-BS
				15	1.0	10A-E13-T014-P1-AS
				31	1.0	10A-E13-T014-P1-BS
				14	1.0	10A-E13-T014-P2-AS
				69	1.0	10A-E13-T014-P2-BS
				15	1.0	10A-E13-T014-P3-AS
				106	1.0	10A-E13-T014-P3-BS
				113	1.0	10A-E13-T014-P3-BT
				22	1.0	10A-E13-T042-P1-AS
				23	1.0	10A-E13-T042-P2-AS
				34	1.0	10A-E13-T042-P3-AS
				14	1.0	10A-E13-T102-P1-AT
				8	1.0	10A-E13-T102-P2-AS
				8	1.0	10A-E13-T102-P2-BS
				10	1.0	10A-E13-T102-P3-AS
				10	1.0	10A-E13-T102-P3-BS
				17	1.0	10A-E12-T014-P1-AS
				103	1.0	10A-E12-T014-P1-BS
				15	1.0	10A-E12-T014-P2-AS

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E14-T042-P1-XR	SSC	13	1.0	19	1.0	10A-E12-T014-P2-BS
				16	1.0	10A-E12-T014-P3-AS
				23	1.0	10A-E12-T014-P3-BS
				29	1.0	10A-E12-T042-P1-AS
				38	1.0	10A-E12-T042-P1-BS
				27	1.0	10A-E12-T042-P2-AS
				39	1.0	10A-E12-T042-P2-BS
				29	1.0	10A-E12-T042-P3-AS
				48	1.0	10A-E12-T042-P3-BS
				7	1.0	10A-E13-T102-P1-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection May Wet Weather Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order			
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Full (10050233 Only) Limited (All except 10050233)		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed August 19, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: PWCM May Wet Weather DOC POC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on May 12, 2010.

SDG	Client Sample ID	Matrix
10050233	10C-E01-T2R1-P1-AS	Aqueous
	10C-E02-T2R1-P1-AS	Aqueous
	10C-E03-T2R1-P1-AS	Aqueous
	10C-E04-T2R1-P1-AS	Aqueous
	10C-E04-T2R1-P1-AT (field duplicate of 10C-E04-T2R1-P1-AS)	Aqueous
	10C-E05-T2R1-P1-AS	Aqueous
	10C-E06-T2R1-P1-AS	Aqueous
10050235	10C-E01-T169-P2-AS	Aqueous
	10C-E02-T169-P2-AS	Aqueous
10050235	10C-E03-T169-P2-AS	Aqueous

SDG	Client Sample ID	Matrix
	10C-E04-T169-P2-AS	Aqueous
	10C-E05-T169-P2-AS	Aqueous
	10C-E06-T169-P2-AS	Aqueous
10050236	10C-E01-T3R1-P1-AS	Aqueous
	10C-E02-T3R1-P1-AS	Aqueous
	10C-E03-T3R1-P1-AS	Aqueous
	10C-E04-T3R1-P1-AS	Aqueous
	10C-E05-T3R1-P1-AS	Aqueous
	10C-E06-T3R1-P1-AS	Aqueous
	10C-E06-T3R1-P1-XR (Equipment blank collected 5/12/10)	Aqueous
10050237	10C-E01-T169-P1-AS	Aqueous
	10C-E02-T169-P1-AS	Aqueous
	10C-E03-T169-P1-AS	Aqueous
	10C-E04-T169-P1-AS	Aqueous
	10C-E05-T169-P1-AS	Aqueous
	10C-E06-T169-P1-AS	Aqueous
10050238	10C-E01-TSR2-P1-AS	Aqueous
	10C-E02-TSR2-P1-AS	Aqueous
	10C-E03-TSR2-P1-AS	Aqueous
	10C-E03-TSR2-P1-AT (Field duplicate of 10C-E03-TSR2-P1-AS)	Aqueous
	10C-E04-TSR2-P1-AS	Aqueous
	10C-E05-TSR2-P1-AS	Aqueous
	10C-E06-TSR2-P1-AS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the

absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	**No**	**NA**
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

<u>Data Completeness</u>

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

All POC results were reported to one significant figure on the Form 1 summaries; however, it is customary for results to be reported to at least two significant figures. The laboratory was contacted and all affected POC Form 1 reports resubmitted.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10C-E06-T3R1-P1-XR, collected on 5/12/2010 and reported in SDG 10050236 is associated with all wet weather event samples collected 5/10/2010 through 5/16/2010. No contaminants were detected above the MDL in any of the EBs associated with the samples in this data set.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria. DOC MS 10050029-03B %R exceeded the criteria, but since these samples were already rejected for EB contamination, no qualifiers were applied on this basis.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No sample results qualified as a result of validation actions.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection May Wet Weather Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10050233, 10050235, 10050236, 10050237, and 10050238		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed July 28, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: PWCM May Wet Weather SSC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on May 12, 2010.

SDG	Client Sample ID	Matrix
10050233	10C-E01-T2R1-P1-AS	Aqueous
	10C-E02-T2R1-P1-AS	Aqueous
	10C-E03-T2R1-P1-AS	Aqueous
	10C-E04-T2R1-P1-AS	Aqueous
	10C-E04-T2R1-P1-AT (Field duplicate of 10C-E04-T2R1-P1-AS)	Aqueous
	10C-E05-T2R1-P1-AS	Aqueous
	10C-E06-T2R1-P1-AS	Aqueous
10050235	10C-E01-T169-P2-AS	Aqueous
	10C-E02-T169-P2-AS	Aqueous
	10C-E03-T169-P2-AS	Aqueous
	10C-E04-T169-P2-AS	Aqueous
	10C-E05-T169-P2-AS	Aqueous
	10C-E06-T169-P2-AS	Aqueous
10050236	10C-E01-T3R1-P1-AS	Aqueous
	10C-E02-T3R1-P1-AS	Aqueous

SDG	Client Sample ID	Matrix
	10C-E03-T3R1-P1-AS	Aqueous
	10C-E04-T3R1-P1-AS	Aqueous
	10C-E05-T3R1-P1-AS	Aqueous
	10C-E06-T3R1-P1-AS	Aqueous
	10C-E06-T3R1-P1-XR (Equipment blank collected 5/12/10)	Aqueous
10050237	10C-E01-T169-P1-AS	Aqueous
	10C-E02-T169-P1-AS	Aqueous
	10C-E03-T169-P1-AS	Aqueous
	10C-E04-T169-P1-AS	Aqueous
	10C-E05-T169-P1-AS	Aqueous
	10C-E06-T169-P1-AS	Aqueous
10050238	10C-E01-TSR2-P1-AS	Aqueous
	10C-E02-TSR2-P1-AS	Aqueous
	10C-E03-TSR2-P1-AS	Aqueous
	10C-E03-TSR2-P1-AT (Field duplicate of 10C-E03-TSR2-P1-AS)	Aqueous
	10C-E04-TSR2-P1-AS	Aqueous
	10C-E05-TSR2-P1-AS	Aqueous
	10C-E06-TSR2-P1-AS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10C-E06-T3R1-P1-XR, collected on 5/12/2010 and reported in SDG 10050236 is associated with all samples collected 5/10/2010 through 5/16/2010. No SSC was detected above the MDL in the EB associated with the 5/10/2010 through 5/16/2010 sample data set. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No sample results were qualified as a result of validation actions.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel
Preliminary Draft – For Discussion Purposes Only

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10060339 and 10060346		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 14, 2010
Reviewed by	Lisa Krowitz/AECOM	File:June Routine PWCM 1060339 346 SSC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on June 21 and 22, 2010.

SDG	Client Sample ID	Matrix
1060339	10A-E16-T175-P1-AS	Aqueous
	10A-E16-T175-P2-AS	Aqueous
	10A-E16-T175-P2-BS	Aqueous
	10A-E16-T175-P3-AS	Aqueous
	10A-E16-T175-P4-AS	Aqueous
1060346	10A-E17-T042-P1-AS	Aqueous
	10A-E17-T042-P1-BS	Aqueous
	10A-E17-T042-P2-AS	Aqueous
	10A-E17-T042-P2-AT (field duplicate of 10A-E17-T042-P2-AS)	Aqueous
	10A-E17-T042-P2-BS	Aqueous
	10A-E17-T042-P3-AS	Aqueous
	10A-E17-T042-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E18-T135-P1-XR, collected on 6/22/2010 and reported in SDG 10060383 is associated with all samples collected 6/21/2010 through 6/27/2010. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

SSC was detected (6 mg/L) >quantitation limit (QL) in EB 10A-E18-T135-P1-XR. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E16-T175-P1-AS	W	SSC	46	1	mg/L	J	be
10A-E16-T175-P2-AS	W	SSC	15	1	mg/L	J	be
10A-E16-T175-P2-BS	W	SSC	13	1	mg/L	J	be
10A-E16-T175-P3-AS	W	SSC	10	1	mg/L	J	be
10A-E16-T175-P4-AS	W	SSC	10	1	mg/L	J	be
10A-E17-T042-P1-AS	W	SSC	14	1	mg/L	J	be
10A-E17-T042-P1-BS	W	SSC	13	1	mg/L	J	be
10A-E17-T042-P2-AS	W	SSC	15	1	mg/L	J	be
10A-E17-T042-P2-AT	W	SSC	14	1	mg/L	J	be
10A-E17-T042-P2-BS	W	SSC	14	1	mg/L	J	be
10A-E17-T042-P3-AS	W	SSC	25	1	mg/L	J	be
10A-E17-T042-P3-BS	W	SSC	18	1	mg/L	J	be
10A-E16-T175-P1-AS	W	SSC	46	1	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E18-T135-P1-XR	SSC	6	1	46	1	10A-E16-T175-P1-AS
				15	1	10A-E16-T175-P2-AS
				13	1	10A-E16-T175-P2-BS
				10	1	10A-E16-T175-P3-AS
				10	1	10A-E16-T175-P4-AS
				14	1	10A-E17-T042-P1-AS
				13	1	10A-E17-T042-P1-BS
				15	1	10A-E17-T042-P2-AS
				14	1	10A-E17-T042-P2-AT
				14	1	10A-E17-T042-P2-BS
				25	1	10A-E17-T042-P3-AS
				18	1	10A-E17-T042-P3-BS
				46	1	10A-E16-T175-P1-AS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel
Preliminary Draft – For Discussion Purposes Only

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10060339		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Full		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 17, 2010
Reviewed by	Lisa Krowitz/AECOM	File: 10060339 June LPR PWCM Routine POC DOC .doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on June 21, 2010.

SDG	Client Sample ID	Matrix
10060339	10A-E16-T175-P1-AS	Aqueous
	10A-E16-T175-P2-AS	Aqueous
	10A-E16-T175-P2-BS	Aqueous
	10A-E16-T175-P3-AS	Aqueous
	10A-E16-T175-P4-AS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic CarbonCarbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E18-T135-P1-XR, collected on 6/22/2010 and reported in SDG 10060351 is associated with all samples collected 6/21/2010 through 6/27/2010. No POC or DOC was detected above the QL in the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No sample results were qualified as a result of validation actions.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Newark Bay Sampling Events	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10060341		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60144462.A410		
Prepared by	Sharon McKechnie/AECOM	Completed September 7, 2010	
Reviewed by	Lisa Krowitz/AECOM	File Name: 10060341 June NB PWCM SSC.doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay New Jersey on June 20, 2010.

SDG	Client Sample ID	Matrix
10060341	NO1-E15-TKVK-P1-BS	Aqueous
	NO1-E15-TKVK-P1-AS	Aqueous
	NO1-E19-TKVK-P1-BS	Aqueous
	NO1-E19-TKVK-P1-AS	Aqueous
	NO1-E15-TNBN-P1-BS	Aqueous
	NO1-E15-TNBN-P1-AS	Aqueous
	NO1-E19-TNBN-P1-BS	Aqueous
	NO1-E19-TNBN-P1-AS	Aqueous
	NO1-E19-TNBN-P1-XR (Equipment blank collected 6/20/10)	Aqueous
	NO1-E15-TNBS-P1-AT (Field duplicate of NO1-E15-TNBS-P1-AS)	Aqueous
	NO1-E15-TNBS-P1-AS	Aqueous
	NO1-E15-TNBS-P1-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB N01-E19-TNBN-P1-XR, collected on 6/20/2010 and reported in SDG 10060341 is associated with all samples collected 6/14/2010 through 6/20/2010. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

SSC was detected (9 mg/L) >quantitation limit (QL) in EB N01-E19-TNBN-P1-XR. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
NO1-E15-TKVK-P1-AS	W	SSC	3	1	mg/L	J	be
NO1-E15-TKVK-P1-BS	W	SSC	4	1	mg/L	J	be
NO1-E15-TNBN-P1-AS	W	SSC	13	1	mg/L	J	be
NO1-E15-TNBS-P1-AS	W	SSC	7	1	mg/L	J	be
NO1-E15-TNBS-P1-AT	W	SSC	7	1	mg/L	J	be
NO1-E15-TNBS-P1-BS	W	SSC	6	1	mg/L	J	be
NO1-E19-TKVK-P1-AS	W	SSC	7	1	mg/L	J	be
NO1-E19-TKVK-P1-BS	W	SSC	22	1	mg/L	J	be
NO1-E19-TNBN-P1-AS	W	SSC	10	1	mg/L	J	be
NO1-E19-TNBN-P1-BS	W	SSC	20	1	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
N01-E19-TNBN-P1-XR (6/20/10)	SSC	4	1	4	1	NO1-E15-TKVK-P1-BS
				3	1	NO1-E15-TKVK-P1-AS
				22	1	NO1-E19-TKVK-P1-BS
				7	1	NO1-E19-TKVK-P1-AS
				13	1	NO1-E15-TNBN-P1-AS
				20	1	NO1-E19-TNBN-P1-BS
				10	1	NO1-E19-TNBN-P1-AS
				7	1	NO1-E15-TNBS-P1-AT
				7	1	NO1-E15-TNBS-P1-AS
				6	1	NO1-E15-TNBS-P1-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel
Preliminary Draft – For Discussion Purposes Only

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10060342 and 10060343		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60144462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed August 31, 2010
Reviewed by	Lisa Krowitz/AECOM	File; PWCM June Routine 2 SDGs SSC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on June 17 and 20, 2010.

SDG	Client Sample ID	Matrix
10060342	10A-E15-T014-P3-AS	Aqueous
	10A-E15-T014-P3-BS	Aqueous
	10A-E15-T042-P1-AS	Aqueous
	10A-E15-T042-P1-BS	Aqueous
	10A-E19-T014-P3-AS	Aqueous
	10A-E19-T014-P3-BS	Aqueous
	10A-E19-T042-P1-AS	Aqueous
	10A-E19-T042-P1-AT (Field duplicate of 10A-E19-T042-P1-AS)	Aqueous
	10A-E19-T042-P1-BS	Aqueous
	10A-E19-T042-P1-XR (Equipment blank collected 6/18/10)	Aqueous
10060343	10A-E15-T067-P3-AS	Aqueous
	10A-E15-T067-P3-BS	Aqueous
	10A-E15-T102-P1-AS	Aqueous
	10A-E15-T102-P1-BS	Aqueous

SDG	Client Sample ID	Matrix
10060343	10A-E15-T135-P3-AS	Aqueous
	10A-E15-T135-P3-BS	Aqueous
	10A-E19-T067-P3-AS	Aqueous
	10A-E19-T067-P3-BS	Aqueous
	10A-E19-T102-P1-AS	Aqueous
	10A-E19-T102-P1-BS	Aqueous
	10A-E19-T135-P3-AS	Aqueous
	10A-E19-T135-P3-BS	Aqueous
	10A-E19-T135-P3-BT (Field duplicate of 10A-E19-T135-P3-BS)	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results		Ö	
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E19-TO42-P1-XR, collected on 6/18/2010 and reported in SDG 10060342 is associated with all samples collected 6/14/2010 through 6/20/2010. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

SSC was detected (12 mg/L) >quantitation limit (QL) in EB 10A-E19-TO42-P1-XR. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC. Data qualification on the basis of field duplicate RPDs was as follows (see above for acceptance criteria):

Criteria	Action	
	Detected	Nondetected
RPD greater than the acceptance criteria, but < 120% and sample and duplicate results >5x the SQL	J	Not Applicable
RPD ≥ 120%	R	Not Applicable
If sample and/or duplicate is <5x the QL and absolute difference is >2x and ≤ 4x the QL	J	UJ
If the sample and/or duplicate is <5x the QL and absolute difference is >4x the QL.	R	R

Qualified sample results are shown in Table 1. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E15-T067-P3-AS	W	SSC	45	1	mg/L	J	be
10A-E15-T067-P3-BS	W	SSC	45	1	mg/L	J	be
10A-E15-T102-P1-AS	W	SSC	45	1	mg/L	J	be
10A-E15-T102-P1-BS	W	SSC	27	1	mg/L	J	be
10A-E15-T135-P3-AS	W	SSC	15	1	mg/L	J	be
10A-E15-T135-P3-BS	W	SSC	17	1	mg/L	J	be
10A-E19-T067-P3-AS	W	SSC	91	1	mg/L	J	be
10A-E19-T102-P1-AS	W	SSC	22	1	mg/L	J	be
10A-E19-T102-P1-BS	W	SSC	22	1	mg/L	J	be
10A-E19-T135-P3-AS	W	SSC	20	1	mg/L	J	be
10A-E19-T135-P3-BS	W	SSC	14	1	mg/L	J	be
10A-E19-T135-P3-BT	W	SSC	18	1	mg/L	J	be
10A-E15-T014-P3-AS	W	SSC	18	1	mg/L	J	be
10A-E15-T014-P3-BS	W	SSC	18	1	mg/L	J	be
10A-E15-T042-P1-AS	W	SSC	31	1	mg/L	J	be
10A-E19-T014-P3-AS	W	SSC	15	1	mg/L	J	be
10A-E19-T014-P3-BS	W	SSC	66	1	mg/L	J	be
10A-E19-T042-P1-AS	W	SSC	37	1	mg/L	J	fd,be
10A-E19-T042-P1-AT	W	SSC	21	1	mg/L	J	fd,be
10A-E19-T042-P1-BS	W	SSC	33	1	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E19-TO42-P1-XR	SSC	12	1	45	1	10A-E15-T067-P3-AS
				45	1	10A-E15-T067-P3-BS
				45	1	10A-E15-T102-P1-AS
				27	1	10A-E15-T102-P1-BS
				15	1	10A-E15-T135-P3-AS
				17	1	10A-E15-T135-P3-BS
				91	1	10A-E19-T067-P3-AS
				22	1	10A-E19-T102-P1-AS
				22	1	10A-E19-T102-P1-BS
				20	1	10A-E19-T135-P3-AS
				14	1	10A-E19-T135-P3-BS
				18	1	10A-E19-T135-P3-BT
				18	1	10A-E15-T014-P3-AS
				18	1	10A-E15-T014-P3-BS
				31	1	10A-E15-T042-P1-AS
				15	1	10A-E19-T014-P3-AS
				66	1	10A-E19-T014-P3-BS
				37	1	10A-E19-T042-P1-AS
				21	1	10A-E19-T042-P1-AT
				33	1	10A-E19-T042-P1-BS

Table A-2 – Field Duplicate RPDs

Sample ID	Duplicate ID	Analyte	Sample Result	Duplicate Result	QL	Units	RPD
10A-E12-T067-P2-BS	10A-E12-T067-P2-BS	SSC	113	65	1	mg/L	54
10A-E19-T042-P1-AS	10A-E19-T042-P1-AS	SSC	37	21	1	mg/L	55

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay June Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10060344		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60144462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed September 7, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10060344 June Newark Bay SSC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on June 19, 2010.

SDG	Client Sample ID	Matrix
10060344	N01-E15-TARK-P1-AS	Aqueous
	N01-E15-TARK-P1-BS	Aqueous
	N01-E19-TARK-P1-AS	Aqueous
	N01-E19-TARK-P1-BS	Aqueous
	N01-E19-TNBS-P1-AS	Aqueous
	N01-E19-TNBS-P1-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	**No**	**NA**
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

<u>Data Completeness</u>

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

<u>Holding Times/Sample Preservation</u>

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB N01-E19-TNBN-P1-XR, collected on 6/20/2010 and reported in SDG 10060341 is associated with all samples collected 6/14/2010 through 6/20/2010. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

SSC was detected (4 mg/L) >quantitation limit (QL) in EB N01-E19-TNBN-P1-XR. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E15-TARK-P1-AS	W	SSC	6	1	mg/L	J	be
N01-E15-TARK-P1-BS	W	SSC	9	1	mg/L	J	be
N01-E19-TARK-P1-AS	W	SSC	6	1	mg/L	J	be
N01-E19-TARK-P1-BS	W	SSC	10	1	mg/L	J	be
N01-E19-TNBS-P1-AS	W	SSC	6	1	mg/L	J	be
N01-E19-TNBS-P1-BS	W	SSC	10	1	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
N01-E19-TNBN-P1-XR (6/20/10)	SSC	4	1	6	1	N01-E15-TARK-P1-AS
				9	1	N01-E15-TARK-P1-BS
				6	1	N01-E19-TARK-P1-AS
				10	1	N01-E19-TARK-P1-BS
				6	1	N01-E19-TNBS-P1-AS
				10	1	N01-E19-TNBS-P1-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel
Preliminary Draft – For Discussion Purposes Only

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10060346		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 17, 2010
Reviewed by	Lisa Krowitz/AECOM	File: 10060346 June LPR PWCM Routine POC DOC .doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on June 22, 2010.

SDG	Client Sample ID	Matrix
10060346	10A-E17-T042-P1-AS	Aqueous
	10A-E17-T042-P1-BS	Aqueous
	10A-E17-T042-P3-AS	Aqueous
	10A-E17-T042-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic CarbonCarbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E18-T135-P1-XR, collected on 6/22/2010 and reported in SDG 10060351 is associated with all samples collected 6/21/2010 through 6/27/2010. No POC or DOC was detected above the QL in the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No sample results were qualified as a result of validation actions.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel
Preliminary Draft – For Discussion Purposes Only

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10060347		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 17, 2010
Reviewed by	Lisa Krowitz/AECOM	File: 10060347 June LPR PWCM Routine POC DOC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on June 22, 2010.

SDG	Client Sample ID	Matrix
10060347	10A-E18-T067-P1-AS	Aqueous
	10A-E18-T067-P1-BS	Aqueous
	10A-E18-T067-P3-AS	Aqueous
	10A-E18-T067-P3-BS	Aqueous
	10A-E18-T102-P1-AS	Aqueous
	10A-E18-T102-P1-BS	Aqueous
	10A-E18-T102-P3-AS	Aqueous
	10A-E18-T102-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic CarbonCarbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations		Ö	
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results		Ö	
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E18-T135-P1-XR, collected on 6/22/2010 and reported in SDG 10060351 is associated with all samples collected 6/21/2010 through 6/27/2010. No POC or DOC was detected above the QL in the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL). The RPD for sample 10A-E18-T067-P3-BS (35%) exceeded the criteria and was qualified as estimated (J).

Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E18-T067-P1-AS	W	POC	7.9	1.0	mg/L	J	c
10A-E18-T067-P3-BS	W	POC	4.3	1.0	mg/L	J	ld,c

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Calibration Recovery

ICV/CCV	Analyte	Standard ppm C	Result (ppm C)	Recovery (%)
CCV #4	POC	13000	13550	104
CCV#5			13520	104
Affected Samples:	10A-E18-T067-P1-AS, 10A-E18-T067-P3-BS			

Table A-2 – Laboratory Duplicate RPD

Sample ID	Duplicate ID	Analyte	Sample Result	Duplicate Result	QL	Units	RPD (%)
10060347-03A*	10060347-03B	POC	4.3	6.1	1.0	mg/L	35
Associated samples: 10A-E18-T067-P3-BS							

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel
Preliminary Draft – For Discussion Purposes Only

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10060348		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 17, 2010
Reviewed by	Lisa Krowitz/AECOM	File: 10060348 June LPR PWCM Routine POC DOC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on June 22, 2010.

SDG	Client Sample ID	Matrix
10060348	10A-E18-T014-P1-AS	Aqueous
	10A-E18-T014-P1-BS	Aqueous
	10A-E18-T014-P3-AS	Aqueous
	10A-E18-T014-P3-AT (field duplicate of 10A-E18-T014-P3-AS)	Aqueous
	10A-E18-T014-P3-BS	Aqueous
	10A-E18-T042-P1-AS	Aqueous
	10A-E18-T042-P1-BS	Aqueous
	10A-E18-T042-P3-AS	Aqueous
	10A-E18-T042-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic CarbonCarbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations		Ö	
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E18-T135-P1-XR, collected on 6/22/2010 and reported in SDG 10060351 is associated with all samples collected 6/21/2010 through 6/27/2010. No POC or DOC was detected above the QL in the EB.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL). The RPD for sample 10A-E18-T014-P3-AT was not calculable due to a non detect result in the duplicate sample. Precision was deemed acceptable since the sample and duplicate results were both < 5 x the QL.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E18-T014-P1-AS	W	POC	0.9		mg/L	J	c
10A-E18-T014-P1-BS	W	POC	1.4		mg/L	J	c
10A-E18-T014-P3-AS	W	POC	1.2		mg/L	J	c
10A-E18-T014-P3-AT	W	POC			mg/L	UJ	c
10A-E18-T014-P3-BS	W	POC	1.2		mg/L	J	c
10A-E18-T042-P1-AS	W	POC	1.9		mg/L	J	c
10A-E18-T042-P1-BS	W	POC	5.3		mg/L	J	c
10A-E18-T042-P3-AS	W	POC	1.4		mg/L	J	c
10A-E18-T042-P3-BS	W	POC	1.5		mg/L	J	c

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- The result column will be empty where the sample result was nondetect

Attachment A

Nonconformance Summary Tables

Table A-1 – Calibration Recovery

ICV/CCV	Analyte	Standard ppm C	Result (ppm C)	Recovery (%)
CCV #4	POC	13000	13550	104
CCV #5			13520	104
CCV #6			13700	105
Affected Samples:	All POC samples			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Newark Bay Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10060349		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 27, 2010
Reviewed by	Lisa Krowitz/AECOM	File: 10060349 June NB PWCM POC DOC .doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on June 22, 2010.

SDG	Client Sample ID	Matrix
10060349	N01-E17-TARK-P1-AS	Aqueous
	N01-E17-TARK-P1-BS	Aqueous
	N01-E17-TARK-P3-AS	Aqueous
	N01-E17-TARK-P3-BS	Aqueous
	N01-E17-TNBN-P1-AS	Aqueous
	N01-E17-TNBN-P1-BS	Aqueous
	N01-E17-TNBN-P3-AS	Aqueous
	N01-E17-TNBN-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB N01-E18-TARK-P3-XR, collected on 6/22/2010 and reported in SDG 10060354 is associated with all samples collected 6/21/2010 through 6/27/2010. No POC was detected > the RL in the EB.

Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

DOC was detected > QL (2.2 mg/L) in the EB. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E17-TARK-P1-AS	W	DOC	2.4	1.5	mg/L	J	be
N01-E17-TARK-P1-BS	W	DOC	2.5	1.5	mg/L	J	be
N01-E17-TARK-P3-AS	W	DOC	2.5	1.5	mg/L	J	be
N01-E17-TARK-P3-BS	W	DOC	2.6	1.5	mg/L	J	be
N01-E17-TNBN-P1-AS	W	DOC	2.4	1.5	mg/L	J	be
N01-E17-TNBN-P1-BS	W	DOC	2.4	1.5	mg/L	J	be
N01-E17-TNBN-P3-AS	W	DOC	2.6	1.5	mg/L	J	be
N01-E17-TNBN-P3-BS	W	DOC	2.6	1.5	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
N01-E18-TARK-P3-XR (6/22/10)	DOC	2.2	1.5	2.4	1.5	N01-E17-TARK-P1-AS
				2.5	1.5	N01-E17-TARK-P1-BS
				2.5	1.5	N01-E17-TARK-P3-AS
				2.6	1.5	N01-E17-TARK-P3-BS
				2.4	1.5	N01-E17-TNBN-P1-AS
				2.4	1.5	N01-E17-TNBN-P1-BS
				2.6	1.5	N01-E17-TNBN-P3-AS
				2.6	1.5	N01-E17-TNBN-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Newark Bay Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10060350		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 27, 2010
Reviewed by	Lisa Krowitz/AECOM	File: 10060350 June NB PWCM POC DOC .doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on June 22, 2010.

SDG	Client Sample ID	Matrix
10060350	N01-E17-TKVK-P1-AS	Aqueous
	N01-E17-TKVK-P1-BS	Aqueous
	N01-E17-TKVK-P3-AS	Aqueous
	N01-E17-TKVK-P3-BS	Aqueous
	N01-E17-TNBS-P1-AS	Aqueous
	N01-E17-TNBS-P1-BS	Aqueous
	N01-E17-TNBS-P3-AS	Aqueous
	N01-E17-TNBS-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity		Ö	
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody. The following issue was noted:

- Sample ID N01-E17-TNBS-P3-BT on the COC did not match the ID on the sample bottle label which was N01-E17-TNBS-P3-BS. The sample was reported by the ID on the bottle label. No qualification action was necessary on this basis.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB N01-E18-TARK-P3-XR, collected on 6/22/2010 and reported in SDG 10060354 is associated with all samples collected 6/21/2010 through 6/27/2010. No POC was detected > the RL in the EB.

Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)

Blank Type	Sample Result	Actions
	> 10x the blank concentration	No action

DOC was detected > QL (2.2 mg/L) in the EB. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E17-TKVK-P1-AS	W	DOC	2.4	1.5	mg/L	J	be
N01-E17-TKVK-P1-BS	W	DOC	2.0	1.5	mg/L	J	be
N01-E17-TKVK-P3-AS	W	DOC	2.2	1.5	mg/L	J	be
N01-E17-TKVK-P3-BS	W	DOC	2.3	1.5	mg/L	J	be
N01-E17-TNBS-P1-AS	W	DOC	0.76	0.3	mg/L	J	be
N01-E17-TNBS-P1-BS	W	DOC	0.62	0.6	mg/L	J	be
N01-E17-TNBS-P3-AS	W	DOC	0.91	0.6	mg/L	J	be
N01-E17-TNBS-P3-BS	W	DOC	0.98	0.6	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
N01-E18-TARK-P3-XR (6/22/10)	DOC	2.2	1.5	2.4	1.5	N01-E17-TKVK-P1-AS
				2.0	1.5	N01-E17-TKVK-P1-BS
				2.2	1.5	N01-E17-TKVK-P3-AS
				2.3	1.5	N01-E17-TKVK-P3-BS
				0.76	0.3	N01-E17-TNBS-P1-AS
				0.62	0.6	N01-E17-TNBS-P1-BS
				0.91	0.6	N01-E17-TNBS-P3-AS
				0.98	0.6	N01-E17-TNBS-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel
Preliminary Draft – For Discussion Purposes Only

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10060351		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 17, 2010
Reviewed by	Lisa Krowitz/AECOM	File: 10060351 June LPR PWCM Routine POC DOC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on June 22, 2010.

SDG	Client Sample ID	Matrix
10060351	10A-E18-T135-P1-AS	Aqueous
	10A-E18-T135-P1-BS	Aqueous
	10A-E18-T135-P1-XR (equipment blank collected 6/22/10)	Aqueous
	10A-E18-T135-P3-AS	Aqueous
	10A-E18-T135-P3-AT (field duplicate of 10A-E18-T135-P3-AS)	Aqueous
	10A-E18-T135-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic CarbonCarbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations		Ö	
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E18-T135-P1-XR, collected on 6/22/2010 and reported in SDG 10060351 is associated with all samples collected 6/21/2010 through 6/27/2010. No POC or DOC was detected above the QL in the EB.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E18-T135-P1-XR	W	POC		1.0	mg/L	UJ	c

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- The result column will be empty where the sample result was nondetect

Attachment A

Nonconformance Summary Tables

Table A-1 – Calibration Recovery

ICV/CCV	Analyte	Standard ppm C	Result (ppm C)	Recovery (%)
CCV #4	POC	13000	13550	104
CCV #5			13520	104
CCV #6			13700	105
Affected Sample:	10A-E18-T135-P1-XR			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel
Preliminary Draft – For Discussion Purposes Only

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10060352		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 17, 2010
Reviewed by	Lisa Krowitz/AECOM	File: 100603452June LPR PWCM Routine POC DOC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on June 22, 2010.

SDG	Client Sample ID	Matrix
10060352	10A-E17-T067-P1-AS	Aqueous
	10A-E17-T067-P1-BS	Aqueous
	10A-E17-T067-P3-AS	Aqueous
	10A-E17-T067-P3-BS	Aqueous
	10A-E17-T067-P3-BT (field duplicate of 10A-E17-T067-P3-BS)	Aqueous
	10A-E17-T102-P1-AS	Aqueous
	10A-E17-T102-P1-BS	Aqueous
	10A-E17-T102-P3-AS	Aqueous
	10A-E17-T102-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic CarbonCarbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results		Ö	
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E18-T135-P1-XR, collected on 6/22/2010 and reported in SDG 10060351 is associated with all samples collected 6/21/2010 through 6/27/2010. No POC or DOC was detected above the QL in the EB.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL). The RPD for sample 10A-E17-T102-P3-BS (40%) exceeded the criteria and was qualified as estimated (J).

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E17-T102-P3-BS	W	POC	5.2	1.0	mg/L	J	ld

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Laboratory Duplicate RPD

Sample ID	Duplicate ID	Analyte	Sample Result	Duplicate Result	QL	Units	RPD (%)
10060352-06A*	10060352-06B	POC	4.3	6.1	1.0	mg/L	35
Associated Sample: 10A-E17-T102-P3-BS							

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel
Preliminary Draft – For Discussion Purposes Only

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10060353		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 23, 2010
Reviewed by	Lisa Krowitz/AECOM	File: 10060353 June LPR PWCM Routine POC DOC .doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on June 22, 2010.

SDG	Client Sample ID	Matrix
10060353	10A-E17-T014-P1-AS	Aqueous
	10A-E17-T014-P1-BS	Aqueous
	10A-E17-T014-P3-AS	Aqueous
	10A-E17-T014-P3-BS	Aqueous
	10A-E17-T135-P1-AS	Aqueous
	10A-E17-T135-P1-BS	Aqueous
	10A-E17-T135-P3-AS	Aqueous
	10A-E17-T135-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic CarbonCarbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E18-T135-P1-XR, collected on 6/22/2010 and reported in SDG 10060351 is associated with all samples collected 6/21/2010 through 6/27/2010. No POC or DOC was detected above the QL in the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No sample results were qualified as a result of validation actions.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Newark Bay Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10060354		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 27, 2010
Reviewed by	Lisa Krowitz/AECOM	File: 10060354 June NB PWCM POC DOC .doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on June 22, 2010.

SDG	Client Sample ID	Matrix
10060354	N01-E18-TARK-P1-AS	Aqueous
	N01-E18-TARK-P1-BS	Aqueous
	N01-E18-TARK-P3-AS	Aqueous
	N01-E18-TARK-P3-BS	Aqueous
	N01-E18-TARK-P3-XR (equipment blank collected 6/22/10)	Aqueous
	N01-E18-TNBN-P1-AS	Aqueous
	N01-E18-TNBN-P1-BS	Aqueous
	N01-E18-TNBN-P3-AS	Aqueous
	N01-E18-TNBN-P3-AT (Field duplicate of N01-E18-TNBN-P3-AS)	Aqueous
10060354	N01-E18-TNBN-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB N01-E18-TARK-P3-XR, collected on 6/22/2010 and reported in SDG 10060354 is associated with all samples collected 6/21/2010 through 6/27/2010. No POC was detected > the RL in the EB.

Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

DOC was detected > QL (2.2 mg/L) in the EB. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 20% (if both results were greater than ten times the QL) for DOC and POC. The RPD for field duplicate pair N01-E18-TNBN-P3-AS/ N01-E18-TNBN-P3-AT exceeded the ≤ 20% criteria (32.6%). Since the sample and duplicate results were each < 5 x the QL, precision was deemed acceptable.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E18-TARK-P1-AS	W	DOC	2.4	1.5	mg/L	J	be
N01-E18-TARK-P1-BS	W	DOC	2.9	1.5	mg/L	J	be
N01-E18-TARK-P3-AS	W	DOC	2.1	1.5	mg/L	J	be
N01-E18-TARK-P3-BS	W	DOC	2.4	1.5	mg/L	J	be
N01-E18-TNBN-P1-AS	W	DOC	0.87	0.6	mg/L	J	be
N01-E18-TNBN-P1-BS	W	DOC	2.8	1.5	mg/L	J	be
N01-E18-TNBN-P3-AS	W	DOC	1.8	1.5	mg/L	J	be
N01-E18-TNBN-P3-AT	W	DOC	2.5	1.5	mg/L	J	be
N01-E18-TNBN-P3-BS	W	DOC	2.8	1.5	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
N01-E18-TARK-P3-XR (6/22/10)	DOC	2.2	1.5	2.4	1.5	N01-E18-TARK-P1-AS
				2.9	1.5	N01-E18-TARK-P1-BS
				2.1	1.5	N01-E18-TARK-P3-AS
				2.4	1.5	N01-E18-TARK-P3-BS
				0.87	0.6	N01-E18-TNBN-P1-AS
				2.8	1.5	N01-E18-TNBN-P1-BS
				1.8	1.5	N01-E18-TNBN-P3-AS
				2.5	1.5	N01-E18-TNBN-P3-AT
				2.8	1.5	N01-E18-TNBN-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Newark Bay Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10060355		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 27, 2010
Reviewed by	Lisa Krowitz/AECOM	File: 10060355 June NB PWCM POC DOC .doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on June 22, 2010.

SDG	Client Sample ID	Matrix
10060355	N01-E18-TKVK-P1-AS	Aqueous
	N01-E18-TKVK-P1-BS	Aqueous
	N01-E18-TKVK-P3-AS	Aqueous
	N01-E18-TKVK-P3-BS	Aqueous
	N01-E18-TNBS-P1-AS	Aqueous
	N01-E18-TNBS-P1-BS	Aqueous
	N01-E18-TNBS-P3-AS	Aqueous
	N01-E18-TNBS-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity		Ö	
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB N01-E18-TARK-P3-XR, collected on 6/22/2010 and reported in SDG 10060354 is associated with all samples collected 6/21/2010 through 6/27/2010. No POC was detected > the RL in the EB.

Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

DOC was detected > QL (2.2 mg/L) in the EB. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E18-TKVK-P1-AS	W	DOC	0.90	0.6	mg/L	J	be
N01-E18-TKVK-P1-BS	W	DOC	0.77	0.6	mg/L	J	be
N01-E18-TKVK-P3-AS	W	DOC	0.87	0.6	mg/L	J	be
N01-E18-TKVK-P3-BS	W	DOC	0.88	0.6	mg/L	J	be
N01-E18-TNBS-P1-AS	W	DOC	2.3	1.5	mg/L	J	be
N01-E18-TNBS-P1-BS	W	DOC	2.6	1.5	mg/L	J	be
N01-E18-TNBS-P3-AS	W	DOC	2.0	1.5	mg/L	J	be
N01-E18-TNBS-P3-BS	W	DOC	2.3	1.5	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
N01-E18-TARK-P3-XR (6/22/10)	DOC	2.2	1.5	0.90	0.6	N01-E18-TKVK-P1-AS
				0.77	0.6	N01-E18-TKVK-P1-BS
				0.87	0.6	N01-E18-TKVK-P3-AS
				0.88	0.6	N01-E18-TKVK-P3-BS
				2.3	1.5	N01-E18-TNBS-P1-AS
				2.6	1.5	N01-E18-TNBS-P1-BS
				2.0	1.5	N01-E18-TNBS-P3-AS
				2.3	1.5	N01-E18-TNBS-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Newark Bay Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10060359		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 23, 2010
Reviewed by	Lisa Krowitz/AECOM	File: 10060359 June NB PWCM Routine POC DOC .doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on June 22, 2010.

SDG	Client Sample ID	Matrix
10060359	N01-E18-THKN-P1-BS	Aqueous
	N01-E18-THKN-P1-AS	Aqueous
	N01-E18-THKN-P3-AS	Aqueous
	N01-E18-THKN-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic CarbonCarbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB N01-E18-TARK-P3-XR, collected on 6/22/2010 and reported in SDG 10060354 is associated with all samples collected 6/21/2010 through 6/27/2010. No POC was detected > the RL in the EB.

Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

DOC was detected > QL (2.2 mg/L) in the EB. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than five times the QL). The RPD for laboratory duplicate analysis of sample N01-E18-THKN-P3-BS (27%) exceeded the criteria. Precision was deemed acceptable since the sample and duplicate results were both < 5x the QL

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E18-THKN-P1-BS	W	DOC	4.0	1.5	mg/L	J	be
N01-E18-THKN-P1-AS	W	DOC	4.5	1.5	mg/L	J	be
N01-E18-THKN-P3-AS	W	DOC	3.1	1.5	mg/L	J	be
N01-E18-THKN-P3-BS	W	DOC	3.2	1.5	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
N01-E18-TARK-P3-XR (6/22/10)	DOC	2.2	1.5	4.0	1.5	N01-E18-THKN-P1-BS
				4.5	1.5	N01-E18-THKN-P1-AS
				3.1	1.5	N01-E18-THKN-P3-AS
				3.2	1.5	N01-E18-THKN-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Newark Bay Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10060360		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 27, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: 10060360 June NB PWCM POC DOC .doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on June 22, 2010.

SDG	Client Sample ID	Matrix
10060360	N01-E17-THKN-P1-AS	Aqueous
	N01-E17-THKN-P1-BS	Aqueous
	N01-E17-THKN-P3-AS	Aqueous
	N01-E17-THKN-P3-AT (Field duplicate of sample N01-E17-THKN-P3-AS)	Aqueous
	N01-E17-THKN-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB N01-E18-TARK-P3-XR, collected on 6/22/2010 and reported in SDG 10060354 is associated with all samples collected 6/21/2010 through 6/27/2010. No POC was detected > the RL in the EB.

Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

DOC was detected > QL (2.2 mg/L) in the EB. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E17-THKN-P1-AS	W	DOC	3.3	1.5	mg/L	J	be
N01-E17-THKN-P1-BS	W	DOC	2.8	1.5	mg/L	J	be
N01-E17-THKN-P3-AS	W	DOC	2.1	1.5	mg/L	J	be
N01-E17-THKN-P3-AT	W	DOC	2.2	1.5	mg/L	J	be
N01-E17-THKN-P3-BS	W	DOC	2.3	1.5	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
N01-E18-TARK-P3-XR (6/22/10)	DOC	2.2	1.5	3.3	1.5	N01-E17-THKN-P1-AS
				2.8	1.5	N01-E17-THKN-P1-BS
				2.1	1.5	N01-E17-THKN-P3-AS
				2.2	1.5	N01-E17-THKN-P3-AT
				2.3	1.5	N01-E17-THKN-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel
Preliminary Draft – For Discussion Purposes Only

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Routine Sampling Events	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10060381, 10060383, 10060385, 10060386, 10060388		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited (All SDGs except 10060386) Full (10060386 only)		
AECOM Project Number	60145884.A407		

Prepared by	Sharon McKechnie/AECOM	Completed September 7, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: June Routine SSC 5 SDGs.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on June 22, 2010.

SDG	Client Sample ID	Matrix
10060381	10A-E18-T014-P1-AS	Aqueous
	10A-E18-T014-P1-BS	Aqueous
	10A-E18-T014-P2-AS	Aqueous
	10A-E18-T014-P2-BS	Aqueous
	10A-E18-T014-P3-AS	Aqueous
	10A-E18-T014-P3-BS	Aqueous
	10A-E18-T042-P1-AS	Aqueous
	10A-E18-T042-P1-BS	Aqueous
	10A-E18-T042-P2-AS	Aqueous
	10A-E18-T042-P2-BS	Aqueous
	10A-E18-T042-P3-AS	Aqueous
	10A-E18-T042-P3-BS	Aqueous

SDG	Client Sample ID	Matrix
10060383	10A-E15-T175-P2-AS	Aqueous
10060383	10A-E15-T175-P2-BS	Aqueous
	10A-E15-T175-P2-BT (Field duplicate of 10A-E15-T175-P2-BS)	Aqueous
	10A-E18-T135-P1-AS	Aqueous
	10A-E18-T135-P1-BS	Aqueous
	10A-E18-T135-P1-XR (Equipment blank collected 6/22/10)	Aqueous
	10A-E18-T135-P2-AS	Aqueous
	10A-E18-T135-P2-BS	Aqueous
	10A-E18-T135-P3-AS	Aqueous
	10A-E18-T135-P3-BS	Aqueous
10060385	10A-E17-T067-P1-AS	Aqueous
	10A-E17-T067-P1-BS	Aqueous
	10A-E17-T067-P2-AS	Aqueous
	10A-E17-T067-P2-BS	Aqueous
	10A-E17-T067-P3-AS	Aqueous
	10A-E17-T067-P3-BS	Aqueous
	10A-E17-T102-P1-AS	Aqueous
	10A-E17-T102-P1-BS	Aqueous
	10A-E17-T102-P2-AS	Aqueous
	10A-E17-T102-P2-BS	Aqueous
	10A-E17-T102-P3-AS	Aqueous
	10A-E17-T102-P3-BS	Aqueous
	10A-E17-T102-P3-BT (Field duplicate of 10A-E17-T102-P3-BS)	Aqueous
10060386	10A-E17-T014-P1-AS	Aqueous
	10A-E17-T014-P1-BS	Aqueous
	10A-E17-T014-P2-AS	Aqueous
	10A-E17-T014-P2-BS	Aqueous
	10A-E17-T014-P3-AS	Aqueous
	10A-E17-T014-P3-BS	Aqueous
	10A-E17-T135-P1-AS	Aqueous
	10A-E17-T135-P1-BS	Aqueous
	10A-E17-T135-P2-AS	Aqueous
	10A-E17-T135-P2-BS	Aqueous
	10A-E17-T135-P3-AS	Aqueous
	10A-E17-T135-P3-BS	Aqueous
10060388	10A-E18-T067-P3-AS	Aqueous
	10A-E18-T067-P1-BS	Aqueous
	10A-E18-T067-P2-AS	Aqueous
	10A-E18-T067-P2-BS	Aqueous

SDG	Client Sample ID	Matrix
	10A-E18-T067-P3-BS	Aqueous
10060388	10A-E18-T067-P1-AS	Aqueous
	10A-E18-T102-P3-AS	Aqueous
	10A-E18-T102-P1-BS	Aqueous
	10A-E18-T102-P2-BS	Aqueous
	10A-E18-T102-P2-AS	Aqueous
	10A-E18-T102-P3-BS	Aqueous
	10A-E18-T102-P1-AS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes:			

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E18-T135-P1-XR, collected on 6/22/2010 and reported in SDG 10060383 is associated with all samples collected 6/21/2010 through 6/27/2010.

Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

SSC was detected > QL (6 mg/L) in the EB. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E18-T014-P1-AS	W	SSC	8	1	mg/L	J	be
10A-E18-T014-P1-BS	W	SSC	21	1	mg/L	J	be
10A-E18-T014-P2-AS	W	SSC	6	1	mg/L	J	h,be
10A-E18-T014-P2-BS	W	SSC	19	1	mg/L	J	h,be
10A-E18-T014-P3-AS	W	SSC	7	1	mg/L	J	be
10A-E18-T014-P3-BS	W	SSC	13	1	mg/L	J	be
10A-E18-T042-P1-AS	W	SSC	13	1	mg/L	J	be
10A-E18-T042-P2-AS	W	SSC	15	1	mg/L	J	h,be
10A-E18-T042-P2-BS	W	SSC	79	1	mg/L	J	h
10A-E18-T042-P3-AS	W	SSC	19	1	mg/L	J	be
10A-E18-T042-P3-BS	W	SSC	27	1	mg/L	J	be
10A-E15-T175-P2-AS	W	SSC	12	1	mg/L	J	h,be
10A-E15-T175-P2-BS	W	SSC	20	1	mg/L	J	h,be
10A-E15-T175-P2-BT	W	SSC	15	1	mg/L	J	h,be
10A-E18-T135-P1-AS	W	SSC	18	1	mg/L	J	h,be
10A-E18-T135-P1-BS	W	SSC	20	1	mg/L	J	h,be
10A-E18-T135-P1-XR	W	SSC	6	1	mg/L	J	h
10A-E18-T135-P2-AS	W	SSC	13	1	mg/L	J	h,be
10A-E18-T135-P2-BS	W	SSC	14	1	mg/L	J	h,be
10A-E18-T135-P3-AS	W	SSC	13	1	mg/L	J	h,be
10A-E18-T135-P3-BS	W	SSC	20	1	mg/L	J	h,be
10A-E17-T067-P1-AS	W	SSC	20	1	mg/L	J	h,be
10A-E17-T067-P1-BS	W	SSC	37	1	mg/L	J	h,be
10A-E17-T067-P2-AS	W	SSC	20	1	mg/L	J	h,be
10A-E17-T067-P2-BS	W	SSC	27	1	mg/L	J	h,be
10A-E17-T067-P3-AS	W	SSC	22	1	mg/L	J	h,be
10A-E17-T067-P3-BS	W	SSC	32	1	mg/L	J	h,be
10A-E17-T102-P1-AS	W	SSC	34	1	mg/L	J	h,be
10A-E17-T102-P1-BS	W	SSC	46	1	mg/L	J	h,be
10A-E17-T102-P2-AS	W	SSC	34	1	mg/L	J	h,be
10A-E17-T102-P2-BS	W	SSC	33	1	mg/L	J	h,be
10A-E17-T102-P3-AS	W	SSC	36	1	mg/L	J	h,be
10A-E17-T102-P3-BS	W	SSC	39	1	mg/L	J	h,be
10A-E17-T102-P3-BT	W	SSC	38	1	mg/L	J	h,be
10A-E17-T014-P1-AS	W	SSC	16	1	mg/L	J	h,be
10A-E17-T014-P1-BS	W	SSC	10	1	mg/L	J	h,be
10A-E17-T014-P2-AS	W	SSC	24	1	mg/L	J	h,be
10A-E17-T014-P2-BS	W	SSC	11	1	mg/L	J	h,be
10A-E17-T014-P3-AS	W	SSC	10	1	mg/L	J	h,be
10A-E17-T014-P3-BS	W	SSC	9	1	mg/L	J	h,be
10A-E17-T135-P1-AS	W	SSC	17	1	mg/L	J	h,be
10A-E17-T135-P1-BS	W	SSC	27	1	mg/L	J	h,be
10A-E17-T135-P2-AS	W	SSC	16	1	mg/L	J	h,be
10A-E17-T135-P2-BS	W	SSC	27	1	mg/L	J	h,be
10A-E17-T135-P3-AS	W	SSC	18	1	mg/L	J	h,be
10A-E17-T135-P3-BS	W	SSC	25	1	mg/L	J	h,be

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E18-T067-P3-AS	W	SSC	52	1	mg/L	J	h,be
10A-E18-T067-P1-BS	W	SSC	106	1	mg/L	J	h
10A-E18-T067-P2-AS	W	SSC	45	1	mg/L	J	h,be
10A-E18-T067-P2-BS	W	SSC	87	1	mg/L	J	h
10A-E18-T067-P3-BS	W	SSC	99	1	mg/L	J	h
10A-E18-T067-P1-AS	W	SSC	53	1	mg/L	J	h,be
10A-E18-T102-P3-AS	W	SSC	35	1	mg/L	J	h,be
10A-E18-T102-P1-BS	W	SSC	105	1	mg/L	J	h
10A-E18-T102-P2-BS	W	SSC	82	1	mg/L	J	h
10A-E18-T102-P2-AS	W	SSC	43	1	mg/L	J	h,be
10A-E18-T102-P3-BS	W	SSC	82	1	mg/L	J	h
10A-E18-T102-P1-AS	W	SSC	57	1	mg/L	J	h,be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E18-T014-P2-AS	SSC	34-60	28
10A-E18-T014-P2-BS			
10A-E18-T042-P2-AS			
10A-E18-T042-P2-BS			
10A-E15-T175-P2-AS			
10A-E15-T175-P2-BS			
10A-E15-T175-P2-BT			
10A-E18-T135-P1-AS			
10A-E18-T135-P1-BS			
10A-E18-T135-P1-XR			
10A-E18-T135-P2-AS			
10A-E18-T135-P2-BS			
10A-E18-T135-P3-AS			
10A-E18-T135-P3-BS			
10A-E17-T067-P1-AS			
10A-E17-T067-P1-BS			
10A-E17-T067-P2-AS			
10A-E17-T067-P2-BS			
10A-E17-T067-P3-AS			
10A-E17-T067-P3-BS			
10A-E17-T102-P1-AS			
10A-E17-T102-P1-BS			
10A-E17-T102-P2-AS			
10A-E17-T102-P2-BS			
10A-E17-T102-P3-AS			
10A-E17-T102-P3-BS			
10A-E17-T102-P3-BT			
10A-E17-T014-P1-AS			
10A-E17-T014-P1-BS			
10A-E17-T014-P2-AS			
10A-E17-T014-P2-BS			
10A-E17-T014-P3-AS			
10A-E17-T014-P3-BS			
10A-E17-T135-P1-AS			
10A-E17-T135-P1-BS			
10A-E17-T135-P2-AS			
10A-E17-T135-P2-BS			
10A-E17-T135-P3-AS			
10A-E17-T135-P3-BS			
10A-E18-T067-P3-AS			
10A-E18-T067-P1-BS			
10A-E18-T067-P2-AS			
10A-E18-T067-P2-BS			
10A-E18-T067-P3-BS			
10A-E18-T067-P1-AS			

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E18-T102-P3-AS	SSC	34-60	28
10A-E18-T102-P1-BS			
10A-E18-T102-P2-BS			
10A-E18-T102-P2-AS			
10A-E18-T102-P3-BS			
10A-E18-T102-P1-AS			

Table A-2 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E18-T135-P1-XR (6/22/10)	SSC	6	1.0	8	1.0	10A-E18-T014-P1-AS
				21	1.0	10A-E18-T014-P1-BS
				6	1.0	10A-E18-T014-P2-AS
				19	1.0	10A-E18-T014-P2-BS
				7	1.0	10A-E18-T014-P3-AS
				13	1.0	10A-E18-T014-P3-BS
				13	1.0	10A-E18-T042-P1-AS
				15	1.0	10A-E18-T042-P2-AS
				79	1.0	10A-E18-T042-P2-BS
				19	1.0	10A-E18-T042-P3-AS
				27	1.0	10A-E18-T042-P3-BS
				12	1.0	10A-E15-T175-P2-AS
				20	1.0	10A-E15-T175-P2-BS
				15	1.0	10A-E15-T175-P2-BT
				18	1.0	10A-E18-T135-P1-AS
				20	1.0	10A-E18-T135-P1-BS
				13	1.0	10A-E18-T135-P2-AS
				14	1.0	10A-E18-T135-P2-BS
				13	1.0	10A-E18-T135-P3-AS
				20	1.0	10A-E18-T135-P3-BS
				20	1.0	10A-E17-T067-P1-AS
				37	1.0	10A-E17-T067-P1-BS
				20	1.0	10A-E17-T067-P2-AS
				27	1.0	10A-E17-T067-P2-BS
				22	1.0	10A-E17-T067-P3-AS
				32	1.0	10A-E17-T067-P3-BS
				34	1.0	10A-E17-T102-P1-AS
				46	1.0	10A-E17-T102-P1-BS
				34	1.0	10A-E17-T102-P2-AS
				33	1.0	10A-E17-T102-P2-BS
				36	1.0	10A-E17-T102-P3-AS
				39	1.0	10A-E17-T102-P3-BS

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
10A-E18-T135-P1-XR (6/22/10)	SSC	6	1.0	38	1.0	10A-E17-T102-P3-BT
				16	1.0	10A-E17-T014-P1-AS
				10	1.0	10A-E17-T014-P1-BS
				24	1.0	10A-E17-T014-P2-AS
				11	1.0	10A-E17-T014-P2-BS
				10	1.0	10A-E17-T014-P3-AS
				9	1.0	10A-E17-T014-P3-BS
				17	1.0	10A-E17-T135-P1-AS
				27	1.0	10A-E17-T135-P1-BS
				16	1.0	10A-E17-T135-P2-AS
				27	1.0	10A-E17-T135-P2-BS
				18	1.0	10A-E17-T135-P3-AS
				25	1.0	10A-E17-T135-P3-BS
				52	1.0	10A-E18-T067-P3-AS
				45	1.0	10A-E18-T067-P2-AS
				53	1.0	10A-E18-T067-P1-AS
				35	1.0	10A-E18-T102-P3-AS
				43	1.0	10A-E18-T102-P2-AS
				57	1.0	10A-E18-T102-P1-AS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection June Newark Bay Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10060359 and 10060360		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60144462.A410		

Prepared by	Sharon McKechnie/AECOM	Completed September 14, 2010
Reviewed by	Lisa Krowitz/AECOM	File:June NB PWCM 1060359 & 360 SSC.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on June 22, 2010.

SDG	Client Sample ID	Matrix
10060359	N01-E18-THKN-P1-AS	Aqueous
	N01-E18-THKN-P1-BS	Aqueous
	N01-E18-THKN-P2-AS	Aqueous
	N01-E18-THKN-P2-BS	Aqueous
	N01-E18-THKN-P3-AS	Aqueous
	N01-E18-THKN-P3-BS	Aqueous
10060360	N01-E17-THKN-P1-AS	Aqueous
	N01-E17-THKN-P1-BS	Aqueous
	N01-E17-THKN-P2-AS	Aqueous
	N01-E17-THKN-P2-BS	Aqueous
	N01-E17-THKN-P3-AS	Aqueous
	N01-E17-THKN-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB N01-E18-TARK-P3-XR, collected on 6/22/2010 and reported in SDG 10060387 is associated with all samples collected 6/21/2010 through 6/27/2010. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

SSC was detected (3 mg/L) >quantitation limit (QL) in EB N01-E18-TARK-P3-XR. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E18-THKN-P1-AS	W	SSC	8	1	mg/L	J	be
N01-E18-THKN-P1-BS	W	SSC	22	1	mg/L	J	be
N01-E18-THKN-P2-AS	W	SSC	9	1	mg/L	J	be
N01-E18-THKN-P2-BS	W	SSC	25	1	mg/L	J	be
N01-E18-THKN-P3-AS	W	SSC	7	1	mg/L	J	be
N01-E18-THKN-P3-BS	W	SSC	24	1	mg/L	J	be
N01-E17-THKN-P1-AS	W	SSC	14	1	mg/L	J	be
N01-E17-THKN-P1-BS	W	SSC	9	1	mg/L	J	be
N01-E17-THKN-P2-AS	W	SSC	10	1	mg/L	J	be
N01-E17-THKN-P2-BS	W	SSC	8	1	mg/L	J	be
N01-E17-THKN-P3-AS	W	SSC	9	1	mg/L	J	be
N01-E17-THKN-P3-BS	W	SSC	8	1	mg/L	J	be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
N01-E18-TARK-P3-XR	SSC	3	1	8	1	N01-E18-THKN-P1-AS
				22	1	N01-E18-THKN-P1-BS
				9	1	N01-E18-THKN-P2-AS
				25	1	N01-E18-THKN-P2-BS
				7	1	N01-E18-THKN-P3-AS
				24	1	N01-E18-THKN-P3-BS
				14	1	N01-E17-THKN-P1-AS
				9	1	N01-E17-THKN-P1-BS
				10	1	N01-E17-THKN-P2-AS
				8	1	N01-E17-THKN-P2-BS
				9	1	N01-E17-THKN-P3-AS
				8	1	N01-E17-THKN-P3-BS

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay June Sampling Events	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10060379, 10060380, 10060382, 10060384, 10060387		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited (All SDGs except 10060379) Full (10060379 only)		
AECOM Project Number	60144462-A410		

Prepared by	Sharon McKechnie/AECOM	Completed September 7, 2010
Reviewed by	Lisa Krowitz/AECOM	File Name: June Newark Bay SSC 5 SDGs.doc

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on June 22, 2010.

SDG	Client Sample ID	Matrix
10060379	N01-E18-TKVK-P1-AS	Aqueous
	N01-E18-TKVK-P1-BS	Aqueous
	N01-E18-TKVK-P2-AS	Aqueous
	N01-E18-TKVK-P2-BS	Aqueous
	N01-E18-TKVK-P3-AS	Aqueous
	N01-E18-TKVK-P3-BS	Aqueous
	N01-E18-TNBN-P3-BT (Field duplicate of N01-E18-TNBN-P3-BS)	Aqueous
	N01-E18-TNBS-P1-AS	Aqueous
	N01-E18-TNBS-P1-BS	Aqueous
	N01-E18-TNBS-P2-AS	Aqueous
	N01-E18-TNBS-P2-BS	Aqueous
	N01-E18-TNBS-P3-AS	Aqueous
10060379	N01-E18-TNBS-P3-BS	Aqueous

SDG	Client Sample ID	Matrix
10060380	N01-E15-THKN-P1-BS	Aqueous
	N01-E17-TNBN-P3-AS	Aqueous
	N01-E17-TNBN-P3-BS	Aqueous
10060382	N01-E17-TKVK-P1-AS	Aqueous
	N01-E17-TKVK-P1-BS	Aqueous
	N01-E17-TKVK-P2-AS	Aqueous
	N01-E17-TKVK-P2-BS	Aqueous
	N01-E17-TKVK-P3-AS	Aqueous
	N01-E17-TKVK-P3-BS	Aqueous
	N01-E17-TNBS-P1-AS	Aqueous
	N01-E17-TNBS-P1-BS	Aqueous
	N01-E17-TNBS-P2-AS	Aqueous
	N01-E17-TNBS-P2-BS	Aqueous
	N01-E17-TNBS-P3-AS	Aqueous
	N01-E17-TNBS-P3-BS	Aqueous
	N01-E17-TNBS-P3-BT (Field duplicate of N01-E17-TNBS-P3-BS)	Aqueous
10060384	N01-E15-THKN-P1-AS	Aqueous
	N01-E17-TARK-P1-AS	Aqueous
	N01-E17-TARK-P1-BS	Aqueous
	N01-E17-TARK-P2-AS	Aqueous
	N01-E17-TARK-P2-BS	Aqueous
	N01-E17-TARK-P3-AS	Aqueous
	N01-E17-TARK-P3-BS	Aqueous
	N01-E17-TNBN-P1-AS	Aqueous
	N01-E17-TNBN-P1-BS	Aqueous
	N01-E17-TNBN-P2-AS	Aqueous
	N01-E17-TNBN-P2-BS	Aqueous
	N01-E19-THKN-P1-AS	Aqueous
	N01-E19-THKN-P1-BS	Aqueous
10060387	N01-E18-TARK-P1-AS	Aqueous
	N01-E18-TARK-P1-BS	Aqueous
	N01-E18-TARK-P1-BT (Field duplicate of N01-E18-TARK-P1-BS)	Aqueous
	N01-E18-TARK-P2-AS	Aqueous
	N01-E18-TARK-P2-BS	Aqueous
	N01-E18-TARK-P3-AS	Aqueous
	N01-E18-TARK-P3-BS	Aqueous
	N01-E18-TARK-P3-XR (Equipment blank collected 6/22/10)	Aqueous
	N01-E18-TNBN-P1-AS	Aqueous
10060387	N01-E18-TNBN-P1-BS	Aqueous

SDG	Client Sample ID	Matrix
	N01-E18-TNBN-P2-AS	Aqueous
	N01-E18-TNBN-P2-BS	Aqueous
	N01-E18-TNBN-P3-AS	Aqueous
	N01-E18-TNBN-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity		Ö	
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results		Ö	
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody. The following discrepancies were noted:

- SDG 10060382: Sample N01-E15-TKVK-P3-BS on the COC should have been N01-E17-TKVK-P3-BS. The error was discovered upon loading the data into the database. The correct sample ID was verified by checking with field staff. No qualifications were necessary on this basis.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB N01-E18-TARK-P3-XR, collected on 6/22/2010 and reported in SDG 10060387 is associated with all samples collected 6/21/2010 through 6/27/2010.

Data qualification on the basis of EB contamination was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

SSC was detected > QL (4 mg/L) in the EB. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC.

Data qualification on the basis of field duplicate RPDs was as follows (see above for acceptance criteria):

Criteria	Action	
	Detected	Nondetected
RPD greater than the acceptance criteria, but < 120% and sample and duplicate results >5x the SQL	J	Not Applicable
RPD ≥ 120%	R	Not Applicable
If sample and/or duplicate is <5x the QL and absolute difference is >2x and ≤ 4x the QL	J	UJ
If the sample and/or duplicate is <5x the QL and absolute difference is >4x the QL.	R	R

Nonconformances are summarized in Attachment A, Table A-3. Qualified sample results are shown in Table 1.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E18-TKVK-P1-AS	W	SSC	15	1	mg/L	J	be
N01-E18-TKVK-P1-BS	W	SSC	36	1	mg/L	J	be
N01-E18-TKVK-P2-AS	W	SSC	14	1	mg/L	J	be
N01-E18-TKVK-P2-BS	W	SSC	12	1	mg/L	J	be
N01-E18-TKVK-P3-AS	W	SSC	8	1	mg/L	J	be
N01-E18-TKVK-P3-BS	W	SSC	10	1	mg/L	J	be
N01-E18-TNBN-P3-BT	W	SSC	6	1	mg/L	J	be
N01-E18-TNBS-P1-AS	W	SSC	8	1	mg/L	J	be
N01-E18-TNBS-P1-BS	W	SSC	6	1	mg/L	J	be
N01-E18-TNBS-P2-AS	W	SSC	8	1	mg/L	J	be
N01-E18-TNBS-P2-BS	W	SSC	6	1	mg/L	J	be
N01-E18-TNBS-P3-AS	W	SSC	10	1	mg/L	J	be
N01-E18-TNBS-P3-BS	W	SSC	5	1	mg/L	J	be
N01-E15-THKN-P1-BS	W	SSC	15	1	mg/L	J	be
N01-E17-TNBN-P3-AS	W	SSC	6	1	mg/L	J	be
N01-E17-TNBN-P3-BS	W	SSC	4	1	mg/L	J	be
N01-E17-TKVK-P1-AS	W	SSC	6	1	mg/L	J	h,be
N01-E17-TKVK-P1-BS	W	SSC	10	1	mg/L	J	h,be
N01-E17-TKVK-P2-AS	W	SSC	5	1	mg/L	J	h,be
N01-E17-TKVK-P2-BS	W	SSC	6	1	mg/L	J	h,be
N01-E17-TKVK-P3-AS	W	SSC	5	1	mg/L	J	h,be
N01-E17-TKVK-P3-BS	W	SSC	7	1	mg/L	J	h,be
N01-E17-TNBS-P1-AS	W	SSC	3	1	mg/L	J	h,be
N01-E17-TNBS-P1-BS	W	SSC	8	1	mg/L	J	h,be
N01-E17-TNBS-P2-AS	W	SSC	4	1	mg/L	J	h,be
N01-E17-TNBS-P2-BS	W	SSC	4	1	mg/L	J	h,be
N01-E17-TNBS-P3-AS	W	SSC	7	1	mg/L	J	h,be
N01-E17-TNBS-P3-BS	W	SSC	3	1	mg/L	J	h,fd,be
N01-E17-TNBS-P3-BT	W	SSC	8	1	mg/L	J	h,fd,be
N01-E15-THKN-P1-AS	W	SSC	11	1	mg/L	J	h,be
N01-E17-TARK-P1-AS	W	SSC	7	1	mg/L	J	h,be
N01-E17-TARK-P1-BS	W	SSC	6	1	mg/L	J	h,be
N01-E17-TARK-P2-AS	W	SSC	5	1	mg/L	J	h,be
N01-E17-TARK-P2-BS	W	SSC	4	1	mg/L	J	h,be
N01-E17-TARK-P3-AS	W	SSC	4	1	mg/L	J	h,be
N01-E17-TARK-P3-BS	W	SSC	5	1	mg/L	J	h,be
N01-E17-TNBN-P1-AS	W	SSC	4	1	mg/L	J	h,be
N01-E17-TNBN-P1-BS	W	SSC	6	1	mg/L	J	h,be
N01-E17-TNBN-P2-AS	W	SSC	5	1	mg/L	J	h,be
N01-E17-TNBN-P2-BS	W	SSC	4	1	mg/L	J	h,be
N01-E19-THKN-P1-AS	W	SSC	8	1	mg/L	J	h,be
N01-E19-THKN-P1-BS	W	SSC	12	1	mg/L	J	h,be
N01-E18-TARK-P1-AS	W	SSC	4	1	mg/L	J	h,be
N01-E18-TARK-P1-BS	W	SSC	4	1	mg/L	J	h,be
N01-E18-TARK-P1-BT	W	SSC	4	1	mg/L	J	h,be
N01-E18-TARK-P2-AS	W	SSC	3	1	mg/L	J	h,be

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E18-TARK-P2-BS	W	SSC	6	1	mg/L	J	h,be
N01-E18-TARK-P3-AS	W	SSC	5	1	mg/L	J	h,be
N01-E18-TARK-P3-BS	W	SSC	4	1	mg/L	J	h,be
N01-E18-TARK-P3-XR	W	SSC	3	1	mg/L	J	h
N01-E18-TNBN-P1-AS	W	SSC	22	1	mg/L	J	h,be
N01-E18-TNBN-P1-BS	W	SSC	13	1	mg/L	J	h,be
N01-E18-TNBN-P2-AS	W	SSC	9	1	mg/L	J	h,be
N01-E18-TNBN-P2-BS	W	SSC	4	1	mg/L	J	h,be
N01-E18-TNBN-P3-AS	W	SSC	6	1	mg/L	J	h,be
N01-E18-TNBN-P3-BS	W	SSC	6	1	mg/L	J	h,be

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E17-TKVK-P1-AS	SSC	34-42	28
N01-E17-TKVK-P1-BS			
N01-E17-TKVK-P2-AS			
N01-E17-TKVK-P2-BS			
N01-E17-TKVK-P3-AS			
N01-E17-TKVK-P3-BS			
N01-E17-TNBS-P1-AS			
N01-E17-TNBS-P1-BS			
N01-E17-TNBS-P2-AS			
N01-E17-TNBS-P2-BS			
N01-E17-TNBS-P3-AS			
N01-E17-TNBS-P3-BS			
N01-E17-TNBS-P3-BT			
N01-E15-THKN-P1-AS			
N01-E17-TARK-P1-AS			
N01-E17-TARK-P1-BS			
N01-E17-TARK-P2-AS			
N01-E17-TARK-P2-BS			
N01-E17-TARK-P3-AS			
N01-E17-TARK-P3-BS			
N01-E17-TNBN-P1-AS			
N01-E17-TNBN-P1-BS			
N01-E17-TNBN-P2-AS			
N01-E17-TNBN-P2-BS			
N01-E19-THKN-P1-AS			
N01-E19-THKN-P1-BS			
N01-E18-TARK-P1-AS			
N01-E18-TARK-P1-BS			
N01-E18-TARK-P1-BT			
N01-E18-TARK-P2-AS			
N01-E18-TARK-P2-BS			
N01-E18-TARK-P3-AS			
N01-E18-TARK-P3-BS			
N01-E18-TARK-P3-XR			
N01-E18-TNBN-P1-AS			
N01-E18-TNBN-P1-BS			
N01-E18-TNBN-P2-AS			
N01-E18-TNBN-P2-BS			
N01-E18-TNBN-P3-AS			
N01-E18-TNBN-P3-BS			

Table A-2 – Equipment Blanks

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
N01-E18-TARK-P3-XR (6/22/10)	SSC	4	1.0	15	1.0	N01-E18-TKVK-P1-AS
				36	1.0	N01-E18-TKVK-P1-BS
				14	1.0	N01-E18-TKVK-P2-AS
				12	1.0	N01-E18-TKVK-P2-BS
				8	1.0	N01-E18-TKVK-P3-AS
				10	1.0	N01-E18-TKVK-P3-BS
				6	1.0	N01-E18-TNBN-P3-BT
				8	1.0	N01-E18-TNBS-P1-AS
				6	1.0	N01-E18-TNBS-P1-BS
				8	1.0	N01-E18-TNBS-P2-AS
				6	1.0	N01-E18-TNBS-P2-BS
				10	1.0	N01-E18-TNBS-P3-AS
				5	1.0	N01-E18-TNBS-P3-BS
				15	1.0	N01-E15-THKN-P1-BS
				6	1.0	N01-E17-TNBN-P3-AS
				4	1.0	N01-E17-TNBN-P3-BS
				6	1.0	N01-E17-TKVK-P1-AS
				10	1.0	N01-E17-TKVK-P1-BS
				5	1.0	N01-E17-TKVK-P2-AS
				6	1.0	N01-E17-TKVK-P2-BS
				5	1.0	N01-E17-TKVK-P3-AS
				7	1.0	N01-E17-TKVK-P3-BS
				3	1.0	N01-E17-TNBS-P1-AS
				8	1.0	N01-E17-TNBS-P1-BS
				4	1.0	N01-E17-TNBS-P2-AS
				4	1.0	N01-E17-TNBS-P2-BS
				7	1.0	N01-E17-TNBS-P3-AS
				3	1.0	N01-E17-TNBS-P3-BS
				8	1.0	N01-E17-TNBS-P3-BT
				11	1.0	N01-E15-THKN-P1-AS
				7	1.0	N01-E17-TARK-P1-AS
				6	1.0	N01-E17-TARK-P1-BS
				5	1.0	N01-E17-TARK-P2-AS
				4	1.0	N01-E17-TARK-P2-BS
				4	1.0	N01-E17-TARK-P3-AS
				5	1.0	N01-E17-TARK-P3-BS
				4	1.0	N01-E17-TNBN-P1-AS
				6	1.0	N01-E17-TNBN-P1-BS
				5	1.0	N01-E17-TNBN-P2-AS
				4	1.0	N01-E17-TNBN-P2-BS
				8	1.0	N01-E19-THKN-P1-AS
				12	1.0	N01-E19-THKN-P1-BS
				4	1.0	N01-E18-TARK-P1-AS
				4	1.0	N01-E18-TARK-P1-BS
				4	1.0	N01-E18-TARK-P1-BT

Blank ID	Analyte	Highest Blank Concentration (mg/L)	QL for Blank (mg/L)	Sample Result (mg/L)	Sample QL (mg/L)	Associated Samples
N01-E18-TARK-P3-XR (6/22/10)	SSC	4	1.0	3	1.0	N01-E18-TARK-P2-AS
				6	1.0	N01-E18-TARK-P2-BS
				5	1.0	N01-E18-TARK-P3-AS
				4	1.0	N01-E18-TARK-P3-BS
				22	1.0	N01-E18-TNBN-P1-AS
				13	1.0	N01-E18-TNBN-P1-BS
				9	1.0	N01-E18-TNBN-P2-AS
				4	1.0	N01-E18-TNBN-P2-BS
				6	1.0	N01-E18-TNBN-P3-AS
				6	1.0	N01-E18-TNBN-P3-BS

Table A-3 – Field Duplicate

Sample ID	Duplicate ID	Compound	Sample Result	Duplicate Result	QL	Units	RPD (%)
N01-E17-TNBS-P3-BS	N01-E17-TNBS-P3-BT	SSC	3	8	1	mg/L	91

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection July Newark Bay Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ (POC) and Columbia Analytical Services, Inc., Kelso, WA (DOC)		
Work Order	10070346 (POC, selected DOC) K1008788 (DOC)		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 and Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60144462.A410		
Prepared by	Sharon McKechnie/AECOM	Completed November 10, 2010	
Reviewed by	Lisa Krowitz/AECOM	File: 10070346 LPR PWCM NB JULY POC DOC .doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on July 21, 2010.

SDG	DOC Laboratory	Client Sample ID	POC Laboratory	Matrix
10070346 (Xenco) K1008778 (CAS Kelso)	CAS Kelso	N01-E21-TKVK-P1-AS	Xenco (Sub CAS Tucson)	Aqueous
	CAS Kelso	N01-E21-TKVK-P1-BS	Xenco (Sub CAS Tucson)	Aqueous
	CAS Kelso	N01-E21-TKVK-P3-AS	Xenco (Sub CAS Tucson)	Aqueous
	CAS Kelso	N01-E21-TKVK-P3-BS	Xenco (Sub CAS Tucson)	Aqueous
	Xenco	N01-E21-TNBN-P1-AS	Xenco (Sub CAS Tucson)	Aqueous
	CAS Kelso	N01-E21-TNBN-P1-BS	Xenco (Sub CAS Tucson)	Aqueous
	CAS Kelso	N01-E21-TNBN-P3-AS	Xenco (Sub CAS Tucson)	Aqueous
	CAS Kelso	N01-E21-TNBN-P3-BS	Xenco (Sub CAS Tucson)	Aqueous
	CAS Kelso	N01-E21-TNBS-P1-AS	Xenco (Sub CAS Tucson)	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results		Ö	
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB N01-E22-TARK-P3-XR, collected on 7/21/2010 and reported in SDG 10070357 is associated with all samples collected 7/19/2010 through 7/25/2010. No POC or DOC was detected above the QL in the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria. The DOC MS %R for sample N01-E21-TNBN-P1-BS, which was analyzed by CAS Kelso, fell below (72%) the laboratory lower limit; therefore, all DOC samples analyzed by CAS Kelso were qualified as estimated (J/UJ). One DOC sample (N01-E21-TNBN-P1-AS) was analyzed by Xenco and was not qualified on the basis of MS nonconformance since a sample from this laboratory was not spiked.

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria of 80-120% for DOC and 95-105% for POC

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than ten times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E21-TKVK-P1-AS	W	DOC	1.36	0.50	mg/L	J	m
N01-E21-TKVK-P1-BS	W	DOC	1.29	0.50	mg/L	J	m
N01-E21-TKVK-P3-AS	W	DOC	1.25	0.50	mg/L	J	m
N01-E21-TKVK-P3-BS	W	DOC	1.26	0.50	mg/L	J	m
N01-E21-TNBN-P1-BS	W	DOC	1.49	0.50	mg/L	J	m
N01-E21-TNBN-P3-AS	W	DOC	1.78	0.50	mg/L	J	m
N01-E21-TNBN-P3-BS	W	DOC	1.63	0.50	mg/L	J	m
N01-E21-TNBS-P1-AS	W	DOC	1.60	0.50	mg/L	J	m

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- Nondetect results will have no value in the result column

Attachment A

Nonconformance Summary Tables

Table A-1 – Matrix Spike Recovery

Sample ID	Analyte	Sample Result (mg/L)	Spike Value (mg/L)	MS Result (mg/L)	MS REC (%)	MSD REC (%)
N01-E21-TNBN-P1-BS	DOC	1.49	25	19.5	72	NA

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection July Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Order	10070347		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		
Prepared by	Sharon McKechnie/AECOM	Completed November 10, 2010	
Reviewed by	Lisa Krowitz/AECOM	File: 10070347 PWCM JULY Routine POC DOC .doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on July 21, 2010.

SDG	DOC Laboratory	Client Sample ID	POC Laboratory	Matrix
10070347	Xenco	10A-E21-T042-P1-AS	Xenco (Sub CAS Tucson)	Aqueous
		10A-E21-T042-P1-BS		Aqueous
		10A-E21-T042-P3-AS		Aqueous
		10A-E21-T042-P3-BS		Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results			Ö
Laboratory control sample (LCS) results		Ö	
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E20-T175-P4-XR, collected on 7/22/2010 and reported in SDG 10070386 is associated with all samples collected 7/19/2010 through 7/25/2010. No POC or DOC was detected above the QL in the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria of 80-120% for DOC and 95-105% for POC. Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than ten times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E21-T042-P1-BS	W	POC	3.6	1.0	mg/L	J	I
10A-E21-T042-P1-AS	W	POC	3.0	1.0	mg/L	J	I
10A-E21-T042-P3-BS	W	POC	3.2	1.0	mg/L	J	I
10A-E21-T042-P3-AS	W	POC	2.6	1.0	mg/L	J	I

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- Nondetect results will have no value in the result column

Attachment A

Nonconformance Summary Tables

Table A-1 – Laboratory Control Sample Recovery

LCS	Analyte	Standard mg/L C	Result (mg/L C)	Recovery (%)
8/13/10@0740	POC	4700	5060	107.7
Affected Samples:	All samples in this SDG			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection July Newark Bay Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ (POC) Columbia Analytical Services, Inc., Kelso, WA (DOC)		
Work Order	10070348 (POC), K1008783 (DOC)		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Full		
AECOM Project Number	60144462.A410		
Prepared by	Sharon McKechnie/AECOM	Completed November 10, 2010	
Reviewed by	Lisa Krowitz/AECOM	File: 10070348 LPR PWCM NB JULY POC DOC .doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on July 21, 2010.

SDG	DOC Laboratory	Client Sample ID	POC Laboratory	Matrix
10070348 (Xenco) K1008783 (CAS Kelso)	CAS Kelso	N01-E21-TARK-P1-AS	Xenco (Sub CAS Tucson)	Aqueous
		N01-E21-TARK-P1-BS		Aqueous
		N01-E21-TARK-P3-AS		Aqueous
		N01-E21-TNBS-P1-BS		Aqueous
		N01-E21-TNBS-P3-AS		Aqueous
		N01-E21-TNBS-P3-BS		Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations		Ö	
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results		Ö	
Field duplicate results			Ö
Laboratory control sample (LCS) results		Ö	
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Several DOC samples were initially analyzed at a dilution due turbidity. The initial analysis produced results < RL. These samples were reanalyzed undiluted, but outside of holding time. DOC results were reported from the reanalysis; therefore, all reanalyzed DOC samples were qualified as estimated (J/UJ).

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. The calibration %R for POC exceeded (107.6%) the criteria. Qualification on the basis of calibration nonconformance was as follows:

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB N01-E22-TARK-P3-XR, collected on 7/21/2010 and reported in SDG 10070357 is associated with all samples collected 7/19/2010 through 7/25/2010. No POC or DOC was detected above the QL in the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria. The DOC MS %R for sample N01-E21-TARK-P3-AS fell below (70%) the laboratory lower limit; therefore, all DOC samples were qualified as estimated (J/UJ).

Nonconformances are summarized in Attachment A, Table A-3. Qualified sample results are shown in Table 1.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria of 80-120% for DOC and 95-105% for POC. The POC LCS %R associated with the samples in this SDG exceeded (110.4%); therefore all positive samples were qualified as estimated (J).

Nonconformances are summarized in Attachment A, Table A-4. Qualified sample results are shown in Table 1.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than ten times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E21-TARK-P1-AS	W	DOC	1.57	0.50	mg/L	J	h,m
N01-E21-TARK-P1-BS	W	DOC	1.68	0.50	mg/L	J	h,m
N01-E21-TARK-P3-AS	W	DOC	1.61	0.50	mg/L	J	h,m
N01-E21-TNBS-P1-BS	W	DOC	1.95	0.50	mg/L	J	h,m
N01-E21-TNBS-P3-AS	W	DOC	2.04	0.50	mg/L	J	h,m
N01-E21-TNBS-P3-BS	W	DOC	1.81	0.50	mg/L	J	h,m
N01-E21-TNBS-P1-BS	W	POC	1	1.0	mg/L	J	l,c
N01-E21-TNBS-P3-BS	W	POC	1	1.0	mg/L	J	l,c
N01-E21-TNBS-P3-AS	W	POC	1.2	1.0	mg/L	J	l,c
N01-E21-TARK-P1-BS	W	POC	1.2	1.0	mg/L	J	l,c

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- Nondetect results will have no value in the result column

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E21-TARK-P1-AS	DOC	36-37	28
N01-E21-TARK-P1-BS			
N01-E21-TARK-P3-AS			
N01-E21-TNBS-P1-BS			
N01-E21-TNBS-P3-AS			
N01-E21-TNBS-P3-BS			

Table A-2 – Calibration Recovery

ICV/CCV	Analyte	Standard (mg/L C)	Result (mg/L C)	Recovery (%)
8/12/10@1710	POC	13000	13990	107.6
Affected Samples:	N01-E21-TNBS-P1-BS, N01-TNBS-P3-BS, N01-E21-TNBS-P3-AS, N01-E21-TARK-P1-BS			

Table A-3 – Matrix Spike Recovery

Sample ID	Analyte	Sample Result (mg/L)	Spike Value (mg/L)	MS Result (mg/L)	MS REC (%)	MSD REC (%)
N01-E21-TARK-P3-AS	DOC	1.61	25	19.1	70	NA
Affected Samples	All DOC samples in this SDG					

Table A-4 – Laboratory Control Sample Recovery

LCS	Analyte	Standard mg/L C	Result (mg/L C)	Recovery (%)
8/12/10@1625	POC	4700	5190	110.4
Affected Samples:	N01-E21-TNBS-P1-BS, N01-TNBS-P3-BS, N01-E21-TNBS-P3-AS, N01-E21-TARK-P1-BS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection July Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ (POC) Columbia Analytical Services, Inc., Kelso, WA (DOC)		
Work Order	10070349 (POC), K1008786 (DOC)		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		
Prepared by	Sharon McKechnie/AECOM	Completed November 10, 2010	
Reviewed by	Lisa Krowitz/AECOM	File: 10070349 PWCM JULY Routine POC DOC .doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on July 21, 2010.

SDG	DOC Laboratory	Client Sample ID	POC Laboratory	Matrix
10070349 (Xenco) K1008786 (CAS Kelso)	Xenco	10A-E21-T102-P3-AS	Xenco (Sub CAS Tucson)	Aqueous
	CAS Kelso	10A-E21-T102-P3-BS		Aqueous
	Xenco	10A-E21-T102-P1-BS		Aqueous
	Xenco	10A-E21-T135-P1-AS		Aqueous
	Xenco	10A-E21-T102-P1-AS		Aqueous
	Xenco	10A-E21-T135-P3-BS		Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results		Ö	
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E20-T175-P4-XR, collected on 7/22/2010 and reported in SDG 10070386 is associated with all samples collected 7/19/2010 through 7/25/2010. No POC or DOC was detected above the QL in the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria. DOC MS %R for sample 10A-E21-T102-P3-AS fell below (80%) the laboratory lower limit of 87%; therefore, all affected samples were qualified as estimated (J/UJ).

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

DOC sample 10A-E21-T102-P3-BS was also used as a MS and met criteria, therefore; this sample was accepted unqualified.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria of 80-120% for DOC and 95-105% for POC.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than ten times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E21-T102-P1-AS	W	DOC	4.6	1.5	mg/L	J	m
10A-E21-T102-P1-BS	W	DOC	4.6	1.5	mg/L	J	m
10A-E21-T102-P3-AS	W	DOC	4.5	1.5	mg/L	J	m
10A-E21-T135-P1-AS	W	DOC	4.7	1.5	mg/L	J	m
10A-E21-T135-P3-BS	W	DOC	4.8	1.5	mg/L	J	m

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- Nondetect results will have no value in the result column

Attachment A

Nonconformance Summary Tables

Table A-1 – Matrix Spike Recovery

Sample ID	Analyte	Sample Result (mg/L)	Spike Value (mg/L)	MS Result (mg/L)	MS REC (%)	MSD REC (%)
10A-E21-T102-P3-AS	DOC	4.5	25	24.6	80%	ok

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection July Newark Bay Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ (POC) Columbia Analytical Services, Inc., Kelso, WA (DOC)		
Work Order	10070350 (POC), K1008779 (DOC)		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60144462.A410		
Prepared by	Sharon McKechnie/AECOM	Completed November 10, 2010	
Reviewed by	Lisa Krowitz/AECOM	File: 10070350 LPR PWCM NB JULY POC DOC .doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on July 21, 2010.

SDG	DOC Laboratory	Client Sample ID	POC Laboratory	Matrix
10070350 (Xenco) K1008779 (CAS Kelso)	CAS Kelso	N01-E22-TKVK-P1-AS	Xenco (Sub CAS Tucson)	Aqueous
		N01-E22-TKVK-P1-BS		Aqueous
		N01-E22-TKVK-P1-BT (Field duplicate of N01-E22-TKVK-P1-BS)		Aqueous
		N01-E22-TKVK-P3-AS		Aqueous
		N01-E22-TKVK-P3-BS		Aqueous
		N01-E22-TNBS-P1-BS		Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results		Ö	
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Five DOC samples were received at the laboratory with one day remaining of hold time. Due to sample foaming these samples were initially analyzed at a dilution. The initial analysis produced results < RL. These samples were reanalyzed undiluted, but outside of holding time; therefore, all affected DOC samples were qualified as estimated J/UJ.

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB N01-E22-TARK-P3-XR, collected on 7/21/2010 and reported in SDG 10070357 is associated with all samples collected 7/19/2010 through 7/25/2010. No POC or DOC was detected above the QL in the EB.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

The field duplicate pair N01-E22-TKVK-P1-BS / N01-E22-TKVK-P1-BT RPD exceeded the criteria for POC (34.5%). Precision was deemed acceptable since the original and duplicate sample results were each < 5x the QL.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria. The DOC MS %R for sample N01-E22-TKVK-P3-AS fell below (73%) the lab lower limit; therefore, all DOC samples in this SDG were qualified as estimated (J/UJ).

Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E22-TKVK-P1-AS	W	DOC	1.48	0.50	mg/L	J	h,m
N01-E22-TKVK-P1-BS	W	DOC	1.27	0.50	mg/L	J	m
N01-E22-TKVK-P1-BT	W	DOC	1.53	0.50	mg/L	J	h,m
N01-E22-TKVK-P3-AS	W	DOC	1.51	0.50	mg/L	J	h,m
N01-E22-TKVK-P3-BS	W	DOC	1.93	0.50	mg/L	J	h,m
N01-E22-TNBS-P1-BS	W	DOC	1.61	0.50	mg/L	J	h,m

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- Nondetect results will have no value in the result column

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E22-TKVK-P1-AS	DOC	37	28
N01-E22-TKVK-P1-BS			
N01-E22-TKVK-P1-BT			
N01-E22-TKVK-P3-AS			
N01-E22-TKVK-P3-BS			
N01-E22-TNBS-P1-BS			

Table A-2 – Matrix Spike Recovery

Sample ID	Analyte	Sample Result (mg/L)	Spike Value (mg/L)	MS Result (mg/L)	MS REC (%)	MSD REC (%)
N01-E22-TNBS-P3-AS	DOC	1.87	25	20.6	75	NA
Affected Samples	All samples in this SDG					

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection July Newark Bay Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ (POC) Columbia Analytical Services, Inc., Kelso, WA (DOC)		
Work Order	10070353 (POC), K1008777 (DOC)		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60144462.A410		
Prepared by	Sharon McKechnie/AECOM	Completed November 10, 2010	
Reviewed by	Lisa Krowitz/AECOM	File: 10070353 LPR PWCM NB JULY POC DOC .doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on July 21, 2010.

SDG	DOC Laboratory	Client Sample ID	POC Laboratory	Matrix
10070353 (Xenco) K1008777 (CAS Kelso)	CAS Kelso	N01-E22-TNBN-P1-AS	Xenco(Sub CAS Tucson)	Aqueous
		N01-E22-TNBN-P1-BS		Aqueous
		N01-E22-TNBN-P3-AS		Aqueous
		N01-E22-TNBN-P3-BS		Aqueous
		N01-E22-TNBS-P1-AS		Aqueous
		N01-E22-TNBS-P3-AS		Aqueous
		N01-E22-TNBS-P3-BS		Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations		Ö	
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results		Ö	
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

All of the DOC samples in this SDG were received at the laboratory with one day remaining of hold time. Due to sample foaming these samples were initially analyzed at a dilution. The initial analysis produced results < RL. These samples were reanalyzed undiluted, but outside of holding time; therefore, all affected DOC samples were qualified as estimated J/UJ.

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. The POC calibration %R (104.6) exceeded the criteria. Qualification on the basis of calibration nonconformance was as follows:

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB N01-E22-TARK-P3-XR, collected on 7/21/2010 and reported in SDG 10070357 is associated with all samples collected 7/19/2010 through 7/25/2010. No POC or DOC was detected above the QL in the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria. The DOC MS %R for sample N01-E22-TNBS-P3-AS fell below the lab lower limit on both the initial and the confirmation runs (81% and 75%, respectively); therefore, all DOC samples in this SDG were qualified as estimated (J/UJ).

Nonconformances are summarized in Attachment A, Table A-3. Qualified sample results are shown in Table 1.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E22-TNBN-P1-AS	W	DOC	2.03	0.50	mg/L	J	h,m
N01-E22-TNBN-P1-BS	W	DOC	1.84	0.50	mg/L	J	h,m
N01-E22-TNBN-P3-AS	W	DOC	2.34	0.50	mg/L	J	h,m
N01-E22-TNBN-P3-BS	W	DOC	2.11	0.50	mg/L	J	h,m
N01-E22-TNBS-P1-AS	W	DOC	1.81	0.50	mg/L	J	h,m
N01-E22-TNBS-P3-AS	W	DOC	1.87	0.50	mg/L	J	h,m
N01-E22-TNBS-P3-BS	W	DOC	1.87	0.50	mg/L	J	h,m
N01-E22-TNBN-P1-BS	W	POC	1.2	1.0	mg/L	J	c
N01-E22-TNBN-P1-AS	W	POC	1	1.0	mg/L	J	c
N01-E22-TNBN-P3-AS	W	POC	1	1.0	mg/L	J	c
N01-E22-TNBS-P3-BS	W	POC	1.3	1.0	mg/L	J	c

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- Nondetect results will have no value in the result column

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E22-TNBN-P1-AS	DOC	37	28
N01-E22-TNBN-P1-BS			
N01-E22-TNBN-P3-AS			
N01-E22-TNBN-P3-BS			
N01-E22-TNBS-P1-AS			
N01-E22-TNBS-P3-AS			
N01-E22-TNBS-P3-BS			

Table A-2 – Calibration Recovery

ICV/CCV	Analyte	Standard (mg/L C)	Result (mg/L C)	Recovery (%)
8/16/10@0944	POC	13000	13600	104.6
Affected Samples	All samples in this SDG			

Table A-3 – Matrix Spike Recovery

Sample ID	Analyte	Sample Result (mg/L)	Spike Value (mg/L)	MS Result (mg/L)	MS REC (%)	MSD REC (%)
N01-E22-TNBS-P3-AS	DOC	1.87	25	20.6	75	NA
Affected Samples	All samples in this SDG					

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection July Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ (POC) Columbia Analytical Services, Inc., Kelso, WA (DOC)		
Work Order	10070356 (POC), K1008778 (DOC)		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Full		
AECOM Project Number	60145884.A407		
Prepared by	Sharon McKechnie/AECOM	Completed November 10, 2010	
Reviewed by	Lisa Krowitz/AECOM	File: 10070356 PWCM JULY Routine POC DOC .doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on July 21, 2010.

SDG	DOC Laboratory	Client Sample ID	POC Laboratory	Matrix
10070356 (Xenco) K1008778 (CAS Kelso)	CAS Kelso	10A-E22-T067-P3-AS	Xenco (Sub CAS Tucson)	Aqueous
	Xenco	10A-E22-T067-P3-BS		Aqueous
	Xenco	10A-E22-T135-P1-AS		Aqueous
	Xenco	10A-E22-T135-P1-AT		Aqueous
	CAS Kelso	10A-E22-T135-P1-BS		Aqueous
	Xenco	10A-E22-T135-P3-AS		Aqueous
	Xenco	10A-E22-T135-P3-BS		Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results		Ö	
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E20-T175-P4-XR, collected on 7/22/2010 and reported in SDG 10070386 is associated with all samples collected 7/19/2010 through 7/25/2010. No POC or DOC was detected above the QL in the EB.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for

conformance with the QAPP QC acceptance criteria of ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria of 80-120% for DOC and 95-105% for POC.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than ten times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Transitioning from Xenco to CAS Kelso due to a malfunctioning DOC analyzer at Xenco resulted in an analytical overlap involving two DOC samples. Samples 10A-E22-T135-P1-AT and 10A-E22-T135-P3-BS were analyzed for DOC by both Xenco and CAS Kelso. Professional judgment was applied to report only the DOC samples analyzed by Xenco for the following reasons:

- 10A-E22-T135-P1-AT was reported from Xenco since parent and field duplicate samples both were only analyzed by Xenco; sample 10A-E22-T135-P1-AS was not analyzed by CAS Kelso.

- 10A-E22-T135-P3-BS was reported from Xenco since the shallow (AS) and deep (BS) samples both were only analyzed by Xenco; sample 10A-E22-T135-P3-AS was not analyzed by CAS Kelso.

The samples were chosen in order to provide as complete an assessment of the DOC at a particular location as possible.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E22-T067-P3-AS	W	DOC	3.97	0.50	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- The result column will be empty where the sample result was nondetect

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E22-T067-P3-AS	DOC	37	28

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection July Newark Bay Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ (POC) Columbia Analytical Services, Inc., Kelso, WA (DOC)		
Work Order	10070357 (POC), K1008776 (DOC)		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60144462.A410		
Prepared by	Sharon McKechnie/AECOM	Completed November 5, 2010	
Reviewed by	Lisa Krowitz/AECOM	File: 10070357 LPR PWCM NB JULY POC DOC .doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on July 21, 2010.

SDG	DOC Laboratories	Client Sample ID	POC Laboratories	Matrix
10070357 (Xenco) K1008776 (CAS Kelso)	CAS Kelso	N01-E22-TARK-P1-AS	Xenco (Sub CAS Tucson)	Aqueous
		N01-E22-TARK-P1-BS		Aqueous
		N01-E22-TARK-P3-AS		Aqueous
		N01-E22-TARK-P3-BS		Aqueous
		N01-E22-TARK-P3-FB (Field blank collected 7/21/10)		Aqueous
		N01-E22-TARK-P3-XR (Equipment blank collected 7/21/10)		Aqueous
10070357	Xenco	N01-E22-THKN-P1-AS		Aqueous
10070357	Xenco	N01-E22-THKN-P1-BS	Xenco (Sub CAS	Aqueous

SDG	DOC Laboratories	Client Sample ID	POC Laboratories	Matrix
		N01-E22-THKN-P3-AS	Tucson)	Aqueous
		N01-E22-THKN-P3-BS		Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Two DOC samples were received at the laboratory with one day remaining of hold time. Due to sample foaming these samples were initially analyzed at a dilution. The initial analysis produced results < RL. These samples were reanalyzed undiluted, but outside of holding time; therefore, all affected DOC samples were qualified as estimated J/UJ.

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB N01-E22-TARK-P3-XR, collected on 7/21/2010 and reported in SDG 10070357 is associated with all samples collected 7/19/2010 through 7/25/2010. No POC or DOC was detected above the RL in the EB.

An additional blank identified as N01-E22-TARK-P3-FB, collected 7/21/10 and reported in this SDG was collected to assess the quality of the water being used for equipment blank samples. No POC or DOC > RL was detected in this blank. The results of this blank are informational only.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria of 80-120% for DOC and 95-105% for POC

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than ten times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E22-TARK-P1-AS	W	DOC	2.26	0.50	mg/L	J	h
N01-E22-TARK-P1-BS	W	DOC	2.00	0.50	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- Nondetect results will have no value in the result column

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E22-TARK-P1-AS	DOC	37	28
N01-E22-TARK-P1-BS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection July Newark Bay Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ (POC) Columbia Analytical Services, Inc., Kelso, WA (DOC)		
Work Order	10070358 (POC), K1008782 (DOC)		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60144462.A410		
Prepared by	Sharon McKechnie/AECOM	Completed November 10, 2010	
Reviewed by	Lisa Krowitz/AECOM	File: 10070358 LPR PWCM NB JULY POC DOC .doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on July 21, 2010.

SDG	DOC Laboratory	Client Sample ID	POC Laboratory	Matrix
10070358 (Xenco) K1008782 (CAS Kelso)	CAS Kelso	N01-E21-TARK-P3-BS	Xenco (SubCAS Tucson)	Aqueous
		N01-E21-THKN-P1-AS		Aqueous
		N01-E21-THKN-P1-BS		Aqueous
		N01-E21-THKN-P3-AS		Aqueous
		N01-E21-THKN-P3-AT (Field duplicate of N01-E21-THKN-P3-AS)		Aqueous
		N01-E21-THKN-P3-BS		Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations		Ö	
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results	Ö		
Laboratory control sample (LCS) results		Ö	
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Four DOC samples were received at the laboratory with one day remaining of hold time. Due to sample foaming these samples were initially analyzed at a dilution. The initial analysis produced results < RL. These samples were reanalyzed undiluted, but outside of holding time; therefore, all affected DOC samples were qualified as estimated J/UJ.

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. The calibration %R for POC exceeded (107.6%) the criteria. Qualification on the basis of calibration nonconformance was as follows:

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB N01-E22-TARK-P3-XR, collected on 7/21/2010 and reported in SDG 10070357 is associated with all samples collected 7/19/2010 through 7/25/2010. No POC or DOC was detected above the QL in the EB.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 20% (if both results were greater than ten times the QL) for DOC and POC.

The field duplicate pair N01-E21-THKN-P3-AS / N01-E21-THKN-P3-AT RPD exceeded (22%) the criteria for DOC. Precision was deemed acceptable since the original and duplicate sample results were each < 5x the QL.

The field duplicate RPD for POC was not calculable due to a nondetect result in the duplicate sample. Precision was deemed acceptable since the detected result in the original sample was < 5x the QL.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria. The DOC MS %R for sample N01-E21-THKN-P3-AT performed on 8/17/10 (inside of sample hold time) met the acceptance criteria. The DOC MS %R for sample N01-E21-THKN-P3-AT performed on 8/27/10 (outside of sample hold time) fell below (72%) the laboratory lower limit. Since the original analysis of the MS, and the LCS analyses performed on 8/17/10 and 8/27/10 both met acceptance criteria, based on professional judgment, no qualifications will be applied to the DOC samples in this SDG on the basis of MS%R nonconformance.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria of 80-120% for DOC and 95-105% for POC. Nonconformances are summarized in Attachment A, Table A-3. Qualified sample results are shown in Table 1.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than ten times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E21-TARK-P3-BS	W	DOC	1.44	0.50	mg/L	J	h
N01-E21-THKN-P1-AS	W	DOC	2.10	0.50	mg/L	J	h
N01-E21-THKN-P1-BS	W	DOC	1.78	0.50	mg/L	J	h
N01-E21-THKN-P3-AT	W	DOC	2.01	0.50	mg/L	J	h
N01-E21-THKN-P1-BS	W	POC	1	1.0	mg/L	J	l,c
N01-E21-THKN-P1-AS	W	POC	1.1	1.0	mg/L	J	l,c
N01-E21-THKN-P3-BS	W	POC	1	1.0	mg/L	J	l,c
N01-E21-THKN-P3-AS	W	POC	1	1.0	mg/L	J	l,c

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- Nondetect results will have no value in the result column

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E21-TARK-P3-BS	DOC	37	28
N01-E21-THKN-P1-AS			
N01-E21-THKN-P1-BS			
N01-E21-THKN-P3-AT			

Table A-2 – Calibration Recovery

ICV/CCV	Analyte	Standard (mg/L C)	Result (mg/L C)	Recovery (%)
8/12/10@1334	POC	13000	13990	107.6
Affected Samples:	N01-E21-THKN-P1-BS, N01-E21-THKN-P1-AS, N01-E21-THKN-P3-BS, N01-E21-THKN-P3-AS			

Table A-3 – Laboratory Control Sample Recovery

LCS	Analyte	Standard mg/L C	Result (mg/L C)	Recovery (%)
8/12/10@1625	POC	4700	5190	110.4
Affected Samples:	N01-E21-THKN-P1-BS, N01-E21-THKN-P1-AS, N01-E21-THKN-P3-BS, N01-E21-THKN-P3-AS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection July Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ (POC) Columbia Analytical Services, Inc., Kelso, WA (DOC)		
Work Order	10070359 (POC), K1008784 (DOC)		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		
Prepared by	Sharon McKechnie/AECOM	Completed November 10, 2010	
Reviewed by	Lisa Krowitz/AECOM	File: 10070359 PWCM JULY Routine POC DOC .doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on July 21, 2010.

SDG	DOC Laboratory	Client Sample ID	POC Laboratory	Matrix
10070359 (Xenco) K1008784 (CAS Kelso)	CAS Kelso	10A-E22-T014-P1-AS	Xenco (Sub CAS Tucson)	Aqueous
		10A-E22-T014-P1-BS		Aqueous
		10A-E22-T014-P3-AS		Aqueous
		10A-E22-T014-P3-BS		Aqueous
		10A-E22-T042-P1-AS		Aqueous
		10A-E22-T042-P1-BS		Aqueous
		10A-E22-T042-P3-AS		Aqueous
		10A-E22-T042-P3-BS		Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results		Ö	
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E20-T175-P4-XR, collected on 7/22/2010 and reported in SDG 10070386 is associated with all samples collected 7/19/2010 through 7/25/2010. No POC or DOC was detected above the QL in the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria. DOC MS %R for sample 10A-E22-T014-P3-AS fell below (77%) the QC lower limit of 80%; therefore, the DOC samples in this SDG were qualified estimated (J/UJ).

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria of 80-120% for DOC and 95-105% for POC.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than ten times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E22-T014-P1-AS	W	DOC	2.19	0.50	mg/L	J	m
10A-E22-T014-P1-BS	W	DOC		5.0	mg/L	UJ	m
10A-E22-T014-P3-AS	W	DOC	2.22	0.50	mg/L	J	m
10A-E22-T014-P3-BS	W	DOC	1.77	0.50	mg/L	J	m
10A-E22-T042-P1-AS	W	DOC	3.14	0.50	mg/L	J	m
10A-E22-T042-P1-BS	W	DOC	2.13	0.50	mg/L	J	m
10A-E22-T042-P3-AS	W	DOC	3.07	0.50	mg/L	J	m
10A-E22-T042-P3-BS	W	DOC	2.63	0.50	mg/L	J	m

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- Nondetect results will have no value in the result column

Attachment A

Nonconformance Summary Tables

Table A-1 – Matrix Spike Recovery

Sample ID	Analyte	Sample Result (mg/L)	Spike Value (mg/L)	MS Result (mg/L)	MS REC (%)	MSD REC (%)
10A-E22-T014-P3-AS	DOC	2.22	25	21.5	77%	NA
Associated Samples	All samples in this SDG					

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection July Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ (POC) Columbia Analytical Services, Inc., Kelso, WA (DOC)		
Work Order	10070364 (POC), K1008789 (DOC)		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		
Prepared by	Sharon McKechnie/AECOM	Completed November 10, 2010	
Reviewed by	Lisa Krowitz/AECOM	File: 10070364 PWCM JULY Routine POC DOC .doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on July 21, 2010.

SDG	DOC Laboratory	Client Sample ID	POC Laboratory	Matrix
10070364 (Xenco) K1008789 (CAS Kelso)	CAS Kelso	10A-E22-T067-P1-AS	Xenco (Sub CAS Tucson)	Aqueous
		10A-E22-T067-P1-BS		Aqueous
		10A-E22-T102-P1-AS		Aqueous
		10A-E22-T102-P1-BS		Aqueous
		10A-E22-T102-P1-BT (Field duplicate of 10A-E22-T102-P1-BS)		Aqueous
		10A-E22-T102-P3-AS		Aqueous
		10A-E22-T102-P3-BS		Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results		Ö	
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E20-T175-P4-XR, collected on 7/22/2010 and reported in SDG 10070386 is associated with all samples collected 7/19/2010 through 7/25/2010. No POC or DOC was detected above the QL in the EB.

Field Duplicate Results

Field duplicates are identified with a “T” as the last character of the sample ID (the associated field sample has the same ID with an “S” as the last character). The RPDs were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 20% (if both results were greater than ten times the QL) for DOC and POC. The RPD for field duplicate pair 10A-E22-T102-P1-BS/ 10A-E22-T102-P1-BT exceeded the ≤ 20% criteria (22%). Since the sample and duplicate results were each > 5 x the QL and < 10x the QL, professional judgment was used to qualify the sample and duplicate as estimated (J).

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E22-T102-P1-BS	W	POC	9.2	1.0	mg/L	J	fd
10A-E22-T102-P1-BT	W	POC	7.4	1.0	mg/L	J	fd

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- Nondetect results will have no value in the result column

Attachment A

Nonconformance Summary Tables

Table A-1 – Field Duplicates

Sample ID	Duplicate ID	Analyte	Sample Result (mg/L)	Duplicate Result (mg/L)	QL	Units	RPD (%)
10A-E22-T102-P1-BS	10A-E22-T102-P1-BT	POC	9.2	7.4	1.0	mg/L	22

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection July Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ (POC) Columbia Analytical Services, Inc., Kelso, WA (DOC)		
Work Order	10070365 (POC), K1008770 (DOC)		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		
Prepared by	Sharon McKechnie/AECOM	Completed November 10, 2010	
Reviewed by	Lisa Krowitz/AECOM	File: 10070365 PWCM JULY Routine POC DOC .doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on July 21, 2010.

SDG	DOC Laboratory	Client Sample ID	POC Laboratory	Matrix
10070365 (Xenco) K1008770 (CAS Kelso)	CAS Kelso	10A-E21-T014-P1-BS	Xenco (Sub CAS Tucson)	Aqueous
		10A-E21-T014-P1-AS		Aqueous
		10A-E21-T014-P3-BS		Aqueous
		10A-E21-T014-P3-AS		Aqueous
		10A-E21-T135-P1-BS		Aqueous
		10A-E21-T135-P3-AS		Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations		Ö	
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results			Ö
Laboratory control sample (LCS) results		Ö	
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Two DOC samples were received at the laboratory with one day remaining of hold time. Due to sample foaming these samples were initially analyzed at a dilution. The initial analysis produced results < RL. These samples were reanalyzed undiluted, but outside of holding time; therefore, all affected DOC samples were qualified as estimated J/UJ.

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method

detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E20-T175-P4-XR, collected on 7/22/2010 and reported in SDG 10070386 is associated with all samples collected 7/19/2010 through 7/25/2010. No POC or DOC was detected above the QL in the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria of 80-120% for DOC and 95-105% for POC. Nonconformances are summarized in Attachment A, Table A-3.

Qualified sample results are shown in Table 1.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than ten times the QL). The POC LD RPD for sample 10A-E21-T135-P3-AS (23%) exceeded the criteria, but since both sample and duplicate results were < 5x the QL, precision was deemed acceptable.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E21-T014-P1-BS	W	POC	1.1	1.0	mg/L	J	l,c
10A-E21-T014-P1-AS	W	POC	1.2	1.0	mg/L	J	l,c
10A-E21-T014-P3-BS	W	POC	1.1	1.0	mg/L	J	l,c
10A-E21-T014-P3-AS	W	POC	1.2	1.0	mg/L	J	l,c
10A-E21-T135-P1-BS	W	POC	2.5	1.0	mg/L	J	l,c
10A-E21-T135-P3-AS	W	POC	2.9	1.0	mg/L	J	l,c
10A-E21-T014-P1-BS	W	DOC	2.22	0.50	mg/L	J	h
10A-E21-T014-P3-AS	W	DOC	2.74	0.50	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- Nondetect results will have no value in the result column

Attachment A

Nonconformance Summary Tables

Table A-1 –Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
10A-E21-T014-P1-BS	DOC	37	28
10A-E21-T014-P3-AS			

Table A-2 – Calibration Recovery

ICV/CCV	Analyte	Standard mg/L C	Result (mg/L C)	Recovery (%)
8/12/10 @1334	POC	13000	13990	107.6
Affected Samples:	All samples in this SDG			

Table A-3 – Laboratory Control Sample Recovery

LCS	Analyte	Standard mg/L C	Result (mg/L C)	Recovery (%)
8/12/10@1245	POC	13000	13670	105
Affected Samples:	All samples in this SDG			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection July Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ (POC) Columbia Analytical Services, Inc., Kelso, WA (DOC)		
Work Order	10070366 (POC), K1008781 (DOC)		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		
Prepared by	Sharon McKechnie/AECOM	Completed November 10, 2010	
Reviewed by	Lisa Krowitz/AECOM	File: 10070366 PWCM JULY Routine POC DOC .doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on July 21, 2010.

SDG	DOC Laboratory	Client Sample ID	POC Laboratory	Matrix
10070366 (Xenco) K1008781 (CAS Kelso)	CAS Kelso	10A-E21-T067-P1-AS	Xenco (Sub CAS Tucson)	Aqueous
		10A-E21-T067-P1-BS		Aqueous
		10A-E21-T067-P3-AS		Aqueous
		10A-E21-T067-P3-AT (Field duplicate of 10A-E21-T067-P3-AS)		Aqueous
		10A-E21-T067-P3-BS		Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results	Ö		
Laboratory control sample (LCS) results		Ö	
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E20-T175-P4-XR, collected on 7/22/2010 and reported in SDG 10070386 is associated with all samples collected 7/19/2010 through 7/25/2010. No POC or DOC was detected above the QL in the EB.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria of 80-120% for DOC and 95-105% for POC. Nonconformances are summarized in Attachment A, Table A-1.

Qualified sample results are shown in Table 1.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than ten times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E21-T067-P1-AS	W	POC	2.8	1.0	mg/L	J	I
10A-E21-T067-P1-BS	W	POC	8.1	1.0	mg/L	J	I
10A-E21-T067-P3-AS	W	POC	4	1.0	mg/L	J	I
10A-E21-T067-P3-AT	W	POC	7	1.0	mg/L	J	I
10A-E21-T067-P3-BS	W	POC	4	1.0	mg/L	J	I

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- Nondetect results will have no value in the result column

Attachment A

Nonconformance Summary Tables

Table A-1 – Laboratory Control Sample Recovery

LCS	Analyte	Standard mg/L C	Result (mg/L C)	Recovery (%)
8/13/10@0740	POC	4700	5060	107.7
Affected Samples:	All samples in this SDG			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection July Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ (POC) Columbia Analytical Services, Inc., Kelso, WA (DOC)		
Work Order	10070384 (POC, DOC), 10070386 (POC), K1008801 and K1008800 (DOC)		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60145884.A407		
Prepared by	Sharon McKechnie/AECOM	Completed November 10, 2010	
Reviewed by	Lisa Krowitz/AECOM	File: 10070386 PWCM JULY Routine POC DOC .doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on July 22, 2010.

SDG	DOC Laboratory	Client Sample ID	POC Laboratory	Matrix
10070384 (Xenco) K1008801 (CAS Kelso)	CAS Kelso	10A-E20-T175-P4-FB (Field blank collected 7/22/10)	Xenco (Sub CAS Tucson)	Aqueous
10070386 (Xenco) K1008800 (CAS Kelso)	CAS Kelso	10A-E20-T175-P1-AS	Xenco (Sub CAS Tucson)	Aqueous
		10A-E20-T175-P2-AS		Aqueous
		10A-E20-T175-P2-BS		Aqueous
		10A-E20-T175-P3-AS		Aqueous
		10A-E20-T175-P4-AS		Aqueous
10070386	CAS Kelso	10A-E20-T175-P4-XR (Equipment blank	Xenco (Sub CAS	Aqueous

SDG	DOC Laboratory	Client Sample ID	POC Laboratory	Matrix
(Xenco) K1008800 (CAS Kelso)		collected 7/22/10)	Tucson)	

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations		Ö	
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met.

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per

Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB 10A-E20-T175-P4-XR, collected on 7/22/2010 and reported in SDG 10070386 is associated with all samples collected 7/19/2010 through 7/25/2010. No POC or DOC was detected above the QL in the EB.

An additional blank identified as 10A-E20-T175-P4-FB, collected on 7/22/10 and reported in SDG 10070384, was collected to assess the quality of the water being used for equipment blank samples. No POC or DOC > RL was detected in this blank. The results of this blank are informational only.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria of 80-120% for DOC and 95-105% for POC.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than ten times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E20-T175-P1-AS	W	POC	19.1	1.0	mg/L	J	c
10A-E20-T175-P2-BS	W	POC	2.7	1.0	mg/L	J	c
10A-E20-T175-P2-AS	W	POC	2.8	1.0	mg/L	J	c
10A-E20-T175-P3-AS	W	POC	2.7	1.0	mg/L	J	c
10A-E20-T175-P4-AS	W	POC	2.6	1.0	mg/L	J	c

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- Nondetect results will have no value in the result column

Attachment A

Nonconformance Summary Tables

Table A-1 – Calibration Recovery

ICV/CCV	Analyte	Standard mg/L C	Result (mg/L C)	Recovery (%)
8/16/10@0944	POC	13000	13600	104.6
Affected Samples:	All samples in this SDG			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection July Newark Bay Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ (POC) Columbia Analytical Services, Inc., Kelso, WA (DOC)		
Work Order	10070422 (POC), K1008802 (DOC)		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited		
AECOM Project Number	60144462.A410		
Prepared by	Sharon McKechnie/AECOM	Completed November 10, 2010	
Reviewed by	Lisa Krowitz/AECOM	File: 10070422 LPR PWCM NB JULY POC DOC .doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on July 25, 2010.

SDG	DOC Laboratory	Client Sample ID	POC Laboratory	Matrix
10070422 (Xenco) K1008802 (CAS Kelso)	CAS Kelso	N01-E23-TNBN-P1-FB (Field blank collected 7/25/10)	Xenco (Sub CAS Tucson)	Aqueous
		N01-E23-TNBN-P1-XR (Equipment blank collected 7/25/10)		Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. The calibration %R for POC exceeded (104.6%) the criteria. Qualification on the basis of calibration nonconformance was as follows:

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

All samples were nondetect; therefore, no data was qualified on the basis of calibration nonconformance.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB N01-E23-TNBN-P1-XR, collected on 7/25/2010 and reported in this SDG is associated with all samples collected 7/19/2010 through 7/25/2010. No POC or DOC was detected above the QL in the EB.

An additional blank identified as N01-E23-TNBN-P1-FB, collected 7/25/10 and reported in this SDG was collected to assess the quality of the water being used for equipment blank samples. No POC or DOC > RL was detected in this blank. The results of this blank are informational only.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria of 80-120% for DOC and 95-105% for POC.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than ten times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

No sample results were qualified as a result of validation actions.

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay July Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10070422		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited		
AECOM Project Number	60144462-A410		
Prepared by	Sharon McKechnie/AECOM	Completed November 1, 2010	
Reviewed by	Lisa Krowitz/AECOM	File Name: 10070422 PWCM July NB SSC.doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on July 25, 2010.

SDG	Client Sample ID	Matrix
10070422	N01-E23-TARK-P1-BS	Aqueous
	N01-E23-TARK-P1-AS	Aqueous
	N01-E23-TNBN-P1-BS	Aqueous
	N01-E23-TNBN-P1-AS	Aqueous
	N01-E23-TNBN-P1-XR (Equipment blank collected 7/25/10)	Aqueous
	N01-E23-TNBN-P1-FB (Field blank collected 7/25/10)	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were

used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	**No**	**NA**
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results			Ö
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

<u>Data Completeness</u>

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

<u>Holding Times/Sample Preservation</u>

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB N01-E22-TARK-P3-XR, collected on 7/21/2010 and reported in SDG 10070381 and EB N01-E23-TNBN-P1-XR collected on 7/25/10 and reported in this SDG, were associated with all samples collected 7/19/2010 through 7/25/2010. No SSC > RL was detected in either EB.

An additional blank identified as N01-E23-TNBN-P1-FB, collected 7/25/10 and reported in this SDG was collected to assess the quality of the water being used for equipment blank samples. No SSC > RL was detected in this blank. The results of this blank are informational only.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E23-TARK-P1-BS	W	SSC	9	1	mg/L	J	h
N01-E23-TARK-P1-AS	W	SSC	8	1	mg/L	J	h
N01-E23-TNBN-P1-BS	W	SSC	12	1	mg/L	J	h
N01-E23-TNBN-P1-AS	W	SSC	13	1	mg/L	J	h
N01-E23-TNBN-P1-XR	W	SSC		1	mg/L	UJ	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- Nondetected results will not have a value in the result column

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E23-TARK-P1-BS	SSC	39-40	28
N01-E23-TARK-P1-AS			
N01-E23-TNBN-P1-BS			
N01-E23-TNBN-P1-AS			
N01-E23-TNBN-P1-XR			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection July Routine Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10070347, 10070366, 10070383, 10070384, 10070386, 10070387, 10070388, 10070392, 10070393, 10070424		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited (All except 10070387) Full (10070387 only)		
AECOM Project Number	60144462.A410		
Prepared by	Sharon McKechnie/AECOM	Completed November 1, 2010	
Reviewed by	Lisa Krowitz/AECOM	File Name: July 2010 PWCM Routine SSC 10 SDGs.doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on July 21, 22 and 23, 2010.

SDG	Client Sample ID	Matrix
10070347	10A-E21-T042-P1-AS	Aqueous
	10A-E21-T042-P1-BS	Aqueous
	10A-E21-T042-P2-AS	Aqueous
	10A-E21-T042-P2-BS	Aqueous
	10A-E21-T042-P3-AS	Aqueous
	10A-E21-T042-P3-BS	Aqueous
10070366	10A-E21-T067-P1-AS	Aqueous
	10A-E21-T067-P1-BS	Aqueous
	10A-E21-T067-P2-AS	Aqueous
	10A-E21-T067-P2-BS	Aqueous
	10A-E21-T067-P2-BT (Field duplicate of 10A-E21-T067-P2-BS)	Aqueous
	10A-E21-T067-P3-AS	Aqueous
10070366	10A-E21-T067-P3-AT (Field duplicate of 10A-E21-T067-P3-AS)	Aqueous

SDG	Client Sample ID	Matrix
10070366	10A-E21-T067-P3-BS	Aqueous
10070383	10A-E21-T014-P1-AS	Aqueous
	10A-E21-T014-P1-BS	Aqueous
	10A-E21-T014-P2-AS	Aqueous
	10A-E21-T014-P2-BS	Aqueous
	10A-E21-T014-P3-AS	Aqueous
	10A-E21-T014-P3-BS	Aqueous
	10A-E21-T102-P2-BT (Field duplicate of 10A-E21-T102-P2-BS in SDG 10070387)	Aqueous
	10A-E21-T135-P1-AS	Aqueous
	10A-E21-T135-P1-BS	Aqueous
10070384	10A-E23-T014-P3-AS	Aqueous
	10A-E23-T014-P3-BS	Aqueous
	10A-E23-T042-P1-AS	Aqueous
	10A-E20-T175-P4-FB (Field blank collected 7/22/10)	Aqueous
	10A-E23-T042-P1-BS	Aqueous
10070386	10A-E20-T175-P1-AS	Aqueous
	10A-E20-T175-P2-AS	Aqueous
	10A-E20-T175-P2-BS	Aqueous
	10A-E20-T175-P3-AS	Aqueous
	10A-E20-T175-P4-AS	Aqueous
	10A-E20-T175-P4-XR (Equipment blank collected 7/22/10)	Aqueous
10070387	10A-E21-T102-P1-AS	Aqueous
	10A-E21-T102-P1-BS	Aqueous
	10A-E21-T102-P2-AS	Aqueous
	10A-E21-T102-P2-BS	Aqueous
	10A-E21-T102-P3-AS	Aqueous
	10A-E21-T102-P3-BS	Aqueous
	10A-E21-T135-P1-AS	Aqueous
	10A-E21-T135-P2-AS	Aqueous
	10A-E21-T135-P2-BS	Aqueous
	10A-E21-T135-P3-BS	Aqueous
10070388	10A-E22-T067-P1-AS	Aqueous
	10A-E22-T067-P1-BS	Aqueous
	10A-E22-T067-P2-AS	Aqueous
	10A-E22-T067-P2-BS	Aqueous
	10A-E22-T067-P3-BT (Field duplicate of 10A-E22-T067-P3-BS in SDG 10070392)	Aqueous
	10A-E22-T102-P1-AS	Aqueous
	10A-E22-T102-P1-BS	Aqueous
10070388	10A-E22-T102-P1-BT (Field duplicate of 10A-E22-T102-P1-BS)	Aqueous

SDG	Client Sample ID	Matrix
10070388	10A-E22-T102-P2-AS	Aqueous
10070388	10A-E22-T102-P2-BS	Aqueous
	10A-E22-T102-P3-AS	Aqueous
	10A-E22-T102-P3-BS	Aqueous
	10A-E22-T135-P3-BT (Field duplicate of 10A-E22-T135-P3-BS in SDG 10070392)	Aqueous
10070392	10A-E22-T067-P3-AS	Aqueous
	10A-E22-T067-P3-BS	Aqueous
	10A-E22-T135-P1-AS	Aqueous
	10A-E22-T135-P1-BS	Aqueous
	10A-E22-T135-P2-AS	Aqueous
	10A-E22-T135-P2-BS	Aqueous
	10A-E22-T135-P3-AS	Aqueous
	10A-E22-T135-P3-BS	Aqueous
10070393	10A-E22-T014-P1-AS	Aqueous
	10A-E22-T014-P1-BS	Aqueous
	10A-E22-T014-P2-AS	Aqueous
	10A-E22-T014-P2-BS	Aqueous
	10A-E22-T014-P3-AS	Aqueous
	10A-E22-T014-P3-BS	Aqueous
	10A-E22-T042-P1-AS	Aqueous
	10A-E22-T042-P1-BS	Aqueous
	10A-E22-T042-P2-AS	Aqueous
	10A-E22-T042-P2-BS	Aqueous
	10A-E22-T042-P3-AS	Aqueous
	10A-E22-T042-P3-BS	Aqueous
	10A-E22-T135-P1-AT (Field duplicate of 10A-E22-T135-P1-AS in SDG 10070392)	Aqueous
10070424	10A-E23-T067-P3-AS	Aqueous
	10A-E23-T067-P3-BS	Aqueous
	10A-E23-T102-P1-AS	Aqueous
	10A-E23-T102-P1-BS	Aqueous
	10A-E23-T135-P3-AS	Aqueous
	10A-E23-T135-P3-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	**No**	**NA**
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results		Ö	
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

<u>COC/Sample Integrity</u>

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

<u>Data Completeness</u>

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10A-E20-T175-P4-XR, collected on 7/22/2010 and reported in SDG 10070386 is associated with all samples collected 7/19/2010 through 7/26/2010. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. No SSC was detected above the RL in the EB.

An additional blank identified as 10A-E20-T175-P4-FB, collected 7/22/10 and reported in SDG 10070384 was collected to assess the quality of the water being used for equipment blank samples. No SSC > RL was detected in this blank. The results of this blank are informational only.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC. Data qualification on the basis of field duplicate RPDs was as follows (see above for acceptance criteria):

Criteria	Action	
	Detected	Nondetected
RPD greater than the acceptance criteria, but < 120% and sample and duplicate results >5x the SQL	J	Not Applicable
RPD ≥ 120%	R	Not Applicable
If sample and/or duplicate is <5x the QL and absolute difference is >2x and ≤ 4x the QL	J	UJ
If the sample and/or duplicate is <5x the QL and absolute difference is >4x the QL.	R	R

Qualified sample results are shown in Table 1. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E21-T102-P1-AS	W	SSC	18	1	mg/L	J	h
10A-E21-T102-P1-BS	W	SSC	19	1	mg/L	J	h
10A-E21-T102-P2-AS	W	SSC	18	1	mg/L	J	h
10A-E21-T102-P2-BS	W	SSC	22	1	mg/L	J	h
10A-E21-T102-P3-AS	W	SSC	18	1	mg/L	J	h
10A-E21-T102-P3-BS	W	SSC	29	1	mg/L	J	h
10A-E21-T135-P1-AS	W	SSC	9	1	mg/L	J	h
10A-E21-T135-P2-AS	W	SSC	9	1	mg/L	J	h
10A-E21-T135-P2-BS	W	SSC	12	1	mg/L	J	h
10A-E21-T135-P3-BS	W	SSC	11	1	mg/L	J	h
10A-E22-T067-P1-AS	W	SSC	35	1	mg/L	J	h
10A-E22-T067-P1-BS	W	SSC	65	1	mg/L	J	h
10A-E22-T067-P2-AS	W	SSC	83	1	mg/L	J	h
10A-E22-T067-P2-BS	W	SSC	95	1	mg/L	J	h
10A-E22-T067-P3-BT	W	SSC	86	1	mg/L	J	h
10A-E22-T102-P1-AS	W	SSC	37	1	mg/L	J	h
10A-E22-T102-P1-BS	W	SSC	104	1	mg/L	J	h
10A-E22-T102-P1-BT	W	SSC	97	1	mg/L	J	h
10A-E22-T102-P2-AS	W	SSC	28	1	mg/L	J	h
10A-E22-T102-P2-BS	W	SSC	51	1	mg/L	J	h
10A-E22-T102-P3-AS	W	SSC	44	1	mg/L	J	h
10A-E22-T102-P3-BS	W	SSC	48	1	mg/L	J	h
10A-E22-T135-P3-BT	W	SSC	7	1	mg/L	J	h
10A-E22-T067-P3-AS	W	SSC	38	1	mg/L	J	h
10A-E22-T067-P3-BS	W	SSC	72	1	mg/L	J	h
10A-E22-T135-P1-AS	W	SSC	7	1	mg/L	J	h
10A-E22-T135-P1-BS	W	SSC	9	1	mg/L	J	h
10A-E22-T135-P2-AS	W	SSC	7	1	mg/L	J	h
10A-E22-T135-P2-BS	W	SSC	6	1	mg/L	J	h
10A-E22-T135-P3-AS	W	SSC	9	1	mg/L	J	h
10A-E22-T135-P3-BS	W	SSC	7	1	mg/L	J	h
10A-E22-T014-P1-AS	W	SSC	12	1	mg/L	J	h
10A-E22-T014-P1-BS	W	SSC	64	1	mg/L	J	h
10A-E22-T014-P2-AS	W	SSC	9	1	mg/L	J	h
10A-E22-T014-P2-BS	W	SSC	85	1	mg/L	J	h
10A-E22-T014-P3-AS	W	SSC	12	1	mg/L	J	h
10A-E22-T014-P3-BS	W	SSC	62	1	mg/L	J	h
10A-E22-T042-P1-AS	W	SSC	14	1	mg/L	J	h
10A-E22-T042-P1-BS	W	SSC	91	1	mg/L	J	h
10A-E22-T042-P2-AS	W	SSC	13	1	mg/L	J	h
10A-E22-T042-P2-BS	W	SSC	96	1	mg/L	J	h
10A-E22-T042-P3-AS	W	SSC	20	1	mg/L	J	h
10A-E22-T042-P3-BS	W	SSC	96	1	mg/L	J	h
10A-E22-T135-P1-AT	W	SSC	6	1	mg/L	J	h
10A-E23-T067-P3-AS	W	SSC	21	1	mg/L	J	h
10A-E23-T067-P3-BS	W	SSC	9	1	mg/L	J	h

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
10A-E23-T102-P1-AS	W	SSC	26	1	mg/L	J	h
10A-E23-T102-P1-BS	W	SSC	33	1	mg/L	J	h
10A-E23-T135-P3-AS	W	SSC	9	1	mg/L	J	h
10A-E23-T135-P3-BS	W	SSC	19	1	mg/L	J	h
10A-E21-T067-P2-BS	W	SSC	117	1	mg/L	J	h,fd
10A-E21-T067-P2-BT	W	SSC	50	1	mg/L	J	h,fd
10A-E23-T042-P1-AS	W	SSC	20	1	mg/L	J	h
10A-E23-T042-P1-BS	W	SSC	5	1	mg/L	J	h
10A-E20-T175-P1-AS	W	SSC	280	1	mg/L	J	h
10A-E20-T175-P2-AS	W	SSC	10	1	mg/L	J	h
10A-E20-T175-P2-BS	W	SSC	11	1	mg/L	J	h
10A-E20-T175-P3-AS	W	SSC	9	1	mg/L	J	h
10A-E20-T175-P4-AS	W	SSC	10	1	mg/L	J	h
10A-E20-T175-P4-XR	W	SSC		1	mg/L	UJ	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- Nondetected results will not have a value in the result column

Attachment A

Nonconformance Summary Tables

Table A-1 – Holding Time

Sample ID	Analyte	Hold Time (Days)	Hold Time Criteria (Days)
10A-E21-T102-P1-AS	SSC	30-42	28
10A-E21-T102-P1-BS			
10A-E21-T102-P2-AS			
10A-E21-T102-P2-BS			
10A-E21-T102-P3-AS			
10A-E21-T102-P3-BS			
10A-E21-T135-P1-AS			
10A-E21-T135-P2-AS			
10A-E21-T135-P2-BS			
10A-E21-T135-P3-BS			
10A-E22-T067-P1-AS			
10A-E22-T067-P1-BS			
10A-E22-T067-P2-AS			
10A-E22-T067-P2-BS			
10A-E22-T067-P3-BT			
10A-E22-T102-P1-AS			
10A-E22-T102-P1-BS			
10A-E22-T102-P1-BT			
10A-E22-T102-P2-AS			
10A-E22-T102-P2-BS			
10A-E22-T102-P3-AS			
10A-E22-T102-P3-BS			
10A-E22-T135-P3-BT			
10A-E22-T067-P3-AS			
10A-E22-T067-P3-BS			
10A-E22-T135-P1-AS			
10A-E22-T135-P1-BS			
10A-E22-T135-P2-AS			
10A-E22-T135-P2-BS			
10A-E22-T135-P3-AS			
10A-E22-T135-P3-BS			
10A-E22-T014-P1-AS			
10A-E22-T014-P1-BS			
10A-E22-T014-P2-AS			
10A-E22-T014-P2-BS			
10A-E22-T014-P3-AS			
10A-E22-T014-P3-BS			
10A-E22-T042-P1-AS			

Sample ID	Analyte	Hold Time (Days)	Hold Time Criteria (Days)
10A-E22-T042-P1-BS	SSC	30-42	28
10A-E22-T042-P2-AS			
10A-E22-T042-P2-BS			
10A-E22-T042-P3-AS			
10A-E22-T042-P3-BS			
10A-E22-T135-P1-AT			
10A-E23-T067-P3-AS			
10A-E23-T067-P3-BS			
10A-E23-T102-P1-AS			
10A-E23-T102-P1-BS			
10A-E23-T135-P3-AS			
10A-E23-T135-P3-BS			
10A-E21-T067-P2-BS			
10A-E21-T067-P2-BT			
10A-E23-T042-P1-AS			
10A-E23-T042-P1-BS			
10A-E20-T175-P1-AS			
10A-E20-T175-P2-AS			
10A-E20-T175-P2-BS			
10A-E20-T175-P3-AS			
10A-E20-T175-P4-AS			
10A-E20-T175-P4-XR			

Table A-2 – Field Duplicate RPDs

Sample ID	Duplicate ID	Analyte	Sample Result	Duplicate Result	QL	Units	RPD
10A-E21-T067-P2-BS	10A-E21-T067-P2-BT	SSC	117	50	1	mg/L	80.2

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection Newark Bay July Sampling Events	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10070367, 10070368, 10070381, 10070382, 10070391, 10070394, 10070423		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited (All SDGs except 10070394) Full (10070394 only)		
AECOM Project Number	60144462-A410		
Prepared by	Sharon McKechnie/AECOM	Completed October 27, 2010	
Reviewed by	Lisa Krowitz/AECOM	File Name: July NB 2010 SSC 7 SDGs.doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in Newark Bay, New Jersey on July 21, 25, and 26, 2010.

SDG	Client Sample ID	Matrix
10070367	N01-E21-TNBN-P1-AS	Aqueous
	N01-E21-TNBN-P1-BS	Aqueous
	N01-E21-TNBN-P2-AS	Aqueous
	N01-E21-TNBN-P2-BS	Aqueous
	N01-E21-TNBN-P3-AS	Aqueous
	N01-E21-TNBN-P3-BS	Aqueous
	N01-E21-TNBS-P1-AS	Aqueous
	N01-E21-TNBS-P1-BS	Aqueous
	N01-E21-TNBS-P1-BT (Field duplicate of N01-E21-TNBS-P1-BS)	Aqueous
	N01-E21-TNBS-P3-AS	Aqueous
	N01-E21-TNBS-P3-BS	Aqueous
10070368	N01-E21-TKVK-P1-AS	Aqueous
10070368	N01-E21-TKVK-P1-BS	Aqueous
	N01-E21-TKVK-P2-AS	Aqueous

SDG	Client Sample ID	Matrix
	N01-E21-TKVK-P2-BS	Aqueous
	N01-E21-TKVK-P3-AS	Aqueous
	N01-E21-TKVK-P3-BS	Aqueous
	N01-E21-TNBS-P2-AS	Aqueous
	N01-E21-TNBS-P2-BS	Aqueous
10070381	N01-E22-TARK-P1-AS	Aqueous
	N01-E22-TARK-P1-BS	Aqueous
	N01-E22-TARK-P2-AS	Aqueous
	N01-E22-TARK-P2-BS	Aqueous
	N01-E22-TARK-P3-AS	Aqueous
	N01-E22-TARK-P3-BS	Aqueous
	N01-E22-TARK-P3-XR (Equipment blank collected 7/21/10)	Aqueous
	N01-E22-THKN-P1-AS	Aqueous
	N01-E22-THKN-P1-BS	Aqueous
	N01-E22-THKN-P2-AS	Aqueous
	N01-E22-THKN-P2-BS	Aqueous
	N01-E22-THKN-P3-AS	Aqueous
	N01-E22-THKN-P3-BS	Aqueous
10070382	N01-E21-TARK-P1-AS	Aqueous
	N01-E21-TARK-P1-BS	Aqueous
	N01-E21-TARK-P2-AS	Aqueous
	N01-E21-TARK-P2-BS	Aqueous
	N01-E21-TARK-P2-BT (Field duplicate of N01-E21-TARK-P2-BS)	Aqueous
	N01-E21-TARK-P3-AS	Aqueous
	N01-E21-TARK-P3-BS	Aqueous
	N01-E21-THKN-P1-AS	Aqueous
	N01-E21-THKN-P1-BS	Aqueous
	N01-E21-THKN-P3-AS	Aqueous
	N01-E21-THKN-P3-AT (Field duplicate of N01-E21-THKN-P3-AS)	Aqueous
	N01-E21-THKN-P3-BS	Aqueous
10070391	N01-E22-THKN-P2-AS	Aqueous
	N01-E22-THKN-P2-BS	Aqueous
	N01-E22-TKVK-P1-AS	Aqueous
	N01-E22-TKVK-P1-BS	Aqueous
	N01-E22-TKVK-P1-BT (Field duplicate of N01-E22-TKVK-P1-BS)	Aqueous
	N01-E22-TKVK-P2-AS	Aqueous
	N01-E22-TKVK-P2-BS	Aqueous
10070391	N01-E22-TKVK-P3-AS	Aqueous
10070391	N01-E22-TKVK-P3-BS	Aqueous

SDG	Client Sample ID	Matrix
	N01-E22-TNBS-P1-BS	Aqueous
10070394	N01-E22-TNBN-P1-AS	Aqueous
	N01-E22-TNBN-P1-BS	Aqueous
	N01-E22-TNBN-P2-AS	Aqueous
	N01-E22-TNBN-P2-BS	Aqueous
	N01-E22-TNBN-P3-AS	Aqueous
	N01-E22-TNBN-P3-BS	Aqueous
	N01-E22-TNBS-P1-AS	Aqueous
	N01-E22-TNBS-P2-AS	Aqueous
	N01-E22-TNBS-P2-BS	Aqueous
	N01-E22-TNBS-P3-AS	Aqueous
	N01-E22-TNBS-P3-AT (Field duplicate of N01-E22-TNBS-P3-AS)	Aqueous
	N01-E22-TNBS-P3-BS	Aqueous
10070423	N01-E23-THKN-P1-AS	Aqueous
	N01-E23-THKN-P1-BS	Aqueous
	N01-E23-TKVK-P1-AS	Aqueous
	N01-E23-TKVK-P1-BS	Aqueous
	N01-E23-TNBS-P1-AS	Aqueous
	N01-E23-TNBS-P1-AT (Field duplicate of N01-E23-TNBS-P1-AS)	Aqueous
	N01-E23-TNBS-P1-BS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Nonconformances are summarized in Attachment A, Table A-1. Samples analyzed beyond the QAPP specified holding times were qualified as estimated for detected results or non-detected results (J/UJ). Additionally, samples analyzed beyond 2x the holding time were rejected (R) for non-detected results.

Qualified sample results are shown in Table 1.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. EBs were associated with all samples collected in the same week as the EB. EB N01-E22-TARK-P3-XR, collected on 7/21/2010 and reported in SDG 10070381 and EB N01-E23-TNBN-P1-XR collected on 7/25/10 and reported in SDG 10070422, were associated with all samples collected 7/19/2010 through 7/25/2010. No SSC > RL was detected in either EB.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Analyte	Result	QL	Units	Validation Qualifiers	Validation Reason
N01-E22-THKN-P2-AS	W	SSC	10	1	mg/L	J	h
N01-E22-THKN-P2-BS	W	SSC	12	1	mg/L	J	h
N01-E22-TKVK-P1-AS	W	SSC	8	1	mg/L	J	h
N01-E22-TKVK-P1-BS	W	SSC	21	1	mg/L	J	h
N01-E22-TKVK-P1-BT	W	SSC	20	1	mg/L	J	h
N01-E22-TKVK-P2-AS	W	SSC	13	1	mg/L	J	h
N01-E22-TKVK-P2-BS	W	SSC	8	1	mg/L	J	h
N01-E22-TKVK-P3-AS	W	SSC	8	1	mg/L	J	h
N01-E22-TKVK-P3-BS	W	SSC	11	1	mg/L	J	h
N01-E22-TNBS-P1-BS	W	SSC	38	1	mg/L	J	h
N01-E22-TNBN-P1-AS	W	SSC	7	1	mg/L	J	h
N01-E22-TNBN-P1-BS	W	SSC	34	1	mg/L	J	h
N01-E22-TNBN-P2-AS	W	SSC	14	1	mg/L	J	h
N01-E22-TNBN-P2-BS	W	SSC	9	1	mg/L	J	h
N01-E22-TNBN-P3-AS	W	SSC	9	1	mg/L	J	h
N01-E22-TNBN-P3-BS	W	SSC	9	1	mg/L	J	h
N01-E22-TNBS-P1-AS	W	SSC	8	1	mg/L	J	h
N01-E22-TNBS-P2-AS	W	SSC	6	1	mg/L	J	h
N01-E22-TNBS-P2-BS	W	SSC	16	1	mg/L	J	h
N01-E22-TNBS-P3-AS	W	SSC	5	1	mg/L	J	h
N01-E22-TNBS-P3-AT	W	SSC	6	1	mg/L	J	h
N01-E22-TNBS-P3-BS	W	SSC	7	1	mg/L	J	h
N01-E23-THKN-P1-AS	W	SSC	12	1	mg/L	J	h
N01-E23-THKN-P1-BS	W	SSC	5	1	mg/L	J	h
N01-E23-TKVK-P1-AS	W	SSC	6	1	mg/L	J	h
N01-E23-TKVK-P1-BS	W	SSC	7	1	mg/L	J	h
N01-E23-TNBS-P1-AS	W	SSC	7	1	mg/L	J	h
N01-E23-TNBS-P1-AT	W	SSC	8	1	mg/L	J	h
N01-E23-TNBS-P1-BS	W	SSC	7	1	mg/L	J	h

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions

Attachment A

Nonconformance Summary Tables

Table A-1 - Hold Time

Sample ID	Analyte	Days from Sampling to Analysis	Contractual Holding Time Criteria (Days)
N01-E22-THKN-P2-AS	SSC	33-42	28
N01-E22-THKN-P2-BS			
N01-E22-TKVK-P1-AS			
N01-E22-TKVK-P1-BS			
N01-E22-TKVK-P1-BT			
N01-E22-TKVK-P2-AS			
N01-E22-TKVK-P2-BS			
N01-E22-TKVK-P3-AS			
N01-E22-TKVK-P3-BS			
N01-E22-TNBS-P1-BS			
N01-E22-TNBN-P1-AS			
N01-E22-TNBN-P1-BS			
N01-E22-TNBN-P2-AS			
N01-E22-TNBN-P2-BS			
N01-E22-TNBN-P3-AS			
N01-E22-TNBN-P3-BS			
N01-E22-TNBS-P1-AS			
N01-E22-TNBS-P2-AS			
N01-E22-TNBS-P2-BS			
N01-E22-TNBS-P3-AS			
N01-E22-TNBS-P3-AT			
N01-E22-TNBS-P3-BS			
N01-E23-THKN-P1-AS			
N01-E23-THKN-P1-BS			
N01-E23-TKVK-P1-AS			
N01-E23-TKVK-P1-BS			
N01-E23-TNBS-P1-AS			
N01-E23-TNBS-P1-AT			
N01-E23-TNBS-P1-BS			

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection November Wet Weather Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ Columbia Analytical Services, Inc., Tucson, AZ (DOC, POC)		
Work Orders	10110002, 10110003, 10110004, 10110005, and 10110006		
Analyses/Method	CHN by Combustion/Thermo-Conductivity Detection/440.0 Total and Dissolved Organic Carbon in Aqueous Matrix/5130C		
Validation Level	Limited (All except 10110005) Full (10110005 only)		
AECOM Project Number	60145884.A452		
Prepared by	Sharon McKechnie/AECOM	Completed January 13, 2011	
Reviewed by	Lisa Krowitz/AECOM	File: LPR PWCM Nov Wet Weather POC DOC .doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on November 4, 2010.

SDG	Client Sample ID	Matrix
10110002 (Xenco) 1001150 (CAS)	10C-E07-T169-P1-AS	Aqueous
	10C-E08-T169-P1-AS	Aqueous
	10C-E09-T169-P1-AS	Aqueous
	10C-E10-T169-P1-AS	Aqueous
	10C-E11-T169-P1-AS	Aqueous
	10C-E12-T169-P1-AS	Aqueous
	10C-E12-T169-P1-XR (Equipment blank)	Aqueous

SDG	Client Sample ID	Matrix
10110003 (Xenco) 1001151 (CAS)	10C-E07-T3R1-P1-AS	Aqueous
	10C-E08-T3R1-P1-AS	Aqueous
	10C-E09-T3R1-P1-AS	Aqueous
	10C-E09-T3R1-P1-AT (Field duplicate of 10C-E09-T3R1-P1-AS)	Aqueous
	10C-E10-T3R1-P1-AS	Aqueous
	10C-E11-T3R1-P1-AS	Aqueous
	10C-E12-T3R1-P1-AS	Aqueous
10110004 (Xenco) 1001152 (CAS)	10C-E07-TSR2-P1-AS	Aqueous
	10C-E08-TSR2-P1-AS	Aqueous
	10C-E09-TSR2-P1-AS	Aqueous
	10C-E09-TSR2-P1-AT (Field duplicate of 10C-E09-TSR2-P1-AS)	Aqueous
	10C-E10-TSR2-P1-AS	Aqueous
	10C-E11-TSR2-P1-AS	Aqueous
	10C-E12-TSR2-P1-AS	Aqueous
10110005 (Xenco) 1001153 (CAS)	10C-E07-T2R1-P1-AS	Aqueous
	10C-E08-T2R1-P1-AS	Aqueous
	10C-E09-T2R1-P1-AS	Aqueous
	10C-E10-T2R1-P1-AS	Aqueous
	10C-E11-T2R1-P1-AS	Aqueous
	10C-E12-T2R1-P1-AS	Aqueous
	10C-E12-T3R1-P1-XR (Equipment blank)	Aqueous
10110006 (Xenco) 1001154 (CAS)	10C-E07-T169-P2-AS	Aqueous
	10C-E08-T169-P2-AS	Aqueous
	10C-E09-T169-P2-AS	Aqueous
	10C-E10-T169-P2-AS	Aqueous
	10C-E11-T169-P2-AS	Aqueous
	10C-E12-T169-P2-AS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Particulate Organic Carbon (POC)	Aqueous	*Determination of Carbon and Nitrogen in Sediments and Particulates of Estuarine/Coastal Waters Using Elemental Analysis*, Method 440.0 (Revision 1.4, September 1997).
Dissolved Organic Carbon (DOC)	Aqueous	*Total Organic Carbon, Standard methods for the Examination of Water and Wastewater*, Method 5310C, 20th Edition, 1995.

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation	Ö		
Calibrations		Ö	
Laboratory method blanks/equipment blanks		Ö	
Matrix spike/matrix spike duplicate (MS/MSD) results	Ö		
Field duplicate results	Ö		
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results	Ö		
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

According to CAS sample check in form for SDG 10110006 (CAS 1001154), preservation of the filtered DOC samples from Xenco was not clear. Confirmation was obtained from Xenco that the DOC samples were preserved. No action was taken other than this note.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Calibrations

The data were reviewed to ensure that the initial and continuing calibrations percent recovery (%R) and correlation coefficient (r) QC acceptance criteria were met. Qualification action on the basis of calibration nonconformance was as follows:

Qualification based on ICV/CCV	%R of Analyte in the ICV/CCV and Recommended Actions			
	< 50%	50 to 96%	104 to 180%	> 180%
Detected results	R	J	J	R
Nondetects	R	UJ	Accept	Accept

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs), continuing calibration blanks (CCBs), and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an “XR” as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination.

The MB associated with the DOC samples reported in SDG 10110002 was positive for DOC above the RL. No contaminants were detected above the MDL in any of the other MBs associated with the remaining samples in this data set.

Qualification action on the basis of MB nonconformance was as follows:

Blank Type	Sample Result	Actions
EB/CCB/MB	Nondetect	No action
	£ the QL	Qualify as nondetect (U) at the QL
	> the QL but £10x the blank concentration	Qualify results as estimated (J)
	> 10x the blank concentration	No action

Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

EBs were associated with all samples collected in the same week as the EB. EB 10C-E12-T169-P1-XR, collected on 11/4/2010 and reported in SDG 10110002 and EB 10C-E12-T3R1-P1-XR collected on 11/4/2010 and reported in SDG 10110005 are associated with all samples collected 11/4/2010. No POC or DOC was detected above the QL in either of the EBs.

MS/MSD Results

The MS/MSD %Rs and the MSD relative percent differences (RPDs) were evaluated for conformance with the QC acceptance criteria.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria of 80-120% for DOC and 95-105% for POC.

Laboratory Duplicate Results

The laboratory duplicate (LD) RPDs were reviewed for conformance with the Region 2 metals guidance and QC acceptance criteria of RPD ≤ 20% (if both results were greater than ten times the QL).

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Compound	Result	QL	Units	Validation Qualifiers	Validation Reason
10C-E07-T169-P1-AS	WS	DOC	7.36	0.50	mg/l	J	bl
10C-E08-T169-P1-AS	WS	DOC	7.69	0.50	mg/l	J	bl
10C-E09-T169-P1-AS	WS	DOC	7.43	0.50	mg/l	J	bl
10C-E10-T169-P1-AS	WS	DOC	7.73	0.50	mg/l	J	bl
10C-E11-T169-P1-AS	WS	DOC	7.53	0.50	mg/l	J	bl
10C-E12-T169-P1-AS	WS	DOC	5.89	0.50	mg/l	J	bl
10C-E07-T169-P1-AS	WS	POC	1.2	1	mg/l	J	c
10C-E08-T169-P1-AS	WS	POC	1.3	0.9	mg/l	J	c
10C-E09-T169-P1-AS	WS	POC	1.6	0.9	mg/l	J	c
10C-E07-T2R1-P1-AS	WS	POC	28.5	1	mg/l	J	c
10C-E08-T2R1-P1-AS	WS	POC	20.2	1	mg/l	J	c
10C-E09-T2R1-P1-AS	WS	POC	12	1	mg/l	J	c
10C-E10-T2R1-P1-AS	WS	POC	10.1	1	mg/l	J	c
10C-E11-T2R1-P1-AS	WS	POC	11.7	1	mg/l	J	c
10C-E12-T2R1-P1-AS	WS	POC	9.6	1	mg/l	J	c
10C-E09-TSR2-P1-AT	WS	POC	3.2	0.9	mg/l	J	c
10C-E10-TSR2-P1-AS	WS	POC	3.9	0.9	mg/l	J	c
10C-E11-TSR2-P1-AS	WS	POC	4.2	1	mg/l	J	c
10C-E12-TSR2-P1-AS	WS	POC	5.7	1	mg/l	J	c
10C-E12-T3R1-P1-XR	WS	POC		0.9	mg/l	J	c

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- Nondetect results will have no value in the result column

Attachment A

Nonconformance Summary Tables

Table A-1 – Calibration Recovery

ICV/CCV	Analyte	Standard mg/L C	Result (mg/L C)	Recovery (%)
12/11/10 @1500	POC	4700	4520	96.2
Affected Samples:	10C-E07-T169-P1-AS, 10C-E08-T169-P1-AS, 10C-E09-T169-P1-AS			
12/11/10 @1710	POC	13000	13460	103.5
Affected Samples:	10C-E09-TSR2-P1-AT, 10C-E10-TSR2-P1-AS, 10C-E11-TSR2-P1-AS, 10C-E12-TSR2-P1-AS, 10C-E12-T3R1-P1-XR, 10C-E12-T2R1-P1-AS, 10C-E07-T2R1-P1-AS, 10C-E08-T2R1-P1-AS, 10C-E11-T2R1-P1-AS, 10C-E09-T2R1-P1-AS, 10C-E10-T2R1-P1-AS			

Table A-2 – Laboratory Method Blanks

Method Blank	Analyte	Result (mg/L)	Reporting Limit (mg/L)
MB#1 (Filter blank)	DOC	1.08	0.50
Affected Samples:	All DOC samples except the EB in SDG 10110002		

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

AECOM
250 Apollo Drive
Chelmsford, MA 01824

978.905.2100 tel
978.905.2101 fax

Privileged and Confidential – Prepared at Request of Counsel

Data Validation Report

Project	Lower Passaic River Restoration Project Remediation Investigation Water Column Monitoring Physical Data Collection November Wet Weather Sampling Event	Page	1
Laboratory	Xenco Laboratories, Phoenix, AZ		
Work Orders	10110002, 10110003, 10110004, 10110005, and 10110006		
Analyses/Method	Suspended Sediment Concentration/ASTM D-3977-97		
Validation Level	Limited (All except 10110005) Full (10110005 only)		
AECOM Project Number	60145884.A452		
Prepared by	Sharon McKechnie/AECOM	Completed January 13, 2011	
Reviewed by	Lisa Krowitz/AECOM	File Name: LPR PWCM Nov Wet Weather SSC.doc	

SUMMARY

The samples listed below were collected by AECOM from the Lower Passaic River Study Area in New Jersey on November 4, 2010.

SDG	Client Sample ID	Matrix
10110002	10C-E07-T169-P1-AS	Aqueous
	10C-E08-T169-P1-AS	Aqueous
	10C-E09-T169-P1-AS	Aqueous
	10C-E10-T169-P1-AS	Aqueous
	10C-E11-T169-P1-AS	Aqueous
	10C-E12-T169-P1-AS	Aqueous
	10C-E12-T169-P1-XR (Equipment blank)	Aqueous
10110003	10C-E07-T3R1-P1-AS	Aqueous
	10C-E08-T3R1-P1-AS	Aqueous
	10C-E09-T3R1-P1-AS	Aqueous
	10C-E09-T3R1-P1-AT (Field duplicate of 10C-E09-T3R1-P1-AS)	Aqueous
	10C-E10-T3R1-P1-AS	Aqueous
	10C-E11-T3R1-P1-AS	Aqueous
10110003	10C-E12-T3R1-P1-AS	Aqueous

SDG	Client Sample ID	Matrix
10110004	10C-E07-TSR2-P1-AS	Aqueous
	10C-E08-TSR2-P1-AS	Aqueous
	10C-E09-TSR2-P1-AS	Aqueous
	10C-E09-TSR2-P1-AT (Field duplicate of 10C-E09-TSR2-P1-AS)	Aqueous
	10C-E10-TSR2-P1-AS	Aqueous
	10C-E11-TSR2-P1-AS	Aqueous
	10C-E12-TSR2-P1-AS	Aqueous
10110005	10C-E07-T2R1-P1-AS	Aqueous
	10C-E08-T2R1-P1-AS	Aqueous
	10C-E09-T2R1-P1-AS	Aqueous
	10C-E10-T2R1-P1-AS	Aqueous
	10C-E11-T2R1-P1-AS	Aqueous
	10C-E12-T2R1-P1-AS	Aqueous
	10C-E12-T3R1-P1-XR (Equipment blank)	Aqueous
10110006	10C-E07-T169-P2-AS	Aqueous
	10C-E08-T169-P2-AS	Aqueous
	10C-E09-T169-P2-AS	Aqueous
	10C-E10-T169-P2-AS	Aqueous
	10C-E11-T169-P2-AS	Aqueous
	10C-E12-T169-P2-AS	Aqueous

The following methods were applicable to the samples in this data set:

Analyte	Matrix	Primary Method Reference
Suspended Sediment Concentration	Aqueous	*Standard Methods for Determining Sediment Concentration for Water Samples,* American Society for Testing and Materials, Method D3977-97, 1997 (revised 2002)

Data validation activities were conducted with reference to the above methods along with USEPA Region II validation SOPs (note that in the absence of a method-specific SOP, related SOPs were used as guidance) and the Quality Assurance Project Plan, RI Water Column Monitoring/Physical Data Collection (QAPP) (AECOM, 2009). Specifically, the analytical data were evaluated for the elements listed below compared to the criteria in QAPP worksheets #12, 15, 19, 24, and 28. In the absence of QAPP-specified criteria, method, laboratory, or Region II limits were used as appropriate.

REVIEW ELEMENTS

Sample data were reviewed for the following quality control (QC) parameters:

Parameter Reviewed	Were acceptance criteria met?		
	Yes	No	NA
Chain-of-custody (COC)/sample integrity	Ö		
Data completeness	Ö		
Holding times and sample preservation		Ö	
Calibrations(Analytical balance for SSC)	Ö		
Laboratory method blanks/equipment blanks	Ö		
Matrix spike/matrix spike duplicate (MS/MSD) results			Ö
Field duplicate results		Ö	
Laboratory control sample (LCS) results	Ö		
Laboratory duplicate results			Ö
Sample results	Ö		
Notes: NA- *Not applicable to this data set since the QC parameter was not collected as part of this data set.*			

RESULTS

COC/Sample Integrity

The COCs were reviewed for completeness of information relevant to the samples and requested analyses, and for signatures indicating transfer of sample custody.

The laboratory sample login sheet(s) were reviewed for issues potentially affecting sample integrity, including the condition of sample containers and COC seals upon receipt at the laboratory.

Data Completeness

The data package was reviewed to verify that the information required in the QAPP was included. Completeness of analyses was verified by comparing the reported results to the COC requests.

Holding Times/Sample Preservation

Sample preservation and preparation/analysis holding times were reviewed for conformance to the QAPP.

Several samples were associated with a prep oven temperature nonconformance. The drying oven used for SSC was set by the analyst prior to leaving for the day. Upon the analyst checking the oven the following morning, the drying oven was noted to be at 160°C. Since the temperature was higher than the method specified temp of 105°C, the associated sample results were qualified as estimated (J/UJ).

Nonconformances are summarized in Attachment A, Table A-1. Qualified sample results are shown in Table 1.

Calibrations

Analytical balance records were reviewed to ensure that QC acceptance criteria were met.

Laboratory Blanks/Equipment Blanks

Method blanks (MBs) and equipment rinsate (EB) blank results were evaluated as to whether there were contaminants detected above the method detection limit (MDL). EBs were identified with an "XR" as the last character of the sample ID. Per Region II guidance, EBs were not qualified on the basis of MB contamination. No contaminants were detected above the MDL in any of the MBs associated with the samples in this data set.

EBs were associated with all samples collected in the same week as the EB. EB 10C-E12-T169-P1-XR collected on 11/4/2010 and reported in SDG 10110002 and EB 10C-E12-T3R1-P1-XR collected on 11/4/2010 and reported in SDG 10110005 are associated with all samples collected 11/4/2010. Data validation qualifiers for individual samples were based on the maximum contaminant concentration detected in all associated blanks. No SSC was detected above the RL in either of the EBs.

Field Duplicate Results

Field duplicates are identified with a "T" as the last character of the sample ID (the associated field sample has the same ID with an "S" as the last character). The relative percent differences (RPDs) were reviewed for conformance with the QAPP QC acceptance criteria of ≤ 50% (if both results were greater than ten times the QL), for SSC. Data qualification on the basis of field duplicate RPDs was as follows (see above for acceptance criteria):

Criteria	Action	
	Detected	Nondetected
RPD greater than the acceptance criteria, but < 120% and sample and duplicate results >5x the SQL	J	Not Applicable
RPD ≥ 120%	R	Not Applicable
If sample and/or duplicate is <5x the QL and absolute difference is >2x and ≤ 4x the QL	J	UJ
If the sample and/or duplicate is <5x the QL and absolute difference is >4x the QL.	R	R

Qualified sample results are shown in Table 1. Nonconformances are summarized in Attachment A, Table A-2. Qualified sample results are shown in Table 1.

LCS Results

The LCS and LCS duplicate (LCSD) %Rs and LCSD RPDs were reviewed for conformance with the QC acceptance criteria.

Sample Results

Any sample that was analyzed at a dilution due to high concentrations of target or non-targets was checked to ensure that the result and/or sample specific QL were adjusted accordingly by the laboratory.

Qualification Actions

Sample results qualified as a result of validation actions are summarized in Table 1. All actions are described above.

ATTACHMENTS

Attachment A: Nonconformance Summary Tables

Attachment B: LPRRP Validation Qualifier Codes and Explanation

Attachment C: LPRRP Validation Reason Codes and Explanation

Table 1

Data Validation Summary Table

Table 1 - Data Validation Summary of Qualified Data

Sample ID	Matrix	Compound	Result	QL	Units	Validation Qualifiers	Validation Reason
10C-E07-T2R1-P1-AS	WS	SSC	113	1	mg/l	J	sp
10C-E08-T2R1-P1-AS	WS	SSC	174	1	mg/l	J	sp
10C-E09-T2R1-P1-AS	WS	SSC	62	1	mg/l	J	sp
10C-E10-T2R1-P1-AS	WS	SSC	43	1	mg/l	J	sp
10C-E11-T2R1-P1-AS	WS	SSC	166	1	mg/l	J	sp
10C-E12-T2R1-P1-AS	WS	SSC	63	1	mg/l	J	sp
10C-E12-T3R1-P1-XR	WQ	SSC		1	mg/l	UJ	sp
10C-E07-T169-P2-AS	WS	SSC	8	1	mg/l	J	sp
10C-E08-T169-P2-AS	WS	SSC	5	1	mg/l	J	sp
10C-E09-T169-P2-AS	WS	SSC	16	1	mg/l	J	sp
10C-E10-T169-P2-AS	WS	SSC	8	1	mg/l	J	sp
10C-E11-T169-P2-AS	WS	SSC	15	1	mg/l	J	sp
10C-E12-T169-P2-AS	WS	SSC	26	1	mg/l	J	sp
10C-E09-TSR2-P1-AS	WS	SSC	34	1	mg/l	J	fd
10C-E09-TSR2-P1-AT	WS	SSC	25	1	mg/l	J	fd
10C-E12-TSR2-P1-AS	WS	SSC	42	1	mg/l	J	sp

- Refer to Attachment A for QC element nonconformance summary
- Refer to Attachment B for validation qualifier definitions
- Refer to Attachment C for validation reason code definitions
- Nondetected results will not have a value in the result column

Attachment A

Nonconformance Summary Tables

Table A-1 – Sample Prep Oven Nonconformance

Sample ID	Oven Temp	Method Specified Oven Temp
10C-E07-T2R1-P1-AS	160°C	105°C
10C-E08-T2R1-P1-AS		
10C-E09-T2R1-P1-AS		
10C-E10-T2R1-P1-AS		
10C-E11-T2R1-P1-AS		
10C-E12-T2R1-P1-AS		
10C-E12-T3R1-P1-XR		
10C-E07-T169-P2-AS		
10C-E08-T169-P2-AS		
10C-E09-T169-P2-AS		
10C-E10-T169-P2-AS		
10C-E11-T169-P2-AS		
10C-E12-T169-P2-AS		
10C-E12-TSR2-P1-AS		

Table A-2 – Field Duplicate RPDs

Sample ID	Duplicate ID	Analyte	Sample Result	Duplicate Result	QL	Units	RPD
10C-E09-TSR2-P1-AS	10C-E09-TSR2-P1-AT	SSC	34	25	1	mg/L	30.5

Attachment B

LPRRP Validation Qualifier Codes and Explanations

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
N	The analysis indicates the presence of an analyte for which there is presumptive evidence to make a “tentative identification”.
JN	The analysis indicates the presence of an analyte that has been “tentatively identified” and the associated numerical value represents its approximate concentration.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
R	The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
B	The result may be a false positive (totally attributed to blank contamination). (radiochemical data only)
JB	The result may be biased high, partially attributed to blank contamination. (radiochemical data only)
Q	The associated sample results combined standard uncertainty exceeded the project required uncertainty.

Rev. 0

Attachment C

LPRRP Validation Reason Codes and Explanations

Reason Code	Explanation
a	Tracer recovery (radiochemical data only)
be	Equipment blank (or trip blank) contamination
bl	Laboratory blank contamination
bm	Missing blank information
c	Calibration issue
cp	Insufficient in growth (radiochemical data only)
cl	Clean-up standard recovery
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
e	Ether interference
fd	Field duplicate RPDs
g	Chromatographic pattern match issue
h	Holding times
i	Internal standard areas
k	Estimated Maximum Possible Concentrations
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs (matrix duplicate, MSD, LCSD)
m	Matrix spike recovery
nb	Negative laboratory blank contamination
p	Chemical preservation issue
pe	Post extraction spike
r	Dual column RPD
q	Quantitation issue
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature preservation issue
u	High combined sample result uncertainty (radiochemical data only)
v	Compound identification issue
x	Low % solids
y	Serial dilution results
z	ICS results

Appendix G

ACDP Current and Wave Data Resubmittal from Fall 2009 and Spring/Summer 2010 Deployments

MARINE AND FRESHWATER
SURVEY SERVICES

OCEAN SURVEYS, INC.
129 MILL ROCK ROAD EAST
OLD SAYBROOK, CT 06475
TEL. (860) 388-4631 FAX (860) 388-5879
www.oceansurveys.com

20 February 2014

SUBJECT: ADCP CURRENT AND WAVE DATA RESUBMITTAL FROM FALL 2009 AND SPRING/SUMMMER 2010 DEPLOYMENTS PASSAIC RIVER AND NEWARK BAY, NJ

To whom it may concern:

During the Fall of 2009 and the Spring/Summer of 2010, Ocean Surveys, Inc. (OSI) deployed a series of oceanographic instrumentation within the Passaic River, Newark Bay, and adjacent water bodies under contract with AECOM. This instrumentation included both Acoustic Doppler Current Profilers (ADCPs) on bottom moorings and YSI Water Quality Sondes on bottom moorings and surface buoys. Since the data submittal in 2010, questions have arisen regarding the current directional data from the ADCPs. I have recently reviewed all the ADCP data from both the Fall 2009 and Spring/Summer 2010 datasets. In doing so, I've come to the conclusion that compass offsets were not originally applied correctly during data processing. As such, I have reworked all of the ADCP data for the entire project and the data has been re-submitted as attached data files to this letter. Below is an explanation of the field procedures and logistical considerations at the time of the deployment along with a description of the data processing steps taken to adjust current directional data.

Field Operations

In understanding the step by step process in collecting and processing this data, one must first look at the logistic scenarios involved the deployments. The compass in each ADCP was calibrated as per the manufacturer's recommended procedures prior to the initial deployment during each of the two project periods (Fall 2009 and Spring/Summer 2010). At approximately one-month intervals, each ADCP was recovered, downloaded, re-powered, and re-deployed. Due to the swift tidal currents in this area, most ADCPs were serviced during slack tidal period. The procedure to calibrate the compass of an ADCP involves rotating the ADCP at various fixed pitch and roll settings in an area free of significant magnetic interference. Due to the movement of the vessel on the water and the magnetic signature of the vessel, a proper calibration of the compass would need to be conducted off the vessel and on land. To transit off station and conduct the calibration on land, the window to re-deploy the ADCP during the same slack tide would be lost. Typically, there are either one or two slack tidal periods during daylight hours on any given day. Essentially, calibrating an ADCP compass on land would have meant a minimum of a six (6) hour data loss if the unit was recovered during a morning slack tide and re-deployed on the afternoon slack tide or possibly as much as a twenty-four (24) hour data loss if the slack tide was around mid-day. After consultation with many involved including those outside OSI, I

ultimately made the decision to have the field crew change the batteries on the vessel and re-deploy without a compass calibration to reduce the amount of lost data due to the tidal concerns.

During each servicing, a number of checks were conducted as part the manufacturer's standard deployment procedures. System checks were conducted on the internal electrical boards, memory, and command library. Pitch and roll sensors were tested. Also, the compass was run through a Compass Verification procedure. During this test, each ADCP was slowly turned for one full rotation. If at any point during the rotation a heading on the compass was not detected, the test would have failed. All units deployed on this project passed this test on every deployment indicating the units were reading a full 360 degree current velocity range. After conclusion of the Compass Verification, each unit displays a total error in degrees. This error is always a positive number so it does not indicate an offset by which to correct the data. Also, since the test was conducted on the vessel the displayed error can be influenced by the vessels environment much like a full calibration would have been affected. The tests conducted in the field indicted fully working ADCPs were deployed at each station with a full 360 degree current velocity range.

There are a number of factors which can influence a compass heading during repeat deployments. First, as I mentioned, the ADCP's compasses were not calibrated during servicings for the reasons mentioned above. Secondly, to counteract the effect of a battery on the compass, all batteries were supposed to be degaussed by our supplier. The degaussing process, if conducted correctly, will remove the magnetic signature of the battery. If the degaussing was not conducted, the influence of the battery would be more significant. Thirdly, any magnetic debris near the deployment location could influence the compass. The instruments were re-deployed at the same location after each servicing but the orientation of the mount was most certainly different. If there were steel debris near the mooring, the influence could vary between deployments. Recently, I was provided GIS data of car and wreck debris in the Passaic River which listed forty (40) possible targets within the river. The possibility of debris on the bottom in the Passaic River and Newark Bay is very high. On a similar project in the Passaic River, our moorings were repeatedly recovered with large amounts of debris over the moorings (typically non-magnetic, see Figure 1) and the 2009 and 2010 deployment projects were no exception. Note, the same magnetic variation was applied internally for both 2009 and 2010 instrumentation but yearly change is very small, about 0.07 degrees per year.

Figure 1. Instrument mooring with debris from the Passaic River.

The ADCPs used during both of these projects were manufacturer between 1999 and 2010. Early models contained flux gate compasses with a long term accuracy of +/- 5 degrees and later models with an accuracy of +/- 2 degrees. The manufacturer recommends calibrating the compass when the compass error is greater than 5 degrees simply due to the accuracy of the compass.

Data Processing

Each ADCP measures current velocity internally in beam coordinates which simply means relative to the face of each of its four transducers. The ADCP then conducts a number of tasks internally within its firmware. The beam velocities are converted to East, North and vertical current vectors relative to the head of the instrument using an internal beam coordinate transformation to account for the transducers mounting angles, pitch and roll. These current vectors are used to calculate the current magnitude and direction but the current direction is relative to the head of the ADCP. At this point current direction is rotated to magnetic north by offsets provided in real-time from the compass and then shifted again by a user defined magnetic variation to convert the final bearing into earth coordinates relative to true north. Note, the current magnitude is not influenced by the compass and should be considered accurate for all data provided to date.

The current velocity data provided with this letter has been re-processed to correct compass offsets for any of the possible reasons listed above. The current magnitude has been untouched from previous datasets as it is considered accurate as previously reported. The only exception would be the initial deployment at Station 042 from the Spring 2010 where data was originally incorrectly imported into our processing procedures. The error has been resolved.

For each project period (Fall 2009 and Spring/Summer 2010), the current directions from the first deployment at each station are considered the most accurate since the internal compasses were calibrated prior to this deployment. Any underwater influences on the compasses during the first deployment were not considered. The dominant flow direction of the Passaic River, Newark Bay, Hackensack River, Kill Van Kull, and Arthur Kill is during the ebb (out-going) tide. As such, the mean ebb tidal flow directions were calculated for each deployment at each station. The difference between the initial deployment and subsequent deployments at each individual station were used as compass offsets to adjust the entire dataset for each individual deployment. The offsets are listed in Table 1 attached to this letter. Current magnitude values were not affected by this adjustment.

Four data files that have been updated to reflect the offsets and adjustments listed above are made available with this submittal.

1) ADCP_Current_Data-LPR-Fall 2009 revised 2-20-2014.xlsx
2) ADCP_Current_Data_LPR-Spring 2010 revised 2-20-20014.xlsx
3) ADCP Current Data-NB-Spring 2010 revised 2-20-2014.xlsx
4) ADCP Wave Data-NB-Spring 2010 revised 02-19-2014.xlsx

If you have any questions regarding these datasets, or I can be of further assistance, please feel free to contact me.

Sincerely,

Ken Cadmus
Manager – Coastal Science
Office: (860)388-4631 x126
kac@oceansurveys.com

Table 1: ADCP Compass Offsets
Fall 2009 and Sping 2010 Datasets

Deployment Year	Station	Deployment Dates	Raw Ebb Flow (° True)	Compass Offset (°)	Adjusted Ebb Flow (° True)
2009	135	10/11/09-11/10/09	200.7		
2009	135	11/10/09-12/15/09	198.8	1.9	200.7
2009	102	10/11/09-11/09/09	182.5		
2009	102	11/09/09-12/15/09	185.8	-3.3	182.5
2009	067	10/12/09-11/09/09	215.2		
2009	067	11/09/09-12/15/09	213.1	2.1	215.2
2009	042	10/10/09-11/10/09	85.4		
2009	042	11/10/09-12/16/09	86.9	-1.5	85.4
2009	014	10/10/09-11/09/09	195.0		
2009	014	11/09/09-12/16/09	198.5	-3.5	195.0
2010	135	03/24/10-05/01/10	198.7		
2010	135	05/01/10-05/19/10	204.3	-5.6	198.7
2010	135	05/19/10-06/17/10	204.2	-5.5	198.7
2010	135	06/17/10-07/23/10	206.8	-8.1	198.7
2010	102	03/23/10-05/01/10	183.3		
2010	102	05/01/10-05/19/10	177.2	6.1	183.3
2010	102	05/19/10-06/17/10	182.0	1.3	183.3
2010	102	06/17/10-07/23/10	180.7	2.6	183.3
2010	067	03/23/10-05/01/10	216.6		
2010	067	05/01/10-05/19/10	211.0	5.6	216.6
2010	067	05/19/10-06/17/10	211.8	4.8	216.6
2010	067	06/17/10-07/23/10	214.3	2.3	216.6
2010	042	03/22/10-05/02/10	82.9		
2010	042	05/02/10-05/20/10	80.6	2.3	82.9
2010	042	05/20/10-06/18/10	82.7	0.2	82.9
2010	042	06/18/10-07/22/10	77.9	5.0	82.9
2010	014	03/22/10-05/02/10	189.4		
2010	014	05/02/10-05/20/10	181.6	7.8	189.4
2010	014	05/20/10-06/18/10	175.4	14.0	189.4
2010	014	06/18/10-07/22/10	198.7	-9.3	189.3
2010	HKN	03/21/10-04/29/10	236.6		
2010	HKN	04/29/10-05/23/10	230.1	6.5	236.6
2010	HKN	05/23/10-06/21/10	231.4	5.2	236.6
2010	HKN	06/21/10-07/23/10	238.7	-2.1	236.6
2010	NBN	03/20/10-04/28/10	214.8		
2010	NBN	04/28/10-05/22/10	195.1	19.7	214.8
2010	NBN	05/22/10-06/20/10	197.6	17.2	214.8
2010	NBN	06/20/10-07/24/10	206.6	8.2	214.8
2010	NBS	03/20/10-04/30/10	191.4		
2010	NBS	04/30/10-05/21/10	204.3	-12.9	191.6
2010	NBS	05/21/10-06/19/10	193.3	-1.9	191.4
2010	NBS	06/19/10-07/25/10	194.5	-3.1	191.4
2010	KVK	03/19/10-04/30/10	90.3		
2010	KVK	04/30/10-05/22/10	86.8	3.5	90.3
2010	KVK	05/22/10-06/20/10	90.3	0.0	90.3
2010	KVK	06/20/10-07/25/10	91.4	-1.1	90.2
2010	ARK	03/19/10-04/29/10	257.0		
2010	ARK	04/29/10-05/21/10	261.0	-4.0	257.1
2010	ARK	05/21/10-06/19/10	251.4	5.6	257.0
2010	ARK	06/19/10-07/24/10	260.1	-3.1	257.0
2010	NBW	03/21/10-04/28/10	211.4		
2010	NBW	04/28/10-05/23/10	227.2	-15.8	211.5
2010	NBW	05/23/10-06/21/10	207.4	4.0	211.4
2010	NBW	06/21/10-07/25/10	205.7	5.7	211.4

Appendix H

Equipment Blanks

Appendix H
Summary of Analytical Results
Equipment Blanks
Physical Water Column Monitoring Sampling Program
Lower Passaic River Restoration Project

		Analyte	Dissolved Organic Carbon	Particulate Organic Carbon	Suspended Solids Concentration (1.2um)
Description	Sample Date	Sample ID			
2009 Physical Water Column Montoring	10/13/2009	09A-E04-T135-P3-XR	0.18 J	0.6 J	< 1 U
2009 Physical Water Column Montoring	11/11/2009	09A-E08-T067-P3-XR	0.20 J	0.5 J	< 1 UJ
2009 Physical Water Column Montoring	12/14/2009	09A-E12-T102-P3-XR	< 1.2 U	< 1.0 UJ	< 1 U
2010 Physical Water Column Monitoring	3/22/2010	10A-E01-T014-P3-XR			7
2010 Physical Water Column Monitoring	3/25/2010	10A-E04-T067-P3-XR	< 0.30 U	< 1.0 UJ	< 1 U
2010 Physical Water Column Monitoring	5/1/2010	10A-E09-T067-P3-XR			< 1 U
2010 Physical Water Column Monitoring	5/3/2010	10A-E09-T042-P3-XR	5.3 J	0.9 J	12 J
2010 Physical Water Column Monitoring	5/20/2010	10A-E14-T042-P1-XR			13
2010 Physical Water Column Monitoring	5/24/2010	10A-E13-T042-P3-XR	0.65	< 1.0 U	5
2010 Physical Water Column Monitoring	6/18/2010	10A-E19-T042-P1-XR			12
2010 Physical Water Column Monitoring	6/22/2010	10A-E18-T135-P1-XR	< 0.30 U	< 1.0 UJ	6 J
2010 Physical Water Column Monitoring	7/22/2010	10A-E20-T175-P4-XR	< 0.50 U	< 1 U	< 1 UJ
2010 Tributary/Wet Weather PWCM Sampling	5/12/2010	10C-E06-T3R1-P1-XR	< 0.30 U	< 1.0 U	< 1 U
2010 Tributary/Wet Weather PWCM Sampling	11/4/2010	10C-E12-T3R1-P1-XR	< 0.50 U	< 0.9 UJ	< 1 UJ
2010 Tributary/Wet Weather PWCM Sampling	11/4/2010	10C-E12-T169-P1-XR	< 0.50 U	< 1 U	< 1 U
March 16, 2010 High Flow PWCM Sampling	3/16/2010	ACKERMAN 4-RB	< 0.30 U	< 1.0 UJ	< 1 U
Newark Bay 2010 Physical Water Column Monitoring	3/20/2010	N01-E01-TNBN-P1-XR			< 1 U
Newark Bay 2010 Physical Water Column Monitoring	3/25/2010	N01-E04-TARK-P3-XR	< 0.30 U	< 1.0 UJ	5
Newark Bay 2010 Physical Water Column Monitoring	4/30/2010	N01-E09-TNBS-P1-XR			< 1 U
Newark Bay 2010 Physical Water Column Monitoring	5/3/2010	N01-E08-TARK-P3-XR	< 0.30 U	< 1.0 UJ	< 1 U
Newark Bay 2010 Physical Water Column Monitoring	5/22/2010	N01-E14-TNBN-P1-XR			9
Newark Bay 2010 Physical Water Column Monitoring	5/24/2010	N01-E13-TARK-P3-XR	2.6	< 1.0 U	6
Newark Bay 2010 Physical Water Column Monitoring	6/20/2010	N01-E19-TNBN-P1-XR			4
Newark Bay 2010 Physical Water Column Monitoring	6/22/2010	N01-E18-TARK-P3-XR	2.2 J	< 1.0 U	3 J
Newark Bay 2010 Physical Water Column Monitoring	7/21/2010	N01-E22-TARK-P3-XR	< 0.50 U	< 1 U	< 1 U
Newark Bay 2010 Physical Water Column Monitoring	7/25/2010	N01-E23-TNBN-P1-XR	< 0.50 U	< 1 U	< 1 UJ

Notes:
1) U or < = Non-detect at laboratory detection limit
2) J = Estimated Value
3) All units are in milligram per liter (mg/l)