

Public Meeting

Short-term Soil Cleanup at East Water St. Soil Source Area Former Hobart Cabinet Property May 1, 2025

East Troy Contaminated Aquifer Sup

TAI

Introduction & Site Team Members

U.S. Environmental Protection Agency

- Adrian Palomeque, Community Involvement Coordinator
- Shari Kolak, Remedial Project Manager
 - Matt Kluge, U.S. Army Corps of Engineers (EPA Oversight Contractor)

Ohio Environmental Protection Agency

• Scott Glum, Site Coordinator



- I. Site Description
- II. Site History
- **III.** Extent of Contamination
- IV. Interim Remedy & Cleanup Projects
 - 1. East Water St Soil Source Area *
 - 2. Residential Plume Source Area
 - a. Pilot Study
 - b. Vapor Intrusion
- V. Q&A

* The East Water St Soil Source Area activities are the main topic of the presentation

Site Description





Located in Miami County, Troy, Ohio

- 20-square block area from South Walnut & the river in the north, to Floral Ave, Canal St. & Scott St. to the south.
- VOCs found in groundwater, soil, and in indoor air of some homes and businesses
- Residents are connected to the muncipal water supply



- **1988**: Cis-1,2-DCE detected in two Troy production wells
- **1999-2005**: Ohio EPA site investigations
- **2007**: EPA TCRA Installed 17 sub-slab depressurization systems (SSDs)
- **2008**: Listed on National Priorities List (eligible for federal funding for cleanup)
- 2009-2014: EPA conducted remedial investigations
- 2015 & 2017: EPA completed Remedial Investigation & Feasibility Study reports

Extent of Contamination





Two Groundwater Plumes with Different Sources

Residential Area Plume

- Tetrachloroethane (PCE)
- Source Former Dry Cleaners 10 E Main St.

East Water Street Plume

- Trichloroethene (TCE)
- Source Former Hobart Cabinet Company
- Source –former Spinnaker Coatings (TCE)

2018 Interim Record of Decision (ROD)

2018 Source Area ROD - Remediates sources of groundwater contamination while U.S. EPA develops long-term cleanup options for groundwater throughout the site.

AGENCY

- <u>East Water St Soil Source Area</u> * Excavation & Off-Site Disposal (Hobart & Spinnaker)
- **2. Residential Plume Source Area** In-situ Treatment using Chemical Oxidation (ISCO) and installation of SSDs
 - a. Pilot Study Evaluates effectiveness of using permanganate to reduce VOCs
 - **b.** Vapor Intrusion Preemptive Measure

* The East Water St Soil Source Area activities are the main topic of the presentation 7



Excavation & Off-Site Disposal (Hobart & Spinnaker)

- a) Spinnaker voluntary cleanup Sept. 2020
- b) Hobart Remedial Design completed August 2024
- c) Hobart Remedial Action Underway from May to end of fall 2025 (includes final reports)

Location of Cleanup East Water Street Soil Source Area





9

East Water Street Soil Source Area Former Hobart Cabinet Company





10

Anticipated Excavation Sequence

STATES STATES

Anticipated Excavation Sequence



- Six areas
- Start excavation from east to west side of property
- Excavate soils, collect confirmation samples, and <u>backfill with clean gravel</u> <u>before moving to next area</u>
- Phased approach to minimize size of open excavation, reduce risk, and enhance public safety
- Site restoration grass, gravel and asphalt



Contamination at Soil Source Area

SNUTED STATES

- Boxes in yellow indicate locations where soil exceeds cleanup goals.
- Cleanup goals for PCE is 44 ppb, and for TCE is 33 ppb



- The sidewalls will be sloped at 2 ft. No vertical cuts in excavation walls.
- Maximum depth of excavation is 15 ft below ground surface
- Estimated volume removed is 4,480 cy³
- Total estimated duration of project is 60 days. Site preparation, surveying, excavation & backfilling is approx. 50 days. Full restoration of the site will be 5-10 more days.

Traffic Route





- Clean trucks will enter site through the former
 Spinnaker property
- Trucks will be cleaned with brooms and brushes, and tarped before leaving site
- Trucks will exit along west side of Hobart from N. Clay St. to Main St.
- Construction traffic signs will be posted along Water St. near work area 14

What You May See







- Construction fencing, equipment, posted signs, and worker vehicles
- Single axle and tandem axle dump trucks transporting:
 - Excavated material from site to landfill
 - Clean backfill and topsoil to Site
- Truckloads and/or piles of clean gravel, backfill & topsoil
- Water tank or truck for dust suppression







- Site preparation activities start May 19, 2025
- Excavation work starts after Memorial Day
- Work Hours Monday-Friday, 7 am to 4 pm; some work on Saturday depending on weather conditions
- Work scheduled to be completed this fall



a. Pilot Study

Evaluates the effectiveness of using permanganate to reduce VOCs in groundwater

- Starts after Strawberry Festival June (duration 30 days) Includes:
 - installing injection well & monitoring wells,
 - assessing migration of permanganate at varying distances
 - evaluating changes in VOCs & metals in groundwater, and
 - measuring the radius of influence from injection points.

Remedial Design begins after pilot study – Tentative September 2025 Remedial Action (cleanup) - Tentative 2027

Pilot Study Location





Parking lot near the intersection of East Franklin St. and South Mulberry St.



b. Vapor Intrusion

- Preemptive measure Installation of Sub-slab Depressurization Systems in homes/business above ISCO treatment area
- Remedial Design completed in January 2023
- Installation of the systems will begin before full-scale ISCO remedy implemented (tentative 2027)



UNITED STATES

SMURDHIMENTAL PROTECTION

 Shari Kolak - Remedial Project Manager kolak.shari@epa.gov / 312-886-6151

EPA Contacts & Webpage

 Adrian Palomeque – Community Involvement Coordinator palomeque.adrian@epa.gov / 440-250-1715

• <u>www.epa.gov/superfund/east-troy-</u> aquifer

Questions & Answers (Q&A)







We appreciate your attention & participation this evening

