

Upgradient Slurry Wall Historical Data Summary

Velsicol Chemical Corporation Superfund Site

Former Plant Area — OU-1



Plant Site in Operation — 1970s



Plant Decommissioning — 1982



Consent Judgement — November 1982

- Specified construction of **site containment system**:
 1. 24-inch thick slurry wall keyed 30-inches into underlying clay till unit, permeability $< 1 \times 10^{-7}$
 2. 36-inch clay cap, permeability $< 1 \times 10^{-7}$
 3. Groundwater collection system
 - Maintain water elevation < 724.13 feet above mean sea level (ft AMSL)

Slurry Wall Installation — 1983



1984 DNR Summary Report of Oversight Activities

- 1982 — Site Decommissioning and Consent Judgement
- 1983 — Slurry Wall Installation
 - Continuous DNR and EPA oversight to ensure construction per consent judgement specifications
- 1983-1984 — Site Cap Installation and Groundwater Collection System Installation

Slurry Wall Effectiveness Concerns


- Increasing water levels inside groundwater containment system
 - 2.53 million gallons water removed between 1993-1994
- Increasing DDT levels in fish within the impoundment
 - 1994-1995 fish sample DDT concentrations doubled since 1989

1997 MEC Containment Assessment Report

- 1995-1996 — Evaluation of slurry wall and containment system after effectiveness concerns
 - Interior and exterior inclinometers and interior settlement plates
 - Slurry wall material sampling for permeability — upgradient and downgradient
 - Interior and exterior slurry wall piezometer pairs for hydraulic gradient analysis
 - NAPL screening and dye tracer studies at piezometer pairs

Slurry Wall Sampling

- 3 locations sampled on upgradient side at 3 depth intervals
- Out of 9 samples, 2 samples at one location failed permeability requirements (1.0×10^{-7})
 - 6-8 ft — 1.1×10^{-7}
 - 25-26 ft — 3.8×10^{-7}
- Spacing interval of sampling insufficient to evaluate effectiveness of upgradient slurry wall



Piezometer Pairs

- 5 Piezometer Pairs Installed — 3 Downgradient, 2 Upgradient
- Hydraulic Gradient Analysis
 - Upgradient groundwater elevation differences on average < 1 ft higher on the interior side
- Dye Tracer Study
 - No dye detected in exterior piezometers after injection on interior side of slurry wall
- Final MEC Conclusion — Slurry wall functioning as designed

MDEQ Phase I Slurry Wall Evaluation (upgradient only)

■ Major Tasks

- 2001 File review and site evaluation by Weston
- Locate slurry wall
- Install Piezometers
- Characterize soil and groundwater inside and outside containment system
- Initial evaluation of slurry wall and cap performance

Slurry Wall Locating

- 80 investigative borings
- Installed on 2-ft centers on transects perpendicular to the slurry wall
 - Advanced to depths ranging from 5-10 ft
- Placed in locations of proposed permanent groundwater monitoring locations

Example of Slurry Wall Material




WPZ-01 Slurry Wall Boring



WPZ-13 5-10 ft Slurry Wall Material


Piezometer Installations

- 16 piezometer pairs
- Interior and exterior along the slurry wall
- 6 pairs along upgradient side
 - WPZ-01I/X
 - WPZ-02I/X
 - WPZ-03I/X
 - WPZ-04I/X
 - WPZ-12I/X
 - WPZ-13I/X





WPZ-13I and WPZ-13X



WPZ-02X



Piezometer Installation


DEC 18 2002


Piezometer Water Level Evaluation

- 4 rounds of water levels in March 2002
- Completed at a time when dewatering of the river was not occurring
- Water levels indicated inward gradient at most locations (i.e., water levels higher outside of slurry wall)
- Northeast portion of upgradient slurry wall showed outward gradient

Shallow Groundwater Flow

March 2002






Phase II Evaluation

- Dye study and geotechnical borings at WPZ-04 and WPZ-12
- Dye injected on interior side of slurry wall not detected at exterior piezometer locations
- GTSB-04 (2 samples) and GTSB-12 (2 samples) do not meet permeability requirements (1.0×10^{-7})

March 2008



Summary

- **Dye Tests**
 - Did not show leakage on upgradient side (only 2 locations tested)
- **Permeability**
 - 3 locations (6 samples) failed
 - 2 locations (7 samples) passed
- **Water Quality**
 - Some Detections on upgradient side (outside the wall)
 - Widespread groundwater contamination not identified
 - Inconclusive if contamination was present prior to slurry wall installation
- **Hydraulic Gradient**
 - 2002-2008 both inward and outward gradients were observed


Major Takeaways

- MEC study concluded the wall was functioning
- MDEQ evaluation indicated portions of the wall (upgradient only) may be working — data was inconclusive and limited
- Hydrogeological setting has changed significantly since studies
- Spatial data gaps along upgradient portion of slurry wall
- Dye tests and hydraulic gradient monitoring preferred lines of evidence

Questions?

Velsicol Chemical Corporation Superfund Site

Former Plant Area — OU-1



**Upgradient Slurry Wall Evaluation
Velsicol Chemical Superfund Site
August 21, 2019**

Agenda

1. Objectives

2. Methodology

- Piezometer installation and groundwater elevation data collection
- Hydraulic conductivity sample collection and analysis
- Dye tracer study

3. Data evaluation and reporting

4. Schedule




Figure 3-8
Shallow Outwash Groundwater Elevation Contours - May 6, 2016
Velsicol Chemical Corporation Superfund Site
St. Louis, Michigan


Objectives

- Evaluate the effectiveness of the upgradient slurry wall.
- Data evaluation to assist in design of perimeter containment and groundwater collection trench.
- Similar investigation methods to the previous slurry wall evaluations.
 - Memphis Environmental Center, Inc (MEC)
 - MDEQ/Weston Phase I and Phase II of the Remedial Investigation

Methodology

- Piezometer Installation and Groundwater Elevation Measurement
 - Direct push drilling (Geoprobe)
 - 45 piezometer clusters along the up-gradient slurry wall (UGSW).
 - Groundwater elevation measurements (30).
 - Dye tracer study (15).

Methodology



Methodology- Dye Tracer Study

- Charcoal dye receptors deployed to assess background dye presence.
- Dye selection and injection volume determined in consultation with the analytical laboratory.
- Tracer dye injection.
- Charcoal dye receptors deployed
- Charcoal dye receptors retrieved and replaced every two weeks for an initial period of 3 months.
- Based on the preliminary data-the sampling schedule may be extended for an additional 1 to 2 months.

Data Evaluation

- Dye receptor results -Presence or absence of the injection dye(s).
- Groundwater elevation differences interior vs exterior.
- Determine if additional design investigation is required.

Schedule

- Piezometer installation- September 2019
- Background dye evaluation-October 2019
- Dye Injections- Late October 2019
- Dye tracer sample collection- November 2019, December 2019, January 2020.
- Groundwater elevation measurement-throughout investigation.
- Reporting- February and March 2020
- Path forward- April 2020

Questions