

WEST LAKE LANDFILL SUPERFUND SITE BRIDGETON, MO



OU-3 RI/FS Process and Objectives

- Define nature and extent of Site-related contamination in groundwater.
 - Investigate impacts to Missouri River Alluvial Aquifer
 - Refine understanding of complex hydrogeologic system
 - Evaluate background groundwater quality
 - Provide predictive tools to evaluate potential future impacts
- Determine risks to human health and environment
- Depending on results of the RI, identify potential groundwater remedies






OU-3 Work Summary

- Well Inventory and Well Repairs
- Periodic sampling events (2 Years)
- Determine radionuclide background concentrations
- Assess and Address Data Gaps
- Sonic Drilling and Direct Push
- Groundwater Modeling
- Baseline Risk Assessment for OU-3









Existing Groundwater Information

- Data indicates groundwater impacts at some of the existing monitoring wells.
- Off-site water-supply wells sampled during the OU-1 RI did not identify Site related impacts in those wells.
- □ Landfill leachate and Radium exceeding the MCL for drinking water have been detected in groundwater.
- Sources of Radium in groundwater under investigation.
- Potential sources include bedrock, RIM in OU-1, and other sources.









Groundwater Units and Interactions

- Groundwater flow in the area is generally towards the Missouri River.
- The leachate collection system in Bridgeton Landfill affects groundwater in many ways.
- Interactions of waste and native materials with leachate is an important mechanism at the Site that will be further investigated.
- The use of isotopic ratios of radionuclides may support investigation objectives.
- Communication between the alluvial unit and bedrock units will investigated in OU-3.





- AD Alluvium, deep LR Leachate Riser

 AI Alluvium, intermediate KS Bedrock, Keokuk Limestone
 AS Alluvium, shallow SD Bedrock, Salem Formation

 BEDROCK, Salem Formation
- Combined radium below 5 pCi/L (picocuries per liter) maximum contaminant level (MCL)
- X Combined radium above 5 pCi/L (picocuries per liter) maximum contaminant level (MCL






EPA, USGS and MDNR will work together on the OU-3 RI planning and implementation process.

 Groundwater sampling data from Bridgeton Landfill will supplement the OU-3 RI.

EPA Contractor Support on OU-3







Community Engagement for OU-3

- Continue to work and meet with the CAG "Technical" subgroup.
- Provide updated OU-3 information in West Lake Updates as it becomes available.
- Maintain the information repository to keep project stakeholders informed.
- Share draft documents and EPA comments during the OU-3 RI/FS process.







Overview of OU-1 Remedial Design (RD) Process

- Initial RD Deliverables
- 2nd Group of RD Deliverables
- OU-1 Design Investigation Field Work
- 3rd Group of Deliverables
- 4th Group of Deliverables
- Final Design





Initial RD Deliverables

- Remedial Design Workplan
- Design Criteria Report
- Emergency Response Plan
- Site Management Plan





Second Group of Deliverables

- Preliminary Excavation Plan
- Design Investigation Workplan
- Field Sampling Plan
- Quality Assurance Project Plan
- Health and Safety Plan
- Data Management Plan
- Preliminary Design (30%)
- Loading, Transportation, and Offsite Disposal Plan



Design Investigation Field Work

- Refine/Confirm boundaries of Area 1 and Area 2 based on the definition of RIM
 - Samples from North Quarry are anticipated to be collected as part of Area 1 boundary confirmation
- Evaluate Preliminary Excavation Plan and update it based on additional data
- Use additional data in order to perform Optimization



Third Group of Deliverables

- Wildlife Hazard Mitigation Plan
 - Coordinate with Airport
- Site-Wide Monitoring Plan
- Design Investigation Report



Fourth Group of Deliverables

- Revised/Final Excavation
- Pre-Final Design (90%)
- Contractor Quality Assurance/Quality Control Plan
- Institutional Control Implementation and Assurance Plan
- Operations and Maintenance Plan and Manual



□ Final Design (100%)

- Will include Final or Pre-Final versions of all Supplemental Documents necessary for RA
- Pre-Final documents will be finalized in coordination with RA workplan by the RA contractor



- EPA
 - Chris Jump project manager
 - Tom Mahler Technical Expert
 - Ben Washburn Public Affairs
- EPA Contractors
- Supporting Agencies
 - MDNR
 - Ryan Seabaugh
 - U.S Army Corps of Engineers







PRP's proposed Consultants




- Ray D'Hollander



- Dan Feezor



- Tom Hansen





- Keeping the Public Informed throughout the Remedial Design Process.
 - Site Profile Page
 - TCAG meetings
 - TASC contract
 - West Lake updates



- OU-2 includes the Closed Demolition Landfill, the Inactive Sanitary Landfill and the Bridgeton Landfill.
- Remedy Design for the Inactive Sanitary Landfill has been restarted per the 2008 Record of Decision.
- Initial OU-2 RD planning documents are due to the EPA later in June.
- The other OU-2 areas have been deferred to the MDNR per the 2008 ROD.
- Geotechnical and engineering evaluations to support the pending design work for the Inactive Sanitary Landfill is anticipated.

