

# PORTLAND HARBOR RI/FS

# Round 3A FIELD SAMPLING PLAN STORMWATER SAMPLING

# DO NOT QUOTE OR CITE

This document is currently under review by US EPA and its federal, state, and tribal partners, and is subject to change in whole or in part.

January <u>24</u>, 2007

# Prepared for:

The Lower Willamette Group

# Prepared by:

Anchor Environmental, L.L.C. and Integral Consulting Inc.



# **Table of Contents**

1.0 INTRODU	JCTION	1			
1.1 Backgro	Background and context				
1.2 Samplir	ng Purpose and Objectives	1			
	ormwater Contribution to Fish Tissue Burdens	2			
1.2.2 Sto	ormwater Contribution to Recontamination Potential	2			
1.3 Summa	ry Stormwater Sampling Approach	3			
	se and Sampling Rationale				
	cations				
1.4.2 Me	easurement Methods	4			
	ow Information				
1.4.4 Ot	her Considered Measurements and Conditions Error! Bookmark not	defined.			
	ent Organization				
2.0 SAMPLIN	IG DESIGN AND RATIONALE	6			
2.1 Data No	eeds	6			
	mpling Locations				
	mpling Types				
	ng Locations				
	Types and Numbers				
	Analysis				
	ater Samples				
	diment Samples				
	COLLECTION AND PROCESSING PROCEDURES				
	ogbook and Forms				
	ent and Supplies				
	ent Decontamination Procedures				
	ater Sampling Equipment				
	diment Sampling Equipment				
	ater Sample Collection Procedures				
	mmary of Composite Stormwater Sampling Methods				
	mmary of Grab Stormwater Sampling Methods				
	ow and Rain Data Collection				
	nt Sample Collection Procedures				
	diment Traps				
	ater Filtering for Sediment Collection (Back up Procedure)				
	identification				
	Handling and Storage				
3.8 QA/QC		26			
	IG IMPLEMENTATION AND SCHEDULE				
	g Teams and Organization				
	Reconnaissance and Preparation				
	and Contingency Process for Location Selection and Sampling				
	nd Use Based Sampling Sites				
	lustrial Sampling Sites				
4.3.3 Ina	dequate Sediment Collection	32			



Portland Harbor RI/FS Field Sampling Plan Stormwater Sampling January <u>24</u>, 2007

4.4 Site	Site Specific Sampling Reports		
	Project Schedule		
	REPORTING 35		
5.1 Lab			
5.2 Fie	ld measurement Data		
5.3 Rej	porting		
6.0 REFE	RENCES		
	List of Tables		
Table 2-1	Proposed Stormwater Sampling Locations		
Table 2-2	Number of Samples Collected		
Table 2-3	Stormwater Analytes, Methods, Detection Limits, and Sample Size		
Table 2-4a	Composite and Grab Water Sample Analyses Priorities		
Table 2-4b	Sediment Sample Analyses Priorities		
Table 2-5a	Laboratory Methods for Sediment Samples		
Table 2-5b	Laboratory Methods for Water Samples		
Table 2-6a	Analytes, Analytical Concentration Goals, Method Detection Limits, and Method		
	Reporting Limits for Sediment Samples		
Table 2-6b	Analytes, Analytical Concentration Goals, Method Detection Limits, and Method		
	Reporting Limits for Water Samples.		
Table 3-1	Estimates of Stormwater Sample Volumes Needed to Meet MinimumMass		
	Requirements		
Table 3-2	Sample Containers and Preservation Requirements for Sediment Trap and		
	Stormwater Samples		
Table 4-1	River Height Statistics (in feet USGS Morrison Street Bridge Gauge*) for		
	Comparison to Sampling Location Elevations		
	List of Figures		
Figure 2-1	Draft Stormwater Sampling Locations		
Figure 2-2	Photo of Prototype Sediment Trap		
Figure 4-1	Stormwater Technical Team Organizational Chart		
Figure 4-2	Stormwater Sampling Schedule		
118010 . 2	Storm water sampling senegate		
	List of Appendices		
	List of Appendices		
Appendix A	Stormwater Composite Sampling SOP		
Appendix B	Stormwater Grab Sampling SOP		
Appendix C-			
Appendix C-			
Appendix D	Flow Meter Measurements		
Appendix E	Field Forms		
Appendix F	Chain of Custody SOP		



Portland Harbor RI/FS Field Sampling Plan Stormwater Sampling January <u>24</u>, 2007

Appendix G Laboratory Protocol for Extraction and Analysis of Large Volume Water

Samples

Output

Outpu

Appendix H Appendix HI Confined Space Health and Safety Plan Addendum





#### 1.0 INTRODUCTION

This stormwater Field Sampling Plan (FSP) presents the approach and procedures to implement stormwater sampling activities in early 2007 for the Remedial Investigation/Feasibility Study (RI/FS) of the Portland Harbor Superfund Site (Site). The RI/FS project is currently conducting Round 3A of sampling for various purposes in the river, which will extend well into 2007. Therefore, this stormwater sampling is considered part of the Round 3A sampling. This FSP describes the field sampling and laboratory analysis procedures to accomplish the following types of data collection:

- <u>sS</u>tormwater chemistry, <u>tTotal <u>s</u>Suspended <u>s</u>Solids (TSS), and associated conventionals; <u>and</u>
  </u>
- <u>S</u>stormwater sediment chemistry and associated conventionals\_s andstormwater runoff volumes.

The field study approach, sampling procedures, methods, and analyses for stormwater sampling are described in this document. This FSP is a companion document to the Rationale for Round 3A Stormwater FSP under separate cover, which describes the reasoning behind the overall approach.

The stormwater investigation approach presented here is based on the December 13, 2006 memorandum (Koch et al. 2006) from the U.S. Environmental Protection Agency (EPA) assigned stormwater technical team for the RL/FS as well as notes from a Portland Harbor managers meeting where the memorandum was discussed on December 20, 2006. The technical team included members of EPA, Oregon Department of Environmental Quality (DEQ), and the Lower Willamette Group (LWG).

practicability,three eventsTerminal 4Portland Terminal 4Terminal 4Terminal 4is ongoingongoing there may be minor differences in implementation details, however, overall approaches and scope are consistent.

SOThe purpose of this sampling and analysis effort is to provide data for evaluating the potential risk and sediment recontamination threat from stormwater discharges to the river. These data will be used for understanding the magnitude of stormwater impacts to the harbor, developing the draft in river Site RI, identifying stormwater data gaps, and eventually, for evaluating remedial alternatives in the Site FS.

The objectives of the stormwater sampling program were developed in coordination with EPA, DEQ, and the LWG. These objectives are defined as:

#### •EPA/LWG RI/FS Objectives

1. Understand stormwater contribution to in-river fish tissue chemical burdens.

2. Determine the potential for recontamination of sediment (after cleanup) from stormwater inputs.

Formatted: Bullets and Numbering

1



#### •DEQ/City of PortlandDEQ Upland Source Control Objectives

- 1. Determine stormwater sources that now contribute (or could in the future) unacceptably to risks in the river (in terms of direct water or sediment toxicity or bioaccumulation).
- 2.Identify and control sources and estimate stormwater contributions to in-river risk after controls.

The primary focus of this FSP is to obtain data that meet RI/FS objectives, and the echnical eam devised a sampling framework with this intent. However, the team also considered techniques and approaches that could feasibly provide potential overlapping data uses to help meet Source Control Objectives.

It should be noted that in addition to the stormwater data collection described in this FSP, DEQ is pursuing collection of stormwater data at a number of Portland Harbor sites as a part of the Joint Source Control Strategy (JSCS) to meet the above source control objective. The City of Portland is also collecting someStormwater data are also being collected under stormwater data for various purposes related to stormwater source control. National Pollutant Discharge Elimination System (NPDES) permittees in Portland Harbor. As these data become available, they will be used wherever possible and technically defensible to augment the estimations of stormwater loads based on data collected as described in this FSP to help meet the above RI/FS objectives.

The RI/FS objectives as they relate to this FSP are discussed in more detail below.

#### 1..1 Stormwater Contribution to Fish Tissue Burdens

Surface water chemicals are suspected to contributeing to fish tissue burdens (and related risks) in the harbor. The importance of various sources of surface water chemicals, particularly stormwater, is not well understood. This lack of understanding could make it difficult to accurately determine sediment (and water) preliminary remediation goals (PRGs) that are intended to minimize fish tissue related risks for the Ssite.

Thus, it is necessary to determine the relative contribution of stormwater (as compared to other sources) to surface water concentrations of selected chemicals. As noted above, this would be done for stormwater in terms of loading estimates. Thus, to understand the stormwater's contribution of stormwater chemicals to fish tissue burdensOther p, similar data needs exist for other sources and are addressed elsewhere in RI/FS planning and reporting documents.

#### 1..2 Recontamination Potential Evaluation

Surface Stormwater chemicals may contribute to recontamination of remediated sediment near outfalls (and/or potentially widespread harbor wide for some chemicals) after cleanup has been completed. The potential for this outcome must be assessed at an FS\_





appropriate level of detail to understand the general extent and need for stormwater source controls at least on a regional basis within the site.

To predict whether sediments would recontaminate at levels above PRGs eventually set for the site, estimates of stormwater loads\_by outfall (or at least regionsegment) are needed. This requires estimates of loads by modeling segment (as described by Hope 2006) of the river. Estimates of the mass of chemicals present in particulate forms to support Fate and Transport modeling predictions of inputs to and eventual concentrations of chemicals in sediments are also needed.

#### STORMWATER SAMPLING APPROACH

This FSP describes sampling stormwater chemical concentrations and flow at 31 select locations in the Site for directly estimating stormwater loads and extrapolation of loads to other unsampled outfalls or modeled river segments. In summary, the sampling approach at each of these select outfallsdrainage basins determined by the technical team is:

- 1.Flow-weighted composite water samples from three storm events including whole water for organic compound analyses and filtered/unfiltered pairs for metals analyses.
- 2.AdditionalOne additional set of grab stormwater samples at 10 of the 31 sampling locations for sampling of filtered/unfiltered pairs and analysis of selected organic compounds.
- 3.Sediment trap deployment and sampling for a minimum duration of three 3 months.
- 4.Continuous flow monitoring at each sampling site for the duration of the sediment trap deployment period.

The rationale for this sampling approach to meet RI/FS objectives and details of each element of the approach is described in more detail in the remainder of this document.

USRSeveral estimation and evaluation tools will be used these assessments. The data needs of these tools were considered to help define the type and quantities of data to be collected. The modeling tool of primary consideration is EPA's Fate and Transport Model described by Hope (2006). This tool is being used by DEQ to help identifyunderstand stormwater sourcesinputs and needed controls. It is also being used by EPA/LWG in combination with the LWG-developed in river Hydrodynamic and Sedimentation Model (West 2005) to directly evaluate the RI/FS objectives discussed in the next subsection. In summary, these models require data input in terms of chemical mass load for each source estimated along model defined segments of the river. For stormwater, a chemical mass "load" per unit time (e.g., kg/yr) is needed for each river segment of the model.



Portland Harbor RI/FS Field Sampling Plan Stormwater Sampling January 24, 2007

In general, to estimate stormwater loads, a chemical concentration in stormwater and the volume of stormwater discharge (i.e., <u>time\_integrated\_flows</u>) must be known. These terms in the loading equation can be either directly measured (the subject of this FSP) or estimated through indirect means (e.g., runoff modeling of stormwater volumes).

# 1.4.1\_

Because of the large number of outfalls present at the Site, it was determined by the technical team that sampling of every outfall was infeasible to calculate the needed Sitewide stormwater chemical loads. Consequently, data on subset of outfalls, as describedrainage basins, as described in more detail below, will be sampled for stormwater chemistry and flows.

polycyclic aromatic hydrocarbon (), are The data from this subset of outfallsfrom these sampling locations will be used to extrapolate loading to other outfalls and/or model segments. Most sampling sites were selected to be representative of particular kinds of land uses.

For example, stormwater chemical concentrations measured from residential land use areas will be applied to other unsampled residential land use areas and converted to extrapolated loads based on the estimated volumes of stormwater discharged from those unsampled areas. The resulting series of extrapolations will provide total stormwater loads for the entire Site that can be input into the fate and transport model and other estimation tools. The exact methodology for extrapolating chemical and/or flows data to unsampled outfalls or model segments for RI/FS purposes is the subject of ongoing discussions between EPA, DEQ, and the LWG.

TTHW,

• TT

the U.S. Geological Survey (), 1.3 Document OOrganization

The remaining sections of this document describe the sampling plan and field procedures that will be used to collect stormwater and sediment samples:

- Section 2 describes the sampling design-and rationale.
- Section 3 summarizes stormwater sample collection, processing, and measurement procedures for stormwater samples, sediment samples, and stormwater flows.
- Section 4 describes the sampling implementation and schedule including contingency procedures that may be employed to collect data.



- Section 5 summarizes how the data will be reported.
- Section 6 provides references.

Detailed standard operating procedures (SOPs) for sampling and flow measurements are provided in appendices. The appendices also contain a Chain of Custody SOP, field sampling forms, and health and safety procedures and are organized as follows:

•	Appendix A	Stormwater Composite Sampling SOP
•	Appendix B	Stormwater Grab Sampling SOP
•	Appendix C-1	Sediment Trap Sampling SOP
•	Appendix C-2	Stormwater Filtering for Sediment Collection (Back Up Procedure)
•	Appendix D	Flow Meter Measurements
•	Appendix E	Field Forms
•	Appendix F	Chain of Custody SOP
•	Appendix G	Laboratory Protocol for Extraction and Analysis of

Large Volume Water Samples •Appendix H **QAPP** Addendum

Appendix HI Health and Safety PlanConfined Space Health and Safety Plan Addendum



# 2.0 SAMPLING DESIGN AND RATIONALE

The Rationale for Stormwater FSP describes the general approach and rationale for the overall study to support RI/FS objectives described in this FSP. This section describes some the overall rationale for the stormwater sampling design based on that rationale that will support the RI/FS objectives.

#### 22.1 DATA NEEDS

Existing stormwater quality data for the Site are sporadic and relatively limited (Integral et al. 2004). Consequently, estimation of stormwater loads to the river based on existing data or literature values would be difficult and highly uncertain. Site specific and land use based stormwater sampling is needed to support stormwater chemical loading estimates for input into the fate and transport model and other estimation tools that will be used to assess the two RI/FS objectives as noted in Section 1.

#### 2.1.1 Sampling Locations

Finally, because the overall purpose of the sampling is to calculate loads for the site, it is important to optimize sampling locations to minimize the amount of extrapolation based on land use. Although all outfalls cannot be directly sampled, the number of outfalls that need to be extrapolated from indirect information should be minimized where possible, in favor of directly measuring loads. That is, directly measured data is preferred over extrapolated data, when a feasible choice can be made. Consequently, preference should be given to sampling locations as close to the outfall discharge point as possible, while taking into account any physical limitations, and maintaining the approach of isolating certain land uses within a reasonable subset of the sampling locations. Similarly, where one location at or near alarge basin's discharge point can be sampled, this would be preferred to extrapolating loads based on land use from many other sampling points outside the basin. The smaller the basin, the less feasible this preference becomes unless the number of sampling locations is to become very large. Consequently, application of this preference should be reserved for basins that represent at least several percent of the overall drainage basin for the site.

#### 2.1.2 Sampling Types

Each measurement method selected should be fully evaluated to understand any types of supporting information that are needed to allow calculation of a long term load. One important supporting measurement will be TSS data in water samples. These TSS data will be needed to calculate chemical concentrations in water from sediment trap data. In this calculation, TSS (mass sediment/volume water) is multiplied by sediment trap chemical concentrations (chemical mass/mass sediment) to obtain a concentration associated with suspended sediments in water (chemical mass on sediments/volume water). This water concentration can then be multiplied by the volume of water



Portland Harbor RI/FS Field Sampling Plan Stormwater Sampling January 24, 2007

discharged over some period to obtain a mass load exactly like<u>to compare to calculations</u> based on direct measurements of water chemical concentrations (after appropriately taking into account estimated loads associated with the dissolved fraction).

In addition, information on grain sizes in sediment traps <u>may</u>would be useful in understanding the potential for particulate associated stormwater pollutants to settle and recontaminate sediment near outfalls.river sediments. However, these data cannot be collected in preference to chemical concentrations without jeopardizing the ability to analyze all chemicals of interest, due to expected sediment sample volume limitations. Because of these logistical considerations, grain size data will likely be obtained for only a subset of sediment samples collected.

Also, the assumptions and calculation methods behind modeling tools that the data will be input to should be fully understood and evaluated to ensure that any ancillary data needed for these tools is collected. One particular data need of this type that has been identified is collection of filtered and unfiltered stormwater samples to help validate the partitioning algorithms used in the fate and transport model and other estimation tools. Such samples will be collected at all sampling locations and analyzed for metals on the analyte list, because site specific metals partitioning is difficult to predict based on literature information. In addition, limited grab sampling of filtered/unfiltered water will be conducted at a subset of sampling locations and analyzed for organic compounds to provide some information on the range of partitioning characteristics for these chemicals. The partitioning of organic compounds is generally more predictable based on literature information, but some limited data collection for organic compounds will help validate these predictions.

#### 2.2 SAMPLING LOCATIONS

Based on the identified data needs, the sampling locations in Table 2-1 were selected and are shown in Figure 2-1. The locations are broken down into several categories in Table 2-1 that reflect the data needs discussed above and the negotiation process of the Technical Team:

- •Industrial locations (12) that may have unique chemical loads chemical loads
- •Land Uuse-bBasedand General Urban locations (12)

oLocations targeting specific isolated land uses (9)

- •Locations targeting large basins with mixed urban<u>multiple land</u> uses (3) urban<u>multiple land uses (3)</u>
- •T-4<u>Terminal 4</u> Recontamination Study locations (7) representing a representing a range of sites that represent both land use basedboth both land use basedboth isolated land uses and relatively unique relatively unique industrial sites.

DO NOT QUOTE OR CITE
This document is currently under review by US EPA and its federal, state, and tribal partners, and is subject to change in whole or in part.

Formatted: Bullets and Numbering

Formatted: Bullets and Numbering

Formatted: Bullets and Numbering



With respect to data needs, the "land use based" outfalls ampling locations are generally those that are targeting particular types of land uses and data from these sites will be used to extrapolate to other unsampled areas. Locations atoutfalls OF17, OF19, and M-1 represent large basins with relatively mixed land uses and will likely(e.g., outfalls OF-17 and OF-19) will not be used in extrapolations of land use based loading rates, but rather represent a direct measurement of a substantial portion of the overall drainage basin to the Site to compare with measured concentrations of isolated land uses and assess uncertainties within the overall approach (i.e., changes between land use locations and discharge to the river, potential for additional sources [for sediment trap data]) to support model input decisions.

The Iindustrial sites reflect those locations that generally fulfill data needs for sampling of specific or unique industrial activities and mostly fall into the land use category of "heavy industrial.". In some cases, chemical signatures from these locations will not be specific to the activities at the site, and these data may be useable for both site loading evaluation and extrapolation to a generalized heavy industrial loading rate for some chemicals. For example, PAH concentrations at the Schnitzer location(s) may be representative of general heavy industrial conditions, while the metals concentrations are likely not.

Finally, there are seven locations identified associated with the Port of Portland's T-4Terminal 4 sampling effort, which is ongoing. This sampling is subject to a separate agency approved work plan and has been designed to meet all four objectives described in Section 1.1 (i.e., including source identification). While some of the implementation details of the T-4Terminal 4 are slightly different than described in this planFSP, the overall sampling approach is the same (sediment traps, sampling of three storm events with total and dissolved analyses) and the data generated will be consistent with those generated at other locations. The Port has agreed to adapt this program to follow the approach defined in this FSP. Data from these locations will be used similar to that described above for "land use\_based" locations using the categories identified in Table 2-1. However, the data will be evaluated to determine if any of these locations exhibit unique or particular chemical signatures related to specific industrial activities on these sites. If so, data from these locations may be more properly evaluated similar to the high priority sites, where only some locations or chemicals are used in the land use based extrapolations to Site\_wide loads.

# 2.31 SAMPLE, LOCATIONS, TYPES AND NUMBERS

Tables 2-1 and 2-2 summarizes the proposed stormwater sampling <u>locations</u>, types, numbers, and analyses. Table 2-3 summarizes the priority order of sampling of analytes for each sample type and the approximate sample volumes that will be needed for these analyses. The analytical concentration <del>goals achievable with these sample volumes</del>



Portland Harbor RI/FS Field Sampling Plan Stormwater Sampling January 24, 2007

isgoals achievable with these sample volumes are discussed more below. Three types of measurements will be conducted each station:

Stormwater Composite Samples. Flow-weighted composite samples of three3 storm events from each location will be collected to obtain Event Mean Concentrations (EMCs) of constituents of interestCOIs. Flow-weighted, whole water (unfiltered) sample aliquots will be collected with ISCO Model 6712 over the course of the storm event with automatic samplers. These whole water samples will be collected by the sampling teams, identified in Section 4, and transported to the LWG Field Laboratory. At the LWG Field Laboratory, these samples will be composited; sampler performance will be evaluated and the water from the individual sample bottles will be combined and mixed in a single container. Whole water samples for organic compounds, and unfiltered/filtered water pairs will be prepared for metals and total organic carbon (TOC)/dissolved organic carbon (DOC) by the sampling teams from the combined composite sample. -Samples will also be prepared for analysis of TSS concentrations. Each sample will be analyzed for the chemicals shown in Tables 2-2 and 2-2-3. In addition, the priority order and list of chemicals analyzed will vary somewhat between locations as shown in Table 2-4a for reasons discussed in the rationale.

organochlorine pesticides will be analyzed in composite water samples at the following sites given their potential source histories:

•WR-96 Arkema

•WR-22B Front Ave. Props.

WR-6 Rhone-PoulencOF-22B Chemical manufacturing

•WR-6 Rhone-Poulenc

Only a subset of sites will be analyzed for phthalates because of the logistical difficulties of avoiding phthalate contamination from field sampling equipment and laboratory analysis. Through Technical Team discussions, it was determined that it was appropriate to analyze for phthalates at those locations where there was a reasonable potential for phthalate related in river risks that might be linked to upland sources. In addition, as a cross check on the assumptions behind potential phthalate sources, analyses should also be conducted for some locations that were not known or suspected phthalate sources. The preliminary risk evaluations currently underway by the LWG were reviewed for potential phthalate related risks near any of the proposed stormwater sampling locations. The following 7 potential phthalate source locations were identified and are recommended for phthalate analyses:

•WR-24 Oregon Steel MillsWR-121/123 SchnitzerWR-96 ArkemaWR-161 Portland ShipyardWR-145 GundersonWR-148 -Gunderson (former Schnitzer)

Formatted: Bullets and Numbering



Portland Harbor RI/FS Field Sampling Plan Stormwater Sampling January 24, 2007

 In addition, the following 5 locations represent a cross-section of land uses that are not known or suspected phthalate sources and should also be analyzed for phthalates:

•WR-161 Portland Shipyard (Heavy Industrial)

•OF-17 City Mixed Use Basin

OF12a Freemont Bridge To Be Determined (Transportation)OF-M2

City Light Industrial Basin

OF-17 City Multiple Land Use Basin

OF12A ODOT Oregon Department of Transportation ( )

•OF 49 City Residential Basin

•OF-22c OF-22C Upsteam at Forest Park (Open Space Land Use)

Also, phthalate analyses will take place at some T 4<u>Terminal 4</u> locations to be determined in consultation with the Port. This results in a total of 12 locations known at this time that will receive phthalate analyses.

The target storm conditions for sampling are: storms predicted to produce more than >0.2 inches rainfall over a minimum of a 3--hour period, not to exceed approximately 24.25 inches in a 24 hour period (equivalent to the 2-year event), and to have been preceded by at least a 24-hour dry period (less than < 0.1 inches rainfall). National Oceanic and Atmospheric Administration (NOAA) storm predictions will generally be used in the evaluation of storms potentially meeting these criteria (http://www.wrh.noaa.gov/forecasts/graphical/sectors/pqrWeek.php#tabs).-\_For each sampling location, drainage basins will be evaluated for basin size and runoff characteristics to facilitate calculation of expected discharge flows for a variety of storm conditions meeting the storm criteria. Samplers will be programmed to collect aliquots of stormwater following the discharge of the calculated "trigger volume" for each storm event. The objective is to get a composite sample that represents aliquots collected into fourseven 1.8-literone gallon bottles over the entire storm hydrograph (the eighth bottle in the sampler will be used for quality assurance/quality control [QA/QC]). However, this is only an approximate guideline that will be considered in the above evaluation of expected discharge flows and may be modified at one or more sampling locations. However, if If storm flows exceed expected volumes, the sampling period will be cut offconcluded when the four-sample bottles are full and thus in some cases, the falling limb of the storm hydrograph may not be sampled in its entirety.

Stormwater Grab Samples. Stormwater During a one-fourth storm event, discrete stormwater "grab" samples will be collected from 10 locations where it is most likely that organics would be detected in water samples. Because the purpose of the grab samples is to collect partitioning rather than loading data, samples will be collected samples and analyze the samples during storm periods expected to have higher COI concentrations (e.g., first flush or rising limb), to increase the likelihood of detecting low level COIs,

Formatted: Bullets and Numbering

Formatted: Bullets and Numbering





While all samples will be analyzed for total and dissolved organic TOC/DOC constituents. The constituents, the sampling locations were reviewed selected based on general knowledge of site uses and potential sources. The following list Table 2-4a describes- theof locations where stormwater grab sampling will take place., spanning the likely primary chemicals of concern for the harbor, was determined for this sampling:

- •WR-24 Oregon Steel Mills (PCBs/phthalates)
- •WR-121/123 Schnitzer (PCBs/phthalates)
- •WR-96 Arkema (DDx/phthalates)
- •WR-107 Gasco (PAHs)
- •WR-145 Gunderson (PCBs/PAHs/phthalates)
- OF-12a Freemont Bridge (PAHs)
- OF-17 Mixed Use (PCBs/PAHs)OF-12A ODOT Fremont Bridge (PAHs) [This will likely change to St. Johns Bridge]
- OF-17 Industrial/Residential/Open Space Land Use (PCBs/PAHs) [Basin likely to change due to sampling infeasibility].
- •WR-22B Front Ave. Props.OF-22B Heavy Industrial (pPesticides, various)
- •WR-161 Portland Shipyard WR-6 Rhone Poulence (Herbicides/Pesticides/PCBs)
- OF-22 Willbridge (PAHs)

Also, erminal similar grab sampling may take place at some T-4 sites as determined in coordination with the Port. In addition, four of these sites are on the potential phthalates list for composite sampling, and thus, will be analyzed for phthalates. Other locations will not be analyzed for phthalates in grab samples.

The sample teams will collect the required quantity of water and transport it to the LWG Field Laboratory, where one aliquot will be filtered and distributed appropriately to bottles for laboratory analyses and a second aliquot will be distributed directly to bottles. Each sSample will be analyzed for the organic compounds shown in Table 2-22-4a and and TSS. Additionally, organochlorine pesticides will be analyzed at Arkema, Front Ave., OF-22B, and Rhone-Poulenc. Because filtering methods (e.g., filter matrix) differ between organic compounds and metals, metals will not be filtered and analyzed for these grab samples. Storm conditions for grab sampling are the same as for composite sampling described above, with grab samples taken sometime in the course ising limb of the hydrograph of a continuous storm meeting the above requirements.

**Sediment Samples.** Sediment traps will be installed in within catch basins, junctions, or pipesat each sampling location immediately upstream of the outfall discharge and



Portland Harbor RI/FS

Field Sampling Plan Stormwater Sampling January <u>24</u>, 2007



downstream of the automatic sampler. -Figure 2-2 presents a photograph of a prototype of the sediment trap that will be deployed. The sediment trap will be placed adjacent to the outlet of the stromwaterstormwater facility with the opening of the collection bottle at the same elevation as the invert of the outlet. Some sampling locations may require the use of sandbags or structural modifications to generate flow conditions conducive to sediment trap sampling. These sediment traps will be deployed at each location for a minimum target period of \_three3 months. Sediment traps will be inspected at a minimum on a monthly basis. When inspected, if the collection bottle more than half full of sediments, the bottle will be collected and archived and an empty collection bottle will be returned to the trap. If the collection bottle is less than one third full at the first monthly inspection, options for repositioning or relocating the equipment or adding additional traps to obtain a better collection rate will be considered.

Sediments will be collected and archived throughout the 3-month deployment period. At the end of the deployment period, all sediments for each location will be combined and homogenized and sampled for analyses in the priority order shown in until sufficient volume of sediment (as shown in Tables 2-2-3 and 2.4b as the available sediment volume allows.) is available for the entire suite of analytes shown in Tables 2-2 and 2-3. If this occurs prior to completion of the 3-month deployment period, collection will continue for a second sample until the three month duration is completed. I

In Tables 2-3 and 2-4b, analytes are ranked in priority order in the event that any collected sample size is insufficient to run all analyses. The Rationale for the Stormwater FSP describes the reasoning for this priority order, Given that some industrial sites are not known or suspected sources of organochlorine pesticides, but are potential sources for PAHs and phthalates, the priority order of these two chemical classes will be reversed for the following locations:

WR-24 Oregon Steel Mills

WR-121/123 Schnitzer

WR-109 Schnitzer Riverside

WR-107 Gasco

WR-14 Chevron

WR-161 — Portland Shipyard

WR-1/5WR-4 Sulzer Pump

WR-145 Gunderson

WR-148 Gunderson (former Schnitzer)

Formatted: Body Text Indent
Formatted: Bullets and Numbering

Formatted: Indent: Left: 0.5

Formatted: Body Text Indent



\_Grain size is the last priority analyte. As discussed above, \_Iit is unlikely that large enough samples for grain size analysis will be obtained at most locations. Thus, it is unlikely that more than one sediment sample will be obtained from each location.

Also, due to physical constraints, it may be impossible to deploy sediment traps at some locations. Contingency procedures in the event of this problem are discussed more in Section 4.3. One possible contingency measure is to pump and actively filter sediments from <u>large volumes of</u> stormwater at some sites. <u>Thus, tThis contingency back up</u> technique is also described in Section 3.5.2.

Flow Measurements. ISCOIsco Model 750 Area Velocity flow modules will be used in conjunction with the ISCOIsco automatic samplers to allow the collection of flow-weighted composites at each sampling location. The flow modules will also continuously record flow data for the duration of sediment trap deployment. This will allow accurate assessment of the total volume discharged While flow meter precision or performance may not generate accurate discharge volumes for the entire monitoring period flow data will be evaluated in conjunction with sediment trap results and modeled discharge volumes to estimat loading during the period of sediment trap deployment.

All sampling equipment will be deployed at locations that are as close to the point of discharge (for outfall locations) or the last junction associated with the land area of interest (for the land use based locations). In all cases, equipment will be placed at elevations sufficient to minimize the potential for river water to back up to the sample location and compromise flow data quality, the integrity of the sediment traps and collection of true stormwater samples.

#### 2.4 SAMPLE ANALYSIS

Stormwater and sediment samples will be analyzed as described below. Table 2-45 summarizes the analytes and methods of analysis for each analyte group for each sample type (sediment and stormwater).

#### 2.4.1 Water Samples

The stormwater samples will be analyzed for pH, conductivity, turbidity, dissolved oxygen, and temperature in the field. Stormwater samples will be analyzed at selected chemical laboratories for conventionals, metals, and organic parameters as summarized on Table 2-45b. It is anticipated that sufficient sample volume (as noted in Table 2-3) will be collected during each stormwater event to conduct all analyses listed in Table 2-

<sup>&</sup>lt;sup>1</sup> The term "junction" refers to any accessible location where two or more pipes are joined by a structure such as a manhole. This may include locations where drainage from surface runoff also enters the junction, such as catch basins that connect two or more pipes.



45b. The specific analytes for each parameter group and the analyte concentration goals (ACGs) are included on Table 2-56b. Table 2-12-2 shows the number of natural samples and identifies the QA/QC samples for each sampling event. A Quality Assurance Project Plan (QAPP) Addendum for the Round 2A QAPP (Integral and Windward 2004) for this investigation is presented under separate coverin Appendix H. The QAPP Addendum summarizes the analytical program and provides details on the laboratory methods, QA procedures, and QA/QC requirements.

#### 2.4.2 Sediment Samples

The sediment samples will be analyzed at selected chemical laboratories for conventionals, metals, and organic parameters as summarized on Table 2-45a. The analytes are listed in the priority for analysis in Table 2-3. If sufficient mass (as shown on Table 2-3) is not available to complete all analyses, the analyses will be conducted by the laboratory in the priority order identified in this table. Any additional mass available, will be used for laboratory quality control analyses (matrix spike samples, laboratory duplicate samples, matrix spike duplicate samples). The specific analytes for each parameter group and the analyte concentration goals (ACGs) are included on Table 2-56a. Table 2-2 shows the number of natural samples and identifies the QA/QC samples for each sampling event. A QAPP Addendum for the Round 2A QAPP (Integral and Windward 2004) for this investigation is presented under separate cover Appendix H. The QAPP Addendum summarizes the analytical program and provides details on the laboratory methods, QA procedures, and QA/QC requirements.



#### 3.0 SAMPLE COLLECTION AND PROCESSING PROCEDURES

The following sections describe the detailed sampling procedures, record keeping, sample handling, storage, and field quality control procedures that will be used during stormwater and sediment sampling.

#### 3.1 FIELD LOGBOOK AND FORMS

All field activities and observations will be noted in a field logbook during fieldwork. The field logbook will be a bound document containing individual field and sample log forms. Information will include personnel, date, time, station designation, sampler, types of samples collected, and general <a href="mailto:sample and runoff">sample and runoff</a> observations. Any changes that occur at the site (e.g., personnel, responsibilities, deviations from the FSP) and the reasons for these changes will be documented in the field logbook. Logbook entries will be clearly written with enough detail so that participants can reconstruct events later, if necessary.

A sample collection checklist will be completed following sampling operations at each station. The checklist will include station designations, types of samples to be collected, and whether field replicates/duplicates, rinsate blanks, or additional sample volumes for laboratory QC analyses are to be collected. A set of field log forms is included in Appendix E

#### 3.2 EQUIPMENT AND SUPPLIES

Equipment and supplies will include sampling equipment, utensils, decontamination supplies, sample containers, coolers, logbooks and forms, personal protection equipment, and personal gear. Protective wear (e.g., gloves, steel\_toed boots) will be worn by field personnel as specified in the <a href="Health and Safety Plan">Health and Safety Plan</a> (HSP-(Appendix H: Integral 2004b.)

A detailed list of sampling equipment and supplies are listed in SOP Appendices as follows:

- Stormwater composite sampling Appendix A
- Stormwater grab sampling Appendix B
- Sediment sampling Appendix C
- Flow meter measurements Appendix D

The analytical laboratory will supply sample containers and preservatives, as well as coolers and packing material. Commercially available pre-cleaned jars will be used, and the laboratory will maintain a record of certification from the suppliers. The bottle shipment documentation will record batch numbers for the bottles. With this



documentation, bottles can be traced to the supplier, and bottle wash analysis results can be reviewed. The bottle wash certificate documentation will be archived in the project file. Field personnel will not obstruct these stickers with sample labels.

Sample containers will be clearly labeled at the time of sampling. Labels will include the project name, sample location and number, sampler's initials, analysis to be performed, date, and time. The nomenclature used for designating field samples is described in Section 3.6.

#### 3.3 EQUIPMENT DECONTAMINATION PROCEDURES

The following is a brief description of decontamination procedures for each set of equipment. Details of these procedures are described in Appendices A, B, and C.

#### 3.3.1 Water Sampling Equipment

Any portion of the tubing, pump, filters, and <a href="ISCOIsco">ISCOIsco</a> sampler or other materials coming into contact with sampled stormwater will decontaminated prior to use or certified precleaned from the equipment source. Appendices A and B contained detailed procedures and equipment material requirements to avoid potential contamination of samples. <a href="These">These</a> procedures are summarized below.

The top cover, center section, retaining ring, and tub of the automatic sampler will be cleaned with warm soapy water and rinsed with tap water. The two pump drain holes will be checked to see that they are open and free of debris or buildup.

The sampler intake tubes and screens will be cleaned and stored until they are deployed using the decontamination procedure in Appendices A and B. During implementation of the FSP, it is not anticipated that screens and intakes tubes will be removed for cleaning between sampling events. The sampler will be programmed to purge the intake tubes several times before and after each stormwater sample is collected, which should ensure that any contamination from previous events is removed or sufficiently diluted to be unimportant. If upon routine inspection, it is observed that algae is growing in the intake tube, debris is blocking the tube, or any other gross contamination issues may exist, it will be replaced with a tube and screen decontaminated per Appendices A and B.

The Teledyne/Isco glass sample bottles will be sent to the analytical lab for cleaning and returned to the LWG Field Laboratory for deployment. The procedure for these bottles is described in Appendices A and B.

Mounting equipment such as slip rings, nuts and bolts, brackets will be washed with warm soap water using a brush to remove any oil, grease, or other residue from the manufacturing process. They will then be rinsed with spectro-grade acetone and then with tap water and allowed to dry. A warm oven could be used to speed drying.



When installing the brackets in the field at the sampling sites, it may be necessary to drill holes or use powder actuated tools to set studs, weld, or use other means to attach the sampling hardware that may create some debris that could become a contaminant source. After the studs are set or other procedures are complete, the work site will be scrubbed with a brush to remove any debris and rinsed with D4deionized water before the sampling hardware (intake screen) is mounted.

#### 3.3.2 Sediment Sampling Equipment

**Sediment Traps.** Any portion of the sediment trap bottle, sample collection, and homogenization equipment coming into contact with sediment samples will decontaminated prior to use or certified pre-cleaned from the equipment source. Detailed decomtamination decontamination procedures for sampling equipment are included in the Appendix C. The following paragraphs summarize the cleaning procedures.

The sediment traps consist of a stainless steel bracket and a glass bottle. The mounting bracket, nuts and bolts, brackets will be washed with warm soap water using a brush to remove any oil, grease or other residue from the manufacturing process. They will then be rinsed with spectro-grade acetone and then with tap water and allowed to dry. A warm oven could be used to speed drying.

The glass sample bottles will be sent to the analytical lab for cleaning and returned to the LWG Field Laboratory for deployment or purchased and delivered as "Certified Clean." The decontamination procedure for the bottles is described in Appendix C.

When installing the brackets in the field at the sampling sites, it may be necessary to drill holes or use powder actuated tools to set studs, weld, or use other means to attach the sampling hardware that may create some debris that could become a contaminant source. After the studs are set or other procedures are complete, the work site will be scrubbed with a brush to remove any debris and rinsed with Dideionized water before the sampling hardware (sample bottle holder) is mounted.

Water Filtering for Sediment Collection (Back up Procedure). Any portion of the tubing, pump, filters, or other materials coming into contact with sampled stormwater will decontaminated prior to use or certified pre-cleaned from the equipment source. Detailed <a href="decontaminationdecontamination">decontamination</a> procedures for sampling equipment are included in Appendix C.

#### 3.4 STORMWATER SAMPLE COLLECTION PROCEDURES

Stormwater collection procedures are described in detail in Appendices A and B. Two methods of stormwater collection will be used:

 Flow weighted composite sampling of organics, metals, and conventionals that will be collected using an automated <u>ISCOIsco</u>



pump and sample container system and Teflon<sup>TM</sup> tubing (Appendix A).

Grab water sampling of organics and conventionals using <u>ISCOIsco</u> pump, sample containers, and Teflon tubing (Appendix B).

The appendix SOPs for stormwater sampling follows the general concepts used in the sampling and analysis of trace metals in relatively clean surface waters. Examples, of these procedures are the guidelines in EPA's Method 1669, Sampling Ambient Water for Trace Metals at EPA Water Quality Criteria Levels (EPA 1996), and by the Field Sampling Manual for the Regional Monitoring Program for Trace Substances (David et al. 2001). These methods use the "clean hand-dirty hand" (or CH/DH) approach to sample collection. Because this sampling effort does not involve sampling trace levels of chemicals in relatively clean surface waters there is no need for a strict CH/DH procedure. However, the general concept of separating equipment and sample handling jobs to minimize the potential for contamination of samples is employed throughout the SOPs. Detailed procedures for each type of sample collection that follow this general conceptese guidelines are described in Appendices A and B.

#### 3.4.1 Summary of Composite Stormwater Sampling Methods

Stormwater samples for standard chemical and conventional analyses will be collected using a peristaltic pump through a Teflon-lined intake tube with a Teflon coated stainless steel pickup screen. The tube and screen will be attached to the bottom of the junction outlet along with the Area Velocity (AV) flow sensor (described more below), with an extended sampling tube fixed at the desired location in the catch basin outlet. The precleaned ISCOIsco sampler (following procedures discussed above) will be delivered to the sample site by the sampling team.

Whereever possible, the sampler will be located above ground and next to the catch basin or the junction selected for sampling. The pick up screen and the AV flow sensor will be installed on the sensor carrier that iswas installed when the sediment traps are were installed. Although there are tools that allow surface installation of sensors, confined space entry may be required to install the pickup screen and flow sensor. If confined space entry is required, it shall be done in accordance with the procedures in the HSP (Appendix H). In addition, at some locations accessible to the public (e.g., manholes on streets), the actual sampler will be installed within the junction or catchbasin selected for sampling. If confined space entry is required for any location, it will follow procedures in the HSP Addendum (Appendix H). This procedure will also have to follow Appendix H.

After the pickup and sensor have been installed, the sampler will be powered up and allowed to go through the self check process. If the sampler checks is acceptable, the



sample bottles will be installed using the CH DH procedure. Once the bottle section of the sampler is closed, the sampler will be enabled. The sampler will then be lowered into the junctioneatch basin, if necessary, or otherwise secured above ground on the site. Care will be taken not to pinch or kink the pick up tube of the flow sensor cable.

Once the sampler is deployed and the cover is closed, the sampling team leader, or designate, will call the sampler to disable it until an appropriate storm is forecasted. The automatic sampler, when enabled, will be programmed to initiate sampling once specified trigger conditions (e.g., flow depth and/or volume) have flow rate has been exceededbeen met and will continue to sample until the flow rate decreases below the trigger levelconditions are no longer met within the 24-hour sampling duration or the bottle capacity is reached. The trigger flow rate will likelyconditions will be different for each sampling station due to differences in as basin sizes, pipe/junction configurations, and runoff characteristics, varyas well as and there may be non-stormwater discharges such as base flow.

The sampler will collect flow weighted samples into 4seven one gallon 1.8-liter glass bottles. The sampler will be programmed to collect flow proportional sample volumes. Samples will collected on a uniform time basis and the volume collected at each time step will be proportional to the volume of water that has passed the flow meter since the previous time step. The sampler collects the stormwater in 10-ml increments. The number of 10-ml increments collected at each time step is dependent on the flow rate and the sampler programming that is unique to each sampling site. The volume of stormwater water that passes the flow module per 10-ml sample increment will be estimated for each basin to maximize the likelihood that the minimum volume of water required for analysis is collected without exceeding the total bottle volume capacity of the sampler.

The samplers will be programmed with several sample routines that will vary the sample size based on the anticipated rainfall. The minimum volume collected will be based on the minimum storm expected to generate runoff (0.2 inches). The maximum volume will be based on the forecasted precipitation with some allowance for under-predictions of rainfall associated with a storm.

It is possible during a given event that not all the sample bottles are filled or that the bottle volume is exceeded due to differences between the forecasted precipitation and the actual precipitation at the site. The flow data collected at the time of sample collection will be examined to determine if the sample appears to be valid or needs special compositing considerations (as described below) before compositing and shipment to the analytical lab.

After the sampling event, the sampling team leader will call the sampler and disable it if the storm event concludes prior to the 24-hour cutoff, to prevent additional stormwater from being collected if the flows increase. The sampling team will retrieve the automatic sampler and using CH/DH procedures remove sample bottles and seal them with Teflon lined caps, label, and package them appropriately for transportation to the LWG Field



Laboratory. The sampling team will install new bottles and re-deploy the sampler as described previously. The Isco samplers will be decontaminated prior to the first installation and will not be subsequently decontaminated except as noted above and in Appendix A.

At the LWG Field Laboratory, the sampling team will be-combine the samples into a single composite and samples will be filtered (for metals analyses only) andor otherwise prepared for laboratory analyses. The compositing, and filtering, and sample preservation will occur at the Field Laboratory as soon as possible after sample collection. The goal will be to conduct filtering within 24 hours of sample retrieval from the samplers. Field filtering procedures for metals are described in detail in Appendix A. Throughout this process, the samples willshall be handled following the procedures described in the Chain of Custody SOP (Appendix F).

As part of the field sampling procedures, the sampling team will download the sampling report and flow data from the data logger. The field collected samples will be transported to the LWG Field Laboratory and left in their respective coolers, or refrigerated, until the sampling report and flow data can be reviewed. If the sampling report and flow data indicate that there was no malfunction and all the sample bottles are intact, the compositing and sample preparation would continue as described in Appendix A. The samples would be emptied into a large sample container and mixed (i.e. using a churn splitter or other suitable apparatus) while samples are distributed to sample bottles for laboratory analyses.

Several problems could occur that may affect the viability of a sample collected. Common potential problems and contingencies are as follows.

- Sample volume is not adequate to do all of desired analyses. This may occur
  when the forecasted precipitation is substantially greater than the actual site
  precipitation. Under these sampling conditions, the sample will be composited as
  normal and samples for analyses will be prepared in the priority shown in Table
  2-3.
- 2. Sample exceeds bottle capacity. The sampler report indicates that the bottle capacity was exceeded. This may occur when the forecasted precipitation is substantially less than the actual site precipitation. In this case the flow data will be evaluated; if the collected samples represent 50 percent% or greater of the total storm and encompasses some of the falling limb of the storm, the total volume will be composited and analyzed per normal procedure. If the sample volume represents less than 50 % percent of the total storm volume, it should be composited and held at the LWG Field Laboratory under conditions shown in Table 3-2 for possible later analyses in the event that no further storm events can be successfully captured.
- 4-3.A portion of the sample is lost. This would occur when one or more of the sampling bottles was damaged or the sampler malfunctioned. In this situation, the



sampling report and flow data will be reviewed to determine what representative portion of the storm volume is missing. In this situation, it may be possible that a significant portion of the storm was not sampled, and/or there is not adequate volume to complete the desired analyses. Following the process of the two previous scenarios, if the sample includes sample that represents 50 percent% of the storm and both rising and falling limb conditions are included, then the sample will be used. If not, it will be archived at the Field Laboratory as described above. If the sample meets the above conditions but the volume is inadequate to conduct all analyses, the sample containers will be filled in the priority order of analyses shown in Table 2-3.

#### 3.4.2 Summary of Grab Stormwater Sampling Methods

Stormwater grab samples for standard chemical and conventional analyses will be collected using a peristaltic pump that is part of the <a href="ISCOIsco">ISCOIsco</a> automatic sampler. The <a href="ISCOIsco">ISCOIsco</a> sampler will be removed from the <a href="eateh-basinsampling location">eateh-basinsampling location</a> by the sampling team. <a href="Using the CH/DH procedure tThe">Using the CH/DH procedure tThe</a> sampler case will be opened and the delivery tube will be removed from the bulk head fitting. A Teflon lined tube will be connected to the bulkhead fitting to collect the desired samples. The sampler will be put into "Grab" mode and the specified volume will be programmed into the sampler. Once activated, the sampler will purge and the grab sample will be collected <a href="into four onel-gallon">into four onel-gallon</a> jars.

The sampling team will seal, using CH/DH procedures, the samples with Teflon lined caps, label, and package them appropriately for transportation to the LWG Field Laboratory. The sampling team will remove, using CH/DH procedures, the grab sampling tube from the bulkhead fitting and reconnect the distribution tube and close up the sampler. The sampling team will re-deploy the sampler as described previously.

At the LWG Fileld Laboratory, the sampling team will combine the samples into a single composite for each event and samples will be filtered ander otherwise pre prepared for laboratory analyses. The compositing, and filtering, and sample preservation will occur at the Field Laboratory as soon as possible after sample collection. The goal will be to conduct filtering within 24 hours of sample retrieval from the samplers. Field filtering procedures for organic compounds are described in detail in Appendix B. The samples shall be handled following the procedures described in the Chain of Custody SOP (Appendix F).

#### 3.4.3 Flow and Rain Data Collection

Flow will be measured with the Teledyne/Isco 750 AV Module (module). The module is an add-on enhancement to the Teledyne/Isco's 6700 Series Samplers that are being used to collect stormwater samples. The module provides the ability to collect flow proportional sample volumes and flow-paced samples. The sampler displays the real-



time level, velocity, flow rate, and total flow provided by the module. The sampler records this data for later analysis.

The module is designed to measure flow in open channels without a primary device. (A primary device is a hydraulic structure, such as a weir or a flume, which modifies a channel so there is a known relationship between the liquid level and the flow rate.) Area velocity flow conversion requires three measurements: water level, velocity, and pipe dimensions. The AV sensor provides the level and velocity measurements. The pipe dimensions will be measured in the field and entered during module programming. The flow calculation is made in two steps. First, the module calculates the pipe cross-section (or area) using the programmed pipe dimensions and the level measurement. Then, the module multiplies the channel cross section and the velocity measurement to calculate the flow rate.

The sampler will be programmed to use the customary U.S. measurement units, such as feet (depth), cubic feet per second or gallons per minute (flow, depending on size of the contributing basin), and gallons or millions of gallons (volume, depending on the size of the contributing basin). The sampler will be programmed to record flow data at 5-minute intervals. These data will be periodically downloaded throughout the course of the sampler deployment (as determined by data storage capacity) and entered into the project database.

In addition, data on rainfall will be obtained from various existing established rain gauge stations around the Portland area. These data will be used to make sampling decisions throughout the course of the sampling and to understand flow results for data reporting.

#### 3.5 SEDIMENT SAMPLE COLLECTION PROCEDURES

Collection procedures for stormwater sediments are detailed in Appendix C and summarized below.

#### 3.5.1 Sediment Traps

As described in Section 2.3, sediment traps will be deployed at each location for a minimum target period of -three3 months. Sediment traps will be inspected on a monthly basis at a minimum on a monthly basis. When inspected, if the collection bottle is half full, sediments will be collected and archived and a clean bottle, filled with Dideionized water (to prevent floating) will be returned to the trap. This process will be repeated, and sampled sediments archived at the LWG Field Laboratory for additional later compositing untilsufficient volume of sample is obtained for all analytes or the trap deployment period ends. If sufficient volume was obtained prior to

the end of the deployment period, the procedure below will be followed at that time and the trap container redeployed. Sample obtained from the remainder of the deployment



period will be handled per the procedures below, except in that case the step regarding compositing with the archives would be skipped.

Sediment samples will be capped with Teflon lined lids, labeled, sealed and packaged appropriately for transport to the LWG Field Laboratory. At the fileld laboratory, the samples will be removed from the sampler bottles and stored in wide-mouth jars in the freezerstored in the refrigerator.

Oncesufficient sample volume has been obtained or the deployment period has ended, all sampled sediments (including archive<u>d aliquotss</u>) will <u>be</u> combined in one decontaminated stainless steel bowl using decontaminated stainless steel implements and thoroughly homogenized and subsampled in sample containers for chemical analyses.

To remove sSediment removal from the sample bottles will require several steps as the bottle opening is approximately 1/2 inch in diameter. The sampling technician will decant most of the water from each sample bottle into a decontaminated flask. The technician will then swirl or stir, with a decontaminated stainless steel implement, the remaining water with a decontaminated stainless steel implement to mobilize the sediments. The technician will then pour the slurry into a decontaminated funnel with 2-5 micron filter paper appropriate filter material and allow the leachate to drain to a decontaminated flask. Once the sediment has drained to the appropriate a consistency allowing homogenization with a stainless steel spoon, the sample can be lifted out by the filter material and placed dumped into the decontaminated mixing bowlstorage jar. The leachate water and the decanted water then can be used to rinse the sample bottle and remove the last of the sediments. Once all the sample bottles have been emptied and the sediments have been added to the mixing bowlstorage jar, a stainless stead spoon can be used to scrape off any sediments that have adhered to the filter material into the mixing bowlstorage jar. The leachate water or decanted water can be used to rinse the filter material or add moisture if needed to homogenize the sediments

Once the deployment period has ended, all sampled sediments (including archived aliquots) will be combined in one decontaminated stainless steel bowl using decontaminated stainless steel implements and thoroughly homogenized and subsampled in sample containers for chemical analyses.

Sample analysis containers will be filled in the priority order shown in Table 2-3, except for the alternate priority for some locations as described in Section 2.3, until the bowl is empty.

# 3.5.2 Water Filtering for Sediment Collection (Back up Procedure)

This procedure will be used in the event that a sediment trap cannot be deployed at a location because of limited space availability or other logistical reasons. To mimic the deployment of sediment traps, this procedure weould be employed over several storm events at the location in question. The sediment samples obtained results over several events will then be composited in the analytical laboratory could then be "composited" on



paper to mimic the deployment of a sediment trap over 3 months. This would require greater number of sample analyses than currently budgeted for sediment trap analyses.

Large volumes of water will be pumped through Teflon<sup>TM</sup> tubing to collect the particulate fraction from the water for subsequent analysis of the particulate fraction. Currently, two techniques are being evaluated as options for sediment collection: collection with a portable continuous flow centrifuge pump; and collection with a peristaltic pump system with sequential filters and glass fiber filter cartridges. The total volume of water pumped for each sample will be determined based on the analytes selected for the station. Table 3-1 provides estimates of stormwater sample volumes required for each of these sample collection techniques

The portable continuous flow centrifuge pump system samples would be collected by pumping water from the sample location (catchbasin or junction) and sequestering the suspended particles in sample collection jar, which would avoid collecting and retaining large volumes of water for subsequent filtration. The accumulated sediment would then be transferred from the centrifuge pump sample collection vessel, homogenized, and subsampled into sample jars for chemical analysis. The peristaltic pump system would require a high pressure tubing setup and large volume capacity filters, in series, to extract the suspended particles. The large capacity filters would be connected in series with the smallest pore size of 4 or 5 µm, which is the low-end range for silt particles (ASTM 1985). The peristaltic system could be conducted by collection of water into a container (e.g., 20L carboy) and subsequent filtration. The reconnaissance survey will help determine whether the high-volume collection could be conducted directly from the outfallsampling location without intermediate storage. The minimum filter pore size to be used will be 4-5 µm.

Samples will be collected using the <u>using methods that minimize the potential for contamination through sample or sample equipment handling and will follow the general concept of the CH-DH approach described above. "clean hand dirty hand" method. Once the desired volume is pumped, the glass fiber filters will be removed, placed in sample jars, and stored in a cooler containing wet ice. At the analytical laboratory, the filters will be archived until the last sampling event is conducted. Once filters from the last event arrive in the laboratory, the laboratory technicians will combine the sediments from all the filters at each location and homogenize using clean implements. The resulting homogenized sediment sample will be analyzed to determine the concentration of chemicals present within the collected particulates. Detailed procedures for this sampling technique are described in Appendix C.</u>

#### 3.6 SAMPLE IDENTIFICATION

All samples will be assigned a unique identification number based on a sample designation scheme designed to meet the needs of the field personnel, laboratory and



LWG data management, validation chemists, and data users. The A-unique code will be assigned to each sample as part of the data record. This code and will indicate the project phase, sampling location, sample type, sampling event, and level of replication/duplication. All samples will be assigned a unique identification number based on a sample designation scheme designed to meet the needs of the field personnel, laboratory and LWG data management, validation chemists, and data users. Sample identifiers will consist of two to three components separated by dashes. The first component, LW23, identifies the data as belonging to the Lower Willamette River RI/FS as a part of the Round 3 sampling. The second component will begin with the abbreviation "STW" to designate the stormwater sample, followed by a CW, GW, or S for composite water, grab water, or sediment, followed by a single-number code that designates the sampling event. The station number will complete the second component.

Additional codes may be adopted, if necessary, to reflect sampling equipment requirements. Leading zeros will be used for stations with numbers below 100 for ease of data management and correct sorting. The third component will be used to code field duplicate and replicate samples and splits. A single digit number will be used to indicate field duplicates or splits in the third component of the sample identifiers. For equipment decontamination blanks, sequential numbers starting at 900 will be assigned instead of station numbers. The sample type code will correspond to the sample type for which the decontamination blank was collected.

Example sample identifiers are:

- LW2-STW-CW-1022: stormwater composite sample from Station 22 collected during the first sampling event.
- LW2-SW-CW-1022-1: stormwater <u>composite</u> sample from Station 22 collected during the first sampling event; field duplicate <u>issections</u> splits are associated with this sample.
- LW2-SW-CW-1022-2: <u>field</u> duplicate-or <u>split</u> <u>stormwater</u> <u>stormwater composite</u> sample from Station 22 collected during first sampling event.

#### 3.7 SAMPLE HANDLING AND STORAGE

The number, size, and type of sample containers needed for each sample are listed in Table 3-2. This table also includes the preservative and holding times for the various analyses. In general, preservatives will be added to the sample containers by the analytical laboratory prior to shipment to the field. The sampling team will confirm the presence or absence of preservative in the containers prior to filling. Any discrepancies with preservatives will be noted on the field sampling records, and corrective action will be initiated.



Once the sample is collected and preserved using the CH/DH technique, the sample container will be capped, labeled, and placed in double-sealed polyethylene bags and stored on ice or refrigerated until shipped to the laboratory under the chain\_of\_custody procedures outlined in Appendix F

Each storage freezer or refrigeration unit in the LWG Field Laboratory will be monitored bi-weeklydaily to ensure temperature compliance. Each unit will have a separate log form containing date, time, and temperature information.

#### 3.8 QA/QC

Field QC samples are used to assess sample <u>method</u> variability (e.g., replicates), and <u>sample variability</u> (e.g., duplicates), evaluate potential sources of contamination (e.g., <u>equipment</u> rinsate <u>and</u>, <u>decontaminate</u>, <u>and</u> trip blanks), or confirm proper storage conditions (e.g., temperature blanks). The estimated numbers of field and QC samples are listed in Table 2-2. Details on field replicate samples and field QC samples are described in the QAPP Addendum. <u>in Appendix H.</u>

In summary, the QAPP Addendum describes quality assurance/quality control (QA/QC) procedures that will be used to complete the storm-water investigation. The QAPP Addendum for the storm-water investigation was developed within the framework of the existing LWG Round 2 QAPP (Integral and Windward 2004) and Addenda (Integral 2004a) for the on-going or LWG investigations.

For sediment trap samples, the mass of material collected is anticipated to be limited. For sediment samples, the QAPP Addendum includes the collection of field QC samples and additional mass for laboratory QC samples (matrix spike, matrix spike duplicate or laboratory duplicate) as follows and per Table 2-2:

- Field replicate, 1 per 20 samples
- Laboratory QC samples, 1 per 20 samples
- Equipment rinsate blank for phthalates, 1 per 20 samples

Field replicates will be generated by deploying sediment traps with additional sample collection vessels, and compositing the sediment from each half of the sediment trap collection vessels, separately, into two subsamples for analysis. Deployment of two vessels will only be possible at some of the locations, due to expected space limitations within the junctions. Consequently, after the location reconnaissance, the locations of the replicate trap deployment will be determined based on available space and other constraints noted above for sediment trap deployment. Replicate trap deployment will be conducted at sufficient locations to meet the 1 in 20 requirement. If this is not possible, the replicate analysis will be substituted with a duplicate analysis consisting of homogenizing sediment from one vessel and splitting into two equal aliquots for





analyses, at locations where sufficient volume is present, so that the 1 in 20 requirement. Analysis for laboratory QC samples will be conducted by dividing the total sediment collected from one sediment trap vessel at select locations with sufficient volume into <a href="https://dx.doi.org/linearing-nc-number-10">https://dx

For water samples, the sampling program will be designed to collect additional volume for field and laboratory QC samples. The QC program for water samples includes:

- Field replicates, duplicates, 1 per 20 samples
- Laboratory QC samples, 1 per 20 samples
- Equipment rinsate blank for all analyte groups, 1 per 20 samples.

The inclusion of phthalates in the analyte list requires careful consideration in the design of the sample collection program to ensure that the sediment and water samples do not come into contact with phthalate-containing material. Because the water samples require pumping and additional handling for compositing, the likelihood of field contamination from contact with phthalate-containing components increases and could result in qualification of the data if phthalates are detected in the associated field blank samples. The procedures detailed in Appendices A, B, and C include careful consideration of the materials and handling procedures used in order to avoid such sampling contamination if at all possible.

It is likely that the samplers may be deployed with open bottles for several weeks before a storm sample is collected. Air-borne deposition of chemicals from the sampler bodies, which are made from various plastic materials, or ambient atmospheric urban sources may be potential source of contamination to the open bottles. Consequently, the bottle eventually used for the rinsate blanks will also be left un-capped inside the samplers during sampler deployment and will be handled identically to the actual samples during the sample collection process.

Formatted: Body Text Indent



# 4.0 SAMPLING IMPLEMENTATION AND SCHEDULE

#### 4.1 SAMPLING TEAMS AND ORGANIZATION

In order to implement the stormwater sampling program, a team approach has been developed to prepare the FSP, install and maintain sampling equipment, collect samples and deliver them to the laboratory, and finally report the data. As shown on the organization chart (Figure 4-1) Anchor has the lead role in implementing the FSP. The following discussion briefly outlines the duties of the key participants.

Mr. Stivers will act as the overall Anchor project manager. As the manager, he will act as the key contact to the Portland Harbor technical and management teams. In addition, Mr. Stivers played a key role in the development of the monitoring strategies, selection of monitoring sites, identifying the constituents to be monitored, and ensuring the FSP meets the overall study objectives noted in Section 1.

Mr. Page is overseeing the field program and is the lead author of the FSP. He will participate in the station reconnaissance and preparation, described in the following section. He will direct the sampling teams when to activate the automatic samplers, equipment installation, assist in troubleshooting equipment problems, and be available to act as an alternate on the sampling teams.

The sampling teams will be lead by an Anchor water quality specialist familiar with the equipment operation. Each team will also have a specialist from Integral to oversee the collection, processing, and shipment of the samples to the laboratory. The team leader will have the responsibility to deploy and redeploy their automatic samplers as needed, activate their automatic samplers when notified of a storm meeting the sampling criteria is imminent, conduct collection the samples in a timely manner, download sampler storm event data, conduct or coordinate delivery of the samples to the LWG Field Laboratory, coordinate delivery of samples to the analytical laboratories, filling out all field forms and chain of custody forms, and ensure that all field work is conducted in accordance to the HSP (Appendix IHIntegral 2004b).

The O&Moperations and maintenance team will be based in Portland and have responsibility to routinely inspect and repair the sediment traps, ISCOIsco samplers, and other equipment, calibrate flow meters and samplers as needed, download the flow data loggers, and rotate the batteries in the automatic samplers to ensure that they are ready at all times to initiate sampling. They may also deliver samples to the LWG Field Laboratory as needed.

#### needed.

The Field Laboratory Team will assist in the processing, tracking, and archiving of samples, maintain sample archives, conduct packing of coolers and filling out chain\_of\_custody forms for laboratory delivery, will coordinate with the laboratories for sample



delivery and/or pickup, facilitate the tracking of samples, and coordinate with laboratories to ensure correct analyses following the QAPP addendum are conducted.

The laboratories used for the sampling program are listed in Table 2-45. The Laboratories will be responsible for providing "certified clean" sample bottles and equipment to the sampling teams, coolers and packaging materials, labels, seals, and chain\_of\_custody forms. The laboratories will designate a project coordinator that\_who will be responsible for receiving the samples from the field laboratory team\_and\_coordination of data reporting. The laboratory coordinator will also be responsible to ensure that the samples are analyzed according to the specified methodologies.

#### **4.2 STATION RECONNAISSANCE AND PREPARATION**

Sample locations will be verified during a reconnaissance visit consisting of the sampling team leader for those sample locations and persons knowledgeable with the particular location in question. Conditions encountered in the field during implementation of this FSPplan may result in modifications to the sampling design at some or all locations. The Stormwater Technical Team will be made aware of the conditions and will approve substantialthe location-specific modifications to the FSPof the plan.

During the reconnaissance survey, the teams will identify the targeted discharge point and inspect the site to identify the location where the equipment can be installed to meet the sampling objectives. At each site, the team will locate the junction or structure acceptables and or structure acceptables are structure acceptables. At these locations, the team will:

- <u>aA</u>ttempt to determine <u>whether the river back up is likely (determine the sampling locationsite elevation from the site map as well as measuring down to the invert of the junctionstructure outlet and comparing known or measured relative elevations to observed elevations of shoreline features such as the limit of permanent vegetation (which is often approximately equivalent to ordinary high water mark within the Portland Harbor area)e invert elevation to MHHWordinary high water (OHW) or specified elevation (Figure</u>
- Vverify that flow conditions are conducive to flow-paced sampling (e.g., orientation of incoming laterals, debris);
- <u>V</u>verify that there is space available within or adjacent to the site forto secure the <u>ISCOIsco</u> automatic sampler;
- V-verify that there is space available to install the sediment trap and/or replicate traps for some locations; and
- Mmeasure outlet pipe size to order or fabricate the appropriate mounting brackets for the sampler pick up tube, flow meter sensor, and the sediment trap.





Portland Harbor RI/FS Field Sampling Plan Stormwater Sampling January 24, 2007

Formatted: Body Text Indent, Indent: Left: 0"

The primary purpose of determining the sampling location elevation will be to determine whether back up of river water into the junction or adjoining pipes is reasonably likely. Such a condition will be avoided to prevent sampling of river water instead of, or in combination with, stormwater. Table 4-1 presents statistics on river heights based on USGS data from the Morrison Street Bridge gauge for the proposed months of sampling. This gauge is located 2.9 feet above City of Portland datum (i.e., add a value of 2.9 to the Morrison Street Bridge gauge height to obtain a value in City of Portland datum). As shown in Table 4-2, the upper range (i.e., above 80<sup>th</sup> percentile) statistics on the average monthly river height in this period is in the range of 10 to 14 feet as measured by the gauge. Because a monthly average does not explicitly capture daily highs that may have occurred within any given period, the daily 90<sup>th</sup> percentile statistics are also presented. The upper range (i.e., above 80<sup>th</sup> percentile) statistics on these values range from 11.9 to 17 feet in this period, as measured by the gauge.

d oe at

No specific criteria for acceptable junction elevation are proposed here. Rather, the field reconnaissance information for each location (and potential alternate locations) should be compared to Table 4-2 to determine the relative likelihood of river back upriver backup at any particular location. The field crews will make determinations in coordination with the Stormwater Technical Team of acceptable levels of risk for river backup at each sampling location. These decisions will also consider other factors such as the relative feasibility of moving to a nearby location (i.e., within the same basin) and the availability of any other alternate locations (i.e., in other basins entirely) that might also meet the objectives of the location in question. For example, where few if any nearby or alternative sampling locations exist that meet the intended objectives of the sampling location, then acceptance of a greater risk of river back upriver backup at a particular location may be warranted. Conversely, if an alternate location that meets all the location objectives can easily be found, there should be a relatively low tolerance for the potential of river back upriver backup at a given location.

Where the junction elevation of a particular location appears to have a reasonable potential for river back upriver backup based on the field reconnaissance information, additional more accurate surveys of the location elevation may be warranted and will be conducted as necessary to reach decisions consistent with the above framework.

Another key measurement that will be needed is the depth of the junction structure below the invert of the outlet. Ideally, The sediment traps will need to be mounted adjacent to the outlet with the opening of the sampling bottle at the same elevation of the invert.\_If the bottle is located higher, it may not effectively collect the heavier fractions of the sediment or may introduce excessive turbulence that interferes with the function of the flow meter.\_In some situations, this ideal location may not be possible and alternate locations within the junction structure that would be expected to still capture substantial amounts of sediments and avoid excessive turbulence may need to be evaluated and determined.

Formatted: Superscript

Formatted: Superscript



In addition, the team will attempt to identify any non-stormwater flows that could enter the conveyance during the sampling period (e.g., groundwater, stream flows, sheet flow from adjacent sites, batch discharges). Depending on the source, the <u>location-specific procedures may sample plan may</u> need to include collection of information on the nature, amount, and timing of those flows.

If space is not adequate to install the equipment, the targeted sampling location is not adequate, the team will move upstream to the next available representative structure for evaluation. Anchor will report the identified sampling locations to the Stormwater Technical Team for approval. It is possible that a suitable monitoring station cannot be found and an alternative outfall will be needed to be selected to meet the study goals, see Section 4.3 for a discussion of the contingency process for selecting and alternative sampling location

# 4.3 BACKUP AND CONTINGENCY PROCESS FOR LOCATION SELECTION AND SAMPLING

If it is determined that a sediment trap or automated water sampler deployment is infeasible for the selected <a href="mailto:basin.outfall-location.basin.or">basin.or</a> that available sampling locations within that basin will not meet location objectives (i.e., are note? representative of targeted land uses or sites activities), several alternatives may be implemented.

#### 4.3.1 Land Use Based Sampling Sites

If it is a land use based sampling site, another representative outfall or basin could be selected; alternately, another location within the basin could be selected, as long as the remaining basin area is still representative of that land use. Based on the identification of a physically suitable site by the reconnaissance team, as described previously, the site will be re-evaluated in the office. The selected location will be first compared to the infrastructure maps to determine what areas will be captured by the sampling location. The land uses in the captured area will be evaluated to determine if they meet the sampling goal.

If the revised basin does\_not meet the land use selection criteria an alternative outfall will be selected and a reconnaissance survey will be conducted to determine if the equipment can be installed.

Time is of the essence to collect the stormwater samples in the 2006/2007 rainy season. From that perspective, selecting a truncated area of the original basin would be superior if the remaining area provided the land use characteristics desired. Deciding to look for an alternative basin and investigating it may result in not getting the desired number of water quality samples or the desired volume of sediment. However, because all the equipment will not be delivered and installed simultaneously, there may be a two2-week period during which an alternative site can be selected and approved of by the Stormwater Technical Team without greatly affecting the implementation of the FSP.



If the primary issue is that a sediment trap cannot be installed, the high volume water filtering alternate technique could be employed at these sites without need for moving to alternate locations.

#### 4.3.2 Industrial Sampling Sites

If it is not feasible to install the sampling equipment at an <u>i</u>-industrial sampling site, the same procedure described above for <u>i</u>-land <u>u</u>-u-se-b-ased sites would be employed by moving <del>up</del>-the pipe <u>up or to another site drainage basin</u> to see if another sampling point that drains most of the desired site can be found. If such an on-site alternate location cannot be found, it may or may not be feasible to select another industrial site to fulfill the role of the desired site. Any such proposals to move sites would be closely coordinated with the Stormwater Technical Team to obtain approval.

It is difficult to speculate what problems may occur and what the solutions may be without the basic reconnaissance of the sites completed. Consequently, we do not attempt to discuss alternate procedures for all potential situations. In general, if an <a href="ISCOIsco">ISCOIsco</a> sampler cannot be installed for any reason and selection of an alternate site is not acceptable, the alternate approach of manually collecting discrete or manual composites could be considered. If a sediment trap cannot be installed, high volume filtered sampling could be conducted.

#### 4.3.3 Inadequate Sediment Collection

The sediment generation rate varies by land use, topography, implementation of <a href="best">best</a> management practices (BMPs), and rainfall intensity. A well swept, nearly level, industrial area may not generate a significant quantity of sediment. Low intensity storms may not detach and mobilize sediments. <a href="Further.Sediment traps may not collect sediments from low flow storm events">Further. Sediment traps may not collect sediments from low flow storm events</a>. Consequently, if the collection bottle is less than one-third full at the first monthly inspection, the rainfall records will be evaluated to determine if there were storms likely to generate runoff, the sampler will be inspected to ensure that it was installed properly, the <a href="junctioneateh basin">junctioneateh basin</a> will be inspected to see if it is accumulating sediment, <a href="mailto:and">and</a> the contributing basin will be visually surveyed to see if sediment is available to wash off. Based on the findings, it may be recommended that the sediment trap be repositioned or relocated to obtain better collection rate, additional bottles deployed, or that another sampling method be employed. An alternative sediment sampling method would be high volume filtered samples.

# 4.4 SITE SPECIFIC SAMPLING ADDENDAREPORTS

A sSite specific sampling reports addendum—will be developed for added to the field sampling report (described in Section 5) based on the this FSP once the field reconnaissance surveys and decisions made in coordination with the Stormwater Technical Team, has been completed and the equipment has been installed.—A



description of each sampling site will be developed <u>for the report</u> that describes the specific details for implementation of this FSP at the each site. The specific details will include:

- 1. Figure showing the <u>drainage basin and actual sampling location within the basin.</u>
- 2. The reconnaissance survey datasheets, notes, and photographs as necessary to describe the situation.
- Diagram of sample equipment set up within the specific site pipe eatch basin, or junction noting key dimensions.
- 4. Photographs of the installation.
- Calculations of <u>estimated</u> runoff quantity <u>and responses</u> for various ranges of storms for sampler programming.
- Key parameters for sampler programming (i.e., number and size of bottles, sampling rate for various storm totals, enabling flow rate, trigger conditions, length of pickup tube, etc.).
- 7. Sample team Leader responsible for sampler.
- 8. Sampler telephone number.
- Any site specific considerations that will result in deviations from the FSP standard procedures.
- 10. Descriptions of any planned deviations from detailed procedures in this FSP including appendices that will be applied to this site.
- 11. Alternate or contingency procedures (as discussed above) that are proposed for that site.

#### 4.5 PROJECT SCHEDULE

The actual start dates for the sampling will be determined following EPA approval of this Stormwater FSP. Other conditions that may affect the sampling schedule are weather and equipment conditions and availability. Currently, it is anticipated that the stormwater and sediment samples will be begin to be collected in late February through early March. Figure 4-32 shows the currently projected schedule. The most critical item beyond EPA approval is the acquisition and deployment of the water samplers. There is a 3 to 6 week lead time to acquire all the equipment. It is anticipated that each sampling crew will be able to install two sampling kits per day. Consequently, it will take approximately 4 to 7 weeks to deploy the first sampler from the time that it is ordered and approximately 8 weeks from the time the samplers are ordered for all of them to be deployed.





The automated samplers will be activated as soon as they are installed to record flow rates and will be enabled to collect samples during the first storm event that exceeds the predetermined precipitation conditions. The sediment traps will also begin functioning as soon as they are installed. While flow is present in the stormwater system the samplers will be trapping sediments. Based on the weather forecasts and anticipated precipitation, sampling teams will be notified to enable the samplers and deployed to collect samples during following the storm events. Additionally, the sampling teams will be deployed based on forecasted weather to collect grab samples from selected locations.



#### 5.0 REPORTING

#### 5.1 LABORATORY AND CHEMICAL DATA

Preliminary data obtained from the laboratory will be validated following the QAPP and QAPP Anddendum procedures. These data will then be entered into the LWG database including any laboratory or validation assigned qualifiers. Validated analytical laboratory data from the LWG database will be provided to EPA in an electronic format within 90 days of completion of each sampling event. A sampling event will generally be considered complete when the last sample of that type described in this FSP has been collected.

#### 5.2 —FIELD MEASUREMENT DATA

Results of field parameters (e.g., pH) and flow data measurements at each location will be provided to EPA on schedule with and as a part of the Stormwater Site Characterization Summary Report described in Section 5.3. Field parameters will be validated consistent with the QAPP and QAPP aAddendum procedures. Flow data results will be compiled into a separate project database. Rainfall data from publicly available area rain gauges will also be obtained and entered into the flow database.

Initially, these data will be reviewed against information obtained on the flow conditions and monitoring history at each site (e.g., structure and sensor placement issues, the presence of base flows, periods of known equipment malfunction) to identify and flag any periods of questionable or censored data. Data will also be reviewed for any questionable data in periods not associated with any of the above known issues and flagged accordingly (e.g., periods of very high recorded flow with no rainfall, highly erratic readings in small periods of time, periods of no flow during high intensity rain fall, etc.). Periods associated with chemistry sample collection will be identified and flagged within the database as well.

#### 5.23 REPORTING

A #Field sSampling rReport will be prepared and submitted to EPA within 60 days of completing all stormwater and sediment field sample collection efforts as-described in this FSP. The Ffield sSampling rReport will summarize field sampling activities, including sampling locations (i.e., information described in Section 4.4 maps), requested sample analyses, sample collection methods, and any deviations from the FSP.

Stormwater and sediment chemistry results, <u>field measurements</u>, <u>and storm flow data</u> will be reported in tabular format in a Stormwater Site Characterization Summary Report that will be submitted to EPA within 120 days of completing sampling and analysis for all stormwater activities. <u>The report will also include summaries of weather conditions (e.g.</u>,





field observations), field observations associated with each location inspection and/or sampling event, and rain gauge data throughout the sampled period. Preliminary Stormwater and other information and data evaluations relevant to the objectives of the study also will be included in the Stormwater Site Characterization Summary Report. However, the report will not include annualized loading estimates for use in modeling evaluations. This information will be developed and reported within the framework of the overall fate and transport modeling and data evaluations for the RI/FS.



#### 6.0 REFERENCES

American Society for Testing and Materials, 1985, D 2487-83, Classification of Soils for Engineering Purposes: Annual Book of ASTM Standards. Vol. 04.08, pp 395-408.

David, N., D. Bell, and J. Gold. 2001. Field Sampling Manual for the Regional Monitoring Program for Trace Substances. San Francisco Estuarine Institute, San Francisco, CA. (February 2001).

EPA. 1996. Method 1669. Sampling Ambient Water for Trace Metals at EPA Water Quality Criteria Levels. U.S. Environmental Protection Agency, Office of Water Engineering and Analysis Division (4303), Washington, DC.

Gray, J.R., G. D. Glysson, L.M. Turcios, and G.E. Schwarz. 2000. Comparability of Suspended Sediment Concentration and Total Suspended Sediment Data. USGS Water-Resources Investigations Report 00-4191. Reston, Virginia 2000.

Hope, B. 2006. A Mult-Segment Rate Constant Model for Estimation of Chemical Fate in the Lower Willamette River, Oregon, U.S.A. Air Quality Division, Oregon Department of Environmental Quality. Portland, Oregon.

Integral. 2004a. Portland Harbor RI/FS Quality Assurance Project Plan Addendum for Stormwater Sampling. Prepared for the Lower Willamette Group, Portland, OR. Integral Consulting, Inc., Mercer Island, WA.

Integral. 2004b. Portland Harbor RI/FS Health and Safety Plan. Prepared for the Lower Willamette Group, Portland, OR. Integral Consulting, Inc., Mercer Island, WA.

Integral and Windward Environmental. 2004. Portland Harbor RI/FS Quality Assurance Project Plan. Prepared for the Lower Willamette Group, Portland, OR. Integral Consulting, Inc., Mercer Island, WA.

Integral, Windward Environmental, Kennedy/Jenks Consultants, Anchor Environmental, and Groundwater Solutions. 2004. Portland Harbor RI/FS Programmatic Work Plan. Prepared for the Lower Willamette Group, Portland, OR. Integral Consulting, Inc., Mercer Island, WA.

Koch, K., C. Stivers, L. Jones, D. Sanders, L. Scheffler, A. Koulermos, and K. Tarnow. Memorandum to Portland Harbor Management Group regarding Framework for Collecting Stormwater Data to Support the Portland Harbor RI/FS. December 13, 2006.

Schueler, T. 1987. Controlling Urban Runoff: A Practical Manual for Planning and Designing Urban BMPs. Metropolitan Washington Council of Governments. Washington, DC.

West Consultants. 2005. Portland Harbor RI/FS Revised Phase 1 Results: Hydrodynamic Sedimentation Modeling for the Lower Willamette River. Prepared for the Lower Willamette Group inn association with Integral Consulting. Seattle, Washington.