

Wyckoff Eagle Harbor Site





Community Interest Group Meeting

November 5, 2013



Agenda

Time	Agenda
9:00 a.m.	Welcome, Introductions
9:15 a.m.	Scope of FFS • FFS Purpose and Overview
9:45 a.m.	Purpose of the Community Interest Group and Format
10:00 a.m.	 FFS Recent Work and Findings TarGOST Results Conceptual Site Model
11:00 a.m.	 Next Steps Alternatives Evaluation Informal Public Meeting (December 10, 2013) Next Community Interest Group Meeting (February 4, 2014)
11:15 a.m.	Questions/Discussion
noon	Meeting Adjourns

The Focused Feasibility Study (FFS) Purpose and Scope

- EPA is underway with Focused Feasibility Study (FFS).
- FFS evaluates remedial alternatives for the soil and groundwater "Operable Units" (OUs) at the Wyckoff Eagle Harbor Superfund Site.
- This is about the 8-Acre Upland Property at "The Point".
- Coordinated with a separate Focused Feasibility Study for the East Harbor OU.
- Conducted by EPA with contractor CH2M Hill.
- In close coordination collaboration with Ecology.
- Howard and Chung are the technical and management leads for EPA and Ecology.

FFS Schedule and Status

- The FFS was initiated in spring 2012.
- Major first step was to conduct significant additional investigation and update understanding of contamination at the site (we will discuss this later today).
- Process to define and evaluate Remedial Action Alternatives between now and June 2014.
- July September 2014 Final FFS defining Preferred Alternative.
- Fall 2014 "Proposed Plan" will be released for formal public comment.

Community Interest Group - Purpose

- Keep the community apprised of content and progress on the Focused Feasibility Study evaluation of remedial alternatives for "The Point".
- Receive informal input during the FFS process, enabling the team to anticipate and consider community concerns, suggestions and interests in the alternatives analysis.
- Assist the Remedial Action Proposed Plan selection and determination process by incorporating input along the way during the FFS development, prior to the formal public comment period.

Community Interest Group - Purpose

- "CIG" will be active during the FFS and Remedial Action Proposed Plan duration.
- Approximately 4 meetings.
- Typically 2 hours this one is longer for introduction.
- Dawn Hooper is contact person for Interest Group communications between meetings.

Typical Meeting Format

- At each CIG meeting, EPA will provide an update on FFS status, recent work and findings.
- Summary materials of this work will be presented.
- For discussion and informal input from group members.
- Informal process does not supplant formal public review and comment process that will occur for Remedial Action Proposed Plan.
- FFS technical documents will be available to CIG members when they are posted on website and available to the public (e.g: recent Sept 2013 posting of Investigation Memo).
- Meetings are not closed, if there are public "audience" members, we will include some time for their input at the end of each agenda.

Other Public Involvement

EPA will hold two informal public meetings. Formal public comment period on Proposed Plan.

Activity	Approximate Date	Notes
Forming a Community Interest Group	May – July 2013	
Community update re: Interest Group formation	August 2013	Update to broad community, provides opportunity for additional member interest
Interest Group Meeting 1 (today)	November 2013	Quarterly, After EPA Source Investigation Report
EPA Informal Public Meeting	December 10, 2013	After EPA Alternatives Screening
Interest Group Meeting 2	February 4, 2014	Quarterly
Interest Group Meeting 3	Spring 2014	Quarterly
EPA Informal Public Meeting	April 2014	After EPA Comparative Analysis of Alternatives
Interest Group Meeting 4	Summer 2014	Quarterly
EPA Formal Public Comment Period on Remedial Action Proposed Plan	September 2014	Formal public comment period

CIG "Ground Rules"

- These meetings have limited duration, and you are all giving generously of your time to participate. Please speak concisely - respect the intent for all group members to be able to participate.
- Please listen respectfully to the full range of issues and input discussed.
- Please do not speak within the community on behalf of the group or other group members.
- We are hopeful that you will bring input to the group from your community constituencies.
- Please help us to make this as productive a process as possible.
- Remember that you will have the opportunity for formal written comment in Fall 2014. Your informal involvement to provide input between now and then is a great benefit to the project. Thank you!

FFS Recent Work and Findings


- TarGOST Results
- Conceptual Site Model

Update Conceptual Site Model

- Many years since subsurface data collected
- Creosote moves in the subsurface
- Are there "pools" of creosote?
- Where are these "pools" located?
 - Against sheet pile (metal) wall?
 - Beneath former retorts?
- Are there areas of the site with smaller amounts of creosote?

TarGOST (Tar-Specific Green Optical Scanning Tool) Can visually "see" creosote product in the boring from below the ground surface






Reference Emitter (RE)

- How does the waveform relate to the amount of product (NAPL)?
- The TarGOST software determines fluorescence intensity as percent RE.
- RE is a standard Dakota Technologies NAPL that you calibrate the TarGOST tool with prior to every sounding. (Similar to the tank of isobutylene used to calibrate a PID)
- The RE normalizes the response for laser energy changes, fiber optic cable length, detector aging, etc.
- The relationship between percent RE and the concentration of NAPL depends on the fuel (PAH).

TarGOST (Tar Green Optical Scanning Tool)

Phase 1 TarGOST Probes (January 14 through February 8, 2013)	77
Phase 2 TarGOST Probes (February 25 through March 22, 2013)	64
Total	141
TarGOST Field Replicates	5% of total = 7
Confirmation Soil Cores	14% of total = 20

TarGOST Confirmation Boring 2013SC-001 and 001R



LEGEND

In-Situ TarGOST Measurements
Insitu TarGOST response graphs are shown as
the base of these figures. The TarGOST graphs
shown correspond to the colorated
confirmation soil cores.

Ex-situ TarGOST Measurements

De pth interval of ex-situ Tar GOST measurement performed on soil core

Approximate a verage value for of % RE response for ex-situ TarGOST interval

Visual NAPL Observations

Visual observation of NAPL in the confirmation soilcores is shown with depth along the left border of the co-located in-situ TarGOST

Interpretation

Selected 2% RE indicating NAPL presence --

≥%RE Chasen to Indicate NAPL Presence = 5

This value was chosen based on the top 2 feet of the log. This is the only portion of the log which had intervals of no visible NAPL. The rest of the visual observations all had some indication of NAPL presence. Though some portions of the top of the log still include sheen at very low %RE values, a more conservative value of 5%RE was chosen to indicate NAPL presence.

Figure 4-1

Example Visual NAPL Evaluation Wyckoff Upland Field Investigation Wyckoff/Eagle Harbor Superfund Site










TarGOST Confirmation Boring 2013SC-046



Confirmation TarGOST Measurements

Location of confirmation TarGOST measure ment

Plotted at approximate average value for TarGOST interval

2%RE indicating NAPL presence ---

≥%RE Chosen to Indicate NAPL Presence = 6

Though there is some mismatch between the visual NAPL observations and the %RE response, the observations and %RE generally match. The %RE cutoff was determined to include the peak at 20 ft bgs but not those between 0 and 20 ft bgs despite some occasional evidence of sheen in the visual observations.

Presence of NAPL vs %RE

METHOD	RESULTING BEST FIT %RE INDICATING PRESENCE OF NAPL
Visual	9.5
In-situ Statistical – Graphical Approach	10
In-situ Statistical – Balancing Approach	7
Ex-situ Statistical – Graphical Approach	15
Ex-situ Statistical – Balancing Approach	5
Average	9.1

TABLE 4-1


Preliminary NAPL Impacted Volumetric Analysis - Upland Area Behind Sheet Pile Wall Only


Volume Sampled	5% RE	10% RE	15% RE	25% RE	50% RE	100% RE	Units
755,018	167,071	109,069	82,563	52,777	21,739	7,109	Cubic Yards
100%	22%	14%	11%	7%	3%	1%	Percent of Volume Sampled

Note:

Wyckoff Upland Field Investigation

The raw response data from each TarGOST reading was converted from a discrete elevation to a thickness interval. Each discrete response measurement was applied to the interval represented by the midpoints between each discrete response depth. For example, for paired depths (Xi) and responses (Yi), (X1, Y1), (X2, Y2), and (X3, Y3), response Y1 at the top of the boring would apply to interval 0 to (X1+X2)/2, Y2 would apply to the interval (X1+X2)/2 to (X2 + X3)/2, and so on. The interval was then converted to a thickness corresponding to each reading.





	NAPL Absent in Both	12,346	12,946	13,376	13,577	13,804	13,950
False Negative	•		1,633	1,975	2,347	2,900	3,219
False Positive			1,568	1,138	937	710	564
	Total	18,586	18,586	18,586	18,586	18,586	18,586
	Comparison of In-Situ TarGOST to Visual Observations	Cutoff Ta	rGOST Respor	ise [%RE] beti	ween presend	e and absence	of NAPL
	(Percent)	5%	7%	10 %	13%	20%	27%
	(Percent) NAPL Present in Both	5% 14%	7% 13%	10% 11%	13% 9%	20% 6%	27% 5%
	NAPL Present in Both	14%	13%	11%	9%	6%	5%
	NAPL Present in Both NAPL Absent in Both	14% 66%	13% 70%	11% 72%	9% 73%	6% 74%	5% 75%
	NAPL Present in Both NAPL Absent in Both	14% 66%	13% 70%	11% 72%	9% 73%	6% 74%	5% 75%

5%

2,683

7%

2,439

8%

17.2%

Comparison of In-Situ TarGOST to Visual Observations (Count of TarGOST readings)

NAPL Present in TarGOST, Absent in Visual Observations

NAPL Present in Both

Disagreement

Edise Positive

Circled values show the optimal %RE cutoff between presence and absence of NAPL for acheiving agreement in between the in-situ TarGOST and the visual NAPL observations as well as the best balance between false positives and false negatives. Selecting the %RE that acheives the best balance prevents introducing bias to the dataset as many factors may prevent a perfect match between in-situ TarGOST readings and colocated visual observation of confirmation borings.

12%

19.1%

Figure 4-3

3%

20.4%

In-Situ TarGOST Statistical Comparison with Co-Located Visual NAPL Observations from Confirmation Boring Logs in Order to Select Best %RE indicating Cutoff between Presence and Absence of NAPL

Cutoff TarGOST Response [%RE] between presence and absence of NAPL

13%

1,725

5%

17.7%

20%

1,172

4%

19.4%

27%

853

10%


2,097

6%

16.7%

Total Volume Above $10\%RE = 109,069 \text{ yd}^3$

Thickness of TarGOST sample above 10%RE




(2.0 acres)

(2.9 acres)


10 - 15 (1.6 acres) 15 - 20 (0.9 acres) >20 (0.3 acres)

Sheet Pile Wall

Total Volume Above 10%RE (Reduced) = 16,352 yd³ Total Volume Above 10%RE (Raw) = 68,908 yd³







229,600

OTHER

ansk

229,500

West New - Lithology

229,183

Plate 4


Make 4
Visita itation of Sibanea 2
20 Constants Instituted in Form from the received productions


229,900

OX OFFI


07.90


Northeast Mew - Lithology


























East View with Lithology


Plate 5
Visitalization of Sitbare 3 3
SOftware See Least Least Conference Process
Reconference See Least Lea























Plate 7
Visitalization of Stibare a 5
SOphyceus Sellombae to be River focus des

Table 5-2Compartmental Volumes of Soil Types with TarGOST Response ≥10% RE 2013 Conceptual Site Model Update for the Former Process Area Wyckoff / Eagle Harbor Superfund Site


	SubArea 2	Total				
Soil Type	(CY)	(CY)	(CY)	(CY)	(CY)	
Compartme						
Gravel	345	4,075	207	4,692	9,320	
Sand	852	10,530	2,582	8,275	22,239	
Silt	1,077	1,889	19	1	2,986	
Clay	692	909	18	0	1,619	
Fill	6	1,118	32	75	1,231	
Total	2,972	18,522	2,859	13,043	37,396	
Compartme	nt 2:-5 ft MLLW to 1	0 ft above Aquitard				
Gravel	38	1,765	319	1,528	3,650	
Sand	1,290	3,793	282	2,334	7,699	
Silt	170	576	21	0	767	
Clay	5	7	0	0	12	
Fill	0	0	0	0	0	
Total	1,504	6,142	622	3,862	12,130	
Compartme	nt 3: 10 ft above Aqu	itard to Bottom of t	Boring			
Gravel	688	363	169	63	1,283	
Sand	6,335	4,004	301	218	10,858	
Silt	2,248	2,121	383	39	4,791	
Clay	1,592	444	33	0	2,069	
Fill	0	0	0	0	0	
Total	10,863	6,932	887	319	19,001	
Compartme	nt Sums					
Gravel	1,071	6,204	696	6,283	14,254	
Sand	8,477	18,328	3,165	10,826	40,796	
Silt	3,495	4,586	424	40	8,545	
Clay	2,290	1,359	51	0	3,700	
Fill	6	1,118	32	75	1,231	
Total	15,339	31,595	4,368	17,224	68,526	

Notes:

CY = cubic yards




Overlay of Combined Subarea 10%RE from Raw TarGOST with TarGOST Sample Thicknesses above 10%RE



Slide 2

Treatment Compartments



Conclusions

- NAPL (creosote) is thickest in the vadose zone and Upper Aquifer in the center of the site.
- The thickest accumulations of creosote are beneath the former retort areas and to the east by the Naphthalene Block Excavation Area.
- Based on MVS analysis, NAPL volume is estimated at approximately 68 thousand cubic yards.
- Based on Theissen Polygon analysis, NAPL volume is estimated at 109 thousand cubic yards.
- 82 percent of the NAPL volume was found in coarsergrained material (sands and gravels)

FFS Next Steps

- Our next CIG meeting is February 4.
- At that meeting, EPA will be able to describe the Remedial Action Alternatives that are being evaluated,
- the Remedial Action Objectives that each alternative is designed to meet,
- and the criteria being used in the Comparative Analysis of Alternatives.

Public Involvement Next Steps

- EPA Public meeting on December 10, at City Hall please encourage your community constituencies to attend.
- Note that Site Investigation Report and FFS process overview are available on the EPA website, you can direct people there.
- CIG meeting February 4.
- If ideas or suggestions in-between meetings, please call Dawn.
- Thank you for your involvement!